yoursmahboob.wordpress.com

arihant

QUANTITATIVE APTITUDE

QUANTUM CAT

Also Useful For

GAT | XAT | IIFT | SNAP | GMAT | CSAT

Sarvesh K Verma

Scanned by CamScanner

yoursmahboob.wordpress.com

CONTENTS

- **CAT 2014** The Flashback Moments
- **Selection Criteria** In Search of Excellence
- **CBT** Tips For Computer Based Testing
- **Paper Analysis** XAT, IIFT, SNAP, CMAT
- **Solved Papers** XAT, IIFT, SNAP
- **CAT 2015** Cutting Edge Techniques To Crack

• **XAT** Solved Paper 2015	1-12
• **IIFT** Solved Paper 2014	13-18
• **XAT** Solved Paper 2014	1-13
• **IIFT** Solved Paper 2013	15-22
• **XAT** Solved Paper 2013	1-13
• **IIFT** Solved Paper 2012	15-21
• **SNAP** Solved Paper 2011	23-30

1. Fundamentals	1 – 145
2. Averages	146 – 170
3. Alligations	171 – 180
4. Ratio, Proportion & Variation	181 – 214
5. Percentages	215 – 246
6. Profit, Loss and Discount	247 – 269
7. CI/SI/Instalments	270 – 285
8. Time and work	286 – 319
9. Time, Speed and Distance	320 – 367
10. Mensuration	368 – 430
11. Trigonometry	431 – 444
12. Geometry	445 – 513
13. Elements of Algebra	514 – 542
14. Theory of Equations	543 – 575
15. Set Theory	576 – 590
16. Logarithm	591 – 613
17. Functions and Graph	614 – 661
18. Sequence, Series and Progressions	662 – 702
19. Permutations & Combinations	703 – 752
20. Probability	753 – 791
21. Co-ordinate Geometry	792 –807

- **CAT Solved Papers** (2003–2008) 1-72

Scanned by CamScanner

yoursmahboob.wordpress.com

1 FUNDAMENTALS

First of all I would like to mention that this chapter is deliberately written to promote your interest for CAT preparation in a systematic approach which will lay the strong foundation. Since this chapter subsumes fundamentals of **calculation techniques** along with various **number systems** besides basic tenets of maths, hence it is named as 'Fundamentals'. Again since most of the problems (*i.e.*, 20–40%) in CAT paper (*viz.*, QA section) belong to this chapter alone hence it becomes inevitable to discuss the nuances and subtleties of the various concepts objectively and comprehensively. That's why this chapter has become very bulky too.

In your own interest it would be better to adhere to my advices and stipulations stated at appropriate places in this chapter even throughout the book. As per my own experiences there are basically three stages in the solution of a problem and each of the stage has its own contribution. The following diagrams illustrates the importance of each stage.



If any of the three above mentioned activities is botched up then you are prone to failure. Hence, it is obvious that speed calculation invariably enhances your rate of success in CAT and most importantly it eliminates the stress and anxiety to ensconce you in your own comfort zone. Remember that you can succeed only when you operate in your comfort zone else it turns out to be a challenge. Due to above mentioned reasons it is imperative to become handy in quick calcualtion which is required in DI too.

The latter part, even major section, of the chapter is devoted to numbers, their kinds, operations and behaviour in mathematical milieu. You are supposed to not to skip a bit of it since every bit and every concept is equally important. It is advised that you should make the flow chart of the solution while reading, since going back to the problem several times means irritation and wastage of invaluable time. Also, you should try to solve maximum no. of problems without pencil and paper since it makes you quick respondent and saves a lot of time. Finally, avoid rote method of learning in maths instead be inqusitive and explorer to gain an advantage. The bottomline is that perceive logic and apply logic, since it is logical.

CALCULATION TECHNIQUES

Multiplication : Multiplication is nothing but the shortest method of addition. In day-to-day life when we have to add-up the same quantity many a times, so we multiply the given number by the number of times to which the given number is to be added repeatedly *e.g.*, $3+3+3+3+3+3+3$ can be added seven times but to get quick result we just multiply 3 by 7. Hence, we get $3 \times 7 = 21$. Thus, I am sure that now you must have become aware of that how much important is the multiplication table. So I hope that you will learn the multiplication table.

Now, I would like to suggest you that in the competitive exams like CAT, where speed and accuracy are totally indispensable. So there are some novel and enticing techniques for multiplication given in this chapter. But in some techniques you have to know the square of some relevent numbers, normally the squares of 1 to 100. Last but not the least you don't need to bother about since I have some very innovative techniques to learn and calculate the squares very readily. Even most of the times you need not to use a pencil and paper for this work and that's my purpose.

Basically we divide these techniques into two categories. The first one which I have derived from some algebraic operations and the second one belongs to our ancient maths *i.e.*, Vedic maths.

In this book I have laid emphasis on my own approach of multiplication, because years of research in numeric maths I have found that I myself and my students find it comfortable as it is very convenient and pragmatic to do within a few seconds.

Scanned by CamScanner

yoursmahboob.wordpress.com

Case 1. Multiplication by 5, 25 $(=5^2)$, 125 $(=5^3)$, 625 $(=5^4)$ etc.

EXAMPLE 1 *Multiply* 187 *by* 5 *i.e.*, 187×5

SOLUTION **Step 1:** Associate as many zeros at the end of the given number as there is the power to 5. Thus we write 187 as 1870. (because $5 = 5^1$)

Step 2: Divide the resultant number by 2 as many times as there is the power to 5.

Thus, $$\frac{1870}{2} = 935$$

EXAMPLE 2 *Multiply* 369 *by* 125.

SOLUTION **Step 1:** 369000 ($\because 125 = 5^3$) hence 3 zeros will be associated.

Step 2: $$\frac{369000}{2 \times 2 \times 2} = \frac{369000}{8} = 46125$$

(Since, there is 5^3 hence it will be divided by 2^3.)

In general, if you want to multiply any number K by 5^n then you just need to divide that number by 2^n, after writing or (associating) 'n' zeros at the end of the number *i. e.*,

$$K \times 5^n = \frac{K0000\ldots n \text{ zeros}}{2^n}$$

e. g., $$732 \times 5^6 = \frac{732000000}{2 \times 2 \times 2 \times 2 \times 2 \times 2}$$

$$= \frac{732000000}{64} = 11437500$$

Case 2. Multiplication of a number by 9^n *i.e.*, 9, 9^2 $(=81)$, 9^3 $(=729)$ etc.

EXAMPLE 1 *Multiply* 238 *by* 9.

SOLUTION Multiply the given number by 10 and then subtract the given number from the resultant number. So

$$238 \times 9 = 238 \times (10 - 1)$$
$$= 2380 - 238 = 2142$$

[using distributive law as $a \times (b - c) = ab - ac$]

EXAMPLE 2 *Multiply* 238 *by* 81.

SOLUTION **Step 1:** $238 \times 81 = 238 \times 9 \times 9$

Step 2: $238 \times (10 - 1) \times (10 - 1)$

Step 3: $[2380 - 238] \times (10 - 1)$

Step 4: $2142 \times (10 - 1)$

Step 5: $21420 - 2142 = 19278$

NOTE To multiply a number by the higher powers of 9 *i.e.*, 9 to power 3, 4, 5, ..., etc. It is better to do it conventionally.

Case 3. Multiplication of a number by the numbers whose unit (*i.e.*, last) digit is 9.

EXAMPLE 1 *Multiply* 287 *by* 19.

SOLUTION $287 \times (10 + 9) = 287 \times 10 + 287 \times 9$
$= 2870 + 287 \times (10 - 1)$
$= 2870 + 2870 - 287$
$= 5740 - 287 = 5453$

or $287 \times 19 = 287 \times (20 - 1)$
$= 287 \times 20 - 287$
$= 287 \times 2 \times 10 - 287$
$= 574 \times 10 - 287$
$= 5740 - 287 = 5453$

Case 4. Multiplication of a number by the number which contains all the digits as 9.

EXAMPLE 1 *Multiply* 743 *by* 99.

SOLUTION $743 \times 99 = 743 \times (100 - 1)$
$= 74300 - 743 = 73557$

EXAMPLE 2 *Multiply* 23857 *by* 9999.

SOLUTION $23857 \times 9999 = 23857 \times (10000 - 1)$
$= 238570000 - 23857 = 238546143$

NOTE In general to multiply a number K by a number which is purely consists of n 9s, put n zeros at the end of the number K then subtract the given number from the resultant number.
e.g., $K \times 9999\ldots n$ times $= (K0000\ldots n \text{ zeros}) - K$

Case 5. To multiply those two numbers, the sum of whose unit digit is 10 and the rest digits (left to the unit digit) are same in both the numbers.

EXAMPLE 1 *Multiply* 38 *by* 32.

SOLUTION **Step 1:** Multiply the unit digits as $8 \times 2 = 16$

Step 2: Add 1 to the left digits then multiply this increased number by the original digits *i. e.*,

$3 \times (3 + 1) = 12$

Thus, we get $38 \times 32 = 1216$

EXAMPLE 2 *Multiply* 83 *by* 87.

SOLUTION **Step 1:** $3 \times 7 = 21$

Step 2: $8 \times (8 + 1) = 72$

$\therefore$ $83 \times 87 = 7221$

EXAMPLE 3 *Multiply* 71 *by* 79.

SOLUTION **Step 1:** $9 \times 1 = 09$

Step 2: $7 \times (7 + 1) = 56$

$\therefore$ $71 \times 79 = 5609$

NOTE The last two places are reserved for the product of unit digits as in the above example $1 \times 9 = 9$ but we fill the last two places by writing "09". So don't write 569 since it is wrong.

EXAMPLE 4 *Multiply* 125 *by* 125.

SOLUTION **Step 1:** $5 \times 5 = 25$

Step 2: $12 \times (12 + 1) = 156$

So, $125 \times 125 = 15625$

EXAMPLE 5 *Multiply* 431 *by* 439.

SOLUTION **Step 1:** $1 \times 9 = 09$

Step 2: $43 \times (43 + 1) = 1892$

So, $431 \times 439 = 189209$

EXAMPLE 6 *Multiply* 1203 *by* 1207.

SOLUTION **Step 1:** $3 \times 7 = 21$

Step 2: $120 \times (120 + 1) = 14520$

So, $1203 \times 1207 = 1452021$

Scanned by CamScanner

yoursmahboob.wordpress.com

Case 6. To multiply the two numbers whose difference is always an even number.

EXAMPLE 1 *Multiply* 38 *by* 52.

SOLUTION **Step 1:** $52 - 38 = 14$ (here 14 is an even number)

Step 2: $\frac{14}{2} = 7$ **Step 3:** $38 + 7$ or $52 - 7 = 45$

Step 4: $(45)^2 = 2025$ **Step 5:** $7^2 = 49$

Step 6: $2025 - 49 = 1976$

EXAMPLE 2 *Multiply* 76 *by* 96.

SOLUTION **Step 1:** $96 - 76 = 20$ (here 20 is an even number)

Step 2: $\frac{20}{2} = 10$

Step 3: $76 + 10 = 96 - 10 = 86$

Step 4: $(86)^2 = 7396$

Step 5: $(10)^2 = 100$ **Step 6:** $7396 - 100 = 7296$

EXAMPLE 3 *Multiply* 185 *by* 215.

SOLUTION **Step 1:** $215 - 185 = 30$

(here 30 is an even number)

Step 2: $\frac{30}{2} = 15$

Step 3: $185 + 15 = 215 - 15 = 200$

Step 4: $(200)^2 - (15)^2 = 40000 - 225 = 39775$

NOTE 1. In general, if there are any two numbers N_1 and N_2 and the difference between N_1 and N_2 is $2d$ then their product i.e.,

$$N_1 \times N_2 = (N_1 + d)^2 - d^2$$

or $$N_1 \times N_2 = (N_2 - d)^2 - d^2$$

2. Even this method can be applied for the two numbers whose difference is an odd number but since it contains decimal values so some students may feel it slightly difficult.

EXAMPLE 1 *Multiply* 17 *by* 22.

SOLUTION **Step 1:** $22 - 17 = 5$

Step 2: $\frac{5}{2} = 2.5$

Step 3: $17 + 2.5 = 22 - 2.5 = 19.5$

Step 4: $(19.5)^2 - (2.5)^2 = 380.25 - 6.25 = 374.00$

SHORTCUT To multiply any two numbers say, N_1 and N_2 we apply the following methods.

$$N_1 \times N_2 = \left(\frac{N_1 + N_2}{2}\right)^2 - \left(\frac{N_2 - N_1}{2}\right)^2$$

So, if you know the square of the required numbers then using this method you can multiply any two number within 2-3 seconds as

$$56 \times 64 = \left(\frac{56 + 64}{2}\right)^2 - \left(\frac{64 - 56}{2}\right)^2$$

$$= (60)^2 - (4)^2 = 3600 - 16 = 3584$$

VEDIC METHODS OF MULTIPLICATION

EXAMPLE 1 *Solve* 23×74.

SOLUTION





EXAMPLE 2 *Solve* 83×65.

SOLUTION





EXAMPLE 3 *Solve* 524×19.

SOLUTION



EXAMPLE 4 *Evaluate* 3456×89.

SOLUTION



Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 5 *Evaluate* 245×367.

SOLUTION

245
367
5 $5 \times 7 = 35$

245
367
15 $(7 \times 4 + 6 \times 5) + 3 = 61$

245
367
915 $(7 \times 2 + 6 \times 4 + 3 \times 5) + 6 = 59$

245
367
9915 $(6 \times 2 + 3 \times 4) + 5 = 29$

245
367
89915 $(3 \times 2) + 2 = 8$



EXAMPLE 6 *Evaluate* 123456×789.

SOLUTION

123456
789
4 $9 \times 6 = 54$

123456
789
84 $(9 \times 5 + 8 \times 6) + 5 = 98$

123456
789
784 $(9 \times 4 + 8 \times 5 + 7 \times 6) + 9 = 127$

123456
789
6784 $(9 \times 3 + 8 \times 4 + 7 \times 5) + 12 = 106$

123456
789
06784 $(9 \times 2 + 8 \times 3 + 7 \times 4) + 10 = 80$

123456
789
406784 $(9 \times 1 + 8 \times 2 + 7 \times 3) + 8 = 54$

123456
789
7406784 $(8 \times 1 + 7 \times 2) + 5 = 27$

123456
789
97406784 $(7 \times 1) + 2 = 9$



EXAMPLE 7 *Find the value of* 4567×1289.

SOLUTION

4567
1289
3 $9 \times 7 = 63$

4567
1289
63 $(9 \times 6 + 8 \times 7) + 6 = 116$

4567
1289
863 $(9 \times 5 + 8 \times 6 + 2 \times 7) + 11 = 118$

4567
1289
6863 $(9 \times 4 + 8 \times 5 + 2 \times 6 + 1 \times 7) + 11 = 105$

4567
1289
86863 $(8 \times 4 + 2 \times 5 + 1 \times 6) + 10 = 58$

4567
×1289
886863 $(2 \times 4 + 1 \times 5) + 5 = 18$

4567
1289
5886863 $(4 \times 1) + 1$

EXAMPLE 8 *Find the value of* 325768×1234.

SOLUTION

325768
1234
2 $4 \times 8 = 32$

325768
1234
12 $(4 \times 6 + 3 \times 8) + 3 = 51$

325768
1234
712 $(4 \times 7 + 3 \times 6 + 2 \times 8) + 5 = 67$

325768
1234
7712 $(4 \times 5 + 3 \times 7 + 2 \times 6 + 1 \times 8) + 6 = 67$

325768
1234
97712 $(4 \times 2 + 3 \times 5 + 2 \times 7 + 1 \times 6) + 6 = 49$

325768
1234
997772 $(4 \times 3 + 3 \times 2 + 2 \times 5 + 1 \times 7) + 4 = 39$

325768
1234
1997712 $(3 \times 3 + 2 \times 2 + 1 \times 5) + 3 = 21$

325768
1234
01997712 $(2 \times 3 + 1 \times 2) + 2 = 10$

325768
1234
401997712 $(1 \times 3) + 1 = 4$

DIVISIBILITY RULES

While solving the mathematical problems we need to divide one number by another number. In general we use four terms for this process as

Divisor) Dividend (Quotient
xyz
Remainder

or Dividend = (Divisor × Quotient) + Remainder

for example $30 = (7 \times 4) + 2$

where quotient is a whole number *i.e.*, 0, 1, 2, 3, ... etc and remainder is always less than 'divisor' or zero.

So, when the remainder is zero, we can say that the given number is divisible by the particular divisor number.

Now, $238 \div 6 = 39\frac{4}{6} = 39.66$ (decimal notation)

Scanned by CamScanner

yoursmahboob.wordpress.com

Since the above number when divided by 6 leaves a remainder of 4 then it is said to be not divisible by 6 where 238 is dividend, 39 is quotient obtained when divided by 6 as a divisor. Thus we get 4 as a remainder.

Further if we subtract the remainder from the dividend then the dividend (the resultant number) becomes divisible by particular divisor. *e.g.*,

$238 - 4 = 234$ (dividend–remainder)

$$\begin{array}{r|l} 6 & 234 \\ & 18 \\ \hline & 54 \\ & 54 \\ \hline & \times \end{array} \quad 39$$

Here, the remainder is zero and the number is perfectly divisible by 6.

Another point is that if we add the difference of divisor and remainder to the given number (*i.e.*, dividend) the number becomes divisible by that particular divisor. *e.g.*,

$6 - 4 = 2$ (Divisor–Remainder)

$238 + 2 = 240$

$$\begin{array}{r|l} 6 & 240 \\ & 240 \\ \hline & \times \end{array} \quad 40$$

Thus $(238 + 2)$ becomes perfectly divisible by the particular divisor.

For negative integers

e.g., $-37 \div 5$

$$\frac{-37-3+3}{5} = \frac{-40+3}{5} = \frac{-40}{5} + \frac{3}{5}$$

Here 8 is quotient and 3 is remainder.

NOTE The remainder is always a non-negative integer.

Rule 1. If a number N is divisible by D then the product of N with any other integral number K is also divisible by D.

i.e., $\frac{N}{D} \rightarrow$ Remainder $0 \Rightarrow \frac{NK}{D} \rightarrow$ Remainder 0

Rule 2. If N_1 and N_2 two different numbers are divisible by D individually then their sum (*i.e.*, $N_1 + N_2$) and their difference ($N_1 \sim N_2$) is also divisible by D.

Rule 3. If a number N_1 is divisible by N_2 and N_2 is divisible by N_3 then N_1 must be divisible by N_3.

Rule 4. If two numbers N_1 and N_2 are such that they divide mutually each other it means they are same *i.e.*, $N_1 = N_2$ only.

HOW TO CHECK THE DIVISIBILITY

We have certain rules to check the divisibility by certain integral numbers. With the help of the following rules it has become easier to know whether a certain number is divisible or not by a particular number without actually dividing the number.

Divisibility by 2

Any integral number whose last digit (*i.e.*, unit digit)is even or in other words the unit digit is divisible by 2. It means any number whose last digit is either 0, 2, 4, 6 or 8, then this number must be divisible by 2.

e.g., 395672, 132, 790, 377754, etc.

Divisibility by 4

If the number formed by last two digits of the given number is divisible by 4 then the actual number must be divisible by 4. *i.e.*, the last two digits of a number can be 00, 04, 08, 12, 16, 20, 24, 28, 32, ..., 96.

e.g., 33932, 7958956, 2300, 1996, 3819764280 etc.

Divisibility by 8

If the number formed by last three digits of the given number is divisible by 8 then the actual number must be divisible by 8 *i.e.*, the last three digits of the divisible number can be 000, 008, 016, 024, 032, 040, ..., 096, 104, ..., 992.

e.g., 8537000, 9317640, 3945080, 23456008, 12345728, 3152408 etc.

Divisibility by 16

If the number formed by last four digits of the given number is divisible by 16 then the actual number must be divisible by 16 *i.e.*, the last 4 digits of the divisible number can be 0000, 0016, 0032, 0048, 0064, 0080, 0096, 0112, 0128, 0144, 0160, ..., 0960, 0976, ..., 0992, ..., 1600, ..., 9984.

Divisibility by 32, 64, 128, ... can be checked just by checking the last 5, 6, 7, ... digits number formed from the given number as in the above cases.

Divisibility by 3

If the sum of the digits of the given number is divisible by 3 then the actual number will also be divisible by 3.

e.g., 12375 is divisible by 3 since the sum of digits $1+2+3+7+5=18$ is divisible by 3.

Similarly 63089154 is also divisible by 3 since the sum of its digits $6+3+0+8+9+1+5+4=36$ is divisible by 3.

Divisibility by 9

If the sum of the digits of the given number is divisible by 9 then the actual number will also be divisible by 9.

e.g., 7329753 is divisible by 9, since

$7+3+2+9+7+5+3=36$ is divisible by 9.

Similarly the divisibility by 27, 81, 243, ... can be checked.

Divisibility by 5

A number is divisible by 5 if and only if the last (*i.e.*, unit) digit is either 0 or 5.

e.g., 5, 10, 15, 20, 25, 30, 35, ..., 275, 365, ..., 995, 70000, 438915 etc.

Divisibility by some special numbers *e.g.*, 7, 11, 13, 17, 19, 23, etc.

Why are these numbers treated differently for checking the divisibility? Since, if we multiply these numbers by any other number (except 10 or multiples of 10) these numbers can never be divisible by 10. So to make the process easier we bring the given number (*i.e.*, divisor) closer to the multiples of 10 with the difference of 1 (*e.g.*, 9 or 11, 19 or 21, 29 or 31, 39 or 41 etc).

Now if the number is one less than the multiples of 10 (*i.e.*, 9, 19, 29, 39, ...) we need to increase it by 1 to make it

Scanned by CamScanner

yoursmahboob.wordpress.com

further multiple of 10. Hence we call it "one more" osculator and the value of multiple of 10 is called the value of "one more" osculator.

Similarly if the number is one more than the multiple of 10 (*i.e.*, 11, 21, 31, 41, ..., etc) we need to decrease it by 1 to make it the multiple of 10. So we call it 'negative' osculator and the value of multiple of 10 is the value of 'negative' osculator.

e.g., The given number is 7 (divisor number) then we bring it closer to the multiple of 10 with the difference of 1, then

$$7 \times 3 = 21 = 20 + 1$$

$$\Rightarrow \quad 20 = 21 - 1 = (2 \times 10) \qquad \ldots(1)$$

Now in the above expression 2 is the multiple of 10 and is known as the negative osculator for 7.

Now let us consider the next example of 13 and then bring it closer to the multiples of 10 with a difference of 1. Thus

$$13 \times 3 = 39$$

and $$39 + 1 = 40 = (4 \times 10) \qquad \ldots(2)$$

In the above expression 4 is the multiple of 10 and 4 is the value of 'one more' osculator.

Similarly for 17 we can find the osculator as

$$17 \times 3 = 51 = 50 + 1$$

So, $$50 = 51 - 1 = (\underline{5} \times 10)$$

Here 5 is the negative osculator for 17.

Similarly for 31 the osculator is negative and the value of negative osculator is 3.

$$\because \quad 31 = 30 + 1$$

$$\Rightarrow \quad 30 = 31 - 1 \quad \Rightarrow \quad (3 \times 10)$$

Now we will apply the osculator techniques to check the divisibility by 7, 11, 13, 17, 19, ... etc.

Divisibility by 7

To check the divisibility of a number by 7 we apply the following method. Let the number be 133.

Step 1. $133 \Rightarrow \underline{13} - \underline{3} \times 2 = 13 - 6 = 7$

Since 7 is divisible by 7, so the given number 133 will also be divisible by 7.

In the above process 2 is multiplied with the last digit is the negative osculator for 7, which I have earlier discussed.

EXAMPLE 1 *Check whether 1071 is divisible by 7.*

SOLUTION **Step 1.** $\underline{1071} \Rightarrow 107 - 1 \times 2 = 105$

Step 2. $\underline{105} \Rightarrow \underline{10} - 5 \times 2 = 0$

Since 0 is divisible by 7 hence the given number 1071 is also divisible by 7.

EXAMPLE 2 *Check whether 939715 is divisible by 7.*

SOLUTION **Step 1.** $\underline{939715} \Rightarrow 93971 - 5 \times 2 = 93961$

Step 2. $\underline{93961} \Rightarrow 9396 - 1 \times 2 = 9394$

Step 3. $\underline{9394} \Rightarrow 939 - 4 \times 2 = 931$

Step 4. $\underline{931} \Rightarrow 93 - 1 \times 2 = 91$

Step 5. $\underline{91} \Rightarrow 9 - 1 \times 2 = 7$

Hence, it is divisible by 7.

NOTE 1. In all the above examples we have to multiply the last digit by the appropriate osculator and then this value will be subtracted from the number formed by the rest digits of the number and this process is continued till you know that the resultant value is divisible by 7. Even you can stop the process in midway when you guess that the obtained value is divisible by 7. For example in the latest problem (example-3) we can stop at step 4 if we know that the 91 is divisible by 7 also we can stop even at step 3 if we have any idea that 931 is divisible by 7.

2. Remember that if the operating osculator is "one more" osculator then we add the product of last digit and one more osculator in the number formed by the rest digit else. We subtract if the operating osculator is 'negative' osculator.

Divisibility by 13

EXAMPLE 1. *Check whether 2366 is divisible by 13.*

SOLUTION **Step 1.** $\underline{2366} \Rightarrow 236 + 6 \times 4 = 260$

[Since, the osculator for 13 is 4 and it is 'one more' osculator. So we use addition]

Step 2. $\underline{260} \Rightarrow 26 + 0 \times 4 = 26$

Since 26 (or 260) is divisible by 13 hence 2366 is also divisible by 13.

EXAMPLE 2. *Check whether 377910 is divisible by 13.*

SOLUTION **Step 1.** $\underline{377910} \Rightarrow 37791 + 0 \times 4 = 37791$

Step 2. $\underline{37791} \Rightarrow 3779 + 1 \times 4 = 3783$

Step 3. $\underline{3783} \Rightarrow 378 + 3 \times 4 = 390$

Step 4. $\underline{390} \Rightarrow 39 + 0 \times 4 = 39$

Since 39 is divisible by 39. So 377910 is also divisible by 13.

Divisibility by 17

EXAMPLE 1 *Find out whether 323 is divisible by 17.*

SOLUTION **Step 1.** $\underline{32}\,\underline{3} \Rightarrow \underline{32} - 3 \times 5 = 17$

[$\because$ 5 is the negative osculator of 17]

Therefore 323 is divisible by 17.

EXAMPLE 2 *Checkout that 12716 is divisible by 17 or not.*

SOLUTION **Step 1.** $\underline{1271}\,\underline{6} \Rightarrow 1271 - 6 \times 5 = 1241$

$\underline{1241}\,\underline{1} \Rightarrow 124 - 1 \times 5 = 119$

$\underline{119} \Rightarrow 11 - 9 \times 5 = -34$

so we can conclude that 12716 is divisible by 17. Since -34 and 119 both are simply visible that these two numbers are divisible by 17.

As I have already mentioned that you can stop your checking process as soon as you can get a number which is easy to know that the particular number is divisible by the given divisor or not. Further you should know that every resultant value in the right hand side might be divisible by the divisor whether you readily recognise it or not.

Scanned by CamScanner

yoursmahboob.wordpress.com

Divisibility by 19

EXAMPLE 1 *Find out whether 21793 is divisible by 19.*

SOLUTION **Step 1.** $\underline{2179}\ \underline{3} \Rightarrow 2179 + 3 \times 2 = 2185$

[$\because$ 2 is the "one more" osculator of 19]

Step 2. $\underline{218}\ \underline{5} \Rightarrow 218 + 5 \times 2 = 228$

Step 3. $\underline{22}\ \underline{8} \Rightarrow 22 + 8 \times 2 = 38$

Hence 21793 is divisible by 19.

Shortcut rule for the divisibility by 7, 11 and 13 : A number can be divisible by 7, 11 or 13 if and only if the difference of the number formed by the last three digits and the number formed by the rest digits is divisible by 7, 11 or 13 respectively.

For example we have to check that 139125 is divisible by 7 or not.

So we take the difference as given below

$$139 - 125 = 14$$

Since, the difference is divisible by 7. Hence the given number is also divisible by 7.

EXAMPLE 1 *Check whether 12478375 is divisible by 13 or not.*

SOLUTION **Step 1.** $12478 - 375 = 12103$

Step 2. $12 - 103 = -91$

Since 91 is divisible by 13 hence 12478375 is also divisible by 13.

Divisibility by 11

A number is divisible by 11 if the difference between the sum of the digits at odd places and sum of the digits at even places is equal to zero or multiple of 11 (*i.e.*, 11, 22, 33 etc.)

For example : 57945822

Here sum of the digits at odd places $= 2 + 8 + 4 + 7 = 21$

and sum of the digits at even places $= 2 + 5 + 9 + 5 = 21$

and thus the difference $= 0\ (= 21 - 21)$

Hence 57945822 is divisible by 11.

Divisibility by Composite Numbers *e.g.*, 4, 6, 8, 10, 12, 14, 15 etc.

Divisibility by 6

A number is divisible by 6 only when it is divisible by 2 and 3 both. So first of all we see that the number is even or not then we check for the divisibility by 3.

Divisibility by 10

A number is divisible by 10 if and only if when it is divisible by both 2 and 5. So it can be easily observed that a number is divisible by 10 must ends up with zero(s) at the right end (*i.e.*, last digits) of itself.

NOTE Thus we can say that if there are '*n*' zeros at the end of the given number the number can be divided by 10^n means 10000... *n* zeros.

Divisibility by 12

A number is divisible by 12 only when it is divisible by 4 and 3 both at the same time. So first of all check the divisibility by 4 then by 3

Divisibility by 15

A number is divisible by 15 only when it is divisible by 3 and 5 both simultaneously. So first of all check the number by 5 then by 3.

Thus we can conclude that any number which is divisible by a composite number, as mentioned above, must be divisible by all its factors whose L.C.M. is the given divisor.

INTRODUCTORY EXERCISE-1.1

1. What is the largest possible two digit number by which 2179782 can be divided ?
   (a) 88 (b) 50
   (c) 66 (d) 99
2. At least which number must be subtracted from 9999999 so that it will become the multiple of 125?
   (a) 124 (b) 4
   (c) 24 (d) none of these
3. A number of the form $10^n - 1$ is always divisible by 11 for every *n* is a natural number, when :
   (a) *n* is odd (b) *n* is prime
   (c) *n* is even (d) can't say
4. Out of the following numbers which is divisible by 132?
   (a) 31218 (b) 78520
   (c) 38148 (d) 52020
5. If 653*xy* is divisible by 80 then the value of $x + y$ is :
   (a) 2 (b) 3
   (c) 4 (d) 6
6. The value of *k* if *k*35624 is divisible by 11 :
   (a) 2 (b) 5
   (c) 7 (d) 6
7. If 42573*k* is divisible by 72 then the value of *k* is :
   (a) 4 (b) 5
   (c) 6 (d) 7
8. How many numbers between 1 and 1000 are divisible by 7?
   (a) 777 (b) 142
   (c) 143 (d) none of these
9. How many numbers between 55 and 555 including both the extreme values are divisible by 5?
   (a) 100 (b) 111
   (c) 101 (d) none of these
10. How many numbers are there from 100 to 200 ?
    (a) 100 (b) 101
    (c) 99 (d) none of these
11. How many numbers are divisible by 3 in the set of numbers 300, 301, 302, ..., 499, 500?
    (a) 200 (b) 66
    (c) 67 (d) none of these
12. How many numbers are there between 200 and 800 which are divisible by both 5 and 7?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 35 (b) 16
(c) 17 (d) can't be determined

13. In the above question total numbers in the set of numbers $S = \{200, 201, ..., 800\}$ which are either divisible by 5 or by 7 is :
(a) 210 (b) 190
(c) 199 (d) can't be determined

14. How many numbers are there in the set $S = \{200, 201, 202, ..., 800\}$ which are divisible by neither of 5 or 7?
(a) 411 (b) 412
(c) 410 (d) none of these

15. Total number of numbers lying in the range of 1331 and 3113 which are neither divisible by 2, 3 or 5 is :
(a) 477 (b) 594
(c) 653 (d) none of these

16. Atleast what number must be subtracted from 434079 so that it becomes divisible by 137 ?
(a) 173 (b) 63
(c) 97 (d) can't be determined

17. In the above question, at least what number be added to 434079, so that it will become divisible by (or multiple of) 137 ?
(a) 97 (b) 74
(c) 75 (d) none of these

18. Which one number is closest to 193 which is divisible by 18 is :
(a) 180 (b) 195
(c) 198 (d) 108

19. The product of two numbers $ab7$ and $cd5$ could be, where $ab7$ and $cd5$ are individually three digit numbers :
(a) 8135 (b) 79236
(c) 8735255 (d) none of these

20. When a 3 digit number 984 is added to another 3 digit number $4p3$, we get a four digit number $13q7$, which is divisible by 11. The value of $p + q$ is :
(a) 10 (b) 11
(c) 12 (d) 13

21. When a number divided by 9235, we get the quotient 888 and the remainder 222, such a least possible number is :
(a) 820090 (b) 8200920
(c) 8200680 (d) none of these

22. The number which when divided by 33 is perfectly divisible and closer to 1000 is :
(a) 990 (b) 999
(c) 1023 (d) can't be determined

23. A number which when divided by 32 leaves a remainder of 29. If this number is divided by 8 the remainder will be :
(a) 0 (b) 1
(c) 5 (d) 3

24. A number when divided by 5 leaves a remainder of 4, when the double (*i.e.*, twice) of that number is divided by 5 the remainder will be :
(a) 0 (b) 1
(c) 3 (d) can't be determined

25. When a number 'N' is divided by a proper divisor 'D' then it leaves a remainder of 14 and if the thrice of that number *i.e.*, $3N$ is divided by the same divisor D, the remainder comes out to be 8. Again if the 4 times of the same number *i.e.*, '$4N$' is divided by D the remainder will be :
(a) 35 (b) 22
(c) 5 (d) can't be determined

26. A number when divided by 5 gives a number which is 8 more than the remainder obtained on dividing the same number by 34. Such a least possible number is :
(a) 175 (b) 75
(c) 680 (d) does not exist

27. When a natural number divided by a certain divisor, we get 15 as a remainder. But when the 10 times of the same number is divided by the same divisor we get 6 as a remainder. The maximum possible number of such divisors is :
(a) 6 (b) 7
(c) 15 (d) can't be determined

28. A certain number 'C' when divided by N_1 it leaves a remainder of 13 and when it is divided by N_2 it leaves a remainder of 1, where N_1 and N_2 are the positive integers. Then the value of $N_1 + N_2$ is, if $\frac{N_1}{N_2} = \frac{5}{4}$:
(a) 36
(b) 27
(c) 54
(d) can't be determined uniquely

29. In the above problem the value of c is :
(a) $50 < c < 100$ (b) any multiplied 11
(c) $20 < c < 50$ (d) can't be determined

30. In how many parts a rod of length 19.5 m can be broken of equal length of 65 cm?
(a) 20 (b) 30
(c) 3 (d) 130

31. A six digit number which is consisting of only one digits either 1, 2, 3, 4, 5, 6, 7, 8 or 9, e.g., 111111, 222222... etc. This number is always divisible by :
(a) 7 (b) 11
(c) 13 (d) all of these

32. The maximum possible difference between the 4 digit numbers formed by using the 4 different digits 1, 2, 3, 5 is :
(a) 4086 (b) 5076
(c) 4386 (d) 3242

33. The sum of all digits except the unity that can be substituted at the place of k inorder to be divisible by 8 in the number $23487k2$:
(a) 5 (b) 14
(c) 9 (d) none of these

34. A certain number N when multiplied by 13, the resultant values consists entirely of sevens. The value of N is :
(a) 123459 (b) 58829
(c) 59829 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

SQUARE TABLE

1	1	21	441	41	1681	61	3721	81	6561
2	4	22	484	42	1764	62	3844	82	6724
3	9	23	529	43	1849	63	3969	83	6889
4	16	24	576	44	1936	64	4096	84	7056
5	25	25	625	45	2025	65	4225	85	7225
6	36	26	676	46	2116	66	4356	86	7396
7	49	27	729	47	2209	67	4489	87	7569
8	64	28	784	48	2304	68	4624	88	7744
9	81	29	841	49	2401	69	4761	89	7921
10	100	30	900	50	2500	70	4900	90	8100
11	121	31	961	51	2601	71	5041	91	8281
12	144	32	1024	52	2704	72	5184	92	8464
13	169	33	1089	53	2809	73	5329	93	8649
14	196	34	1156	54	2916	74	5476	94	8836
15	225	35	1225	55	3025	75	5625	95	9025
16	256	36	1296	56	3136	76	5776	96	9216
17	289	37	1369	57	3249	77	5929	97	9409
18	324	38	1444	58	3364	78	6084	98	9604
19	361	39	1521	59	3481	79	6241	99	9801
20	400	40	1600	60	3600	80	6400	100	10,000

SQUARING

Dear students the importance of squaring of numbers is somewhat crucial particularly in the context of CAT. I think that initially you may not consider the importance of squaring but later on you have to delve deep into the basics of the squaring because most of the calculative problems can be solved easily if you learn the squares just upto 100. Get surprised! No there will be no any difficulty in learning these squares, since I have some breakthrough techniques to find the square of any number faster than any one and I can consider that you will find no where these methods and their efficacy as in this book. Now we will proceed step by step toward our learning goal. Last but not the least you will consciously observe the "square table" you will find some peculiarities,as these peculiarities of the numbers (*i.e.*, their distinct nature) help us in remembering for long time and making a network with other numbers.

1. Square of the numbers whose unit (*i.e.*, last) digit is zero (0) : Any number whose last digit is zero, we double the number of zeros at the right side of the number and in the left of there zeros we write the square of the non-zero numbers (or rest digits) which is in the left of the zero(s)

e.g., square of 40 :

$(40)^2 \Rightarrow$ **Step 1.** 00

Step 2. $4^2 = 16$

Step 3. 1600

Similarly square of 700 :

$(700)^2 \Rightarrow$ **Step 1.** 0000

Step 2. $(7)^2 = 49$

Step 3. 490000

Square of 13000 :

$(13000)^2 \Rightarrow$ **Step 1.** 000000

Step 2. $(13)^2 = 169$

Step 3. 169000000

Square of 21000 :

$(21000)^2 \Rightarrow$ **Step 1.** 000000

Step 2. $(21)^2 = 441$

Step 3. 441000000

2. Square of the numbers whose unit digit is 5 : Any number whose unit digit is 5. We write 25 in the rightmost in place of 5, then we multiply the rest (left digits to the 5 of original number) number with its successive number (i,e, one more than the previous one)

For example : (i) The square of 35 :

$(35)^2 \Rightarrow$ **Step 1.** 25

Step 2. $3 \times (3+1) = 12$

Step 3. 1225

(ii) The square of 65 :

$(65)^2 \Rightarrow$ **Step 1.** 25

Step 2. $6 \times (6+1) = 42$

Step 3. 4225

(iii) The square of 75 :

$(75)^2 \Rightarrow$ **Step 1.** 25

Step 2. $7 \times (7+1) = 56$

Step 3. 5625

(iv) The square of 125 :

$(125)^2 \Rightarrow$ **Step 1.** 25

Step 2. $12 \times (12+1) = 156$

Step 3. 15625

Scanned by CamScanner

yoursmahboob.wordpress.com

(v) The square of 1405

Step 1. 25

Step 2. $140 \times (140+1) = 19740$

Step 3. 1974025

(vi) The square of 139005

$(139005)^2 \Rightarrow$ **Step 1.** 25

Step 2. $13900 \times (13900+1) = 193223900$

Step 3. 19322390025

(vii) The square of 155 :

$(155)^2 \Rightarrow$ **Step 1.** 25

Step 2. $15 \times (15+1) = 240$

Step 3. 24025

3. (i) Square of the numbers ending with the digit 1 : These numbers are very easy to solve. To get the square of any such number just write the square of the previous number and then add the previous number and the number whose square is being asked.

For example the square of 21

$$(21)^2 = (20)^2 + (20+21) = 441$$

Similarly, $(31)^2 = (30)^2 + (30+31) = 961$

and $(41)^2 = (40)^2 + (40+41) = 1681$

and $(81)^2 = (80)^2 + (80+81) = 6561$

and $(131)^2 = (130)^2 + (130+131)$

$= 16900 + 261 = 17161$

and $(151)^2 = (150)^2 + (150+151)$

$= 22500 + 301 = 22801$

and $(1111)^2 = (1110)^2 + (1110+1111)$

$= (1110)^2 + 2221$

$= 1232100 + 2221 = 1234321$

(ii) Square of the numbers whose unit digit is 9 : It is very similar to the previous case. The difference is that here we have to subtract instead of addition. For example the square of 39

$$(39)^2 = (40)^2 - (39+40)$$

$$= 1600 - 79 = 1521$$

Similarly, $(49)^2 = (50)^2 - (49+50)$

$= 2500 - 99 = 2401$

and $(89)^2 = (90)^2 - (89+90)$

$= 8100 - 179 = 7921$

and $(139)^2 = (140)^2 - (139+140)$

$= 19600 - 279 = 19321$

and $(249)^2 = (250)^2 - (249+250)$

$= 62500 - 499 = 62001$

NOTE In the case of unit digit of 9, we subtract from the base square because base is higher than the number whose square is to be calculated.

(iii) Square of the numbers whose last digit is 2 or 8 :

For example $(52)^2 = (50)^2 + 2(50+52)$

$= 2500 + 204 = 2704$

Similarly, $(112)^2 = (110)^2 + 2(110+112)$

$= 12100 + 444 = 12544$

and $(38)^2 = (40)^2 - 2(38+40)$

$= 1600 - 156 = 1444$

and $(88)^2 = (90)^2 - 2(88+90)$

$= 8100 - 356 = 7744$

(iv) Square of the numbers whose unit digit is 3 or 7 :

For example : $(23)^2 = (20)^2 + 3(20+23)$

$= 400 + 129 = 529$

Similarly, $(53)^2 = (50)^2 + 3(50+53)$

$= 2500 + 309 = 2809$

and $(123)^2 = (120)^2 + 3(120+123)$

$= 14400 + 729 = 15129$

and $(47)^2 = (50)^2 - 3(47+50)$

$= 2500 - 291 = 2209$

and $(137)^2 = (140)^2 - 3(137+140)$

$= 19600 - 831 = 18769$

and $(2347)^2 = (2350)^2 - 3(2347+2350)$

$= 5522500 - 4691 = 5517809$

(v) Square of the numbers which ends with 4 or 6 :

For example : $(34)^2 = (30)^2 + 4(30+34)$

$= 900 + 256 = 1156$

or $(34)^2 = (35)^2 - (34+35)$

$= 1225 - 69 = 1156$

Similarly, $(36)^2 = (35)^2 + (35+36)$

$= 1225 + 71 = 1296$

and $(126)^2 = (125)^2 + (125+126)$

$= 15625 + 251 = 15876$

In general square of any number can be found by using the square of any convenient number as base square *e.g.*, the numbers whose unit digit is either 0 or 5, since the square of these numbers is easy to find and learn. However we can calculate the square by considering any base square. For example if

$$(32)^2 = (30)^2 + 2(30+32) = 1024$$

or $(32)^2 = (31)^2 + (30+31)$

$= 961 + 61 = 1024$

or $(32)^2 = (33)^2 - (32+33)$

$= 1089 - 65 = 1024$

Scanned by CamScanner

yoursmahboob.wordpress.com

or $(32)^2 = (35)^2 - 3(32+35)$

$= 1225 - 201 = 1024$

Now, it can be generalized as :

If N is the number whose square is to be calculated and B is the base and d is difference between N and B then

$(N)^2 = (B)^2 + d(B+N)$ when $B < N$

or $(N)^2 = B^2 - d(B+N)$ when $B > N$

Properties of Squares

(i) If the unit digit of the number is zero then the unit digit of the square of this number will also be zero and the number of zeros will be double in the square than that of its root.

e.g., $(60)^2 = 3600$, $(130)^2 = 16900$

(ii) If the unit digit of the number is 5 then the unit digit of its square is also 5 and the number formed by last two digits is 25.

e.g., $(35)^2 = 1225$, $(45)^2 = 2025$, $(55)^2 = 3025$ etc.

(iii) If the unit digit of any number is 1 or 9 then the unit digit of the square of its number is always 1.

e.g., $(71)^2 = 5041$, $(31)^2 = 961$, $(19)^2 = 361$

(iv) If the unit digit of any number is 2 or 8 then the unit digit of the square of its number is always 4.

(v) If the unit digit of any number is 3 or 7 then the unit digit of its square is always 9.

e.g., $(23)^2 = 529$, $(27)^2 = 729$

(vi) If the unit digit of any number is 4 or 6 then the unit digit of its square is always 6.

e.g., $(26)^2 = 676$, $(24)^2 = 576$,

$(14)^2 = 196$, $(16)^2 = 256$ etc.

(vii) The square of any number is always positive irrespective of the nature of the given number.

Remember :

(a) The numbers with unit digit 0, 1, 5 and 6 always give the same unit digits respectively, on squaring.

(b) 2, 3, 7 and 8 never appear as unit digit in the square of a number.

Perfect Square : The square of any natural number is known as perfect square *e.g.*, 1,4, 9, 16, 25, 36, 49, 64, 81, 100, 121, 144, ... etc. are the squares of 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, ... etc.

SQUARE ROOT

A number n is called the square root of a number $n^2 = (n \times n)$ where n^2 is obtained by multiplying the number n with itself only once. The symbol for square root is '$\sqrt{\ }$'.

For example the square root of 4 *i.e.*, $\sqrt{4} = 2$, and $\sqrt{9} = 3$, $\sqrt{25} = 5$ etc.

Generally there are two methods for finding the square root :

(i) Prime Factorisation method

(ii) Division method

(i) Factorisation Method : In this method first we find out the prime factors and then we paired them as given below.

EXAMPLE 1 *Find the square root of* 3600.

SOLUTION The factors of 3600

$= \underline{2 \times 2} \times \underline{2 \times 2} \times \underline{3 \times 3} \times \underline{5 \times 5}$

So the square root of 3600 *i.e.*,

$\sqrt{3600} = 2 \times 2 \times 3 \times 5$

$= 60$

2	3600
2	1800
2	900
2	450
5	225
5	45
3	9
3	3
	1

EXAMPLE 2 *Find the square root of* 144.

SOLUTION Factors of $144 = \underline{2 \times 2} \times \underline{2 \times 2} \times \underline{3 \times 3}$

So $\sqrt{144} = 2 \times 2 \times 3$

$\sqrt{144} = 12$

2	144
2	72
2	36
2	18
3	9
3	3
	1

EXAMPLE 3 *Find the square root of* 10404.

SOLUTION The factors of 10404

$= \underline{2 \times 2} \times \underline{3 \times 3} \times \underline{17 \times 17}$

$\therefore \sqrt{10404} = 2 \times 3 \times 17$

or $\sqrt{10404} = 102$

2	10404
2	5202
3	2601
3	867
17	289
17	17
	1

(ii) Division Method : In this method first of all we make pairs from the right side towards left and then solve as given below.

EXAMPLE 1 *Find the square root of* 3600.

SOLUTION

	60
6	36 00
6	36
120	00 00
0	00 00

$\therefore \sqrt{3600} = 60$

EXAMPLE 2 *Find the square root of* 10404.

SOLUTION

	102
1	1 04 04
1	1
202	0 04 04
02	4 04
	× ×

$\therefore \sqrt{10404} = 102$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *Find the square root of 15876.*

SOLUTION

	126
1	1 58 76
1	1
22	58
2	44
246	1476
6	1476
	×

$\therefore \quad \sqrt{15876} = 126$

EXAMPLE 4. *Find the square root of 120409.*

SOLUTION

	347
3	12 04 09
3	9
64	304
4	256
687	4809
7	4809
	×

$\therefore \quad \sqrt{120409} = 347$

EXAMPLE 5 *Find the square root of 5793649.*

SOLUTION

	2407
2	5 79 36 49
2	4
44	179
4	176
4807	33649
07	33649
	×

$\therefore \quad \sqrt{5793649} = 2407$

Did you know If $(11)^2 = 121$ then $(101)^2 = 10201$
$(21)^2 = 441$ then $(201)^2 = 40401$ and so on...
If $(11)^2 = 121$ then $(1001)^2 = 1002001$
$(31)^2 = 961$ then $(3001)^2 = 9006001$
$(12)^2 = 144$ then $(1002)^2 = 1004004$ and so on
Go in depth and find the limitation of this logic ...

Did you know
$1^2 = 1$
$11^2 = 121$
$111^2 = 12321$
$1111^2 = 1234321$
$11111^2 = 123454321$
$111111^2 = 12345654321$
... ...
... ...
... ...

INTRODUCTORY EXERCISE-1.2

1. The square root of 6280036 is :
   (a) 1308 (b) 2903
   (c) 2506 (d) none of these
2. The square root of 1296 is :
   (a) 33 (b) 44
   (c) 34 (d) 36
3. The square root of 7744 is :
   (a) 94 (b) 88
   (c) 77 (d) none of these
4. The square root of 56169 is :
   (a) 359 (b) 323
   (c) 227 (d) none of these
5. The square root of 1238578 is :
   (a) 3254 (b) 3724
   (c) 3258 (d) none of these
6. The least number by which we multiply to the 11760, so that we can get a perfect square number :
   (a) 2 (b) 3
   (c) 5 (d) none of these
7. In the above question, by which least possible number we divide to the 11760 so the resultant number becomes a perfect square :
   (a) 3 (b) 15
   (c) 7 (d) can't be determined
8. The least possible positive number which should be added to 575 to make a perfect square number is :
   (a) 0 (b) 1
   (c) 4 (d) none of these
9. The least possible number which must be subtracted from 575 to make a perfect square number is :
   (a) 5 (b) 50
   (c) 46 (d) 37
10. The square of a number 'A' is the sum of the square of other two numbers 'B' and 'C'. Where $5B = 12C$ and B, C are positive numbers. The least possible positive value of A is :
    (a) 10 (b) 12
    (c) 13 (d) 16
11. Lieutenant Kalia when arranged all his 1500 soldiers in such a way that the number of soldiers in a line were the same as there were the number of lines. So he was left with 56 soldiers, who were not a part of this arrangement. The number of lines in this arrangement is :
    (a) 44 (b) 36
    (c) 38 (d) none of these
12. $\sqrt{289} \div \sqrt{x} = \frac{1}{5}$, then the value of x is :
    (a) $\frac{17}{25}$ (b) $\frac{34}{35}$
    (c) 235 (d) 7225
13. Out of the following statements which one is incorrect?
    (a) $\sqrt{5184} = 72$ (b) $\sqrt{15625} = 125$
    (c) $\sqrt{1444} = 38$ (d) $\sqrt{1296} = 34$
14. If $2 * 3 = \sqrt{13}$ and $3 * 4 = 5$, then the value of $5 * 12$ is :
    (a) 17 (b) $\sqrt{29}$
    (c) 21 (d) 13
15. If $a * b * c = \sqrt{\frac{(a+2)(b+3)}{(c+1)}}$, then the value of $(6 * 15 * 3)$ is :
    (a) 6
    (b) 3
    (c) 4
    (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

CUBE

If a number is multiplied by itself, twice, then the resultant value is called as the cube of that number. For example $n \times n \times n = n^3$, read as n cube. As most of you are aware of the ice cubes, dice and some boxes, which are the examples of cubes, so there is no problem in getting it.

If we say that what is the cube of 4 then it means

$$4^3 = 4 \times 4 \times 4 = 64$$

Similarly $7^3 = 7 \times 7 \times 7 = 343$

and $8^3 = 8 \times 8 \times 8 = 512$

But for the greater (or larger) number sometimes it becomes tedious to calculate the cube very quickly. So use a new approach to calculate the cube of larger numbers from 11 to 99. Since you can easily calculate the cubes of 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 20, 30, 40, 50, 60, 70, 80, 90 and 100 etc. So you can use it for further calculation.

The most important point which you should know that a CAT aspirant must use his brain with his own genius, because it is a test of virtual intelligence in real time. So you have to delve deep into your own mind and evolve the new techniques, and solutions as an effective manager. So think now.

Method to find cube of two digit numbers.

Step 1. Write down the cube of tens digit.

Step 2. Write down the resultant value in the same ratio as the ratio of tens and unit digit in four terms as a G.P.

Step 3. Write down twice the value obtained in the second and third term below the second and third term respectively.

Step 4. Now you can add all the numbers in the prescribed manner as given in the following examples :

NOTE While doing the addition (in step 4) subscripts should be treated as a "carryover" for the next term.

EXAMPLE 1 $(11)^3 \Rightarrow$ **Step 1.** $1^3 = 1$

Step 2. 1 1 1 1

Step 3. 1 1 1 1

$+2\ 2$

Step 4. 1 3 3 1

$\therefore (11)^3 = 1331$

EXAMPLE 2 $(12)^3 \Rightarrow$ **Step 1.** $1^3 = 1$

Step 2. 1 2 4 8

Step 3. 1 2 4 8

$4\ 8$

Step 4. 1 7 2 8

$\therefore (12)^3 = 1728$

EXAMPLE 3 $(13)^3 \Rightarrow$ **Step 1.** $1^3 = 1$

Step 2. 1 3 9 27

Step 3. 1 3 9 27

$6\ 18$

Step 4. $2\ \ 1\ \ {}_2 9\ \ {}_2 7$

$\therefore (13)^3 = 2197$

EXAMPLE 4 $(25)^3 \Rightarrow$ **Step 1.** $2^3 = 8$

Step 2. 8 20 50 125

Step 3. 8 20 50 125

$40\ 100$

Step 4. $15\ \ {}_7 6\ \ {}_{16} 2\ \ {}_{12} 5$

$\therefore (25)^3 = 15625$

EXAMPLE 5 $(26)^3 \Rightarrow$ **Step 1.** $2^3 = 8$

Step 2. 8 24 72 216

Step 3. 8 24 72 216

$+\ 48\ 144$

Step 4. $17\ \ {}_9 5\ \ {}_{23} 7\ \ {}_{21} 6$

$\therefore (26)^3 = 17576$

EXAMPLE 6 $(27)^3 \Rightarrow$ **Step 1.** $2^3 = 8$

Step 2. 8 28 98 343

Step 3. 8 28 98 343

$+\ 56\ 196$

Step 4. $19\ \ {}_{11} 6\ \ {}_{32} 8\ \ {}_{34} 3$

$\therefore (27)^3 = 19683$

EXAMPLE 7 $(53)^3 \Rightarrow$ **Step 1.** $5^3 = 125$

Step 2. 125 75 45 27

Step 3. 125 75 45 27

$+\ 150\ 90$

Step 4. $148\ \ {}_{23} 8\ \ {}_{13} 7\ \ {}_2 7$

$\therefore (53)^3 = 148877$

EXAMPLE 8 $(67)^3 \Rightarrow$ **Step 1.** $(6)^3 = 216$

Step 2. 216 252 294 343

Step 3. 216 252 294 343

$+\ 504\ 588$

Step 4. $300\ \ {}_{84} 7\ \ {}_{91} 6\ \ {}_{34} 3$

$\therefore (67)^3 = 300763$

EXAMPLE 9 $(94)^3 \Rightarrow$ **Step 1.** $(9)^3 = 729$

Step 2. 729 324 144 64

Step 3. 729 324 144 64

$+\ 648\ 288$

Step 4. $830\ \ {}_{101} 5\ \ {}_{43} 8\ \ {}_6 4$

$\therefore (94)^3 = 830584$

EXAMPLE 10 $(88)^3 \Rightarrow$ **Step 1.** $(8)^3 = 512$

Step 2. 512 512 512 512

Step 3. 512 512 512 512

$+\ 1024\ 1024$

Step 4. $681\ \ {}_{169} 4\ \ {}_{158} 7\ \ {}_{51} 2$

$\therefore (88)^3 = 681472$

EXAMPLE 11 $(55)^3 \Rightarrow$ **Step 1.** $(5)^3 = 125$

Step 2. 125 125 125 125

Step 3. 125 125 125 125

$+\ 250\ 250$

Step 4. $166\ \ {}_{41} 3\ \ {}_{38} 7\ \ {}_{12} 5$

$\therefore (55)^3 = 166375$

EXAMPLE 12 $(72)^3 \Rightarrow$ **Step 1.** $(7)^3 = 343$

Step 2. 343 98 28 8

Step 3. 343 98 28 8

$+\ 196\ 56$

Step 4. $373\ \ {}_{30} 2\ \ {}_8 4\ \ 8$

$\therefore (72)^3 = 373248$

Scanned by CamScanner

yoursmahboob.wordpress.com

CUBE ROOT

The cube root of a number n is expressed as $\sqrt[3]{n}$ or $(n)^{1/3}$ or in other words $n = (n)^{1/3} \times (n^{1/3}) \times (n^{1/3})$

For example cube root of 27 *i.e.*, $\sqrt[3]{27} = 3$

and $\sqrt[3]{343} = 7$ and $\sqrt[3]{64} = 4$

EXAMPLE 1 *Find the cube root of* 125.

SOLUTION $\because \quad 125 = 5 \times 5 \times 5$

$\therefore \quad \sqrt[3]{125} = 5$

5	125
5	25
5	5
	1

EXAMPLE 2 *Find the cube root of* 1728.

SOLUTION $1728 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 3 \times 3 \times 3$

$\sqrt[3]{1728} = 2 \times 2 \times 3$

$\sqrt[3]{1728} = 12$

2	1728
2	864
2	432
2	216
2	108
2	54
3	27
3	9
3	3
	1

NOTE In this method first we factorize the given numbers then we make the triplet of the factors and thus we multiply these triplets to get the cube root of the given number.

EXAMPLE 3 *On 14th November, in my school, each child received as many packs of chocolates as there were total number of the students in the school. Further, each pack of chocolates contains as many chocolates as there were the total number of packs which a child had. Total how many chocolates have been distributed among all the children of school :*

(a) 729 (b) 196
(c) 961 (d) can't be determined

SOLUTION (d) is the appropriate answer since we don't have sufficient data to calculate.

EXAMPLE 4 *In the above question if there were 8 packs of chocolates with every child. Then the total number of chocolates distributed among them was :*

(a) 512 (b) 64
(c) 256 (d) can't be determined

SOLUTION Let there are n children it means each child has n packs of chocolates and since every pack contains n chocolates. Therefore total number of chocolates

$= n \times n \times n = n^3$

Hence total number of chocolates $= (8)^3 = 512$

Thus option (a) is correct.

PRACTICE EXERCISE

1. The least possible number which we should add to 1720 to make a perfect cube number is :
(a) 0 (b) 1
(c) 8 (d) 7

2. The least positive number which is subtracted from 1369 to make it a perfect cube is :
(a) 17 (b) 38
(c) 34 (d) none of these

3. The least possible natural number by which if we multiply to the 1372, we get a perfect cube number is :
(a) 2 (b) 3
(c) 5 (d) can't be determined

4. The least possible number by which if we divide 1372, it will become a perfect cube number is :
(a) 2 (b) 7
(c) 3 (d) 4

ANSWERS

1. (c) 2. (b) 3. (a) 4. (d)

NUMBER SYSTEMS

It has been said by a great mathematician that "Mathematics is the queen of Science and Arithmetic is the queen of Mathematics." Arithmetic is the maths of numerals and digits and so the other branches of Maths are dependent upon Arithmetic. Either the counting of the currency or counting of the stars in all the ways it has been a very popular subject especially among Indians. One thing which is very well known that the great Indian Mathematician Aryabhatta has introduced '0' (zero) in the counting numbers and the whole world has adopted it. None other than computer is dead if this figure does not exist. So one can say zero has revolutionised the whole world. Here we will discuss all sorts of numbers, their properties, application besides the different number systems used widely. The following chart briefly illustrates the different kinds of numbers with their relationship.



Scanned by CamScanner

yoursmahboob.wordpress.com

Natural Numbers : The counting numbers 1, 2, 3, 4, 5, ... are called the natural numbers and are denoted by N. As you can recall that a child at his very young stage try to count the things *e.g.*, chocolates, toys, sweets etc. He just know the numbers *viz.*, 1, 2, 3, 4, 5, ... and has no idea about zero. Here we are discussing the numbers which are represented in international symbols. So $N = \{1, 2, 3, 4, 5, 6, 7...\}$

PROPERTIES OF NATURAL NUMBERS

1. **Successor :** The next natural number just after any natural number n is called its successor 'n^+' where $n^+ = n+1$ for example the successor of 2 is 3, successor of 6 is 7 etc.
2. **Closure law :** For any two natural numbers a and b
   $(a+b) \in N$ and $(a \times b) \in N$
   e.g., $3+4=7 \in N$ **and** $3 \times 4 = 12 \in N$
3. **Commutative law :** For any two natural numbers a and b
   $a+b=b+a$
   and $a \times b = b \times a$
   e.g., $5+6=6+5=11$
   and $5 \times 6 = 6 \times 5 = 30$
4. **Associative law :** For any three natural numbers
   $(a+b)+c=a+(b+c)$
   $(a \times b) \times c = a \times (b \times c)$
   e.g., $(7+8)+9=7+(8+9)=24$
   $(7 \times 8) \times 9 = 7 \times (8 \times 9) = 504$
5. **Multiplicative Identity :** 1 is the multiplicative identity of every natural number as
   $4 \times 1 = 4$
   $5 \times 1 = 5$
   $10 \times 1 = 10$
   $17 \times 1 = 17$
6. **Cancellation law :** For any three natural numbers a, b, c
   $a+b=c+b \Rightarrow a=c$
   and $a \times b = c \times b \Rightarrow a = c$
7. **Distributive law :** For any three natural numbers a, b, c
   $a \times (b+c) = a \times b + a \times c$
   but $a+(b \times c) \neq (a+b) \times (a+c)$
   e.g., $3 \times (4+5) = 3 \times 4 + 3 \times 5 = 27$

Even Numbers : All the natural numbers which are divisible by 2 are known as even numbers *e.g.*, 2, 4, 6, 8, 10, ...

Odd Numbers : All the natural numbers which are not divisible by 2 are known as 'Odd numbers' *e.g.*, 1, 3, 5, 7, ...

IMPORTANT NOTE

- Even + Even = Even
- Even − Even = Even
- Even × Even = Even
- Even ÷ Even = Even or odd

- Odd + Odd = Even
- Odd − Odd = Even
- Odd × Odd = Odd
- Odd ÷ Odd = Odd

- Even + Odd = Odd
- Even − Odd = Odd
- Even × Odd = Even
- Even ÷ Odd = Even

- Odd + Even = Odd
- Odd − Even = Odd
- Odd × Even = Even
- Odd ÷ Even = (never divisible)

- $(\text{even})^{\text{even/odd}} = \text{Even}$
- $(\text{odd})^{\text{odd/even}} = \text{Odd}$

Prime Numbers : Except 1 each natural number which is divisible by only 1 and itself is called as prime number *e.g.*, 2, 3, 5, 7, 11, 13, 17, 19, 23, 29, 31, ... etc.

- There are total 25 prime numbers upto 100
- There are total 46 prime numbers upto 200
- 2 is the only even prime number and the least prime number.
- 1 is neither prime nor composite number.
- There are infinite prime numbers.
- A list of all the prime numbers upto 100 is given below.

Table of Prime Numbers (1 – 100) :

2	11	23	31	41	53	61	71	83	97
3	13	29	37	43	59	67	73	89	
5	17			47			79		
7	19								

How to test whether a number is prime or not : To test a number n take the square root of n and consider as it is , if it is a natural number otherwise just increase the square root of it to the next natural number. Then divide the given number by all the prime numbers below the square root obtained. If the number is divisible by any of these prime numbers then it is not a prime number else it is a prime number.

EXAMPLE *Check that whether 241 is prime.*

SOLUTION When we take the square root of 241 it is approximate 15, so we consider it 16. Now we divide 241 by all the prime numbers below 16 *viz.*, 2, 3, 5, 7, 11, 13

Since 241 is not divisible by any one of the prime numbers below 16. So it is a **prime number.**

NOTE Any digit if it is written continuously 3 times, 6 times, 9 times ... etc. then it is divisible by 3
e.g., 111; 555555; 777777; 222222222; 888, 222 etc.

Co-prime Numbers : Two natural numbers are called co-prime (or relatively prime) numbers if they have no common factor other than 1 or in other words. The highest common factor *i.e.*, H.C.F. between co-prime numbers is 1. *e.g.*, (15, 16), (14, 25), (8, 9), (13, 15) etc.

NOTE It is not necessary that the numbers involved in the pair of co-primes will be prime even they can be composite numbers as seen in the above examples.

Composite Numbers : A number other than one which is not a prime number is called a composite number. It means it

Scanned by CamScanner

yoursmahboob.wordpress.com

is divisible by some other number(s) other than 1 and the number itself. *e.g.*, 4, 6, 8, 9, 10, 12, 14, 15, 16, 18, 20, 21, 22, 24, 25, 26...

- Every natural number except 1 is either prime or composite.

Trichotomy law : If there are any two natural numbers a and b then there exists one and only one relation necessarily is

(i) $a > b$ (ii) $a = b$ (iii) $a < b$

Whole Numbers : The extended set of natural numbers in which '0' is also included is called as the set of whole numbers and is denoted by $W = \{0, 1, 2, 3, 4, 5, ...\}$

- '0' (zero) is an even number

Consecutive Numbers : A series of numbers in which the next number is 1 more than the previous number or the predecessor number is 1 less than the successor or just they can be differed by 1 *e.g.*, 10, 11, 12, or 17, 18, 19, 20, 21 or 717, 718, 719, 720, 721... etc.

Perfect Number : When the sum of all the factors (including 1 but excluding the number itself) of the given number is the same number then this number is called as Perfect Number. For example 6, 28, 496, 8128, ...etc

So far only 27 perfect numbers are known.

As the factors of 28 are 1, 2, 4, 7, 14, 28

Now, $1+2+4+7+14=28$

Hence 28 is a perfect Number.

Triangular Number : A triangular number is obtained by adding the previous number to the nth position in the sequence of triangular numbers, where the first triangular number is 1. The sequence of triangular numbers is given as follows

1, 3, 6, 10, 15, 21, 28, 36, 45, 55, 66, 78, ...etc.

Integers : The extended set of whole numbers in which negative integers are also included is known as the set of integers and is denoted by

Z or $I = \{..., -4, -3, -2, -1, 0, 1, 2, 3, 4, 5, 6, ...\}$

(a) **Positive integers :** The set of integers $\{1, 2, 3, ...\}$ is known as positive integers.

(b) **Negative integers :** The set of integers $\{-1, -2, -3, -4, ...\}$ is known as negative integers.

(c) **Non-negative integers :** The set of integers $\{0, 1, 2, 3, 3....\}$ is called as non-negative integers.

(d) **Non-positive integers :** The set of integers $\{0, -1, -2, -3, ...\}$ is called as non-positive integers.

- '0' is neither positive nor negative integer.

REPRESENTATION OF THE INTEGERS ON A NUMBER LINE



All the integers (whole number, natural number etc.) can be shown on this number line, where every integer is represented by some point on the line.

It can be said that :

(a) There is no any largest or smallest integer.

(b) Every integer has a predecessor and a successor.

(c) An integer is smaller than all those integers which are on the right side of it and is greater than all those integers which are on the left side of it on the number line.

e.g., $-4 > -5, 3 > 1, 10 > -4$ etc.

or $-6 < 0, -2 < 1$ etc.

EXAMPLE 1 *Arrange the following integers in ascending order* $-3, -7, 8, 5, 0, 3, 17, -23$

SOLUTION $-23, -7, -3, 0, 3, 5, 8, 17$

EXAMPLE 2 *Arrange the following integers in descending order* $-17, 18, 15, 32, 81, -5, 87.$

SOLUTION $87, 81, 32, 18, 15, -5, -17$

Properties of Integers

1. Closure law is followed by all the integers
2. Commutative law and Associative law is not followed by all the integers for the subtraction.

e.g., $4-6 \neq 6-4$

and $(4-6)-2 \neq 4-(6-2)$

but it is valid for the addition and multiplication as

$4+6=6+4$

or $(-3)+(-2)=(-2)+(-3)$

and $4\times 6=6\times 4$

or $-3\times -2=-2\times -3$

and $(-2)+[(-3)+(-7)]=[(-2)+(-3)]+(-7)$ etc.

3. Additive identity of all the integers is zero (0) and Multiplicative identity of all the integers is 1.

e.g., $-3+0=-3, \quad 8+0=8$

and $-5\times 1=-5, \quad 7\times 1=7$ etc.

4. Additive inverse of an integer a is $-a$.

e.g. the additive inverse of 7, 8, 9, 15, $-3, -5, -6$ etc. are $-7, -8, -9, -15, 3, 5$ and 6 respectively.

5. Distributive law of multiplication over addition or subtraction

i.e., $a\times(b\pm c)=a\times b\pm a\times c$

For example: $3\times(4\pm 6)=3\times 4\pm 3\times 6$

NOTE
1. Division by zero is not defined in Mathematics.
2. Division by 1 is actually unification (not division) so it is an improper divisor.

Some important rules regarding the sign convention in mathematical operations :

(i) $(a)+(b)=+(a+b)$

$(-a)+(b)=b-a$

$(a)+(-b)=a-b$

$(-a)+(-b)=-(a+b)$

i.e., $(+)+(+)=+$

$(-)+(+)=+$ if the numerical value of $+$ is greater

Scanned by CamScanner

yoursmahboob.wordpress.com

$(-)+(+)=-$ if the numerical value of $-$ is greater

$(-)+(-)=-$

For example $(4)+(7)=11, (-3)+(8)=5$

$(-8)+(3)=-5$

$(-5)+(-3)=-8$ etc.

Similarly, $(5)-(2)=3, (2)-(5)=-3$

$(-5)-(2)=-7, (5)-(-2)=7$

$(-5)-(-2)=-3, (-2)-(-5)=3$

(ii) $a\times b=ab$ *i.e.,* $(+)\times(+)=+$

$-a\times b=-ab$ *i.e.,* $(-)\times(+)=-$

$a\times -b=-ab$ *i.e.,* $(+)\times(-)=-$

$-a\times -b=ab$ *i.e.,* $(-)\times(-)=+$

For example, $(2)\times(3)=6, (-2)\times(3)=-6, 2\times(-3)=-6$ and $(-2)\times(-3)=6$

Similarly, $\frac{8}{2}=4, \frac{-8}{2}=-4, \frac{8}{-2}=-4, \frac{-8}{-2}=4$

i.e., $\frac{(+)}{(+)}=(+), \frac{(-)}{(+)}=(-), \frac{(+)}{(-)}=(-), \frac{(-)}{(-)}=(+)$

PRACTICE EXERCISE

1. Evaluate the following

(a) $4+(-5)$ (b) $-4-(-2)$

(c) $8-(-5)$ (d) $-13+(56)$

(e) $(-94)+(-239)$ (f) $(-526)-(-217)$

(g) $7+(-5)+(-2)$ (h) $-6+(-2)-(-3)+1$

(i) 6×9 (j) $(-9)\times(-13)$

(k) -7×8 (l) $13\times(-15)$

(m) $(-3)\times(8)\times(-5)$ (n) $(-8)\times(-19)\times(-15)$

(o) $[(-6)\times(-8)]\times5$ (p) $(-18)\div6$

(q) $126\div(-14)$ (r) $-13\times(7-8)$

(s) $(-32)\div(-4)$ (t) $(-31)+(31)$

ANSWERS

(a) –1	(b) –2	(c) 13	(d) 43	(e) –333
(f) –309	(g) 0	(h) –4	(i) 54	(j) 117
(k) –56	(l) –195	(m) 120	(n) –2280	(o) 240
(p) –3	(q) –9	(r) 13	(s) 8	(t) 0

Numerical Expression : Collection of numbers connected by one or more operations of addition, subtraction, multiplication and division is called a numerical expression. It can also involve some brackets.

e.g., $7+18\div3\div1\times6$

$84-6\div2-3\times(-7)$

and $9+(-2)\times\{72\div8\}+21$ etc.

RULE OF SIMPLIFICATION OR CALCULATION

The order in which various mathematical operations must be done can be remembered with the word 'BODMAS'

Where B → Brackets

O → Off

D → Division

M → Multiplication

A → Addition

S → Subtraction

So first of all we solve the inner most brackets moving outwards. Then we perform 'of' which means multiplication then, Division, Addition and Subtraction.

- Addition and Subtraction can be done together or separately as required.
- Between any two brackets if there is no any sign of '+' or '–' it means we have to do multiplication *e.g.,*

$(7)(2)=7\times2=14$

$[3(5)+7]=15+7=22$

Brackets : They are used for the grouping of things or entities. The various kind of brackets are :

(i) '–' is known as line (or bar) bracket or vinculum

(ii) ( ) is known as parenthesis or common bracket

(iii) { } is known as curly bracket or brace.

(iv) [ ] is known as rectangular (or big) bracket.

The order of eliminating brackets is :

(i) line bracket

(ii) common bracket

(iii) curly bracket

(iv) rectangular bracket

EXAMPLE 1 *Solve the following expressions :*

(a) $3+2-1\times4\div2$ *(b)* $7\times3+8-2$

(c) $53\times2-1\times6$ *(d)* $12+(-3)+5-(-2)$

SOLUTION (a) $3+2-1\times4\div2=3+2-1\times2=3+2-2=3$

(b) $7\times3+8-2=21+8-2=27$

(c) $53\times2-1\times6=106-6=100$

(d) $12+(-3)+5-(-2)=12-3+5+2=9+7=16$

EXAMPLE 2 *Evaluate or simplify the following expression*

(a) $9-\{7-24\div(8+6\times2-16)\}$

(b) $(-3)\times(-12)\div(-4)+3\times6$

(c) $17-\{8+(2\times3-4)\}$

(d) $5\times2-[3-\{5-(7+2\text{ of }4-19)\}]$

SOLUTION (a) $9-\{7-24\div(8+6\times2-16)\}$

$=9-\{7-24\div(8+12-16)\}$

$=9-\{7-24\div4\}$

$=9-\{7-6\}=9-\{1\}=8$

(b) $(-3)\times(-12)\div(-4)+3\times6=36\div(-4)+18$

$=-9+18=9$

(c) $17-\{8\div(2\times3-4)\}=17-\{8\div(6-4)\}$

$=17-\{8\div2\}=17-\{4\}=13$

(d) $5\times2-[3-\{5-(7+2\text{ of }4-19)\}]$

$=5\times2-[3-\{5-(7+8-19)\}]$

$=10-[3-\{5-(-4)\}]$

$=10-[3-\{9\}]$

$=10-[-6]=10+6=16$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *Which one of the following options is correct in the given expressions?*

(i) $45-[28-\{37-(15-k)\}]=58$, *the value of k is :*

(a) 19 *(b)* −19
(c) −39 *(d)* *none of these*

(ii) $1+[1\div\{5+4-1\div(13\div3-1\div3)\}]$ *equal to :*

(a) 2/5 *(b)* 2
(c) 3/2 *(d)* *none of these*

(iii) $2-[3-\{6-(5\div\overline{4-3})\}]$:

(a) 0 *(b)* 1
(c) −3 *(d)* *none of these*

ANS. (i) (a), (ii) (b), (iii) (a)

EXAMPLE 4 *A student gets 4 marks for a correct answer and 1 mark is deducted for a wrong answer. If she has done 80 questions at all and she has gotten only 240 marks. The correct answers she has attempted is :*

(a) 40 *(b)* 60
(c) 64 *(d)* *can't be determined*

SOLUTION If she has done all the 80 questions correctly she must have gotten 320 (= 80 × 4) marks, but if she does one wrong answer it means she is liable to lose 5 marks (4 + 1). Thus for every wrong answer she loses 5 marks.

Now since she has lost total 80 marks (320 − 240 = 80)

This implies that she has done 16 questions wrong $\left(\because \frac{80}{5}=16\right)$. It means she has done only 64 questions (80 − 16 = 64) correctly. Hence (c) is the correct option.

Alternatively: Since she has obtained less marks than the maximum possible marks it means she must has done some questions wrong. Now, we can check through options. Let us consider option (c).

Correct answer	Wrong answers	Total questions
64	16	80
Marks for correct answers	Marks for wrong answers	Net marks
$64\times4=256$	$16\times-1=-16$	$256-16=240$

Hence the assumed option (c) is correct.

Alternatively : If she has done x question correctly it means she has done $(80-x)$ questions wrong.

So $4\times(x)-1\times(80-x)=240$

$\Rightarrow 5x-80=240$

$\Rightarrow 5x=320$

$\Rightarrow x=64$

Hence she has done 64 correct answers.

Absolute value of an integer or Modulus : The absolute value of an integer is its numerical value irrespective of its sign (or nature)

The absolute value of an integer x is written as $|x|$ and is defined as

$$|x|=\begin{cases}x \text{ if } x\geq 0\\ -x \text{ if } x<0\end{cases}$$

MODULUS (MACHINE MODEL)



It means any integer whether it is positive or negative if it is operated upon modulus, it always gives a positive integer.

for example $|-7|=7, |-4|=4$
$|3|=3$ etc.

Also, $\text{Max}\{x,-x\}=|x|$

and $-\text{Min}\{x,-x\}=|x|$

and $\sqrt{(x)^2}=|x|$

Properties of a Modulus or Mod

1. $|a|=|-a|$ 2. $|ab|=|a||b|$
3. $\left|\frac{a}{b}\right|=\frac{|a|}{|b|}$
4. $|a+b|\leq|a|+|b|$
   (The sign of equality holds only when the sign of a and b are same)
5. If $|a|\leq k \Rightarrow -k\leq a\leq k$
6. If $|a-b|\leq k \Rightarrow -k\leq a-b\leq k \Rightarrow b-k\leq a\leq b+k$

EXAMPLE 1 *Solution set of the equation* $|x-2|=5$ *is :*

(a) {3, −7} *(b)* {−3, 7}
(c) {3, 6} *(d)* *none of these*

SOLUTION $|x-2|=5 \Rightarrow x-2=5$ or $x-2=-5$

$\Rightarrow x=7$ or $x=-3$

Hence $x=\{-3, 7\}$, (b) is the correct option.

NOTE
- { } consists only the mentioned value particularly,
- ( ) does not include the extreme values
- [ ] includes the values of extremity
- ( ] includes only the highest value of extreme but not the lowest extreme value
- [ ) includes only lowest extreme value but not includes the highest extreme value.

EXAMPLE 2 *The maximum value of the expression* $27-|9x-8|$ *is:*

(a) 27 *(b)* 17 *(c)* 44 *(d)* 26

SOLUTION The maximum value of the expression $27-|9x-8|$ will be maximum only when the value of $|9x-8|$ is minimum, but the minimum possible value of any $|k|$ is zero. Hence the maximum value of

$$27-|9x-8|=27-(0)=27$$

Hence option (a) is correct.

EXAMPLE 3 *The minimum value of the expression* $|17x-8|-9$ *is:*

(a) 0 *(b)* −9
(c) 8/17 *(d)* *none of these*

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION The minimum value of expression $|17x-8|-9$ is minimum only when $|17x-8|$ is minimum. But the minimum value of $|k|$ is zero.

Hence minimum value of $|17x-8|-9 = 0-9 = -9$

EXAMPLE 4 *If* $2a-9=b+a$, *then the value of* $(|a-b|+|b-a|)$ *is :*

(a) 18 *(b) 11* *(c) 1* *(d) 0*

SOLUTION $\because$ $2a-9=b+a$

$\Rightarrow$ $2a-a=b+9$

$\Rightarrow$ $a=b+9$

$\Rightarrow$ $a-b=9$ or $b-a=-9$

Hence $|a-b|+|b-a| = |9|+|-9|$

$= 9+9 = 18$

Thus (a) is the correct option.

EXAMPLE 5 *The value of x for which the value of* $|3x+15|$ *is minimum :*

(a) 3 *(b) 5*

(c) −5 *(d) none of these*

SOLUTION The minimum value of $|3x+15| = 0$

$\Rightarrow$ $3x+15=0$

$\Rightarrow$ $x=-5$

Hence (c) is correct option.

FACTORS AND MULTIPLES

When two or more integers are multiplied together then the resultant value is called their product :

For example

$3\times4=12$, $2\times7\times5=70$, $3\times5\times11=165$

where 12, 70 and 165 are called the products.

But we see that $12=4\times3$ it means 4 and 3 are the **factors** of 12.

and $70=2\times5\times7$

where 2, 5, 7 are known as **factors** of 70.

Again 12 is called as the **multiple of** 3 or **multiple of** 4.

Similarly 70 is called as the **multiple of** 2 or 5 or 7 or 10 or 35 or 14.

Thus a number which divides a given number exactly is called factor (or divisor) of that given number and the given number is called a multiple of that number.

Now, 15 is exactly divisible by 1, 3, 5, 15 so 1, 3, 5, 15 are called as the factors of 15 while 15 is called as the multiple of these factors. Where 1, 15 are **improper factors** and 3, 5 are called **proper factors of** 15.

Therefore 1 and itself (the number) are called the improper factors of the given number.

So the factors of 24 = 1, 2, 3, 4, 6, 8, 12, 24

Factors of 35 = 1, 5, 7, 35

Factors of 36 = 1, 2, 3, 4, 6, 9, 12, 18, 36

Similarly the multiples of 2 are 2, 4, 6, 8, 10, 12, ...

multiples of 7 are 7, 14, 21, 28, 35, 42, 49....

multiples of 10 are 10, 20, 30, 40, 50...

- 1 is a factor of every number.
- Every number is a factor of itself.
- Every number, except 1 has atleast two factors *viz.*, 1 and itself.
- Every factor of a number is less than or equal to that number.
- Every multiple of a number is greater than or equal to itself.
- Every number has infinite number of its multiples.
- Every number is a multiple of itself.

Prime Factorisation : If a natural number is expressed as the product of prime numbers (factors) then the factorisation of the number is called its prime factorisation.

For example :

(i) $72=2\times2\times2\times3\times3$

2	72
2	36
2	18
3	9
3	3
	1

(ii) $420=2\times2\times3\times5\times7$

2	420
2	210
3	105
5	35
7	7
	1

(iii) $3432=2\times2\times2\times3\times11\times13$

2	3432
2	1716
2	858
3	429
11	143
13	13
	1

PRACTICE EXERCISE

1. Find the prime factors of the following :
   (i) 210 (ii) 120 (iii) 3315 (iv) 3465
   (v) 1197 (vi) 157573
2. Find the least number by which 22932 must be multiplied or divided so as to make it a perfect square :
   (a) 10 (b) 4 (c) 11 (d) 13
3. How many natural numbers upto 150 are divisible by 7?
   (a) 21 (b) 14 (c) 22 (d) 17
4. How many numbers between 333 and 666 are divisible by 5?
   (a) 67 (b) 70 (c) 75 (d) 55
5. How many numbers between 11 and 111 are the multiples of both 2 and 5?
   (a) 10 (b) 12 (c) 11 (d) 70
6. Find the total number of prime factors in $2^{17}\times6^{31}\times7^{5}\times10^{11}\times11^{10}\times(323)^{23}$:
   (a) 162 (b) 161 (c) 346 (d) 97

Scanned by CamScanner

yoursmahboob.wordpress.com

ANSWERS & SOLUTIONS

1. (i) $2\times3\times5\times7$ (ii) $2\times2\times2\times3\times5$ (ii) $3\times5\times13\times17$
(iv) $3\times3\times5\times7\times11$ (v) $3\times3\times7\times19$ (vi) $13\times17\times23\times31$

2. (d) **3.** (a) **4.** (a) **5.** (a)

6. (a) $2^{17}\times6^{31}\times7^5\times10^{11}\times11^{10}\times(323)^{23}$
$=2^{17}\times2^{31}\times3^{31}\times7^5\times2^{11}\times5^{11}\times11^{10}\times17^{23}\times19^{23}$
$=2^{59}\times3^{31}\times5^{11}\times7^5\times11^{10}\times17^{23}\times19^{23}$
$\therefore$ Total number of prime factors =
$59+31+11+5+10+23+23=162$

NUMBER OF FACTORS (OR DIVISORS) OF A GIVEN NUMBER (COMPOSITE NUMBER)

Let us assume a composite number say 24 then find the no. of factors.

$24=1\times24$
2×12
3×8
4×6

We see that there are total 8 factors namely,
1, 2, 3, 4, 6, 8, 12 and 24.

But for the larger numbers it becomes difficult to find the total number of factors. So we use the following formula which can be derived with the help of theory of permutation and combination.

Let there be a composite number N and its prime factors be $a, b, c, d, \ldots$ etc. and $p, q, r, s, \ldots$ etc. be the indices (or powers) of the $a, b, c, d, \ldots$ etc respectively *i.e.*, if N can be expressed as

$$N=a^p.b^q.c^r.d^s\ldots$$

then the number of total divisors or factors of N is

$$(p+1).(q+1)(r+1)(s+1)\ldots$$

EXAMPLE 1 *Find the total number of factors of 24.*

SOLUTION $24=2^3\times3^1$ [$\because 24=2\times2\times2\times3$]
$\therefore$ Number of factors $=(3+1).(1+1)=8$

EXAMPLE 2 *Find the total number of factors of 540 :*
(a) 24 *(b)* 20
(c) 30 *(d) none of these*

SOLUTION $540=2\times2\times3\times3\times3\times5$
or $540=2^2\times3^3\times5^1$
Therefore total number of factors of 540 is
$(2+1)(3+1)(1+1)=24$

EXAMPLE 3 *The total number of divisors of 10500 except 1 and it self is :*
(a) 48 *(b)* 50 *(c)* 46 *(d)* 56

SOLUTION $10500=2\times2\times3\times5\times5\times5\times7$
$10500=2^2\times3^1\times5^3\times7^1$
$\therefore$ Total number of divisors of 10500 is
$(2+1)(1+1)(3+1)(1+1)=48$
But we have to exclude 1 and 10500
So there are only $48-2=46$ factors of 10500 except 1 and 10500. So (c) is the correct option.

EXAMPLE 4 *Total number of factors of 36 is :*
(a) 4 *(b)* 9
(c) 6 *(d) none of these*

SOLUTION $36=2^2\times3^2$
$\therefore$ Number of factors $=(2+1)(2+1)=3\times3=9$
Hence (b) is the correct option.

NOTE A perfect square number always contains odd no. of factors.

PRACTICE EXERCISE

Find the number of factors of the following :

1. 1008 **2.** 101 **3.** 111 **4.** 7056 **5.** 18522
6. 7744 **7.** 3875 **8.** 1458 **9.** 1339 **10.** 512

ANSWERS

1. 30 **2.** 2 **3.** 4 **4.** 45 **5.** 32
6. 21 **7.** 8 **8.** 14 **9.** 4 **10.** 10

SUM OF FACTORS OF A GIVEN NUMBER

Once again if you want to find the sum of smaller composite numbers, then you can do it manually, but for larger numbers its a problem.

e.g., Sum of factors of 24
$=1+2+3+4+6+8+12+24=60$

Let N be the composite number and $a, b, c, d..$ be its prime factors and p, q, r, s be the indices (or powers) of a, b, c, d *i.e.*, if N can be expressed as

$$N=a^p.b^q.c^r.d^s\ldots$$

then the sum of all the divisors (or factors) of N

$$=\frac{(a^{p+1}-1)(b^{q+1}-1)(c^{r+1}-1)(d^{s+1}-1)}{(a-1)(b-1)(c-1)(d-1)}\ldots$$

EXAMPLE 1 *Find the sum of factors of 24.*

SOLUTION $\because$ $24=2^3\times3^1$
$\therefore$ Sum of factors of $24=\frac{(2^4-1)(3^2-1)}{(2-1)(3-1)}$
$=\frac{15\times8}{1\times2}=60$

EXAMPLE 2 *Find the sum of factors of 270.*

SOLUTION $\because$ $270=2\times3^3\times5$
$\therefore$ Sum of factors of $270=\frac{(2^{1+1}-1)(3^{3+1}-1)(5^{1+1}-1)}{(2-1)(3-1)(5-1)}$
$=\frac{3\times80\times24}{1\times2\times4}=720$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *The sum of factors of* 1520 *except the unity is :*

(a) 3720 *(b)* 2730
(c) 2370 *(d) none of these*

SOLUTION Since $1520 = 2^4 \times 5 \times 19$

$\therefore$ Sum of all the factors of $1520 = \dfrac{(2^5-1)(5^2-1)(19^2-1)}{(2-1)(5-1))(19-1)}$

$= \dfrac{31 \times 24 \times 360}{1 \times 4 \times 18} = 3720$

But since unity is to be excluded.
$\therefore$ The net sum of the factors = 3719
$\therefore$ (d) is the correct option.

EXAMPLE 4 *The sum of factors of 19600 is :*

(a) 54777 *(b) 33667*
(c) 5428 *(d) none of these*

SOLUTION $19600 = 2^4 \times 5^2 \times 7^2$

$\therefore$ Sum of factors of $19600 = \dfrac{(2^{4+1}-1)(5^{2+1}-1)(7^{2+1}-1)}{(2-1)(5-1)(7-1)}$

$= \dfrac{31 \times 124 \times 342}{1 \times 4 \times 6}$

$= 54777$

Hence (a) is the correct option.

PRODUCT OF FACTORS

Let us assume a very small number 24 and see the factors

$24 = 1 \times 24$
$= 2 \times 12$
$= 3 \times 8$
$= 4 \times 6$

Now, it is obvious from the above explanation that the product of factors of 24

$= (1 \times 24) \times (2 \times 12) \times (3 \times 8) \times (4 \times 6)$
$= 24 \times 24 \times 24 \times 24 = (24)^4$

Thus, the product of factors of composite number $N = N^{n/2}$, where n is the total number of factors of N.

EXAMPLE 1 *Product of divisors of* 7056 *is :*

(a) $(84)^{48}$ *(b)* $(84)^{44}$
(c) $(84)^{45}$ *(d) none of these*

SOLUTION $\because$ $7056 = 2^4 \times 3^2 \times 7^2$

$\therefore$ Number of factors/divisors of 7056
$= (4+1)(2+1)(2+1) = 45$

$\therefore$ Product of factors $= (7056)^{45/2} = (84)^{45}$

Hence (c) is the correct option.

EXAMPLE 2 *Product of factors of* 360 *is :*

(a) $(360)^{12}$ *(b)* $(36)^{120}$ *(c)* $(360)^{22}$ *(d)* $6^{24} \times 10^{10}$

SOLUTION $\because$ $360 = 2^3 \times 3^2 \times 5^1$

$\therefore$ Number of factors of $360 = (3+1)(2+1)(1+1) = 24$

Thus the product of factors $= (360)^{24/2} = (360)^{12}$

Hence (a) is the correct option.

NOTE As we know the number of divisors of any perfect number is an odd number so we take the square root of the perfect square to eliminate the $\frac{1}{2}$ from the power of the number as it can be seen in the above example no. 1.

NUMBER OF ODD FACTORS OF A GIVEN NUMBER

Let us assume a smaller number *e.g.*., 24

$24 = 1 \times 24$ also $24 = 2^3 \times 3^1$
$= 2 \times 12$
$= 3 \times 8$

We can see that there are total 2 odd factors namely 1 and 3.
Further assume another number say 36

$36 = 1 \times 36$ also $36 = 2^2 \times 3^2$
$= 2 \times 18$
$= 3 \times 12$
$= 4 \times 9$
$= 6 \times 6$

So, we can see that there are only 3 odd factors *viz.*, 1, 3 and 9.

Once again we assume another number say 90

then $90 = 1 \times 90$ also $90 = 2 \times 3^2 \times 5$
$= 2 \times 45$
$= 3 \times 30$
$= 5 \times 18$
$= 6 \times 15$
$= 9 \times 10$

Thus there are only 6 odd factors namely 1, 3, 5, 9, 15, 45.
To get the number of odd factors of a number N first of all express the number N as

$$N = (p_1^{\,a} \times p_2^{\,b} \times p_3^{\,c} \times \ldots) \times (e^x)$$

(where, $p_1, p_2, p_3, \ldots$ are the odd prime factors and e is the even prime factor.)

Then the total number of odd factors

$= (a+1)(b+1)(c+1)\ldots$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *The number of odd factors (or divisors) of 24 is*

SOLUTION ∵ $24 = 2^3 \times 3^1$

Here 3 is the odd prime factor

So, total number of odd factors = (1 + 1) = 2

EXAMPLE 2 *The number of odd factors of 36 is ...*

SOLUTION ∵ $36 = 2^2 \times 3^2$

∴ Number of odd factors = (2 + 1) 3

EXAMPLE 3 *The number of odd factors of 90 is ....*

SOLUTION ∵ $90 = 2^1 \times 3^2 \times 5^1$

∴ Total number of odd factors of 90 = (2 + 1) (1 + 1) = 6

NUMBER OF EVEN FACTORS OF A COMPOSITE NUMBER

Number of even factors of a number
= (Total number of factors of the given number
− Total number of odd factors)

Thus in the above
Example (1) number of even factors = 8 − 2 = 6
Example (2) number of even factors = 9 − 3 = 6
Example (3) number of even factors = 12 − 6 = 6

NUMBER OF WAYS OF EXPRESSING A COMPOSITE NUMBER AS A PRODUCT OF TWO FACTORS

It has long been discussed in the previous examples of composite numbers but you might have not noticed it.

Let us consider an example of small composite number say, 24

then $24 = 1 \times 24$
2×12
3×8
4×6

So it is clear that the number of ways of expressing a composite no. as a product of two factors

$= \frac{1}{2} \times$ the no. of total factors

EXAMPLE 1 *Find the number of ways of expressing 180 as a product of two factors.*

SOLUTION $180 = 2^2 \times 3^2 \times 5^1$

Number of factors = (2 + 1) (2 + 1) (1 + 1) = 18

Hence, there are total $\frac{18}{2} = 9$ ways in which 180 can be expressed as a product of two factors.

NOTE As you know when you express any perfect square number '*N*' as a product of two factors namely $\sqrt{N}$ and $\sqrt{N}$, and you also know that since in this case $\sqrt{N}$ appears two times but it is considered only once while calculating the no.of factors so we get always an odd number as number of factors so we can not divide the odd number exactly by 2 as in the above formula. So if we have to consider these two same factors then we find the number of ways of expressing *N* as a product of two factors $= \frac{(\text{Number of factors} + 1)}{2}$.

Again if it is asked that find the no. of ways of expressing *N* as a product of Two distinct factors then we do not consider 1 way (*i.e.*, $N = \sqrt{N} \times \sqrt{N}$) then no. of ways $= \frac{(\text{Number of factors} - 1)}{2}$.

EXAMPLE 2 *Find the number of ways expressing 36 as a product of two factors.*

SOLUTION $36 = 2^2 \times 3^2$

Number of factors = (2 + 1) (2 + 1) = 9

Hence the no. of ways of expressing 36 as a product of two factors $= \frac{(9 + 1)}{2} = 5$.

as $36 = 1 \times 36, 2 \times 18, 3 \times 12, 4 \times 9$ and 6×6

EXAMPLE 3 *In how many ways can 576 be expressed as the product of two distinct factors?*

SOLUTION ∵ $576 = 2^6 \times 3^2$

∴ Total number of factors = (6 + 1) (2 + 1) = 21

So the number of ways of expressing 576 as a product of two distinct factors $= \frac{(21 - 1)}{2} = 10$.

NOTE Since the word 'distinct' has been used therefore we do not include $576 = 26 \times 26$.

LCM AND HCF

In the previous articles I have discussed in detail about the factors. Now I will move towards common factor, Highest common factors (HCF) and least common multiple (LCM).

Common Factors : When any factor which is the factor of two or more given numbers then it is said that this particular factor is common.

For example $6 = 2 \times 3$
$15 = 3 \times 5$

We see that 3 is a common factor in both 6 and 15.

Similarly, $6 = 2 \times 3$
$8 = 2 \times 2 \times 2$
$30 = 2 \times 3 \times 5$

So, we can see that only 2 is common in all the three numbers 6, 8 and 30. No other factor is common in all.

Highest Common factor (HCF) or Greatest Common divisor (GCD) : HCF of two or more than two numbers is the greatest possible number that can divide all these numbers exactly, without leaving any remainder. For example

Find the HCF of 84, 126.

∴ $84 = 2 \times 3 \times 7 \times 2 = 42 \times 2$
$126 = 2 \times 3 \times 7 \times 3 = 42 \times 3$

So, the HCF of 84 and 126 $= 2 \times 3 \times 7 = 42$

Thus we can see that 42 is the greatest common divisor since it can divide exactly both 84 and 126.

Scanned by CamScanner

yoursmahboob.wordpress.com

Basically there are two methods of finding the HCF.
(i) Factor Method (ii) Division Method

(i) Factor Method : In this method first we break (or resolve) the numbers into prime factors then take the product of all the common factors. This obtained resultant product is known as the HCF of the given numbers.

EXAMPLE 1 *Find the HCF of 1680 and 3600.*

SOLUTION $\because$ $1680 = 2\times2\times2\times2\times3\times5\times7$

$3600 = 2\times2\times2\times2\times3\times5\times3\times5$

So the product of common factors $= 2\times2\times2\times2\times3\times5 = 240$

Hence, the HCF of 1680 and 3600 is 240.

EXAMPLE 2 *Find the HCF of 750, 6300, 18900.*

SOLUTION $750 = 2\times3\times5\times5\times5$

$6300 = 2\times3\times5\times5\times3\times2\times7$

$18900 = 2\times3\times5\times5\times3\times2\times3\times7$

So the product of common factors $= 2\times3\times5\times5 = 150$

Hence 150 is the HCF of 750, 6300, 18900.

(ii) HCF by Division Method : Consider two smallest numbers, then divide the larger one of them by the smaller one and then divide this divisor by the remainder and again divide this remainder by the next remainder and so on until the remainder is zero.

If there are more than two numbers of which HCF is to be found, we continue this process as we divide the third lowest number by the last divisor obtained in the above process.

EXAMPLE 1 *Find the HCF of 120 and 180.*

SOLUTION

$$\begin{array}{r} 120\overline{)180}(1 \\ \underline{120} \\ 60\overline{)120}(2 \\ \underline{120} \\ \times \end{array}$$

Hence, 60 is the HCF of 120 and 180.

EXAMPLE 2 *Find the HCF of 420 and 1782.*

SOLUTION

$$\begin{array}{r} 420\overline{)1782}(4 \\ \underline{1680} \\ 102\overline{)420}(4 \\ \underline{408} \\ 12\overline{)102}(8 \\ \underline{96} \\ 6\overline{)12}(2 \\ \underline{12} \\ \times \end{array}$$

Hence 6 is the HCF of 420 and 1782.

EXAMPLE 3 *Find the HCF of 210, 495 and 980.*

SOLUTION First we consider the two smallest number *i.e.*, 210 and 495.

$$\begin{array}{r} 210\overline{)495}(2 \\ \underline{420} \\ 75\overline{)210}(2 \\ \underline{150} \\ 60\overline{)75}(1 \\ \underline{60} \\ 15\overline{)60}(4 \\ \underline{60} \\ \times \end{array}$$

$$\begin{array}{r} 15\overline{)980}(65 \\ \underline{975} \\ 5\overline{)15}(3 \\ \underline{15} \\ \times \end{array}$$

Hence the HCF is 5.

Did you notice something?

If you watch carefully the above discussion you will find that the HCF is the factor of difference of the given numbers. So there is short cut for you to find the HCF.

You can divide the given numbers by their lowest possible difference if these numbers are divisible by this difference then this difference itself is the HCF of the given numbers. If this difference is not the HCF then any factor of this difference must be the HCF of the given numbers.

EXAMPLE 1 *Find the HCF of 63 and 84.*

SOLUTION The difference $= 84 - 63 = 21$

Now divide 63 and 84 by 21, since the given numbers 63 and 84 are divisible by their difference 21, thus 21 itself is the HCF of 63 and 84.

EXAMPLE 2 *Find the HCF of 42 and 105.*

SOLUTION The difference $= 105 - 42 = 63$

Now divide 42 and 105 by 63 but none of these is divisible by their difference 63. So we factorize 63 and then divide 42 and 105 by the factor of 63. The greatest factor of 63 which can divide 42 and 105 that will be the HCF of the given numbers.

So $63 = 1\times63,\ 3\times21,\ 7\times9$

$\therefore$ The factor of 63 are 1, 3, 7, 9, 21 and 63.

Obviously we divide 42 and 105 by 21 (since the division by 63 is not possible) and we see that the given numbers are divisible hence 21 is the HCF of 42 and 105.

EXAMPLE 3 *Find the HCF of 30, 42 and 135.*

SOLUTION The difference between 30 and 42 = 12

The difference between 42 and 135 = 93

Now divide, 30, 42 and 135 by 12 but it can not divide all the numbers.

So take the factors of 12.

The factors of 12 are 1, 2, 3, 4, 6, 12

Now we divide 30, 42 and 135 by 6 but it can not divide all these numbers. So we divide now 30, 42 and 135 by 4, but 4 also can not divide all the numbers, Now we divide the given numbers by 3. We will find that all the numbers are divisible by 3 hence 3 is the HCF of the given numbers.

1. Euclidean Algorithm : If 'H' be the HCF of any two positive integers a and b then there exists unique integers p and q such that $H = ap + bq$.

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE-1.3

1. The product of two numbers is 84 and their HCF is 2. Find the numbers of such pairs.
2. The product of two numbers is 15120 and their HCF is 6, find the number of such pairs.
3. The number of pairs of two numbers whose product is 300 and their HCF is 5 :
   (a) 2 (b) 3
   (c) 4 (d) can't be determined

HCF WITH REMAINDERS

Case 1. Find the greatest possible number with which when we divide 37 and 58, it leaves the respective remainder of 2 and 3.

SOLUTION Since when we divide 37 and 58 by the same number then we get remainders 2 and 3 respectively.

So $(37-2)$ and $(58-3)$ must be divisible hence leaving the remainders zero.

It means 35 and 55 both are divisible by that number so the HCF of 35 and 55 is 5.

Hence the greatest possible number is 5.

Case 2. Find the largest possible number with which when 60 and 98 are divided it leaves the remainders 3 in each case.

SOLUTION Since 60 and 98 both leave the remainders 3 when divided by such a number.

Thus $57 = (60-3)$ and $95 = (98-3)$ will be divisible by the same number without leaving any remainder. So the HCF of 57 and 95 is 19. Hence 19 is the highest possible number.

Case 3. Find the largest possible number with which when 38, 66 and 80 are divided the remainders remains the same.

SOLUTION In this case (since we donot know the value of remainder) we take the HCF of the differences of the given numbers.

So the HCF of $(66-38), (80-66), (80-38)$

$= \text{HCF of } 28, 14, 42 = 14$

Hence 14 is the largest possible number which leaves same remainder $(= 10)$ when it divides either 38, 66 or 80.

CAT CONCISE

In case 1, the remainders are different
In case 2, the remainders are same in each case.
In case 3, the remainders are same in each case, but the value of remainder is unknown.

INTRODUCTORY EXERCISE-1.4

1. The largest possible number with which when 76, 132 and 160 are divided the remainders obtained are the same is :
   (a) 6 (b) 14
   (c) 18 (d) none of these
2. Find the number of pairs of two numbers whose HCF is 5 and their sum is 50.
3. The largest possible length of a tape which can measure 525 cm, 1050 cm and 1155 cm length of cloths in a minimum number of attempts without measuring the length of a cloth in a fraction of the tape's length
   (a) 25 (b) 105
   (c) 75 (d) none of these
4. In the above question minimum how many attempts are required to measure whole length of cloths?
5. Minimum how many similar tiles of square shape are required to furnish the floor of a room with the length of 462 cm and breadth of 360 cm?
6. The ratio of two numbers is 15 : 11. If their HCF be 13 then these numbers will be :
   (a) 15 : 11 (b) 75 : 55
   (c) 105 : 77 (d) 195 : 143
7. The three numbers are in the ratio 1 : 2 : 3 and their HCF is 12. These numbers are :
   (a) 4, 8, 12 (b) 5, 10, 15
   (c) 24, 48, 72 (d) 12, 24, 36
8. There are three drums with 1653 litre 2261 litre and 2527 litre of petrol. The greatest possible size of the measuring vessel with which we can measure up the petrol of any drum while every time the vessel must be completely filled :
   (a) 31 (b) 27
   (c) 19 (d) 41
9. Two pencils are of 24 cm and 42 cm. If we want to make them of equal size then minimum no. of similar pencils is :
   (a) 6 (b) 11
   (c) 12 (d) none of these
10. The HCF of two numbers is 27 and their sum is 216. These numbers are :
    (a) 27, 189 (b) 81, 189
    (c) 108, 108 (d) 154, 162
11. Mr. Baghwan wants to plant 36 mango trees, 144 orange trees and 234 apple trees in his garden. If he wants to plant the equal no. of trees in every row, but the rows of mango, orange and apple trees will be separate, then the minimum number of rows in his garden is :
    (a) 18 (b) 23
    (c) 36 (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

LCM (LEAST COMMON MULTIPLE)

In this chapter I have already discussed the multiples of a number for example integral multiples of 7 are 7, 14, 21, 28, 35, 42, ...

and the integral multiples of 8 are 8, 16, 24, 32, 40, 48, 56, ...etc. in short we can write the positive integral multiples of any number N as NK, where $K = 1, 2, 3, 4, 5, 6, ...$

Now if we consider altcast two numbers say 2 and 3 then we write the multiples of each as 2, 4, 6, 8, 10, 12, 14, 16, 18, 20, 22, 24, 26, 28, 30... and 3, 6, 9, 12, 15, 18, 21, 24, 27, 30, ...

Thus it is clear from the above illustrations that the some of the multiples of 2 and 3 are common *viz.*, 6, 12, 18, 24, 30...

Again if we consider any 3 numbers say, 3, 5 and 6 then the multiples of each of the 3, 5, 6 are

3, 6, 9, 12, 15, 18, 21, 24, 27, 30, 33, 36, 39, 42, 45, 48, 51, 54, 57, 60

5, 10, 15, 20, 25, 30, 35, 40, 45, 50, 55, 60...

6, 12, 18, 24, 30, 36, 42, 48, 54, 60...

So, we can see that the common multiples of 3, 5 and 6 are 30, 60, 90, 120, ...etc.

But out of these common multiples, 30 is the least common multiple. Similarly in the previous example 6 is the least common multiple.

NOTE Generally there is no any greatest common multiple unless otherwise the condition is stated.

Basically, there are two methods to find the LCM.

(i) Factor Method (ii) Division Method

(i) Factor Method : Resolve the given numbers into their prime factors, then take the product of all the prime factors of the first number with those prime factors of second number which are not common to the prime factors of the first number. Now this resultant product can be multiplied with those prime factors of the third number which are not common to the factors of the previous product and this process can be continued for further numbers if any.

EXAMPLE 1 *Find the LCM of* 48, 72, 140.

SOLUTION We can write the given numbers as

$48 = \boxed{2} \times \boxed{2} \times 2 \times 2 \times 3 = \boxed{2} \times \boxed{2} \times 2 \times 3 \times 2$

$72 = \boxed{2} \times \boxed{2} \times 2 \times 3 \times 3 = \boxed{2} \times \boxed{2} \times 2 \times 3 \times 3$

$140 = \boxed{2} \times \boxed{2} \times 5 \times 7 = \boxed{2} \times \boxed{2} \times 5 \times 7$

So the LCM of 48, 72 and 140

$= 2 \times 2 \times 2 \times 3 \times 2 \times 3 \times 5 \times 7 = 5040$

EXAMPLE 2 *Find the LCM of* 42, 63 *and* 231.

SOLUTION $42 = 2 \times 3 \times 7 = \boxed{3} \times \boxed{7} \times 2$

$63 = 3 \times 3 \times 7 = \boxed{3} \times \boxed{7} \times 3$

$231 = 3 \times 7 \times 11 = \boxed{3} \times \boxed{7} \times 11$

$\therefore$ The LCM of 42, 63 and $231 = 3 \times 7 \times 2 \times 3 \times 11 = 1386$

(ii) Division Method : First of all write down all the given numbers in a line separating by the comma (,) then divide these numbers by the least common prime factors say 2, 3, 5, 7, 11... to the given numbers, then write the quotients just below the actual numbers separating by comma (,). If any number is not divisible by such a prime factor then write this number as it is just below itself, then continue this process of division by considering higher prime factors, if the division is complete by lower prime factor, till the quotient in the last line is 1. Then take the product of all the prime factors by which you have divided the numbers (or quotient) in different lines (or steps). This product will be the LCM of the given numbers.

EXAMPLE 3 *Find the LCM of* 108, 135 *and* 162.

SOLUTION

2	108, 135, 162
2	54, 135, 81
3	27, 135, 81
3	9, 45, 27
3	3, 15, 9
3	1, 5, 3
5	1, 5, 1
	1, 1, 1

Thus the required LCM $= 2 \times 2 \times 3 \times 3 \times 3 \times 3 \times 5 = 1620$

EXAMPLE 4 *Find the LCM of* 420, 9009, 6270.

SOLUTION

2	420, 9009, 6270
2	210, 9009, 3135
3	105, 9009, 3135
3	35, 3003, 1045
5	35, 1001, 1045
7	7, 1001, 209
11	1, 143, 209
13	1, 13 19
19	1, 1, 19
	1, 1, 1

Thus the required LCM $= 2 \times 2 \times 3 \times 3 \times 5 \times 7 \times 11 \times 13 \times 19$

$= 3423420$

EXAMPLE 5 *Find the least possible number which can be divided by 32, 36 and 40.*

SOLUTION The number which is divisible by 32, 36 and 40 it must be the common multiple of all the given numbers. Since we need such a least number then we have to find out just the LCM of 32, 36 and 40.

The LCM of 32, 36 and 40 = 1440

Hence, the least possible no. is 1440, which is divisible by all the given numbers.

EXAMPLE 6 *In the above problem what is the least possible number of* 5 *digits which is divisible by all the numbers* 32, 36 *and* 40.

SOLUTION Since the least possible no. is 1440, but it is a four digit number. So we can take the integral multiples of 1440 which must be divisible by the given numbers.

Scanned by CamScanner

yoursmahboob.wordpress.com

Now since the least possible 5 digit number is 10000, so the required number must be equal to or greater than 10,000. So when we multiply 1440 by 7. We get the required result *i.e.*, 10,080.

Thus 10080 is the least possible 5 digit number which is divisible by 32, 36 and 40.

Alternatively : Divide the least possible 5 digit no.by 1440 and then add the difference of the divisor and remainder to the least possible 5 digit number. This will be the required number.

So,

$$1440\overline{)10000}(6$$
$$\underline{8640}$$
$$1360$$

Now, $1440 - 1360 = 80$

Thus the required number = 10000 + 80 = 10080

EXAMPLE 7 *According to above problem find the largest possible number of 4 digits which is exactly divisible by 32, 36 and 40.*

SOLUTION Since the largest 4 digit number is 9999. So the required number can not exceed 9999 any how, now we take the appropriate multiple of 1440. Since 1440 is divisible by the given numbers, so the multiples of 1440 must be divisible by the given numbers.

Hence $1440 \times 6 = 8640$ is the largest possible number since $1440 \times 7 = 10080$ is greater than 9999 which is not admissible. Hence, 8640 is the largest possible 4 digit no. which is divisible by all the given numbers.

Alternatively : Divide the greatest 4 digit number by 1440 (the LCM of the given no.) and then subtract the remainder from the greatest 4 digit number. So,

$$1440\overline{)9999}(6$$
$$\underline{8640}$$
$$1359$$

Hence, the required number = 9999 – 1359 = 8640

EXAMPLE 8 *Find the number of numbers lying between 1 and 1000 which are divisible by each of 6, 7 and 15.*

SOLUTION The least possible number which is divisible by 6, 7, and 15 = LCM of 6, 7, 15 = 210

So, the first such number is 210 and the other numbers are the multiples of 210 *i.e.*, 210, 420, 630, 840.

Thus there are total 4 numbers lying between 1 and 1000 which are divisible by 6, 7 and 15.

EXAMPLE 9 *Find the number of numbers lying between 1000 and 1,00,000 which are divisible by 15, 35 and 77 and are even also.*

SOLUTION The required numbers must be the multiples of the LCM of 15, 35 and 77.

Now the LCM of 15, 35 and 77 = 1155.

So the other numbers are

1155, 2310, 3465, 4620, 5775, ..., 99330

Thus there are total 86 numbers which are divisible by 15, 35 and 77 but only 43 numbers are even *i.e.*, every alternate number is even.

Thus there are total 43 required numbers.

EXAMPLE 10 *Find the least possible perfect square number which is exactly divisible by 6, 40, 49 and 75.*

SOLUTION The required number must be divisible by the given numbers so it can be the LCM or its multiple number.

Now the LCM of 6, 40, 49 and 75

$$= 2 \times 2 \times 2 \times 3 \times 5 \times 5 \times 7 \times 7$$

But the required number is a perfect square

Thus the LCM must be multiplied by $2 \times 3 = 6$.

Thus the required number

$$= (2 \times 2 \times 2 \times 3 \times 5 \times 5 \times 7 \times 7) \times (2 \times 3)$$
$$= 2 \times 2 \times 2 \times 2 \times 3 \times 3 \times 5 \times 5 \times 7 \times 7$$
$$= 176400$$

EXAMPLE 11 *Three bells in the bhootnath temple toll at the interval of 48, 72 and 108 second individually. If they have tolled all together at 6 : 00 AM then at what time will they toll together after 6 : 00 AM?*

SOLUTION The three bells toll together only at the LCM of the times they toll individually.

Thus the LCM of 48, 72 and 108 is 432 seconds.

Therefore all the bells will toll together at 6 : 07 : 12 AM

(∵ 432 seconds = 7 minuts 12 seconds)

EXAMPLE 12 *In the above problem how many times these bells will toll together till the 6 : 00 PM on the same day.*

SOLUTION The total time since 6 : 00 AM till 6 : 00 PM

$$= 12 \times 60 \times 60 \text{ seconds.}$$

Now since all these bells toll together at the interval of 432 seconds.

So the number of times when they will toll together

$$= \frac{\text{Total time}}{\text{least duration of tolling together}}$$
$$= \frac{12 \times 60 \times 60}{432} = 100$$

but since the bells toll together at 6 : 00 PM also. Hence total 101 (= 100 + 1) times these bells will toll together in the given duration of time.

LCM WITH REMAINDERS

Case 1. When the remainders are same for all the divisors.

Case 2. When the remainders are different for different divisors but the respective difference between the divisors and the remainders remain constant.

Case 3. When neither the divisors are same nor the respective difference between divisors and the remainders remain constant.

CASE 1

EXAMPLE 13 *What is the least possible number which when divided by 24, 32 or 42 in each case it leaves the remainder 5?*

SOLUTION Since we know that the LCM of 24, 32 and 42 is divisible by the given numbers. So the required number is

= (LCM of 24, 32, 42) + (5) = 672 + 5 = 677

Hence such a least possible number is 677.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 14 *In the above question how many numbers are possible between 666 and 8888?*

SOLUTION Since the form of such a number is $672m + 5$, where $m = 1, 2, 3, \ldots$

So, the first no. $= 672 \times 1 + 5 = 677$ and the highest possible number in the given range $= 672 \times 13 + 5$

$= 8736 + 5 = 8741$

Thus the total numbers between 666 and 8888 are 13.

EXAMPLE 15 *What is the least possible number which when divided by 21, 25, 27 and 35 it leaves the remainder 2 in each case?*

SOLUTION The least possible no.

$=$ (LCM of 21, 25, 27 and 35) $m + 2$

$= 4725m + 2$

$= 4727$ (for the least possible value we take $m = 1$)

EXAMPLE 16 *What is the least possible no. which must be added to 4722 so that it becomes divisible by 21, 25, 27 and 35?*

SOLUTION The number which is divisible by 21, 25, 27 and 35 is the LCM of 21, 25, 27 and 35 $= 4725$

So the required number $= 4725 - 4722 = 3$

EXAMPLE 17 *What is the least number which when divided by 8, 12 and 16 leaves 3 as the remainder in each case, but when divided by 7 leaves no any remainder?*

SOLUTION The possible value $= m$ (LCM of 8, 12 and 16) $+ 3$

$= m\,(48) + 3$

Now put the value of m such that "$m\,(48) + 3$" becomes divisible by 7. So $3 \times 48 + 3 = 147$ which is the least possible required number.

CASE 2

EXAMPLE 18 *What is the least possible number which when divided by 18, 35 or 42 it leaves the 2, 19, 26 as the remainders respectively?*

SOLUTION Since the difference between the divisors and the respective remainders is same.

Hence the least possible number

$=$ (LCM of 18, 35 and 42) $- 16$

$= 630 - 16$ $[\because (18 - 2) = (35 - 19) = (42 - 26) = 16]$

$= 614$

EXAMPLE 19 *What is the least possible number which when divided by 2, 3, 4, 5, 6 it leaves the remainders 1, 2, 3, 4, 5 respectively?*

SOLUTION Since the difference is same as

$(2 - 1) = (3 - 2) = (4 - 3) = (5 - 4)\,(6 - 5) = 1$

Hence the required number $=$ (LCM of 2, 3, 4, 5, 6) $- 1$

$= 60 - 1 = 59$

EXAMPLE 20 *In the above problem what is the least possible 3 digit number which is divisible by 11?*

SOLUTION Since the form of the number is $60m - 1$, where $m = 1, 2, 3, \ldots$.

but the number $(60m - 1)$ should also be divisible by 11 hence at $m = 9$ the number becomes 539 which is also divisible by 11. Thus the required number $= 539$.

EXAMPLE 21 *Find the least possible 5 digit number which when divided by 2, 4, 6 and 8, it leaves the remainders 1, 3, 5 and 7 respectively.*

SOLUTION The possible value $=$ (LCM of 2, 4, 6, 8) $m - 1$

$= 24m - 1$

Since, the least 5 digit number is 10000. So the required number must be atleast 10000. So putting the value of $m = 417$, we get $(10008 - 1) = 10007$, which is the required number.

CASE 3

EXAMPLE 22 *What is the least possible number which when divided by 13 leaves the remainder 3 and when it is divided by 5 it leaves the remainder 2.*

SOLUTION Let the required number be N then it can be expressed as follows

$$N = 13k + 3 \quad \ldots(1)$$

and

$$N = 5l + 2 \quad \ldots(2)$$

where k and l are the quotients belong to the set of integers.

Thus $5l + 2 = 13k + 3$

$\Rightarrow$ $5l - 13k = 1$

$\Rightarrow$ $5l = 13k + 1$

$\Rightarrow$ $l = \dfrac{13k + 1}{5}$

now we put the value of k such that numerator will be divisible by 5 or l must be integer so considering $k = 1, 2, 3, \ldots$ we find that $k = 3$, l becomes 8. So the number $N = 5 \times 8 + 2 = 42$

Thus the least possible number $= 42$

To get the higher numbers which satisfy the given conditions in the above problem we just add the multiples of the given divisors (i.e., 13 and 5) to the least possible number (i.e., 42)

NOTE The next higher number $=$ (Multiple of LCM of 13 and 5) $+ 42$

$= 65m + 42$

EXAMPLE 23 *In the above problem what is the greatest possible number of 4 digits?*

SOLUTION Since the general form of this number is $65m + 42$ So by putting $m = 153$ we get $(9945 + 42 =) 9987$, which is required number.

HINT To get the value of 9945 we can simply divide 9999 (which is the greatest 4 digit number) by 65 and then subtract the remainder from 9999.

EXAMPLE 24 *How many numbers lie between 11 and 1111 which when divided by 9 leave a remainder of 6 and when divide by 21 leave a remainder of 12?*

SOLUTION Let the possible number be N then it can be expressed as

$$N = 9k + 6$$

and $$N = 21l + 12$$

$\therefore$ $9k + 6 = 21l + 12$

$\Rightarrow$ $9k - 21l = 6$

or $3\,(3k - 7l) = 6$

Scanned by CamScanner

yoursmahboob.wordpress.com

or $3k = 7l + 2$ or $k = \frac{7l+2}{3}$

So put the min. possible value of l such that the value of k is an integer or in other words numerator (*i.e.*, $7l + 2$) will be divisible by 3.

Thus at $l = 1$, we get $k = 3$ (an integer). So the least possible number $N = 9 \times 3 + 6 = 21 \times 1 + 12 = 33$.

Now the higher possible values can be obtained by adding 33 in the multiples of LCM of 9 and 21. *i.e.*, The general form of the number is $63m + 33$. So the other number in the given range including 33 are 96, 159, 222, 285, 348, ..., 1104. Hence there are total 18 numbers which satisfy the given condition.

Important Formula : Product of two numbers = Product of their HCF and their LCM.

EXAMPLE 25 *The HCF and LCM of the two numbers is 12 and 600 respectively. If one of the number is 24, then the other number will be*
(a) 300 *(b)* 400
(c) 1500 *(d) none of these*

SOLUTION The answer is (a)

since product of numbers = HCF × LCM

$\therefore \quad N \times 24 = 12 \times 600 \Rightarrow N = 300$

Successive Division : If the quotient in a division is further used as a dividend for the next divisor and again the latest obtained divisor is used as a dividend for another divisor and so on, then it is called the "successive division" *i.e.*, if we divide 625 by 3, we get 208 as quotient and 1 as a remainder then if 208 is divided by another divisor say 4 then we get 52 as a quotient and '0' (zero) as remainder and again, if we divide 52 by another divisor say 6 we get 8 as quotient and 4 as a remainder *i.e.*, we can represent it as following

3 | 625
4 | 208 → 1 (Remainder)
6 | 52 → 0 (Remainder)
8 → 4 (Remainder)

Now you can see that the quotient obtained in the first division behaves as a dividend for another divisor 4. Once again the quotient 52 is treated as a dividend for the next divisor 4. Thus it is clear from the above discussion as

Dividend	Divisor	Quotient	Remainder
625	3	208	1
208	4	52	0
52	6	8	4

So the 625 is successively divided by 3, 4 and 6 and the corresponding remainders are 1, 0 and 4.

EXAMPLE 1 *The least possible number of 3 digits when successively divided by 2, 5, 4, 3 gives respective remainders of 1, 1, 3, 1 is :*
(a) 372 *(b)* 275 *(c)* 273 *(d)* 193

SOLUTION The problem can be expressed as

2 | A
5 | B → 1
4 | C → 1
3 | D → 3
E → 1

} Remainder

So it can be solved as

$$(((((E \times 3) + 1)4 + 3)5 + 1)2 + 1) = A$$

(where A is the required number)

So for the least possible number E

= 1 (the least positive integer)

then $A = (((((1 \times 3) + 1) \times 4 + 3)5 + 1)2 + 1)$

[Since at E = 0, we get a two digit number]

Alternatively : We use the following convention while solving this type of problem. First we write all the divisors as given below then their respective remainders just below them.

2 ↖ 5 ↖ 4 ↖ 3] Divisors
1 1 3 1] Remainders

Where the arrow downwards means to add up and the arrow slightly upward (at an angle of 45°) means multiplication.

So we start from the right side remainder and move towards left since while writing down the divisors and remainders we write the first divisor first (*i.e.*, leftmost), second divisor at second position (from the left) and so on.

Now solve it as : **Step 1.** $(1 \times 4) + 3 = 7$

Step 2. $7 \times 5 + 1 = 36$

Step 3. $36 \times 2 + 1 = 73$

or $((((1 \times 4) + 3)5 + 1)2 + 1) = 73$

but we are required to find a three digit number so the next higher numbers can be obtained just by taking the multiples of the product of the divisors and then adding to it the least such number.

The next higher number = $(2 \times 5 \times 4 \times 3)m + 73 = 120m + 73$

So by putting $m = 1, 2, 3 \ldots$ we can get the higher possible numbers.

Now we just need a least possible 3 digit number so we can get it by putting $m = 1$

Hence the required number = $120 \times 1 + 73 = 193$

Hence (d) is the correct answer.

EXAMPLE 2 *A number when successively divided by 2, 3, 5 it leaves the respective remainders 1, 2 and 3. What will be the remainder if this number will be divided by 7?*

SOLUTION Write the divisors and remainders as given below

2 ↖ 3 ↖ 5
1 2 3

then solve it as follows

$$(((3 \times 3) + 2)2 + 1) = 23$$

or
$3 \times 3 = 9$
$9 + 2 = 11$
$11 \times 2 = 22$
$22 + 1 = 23$

So, the least possible number is 23 and the higher numbers can be obtained as $(2 \times 3 \times 5)m + 23 = 30m + 23$.

So the higher numbers are 53, 83, 113, 143, 173, 213, 333, ...etc.

But when we divide all these possible numbers by 7 we get the different remainders. So we can not conclude the single figure as a remainder.

Scanned by CamScanner

yoursmanboob.wordpress.com

EXAMPLE 3 *A number when divided successively by 6, 7 and 8, it leaves the respective remainders of 3, 5 and 4, what will be the last remainder when such a least possible number is divided successively by 8, 7 and 6?*

SOLUTION First we find the actual least possible no. then we move further

$$\underset{3}{\downarrow 6} \quad \underset{5}{\downarrow 7} \quad \underset{4}{8}$$

$$((((4\times7)+5)\times6)+3) = (((28+5)\times6)+3)$$
$$= 33\times6+3 = 198+3 = 201$$

Now we divide 201 successively by 8, 7 and 6.

8	201	
7	25	→ 1 (Remainder)
6	3	→ 4 (Remainder)
	0	→ 3 (Remainder)

So 3 is the last remainder.

EXAMPLE 4 *How many numbers lie between 100 and 10000 which when successively divided by 7, 11 and 13 leaves the respective remainders of 5, 6 and 7?*

SOLUTION The least possible number can be obtained as

$$\underset{5}{\downarrow 7} \quad \underset{6}{\downarrow 11} \quad \underset{7}{13}$$

$$(((7\times11)+6)7+5) = ((77+6)7+5)$$
$$= (83\times7+5) = (581+5) = 586$$

The general form for the higher numbers is

$$(7\times11\times13)m + 586 = (1001)m + 586$$

So, the numbers can be obtained by considering $m = 0, 1, 2, 3, \ldots$ so the first number is 586 and the last number is 9595 which can be attained at $m = 9$. So there are total 10 such numbers lying between 100 and 10000.

FRACTIONS

Suppose you have borrowed Rs. 20 from your friend in the last month. Now he has asked you to return his money. But you are paying him only Rs. 10 and the rest amount you want to return in the next month. It means you are paying the total amount not in a one lot but in a fraction that means "in parts".

From figures you can see that these things are in fraction.



So, we can say that when any unit of a thing is divided into equal parts and some parts are considered, then it is called a fraction. For example $\frac{1}{2}, \frac{3}{4}, \frac{2}{5}, \frac{3}{7}$ etc.

$\frac{1}{2}$ is read as one half

$\frac{3}{4}$ is read as three fourth

Denominator : The lower value indicates the number of parts into which the whole thing or quantity is being equally divided and it is known as Denominator.

Numerator : The upper value indicates the number of parts taken into consideration (or for use) out of the total parts in known as Numerator.

So in the fractions $\frac{2}{3}, \frac{5}{7}, \frac{1}{4}$ etc. 2, 5, 1 are the numerators and 3, 7, 4 are the denominators.

The numerators and denominators of a fraction are also called the 'terms' of a fraction.

Proper Fraction : A fraction whose numerator is less then its denominator,but not equal to zero) is called a proper fraction. For example $\frac{1}{2}, \frac{3}{4}, \frac{2}{7}, \frac{11}{20}$, etc.

Improper Fraction : A fraction whose numerator is equal to or greater than its denominator is called an improper fraction . For example $\frac{7}{2}, \frac{8}{5}, \frac{215}{15}, \frac{63}{15}$ etc.

NOTE
1. Every natural number can be expressed as a fraction, for example $7 = \frac{7}{1}, 8 = \frac{8}{1}, 11 = \frac{11}{1}$ etc. which are improper fraction.
2. When the numerator and denominator of a fraction are equal, then it is equal to unity.
3. The denominator of a fraction can never be equal to zero.

Mixed Fraction : A number which consists of two parts (i) a natural number (ii) a proper fraction is called a **mixed fraction.**For example $2\frac{5}{13}, 1\frac{7}{8}, 18\frac{9}{17}$ etc. where 2, 1, 18 are natural numbers and $\frac{5}{13}, \frac{7}{8}$ and $\frac{9}{17}$ are proper fractions.

and $2\frac{5}{13} = 2+\frac{5}{13}, 1\frac{7}{8} = 1+\frac{7}{8}$ and $18\frac{9}{17} = 18+\frac{9}{17}$

NOTE
1. Every mixed fraction can be written as an improper fraction and every improper fraction can be written as a mixed fraction as $\frac{45}{7} = 6\frac{3}{7}$
2. The numbers for example $-\frac{2}{3}, \frac{-7}{8}, \frac{-9}{5}$ etc are not the fraction numbers, but these are called as fraction like numbers.

Like Fractions : The fractions whose denominators are same are called like fractions, for example $\frac{3}{11}, \frac{4}{11}, \frac{9}{11}, \frac{8}{11}, \frac{17}{11}$ etc.

Equivalent Fractions : The fractions whose values are same *i.e.*, the ratio is same are called equivalent fractions for example,

$$\frac{2}{3} = \frac{4}{6} = \frac{6}{9} = \frac{8}{12} = \frac{10}{15} = \frac{12}{18} = \frac{20}{30} = \frac{26}{39}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

It implies that :

1. If we multiply the numerator and the denominator by the same non-zero number, the value of the fraction remains unchanged.
2. If we divide the numerator and the denominator by the same non zero number, the value of the fractions remains unchanged.

Cancellation : Division of the numerator and denominator by the same (non-zero) number is called the cancellation when the numerator and denominator of a fraction have no any common factors between them, then it is said the Reduced or Simplest form of fraction or in lowest term.

For example $\frac{2}{3}, \frac{3}{4}, \frac{7}{8}$ etc are the reduced fraction in its lowest term.

Reduction of a fraction to its lowest terms or simplest form :

1. HCF Method : Divide the numerator and denominator both by their HCF. *e.g.,* to reduce $\frac{21}{35}$ to its lowest term just divide 21 and 35 by their HCF.

So, $$\frac{21 \div 7}{35 \div 7} = \frac{3}{5}$$

2. Prime Factorisation Method : Just cancel out the common prime factors of both the numerator and denominator. For example to reduce 42 and 140 we cancel out the common prime factors as

$$\frac{42}{140} = \frac{2 \times 3 \times 7}{2 \times 2 \times 5 \times 7} = \frac{3}{10}$$

Reduction of the given fractions into like fractions : Obtain the LCM of the denominators of the given fractions and then make all the denominators equal to the LCM obtained, in such a way that the value of every fraction remain unchanged.

For example $\frac{6}{35}, \frac{10}{21}$.

Since the LCM of the 35 and 21 is 105 so the new fraction will be as

$$\frac{6 \times 3}{35 \times 3}, \frac{10 \times 5}{21 \times 5} \Rightarrow \frac{18}{105}, \frac{50}{105}$$

Relationship among fractions : If the denominators of all the fractions are same then the fraction whose numerator is greater, the fraction will be greater.

For example $\frac{8}{19} > \frac{7}{19} > \frac{5}{19} > \frac{4}{19}$

NOTE

1. To equalize the denominator of the fractions, take the LCM of the denominators.
2. (A) If $\frac{x}{y}$ be proper positive fraction and 'a' be a positive integers when $y \neq 0$

1. $\frac{x+a}{y+a} > \frac{x}{y}$ 2. $\frac{x-a}{y-a} < \frac{x}{y}$

If 'b' being a positive integer such that $a > b$, then

3. $\frac{x}{y} \times \frac{a}{b} > \frac{x}{y}$ 4. $\frac{x}{y} \times \frac{b}{a} < \frac{x}{y}$

(B) If $\frac{x}{y}$ be an improper positive fraction, then

5. $\frac{x+a}{y+a} < \frac{x}{y}$ 6. $\frac{x-a}{y-a} > \frac{x}{y}$

7. $\frac{x}{y} \times \frac{a}{b} > \frac{x}{y}$ 8. $\frac{x}{y} \times \frac{b}{a} < \frac{x}{y}$

(C) For any fraction $\frac{x}{y}$

9. $\frac{x+nx}{y+ny} = \frac{x}{y}$ 10. $\frac{x-nx}{y-ny} = \frac{x}{y}$

11. $\frac{x \pm m}{y \pm n} \neq \frac{x}{y}$ if $\frac{m}{n} \neq \frac{x}{y}$

PRACTICE EXERCISE

1. State (a) if the fraction is proper (b) if the fraction is improper (c) if the fraction is mixed (d) none of these
   (i) $\frac{3}{7}$ (ii) $\frac{7}{3}$
   (iii) $\frac{35}{12}$ (iv) $4\frac{3}{11}$
2. State (a) if the fractions are equivalent and (b) if the fractions are like fractions else (c)
   (i) $\frac{7}{16}, \frac{8}{16}, \frac{9}{16}, \frac{31}{16}$ (ii) $\frac{-5}{-6}, \frac{15}{18}, \frac{-45}{-54}$
   (iii) $\frac{3}{5}, \frac{7}{10}, \frac{14}{20}$ (iv) $\frac{9}{25}, \frac{4}{16}, \frac{13}{29}$
3. State (a) if the fractions are in ascending order, (b) if the fractions are in descending order, else (c)
   (i) $\frac{3}{5}, \frac{7}{9}, \frac{13}{8}$ (ii) $\frac{9}{25}, \frac{11}{26}, \frac{13}{28}$
   (iii) $\frac{17}{16}, \frac{35}{52}, \frac{65}{75}$ (iv) $\frac{30}{45}, \frac{30}{50}, \frac{38}{80}$

ANSWERS

1. (i) a, (ii) b, (iii) b, (iv) c
2. (i) b, (ii) a, (iii) c, (iv) c
3. (i) a, (ii) a, (iii) a, (iv) b

Reciprocal Fraction : The reciprocal fraction of a number k be $1/k$ *i.e.,* the product of a reciprocal number with the number itself is unity (*i.e.,* 1) hence the reciprocal of 6 is $\frac{1}{6}$, the reciprocal of $\frac{1}{8}$ is 8, the reciprocal of $\frac{3}{5}$ is $\frac{5}{3}$.

Compound Fraction : The fraction of a fraction is called its compound fraction for examples $\frac{1}{3}$ of $\frac{1}{2}\left(i.e., \frac{1}{3} \times \frac{1}{2} = \frac{1}{6}\right)$ is the compound fraction.

Scanned by CamScanner

yoursmahboob.wordpress.com

Complex Fraction : If the numerator or denominator or both of a fraction are fraction then it is called as complex fraction. For example $\frac{2/3}{7/8}, \frac{7/5}{2}, \frac{3/7}{8/9}, \frac{2}{3/7}$ etc.

Remember :

$$\frac{a/b}{c/d} = \frac{a}{b} \times \frac{d}{c}$$

$$\frac{a/b}{c} = \frac{a}{b \times c}$$

$$\frac{a}{b/c} = \frac{a \times c}{b}$$

Continued Fraction : A continued fraction consists of the fractional denominators

e.g., (i) $1+\cfrac{1}{2+\cfrac{1}{3+\cfrac{1}{4+\frac{1}{5}}}}$ (ii) $2+\cfrac{3}{5+\cfrac{2}{7+\cfrac{6}{5+\frac{2}{3}}}}$

NOTE These fractions are solved starting from the bottom towards upside.

SIMPLIFICATION OF FRACTIONS

EXAMPLE 1 *Solve the following expressions :*

(i) $\frac{3}{5}+\frac{2}{7}$ (ii) $\frac{7}{3}+\frac{9}{2}$ (iii) $8\frac{3}{7}+6\frac{1}{5}$ (iv) $\frac{8}{3}-\frac{13}{6}$

(v) $\frac{6}{55}-\frac{7}{88}$ (vi) $9\frac{3}{5}-5\frac{3}{9}$ (vii) $\frac{16}{5}-\frac{3}{8}+\frac{11}{10}$

(viii) $\frac{193}{75}+\frac{37}{81}-\frac{18}{65}$

SOLUTION (i) $\frac{3}{5}+\frac{2}{7}=\frac{3\times7}{5\times7}+\frac{2\times5}{7\times5}=\frac{21+10}{35}=\frac{31}{35}$

(ii) $\frac{7}{3}+\frac{9}{2}=\frac{7\times2}{3\times2}+\frac{9\times3}{2\times3}=\frac{14+27}{6}=\frac{41}{6}=6\frac{5}{6}$

(iii) $8\frac{3}{7}+6\frac{1}{5}=\frac{59}{7}+\frac{31}{5}=\frac{59\times5}{7\times5}+\frac{31\times7}{5\times7}$

$=\frac{295+217}{35}=\frac{512}{35}=14\frac{22}{35}$

(iv) $\frac{8}{3}-\frac{13}{6}=\frac{8\times2}{3\times2}-\frac{13}{6}=\frac{16}{6}-\frac{13}{6}=\frac{3}{6}=\frac{1}{2}$

(v) $\frac{6}{55}-\frac{7}{88}=\frac{6\times8}{55\times8}-\frac{7\times5}{88\times5}=\frac{48}{440}-\frac{35}{440}=\frac{13}{440}$

(vi) $9\frac{3}{5}-5\frac{3}{9}=\frac{48}{5}-\frac{48}{9}=\frac{48\times9}{5\times9}-\frac{48\times5}{9\times5}$

$=\frac{432}{45}-\frac{240}{45}=\frac{192}{45}=\frac{64}{15}=4\frac{4}{15}$

(vii) $\frac{16}{5}-\frac{3}{8}+\frac{11}{10}=\frac{16\times8}{5\times8}-\frac{3\times5}{8\times5}+\frac{11\times4}{10\times4}$

$=\frac{128-15+44}{40}=\frac{157}{40}=3\frac{37}{40}$

(viii) $\frac{193}{75}+\frac{37}{81}+\frac{18}{65}=\frac{193\times27\times13}{75\times27\times13}+\frac{37\times25\times13}{81\times25\times13}+\frac{18\times81\times5}{65\times81\times5}$

$=\frac{67743+12025+7290}{26325}$

$=\frac{87058}{26325}=3\frac{8083}{26325}$

EXAMPLE 2 *Simplify the following expressions :*

(i) $\frac{3}{7}\times\frac{5}{4}$ (ii) $\frac{3}{8}\times\frac{9}{16}\times\frac{7}{5}$

(iii) $\frac{9}{7}\times\frac{21}{6}\times\frac{5}{8}\times3\frac{5}{6}$ (iv) $\frac{4}{9}$ *of* $\frac{729}{48}$

(v) $\frac{1}{2}$ *of* $\left(\frac{16}{7}+\frac{5}{3}\right)$ (vi) $\frac{2}{3}$ *of* $21\frac{4}{9}-9\frac{4}{11}$

(vii) $\frac{6}{15}\div\frac{3}{2}$ (viii) $\frac{14}{9}\div\frac{3}{7}$

(ix) $\frac{3}{7}\div\frac{2}{7}\times\frac{21}{8}$ (x) $\frac{9}{5}$ *of* $\frac{37}{8}\times\frac{36}{74}$

(xi) $5\frac{1}{3}\div\frac{4}{15}$ (xii) $36\div4$ *of* $\frac{1}{2}+\frac{3}{4}\times\frac{3}{2}$

SOLUTION (i) $\frac{3}{7}\times\frac{5}{4}=\frac{15}{28}$

(ii) $\frac{3}{8}\times\frac{9}{16}\times\frac{7}{5}=\frac{189}{640}$

(iii) $\frac{9}{7}\times\frac{21}{6}\times\frac{5}{8}\times3\frac{5}{6}=\frac{9}{7}\times\frac{21}{6}\times\frac{5}{8}\times\frac{23}{6}=\frac{345}{32}=10\frac{25}{32}$

(iv) $\frac{4}{9}$ of $\frac{729}{48}=\frac{4}{9}\times\frac{729}{48}=\frac{1}{9}\times\frac{729}{12}$

$=\frac{1}{1}\times\frac{81}{12}=\frac{1}{1}\times\frac{27}{4}=\frac{27}{4}=6\frac{3}{4}$

(v) $\frac{1}{2}$ of $\left(\frac{16}{7}+\frac{5}{3}\right)=\frac{1}{2}\times\left(\frac{16}{7}+\frac{5}{3}\right)$

$=\frac{1}{2}\times\left(\frac{48}{21}+\frac{35}{21}\right)=\frac{1}{2}\left(\frac{83}{21}\right)=\frac{83}{42}=1\frac{41}{42}$

(vi) $\frac{2}{3}$ of $21\frac{4}{9}-9\frac{4}{11}=\frac{2}{3}\times21\frac{4}{9}-9\frac{4}{11}$

$=\frac{2}{3}\times\frac{193}{9}-\frac{103}{11}=\frac{386}{27}-\frac{103}{11}$

$=\frac{386\times11}{27\times11}-\frac{103\times27}{11\times27}=\frac{4246-2781}{297}$

$=\frac{1465}{297}=4\frac{277}{297}$

(vii) $\frac{6}{15}\div\frac{3}{2}=\frac{6/15}{3/2}=\frac{6}{15}\times\frac{2}{3}=\frac{4}{15}$

(viii) $\frac{14}{9}\div\frac{3}{7}=\frac{14/9}{3/7}=\frac{14}{9}\times\frac{7}{3}=\frac{98}{27}=3\frac{17}{27}$

(ix) $\frac{3}{7}\div\frac{2}{7}\times\frac{21}{8}=\frac{3}{7}\times\frac{7}{2}\times\frac{21}{8}=\frac{63}{16}=3\frac{15}{16}$

(x) $\frac{9}{5}$ of $\frac{37}{8}\times\frac{36}{74}=\frac{9}{5}\times\frac{37}{8}\times\frac{36}{74}=\frac{81}{20}=4\frac{1}{20}$

(xi) $5\frac{1}{3}\div\frac{4}{15}=\frac{16}{3}\div\frac{4}{15}=\frac{16}{3}\times\frac{15}{4}=\frac{20}{1}=20$

(xii) $36\div4$ of $\frac{1}{2}+\frac{3}{4}\times\frac{3}{2}=36\div4\times\frac{1}{2}+\frac{3}{4}\times\frac{3}{2}$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= 36 \div 2 + \frac{9}{8} = 18 + \frac{9}{8}$$

$$= \frac{153}{8} = 19\frac{1}{8}$$

EXAMPLE 3 *Simplify the following expressions :*

(a) $1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{6}}}$

(b) $1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{1}}}}}$

(c) $2 - \cfrac{1}{3 + \cfrac{1}{4 - \cfrac{1}{5 + \cfrac{1}{6 - \cfrac{1}{7}}}}}$

SOLUTION (a) $1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{6}}} = 1 + \cfrac{1}{1 + \cfrac{1}{7/6}}$

$$= 1 + \frac{1}{1 + \frac{6}{7}} = 1 + \frac{1}{13/7}$$

$$= 1 + \frac{7}{13} = \frac{20}{13} = 1\frac{7}{13}$$

(b) $1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{1}}}}} = 1 + \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{1}{1 + \frac{1}{2}}}}$

$$= 1 + \frac{1}{1 + \cfrac{1}{1 + \frac{1}{\frac{3}{2}}}} = 1 + \frac{1}{1 + \cfrac{1}{1 + \frac{2}{3}}}$$

$$= 1 + \frac{1}{1 + \frac{1}{\frac{5}{3}}} = 1 + \frac{1}{1 + \frac{3}{5}} = 1 + \frac{1}{\frac{8}{5}}$$

$$= 1 + \frac{5}{8} = \frac{13}{8} = 1\frac{5}{8}$$

(c) $2 - \cfrac{1}{3 + \cfrac{1}{4 - \cfrac{1}{5 + \cfrac{1}{6 - \frac{1}{7}}}}} = 2 - \cfrac{1}{3 + \cfrac{1}{4 - \cfrac{1}{5 + \frac{1}{41/7}}}}$

$$= 2 - \frac{1}{3 + \cfrac{1}{4 - \cfrac{1}{5 + \frac{7}{41}}}} = 2 - \frac{1}{3 + \cfrac{1}{4 - \frac{1}{212/41}}}$$

$$= 2 - \frac{1}{3 + \cfrac{1}{4 - \frac{41}{212}}} = 2 - \frac{1}{3 + \frac{1}{\frac{807}{212}}}$$

$$= 2 - \frac{1}{3 + \frac{212}{807}} = 2 - \frac{1}{\frac{2633}{807}} = 2 - \frac{807}{2633}$$

$$= \frac{4459}{2633} = 1\frac{1826}{2633}$$

HCF AND LCM OF FRACTIONS

HCF of fractions : The greatest common fraction is called the HCF of the given fractions.

$$\text{HCF of fractions} = \frac{\text{HCF of Numerator}}{\text{LCM of denominator}}$$

For example, The HCF of $\frac{4}{3}, \frac{4}{9}, \frac{2}{15}, \frac{36}{21}$

$$= \frac{\text{HCF of } 4,\ 4,\ 2,\ 36}{\text{LCM of } 3,\ 9,\ 15,\ 21} = \frac{2}{315}$$

LCM of fractions : The least possible number of fraction which is exactly divisible by all the given fractions is called the LCM of the fractions.

$$\text{LCM of fractions} = \frac{\text{LCM of Numerator}}{\text{HCF of Denominator}}$$

For example The LCM of $\frac{4}{3}, \frac{4}{9}, \frac{2}{15}, \frac{36}{21}$

$$= \frac{\text{LCM of } 4,\ 4,\ 2,\ 36}{\text{HCF of } 3,\ 9,\ 15,\ 21} = \frac{36}{3} = 12$$

EXAMPLE 1 *Find the smallest positive number which is exactly divisible by* $\frac{1}{3}, \frac{1}{2}, \frac{3}{7}$ *and* $\frac{4}{11}$.

SOLUTION The LCM of the given numbers will be the required number. So, the LCM of $\frac{1}{3}, \frac{1}{2}, \frac{3}{7}, \frac{4}{11}$

$$= \frac{\text{LCM of } 1,\ 1,\ 3,\ 4}{\text{HCF of } 3,\ 2,\ 7,\ 11} = \frac{12}{1} = 12$$

Thus 12 is the smallest positive numbers, which is required.

EXAMPLE 2 *Four runners started running the race in the same direction around a circular path of 7 km. Their speeds are 4, 3, 9 and 3.5 km/hr individually. If they have started their race at 6 o'clock in the morning, then at what time they will be at the starting point?*

SOLUTION Time required by everyone to complete one revolution individually is $\frac{7}{4}, \frac{7}{3}, \frac{7}{9}, \frac{7}{3.5}$ hours.

Therefore everyone must reach at the starting point after the time of the LCM of the individual time period for one revolution.

Scanned by CamScanner

yoursmahboob.wordpress.com

So the LCM of $\frac{7}{4}, \frac{7}{3}, \frac{7}{9}, \frac{7}{3.5} = \frac{7}{4}, \frac{7}{3}, \frac{7}{9}, \frac{2}{1}$

$= \frac{\text{LCM of } 7, 7, 7, 2}{\text{HCF of } 4, 3, 9, 1} = \frac{14}{1} = 14$ hours.

Hence after 14 hours i.e., at 8 o'clock in the evening of the same day they will meet at the starting point.

Square, square root, cube and cube root of fractions

Remember : $\sqrt{ab} = \sqrt{a}\sqrt{b}$ and $\sqrt{\frac{a}{b}} = \frac{\sqrt{a}}{\sqrt{b}}$

$(ab)^2 = a^2 b^2$ and $\left(\frac{a}{b}\right)^2 = \frac{a^2}{b^2}$

$$\text{Square of a fraction} = \frac{\text{Square of numerators}}{\text{Square of denominators}}$$

$$\text{Similarly, Cube of a fraction} = \frac{\text{Cube of numerator}}{\text{Cube of denominator}}$$

EXAMPLE 3 *Evaluate the following :*

(a) $\left(\frac{3}{4}\right)^2$ (b) $\left(\frac{17}{25}\right)^2$ (c) $\left(\frac{19}{-31}\right)^2$ (d) $\left(\frac{78}{36}\right)^2$

(e) $\left(\frac{9}{7}\right)^3$ (f) $\left(-\frac{13}{12}\right)^3$ (g) $\left(\frac{20}{7}\right)^3$ (h) $\left(6\frac{1}{2}\right)^3$

SOLUTION (a) $\frac{9}{16}$ (b) $\frac{289}{625}$ (c) $\frac{361}{961}$ (d) $\frac{1521}{324}$

(e) $\frac{729}{343}$ (f) $-\frac{2197}{1728}$ (g) $\frac{8000}{343}$ (h) $\frac{2197}{8}$

EXAMPLE 4 *Evaluate the following :*

(a) $\sqrt{\frac{961}{625}}$ (b) $\frac{\sqrt{7744}}{20}$ (c) $\frac{31}{\sqrt{1681}}$ (d) $\sqrt{\frac{1156}{529}}$

(e) $\sqrt{50} \times \sqrt{18}$ (f) $\sqrt{39} \times \sqrt{\frac{75}{2197}}$

SOLUTION (a) $\sqrt{\frac{961}{625}} = \frac{31}{25}$

(b) $\frac{\sqrt{7744}}{20} = \frac{88}{20} = 4\frac{8}{20} = 4\frac{2}{5}$

(c) $\frac{31}{\sqrt{1681}} = \frac{31}{41}$

(d) $\frac{\sqrt{1156}}{\sqrt{529}} = \frac{34}{23}$

(e) $\sqrt{50} \times \sqrt{18} = \sqrt{50 \times 18} = \sqrt{900} = 30$

(f) $\sqrt{39} \times \sqrt{\frac{75}{2197}} = \sqrt{\frac{39 \times 75}{2197}}$

$= \sqrt{\frac{13 \times 3 \times 3 \times 25}{13 \times 13 \times 13}} = \frac{15}{13} = 1\frac{2}{13}$

EXAMPLE 5 *The value of* $\left\{\frac{1}{(\sqrt{2}-2)} + \frac{1}{(\sqrt{2}+2)} + (\sqrt{2}+2)\right\}$ *is :*

(a) 2 (b) 4

(c) $2\sqrt{2}$ (d) *none of these*

SOLUTION $\left\{\frac{(\sqrt{2}+2)+(\sqrt{2}-2)}{(\sqrt{2}-2)(\sqrt{2}+2)} + (\sqrt{2}+2)\right\} = 2$

EXAMPLE 6 *The value of* $\left\{\frac{1}{(\sqrt{6}-\sqrt{5})} - \frac{1}{(\sqrt{5}-\sqrt{4})} + \frac{1}{(\sqrt{4}-\sqrt{3})} - \frac{1}{(\sqrt{3}-\sqrt{2})} + \frac{1}{(\sqrt{2}-1)}\right\}$ *is :*

(a) 5 (b) 7

(c) $\sqrt{12}$ (d) *none of these*

SOLUTION $\frac{1}{(\sqrt{6}-\sqrt{5})} - \frac{1}{(\sqrt{5}-\sqrt{4})} + \frac{1}{(\sqrt{4}-\sqrt{3})} - \frac{1}{(\sqrt{3}-\sqrt{2})} + \frac{1}{(\sqrt{2}-1)}$

$= (\sqrt{6}+\sqrt{5}) - (\sqrt{5}+\sqrt{4}) + (\sqrt{4}+\sqrt{3}) - (\sqrt{3}+\sqrt{2}) + (\sqrt{2}+1)$

$= \sqrt{6} + 1$

$\left[\because \frac{1}{\sqrt{a}-\sqrt{b}} = \frac{(\sqrt{a}+\sqrt{b})}{(\sqrt{a}-\sqrt{b})(\sqrt{a}+\sqrt{b})} = \frac{\sqrt{a}+\sqrt{b}}{(a-b)}\right]$

Hence (d) is the correct option.

PRACTICE EXERCISE

1. Find the value of $\frac{1}{\sqrt{9}-\sqrt{4}}$.

2. Find the value of x if $\sqrt{1+\frac{x}{169}} = \frac{14}{13}$.

3. Find the value of x if $140\sqrt{x} + 315 = 1015$.

4. If $\sqrt{\left(1+\frac{27}{169}\right)} = \left(1+\frac{x}{13}\right)$ then find the value of x.

5. Find the value of $\left[6\frac{1}{4} \div \left\{2\frac{1}{4} - \frac{1}{2}\left(2\frac{1}{2} - \overline{\frac{1}{4} - \frac{1}{6}}\right)\right\}\right]$.

6. Find the value $\frac{3}{2}$ of $\left(\frac{4}{3} \div \frac{5}{7}\right) + \frac{1}{2} \div \left[3\frac{4}{5} - \left\{\frac{2}{5} \div \left(\frac{1}{3} + \frac{1}{2} + \overline{\frac{1}{5} - \frac{1}{6}}\right)\right\}\right]$.

7. Find the value of $1 + \cfrac{1}{2 + \cfrac{1}{4 + \cfrac{1}{8 + \cfrac{1}{16}}}}$.

8. Find the value of $1 - \cfrac{1}{2 + \cfrac{1}{2 - \cfrac{1}{2 + \cfrac{1}{2}}}}$.

9. Calculate the value of $\frac{2}{5} + 2\frac{4}{9} \div \left[\left(7\frac{5}{12} - 5\frac{3}{4}\right) \div 22\frac{1}{2} + 10 \times \frac{5}{18}\right] - \frac{4}{5}$.

10. Calculate the value of $\cfrac{1}{2 + \cfrac{1}{2 + \cfrac{1}{2 - \frac{1}{2}}}}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

11. Calculate the value of $\left(1\frac{29}{36}+1\frac{7}{11}\times 4\frac{1}{8}\right)\div\left(5\frac{1}{9}-\frac{63}{8}\div 9\frac{9}{20}\right)$.

12. Calculate the value of $\frac{4}{2\frac{1}{3}}+\frac{3}{1\frac{3}{4}}-\frac{5}{3\frac{1}{2}}$.

ANSWERS

1. 1 **2.** 27 **3.** 25 **4.** 1 **5.** 6
6. $2\frac{2061}{2170}$ **7.** $1\frac{532}{1193}$ **8.** $\frac{13}{21}$ **9.** $\frac{16}{35}$ **10.** $\frac{8}{19}$
11. 2 **12.** 2

EXAMPLE 1 *From a rope of length* $38\frac{3}{5}$ *m, a piece of length* $5\frac{3}{38}$ *m is cut off. The length of the remaining rope is :*

(a) $190\frac{99}{33}$ *(b)* $33\frac{90}{190}$
(c) $33\frac{99}{190}$ *(d) none of these*

SOLUTION Total length of the rope $= 38\frac{3}{5}=\frac{193}{5}$

The length of the rope which has been removed $= 5\frac{3}{38}=\frac{193}{38}$

$\therefore$ The length of the remaining part of the rope

$$=\frac{193}{5}-\frac{193}{38}=33\frac{99}{199}$$

Hence (c) is the correct option.

EXAMPLE 2 *The cost of 1 metre cloth is Rs.* $21\frac{1}{2}$ *then the cost of* $\frac{42}{43}$ *metre :*

(a) Rs. 21 *(b) Rs. 42*
(c) Rs. $\frac{43}{2}$ *(d) none of these*

SOLUTION $\because$ The price of 1m cloth $= 21\frac{1}{2}=\frac{43}{2}$

$\therefore$ the price of $\frac{42}{43}$ m cloth $=\frac{42}{43}\times\frac{43}{2}=21$

Hence option (a) is correct.

EXAMPLE 3 *A drum of kerosene oil is* $\frac{3}{4}$ *full. When 15 litres of oil is drawn from it, it is* $\frac{7}{12}$ *full. The capacity of the drum is :*

(a) 45 *(b) 90*
(c) 60 *(d) can't be determined*

SOLUTION Let the capacity of drum be x

then $\frac{3}{4}x-15=\frac{7}{12}x$

$\Rightarrow \frac{9x-7x}{12}=15$

$\Rightarrow x=90$

Thus (b) is the correct option.

Alternatively : If you consider option (b) then

$$90\times\frac{3}{4}-15=90\times\frac{7}{12}$$

Alternatively: The decrease in amount $=\frac{x}{6}=15$

$\Rightarrow x=90$ litre.

EXAMPLE 4 *A sum of Rs. 11200 is shared among Mr. Khare, Mr. Patel and Mr. Verma. Mr. Khare gets* $\frac{1}{4}$*th of it while Mr. Patel gets* $\frac{1}{5}$*th of it. The amount of Mr. Verma is :*

(a) 6006 *(b) 6160*
(c) 3080 *(d) data insufficient*

SOLUTION The share of Mr. Khare $=\frac{1}{4}$

The share of Mr. Patel $=\frac{1}{5}$

$\therefore$ The share of Mr. Verma $= 1-\left(\frac{1}{4}+\frac{1}{5}\right)=\frac{11}{20}$

So, the amount of Mr. Verma $=\frac{11}{20}\times 11200=6160$

Thus option (b) is correct.

EXAMPLE 5 *When Sarvesh travelled 33 km, he found that* $\frac{2}{3}$*rd of the entire journey was still left. The length of the total journey is :*

(a) 66 *(b) 132* *(c) 99* *(d) 100*

SOLUTION Since $\frac{2}{3}$rd journey is left, it means Sarvesh has travelled only $\frac{1}{3}$rd of his journey which is equal to 33. Thus i.e.,

$$\frac{1}{3}x=33 \Rightarrow x=99$$

Hence (b) is the right choice.

EXAMPLE 6 *Mrs. Verma earns Rs. 18000 per month. She spends* $\frac{7}{12}$ *on house hold items and* $\frac{1}{8}$ *on rest of the things. The amount she saves is :*

(a) 7120 *(b) 5250*
(c) 5520 *(d) none of these*

SOLUTION Her total expenditure $=\frac{7}{12}+\frac{1}{8}=\frac{17}{24}$

$\therefore$ Her savings $= 1-\frac{17}{24}=\frac{7}{24}$

$\therefore$ Her saving in Rs. $=\frac{7}{24}\times 18000$

$= 5250$

Hence (b) is the correct option.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 7 *Neha, a working lady, earns Rs. x per month. If she spends $\frac{2}{5}$th of her earning for personal uses and $\frac{3}{4}$th of the personal uses, she spends in entertainment while $\frac{7}{20}$th of the expenditure in entertainment she spends in movies only. Her salary would be , if her expenditure in movies is in integers.*

(a) 4225 *(b)* 2175 *(c)* 200 *(d)* 3465

SOLUTION Since her salary is Rs. x then her expenditure in movies is

$$\frac{7}{20}\text{ of }\frac{3}{4}\text{ of }\frac{2}{5}\text{ of }x=\frac{7}{20}\times\frac{3}{4}\times\frac{2}{5}\times x=\frac{21x}{200}$$

Now, In order to $\frac{21x}{200}$ be an integer so x must be equal to 200.

Thus (c) is the correct option.

DECIMAL FRACTIONS

In the previous topics I have discussed the integral and fractional numbers. Now in the ongoing discussion. I am extenting the theory of numbers as "decimal numbers".

In the number 8637, the place value of 7 is $7\times1=7$, the place value of 3 is $10\times3=30$, the place value of 6 is $6\times100=600$ and the place vale of 8 is $8\times1000=8000$.

Thus, as we move from right to left each next digit is multiplied by 10, 100, 1000, 10000, 100000 etc.

It means moving from left to right the place value of each digit is divided by 10, 100, 1000, etc.....

In the above number 7 is known as unit digit (the right most digit), 3 is known as tens digit, 6 as hundreds digit and 8 as thousands digit.

Now if we move towards the right of unit place, the place value of the digit next to the right of unit digit (is the tenths digit) is being divided by 10, while the place value of the next digit is the hundredth digit is being divided by 100 and so on.

So, for our convenience we put a small dot just right to the unit digit and it is known as decimal point.

Hence, the place value of a digit in a number depends on the place or position with respect to the unit digit position while the **face value** of a digit is always fixed as the face value of 1 is 1, 2 is 2, 3 is 3, 4 is 4 and so on.

Place Value Chart

Places	Ten thousands	Thousands	Hundreds	Tens	Unit	Decimal point	Tenths	Hundredths	Thousandths
Value	10000	1000	100	10	1	.	$\frac{1}{10}$	$\frac{1}{100}$	$\frac{1}{1000}$

Thus a decimal number say 4637.938 can be expressed as

$$4\times1000+6\times100+3\times10+7\times1+\frac{9}{10}+\frac{3}{100}+\frac{8}{1000}.$$

NOTE The digits written in the right side of decimal point read separately as we read 2.359 as two point three five nine.

Thus the fraction whose denominators are 10, 100, 1000 etc. are called decimal fractions.

The number left to the decimal point is a whole or integral number, while the number to right to the decimal point is a **decimal number.** In the number 735.82, 735 is a whole number and .82 is the **decimal number.**

Conversion of decimal numbers into decimal fractions : Write the number of zeros as the number of digits in the decimal number preceded by 1, below the actual number without decimal point as

$$23.6=\frac{236}{10},\qquad 4.579=\frac{4579}{1000}$$

$$75.89=\frac{7589}{100},\quad 0.18870=\frac{18870}{100000}=\frac{1887}{10000}$$

Conversion of decimal fractions into decimal numbers : Count the number of zeros in the denominator and then count the same number of digits in the numerator starting from the unit digit of the numerator moving to the left and then place the decimal point as :

$$\frac{2375}{10}=237.5,\qquad \frac{2375}{100}=23.75,\quad \frac{2375}{1000}=2.375,$$

$$\frac{2375}{100000}=0.02375,\quad \frac{2375}{10000000}=0.0002375\text{ etc.}$$

NOTE $0.35=0.350=0.3500=0.35000$ etc. because increasing the number of zeros in the rightmost of a decimal number is inconsiderable.

For example $0.35=\frac{35}{100}$

$$0.350=\frac{350}{1000}=\frac{35}{100}$$

and $$0.3500=\frac{3500}{10000}=\frac{35}{100}$$

Some mathematical operations on decimal numbers :

(i) Addition and Subtraction : The decimal numbers are written in such a manner that decimal points of all the numbers fall in one column or fall below one another. For example

$$\begin{array}{r}2.358\\709.21\\0.35\\+\ 2.0067\\\hline 713.9247\end{array}\qquad\text{and}\qquad\begin{array}{r}635.888\\-\ 28.0125\\\hline 607.8755\end{array}$$

(ii) Multiplication : Suppose there is no decimal point as natural numbers and then multiply them.

Then put the decimal point in the product as the sum of the decimal places in the multiplicands. For example

	Decimal Places
(i) $23\times1.1=25.3$	$0+1=1$
(ii) $3.8\times4.6=17.48$	$1+1=2$
(iii) $2.456\times7.8=19.1568$	$3+1=4$
(iv) $8.125\times100=812.500$	$(3+0)=3$
(v) $75\times0.3=22.5$	$(0+1)=1$

Scanned by CamScanner

yoursmahboob.wordpress.com

(iii) Division : Make the divisor as a natural number by shifting the decimal in the right hand side equally in dividend and divisor. Now divide the resultant dividend by this resultant divisor as usual.

For Example :

$$65 \div 1.3 = \frac{65}{1.3} = \frac{650}{13} = 50$$

$$235 \div 4.7 = \frac{235}{4.7} = \frac{2350}{47} = 50$$

$$1.17 \div 13 = \frac{1{\cdot}17}{13} = 0.09 \quad \left[\because \frac{1{\cdot}17}{13} = \frac{117}{13} \times \frac{1}{100} = 9 \times \frac{1}{100}\right]$$

$$172.8 \div 0.12 = \frac{172.8}{0.12} = \frac{17280}{12} = 1440$$

$$1{\cdot}068 \div 8.9 = \frac{1.068}{8.9} = \frac{10.68}{89} = 0.12$$

$$78 \div 0.0039 = \frac{78}{0.0039} = \frac{780000}{0039}$$

$$= \frac{780000}{39} = 20000$$

Recurring Decimal : A decimal number in which a digit or a set of digits repeats regularly, over a constant period, is called a recurring decimal or periodic decimal. For example

2.33333..., 7.5555, ..., 108.232323...

9.142857142857142857.....

where $2.3333\ldots = 2.\overline{3}$ or $2.\dot{3}$

$7.5555\ldots = 7.\overline{5}$ or $7.\dot{5}$

$108.232323\ldots = 108.\overline{23}$

and $9.142857142857142857\ldots = 9.\overline{142857} = 9.\dot{1}4285\dot{7}$

So the recurring of the decimal number is expressed by putting the bar or dot over the period of a recurring decimal.

(i) Pure Recurring decimal : A decimal fraction in which all the figures (or digits) occur repeatedly, is called a pure recurring decimal as 7.4444, ..., 2.666, ..., 9.454545, ... etc.

Mixed Recurring decimal : A decimal, number in which some of the digits do not recur is called a mixed recurring decimal for example 327.63454545...

Non-recurring decimals : A decimal number in which there is no any regular pattern of repetition of digits after decimal point is called a non-recurring decimal.

e.g., 3.2466267628....

CONVERSION OF RECURRING DECIMAL INTO VULGAR FRACTION

(a) Pure Recurring Decimal

Write down as many 9's in the denominator as the number of digits in the period of decimal number, below the given decimal no., for example,

(i) $0.77777\ldots = 0.\overline{7} = \frac{7}{9}$

(ii) $0.545454\ldots = 0.\overline{54} = \frac{54}{99}$

(iii) $2.357357357357\ldots = 2.\overline{357} = 2 + 0.\overline{357}$

$$= 2 + \frac{357}{999} = \frac{2355}{999}$$

(iv) $0.768397683976839\ldots = 0.\overline{76839} = \frac{76839}{99999}$

(b) Mixed Recurring Decimal

Step 1. Write down the number and then subtract from it the no. formed by the non recurring digits after decimal point.

Step 2. Write down as many 9's as there are digits in the period of the recurring decimal followed by as many zeros as there is number of digits which are not recurring after the decimal point.

Step 3. Divide the value of step 1 by the value obtained in step 2.

For example :

1. $0.17777\ldots = 0.1\overline{7} = \frac{17-1}{90} = \frac{16}{90} = \frac{8}{45}$

2. $0.8737373\ldots = 0.\overline{873} = \frac{873-8}{990} = \frac{865}{990} = \frac{173}{198}$

3. $0.78943943943\ldots = 0.78\overline{943} = \frac{78943-78}{99900}$

$$= \frac{78865}{99900} = \frac{15773}{19980}$$

4. $0.250121212\ldots = 0.25\overline{012} = \frac{25012-250}{99000}$

$$= \frac{24762}{99000} = \frac{12381}{49500}$$

5. $5.00\overline{72} = 5 + 0.00\overline{72} = 5 + \left(\frac{72-00}{9900}\right)$

$$= 5 + \frac{72}{9900} = 5 + \frac{2}{275} = 5\frac{2}{275}$$

ADDITION AND SUBTRACTION OF RECURRING DECIMALS

EXAMPLE 1 $5.7\overline{32} + 8.\overline{613}$

SOLUTION $5.7\overline{32} + 8.\overline{613} = 5 + 0.7\overline{32} + 8 + 0.\overline{613}$

$$= 5 + \frac{732-7}{990} + 8 + \frac{613}{999}$$

$$= 5 + \frac{725}{990} + 8 + \frac{613}{999}$$

$$= 13 + \frac{725}{990} + \frac{613}{999} = 13 + \frac{145}{198} + \frac{613}{999}$$

$$= 13 + \frac{145 \times 3 \times 37 + 613 \times 2 \times 11}{2 \times 3 \times 9 \times 11 \times 37}$$

$$= \frac{13 \times 2 \times 3 \times 9 \times 11 \times 37 + 145 \times 3 \times 37 + 613 \times 2 \times 11}{2 \times 3 \times 9 \times 11 \times 37}$$

Scanned by CamScanner

yoursmanboob.wordpress.com

$$= \frac{285714 + 16095 + 13486}{21978} = \frac{315295}{21978} = 14.3459368$$

Alternatively : Step 1. Express the numbers without bar as

$5.732323232 + 8.613613613613$

Step 2. Write the numbers as one above other *i.e.*,

5.732323232
8.613613613

Step 3. Divide this number into two parts. In the first part *i.e.*, left side write as many digits as there will be integral value with non recurring decimal. In the right side write as many digits as the LCM of the number of recurring digits in the given decimal number *e.g.*,

5.7	323232 (Since 5.7 is the integral + non-recurring part]
8.6	136136 (The LCM of 2 and 3 is 6]

Step 4. Now add or subtract as usual.

5.7	323232
8.6	136136
14.3	459368

Step 5. Put the bar over the digits which are on the right side in the resultant value.

$14.3\overline{459368}$

Thus $5.7\overline{32} + 8.\overline{613} = 14.3\overline{459368}$

EXAMPLE 2 *Solve the following :* $19.3\overline{684216} - 16.20\overline{53}$

SOLUTION $19.3684216842168421 - 16.2053535353...$

$= 19.3684216842168421$

$= 16.205353535353535353$

19 . 36	8421684216
− 16.20	5353535353
3.16	3068148863

(Since 16.20 is integral part with non recurring digits]

[The LCM of 5 and 2 is 10]

In the first no. there are 5 recurring digits and in the second no. there are 2 recurring digits]

$19.3\overline{684216} - 16.20\overline{53} = 3.16\overline{3068148863}$

MULTIPLICATION AND DIVISION OF RECURRING DECIMALS

It can be done as usual. Just convert the decimals into vulgar fractions and then operate as required.

Example 1. $97.2\overline{81} \times 100 = 97.2818181 \times 100$

$= 9728.181818 = 9728.1\overline{81}$

(Remember that the set of recurring digits is not altered as in the above problem the set of recurring digit will remain $\overline{81}$ but not $\overline{18}$ since initially it was $\overline{81}$.)

Example 2. $25.6\overline{32} \times 55 = (25 + 0.6\overline{32}) \times 55$

$$= 25\frac{632-6}{990} \times 55 = 25\frac{626}{990} \times 55$$

$$= 25\frac{313}{495} \times 55 = \frac{12688}{495} \times 55$$

$$= \frac{12688}{9} = 1409.7777 = 1409.\overline{7}$$

Example 3. $13.00\overline{5} \times 20 \times 8.4\overline{23} = 13\frac{5}{900} \times 20 \times 8\frac{423-4}{990}$

$$= 13\frac{1}{180} \times 20 \times 8\frac{419}{990}$$

$$= \frac{2341}{180} \times 20 \times \frac{8339}{990} = \frac{2341 \times 8339}{9 \times 990}$$

$$= \frac{19521599}{9 \times 990} = 2190.9763187$$

Example 4. $0.08\overline{9} \div 100 = 0.089999... \div 100$

$= 0.00089999... = 0.0008\overline{9}$

Example 5. $53.08\overline{53} \div 6 = \frac{53 + 0.08\overline{53}}{6} = \frac{53 + \frac{0853-08}{9900}}{6}$

$$= \frac{53 + \frac{845}{9900}}{6} = \frac{53 + \frac{169}{1980}}{6}$$

$$= \frac{\left(\frac{105109}{1980}\right)}{6} = \frac{105109}{1980 \times 6} = \frac{105109}{11880}$$

$= 8.847558922558922558922$

$= 8.847\overline{558922}$

Alternatively : $53.08\overline{53} \div 6 = 53.08535353... \div 6$

$6\overline{)53.08535353...}\,(8.847558922558922$

48
50
48
28
24
45
42
33
30
35
30
53
48
55
54
13
12
15
12
33
30
35
30
53
48
55
54
1 etc.

Square of Decimals : First we assume that there is no decimal point and then square up the given decimal number. But at last we put the dot (as decimal point), counting the digits from the rightmost digit. The no. of places will be double as that of the given number.

Scanned by CamScanner

yoursmahboob.wordpress.com

For example :

1. $(2.3)^2 = 5.29$ $[(23)^2 = 529]$
2. $(1.07)^2 = 1.1449$ $[(107)^2 = 11449]$
3. $(0.11)^2 = 0.0121$ $[(11)^2 = 121]$
4. $(1.352)^2 = 1.827904$ $[\because (1352)^2 = 1827904]$
5. $0.1 = 0.01$ $[\because (1)^2 = 1]$
6. $(9.99)^2 = 99.8001$ $[(999)^2 = 998001]$

Square root of Decimals : The process of finding the square root is same as that of integers. Here we put the decimal point as in the division of decimal numbers.

For example :

1. Find the square root of 5.29

	2.3
2	5.29
2	4
43	129
3	129
	×

$\therefore \sqrt{5.29} = 2.3$

2. Find the square root of 0.0121

	0.11
0	0.0121
0	0
01	01
1	01
21	21
1	21
	×

$\therefore \sqrt{0.0121} = 0.11$

3. Find the square root of 536.85374

	23.1701
2	536.85374
2	4
43	136
3	129
461	785
1	461
4627	32437
7	32389
463401	484000
01	463401

The process can be continued if required. But generally we stop our calculation after 2-3 places of decimal point.

NOTE To find the nth power of a decimal number in which the decimal point is placed at m places before the rightmost digit, we simply solve it considering as an integer then we put the decimal point in the resultant value before the $m.n$ places from the right most digit, where m, n are positive integers.

For example : $(2.13)^4 = 20.58346161$ [The no. of places of decimal point $= 2 \times 4 = 8$]

HCF AND LCM OF DECIMALS

HCF

Step 1. First of all equate the number of places in all the numbers by using zeros, wherever required.

Step 2. Then considering these numbers as integers find the HCF of these numbers.

Step 3. Put the decimal point in the resultant value as many places before the right most digit as that of in the every equated number.

EXAMPLE 1 *Find the HCF of 0.0005, 0.005, 0.15, 0.175, 0.5 and 3.5.*

SOLUTION.

$0.0005 \Rightarrow 5$
$0.0050 \Rightarrow 50$
$0.1500 \Rightarrow 1500$
$0.1750 \Rightarrow 1750$
$0.5000 \Rightarrow 5000$
$3.5000 \Rightarrow 35000$

Then the HCF of 5, 50, 1500, 1750, 5000 and 35000 is 5.

So the HCF of the given number is 0.0005 (since there are four digits in all the adjusted (or equated) decimal places.

EXAMPLE 2 *Find the HCF of 0.9, 0.36 and 1.08.*

SOLUTION

$0.9, 0.36, 1.08 \rightarrow 0.90, 0.36, 1.08 \rightarrow 90, 36, 108$

Now the HCF of 90, 36 and 108 is 18.

So the required HCF of the given numbers is 0.18.

(Since there are two digits after decimal places in every number in second step)

LCM

Step 1. First of all equate the no. of places in all the given numbers by putting the minimum possible no. of zeros at the end of the decimal numbers, wherever ever required.

Step 2. Now consider the equated numbers as integers and then find the LCM of these numbers.

Step 3. Put the decimal point in the LCM of the numbers as many places as that of in the equated numbers.

EXAMPLE 1 *Find the LCM of 1.8, 0.54 and 7.2*

SOLUTION

$1.8, 0.54, 7.2 \rightarrow 1.80, 0.54, 7.20 \rightarrow 180, 54, 720$

Now the LCM of 180, 54 and 720 is 2160

Therefore the required LCM is 21.60.

EXAMPLE 2 *Find the LCM of 4.44, 37 and 55.5*

SOLUTION

$4.44, 37.0, 55.5 \rightarrow 4.44, 37.00, 55.50 \rightarrow 444, 3700, 5550$

Now the LCM of 444, 3700, 5550 is 11100.

Hence the required LCM is 111.00 = 111.

Scanned by CamScanner

yoursmahboob.wordpress.com

INDICES AND SURDS

In the previous articles we have studied the multiplication, as $2\times2=4, 2\times2\times2=8, 2\times2\times2\times2=16, \ldots$

Now, here we extend our discussion to the higher power or index of a number.

as
$$2\times2=2^2=4$$
$$2\times2\times2=2^3=8$$
$$2\times2\times2\times2=2^4=16$$
$$2\times2\times2\times2\times2=2^5=32$$

Similarly, $2\times2\times2\times\ldots\ldots$ upto n times $=2^n$

Thus
$$\underbrace{a\times a\times a\times a\times a\ldots a}_{n \text{ factors}}=a^n$$

Where a is any number and n is a natural number. *i.e.*, a^n is continued product of n equal quantities, each equal to a and is called the nth power of a. 'n' is called the **index** or **exponent** and 'a' is called the **base** of a^n.

Therefore a^n is the exponential expression. a^n is read as 'a raised to the power n' or 'a to the power n'

Laws of Indices

If m and n are positive integers, then

1. $a^m\times a^n=a^{m+n}$
2. $\dfrac{a^m}{a^n}=a^{m-n};\ (a\neq0, m\geq n)$
3. $(ab)^n=a^n.b^n$ 4. $\left(\dfrac{a}{b}\right)^n=\dfrac{a^n}{b^n};\ (b\neq0)$
5. $(a^m)^n=a^{m.n}$ 6. $(a^0)=1;\ (a\neq0)$

Some Important Results

1. If $a^x=k$, then $a=(k)^{1/x}$
2. If $a^{1/x}=k$, then $a=k^x$
3. If $a^x=b^y$, then $a=(b)^{y/x}$ and $b=(a)^{x/y}$
4. If $a^x=a^y$, then $x=y$, where $a\neq0,1$
5. $a^{-n}=\dfrac{1}{a^n}$ and $a^n=\dfrac{1}{a^{-n}}$
6. $a^{b^c}\neq(a^b)^c;\ b\neq c$

EXAMPLE 1 *Solve the following :*
(i) $(5)^3$ *(ii)* $(-6)^4$ *(iii)* $(-2)^5$ *(iv)* $(4)^3$ *(v)* $(-4)^3$

SOLUTION (i) $5^3=5\times5\times5=125$

(ii) $(-6)^4=(-6)\times(-6)\times(-6)\times(-6)=1296$

(iii) $(-2)^5=(-2)\times(-2)\times(-2)\times(-2)\times(-2)=-32$

(iv) $(4)^3=4\times4\times4=64$

(v) $(-4)^3=(-4)\times(-4)\times(-4)=-64$

EXAMPLE 2 *Solve the following expressions.*
(i) $(-2)^3\times5^2$ *(ii)* $(-4)^3\times5^2\times7^0$
(iii) $(32)^{-1/5}$ *(iv)* $(243)^{4/5}$
(v) $(36)^{1/6}$ *(vi)* $\left(-\dfrac{1}{343}\right)^{-2/3}$
(vii) $3^{-3}+(-3)^3$ *(viii)* $(2^2+2^3+2^{-2}+2^{-3})$
(ix) $2^{2x-1}=\dfrac{1}{8^{(x-3)}}$, *then* $x=?$
(x) $4^{2x+1}=8^{x+3}$ *then* $x=?$
(xi) $3^{x-1}+3^{x+1}=90$, *then* $x=?$

SOLUTION (i) $(-2)^3\times5^2=-8\times25=-200$

(ii) $(-4)^3\times5^2\times7^0=-64\times25\times1=-1600$

(iii) $(32)^{-1/5}=(2^5)^{-1/5}=2^{5\times-\frac{1}{5}}=2^{-1}=\dfrac{1}{2}$

(iv) $(243)^{4/5}=(3^5)^{4/5}=3^{5\times\frac{4}{5}}=3^4=81$

(v) $(36)^{1/6}=(6^2)^{1/6}=6^{2\times\frac{1}{6}}=6^{\frac{1}{3}}$

(vi) $\left(-\dfrac{1}{343}\right)^{-2/3}=\left(-\dfrac{1}{7^3}\right)^{-2/3}=(-7^{-3})^{-2/3}$
$=(-7)^{-3\times-2/3}=(-7)^2=49$

(vii) $3^{-3}+(-3)^3=\dfrac{1}{3^3}+(-3)^3=\dfrac{1}{27}-27$
$=\dfrac{1-729}{27}=-\dfrac{728}{27}$

(viii) $(2^2+2^3+2^{-2}+2^{-3})=\left(4+8+\dfrac{1}{4}+\dfrac{1}{8}\right)$
$=12+\dfrac{3}{8}=\dfrac{99}{8}$

(ix) $2^{2x-1}=\dfrac{1}{8^{x-3}}\Rightarrow 2^{2x-1}=\dfrac{1}{2^{3(x-3)}}$

$\Rightarrow 2^{2x-1}=\dfrac{1}{2^{3x-9}}$

$\Rightarrow (2^{2x-1})(2^{3x-9})=1$

$\Rightarrow 2^{(2x-1)+(3x-9)}=1$

$\Rightarrow 2^{5x-10}=1\Rightarrow 2^{5(x-2)}=1$

$\Rightarrow 2^{5(x-2)}=2^0$

$\Rightarrow 5(x-2)=0$

$\Rightarrow x-2=0\Rightarrow x=2$

(x) $4^{2x+1}=8^{x+3}$

$\Rightarrow (2^2)^{(2x+1)}=(2^3)^{(x+3)}$

$\Rightarrow 2^{4x+2}=2^{3x+9}$

$\Rightarrow 4x+2=3x+9$ (∵ base in both side is same)

$\Rightarrow x=7$

(xi) $3^{x-1}+3^{x+1}=90$

$\Rightarrow \dfrac{3^x}{3}+3.3^x=90$

$\Rightarrow 3^x+3^2.3^x=90\times3$

$\Rightarrow 3^x(1+3^2)=270$

$\Rightarrow 3^x(10)=270$

$\Rightarrow 3^x=27$

$\Rightarrow 3^x=3^3$

$\Rightarrow x=3$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *Solve the followings :*

(i) $\left[\left(x+\frac{1}{y}\right)^a\left(x-\frac{1}{y}\right)^b\right]\div\left[\left(y+\frac{1}{x}\right)^a\left(y-\frac{1}{x}\right)^b\right]$ *is equal to :*

(a) $\left(\frac{x}{y}\right)^{a+b}$ (b) $\left(\frac{y}{x}\right)^{(a+b)}$ (c) $\frac{x^a}{y^b}$ (d) $(xy)^{a+b}$

(ii) $\left(\frac{x^b}{x^c}\right)^a\times\left(\frac{x^c}{x^a}\right)^b\times\left(\frac{x^a}{x^b}\right)^c$ *is equal to :*

(a) 0 (b) 1
(c) abc (d) none of these

(iii) *If* $x^{x^{3/2}}=(x^{3/2})^x$, *then the value of x is :*

(a) $\frac{3}{2}$ (b) $\frac{9}{4}$ (c) $\frac{16}{25}$ (d) $\frac{8}{27}$

(iv) *If* $x^a=y^b=z^c$ *and* $y^2=zx$ *then the value of* $\frac{1}{a}+\frac{1}{c}$ *is :*

(a) $\frac{b}{2}$ (b) $\frac{c}{2}$ (c) $\frac{2}{b}$ (d) $2a$

(v) $(a^{m-n})^l\times(a^{n-l})^m\times(a^{l-m})^n$

(a) 1 (b) 0 (c) 2 (d) a^{lmn}

(vi) *If* $a^x=b$, $b^y=c$ *and* $c^z=a$, *then the value of xyz is:*

(a) 0 (b) 1 (c) $x+y+z$ (d) abc

(vii) $\left(\frac{x^a}{x^b}\right)^{a+b}\times\left(\frac{x^b}{x^c}\right)^{b+c}\times\left(\frac{x^c}{x^a}\right)^{c+a}$ *is equal to :*

(a) 1 (b) 0
(c) 2 (d) none of these

(viii) *The value of*

$$\frac{1}{1+x^{b-a}+x^{c-a}}+\frac{1}{1+x^{c-b}+x^{a-b}}+\frac{1}{1+x^{a-c}+x^{b-c}}$$ *is :*

(a) 0 (b) x^{abc} (c) 1 (d) $x^{(a+b+c)}$

(ix) $2^{2^x}=16^{2^{3x}}$, *then x is equal to*

(a) -1 (b) 0
(c) 1 (d) none of these

(x) *The value of the expression*

$$\frac{4^n\times20^{m-1}\times12^{m-n}\times15^{m+n-2}}{16^m\times5^{2m+n}\times9^{m-1}}$$ *is :*

(a) 500 (b) 1 (c) 200 (d) $\frac{1}{500}$

(xi) *The value of the expression*

$$\frac{(0.3)^{1/3}\cdot\left(\frac{1}{27}\right)^{1/4}\cdot(9)^{1/6}\cdot(0.81)^{2/3}}{(0.9)^{2/3}\cdot(3)^{-1/2}\cdot\left(\frac{1}{3}\right)^{-2}\cdot(243)^{-1/4}}$$ *is :*

(a) 0.3 (b) 0.9 (c) 1.27 (d) 0.09

(xii) *The value of expression* $\frac{(0.6)^0-(0.1)^{-1}}{\left(\frac{3}{2^3}\right)^{-1}\cdot\left(\frac{3}{2}\right)^3+\left(-\frac{1}{3}\right)^{-1}}$ *is :*

(a) $-\frac{3}{2}$ (b) $\frac{2}{3}$ (c) $\frac{3}{2}$ (d) $\frac{9}{4}$

(xiii) *If* $\frac{9^n\times3^2\times(3^{-n/2})^{-2}-(27)^n}{3^{3m}\times2^3}=\frac{1}{27}$ *then the value of* $(m-n)$ *is :*

(a) -1 (b) 1 (c) 2 (d) -2

SOLUTION (i) $\left[\left(x+\frac{1}{y}\right)^a\cdot\left(x-\frac{1}{y}\right)^b\right]\div\left[\left(y+\frac{1}{x}\right)^a\left(y-\frac{1}{x}\right)^b\right]$

$$=\frac{\left(x+\frac{1}{y}\right)^a\left(x-\frac{1}{y}\right)^b}{\left(y+\frac{1}{x}\right)^a\left(y-\frac{1}{x}\right)^b}=\frac{\left(\frac{xy+1}{y}\right)^a\left(\frac{xy-1}{y}\right)^b}{\left(\frac{xy+1}{x}\right)^a\left(\frac{xy-1}{x}\right)^b}$$

$$=\frac{\frac{(xy+1)^a}{y^a}\cdot\frac{(xy-1)^b}{y^b}}{\frac{(xy+1)^a}{x^a}\cdot\frac{(xy-1)^b}{x^b}}$$

$$=\frac{(xy+1)^a(xy-1)^b}{y^{(a+b)}}\times\frac{x^{(a+b)}}{(xy+1)^a(xy-1)^b}$$

$$=\frac{x^{a+b}}{y^{a+b}}=\left(\frac{x}{y}\right)^{a+b}$$

Hence (a) is the correct option.

(ii) $\left(\frac{x^b}{x^c}\right)^a\times\left(\frac{x^c}{x^a}\right)^b\times\left(\frac{x^a}{x^b}\right)^c=(x^{b-c})^a\times(x^{c-a})^b\times(x^{a-b})^c$

$$=x^{(ab-ac)}\times x^{(bc-ab)}\times x^{(ac-bc)}$$
$$=x^{(ab-ac)+(bc-ab)+(ac-bc)}$$
$$=x^0=1$$

Hence (b) is the correct option.

(iii) $x^{x^{3/2}}=(x^{3/2})^x$

$\Rightarrow$ $x^{x^{3/2}}=x^{(3/2)x}$

$\Rightarrow$ $x^{3/2}=\frac{3}{2}x$

$\Rightarrow$ $x^{1/2}=\frac{3}{2}\Rightarrow x=\frac{9}{4}$

Hence (b) is the correct option.

(iv) If $x^a=y^b=z^c$ and $y^2=zx$

Let $x^a=y^b=z^c=k$

$\Rightarrow$ $x=k^{1/a}, y=k^{1/b}, z=k^{1/c}$

Now, $\because$ $y^2=zx$

$\therefore$ $(k^{1/b})^2=(k^{1/c}).(k^{1/a})$

$\Rightarrow$ $k^{2/b}=k^{\frac{1}{c}+\frac{1}{a}}$

$\Rightarrow$ $\frac{1}{a}+\frac{1}{c}=\frac{2}{b}$

Hence (c) is the correct option.

(v) $(a^{m-n})^l\times(a^{n-l})^m\times(a^{l-m})^n=a^{ml-nl}\times a^{nm-lm}\times a^{ln-mn}$

$$=a^{ml-nl+nm-lm+ln-mn}$$
$$=a^0=1$$

Thus (a) is correct option.

(vi) If $a^x=b$, $b^y=c$, $c^z=a$

$\because$ $a^x=b$

$\therefore$ $(c^z)^x=b$

$\Rightarrow$ $c^{zx}=b\Rightarrow(b^y)^{zx}=b$

$\Rightarrow$ $b^{yzx}=b\Rightarrow xyz=1$

Hence (b) is the correct option.

Scanned by CamScanner

yoursmahboob.wordpress.com

(vii) $\left(\frac{x^a}{x^b}\right)^{a+b} \times \left(\frac{x^b}{x^c}\right)^{b+c} \times \left(\frac{x^c}{x^a}\right)^{c+a}$

$= (x^{a-b})^{(a+b)} \times (x^{b-c})^{(b+c)} \times (x^{c-a})^{(c+a)}$

$= x^{(a-b)(a+b)} \times x^{(b-c)(b+c)} \times x^{(c-a)(c+a)}$

$= x^{a^2-b^2} \times x^{b^2-c^2} \times x^{c^2-a^2}$

$= x^{a^2-b^2+b^2-c^2+c^2-a^2} = x^0 = 1$

Thus (a) is the correct option.

(viii) $\frac{1}{1+x^{b-a}+x^{c-a}} + \frac{1}{1+x^{c-b}+x^{a-b}} + \frac{1}{1+x^{a-c}+x^{b-c}}$

$= \frac{1}{1+\frac{x^b}{x^a}+\frac{x^c}{x^a}} + \frac{1}{1+\frac{x^c}{x^b}+\frac{x^a}{x^b}} + \frac{1}{1+\frac{x^a}{x^c}+\frac{x^b}{x^c}}$

$= \frac{x^a}{x^a+x^b+x^c} + \frac{x^b}{x^b+x^c+x^a} + \frac{x^c}{x^c+x^a+x^b}$

$= \frac{x^a+x^b+x^c}{x^a+x^b+x^c} = 1$

Hence (c) is correct option.

(ix) $2^{2^x} = 16^{2^{3x}}$

$\Rightarrow 2^{2^x} = (2^4)^{2^{3x}}$

$\Rightarrow 2^{2^x} = 2^{4 \cdot 2^{3x}} = 2^{2^{3x+2}}$

$\Rightarrow 2^{2^x} = 2^{2^{3x+2}}$ [Since base in both sides is equal]

$\Rightarrow 2^x = 2^{3x+2}$

$\Rightarrow x = 3x + 2$

$\Rightarrow 2x = -2$

$\Rightarrow x = -1$

Hence (a) is correct option.

(x) $\frac{4^n \times 20^{m-1} \times 12^{m-n} \times 15^{m+n-2}}{16^m \times 5^{2m+n} \times 9^{m-1}}$

$= \frac{2^{2n} \times 2^{2m-2} \times 5^{m-1} \times 2^{2m-2n} \times 3^{m-n} \times 3^{m+n-2} \times 5^{m+n-2}}{2^{4m} \times 5^{2m+n} \times 3^{2m-2}}$

$= 2^{2n+2m-2+2m-2n-4m} \times 3^{m-n+m+n-2-2m+2} \times 5^{m-1+m+n-2-2m-n}$

$= 2^{-2} \times 3^0 \times 5^{-3}$

$= \frac{1}{4} \times \frac{1}{125} = \frac{1}{500}$

Hence (d) is the correct option.

(xi) $\frac{(0.3)^{1/3} \cdot \left(\frac{1}{27}\right)^{1/4} \cdot (9)^{1/6} \cdot (0.81)^{2/3}}{(0.9)^{2/3} \cdot (3)^{-1/2} \cdot \left(\frac{1}{3}\right)^{-2} \cdot (243)^{-1/4}}$

$= \frac{\left(\frac{3}{10}\right)^{1/3} \left(\frac{1}{3}\right)^{3/4} (3)^{1/3} \cdot \left(\frac{81}{100}\right)^{2/3}}{\left(\frac{9}{10}\right)^{2/3} \left(\frac{1}{3}\right)^{1/2} \cdot (3)^2 \, (3)^{-5/4}}$

$= \frac{3^{\frac{1}{3}+\frac{1}{3}-\frac{3}{4}+\frac{8}{3}} \times 10^{-\frac{1}{3}-\frac{4}{3}}}{3^{\frac{4}{3}+2-\frac{1}{2}-\frac{5}{4}} \times 10^{-\frac{2}{3}}}$

$= \frac{3^{31/12} \times 10^{-\frac{5}{3}}}{3^{\frac{19}{12}} \times 10^{-\frac{2}{3}}}$

$= 3 \times 10^{-1} = \frac{3}{10} = 0.3$

(xii) $\frac{(0.6)^0 - (0.1)^{-1}}{\left(\frac{3}{2^3}\right)^{-1} \cdot \left(\frac{3}{2}\right)^3 + \left(-\frac{1}{3}\right)^{-1}}$

$= \frac{1 - \left(\frac{1}{10}\right)^{-1}}{(3^{-1})(2^3) \times 3^3 \times 2^{-3} + (-3)^1}$

$= \frac{1-10}{3^{3-1} \cdot 2^0 - 3} = \frac{-9}{9-3} = \frac{-9}{6} = \frac{-3}{2}$

Hence (a) is the correct option.

(xiii) $\frac{9^n \times 3^2 \times (3^{-n/2})^{-2} - (27)^n}{3^{3m} \times 2^3} = \frac{1}{27}$

$\Rightarrow \frac{3^{2n} \times 3^2 \times 3^n - 3^{3n}}{3^{3m} \times 2^3} = \frac{1}{3^3}$

$\Rightarrow \frac{3^{2n+2+n} - 3^{3n}}{8 \times 3^{3m}} = \frac{1}{3^3}$

$\Rightarrow \frac{3^{3n+2} - 3^{3n}}{3^{3m} \times 8} = 3^{-3}$

$\Rightarrow \frac{3^{3n}(3^2-1)}{3^{3m} \times 8} = 3^{-3}$

$\Rightarrow 3^{3n-3m} = 3^{-3}$

$\Rightarrow 3n - 3m = -3$

$\Rightarrow m - n = 1$

Hence (b) is the correct option.

HCF : The HCF of $(a^m - 1)$ and $(a^n - 1)$ is equal to the $(a^{\text{HCF of } m, n} - 1)$

EXAMPLE 4 *Find the HCF of* $(2^{315} - 1)$ *and* $(2^{25} - 1)$ *is*

(a) 5 *(b)* 2

(c) 31 *(d) none of these*

SOLUTION The required HCF $= (2)^{\text{HCF of } 315, 25} - 1$

$= 2^5 - 1 = 31$

Hence (c) is the correct option.

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE-1.5

1. Simplify : $(x^{2^{n-1}} + y^{2^{n-1}})(x^{2^{n-1}} - y^{2^{n-1}})$
(a) $x^{2^n} - y^{2^n}$ (b) $x^{2n} + y^{2n}$
(c) $(x^n - y^n)^2$ (d) $(x^2 - y^2)^{n-1}$

2. If $x = 2^{1/3} + 2^{-1/3}$, then the value of $2x^3$ is :
(a) $6x + 5$ (b) $5x + 6$
(c) $6x - 5$ (d) $5x - 6$

3. If $x = 3 + 3^{2/3} + 3^{1/3}$, then the value of $x^3 - 9x^2 + 18x - 12$ is :
(a) 1 (b) 0
(c) -1 (d) $\sqrt{2}$

4. If $x^{1/3} + y^{1/3} + z^{1/3} = 0$, then the value of $(x + y + z)^3$ is :
(a) 27 (b) $27xyz$
(c) 81 (d) $(xyz)^3$

5. If $x^{x(\sqrt{x})} = (x\sqrt{x})^x$, then the value of x is :
(a) $\frac{9}{4}$ (b) $\frac{4}{9}$
(c) 8 (d) 4

6. The value of (x, y) if $5^x + 3^y = 8, 5^{x-1} + 3^{y-1} = 2$ is :
(a) 2, 3 (b) 3, 2
(c) 1, 1 (d) 0, 1

7. The value of (x, y) if $x^y = y^x$ and $x^2 = y^3$ is :
(a) $\frac{27}{8}, \frac{9}{4}$ (b) $\frac{9}{8}, \frac{27}{4}$
(c) $\frac{8}{27}, \frac{4}{9}$ (d) $\frac{8}{9}, \frac{4}{27}$

8. The value of $(ax^{1/4} + 3a^{1/2}x^{1/2} + 4x^{3/4})(a - 3a^{1/2}x^{1/4} + 4x^{1/2})$ is :
(a) $a^2x^{1/4} - ax^{3/4} + 16x^{5/4}$
(b) $ax^2 + x^{3/4} + 9x^{1/4}$
(c) 0
(d) 1

9. The value of $\frac{1}{x^b + x^{-c} + 1} + \frac{1}{x^c + x^{-a} + 1} + \frac{1}{x^a + x^{-b} + 1}$ given that $a + b + c = 0$ is :
(a) 1 (b) 0
(c) abc (d) x

10. The value of $\frac{1}{1 + p + q^{-1}} + \frac{1}{1 + q + r^{-1}} + \frac{1}{1 + r + p^{-1}}$ given that $pqr = 1$ is :
(a) 1 (b) 0
(c) pqr (d) $p + q + r$

SURDS

In the previous articles we have studied about the square roots and cube roots etc. There we have studied those numbers whose roots can be found in the form of an integer, but here we study only those numbers whose roots are not the integers.

Surds : When a root of a rational number (*i.e.*, quantities of the type $\sqrt[n]{a}$, a being a rational number) can not be exactly obtained, then this root is called a **surd.**

For Example $\sqrt{2}, \sqrt{3}, \sqrt{5}, \sqrt{6}, \sqrt{7}, \sqrt{8}, \sqrt{10}$ etc.

$\sqrt[3]{2}, \sqrt[3]{3}, \sqrt[3]{4}, \sqrt[3]{5}, \sqrt[3]{6}, \sqrt[3]{7}, \sqrt[3]{9}, \sqrt[3]{10}$ ...etc

$\sqrt[4]{2}, \sqrt[4]{3}, \sqrt[4]{4}, \sqrt[4]{5}, \sqrt[4]{6}, \sqrt[4]{7}$... etc.

But $\sqrt{4} = 2, \sqrt[3]{27}, \sqrt[4]{16}, \sqrt[5]{32}, \sqrt[6]{729}$... etc are not the surds.

Thus it can be said that "all surds are irrational numbers, but all irrational numbers are not the surds".

For example π, e are irrational, but not surds.

Order of Surds : In a surd $\sqrt[n]{a}$ $[= (a)^{1/n}]$, the value of n is called the order of the surd and a is called the **radicand.**

The surds of second order are called quadratic surds *e.g.*, $\sqrt{5}, \sqrt{6}, (7)^{3/2}$.. The surds of third order are called cubic surds *e.g.*, $\sqrt[3]{3}, \sqrt[3]{7}, (6)^{5/3}, (9)^{2/3}$.

The surds of fourth order are called biquadratic surds *e.g.*, $\sqrt[4]{2}, \sqrt[4]{3}, \sqrt[4]{7}, (5)^{7/4}$.

Mixed Surds : The product of a rational number with a surd is known as a **mixed surd.**

For example, $3\sqrt{2}, 4\sqrt{7}, 5\sqrt[3]{6}, \sqrt{18}\ (=3\sqrt{2})$

NOTE A surd having no rational factor is known as pure surd. *e.g.*, $\sqrt[4]{2}, \sqrt[3]{7}, \sqrt[6]{8}$ etc.

Similar Surds : If the radicands of two or more rationalised surds are same, then these surds are called the **similar surds.** For example, $\sqrt{5}, 3\sqrt{5}, \sqrt{20}\ (=2\sqrt{5})$ and $\sqrt{80}\ (=4\sqrt{5})$ etc.

Conjugate or Complementary Surds : For every surd of the form $\sqrt{a} + \sqrt{b}$ there exists another surd $\sqrt{a} - \sqrt{b}$, which is called the conjugate surd of previous surd and *vice-versa.* For example

$(2\sqrt{3} + 5\sqrt{3})$ and $(2\sqrt{3} - 5\sqrt{3}), (\sqrt{7} + \sqrt{8})$ and $(\sqrt{7} - \sqrt{8}), \ldots$ etc are the pair of conjugate surds.

Properties of Surds

1. A quadratic surd cannot be equal to the sum or difference of a rational number and a quadratic surd *e.g.*, $\sqrt{a} + b \neq \sqrt{c}$ or $\sqrt{a} - b \neq \sqrt{c}$, where $\sqrt{a}, \sqrt{c}$ are quadratic surds and b is a rational number.
2. The product and quotient of two dissimilar quadratic surds can not be rational *e.g.*, $\sqrt{2} \cdot \sqrt{5} = \sqrt{10}$ or $\frac{\sqrt{6}}{\sqrt{2}} = \sqrt{3}$
3. If $a + \sqrt{b} = c + \sqrt{d}$ or $a - \sqrt{b} = c - \sqrt{d}$, then $a = c$ and $b = d$.
4. If $a \pm \sqrt{b} = 0$ then $a = b = 0$
5. If $a + \sqrt{b} = c + \sqrt{d}$, then $a - \sqrt{b} = c - \sqrt{d}$ and its *vice-versa.*
6. If $\sqrt{a + \sqrt{b}} = \sqrt{c} + \sqrt{d}$, then $\sqrt{a - \sqrt{b}} = \sqrt{c} - \sqrt{d}$ and its *vice-versa.*

Scanned by CamScanner

yoursmahboob.wordpress.com

Addition : Only similar surds can be simplified

e.g., $2\sqrt{3}+7\sqrt{3}=9\sqrt{3}$.

$8\sqrt{5}+3\sqrt{5}+\sqrt{20}=8\sqrt{5}+3\sqrt{5}+2\sqrt{5}=13\sqrt{5}$

Subtraction : Only similar surds can be simplified

e.g., $7\sqrt{3}-2\sqrt{3}=5\sqrt{3}$

$8\sqrt{5}-3\sqrt{5}=5\sqrt{5}$ etc.

NOTE $8\sqrt{5}\pm 2\sqrt{6}$ can not be simplified, because radicands are different.

Multiplication : $3^{1/4}\times 6^{1/2}\times 9^{1/3}$

$=3^{3/12}\times 6^{6/12}\times 9^{4/12}$

$=(3^3\times 6^6\times 9^4)^{1/12}$

$=(27\times 46656\times 6561)^{1/12}$

$=(8264970432)^{1/12}$

Division : $25\div\sqrt{5}=\dfrac{25}{\sqrt{5}}=\dfrac{(5)^2}{(5)^{1/2}}=5^{2-\frac{1}{2}}$

$=5^{3/2}=\sqrt{125}$

Rationalisation : Making two or more surds a rational number by multiplication, is called the rationalisation

e.g., $3\sqrt{2}\times 4\sqrt{2}=24$

$7\sqrt{5}\times\sqrt{5}=35$

$(9\sqrt{3}-5\sqrt{3})(9\sqrt{3}+5\sqrt{3})=(9\sqrt{3})^2-(5\sqrt{3})^2=168$

LAWS OF SURDS

(i) $\sqrt[n]{a.b}=\sqrt[n]{a}.\sqrt[n]{b}$ (ii) $\sqrt[n]{\dfrac{a}{b}}=\dfrac{\sqrt[n]{a}}{\sqrt[n]{b}}$

(iii) $(\sqrt[n]{a})^m=\sqrt[n]{a^m}$ (iv) $(\sqrt[n]{a})^n=(a^{1/n})^n=a$

(v) $\sqrt[n]{\sqrt[m]{a}}=\sqrt[mn]{a}$

EXAMPLE 1 *Which one is smaller out of* $\sqrt[3]{2}$ *and* $\sqrt[4]{3}$?

SOLUTION $\sqrt[3]{2}=(2)^{1/3}=2^{4/12}=(16)^{1/12}$

and $\sqrt[4]{3}=(3)^{1/4}=3^{3/12}=(27)^{1/12}$

(Taking the LCM of surd)

Hence $\sqrt[3]{2}<\sqrt[4]{3}$

EXAMPLE 2 *Which one is greatest out of* $\sqrt[3]{5}$, $\sqrt[4]{3}$, $\sqrt[5]{4}$?

SOLUTION $\sqrt[3]{5}=(5)^{1/3}=(5)^{20/60}=(5^{20})^{1/60}=\sqrt[60]{5^{20}}$

$\sqrt[4]{3}=(3)^{1/4}=(3)^{15/60}=(3^{15})^{1/60}=\sqrt[60]{3^{15}}$

$\sqrt[5]{4}=(4)^{1/5}=(4)^{12/60}=(4^{12})^{1/60}=\sqrt[60]{4^{12}}$

Obviously $\sqrt[3]{5}$ is the greatest.

EXAMPLE 3 *If* $p=\sqrt[3]{5}$, $q=\sqrt[4]{3}$, $r=\sqrt[5]{4}$ *then the correct relationship is :*

(a) $p>q>r$ *(b)* $q<r<p$

(c) $r>p>q$ *(d) can't be determined*

SOLUTION In the previous question we have found that p is the greatest.

Again $q=\sqrt[60]{3^{15}}$ and $r=\sqrt[60]{4^{12}}$

Now $3^{15}\ \text{⋀}\ 4^{12}$ [Here the sign ⋀ signifies the trichotomy-relation i.e.,if x ⋀ y, then either $x<y$ or $x=y$ or $x>y$]

$\Rightarrow\quad 3^{12}.3^3\ \text{⋀}\ 4^{12}$

$\Rightarrow\quad 3^3\ \text{⋀}\ \dfrac{4^{12}}{3^{12}}$

$\Rightarrow\quad 3^3\ \text{⋀}\ \left(\dfrac{4}{3}\right)^{12}$

$\Rightarrow\quad 3^3\ \text{⋀}\ (1.33)^{12}$

$\Rightarrow\quad 3^3\ \text{⋀}\ [(1.33)^4]^3$

$\Rightarrow\quad 3^3<(3.16)^3$

Thus $q<r$

Hence $p>r>q$, so (b) is the correct option.

EXAMPLE 4 *If* $5\sqrt{5}\times 5^3\div 5^{-3/2}=5^{a+2}$ *then the value of* a *is :*

(a) 4 *(b)* 5 *(c)* 9 *(d)* 16

SOLUTION $\dfrac{5\sqrt{5}\times 5^3}{5^{-3/2}}=5^{a+2}$

$\Rightarrow\quad \dfrac{5^{4+\frac{1}{2}}}{5^{-\frac{3}{2}}}=5^{a+2}\quad\Rightarrow\quad 5^{4+\frac{1}{2}+\frac{3}{2}}=5^{a+2}$

$\Rightarrow\quad 5^6=5^{a+2}$

$\Rightarrow\quad 6=a+2\quad\Rightarrow\quad a=4$

Hence (a) is the correct option.

EXAMPLE 5 *Find the value of* $\dfrac{2+\sqrt{3}}{2-\sqrt{3}}$.

SOLUTION $\dfrac{2+\sqrt{3}}{2-\sqrt{3}}=\dfrac{2+\sqrt{3}}{2-\sqrt{3}}\times\dfrac{2+\sqrt{3}}{2+\sqrt{3}}$

(Multiplying numerator and denominator by conjugate)

$=\dfrac{(2+\sqrt{3})^2}{4-3}=\dfrac{4+3+4\sqrt{3}}{1}=7+4\sqrt{3}$

EXAMPLE 6 *The value of* $\dfrac{\sqrt{5}-2}{\sqrt{5}+2}$ *is :*

(a) $4-9\sqrt{5}$ *(b)* $9+4\sqrt{5}$

(c) $9-4\sqrt{5}$ *(d)* $7+4\sqrt{5}$

SOLUTION $\dfrac{\sqrt{5}-2}{\sqrt{5}+2}=\dfrac{(\sqrt{5}-2)}{(\sqrt{5}+2)}\times\dfrac{(\sqrt{5}-2)}{(\sqrt{5}-2)}$

$=\dfrac{(\sqrt{5}-2)^2}{5-4}=\dfrac{5+4-4\sqrt{5}}{1}=9-4\sqrt{5}$

Thus (c) is the correct option.

EXAMPLE 7 *Find the value of* $\dfrac{5}{6\sqrt{6}}\times\dfrac{12\sqrt{30}}{25\sqrt{5}}$.

SOLUTION $\dfrac{5}{6\sqrt{6}}\times\dfrac{12\sqrt{30}}{25\sqrt{5}}=\dfrac{5}{6\sqrt{6}}\times\dfrac{12\sqrt{6}\ \sqrt{5}}{25\sqrt{5}}=\dfrac{2}{5}$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 8 *Arrange the following in descending order* $\sqrt{3}-\sqrt{2}, \sqrt{4}-\sqrt{3}, \sqrt{5}-\sqrt{4}, \sqrt{2}-1$.

SOLUTION $\sqrt{3}-\sqrt{2}=\dfrac{\sqrt{3}-\sqrt{2}}{1}\times\dfrac{\sqrt{3}+\sqrt{2}}{\sqrt{3}+\sqrt{2}}$

$=\dfrac{3-2}{\sqrt{3}+\sqrt{2}}=\dfrac{1}{\sqrt{3}+\sqrt{2}}$

Similarly, $\sqrt{4}-\sqrt{3}=\dfrac{1}{\sqrt{4}+\sqrt{3}}, \sqrt{5}-\sqrt{4}=\dfrac{1}{\sqrt{5}+\sqrt{4}}$

and $\sqrt{2}-1=\dfrac{1}{\sqrt{2}+1}$

As we know, if the numerator is same then the fraction whose denominator is larger the fraction will be lower. Hence the correct order of descending is

$$(\sqrt{2}-1)>(\sqrt{3}-\sqrt{2})>(\sqrt{4}-\sqrt{3})>(\sqrt{5}-\sqrt{4})$$

EXAMPLE 9 $\sqrt[r]{\dfrac{9^{\left(r+\frac{1}{4}\right)}\sqrt{3.3^{-r}}}{3.\sqrt{3^{-r}}}}=k$, *then the value of* k *is*

(a) 3 (b) 3^2 (c) 3^3 (d) $\sqrt[r]{3}$

SOLUTION $\sqrt[r]{\dfrac{3^{2r+\frac{1}{2}3^{\left(\frac{1-r}{2}\right)}}}{3^{1-\frac{r}{2}}}}=\sqrt[r]{\dfrac{3^{\frac{4r+1+1-r}{2}}}{3^{\frac{2-r}{2}}}}$

$=\sqrt[r]{3^{\left(\frac{3r+2}{2}\right)-\left(\frac{2-r}{2}\right)}}=\sqrt[r]{3^{2r}}=3^{\frac{2r}{r}}=3^2$

Hence (b) is the correct option.

EXAMPLE 10 *If* m, n *are the positive integers* $(n>1)$ *such that* $m^n=121$, *then value of* $(m-1)^{n+1}$ *is :*

(a) 12321 (b) 1 (c) 1000 (d) 11

SOLUTION $\because$ $m^n=121$

and $n>1$

$\therefore$ $(11)^2=121$

$\Rightarrow$ $m=11$ and $n=2$

Hence $(m-1)^{n+1}=(10)^3=1000$

Thus (c) is correct option.

EXAMPLE 11 *Simplify :* $\sqrt{192}-\dfrac{1}{2}\sqrt{48}-\sqrt{75}$

SOLUTION $\sqrt{192}-\dfrac{1}{2}\sqrt{48}-\sqrt{75}=8\sqrt{3}-\dfrac{4}{2}\sqrt{3}-5\sqrt{3}$

$=8\sqrt{3}-2\sqrt{3}-5\sqrt{3}=\sqrt{3}$

EXAMPLE 12 *Find the square root of* $7-2\sqrt{10}$.

SOLUTION $7-2\sqrt{10}=5+2-2\sqrt{5\times2}$

$\Rightarrow$ $7-2\sqrt{10}=(\sqrt{5})^2+(\sqrt{2})^2-2\sqrt{5}.\sqrt{2}$

$\Rightarrow$ $7-2\sqrt{10}=(\sqrt{5}-\sqrt{2})^2$

Thus the $\sqrt{7-2\sqrt{10}}=\pm(\sqrt{5}-\sqrt{2})$

EXAMPLE 13 *Find the value of* $\left(\dfrac{1}{\sqrt{5}-2}+\dfrac{1}{\sqrt{5}+2}\right)^2$.

SOLUTION $\left(\dfrac{1}{\sqrt{5}-2}+\dfrac{1}{\sqrt{5}+2}\right)^2=\left[\dfrac{\sqrt{5}+2+\sqrt{5}-2}{(\sqrt{5}-2)(\sqrt{5}+2)}\right]^2$

$=\left[\dfrac{2\sqrt{5}}{(\sqrt{5})^2-(2)^2}\right]^2$

$=\dfrac{4\times5}{5-4}=\dfrac{20}{1}=20$

INTRODUCTORY EXERCISE-1.6

1. If $x=\dfrac{1}{\sqrt{2}-1}$, then the value of $x^2-6+\dfrac{1}{x^2}$ is :
   (a) 0 (b) 1
   (c) $\sqrt{2}$ (d) can't be determined
2. The value of $\dfrac{3}{5\sqrt[4]{27}}$, when its denominator is a rational number :
   (a) $\dfrac{\sqrt[2]{3}}{6}$ (b) $\dfrac{\sqrt[4]{3}}{5}$
   (c) $\dfrac{\sqrt[3]{4}}{5}$ (d) none of these
3. The value of denominator when $\dfrac{7\sqrt{3}-5\sqrt{2}}{\sqrt{18}+\sqrt{48}}$ is rationalised :
   (a) 15 (b) 25
   (c) 30 (d) 50
4. If $\sqrt{5+\sqrt[3]{x}}=3$, then the value of x is :
   (a) 9 (b) 27
   (c) 64 (d) 343
5. If $A=\sqrt{2}$, $B=\sqrt[3]{3}$ and $C=\sqrt[4]{4}$ then which of the relation is correct?
   (a) $A>B>C$ (b) $A>B=C$
   (c) $A=C<B$ (d) none of these

Factorial : The product of n consecutive natural numbers (or positive integers) starting from 1 to n is called as the factorial 'n'.

i.e., $n!=1\times2\times3\times4\times5\times6....(n-2)(n-1)n$

So, the $4!=1\times2\times3\times4=4\times3\times2\times1$

$5!=1\times2\times3\times4\times5=5\times4\times3\times2\times1$

$6!=1\times2\times3\times4\times5\times6=6\times5\times4\times3\times2\times1$

NOTE 1. Factorial n is written as "n!".
2. $0!=1$ and $1!=1$

Properties

1. $n!$ is always an even number if $n\geq2$
2. $n!$ always ends with zero if $n\geq5$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *If* $m^n - m = (m-n)!$ *where* $m > n > 1$ *and* $m = n^2$ *then the value of* $m^2 + n^2$ *is :*

(a) 272 *(b)* 90
(c) 20 *(d)* none of (a), (b), (c)

SOLUTION Let us consider $n = 2$ $(\because n > 1)$

Then $m^n - m = 4^2 - 4 = 12$ $(\because m = n^2)$

and $(m-n)! = (4-2)! = 2! = 2$

Hence it is impossible.

Again consider $n = 3$, then

$$m^n - m = 9^3 - 9 = 720$$

and $(m-n)! = (9-3)! = 6! = 720$

Thus we get $n = 3$ and $m = 9$ the probable values

Now $m^2 + n^2 = 9^2 + 3^2 = 81 + 9 = 90$

Hence (b) is the correct option.

EXAMPLE 2 *If* $P + P! = P^3$, *then the value of* P *is :*

(a) 4 *(b)* 6 *(c)* 0 *(d)* 5

SOLUTION Consider $P = 5$, then

$$5 + 5! = 5^3$$
$$5 + 120 = 125$$
$$125 = 125$$

Thus (d) is correct option.

EXAMPLE 3 *If* $P + P! = P^2$ *then the value of* P *is :*

(a) 5 *(b)* 7 *(c)* 3 *(d)* 0

SOLUTION Consider $P = 3$ then

$$3 + 3! = 3^2$$
$$3 + 6 = 9$$
$$9 = 9$$

Hence (c) is the correct option.

EXAMPLE 4 *If* $n! - n = n$, *then the value of* n *is :*

(a) 4 *(b)* 5 *(c)* 6 *(d)* 3

SOLUTION Consider $n = 3$ then

$$3! - 3 = 3$$
$$6 - 3 = 3$$
$$3 = 3$$

Hence (d) is the correct answer.

EXAMPLE 5 *The appropriate value of* P *for the relation* $(P! + 1) = (P+1)^2$ *is :*

(a) 3 *(b)* 4
(c) 5 *(d)* none of these

SOLUTION Let us consider $P = 4$ then

$$4! + 1 = (4+1)^2$$
$$24 + 1 = 5^2$$
$$25 = 25$$

Hence (b) is the correct option.

EXAMPLE 6 *The value of* $8! + 4!$ *is :*

(a) 4 *(b)* 16 *(c)* 2 *(d)* 1680

SOLUTION $$\frac{8!}{4!} = \frac{8.7.6.5.4.3.2.1}{4.3.2.1}$$

$$= 8.7.6.5 = 1680$$

Hence (d) is the correct option.

EXAMPLE 7 *If* $n! = \frac{(n+4)!}{(n+1)!}$, *then the value of* n *is :*

(a) 5 *(b)* 18 *(c)* 6 *(d)* 9

SOLUTION $$n! = \frac{(n+4)!}{(n+1)!}$$

$$= \frac{1.2.3\ldots n.(n+1)(n+2)(n+3)(n+4)}{1.2.3\ldots n.(n+1)}$$

$$= (n+2)(n+3)(n+4)$$

$$n! = (n+2)(n+3)(n+4)$$

now $5! \neq 7 \times 8 \times 9$

and $18! \neq 20 \times 21 \times 22$

and $9! \neq 11 \times 12 \times 13$

but $6! = 8 \times 9 \times 10$

$720 = 720$

Hence $n = 6$ is the correct answer, thus (c) is the right choice.

EXAMPLE 8 *The value of*

$(1.2.3\ldots9).(11.12.13\ldots19).(21.22.23\ldots29).(31.32.33\ldots39).$
$(41.42.43\ldots49)\ (51.52.53\ldots59)\ldots(91.92\ldots99)$

(a) $\frac{100!}{36288 \times 10^{11}}$ *(b)* $\frac{99!}{388 \times 10^{11}}$

(c) $\frac{99!}{36288 \times 10^{10}}$ *(d) can't be determined*

SOLUTION $(1.2.3\ldots9).(11.12.13\ldots19).(21.22.23\ldots29)\ldots$
$\ldots.(91.92.93\ldots99)$

$$= (1.2.3\ldots9)\frac{10}{10}(11.12.13\ldots19)\frac{20}{20}$$

$$(21.23.23\ldots29)\frac{30}{30}\ldots(91.92.93\ldots99)$$

$$= \frac{1.2.3\ldots99}{10.20.30\ldots90} = \frac{99!}{362880 \times 10^9} = \frac{99!}{36288 \times 10^{10}}$$

Hence (c) is the correct option.

EXAMPLE 9 *The expression* $1! + 2! + 3! + 4! + \ldots + n!$ *(where* $n \geq 5$*) is not a/an :*

(a) composite number *(b) odd number*
(c) perfect square *(d) multiple of 3*

SOLUTION $1! + 2! + 3! + 4! + 5! = 1 + 2 + 6 + 24 + 120 = 153$

Since, the option (a), (b) and (d) are ruled out so the rest option (c) is the correct one.

EXAMPLE 10 *The HCF and LCM of* $13!$ *and* $31!$ *are respectively :*

(a) $12!$ *and* $32!$ *(b)* $13!$ *and* $31!$
(c) 26 *and* 403 *(d) can't be determined*

SOLUTION Since $13!$ is contained in $31!$ so the LCM is $31!$ and $13!$ is common in $13!$ and $31!$, so the HCF is $13!$

Scanned by CamScanner

yoursmahboob.wordpress.com

Number of zeros at the end of the product of numbers : We know that $10=5\times2$, $100=5^2\times2^2$, $1000=5^3\times2^3$ etc. So we can say that for n number of zeros at the end of the product we need exactly n combinations of "5×2". For example.

$2\times3\times5\times7=210$ there is only one zero at the end of the product (or resultant value)

Again, $2\times3\times5\times6\times7\times15=2\times3\times5\times2\times3\times7\times3\times5$

$=\underline{2\times2}\times\underline{5\times5}\times3\times3\times3\times7$

$=100\times189=18900$

Thus there are two zeros because there are two combinations of "5×2".

Now, $1\times2\times3\times4\times5\times6\times7\times8\times9$

$=1\times2\times3\times2\times2\times5\times2\times3\times7\times2\times2\times2\times3\times3$

$=1\times2\times2\times2\times2\times2\times2\times2\times5\times3\times3\times3\times3\times7$

$=1\times2^7\times5\times3^4\times7$

$=1\times2^6\times2\times5\times3^4\times7$

$=10\times2^6\times3^4\times7$

$=10\times64\times81\times7$

$=10\times36288=362880$

Thus there is only one zero at the end of the product since there is only one combination of 5×2..

Again $4\times125\times3=2\times2\times5\times5\times5\times3$

$=2^2\times5^3\times3$

$=2^2\times5^2\times5\times3$

$=(2\times5)^2\times15$

$=100\times15=1500$

Thus there are only two zeros at the end of the product since there are only two combinations of "5×2".

NOTE The number of zeros at the end of the product depends upon 2×5, but the condition is that

(i) $2^k\times5^l$ gives k number of zeros if $k<l$

(ii) $2^k\times5^l$ gives l number of zeros if $l<k$

EXAMPLE 1 *Find the number of zeros in the product of* 10!.

SOLUTION $10!=1\times2\times3\times4\times5\times6\times7\times8\times9\times10$

It is obvious from the above expression that there are only two 5's and eight 2's.

Since the number of 5's are less (than the number of 2's) so the number of 5's will be effective to form the combination of '5×2. Thus there are only 2 zeros at the end of the product of 10!.

EXAMPLE 2 *Find the number of zeros at the end of the product of* $2^{222}\times5^{555}$.

SOLUTION Since the number of 2's are less than the number of 5's hence the restriction is imposed by the number of 2's.

Thus there can be only 222 pairs of (5×2). Hence the number of zeros at the end of the product of the given expression will be 222.

EXAMPLE 3 *Find the number of zeros at the end of the product of the expression* $2^1\times5^2\times2^3\times5^4\times2^5\times5^6\times2^7\times5^8\times2^9\times5^{10}$

SOLUTION Since the number of 2's are less than the number of 5's hence number of 2's will be effective. Thus

$2^1\times2^3\times2^5\times2^7\times2^9\times5^2\times5^4\times5^6\times5^8\times5^{10}$

$=2^{25}\times5^{30}=2^{25}\times5^{25}\times5^5=(2\times5)^{25}\times5^5$

$=10^{25}\times5^5=5^5\times10^{25}$

Thus there will be 25 zeros at the end of the product of the given expression.

EXAMPLE 4 *The number of zeros at the end of the expression* $10+100+1000+\ldots+10000000000$ *is :*

(a) 1 *(b)* 10

(c) 55 *(d) none of these*

SOLUTION

$$\begin{array}{r}10\\100\\1000\\\cdots\cdots\\\cdots\cdots\\\underline{10000000000}\\11111111110\end{array}$$

Thus there is only one zero at the end of resut.

Hence (a) is the correct option.

EXAMPLE 5 *The number of zeros at the end of the product of the expression* $10\times100\times1000\times10000\times\ldots10000000000$ *is :*

(a) 10 *(b)* 100 *(c)* 50 *(d)* 55

SOLUTION $10\times100\times1000\times\ldots10000000000$

$=10^1\times10^2\times10^3\times\ldots\times10^{10}$

$=10^{(1+2+3+\ldots+10)}=10^{55}$

Hence (d) is the correct option.

EXAMPLE 6 *Number of zeros at the end of the following expression* $(5!)^{5!}+(10!)^{10!}+(50!)^{50!}+(100!)^{100!}$ *is :*

(a) 165 *(b) 120*

(c) 125 *(d) none of these*

SOLUTION The number of zeros at the end of $(5!)^{5!}=120$

[$\because 5!=120$ and thus $(120)^{120}$ will give 120 zeros]

and the number of zeros at the end of the $(10!)^{10!}$, $(50!)^{50!}$ and $(100!)^{100!}$ will be greater than 120.

Now since the number of zeros at the end of the whole expression will depend on the number which has least number of zeros at the end of the number among other given numbers.

So, the number of zeros at the end of the given expression is 120.

Divisibility of a factorial number by the largest power of any number : Let us start with very simple example. As if we consider 1!, 2!, 3! or 4!, none of them is divisible by 5, because 5 is not the factor, involved in the given factorial number.

Now, if we consider any factorial number greater than 4!, every number consists 5 or the higher powers of 5 in the factorial numbers. For example starting from 5! every number has 5 as its factor

i.e., $5!=1\times2\times3\times4\times5$

$6!=1\times2\times3\times4\times5\times6$

Scanned by CamScanner

yoursmahboob.wordpress.com

$7! = 1\times2\times3\times4\times5\times6\times7$

... ...

$10! = 1\times2\times3\times4\times5\times6\times7\times8\times9\times10$ etc.

Thus it is obvious that every number greater than 4! is divisible by 5. But as we move towards higher number we will find that the frequency of the occurrence of 5 (or any particular number) will increase. As 5! contains only one 5, 10! contains two 5's, 15! contains three 5's, 20! contains four 5's but 25! contains suddenly six 5's instead of five 5's. So it becomes a very tedious work to calculate the occurrence of any particular number involved as a factor of any higher factorial number.

Similarly if we have to know that how many times 3 is contained in the 30! or in other words what is the largest power of 3 that can divide 30!

Now, if we try to do it manually, we see that there are 10 multiples of 3 *viz.*, 3, 6, 9, 12, 15, 18, 21, 24, 27, 30. But there are some multiples which contains 3 at least two times for example 9, 18 and 27. Again there are some multiples which contain 3 three times as in 27. Thus the factor 3 totally occurs 14 (=10+3+1) times in 30!. Hence you can understand that how tedious can be the calculation if we have to find the highest power of 3 that can exactly divide to 9235!

Therefore to make the calculation easier we can use the following formula.

Suppose we have to find the highest power of k that can exactly divided n!, we divide n by k, n by k^2, n by k^3... and so on till we get $\left[\frac{n}{k^x}\right]$ equal to 1 (where, $[P]$ means the greatest integer less than or equal to P) and then add up as $\left[\frac{n}{k}\right]+\left[\frac{n}{k^2}\right]+\left[\frac{n}{k^3}\right]+\left[\frac{n}{k^4}\right]+\ldots+\left[\frac{n}{k^x}\right]$.

NOTE For more information about greatest integer number (or function) *i.e.*, GIF refer the chapter "FUNCTIONS".

EXAMPLE 1 *Find the largest power of 5 contained in 124!*

SOLUTION $\left[\frac{124}{5}\right]+\left[\frac{124}{5^2}\right]=24+4=28$

[We cannot do it further since 124 is not divisible by 5^3]
Hence, there are 28 times 5 involved as a factor in 124!

EXAMPLE 2 *Find the largest power of 2 that can divide 268!*

SOLUTION $\left[\frac{268}{2}\right]+\left[\frac{268}{2^2}\right]+\left[\frac{268}{2^3}\right]+\left[\frac{268}{2^4}\right]+\left[\frac{268}{2^5}\right]+\left[\frac{268}{2^6}\right]+\left[\frac{268}{2^7}\right]+\left[\frac{268}{2^8}\right]$

$=134+67+33+16+8+4+2+1=265$

Thus the greatest power of 2 is 265 that can divide exactly 268!

Dear students you might have notice that if we further increase the value of n! and consider a very typical number say 7, 13, 17, 19 etc. for the divisibility then we feel the real pain in solving the problem since we don't know the values of higher powers of these divisors say $17^4, 17^5, 19^8, 19^9, \ldots$ etc. So this formula in this present form is not appropriate.

Now you must have noticed that we consider only integral values of the quotient q as $[q]$ which gives an integer just less than or equal to q. So we can do this calculation slightly in a easier manner. Here we just divide the given number and then the succeeding quotients will be divided by the same remainder as in the case of successive division, so for better understanding we solve the previous problem in this manner as follows.

2	268	[Divide successive quotients till we get 0 as the last quotient]
2	134 →	
2	67 →	
2	33 →	
2	16 →	
2	8 →	265 (Add up all the quotients)
2	4 →	
2	2 →	
2	1 →	
	0	

So we can frankly say that this method of calculation is easy since we need not to know the values of $2^1, 2^2, 2^3, 2^4, \ldots, 2^8$ etc. Also the division by 2 is easier than the division by 2^x, where x is any large integer.

EXAMPLE 3 *Find the largest power of 7 that can exactly divide 777!*

SOLUTION

7	777	
7	111 →	
7	15 →	128
7	2 →	
	0	

Thus the highest power of 7 is 128 by which 777! can be divided.

EXAMPLE 4 *Find the largest value of n in the 10^n which can exactly divide 1000!*

SOLUTION Since 10 is made up of 5 and 2 *i.e.*, $10 = 2\times5$

So you can see that before 10! there is the presence of 10 in 5!, 6!, 7!, 8! or 9!.

So $10^n = (5\times2)^n = 5^n\times2^n$

Thus we find the powers of 2 and 5 individually

2	1000	
2	500 →	
2	250 →	
2	125 →	
2	62 →	
2	31 →	994
2	15 →	
2	7 →	
2	3 →	
	1 →	

Scanned by CamScanner

yoursmahboob.wordpress.com

and

5	1000
5	200 →
5	40 → 249
5	8 →
	1 →

So there is 2^{994} and 5^{249} but we can make only 249 combinations due to the restriction imposed by the lower power of 5!.

Thus the highest power of 10 is 249 which can divide 1000!

$\left(\because 2^{994} \times 5^{249} \Rightarrow 2^{745} \times 2^{249} \times 5^{249} \right.$
$\left. \Rightarrow 2^{745} \times (10)^{249} \right)$

EXAMPLE 5 *Find the number of zeros at the end of* 1000!

SOLUTION Since we know that the zeros at the end of any product are due to the presence of 10 as the factor of the product and the number of zeros depends upon the number of times 10 is involved. For example if there are seven 10's (*i.e.*, 7 combinations of 5×2) in the $n!$ then the number of zeros at the end of $n!$ will be 7.

But since, we have solved the same problem previous to this problem so we can conclude that the number of 10's in 1000! is 249. Hence the number of zeros at the end of the 1000! is 249.

EXAMPLE 6 *The number of zeros at the end of* 100! *is :*

(a) 25 *(b)* 50 *(c)* 24 *(d)* 100

SOLUTION

2	100
2	50 →
2	25 →
2	12 → 97
2	6 →
2	3 →
	1 →

and

5	100
5	20 → 24
	4 →

So, there will be only 24 combinations of 5×2 it means there will be 24 zeros at the end of 100!.

Hence (c) is the correct answer.

EXAMPLE 7 *Find the highest power of* 63 *which can exactly divide* 6336!.

SOLUTION $63 = 3^2 \times 7$

Since this technique is applicable only for the prime factors. So we solve it by breaking 63 in its prime factors.

3	6336
3	2112 →
3	704 →
3	234 →
3	78 → 3164
3	26 →
3	8 →
	2 →

and

7	6336
7	905 →
7	129 → 1054
7	18 →
	2 →

$\because \quad 63 = 9 \times 7 = 3^2 \times 7$

$\therefore$ Since to make a 9 we need 3×3 *i.e*, two times. So we divide 3164 by 2 and get 1582.

So $3^{3164} \times 7^{1054} \Rightarrow 9^{1582} \times 7^{1054}$

Thus the largest power of 63 is 1054. That can exactly divide 6336!

EXAMPLE 8 *Find the highest power of* 40 *which can exactly divide* 4000!

SOLUTION $40 = 8 \times 5 = 2^3 \times 5$

So,

2	4000
2	2000 →
2	1000 →
2	500 →
2	250 →
2	125 →
2	62 → 3994
2	31 →
2	15 →
2	7 →
2	3 →
	1 →

and

5	4000
5	800 →
5	160 →
5	32 → 999
5	6 →
	1 →

Now since $2^{3m} \times 5^n = 8^m \times 5^n$

$\therefore \quad 2^{3994} \times 5^{999} = (2^3)^{1331} \times 2 \times 5^{999}$

$\Rightarrow \quad 2 \times (8^{1331} \times 5^{999}) \Rightarrow 2 \times 8^{332} \times (8 \times 5)^{999}$

Thus the highest power of 40 is 999 that can exactly divide 4000!.

EXAMPLE 9 *Find the highest power of* 81 *that can divide* 1800!.

SOLUTION $81 = 3^4$

So,

3	1800
3	600 →
3	200 →
3	66 → 897
3	22 →
3	7 →
	2 →

Scanned by CamScanner

yoursmahboob.wordpress.com

Thus we get 3^{897}. But we need 81.

Now since $81 = 3^4$

Therefore $3^{897} = (3^4)^{224} \times 3^1 = (81)^{224} \times 3$.

Therefore the highest power of 81 is 224 which can divide exactly 1800! so $(81)^{224}$ can divide 1800!

NOTE Sometimes for your convenience you can skip some unnecessary calculation.
As if you are asked to find the highest power of 30 which can exactly divide 1357!
Since $30 = 2 \times 3 \times 5$. Now if you have been serious while doing the previous examples so you can conclude that you need not to solve to find the highest powers of 2 and 3. What you need is just to find the highest power of 5 (which is the greatest factor therefore it occurs least frequently) and as you know that the least frequent factor impose the restriction and hence it is the only effective value. Hence we just calculate the highest power of 5 and get the required result. Still there are some special points which are really difficult to explain on the paper. These points can be effectively explained only in the classroom by teacher and last but not the least if you are intelligent enough so you can pick up these subtle but the important points by yourself as you are learning the concept religiously.
Please note that there can be some shortcuts which I have not mentioned because it is difficult to explain exactly on paper and even some students don't fathom the logic of the shortcut. So it becomes dangerous and hence it is better to find the shortcuts by themselves just by intensive practice or seeking the help of an expert.

CONCEPT OF UNIT DIGIT

Look at the following :

$$1 \times 5 = 5$$
$$3 \times 5 = 15$$
$$5 \times 5 = 25$$
$$7 \times 5 = 35$$
$$9 \times 5 = 45$$
$$11 \times 5 = 55$$
$$\ldots \ldots \ldots \ldots$$
$$\ldots \ldots \ldots \ldots$$

i.e., if the number whose last digit is 5, is multiplied by any odd number, the unit digit of the product will always be 5.

For example

$$13 \times 15 = 195, 19 \times 35 = 665 \text{ etc.}$$

Now,
$$2 \times 5 = 10$$
$$4 \times 5 = 20$$
$$6 \times 5 = 30$$
$$8 \times 5 = 40$$
$$10 \times 5 = 50$$
$$12 \times 5 = 60$$
$$\ldots \ldots \ldots \ldots$$
$$\ldots \ldots \ldots \ldots$$

i.e., if the number whose last is 5, is multiplied by any even number (including zero), the unit digit of the product is always zero. For example

$$82 \times 15 = 1230, 156 \times 45 = 7020$$
$$62 \times 13 \times 65 = 52390 \text{ etc.}$$

Now we will discuss that the unit digit of the resultant value depends upon the unit digits of all the participating numbers *i.e.*,

$$12 + 17 + 13 + 47 = 89$$

Thus it is clear that the unit digit of the resultant value 89 depends upon the unit digits 2, 7, 3, 7.

Similarly, $6 \times 7 \times 9 = 378$
$$3 \times 7 \times 8 = 168$$

So we can find out the unit digit of the resultant value only by solving the unit digits of the given expression.

EXAMPLE 1 *Find the unit digit of* $123 + 345 + 780 + 65 + 44$.

SOLUTION We can find the unit digit just by adding the unit digits 3, 5, 0, 5, 4 as

$$3 + 5 + 0 + 5 + 4 = 17$$

So the unit digit (or the last digit) of the resultant value of the expression $123 + 345 + 780 + 65 + 44$ will be 7. (you can verify it by doing the whole sum)

EXAMPLE 2 *Find the unit digit of* $676 \times 543 \times 19$.

SOLUTION We can find the unit digit of the product of the given expression just by multiplying the unit digits (6, 3, 9) instead of doing the whole sum.

Thus $6 \times 3 \times 9 = 162$

Hence, the unit digit of the product of the given expression will be 2. (you can verify it by doing the complete sum)

EXAMPLE 3 *Find the unit digit of* $135 \times 361 \times 970$.

SOLUTION The unit digit can be obtained by multiplying the unit digits 5, 1, 0. then $5 \times 1 \times 0 = 0$ thus the unit digit will be zero.

EXAMPLE 4 *Find the unit digit of the product of all the odd prime numbers.*

SOLUTION The prime numbers are 3, 5, 7, 11, 13, 17, 19...etc.
Now we know that if 5 is multiplied by any odd number it always gives the last digit 5. So the required unit digit will be 5.

Scanned by CamScanner

yoursmahboob.wordpress.com

Now look at the following

$1 \times 1 = 1$

$1 \times 1 \times 1 = 1$

$1 \times 1 \times 1 \times 1 = 1$

$1 \times 1 \times 1 \times 1 \times 1 = 1$ etc.

$2^1 = 2$

$2^2 = 2 \times 2 = 4$

$2^3 = 2 \times 2 \times 2 = 8$

$2^4 = 2 \times 2 \times 2 \times 2 = 16$

$2^5 = 2 \times 2 \times 2 \times 2 \times 2 = 32$

$2^6 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 64$

$2^7 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 128$

$2^8 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 256$

$2^9 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 512$

$2^{10} = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 1024$

$2^{11} = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 2048$

$2^{12} = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 4096$

Similarly, $3^1 = 3$

$3^2 = 9$

$3^3 = 27$

$3^4 = 81$

$3^5 = 243$

$3^6 = 729$

$3^7 = 2187$

$3^8 = 6561$

$3^9 = 19683$ etc.

Similarly, $4^1 = 4$

$4^2 = 16$

$4^3 = 64$

$4^4 = 256$

$4^5 = 1024$

$4^6 = 4096$

Thus we can say that the unit digit follows a periodic pattern that is after a particular period it repeats in a cyclic form.

the unit digit of $2^1, 2^5, 2^9, 2^{13}, \ldots$ is the same which is 2.

Similarly $2^2, 2^6, 2^{10}, 2^{14}, \ldots$ etc. has the same unit digit, which is 4.

Again the last digit of 3^1 is 3.

and the last digit of 3^2 is 9.

and the last digit of 3^3 is 7.

and the last digit of 3^4 is 1.

and the last digit of 3^5 is 3.

and the last digit of 3^6 is 9.

and the last digit of 3^7 is 7.

and the last digit of 3^8 is 1.

Thus the last digit must follow a pattern. It can be seen that the last digit of 2 repeats after every four steps and the last digit of 4 repeats after every 2 steps.

NOTE
1. The last digit (or unit digits) of 0, 1, 5 and 6 is always the same irrespective of their powers raised on them.
2. The last digit of 4 and 9 follows the pattern of odd-even *i.e.*, their period is 2.
3. The last digit of 2, 3, 7, 8 repeats after every 4 steps *i.e.*, their cyclic period is 4.

EXAMPLE 1 *Find the last digit of* 2^{35}.

SOLUTION The last digit of $2^1 \Rightarrow 2$

$2^2 \Rightarrow 4$

$2^3 \Rightarrow 8$

$2^4 \Rightarrow 6$

$2^5 \Rightarrow 2$

Since its cyclic period is four, it means the unit digit of 2 will repeat after every 4 steps. Hence we can say that the last digit of $2^1, 2^5, 2^9, 2^{13}, 2^{17}, 2^{21}, 2^{25}, 2^{29}, 2^{33}, 2^{37}$ is the same and the last digit of $2^2, 2^6, 2^{10}, 2^{14}, 2^{18}, \ldots, 2^{30}, 2^{34}, 2^{38}$ is same and the last digit of $2^3, 2^7, 2^{11}, \ldots, 2^{31}, 2^{35}, 2^{39}$ is same and the last digit of $2^4, 2^8, 2^{12}, 2^{16}, \ldots, 2^{32}, 2^{36}, 2^{40}$ etc. is same.

Hence the last digit of 2^{35} is 8.

Alternatively : You can see that the powers which are divisible by 4 (*i.e.*, cyclic period) give the same unit digit as 2^4. As $2^8, 2^{12}, 2^{16}, \ldots$ etc.

Again the powers which leave the remainder 1 when divided by 4 (which is the cyclic period) give the same unit digit as 2^1. As $2^5, 2^9, 2^{13}, \ldots$ etc.

Similarly the powers which leave the remainder 2 when divided by 4, give the same unit digit as 2^2. As $2^6, 2^{10}, 2^{14}, 2^{18}, \ldots$ etc.

Similarly the powers which leave the remainder 3 when divided by 4 give the same unit digit as 2^3. As $2^7, 2^{11}, 2^{15}, \ldots$ etc.

Since when 35 is divided by 4, the remainder is 3. Hence, the unit digit of 2^{35} is equal to the unit digit of 2^3, which is equal to 8.

EXAMPLE 2 *Find the unit digit of* $(12)^{78}$.

SOLUTION The unit digit of $(12)^{78}$ will be same as $(2)^{78}$. Now since we know that the cyclic period of unit digit of 2 is 4. The remainder when 78 is divided by 4 is 2. Hence the unit digit of 2^{78} will be same as 2^2 which is 4. Thus the unit digit of 12^{78} is 4.

EXAMPLE 3 *Find the unit digit of* $(33)^{123}$.

SOLUTION Since we know that the unit digit of $(33)^{123}$ will be same as $(3)^{123}$. Now the unit-digit of 3^{123} will be 7 since it will be equal to the unit digit of 3^3.

Thus the unit digit of $(3)^{123}$ is 7.

EXAMPLE 4 *Find the unit digit of* $3^{47} + 7^{52}$.

SOLUTION The unit digit of the given expression will be equal to the unit digit of the sum of the unit digits of both the terms individually.

Now, unit digit of 3^{47} is 7 (since it will be equal to 3^3) and the unit digit of 7^{52} is 1 (since it will be equal to 7^4)

Thus the unit digit of $3^{47} + 7^{52}$ is $7 + 1 = 8$.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 5 *Find the unit digit of* $3^6 \times 4^7 \times 6^3 \times 7^4 \times 8^2 \times 9^5$.

SOLUTION The unit digit of 3^6 is 9
The unit digit of 4^7 is 4
The unit digit of 6^3 is 6
The unit digit of 7^4 is 1
The unit digit of 8^2 is 4
The unit digit of 9^5 is 9
Therefore the unit digit of the given expression is 6, (since $9 \times 4 \times 6 \times 1 \times 4 \times 9 = 7776$).

EXAMPLE 6 *Find the unit digit of* 111! *(factorial* 111).

SOLUTION $111! = 1 \times 2 \times 3 \times 4 \times 5 \times \ldots \times 110 \times 111$
Since there is a product of 5 and 2 hence it will give zero as the unit digit.
Hence the unit digit of 111! is 0 (zero).

EXAMPLE 7 *Find the unit digit of the product of all the prime number between* 1 *and* $(11)^{11}$.

SOLUTION The set of prime number $S = \{2, 3, 5, 7, 11, 13, \ldots\}$
Since there is one 5 and one 2 which gives 10 after multiplying mutually, it means the unit digit will be zero.

EXAMPLE 8 *Find the unit digit of the product of all the elements of the set which consists all the prime numbers greater than 2 but less than* 222.

SOLUTION The set of required prime number = $\{3, 5, 7, 11, \ldots\}$
Since there is no any even number in the set so when 5 will multiply with any odd number, it will always give 5 as the last digit.
Hence the unit digit will be 5.

EXAMPLE 9 *Find the last digit of* $222^{888} + 888^{222}$.

SOLUTION The last digit of the expression will be same as the last digit of $2^{888} + 8^{222}$.
Now the last digit of 2^{888} is 6 and the last digit of the 8^{222} is 4.
Thus the last digit of $2^{888} + 8^{222}$ is 0 (zero), since $6 + 4 = 10$.

EXAMPLE 10 *Find the last digit of* $32^{32^{32}}$.

SOLUTION The last digit of $32^{32^{32}}$ is same as $2^{32^{32}}$.
But $2^{32^{32}} = 2^{32 \times 32 \times 32 \times \ldots \times 32 \text{ times}}$
$\Rightarrow$ $2^{32^{32}} = 2^{4 \times 8 \times (32 \times 32 \times \ldots \times 31 \text{ times})}$
$\Rightarrow$ $2^{32^{32}} = 2^{4n}$,
where $n = 8 \times (32 \times 32 \times \ldots \times 31 \text{ times})$
Again $2^{4n} = (16)^n \Rightarrow$ unit digit is 6, for every $n \in N$
Hence, the required unit digit = 6.

EXAMPLE 11 *Find the last digit of the expression :*
$1^2 + 2^2 + 3^2 + 4^2 + \ldots + 100^2$.

SOLUTION The unit digit of the whole expression will be the equal to the unit digit of the sum of the unit digits of the expression.
Now adding the unit digits of $1^2 + 2^2 + 3^2 + \ldots + 10^2$
we get $1 + 4 + 9 + 6 + 5 + 6 + 9 + 4 + 1 + 0 = 45$
Hence, the unit digit of $1^2 + 2^2 + 2^2 + \ldots + 10^2$ is 5.
Now since there are 10 similar columns of numbers which will yield the same unit digit 5. Hence the sum of unit digits of all the 10 columns is 50 $(= 5 + 5 + 5 + \ldots + 5)$
Hence, the unit digit of the given expression is 0 (zero).

EXAMPLE 12 *Find the unit digit of* $1^1 + 2^2 + 3^3 + \ldots 10^{10}$.

SOLUTION
The unit digit of $1^1 = 1$
The unit digit of $2^2 = 4$
The unit digit of $3^3 = 7$
The unit digit of $4^4 = 6$
The unit digit of $5^5 = 5$
The unit digit of $6^6 = 6$
The unit digit of $7^7 = 3$
The unit digit of $8^8 = 6$
The unit digit of $9^9 = 9$
The unit digit of $10^{10} = 0$
Thus the unit digit of the given expression will be 7. $(\because 1 + 4 + 7 + 6 + 5 + 6 + 3 + 6 + 9 = 47)$

EXAMPLE 13 *Find the unit digit of*
$13^{24} \times 68^{57} + 24^{13} \times 57^{68} + 1234 + 5678$.

SOLUTION The unit digit of 3^{24} is 1
The unit digit of 8^{57} is 8
The unit digit of 4^{13} is 4
The unit digit of 7^{68} is 1
So the resultant value of the unit digits
$= 1 \times 8 + 4 \times 1 + 4 + 8$
$= 8 + 4 + 4 + 8 = 24$
Thus the unit digit of the whole expression is 4.

EXAMPLE 14 *The unit digit of the expression* $\dfrac{1 \times 2 \times 3 \times 4 \times 5 \times 6 \times 7 \times 8 \times 9 \times 10}{100}$ *is :*

(a) 7 *(b)* 9
(c) 8 *(d) none of these*

SOLUTION Since in the numerator of the product of the expression there will be 2 zeros at the and these two zeros will be cancelled by 2 zeros of the denominator. Hence finally we get a non-zero unit digit in the expression.

Now, $\dfrac{1 \times 2 \times 3 \times 4 \times 5 \times 6 \times 7 \times 8 \times 9 \times 10}{100}$

$= \dfrac{1 \times 2^8 \times 3^4 \times 5^2 \times 7^1}{5^2 \times 2^2}$

$= 1 \times 2^6 \times 3^4 \times 7$

Therefore, the unit digit of the given expression will be same as that of $1 \times 2^6 \times 3^4 \times 7$.
Now, the unit digit of $1 \times 2^6 \times 3^4 \times 7$ is 8.
$(\because$ the product of unit digits of $1, 2^6, 3^4, 7$ is $1 \times 4 \times 1 \times 7 = 28)$
Hence, the unit digit of $\dfrac{10!}{100}$ is 8.

EXAMPLE 15 *Find the unit digit of the expression*
$888^{92351} + 222^{92351} + 666^{23591} + 999^{99991}$.

SOLUTION First of all we find the unit digit individually of all the four terms,
So, the unit digit of 888^{92351} is equal to the unit digit of 8^{92351}
Now, the unit digit of 8^{92351} is equal to the unit of 8^4 (since 92351 is divisible by 4), which is 6.

Scanned by CamScanner

yoursmahboob.wordpress.com

Again the unit digit 222^{92351} is equal to the unit digit of 2^{92351} and the unit digit of 2^{92351} is same as that of 2^4 which is 6, since 92351 is divisible by 4. Further the unit digit of 666^{23591} is 6, which always constant for all the powers except zero and the unit digit of 999^{99991} is 1 since the value of 9999! is even.

Thus the unit digit of the expression is 9. ($\because 6 + 6 + 6 + 1 = 19$)

EXAMPLE 16 *The last digit of the following expression is :*

$(11)^1 + (21)^2 + (31)^3 + (41)^4 + \ldots + (101)^{10}$

(a) 4 (b) 5 (c) 6 (d) 7

SOLUTION The unit digit of the given expression will be equal to the unit digit of the sum of the unit digits of every term of the expression.

Now,
The unit digit of $(11)^2 = 1$
The unit digit of $(21)^2 = 4$
The unit digit of $(31)^3 = 6$
The unit digit of $(41)^4 = 6$
The unit digit of $(51)^5 = 0$
The unit digit of $(61)^6 = 0$

Thus the last digit of the $(71)^7$, $(81)^8$, $(91)^9$, $(101)^{10}$ will be zero.
So, the unit digit of the given expression = 7
($\because 1 + 4 + 6 + 6 + 0 + 0 + 0 + 0 + 0 + 0 = 17$)

EXAMPLE 17 *The last 5 digits of the following expression will be*

$(11)^5 + (21)^4 + (31)^3 + (41)^2 + (51)^1 + (101)^5 + (1001)^4 + (10001)^3 + (100001)^2 + (1000001)$

(a) 45939 (b) 00929
(c) 20929 (d) can't be determined

SOLUTION The last digit of $(11)^5 = 1$
The last digit of $(21)^4 = 16$
The last digit of $(31)^3 = 216$
The last digit of $(41)^2 = 576$
The last digit of $(51)^1 = 120$
The last 5 digit of $(101)^5 = 00000$
The last 5 digit of $(1001)^4 = 00000$
$(10001)^3 = 00000$
$(100001)^2 = 00000$
$(1000001)^1 = 00000$

Thus the last 5 digits of the given expression = 00929
[$\because 1 + 16 + 216 + 576 + 120 + 00000 + 00000 + 00000 + 00000 + 00000 = 00929$]

INVOLUTION

As in the previous articles we have been studied that $a \cdot a \cdot a \ldots (n \text{ times}) = a^n$. So the process of multiplication of a number several times by itself is known as INVOLUTION.

Similarly,we use the same method in some algebraic expressions as follows.

1. $(a+b)^2 = a^2 + b^2 + 2ab = (a+b)(a+b)$
2. $(a-b)^2 = a^2 + b^2 - 2ab = (a-b)(a-b)$
3. $(a+b+c)^2 = a^2 + b^2 + c^2 + 2(ab+bc+ca)$
   $= (a+b+c)(a+b+c)$
4. $(a+b)^3 = a^3 + b^3 + 3ab(a+b)$
5. $(a-b)^3 = a^3 - b^3 - 3ab(a-b)$
6. $(a+b+c)^3 = a^3 + b^3 + c^3 + 3(a+b)(b+c)(c+a)$
7. $(a+b)^2 = (a-b)^2 + 4ab$
8. $(a-b)^2 = (a+b)^2 - 4ab$
9. $a^2 - b^2 = (a+b)(a-b)$
10. $a^3 + b^3 = (a+b)(a^2 + b^2 - ab)$
11. $a^3 - b^3 = (a-b)(a^2 + b^2 + ab)$
12. $a^3 + b^3 + c^3 - 3abc = (a+b+c)$
    $(a^2 + b^2 + c^2 - ab - bc - ac)$

The above rules are used widely. But these are important in finding the square, cube, etc. of a number besides help in finding the remainder or divisibility of a number.

1. $a^n + b^n$ is divisible by $(a+b)$, when n is odd.
2. $a^n + b^n$ is never divisible by $(a-b)$
3. $a^n + b^n$ is not divisible by $(a+b)$, when n is even.
4. $a^n - b^n$ is always divisible by $(a-b)$
5. $a^n - b^n$ is divisible by $(a+b)$ only when n is even.
6. $a^n - b^n$ is not divisible by $(a+b)$ when n is odd.

EXAMPLE 1 *Find the value of* $107 \times 107 - 93 \times 93$

SOLUTION $(107)^2 - (93)^2$ [$\because a^2 - b^2 = (a+b)(a-b)$]
$= (107 + 93)(107 - 93)$
$= 200 \times 14 = 2800$

EXAMPLE 2 *Find the value of* 734856×9999..

SOLUTION $734856 \times 9999 = 734856 \times (10000 - 1)$
$= 7348560000 - 734856$
$= 7347825144$

EXAMPLE 3 *$6798 \times 223 + 6798 \times 77 = k$, then the value of k will be :*

(a) 2034900 (b) 3029400
(c) 2039400 (d) none of these

SOLUTION $6798 \times 223 + 6798 \times 77 = 6798(223 + 77)$
$= 6798(300) = 2039400$

EXAMPLE 4 $123 \times 123 + 77 \times 77 + 2 \times 123 \times 77 = ?$

SOLUTION $123 \times 123 + 77 \times 77 + 2 \times 123 \times 77$
$= (123)^2 + (77)^2 + 2 \times 123 \times 77$
$= (123 + 77)^2$ [$(a+b)^2 = a^2 + b^2 + 2ab$]
$= (200)^2 = 40000$

EXAMPLE 5 $\dfrac{(941 + 149)^2 + (941 - 149)^2}{(941 \times 941 + 149 \times 149)} = ?$

SOLUTION $\dfrac{(941 + 149)^2 + (941 - 149)^2}{(941 \times 941 + 149 \times 149)}$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$\because \quad \frac{(a+b)^2+(a-b)^2}{a^2+b^2} = \frac{(a^2+b^2+2ab)+(a^2+b^2-2ab)}{(a^2+b^2)}$$

$$= \frac{2(a^2+b^2)}{(a^2+b^2)} = 2$$

Hence, the value of the given expression is 2. So you need not to calculate the given numbers in the expression, where $a = 941, b = 149$

EXAMPLE 6 $\dfrac{888\times888\times888 - 222\times222\times222}{888\times888 + 888\times222 + 222\times222} = ?$

SOLUTION $\dfrac{888\times888\times888 - 222\times222\times222}{888\times888 + 888\times222 + 222\times222}$

$$= \frac{(888)^3-(222)^3}{(888)^2+888\times222+(222)^2}$$

$$= \frac{(888)^3-(222)^3}{(888)^2+888\times222+(222)^2}$$

$$= 888 - 222 \qquad \left[\because \frac{a^3-b^3}{(a^2+b^2+ab)} = \frac{(a-b)(a^2+b^2+ab)}{(a^2+b^2+ab)} = (a-b)\right]$$

$$= 666$$

EXAMPLE 7 *If* $(64)^2 - (36)^2 = 20k$ *then the value of* k *is :*

(a) 140 (b) 120
(c) 80 (d) none of these

SOLUTION

$$(64)^2 - (36)^2 = 20k$$
$$\Rightarrow \quad (64+36)(64-36) = 20k$$
$$\Rightarrow \quad 100 \cdot 28 = 20k$$
$$\Rightarrow \quad 20\times5\times28 = 20k$$
$$\Rightarrow \quad k = 28\times5 = 140$$

Hence (a) is the correct answer.

EXAMPLE 8 *If* $a + \dfrac{1}{a} = 3$, *then the value of* $a^2 + \dfrac{1}{a^2}$ *is :*

(a) 6 (b) 7
(c) 9 (d) can't be determined

SOLUTION $\because \quad \left(a+\dfrac{1}{a}\right) = 3$

$$\therefore \quad \left(a+\frac{1}{a}\right)^2 = a^2 + \frac{1}{a^2} + 2a\times\frac{1}{a} = 9$$

$$\Rightarrow \quad a^2 + \frac{1}{a^2} + 2 = 9 \quad \Rightarrow \quad a^2 + \frac{1}{a^2} = 7$$

Hence (b) is the correct option.

EXAMPLE 9 *If* $a + \dfrac{1}{a} = 3$, *then the value of* $a^3 + \dfrac{1}{a^3}$ *is :*

(a) 15 (b) 18
(c) 27 (d) none of these

SOLUTION $\left(a+\dfrac{1}{a}\right)^3 = a^3 + \dfrac{1}{a^3} + 3a\cdot\dfrac{1}{a}\left(a+\dfrac{1}{a}\right)$

$$\Rightarrow \quad (3)^3 = a^3 + \frac{1}{a^3} + 3(3) \qquad \left[\because \ a\times\frac{1}{a} = 1 \ \text{and} \ (a+b)^3 = a^3+b^3+3ab(a+b)\right]$$

$$\Rightarrow \quad 27 = a^3 + \frac{1}{a^3} + 9 \quad \Rightarrow \quad a^3 + \frac{1}{a^3} = 18$$

Hence (b) is the correct option.

EXAMPLE 10 *What is the value of* $\dfrac{2.75\times2.75\times2.75 - 2.25\times2.25\times2.25}{2.75\times2.75 + 2.75\times2.25 + 2.25\times2.25}$?

SOLUTION $\because \quad a^3 - b^3 = (a-b)(a^2+b^2+ab)$

$$\therefore \quad \frac{a^3-b^3}{(a^2+b^2+ab)} = \frac{(a-b)(a^2+b^2+ab)}{(a^2+b^2+ab)} = (a-b)$$

$\therefore$ The value of the expression $= 2.75 - 2.25 = 0.50$

EXAMPLE 11 *If* $(\sqrt{a}+\sqrt{b}) = 17$ *and* $(\sqrt{a}-\sqrt{b}) = 1$, *then the value of* $\sqrt{ab}$ *is :*

(a) 72 (b) 27
(c) 35 (d) none of these

SOLUTION $(x+y)^2 - (x-y)^2 = (x^2+y^2+2xy) - (x^2+y^2-2xy)$

$$(x+y)^2 - (x-y)^2 = 4xy$$
$$xy = \frac{(x+y)^2-(x-y)^2}{4}$$

Thus
$$\sqrt{ab} = \frac{(\sqrt{a}+\sqrt{b})^2 - (\sqrt{a}-\sqrt{b})^2}{4}$$
$$= \frac{(17)^2-(1)^2}{4} = \frac{288}{4} = 72$$

Hence (a) is the correct option.

EXAMPLE 12 *Find the value of* $a^3+b^3+c^3-3abc$ *if* $a+b+c = 12$ *and* $ab+bc+ca = 47$.

SOLUTION $\because \ a+b+c = 12$

$$\therefore \ (a+b+c)^2 = a^2+b^2+c^2+2(ab+bc+ac) = 144$$
$$\Rightarrow \quad a^2+b^2+c^2+2\times47 = 144$$
$$\Rightarrow \quad a^2+b^2+c^2 = 50$$

Now, since $a^3+b^3+c^3-3abc$

$$= (a+b+c)(a^2+b^2+c^2-ab-bc-ac)$$

or $a^3+b^3+c^3-3abc = 12(50-47) = 12\times3 = 36$

EXAMPLE 13 *If* $a+b+c = 0$, *then the value of* $a^3+b^3+c^3$ *is :*

(a) 0 (b) abc
(c) 3abc (d) none of these

SOLUTION $\because \quad a^3+b^3+c^3-3abc = (a+b+c)(a^2+b^2+c^2-ab-bc-ac)$

or $\quad a^3+b^3+c^3-3abc = 0$

$$\Rightarrow \quad a^3+b^3+c^3 = 3abc$$

Hence (c) is the correct option.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 14 *If* $x+y+z=0$ *then the value of* $\frac{x^2y^2+y^2z^2+z^2x^2}{x^4+y^4+z^4}$ *is :*

(a) 0 *(b)* 1/2 *(c)* 1 *(d)* 2

SOLUTION $\because \quad (x+y+z)=0$

$\Rightarrow \quad x^2+y^2+z^2+2(xy+yz+zx)=0$

$\Rightarrow \quad x^2+y^2+z^2=-2(xy+yz+zx)$

$\Rightarrow \quad (x^2+y^2+z^2)^2=4(xy+yz+zx)^2$

$\Rightarrow \quad x^4+y^4+z^4+2(x^2y^2+y^2z^2+z^2x^2)$
$=4[x^2y^2+y^2z^2+z^2x^2+2xyz(x+y+z)]$

$\therefore \quad x^4+y^4+z^4=2(x^2y^2+y^2z^2+z^2x^2)$
$[\because (x+y+z)=0]$

$\therefore \quad \frac{x^2y^2+y^2z^2+z^2x^2}{x^4+y^4+z^4}=\frac{1}{2}$

Hence (b) is the correct option.

EXAMPLE 15 *The value of* $a^3+b^3+c^3-3abc$, *when* $a=87$, $b=-126$ *and* $c=39$ *is :*

(a) 0 *(b)* 1259
(c) −48 *(d)* none of these

SOLUTION $\because \quad a+b+c=0$

$\therefore \quad a^3+b^3+c^3-3abc=0$

Thus (a) is the correct option.

EXAMPLE 16 *The greatest divisor of*
$(a-b)(a+b)(a^2+b^2)(a^4+b^4)(a^8+b^8)(a^{16}+b^{16})$ *is :*

(a) $a^{16}-b^{16}$ *(b)* $a^{16}+b^{16}$
(c) $a^{31}-b^{31}$ *(d)* $a^{32}-b^{32}$

SOLUTION $(a-b)(a+b)(a^2+b^2)(a^4+b^4)(a^8+b^8)(a^{16}+b^{16})$
$=a^{32}-b^{32}$

Hence, the greatest divisor is $a^{32}-b^{32}$. Hence (d) is the correct option.

EXAMPLE 17 *In the above question which of the following can not divide the given expression :*

(a) a^4-b^4 *(b)* $a^{12}-b^{12}$
(c) $a^{16}-b^{16}$ *(d) can't be determined*

SOLUTION Since $a^{12}-b^{12}$ is not the factor of the given expression.

Hence, it can not divide the given expression. Thus (b) is the appropriate option.

EXAMPLE 18 *The expression* 31^n+17^n *is divisible by, for every odd positive integer* n *:*

(a) 48 *(b)* 14
(c) 16 *(d) both (a) and (c)*

SOLUTION a^n+b^n is divisible by $(a+b)$ for every odd n, $n \in N$

Hence 31^n+17^n is divisible by 48 (= 31 + 17) and since 16 is the factor of 48. So the given expression is divisible by both (a) and (c). Hence (d) is the most appropriate answer.

EXAMPLE 19 *Which is not the factor of* $4^{6n}-6^{4n}$ *for any positive integer* n*?*

(a) 5 *(b)* 25
(c) 7 *(d) none of these*

SOLUTION $\because 4^{6n}-6^{4n}=(64)^{2n}-(36)^{2n}$
$=(64^n+36^n)(64^n-36^n)$

For $n=1, 3, 5, \ldots$ etc. (64^n+36^n) is divisible by 100 and all its factors. Also (64^n-36^n) is divisible by 28 and all its factors.

Again for $n=2, 4, 6, \ldots$ etc. (64^n-36^n) is always divisible by 100 and all its factors. Also it is divisible by 28 and all its factors. Hence (d).

EXAMPLE 20 19^n-1 *is :*

(a) always divisible by 9 *(b) always divisible by* 20
(c) is never divisible by 19 *(d) only (a) and (c) are true*

SOLUTION 19^n-1 is divisible by 18 (= 19 − 1) when n is even or odd. So (a) is correct.

19^n-1 is divisible by 20 only when n is even so (b) is wrong.

19^n-1 is never divisible by 19 which is correct. Thus (d) is the most appropriate answer.

CONCEPTS OF REMAINDER

Some Important Results

1. When $a_1, a_2, a_3, \ldots$ are divided by 'd' individually the respective remainders obtained are $R_1, R_2, R_3, \ldots$ etc. and when $a_1+a_2+a_3, \ldots)$ is divided by d the remainders can be obtained by dividing $(R_1+R_2+R_3, \ldots)$ by d.

EXAMPLE 1 *Find the remainder when* 38 + 71 + 85 *is divided by* 16.

SOLUTION When we divide 38, 71 and 85 we obtain the respective remainders as 6, 7 and 5. Now we can obtain the required remainder by dividing the sum of remainders (*i.e.*, $+7+5=18$) by 16, which is 2 instead of dividing the sum of actual given numbers (*i.e.*, $38+71+85=194$) by 16, which also gives us the same remainder 2.

EXAMPLE 2 *Find the remainder when* 1661 + 1551 + 1441 + 1331 + 1221 *is divided by* 20.

SOLUTION The remainders when 1661, 1551, 1441, 1331, 1221 are divided by 20 are 1, 11, 1, 11, 1. So the required remainder can be obtained just by dividing 1 + 11 + 1 + 11 + 1 (= 25) by 20. Hence the required remainder is 5.

EXAMPLE 3 *What is the remainder when* 678 + 687 + 6879 + 6890 *is divided by 17?*

SOLUTION The individual remainders when 678, 687, 6879, 6890 are divided by 17 are 15, 7, 11, 5 respectively. Hence the required remainder can be obtained by dividing 15 + 7 + 11 + 5 (= 38) by 17. Thus the required remainder is 4.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 4 *What is the remainder when* $(10+10^2+10^3+10^4+10^5)$ *is divided by 6?*

SOLUTION The remainder when 10 is divided by 6 is 4
The remainder when 100 is divided by 6 is 4
The remainder when 1000 is divided by 6 is 4
The remainder when 10000 is divided by 6 is 4
The remainder when 100000 is divided by 6 is 4
So the required remainder can be obtained by dividing $4+4+4+4+4\ (=20)$ by 6. Thus the required remainder is 2.

2. When 'a' is divided by 'd' the remainder is R and 'a_1' and 'a_2' are divided by 'd' the remainders are R_1 and R_2, then the remainder R will be equal to the difference of remainders R_1 and R_2 if $a_1 - a_2 = a$.

For example the remainder when 63 is divided by 35 is 28 and this can be obtained by taking the 63 as difference of any two numbers say 100 and 37 then the remainders when 100 and 37 are divided by 35 are 30 and 2 then the required remainder is $28\ (=30-2)$

[*i.e.*, Remainder of $\frac{63}{35}$

$= \text{Remainder of } \frac{100}{35} - \text{Remainder of } \frac{37}{35} = 30-2=28$]

NOTE If the obtained remainder in a division has negative sign, then the actual remainder can be obtained by adding the divisor with initially obtained remainder containing negative sign.

For example, the remainder of $\frac{63}{35}$

$= \text{Remainder of } \frac{120}{35} - \text{Remainder of } \frac{57}{35} = 15-22=-7$

So, the required remainder $= 35-7=28$

3. When $a_1, a_2, a_3, \ldots$ are divided by a divisor d the respective remainders obtained are $R_1, R_2, R_3 \ldots$ then the remainder when $(a_1 \times a_2 \times a_3 \times \ldots)$ is divided by 'd' can be obtained by dividing $(R_1 \times R_2 \times R_3 \times \ldots)$ by d.

For example when $365 \times 375 \times 389$ is divided by 35 the remainders can be obtained by dividing the product of the remainders which are obtained by dividing 365, 375, 389 individually.

Now since the remainders are 15, 25, 4 so the required remainder = Remainder of $(15 \times 25 \times 4)$ when divided by 35.

Thus the required remainder $= \frac{15\times25\times4}{35} = \frac{60\times25}{35}$

$= \frac{25\times25}{35} = \frac{625}{35} = 30$

Thus 30 is the remainder.

NOTE The required remainder can be obtained by considering the remainders as the dividends.

Thus the required remainder $= R_1 \times R_2 \times R_3 \times R_4$
$= R_5 \times R_3 \times R_4$
$= R_6 \times R_4 = R_7$

where R_7 is the required remainder and $R_1, R_2, \ldots, R_6$ are the remainders which are obtained by dividing the remainders perse.

EXAMPLE 1 *Find the remainder when* 123×1234 *is divided by* 15.

SOLUTION The remainder of $\frac{123\times1234}{15}$ = Remainder of $\frac{3\times4}{15}$

(3 and 4 are the remainders of 123 and 1234 when divided by 15)

$= \text{Remainder of } \frac{12}{15} = 12$

EXAMPLE 2 *Find the remainder when* $1719 \times 1721 \times 1723 \times 1725 \times 1727$ *is divided by* 18.

SOLUTION Since you can understand that applying the traditional method of getting the remainder is very difficult since first of all you have to take the product of all the numbers as given in the expression, then this a very large product has to be divided by 18, which is very lengthy and tedious process.

Thus we find the remainder of the remainders.

Hence, the remainder of $\frac{1719\times1721\times1723\times1725\times1727}{18}$

$= \frac{9\times11\times13\times15\times17}{18}$

(9, 11, 13, 15, 17 are the remainder when the given numbers are divided by 18.)

$= \frac{99\times13\times15\times17}{18}$

$= \frac{9\times13\times255}{18} = \frac{117\times255}{18}$

$= \frac{9\times3}{18} = \frac{27}{18} = 9$

EXAMPLE 3 *Find the remainder when* 7^7 *is divided by* 4.

SOLUTION $\frac{7^7}{4} = \frac{7\times7\times7\times7\times7\times7\times7}{4}$

$= \frac{3\times3\times3\times3\times3\times3\times3}{4}$

$= \frac{9\times9\times9\times3}{4}$

$= \frac{1\times1\times1\times3}{4} = \frac{3}{4}$

Thus the required remainder is 3.

EXAMPLE 4 *Find the remainder when* 11^8 *is divided by* 7.

SOLUTION $\frac{11^8}{7} = \frac{11\times11\times11\times11\times11\times11\times11\times11}{7}$

$= \frac{4\times4\times4\times4\times4\times4\times4\times4}{7}$

$= \frac{16\times16\times16\times16}{7}$

$= \frac{2\times2\times2\times2}{7} = \frac{16}{7}$

Thus the required remainder = 2

Now you can see that, if in the above problem it is to be asked that find the remainder when 11^{75} is divided by 7, then it would be very difficult to solve it within a short span of time because it would involve a very large calculations if done in the above shown manner.

Scanned by CamScanner

yoursmahboob.wordpress.com

So follow the steps in which I will show the appropriate process, which is generally known as "pattern method to find the remainder."

The remainder when 11^1 is divided by 7 is 4
The remainder when 11^2 is divided by 7 is 2
The remainder when 11^3 is divided by 7 is 1
The remainder when 11^4 is divided by 7 is 4
The remainder when 11^5 is divided by 7 is 2
The remainder when 11^6 is divided by 7 is 1
The remainder when 11^7 is divided by 7 is 4

So you can see that you are getting a pattern, if you follow it you can get the remainder for higher powers of 11.

Now you are seeing that after every 3 steps the cycle of remainders is repeating its course as after every 7 days a particular day repeats itself.

Now if we assume that the month of March starts with Monday, then which day will fall on 24th March of the same year? So you will quickly respond that it would be Wednesday.

Let us see how?

M	T	W	Th	F	Sat	Sun
1	2	3	4	5	6	7
8	9	10	11	12	13	14
15	16	17	18	19	20	21
22	23	24	25	26	27	28
29	30	31				

As we can see that after every 7 days Monday comes on 1st, 8th, 15th, 22nd etc. So what we do is just divide the given date by 7. If it is divisible by 7 then the last day of the week (*i.e.*, last day of the cycle) will be the required day. If it is not divisible by 7 then it must leaves some remainder then we calculate the day according to the remainder. For instance in the above example when we divide 24 by 7, then we get the remainder 3. So we calculate the 3rd day starting from the first day of the week (or cycle). So the required day will be Wednesday.

Now, If I ask that which day will fall on 7th, 14th, 21st or 28th of this month then your response will be Sunday since all the dates given above are divisible by 7 which is the period of the cycle.

If the dates were 1, 8, 15, ... etc then the required day would have been Monday since when we divide these given dates by 7 the remainder is 1 so the dates which are corresponding to 1 *i.e.*, 8, 15, 22, 29 etc. will fall on Monday.

So I hope this discussion will be very helpful to you while solving the concerned problems.

Thus we can say that the remainder when 11^{75} is divided by 7 is 1, since 75 is divisible by 3.

EXAMPLE 5 *Find the remainder when 5^{123} is divided by 7.*

SOLUTION The remainder when 5^1 is divided by 7 is 5
The remainder when 5^2 is divided by 7 is 4
The remainder when 5^3 is divided by 7 is 6
The remainder when 5^4 is divided by 7 is 2
The remainder when 5^5 is divided by 7 is 3
The remainder when 5^6 is divided by 7 is 1
The remainder when 5^7 is divided by 7 is 5
The remainder when 5^8 is divided by 7 is 4 etc.

So we see that the cyclic period of remainder is 6,since after 6 steps the remainders start repeating. Now we divide the power of 5 *i.e.*, 123 by 6, then it leaves the remainder 3. It means the required remainder will be equal to the corresponding remainder when 5^3 is divided by 7, which is 6. So the remainder when 5^{123} is divided by 7 is 6.

Explanation : $\text{Remainder } \frac{5^{123}}{7} = \text{Remainder } \frac{5^{120} \times 5^3}{7}$

$= \text{Remainder } \frac{(5^6)^{20} \times 5^3}{7}$

$= \text{Remainder} = \frac{5^3}{7}$

= Remainder is 6.

NOTE Remember that when you get the remainder 1 while obtaining the cyclic period, you can stop the further calculation because at this step your cyclic period ends and in the next step the remainder starts repeating as in the above examples at 5^6 we get the remainder 1. So we need not to calculate further for $5^7, 5^8, 5^9$ etc., because all these numbers will give the same remainders as $5^1, 5^2, 5^3$.. etc. respectively.

EXAMPLE 6 *Find the remainder when 123^{321} is divided by 5.*

SOLUTION The remainder when 123 is divided by 5 is 3
So, the remainder when 123^{321} is divided by 5 is same as when 3^{321} is divided by 5.
Now, the remainder when 3^1 is divided by 5 is 3
The remainder when 3^2 is divided by 5 is 4
The remainder when 3^3 is divided by 5 is 2
The remainder when 3^4 is divided by 5 is 1
The remainder when 3^5 is divided by 5 is 3
So the cyclic period is 4 since at 3^4, we get the remainder 1 (after which the cyclic starts repeating)
Thus the remainder when 3^{321} is divided by 5 is 3 since we get the remainder 1 when 321 is divided by 4 (the cyclic period).

or $\text{Rem. } \frac{123^{321}}{5} = \text{Rem. } \frac{3^{321}}{5} = \text{Rem. } \frac{3^{320} \times 3^1}{5}$

$= \text{Rem } . \frac{(3^4)^{80} \times 3^1}{5} = \text{Rem. } \frac{3^1}{5}$

= Remainder is 3.

EXAMPLE 7 *Find the remainder when $923^{888} + 235^{222}$ is divided by 4.*

SOLUTION $\text{Rem } \frac{923^{888} + 235^{222}}{4} = \text{Rem. } \frac{3^{888} + 3^{222}}{4}$

$= \text{Rem. } \frac{1+1}{4} = \frac{2}{4}$

Thus the remainder is 2.

EXAMPLE 8 *Find the remainder of $\frac{3^{9415}}{80}$.*

SOLUTION $\text{Rem } \frac{3^{9415}}{80} = \text{Rem } \frac{3^{9412} \times 3^3}{80}$

$= \text{Rem } \frac{(3^4)^{2353} \times 3^3}{80}$ [Since the cyclic period is 4]

$= \text{Rem } \frac{(81)^{2353} \times 3^3}{80}$

$= \text{Rem } \frac{1 \times 27}{80} = \text{Rem } \frac{27}{80}$

Thus the remainder is 27.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 9 *Find the remainder when* $10^1 + 10^2 + 10^3 + 10^4 + 10^5 + \ldots + 10^{99}$ *is divided by 6.*

SOLUTION The remainder when 10^1 is divided by 6 is 4
The remainder when 10^2 is divided by 6 is 4
The remainder when 10^3 is divided by 6 is 4
The remainder when 10^4 is divided by 6 is 4
The remainder when 10^5 is divided by 6 is 4
Thus the remainder is always 4.

So, the required remainder $= \frac{4 + 4 + 4 + \ldots \text{ 99 times}}{6} = \frac{396}{6}$

Thus the remainder is zero.

EXAMPLE 10 *The remainder of* $\frac{888^{222} + 222^{888}}{3}$ *is :*

(a) 0 *(b)* 1 *(c)* 2 *(d)* 3

SOLUTION Remainder $\frac{888^{222} + 222^{888}}{3}$ = Remainder is zero,

since 888 and 222 both (bases) are divisible by 3.

EXAMPLE 11 *The remainder of* $\frac{888^{222} + 222^{888}}{5}$ *is :*

(a) 0 *(b)* 1 *(c)* 3 *(d)* 4

SOLUTION Rem. $\frac{888^{222} + 222^{888}}{5}$

$= \text{Rem.}\frac{888^{222}}{5} + \text{Rem.}\frac{222^{888}}{5}$

$= \text{Rem.}\frac{3^{222}}{5} + \text{Rem.}\frac{2^{888}}{5}$

$= \text{Rem.}\frac{(3^4)^{55} \times 3^2}{5} + \text{Rem.}\frac{(2^4)^{222}}{5}$

$= \text{Rem.}\frac{1 \times 9}{5} + \text{Rem. } 1$

$= \text{Rem.}\frac{4}{5} + \text{Rem.}\frac{1}{5} = \text{Rem.}\frac{4+1}{5} \Rightarrow \frac{5}{5}$

Thus the remainder is zero.

Alternatively: [To check the divisibility by 5 just see the sum of the unit digits which is 10 (= 4 +6)

$\because$ $8^{222} \rightarrow 4$ (unit digit)

and $2^{888} \rightarrow 6$ (unit digit)

Hence it is divisible. So there is no remainder]

EXAMPLE 12 *The remainder of* $\frac{32^{32^{32}}}{7}$ *:*

(a) 2 *(b)* 1
(c) 4 *(d) none of these*

SOLUTION $32^{32^{32}}$ means $32^{(32 \cdot 32 \cdot 32 \ldots 32 \text{ times})}$

Now the remainder of $\frac{32}{7}$ is 4.

Again $\frac{4^{32 \cdot 32 \cdot 32 \cdot 32 \ldots 32 \text{ times}}}{7} \Rightarrow \frac{4^{2 \cdot 2 \cdot 2 \ldots 32 \text{ times}}}{7}$

$\left[\because \frac{4^1}{7} \rightarrow 4, \frac{4^2}{7} \rightarrow 2, \frac{4^3}{7} \rightarrow 1\right]$,

Remainder = 4

Since remainder of $\frac{4^2}{7} = \frac{4^8}{7} = \frac{4^{32}}{7} = \frac{4^{128}}{7} = \ldots$ is 2

and remainder of $\frac{4^4}{7} = \frac{4^{16}}{7} = \frac{4^{64}}{7} = \frac{4^{256}}{7} = \ldots$ is 4

NOTE 1. $\frac{(a+1)^n}{a}$ gives always remainder 1.

2. $\frac{a^n}{(a+1)}$ gives remainder 1 when n is even and gives the remainder a itself when n is odd, where a is any integer and n being the positive integer.

EXAMPLE 13 *The remainder when* 8^{1785} *is divided by 7 is :*

(a) 5 *(b) 1*
(c) 6 *(d) can't be determined*

SOLUTION $\because \frac{(a+1)^n}{a}$ leaves always remainder 1.

So $\frac{8^{1785}}{7} = \frac{(7+1)^{1785}}{7}$ gives the remainder 1.

EXAMPLE 14 *The remainder when* $(16)^{3500}$ *is divided by 17 is :*

(a) 1 *(b) 0*
(c) 16 *(d) none of these*

SOLUTION $\because \frac{a^n}{a+1}$ gives remainder 1 when n is even

So the remainder of $\frac{16^{3500}}{17} = \frac{16^{3500}}{(16+1)}$ is 1.

Hence (a) is the correct option.

EXAMPLE 15 *The remainder when* $(3)^{81}$ *is divided by 28 is :*

(a) 1 *(b)* 8 *(c)* 18 *(d)* 26

SOLUTION The remainder of $\frac{3^{81}}{28}\left[= \frac{(3^3)^{27}}{28} = \frac{(27)^{27}}{28}\right]$ is 27.

Since $\frac{a^n}{(a+1)}$ gives remainder a when n is odd.

EXAMPLE 16 *The remainder of* $\frac{2^{243}}{3^2}$ *is :*

(a) 8 *(b) 10*
(c) 4 *(d) none of these*

SOLUTION $\frac{2^{243}}{3^2} = \frac{(2^3)^{81}}{9} = \frac{8^{81}}{9} = \frac{8^{81}}{(8+1)}$

Hence the remainder is 8 since the power of 8 is odd.

EXAMPLE 17 *The remainder when* $(3)^{67!}$ *is divided by 80 :*

(a) 0 *(b)* 1
(c) 2 *(d) can't be determined*

SOLUTION $\because 3^4 = 81$ so $\frac{3^{4n}}{80}$ gives remainder 1.

Thus $\frac{3^{67!}}{80}$ will also give the remainder 1.

Since $67! = 4n$ for a positive integer n.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 18 *The remainder of* $\frac{39^{931}}{40}$ *is :*

(a) 0 (b) 1 (c) 39 (d) 13

SOLUTION $\because \frac{a^n}{a+1}$ gives remainder 1, when n is even, Now since 931 is an even number, hence the remainder is 1. Thus (b) is the correct choice.

EXAMPLE 19 *The remainder of* $\frac{2^{591}}{255}$ *is :*

(a) 0 (b) 1 (c) 55 (d) 5

SOLUTION 2^{591} can be expressed as 2^{8n}

So, $\text{Rem.}\frac{2^{591}}{255} = \text{Rem.}\frac{2^{8n}}{255} = \text{Rem.}\frac{(256)^n}{255}$

Hence the remainder is 1.

Rational Numbers : The numbers which can be expressed as the ratio of any two integers *i.e,* in the form of $\frac{p}{q}$ where p, q are integers, prime to each other (*i.e,* p and q must be coprime) and $q \neq 0$ are called the rational numbers. These numbers are denoted by 'Q'.

Thus $3, -4, \frac{1}{7}, -\frac{3}{8}, \sqrt{16}, \sqrt{25}$ etc. are rational numbers.

All integers and all fractions are rational numbers which are also called commensurable quantities.

FACTS ABOUT RATIONAL NUMBERS

1. The denominator of any rational number can never be zero since the division by zero is undefined.
2. Every integer *e.g.,* $0, \pm 1, \pm 2, \pm 3$.. etc. is a rational number since these can be expressed as $7 = \frac{7}{1}, -3 = -\frac{3}{1}, 0 = \frac{0}{1}$ etc.
3. All the decimal numbers which are terminating are rational numbers *e.g.,*
   $0.14 = = \frac{14}{100}, -8.5 = \frac{-85}{10}, 0.006 = \frac{6}{1000}$ etc.
4. All the recurring decimals, which are non terminating, are the rational numbers.
   e.g., 0.4444..., 1.4141...., 6.785785..., 1.42857142857 ... $\frac{22}{7}$ etc.

NOTE π is not a rational number, since the exact value of π is not $\frac{22}{7}$.

PROPERTIES OF RATIONAL NUMBERS

1. **Closure law :** Addition and multiplication of any two rational number is also a rational number.
2. **Commutative law :** For any two rational numbers $\frac{a}{b}, \frac{c}{d}$,
   $\frac{a}{b} + \frac{c}{d} = \frac{c}{d} + \frac{a}{b}$ and $\frac{a}{b} \times \frac{c}{d} = \frac{c}{d} \times \frac{a}{b}$
3. **Associative law :** For any three rational numbers $\frac{a}{b}, \frac{c}{d}$ and $\frac{e}{f}$.
   $\left(\frac{a}{b} + \frac{c}{d}\right) + \frac{e}{f} = \frac{a}{b} + \left(\frac{c}{d} + \frac{e}{f}\right)$
   and $\left(\frac{a}{b} \cdot \frac{c}{d}\right) \cdot \frac{e}{f} = \frac{a}{b} \cdot \left(\frac{c}{d} \cdot \frac{e}{f}\right)$
4. **Additive and Multiplicative Identity :**
   $\frac{a}{b} + 0 = \frac{a}{b}$ [$\because 0 = \frac{0}{1}$ is an additive identity]
   and $\frac{a}{b} \times 1 = \frac{a}{b}$ [$\because 1 = \frac{1}{1}$ is a multiplicative identity]
5. **Additive and Multiplicative Inverse :**
   $\frac{a}{b} + \left(-\frac{a}{b}\right) = \frac{0}{1}$ [$-\frac{a}{b}$ is additive inverse of $\frac{a}{b}$]
   $\frac{a}{b} \times \left(\frac{b}{a}\right) = \frac{1}{1}$ [$\frac{b}{a}$ is multiplicative inverse of $\frac{a}{b}$]
   where $a \neq 0, b \neq 0$
6. **Rational Numbers :** Do not follow the Commutative law and Associative law for the subtraction and division.
7. **Distribution law :** For any three rational numbers a, b, c
   $a.(b+c) = a.b + a.c$
   and $a.(b-c) = a.b - a.c$
8. If x and y are any two rational numbers such that $x < y$ then $\frac{1}{2}(x+y)$ is also a rational number lying between x and y which shows that **there are infinite number of rational numbers between any two rational numbers.**

Irrational Numbers : The numbers which can't be expressed in the form $\frac{p}{q}$, where p, q are two integers prime to each other and $q \neq 0$ are called irrational numbers. Thus $\sqrt{2}, \sqrt{3}, -\sqrt{3}, \sqrt[3]{4}, \sqrt[3]{6}, \sqrt{5}, \pi$, etc. are irrational numbers.

The decimal representation of these numbers is non-repeating and non-terminating.

e.g., 7.2030030003 ..., $\sqrt{2} = 1.41421...., \sqrt{3} = 1.732....$

Properties of Irrational Numbers

(i) The set 'P' of all irrational numbers is not closed for addition since the sum of two irrationals need not be irrational *e.g.,* $(3+\sqrt{5}) \in P$, $(3-\sqrt{5}) \in P$ but $(3+\sqrt{5}) + (3-\sqrt{5}) = 6 \notin P$

(ii) The set P of all irrational number is not closed for multiplication since the product of two irrationals need not be irrational.

Scanned by CamScanner

yoursmahboob.wordpress.com

e.g., $\sqrt{3} \in P, -\sqrt{3} \in P$

but $\sqrt{3} \times -\sqrt{3} = -3 \notin P$

Real Numbers : All the rational and all irrational numbers are called as real numbers *i.e.* the set of real numbers is the union of entire rational and irrational numbers.

e.g., $-3, 2, 0, \frac{5}{7}, \sqrt{4}, \sqrt{2}, \sqrt{3}, \pi, e, \frac{22}{7}, 0$, etc.

NOTE For any real number a and b

1. $a > b \Rightarrow -a < -b$
2. $a > b \Rightarrow \frac{1}{a} < \frac{1}{b}$
3. $a > b \Rightarrow a + k > b + k$
4. $a > b \Rightarrow ak > bk$ when $k > 0$
5. $a.b = 0 \Rightarrow$ either a is zero or b is zero or both a and b are zero.

Imaginary Numbers : If the square of a number is negative then this number is called as an imaginary number. e.g., $\sqrt{-1}, \sqrt{-2}, \sqrt{-3}$ etc.

An imaginary number is denoted by 'i', where $i = \sqrt{-1}$

FACTS ABOUT IMAGINARY NUMBERS

1. $i^0 = 1, i^1 = i, i^2 = -1, i^3 = -i, i^4 = 1$ etc.
2. $i^n = i^{4p+r} = (i^4)^p \times i^r = 1 \times i^r = i^r$
3. $\sqrt{a} \times \sqrt{b} \neq \sqrt{ab}$ if both a, b are negative *i.e.*, imaginary otherwise atleast one of a, b must be whole number *e.g.*,

$$\sqrt{-5} \times \sqrt{-7} = \sqrt{5}i \times \sqrt{7}i = \sqrt{35}i^2 = -\sqrt{35}$$

but $\sqrt{-5} \times \sqrt{-7} = \sqrt{-5 \times -7} \neq \sqrt{35}$

EXAMPLE 1 *Find the value of* i^{63}.

SOLUTION $i^{63} = (i^4)^{15} \times i^3 = i^3 = -i$

EXAMPLE 2 *Find the value of* i^{170}.

SOLUTION $i^{170} = (i^4)^{42} \times i^2 = i^2 = -1$

EXAMPLE 3 *Find the value of* $\frac{1}{i^{123}}$

SOLUTION $\frac{1}{i^{123}} = \frac{1}{i^{120} \times i^3} = \frac{1}{1 \times i^3} = \frac{1}{i^3} = \frac{1}{i^3} \times \frac{i}{i} = \frac{i}{i^4} = i$

EXAMPLE 4 *Find the value of* $\sqrt{-16} \times \sqrt{-25}$.

SOLUTION $\sqrt{-16} \times \sqrt{-25} = 4i \times 5i = 20i^2 = -20$

EXAMPLE 5 *Find the value of* $(\sqrt{-1})^{4n+1}$.

SOLUTION $(\sqrt{-1})^{4n+1} = i^{4n+1} = i^{4n} \times i = i$

EXAMPLE 6 *Find the value of* i^{-343}.

SOLUTION $i^{-343} = \frac{1}{i^{343}} = \frac{1}{(i^4)^{85} \times i^3} = \frac{1}{1 \times i^3} = \frac{1 \times i}{i^3 \times i} = i$

EXAMPLE 7 *Find the value of* $i^{248} + i^{341} + i^{442} + i^{543}$.

SOLUTION $i^{248} + i^{341} + i^{442} + i^{543} = 1 + i + (-1) + (-i) = 0$

EXAMPLE 8 *The value of* $\frac{1}{i^n} + \frac{1}{i^{(n+3)}} + \frac{1}{i^{(n+2)}} + \frac{1}{i^{(n+1)}}$ *is :*

(a) -1 (b) 1
(c) 0 (d) *can't be determined*

SOLUTION $\frac{1}{i^n} + \frac{1}{i^{(n+3)}} + \frac{1}{i^{(n+2)}} + \frac{1}{i^{(n+1)}}$ is :

$$= \frac{1}{i^n} + \frac{1}{i^n \times i^3} + \frac{1}{i^n \times i^2} + \frac{1}{i^n \times i}$$

$$= \frac{1}{i^n} + \frac{1}{i^n} \times \frac{i}{i^4} + \frac{1}{i^n} \times \frac{i^2}{i^4} + \frac{1}{i^n} \times \frac{i^3}{i^4}$$

$$= \frac{1}{i^n} + \frac{i}{i^n} + \frac{i^2}{i^n} + \frac{i^3}{i^n} = \frac{1}{i^n} + \frac{i}{i^n} + \frac{-1}{i^n} - \frac{i}{i^n} = 0$$

Hence (c) is the correct option.

COMPLEX NUMBERS

The combination of real number and imaginary number is known as complex number *i.e.*, the number of the form $a + ib$ where a and b are purely real numbers and $i = \sqrt{-1}$, is called as a complex number. It is denoted by $z = a + ib$ where real $z = a$ and imaginary $z = b$.

1. **Property of order :** For any two complex numbers $(a + ib)$ and $(c + id)$ $(a + ib) <$ (or $>$) $c + id$ is not defined *e.g.*, $9 + 4i < 3 - i$ makes no sense.
2. A complex number is said to be purely real if $\text{Im}(z) = 0$ is and said to be purely imaginary if $Re(z) = 0$. The complex number $0 = 0 + i.0$ is both purely real and purely imaginary.
3. The sum of four consecutive powers of i is zero.

i.e., $i^k + i^{k+1} + i^{k+2} + i^{k+3} = 0$

OPERATIONS ON COMPLEX NUMBERS

Let z_1, z_2 be two complex numbers such that $z_1 = (a_1 + ib_1)$ and $z_2 = (a_2 + ib_2)$ then :

1. $z_1 \pm z_2 = (a_1 \pm a_2) + i(b_1 \pm b_2)$
2. $z_1 . z_2 = (a_1 a_2 - b_1 b_2) + i(a_1 b_2 + b_1 a_2)$
3. $z_1 = z_2 \Leftrightarrow a_1 = a_2$ and $b_1 = b_2$

Conjugate Complex Number : The complex number $z = a + ib$ and $\bar{z} = (a - ib)$ are called the complex conjugate of each other, where $i = \sqrt{-1}, b \neq 0$ and a, b are real numbers.

Properties of Conjugate

For any z there exists the mirror image of z along the real axis denoted as $\bar{z}$, then

(i) $z = \bar{z} \Leftrightarrow z$ is purely real

(ii) $z = -\bar{z} \Leftrightarrow z$ is purely imaginary

Scanned by CamScanner

yoursmahboob.wordpress.com

(iii) $\overline{(\bar{z})} = z$

(iv) $\text{Re}(z) = \text{Re}(\bar{z}) = \dfrac{z+\bar{z}}{2}$

(v) $\text{Im}(z) = \dfrac{z-\bar{z}}{2i}$

(vi) $\overline{z_1 + z_2} = \bar{z}_1 + \bar{z}_2$

(vii) $\overline{z_1 - z_2} = \bar{z}_1 - \bar{z}_2$

(viii) $\overline{z_1 z_2} = \bar{z}_1 \bar{z}_2$

(ix) $\overline{\left(\dfrac{z_1}{z_2}\right)} = \dfrac{\bar{z}_1}{\bar{z}_2}$

(x) $z_1\bar{z}_2 + \bar{z}_1 z_2 = 2\,\text{Re}(\bar{z}_1 z_2) = 2\,\text{Re}(z_1\bar{z}_2)$

(xi) $\overline{z^n} = (\bar{z})^n$

(xii) If $z = f(z_1)$, then $\bar{z} = f(\bar{z}_1)$

Modulus of a Complex Number : The modulus of a complex number $z = (a + ib)$ is represented as $|z| = \sqrt{a^2 + b^2}$.

Properties of Modulus

(i) $|z| \geq 0 \Rightarrow |z| = 0$ iff $z = 0$ and $|z| > 0$ iff $z \neq 0$

(ii) $-|z| \leq \text{Re}(z) \leq |z|$ and $-|z| \leq \text{Im}(z) \leq |z|$

(iii) $|z| = |\bar{z}| = |-z| = |-\bar{z}|$

(iv) $z\bar{z} = |z|^2$

(v) $|z_1 \pm z_2| \leq |z_1| + |z_2|$
In general $|z_1 \pm z_2 \pm z_3 \pm \ldots z_n| \leq |z_1| \pm |z_2| \pm |z_3| \pm \ldots |z_n|$

(vi) $|z_1 \pm z_2| \geq ||z_1| - |z_2||$

(vii) $|z_1 z_2| = |z_1||z_2|$

(viii) $\left|\dfrac{z_1}{z_2}\right| = \dfrac{|z_1|}{|z_2|}$

(ix) $|z^n| = |z|^n$

(x) $||z_1| - |z_2|| \leq |z_1 + z_2| \leq |z_1| + |z_2|$

(xi) $|z_1 \pm z_2|^2 = (z_1 \pm z_2)(\bar{z}_1 \pm \bar{z}_2)$
$= |z_1|^2 + |z_2|^2 \pm (z_1\bar{z}_2 + \bar{z}_1 z_2)$

(xii) $|z_1 + z_2|^2 + |z_1 - z_2|^2 = 2(|z_1|^2 + |z_2|^2)$

nth ROOT OF UNITY

1. Unity has n roots namely $1, \omega, \omega^2, \omega^3, \ldots, \omega^{n-1}$ which are in geometric progression and the sum of these n roots is zero.
2. Product of n roots is $(-1)^{n-1}$.

Square Root

The square root of $z = a + ib$ are

$$\pm\left(\sqrt{\frac{|z|+a}{2}} + i\sqrt{\frac{|z|-a}{2}}\right) \text{ for } b > 0$$

and $$\pm\left(\sqrt{\frac{|z|+a}{2}} - i\sqrt{\frac{|z|-a}{2}}\right) \text{ for } b < 0$$

Remember

1. The square root of i are $\pm\left(\dfrac{1+i}{\sqrt{2}}\right)$ when $b = 1$
2. The square root of $-i$ are $\left(\dfrac{1-i}{\sqrt{2}}\right)$ when $b = -1$

or $$\sqrt{a+ib} = \pm(x+iy)$$

and $$\sqrt{a-ib} = \pm(x-iy)$$

where $$x = \left(\frac{a+\sqrt{a^2+b^2}}{2}\right)^{1/2}$$

and $$y = \left(\frac{\sqrt{a^2+b^2}-a}{2}\right)^{1/2}$$

CUBE ROOT OF UNITY

Cube root of unity are $1, \omega, \omega^2$ where

(a) $1 + \omega + \omega^2 = 0$

(b) $\omega^3 = 1$

(c) $\bar{\omega} = \omega^2$ and $(\bar{\omega})^2 = \omega$

(d) $\omega^{3n} = 1, \omega^{3n+1} = \omega, \omega^{3n+2} = \omega^2$

NOTE Iota (i) is neither 0, nor greater than 0, or nor less than 0.

EXAMPLE 1 *Find the modulus of* $5 + \sqrt{-11}$.

SOLUTION $\because \quad z = 5 + \sqrt{-11} = 5 + \sqrt{11}\,i$

$\therefore \quad |z| = \sqrt{25 + 11} = \sqrt{36} = 6$

EXAMPLE 2 *If the multiplicative inverse of a complex number is* $\dfrac{\sqrt{5}+6i}{41}$ *then the complex number itself is:*

(a) $\sqrt{5} - 6i$ (b) $\sqrt{5} + 6i$

(c) $6 + \sqrt{7}i$ (d) *none of these*

SOLUTION Since $z \cdot \dfrac{(\sqrt{5}+6i)}{41} = 1$

$$\Rightarrow \quad z = \frac{41}{(\sqrt{5}+6i)} \times \frac{\sqrt{5}-6i}{\sqrt{5}-6i} = \sqrt{5} - 6i$$

Hence (a) is the correct option.

EXAMPLE 3 *Which of the following is correct?*

(a) $7 + i > 5 - i$ (b) $8 + i > 9 - i$

(c) $13 + i < 25 - 3i$ (d) *none of these*

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION Since the relation is not defined i.e., $(a+ib) \gtrless (c+id)$ is indeterminable.

Hence (d) is the correct option.

EXAMPLE 4 *The smallest positive integer n for which* $\left(\frac{1+i}{1-i}\right)^n = -1$ *is :*

(a) 5 (b) 1

(c) 2 (d) none of these

SOLUTION Given that $\left(\frac{1+i}{1-i}\right)^n = -1$

$$\Rightarrow \quad \left[\frac{(1+i)(1+i)}{(1-i)(1+i)}\right]^n = -1$$

$$\Rightarrow \quad i^n = -1$$

$$\Rightarrow \quad (-1)^{\frac{n}{2}} = (-1) \Rightarrow \frac{n}{2} = 1$$

$$\therefore \quad n = 2$$

Hence (c) is the correct option.

EXAMPLE 5 *The smallest positive integer n for which* $\left(\frac{1+i}{1-i}\right)^n = 1$ *is:*

(a) 2 (b) 4 (c) 6 (d) 8

SOLUTION $\left(\frac{1+i}{1-i}\right)^n = \left(\frac{(1+i)(1+i)}{(1-i)(1+i)}\right)^n$

$$= \left(\frac{(1+i)^2}{2}\right)^n = i^n = 1$$

$$\Rightarrow \quad i^n = 1 = i^4 \Rightarrow n = 4$$

Hence (b) is the correct option.

EXAMPLE 6 $(3+2i)^3 = ?$

(a) $9-46i$ (b) $9+46i$

(c) $-9+46i$ (d) none of these

SOLUTION $(3+2i)^3 = 3^3 + (2i)^3 + 3.3.2i\,(3+2i)$

$= 27 + 8i^3 + 18i\,(3+2i)$

$= 27 + 8i^3 + 54i + 36i^2$

$= 27 - 8i + 54i - 36 = (-9 + 46i)$

Hence (c) is the correct option.

EXAMPLE 7 *The multiplicative inverse of* $(3+2i)^2$ *is :*

(a) $\frac{12}{169} - \frac{5i}{169}$ (b) $\frac{5}{169} - \frac{12i}{169}$

(c) $\frac{5}{13} - \frac{12i}{13}$ (d) none of these

SOLUTION $(3+2i)^2 = 9 + 4i^2 + 12i$

$= 9 - 4 + 12i = 5 + 12i$

then $z^{-1} = \frac{1}{5+12i} = \frac{1}{5+12i} \times \frac{5-12i}{5-12i}$

$$= \frac{5-12i}{25-144i^2} = \frac{5-12i}{169} = \left(\frac{5}{169} - \frac{12i}{169}\right)$$

Thus (b) is the correct option.

EXAMPLE 8 *If* $|z| = 1$ *then* $\left(\frac{1+z}{1+\bar{z}}\right)$ *equals :*

(a) $\bar{z}$ (b) z

(c) z^{-1} (d) none of these

SOLUTION $\frac{1+z}{1+\bar{z}} = \left(\frac{1+z}{1+\bar{z}}\right)\frac{z}{z} = \frac{z(1+z)}{(z+1)} = z$ $(\because |z| = 1)$

Hence (b) is the correct option.

EXAMPLE 9 *The value of* $\sqrt{i} + \sqrt{-i}$ *is :*

(a) 1 (b) $\sqrt{2}$

(c) $-i$ (d) none of these

SOLUTION $\sqrt{i} + \sqrt{-i} = \sqrt{(\sqrt{i} + \sqrt{-i})^2}$

$$= \sqrt{i - i + 2\sqrt{i}\sqrt{-i}} = \sqrt{2\sqrt{-i^2}} = \sqrt{2}$$

Hence (b) is the correct option.

EXAMPLE 10 *The value of* $\log_e(-1)$ *is :*

(a) $i\pi$ (b) 0

(c) i^{-1} (d) does not exist

SOLUTION $\log_e(-1) = \log_e(e^{i\pi}) = i\pi$

Hence (a) is the correct option.

EXAMPLE 11 *The number of solutions of the equation* $z^2 + |z|^2 = 0$, *where z is a complex number is :*

(a) 1 (b) 2

(c) 4 (d) infinitely many

SOLUTION $z^2 + |z|^2 = 0 \Rightarrow z^2 + z\bar{z} = 0$

$$\Rightarrow \quad z(z+\bar{z}) = 0$$

or $\quad z \cdot 2\,\mathrm{Re}(z) = 0$

$$\therefore \quad z = 0 \quad \text{and} \quad \mathrm{Re}(z) = 0$$

If $z = x + iy \Rightarrow 0 = x + iy \Rightarrow (x, y) = (0, 0)$

and if $z = 0 + ib \Rightarrow (a, b) = (0, b)$ but $b \in R$

So, there are infinitely many solutions. Since $b \in R$ Hence (d) is the correct option.

EXAMPLE 12 *The value of* $\left(\frac{i+\sqrt{3}}{2}\right)^{100} + \left(\frac{i-\sqrt{3}}{2}\right)^{100}$ *is :*

(a) -1 (b) 1 (c) 0 (d) i

SOLUTION $\frac{i+\sqrt{3}}{2} = \left(\frac{i+\sqrt{3}}{2}\right)\frac{i}{i} = \left(\frac{-1+\sqrt{3}i}{2i}\right) = \frac{\omega}{i}$

($\because$ A complex number $a + ib$ for which $|a : b| = 1 : \sqrt{3}$ or $\sqrt{3} : 1$ can always be expressed in terms of i, ω or ω^2)

Similarly, $\frac{i-\sqrt{3}}{2} = \frac{\omega^2}{i}$

$$\therefore \quad \left(\frac{i+\sqrt{3}}{2}\right)^{100} + \left(\frac{i-\sqrt{3}}{2}\right)^{100} = \left(\frac{\omega}{i}\right)^{100} + \left(\frac{\omega^2}{i}\right)^{100}$$

$$= \omega^{99} \cdot \omega + \omega^{198} \cdot \omega^2 \qquad [\because \omega^{99} = \omega^{198} = 1]$$

$$= \omega + \omega^2 = -1$$

Hence (a) is the correct option.

Scanned by CamScanner

yourmathbooks.wordpress.com

EXAMPLE 13 *If* $1, \omega, \omega^2$ *be the cube roots of unity, then the value of* $(1-\omega+\omega^2)^5+(1+\omega-\omega^2)^5$ *is :*

(a) 0 *(b)* 16 *(c)* 32 *(d)* 64

SOLUTION $\because \quad 1+\omega+\omega^2=0$

$\therefore \quad 1+\omega=-\omega^2$ and $1+\omega^2=-\omega$

$\therefore (1-\omega+\omega^2)^5+(1+\omega-\omega^2)^5=(-2\omega)^5+(-2\omega^2)^5$

$=-32(\omega^5+\omega^{10}) \quad [\because \omega^5=\omega^2$ and $\omega^{10}=\omega$ and $\omega+\omega^2=-1]$

$=32$

Hence (c) is the correct option.

EXAMPLE 14 *If* $1, \omega, \omega^2, \omega^3, \ldots, \omega^{n-1}$ *be the n, nth roots of unity, the value of* $(9-\omega)(9-\omega^2)\ldots(9-\omega^{n-1})$ *will be :*

(a) 0 *(b)* $\dfrac{9^n-1}{8}$

(c) $\dfrac{8^n-1}{3}$ *(d) none of these*

SOLUTION Let $x^n=1 \Rightarrow x=(1)^{1/n}$

$\Rightarrow \quad x^n-1=0$

or $x^n-1=(x-1)(x-\omega)(x-\omega^2)\ldots(x-\omega^{n-1})$

$\Rightarrow \quad \dfrac{x^n-1}{x-1}=(x-\omega)(x-\omega^2)\ldots(x-\omega^{n-1})$

Putting $x=9$ in both sides, we have

$(9-\omega)(9-\omega^2)(9-\omega^3)\ldots(9-\omega^{n-1})=\dfrac{9^n-1}{8}$

Thus (b) is the correct choice.

EXAMPLE 15 *If* $\left(\dfrac{1-i}{1+i}\right)^{100}=x+iy$ *then the value of* (x, y) *is :*

(a) (0, 1) *(b)* (0, 0)
(c) (1, 0) *(d)* (−1, 0)

SOLUTION $\dfrac{1-i}{1+i}=\dfrac{(1-i)(1-i)}{(1+i)(1-i)}=\dfrac{-2i}{2}=-i$

Hence $\left(\dfrac{1-i}{1+i}\right)^{100}=(-i)^{100}=1$

Thus $x+iy=1 \Rightarrow x=1, y=0$

So the value of $(x, y)=(1, 0)$

Hence (c) is the correct option.

EXAMPLE 16 *The inequality* $a+ib<c+id$ *holds if*

(a) $a<c, b<d$ *(b)* $a<c, b>d$
(c) $a>c, b<d$ *(d) none of these*

SOLUTION Option (d) is correct.

EXAMPLE 17 *The points* z_1, z_2, z_3, z_4 *in the complex plane form the vertices of a parallelogram iff :*

(a) $z_1+z_2=z_3+z_4$ *(b)* $z_1+z_3=z_2+z_4$
(c) $z_1+z_3>z_2+z_4$ *(d) none of these*

SOLUTION If the mid point of z_1z_3 is the same as that of z_2z_4.

i.e., $\dfrac{1}{2}(z_1+z_3)=\dfrac{1}{2}(z_2+z_4)$

$\Rightarrow z_1+z_3=z_2+z_4$, only then these points can form a parallelogram.

EXAMPLE 18 *If* $a+ib=\sqrt{\dfrac{(u+iv)}{(x+iy)}}$ *then the value of* a^2+b^2 *is :*

(a) $\sqrt{\dfrac{u^2+v^2}{x^2+y^2}}$ *(b)* $\dfrac{u^2-v^2}{x^2-y^2}$

(c) can't be determined *(d) none of these*

SOLUTION $a^2+b^2=|a+ib|^2$

$=\left|\dfrac{u+iv}{x+iy}\right|$ (Putting the value of $a+ib$)

$=\dfrac{\sqrt{u^2+v^2}}{\sqrt{x^2+y^2}}$

Hence (a) is the correct option.

EXAMPLE 19 *The maximum value of* $|z|$ *when z satisfies the condition* $\left|z+\dfrac{2}{z}\right|=2$ *is :*

(a) $\sqrt{3}-1$ *(b)* $\sqrt{3}$ *(c)* $\sqrt{3}+1$ *(d)* 1

SOLUTION $\because \quad |z|=\left|z+\dfrac{2}{z}-\dfrac{2}{z}\right|$

$|z| \le \left|z+\dfrac{2}{z}\right|+\left|\dfrac{2}{z}\right|$

It means $|z| \le 2+\dfrac{2}{|z|}$

$\Rightarrow \quad |z|^2 \le 2|z|+2$

$\Rightarrow \quad |z|^2-2|z|+1 \le 2+1$

$\Rightarrow \quad (|z|-1)^2 \le 3$

$\Rightarrow \quad -\sqrt{3} \le |z|-1 \le \sqrt{3}$

$\Rightarrow \quad 1-\sqrt{3} \le |z| \le 1+\sqrt{3}$

Therefore the maximum value of $|z|$ is $1+\sqrt{3}$

EXAMPLE 20 *The modulus of the complex number* $\dfrac{(2-i\sqrt{5})}{(1+2\sqrt{2}i)}$ *is :*

(a) −1 *(b)* 1 *(c)* $\sqrt{3}$ *(d)* $-\sqrt{3}$

SOLUTION The modulus of $\left(\dfrac{2-i\sqrt{5}}{1+2\sqrt{2}i}\right)=\left|\dfrac{2-i\sqrt{5}}{1+2\sqrt{2}i}\right|$

$=\dfrac{\sqrt{4+5}}{\sqrt{1+8}}=\dfrac{3}{3}=1$

Hence (b) is the correct answer.

EXCLUSIVE DISCUSSION ABOUT NUMBERS

Generally we use decimal system in our day to day mathematical applications *e.g.,* counting of the things, accounting in offices etc. Why we call it decimal system?

Since there we use 10 symbols *viz.,* 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 to represent the data, so we said the representation is in decimal system. The sequence of decimal numbers goes on as 0, 1, 2, 3 4, 5, 6, 7, 8, 9, 10, 11,12, 13, 14, 15, 16, 17, 18, 19, 20, 21.. etc. So after 9, each successive number is a combination of 2 (or more) unique symbols of this system.

Scanned by CamScanner

yoursmahboob.wordpress.com

The decimal system is a positional-value system in which the value of a digit in a number depends on its position. For example 879. Here 8 represents 800, 7 represents 70 and 9 represents 9 units. In essence, 8 carries the most weight of three digits, it is referred as the most significant digit (MSD). The 9 carries the least weight and is called as the least significant digit (LSD)

i.e., $879 = 8\times10^2 + 7\times10^1 + 9\times10^0$

Similarly $63.78 = 6\times10^1 + 3\times10^0 + 7\times10^{-1} + 8\times10^{-2}$

So, this number is actually equal to 6 tens plus 3 units plus 7 tenths plus 8 hundredths.

So $3859276 = 3\times10^6 + 8\times10^5 + 5\times10^4 + 9\times10^3 + 2\times10^2 + 7\times10^1 + 6\times10^0$

and $9253.827 = 9\times10^3 + 2\times10^2 + 5\times10^1 + 3\times10^0 + 8\times10^{-1} + 2\times10^{-2} + 7\times10^{-3}$

In general, any number is simply the sum of the products of each digit value and its positional (or place) value.

Positional →	10^3	10^2	10^1	10^0	10^{-1}	10^{-2}	10^{-3}
values (weights)	9	2	5	3	8	2	7
	MSD			Decimal point			LSD

Thus a two digit numbers can be expressed as $x\times10^1 + y\times10^0$, where x is the tens and y is the unit digit.

Thus the two digit number xy is expressed as $10x + y$ Similarly a three digit number xyz is expressed as $10^2x + 10^1y + 10^0z$

or xyz is expressed as $100x + 10y + z$ where x, y, z are the hundreds tens and unit digit respectively.

In general an n digit number in decimal representation, can be expressed as

$k_1\times10^{n-1} + k_2\times10^{n-2} + k_3\times10^{n-3} + \ldots + k_n\times10^0$

Some Facts about Decimal Numbers

1. The digits which are always same *i,e,* when they are seen upside down, they appears the same. *e.g.,* 0, 1 and 8.
2. The digits which create confusion when they are written upside down they change their face values. *e.g.,* 6 and 9.
3. When the digits of a two digits number are reversed *i.e.,* when their position is interchanged, then the difference of the original number and this resultant number is always divisible by 9. Also the difference of these two numbers is exactly the product of the difference of the two digits (*i.e.,* difference of their face values) with 9.

For example, $\begin{array}{r} xy \\ -\ yx \\ \hline 9(x-y) \end{array}$

$[\because (10x + y) - (10y + x) = 9(x - y)]$

e.g., $53 - 35 = 9\times2 = 18$ $(\because 5 - 3 = 2)$

e.g., $82 - 28 = 9\times6 = 54$ $(\because 8 - 2 = 6)$

NOTE The sum of these two numbers is always divisible by 11.

4. When the digits of a three digit number are reversed *i.e.,* the unit digit becomes hundreds digit and vice versa, then the difference between these two numbers is always divisible by 99. Also the difference of these two numbers (*i.e.,* original and resultant number) is exactly equal to the product of the difference of unit and hundreds digit, with 99, *i.e.,* $xyz - zyx = 99(x - z)$

$[\because (100x + 10y + z) - (100z + 10y + x) = 99(x - z)]$

For example (i) $852 - 258 = 99\times6$ $[\because 8 - 2 = 6]$

$= 594$

(ii) $703 - 307 = 99\times4$ $[\because 7 - 3 = 4]$

$= 396$

5. When the digits of a four digit number are reversed *i.e,* unit digit with thousands digit and vice versa and tens digit with hundreds digit and vice versa, then the difference between the original number and the resultant number is always divisible by 9.

EXAMPLE 1 *The difference between the highest and lowest two digit numbers is :*

(a) 88 (b) 89 (c) 22 (d) 99

SOLUTION Simply 99 – 10 = 89

Hence (b) is the correct option.

EXAMPLE 2 *When a two digit number is reversed, then the new number becomes $\frac{5}{6}$th of the original number. The original number is :*

(a) 56 (b) 45 (c) 48 (d) 54

SOLUTION The best way is to go through options.

Now, we consider those options which are divisible by 6. Since, the number is an integer. Again we pick up only those values which on being reversed (their digits) decreases. So only option (d) is suitable. Check it out.

Alternatively: Let the original number be $(10x + y)$ then the new number will be $(10y + x)$, then

$$(10y + x) = \frac{5}{6}(10x + y)$$

$$\Rightarrow \quad 55y = 44x$$

$$\Rightarrow \quad \frac{x}{y} = \frac{5}{4}$$

Thus the only possible values of x, y are 5, 4 respectively. Hence the original number is 54.

Alternatively : When you multiply the given (original) number by $\frac{5}{6}$ then the digit of the resultant value gets interchanged.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *The number of two digit numbers which on being reversed (i.e., their digits exchanged the position) gives out perfect square two digit numbers :*

(a) 1 *(b)* 4 *(c)* 6 *(d)* 10

SOLUTION These numbers are 61, 52, 63, 94, 46 and 18. Since these numbers on being reversed give out 16, 25, 36, 49, 64, 81 the two digit perfect square numbers.

Hence (c) is the correct answer.

EXAMPLE 4 *The number of two digit numbers which are prime :*

(a) 25 *(b)* 23

(c) 21 *(d) can't be determined*

SOLUTION Prime numbers between 1 and 100 are 25

Prime numbers of 1 digit are 4 (*viz*, 2, 3, 5, 7)

So, only two digit prime numbers = 25 – 4 = 21

Thus (c) is the correct option.

EXAMPLE 5 *The number of two digit prime numbers, with distinct digits, on being reversed they give again the prime number is :*

(a) 3 *(b)* 5 *(c)* 8 *(d)* 11

SOLUTION See, the total number of prime numbers in this case (when there are distinct digits *i.e.*, there are no same digits) the number of prime numbers must be an even number hence (c) is the correct option.

Alternatively : These numbers are 13, 31, 17, 71, 37, 73 and 79, 97.

Thus there are total 8 such numbers.

EXAMPLE 6 *The total number of two digit numbers whose unit digit is either, same, double, triple or quadruple of the tens digit :*

(a) 13 *(b)* 9 *(c)* 18 *(d)* 90

SOLUTION 11, 22, 33, 44, 55, 66, 77, 88, 99

12, 24, 36, 48

13, 26, 39

14, 28

Thus there are total 18 such numbers. Hence (c) is the correct answer.

EXAMPLE 7 *The number of two digit numbers which are perfect square and perfect cube both is :*

(a) 0 *(b)* 2

(c) can't be determined *(d) none of these*

SOLUTION Two digit perfect cubes are 27, 64

Two digit perfect squares are 16, 25, 36, 49, 64, 81

Thus there is only one value *i.e.*, 64 which is both perfect square and perfect cube.

Thus (d) is the most appropriate choice.

EXAMPLE 8 *Aprajita multiplies a number by 72 instead of 27, then her new answer will increase by, than the actual result :*

(a) $\frac{7}{2}$ *(b)* $\frac{8}{3}$

(c) $\frac{5}{3}$ *(d) none of these*

SOLUTION Let the number be k then the original product will be $k \times 27$ and the new product will be $k \times 72$

So, the difference in the product value = $72k - 27k = 45k$

Thus, new product will increase by $\frac{45k}{27k} = \frac{5}{3}$

Hence (c) is the correct answer.

Alternatively : $\frac{72-27}{27} = \frac{5}{3}$

EXAMPLE 9 *If the numerator and denominator of a fraction are exchanged then the product of these two fractions becomes equal to*

1. *The total number of such fractions is :*

(a) 1 *(b)* 31

(c) 13 *(d) infinitely many*

SOLUTION Let $\frac{x}{y}$ be the fraction where $x, y \neq 0$, then

$$\frac{x}{y} \times \frac{y}{x} = 1 \quad \text{(always)}$$

Now since x and y can assume infinite values so (d) is the best answer.

EXAMPLE 10 $\frac{3}{4}$*th of a number is 20 more than half of the same number. The required number is :*

(a) 50 *(b)* 180 *(c)* 90 *(d)* 80

SOLUTION Since the number is an integer so it must be divisible by 4. Hence option (a) and (c) are ruled out.

Now, if we check option (b) we find it is wrong so (d) is the correct.

As $80 \times \frac{3}{4} = 80 \times \frac{1}{2} + 20$

$60 = 60$

Alternatively : $x \times \frac{3}{4} = x \times \frac{1}{2} + 20 \Rightarrow x = 80$

EXAMPLE 11 *When 50 is added to the 50% of a number, then the number becomes itself. The required number is :*

(a) 375 *(b)* 100 *(c)* 150 *(d)* 500

SOLUTION

$$50 + \frac{x}{2} = x$$

$$\Rightarrow \quad \frac{x}{2} = 50 \Rightarrow x = 100$$

Hence (b) is the correct option.

EXAMPLE 12 *If we reverse the digits of a two digit number then the difference between the original number and new number is 27, the difference between the digits is :*

(a) 9 *(b)* 3

(c) can't be determined *(d) none of these*

SOLUTION Since $xy - yx = 9(x - y)$

Here $9(x - y) = 27$

Thus $x - y = 3$

So (b) is the correct answer.

EXAMPLE 13 *A two digit number is 4 times the sum of its digits and the unit digit is 3 more than the tens digit. The number is :*

(a) 52 *(b)* 61 *(c)* 63 *(d)* 36

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION Go through option

$$36 = 4(3 + 6)$$

and $$6 - 3 = 3$$

Hence (d) is the correct answer.

Alternatively : Let x, y be the tens and unit digits respectively, then

$$(10x + y) = 4(x + y) \quad ...(1)$$

$$\Rightarrow \quad 6x = 3y$$

$$\Rightarrow \quad \frac{x}{y} = \frac{1}{2} \quad ...(2)$$

and $$y - x = 3 \quad ...(3)$$

from equation (2) and (3)

$$x = 3 \quad \text{and} \quad y = 6$$

Thus the required number is 36.

EXAMPLE 14 *When a two digit number is subtracted from the other two digit number which consists of the same digits but in reverse order, then the difference comes out to be a two digit perfect square. The number is :*

(a) 59 *(b)* 73
(c) 36 *(d)* *not unique*

SOLUTION Since the difference between number is a perfect square. So this difference can be only 36, because 36 is the only two digit perfect square contains 9 as a factor.

But there are total 5 numbers possible *viz.*, 15, 26, 37, 48, 59. Since the only condition is that

$$(10x + y) - (10y + x) = 9(x - y) = 36$$

$$\Rightarrow \quad (x - y) = 4$$

Thus (d) is the most appropriate answer.

EXAMPLE 15 *There is a three digit number such that the sum of its end digits (unit digit and hundredth place digit) is always a single digit number. Another three digit number is obtained by reversing the position of end digits of the original number. Then what can be the possible sum of the tens digits of both these numbers?*

(a) 5 *(b)* 12 *(c)* 15 *(d)* 26

SOLUTION Since in both the numbers the middle digits *i.e.*, the tens digits are same it means the sum of these tens digits is always an even number ($\because x + x = 2x$)

So the option (a) and (c) are ruled out.

Now, the largest possible digit is 9 so the maximum possible sum of these two digits can be 18 (= 9 + 9). So the option (d) is also ruled out.

Thus the possible answer is (b).

EXAMPLE 16 *A three digit number which on being subtracted from another three digit number consisting of the same digits in reverse order gives 594. The minimum possible sum of all the three digits of this number is :*

(a) 8 *(b)* 12
(c) 6 *(d)* *can't be determined*

SOLUTION Let x, y, z be the hundred, tens and unit digits of the original number then

$$(100z + 10y + x) - (100x + 10y + z) = 594$$

$$\Rightarrow \quad 99(z - x) = 594 \quad \Rightarrow \quad (z - x) = 6$$

So the possible values of (x, z) are (1, 7), (2, 8) and (3, 9). Again the tens digit can have the values *viz.*, 0, 1, 2, 3, ... 9.

So the minimum possible value of $x + y + z = 1 + 0 + 7 = 8$.

Hence (a) is the correct option.

NOTE x and z can never be zero since if the left most digit becomes zero, then it means this number is only two digit number.

DIGITAL NUMBER SYSTEMS

There are various number systems used in digital representation. The most common number systems are binary octal, decimal, hexadecimal systems.

Base : The number that determines the positional value of every digit in a number is called the base of that number. For example the base of binary system is 2, octal is 8, decimal is 10 and hexadecimal is 16. It is also known as **"Radix."**

Also the base tells us that the number of distinct (or unique) symbols used in that system. For example we use only 2 distinct symbols *viz.*, 0 and 1 in binary system. Also in decimal system there are 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 unique symbols.

In the binary system (base is 2) there are only two symbols or possible digits *viz.*, 0 and 1. Even it can represent a very-very large number that can be represented in any other number system.

CONVERSION OF DECIMAL NUMBERS INTO ANOTHER

To convert any decimal number in any base 'n'. We divide the number successively by 'n' *i.e.*, first of all divide the given number, then divide the quotients obtained one by one succevily, till the last quotient becomes zero, then write down all the remainders in proper order. As the last remainder is MSD (most significant digit) and the first remainder is least significant digit. It means the first remainder will be the right most digit and the last remainder will be left most digit.

EXAMPLE 1 *Convert* $(17)_{10}$ *to binary system (or in base 2)*

SOLUTION

2	17	
2	8	→ 1
2	4	→ 0
2	2	→ 0
2	1	→ 0
	0	→ 1

→ Remainders

So $(17)_{10} = (10001)_2$

EXAMPLE 2 *Convert* $(35)_{10}$ *into base 3.*

SOLUTION

3	35	
3	11	→ 2
3	3	→ 2
3	1	→ 0
	0	→ 1

→ Remainders

So $(35)_{10} = (1022)_3$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *Convert* $(169)_{10}$ *in base 7.*

SOLUTION

7	169	
7	24	→ 1
7	3	→ 3 → Remainders
	0	→ 3

$\therefore$ $(169)_{10} = (331)_7$

EXAMPLE 4 *Convert* $(8976)_{10}$ *in base 9.*

SOLUTION

9	8976	
9	997	→ 3
9	110	→ 7 → Remainders
9	12	→ 2
9	1	→ 3
	0	→ 1

So $(8976)_{10} = (13273)_9$

EXAMPLE 5 *Convert* $(128)_{10}$ *into binary system.*

SOLUTION

2	128	
2	64	→ 0
2	32	→ 0
2	16	→ 0
2	8	→ 0
2	4	→ 0
2	2	→ 0
2	1	→ 0
	0	→ 1

Thus $(128)_{10} = (10000000)_2$

EXAMPLE 6 *Convert* $(127)_{10}$ *into binary system.*

SOLUTION

2	127	
2	63	→ 1
2	31	→ 1
2	15	→ 1
2	7	→ 1
2	3	→ 1
2	1	→ 1
	0	→ 1

Thus $(127)_{10} = (1111111)_2$

REPRESENTATION OF BINARY NUMBER SYSTEM

The binary system is also a positional value system, wherein each binary digit has its own value or weight expressed as a power of 2.

NOTE We have studied the representation of the Decimal number system in the previous articles.

The number 1101.0101 is shown represented in the figure



Here, places to the left of the binary point (*i.e.*, counter part of the decimal point) are positive powers of 2 and places to the right are negative powers of 2.

CONVERSION OF BINARY INTO DECIMAL

To find the decimal equivalent of binary number, we take the sum of the products of each digit value (0 or 1) with its positional value.

EXAMPLE 1 *Convert* $(100101)_2$ *into decimal representation.*

SOLUTION $1\times2^5 + 0\times2^4 + 0\times2^3 + 1\times2^2 + 0\times2^1 + 1\times2^0$

$= 32 + 0 + 0 + 4 + 0 + 1 = 37$

EXAMPLE 2 *Convert* $(1101.0101)_2$ *in base 10 (i.e., decimal system)*

SOLUTION $(1101.0101) = 1\times2^3 + 1\times2^2 + 0\times2^1 + 1\times2^0 + 0\times2^{-1} + 1\times2^{-2} + 0\times2^{-3} + 1\times2^{-4}$

$= 8 + 4 + 0 + 1 + 0 + 0.25 + 0 + 0.0625 = (13.3125)_{10}$

EXAMPLE 3 *The decimal number corresponding to the binary number* $(111000.0101)_2$ *is :*

(a) $(5.6312)_{10}$ *(b)* $(56.3125)_{10}$

(c) $(563.125)_{10}$ *(d)* $(5631.2)_{10}$

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION $1\times2^5+1\times2^4+1\times2^3+0\times2^2$
$+0\times2^1+0\times2^0+0\times2^{-1}+1\times2^{-2}+0\times2^{-3}+1\times2^{-4}$
$=32+16+8+0+0+0+0+0.25+0+0.0625$
$=(56.3125)_{10}$

NOTE We use the subscripts to denote the base number so as to avoid confusion. For example $(10010)_2$ means the base of the number is 2 and $(201021)_3$ means the base of the number is 3 etc.
In the binary system the term "binary digit" is often abbriviated as "bit". The leftmost bit carries the largest weight and hence is called the most significant bit (MSB). The rightmost bit carries the smallest weight and hence called least significant bit (LSB). So the sequence of binary numbers goes as
00, 01, 10, 11, 100, 101, 110, 111, 1000, 1001, ... etc.
See the peculiarity in the pattern of binary numbers.

00
01
10
11
100
101
110
111
1000
1001
1010
1011
1100
1101
1110
1111
10000
10001

Now, you can see that the unit digit goes as 0, 1, 0, 1, 0, 1... and tens digit goes as 0, 0, 1, 1, 0,0, 1, 1, 0, 0, 1, 1 and Hundreds digit goes as 0000, 1111, 0000, 1111, 0000, 1111, ...' etc. and thousands digit goes as 00000000, 11111111, 00000000, 11111111, ... etc.

REPRESENTATION OF OCTAL NUMBERS

This system has base of 8. So there are 8 unique symbols *viz.*,0, 1, 2, 3, 4, 5, 6, 7 are used for representation. For example consider a number 5324.01246. Then



The decimal equivalent of $(5324.012)_8$ is given below :
$(5324.012)_8=5\times8^3+3\times8^2+2\times8^1$
$+4\times8^0+0\times8^{-1}+1\times8^{-2}+2\times8^{-3}$
$=2560+192+16+4+0.015625+2\times0.001953125$
$=(2772.01953125)_{10}$
The sequence of octal number goes as :
0, 1, 2, 3, 4, 5, 6, 7, 10, 11, 12, 13, 14, 15, 16, 17, 20, 21, 22, 23, 24, 25, 26, 27, 30, 31, ...

HEXADECIMAL NUMBER SYSTEM

It has base 16. So it uses 16 unique symbols *viz.*, 1, 2, 3, ...9 and *A*, *B*, *C*, *D*, *E*, and *F*.

Thus $(1)_{10}=(1)_{16}$, $(2)_{10}=(2)_{16}$,
$(3)_{10}=(3)_{16}$ .... $(9)_{10}=(9)_{16}$
and $(10)_{10}=(A)_{16}$
$(11)_{10}=(B)_{16}$, ... $(15)_{10}=(F)_{16}$.

CONVERSION OF DECIMAL FRACTIONS INTO BINARY

To convert a decimal fraction into binary, we multiply successively the decimal fraction by the radix i.e., base 2 (in case of binary) and write down all the integral values (i.e., the figures left of the decimal point) in order. As the first integral figure (0 or 1) will be just right to the binary point and the last integral will be the right most figure in the binary representation.

EXAMPLE 1 *Convert* $(0.875)_{10}$ *to binary.*

SOLUTION

	Integer part
$2\times0.875=1.750$	1
$2\times0.75=1.50$	1
$2\times0.50=1.00$	1

$\therefore\quad (0.875)_{10}=(0.111)_2$

EXAMPLE 2 *Convert* $(0.3125)_{10}$ *to binary equivalent.*

SOLUTION

	Integer part
$2\times0.3125=0.625$	0
$2\times0.625=1.25$	1
$2\times0.25=0.50$	0
$2\times0.50=1.00$	1

Thus $(0.3125)_{10}=(0.1010)_2$

EXAMPLE 3 *Convert* 0.454545 *to binary equivalent.*

SOLUTION

	Integer part
$2\times0.454545=0.909090$	0
$2\times0.90909=1.81816$	1
$2\times0.81818=1.63638$	1
$2\times0.63636=1.27272$	1
$2\times0.27272=0.54544$	0
$2\times0.54544=1.09088$	1
$2\times0.09088=0.18176$	0
$2\times0.18176=0.36352$	0
$2\times0.36352=0.72704$	0
$2\times0.72704=1.45408$	1

Since, the sequence is continuous so can never be expressed as exactly in binary. Therefore writing down the integral parts.

$(0.454545)_{10}=(0.1000101110)_2$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 4 *Convert $(38.21)_{10}$ to its binary equivalent.*

SOLUTION First we convert the integer part *i.e.*, 38.

2	38		
2	19	→ 0	Remainder
2	9	→ 1	
2	4	→ 1	
2	2	→ 0	
2	1	→ 0	
	0	→ 1	

$(38)_{10} = (100110)_2$

Now we convert the fractional part *i.e.* 0.21

	Integer part
$2 \times 0.21 = 0.42$	0
$2 \times 0.42 = 0.84$	0
$2 \times 0.84 = 1.68$	1
$2 \times 0.68 = 1.36$	1
$2 \times 0.36 = 0.72$	0
$2 \times 0.72 = 1.44$	1
$2 \times 0.44 = 0.88$	0
$2 \times 0.88 = 1.76$	1
$2 \times 0.76 = 1.52$	1
$2 \times 0.52 = 1.04$	1

Thus $(0.21)_{10} = (0.0011010111)_2$

$\therefore$ $(38.21)_{10} = (100110.0011010111)_2$

EXAMPLE 5 *Convert $(0.825)_{10}$ to octal.*

SOLUTION

	Integer part
$8 \times 0.825 = 6.600$	6
$8 \times 0.6 = 4.8$	4
$8 \times 0.8 = 6.4$	6
$8 \times 0.4 = 3.2$	3
$8 \times 0.2 = 1.6$	1
$8 \times 0.6 = 4.8$	4

Since its recurring number so it will not be stop.
Thus we write only 5 figures.

Hence, $(0.825)_{10} = (.64631)_8$

OCTAL TO BINARY CONVERSION

The following table helps in quick conversion.

Octal Digit	0	1	2	3	4	5	6	7
Binary Equivalent	000	001	010	011	100	101	110	111

EXAMPLE 6 *Convert $(273)_8$ to binary.*

SOLUTION

2	7	3
↓	↓	↓
010	111	011

Hence $(273)_8 = (010111011)_2$

EXAMPLE 7 *Convert $(16504)_8$ to binary.*

SOLUTION

1	6	5	0	4
↓	↓	↓	↓	↓
001	110	101	000	100

Hence $(16504)_8 = (001110101000100)_2$

EXAMPLE 8 *Convert $(37.42)_8$ to binary.*

SOLUTION

3	7	4	2
↓	↓	↓	↓
011	111	100	010

$\therefore$ $(37.42)_8 = (0111\ 111.100010)_2$

BINARY TO OCTAL CONVERSION

This is the inverse process of the previous conversion. In this process we make the triplets starting from the right (*i.e.*, LSB). If the number of digits in the binary representation are not in the group of 3 (*i.e.*, 3, 6, 9, 12, ... etc) then we associate either 1 or 2 zeros at the left of the MSB, then we write the octal equivalent of each triplet.

EXAMPLE 9 *Convert $(100011010110)_2$ to octal.*

SOLUTION

100	011	010	110	(see the table)
↓	↓	↓	↓	
4	3	2	6	

Hence $(100011010110)_2 = (4326)_8$

EXAMPLE 10 *Convert $(1001011001)_2$ to octal.*

SOLUTION

001	001	011	001	[two more zeros are added in the left to make the triplet]
↓	↓	↓	↓	
1	1	3	1	

Thus $(1001011001)_2 = (1131)_8$

EXAMPLE 11 *Convert $(10110.0101)_2$ to octal.*

SOLUTION

010	110	010	100
↓	↓	↓	↓
4	6	2	4

Thus $(10110.0101)_2 = (46.24)_8$

Note that, after binary point, the groups of 3 bits are made starting from left to right. That's why we added two zeros to make a group of three bits as the, last group had only 1.

Scanned by CamScanner

yoursmahboob.wordpress.com

DECIMAL TO HEX CONVERSION

EXAMPLE 12 *Convert $(725)_{10}$ to hexadecimal.*

SOLUTION

16	725		$[\because (13)_{10} = (D)_{16}]$
16	45	→ 5	
16	2	→ D	
	0	→ 2	

$\therefore \quad (725)_{10} = (2D5)_{16}$

EXAMPLE 13 *Convert $(0.03125)_{10}$ to base 16.*

SOLUTION

	Integer part
$16 \times 0.03125 = 0.5$	0
$16 \times 0.5 = 8.0$	8

So $(0.03125)_{10} = (0.08)_{16}$

HEX TO DECIMAL CONVERSION

EXAMPLE 14 *Convert $(765)_{16}$ to decimal.*

SOLUTION $(765)_{16} = 7 \times 16^2 + 6 \times 16^1 + 5 \times 16^0$

$= 1792 + 96 + 5 = 1893$

Thus $(765)_{16} = (1893)_{10}$

EXAMPLE 15 *Convert $(3C8.08)_{16}$ to decimal.*

SOLUTION $(3C8.08)_{16} = 3 \times 16^2 + C \times 16^1 + 8 \times 16^0 + 0 \times 16^{-1} + 8 \times 16^{-2}$

$= 3 \times 16^2 + 12 \times 16^1 + 8 \times 16^0 + 0 \times 16^{-1} + 8 \times 16^{-2}$

$= 768 + 192 + 8 + 0 + 0.03125 = (968.03125)_{10}$

So $(3C8.08)_{16} = (968.03125)_{10}$

INTRODUCTORY EXERCISE-1.7

1. The value of x when $(25)_x = (85)_{10}$ is :
   (a) 2 (b) 8
   (c) 40 (d) can't be determined
2. Which one is an invalid number?
   (a) $(325)_7$ (b) $(345)_5$
   (c) $(543)_6$ (d) none of these
3. $(35)_n$, $(37)_n$, $(45)_n$ and $(51)_n$ all are written in base n then the value of n, such that all these four numbers when written in decimal system, they must be the consecutive prime numbers :
   (a) $n = 8$ (b) $n = 2$
   (c) $n = 12$ (d) $n = 6$
4. The last three digits in the binary representation of $(365247728)_{10}$ is :
   (a) 000 (b) 100
   (c) 110 (d) 010
5. The last three digits, if $(12345956)_{10}$ is expressed in binary system :
   (a) 210 (b) 100
   (c) 110 (d) 010
6. The last four digits in the binary representation of $(8009)_{10}$ is :
   (a) 1001 (b) 0001
   (c) 0101 (d) none of these
7. A number of decimal system when represented in binary system then its first and last digits are same and the rest digits are also of another kind. Further this number appears to be palindrome of numerals. The number is :
   (a) 57 (b) 19
   (c) 8 (d) 9
8. When a two digit number is reversed, the new number is reduced by 63 and the sum of digits of these individual numbers is 9. Now, if these same numbers are converted into base 'x' the larger number becomes 5 times that of smaller one the value of x is :
   (a) 36 (b) 13
   (c) 15 (d) 18
9. If $(25)_n \times (31)_n = (1015)_n$ then the value of $(13)_n \times (52)_n$ is when $n > 0$:
   (a) $(626)_4$ (b) $(462)_n$
   (c) $(716)_n$ (d) $(676)_n$
10. What is the decimal equivalent of the hexadecimal number $(\underbrace{100\ldots001}_{23\text{ zeros}})_{16}$?
    (a) $2^{23} + 1$ (b) $2^{24} + 1$
    (c) $2^{92} + 1$ (d) $2^{96} + 1$
11. If the decimal number 2^{111} is written in the octal system, then what is its unit place digit?
    (a) 0 (b) 1
    (c) 2 (d) 3
12. Match list I (Binary) with list II (Octal) and select the correct answer using the codes given below the lists :

List I (Binary)	List II (Octal)
I - 101110	(A) 135
II - 1101110	(B) 56
III - 1011101	(C) 176
IV - 1111110	(D) 156

Codes :
(a) I-A, II-C, III-B, IV-D (b) I-B, II-D, III-A, IV-C
(c) I-A, II-D, III-B, IV-C (d) I-B, II-C, III-A, IV-D

Scanned by CamScanner

yoursmahboob.wordpress.com

PROGRESSIONS

This topic is directly related to our real life. For example whenever the things (or activities) occur in a definite pattern, we say there is a progression.

Suppose A has 2 books, B has 4 books, C has 6 books, D has 8 books etc., then we can say that E must has 10 books, if all these form a progression.

So if the same quantity is added in the next term or value, then it is said to be in Arithmetic Progression *e.g.*, $a, (a+d), (a+2d), (a+3d), (a+4d), \ldots$

Here you can see that each next term is 'd' more than its previous term.

Some more examples of **Arithmetic Progression** are as follows

1, 2, 3, 4, 5, 6, 7, ...
3, 5, 7, 9, 11, ...
7, 11, 15, 19, 23, ...
$-9, -4, 1, 6, 11, 16, \ldots$
$13, 9, 5, 1, -3, -7, -11, \ldots$

The first term of the series is denoted by 'a' and the common difference by 'd' and nth term by t_n and sum of the n terms of the series is denoted by 'S_n'.

Also the last term is denoted by 'l'

The common difference is the difference between any two consecutive terms of the series.

Let a_1 be the first term and a_2 be the second term and a_3 be the third term then $d = a_3 - a_2 = a_2 - a_1$ etc.

The n^{th} term of a series is $T_n = a + (n-1)d$

and the sum of the n terms of a series is

$$S_n = \frac{n}{2}[2a + (n-1)d]$$

and the arithmetic mean A.M. $= \left(\frac{a_1 + a_2 + a_3 + \ldots + a_n}{n}\right)$

and the last term $= l = a + (n-1)\,d$.

EXAMPLE 1 *Find the 10th term of the following series 7, 10, 13, 16, ... etc.*

SOLUTION $T_{10} = 7 + (10-1)\,3$ [Here $a = 7$, $d = 3$]

$T_{10} = 34$

EXAMPLE 2 *Find the sum of the 10 terms of the following series $-11, -8, -5, -2, \ldots$*

SOLUTION $S_n = \frac{n}{2}[2a + (n-1)\,d]$

$S_{10} = \frac{10}{2}[2 \times (-11) + (9)\,3]$ [Here $a = -11$, $d = 3$]

$= 5 \times (-22 + 27) = 25$

EXAMPLE 3 *Find the arithmetic mean of the following series $-17, -13, -9, -5, -1, \ldots$.*

SOLUTION A.M. $= \frac{(-17) + (-13) + (-9) + (-5) + (-1)}{5}$

$= -\frac{45}{5} = -9$

NOTE
1. The arithmetic mean (A.M.) of odd numbers of consecutive terms is the middle most term itself.
2. If a, b, c be three consecutive terms of an A.P. then the A.M. $= b = \frac{a+c}{2}$
3. The consecutive odd number of terms of an A.P. are written as $(a-2d)\,(a-d), a, (a+d), (a+2d), \ldots$ etc.
4. The consecutive even number of terms on an A.P. are written as $(a-5d)\,(a-3d)\,(a-d)\,(a+d)\,(a+3d)\,(a+5d)\ldots$ etc.

GEOMETRIC SERIES (OR PROGRESSION)

In the series each successive (or next) term is multiplied by a fix number.

For example: 1, 3, 9, 27, 81, ...
2, 8, 32, 128, 512, ...
$-3, 6, -12, 24, -48, \ldots$

If a is the first term, l is the last term, r is the common ratio, T_n is the nth and S_n is the sum of n term.

then, $l = ar^{(n-1)}$

$T_n = ar^{(n-1)}$

$S_n = \frac{a(r^n - 1)}{r - 1}$ if $r > 1$

and $S_n = \frac{a(1 - r^n)}{1 - r}$ if $r < 1$

also the geometric mean G.M. $= (a_1 \,.\, a_2 \,.\, a_3 \,.\, a_4 \ldots a_n)^{1/n}$

EXAMPLE 1 *Find the 6th term of 2, 4, 8, ...*

SOLUTION $T_6 = 2(2)^5 = 2^6 = 64$ [$\because T_n = a(r)^{n-1}$]

EXAMPLE 2 *Find the sum of 7 terms of the following series 1, 3, 9, 27, 81, ...*

SOLUTION $\because S_n = \frac{a(r^n - 1)}{r - 1}$

$\therefore \quad S_7 = \frac{1(3^7 - 1)}{3 - 1} = \frac{(2187 - 1)}{2} = 1093$

EXAMPLE 3 *Find the Geometric mean of 3, 9, 27.*

SOLUTION G.M. $= (a_1 \,.\, a_2 \,.\, a_3)^{1/3}$

$= (3 \,.\, 9 \,.\, 27)^{1/3} = (3^6)^{1/3} = 3^2 = 9$

NOTE
1. The G.M. of odd number of consecutive terms of a G.P. is the middlemost term itself.
2. If a, b, c be three consecutive terms of a G.P. then G.M. $= b = \sqrt{ac} = (a \,.\, c)^{1/2}$
3. The consecutive odd number of terms of a G.P. is written as ... $\frac{a}{r^2}, \frac{a}{r}, a, ar, ar^2 \ldots$ etc.
4. The consecutive even number of terms of a G.P. is written as ... $\frac{a}{r^3}, \frac{a}{r}, ar, ar^3, \ldots$ etc.

Scanned by CamScanner

yoursmahboob.wordpress.com

SOME IMPORTANT FORMULAE

1. The sum of first n terms of natural numbers $= \frac{n(n+1)}{2}$
2. The sum of first n even natural numbers $= n(n+1)$
3. The sum of first n odd natural numbers $= n^2$
4. The sum of first n perfect squares (numbers) $= \frac{n(n+1)(2n+1)}{6}$
5. The sum of first n perfect cubes (numbers) $= \left[\frac{n(n+1)}{2}\right]^2$
6. The sum of the first n terms of the following series : 1, 3, 6, 10, 15, 21, ... is $\frac{n(n+1)(n+2)}{6}$.

FUNCTIONS/OPERATIONS/CODING-DECODING

In this article we will learn to operate the numbers with specially defined *i.e.*, user defined operations. Basically this is a kind of coding-decoding.

Directions : Solve the following questions (1–3) on the basis of information given below :

If $a \oplus b = a^3 + b^2 + 1$

$a \copyright b = (a - b)^2 + 1$

$a * b = a^3 - b^2 + 1$

EXAMPLE 1 *If* $P = (2 \oplus 3) \copyright (3 * 5)$, *then the value of P is :*

(a) 225 (b) 226

(c) 256 (d) none of these

SOLUTION

$P = (2 \oplus 3) \copyright (3 * 5)$

$= (2^3 + 3^2 + 1) \copyright (3^3 - 5^2 + 1)$

$= 18 \copyright 3 = (18 - 3)^2 + 1$

$P = 226$

EXAMPLE 2 *The value of* $P = ((1 \oplus 2) * 2) \copyright 1)$ *is :*

(a) 40001 (b) 10804

(c) 40401 (d) none of these

SOLUTION

$((1 \oplus 2) * 2) \copyright 1) = ((6 * 2) \copyright 1)$

$= (213 \copyright 1)$

$= (212)^2 + 1 = 44945$

EXAMPLE 3 *The value of* $P = (((2 \oplus 2) \copyright 2) \copyright 2)$ *is :*

(a) 14441 (b) 14401

(c) 144001 (d) none of these

SOLUTION

$P = (((2 \oplus 2) \copyright 2) \copyright 2)$

$= (((13) \copyright 2) \copyright 2)$

$= (122 \copyright 2) = 14401$

Directions for example number 4, 5, 6: In the following division problem some digits are replaced by letters a, b, c.... etc. Every missing digit is uniquely determinable by a, b, c,... etc.

$$
\begin{array}{r|l}
ab3 & c61de1 \;\big\backslash\; 4cfd \\
 & eg2 \\
\hline
 & 6gd \\
 & fa5 \\
\hline
 & 8be \\
 & d3j \\
\hline
 & 8f1 \\
 & 8f1 \\
\hline
 & \times
\end{array}
$$

EXAMPLE 4 *The value of J is :*

(a) 1 (b) 6

(c) 8 (d) none of these

EXAMPLE 5 *The value of f is :*

(a) 4 (b) 6

(c) 0 (d) can't be determined

EXAMPLE 6 *The value of* $a + g$ *is :*

(a) 7 (b) 8

(c) 10 (d) none of these

SOLUTION (4–6) From the second step, $g = 9$, since $11 - 2 = 9$

again from the second step, $c = 5$, since $ab3 \times c = fa5$ (using unit digit property)

Now, from the last step $ab3 \times d = 8f1$

$\Rightarrow$ $d = 7$ (only)

so, the value of $a = 1$ (only)

therefore $f = 6$ (only) $\Rightarrow$ $b = 2$

Therefore, $e = 4$, from first step (since $a = 1$, $b = 2$)

Thus $a = 1$, $b = 2$, $c = 5$, $d = 7$, $e = 4$, $f = 6$, $g = 9$, $j = 8$

EXAMPLE 7 *If* $F = a.(|b|).c.(|d|).e.(|f|).g(|h|).i.(|j|)$ *and* $G = a.b.c.d.e.f.g.h.i.j$

Again, if $a = (-1)^1$, $b = (2)^{-2}$, $c = (-3)^3$, $d = (4)^{-4}$, ... $j = (10)^{-10}$ *then the correct relation is :*

(a) $F = -G$ (b) $F = G$

(c) $F \cdot G = 1$ (d) none of these

SOLUTION For F, the modulus of b, d, f, h, j is ineffective since for the given values of b, d, f, h, j the value of $(|b|) = b, |d| = d$.... etc.

Therefore $F = G$

EXAMPLE 8 *If* $2f(x) = f(2x)$, $3f(x) = f(3x)$, $4f(x) = f(4x)$.... *etc, then* $f(1) + f(2) + f(3) + \ldots + f(n)$ *equals to where* $f(1) = 1$ *:*

(a) $n(n+1)$ (b) 0

(c) $\frac{n(n+1)}{2}$ (d) $n!$

SOLUTION

$f(1) = 1$

$f(2) = 2$

$f(3) = 3$

$f(4) = 4$

... ...

$f(n) = n$

$\therefore$ $f(1) + f(2) + f(3) + \ldots f(n) = \frac{n(n+1)}{2}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 9 *If* $f\left(x-\frac{1}{x}\right)=x^2+\frac{1}{x^2}$, *then* $f(t)$ *equals to :*

(a) $t^2-\frac{1}{t^2}$ (b) $t^2+\frac{1}{t^2}$ (c) t^2+2 (d) $(t-1)^2$

SOLUTION Since $f\left(x-\frac{1}{x}\right)=x^2+\frac{1}{x^2}$

$$\Rightarrow \quad f\left(x-\frac{1}{x}\right)=\left(x-\frac{1}{x}\right)^2+2$$

Hence $f(t)=t^2+2$

✍ ***Directions for example number 10, 11 and 12 :***

$$p * q = p^2 - q^2$$

$$p \$ q = p^2 + q^2$$

$$p @ q = pq + p + q$$

$p \Delta q$ = Remainder of $\frac{p}{q}$

$p \copyright q$ = greatest integer less than or equal to $\frac{p}{q}$

EXAMPLE 10 *If* $p=11$ *and* $q=7$, *then the value of* $(p * q) @ (p \$ q)$ *is :*

(a) *14641* (b) *12482*
(c) *12243* (d) *none of these*

SOLUTION $(11 * 7) @ (11 \$ 7) = 72 @ 170$

$= 72 \times 170 + 72 + 170 = 12482$

EXAMPLE 11 *If* $p=8$ *and* $q=10$, *then the value of* $[(p \$ q) \Delta (p @ q)] * [(q * p) @ (q \copyright p)]$ *is :*

(a) *5329* (b) *5239* (c) *12100* (d) -973

SOLUTION $[(8 \$ 10) \Delta (8 @ 10)] * [(10 * 8) @ (10 \copyright 8)]$

$= (164 \Delta 98) * (36 @ 1)$

$= 66 * 73 = -973$

EXAMPLE 12 *If* $p=15$ *and* $q=25$, *then the value of the expression* $[(q \copyright p) @ (p \$ q)] \copyright [(q * p) \Delta (p \$ q)]$ *is :*

(a) *4* (b) *5* (c) *101* (d) *6*

SOLUTION $[(25 \copyright 15) @ (15 \$ 25)] \copyright [(25 * 15) \Delta (15 \$ 25)]$

$= (1 @ 850) \copyright (400 \Delta 850)$

$= (1701) \copyright (400) = 4$

✍ ***Directions for question number 13 :*** *Follow the steps to solve the given problem :*

Step 1. *Put* $x=2$ *and* $y=3$

Step 2. *Multiply* x *by 2*

Step 3. *Multiply* y *by 3*

Step 4. *If* y = *greatest possible 3 digit perfect square, then stop, else follow step 5.*

Step 5. *Go to step 2.*

EXAMPLE 13 *What is the maximum possible value of* x?

(a) *32* (b) *64*
(c) *less than 50* (d) *none of these*

SOLUTION $x = 2, 4, 8, 16, 32, 64$

$y = 3, 9, 27, 81, 243, 729$

Hence, the required maximum value of $x = 64$.

EXAMPLE 14 $p @ q = p^2 - 20$ *if* $p > q$, $p @ q = p^2 + 20$ *if* $p \le q$, *then for* $a=5$ *and* $b=4$ *the value of* $[(a @ b) @ (a @ b)] - [(b @ a) @ (b @ a)]$ *is :*

(a) *416* (b) -461
(c) -1271 (d) *none of these*

SOLUTION $[(5 @ 4) @ (5 @ 4)] - [(4 @ 5) @ (4 @ 5)]$

$= [5 @ 5) - (36 @ 36)$

$= 45 - 1316 = -1271$

EXAMPLE 15 *If* $x \# y = \frac{x+y}{xy}$, *then the value of* $p \# (q \# r)$ *for every* $p, q, \in N$ *:*

(a) $\frac{pq+qr+r^2}{p(p+q+r)}$ (b) $\frac{pqr+q+r}{p(q+r)}$

(c) $\frac{p(qr+q+r)}{pqr}$ (d) *none of these*

SOLUTION $p \# (q \# r) = p \# \left(\frac{q+r}{qr}\right)$

$$= \frac{p+\left(\frac{q+r}{qr}\right)}{p\left(\frac{q+r}{qr}\right)} = \frac{\frac{pqr+q+r}{qr}}{\frac{p(q+r)}{qr}}$$

$$= \frac{pqr+q+r}{p(q+r)}$$

EXAMPLE 16 *If* $f(x, y) = \frac{(x+y)^2}{xy}$ *for every* $x, y > 0$ *then* $f(x, y)$ *must be :*

(a) ≥ 2 (b) < 5
(c) ≥ 4 (d) *none of these*

SOLUTION $f(x, y) = \frac{x^2+y^2+2xy}{xy} = \frac{x}{y} + \frac{y}{x} + 2$

The minimum value of $\frac{x}{y} + \frac{y}{x} = 2$ at $x = y$

Therefore $f(x, y) = \left(\frac{x+y}{xy}\right)^2 \ge 4$

EXAMPLE 17 *The function* f_1 *and* f_2 *are defined as follows :* $f_1 = a! + b!$ *and* $f_2 = a^a + b^b$ *for* $a, b > 1$ *and* $a, b \in N$ *then the correct relation is :*

(a) $f_1 < f_2$ (b) $f_1 = f_2$
(c) $f_1 > f_2$ (d) *can't say*

SOLUTION Check for any value of $(a, b) > 1$ and $a, b \in N$

since $a! = a.(a-1)(a-2)\ldots 1$

but $a^a = a.a.a.\ldots.a$ times

Therefore, $f_1 < f_2$

✍ ***Directions :*** *For any natural number* p *and* q

(i) $p \# q = p^3 + q^3 + 3$ *and* $p * q = p^2 + q^2 + 2$ *and* $p \$ q = |p - q|$

(ii) $Max\,(p, q)$ = *Maximum of* (p, q) *and* $Min\,(p$ *and* $q) =$ *Minimum of* (p, q)

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 18 *The value of* $[(4 \# 5) \$ (14 * 15)]$ *is :*
(a) -196 *(b)* 231 *(c)* -225 *(d)* 229

SOLUTION $[(4 \# 5) \$ (14 * 15)]$
$= (64 + 125 + 3) \$ (196 + 225 + 2)$
$= (192 \$ 423) = 231$

EXAMPLE 19 *The value of* $[(1 \$ 2) \# (3 \$ 4)] * [(5 \$ 6) \# (7 \$ 8)]$ *is :*
(a) 25 *(b)* 52
(c) 36 *(d) none of these*

SOLUTION $[(1 \$ 2) \# (3 \$ 4)] * [(5 \$ 6) \# (7 \$ 8)]$
$= (1 \# 1) * (1 \# 1) = 5 * 5 = 52$

EXAMPLE 20 *The value of :*
$[\text{Max}\,(2, 4) \$ \text{Min}\,(6, 8)] \# [\text{Min}\,(10, 12) \$ \text{Max}\,(14, 16)]$
(a) 227 *(b)* 225
(c) 224 *(d) none of these*

SOLUTION $[\text{Max}\,(2, 4) \$ \text{Min}\,(6, 8)] \# [\text{Min}\,(10, 12) \$ \text{Max}\,(14, 16)]$
$= (4 \$ 6) \# (10 \$ 16)$
$= 2 \# 6 = 227$

ROMAN NUMBER SYSTEM

In this system there are basically seven symbols used to represent the whole number system. The symbols and their respective values are given below.

$I = 1,\ V = 5,\ X = 10,\ L = 50,$
$C = 100,\ D = 500$ and $M = 1000$

In general, the symbols in the numeral system are read from left to right, starting with the symbol representing the largest value; the same symbol cannot occur contiguously more than three times; the value of the numeral is the sum of the values of the symbols.

For example LX VII $= 50 + 10 + 5 + 1 + 1 = 67$.

An exception to the left to the right reading occurs when a symbol is followed immediately by a symbol of greater value, then the smaller value is subtracted from the larger. For example,

CDXLVIII $= (500 - 100) + (50 - 10) + 5 + 1 + 1 + 1 = 448$.

IMPORTANT CONVERSION

1 trillion $= 10^{12} = 1000000000000$
1 billion $= 10^{9} = 1000000000$
1 million $= 10^{6} = 1000000$
1 crore $= 10^{7} = 100$ lakh
10 lakh $= 10^{6} = 1$ million
1 lakh $= 10^{5} = 100000 = 100$ thousand
1 thousand $= 10^{3} = 1000$

EXAMPLE 1 *The value of the numeral MCDLXIV is :*
(a) 1666 (b) 664 (c) 1464 (d) 656

EXAMPLE 2 *Which of the following can represent the numeral for 2005 ?*
(a) DDDDV (b) MMV
(c) MDDXV (d) MDVX

EXAMPLE 3 *The value of the numeral MDCCLXXXIX is :*
(a) 1789 (b) 1987 (c) 2989 (d) 2311

EXAMPLE 4 *Which of the following represents the numeral for 2949?*
(a) MMMIXL (b) MMXMIX
(c) MMCMIL (d) MMCMXLIX

SOLUTION

1. MCDLXIV $= 1000 + (500 - 100) + 50 + 10 + (5 - 1)$
$= 1464$
2. $2005 = 2000 + 5 = 1000 + 1000 + 5 =$ MMV
3. MDCCLXXXIX $= 1000 + 500 + 100 + 100 + 50 + 10 + 10 + 10 + (10 - 1)$
4. $2949 = 2000 + 900 + 40 + 9$
$= (1000 + 1000) + (1000 - 100) + (50 - 10) + (10 - 1)$
$=$ MMCMXLIX

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

MISCELLANEOUS

1. $\frac{-2}{3}, \frac{5}{2}, \frac{-1}{6}$ in descending order can be arranged as :

(a) $\frac{5}{2}, \frac{-1}{6}, \frac{-2}{3}$ (b) $\frac{-2}{3}, \frac{5}{2}, \frac{-1}{6}$

(c) $\frac{-1}{6}, \frac{5}{2}, \frac{-2}{3}$ (d) $\frac{5}{2}, \frac{-2}{3}, \frac{-1}{6}$

2. The sum of a number and its reciprocal is thrice the difference of the number and its reciprocal. The number is :

(a) $\pm\sqrt{2}$ (b) $\pm\frac{1}{\sqrt{2}}$

(c) $\pm\sqrt{3}$ (d) $\pm\frac{1}{\sqrt{3}}$

3. If x and y are positive real number, then :

(a) $x > y \Rightarrow -x > -y$ (b) $x > y \Rightarrow -x < -y$

(c) $x > y \Rightarrow \frac{1}{x} > \frac{1}{y}$ (d) $x > y \Rightarrow \frac{-1}{x} < \frac{-1}{y}$

4. If x be a rational number and y be an irrational number, then :

(a) both $x + y$ and xy are necessarily irrational

(b) both $x + y$ and xy are necessarily rational

(c) xy is necessarily irrational, but $x + y$ can be either rational or irrational

(d) $x + y$ necessarily irrational, but xy can be either rational or irrational.

5. The smallest number must be added to 1780 to make it a perfect square is :

(a) 69 (b) 156

(c) 49 (d) 59

6. If p be a prime, $p > 3$ and let x be the product of positive integers 1, 2, 3, ..., $(p-1)$, then consider the following statements :

1. x is a composite number divisible by p.
2. x is a composite number not divisible by p, but some prime greater than p may divide x.
3. x is not divisible by any prime $(p-2)$.
4. All primes less than $(p-1)$ divide x.

Of these statements :

(a) 1 and 2 are correct (b) 2 and 3 are correct

(c) 3 and 4 are correct (d) 4 alone is correct

7. Consider the following statements :

1. If $p > 2$ is a prime, then it can be written as $4n + 1$ or $4n + 3$ for suitable n.
2. If $p > 2$ is a prime, then $(p-1)(p+1)$ is always divisible by 4.

Of these statements :

(a) 1 and 2 are false (b) 1 and 2 are true

(c) 1 is true but 2 is false (d) 1 is false but 2 is true

8. 111111111111 is divisible by :

(a) 3 and 37 only (b) 3, 37 and 11 only

(c) 3, 11, 37 and 111 only (d) 3, 11, 37, 111 and 1001

9. An integer is divisible by 16 if and only if its last X digits are divisible by 16. The value of X would be :

(a) three (b) four

(c) five (d) six

10. The number of pairs lying between 40 and 100 such that HCF is 15, is :

(a) 3 (b) 4

(c) 5 (d) 6

11. If the product of the HCF and the LCM of 3 natural numbers p, q, r equals pqr, then p, q, r must be :

(a) such that $(p, q, r) = 1$

(b) prime number

(c) odd number

(d) such that $(p, q) = (p, r) = (q, r) = 1$

12. If x and y be integer such that $3x + 2y = 1$ then consider the following statements regarding x and y :

1. x and y can be found using euclidean algorithm.
2. x and y are positive.
3. x and y are uniquely determined.

Of these statements :

(a) 1 and 2 are correct (b) 1 alone is correct

(c) 1 and 3 are correct (d) 1, 2 and 3 are correct

13. In the equation $4^{x+2} = 2^{x+3} + 48$ the value of x will be :

(a) $-\frac{3}{2}$ (b) -2

(c) -3 (d) 1

14. A lad was asked his age by his friend. The lad said, "The number you get when you subtract 25 times my age from twice the square of my age will be thrice your age". If the friend's age is 14, then the age of the lad is :

(a) 21 (b) 28

(c) 14 (d) 25

15. Consider the following statements :

Assertion (A): $a^0 = 1, a \neq 0$

Reason (R): $a^m \div a^n = a^{m-n}$, m, n being integers.

Of these statements :

(a) both A and R are true and R is the correct explanation of A

(b) both A and R are true and R is not the correct explanation of A

(c) A is true, but R is false

(d) A is false, but R is true

Scanned by CamScanner

yoursmahboob.wordpress.com

16. If the sum of two numbers added to the sum of their squares is 42 and the product of these numbers is 15, then the numbers are :
(a) 15, 1 (b) $\frac{15}{6}$, 6
(c) $2\frac{1}{2}$, 6 (d) 5, 3

17. If the equality $\frac{1}{x-1} = \frac{2}{x-2}$ is satisfied by x then the value of x will be :
(a) 2 (b) 1
(c) 1/2 (d) 0

18. If $x + \frac{1}{x} = 2$, then the value of $x^2 + \frac{1}{x^2}$ is :
(a) 6 (b) 4
(c) 2 (d) 0

19. If $a = 24$, $b = 26$, $c = 28$, then the value of $a^2 + b^2 + c^2 - ab - bc - ac$ will be :
(a) 0 (b) 4
(c) 8 (d) 12

20. A number n is said to be 'perfect' if the sum of all its divisors excluding n 'itself' is equal to n. An example of perfect number is :
(a) 9 (b) 15
(c) 21 (d) 6

21. The product $\frac{a}{b^2} \times \frac{b}{a^2}$ expressed as the sum of two identical terms, is :
(a) $\frac{1}{a+b} + \frac{1}{a+b}$ (b) $\frac{a}{b} + \frac{a}{b}$
(c) $\frac{b}{a} + \frac{b}{a}$ (d) $\frac{1}{2ab} + \frac{1}{2ab}$

22. If $x = 6$ and $y = 3$ then the value of $[x + y]^{x/y}$ is :
(a) 30 (b) 36
(c) 81 (d) 18

23. If the arithmetic mean of the numbers $x_1, x_2, x_3, \ldots, x_n$ is $\bar{x}$, then the arithmetic mean of the numbers $ax_1 + b, ax_2 + b, ax_3 + b, \ldots, ax_n + b$, where a and b are two constants, would be :
(a) $\bar{x}$ (b) $na\bar{x} + nb$
(c) $a\bar{x}$ (d) $a\bar{x} + b$

24. The arithmetic mean of first 50 odd natural numbers is :
(a) 50 (b) 625
(c) 175 (d) none of these

25. A boy draws n squares with sides 1, 2, 3, 4, 5, ... in inches. The average area covered by these n squares will be :
(a) $\left(\frac{n+1}{2}\right)$ (b) $\left(\frac{n+1}{2}\right)\left(\frac{2n+1}{3}\right)$
(c) $\left(\frac{n+1}{2}\right)\left(\frac{2n+1}{3}\right)^{-1}$ (d) $\left(\frac{n+1}{2}\right) - 1\left(\frac{2n+1}{3}\right)$

26. Which one of the following sets of surds is in correct sequence of ascending order of their values?
(a) $\sqrt[4]{10}, \sqrt[3]{6}, \sqrt{3}$ (b) $\sqrt{3}, \sqrt[4]{10}, \sqrt[3]{6}$
(c) $\sqrt{3}, \sqrt[3]{6}, \sqrt[4]{10}$ (d) $\sqrt[4]{10}, \sqrt{3}, \sqrt[3]{6}$

27. Which one of the following statements is not correct :
(a) every integer is a rational number
(b) every natural number is an integer
(c) every natural number is a real number
(d) every real number is a rational number

28. If $(a^2 + b^2)^3 = (a^3 + b^3)^2$ and $ab \neq 0$ then $\left(\frac{a}{b} + \frac{b}{a}\right)^6$ is equal to :
(a) $\frac{a^6 + b^6}{a^3 b^3}$ (b) $\frac{64}{729}$
(c) 1 (d) $\frac{a^6 + a^3 b^3 + b^6}{a^2 b^4 + a^4 b^2}$

29. A page contains 60 lines. A chapter contains 125 pages. A book contains 5 chapters. 20 such books form a bound. If there are totally 30 lakhs lines in an x number of bounds then the value of x is :
(a) 4 (b) 2
(c) 5 (d) 6

30. If x is a natural number which is a perfect square, then the number $x + \sqrt{x}$ must end in :
(a) 0 or 5 (b) 0 or 1 or 9
(c) 0 or 2 or 6 (d) 0 or 4 or 8

31. If $2^p + 1$ is a prime number, then p must be power of :
(a) 2 (b) 3
(c) 5 (d) 6

32. The number of composite numbers between 101 and 120 is :
(a) 11 (b) 12
(c) 13 (d) 14

33. The number $10^N - 1$ is divisible by 11 for :
(a) even values of N
(b) all values of N
(c) odd values of N
(d) N must be a multiple of 11

34. A merchant has 140 litres, 260 litres, 320 litres of three kinds of oil. He wants to sell the oil by filling the three kinds separately in tins of equal volume. The volume of such a tin is :
(a) 20 litres (b) 13 litres
(c) 16 litres (d) 70 litres

35. If d is the HCF of a and b, then $d = \lambda a + \mu b$ where :
(a) λ and μ are uniquely determined
(b) λ and μ are both positive
(c) λ and μ are both negative
(d) one of the λ and μ is negative and the other is positive

36. The expression $\left(1 + \frac{1}{3}\right)\left(1 + \frac{1}{4}\right)\left(1 + \frac{1}{5}\right)\ldots\left(1 + \frac{1}{n}\right)$ simplifies to :
(a) $\frac{n+1}{3}$ (b) $\frac{n}{n+1}$
(c) $\frac{3}{n}$ (d) $1 + \frac{1}{3}\cdot\frac{1}{4}\cdot\frac{1}{5}\ldots\frac{1}{n}$

37. If $x = 2^{1/3} + 2^{-1/3}$ then the value of $2x^3 - 6x$ will be :
(a) 5 (b) −5
(c) 1 (d) 0

38. On the set of integers I, if a binary operation 'o' be defined as $aob = a - b$ for every $a, b \in I$, then :
(a) association law holds
(b) commutative law holds
(c) I is not closed under this operation
(d) I is closed under this operation

39. If $x - y = 1$, then the value of $x^3 - y^3 - 3xy$ will be :
(a) 1 (b) −1
(c) 3 (d) −3

40. Among the expression $(1 - 3P)$, $[1 - (3P)^2]$, $[1 - (3P)^3]$ and $[1 - (3P)^4]$ the number of factors of $(1 - 81P^4)$ is :
(a) one (b) two
(c) four (d) three

Scanned by CamScanner

yoursmahboob.wordpress.com

41. If the sum of three consecutive integers is 21, then the sum of the two smaller integers is :
(a) 11 (b) 5
(c) 12 (d) 13

42. If $2s = a + b + c$, then the value of $(s-a)^2 + (s-b)^2 + (s-c)^2 + s^2 - a^2 - b^2 - c^2$ will be :
(a) -1 (b) 1
(c) 2 (d) 0

43. If $ab + bc + ca = 0$ then the value of $\frac{1}{a^2 - bc} + \frac{1}{b^2 - ca} + \frac{1}{c^2 - ab}$ will be :
(a) -1 (b) $a + b + c$
(c) abc (d) 0

44. If $4^{x+3} \times 2^{x-3} - 128 = 0$ then the value of x is :
(a) $\frac{1}{3}$ (b) $\frac{2}{3}$
(c) $\frac{3}{3}$ (d) $\frac{4}{3}$

45. If $a^m \cdot a^n = a^{mn}$, then $m(n-2) + n(m-2)$ is :
(a) 0 (b) 1
(c) -1 (d) $\frac{1}{2}$

46. $\frac{6^6 + 6^6 + 6^6 + 6^6 + 6^6 + 6^6}{3^6 + 3^6 + 3^6} \div \frac{4^6 + 4^6 + 4^6 + 4^6}{2^6 + 2^6} = 2^n$, then the value of n is :
(a) -1 (b) 0
(c) $\frac{1}{2}$ (d) 1

47. If $a^{1/m} = b^{1/n} = c^{1/p}$ and $abc = 1$ then $m + n + p$ is equal to :
(a) 0 (b) 2
(c) 1 (d) -2

48. Which one of the following among the numbers $-\frac{3}{7}, \frac{2}{3}$ and $\frac{-1}{3}$ is in descending order?
(a) $\frac{-1}{3}, \frac{-3}{7}, \frac{2}{3}$ (b) $\frac{2}{3}, \frac{-1}{3}, \frac{-3}{7}$
(c) $\frac{-3}{7}, \frac{2}{3}, \frac{-1}{3}$ (d) $\frac{2}{3}, \frac{-3}{7}, \frac{-1}{3}$

49. A rational equivalent to $\frac{-24}{20}$ with denominator 25 is :
(a) $\frac{-30}{25}$ (b) $\frac{30}{25}$
(c) $\frac{-29}{25}$ (d) $\frac{-19}{25}$

50. $\frac{3}{4} \times \left(\frac{-2}{3} + \frac{3}{5}\right)$ is equal to :
(a) $\frac{-3}{20}$ (b) $\frac{-19}{20}$
(c) $\frac{-1}{20}$ (d) $\frac{1}{20}$

51. In a problem involving division, the divisor is eight times the quotient and four times the remainder. If the remainder is 12, then the dividend is :
(a) 300 (b) 288
(c) 512 (d) 524

52. Which one of the following is not correct?
(a) $\sqrt{0.4096} = 0.64$ (b) $\sqrt{40.96} = 6.4$
(c) $\sqrt{0.04096} = 0.064$ (d) $\sqrt{4096} = 64$

53. Let $\frac{a}{b} = \frac{c}{d}$, (where a and b are odd prime numbers). If $c > a$ and $d > b$, then :
(a) c is not a multiple of a (b) d is not a multiple of b
(c) $c = ka$, $d = kb$ with $k > 1$ (d) $c = ka$, $d = lb$ with $k \neq l$

54. Which one of the following numbers belong to the given series 18, 26, 34, 42, 50?
(a) 438 (b) 338
(c) 232 (d) 132

55. The number of prime factors in the expression $6^4 \times 8^6 \times 10^8 \times 12^{10}$ is :
(a) 48 (b) 64
(c) 72 (d) 80

56. x is a five digit number. The digit in ten thousands place is 1. The number formed by its digits in units and tens places is divisible by 4. The sum of all the digits is divisible by 3. If 5 and 7 also divide x, then x will be :
(a) 14020 (b) 12060
(c) 10020 (d) 10080

57. The sum of all possible factors of 500 (including 1 and 500 themselves) equals :
(a) 784 (b) 980
(c) 1092 (d) 1350

58. HCF of 1007 and 1273 is :
(a) 1 (b) 17
(c) 23 (d) 19

59. If $2s = 9$ then the value of $s^2 + (s-1)^2 + (s-3)^2 + (s-5)^2$ is :
(a) 9 (b) 25
(c) 45 (d) 35

60. The sum of the digits of a two digit number is 8. The number obtained by reversing the digits is 18 less than the original number. The original number is :
(a) 62 (b) 17
(c) 53 (d) 35

61. If $x^y = y^x$ and $y = 2x$ then x is equal to :
(a) 2 (b) -2
(c) 1 (d) -1

62. Value of $[(x^l)^{1-\frac{1}{l}}]^{\frac{1}{l-1}}$ is :
(a) x (b) 1
(c) x^{-1} (d) x^{-l}

63. If $x^a \times x^b \times x^c = 1$, then $a^3 + b^3 + c^3$ is equal to :
(a) 9 (b) abc
(c) $a + b + c$ (d) $3abc$

64. Which one of the following is a rational number?
(a) $(\sqrt{2})^2$ (b) $2\sqrt{2}$
(c) $2 + \sqrt{2}$ (d) $\frac{\sqrt{2}}{2}$

65. Rational number $\frac{-18}{5}$ lies between consecutive integers :
(a) -2 and -3 (b) -3 and -4
(c) -4 and -5 (d) -5 and -6

66. $1 \div \frac{1}{1 \div \frac{1}{1 \div \frac{1}{3}}}$ is equal to :
(a) $\frac{1}{3}$ (b) 1
(c) 3 (d) $1\frac{1}{3}$

Scanned by CamScanner

yoursmahboob.wordpress.com

67. The divisor when the quotient, dividend and the remainder are respectively 547, 171282 and 71 is equal to :
(a) 333 (b) 323
(c) 313 (d) 303

68. The value of $\sqrt{900} + \sqrt{0.09} - \sqrt{0.000009}$ is :
(a) 30.297 (b) 30.197
(c) 30.097 (d) 30.397

69. The greatest integer that divides 358, 376, 232 leaving the same remainder in each case is :
(a) 6 (b) 7
(c) 8 (d) 9

70. The units digit of every prime number (other than 2 and 5) must be necessarily :
(a) 1, 3 or 5 (b) 1, 3, 7 or 9
(c) 7 or 9 (d) 1 or 7

71. If the number 243 x 51 is divisible by 9 then the value of the digit marked as x would be :
(a) 3 (b) 1
(c) 2 (d) 4

72. The GCD of two whole numbers is 5 and their LCM is 60. If one of the number is 20, then other number would be :
(a) 25 (b) 13
(c) 16 (d) 15

73. The number of possible pairs of numbers, whose product is 5400 and HCF is 30 :
(a) 1 (b) 2
(c) 3 (d) 4

74. The least number which when divided by 2, 3, 4, 5 and 6 leaves the remainder 1 in each case. If the same number is divided by 7 it leaves no remainder. The number is :
(a) 231 (b) 301
(c) 371 (d) 441

75. Three bells, toll at interval of 36 sec, 40 sec and 48 sec respectively. They start ringing together at particular time. They next toll together after :
(a) 6 minutes (b) 12 minutes
(c) 18 minutes (d) 24 minutes

76. A has certain amount in his account. He gives half of this to his eldest son and one third of the remaining to his youngest son. The amount with him now is :
(a) 1/3 of the original (b) 2/3 of the original
(c) 3/4 of the original (d) 1/6 of the original

77. If $x + y + z = 0$, then $x^3 + y^3 + z^3$ is equal to :
(a) 0 (b) $3xyz$
(c) $\frac{xy + yz + zx}{xyz}$ (d) $xyz\,(xy + yz + zx)$

78. The remainder when $x^4 - y^4$ is divided by $x - y$ is :
(a) 0 (b) $x + y$
(c) $x^2 - y^2$ (d) $2y^4$

79. If $x - \frac{1}{x} = 2$, then the value of $x^4 + \frac{1}{x^4}$ is :
(a) 4 (b) 8
(c) 12 (d) 34

80. If the sum and the product of two numbers are 25 and 144 respectively then the difference of the numbers must be :
(a) 3 (b) 5
(c) 7 (d) 11

81. The sum of two numbers is 9 and the sum of their squares is 41. The numbers are :
(a) 4 & 5 (b) 1 & 8
(c) 3 & 6 (d) 2 & 7

82. If $3^n = 27$ then 3^{n-2} is :
(a) 3 (b) 1/3
(c) 1/9 (d) 9

83. If $a = b^x$, $b = c^y$, $c = a^z$, then xyz is :
(a) -1 (b) 0
(c) 1 (d) abc

84. If $p = x^{1/3} + x^{-1/3}$, then $p^3 - 3p$ is equal to :
(a) 3 (b) $\frac{1}{2}(x + x^{-1})$
(c) $x + x^{-1}$ (d) $2(x + x^{-1})$

85. The sum of squares of first ten natural numbers is :
(a) 375 (b) 385
(c) 475 (d) 485

86. If a language of natural numbers has binary vocabulary of 0 and 1, then which one of the following strings represents the natural number 7?
(a) 11 (b) 101
(c) 110 (d) 111

87. The least number which must be subtracted from 6708 to make it exactly divisible by 9 is :
(a) 1 (b) 2
(c) 3 (d) 4

88. Which one of the following statements is not correct?
(a) If 'a' is a rational number and b is irrational, then $a + b$ is irrational.
(b) The product of a non-zero rational number with an irrational number is always irrational.
(c) Addition of any two irrational numbers can be an integer.
(d) Division of any two integers is an integer.

89. The value of $\frac{10\sqrt{6.25}}{\sqrt{6.25} - 0.5}$ is :
(a) 125 (b) 0.125
(c) 1.25 (d) 12.5

90. The fundamental arithmetical operations on 2 recurring decimals can be performed directly without converting them to vulgar fractions :
(a) only in addition and subtraction
(b) only in addition and multiplication
(c) only in addition, subtraction and multiplication
(d) in all the four arithmetical operations

91. The greatest number that will divide 398, 436 and 542 leaving 7, 11 and 15 as remainders, respectively is :
(a) 16 (b) 17
(c) 18 (d) 19

92. Which one of the following statements is correct?
(a) If $x^6 + 1$ is divided by $x + 1$, then the remainder is -2
(b) If $x^6 + 1$ is divided by $x - 1$, then the remainder is 2
(c) If $x^6 + 1$ is divided by $x + 1$, then the remainder is 1
(d) If $x^6 + 1$ is divided by $x - 1$, then the remainder is -1

93. The value of
$$\frac{(1.5)^3 + (4.7)^3 + (3.8)^3 - 3 \times 1.5 \times 4.7 \times 3.8}{(1.5)^2 + (4.7)^2 + (3.8)^2 - (1.5 \times 4.7) - (4.7 \times 3.8) - (1.5 \times 3.8)}$$ is :
(a) 8 (b) 9
(c) 10 (d) 11

Scanned by CamScanner

yoursmahboob.wordpress.com

94. The smallest number which must be added to 803642 in order to obtain a multiple of 9 is :
(a) 1 (b) 2
(c) 3 (d) 4

95. Simplified value of $\frac{8.73\times8.73\times8.73+4.27\times4.27\times4.27}{8.73\times8.73-8.73\times4.27+4.27\times4.27}$ is :
(a) 11 (b) 12
(c) 13 (d) 14

96. If $\left(x-\frac{1}{x}\right)=5$, then $x^3-\frac{1}{x^3}$ equals :
(a) 125 (b) 130
(c) 135 (d) 140

97. Mohan gets 3 marks for each correct sum and loses 2 marks for each wrong sum. He attempts 30 sums and obtains 40 marks. The number of sums solved correctly is :
(a) 10 (b) 15
(c) 20 (d) 25

98. If x satisfies $|x-1|+|x-2|+|x-3|\geq 6$, then :
(a) $0\leq x\leq 4$ (b) $x\leq 0$ or $x\geq 4$
(c) $x\leq -2$ or $x\geq 4$ (d) $x\geq -2$ or $x\leq 4$

99. It costs Rs. 10 a kilometer to fly and Rs. 2 a km to drive. If one travels 200 km covering x km of the distance by flying and the rest by driving, then the cost of the trip is :
(a) Rs. 2000 (b) Rs. 24000
(c) Rs. $(8x + 400)$ (d) Rs. $(12x + 400)$

100. If $2^{x+3}\cdot 4^{2x-5}=2^{3x+7}$, then the value of x is :
(a) 3 (b) 4
(c) 6 (d) 7

101. The value of $\left(\frac{x^a}{x^b}\right)^{(a^2+ab+b^2)}\left(\frac{x^b}{x^c}\right)^{(b^2+bc+c^2)}\left(\frac{x^c}{x^a}\right)^{(c^2+ca+a^2)}$ is :
(a) -1 (b) x^{abc}
(c) 1 (d) $x^{(a+b+c)}$

102. The value of $4\times100+3\times10+\frac{9}{1000}$ is :
(a) 430.09 (b) 430.0009
(c) 430.009 (d) 430.900

103. Which one of the following statements is correct?
(a) There can be a real number which is both rational and irrational
(b) The sum of two irrational number is always irrational
(c) For any real numbers x and y, $x<y\Rightarrow x^2<y^2$
(d) Every integer is a rational number

104. The least number which is a perfect square and has 540 as a factor is :
(a) 8100 (b) 6400
(c) 4900 (d) 3600

105. The set of natural numbers is closed under the binary operations of :
(a) addition, subtraction, multiplication and division
(b) addition, subtraction, multiplication but not division
(c) addition and multiplication but not subtraction and division
(d) addition and subtraction but not multiplication and division

106. If $\frac{100\sqrt{25}}{\sqrt{25}+x}=50$ then the value of x is :
(a) 25 (b) $\frac{1}{\sqrt{25}}$
(c) $\sqrt{25}$ (d) $\frac{1}{25}$

107. The total number of prime numbers between 120 and 140 is:
(a) 7 (b) 6
(c) 5 (d) 4

108. The number 12375 is divisible by :
(a) 3, 11 and 9 (b) 3 and 11 only
(c) 11 and 9 only (d) 3 and 9 only

109. $\left(1-\frac{1}{3}\right)\left(1-\frac{1}{4}\right)\left(1-\frac{1}{5}\right)\ldots\left(1-\frac{1}{n}\right)$ equals :
(a) $\frac{1}{n}$ (b) $\frac{2}{n}$
(c) $\frac{3}{n}$ (d) $\frac{4}{n}$

110. If $\frac{x}{2}=\frac{y}{3}$, then $\left[\frac{4}{5}+\frac{y-x}{y+x}\right]$ equals :
(a) $\frac{3}{5}$ (b) $\frac{4}{5}$
(c) 1 (d) $\frac{6}{5}$

111. The value of $\frac{(119)^2+(119)(111)+(111)^2}{(119)^3-(111)^3}$ is :
(a) 8 (b) $\frac{1}{8}$
(c) 230 (d) $\frac{1}{230}$

112. A number consists of two digits. The sum of the digits is 11, reversing the digits, the number decreases by 45, the number is :
(a) 38 (b) 65
(c) 74 (d) 83

113. For a journey the cost of a child ticket is 1/3rd of the cost of an adult ticket. If the cost of the tickets for 4 adults and 5 children is Rs. 85, the cost of a child ticket is :
(a) Rs. 5 (b) Rs. 6
(c) Rs. 10 (d) Rs. 15

114. $9^{3/2}\div(243)^{-2/3}$ simplifies to :
(a) $3^{10/3}$ (b) $3^{19/3}$
(c) $3^{1/3}$ (d) 3^{19}

115. The solution of $(25)^{x-2}=(125)^{2x-4}$:
(a) 3/4 (b) 0
(c) 2 (d) -2

116. If $a^x=b^y=c^z$ and $\frac{b}{a}=\frac{c}{b}$ then $\frac{2z}{x+z}$ is equal to :
(a) $\frac{y}{x}$ (b) $\frac{x}{y}$
(c) $\frac{x}{2}$ (d) $\frac{z}{x}$

117. If $x<0<y$, then :
(a) $\frac{1}{x^2}<\frac{1}{xy}<\frac{1}{y^2}$ (b) $\frac{1}{x^2}>\frac{1}{xy}>\frac{1}{y^2}$
(c) $\frac{1}{x}<\frac{1}{y}$ (d) $\frac{1}{x}>1$

Scanned by CamScanner

yoursmahboob.wordpress.com

118. The expression $33.33 \div 1.1$ simplifies as :
(a) 33.3 (b) 303
(c) 33.0 (d) 30.3

119. If $|x-2| < 3$ then :
(a) $1 < x < 5$ (b) $-1 < x < 2$
(c) $-1 < x < 5$ (d) $0 < x < 6$

120. A fraction becomes 4 when 1 is added to both the numerator and denominator and it becomes 7 when 1 is subtracted from both the numerator and denominator. The numerator of the given fraction is :
(a) 2 (b) 3
(c) 7 (d) 15

121. The expression $(a-b)^3 + (b-c)^3 + (c-a)^3 = 0$ if :
(a) $a < b < c$ (b) $a > b > c$
(c) $a = b = c$ (d) $a \neq b = c$

122. If $a+b+c = 11$, $a^2+b^2+c^2 = 51$, what is the value of $ab+bc+ac$?
(a) 24 (b) 28
(c) 32 (d) 35

123. If $x+y+z = 0$, then the value of $\frac{x^2}{yz} + \frac{y^2}{zx} + \frac{z^2}{xy}$ is :
(a) 3 (b) -3
(c) 0 (d) $3xyz$

124. The value of $\left(\frac{e^x + e^{-x}}{2}\right)^2 - \left(\frac{e^x - e^{-x}}{2}\right)^2$ is :
(a) 0 (b) 1
(c) 4 (d) 16

125. The continued product of $(1+x)$, $(1+x^2)$, $(1+x^4)$, $(1+x^8)$ and $(1-x)$ is :
(a) $(1-x^8+x^{16})$ (b) (x^8+x^{16})
(c) $(1-x^{16})$ (d) $(x^{16}-1)$

126. Find the value of x and y in the given equation $5\frac{7}{x} \times y\frac{1}{13} = 12$:
(a) $-2, 9$ (b) 9, 2
(c) 4, 3 (d) 9, 4

127. The square root of $32\frac{137}{484}$ is :
(a) $5\frac{15}{22}$ (b) $15\frac{5}{32}$
(c) $5\frac{15}{28}$ (d) none of these

128. Simplify $\frac{\sqrt{25.4016} - \sqrt{1.0609}}{\sqrt{25.4016} + \sqrt{1.0609}}$:
(a) $\frac{401}{607}$ (b) $\frac{104}{706}$
(c) 41/76 (d) none of these

129. The square root of $\frac{\left(3\frac{1}{4}\right)^4 - \left(4\frac{1}{3}\right)^4}{\left(3\frac{1}{4}\right)^2 - \left(4\frac{1}{3}\right)^2}$:
(a) $5\frac{7}{12}$ (b) $5\frac{5}{12}$
(c) $5\frac{12}{13}$ (d) $5\frac{1}{6}$

130. Two numbers 34041 and 32506 when divided by certain number of three digits, leave the same remainder. The number is :
(a) 307 (b) 211
(c) 247 (d) 299

131. Mr. Black has three kinds of wine, of the first kind 403 litres, of the second 434 litres of the third 465 litres what is the least number of full carks of equal size in which this can be stored without mixing?
(a) 31 (b) 39
(c) 42 (d) 51

132. The largest sum of money which is contained in both Rs. 49.56 and Rs. 38.94 an exact number of time is :
(a) 2.7 (b) 3.54
(c) 4.28 (d) none of these

133. Tanya gives away to each of four girls $\frac{1}{12}, \frac{5}{18}, \frac{7}{30}, \frac{7}{48}$ of the apples in a basket and has only just enough apples to be able to do so without dividing an apple. The minimum number of apple had she?
(a) 250 (b) 720
(c) 750 (d) none of these

134. Abhishek, Bobby and Charlie start from the same point and travel in the same direction round an Island 6 km in circumference. Abhishek travels at the rate of 3, Bobby at the rate of $2\frac{1}{2}$ and Charlie at the rate of $1\frac{1}{4}$ km/hour. In how many hours will they come together again?
(a) 6 hrs (b) 12 hrs
(c) 24 hrs (d) 15 hrs

135. The value of $\frac{4\frac{1}{7} - 2\frac{1}{4}}{3\frac{1}{2} + 1\frac{1}{7}} \div \frac{1}{2 + \frac{1}{2 + \frac{1}{5 - \frac{1}{5}}}}$:
(a) 7/29 (b) 5/6
(c) 1 (d) 9/13

136. Mallika travelled $\frac{5}{16}$ of his journey by coach and $\frac{7}{20}$ by rail, she walked the remaining 10 km, how far did she go altogether?
(a) $27\frac{17}{29}$ (b) $33\frac{7}{27}$
(c) $19\frac{7}{27}$ (d) $29\frac{17}{27}$

137. $2^{\sqrt{3}}$ is :
(a) a natural number (b) an integer
(c) a rational number (d) an irrational number

138. If $p > 0, q < 0$ then which of the following is correct?
(a) $p+q > 0$ (b) $p-q > 0$
(c) $p+q < 0$ (d) $p-q < 0$

139. Let n be a positive integer. If $\frac{1}{n}$ has a terminating decimal expansion, then which one of the following is true?
(a) n is of the form 5^x, where x is a positive integer
(b) n is of the form 2^y, where y is non-positive integer
(c) n is of the form $2^x \cdot 5^y$ for some non-negative x and y
(d) n is of the form 10^z for some positive integer z

140. If a number of two digit is 'k' times the sum of its digits then the number formed by interchanging the digits is the sum of the digits multiplied by :
(a) $(9+k)$ (b) $(10-k)$
(c) $(11-k)$ (d) $(k-1)$

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL 1

1. When the natural numbers 1, 2, 3, ..., 500 are written, then the digit 3 is used n times in this way. The value of n is :
(a) 100 (b) 200
(c) 300 (d) 280

2. In how many ways can 1146600 be written as the product of two factors?
(a) 100 (b) 108
(c) 216 (d) 273

3. How many natural numbers upto 990 are divisible by 5 & 9 both but not by 7?
(a) 18 (b) 19
(c) 22 (d) none of a, b, c

4. The number of solution of $|x| + |y| \le 0$, for $(x, y) \in R$, is :
(a) 0 (b) 1
(c) 2 (d) infinitely many

5. The remainder when 2^{39} is divided by 39 is :
(a) 0 (b) 2
(c) 8 (d) 1

6. The unit digit of the following expression
$(1!)^{99} + (2!)^{98} + (3!)^{97} + (4!)^{96} + \ldots (99!)^1$ is :
(a) 1 (b) 3
(c) 7 (d) 6

7. The sum of all four digit numbers which are divisible by 7 is :
(a) 7071071 (b) 7^7
(c) 7107073 (d) 10019996

8. When the numerator of a positive fraction is increased by 2 and the denominator of the same fraction is multiplied by 2, the new fraction can be reduced to $\frac{1}{2}$ to its lowest term. The sum of the numerator and denominator of the original fraction can be :
(a) 13
(b) 45
(c) 16
(d) any even integer greater than 3

9. In the given expression $pq = p - q + 9$; q is a fraction and p is any positive integer. The value of p, which is inadmissible is :
(a) 5 (b) 4
(c) 8 (d) 7

10. The digits of a three digit number are in G.P. when the digits of this number are reversed and this resultant number is subtracted from the original number the difference comes out to be 792. The actual number is :
(a) 842 (b) 961
(c) 421 (d) 931

11. How many even integers n; $13 \le n \le 313$ are of the form of $3k + 4$, where k is any natural number?
(a) 101 (b) 51
(c) 50 (d) none of these

12. In the above question the number of values of n which are odd :
(a) 10 (b) 51
(c) 32 (d) none of a, b, c

13. If a and b are two odd distinct prime numbers and if $a > b$ then $a^2 - b^2$ can never be divided by :
(a) 13 (b) 11
(c) 17 (d) none of these

14. If $P = (101)^{100}$ and $Q = (100)^{101}$, then the correct relation is :
(a) $P > Q$ (b) $P < Q$
(c) $P = Q$ (d) $P = \frac{11}{10}Q$

15. If $k^2 - 25$ is an odd integer then which one of the following values gives the even number?
(a) $k^{(2k-1)}$ (b) $(3k - 3)(2k - 2)$
(c) $(k + 5)(k - 5)$ (d) any two of these

16. $(a + 1)(b - 1) = 625$; $(a \ne b) \in I^+$ then the value of $(a + b)$ is :
(a) $a + b \ge 25$ (b) $a + b \ge 50$
(c) $a + b = 24$ (d) $a + b = 26$

17. If $p + \frac{1}{p} = q$, then for $p > 0$:
(a) $q = 0$ (b) $-2 < q < 2$
(c) $q \ge 2$ (d) none of a, b, c

18. If $a^b = b^a$; $(a \ne b) > 1$, then the value of $(a + b)$ is :
(a) 5 (b) 6
(c) 7 (d) does not exist

19. If $m^n - n^m = (m + n)$; $(m, n) \in$ prime numbers, then what can be said about m and n :
(a) m, n are only even integers
(b) m, n are only odd integers
(c) m is even and n is odd
(d) none of these

20. There is unique 3 digit number which is cube of a natural number, if we shift the position of the digits of this number. The new number also becomes the cube of another number. The number is :
(a) 343 (b) 729
(c) 125 (d) does not exist

21. The given expression $n^4 - n^2$ is divisible by for $n \in I^+$ and $n > 2$:
(a) 4 (b) 8
(c) 12 (d) all of these

22. If a, b represents two distinct positive integers and thus $(aa)^b = abba$ is a valid relation. Then the value of $(a^b . b^a + b^a . a^b)$ is :
(a) 4 (b) 6
(c) 13 (d) none of these

23. At our training institute we have p-1, p-2, p-3 and p-4 processors in the ratio of $\frac{1}{6}, \frac{1}{5}, \frac{1}{3}$ and $\frac{1}{2}$ respectively. Minimum number of processors in our institute is :
(a) 16 (b) 30
(c) 32 (d) 36

Scanned by CamScanner

yoursmahboob.wordpress.com

24. $(392)^n - (392)^{n-1}$ is not divisible by :
(a) 56 (b) 23
(c) 13 (d) 17

25. Mr. Chaalu while travelling by Ferry Queen has travelled the distance one kilometre more, than the fare he paid per km. Initially he had total amount of Rs. 350 in his wallet. Now he is only left with the minimum sum of (if all the distance travelled by him is in integers) :
(a) Rs. 26 (b) Rs. 8
(c) Rs. 19 (d) can't be determined

26. A person starts typing the numbers from 1 to 1999. He press the keys total `n' number of times. The value of n is :
(a) 6889 (b) 1000
(c) 2888 (d) none of these

27. The remainder when $(20)^{23}$ is divided by 17 is :
(a) 11 (b) 3
(c) 6 (d) can't be determined

28. Let p be a prime number such that $3 < p < 50$, then $p^2 - 1$ is :
(a) always divisible by 8 (b) always divisible by 24
(c) always divisible by 12 (d) all of a, b, c

29. If p be a prime number, then $p^2 + 1$ can not have its unit digit is :
(a) 3 (b) 9
(c) 7 (d) all of these

30. The number of numbers from 1 to 200 which are divisible by neither 3 nor 7 is :
(a) 115 (b) 106
(c) 103 (d) less than 100

31. p is a prime number and $(p^2 + 3)$ is also a prime no. The no. of numbers that p can assume is :
(a) 3 (b) 2
(c) 1 (d) can't say

32. In a bangle shop, the shopkeeper displays the bangles in the form of a square then he is left with 38 bangles with him. If he wanted to increase the size of square by one unit each side of the square he found that 25 bangles fall short of in completing the square. The actual number of bangles which he had with him in the shop was :
(a) 1690 (b) 999
(c) 538 (d) can't be determined

33. If a and b are two integers which are multiples of 5 which of the following is not necessarily true :
(a) $a - b$ is divisible by 5
(b) $a + b$ is divisible by 10
(c) $a^2 - b^2$ is divisible by 5
(d) none of the above

34. What are the values of the digits a and b, respectively, in the number a 5523879 b, if it is divisible by both a and b is :
(a) (8, 6) (b) (7, 2)
(c) (8, 1) (d) not unique

35. A six digit number $abcabc$ such that $a, b, c \in N$, then which is the most correct statement is :
(a) It is divisible by 91
(b) It can be divided by 143
(c) It is divisible by 6
(d) Only a and b are correct

36. Two numbers a and b are such that one is odd and the other is even. Which statement is necessarily true?
(A) a^{2b} is even (b) $(a + b)$ is even
(C) $a^b \times b^a$ is even (d) $a^2 - b^2$ is even

37. A gardener plants his garden with 5550 trees and arranged them so that there is one plant more per row as there are rows then number of trees in a row is :
(a) 56 (b) 74
(c) 76 (d) 75

38. The value of 'a' when $3^a = 9^b$ and $4^{(a+b+2)b} = 16^{ab}$ is :
(a) 2 (b) 1
(c) 4 (d) none of these

39. The number of two digit prime numbers which remain prime even on inverting the position of its digits is :
(a) 4 (b) 5
(c) 9 (d) 10

40. Half way through the journey from Delhi to Lahore Atalji began to look out of the window of the Samjhauta Express and continued it until the distance which was remained to cover was half of what he has covered. Now at this time how much distance he has to cover?
(a) $\frac{2}{2}$ (b) $\frac{1}{4}$
(c) $\frac{1}{3}$ (d) $\frac{1}{6}$

41. Some times ago the height of my son was 90 cm at the end of 1996. When I have observed that his height is increasing equally every year. After seven years in the last month of 2003. I have found that his height was $\frac{1}{9}$th more than that at the end of 2002. Can you find the height of my son at the end of 2008?
(a) 360 cm (b) 450 cm
(c) 250 cm (d) 270 cm

42. Chris widener had a servant who was determined to be paid \$ 250, a wrist watch and a ration for whole year? But after 9 months Widener migrated to India and he has just paid him \$ 270 and the ration for the 9 months. What is the cost of the wrist watch?
(a) \$ 20 (b) \$ 120
(c) \$ 110 (d) data insufficient

43. The sum of the squares of a two digit number is 10. If we add 18 to this number we get another number consisting of the same digits written in reverse order. The original number is :
(a) 10 (b) 46
(c) 13 (d) none of (a), (b), (c)

44. A two digit number ab is added to another number ba, which is obtained by reversing the digits then we get a three digit number. Thus $a + b$ equals to :
(a) at least 18 (b) $2ab$
(c) $2(a + b)$ (d) $(a + b) \geq 10$

45. At Wharton School every student is awarded with the grades A, B or C only. 57.1428571428 ...% students obtained 'A' grade while 26.4444...% students obtained 'B' grade. If there are less than 3500 students then the maximum number of students obtained the grade 'C' while no one is declared fail.

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 517 (b) 533
(c) 428 (d) can't be determined

46. Which one of the following is wrong?
(a) The sum of two even numbers, each raised to an odd power is even.
(b) The sum of two odd numbers, each raised to an odd power is even
(c) The remainder when dividing an even number by an odd number is even or zero.
(d) The remainder when dividing an odd number by an even number is always odd.

47. The sum of the expression $551 + 552 + 553 + \ldots + 560$ is :
(a) 3450 (b) 5555
(c) 555 (d) 6060

48. Find x, if $x^2 + x = x^3 - x$:
(a) 1 (b) 2
(c) 3 (d) 4

49. In the above problem the number of values of x is :
(a) 1 (b) 2
(c) 3 (d) 4

50. How many 3's you have to write down while writing the numbers from 3301 to 3401?
(a) 220 (b) 218
(c) 198 (d) none of these

51. $(2^{19} + 1)$ is divisible by :
(a) 3 (b) 4
(c) 6 (d) 3 & 6 both

52. Which of these is a prime number 3123, 219, 573, 467 :
(a) 219 (b) 467
(c) 573 (d) 3123

53. Which is not a prime number?
(a) 97 (b) 1001
(c) 127 (d) 101

54. What is the least number which must be multiplied to 5400 to get a perfect square?
(a) 2 (b) 3
(c) 6 (d) 10

55. For every p, q positive integers at $x = 0$ or $x = 1$, the valid relation can be :
(a) $p^x q^{(1-x)} = qx + p(1-x)$
(b) $p^x q^{(1-x)} = px + q(1-x)$
(c) $p^x q^{(1-x)} = p^{(1-x)} qx$
(d) either (b) or (c)

56. How many times does the sum of 3780 and 2835 contains their difference?
(a) 4 (b) 5
(c) 6 (d) 7

57. The expression $(x + y)^{-1} \cdot (x^{-1} + y^{-1})$ is equivalent to :
(a) 1 (b) $(xy)^{-1}$
(c) x^y (d) $xy^{-1} + x^{-1}y$

58. For any odd prime number p there exists a positive integer k where $1 < k < p$, such that the remainder of $\frac{k^2}{p}$ is 1. Then the number of positive integers k is :
(a) 0 (b) 1
(c) $p - 1$ (d) can't be determined

59. At Lucknow Public School $\frac{1}{9}$ students were absent in an exam and only $\frac{19}{24}$ of those who appeared for the exam passed it. Now we know that 500 students failed in the exam. Total number of students registered for the exam :
(a) 2000 (b) 2400
(c) 2700 (d) 3000

60. If, $0 < m < n < 1$. Then the expression $km < kn$ is true if :
(a) $k < 0$ (b) $k > 0$
(c) $k = 1$ only (d) all of a, b, c

61. If $a = 0.1818181818 \ldots$ and $b = 0.3030030003 \ldots$ then $(a + b)$ is :
(a) a rational no. (b) perfect number
(c) an irrational no. (d) both (b) and (c)

62. Half life of a substance is defined as the time period in which a substance becomes just half of it. If it is known that the half life of a substance "DECAY" is 1122 years, then after 4488 years, 80 gm of "DECAY" becomes.
(a) 4 gm (b) 20 gm
(c) 5 gm (d) none of these

63. In the examination of CBSE, a candidate must get $\frac{2}{5}$th marks to pass, out of total marks. Vinod appeared in the same exam and got 210 marks and still failed by 40 marks. The maximum marks which a candidate can get is :
(a) 500 (b) 625
(c) 390 (d) can't be determined

64. Sunny gets $3\frac{1}{2}$ times as many marks in 'QA' as in 'English'. If his total combined marks in both the papers is 90. His marks in 'QA' is :
(a) 50 (b) 60
(c) 70 (d) none of these

65. I know a two digit number, but when its digits swap their places and we get another two digit number But when these two digit numbers are added, it amounts to 99. Further if I just consider the difference between these numbers, it comes out to be 45. What is the number which I know?
(a) 27 (b) 38
(c) 72 (d) data insufficient

66. Which of the following is/are correct?
(i) $a^{x+y} = ax + ay$ (ii) $(a^x)^y = ya^x$
(iii) $a(x \cdot y) = ax \cdot ay$ (iv) $\frac{a^x}{a^y} = a^{x-y}$
(a) (i) only (b) (ii) & (iii) only
(c) (iv) only (d) none of these

67. In the MOCK CAT at 'i4 IIM' a student while doing the multiplication he reversed the digits (*i.e.*, tens to unit and unit to tens) of both the numbers respectively, still his answer was correct. Such a pair of numbers is :
(a) 16, 32 (b) 28, 42
(c) 31, 23 (d) 12, 63

Scanned by CamScanner

yoursmanboob.wordpress.com

68. The relation $\frac{p}{(p+1)} > 1$ is valid when :

(a) $p \geq -1$ (b) $p > -1$
(c) $p < -1$ (d) $-1 < p < 0$

69. A number when divided by 14 leaves a remainder of 8, but when the same number is divided by 7, it will leave the remainder :

(a) 3 (b) 2
(c) 1 (d) can't be determined

70. The unit digit of $(316)^{3^{4n}} + 1$ is :

(a) 4 (b) 5
(c) 1 (d) 7

71. The sum of two numbers is 18. The greatest product of these two numbers can be :

(a) 17 (b) 81
(c) 80 (d) can't be determined

72. Largest four digit number which when divided by 15 leaves a remainder of 12 and if the same number is divided by 8 it leaves the remainder 5. Such a greatest possible number is :

(a) 9963 (b) 9957
(c) 9945 (d) 9999

73. In a mobileshop $\frac{7}{12}$ mobiles are imported and rest are manufactured in India. Further $\frac{1}{5}$th Indian mobiles are coloured while $\frac{5}{7}$th imported mobile are black and white. If there are total 150 coloured mobile in his shop, then total number of mobile phones in his shop is :

(a) 500 (b) 600
(c) 800 (d) data insufficient

74. In a call centre at New Delhi, it is observed that it gets a call at a interval of every 10 minutes from California, at every 12 minutes from Texas, at the interval of 20 minutes from Washington DC and after every 25 minutes it gets the call from London. If in the early morning at 5 : 00 a.m. it has recieved the calls simultaneously from all the four destinations, then at which time it will receive the calls at a time from all the places on the same day?

(a) 10 : 00 a.m. (b) 3 : 00 a.m.
(c) 5 : 00 p.m. (d) both (a) and (b)

75. The H.C.F. and L.C.M. of 2^4, 8^2, 16^2, 20^3 are :

(a) 2^3; 32000 (b) 2^4; 32000
(c) 2^4; 25600 (d) 2^2; 3200

76. When we divide 15192327 by 99 the remainder will be :

(a) 98 (b) 84
(c) 30 (d) none of these

77. The number of numbers lying between 1 and 200 which are divisible by either of 2, 3 or 5 is :

(a) 146 (b) 145
(c) 158 (d) none of these

78. If xAy means $x + y$, xSy means $x - y$, xMy means $x \times y$ and xDy means $x \div y$. Then the value of $4D2S3M6A12$ is :

(a) -4 (b) 18
(c) $\frac{-47}{4}$ (d) none of these

79. The L.C.M. of two numbers is 1020 and their H.C.F. is 34 the possible pair of numbers is :

(a) 255, 34 (b) 102, 204
(c) 204, 170 (d) none of these

80. The sum of 100 terms of the series

$1 - 3 + 5 - 7 + 9 - 11 + 13 - 15 + \ldots$ is :

(a) 100 (b) 50
(c) 200 (d) none of these

81. The value of $\left(1-\frac{1}{2}\right)\left(1-\frac{1}{3}\right)\left(1-\frac{1}{4}\right)\left(1-\frac{1}{5}\right)\ldots\left(1-\frac{1}{n}\right)$ is :

(a) 1 (b) $\left(1-\frac{1}{n}\right)^n$
(c) $\frac{1}{n}$ (d) can't be determined

82. The minimum and maximum possible values of $\frac{x}{y}$, where $2 \leq x \leq 8$ and $16 \leq y \leq 32$ respectively are :

(a) $\frac{1}{8}, \frac{1}{4}$ (b) $\frac{1}{16}, \frac{1}{2}$
(c) 2, 16 (d) not unique

83. A rectangular floor in my office has its area equal to 56 m^2. The minimum number of tiles required, if all the tiles are in square shape is :

(a) 15 (b) 9
(c) 14 (d) can't be determined

84. A string of length 221 metre is cut into two parts such that one part is $\frac{9}{4}$th as long as the rest of the string, then the difference between the larger piece and the shorter piece is :

(a) 58 m (b) 53 m
(c) 85 m (d) none of these

85. Total number of prime numbers between 1 and 200 is :

(a) 34 (b) 46
(c) 56 (d) 71

86. What is the remainder of $\frac{6^{36}}{215}$?

(a) 0 (b) 1
(c) 2 (d) none of these

87. The remainder when $(12^{13} + 23^{13})$ is divided by 11 :

(a) 0 (b) 1
(c) 2 (d) none of these

88. The four digit smallest positive number which when divided by 4, 5, 6 or 7, it leaves always the remainder as 3 :

(a) 1000 (b) 1257
(c) 1263 (d) 1683

89. Which one of the following is correct?

(i) $13^{31} > 31^{13}$ (ii) $10^{100} < 100^{10}$
(iii) $2^{32} < 32^2$

(a) (i) and (ii) (b) (i) and (iii)
(c) (ii) and (iii) (d) (i) only

90. If $n_1, n_2, n_3 \ldots, n_k$ are such that, out of these k elements $\frac{k}{2}$ elements are even and rest are odd numbers. Which is necessarily even?

(a) $(n_1 + 2n_2 + 3n_3 + 4n_4 + \ldots + k.n_k)$

Scanned by CamScanner

yoursmahboob.wordpress.com

(b) $n_1 \cdot n_2 \cdot n_3 \ldots n_{\left(\frac{k}{2}+1\right)}$
(c) $(n_1 + n_3 + n_5 + n_7 + \ldots + n_{k-1})$
(d) $n_2 + n_4 + n_6 + \ldots + n_k$

91. The H.C.F. of two numbers is 43 and their sum is 430. Total number of distinct pairs of two such numbers is :
(a) 5 (b) 2
(c) 6 (d) data insufficient

92. $2^{73} - 2^{72} - 2^{71}$ is same as :
(a) 2^{72} (b) 2^{71}
(c) 2^{70} (d) none of these

93. $N = 55^3 + 17^3 - 72^3$, then N is divisible by :
(a) 3 & 17 (b) 40 & 11
(c) 11 & 15 (d) all of these

94. $abcde$ is a five digit number when multiplied by 13 it gives a number, purely formed by the digit 9. Then the value of $a + b + c + d + e$ is :
(a) divisible by 8 (b) equal to 27
(c) divisible by 11 (d) all of these

95. The sum of 3 consecutive even numbers is always divisible by :
(a) 24 (b) 48
(c) 10 (d) none of these

96. The remainder obtained when $23^3 + 31^3$ is divided by 54 :
(a) 0 (b) 1
(c) 3 (d) can't be determined

97. The largest possible number by which the product of any five consecutive natural numbers can be divided :
(a) 120 (b) 160
(c) 100 (d) none of these

98. If $x^2 + y^2 = 25$ and $xy = 12$, then the value of $x^{-1} + y^{-1}$ is :
(a) $\frac{12}{5}$ (b) $\frac{7}{12}$
(c) $\frac{-7}{12}$ (d) both (b) and (c)

99. The remainder when $75^{75^{75}}$ is divided by 37 :
(a) 0 (b) 1
(c) 5 (d) 7

100. Let p be a prime number stricly greater than 3. Then $p^2 + 17$ will leave remainder k, when divided by 12, the value of k is :
(a) 1 (b) 5
(c) 6 (d) none of these

101. The unit digit of $(12345k)^{72}$ is 6. The value of k is :
(a) 6 (b) 8
(c) 2 (d) all of these

102. What is the least number which must be subtracted from 369 to make it a perfect cube?
(a) 8 (b) 26
(c) 2 (d) 25

103. The product of two consecutive even numbers is 624, then one of the numbers is :
(a) 13 (b) 25
(c) 26 (d) 28

104. What is the remainder when $1719 \times 1715 \times 1713$ is divided by 17?
(a) 1 (b) 16
(c) 3 (d) none of these

105. The quotient when 12.5 is divided by $\frac{1}{6}$ is :
(a) 75 (b) 25
(c) 2.48 (d) none of these

106. Kavita had to do a multiplication. Instead of taking 23 as a multiplicant she took 32 and got the result increased by 315. The original product was :
(a) 135 (b) 805
(c) 775 (d) data insufficient

107. A fraction in its lowest form is such that when it is squared and then its numerator is reduced by $\frac{1}{3}$rd and denominator is reduced to $\frac{1}{5}$th, it results as twice of the original fraction the sum of numerator and denominator can be :
(a) 7 (b) 8
(c) 9 (d) 17

108. The largest number which will divide the numbers 104, 221 and 377 leaving the same remainder in each case is :
(a) 56 (b) 13
(c) 39 (d) it does not exist

109. If $(ab^2)^{1/3} = 125$ where $a > b > 1$ and $(a, b^2) \in N$ then the correct relation is :
(a) $a = b$ (b) $a = b^4$
(c) $a^{3/2} = b^{2/3}$ (d) none of these

110. If a five digit number "m21n2" is divisible by 24 then the maximum number of possible combinations of m and n :
(a) 4 (b) 9
(c) 16 (d) 10

111. If a fraction is divided by its reciprocal and then multiplied by itself then the fraction becomes $\frac{512}{125}$. The difference between the actual fraction and its reciprocal fraction is :
(a) $\frac{29}{30}$ (b) $\frac{39}{40}$
(c) data insufficient (d) none of these

112. A perfect square less than 500 is such that when a prime number p_1 is subtracted or another prime number p_2 is added to it in both cases it becomes the perfect square when $p_2 = 2 + p_1$. Then the $p_1 + p_2$ is necessarily divisible by :
(a) 8 (b) 11
(c) 4 (d) all of these

113. If $(11)^a = (19)^b = (209)^c$ then the correct relation is :
(a) $ab = (c)^{ab}$ (b) $a^b = c$
(c) $ab = c(a + b)$ (d) none of these

114. The remainder when $(2^{54} - 1)$ is divided by 9 is :
(a) 0 (b) 8
(c) 7 (d) none of these

115. A number $1 < N < 100$ is such that it is a perfect square and perfect cube both, then the sum of digits of N is :
(a) 1 (b) 10
(c) 20 (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

116. The product of the digits of a three digit number which is a perfect square and perfect cube both is :
(a) 126 (b) 256
(c) 18 (d) none of these

117. A natural number N is such that $N = a^2 = b^4 = c^8$, where a, b, c are distinct positive integers, then the least possible value of N is :
(a) 729 (b) 1000
(c) 256 (d) none of these

118. The possible value of $|x| + |x - 1| = 2$ is :
(a) $\left\{\frac{3}{2}, -\frac{1}{2}\right\}$ (b) $\left\{\frac{3}{2}, \frac{1}{2}\right\}$
(c) $\left\{\frac{2}{3}, -\frac{1}{2}\right\}$ (d) none of these

119. If $(pqr)^2 = (ijk\ pqr)$, where $i, j, k, p, q, r \in W$, and pqr and $ijkpqr$ are three digits and 6 digits numbers respectively. Then the value of $i \times j \times k \times p \times q \times r$ is :
(a) 0 (b) 720
(c) can't say (d) none of these

120. $3^{6n} + 4^{6n}$ is necessarily divisible by 25 when :
(a) n is an even integer (b) n is an odd integer
(c) only n is a prime (d) $n \geq 6; n \in I^+$

121. The number of zeros at the end of 100! is :
(a) $(100)^{100}$ (b) 100×10
(c) data insufficient (d) none of these

122. The greatest power of 3, when 41! is expressed in prime factors :
(a) 13 (b) 18
(c) can't be determined (d) none of these

123. A two digit number is such that it is the product of the two distinct perfect squares. The tens digit, unit digit and the sum of these two digits are in A.P. Further if we reverse the digits mutually, it increases by 27. The original number is :
(a) 72 (b) 19
(c) 36 (d) none of these

124. The value of the expression
$$7777 + 7777 \times 7777 \times (5 \div 77) \times (11 \div 35) :$$
(a) 1234321 (b) 12344321
(c) 7^{7777} (d) none of these

125. The sum and difference of a number with its reciprocal are $\frac{113}{56}$ and $\frac{15}{56}$ respectively, the number is :
(a) $\frac{11}{4}$ (b) $\frac{13}{6}$
(c) $\frac{14}{8}$ (d) $\frac{7}{8}$

126. If 4 is added to the numerator of a fraction, it becomes 1/3 and if 3 is added to the denominator of the same fraction it becomes 1/6 then the sum of the numerator and denominator is :
(a) 32 (b) 7
(c) 4 (d) 3

127. In an opera HOUSE, there are 7777 chairs to be placed, but the organiser of the event arranged all the chairs in such a way that there were as many columns as there were rows. So he had to remove minimum 'n' chairs from the total 7777 chairs. The minimum value of n is :
(a) 121 (b) 44
(c) 33 (d) 25

128. If $p^r \cdot p^{-1} \cdot p^s = (\sqrt{p^3})^2$ and $p^{3/2} \cdot p^r = p^s \cdot p^{-1/2}$ then the value of $(r + s)^{(r+s)}$ is :
(a) 27 (b) 64
(c) 4 (d) none of these

129. If $5^{-k} = \frac{1}{l}$, then the value of 5^{3k} is equal to :
(a) $\frac{1}{3l}$ (b) $3l$
(c) l^3 (d) data insufficient

130. $5^{x-1} + 5^x + 5^{x+1} = 775$ then the value of x for every positive integer x, is :
(a) 1 (b) 3
(c) 2 (d) can't be determined

131. If a, b are two perfect square digits and ab is a two digit perfect square number, such that $(a \times b) + (a + b) = ab$ then the value of $[ba - (b + a)]$ is :
(a) 27 (b) b^2
(c) 81 (d) either of b and c

132. The greatest possible number which can always divide the sum of the cubes of any three consecutive integer is :
(a) 3 (b) 4
(c) 9 (d) 11

133. The least possible divisor of 25930800 by which we divide this number, we get the quotient as a perfect square :
(a) 2 (b) 3
(c) 5 (d) can't be determined

134. Arun and Prabhat have some books with them. Once Prabhat said to Arun that if Arun gives 3 books to Prabhat then Arun will have only $\frac{1}{2}$ of the books that Prabhat will have with him. Then Arun asked frankly that if Prabhat gives him only two books (to Arun), then Prabhat will have as many books as Arun will have. The total number of books that Arun and Prabhat have with them is :
(a) 25 (b) 56
(c) 30 (d) can't be determined

135. The number of co-primes of 200 lying between 1 to 100 is :
(a) 100 (b) 40
(c) 50 (d) none of these

136. A soda water bottle is exactly filled with coke weighs 1600 gm but when it is $\frac{1}{3}$rd filled it weighs only 900 gm. The weight of the empty bottle is :
(a) 650 (b) 1100
(c) 550 (d) data insufficient

137. If ab, cd, ba and dc are two digit numbers then the maximum value of $(ab \times cd) - (ba \times dc)$ is, where a, b, c, d are distinct non-zero integers :
(a) 7938 (b) 7128
(c) 6930 (d) none of these

Scanned by CamScanner

yourmathbook.wordpress.com

138. In how many ways 12600 can be expressed as a product of two factors which are relatively prime is :
(a) 12 (b) 4
(c) 8 (d) 72

139. The solution set of the expression $\frac{1}{(1+p)^p} = 1$ is :
(a) $[-1, 2]$ (b) $(0, 1)$
(c) $\{-2, 0\}$ (d) $\{-1, 1\}$

140. The number of zeros at the end of $(2^{123} - 2^{122} - 2^{121}) \times (3^{234} - 3^{233} - 3^{232})$:
(a) 0 (b) 1
(c) 121 (d) none of these

LEVEL 2

1. In Mahabalipuram Temple there are some magical bells which tolls 18 times in a day, simulateneously. But every bell tolls at a different interval of time, but not in fraction of minutes. The maximum number of bells in the temple can be :
(a) 18 (b) 10
(c) 24 (d) 6

2. Three numbers p, q, r are such that $p^q = q^r$, where $p, q, r > 1$ then the correct relation between q and r is :
(a) $\frac{q}{r} = 1$ (b) $q < r$
(c) $q > r$ (d) indeterminable

3. $p^q - q^r = (p+q)^{r-q}$, where $1 < q < r < p < 10$ then the value of $p + q + r$ is :
(a) 31 (b) 21
(c) 15 (d) 12

4. If $a^2 + b^2 + c^2 + d^2 = 1$, then the maximum value of $a.b.c.d$ is :
(a) 1 (b) 2
(c) $\frac{1}{16}$ (d) data insufficient

5. The value of n in the expression $n^2 - 2(n!) + n = 0$ for every $n \in N$ is :
(a) 6 (b) 1
(c) 3 (d) both b, c are true

6. If m, n, p are in A.P. and $m^n = p^m = n!$; $m, n, p \in N$, then the value of $m.n.p$ is, where $2 < m, n < p < 10$:
(a) 136 (b) 72
(c) 162 (d) none of these

7. The value of $(n!)^n$ if $n + (n-1) + (n-2) = n(n-1)(n-2)$, where $n^3 > 9$, a positive number :
(a) 27 (b) 216
(c) 256 (d) 331776

8. If $(n)^3 - (n)^2 - n = n$, then the number of values of n that satisfy the given relation is :
(a) 1 (b) 2
(c) 3 (d) can't be determined

9. If $k = (k_1, k_2, k_3, \ldots, k_n) \in I$ and
$k_1k_2k_3 + k_2k_3k_4 + k_3k_4k_5 + \ldots + k_{(n-2)}\,k_{(n-1)}\,k_n = 0$
Then minimum how many entities *i.e.* k_i $(i = 1, 2, 3, \ldots)$ must be zero? If there are total 12 terms in the above expression :
(a) 3 (b) 4
(c) 6 (d) ${}^nC_3$

10. The given relation $n^{(n-1)} + n^{(n+1)} = (n^2+1)^2 - (n^2+1)$ is valid for every $n \in N$ if n equals to :
(a) 3 (b) 5
(c) 1 (d) both (a) and (c)

11. The smallest possible number that can be expressed as the sum of cube of two natural numbers in two different combinations.
(a) 1000 (b) 1728
(c) 1729 (d) none of these

12. $8^6 - 5^6$ is divisible by individually :
(a) 91 (b) 49
(c) 129 (d) all of these

13. Total number of factors of a number is 24 and the sum of its 3 prime factors out of four, is 25. The product of all 4 prime factors of this number is 1365. Then such a greatest possible number can be :
(a) 17745 (b) 28561
(c) 4095 (d) can't be determined

14. If p be any odd natural number, greater than 3 then which digit will never appear as the last digit in the product of $(p^2-1)(p^2+1)$ is :
(a) 9 and 7 (b) 5 and 3
(c) 1 and 5 (d) all of these

Directions for question number 15 to 18 : The relation $R(m, n)$ can be defined for every positive integer m, n as $R(m, n) = m \times (m+1) \times (m+2) \times (m+3) \times \ldots (m+n)$ and the relation $R(1, n)$ is equal to $n!$ or can be written as $R(n)$.

15. The value of $\frac{R(135)}{R(100, 35)}$ is :
(a) 99! (b) 100!
(c) 270 (d) none of these

16. The value of $R(17) . R(19, 62)$ is :
(a) $\frac{81!}{18}$ (b) $(81!) \times 18$
(c) 36! (d) $17 \times (19 + 62)$

17. The L.C.M. of $R(2, 995)$ and $R(996, 1)$ is :
(a) 1994 (b) 996!
(c) 997! (d) can't be determined

18. The H.C.F. of $R(139, 2)$ and $R(141)$:
(a) 141 (b) 2743860
(c) 32,16,839 (d) 19599

19. A six digit number of the form $abcabc$ is written where $a, b, c \in I^+$, then which statement is true about this number :
(a) it is always divisible by 7 and 11
(b) it is divisible by 143
(c) it is divisible by 1001
(d) all of (a), (b) and (c) are correct

Scanned by CamScanner

yoursmahboob.wordpress.com

20. How many natural numbers upto 1155 are divisible by either 5 or 7 but not by 11?
(a) 105 (b) 330
(c) 333 (d) none of these

21. The number of solution set (x, y) for the given equation $4x + 7y = 3$, such that $-99 \le x \le 99$ and $-100 \le y \le 100$, where $x, y \in I$:
(a) 14 (b) 29
(c) 15 (d) 30

22. When any two natural numbers N_1 and N_2, such that $N_2 = N_1 + 2$, are multiplied with each other, then which digit appears least time as a unit digit if $N_2 \le 1000$?
(a) 0 (b) 9
(c) 4 (d) both (a) and (c)

23. In the above problem (no. 22), if all such unit digits will be added the maximum sum can be :
(a) 4491 (b) 4500
(c) 3609 (d) 5400

24. A diamond expert cuts a huge cubical diamond into 960 identical diamond pieces in minimum number of 'n' cuts. If he wants to maximize the number of identical diamond pieces making same number of n cuts to it. So the maximum number of such diamond pieces are :
(a) 1000 (b) 1331
(c) 1200 (d) none of (a), (b), (c)

25. The sum of all the factors of 45000 which are exactly the multiples of 10 is :
(a) 152295 (b) 141960
(c) 600 (d) none of these

26. The unit digit of the expression
$(1!)^{1!} + (2!)^{2!} + (3!)^{3!} + \ldots + (100!)^{100!}$:
(a) 0 (b) 1
(c) 2 (d) 7

27. When $(1!)^{1!} + (2!)^{2!} + (3!)^{3!} + \ldots + (100!)^{100!}$ is divided by 5, the remainder obtained is :
(a) 2 (b) 0
(c) 4 (d) none of these

28. The digit at the tens place in the sum of the expression :
$(1!) + (2!)^2 + (3!)^3 + (4!)^4 + (5!)^5 + \ldots (111!)^{111}$ is :
(a) 0 (b) 1
(c) 8 (d) 9

29. A number is divided strictly into two unequal parts such that the difference of the squares of the two parts equals 50 times the difference between the two parts. The number is :
(a) 100 (b) 250
(c) 50 (d) can't be determined

30. A positive number p is such that $(p + 4)$ is divisible by 7. 'N' being a smallest possible number larger than first prime number, which can make $(p + N^2)$ divisible by 7. The value of N is :
(a) 3 (b) 9
(c) 5 (d) 7

31. Anjali and Bhagwat fired 45 shots each. Total 66 bullets hit the target and the remaining bullets missed it. How many times does the Anjali hit the target if it is known that the number of hits per one miss shown by the Anjali is twice that of Bhagwat?
(a) 30 (b) 36
(c) 40 (d) 35

32. The remainder when n is divided by 3 is 1 and the remainder when $(n + 1)$ is divided by 2 is 1. The remainder when $(n - 1)$ is divided by 6 is :
(a) 2 (b) 3
(c) 5 (d) none of (a), (b), (c)

33. The expression $2222^{7777} + 7777^{2222}$ is divisible by :
(a) 99 (b) 101
(c) 13 (d) any two of these

34. In a Business school we have found that every two student share the book of 'Organisational Behaviour' between them. Every 3 student shared among them the book of Financial Management and every four students used to share Operation Research's book from the library. But it is well known that there were only 91 books of the above mentioned topics. The number of students in the school was :
(a) 81 (b) 84
(c) 48 (d) can't be determined

35. After two successive rises, the salary of Eckhart Tolle, working in a BPO company became equal to $\frac{15}{8}$ times of his initial salary. By how much percent was the salary raised second time if the first time rise in salary was half of the rise in second time in percent?
(a) 82.5 % (b) 60 %
(c) 50 % (d) can't be determined

36. The number of digits in the product of $5^{72} \times 8^{27}$ is :
(a) 77 (b) 75
(c) 99 (d) none of (a), (b), (c)

37. A student of 5^{th} standard started writing down the counting numbers as 1, 2, 3, 4, ... and then he added all those numbers and got the result 500. But when I checked the result I have found that he had missed a number. What is the missing number?
(a) 25 (b) 32
(c) 30 (d) 28

38. A stairway of 20 ft height is such that each step account for half a foot upward and one foot forward. What distance will an ant travel if it starts from ground level to reach the top of the stairway?
(a) 59 (b) 60
(c) 58 (d) none of these

39. Paltry and Sundry, the two bird hunters went to woods. Paltry fires 5 shots when Sundry fires 7 shots. But Paltry kills 2 out of 5 while Sundry kills 3 out of 7. When Sundry has missed 32 shots, then how many birds has Paltry killed?
(a) 25 (b) 24
(c) 16 (d) 12

40. A cigarette pack is $\frac{5}{6}$th full of its capacity, then 5 cigarettes were taken out and 2 another cigarettes were put inside the

Scanned by CamScanner

yoursmahboob.wordpress.com

pack. Now it is $\frac{4}{5}$ full. How many cigarettes can this pack contain when it is full?

(a) 90 (b) 80
(c) 72 (d) can't be determined

41. Around a square table chairs are arranged in a sequence starting from one corner, numbered as 1, 2, 3, ... etc. The chair number 2 is opposite to chair number 14. So how many chairs are there in all?

(a) 10 (b) 20
(c) 14 (d) can't be determined

42. The value of y for which the expression $p = \frac{1}{(|y-1|-3)}$ becomes undefined :

(a) {2, 8} (b) {– 2, 4}
(c) {– 1, 3} (d) {1, 2}

43. What is the sum of the following series?

$$\frac{1}{1\times 2}+\frac{1}{2\times 3}+\frac{1}{3\times 4}+\ldots+\frac{1}{100\times 101}$$

(a) $\frac{100}{101}$ (b) $\frac{1}{101}$
(c) $\frac{101}{100}$ (d) 101!

44. If Rupert has 4 more coins than Laxmi, Laxmi has 1 more coin than Bill and Bill has 1 more coin than Hawkins. Finally Hawkins has 4 more coins than Ajim. Then minimum number of coins that must be transfered if all of them wish to have an equal number of coins :

(a) 5 (b) 6
(c) 7 (d) none of these

45. If $f(x) = \frac{7}{x^7}+\frac{5}{x^5}+\frac{3}{x^3}+1+3x^3+5x^5+7x^7$. Now, if the value of $f(2)$ is 1081.58 then the value of $f\left(\frac{1}{2}\right)$ is :

(a) 540.79 (b) $\frac{1}{1081.58}$
(c) 1081.58 (d) 367.42

46. The last digit of the expression

$4\times 9^2\times 4^3\times 9^4\times 4^5\times 9^6\times\ldots\times 4^{99}\times 9^{100}$ is :

(a) 4 (b) 6
(c) 9 (d) 1

47. The last digit of the expression

$4+9^2+4^3+9^4+4^5+9^6+\ldots+4^{99}+9^{100}$ is :

(a) 0 (b) 3
(c) 5 (d) none of these

48. p, q, r are the decimal numbers (e.g., 5.8) and $[x]$ means the greatest integer less than or equal to x and $A = [p+q+r]$ and $B = [p]+[q]+[r]$, then the maximum value of $A - B$ is :

(a) 0 (b) 2
(c) 2.99 (d) none of these

49. If p, q, r be integers such that $p^2 = q^2.r$ then :

(a) p is an even number (b) q is an even number
(c) r is an even number (d) r is a perfect square

50. The sum of n positive integers $k_1, k_2, k_3, \ldots, k_n$ is an even number, then number of odd integers involve in the expression is :

(a) odd (b) even
(c) $(n-1)$ (d) none of these

51. If $1+2+3+\ldots+k = N^2$ and N is less than 100 then the value of k can be, where $N \in$ Natural Numbers :

(a) 8 (b) 1 and 49
(c) 8 and 36 (d) both (a) and (b)

52. If a and b be two co-prime numbers, then $(a+b)$ and $(a-b)$:

(a) are always co-primes
(b) have atleast one common factor other than 1
(c) if $(a+b)$ or $(a-b)$ is not a prime number, then their HCF is 2
(d) none of the above

53. The G.M. of two positive numbers is 35 and the A.M. of the same number is $43\frac{3}{4}$, then the greater of these numbers is :

(a) 28 (b) 30
(c) 70 (d) 35

54. When a number is divided by 1, 2, 3, 4, 5, ..., $(n-1)$, n individually it leaves 0, 1, 2, 3, 4, ..., $(n-2)$, $(n-1)$ respective remainders, then this number can be :

(i) $n!$ (ii) $(n!-1)$
(iii) [(L.C.M. of 1, 2, 3, ..., n) – 1]

(a) both (i) and (ii) (b) both (ii) and (iii)
(c) only (iii) (d) only (ii)

55. Four consecutive even numbers are such that 3 times of the first number is equal to twice of the third number. The sum of all the four numbers is :

(a) 20 (b) 40
(c) 44 (d) can't be determined

56. In the morning batch at "i4IIM" we have observed that when five-five students took seat on a bench, 4 students remained unseated. But when eleven students took seat per bench, 4 benches remained vaccant. The number of students in our morning batch were?

(a) 55 (b) 48
(c) 26 (d) none of these

57. When $\left(\frac{m}{n}\right) = 25\left(\frac{n}{m}\right)$, then the value of $m : n$ is :

(a) 1/25 (b) 5
(c) 1/5 (d) 2.5

58. Which one of the following is greatest one?

(a) 3^{3322} (b) 33^{322}
(c) 333^{22} (d) 22^{333}

59. The product of any two integers is 25, then the minimum possible sum is :

(a) 5 (b) 10
(c) 26 (d) none of these

60. If $4 \le p \le 5$ and $-10 \le q \le -9$, then the least value is given by the expression :

(a) $p.q$ (b) pq^6
(c) p^6q (d) $(pq)^5$

Scanned by CamScanner

yoursmahboob.wordpress.com

61. The remainder obtained when $1! + 2! + 3! + ... + 77!$ is divided by 7 is :
(a) 0 (b) 5
(c) 4 (d) can't be determined

62. If $(a, n) \in I^+$ and $(a, n) > 1$, then the remainder when $[(a+1)^{2n-1} - 1]$ is divided by $(a-1)$ is :
(a) 1 (b) $a - 1$
(c) n (d) none of these

63. A typist starts to type the serial numbers of candidates in a list, upto 500. Minimum how many times he has to press the keys of numerals only?
(a) 1389 (b) less than 1000
(c) 1392 (d) can't say

64. If a, b, c, d, e, f are sequentially the terms of an A.P. belong to set $\{1, 2, 3, ..., 9\}$ where all the terms $a, b, c, ...$ are in increasing order, then the last digit of $a^b \times c^d \times e^f$ is :
(a) 5 (b) 2
(c) 7 (d) either of (a) and (b)

65. Total number of factors of a greatest possible number which when divides 1313 and 621, the respective remainders obtained are 17 and 9 :
(a) 9 (b) 10
(c) 11 (d) can't be determined

66. The set of values of x for which $|(x-5)x| > 0$ is :
(a) all real numbers (b) $R - \{0\}$
(c) $R - \{0, 5\}$ (d) $R - (0, 5)$

67. The sum of four prime numbers of two digits is 204. The sum of the first and last *i.e.* $(p_1 + p_4)$ is same as the sum of second number p_2 and third number p_3 (*i.e.* $p_2 + p_3$). Again $p_3 - p_2 = 2(p_2 - p_1) = 2(p_4 - p_3)$. The average number of all the four numbers is not a prime number, but a product of two prime numbers one of these prime numbers (out of four) is :
(a) 23 (b) 89
(c) 71 (d) can't be determined

68. Jai Bhan wanted to sell his mobilephone consists of the instrument and a SIM card, but Praveen who intended to buy it, asked the price of SIM card only? Jai Bhan told him that the price of the SIM card is Rs. 4000 less than the price of the instrument but if he wished to buy the complete set he had to pay Rs. 5000 only. The price of the instrument was :
(a) 5500 (b) 2500
(c) 4500 (d) can't be determined

69. If $|x + y| = |x - y|$ then the number of ordered pairs of (x, y) which satisfy the given condition is :
(a) 1 (b) 4
(c) infinite (d) none of these

70. If $292k + 7 = 23l$, where $(k, l) \in I$, then the value of l is :
(a) 23 (b) 31
(c) does not exist (d) none of these

71. If $ab + 4 = cd$ and $ba + 40 = dc$, where ab, cd, ba and dc are the two digit prime numbers. Further b and d are the prime number digits and a, c are neither prime nor composite. The value of $\frac{(ab + ba)}{(cd + dc)}$ is :
(a) 1 (b) $\frac{1}{2}$
(c) 2 (d) can't be determined

72. A man sells chocolates which are in the boxes. Only either full box or half a box of chocolates can be purchased from him. A customer comes and buys half the number of boxes which the seller had plus half a box more. A second customer comes and purchases half the remaining number of boxes plus half a box. After this the seller is left with no chocolate boxes. How many chocolate boxes the seller had initially?
(a) 2 (b) 3
(c) 4 (d) 3.5

73. If $n^2 = 123454321$, then the value of n is :
(a) 1001 (b) not a natural number
(c) 111, 111 (d) none of these

74. $1^2 - 2^2 + 3^2 - 4^2 + ... - 198^2 + 199^2$:
(a) 19900 (b) 12321
(c) 19998 (d) none of these

75. The quotient when L.C.M. is divided by the H.C.F. of a G.P. with first term 'a' and common ratio 'r' is :
(a) r^{n-1} (b) r^n
(c) $a^{-1}r^{n-2}$ (d) $(r^n - 1)$

76. Once I met two persons of the same parents namely Ashmit and Amisha. Mean while Ashmit told me that he has twice the number of sisters as the number of brothers. Further Amisha told me that she has twice the number of brothers as the number of sisters. Actually it was very confusing for me, so do you know that how many brothers and sisters are in their family?
(a) 4 (b) 5
(c) 6 (d) can't be determined

77. If $p < q$, then $p @ q = p \# q$ else $p @ q = q \# p$ where $a \# b = \frac{a}{b}$. Then the value of $(4 @ 5) @ (6 @ 5)$ is :
(a) $\frac{24}{25}$ (b) $\frac{2}{3}$
(c) 3/4 (d) none of these

78. A six digit number is such that every alternate digit is a prime digit and the three leftmost digit forms a G.P. while last three digits (*i.e.* Hundreds, tens and unit) form an A.P. If it is expressed as $pqrstu$, where $p + q + r = u$, $q + r = t$, $p + r = s$, $\frac{r}{t} = \frac{2}{3}$ and $p \neq q \neq r \neq s \neq t \neq u$. Then the sum of all the digits must be :
(a) 25 (b) 16
(c) 21 (d) can't be determined

79. Total number of digits in the product of $(4)^{1111} \times (5)^{2222}$ is :
(a) 3333 (b) 2223
(c) 2222 (d) can't be determined

80. If $p = N + 5$ when N is the product of any three consecutive positive integer. Then :
(a) p is prime (b) p is odd
(c) p is divisible by 6 (d) either of (b), (c)

Scanned by CamScanner

yoursmahboob.wordpress.com

81. If $\frac{p}{q}$ and $\frac{r}{s}$ are two rational numbers then the relation $\left|\frac{p}{q}\right| < \left|\frac{r}{s}\right|$ is :
(a) always true (b) always false
(c) never true (d) none of these

82. If $u^v + v^w + w^x = 0$ for every negative integer u, v, w, x the value of $u \times v \times w \times x$ is necessarily be :
(a) 0 (b) less than zero
(c) even (d) odd

83. The unit digit of $2^{3^4} \times 3^{4^5} \times 4^{5^6} \times 5^{6^7} \times 6^{7^8} \times 7^{8^9}$ is :
(a) 0 (b) 5
(c) can't be determined (d) none of these

84. If $(a-7)(b-10)(c-12) = 1000$, then the least possible value of $(a+b+c)$ equals :
(a) 59
(b) 29
(c) 14
(d) any integer less than 1000

85. If the number $23^{32} - 9$ is divided by 16, then the remainder is :
(a) 8 (b) 0
(c) 6 (d) none of these

86. If $(x-5)(y+6)(z-8) = 1331$, then the minimum value of $x+y+z$ is :
(a) 40 (b) 33
(c) 19 (d) not unique

87. If $x+y+z = 21$, then the maximum value of $(x-6)(y+7)(z-4)$ is :
(a) 343 (b) 216
(c) 125 (d) not unique

88. The remainder 'R' when $3^{37} + 4^{37}$ is divided by 7 is :
(a) 0 (b) 1
(c) $2 < R < 6$ (d) none of these

89. $7^{74} - 4^{74}$ is divisible by :
(a) 3 (b) 11
(c) 7 (d) both (a) and (b)

90. The factorial of a number n is exactly divisible by $(2^{11} \times 11^2)$ then the least possible value of n is :
(a) 22 (b) 25
(c) does not exist (d) none of these

91. The number of zeros at the end of the product of :
$2^3 \times 3^4 \times 4^5 \times 5^6 + 3^5 \times 5^7 \times 7^9 \times 8^{10} + 4^5 \times 5^6 \times 6^7 \times 7^8 - 10^2 \times 15^3 \times 20^4$ is :
(a) 5 (b) 6
(c) 28 (d) none of these

92. A nine digit number *abcdefghi* is such that *a* is divisible by 1, *ab* is divisible by 2, *abc* is divisible by 3 and *abcd* is divisible by 4 and so on where none of *a, b, c, d, ...* is same and every digit is a non-zero digit such a number is :
(a) 123456789
(b) 381654729
(c) 126453789
(d) 826435791

Directions for question numbers 93, 94 and 95 :
If Minimum (x, y, z) = Minimum of (xy, yz, zx)
Maximum (x, y, z) = Maximum of (x^y, y^z, z^x)
Labh (x, y, z) = Average of (x, y, z)
Hani (x, y, z) = Modulus of $(x - y - z)$ i.e., $|x - y - z|$

93. The value of Minimum (1, 2, 3) + Maximum (1, 2, 3) is :
(a) 10 (b) 8
(c) 12 (d) 4

94. Labh [Hani (1, 2, 3), Hani (2, 3, 4), Hani (3, 4, 5)] is equal to :
(a) 4 (b) 5
(c) 6 (d) can't be determined

95. Minimum [Hani (1, 2, 3), Hani (2, 3, 4), Hani (3, 4, 5)] + Maximum [Labh (1, 2, 3), Labh (2, 3, 4), Labh (3, 4, 5)] is :
(a) 101 (b) 111
(c) 60 (d) none of these

96. When $(55)_{10}$ is represented in base 25 then the expression is :
(a) $(25)_{25}$ (b) $(35)_{25}$
(c) $(55)_{25}$ (d) none of these

97. For $(P, Q) > 0$ the number 340 PQQ 0 is divisible by both 3 and 8 then the total possible values of (P, Q) is :
(a) 2 (b) 3
(c) 6 (d) none of these

98. A typist while typing the numbers from 600 to 799 mistakenly he typed 8 every time in place of 6. So the total number of times he has typed 8 is :
(a) 300 (b) 230
(c) 180 (d) none of these

99. If p and q are two distinct integers such that $p^2 - pq = 0$ then we can deduce that :
(a) $p = q$
(b) q is only negative integer
(c) $p = 0$
(d) either (a) or (c)

100. In a survey it was found that YTC sells the cigarettes of Rs. 15990 per day. If the cost of a pack is not less than Rs. 100 then what can be the price of each pack which it sells per day is :
(a) 150 (b) 420
(c) 78 (d) 205

101. If $5n + 12 < 50$; where $n \in N$, then the value of n which satisfies the given inequality is :
(a) $5 < n < 12$ (b) $3n^2 \leq 150$
(c) $4n + 5 \leq 33$ (d) $4n^2 + 3 > 200$

102. If A and B are divided by D, then the remainder obtained are 13 and 31 respectively where A, B, D are natural numbers. Further $A + B$ is divided by the same divisor D the remainder is 4, then the divisor D is :
(a) 14 (b) 23
(c) 40 (d) 18

103. The unit digit of N^{2p} and $(N)^{(2p+1)}$ are 6 and 4 respectively. The greatest two digit number that follows the afore-said condition is :
(a) 49 (b) 84
(c) 94 (d) 98

Scanned by CamScanner

yoursmahboob.wordpress.com

104. If $f(x) = x^3 + 3x^2 - 4x$ then $f(x+1)$ is :
(a) $x^3 + 7x^2 - 5$ (b) $x^3 + 6x^2 + 5x$
(c) $(x+1)^3$ (d) none of these

105. If $a + b = n$, $n \in I$ and $ab = 60$ then n cannot be equal to :
(a) 33 (b) – 19
(c) 17 (d) 32

Direction for questions 106 to 108 : If a sequence is as given below :
1, 1, 2, 3, 5, 8, 13, 21, 34, ...

106. The unit digit of the 75th term of this sequence will be :
(a) 0 (b) 5
(c) 7 (d) none of these

107. In the above sequence the 55th term will be :
(a) an even number (b) an odd number
(c) either even or odd (d) can't be determined

108. The unit digit of the sum of the 88th and 89th term of the same sequence will be :
(a) 5 (b) 2
(c) 0 (d) none of these

109. The unit digit of the product of n consecutive numbers of the form $2k + 1$, where $k \in I^+$ and n must be at least 5.
(a) zero (b) any odd number
(c) 5 (d) both (b) and (c)

110. In the above question the sum of the n terms of the sequence is :
(a) $n^2 - 1$ (b) $n(2n - 1)$
(c) $[(n-1)!]\, n$ (d) none of these

111. If $n_1, n_2, n_3, \ldots, n_k \in I$ such that $-5 \le n_k \le 25$, then the least possible product of any 3 numbers can be :
(a) – 60 (b) 0
(c) – 3000 (d) none of these

112. If p, q, r are such that $q - p = r - q = 2$ for every $p, q, r \in I^+$, then the least possible value of $(p+q)(q+r)(r+p)$ is :
(a) 192 (b) 720
(c) 129 (d) data insufficient

113. The H.C.F. of 38024 and 16296 is :
(a) 1234 (b) 6431
(c) 5432 (d) none of these

114. For any positive real number R, $[R]$ is the greatest integer less than or equal to R, then the value of $\left[\frac{R}{2}\right] + \left[\frac{R+1}{2}\right]$ is :
(a) $[R]$ (b) $[2R]$
(c) $\left[R + \frac{1}{3}\right]$ (d) can't be determined

115. For the natural numbers n_1 and n_2 if $2n_1 + 3n_2 = n_1 \times n_2$, then the least possible value of the $2n_1 + 3n_2$ is :
(a) 6 (b) 12
(c) 24 (d) can't be determined

116. A company offers total 150 pens to its customers. As per the scheme one pen will be offered on the purchase of a "Quantitative Aptitude" book. Out of 150 pens the cost of some pens is Rs. 3 and the cost of the rest pens is Rs. 5. Maximum how many customers can avail a pen of Rs. 5 as an offer from the company if the total cost of the pens cannot exceed Rs. 745.
(a) 45 (b) 120
(c) can't be determined (d) none of these

Directions for question numbers 117 to 118 : A number of 109 digits is written as follows :
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 ...

117. What is the least possible a positive number is required to add up in the given number to make it divisible by 2 and 5 both?
(a) 0 (b) 1
(c) 3 (d) can't be determined

118. What is the least possible whole number which must be subtracted from the given number so that it will become divisible by 3 and 11 both?
(a) 8 (b) 3
(c) 0 (d) none of these

119. Each family in Gyanpur village has atmost two adults and the total number of boys in this village is less than the number of girls. Similarly the number of girls is less than the number of adults in the village. Raghubir Singh, the chief of this village is the only adult in his family. The minimum number of families in his village is :
(a) 2 (b) 3
(c) 4 (d) none of these

120. Which of the following is correct if $A = 3^{3^3}$, $B = 3^{33^3}$, $C = 3^{3^{33}}$ and $D = 3^{333}$?
(a) $A > B = C > D$ (b) $C > A > B > D$
(c) $A > C > D > B$ (d) $C > B > D > A$

121. When two positive integers A and B are divided by another number D, then the remainders obtained were 23 and 3 respectively. Further when $(A + B)$ is divided by D, the remainder is 26, then the value of D is :
(a) 62 (b) 69
(c) 26
(d) Any value greater than 26

122. In how many ways can 729 be expressed as a difference of the square of whole numbers?
(a) 4 (b) 6
(c) 8 (d) none of these

123. In how many ways can 2310 be expressed as a product of 3 factors?
(a) 41 (b) 23
(c) 56 (d) 46

Scanned by CamScanner

yoursmahboob.wordpress.com

Final Round

1. Sania wanted to cut a cubical cake into 120 identical pieces applying minimum number of 'n' cuts. Later on she realised that she had to cut this cake into maximum number of identical pieces i.e., 125 pieces. Now she applies the number of cuts is :
(a) n (b) $n + 5$
(c) $n + 1$ (d) can't be determined

Directions for questions 2 to 4 :
If $s_1 = (1)$; $s_2 = (2), (3)$;
$s_3 = (4), (5), (6)$;
$s_4 = (7), (8), (9), (10)$;
$s_5 = (11), (12), (13), (14), (15)$ ...*etc.*
where $s_1, s_2, s_3, \ldots$ *etc. are the first, second and third terms ... of the given sequence.*

2. The last digit and tens digit of the sum of all the elements of the first 21 terms of this sequence respectively are :
(a) 7, 0 (b) 6, 9
(c) 9, 6 (d) none of (a), (b), (c)

3. The number of zeros at the end of the product of the elements of s_{19}.
(a) 4 (b) 5
(c) 1 (d) none of these

4. The largest power of 10 that can exactly divide the product of all the elements of s_{19} and s_{20} is :
(a) 10 (b) 9
(c) 19 (d) can't be determined

5. A set 'S' contains first 50 elements of the form $2n$; $n \in N$. Further a subset 'P' of set 'S' is formed such that the product of any 3 elements of 'P' is not divisible by 16. Then maximum number of elements that 'p' can have is :
(a) 12 (b) 13
(c) 25 (d) none of (a), (b), (c)

6. A cuboid of dimensions 51, 85 and 102 cm is first painted by red colour then it is cut into minimum possible identical cubes. Now the total surface area of all those faces of cubes which are not red is :
(a) 119646 cm² (b) 52020 cm²
(c) 18514 cm² (d) 36414 cm²

7. A number 'p' is such that it is divisible by 7 but not by 2. Another number 'q' is divisible by 6 but not by 5, then the following expression which necessarily be an integer is :
(a) $\frac{7p + 6q}{42}$ (b) $\frac{5p + 6q}{71}$
(c) $\frac{6p + 7q}{42}$ (d) none of these

8. If $p^q - q^r = (p + q)^{r-q}$; $p > r > q \in$ Prime numbers less than 11 then $p + q$ is equal to :
(a) $r(r - q)$ (b) $r(q - p)$
(c) $r(p + q)$ (d) pq

9. To visit the Republic Day Parade on 26th January 2005, the people from every nook and corner including intellectuals, artists, farmers and mathematicians thronged in New Delhi. There were 100 seats in front row numbered 1, 2, 3, ..., 100. But the smart mathematician chose not to sit on those seats which are the multiples of any number greater than unity. How many mathematician could sit on these front row chairs?
(a) 25 (b) 26
(c) 33 (d) none of these

Direction for questions 10 to 12 : In South-Asia the New Desh follows a septarian calender in which every month starts with Monday and a week has 7 days. There are only four months, the first 3 months consists of 98 days each and the last month has 70 days only.

10. Which day falls on the 88th day of the first month?
(a) Sunday (b) Monday
(c) Thursday (d) Saturday

11. Which date cannot fall on the Thursday of the first month?
(a) 46 (b) 18
(c) 81 (d) 64

12. Which day occurs maximum number of time in a year?
(a) Monday (b) Saturday
(c) Sunday (d) none of these

13. The last two digit in the expansion of $(1989)^{91}$ are :
(a) 9, 1 (b) 8, 1
(c) 6, 9 (d) 8, 9

14. Earlier when I have created my e-mail-ID, the password was consisting of first 4 prime numbers. Recently when I tried to check my emails I got dumbfounded since I could not remember my password exactly. So when I have written 2735, my computer indicated me that no digit is correctly placed. Again I tried 5273, I got the same response. So once again I have written only 3 as the left most digit for my password it again indicated me that it was wrong. Finally I have taken one more attempt and got the account open. The code of my password is :
(a) 2537 (b) 7352
(c) 7325 (d) none of these

15. The remainder when $(8881)^{9999}$ is divided by 77 is :
(a) 1 (b) 2
(c) 3 (d) none of these

16. We publish a monthly magazine of 84 pages. Once I found that in a magazine 4 pages were missing. One out of them was page number 29 it is known that the page number of the last page of the magazine is 84, (including the coverpages). The numbers printed on the missing pages were :
(a) 29, 52, 53 (b) 30, 55, 56
(c) 28, 52, 53 (d) can't be determined

17. There are six locks exactly with one key for each lock. All the keys are mixed to each other. The maximum number of attempts needed to get the correct combination is :
(a) 21 (b) 15
(c) 6 (d) can't be determined

18. If n is an integer, how many values of n will give an integral value of $51n^2 + 17n + 6$?
(a) 4 (b) 3
(c) 2 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

19. Sania always beats Plexur in tennis, but loses to Venus. Lindse usually beats Plexur and sometimes Sania, but cannot win against Venus. The worst player can be :
(a) Venus (b) Plexur
(c) Sania (d) can't say

20. Winner and Loser two brothers are playing a game in recreational room at Amausi Airport, Lucknow. In this game each one in turn has to pick up a number m such that $1 \le m \le n$; $m, n \in I^+$. The game stops as soon as the sum of all the numbers picked so far attains the value of $2n+1$ or exceeds and thus the player who picked last number was loser. With which number winner starts if he were to pick up first to defeat necessarily to loser is?
(a) $(n+1)$ (b) n
(c) $(n-1)$ (d) $2n$

21. The sum of the last 10 digits of the sum of the expression :
$(1^1 \times 2^2 \times 3^3 \times 4^4 \times 5^5) + (1^6 \times 2^7 \times 3^8 \times 4^9 \times 5^{10}) + (1^{11} \times 2^{12} \times 3^{13} \times 4^{14} \times 5^{15}) + \ldots + (1^{96} \times 2^{97} \times 3^{98} \times 4^{99} \times 5^{100})$ is :
(a) 16 (b) 18
(c) 20 (d) none of these

22. One day very early morning Ravishankar went to temple to offer some flowers as a part of *Puja*. He purchased some flowers but the seller offered him that if he would give him all his Rs. 2, he could get all the remaining 6 flowers and thus could gain 60 paise per dozen. If each time the transaction is possible only in rupees then how many flowers did Ravishankar purchase initially?
(a) 6 (b) 3
(c) 4 (d) 12

23. Maximum number of squares possible that can be constructed using 31 pencils of equal length on the table :
(a) 30 (b) 20
(c) 15 (d) 29

Directions for question number 24 and 25 : Kavita, a student of i4 IIM, told me that she did everyday 3 more passages of English than that of previous day and thus she completed all the passages in 10 days. Later on she told me that the number of passages she did on the last but one day were four times that she did on the second day.

24. Number of passages she has done on the last day :
(a) 30 (b) 41
(c) 32 (d) none of these

25. Total number of passages that she has completed in those 10 days :
(a) 84 (b) 180
(c) 175 (d) can't be determined

26. Recently, a small village, in Tamilnadu where only male shepherd reside with four sheep each, was devastated by Tsunami waves. Therefore 8 persons and 47 sheep were found to be dead and the person who luckily survived, left the village with one sheep each since 21 sheep were too injured to move so have been left on their own luck, in the village. The number of sheep which were earlier in the village is :
(a) 84 (b) 120
(c) can't be determined (d) none of these

27. The number of 3-digit numbers which consists of the digits in A.P., strictly in increasing order using the non-zero digits of the decimal system is :
(a) 14 (b) 16
(c) 15 (d) none of these

28. The sum of :
$(2^2 + 4^2 + 6^2 + \ldots + 100^2) - (1^2 + 3^2 + 5^2 + \ldots + 99^2)$ is :
(a) 5555 (b) 5050
(c) 888 (d) 222

29. If an integer p is such that $(8p+1)$ is prime, where $p > 2$, then $(8p-1)$ is :
(a) divisible by 7 (b) divisible by 3
(c) a prime number (d) none of these

30. The remainder when $3^0 + 3^1 + 3^2 + \ldots + 3^{200}$ is divided by 13 is :
(a) 0 (b) 12
(c) 3 (d) none of these

31. The remainder when $4^0 + 4^1 + 4^2 + 4^3 + \ldots + 4^{40}$ is divided by 17 is :
(a) 0 (b) 16
(c) 4 (d) none of these

32. In the problem number 31, if the divisor is 7 then the remainder is :
(a) 4 (b) 5
(c) 6 (d) 1

33. A monkey wanted to climb on the smooth vertical pole of height of 35 metre. In the first one minute he climbs up 5 metre in the next one minute he slips down by 2 metre. Further he repeated the same process till he has reached on the top of the pole. How many times it has to go upward to reach the apex of the pole?
(a) 35 (b) 12
(c) 11 (d) can't say

34. In the above question the minimum time required for this job is :
(a) 21 minute (b) 22 minute
(c) 24 minute (d) none of these

35. In the same problem, if the height of the pole is 36 metre then the time taken by monkey to reach at the top of the pole is :
(a) 22 min. 36 sec. (b) 22 min. 24 sec.
(c) 23 min. 12 sec. (d) none of these

36. The remainder when $1^3 + 2^3 + 3^3 + \ldots + 999^3 + 1000^3$ is divided by 13 is :
(a) 7 (b) 11
(c) 12 (d) none of these

37. If $22^3 + 23^3 + 24^3 + \ldots + 87^3 + 88^3$ is divided by 110 then the remainder wil be :
(a) 55 (b) 1
(c) 0 (d) 44

38. The sum of the n terms of a series is $n1 + n^2$ then the 6th term is, if $n \in N$:
(a) 756 (b) 611
(c) data insufficient (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

39. A smallest possible number which is divisible by either 3, 5 or 7 when represented by only two digits either 0 or 1, then the minimum number of digits required to represent it :
(a) 6 (b) 5
(c) 7 (d) can't be determined

40. The sum of first n odd numbers (*i.e.*, $1 + 3 + 5 + 7 + \ldots + 2n - 1$) *is divisible by 11111 then the value of* n is :
(a) 12345 (b) 11111
(c) can't be determined (d) none of these

41. Anjuli bought some chocolates from Nestle's exclusive shop, she gave to Amit one less than half of what she had initially. Then she had given 3 chocolates to Babli and then half of the chocolates which she had then given to Charles. Thus finally she gave one chocolate to Deepak and the remaining one she ate herself. The number of chocolates she had purchased.
(a) 9 (b) 12
(c) 10 (d) 15

42. If $(a_1b_1c_1)^{100} + (a_2b_2c_2)^{100} + (a_3b_3c_3)^{100} + \ldots (a_{100}b_{100}c_{100})^{100}$, where $a_ib_ic_i$ is a three digit positive number and in the expression all the 100 numbers are any consecutive 3 digit numbers. The last digit is :
(a) 0 (b) 1
(c) 3 (d) none of these

Directions for question number 43 to 45 : If [x] read as the greatest integer less than or equal to x, {x} is the least integer greater than or equal to x. Further $f(x, y) = [x] + \{y\}$
and $g(x, y) = [x] - \{y\}$
and $P(x, y) = f(x, y) + g(x, y)$
and $Q(x, y) = f(x, y) - g(x, y)$

43. If $x = 16$ and $y = 25$ then the value of $P(x, y) + Q(x, y)$ is :
(a) 90 (b) 200
(c) can't be determined (d) none of these

44. If $x^2 = 16$ and $y^2 = 25$ then $P(x, y)Q(x, y)$ is :
(a) 80 (b) – 80
(c) 72 (d) none of these

45. If $x, y \in I^+$ then $P(x, y) + Q(x, y)$ is always :
(a) an even number (b) an odd number
(c) can't say (d) none of these

46. Which of the following is/are true?
(i) $43^3 - 1$ is divisible by 11
(ii) $56^2 + 1$ is divisible by 19
(iii) $50^2 - 1$ is divisible by 17
(iv) $(729)^5 - 729$ is divisible by 5
(a) (i) and (ii) (b) (iii) and (iv)
(c) (ii), (iii) and (iv) (d) (ii) and (iii)

47. Capt. Manoj Pandey once decided to distribute 180 bullets among his 36 soldiers. But he gave n bullets to a soldier of nth row and there were same number of soldiers in each row. Thus he distributed all his 180 bullets among his soldiers. The number of soldiers in $(n - 1)$th row was :
(a) 3 (b) 8
(c) 9 (d) none of these

48. If $(n - 5)$ is divisible by 17 for every $n \in I^+$ then the greatest integer which will necessarily divide $(n + 12)(n + 29)$ is :
(a) 578
(b) 289
(c) such a number does not exist
(d) none of these

49. A certain number 'n' can exactly divide $(3^{24} - 1)$ then this number can also divide the number :
(a) $(3^{16} + 1)$ (b) $(3^8 - 1)$
(c) $(3^{70} - 1)$ (d) $(3^{96} - 1)$

50. If a number 'n' can exactly divide $(5^{14} - 1)$ then 'n' can divide necessarily :
(a) $(5^{28} - 1)$ (b) $(5^{42} - 1)$
(c) $(5^{21} + 1)$ (d) both (a) and (b)

51. The nth term of a series of which all the terms are positive is defined as $T_n = n^2 + n$ then the sum of n terms of the series is:
(a) $\frac{n(n+1)(n+2)}{6}$ (b) $\frac{n^3 + 4n}{n}$
(c) $\frac{5n}{9}[n^2 + n]$ (d) $\frac{n(n+1)(n+2)}{3}$

52. The number of zeros at the end of the product of $222^{111} \times 35^{53} + (71)^{61} \times (101)^{51} + 42^{42} \times 25^{25}$ is :
(a) 42 (b) 53
(c) 1055 (d) none of these

53. $\frac{12345}{12346} + \frac{12346}{12347} + \frac{12347}{12345}$ is equal to :
(a) 2.67 (b) 6.27
(c) 3 (d) 5

Directions for question numbers 54 to 56 : The set $S_1 = \{1\}$ $S_2 = \{3, 5\}$, $S_3 = \{7, 9, 11\}$, *etc. forms a sequence.*

54. Sum of all the elements of S_{10} is :
(a) 55 (b) 300
(c) 3375 (d) none of these

55. The 11th element of the set S_{21} is :
(a) 21 (b) 121
(c) 221 (d) 441

56. The sum of the first and last element of the set S_{51} is :
(a) 5202 (b) 5151
(c) 5152 (d) 5102

57. During my studies once I brought a book from library which was written in early days, when there were only 9 digits *i.e.*, the digit 0 did not exist. There was a sum in that book as follows :

$$k = 13 + 17 + 31 + 2$$

Then the value of k if $9 + 1 = 11$, $19 + 4 = 24$ etc.
(a) 70 (b) 71
(c) 63 (d) 64

58. The sum of $4 + 16 - 5 + 12$ is according to that book.
(a) 27 (b) 26
(c) 29 (d) none of these

59. The value of x for which the unit digits of $(2357)^{\log_{10} x}$ and $(5723)^x$ is same for $x > 1$.
(a) 10 (b) 100
(c) 1000 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

60. The value of x for which the unit digits of the following two expressions $(1+2+3+4+7)^{x^2+x}$ and $(11\times11\times13)^x$ are same for $x>0$:
(a) 1 (b) 2
(c) 3 (d) none of these

61. When any odd number greater than unity multiplied by even times by itself then dividing this product by 8, we get the remainder as :
(a) 1 (b) 7
(c) not unique (d) none of these

62. Stephen's birthday, this year falls on 2nd April, Wednesday. But coincidently his marriage anniversary is 2 days before the 23rd of the same month. On which day he will celebrate his marriage anniversary?
(a) Monday (b) Wednesday
(c) Friday (d) can't be determined

63. In the above problem if there are only 6 days in a week *i.e.*, there is no Sunday and the week starts with Monday and ends with Saturday then his marriage anniversary will fall on :
(a) Wednesday (b) Thursday
(c) Friday (d) data insufficient

64. An N.G.O. (non-government organisation) STRANGE working for the relief of Tsunami Victims in Srilanka consisting of 7 members S, T, R, A, N, G, E of the same family.

The eldest one '*S*' spoke to me "I have deployed equal number of brothers and sisters for medical relief and psychological counselling under the supervision of myself". Later on the youngest member *E* spoke to me as "we have been working for rehabilitation and food supply as twice the number of sisters as the number of brothers have been deployed there, but I did not actually do any thing due to a severe injury in my leg". Then we can conclude that :
(a) youngest person is a lady
(b) eldest person's wife is youngest
(c) the brother of *S* is youngest
(d) nothing can be said

65. When the sum of n digits of an n digit number is subtracted from the number itself, where the number must be atleast two digit number, then the correct statement is :
(a) the difference is a prime number
(b) the resultant value is a perfect square
(c) the resultant value is an odd number
(d) the resultant value is a multiple of 9

66. For every natural number x and y the value of $x-y$ when $y+\frac{7}{x}+\frac{y}{13}=6\frac{3}{143}$, is :
(a) 5 (b) 6
(c) 2 (d) not unique

Directions for question 67 and 68 : The $S=\{(1,3,5,7,9,\ldots,99)\ (102,104,106,\ldots,200)\}$ *i.e., in the first part there are odd integers less than 100 and in the second part there are even integers greater than 100, but upto 200.*

67. The highest power of 3 in the product of the element of the set is :
(a) 52 (b) 51
(c) 97 (d) can't be determined

68. The highest power of 5 that can exactly divide the product is :
(a) 25 (b) 24
(c) 30 (d) 26

69. The number of zeros at the end of the following expression :
$P=\{(2\times4\times6\times8\times10\times\ldots50)\times(55\times60\times65\times70\times75\times\ldots100)\}$
(a) less than 20 (b) 57
(c) 20 (d) 36

70. 1, 2, 3, 4, 10, 11, 12, 13, 14, 20, 21, 22, 23, 24, ... are the consecutive numbers written in base 5. The twenty fifth number in the above sequence would be :
(a) 52 (b) 100
(c) 25 (d) none of these

71. Watch India Corporation made a wrist watch in which the minute hand makes one complete round of dial in 12 minute and accordingly the hour hand too. When I have set this watch at 12 : 00 noon on Ist February this year. Which time will be shown by this watch at 3 O'clock on the same day.
(a) 2 : 30 P.M. (b) 6 : 15 A.M.
(c) 3 O'clock (d) can't be determined

72. The sum of first n numbers of the form $(5k+1)$, where $k\in I^+$ is :
(a) $\frac{n}{2}[5n^2-3]$ (b) $n(20-3n)$
(c) $\frac{n}{2}(5n+7)$ (d) none of these

73. A series is given as : 1, 4, 9, 16, 25, 36, ...
Then the value of $T_{n+1}-T_n$ is, where T_n is the nth term of the series is :
(a) n^2-1 (b) $2n+1$
(c) n^2+1 (d) none of these

74. The area of paper can be divided into 144 squares, but if the dimensions of each square were reduced by 2 cm each, then the number of squares so formed are 400. The area of the paper initially was :
(a) 544 cm^2 (b) 1444 cm^2
(c) 3600 cm^2 (d) none of these

75. If $(ab)^2=bcb$ and $(dd)^2=ccff$, where a, f, d are strictly in increasing order of G.P. and b, c, d are in increasing order of A.P. Then the value of f will be, where ab and bcb etc. are the two digit and 3 digit numbers etc.
(a) 9 (b) 8
(c) can't be determined (d) none of these

76. If $A=555!$ and $B=(278)^{555}$ then which one of the following relation is appropriate?
(a) $A>B$ (b) $A=B$
(c) $A<B$ (d) can't say

Directions for question number 77 to 81 : *For any natural number n the sets* $S_1, S_2, \ldots$ *are defined as below :*
$S_1=\{1\}$, $S_2=\{2,3\}$, $S_3=\{4,5,6\}$
$S_4=\{7,8,9,10\}$, $S_5=\{11,12,13,14,15\}$ ... *etc.*

Scanned by CamScanner

yoursmamboob.wordpress.com

77. The last element in the S_{24} is :
(a) 576 (b) 600
(c) 300 (d) 625

78. The middlemost element of the set S_{15} is :
(a) 196 (b) 169
(c) 131 (d) none of these

79. The sum of the elements of set S_{25} is :
(a) 7825 (b) 3125
(c) 3250 (d) none of these

80. In which set, there are maximum number of prime number elements among $S_1, S_2, S_3, \ldots, S_{13}$ is :
(a) S_{12} (b) S_{13}
(c) S_{12} and S_{13} (d) S_9, S_{12}, S_{13}

81. Of which set the sum of all the elements of the set is even :
(a) S_{39} (b) S_{50}
(c) S_{72} (d) S_{94}

Directions for question numbers 82 to 85 : *The sequence of sets* $S_1, S_2, S_3, S_4, \ldots$ *is defined as* $S_1 = \{1\}$, $S_2 = \{3, 5\}$, $S_3 = \{7, 9, 11\}$, $S_4 = \{13, 15, 17, 19\}$ ... *etc.*

82. The first element of the nth set S_n is :
(a) n (b) $n^2 - 1$
(c) $2n + 1$ (d) $n^2 - n + 1$

83. The last element of the set S_{100} is :
(a) 10099 (b) 9899
(c) 9900 (d) none of these

84. The middlemost element of an odd numbered set S_{125} is :
(a) 12500 (b) 15625
(c) 3125 (d) none of these

85. The sum of all the elements of S_{101} :
(a) 1531441 (b) 1189811
(c) 1030301 (d) none of these

86. The sum of the series :
$$S = \frac{1}{1.2} + \frac{1}{2.3} + \frac{1}{3.4} + \frac{1}{4.5} + \ldots + \frac{1}{99.100} \text{ is :}$$
(a) $\frac{98}{99}$ (b) $\frac{99}{100}$
(c) $S > 1$ (d) none of these

87. A number P when divided by D it leaves the remainder 18 and if another number Q is divided by the same divisor D it leaves the remainder 11. Further if we divide $P + Q$ by D then we obtain the remainder 4. Then the common divisor D is :
(a) 22 (b) 15
(c) 25 (d) can't be determined

88. If the product of $1 \times 2 \times 3 \times 4 \times \ldots n$ contains 68 zeros in the end of the number. Then the maximum possible number of values of n is :
(a) 1 (b) 3
(c) 5 (d) 6

89. The remainder when $6^{6^{6^{6^{\ldots}}}}$ (∞ times) is divided by 10 is :
(a) 3 (b) 6
(c) 0 (d) can't be determined

90. $53^3 - 46^3 - 7^3$ is divisible by :
(a) 6 and 9 (b) 2 and 21
(c) 21 and 23 (d) both (b) and (c)

91. A number of decimal system when written in base n, $2 < n < 10$, we get a two digit number. Further if we reverse the digits of the obtained number in base 'n' we get a number which is twice of the original number in decimal system. The sum of original and resultant number both in decimal system for the largest possible value of n is :
(a) 45 (b) 63
(c) 77 (d) can't be determined

92. In the above question how many values of n are possible?
(a) 0 (b) 2
(c) 4 (d) 7

93. Pandavas won a hen in the war of the Mahabharat. They brought it on the Ist January, 2002. This hen gave birth to the 7 new hens on the very first day. After it every new hen irrespective of its age everyday gave birth (only once in a lifetime) to 7 new hens. This process continued throughout the year, but no any hen had been died so far. On the 365th day all the Pandavas shared equally all the hens among all the five brothers. The remaining (if these can not be shared equally) hens were donated to Krishna. The number of hens which the Krishna had received is :
(a) 3 (b) 2
(c) can't be determined (d) none of these

94. Total number of natural numbers being the perfect square whose square root is equal to the sum of the digits of the perfect square is :
(a) 0 (b) 1
(c) 2 (d) 12

95. At our training Institute the number of boys is same as that of the girls. Last week, except $\frac{2}{3}$rd of the girls all the students went to picnic, where they bought some samosas but later on they found exactly one dozen samosas were not fresh so those 12 samosas have been thrown away. After it half-half the samosas were divided between boys and girls. Further when boys dealtout the samosas equally among themselves 39 samosas left undistributed, but when the girls dealtout the same number of samosas equally among themselves 12 samosas were still left undistributed. The number of students at out training institute is :
(a) 60 (b) 156
(c) 162 (d) can't be determined

96. Darwin Miya has 6 kinds of fruits in large amount and has sufficient number of identical boxes to store the fruits. He can put at least 10 and atmost 15 fruits in any box and he put only one kind of fruits in a box. Further not more than 5 boxes can contain same number of fruits. Maximum number of fruits that he can put in the boxes is :
(a) 325 (b) 375
(c) 75 (d) can't be determined

97. In the above question if he is allowed to put the equal number of fruits in atmost 7 boxes and he has only 33 boxes and now he can put any kind of fruit with any other kind of fruits. At least how many boxes are there in which the number of fruits are same if he fills every box to its maximum capacity.
(a) 5 (b) 6
(c) 3 (d) can't be determined

98. If $n \in 1, 3, 5, 7, \ldots$ etc., then the value of $19^n - 23^n - 43^n + 47^n$ is necessarily divisible by :
(a) 264 (b) 246
(c) 76 (d) 129

Scanned by CamScanner

yoursmahboob.wordpress.com

99. The sum of the following series :

$$1.1^2\left(1-\frac{0}{1}\right)+2.2^2\left(1-\frac{1}{2}\right)+3.3^2\left(1-\frac{2}{3}\right)+4.4^2\left(1-\frac{3}{4}\right)+\ldots \text{upto } n \text{ terms is :}$$

(a) $n.n^2\left(1-\frac{1}{n}\right)$ (b) $\frac{n(n+1)(2n+1)}{6}$

(c) $\frac{n(n+1)^2}{4}$ (d) none of these

100. The distance between the houses of Sarvesh and Ravi is 900 km and the house of former is at 100th milestone where as the house of Ravi's is at 1000th milestone. There are total 901 milestones at a regular interval of 1 km each. When you go to Ravi's house from the house of Sarvesh which are on the same highway, you will find that if the last digit (*i.e.*, unit digit) of the 3 digit number on every milestone is same as the first (*i.e.*, hundreds digit) of the number on the next mile stone is same, then these milestones must be red colour and rest will be of black. Total number of red colour milestones is :

(a) 179 (b) 90

(c) can't be determined (d) none of these

101. The highest power of 17 which can divide exactly the following expression :

$(18^2-1)(18^4-1)(18^6-1)(18^8-1)(18^{10}-1)\times\ldots(18^{16}-1)(18^{18}-1)$ is :

(a) 1 (b) 17

(c) 9 (d) can't be determined

102. "Help India Foundation" and "People for People Organisation" decided to distribute the blankets among 22 men and 28 women who are Tsunami victims. When HIF and PPO distributed their respective blankets evenly among 28 women they were left with 24 and 16 blankets respectively. If they distributed their blankets evenly among 22 men they were left with 12 blankets each. So finally they decided to combine all their blankets and then distributed among 22 men and 28 women altogether then no any blanket remained undistributed. Minimum total blankets distributed by them were :

(a) 960 (b) 700

(c) 1300 (d) none of these

103. In the above problem the ratio of blankets between HIF and PPO is :

(a) $\frac{43}{157}$ (b) $\frac{147}{179}$

(c) $\frac{59}{101}$ (d) can't be determined

104. The total number of 3 digit numbers which have two or more consecutive digits identical is :

(a) 171 (b) 170

(c) 90 (d) 180

105. The expression, for $p \neq 1$, $(1+p^{256})\times(1+p^{128})\times(1+p^{64})\times(1+p^{32})\times(1+p^{16})\times(1+p^8)\times(1+p^4)\times(1+p^2)\times(1+p)$ is equivalent to :

(a) $\frac{1+p^{256}}{1+p^{128}}$ (b) $\frac{1-p^{512}}{1-p}$

(c) $\frac{1-p^{256}}{1-p}$ (d) p^{255}

106. For the given fixed perimeter of 50 cm, the total number of rectangles which must have its sides in integers (cm) is :

(a) 50 (b) 25

(c) 12 (d) infinite

107. The total number of factors of a number is 24 and the product of the prime factors of the same number is 30. The square root of the ratio of such a smallest and the greatest possible numbers is :

(a) 5/6 (b) 6/9

(c) 9/25 (d) 4/25

108. In the above problem, maximum how many numbers are possible?

(a) 9 (b) 8

(c) 7 (d) data insufficient

109. Mr. Oberai appeared in CAT for four consecutive years, but coincidentlly each time his net score was 75. He told me that there was $\frac{1}{3}$rd negative marking for every wrong answer and 1 mark was alloted for every correct answer. He has attempted all the questions every year, but certainly some answers have been wrong due to stress and conceptual problems. Which is not the total number of questions asked for CAT in any year, in that period?

(a) 231 (b) 163

(c) 150 (d) 123

110. A thief somehow managed to steal some golden coins from a bank's cash but while coming out of it at the first door he was caught by the watch man and he successfully dealt him by paying 1 coin plus half of the rest coins. Further he had to pay 2 coins, then half of the rest to the second watchman. Once again at the third gate (outermost) he gave 3 coins and then half of the rest. After it he was left with only one coin. How many coins had he stolen?

(a) 32 (b) 36

(c) 25 (d) none of these

111. The number $\log_2 7$ is :

(a) an integer (b) a rational number

(c) an irrational number (d) a prime number

112. The product of n positive numbers is unity. Then their sum is :

(a) a positive integer (b) divisible by n

(c) equal to $\left(n+\frac{1}{n}\right)$ (d) never less than n

113. Let $n > 1$, be a positive integer. Then the largest integer m, such that (n^m+1) divides $(1+n+n^2+n^3+\ldots+n^{127})$ is :

(a) 127 (b) 63

(c) 64 (d) 32

114. Number of divisors of the form $4n+2$; $n \geq 0$ which can divide 240 is :

(a) 4 (b) 8

(c) 10 (d) 3

115. If the integers m and n are chosen at random between 1 and 100, then atmost distinct numbers of the form 7^m+7^n is divisible by 5 equals to :

(a) 1250 (b) 10000

(c) 2500 (d) none of these

116. If a, b, c, d are positive real numbers such that $a+b+c+d=2$, then $M=(a+b)(c+d)$ satisfies the relation is :

(a) $0 \leq M \leq 1$ (b) $1 \leq M \leq 2$

(c) $2 \leq M \leq 3$ (d) $3 \leq M \leq 4$

Scanned by CamScanner

yoursmahboob.wordpress.com

Test of Your Learning-1

1. A monkey wants to climb up a pole of 50 metre height. He first climbs up 1 metre but he falls back by the same height. Again he climbs up 2 metre but he falls back by 1 metre. Once again he climbs up 3 metre but he falls back by 1 metre. Again he climbs up 4 metre but he falls back by 1 metre. In this way he reaches at the top of the pole. If it is known that the monkey needs 10 seconds for 1 metre in upward direction and 5 seconds for 1 metre in downward direction, then the total time required by monkey to reach at the top of the pole. For your kind information it must be clear to you that when he will reach on the top, he will not be slip back. The total time required by this monkey to reach on the top of the poll is :

(a) 9 minutes 10 seconds (b) 10 minutes
(c) 8 minutes 20 seconds (d) none of these

2. Which one of the following is correct?

(i) $(123)^{369} > (369)^{123}$ (ii) $(246)^{642} < (642)^{246}$
(iii) $(50)^{50!} = (50!)^{50}$ (iv) $3^{4^5} > 5^{4^3}$

(a) (i) and (ii) (b) (ii) and (iii)
(c) (i) only (d) (i) and (iv)

3. The tens digit of the 2^{248} is :

(a) 1 (b) 7
(c) 5 (d) none of these

4. For a community marriage 300 boys and 300 girls gathered for their marriage. But out of 600 people 200 were from America and 200 from France and rest 200 were from India itself. The rule was that no any person can marry with a person of different ethnicity or nationality. Minimum how many married couples will be formed, after marriage?

(a) 100 (b) 150
(c) 200 (d) none of these

5. The 444th term of the following sequence 1, 2, 3, 10, 11, 12, 13, 20, 21, 22, 23, 30, 31, ... is :

(a) 1331 (b) 17776
(c) 12330 (d) 13330

6. If $P = 3[x] + 5$ and $Q = 4[x + 3] + 6$ and $P : Q = 1 : 2$, where $[x]$ is the greatest integer less than or equal to x then the value of $\left[P + \frac{Q}{2}\right]$ is :

(a) 34 (b) 51
(c) 40 (d) data insufficient

7. The maximum possible value of $a + b + c + d$ will be where $(a + b) = c, (b + c) = d, (c + d) = a$, for every $a, b, c, d \in I^+$:

(a) -4 (b) 0
(c) 16 (d) can't be determined

8. The number of divisors of 720 which are multiples of perfect square of first prime number is :

(a) 12 (b) 14
(c) 18 (d) can't be determined

9. The number of zeros which are not possible at the end of the $n!$ is :

(a) 82 (b) 73
(c) 156 (d) none of these

Directions for questions number 10 and 11 : The following sequence is given below :

1, 3, 3, 3, 5, 5, 5, 5, 5, 7, 7, 7, 7, 7, 7, 9, 9, 9, 9, 9, 9, 9, 9, 9, ...

10. The 111th term of this sequence will be :

(a) 111 (b) 19
(c) 21 (d) none of these

11. The sum of the 1st, 3rd, 8th, 15th, 24th, 35th, ..., 99th term will be :

(a) 100 (b) 101
(c) 121 (d) 81

Directions for questions number 12 to 14 : The following sequence is given below :

1, 2, 2, 3, 3, 3, 4, 4, 4, 4, 5, 5, 5, 5, 5, 6, 6, 6, 6, 6, 6, ... etc.

12. The sum of the first 100 terms of this sequence is :

(a) 945 (b) 358350
(c) 1001 (d) none of these

13. The 77th element is :

(a) 10 (b) 12
(c) 15 (d) 13

14. The sum of the 1st, 2nd, 4th, 7th, 11th, 16th, ..., 211th terms is :

(a) 221 (b) 400
(c) 231 (d) 211

15. Which one of the following is true?

(i) The least positive value of n for which $n!$ can be divided by $(n + 1)$ is 5

(ii) The square root of 123454321 is 1111

(iii) The sum of the squares of the first 24 natural numbers is a perfect square

(a) (i) and (ii) (b) (ii) and (iii)
(c) (i) and (iii) (d) all of these

16. The number of zeros at the end of $1^{99} \times 2^{98} \times 3^{97} \times ... 99^1$ is :

(a) 1100 (b) 1111
(c) 1099 (d) none of these

Directions for questions number 17 to 20 : Mewalal is selling fruits in Charbagh, Lucknow, which were imported from Kesharbagh and Dayalbagh only. He has 13 apples, 25 bananas, 17 cherries, 29 goose berries, 35 mangoes and 42 pine apples. When I wanted to purchase some fruits from his shop, he told me that he can sell only in lots (i.e., either total apples or total bananas or total cherries etc., but anyhow he can't sell say 12 bananas or 10 apples) and he told me that he himself can import any type of fruits without any lot, say 20 mangoes from Kesharbagh and 15 mangoes from Dayalbagh and so on if he wished.

Scanned by CamScanner

yoursmahboob.wordpress.com

17. Mewalal sold some fruits and then he told me that he is now left with twice the fruits of Kesharbagh than that of Dayalbagh. The number of fruits of Dayalbagh left after this selling is :
(a) 35 (b) 43
(c) 46 (d) can't be determined

18. In the above question (no. 17) how many lots or category of fruits from A, B, C, G, M, P he has sold?
(a) 1 (b) 2
(c) 3 (d) can't be determined

19. As per the given constraints if Mewalal has sold some fruits in such a way that he is now left with $\frac{3}{4}$ fruits of Dayalbagh than that of Kesarbagh. Maximum how many lots (*i.e.*, categories) of fruits he can sell out in such a way?
(a) 1 (b) 2
(c) 3 (d) can't be determined

20. If all the fruits were bought by a single person and were distributed equally among maximum possible number of children and each child has must received more than one fruit, then minimum how many children had received different kind of fruits?
(a) 2 (b) 3
(c) 4 (d) can't be determined

21. Total number of factors of the expression $62^3 - 54^3 - 8^3$ is :
(a) 60 (b) 62
(c) 46 (d) can't be determined

22. The least possible number with which (180)! should be multiplied so that it can be divided by $(45)^{44}$ is :
(a) 44 (b) 25
(c) 9 (d) none of these

23. If $P = abc$ and $Q = uv$ are three digits and 2 digits two natural numbers respectively, such that u and v must be distinct integers. How many pairs of P and Q are there in total which gives the same result when we multiply abc with uv as the product of cba with vu (*i.e.*, the position of digits is inter changed) :
(a) 2 (b) 8
(c) 5 (d) can't be determined

24. There is a three digits number 'abc' and a two digit number 'xy' such that the product of 'abc' with 'xy' is same as the product of cba with 'yx', if x and y can be similar digits, then the number of such pairs of P and Q is :
(a) 99 (b) 900
(c) 810 (d) can't be determined

25. If $(N)_{10} = (ab)_n$ and $(3N)_{10} = (ba)_n$; where $3 < n < 10$, then the least possible value of n is :
(a) 4 (b) 6
(c) 7 (d) can't be determined

26. At his birthday party Pravesh invited his 100 friends and they took their seats numbered as 1, 2, 3, ..., 100. Starting from seat number 1 every third guest was served with Chapatis, every fourth guest was served with Poori and every fifth guest was served with Dahibara and the remaining guests were served with coca-cola only. How many guests enjoyed coca-cola in that party?
(a) 33 (b) 13
(c) 41 (d) can't be determined

27. In the above question (no. 26) if Pravesh served every guest who were sitting on the chair number 3, 6, 9, 12, 15, ... etc. with chapatis and to those who were, sitting on the chair number 5, 10, 15, 20, ... etc. with poori and to the rest with Idli. The number of guests who has not received the Idlis is :
(a) 38 (b) 47
(c) 41 (d) none of these

28. The number of ways in which 5^7 can be expressed as a product of three factors :
(a) 7 (b) 8
(c) 9 (d) none of these

29. If $[x]$ means the greatest integer less than or equal to x and $\{x\}$ means the least integer greater than or equal to x and $|x|$ means the absolute value of x, then $\{x\} - [x]$ equals to :
(a) -1 (b) 0
(c) 1 (d) any one of (a), (b), (c)

30. In the previous question if x is not an integer then the value of $|\{x\} - [x]|$ is :
(a) 0 (b) -1
(c) 1 (d) either (a) or (c)

31. If mnp is a three digit number such that :
$m^3 + n^3 + p^3 = mnp = \Sigma(n!)$, then the value of $m \times n \times p$ is :
(a) 30 (b) 21
(c) 15 (d) none of these

32. A square field is fenced by fixing the polls all around it in such a way that in each side of the field the farmer fixed 19 polls. The total number of polls required to fence the field is :
(a) 76 (b) 75
(c) 72 (d) 80

33. Swarn Jayanti Park is a regular hexagonal park, around which there are 'n' trees on each side. Which of the following can't be the total number of trees around it?
(a) 74070 (b) 81474
(c) 591 (d) 325960

34. Pentabhai purchased the ticket of a movie for all his 200 friends. Luckily he was the first person to buy the ticket for the evening show. So he got the tickets number 1, 2, 3, 4, 6, 7, ... etc. Since he denied to have the tickets on which the digit '5' is printed as the part of ticket number. The last ticket number which he has purchased if no one else has bought the tickets until he has purchased for all his friends.
(a) 244 (b) 242
(c) 222 (d) can't be determined

35. The expression
$N = \frac{1}{1+1\times1} + \frac{1}{2+2\times2} + \frac{1}{3+3\times3} + \frac{1}{4+4\times4} + \ldots$
$\frac{1}{n+n\times n}$, where $n = 100$, then value of N is :
(a) $\frac{100}{101}$ (b) $\frac{99}{100}$
(c) 9900 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

36. Anjuli has written all the letters (or characters) of English alphabets (*i.e.*, *A, B, C, D, ... Y, Z*) horizontally in a single line. She started counting as *A*-1, *B*-2, *C*-3, *D*-4, ... *Y*-25, *Z*-26 and reversed back as *Y*-27, *X*-28, *W*-29, *V*-30, ... *B*-50, *A*-51 and further reversed back as *B*-52, *C*-53, *D*-54, ... etc. She continued counting till she reached the 777th character. At which letter or character she stopped counting?
(a) *Y* (b) *B*
(c) *R* (d) none of these

37. The reading style of Sunny is quite unusual. He reads one page on the first day, 2 pages on the second day, 3 pages on the third day etc. How many pages Sunny can read in 24 days?
(a) 242 (b) 300
(c) 276 (d) none of these

38. All the natural numbers less than 1000 but not containing the digit '5' are arranged horizontally in descending order. What is the 555th number on the list?
(a) 111 (b) 212
(c) 213 (d) none of these

39. A shopkeeper told me when I have asked him the total number of cellphones in his shop, that he had all Kyocera except three, all Nokia except three, all samsung except three and all L.G. except three. The number of mobile (*i.e.*, cell phones) he had is :
(a) 24 (b) 256
(c) can't be determined (d) none of these

40. The number of zeros at the end of the product of all the prime numbers between 1 and 1111 is :
(a) 222 (b) 21
(c) can't be determined (d) none of these

Test of Your Learning-2

1. The remainder when 888222688222888222 ... upto 9235 digits is divided by 5^3 is :
(a) 103 (b) 38
(c) can't be determined (d) none of these

2. Shakuntala asked Aryabhatta to assume any two values of three digits say *P* and *Q* then she told him to multiply *P* by *R* and *Q* by *S* where the values of *R* and *S* were given by Shakuntala herself. Aryabhatta exactly told her the values of $PR \div QS = 888222$. Then Shakuntala told him the value of *P* by *Q* (*i.e.*, *P*/*Q*) is :
(a) 1/4 (b) 4
(c) can't be determined (d) none of these

3. In the above question the value of $P + Q$ is :
(a) 1001 (b) 1110
(c) 3108 (d) none of these

4. The sum of the following series
$(1^2 + 1) + (2^2 + 2) + (3^2 + 3) + (4^2 + 4) + ... + (n^2 + n)$ is :
(a) n^3 (b) $\frac{(n^2 + n)5}{3}$
(c) $\frac{n(n+1)(n+2)}{3}$ (d) can't be determined

Directions for questions number 5 to 8 : *Earlier when I attended a close door meeting to discuss the outsourcing of CAT papers. Including the chairman there were n people viz. A, B, C, D, E, F, ... etc.*
As per the convention everyone has gotten some chocolates in the following manner. As A, B, C, D, E, ... etc. have received 1, 2, 3, 4, 5, ... etc. chocolates respectively. Before anyone has eaten a bit of chocolate, due to some urgent call, the chairman left the meeting with his chocolates. Later on the rest attendants recollected their chocolates in a box and then redistributed all the chocolates evenly among themselves and thus everyone has received 13 chocolates.

5. Who is the Chairman of the meeting?
(a) A (b) Q
(c) M (d) can't be determined

6. Total number of people, initially who have attended the meeting is :
(a) 18 (b) 25
(c) 30 (d) can't be determined

7. Minimum number of person who attended the party can be:
(a) 18 (b) 15
(c) 24 (d) can't be determined

8. As per the question number 7, maximum how many chocolates were there to be received by all of them, initially?
(a) 300 (b) 676
(c) 351 (d) none of these

Directions for questions number 9 to 10 : *Under the scheme of Kisan Vikas, the Govt. of U.P. purchased 't' number of tractors and these were allocated equally among 7 districts of U.P. and thus 4 tractors remained unallocated. Similarly every district allocated these tractors equally to 10 blocks in each district and still 3 tractors remained without allocation, in every district. Further every block assigned these tractors equally to every 16 village in each block and thus 2 tractors per block remained unallocated.*
According to the scheme every village must receive at least one tractor.

9. The number of tractors allocated to each block is :
(a) 18 (b) 30
(c) 34 (d) can't be determined

10. If the state govt. of U.P. purchased '*k*' tractors to provide exactly 1 tractor to each village as mentioned in the scheme but later on it has sent one tractor to each village of U.P. (as mentioned in the scheme) directly without any involvement of a block or a district. The number of tractors which the govt. of U.P. has saved more in comparison to the previous scheme.
(a) 161 (b) 181
(C) 24 (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

11. If 2^n can exactly divide $p!$ Such that the quotient is an odd positive integer, then the value of n which is not possible is :
(a) 43 (b) 44
(c) 45 (d) all of these

12. Each of the numbers $x_1, x_2, x_3, x_4, x_5, \ldots, x_n, x_n \geq 4$ is equal to -1 or 1. If $x_1x_2x_3 + x_2x_3x_4 + x_3x_4x_5 + \ldots x_{n-3}x_{n-2}x_{n-1} + x_{n-2}x_{n-1}x_n = 0$, then the value of n is :
(a) odd (b) even
(c) prime (d) multiple of 3

13. In the above question number 12, the minimum number of x_i (*i.e.*, $x_1, x_2, x_3, \ldots, x_n$) are equal to -1, is :
(a) $\frac{n}{3}$ (b) $\frac{n}{2}$
(c) $\frac{(n-2)}{2}$ (d) can't be determined

14. If in the above question (no. 13) the value of x_i is either 0 or 1 only (*i.e.*, each of $x_1, x_2, x_3, \ldots, x_n$ is either zero or 1) then the minimum number of x_i, such that $x_i = 0$ is required, when $n = 6, 12, 18, 24, \ldots$ etc.
(a) $\frac{n}{3}$ (b) $\frac{(n+2)}{3}$
(c) $\frac{(n-2)}{2}$ (d) none of these

15. If $m + n = mn - 5$, then the maximum number of ordered pairs of (m, n) for every m, n is a natural number.
(a) 4 (b) 5
(c) 6 (d) none of these

16. At the eve of marriage anniversary of Tristan and Iseult some special couples were invited. Out of them only 23 couples were there having one child per couple with them. When I observed it, I found that 13 men were without any child and 20 women were also without any child. It is known that there were only couples allowed to attend the ceremony. For your kind information we will not consider the couple (*i.e.*, Tristan and Iseult) for any calculation, since they are hosts. The total number of couples who attended the party (*i.e.*, anniversary).
(a) 28 (b) 30
(c) 33 (d) can't be determined

17. The number of numbers less than or equal to 666 which are the products of exactly 4 distinct positive prime numbers is :
(a) 4 (b) 8
(c) 7 (d) can't be determined

18. Tata, Hutch and Idea started of with a game. The rule is that the loser of the game distributes $\frac{1}{3}$rd of his money amongst the other two players in the ratio of the amount as they are holding with them. After playing three round game Tata, Hutch and Idea endup with Rs. 450, 150 and 300 respectively. The total amount of money what they were initially holding is :
(a) 575 (b) 750
(c) $\frac{5}{4}(6!)$ (d) can't be determined

19. Remainder when $4^{4^n} + 3$ is divided by 7 is :
(a) 0 (b) 1
(c) 5 (d) none of these

20. All the soldiers are arranged in the form of an equilateral triangle *i.e.*, one soldier in the front and 2 soldiers in the second row and 3 soldiers in the third row, 4 soldiers in the fourth row and so on. If 669 more soldiers of another company are added in such a way that all the soldiers now are in the form of an square and each of the sides then contain 8 soldiers less than each side of equilateral triangle. Initially, how many soldiers were there?
(a) 2056 (b) 1540
(c) 1400 (d) 1220

21. A natural number when divided by the quotient, which in turn obtained by dividing the leading digit by the unit digit of the same number, we get another number consisting of the same digits, but in reverse order. The original number is :
(a) 98658823 (b) 91703
(c) 87912 (d) 27918

22. One day my friend Dorsey told me from LA, that he gets the same salary in each month but when he adds up his six figure salary of two months, three months, four months, five months or six months each time the figures (or digits) of his salary remains the same, but not in a fix order. Later, he told me that when he add up his salary of 7 months his total salary become $(10^6 - 1)$. What is the salary of Dorsey?
(a) 123456 (b) 285614
(c) 142857 (d) can't be determined

23. A leading chocolate producing company produces '*abc*' chocolates per hour (*abc* is a three digit positive number). In how many hours it will produce '*abcabc*' chocolates?
(a) *abc* (b) 101
(c) 1001 (d) can't be determined

24. A number D236D0 can be divided by 36 if D is :
(a) 8
(b) 6
(c) 1
(d) more than one values are possible

25. In the christmas eve of his 7th birthday anniversary, Martin, the eldest son of his parents, went to picnic with all his family members. There his family purchased the tickets for everyone. The entire family consists of 3 children, 1 grand father, 1 grand mother, two fathers and two mothers 1 brother and 1 sister. Also there is one daughter-in-law, one father in law, one mother in law. Minimum how many tickets his family has purchased for the entire family?
(a) 5 (b) 6
(c) 8 (d) 14

26. In the above question (no. 25), if the rate of a ticket for a child (considered to be unmarried and below 18 years) is Rs. 6, while the price of a ticket for an adult (*i.e.*, married and above 18) is Rs. 10. So what is the minimum price has to pay for the tickets?
(a) Rs. 52 (b) Rs. 58
(c) Rs. 90 (d) data insufficient

Scanned by CamScanner

yoursmahboob.wordpress.com

27. Which one of the following is not the correct relation?
(a) $(25)^3 + (38)^3 + (87)^3 = (90)^3$
(b) $(3)^3 + (4)^3 + (5)^3 = (6)^3$
(c) $(17)^3 + (29)^3 = (57)^3$
(d) $1^3 + 6^3 + 8^3 = 9^3$

28. In a college of 300 students, every student reads 5 newspapers and every newspapers is read by 60 students. The number of newspapers is :
(a) at least 30
(b) at most 20
(c) 25
(d) none of (a), (b) and (c)

29. At East End Mall, burgers can be bought in quantities of either 6, 9 or 20 only. For example one can purchase 26 (20 + 6), 15 (6 + 9) and 24 (9 × 2 + 6) etc. but can't purchase 10 burgers *i.e.*, without any lot. What is largest number of burgers that can not be purchased?
(a) 83 (b) 37
(c) can't be determined (d) none of (a), (b), (c)

30. Let there be a fraction whose denominator is one less than the square of its numerator. If we add 2 to both the numerator and denominator, the fraction will exceed to $\frac{1}{3}$ and if we subtract 3 from numerator and denominator the fraction will lie between 0 and $\frac{1}{10}$. The actual fraction is :
(a) $\frac{3}{8}$ (b) $\frac{7}{48}$
(c) $\frac{4}{17}$ (d) none of these

31. When a two digit number is subtracted from another two digits number consisting of the same digits in reverse order, then the resultant value we get is equal to the sum of the digits of that number. The square of sum of digits of that number can be :
(a) 49 (b) 64
(c) 81 (d) 36

32. If $A = [k^3 + (k+2)^3 + (k+4)^3 + (k+6)^3 + (k+8)^3 + \ldots (k+38)^3]$ and
$B = [k + (k+2) + (k+4) + (k+6) + (k+8) + \ldots (k+38)]$
Now, if 'A' is divided by 'B', then the remainder will be (for every positive integer k) :
(a) 0 (b) 1
(c) k (d) none of these

33. If $1^3 = 1$, $2^3 = 3 + 5$, $3^3 = 7 + 9 + 11$, $4^3 = 13 + 15 + 17 + 19$, $5^3 = 21 + 23 + 25 + \ldots + 29$, etc. Then the value of $(100)^3$ is equal to :
(a) $9901 + 9903 + \ldots + 10099$
(b) $9999 + 10001 + 10003 + \ldots + 10199$
(c) $9989 + 9991 + \ldots + 10089$
(d) Any two of (a), (b), (c)

34. If $\{x\}$ denotes the fractional part of x, then $\left\{\frac{5^{200}}{8}\right\}$ is :
(a) 1/8 (b) 1/4
(c) 5/8 (d) 0.625

35. Which one of the following is correct?
(a) $25^{26} > 26^{25}$ (b) $100^{101} < 101^{100}$
(c) $199^{199} > 198^{199}$ (d) $399^{400} < 400^{399}$

36. If x and y are positive prime number and if $x^2 - 2y^2 = 1$, then the value of $x + y$ is :
(a) 7 (b) 24
(c) 13 (d) none of these

37. The greatest possible divisor of $3^{2n+3} - 24n - 27$ for every $n \in N$, which necessarily divides is :
(a) 64 (b) 24
(c) 96 (d) none of these

38. If $(\sqrt{3} + 1)^5 = I + F$, where I is an integer and F is a proper fraction, then the value of $F.(I + F)$ is :
(a) $(\sqrt{3})^5$ (b) 32
(c) $(1.99)^5$ (d) 31.232

39. When the product of 'r' consecutive positive integers is divided by 'r!', then the quotient is :
(a) any natural number (b) a perfect square
(c) a proper fraction (d) either (b) or (a)

40. Two digits p, q, where $q > p > 1$ such that $p + q < pq$ and $(p + q)$, $(p + q)^n$, $(p + q)^{n+1}$ have the same unit digits and $(p.q)$, $(p.q)^n$, $(pq)^{n+1}$ have the same unit digits. The value of p is :
(a) 2 (b) 3
(c) 4 (d) 5

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-1.1

1. (d)	2. (a)	3. (c)	4. (c)	5. (d)	6. (d)	7. (c)	8. (b)	9. (c)	10. (b)
11. (c)	12. (c)	13. (b)	14. (a)	15. (a)	16. (b)	17. (b)	18. (c)	19. (d)	20. (a)
21. (d)	22. (a)	23. (c)	24. (c)	25. (d)	26. (b)	27. (b)	28. (d)	29. (d)	30. (b)
31. (d)	32. (a)	33. (b)	34. (c)						

INTRODUCTORY EXERCISE-1.2

1. (c)	2. (d)	3. (b)	4. (d)	5. (d)	6. (d)	7. (b)	8. (b)	9. (c)	10. (c)
11. (c)	12. (d)	13. (d)	14. (d)	15. (a)					

INTRODUCTORY EXERCISE-1.3

1. (d)	2. (d)	3. (a)							

INTRODUCTORY EXERCISE-1.4

1. (d)	2. (d)	3. (b)	4. (d)	5. (d)	6. (d)	7. (d)	8. (c)	9. (b)	10. (a)
11. (b)									

INTRODUCTORY EXERCISE-1.5

1. (a)	2. (a)	3. (b)	4. (b)	5. (a)	6. (c)	7. (a)	8. (a)	9. (a)	10. (a)

INTRODUCTORY EXERCISE-1.6

1. (a)	2. (b)	3. (c)	4. (c)	5. (c)					

INTRODUCTORY EXERCISE-1.7

1. (c)	2. (b)	3. (a)	4. (a)	5. (b)	6. (a)	7. (d)	8. (b)	9. (c)	10. (d)
11. (a)	12. (b)								

MISCELLANEOUS

1. (a)	2. (a)	3. (b)	4. (a)	5. (a)	6. (d)	7. (b)	8. (d)	9. (b)	10. (b)
11. (b)	12. (c)	13. (d)	14. (c)	15. (a)	16. (d)	17. (d)	18. (c)	19. (d)	20. (d)
21. (d)	22. (c)	23. (d)	24. (a)	25. (b)	26. (b)	27. (d)	28. (b)	29. (a)	30. (c)
31. (a)	32. (d)	33. (a)	34. (a)	35. (a)	36. (a)	37. (a)	38. (d)	39. (a)	40. (d)
41. (d)	42. (d)	43. (d)	44. (d)	45. (a)	46. (b)	47. (a)	48. (b)	49. (a)	50. (c)
51. (a)	52. (c)	53. (c)	54. (b)	55. (c)	56. (d)	57. (c)	58. (d)	59. (d)	60. (c)
61. (a)	62. (a)	63. (d)	64. (a)	65. (b)	66. (c)	67. (c)	68. (a)	69. (d)	70. (b)
71. (a)	72. (d)	73. (b)	74. (b)	75. (b)	76. (a)	77. (b)	78. (a)	79. (d)	80. (c)
81. (a)	82. (a)	83. (c)	84. (c)	85. (b)	86. (d)	87. (c)	88. (d)	89. (d)	90. (d)
91. (b)	92. (b)	93. (c)	94. (d)	95. (c)	96. (d)	97. (c)	98. (b)	99. (c)	100. (d)
101. (c)	102. (c)	103. (d)	104. (a)	105. (c)	106. (c)	107. (d)	108. (a)	109. (b)	110. (c)
111. (b)	112. (d)	113. (a)	114. (b)	115. (c)	116. (a)	117. (c)	118. (d)	119. (c)	120. (d)
121. (c)	122. (d)	123. (a)	124. (b)	125. (c)	126. (b)	127. (a)	128. (a)	129. (b)	130. (a)
131. (c)	132. (b)	133. (b)	134. (c)	135. (c)	136. (d)	137. (d)	138. (b)	139. (c)	140. (c)

LEVEL-1

1. (b)	2. (b)	3. (b)	4. (b)	5. (c)	6. (c)	7. (a)	8. (d)	9. (d)	10. (d)
11. (c)	12. (b)	13. (d)	14. (b)	15. (d)	16. (b)	17. (c)	18. (b)	19. (c)	20. (c)
21. (d)	22. (b)	23. (d)	24. (c)	25. (b)	26. (a)	27. (a)	28. (d)	29. (d)	30. (a)
31. (c)	32. (b)	33. (b)	34. (d)	35. (d)	36. (c)	37. (d)	38. (c)	39. (c)	40. (c)

Scanned by CamScanner

yoursmahboob.wordpress.com

41. (b)	42. (c)	43. (c)	44. (d)	45. (a)	46. (c)	47. (b)	48. (b)	49. (c)	50. (a)
51. (a)	52. (b)	53. (b)	54. (c)	55. (b)	56. (d)	57. (b)	58. (b)	59. (c)	60. (d)
61. (c)	62. (c)	63. (b)	64. (c)	65. (d)	66. (c)	67. (d)	68. (c)	69. (c)	70. (d)
71. (b)	72. (b)	73. (b)	74. (d)	75. (b)	76. (b)	77. (b)	78. (a)	79. (c)	80. (d)
81. (c)	82. (b)	83. (c)	84. (c)	85. (b)	86. (b)	87. (c)	88. (c)	89. (d)	90. (b)
91. (b)	92. (b)	93. (d)	94. (b)	95. (d)	96. (a)	97. (a)	98. (d)	99. (b)	100. (c)
101. (d)	102. (b)	103. (c)	104. (b)	105. (a)	106. (b)	107. (b)	108. (c)	109. (b)	110. (b)
111. (b)	112. (c)	113. (c)	114. (a)	115. (b)	116. (a)	117. (c)	118. (a)	119. (a)	120. (b)
121. (d)	122. (b)	123. (c)	124. (d)	125. (d)	126. (a)	127. (c)	128. (d)	129. (c)	130. (b)
131. (d)	132. (c)	133. (b)	134. (c)	135. (b)	136. (c)	137. (c)	138. (c)	139. (c)	140. (b)

LEVEL-2

1. (b)	2. (d)	3. (c)	4. (c)	5. (d)	6. (c)	7. (b)	8. (c)	9. (b)	10. (d)
11. (c)	12. (d)	13. (a)	14. (d)	15. (a)	16. (a)	17. (c)	18. (b)	19. (d)	20. (b)
21. (b)	22. (b)	23. (a)	24. (a)	25. (b)	26. (d)	27. (a)	28. (d)	29. (c)	30. (c)
31. (h)	32. (b)	33. (b)	34. (b)	35. (c)	36. (b)	37. (d)	38. (a)	39. (c)	40. (a)
41. (b)	42. (b)	43. (a)	44. (b)	45. (c)	46. (b)	47. (a)	48. (b)	49. (d)	50. (b)
51. (d)	52. (c)	53. (c)	54. (b)	55. (c)	56. (d)	57. (b)	58. (a)	59. (d)	60. (d)
61. (b)	62. (d)	63. (c)	64. (d)	65. (a)	66. (c)	67. (c)	68. (c)	69. (c)	70. (d)
71. (b)	72. (b)	73. (d)	74. (a)	75. (a)	76. (a)	77. (a)	78. (a)	79. (b)	80. (b)
81. (d)	82. (c)	83. (a)	84. (a)	85. (a)	86. (a)	87. (b)	88. (a)	89. (d)	90. (a)
91. (b)	92. (b)	93. (a)	94. (b)	95. (d)	96. (a)	97. (c)	98. (c)	99. (c)	100. (d)
101. (c)	102. (c)	103. (c)	104. (a)	105. (a)	106. (a)	107. (b)	108. (c)	109. (c)	110. (d)
111. (c)	112. (a)	113. (c)	114. (a)	115. (c)	116. (d)	117. (b)	118. (b)	119. (c)	120. (b)
121. (d)	122. (a)	123. (a)							

FINAL ROUND

1. (a)	2. (b)	3. (b)	4. (a)	5. (c)	6. (a)	7. (c)	8. (a)	9. (b)	10. (c)
11. (d)	12. (d)	13. (d)	14. (b)	15. (d)	16. (b)	17. (b)	18. (a)	19. (b)	20. (c)
21. (b)	22. (c)	23. (b)	24. (d)	25. (c)	26. (d)	27. (b)	28. (b)	29. (b)	30. (a)
31. (d)	32. (b)	33. (c)	34. (a)	35. (a)	36. (d)	37. (a)	38. (b)	39. (c)	40. (b)
41. (b)	42. (a)	43. (d)	44. (d)	45. (a)	46. (b)	47. (d)	48. (d)	49. (d)	50. (d)
51. (d)	52. (a)	53. (c)	54. (d)	55. (d)	56. (a)	57. (d)	58. (a)	59. (d)	60. (b)
61. (a)	62. (a)	63. (b)	64. (c)	65. (d)	66. (c)	67. (a)	68. (b)	69. (a)	70. (b)
71. (c)	72. (c)	73. (b)	74. (c)	75. (d)	76. (c)	77. (c)	78. (d)	79. (a)	80. (d)
81. (c)	82. (d)	83. (a)	84. (b)	85. (c)	86. (b)	87. (c)	88. (c)	89. (b)	90. (d)
91. (b)	92. (b)	93. (a)	94. (c)	95. (c)	96. (b)	97. (a)	98. (a)	99. (b)	100. (a)
101. (c)	102. (c)	103. (d)	104. (a)	105. (b)	106. (c)	107. (d)	108. (a)	109. (c)	110. (c)
111. (c)	112. (d)	113. (c)	114. (a)	115. (a)	116. (a)				

TEST OF YOUR LEARNING-1

1. (a)	2. (d)	3. (c)	4. (a)	5. (c)	6. (a)	7. (d)	8. (c)	9. (b)	10. (c)
11. (a)	12. (a)	13. (b)	14. (c)	15. (c)	16. (a)	17. (d)	18. (d)	19. (b)	20. (a)
21. (a)	22. (d)	23. (b)	24. (c)	25. (c)	26. (a)	27. (b)	28. (b)	29. (d)	30. (c)
31. (c)	32. (c)	33. (d)	34. (b)	35. (a)	36. (a)	37. (b)	38. (c)	39. (d)	40. (d)

TEST OF YOUR LEARNING-2

1. (a)	2. (c)	3. (b)	4. (c)	5. (d)	6. (d)	7. (c)	8. (c)	9. (d)	10. (a)
11. (d)	12. (b)	13. (c)	14. (a)	15. (a)	16. (a)	17. (c)	18. (c)	19. (a)	20. (b)
21. (c)	22. (c)	23. (c)	24. (a)	25. (b)	26. (a)	27. (c)	28. (c)	29. (d)	30. (d)
31. (c)	32. (a)	33. (a)	34. (a)	35. (a)	36. (d)	37. (d)	38. (b)	39. (a)	40. (a)

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 10.1

1. As per the given choices first of all we check it by 99 since in the question largest possible number of two digits is being asked.
Now, since $(2+7+7+2)-(8+9+1)=18-18=0$
Hence it is divisible by 11
again $2+1+7+9+7+8+2=36$
Hence it is also divisible by 9.
Thus we can say that the given number 2179782 is divisible by 99 $(=11\times 9)$
So, the option (d) is correct answer.

2. A number which is multiple of 125 must be divisible by 125. So the number formed by last three digits must be divisible by 125 hence it can be 000, 125, 250, 375, 500, 675, 750, 875.
So the number which is divisible by 125 must be 9999875 since we have to subtract minimum possible number. Thus we see that we have to subtract 124.
[$\because$ 9999999 – 9999875 = 124]
Alternatively : Divide 9999999 by 125 and then the obtained remainder is the required result.

3. As per the divisibility rule of 11, the difference of sum of the digits at odd places and sum of the digits at even places be either 0, 11, 22, 33, ... etc. So n must be an even number. Correct choice is (c).
Alternatively : Go through the options. Now when you write prime of any odd value of n you will find odd prime or odd number of nines then you will also observe that these numbers are not divisible by 11.
Further using option (c) you will find that it is always correct for any even number. Thus option (c) is correct.

4. If we look at the options we see that option (a) is not correct since in the first instance it is not divisible by 4. Again if we look at option (b) we see that it is not divisible by 3. Similarly option (d) is wrong because it is not divisible by 11 and at last when we check the option (c) then we find it is correct. Remember a number is divisible by 132 if the number is divisible by its factors as 3, 4, and 11 simultaneously as $132=3\times 4\times 11$
Thus option (c) is correct.

5. Since $80=8\times 10$ or $80=16\times 5$
Thus y (*i.e.*, unit digit) must be zero.
$\therefore$ $653xy = 653x0$, where $653x0$ must be divisible by 16 or $653x$ is divisible by 8.
Thus the last 3-digit number $53x$ will be divisible by 8.
Hence, at $x=6$, we get the required result.
$\therefore$ $x+y=6+0=6$

6. The best way to use the options
Alternatively : $(4+6+3)-(2+5+k)=0/11/22\ldots$
$(13)-(7+k)=0$ [$\because$ 11/22 ... are not possible]
$\Rightarrow$ $k=6$
Hence option (d) is correct.

7. The quickest method is to use appropriate option. As the divisor is 72 so the given number must be divisible 9 and 8 both. Therefore, it is clear that option (b) and (d) are useless, since unit digit can't be odd inorder to be divisible by 8. Now option (a) and (c) can be tried out. Thus we can get the value of $k=6$. Hence option (c) is correct.

8. The first number which is divisible by 7 is 7 and the last number is 994. It can be easily calculated just by dividing 1000 by 7 and then subtract the remainder from 1000. So total numbers between 1 and 1000 which are divisible by 7 are 142.The sequence is as follows 7, 14, 21, 28, 35, ... 987, 994.

9. The sequence is as follows 55, 60, 65, 70, ..., 550, 555. So the number of number divisible by 5 is $\left(\frac{555-55}{5}\right)+1=101$
Note we have added 1 from outside because here both the extremes (i.e., 55 and 555) are included.
SHORTCUT If D be the divisor of numbers lying between N_1 and N_2, $N_2 > N_1$ then the number of numbers which are divisible by D (or multiple of D) is
(a) When no one extreme is divisible by such a divisor D :
$$\left(\frac{N_2-N_1}{D}\right)-1$$
(b) When any one of the extreme is divisible by D :
$$\left(\frac{N_2-N_1}{D}\right)$$
(c) When both the extremes are divisible by D is :
$$\left(\frac{N_2-N_1}{D}\right)+1$$

10. $(200-100)+1=101$
Alternatively : Since you know that you are counting the numbers from 100, so only 99 numbers (1, 2, 3, ..., 99) are not included
i.e., 1, 2, ... 99, 100, 101, 102, 103, ..., 200.
Hence total numbers = 200 – 99 = 101.

11. The first number which is divisible by 3 is 300 and the last number which is divisible by 3 is 498.
So, the total numbers $=\left(\frac{498-300}{3}\right)+1=66+1=67$
Hence (c) is the correct option.
Alternatively : When we form the sequence of numbers which are divisible by 3, the number 300 is lying at the 100th position and 498 at the 166th position (i.e., 3, 6, 9, 12, ... 297, 300, 303, 306, ..., 498) so there are total 166 numbers upto 498 but 99 numbers are not included in this sequence. Thus the required numbers are 166 – 99 = 67 numbers, which are divisible by 3.

12. In the given range, the least number which is divisible by both 5 and 7, i.e., 35 is 210 and the highest number is 770. So the total number of numbers between 200 and 800 which are divisible by both 5 and 7 is $\left(\frac{770-210}{35}\right)+1=17$
Hence option (c) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

13. Total numbers in the set are

$$(800 - 200) + 1 = 601$$

Total number of numbers which are divisible by 5

$$= \frac{(800 - 200)}{5} + 1 = 121$$

Total number of numbers which are divisible by 7

$$= \frac{(798 - 203)}{7} + 1 = 86$$

Total number of numbers which are divisible by both 5 and 7

$$= \frac{770 - 210}{35} + 1 = 17$$

So the total number of numbers which are either divisible by 5 or 7 or both $= (121 + 86) - 17 = 190$

Hence option (b) is correct.

14. Total numbers in the set $= (800 - 200) + 1 = 601$

Number of numbers which are divisible by 5

$$= \frac{(800 - 200)}{5} + 1 = 121$$

Number of numbers which are divisible by 7

$$= \frac{(798 - 203)}{7} + 1 = 86$$

Number of numbers which are divisible by both 5 & 7

$$= \left(\frac{770 - 210}{35}\right) + 1 = 17$$

$\therefore$ Number of numbers which are either divisible by 5 or 7 or both

$$= (121 + 86) - 17 = 190$$

Thus the number of numbers in the given set which are neither divisible by 5 nor by 7 = 601 − 190 = 411.

Hence (a) is correct option.

15. To find the answer of this problem first of all we need to calculate total number of numbers in the given set which are divisible by any of 2, 3 or 5 then these numbers will be subtracted from the total number of the original set of numbers. Thus we get the total number of numbers which are neither divisible by 2, 3 or 5.

Total numbers in the set $= (3113 - 1331) + 1$

$$= 1782 + 1 = 1783$$

Total number of numbers in the set which are divisible by 2

$$= \left(\frac{3112 - 1332}{2}\right) + 1 = 891$$

Total numbers divisible by $3 = \left(\frac{3111 - 1332}{3}\right) + 1 = 594$

Total numbers divisible by $5 = \left(\frac{3110 - 1335}{5}\right) + 1 = 356$

Total numbers which are divisible by 2 and 3 both

$$= \left(\frac{3108 - 1332}{6}\right) + 1 = 297$$

Total numbers which are divisible by 3 and 5 both

$$= \left(\frac{3105 - 1335}{15}\right) + 1 = 119$$

Total numbers which are divisible by 2 and 5 both

$$= \left(\frac{3110 - 1340}{10}\right) + 1 = 178$$

Total numbers which are divisible by 2, 3 and 5

$$= \left(\frac{3090 - 1350}{30}\right) + 1 = 59$$

So, the total number of numbers in the given set which are neither divisible by any of the 2, 3 or 5 = 477.



$\because$ $n(A \cup B \cup C) = [n(A) + n(B) + n(C)]$

$- [n(A \cap B) + n(B \cap C) + n(A \cap C)] + n(A \cap B \cap C)$

So the divisible numbers

$= (891 + 594 + 356) - (297 + 119 + 178) + 59$

$= 1306$

$\therefore$ Number of numbers which are not divisible by 2, 3 or 5.

$$= 1783 - 1306 = 477$$

Hence (a) is the correct option.

Alternatively : Number of numbers in the given set which are only divisible by 2 = 891

the number of numbers which are only divisible by 3, but not by 2

$$= \frac{(3111 - 1335)}{6} + 1 = 297$$

The number of numbers which are only divisible by 5 but not by 2or 3

$$= \left\{\frac{(3105 - 1335)}{10} + 1\right\} - \left\{\frac{(3105 - 1335)}{30} + 1\right\}$$

$$= 178 - 60 = 118$$

So the total number of numbers which are divisible by any of the 2, 3 or 5 = 891 + 297 + 118 = 1306

Thus the total number of numbers which are neither divisible by 2, 3 or 5 = 1783 − 1306 = 477.

16. Just divide 434079 by 137 and then the obtained remainder is your correct answer which is 63, so (b) is the right choice.

17. To make 434079 divisible by 137 we have to add just the difference of remainder and the divisor. So the choice (b) is correct and the answer is 74.

18. Obviously (c) is the right choice because there can be maximum two numbers closest to any particular number. So out of 180 and 198 the number 198 is closer than the number 180 and 195 is not divisible by 18 also 108 is the farthest from 193.

Scanned by CamScanner

yoursmahboob.wordpress.com

19. Since when we multiply the least three digit numbers ($100 \times 100 = 10000$) we get a 5 digit number and when we multiply the greatest possible 3 digit numbers ($999 \times 999 = 998001$) we get a 6 digit number. So anyhow the product of a 3 digit number with another 3 digit number can never be a number of less than 5 digit or greater than 6 digit number. So the option (a) and (c) are ruled out because these are 4 digit and 7 digit numbers respectively.
Further whenever we multiply any two numbers whose unit digits are 7 and 5 individually then the unit digit of the resultant number is always 5 ($\because 5\times1=5,\ 5\times3=15,\ 5\times5=25,\ 5\times7=35,\ 5\times9=45$ and $5\times2=10,\ 5\times4=20,\ 5\times6=30,\ 5\times8=40$, and $5\times10=50$)
Thus the option (b) is also wrong since the required unit digit can never be 6 (i.e., an even number).
Hence the appropriate option is (d).

20.
$$\begin{array}{r} 9\ 8\ 4 \\ +\ 4\ p\ 3 \\ \hline 13\ q\ 7 \end{array}$$

It is clear from the above expression that there is no any carry over obtained in the addition of unit digits. Further it is very simple to see that there is no carry over value taken while adding hundredths digit of both the numbers. So we get
$8 + p = q$
Now if $13q7$ is divisible by 11 then

$$(7+3)-(1+q)=11k \qquad \text{where, } k=0,1,2,\ldots\ldots$$
$$10-(1+q)=0$$
$$\Rightarrow \quad q=9$$

here $k = 0$ is the only possible value because if
$k = 1$ then q must be either -2 or 20.
but neither -2 nor 20 is possible because q is a single positive digit i.e., $q \in 1, 2, 3, 4, 5, 6, 7, 8, 9, 0$.
Thus the value of $p + q = 1 + 9 = 10$ $\quad [\because p = q - 8,\ \therefore p = 1]$
Hence, (a) is the correct option.

21. Since Dividend = Divisor × Quotient + Remainder
$\therefore$ Dividend $= 9235 \times 888 + 222$
Thus the number = 8200902
Hence (d) is the correct choice.

22. Option (a) is correct. There are only two relevant options (a) and (c). Option (b) is redundant since 999 is not divisible by 33. Now 990 and 1023 both are close to 1000 and both are divisible by 33 but it is obvious that 990 is much closer to 1000 than 1023.

23. Let this number be N then
$$N = 32 \times Q_1 + 29 \qquad \ldots(1)$$
Again $\quad N = 8 \times Q_2 + R \qquad \ldots(2)$
From (1) and (2)
$$32Q_1 + 29 = 8Q_2 + R \quad \text{(where } R \text{ is the remainder)}$$
$$8Q_2 - 32Q_1 = 29 - R$$
$$8(Q_2 - 4Q_1) = 29 - R$$
or $$(Q_2 - 4Q_1) = \frac{29-R}{8}$$
Since Q_1, Q_2, R are integers also $Q_2 - 4Q_1$ is an integer. Therefore $29 - R$ must be divisible by 8.
So the probable values of R are 29, 21, 13 and 5.
But since the remainder can never be greater than the divisor so the only possible value of R is 5. Hence (c) is the correct option.
Alternatively : $N = 32Q + 29 = 8 \times 4Q + 8 \times 3 + 5$ (where Q is Quotient)
$$\Rightarrow \quad N = 8(4Q + 3) + 5$$
$$\Rightarrow \quad N = 8P + 5$$
(where p is any positive integer)
Thus the remainder is 5.
Shortcut : In this kind of question where the same number is divided by another divisor (proper factor of the original divisor), we just need to divide the original remainder by the new divisor to get the value of new remainder e.g. when we divide 29 by the new divisor '8' then we get new remainder 5.

24. Let the number be N and the quotient be Q then $N = 5Q + 4$
Again $\quad 2N = 2(5Q + 4) = 10Q + 8$
or $\quad 2N = 5 \times 2Q + 5 + 3$
or $\quad 2N = 5(2Q + 1) + 3$
Hence, the remainder will be 3.
Alternatively : Since the number becomes double then the remainder will also be double but when the remainder will become twice it will exceed the divisor which is not possible so to get the correct remainder we further divide the twice of the remainder by the divisor and in this way we obtain the required remainder which is admissible. For example in the given problem the divisor is 5 and the original remainder is 4. So this remainder will become twice i.e., 8 (since the number i.e.,dividend becomes twice) but since $8 > 5$ which is not possible so we divide 8 by 5 then we get the correct remainder 3.

25. In the first case $\quad N = DQ + 14$
In the second case $3N = 3(DQ + 14)$
$$= 3DQ + 42$$
$$= 3DQ + 34 + 8$$
$$3N = (3DQ + 34) + 8$$
It shows that 34 must be divisible by 34 or its factor *i.e.*, 1,2, 17,34. But 1 and 2 can't be values of D. Since the divisor D must be greater than the remainder (*viz.* 8, 14) Hence we are now left with two possible values of D *viz.* $D = 17$ and $D = 34$
Now, if remainder $D = 17$, then
$$N = 17Q + 14$$
$$4N = 4(17Q + 14) = 4 \times 17Q + 56$$
$$= 17 \times 4Q + 17 \times 3 + 5$$
$$4N = 17(4Q + 3) + 5$$
Thus the remainder will be 5.
But if we consider $D = 34$, then
$$N = 34Q + 14$$
$$4N = 4(34Q + 14)$$
$$= 34 \times 4Q + 56$$
$$= 34 \times 4Q + 34 + 22$$
$$4N = 34(4Q + 1) + 22$$
Thus the remainder will be 22.
Hence we can't say exactly whether the remainder will be 5 or 22. So (d) is the correct option.

Scanned by CamScanner

yoursmahboob.wordpress.com

26. Let the number be N then

$$N = 34Q + R, \quad \ldots(1)$$

where Q is any quotient

Again $N = 5D$ and D is also a quotient

but $D = R + 8$

so $N = 5(R + 8) \quad \ldots(2)$

$\therefore \quad 5(R + 8) = 34Q + R$

$5R + 40 = 34Q + R$

$\Rightarrow \quad 34Q - 40 = 4R$

$\Rightarrow \quad 17Q - 2R = 20$

So the minimum possible value of $Q = 2$ and the corresponding value of $R = 7$

So $N = 34 \times 2 + 7$

$N = 75,$

Hence (b) is correct choice.

27. Let N be the number and d be the divisor then $N = dQ + 15$

Again, $10N = 10(dQ + 15)$

$\Rightarrow \quad 10N = 10dQ + 150$

$\Rightarrow \quad 10N = d\,10Q + 144 + 6$

$\Rightarrow \quad 10N = (d \times 10Q + 144) + 6$

$\Rightarrow \quad 10N = d\left(10Q + \frac{144}{d}\right) + 6$

$\therefore$ 144 must be divisible by d. Thus the probable values of d are 1, 2, 3, 4, 6, 8, 9, 12, 16, 18, 24, 36, 48, 72, 144 (as these numbers are the factors of 144).

But the value of divisor d must be greater than the remainder (here 6 and 15) so 1, 2, 3, 4, 6, 8, 9, 12 can not be the values of d. Hence only 7 values (greater than 15) are possible.

Thus the option (b) is correct.

28. $C = N_1Q_1 + 13$ and $C = N_2Q_2 + 1$

where Q_1 and Q_2 are the quotients and hence Q_1 and Q_2 must be integers

So, $N_1Q_1 + 13 = N_2Q_2 + 1$

$N_2Q_2 - N_1Q_1 = 12$

$\frac{4}{5}N_1Q_2 - N_1Q_1 = 12$

$N_1(4Q_2 - 5Q_1) = 60$

where N_1 and $(4Q_2 - 5Q_1)$ both will be integers so that N_1 can be one of the values of factors of 60 *i.e.*, 1, 2, 3, 4, 15, 20, 30 and 60. But N_1 can not be less than the remainder 13. So the possible values are 15, 20, 30 and 60. Thus we see that the corresponding values of N_2 are 12, 16, 24 and 48.

So there are more than one possible values of N_1 and N_2. Thus there is no unique value of $N_1 + N_2$. Hence (d) is correct option.

29. Since we know that the values of N_1 and N_2 are not unique so the value of C is also not unique hence it is indeterminable.

30. Number of parts $= \dfrac{\text{Total length}}{\text{length of each piece}}$

$= \dfrac{1950}{65} = 30 \qquad (\because 19.5 \text{ m} = 1950 \text{ cm})$

Thus option (b) is correct.

31. Since the 7, 11 and 13 all are the factors of such a number so (d) is the correct answer.

32. (a) is the correct option. Since 5321 is the greatest and 1235 is the least number then $5321 - 1235 = 4086$.

33. The possible values of k are 5 and 9. So the sum of $5 + 9 = 14$.

34. When we multiply 59829 with 13 we get the required number 777777. So (c) is the correct option.

INTRODUCTORY EXERCISE 1.2

1. Option (a) and (b) are ruled out due to unit digit property. Now to check whether (c) is correct or not. Now it would be better to square 2506 instead of finding the square root of 6280036.

Let us find the square of 2506.

Step 1. $(2505)^2 + (2505 + 2506)$

Step 2. $(2500)^2 + 5(2500 + 2505) + 5011$

Step 3. $6250000 + 25025 + 5011$

Step 4. $6275025 + 5011 = 6280036$

Hence option (c) is correct.

2. From your basic knowledge you know that $(30)^2 = 900$ again $(40)^2 = 1600$. This shows that the square root lies between 30 and 40.

Further you know that $(35)^2 = 1225$. From this it is clear that only option (d) is correct.

3. Since you know that $(80)^2 = 6400$ and $(90)^2 = 8100$. It shows that the square root of 7744 must lie between 80 and 90. So now there is only one option to check i.e.,,88. So we try to square 88 instead of finding the square root of 7744.

So $(88)^2 = (11 \times 8)^2 = 11^2 \times 8^2$

$= 121 \times 64 = 7744$

Hence option (b) is correct.

4. First of all option (a) is ruled out due to unit digit property. Again if we do some rough calculation we see that $(300)^2 = 90000$ then the value of $(323)^2$ will be very large even more than 90000 so this option is also ruled out. Now, if we find the square of 225 we will get $(225)^2 = 50625$ and the value of $(230)^2 = 52900$ since the value of 227 lies between 225 and 230, but 56169 does not lie between these values so this value is also not correct. Hence option (d) is correct.

5. (d) is right option since 8 can't be the unit digit of the square of any natural number.

6. Since the factors of 11760 are $2 \times 2 \times 2 \times 2 \times 3 \times 5 \times 7 \times 7$ so we need to multiply it with 3×5 because all the factors are paired but 3 and 5 are unpaired, hence (d) is the correct choice.

7. Since we know that there are two factors viz. 3 and 5 which are unpaired so if we remove them the number will become a perfect square. Hence we have to divide11760 by 15 $(= 3 \times 5)$ in order to make a perfect square number.

8. This problem can't be solved by factorisation because we need not factor. So we have to solve it by division method as follows

Scanned by CamScanner

yoursmahboob.wordpress.com

	23.9
2	5 75
2	4
43	175
3	129
469	4600
9	4221

(If the number is not a perfect square then by putting decimal we can increase the zeros in pairs for further calculation.)
The result obtained is ≈ 23.9.
So by adding some number we can make it the perfect square of 24. Now since we know that $(24)^2 = 576$. So we need to add 1 (∵ $576 - 575 = 1$)
Thus (b) is the correct option.

Alternatively : Using options we can solve this problem as if we consider option (a) then 575 itself be a perfect square but its not a perfect square. Again if we add 1 (i.e., using option (b) we get the number 576 and then check it, we find that 576 is a perfect square. Hence (b) is correct.

Alternatively : Since we know that $(20)^2 = 400$ and $(25)^2 = 625$. It means the value of perfect square must lies in the range of 400 and 625. So we can try it manually and get that $(23)^2 = 529$ and $(24)^2 = 576$. So simply we need to add 1 to make a perfect square number.

9. From the discussion done in the previous question we know that we have to subtract 46 to make the perfect square number. Since the closest perfect square numbers are 529 and 576. Since we have to subtract the number therefore we choose 529 and then we get $(575 - 529 =) 46$.
Hence (c) is the correct option.

Alternatively : If we subtract 5 then 570 is not a perfect square. Again if we subtract 38 then 538 is not a perfect square (simply due to unit digit concept of 2, 3, 7 and 8). Further if we subtract 46 we get 529 which is found to be a perfect square.

NOTE In the checking through option we have to follow the basic constraints imposed by the problem and here we have to find the least possible number so we start from the least option towards higher valued option *i.e.*, 5 then 37 then 46 and then 50.

10. It is given that $A^2 = B^2 + C^2$
But $\frac{B}{C} = \frac{12}{5}$ and B, C are integers.
So the least possible values of B and C are 12 and 5 respectively. Hence

$$A^2 = 12^2 + 5^2$$
$$A^2 = 169$$
$$A = 13$$

11. Since Lieutenant Kalia can arrange only 1444 soldiers in the square form. Now if he had arranged n soldiers in each of the n rows then

$$n \times n = 1444 \Rightarrow n = 38$$

Hence option (c) is correct.

12. $$\frac{\sqrt{289}}{\sqrt{x}} = \frac{1}{5} \Rightarrow \frac{289}{x} = \frac{1}{25}$$
$$\Rightarrow x = 7225$$

13. Option (d) is the required answer.

14. By observation we get to know that

$$2 * 3 = \sqrt{2^2 + 3^2} = \sqrt{13}$$
and $$3 * 4 = \sqrt{3^2 + 4^2} = 5$$
then $$5 * 12 = \sqrt{5^2 + 12^2} = 13$$

15. $$6 * 15 * 3 = \sqrt{\frac{(6+2)(15+3)}{(3+1)}} = \sqrt{\frac{8 \times 18}{4}} = 6$$

INTRODUCTORY EXERCISE 1.3

1. Let the numbers be $2a$ and $2b$ since 2 is the HCF of the numbers.
Therefore $2a \times 2b = 84$
$\Rightarrow$ $ab = 21$
Now, since $21 = 1 \times 21 = 3 \times 7$
$\therefore$ $(a, b) = (1, 21)$ and $(3, 7)$
Hence the values of pairs = (2, 42), (6, 14)
Thus there are only 2 pairs of numbers whose HCF is 2 and the product is 84.

2. Let the numbers be $6a$ and $6b$, since 6 is the HCF of the required numbers.
then $6a \times 6b = 15120$
$\Rightarrow$ $ab = 420$
Now $420 = 1 \times 420$
$= 2 \times 210 \rightarrow \times$
$= 3 \times 140$
$= 4 \times 105$
$= 5 \times 84$
$= 6 \times 70 \rightarrow \times$
$= 7 \times 60$
$= 10 \times 42 \rightarrow \times$
$= 12 \times 35$
$= 14 \times 30 \rightarrow \times$
$= 15 \times 28$
$= 20 \times 21$
Thus out of 12 pairs only 8 pairs are possible since the rest 4 pairs are not the coprimes.
Since 6 is the highest common factor of the two numbers (*i.e.*, pair of numbers)
So further there must not be any number (or factor) common in both the numbers otherwise the HCF will be changed so the only possible values of (a, b) are
(1, 420), (3, 140), (4, 105), (5, 84), (7, 60), (12, 35), (15, 28) and (20, 21).
Thus the possible numbers can be
(6, 520), (18, 840), (24, 630), (30, 504), (42, 360), (72, 210), (90, 168), (120, 126).
Hence, there are 8 pairs of such numbers whose HCF is 6 and the product is 15120.

3. (a) Only two pair of numbers.

Scanned by CamScanner

yourshahboob.wordpress.com

INTRODUCTORY EXERCISE 1.4

1. 28 is the largest possible number by which we can divide the given numbers in order to obtain the same remainders and thus dividing by 28 we get the remainder 20 in each division.

2. Let the two numbers of a pair be $5a$ and $5b$ then

$$5a + 5b = 50 \Rightarrow 5(a + b) = 50$$

$$\Rightarrow (a + b) = 10$$

So the possible values of (a, b) can be $(1, 9), (2, 8), (3, 7), (4, 6), (5, 5)$ but $(2, 8), (4, 6)$ and $(5, 5)$ are inadmissible since these pairs are not the coprimes, hence they can change the value of HCF. Thus only two pairs [(1, 9) & (3, 7)] are possible. Thus the actual pairs of such numbers are (5, 45) and (15, 35).

3. The largest possible length of the tape = HCF of 525, 1050, 1155
$= 105$
Hence (b) is the correct answer.

4. Minimum number of attempts $= \dfrac{\text{Total length of cloths}}{\text{Max. possible length of tape}}$

$$= \frac{2730}{105} = 26$$

Hence in 26 attempts the whole length of cloth can be measured using the tape of 105 cm length.

5. In order to have minimum number of tiles we need the largest possible tiles of square shape (in area).
So the maximum possible dimension (length and breadth) of a tile is the HCF of the dimension of the room.
Thus the HCF of 462 and 360 is 6 cm.
Hence the area of a square tile be $6 \times 6 = 36\ \text{cm}^2$.
Now the number of tiles required

$$= \frac{\text{Area of floor of the room}}{\text{Area of one tile}}$$

$$= \frac{462 \times 360}{6 \times 6} = 77 \times 60 = 4620$$

Thus total 4620 tiles are required.

6. (d) is correct answer. The numbers will be 195 and 143.

7. (d) is the correct option. In the options (a), (b) and (c) the HCF is not 12.

8. The maximum capacity of the vessel = HCF of 1653, 2261 and 2527 = 19
Hence (c) is the correct option.

9. To be the minimum number of pencils the size of all the pencils must be maximum. So the length of each pencil
= HCF of 24 and 42 = 6
Thus the number of pencils $= \dfrac{\text{Total length of pencils}}{\text{length of one pencil}}$

$$= \frac{24 + 42}{6} = 11$$

Thus (b) is the correct choice since there can be min. 11 pencils of same size.

10. (a) The correct pair of numbers is (27, 189).

11. Minimum number of rows means max. number of trees per row, also equal number of trees per row is required so we need to find the HCF of 36, 144 and 234 to find the maximum number of trees in a row.
Thus HCF of 36, 144 and 234 = 18
Thus the number of rows $= \dfrac{\text{Total no. of trees}}{\text{No. of trees in a row}}$

$$= \frac{36 + 144 + 234}{18} = 23$$

Hence (b) is correct answer.

INTRODUCTORY EXERCISE 1.7

1. Going through options :
Option (a) is invalid since $5 > 2$
Try option (c) $2 \times 40^1 + 5 \times 40^0 = 80 + 5 = 85$
Hence (c) is the correct option.
Alternatively : $(25)_x = (85)_{10}$

$$\Rightarrow 2 \times x^1 + 5 \times x^0 = (85)_{10}$$

$$\Rightarrow 2x + 5 = 85$$

$$\Rightarrow 2x = 80$$

$$\Rightarrow x = 40$$

Hence (c) is the correct option.

2. Obviously option (b) is the required answer.
Since base must be greater than any integer of the number.

3. Going through option (b) is the invalid option.
Option (d) is also wrong since $(53)_6 = 33$ which is not a prime number and option (c) is also wrong since $(53)_{12} = 60 + 3 = 63$ which is not a prime number.
Hence option (a) is the correct. You can verify by assuming the value of n.

4. Since the last three digits in the given number are divisible by 2^3 (= 8). Hence the equivalent binary digits will be 000.
Alternatively : Divide the given number successively by 2 and get the last three digits as

2	365247728	
2	182623864 →	0
2	91311932 →	0
	45655966 →	0

Remainders

Thus the last three digits in the binary representation will be 000.

5. Since last three digits (*i.e.*, 956) is not divisible by 2^3(= 8).
Hence all the last three digits will not be zero. Now since 956 is divisible by 4. Hence the last two digits will be 00. Thus only option (b) is correct.

NOTE Option (a) is invalid.

Scanned by CamScanner

yoursmahboob.wordpress.com

6.

2	8009	
2	4000 →	1
2	2000 →	0
2	1000 →	0
	500 →	0

Remainders

Hence the last four digits in the binary representation of the given number are 0001.
Hence (a) is the correct option.

7. Going through option :
Let us assume option (c) ,then

2	8	
2	4 →	0
2	2 →	0
2	1 →	0
	0 →	1

Since $(1000)_2$ does not satisfy the given condition hence presumed option is wrong.
Now, consider option (d).

2	9	
2	4 →	1
2	2 →	0
2	1 →	0
	0 →	1

Thus $(9)_{10} = (1001)$, which satisfies all the given condition hence correct option.

8. Let the tens digit and unit digit of the original number be a, b then the original number $= 10a + b$
Again if the digits are reversed then the new number $= 10b + a$
So $(10a + b) - (10b + a) = 9(a - b)$
Now since it is given that $a + b = 9$ and $9 . (a - b) = 63$
So solving for $(a + b)$ and $(a - b)$, we get $a = 8$ and $b = 1$
It means the given two digit number is 81 and its reverse is 18.
Further $(81)_x = 5(18)_x$

$$\Rightarrow \quad 8x + 1 = 5[x + 8]$$
$$\Rightarrow \quad 8x + 1 = 5x + 40$$
$$\Rightarrow \quad 3x = 39$$
$$x = 13$$

Thus the value of $x = 13$ and hence option (b) is correct.

9.
$$(25)_n \times (31)_n = (1015)_n$$
$$\Rightarrow \quad (2n + 5)(3n + 1) = n^3 + n + 5$$
$$\Rightarrow \quad 6n^2 + 17n + 5 = n^3 + n + 5$$
$$\Rightarrow \quad n^3 - 6n^2 - 16n = 0$$
$$\Rightarrow \quad n(n^2 - 6n - 16) = 0$$
$$\Rightarrow \quad n = 0 \quad \text{or} \quad n^2 - 6n - 16 = 0$$
$$\text{or} \quad n^2 - 6n - 16 = 0$$
$$\Rightarrow \quad (n - 8)(n + 2) = 0$$
$$\Rightarrow \quad n = 8 \quad \text{or} \quad n = -2$$

So the only admissible value of $n = 8$
Now, $(13)_8 \times (52)_8 = (11)_{10} \times (42)_{10}$
$= (462)_{10} = (716)_8$
Hence option (c) is correct.

10. $(100000\ldots001)_{16} = 1 \times (16)^{24} + \underbrace{0 + 0 + \ldots}_{23 \text{ zeros}} + 1 \times 16^0$

$$= 16^{24} + 1$$
$$= (2^4)^{24} + 1 = 2^{96} + 1$$

11. Since 2^{111} is divisible by 2^3 (*i.e.*,,8) hence the unit digit in octal system will be 0.

12. Option (b) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

MISCELLANEOUS

1. $\because \frac{-2}{3} = -0.66$ and $\frac{5}{2} = 2.5$ and $\frac{-1}{6} = -0.16$

$\therefore$ The correct required order is

$$\frac{5}{2} > \frac{-1}{6} > \frac{-2}{3}$$

Thus (a) is the correct answer.

2. $x + \frac{1}{x} = 3\left(x - \frac{1}{x}\right) \Rightarrow \frac{x^2+1}{x} = 3\left(\frac{x^2-1}{x}\right)$

$\Rightarrow \quad 2x^2 = 4 \Rightarrow x^2 = 2 \Rightarrow x = \pm\sqrt{2}$

Hence, (a) is correct.

3. Let us assume some values as 4 and 2, then

$$4 > 2 \Rightarrow -4 < -2$$

Hence, (b) is correct.

NOTE Other three option are wrong as

(a) $4 > 2 \Rightarrow -4 < -2$

(c) $4 > 2 \Rightarrow \frac{1}{4} < \frac{1}{2}$

(d) $4 > 2 \Rightarrow -\frac{1}{4} > -\frac{1}{2}$

4. Go back to the Basics.

5. $1780 + x = 1849$, which is nearest perfect square.

So, $x = 1849 - 1780$

$x = 69$

Hence, (a) is the least possible number.

Remark : If you have any problem in finding the value of nearest perfect square so try the following method.

$(40)^2 = 1600$, $(50)^2 = 2000$ it means your required value is lying somewhere between 40^2 & 50^2. Now $45^2 = 2025$, so it is clear that the value is lying between $(40)^2$ & $(45)^2$. Now in this way you can attain the required value.

6. Statement (1) and (2) are wrong since when p is a prime number so it does not have any factor so when all the factors (or numbers) before 'p' do not involve in the product so it is not divisible by p or any prime number greater than p. Statement (3) is wrong, since $1 \times 2 \times 3 \times 4 \times 5 \times 6$ is divisible by 5.

7. Statement (1) is true since all the prime numbers are either at a difference of 2 or 4. So for a suitable value of n it can be expressed. Statement (2) is correct since $(p-1)$ and $(p+1)$ both must be even numbers so $2k \times 2l = 4kl$. Thus it must be divisible by 4.

8. Since we know that $111 = 3 \times 37$, so the whole number is divisible by 3, 37 and 111. Now since the digit 1 is being repeated even number of times so it is divisible by 11. Again since the given number is such that the digits are being repeated and can be broken into triplets, so it is also divisible by 1001.

9. Since $16 = 2^4$ so the last four digits, thus $x = 4$ or go back to the Basics.

10. The pair will be of the form $(15k, 15l)$, where k and l must be coprimes. The values of k and l be such that $15k$ and $15l$ will remain between 40 and 100. So, the pairs are (45, 60), (45, 75), (60 75), (75, 90).

11. It is possible only when there is no common factor among p, q and r. Hence, the HCF of $p, q, r = 1$

and the LCM of $p, q, r = p \cdot q \cdot r$

$\therefore$ (HCF $\times$ LCM) of $p, q, r = 1 \times p \cdot q \cdot r = pqr$

12. Statement (2) is wrong since $3 \times (1) + 2 \times (-1) = 1$, here y is negative. Again since x and y depends on each other. Hence they are uniquely determined.

13. Go through options and put $x = 1$.

Alternatively: Solve with the help of quadratic equations.

14. **Go through options:** Then consider option (c). As

$$2 \times (14)^2 - 25 \times 14 = 3 \times 14$$

Alternatively: Let the age of the lad be x then

$$2x^2 - 25x = 42$$

$\Rightarrow \quad 2x^2 - 25x - 42 = 0$

Now, either solve this quadratic equation to get the answer or put the appropriate value from the option to get the required answer.

15. Go back to the Basics.

16. Check through options: As

$$(5+3) + (5^2 + 3^2) = 42$$

and $5 \times 3 = 15$

17. Check through alternatives: As

$$\frac{1}{0-1} = \frac{2}{0-2} \Rightarrow \frac{1}{-1} = \frac{2}{-2} = \frac{1}{-1}$$

Option (a) and (b) are clearly inadmissible.

Alternatively: $\frac{1}{x-1} = \frac{2}{x-2}$

$\Rightarrow \quad x - 2 = 2x - 2 \Rightarrow x = 0$

18. $\because \quad \left(x + \frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} + 2 \cdot \left(x \cdot \frac{1}{x}\right)$

$\Rightarrow \quad (2)^2 = x^2 + \frac{1}{x^2} + 2(1)$

$\left\{\text{Substituting the value of } x + \frac{1}{x}\right\}$

$\Rightarrow \quad 4 = x^2 + \frac{1}{x^2} + 2$

$\Rightarrow \quad x^2 + \frac{1}{x^2} = 2$

Hence, (c) is the right choice.

19. $\because \quad a^2 + b^2 + c^2 - ab - bc - ac$

$$= \frac{1}{2}[(a-b)^2 + (b-c)^2 + (c-a)^2]$$

$$= \frac{1}{2}[(2)^2 + (-2)^2 + (4)^2] = 12$$

Alternatively: Substitute the values of a, b, c into given expression.

20. Go through options or Go back to the Basics.

The factors of 6 = 1, 2, 3, 6

Now, since $1 + 2 + 3 = 6$

Hence, (d) is correct choice.

Scanned by CamScanner

yoursmahboob.wordpress.com

21. $\because \quad \frac{a}{b^2} \times \frac{b}{a^2} = \frac{1}{ab}$

Now, consider option (d).

$$\frac{1}{2ab} + \frac{1}{2ab} = 2\left(\frac{1}{2ab}\right) = \frac{1}{ab}$$

Hence, (d) is the appropriate option.

22. Substitute the value of x and y in the given expression

$$(6+3)^{6/3} = 9^2 = 81$$

23. AM of $ax_1 + b, ax_2 + b, ax_3 + b, \ldots, ax_n + b$ is

$$= \frac{(ax_1 + b) + (ax_2 + b) + (ax_3 + b) + \ldots + (ax_n + b)}{n}$$

$$= \frac{(ax_1 + ax_2 + ax_3 + \ldots + ax_n) + (b + b + b + \ldots + b)}{n}$$

$$= \frac{a(x_1 + x_2 + \ldots + x_n) + nb}{n}$$

$$= \frac{a(x_1 + x_2 + x_3 + \ldots + x_n)}{n} + \frac{nb}{n} = a\bar{x} + b$$

24. The arithmetic mean of first 'n' odd natural number $= \frac{n^2}{n} = n$

Thus, the required answer is 50. Hence, (a) is correct.

25. Average area $= \frac{1^2 + 2^2 + 3^2 + \ldots + n^2}{n} = \frac{\left(\frac{n(n+1)(2n+1)}{6}\right)}{n}$

$$= \frac{(n+1)(2n+1)}{6} = \frac{(n+1)}{2} \cdot \frac{(2n+1)}{3}$$

Hence, (b) is the correct option.

26. $\sqrt[4]{10} = (10)^{1/4} = (10)^{3/12} = (1000)^{1/12}$

$\sqrt[3]{6} = (6)^{1/3} = (6)^{4/12} = (1296)^{1/12}$

$\sqrt{3} = (3)^{1/2} = (3)^{6/12} = (729)^{1/12}$

$\therefore \sqrt{3} < \sqrt[4]{10} < \sqrt[3]{6}$ is the correct order and hence (b) is correct.

27. Go back to the Basic. As $\sqrt[3]{2}$ is a real number but not a rational number.

28. $\because \quad (a^2 + b^2)^3 = (a^3 + b^3)^2$

$\Rightarrow \quad a^6 + b^6 + 3a^2b^2(a^2 + b^2) = a^6 + b^6 + 2a^3b^3$

$\Rightarrow \quad 3a^2b^2(a^2 + b^2) = 2a^3b^3$

$\Rightarrow \quad 3(a^2 + b^2) = 2ab$

$\Rightarrow \quad \frac{a^2 + b^2}{ab} = \frac{2}{3}$

Now, $\left(\frac{a}{b} + \frac{b}{a}\right)^6 = \left(\frac{a^2 + b^2}{ab}\right)^6 = \left(\frac{2}{3}\right)^6 = \frac{64}{729}$

Hence, (b) is the correct choice.

29. Total number of lines (in one bound)

= [Number of lines per page
× Number of page per chapter
× Number of chapter per book
× Number of books per bound]

$= 60 \times 125 \times 5 \times 20 = 750000$

$\therefore$ Number of bounds $= \frac{3000000}{750000} = 4$

Hence, there are total 4 bounds.

30.

$$1 + \sqrt{1} = 2$$
$$4 + \sqrt{4} = 6$$
$$9 + \sqrt{9} = 12$$
$$16 + \sqrt{16} = 20$$
$$25 + \sqrt{25} = 30$$
$$36 + \sqrt{36} = 42$$

Thus, we get the unit digits as 0, 2 and 6 only. Hence (c) is the correct option.

31. Since $2^p + 1$ is a prime number so

$$2^0 + 1 = 2$$
$$2^1 + 1 = 3$$
$$2^2 + 1 = 5$$
$$2^{(2)^2} = 2^4 + 1 = 17$$
$$2^{(2)^3} = 2^8 + 1 = 257$$

Hence, the value of p is 2 or the power of 2.

32. Since, the prime number between 101 and 120 is 4 *viz.*, 103, 107, 109, 113.

Hence, the number of composite numbers between 101 and $120 = 18 - 4 = 14$.

33. Since $(10^N - 1) = (10^{2n} - 1)$

$= (10^2)^n - 1 = (100)^n - 1$

So, $= 100^n - 1^n = (100 - 1)[X] = 99[X]$

Thus, for any even power it is divisible by 11. *i.e.*, $N = 2n$.
Hence, (a) is the correct option.

34. The volume of tin is = HCF of 140, 260 and 320 = 20
Hence, (a) is the correct answer.

35. Go back to the Basics.

36. $\left(1 + \frac{1}{3}\right)\left(1 + \frac{1}{4}\right)\left(1 + \frac{1}{5}\right)\ldots\left(1 + \frac{1}{n}\right)$

$$= \frac{4}{3} \times \frac{5}{4} \times \frac{6}{5} \times \ldots \frac{n}{(n-1)} \times \left(\frac{n+1}{n}\right) = \frac{n+1}{3}$$

Hence, (a) is the correct option.

37. $(x)^3 = (2^{1/3} + 2^{-1/3})^3 = 2 + 2^{-1} + 3 \times 2^{1/3} \times 2^{-1/3}(x)$

$$= 2 + \frac{1}{2} + 3x$$

$\Rightarrow \quad x^3 - 3x = \frac{5}{2}$

$\Rightarrow \quad 2(x^3 - 3x) = 5$

$\Rightarrow \quad 2x^3 - 6x = 5$

Hence, (a) is the correct answer.

38. Go back to Basics.

39. $\because \quad (x - y)^3 = x^3 - y^3 - 3xy(x - y)$

$\therefore \quad (1)^3 = x^3 - y^3 - 3xy(1)$

[Substituting the value of $(x - y)$]

$\Rightarrow \quad x^3 - y^3 - 3xy = 1$

40. $\because (1 - 81P^4) = (1 + 9P^2)(1 - 9P^2)$

$= (1 + 9P^2)(1 + 3P)(1 - 3P)$

Thus, $(1 - 3P)$, $[1 - (3P)^2]$ and $[1 - (3P)^4]$ are the 3 factors possible.

41. Let the three consecutive integers be $(n - 1)$, n and $(n + 1)$ then

$$(n-1) + n + (n+1) = 21$$

$\Rightarrow \quad 3n = 21 \quad \Rightarrow \quad n = 7$

$\therefore \quad (n-1) + n = (7-1) + 7 = 13$

Scanned by CamScanner

yourshahboob.wordpress.com

42. $\because (s-a)^2+(s-b)^2+(s-c)^2+s^2-a^2-b^2-c^2$
$= s^2+a^2-2as+s^2+b^2-2bs+s^2+c^2-2cs$
$\quad +s^2-a^2-b^2-c^2$
$= 4s^2+(a^2+b^2+c^2)-2s(a+b+c)-(a^2+b^2+c^2)$
$= 4s^2-2s(a+b+c)$
$= 4s^2-4s^2=0 \quad [\because 2s=(a+b+c)]$
Hence, (d) is the correct option.

43. Given that $ab+bc+ca=0$
Now $a^2-bc=a^2+ab+ca \quad [\because -bc=ab+ca]$
$\Rightarrow a^2-bc=a(a+b+c)$
Similarly $b^2-ca=b(a+b+c)$
and $c^2-ab=c(a+b+c)$
$\therefore \frac{1}{a^2-bc}+\frac{1}{b^2-ca}+\frac{1}{c^2-ab}$
$=\frac{1}{a(a+b+c)}+\frac{1}{b(a+b+c)}+\frac{1}{c(a+b+c)}$
$=\frac{1}{a+b+c}\left[\frac{1}{a}+\frac{1}{b}+\frac{1}{c}\right]$
$=\frac{1}{a+b+c}\left[\frac{bc+ac+ab}{abc}\right]=0 \quad [\because ab+bc+ac=0]$

44. $4^{x+3}\times 2^{x-3}-128=0$
$\Rightarrow 2^{2x+6}\times 2^{x-3}-2^7=0$
$\Rightarrow 2^{3x+3}-2^7=0$
$\Rightarrow 3x+3=7$
$\Rightarrow 3x=4 \Rightarrow x=\frac{4}{3}$
Hence, (d) is the correct option.

45. $\because a^m\cdot a^n=a^{mn}$
$\Rightarrow a^{m+n}=a^{mn}$
$\Rightarrow m+n=mn$
$\therefore m(n-2)+n(m-2)=mn-2m+nm-2n$
$=(m+n)-2m+(m+n)-2n$
$=2m+2n-2m-2n=0$
Hence, (a) is the correct option.

46. $\frac{6^6+6^6+6^6+6^6+6^6+6^6}{3^6+3^6+3^6}+\frac{4^6+4^6+4^6+4^6}{2^6+2^6}=2^n$
$\Rightarrow \frac{6(6)^6}{3(3^6)}+\frac{4(4^6)}{2(2^6)}=2^n$
$\Rightarrow 1=2^n \Rightarrow 2^0$
thus, $n=0$
Hence, (b) is the correct option.

47. $a^{1/m}=b^{1/n}=c^{1/p}=k$
$\Rightarrow a=k^m, \quad b=k^n, \quad c=k^p$
$\because a\cdot b\cdot c=1$
$\Rightarrow k^m\cdot k^n\cdot k^p=1$
$\Rightarrow k^{m+n+p}=1=k^0$
$\Rightarrow m+n+p=0$
Hence, (a) is the correct option.

48. $\frac{-3}{7}=-0.42$ and $\frac{-1}{3}=-0.33$
So, the value in descending order will be as follows:
$\frac{2}{3}>\frac{-1}{3}>\frac{-3}{7}$
Hence, (b) is the correct option.

49. $\frac{-24}{20}=\frac{x}{25} \Rightarrow x=-30$
Hence, the equivalent rational number is $\frac{-30}{25}$.

50. $\frac{3}{4}\times\left(\frac{-2}{3}+\frac{3}{5}\right)=\frac{3}{4}\times\left(\frac{-1}{15}\right)=\frac{-1}{20}$

51. If the dividend is X, divisor be y and quotient be q, then
$X=yq+r$
Now, since $y=8q$
and $y=4r=4\times 12=48$ (r is remainder)
$\Rightarrow q=6$
$\therefore X=48\times 6+12$
$X=300$

52. Go back to the Basics.

53. Options (a) and (b) are wrong since when $c>a$ and $d>b$ still $\frac{a}{b}=\frac{c}{d}$ it means $\frac{a}{b}$ and $\frac{c}{d}$ are equivalent rational number and $\frac{a}{b}$ is in standard form.
Thus, $\frac{c}{d}=\frac{ka}{kb};\ k>1$
Hence, (c) is the correct answer.

54. Since all the numbers in the given series are of the form $4n+2;\ n\in N$.
It means the number after division by 4 leaves remainder 2.
So, the possible value is 338. Hence, (b) is the correct option.

55. $6^4\times 8^6\times 10^8\times 12^{10}=(2\times 3)^4\times(2^3)^6\times(2\times 5)^8\times(2^2\times 3)^{10}$
$=2^4\times 3^4\times 2^{18}\times 2^8\times 5^8\times 2^{20}\times 3^{10}$
$=2^{50}\times 3^{14}\times 5^8$
Thus, there are total 72 (= 50 + 14 + 8) prime factors.

56. Check the options for the given condition. 10080 fulfills all the requirements.

57. $500=2^2\times 5^3$
The sum of all the factors $=\frac{(2^{2+1}-1)\times(5^{3+1}-1)}{(2-1)(5-1)}$
$=\frac{7\times 624}{1\times 4}=1092$
Hence, (c) is the correct option.

58. Go through option. It would be better to try to divide the given numbers. Then 19 divides 1007 and 1273 both. Hence, (d) is the correct option.

59. $s^2+(s-1)^2+(s-3)^2+(s-5)^2$
$=\left(\frac{9}{2}\right)^2+\left(\frac{7}{2}\right)^2+\left(\frac{3}{2}\right)^2+\left(\frac{-1}{2}\right)^2 \quad \left[\because 2s=9\Rightarrow s=\frac{9}{2}\right]$
$=\frac{81}{4}+\frac{49}{4}+\frac{9}{4}+\frac{1}{4}=35$
Hence, (d) is the correct option.

60. Go through option $5+3=8$
$53-35=18$
Hence, option (c) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

61. $x^y = y^x \Rightarrow y = x^{y/x}$

$\Rightarrow \quad 2x = x^{y/x} = x^{2x/x} = x^2$

$\Rightarrow \quad 2x = x^2 \Rightarrow x = 2$

Hence, (a) is the correct option.

Alternatively: Go through options and put $x = 2$ in both the values if they satisfy, then the presumed option is correct. As

$y = 2x = 4$

then $2^4 = 4^2$

$16 = 16$

Hence, it is correct.

62. $[(x^l)^{1-\frac{1}{l}}]^{\frac{1}{l-1}} = (x^{l-1})^{\frac{1}{l-1}} = x$

Hence, (a) is the correct choice.

63. $\because x^a \times x^b \times x^c = 1 \Rightarrow x^{a+b+c} = 1 = x^0$

$\Rightarrow \quad a + b + c = 0$

Now since $a^3 + b^3 + c^3 - 3abc$

$= (a + b + c)(a^2 + b^2 + c^2 - ab - bc - ac)$

$\Rightarrow \quad a^3 + b^3 + c^3 - 3abc = 0$

$\therefore \quad a^3 + b^3 + c^3 = 3abc$

Hence, (d) is the right choice.

64. $(\sqrt{2})^2 = (2^{1/2})^2 = 2$ is a rational number.

65. $\frac{-18}{5} = -3.6$, which lies between -3 and -4.

Hence, (b) is the correct option.

66. $1 \div \frac{1}{1 \div \frac{1}{1 \div \frac{1}{3}}} = 1 \div \frac{1}{1 \div \frac{1}{3}} = 1 \div \frac{1}{3} = 3$

Hence, (c) is the correct answer.

67. $171282 = 547 \times \text{divisor} + 71$

$\Rightarrow \quad 171211 = 547 \times \text{divisor}$

$\Rightarrow \quad \text{divisor} = 313$

Hence, (c) is the correct answer.

68. $\sqrt{900} + \sqrt{0.09} - \sqrt{0.000009}$

$= 30 + 0.3 - 0.003 = 30.297$

Hence, (a) is the correct option.

69. $376 - 358 = 18, \quad 358 - 232 = 126, \quad 376 - 232 = 144$

Now, the HCF of 18, 126 and 144 = 18

Hence, 18 and all its factor can fulfill the required condition. But 9 is the greatest available such number. Hence, (d) is the correct choice.

Alternatively: According to the given condition go through options starting with the greatest value from the choices available and see the remainders must be same.

71. $2 + 4 + 3 + x + 5 + 1 = 18$ (the only possible sum)

$\Rightarrow \quad x = 3$

Hence, (a) is the correct choice.

72. $5 \times 60 = 20 \times N$

$\Rightarrow 15$, Hence (d).

73. $30k \times 30l = 5400$, where k and l are coprimes.

$k \times l = 6$

Now, since $6 = 1 \times 6$ and 2×3

Hence, there are two pairs *viz.*, (30, 1800) and (60 and 90). Thus (b).

74. The required number = (LCM of 2, 3, 4, 5, 6) $K + 1 = 7l$

$= 60k + 1 = 7l$

$\Rightarrow \quad \frac{60k + 1}{7} = l$

Now put the least possible value of k such that l must be a positive integer. Hence at $k = 5$, l is an integer. Thus, the required value is $60 \times 5 + 1 = 301$.

75. The required time = LCM of 36, 40 and 48

$= 720$ second $= 12$ minutes

Hence, (b) is the right choice.

76. $\left(1 - \frac{1}{2}\right) = \frac{1}{2}$

Now $\frac{1}{2} \times \frac{1}{3} = \frac{1}{6}$

Thus $1 - \frac{1}{2} - \frac{1}{6} = \frac{1}{3}$

Thus, (a)is the correct answer.

77. See question number 63 or see the list of formulae and then solve it.

78. Since $x^4 - y^4 = (x^2)^2 - (y^2)^2$

$= (x^2 + y^2)(x + y)(x - y)$

Thus, $(x^4 - y^4)$ is exactly divisible by $(x - y)$ as one of the factors. Hence, no remainder will leave.

79. $\left(x - \frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} - 2 \cdot x \cdot \frac{1}{x}$

$\Rightarrow \quad 4 = \left(x^2 + \frac{1}{x^2}\right) - 2$

$\Rightarrow \quad x^2 + \frac{1}{x^2} = 6$

Now $\left(x^2 + \frac{1}{x^2}\right)^2 = x^4 + \frac{1}{x^4} + 2x^2 \cdot \frac{1}{x^2}$

$\Rightarrow \quad 36 = x^4 + \frac{1}{x^4} + 2$

$\Rightarrow \quad x^4 + \frac{1}{x^4} = 34$

Hence, (d) is the correct answer.

80. $(x + y) = 25 \quad \text{and} \quad xy = 144$

$(x - y)^2 = (x + y)^2 - 4xy$

$(x - y)^2 = 625 - 576$

$(x - y)^2 = 49$

$\Rightarrow \quad x - y = 7$

Hence, (c) is correct.

81. $x + y = 9 \quad \text{and} \quad x^2 + y^2 = 41$

$(x + y)^2 = x^2 + y^2 + 2xy$

$81 = 41 + 2xy$

$\Rightarrow \quad 40 = 2xy \Rightarrow xy = 20$

Now $(x - y)^2 = (x + y)^2 - 4xy$

$(x - y)^2 = 81 - 80$

$(x - y)^2 = 1 \Rightarrow x - y$

Thus $x + y = 9 \quad \text{and} \quad x - y = 1$

Hence, $x = 5 \quad \text{and} \quad y = 4$

Therefore (a) is the correct answer.

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively: Go through options:

$4 + 5 = 9$

and $16 + 25 = 41$

82. $3^n = 27 \Rightarrow 3^n = 3^3 \Rightarrow n = 3$

$\therefore 3^{n-2} = 3^1 = 3$

Thus, (a) is the right choice.

83. $a = b^x = (c^y)^x = (c)^{xy} = (a^z)^{xy} = a^{xyz}$

Thus $a = a^{xyz} \Rightarrow xyz = 1$

Hence, (c).

84. See the question number 37. Hence (c).

85. $1^2 + 2^2 + \ldots + 10^2 = \frac{10 \times 11 \times 21}{6} = 385$

$\left[\because 1^2 + 2^2 + \ldots + n^2 = \frac{n(n+1)(2n+1)}{6}\right]$

86. $\because$

2	7
2	3 → 1
2	1 → 1
	0 → 1

Thus $(7)_{10} = (111)_2$

87. The remainder will be the required answer.

Since $6 + 7 + 5 = 18$

$\therefore$ 6705 will be divisible by 5 and 3 will be remainder. Hence, (c).

88. For example $\frac{3}{2} = 1.5$ which is not an integer, while 3, 2 are integers. Hence, (d).

89. $\frac{10\sqrt{6.25}}{\sqrt{6.25} - 0.5} = \frac{10 \times 2.5}{2.5 - 0.5} = \frac{25}{2} = 12.5$

90. Go back to the Basics.

91. The required number = HCF of $(398 - 7)$, $(436 - 11)$ and $(542 - 15)$

= HCF of (391, 425 and 527) = 17

Hence, (b) is the right choice.

Alternatively: If your speed of calculation is very fast then pickup the suitable option and then divide the given numbers and see the required result.

92. Option (a) and (d) are invalid since remainder is always a positive value. Again if you know the remainder theorem, then apply it. Otherwise consider any appropriate value of x and then perform the division.

93. $\because \frac{a^3 + b^3 + c^3 - 3abc}{a^2 + b^2 + c^2 - ab - bc - ac}$

$= \frac{(a+b+c)(a^2 + b^2 + c^2 - ab - bc - ac)}{(a^2 + b^2 + c^2 - ab - bc - ac)}$

$= a + b + c$

$\therefore$ The required answer $= 10 - (1.5 + 4.7 + 3.8)$

94. Go through options

$\because 8 + 0 + 3 + 6 + 4 + 2 = 23$

So, the required number $= 27 - 23 = 4$

Alternatively: Divide 803642 and find the remainder. Now the required number = (9 – Remainder)

95. $\because \frac{a^3 + b^3}{a^2 + b^2 - ab} = \frac{(a+b)(a^2 + b^2 - ab)}{(a^2 + b^2 - ab)} = (a + b)$

Hence, the required number $= 8.73 + 4.27 = 13$

96. $\left(x - \frac{1}{x}\right)^3 = x^3 - \frac{1}{x^3} - 3x \cdot \frac{1}{x}\left(x - \frac{1}{x}\right)$

$125 = x^3 - \frac{1}{x^3} - 3(5)$

$\Rightarrow x^3 - \frac{1}{x^3} = 140$ Hence, (d).

97. Best way is to go through option. Consider option (c)

Correct answer = 20, marks for correct answer = 60

So wrong answer = 10, marks for wrong answer = –20

$\therefore$ Net marks = 60 – 20 = 40

Hence, presumed option is correct.

Alternatively: $30 \times 3 - x \times 5 = 40$

$90 - 5x = 40$

$x = 10$

Hence, the wrong answer = 10

Thus, the correct answer = 20

(for more detailed discussion see the example)

98. Since $|x| = x$ or $-x$

$\therefore |x - 1| + |x - 2| + |x - 3| \geq 6$

$\Rightarrow 3x - 6 \geq 6$ or $6 - 3x \geq 6$

$\Rightarrow x \geq 4$ or $x \leq 0$

Hence, (b).

99. Total cost = Distance covered × Rate (or charge/km)

$= x \times 10 + (200 - x) \times 2$

$= 10x + 400 - 2x = 8x + 400$

Hence, (c).

100. $2^{x+3} \cdot 4^{2x-5} = 2^{3x+7}$

$\Rightarrow 2^{x+3} \cdot 2^{4x-10} = 2^{3x+7}$

$\Rightarrow 2^{5x-7} = 2^{3x+7}$

$\Rightarrow 5x - 7 = 3x + 7$

$\Rightarrow 2x = 14$

$x = 7$ Hence, (d).

101. $\left(\frac{x^a}{x^b}\right)^{(a^2+b^2+ab)} \cdot \left(\frac{x^b}{x^c}\right)^{(b^2+c^2+bc)} \cdot \left(\frac{x^c}{x^a}\right)^{(c^2+a^2+ac)}$

$= x^{(a-b)(a^2+b^2+ab)} \cdot x^{(b-c)(b^2+c^2+bc)} \cdot x^{(c-a)(c^2+a^2+ac)}$

$= x^{(a^3 + ab^2 + a^2b - a^2b - b^3 - ab^2 + b^3 + bc^2 + b^2c - b^2c - c^3 - bc^2 + c^3 + a^2c + ac^2 - ac^2 - a^3 - a^2c)}$

$= x^0 = 1$ Thus, (c).

102. $4 \times 100 + 3 \times 10 + \frac{9}{1000} = 400 + 30 + 0.009$

$= 430.009$ Hence, (c).

103. The same number can not be rational and irrational both, simultaneously. So (a) is wrong.

Again $(2 + \sqrt{3}) + (2 - \sqrt{3}) = 4$

So, (b) is wrong, as irrational + irrational = Rational.

Once again, $-3 < 2 \Rightarrow 9 > 4$

For more information go back to the basics.

Scanned by CamScanner

yoursmahboob.wordpress.com

104. $\because \quad 540 = 2^2 \times 3^3 \times 5$

So, the least perfect square

$= 2^2 \times 3^4 \times 5^2 = [(2^2 \times 3^3 \times 5) \times (3 \times 5)]$

$= 8100$ Hence, (a).

105. Go back to the basics.

Since $2 - 2 = 0$

[Natural number − Natural number] = Not a natural number

$\frac{3}{2} = 1.5$

$\frac{\text{Natural number}}{\text{Natural number}}$ = Not a natural number

Hence, it is not closed for subtraction and division.

106. $\frac{100\sqrt{25}}{\sqrt{25}+x} = 50 \Rightarrow \frac{500}{5+x} = 50 \Rightarrow x = 5$

$\because \quad 5 = \sqrt{25}$ Hence (c).

107. 127, 131, 137, 139.

108. $1 + 2 + 3 + 7 + 5 = 18$, hence, divisible by 3 and 9 both.

Again $(5 + 3 + 1) - (7 + 2) = 0$

Hence, divisible by 11 also. Thus (a).

109. $\left(1-\frac{1}{3}\right)\left(1-\frac{1}{4}\right)\left(1-\frac{1}{5}\right)\ldots\left(1-\frac{1}{n}\right) = \frac{2}{3}\times\frac{3}{4}\times\frac{4}{5}\times\ldots\times\frac{n-1}{n}$

$= \frac{2}{n}$

Thus, (b) is correct.

110. $\frac{4}{5} + \frac{y-x}{y+x} = \frac{4}{5} + \frac{3-2}{3+2}$ $\left(\because \frac{x}{2} = \frac{y}{3} \Rightarrow \frac{x}{y} = \frac{2}{3} \Rightarrow x = 2 \text{ and } y = 3\right)$

$= \frac{4}{5} + \frac{1}{5} = \frac{5}{5} = 1$ Hence, (c).

111. $\frac{a^2+ab+b^2}{a^3-b^3} = \frac{a^2+ab+b^2}{(a-b)(a^2+ab+b^2)} = \frac{1}{(a-b)}$

$= \frac{1}{119-111} = \frac{1}{8}$ Thus, (b).

112. Go through options : $8 + 3 = 11$

and $83 - 38 = 45$ Hence, (d).

Alternatively: $x + y = 11$

and $9(x - y) = 45$

$\Rightarrow \quad x - y = 5$

Thus, $8 - 3 = 5$, hence 83.

113. $4A + \frac{5A}{3} = 85$

$\Rightarrow \quad A = 15 \Rightarrow \frac{A}{3} = 5$

Hence, the cost of child ticket = Rs. 5/-. Thus (a) is the correct option.

114. $9^{3/2} \div (243)^{-2/3} = (3^2)^{3/2} \div \left(\frac{1}{3^5}\right)^{2/3}$

$= 3^3 \div 3^{-10/3} = 3^{3+\frac{10}{3}} = 3^{19/3}$

115. At $x = 2$, both sides are equal.

116. $\frac{b}{a} = \frac{c}{b} = b^2 = ca$

Again, $a^x = b^y = c^z = k$

$\Rightarrow \quad a = k^{1/x}, b = k^{1/y}, c = k^{1/z}$

$\therefore \quad b^2 = ac$

$\Rightarrow \quad k^{2/y} = k^{1/x} \cdot k^{1/z}$

$\Rightarrow \quad \frac{2}{y} = \frac{1}{x} + \frac{1}{z} = \frac{z+x}{zx}$

$\Rightarrow \quad \frac{2z}{x+z} = \frac{y}{x}$

117. $-\frac{1}{2} < 1$, hence (d) is wrong.

$-\frac{1}{2} < \frac{1}{2}$, hence, it is correct ($x \in I^-$ and $y \in I^+$)

$\because \quad x < 0 \Rightarrow \frac{1}{x} < 0$

and $y > 0 \Rightarrow \frac{1}{y} > 0$

$\therefore \quad \frac{1}{x} < \frac{1}{y}$ Hence, (c).

118. $33.33 \div 1.1 = \frac{33.33}{1.1} = \frac{33.33}{1.10}$

$= \frac{3333}{110} = 30.3$

119. $|x - 2| < 3$

$\Rightarrow \quad (x - 2) < 3 \text{ or } (2 - x) < 3$

$\Rightarrow \quad x < 5 \text{ or } x > -1$

$\Rightarrow \quad -1 < x < 5$

120. Let the fraction be $\frac{x}{y}$, then

$\frac{x+1}{y+1} = 4$ ...(1)

and $\frac{x-1}{y-1} = 7$ ...(2)

Solving equations (1) and (2),

$x = 15$ and $y = 3$

Thus, (d) is correct.

121. $\because \quad (a-b)^3 + (b-c)^3 + (c-a)^3 = 0$

$\Rightarrow \quad (a-b) = 0 \Rightarrow a = b$

$(b-c) = 0 \Rightarrow b = c$

$(c-a) = 0 \Rightarrow c = a$

Thus, $a = b = c$ Hence, (c)

122. $(a+b+c)^2 = a^2 + b^2 + c^2 + 2(ab + bc + ac)$

$121 = 51 + 2(ab + bc + ac)$

$70 = 2(ab + bc + ca)$

$\Rightarrow \quad (ab + bc + ca) = 35$

123. $\frac{x^2}{yz} + \frac{y^2}{zx} + \frac{z^2}{xy} = \frac{x^3}{xyz} + \frac{y^3}{xyz} + \frac{z^3}{xyz}$

$= \frac{x^3+y^3+z^3}{xyz} = \frac{3xyz}{xyz} = 3$

($\because a^3 + b^3 + c^3 = 3abc$, when $a + b + c = 0$)

124. $\left(\frac{e^x+e^{-x}}{2}\right)^2 - \left(\frac{e^x-e^{-x}}{2}\right)^2 = \frac{e^{2x}+e^{-2x}+2}{4} - \frac{e^{2x}+e^{-2x}-2}{4}$

$= 1$

Scanned by CamScanner

yoursmahboob.wordpress.com

125. $(1-x)(1+x)(1+x^2)(1+x^4)(1+x^8)$

$=(1-x^2)(1+x^2)(1+x^4)(1+x^8)$

$[\because (a-b)(a+b)=a^2-b^2]$

$=(1-x^4)(1+x^4)(1+x^8)$

$=(1-x^8)(1+x^8)=(1-x^{16})$ Hence, (c)

126. Go through option : Consider the value of x such that $(5x+7)$ must be divisible by 13. Since, the product is an integer and the value of y must be such that $(13y+1)$ will be divisible by x.

Thus option (b) is correct.

127. Option (b) is clearly wrong. Again since $(28)^2=784$.

So, option (c) is also wrong. Now check for option (a)

$$\left(5\frac{15}{22}\right)^2=\left(\frac{125}{22}\right)^2=\frac{15625}{484}=32\frac{137}{484}$$

Thus, (a) is the correct option.

128. $\because \quad \sqrt{254016}=504$

and $\quad \sqrt{10609}=103$

$$\therefore \quad \frac{\sqrt{25.4016}-\sqrt{1.0609}}{\sqrt{25.4016}+\sqrt{1.0609}}=\frac{5.04-1.03}{5.04+1.03}$$

$$=\frac{4.01}{6.07}=\frac{401}{607}$$

129. $$\sqrt{\frac{\left(3\frac{1}{4}\right)^4-\left(4\frac{1}{3}\right)^4}{\left(3\frac{1}{4}\right)^2-\left(4\frac{1}{3}\right)^2}}=\sqrt{\frac{\left(\frac{13}{4}\right)^4-\left(\frac{13}{3}\right)^4}{\left(\frac{13}{4}\right)^2-\left(\frac{13}{3}\right)^2}}$$

$$=\sqrt{\left(\frac{13}{4}\right)^2+\left(\frac{13}{3}\right)^2}$$

$$=\sqrt{169\left(\frac{25}{144}\right)}=13\times\frac{5}{12}$$

$\left[\because \frac{a^2-b^2}{a-b}=\frac{(a+b)(a-b)}{(a-b)}=a+b,\right.$

$\left.a=\left(\frac{13}{2}\right)^2 \text{ and } b=\left(\frac{13}{3}\right)^2\right]$

$$=\frac{65}{12}=5\frac{5}{12}$$

130. The required number must be a factor of

$=34041-32506=1535$

Now since $\quad 1535=5\times307$

So, clearly 307 is the required number because it has 3 digits and is also a prime number.

131. Minimum number of corks $=\dfrac{403+434+465}{\text{HCF of }(403, 434, 465)}$

$$=\frac{1302}{31}=42$$

Hence, (c). For detailed discussion go back to examples.

132. The required value = HCF of 49.56 and 38.94 = 3.54

Hence, the sum = Rs. 3.54.

Thus, (b) is correct.

133. The required value = LCM of 12, 30, 18, 48 = 720

Hence, (b).

134. Time taken for each of three persons A, B and C is respectively $\frac{6}{3}$, $\frac{6}{2\frac{1}{2}}$ and $\frac{6}{1\frac{1}{4}}$ hrs

i.e., $\frac{2}{1}$, $\frac{12}{5}$ and $\frac{24}{5}$ hrs.

So, it is required to find the LCM of $\frac{2}{1}, \frac{12}{5}, \frac{24}{5}=\frac{24}{1}=24$ hr

Hence, (c).

135. $\because \dfrac{4\frac{1}{7}-2\frac{1}{4}}{3\frac{1}{2}+1\frac{1}{7}}=\frac{53}{130}$ and $\dfrac{1}{2+\dfrac{1}{2+\dfrac{1}{5-\frac{1}{5}}}}=\frac{53}{130}$

$$\therefore \quad \frac{53}{130}\div\frac{53}{130}=1$$ Hence, (c).

136. Let the total journey be x kms then,

$$\frac{5x}{16}+\frac{7x}{20}+10=x$$

$$\Rightarrow \quad x=29\frac{17}{27}$$

Hence, (d).

137. Since $\sqrt{3}$ is an irrational number.

138. $p>0$ and $q<0$

Now, let $p=3$ and $q=-4$

therefore $p-q=3-(-4)=7>0$

Hence, (b) is correct.

140. $(10x+y)=k(x+y)$ ...(1)

Again $(10y-x)=l(x+y)$ ...(2)

Now, adding equation (1) and (2)

$11(x+y)=(k+l)(x+y)$

$\Rightarrow \quad k+l=11 \Rightarrow l=(11-k)$

Hence, (c).

Scanned by CamScanner

yoursmahboob.wordpress.com

1. $5\times(3, 13, 23, 33, 43, 53, 63, 73, 83, 93)$
$+ 5\times(30, 31, 32, 33, 34, 35, 36, 37, 38, 39)$
$+ (301, 302, 303, 304, \ldots, 399)$
$= 5\times10 + 5\times10 + 100 = 200$

Explanation : In every set of 100 numbers there are 10 numbers whose unit digit is 3. Similarly in every set of 100 numbers there are 10 numbers whose tens digit is 3 and there are total 100 numbers whose hundreds digit is 3.

2. $1146600 = 2^3\times3^2\times5^2\times7^2\times13$
Thus total number of factors of
$1146600 = (3+1)(2+1)(2+1)(2+1)(1+1)$
$= 4\times3\times3\times3\times2 = 216$
So the number of ways in which 1146600 can be expressed as a product of two factors $= \frac{216}{2} = 108$
(for more discussion go back to the Basics)

3. The numbers which are divisible by 5 & 9 both means the number be divisible by 45. So the total number which are divisible by $45 = 22$ [45, 90, 135, ..., 990]
[i.e. all the numbers of the form $45k$, where $k = 1, 2, 3, \ldots, 22$]
Now since these obtained numbers will not be divisible by 7 so, the numbers of the form $45\times7l$ must be subtracted from these 22 numbers.
Thus the required number $= 22 - 3 = 19$
($\because k = 7l$). Thus the possible values of $l = 1, 2, 3$ for $k = 1, 2, \ldots, 22$

4. $\because |x| + |y| \le 0$ for $x, y \in R$
$\Rightarrow \quad |x| = 0 \text{ and } |y| = 0$
$\Rightarrow \quad x = 0 \text{ and } y = 0$
So there is only one solution for the expression i.e. $(x, y) = (0, 0)$

5. $\frac{2^{39}}{39} \to \frac{(2^6)^6\times2^3}{39} \to \frac{64^6\times8}{39} \to \frac{25^6\times8}{39} \to \frac{(625)^3\times8}{39} \to \frac{(1)^3\times8}{39} \to \frac{8}{39}$

Thus the remainder is 8.
(Since the final remainder can be obtained by the dividing the factors of the given number) for more information GO BACK TO THE BASICS.

6. The unit digit of $(1!)^{99}$ is 1
The unit digit of $(2!)^{98}$ is 4
The unit digit of $(3!)^{97}$ is 6
The unit digit of $(4!)^{96}$ is 6
The unit digit of $(5!)^{95}$ is 0
Now since we know that all the factorial numbers starting with 5! has its unit digits 0. So we need not to calculate it.
Thus the required unit digit
= unit digit of the sum of the unit digits
Thus the unit digit = 7 ($\because 1 + 4 + 6 + 6 + 0 = 17$)

7. The first four digit number which is divisible by 7 is 1001 and the last digit is 9996 and such total numbers are
$= \frac{8995}{7} + 1 = 1286$
So the sum of all these numbers $= \left(\frac{9946 + 1001}{2}\right)\times1286$
$= 7071071$
[Since all these numbers are in A.P. with common difference 7]

8. Let the fraction be $\frac{x}{y}$ then,
$$\frac{x+2}{2y} = \frac{1}{2}$$
$$\Rightarrow \quad \frac{x+2}{y} = 1$$
$$\Rightarrow \quad x + 2 = y$$
$$\Rightarrow \quad y - x = 2$$
Thus any even number greater than 3 can be the sum of x and y. Where x and y are some integers where $y - x = 2$
Further we know that the even − even = even
or odd − odd = even
Again even + even = even
and odd + odd = even
Thus in all the cases $x + y$ must be an even number.

9. $$pq = p - q + 9$$
$$\Rightarrow \quad pq + q = p + 9$$
$$\Rightarrow \quad q(p+1) = p + 9$$
$$\Rightarrow \quad q = \left(\frac{p+9}{p+1}\right)$$
Now since p is an integer such that q is a fraction.
So go through options and you will find that at $p = 7$ q is not a fraction. Hence (d) is the required answer
$\because q = \frac{7+9}{7+1} = 2$, which is inadmissible.

10. Option (b) is clearly invalid. Now since the difference between these numbers $= 792 = 99\times8$
Hence the difference between unit digit and hundreds digit must be 8. Thus option (d) is the right choice.
As $931 - 139 = 792$ and 1, 3, 9 are in G.P. also.
Alternatively :
$$(100a + 10ar + ar^2) - (100ar^2 + 10ar + a) = 792$$
$$\Rightarrow \quad 100a(1 - r^2) + a(r^2 - 1) = 792$$
$$\Rightarrow \quad 99a(1 - r^2) = 792$$
$$\Rightarrow \quad a(1 - r^2) = 8$$
But since $8 = 1\times8, 2\times4, 4\times2, 8\times1$
So at $a = 1$, $(1 - r^2) = 8$
$$\Rightarrow \quad r^2 = 9$$
$$\Rightarrow \quad r = \pm3$$
Therefore the digits are 1, 3 and 9.
(Note at $a = 2, 4$ and 8, r^2 is not a perfect square, thus inadmissible)

Scanned by CamScanner

yourSmallbooks.wordpress.com

11. The possible values can be obtained by substituting

$$k = 4, 6, 8, 10, \ldots, 102$$

Thus the number of required values $= \left(\frac{102-4}{2}\right) + 1 = 50$

12. Here $k = 3, 5, 7, \ldots, 103$

Thus the number of required values $= \left(\frac{103-3}{2}\right) + 1 = 51$

13. $\because a^2 - b^2 = (a+b)(a-b)$

Let us consider two odd prime number as 3 and 29.

Then $(29)^2 - 3^2 = (29+3)(29-3)$

$= 32 \times 26,$

which is divisible by 13.

Again consider 7 and 29,

Then $(29)^2 - 7^2 = (29+7)(29-7)$

$= 36 \times 22$, which is divisible by 11.

Further consider 3 and 37, then $(37)^2 - (3)^2 = 40 \times 34$ which is divisible by 17.

Hence (d) is correct.

NOTE As we know odd + odd = even = odd – odd. Thus consider such two number whose difference must be even multiple of the required divisor. As

$29 - 3 = 26 = 13 \times 2$

$29 - 7 = 22 = 11 \times 2$

$37 - 3 = 34 = 17 \times 2$

14. $P = (101)^{100}$, $Q = (100)^{101}$

$= (101)^{100}$ $= (100)^{100} \times (100)$

$= \frac{(101)^{100}}{(100)^{100}}$ $= \frac{(100)^{100}}{(100)^{100}} \times 100$ [Dividing both numbers by $(100)^{100}$]

$= (1.01)^{100} < 100$

Thus $P < Q$ hence (b).

15. $k^2 - 25 =$ An odd number

$\Rightarrow k^2$ must be even

$\Rightarrow k$ must be even

Thus both (a) and (b) are even numbers so (d) is correct as $(\text{even})^{\text{odd/even}} \rightarrow$ always even number

and odd × even → even

16. $(a+1)(b-1) = 625$

$\Rightarrow$ But $625 = 1 \times 625 = (a+1) \times (b-1) \Rightarrow a = 0, b = 626$

$5 \times 125 = (a+1) \times (b-1) \Rightarrow a = 4, b = 126$

$25 \times 25 = (a+1) \times (b-1) \Rightarrow a = 24, b = 26$

$125 \times 5 = (a+1) \times (b-1) \Rightarrow a = 124, b = 6$

$625 \times 1 = (a+1) \times (b-1) \Rightarrow a = 624, b = 2$

Thus $(a+b)$ is always equal to or greater than 50. Since the min $(a+b) = 50 = (24+26)$

Alternatively : $(a+1)(b-1) = 625$

$ab + b - a - 1 = 625$

$\Rightarrow b(a+1) - a = 626$

$\Rightarrow b(a+1) = a + 626$

$\Rightarrow b = \frac{(a+626)}{(a+1)} = \frac{(a+1)+625}{(a+1)} = \frac{625}{(a+1)} + 1$

Let us consider $a = 4$ then $b = 126$

Thus the only suitable option is (b) since option (c) and (d) are wrong and at $a = 24, b = 26 \Rightarrow a + b = 50$, which is least possible answer because in this case when the difference between a and b is least then $(a+b)$ is also least.

17. Since $p > 0$ then at $p = 1$, we get $q = 2$ and for the rest values $q > 2$

as when $0 < p < 1$ $\quad p + \frac{1}{p} > 2$

and also at $p > 1$ $\quad p + \frac{1}{p} > 2$

Hence $\quad p + \frac{1}{p} = q \geq 2$

18. $a^b = b^a; (a \neq b) > 1$

Let us consider $a = 2$ and $b = 4$ then

$2^4 = 4^2$

$16 = 16$ Hence (b)

NOTE $a + b = 5$ is not admissible since

$2^3 \neq 3^2$

and $a + b = 7$ is also not possible since

$2^5 \neq 5^2$ and $3^4 \neq 4^3$; where a and b are greater than 1.

19. $m^n - n^m = m + n$

Consider $m = 2$ and $n = 5$, then

$2^5 - 5^2 = 5 + 2$

$7 = 7$

Thus option (a) and (b) are wrong and option (c) is correct.

20. Since 334 or 433 are not the perfect cube hence (a) is wrong

Again 792, 279, 297, 972 or 927 are not the perfect cubes hence (b) is also wrong.

Further 512 is also a perfect cube hence (c) is correct answer.

Alternatively : See the perfect cubes of three digits as

$5^3 = 125$, $6^3 = 216$, $7^3 = 343$, $8^3 = 512$, $9^3 = 729$

So the digits of $5^3 = 125$ and $8^3 = 512$ are same. Hence (c) is the correct answer.

21. $n^4 - n^2 = n^2(n^2 - 1) = n^2(n+1)(n-1)$

Thus at $n = 3$ the given expression is divisible by 8, 4 and 12.

Hence it is divisible by all of a, b, c.

22. Since $(11)^4 = 14641$, hence b will be less than 4 always because 11 is the least two digit appropriate number but 14641 is a 5 digit number. Also $b \neq 1$, hence b lies between 1 and 4 i.e. b is equal to either 2 or 3.

Now try for suitable values of (aa) and b, we find that the only possible relation is

$(11)^3 = 1331$

Thus $\quad 1^3.3^1 + 3^1.1^3 = 6$

Hence (b) is the correct option.

23. $\frac{1}{6} : \frac{1}{5} : \frac{1}{3} : \frac{1}{2} = \frac{30}{6} : \frac{30}{5} : \frac{30}{3} : \frac{30}{2} = 5 : 6 : 10 : 15$

Therefore min. number of processers $= (5 + 6 + 10 + 15) = 36$

Hence (d) is correct.

24. $(392)^n - (392)^{n-1} = (392)^{n-1}[392 - 1]$

$= 392^{(n-1)}(391)$

Now since 13 is not the factor of either 391 or 392.

Hence (c) is the required answer.

Scanned by CamScanner

yoursmahboob.wordpress.com

25. Let the fair (*i.e.*, charge) per km be Rs. x, then the total distance travelled by Mr. Chaalu is $(x + 1)$.
Hence the total expenses $= x.(x + 1)$
but $x(x + 1) \le 350$
Thus the greatest possible value of $x = 18$
hence $18 \times 19 = 342$
Thus he is left with Rs. 8 only.

26. The number of times he pressed the keys for one digit number = 9
The number of times he pressed the keys for two digit number $= 90 \times 2 = 180$
The number of times he pressed the keys for three digit number $= 900 \times 3 = 2700$
The number of times he pressed the keys for the number 1000 to 1999 is $1000 \times 4 = 4000$
Then total number of times the keys are pressed = 6889

27. $\frac{(20)^{23}}{17} \to \frac{(3)^{23}}{17} \to \frac{(3^3)^7 \times 3^2}{17} \to \frac{(27)^7 \times 9}{17} \to \frac{(10)^7 \times 9}{17}$
$\to \frac{(10^2)^3 \times 90}{17} \to \frac{(15)^3 \times 5}{17} \to \frac{225 \times 75}{17} \to \frac{4 \times 7}{17} \to 11$
Hence the required remainder is 11.

28. Check for all the prime numbers between 3 and 50 you will find that option (d) is correct since all such numbers are always divisible by 8, 12 and 24.
Because $p^2 - 1 = (p + 1)(p - 1)$

29. Since the unit digit of primes number = 1, 2, 3, 5, 7, 9
So the unit digit of the squares of prime number
$= 1, 4, 9, 5, 9, 1$
Thus $1 + 1 = 2, 4 + 1 = 5, 9 + 1 = 10, 5 + 1 = 6, 9 + 1 = 10$ and $1 + 1 = 2$,
Hence the possible unit digits are 2, 5, 6, 0.
Thus 3, 7 or 9 are not possible hence (d) is correct.

30. The required number = Number of number, which are (divisible by 3 + divisible by 7 − divisible by 21)
Number of numbers which are divisible by 3
$= \left(\frac{198 - 3}{3}\right) + 1 = 66$
Number of numbers which are divisible by 7
$= \left(\frac{196 - 7}{7}\right) + 1 = 28$
Number of numbers which are divisible by 21
$= \left(\frac{189 - 21}{21}\right) + 1 = 9$
Thus the divisible value $= (66 + 28 - 9) = 85$
Hence the number of numbers which are not divisible
$= 200 - 85 = 115$
Hence (a) is the correct answer.

31. Only one value P can assume, which is 2 at $P = 2, P^2 + 3 = 7$, which is also prime.
Again at $P = 3, 5, 7, 11, \ldots$
$P^2 + 3 =$ an even number which can not be a prime number.

32. Let there be x bangles each side, then the total number of bangles he had $= x^2 + 38$
If he increases the size of the square by one unit each side, then the total number of bangles
$= (x + 1)^2 - 25$
Thus $x^2 + 38 = (x + 1)^2 - 25$
$x^2 + 38 = x^2 + 1 + 2x - 25$
$\Rightarrow 2x = 62$
$\Rightarrow x = 31$
Thus total number of bangles $= x^2 + 38$
$= 961 + 38 = 999$

Alternatively : Go through options, consider a suitable value from the options and check that in each case it must produce a perfect square number.
As $999 - 38 = 961$ is a perfect square
and $999 + 25 = 1024$ is also a perfect square.

33. Let $a = 20$ and $b = 15$
$a + b = 35$, which is not divisible by 10.

34. At $a = 7$ and $b = 2$, the following number becomes $\underline{7}55238792\underline{2}$, which is divisible by both 7 and 2.
But there are other values of (a, b) are possible consider $a = 4$ and $b = 2$, $a = 8$, $b = 2$ etc.
So there is no any unique value of a and b. Hence (d).

35. Any number of the form "*abcabc*" must be divisible by 1001 or its factors i.e. $1001 = 7 \times 13 \times 11$
Hence (a) and (b) are correct, thus (d) is the most appropriate statement.

36. Let suppose $a \to$ odd and $b \to$ even
then $\text{odd}^{\text{even}} \times \text{even}^{\text{odd}} = \text{odd} \times \text{even} = \text{even}$
even if a is even and b is odd, the result is an even number.

37. Let there be n rows, then the number of trees in each row $= (n + 1)$
Thus total number of trees $= n(n + 1)$
$\therefore n(n + 1) = 5550$
Now, at this moment this problem can be solved in two ways. First by finding the roots of quadratic equation. Second by using the values from options.
Again since the value of $(n + 1)$ is given in the options so consider option (d)
$74(75) = 5550.$
Hence (d) is correct.

38. $3^a = 9^b \Rightarrow a = 2b$
and $4^{(a+b+2)b} = 16^{ab}$
$\Rightarrow (a + b + 2)b = 2ab$
$\Rightarrow a + b + 2 = 2a$
$\Rightarrow a - b = 2$
$\Rightarrow b = 2$ $(\because a = 2b)$
$\therefore a = 4$

39. These numbers are 11, 13, 31, 17, 71, 37, 73, 79, 97.

40. Since he has covered twice the distance which yet he has to cover. It means he has covered $\frac{2}{3}$ of the whole journey and remaining journey is $\frac{1}{3}$rd.

Scanned by CamScanner

yoursmahboob.wordpress.com

41. Let the x cm height increases per year then the height at the end of $2002 = 6x + 90$

and the height at the end of $2003 = 7x + 90$

but $$7x + 90 = (6x + 90) + (6x + 90)\frac{1}{9}$$

$$\Rightarrow \quad (7x + 90) = (6x + 90) \times \frac{10}{9}$$

$$\Rightarrow \quad 63x + 810 = 60x + 900$$

$$\Rightarrow \quad 3x = 90$$

$$x = 30 \text{ cm}$$

Thus the height at the end of $2008 = 90 + 12x$

$$= 90 + 12 \times 30 = 450 \text{ cm}$$

42. Let the cost of watch be Rs. x

Then the total amount for 12 months except ration $= 250 + x$

Therefore the amount for 9 months $= (250 + x) \times \frac{3}{4}$

Thus $$(250 + x)\frac{3}{4} = 270$$

$$\Rightarrow \quad 750 + 3x = 1080$$

$$\Rightarrow \quad 3x = 330$$

$$\Rightarrow \quad x = 110$$

Therefore the cost of wrist watch = 110

(It can also be solved using options.)

43. $$1^2 + 3^2 = 10$$

$$13 + 18 = 31$$

44. When two "two digit" numbers are added and the resultant value is a 'three digit number". It means there must be carry over (*i.e.* the sum of the unit digits be greater than 9. Similarly the sum of the tens digit is also greater than 9.)

Hence (d) is correct as $\begin{array}{r} 72 \\ 27 \\ \hline 99 \end{array}$ inadmissible but $\begin{array}{r} 64 \\ 46 \\ \hline 110 \end{array}$ is admissible value.

45. '*A*' grade student $= 57.\overline{142857}\% = \left[57 + \frac{1}{7}\right]\%$

$$= \frac{400}{7}\% = \frac{4}{7} \text{ of the total student}$$

'*B*' grade student $= 26.444\%$

$$= \left[26 + \frac{4}{9}\right]\% = \frac{238}{9}\%$$

$$= \frac{238}{900} \text{ of the total student}$$

Now the total student of '*A*' and '*B*' grade

$$= \frac{4}{7} + \frac{238}{900}$$

$$= \frac{3600 + 1666}{6300} = \frac{5266}{6300}$$

$$= \frac{2633}{3150} \text{ of the total student}$$

$\therefore$ The number of students who achieved the grade (c)

$$= 1 - \frac{2633}{3150} = 517 \text{ students}$$

Since the maximum number of students are below 3500. So there can not be the number of students in the multiple of 3150.

46. $3\overline{)16}(5$ Remainder is odd.
$\underline{15}$
1

47. $551 + 552 + 553 + \ldots + 559 + 560$

$= (500 + 500 + 500 \ldots 10 \text{ times}) + (51 + 52 + 53 + \ldots + 60)$

$= 5000 + (50 + 50 + 50 \ldots 10 \text{ times}) + (1 + 2 + 3 + \ldots + 10)$

$= 5000 + 500 + 55 = 5555$

48. $$x^2 + x = x^3 - x$$

$$\Rightarrow \quad x^3 - x^2 - 2x = 0$$

$$\Rightarrow \quad x(x^2 - x - 2) = 0$$

$$\Rightarrow \quad x = 0 \quad \text{or} \quad x^2 - x - 2 = 0$$

If $$x^2 - x - 2 = 0$$

$$\Rightarrow \quad (x - 2)(x + 1) = 0$$

$$\Rightarrow \quad x = 2 \quad \text{or} \quad x = -1$$

Thus $x = 2$ is the possible value of x.

Hence (b).

Alternatively : Go through options

$$2^2 + 2 = 2^3 - 2$$

$$6 = 6$$

49. As we have seen in above problem that the equation is of 3 degree equation. Hence there are 3 solution for x *viz.* $x = 0, 2$ and -1.

50. The required number of digits written as the thousands digit = 101

The required number of digits written as the hundreds digit = 99

The required number of digits written as the tens digit = 10

The required number of digits written as the unit digit = 10

Thus total number of 3-digits = 220

51. $(2^{19} + 1) = (2^{19} + 1^{19})$

Now, $2^{19} + 1^{19}$ is divisible by $3 (= 2 + 1)$

Since $(a^n + b^n)$ is always divisible by $(a + b)$, when 'n' is odd.

Again since $(2^{19} + 1)$ is an odd number, hence no any even number can divide it. Thus (a) is the correct option.

52. Except to 467 all the rest numbers are divisible by 3.

53. $\because \quad 1001 = 7 \times 11 \times 13$

Hence (b).

54. $\because \quad 5400 = 2^3 \times 3^3 \times 5^2$

To get a perfect square there must be even number of powers of each prime factors.

So the least such perfect square $= 2^3 \times 3^3 \times 5^2 \times 2 \times 3$

$$= 32400$$

Thus we have to multiply it by 6 inorder to get a perfect square.

55. At $x = 0$ and 1 the valid relation is

$$p^x q^{(1-x)} = px + q(1 - x)$$

Hence (b).

56. $$3780 - 2835 = 945$$

Now $$\frac{3780 + 2835}{945} = \frac{6615}{945} = 7$$

57. $(x + y)^{-1}.(x^{-1} + y^{-1}) = \frac{1}{(x + y)}\left(\frac{1}{x} + \frac{1}{y}\right)$

$$= \frac{1}{(x + y)}\left(\frac{x + y}{xy}\right) = \frac{1}{xy} = (xy)^{-1}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

58. In every set there is only one such relation exists as if $p = 3$, $k = 2$

Then the remainder is 1 when $\frac{k^2}{p} = \frac{4}{3}$

Similarly if $p = 7$ and $k = 6$

Then the remainder is 1 when $\frac{k^2}{p} = \frac{36}{7}$ etc.

Hence k is always $(p - 1)$.

59. Go through option consider the correct option (c).

Absent students $= 2700 \times \frac{1}{9} = 300$

$\therefore$ Number of students appeared in exam = 2400

Number of students who passed $= 2400 \times \frac{19}{24} = 1900$

Thus number of failed students = 2400 – 1900 = 500

Hence presumed option is correct.

Alternatively : Failed students $= 500 = \frac{5}{24}$

$\therefore$ Passed students $= \frac{19}{24} = 1900$

Thus the number of students appeared in exam $= 2400 = \frac{8}{9}$

$\therefore$ Total number of students registered $= \frac{2400 \times 9}{8} = 2700$

Alternatively : Let the x students registered for the exam then the number of students appeared in exam $= x - \frac{x}{9} = \frac{8x}{9}$

Again the number of passed students $= \frac{8x}{9} \times \frac{19}{24} = \frac{19x}{27}$

Thus the number of failed students $= \frac{5x}{27} = 500$

$\Rightarrow$ $x = 2700$

60. $km < kn \Rightarrow \frac{km}{kn} < 1$

Since for any value of k the above relation is true thus we can't specify that whether for $k < 0$, or $k > 0$ this is True.

Hence (d).

61. Rational + Irrational = Irrational Number

62. In first 1122 years 'Decay' becomes 40 gm
In next 1122 years 'Decay' becomes 20 gm
In next 1122 years 'Decay' becomes 10 gm
and In last 1122 years 'Decay' becomes 5 gm

63. Vinod gets 210 marks and failed by 40 marks

It means the min. marks required = 250 = $\frac{2}{5}$th of total.

Therefore maximum (or total) marks $= 250 \times \frac{5}{2} = 625$

64. Marks in QA : Marks in English $= \frac{3\frac{1}{2}}{1} = \frac{\frac{7}{2}}{1} = \frac{7}{2}$

Thus his marks in QA $= 70 \left(= 90 \times \frac{7}{9}\right)$

65. $\begin{array}{r} 72 \\ +27 \\ \hline 99 \end{array}$ and $\begin{array}{r} 72 \\ -27 \\ \hline 45 \end{array}$

But we are not sure whether it is larger or smaller number so (d) is the most appropriate answer.

66. Go back to the Basics. (Refer Indices)

67. $12 \times 63 = 756$ and $21 \times 36 = 756$

68. The best way to consider the values from given range in options.

Thus option (a) is obviously ruled out since at $p = -1$ the relation is undefined. Similarly if we consider option (d) then at $p = -\frac{1}{2}$.

$\frac{p}{p-1} = -1$, which is wrong. Thus (b) is also wrong.

Hence (c) is correct.

69. The form of the required number is $14k + 8$

but when $14k + 8$ is divided by 7, then

$$\frac{14k+8}{7} = \frac{14k+(7+1)}{7} = \frac{(14k+7)+1}{7}$$

Thus the remainder will be 1.

NOTE $14k$ is already divisible by 7 and thus $14k + 7$ will also be divisible by 7.

Remember : In this type of problem just divide the existing remainder and get the required answer. As $\frac{8}{7} \rightarrow$ Remainder is 1.

70. The unit digit of $(316)^{3^{4n}}$ is always 6.

So the unit digit of $(316)^{3^{4n}} + 1$ will be 7.

71. $a + b = 18$

So maximum of $(a \times b)$ will be only when $a = b$

$\therefore$ $a = b = 9$

$\therefore$ Maximum of $a \times b = 9 \times 9 = 81$

72. Let the smallest possible number be x, then

$$x = 15k + 12$$

and $$x = 8l + 5$$

$\Rightarrow$ $15k + 12 = 8l + 5$

$\Rightarrow$ $15k + 7 = 8l$

$\Rightarrow$ $l = \frac{15k + 7}{8}$,

l must be an integer putting $k = 1, 2, 3, \ldots$ etc.

But at $k = 7$, we get a number which on being divided by 8, gives 'l' as an integer.

So the $x = 15 \times 7 + 12$

$x = 117$

The next higher numbers = (L.C.M. of divisors) $m + 117$

= (L.C.M. of 15 and 8) $m + 117$

$= 120\,m + 117$

So consider the highest possible value of m such that $120m + 117 \leq 9999$ (largest possible number of four digit)

Thus at $m = 82$, the value of $120m + 117 = 9957$, which is the required number.

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively : Go through option.
It is very obvious from the option that the option (a), (c) and (d) are wrong because when you multiply any number by 15, it will give the unit digit either 0 or 5 and when you add 12 to this product the unit digit will be either 2 or 7.
Or in other way divide the values in the given options by 8 and it must leave the remainder 5.

73. Go through alternatives. Consider option (b)

Total mobiles = 600

$$\text{Indian mobiles} = 600 \times \frac{5}{12} = 250$$

and $$\text{imported mobiles} = 600 \times \frac{7}{12} = 350$$

$$\text{The coloured mobiles of Indian origin} = 250 \times \frac{1}{5} = 50$$

The coloured mobiles of which are imported

$$= 350 \times \frac{2}{7} = 100$$

Thus total coloured mobiles = 50 + 100 = 150, which is same as given in the problem. Hence the presumed option is correct.

Alternatively : Solve through equation.

74. The minimum time interval, at which time from all the destinations, the call centre received the calls

= the L.C.M. of 10, 12, 20 and 25
= 300 minutes
= 5 hours

Thus 5 + 5 = 10 A.M. and 10 + 5 = 15 = 3 : 00 P.M.
Hence (d).

75. H.C.F. of $2^4, 8^2, 16^2, 20^3 = 2^4$
L.C.M. of $2^4, 8^2, 16^2, 20^3 = 2^8 \times 125 = 32{,}000$

76. Go through options : Consider option (b)

$$15192327 - 84 = 15192243$$

Now, $(3 + 2 + 9 + 5) - (4 + 2 + 1 + 1) = 11$

and $1 + 5 + 1 + 9 + 2 + 2 + 4 + 3 = 27$

Thus 15192243 is divisible by both 11 & 9 hence by 99.
Thus the presumed remainder 84, is correct.

77. The total numbers (integral) between 1 and 200 = 198
The number of numbers divisible by 2 = 99 (2, 4, 6, ..., 198)
The number of numbers which are purely divisible by 3 but not by 2.
(Since the division by 2 is taken into account, already)

$$= \frac{(195 - 3)}{6} + 1 = 33 \qquad (3, 9, 15, 21, \ldots, 195)$$

The number of numbers which are purely divisible by 5 but not by 2 and 3

$$= \left\{\frac{(195 - 5)}{10} + 1\right\} - \left\{\frac{195 - 15}{30} + 1\right\}$$

$$= 20 - 7 = 13$$

Thus the total number of numbers lying between 1 and 200, which are divisible by 2, 3 or 5 = 99 + 33 + 13 = 145.

NOTE In ill case we did not consider 10, 20, 30, ... etc. for the division of 5 because these numbers have been divided already by 2.

Alternatively : So the required number

= (53 + 13 + 26) + (27 + 13 + 7) + 6 = 145



(for more clarification of the solution see the chapter of set theory or the example discussed in the theory of this same chapter.)

78.

$$xAy \to x + y$$
$$xSy \to x - y$$
$$xMy \to x \times y$$
$$xDy \to x \div y$$

$$4D2S3M6A12 = 4 \div 2 - 3 \times 6 + 12$$
$$= 2 - 3 \times 6 + 12$$
$$= 2 - 18 + 12 = -4$$

79. Go through options
L.C.M. of 204 and 170 = 1020.

80. $1 - 3 + 5 - 7 + 9 - 11 + \ldots + 197 - 199$
$= (-2) + (-2) + (-2) + \ldots + (-2)$ [50 times]
$= 50 \times (-2) = -100,$ Hence (d).

81. $\left(1 - \frac{1}{2}\right)\left(1 - \frac{1}{3}\right)\left(1 - \frac{1}{4}\right)\left(1 - \frac{1}{5}\right)\ldots\left(1 - \frac{1}{n}\right)$

$$= \frac{1}{2} \times \frac{2}{3} \times \frac{3}{4} \times \frac{4}{5} \times \ldots \times \frac{(n-2)}{(n-1)} \times \frac{(n-1)}{n} = \frac{1}{n}$$

82. $\text{Minimum of } \frac{x}{y} = \frac{\text{Max. of } x}{\text{Min. of } y} = \frac{2}{32} = \frac{1}{16}$

and $\text{Maximum of } \frac{x}{y} = \frac{\text{Max. of } x}{\text{Min. of } y} = \frac{8}{16} = \frac{1}{2}$

83. $56 = 1 \times 56 \Rightarrow$ H.C.F. is 1, hence number of tiles = 56
$2 \times 28 \Rightarrow$ H.C.F. is 2, hence number of tiles = $1 \times 14 = 14$
$4 \times 14 \Rightarrow$ H.C.F. is 2, therefore number of tiles = $2 \times 7 = 14$
$7 \times 8 \Rightarrow$ H.C.F. is 1, therefore number of tiles = $7 \times 8 = 56$
hence the minimum number of tiles can be 14. Thus (c) is correct option.

84. $x + \frac{9x}{4} = 221 \Rightarrow x = 68$ metre

and $\frac{9}{4}x = 153$ metre

Thus the difference between two parts = 153 − 68 = 85 metre

85. Total prime numbers between 1 and 100 = 25
and total prime numbers between 101 and 200 = 21 } 46

86. $\frac{6^{36}}{215} \to \frac{(6^3)^{12}}{215} \to \frac{(216)^{12}}{215} \to \frac{1^{12}}{215} \to 1$ is the remainder.

Scanned by CamScanner

yoursmahboob.wordpress.com

87. $\frac{12^{13}}{11} \rightarrow$ Remainder is 1.

$\frac{23^{13}}{11} \rightarrow$ Remainder is 1.

$\therefore$ The remainder of $\frac{(12^{13} + 23^{13})}{11}$ is $(1 + 1) = 2$

88. The least possible number = (L.C.M. of 4, 5, 6, and 7) + 3

$= 420 + 3 = 423$

The next higher number $= (420m) + 3$

Now put the least possible value of m such that

$(420m + 3) \geq 1000$

So at $m = 3$, the required value $= 1260 + 3 = 1263$

Alternatively : Option (a) and (b) are ruled out since when we divide these numbers by 5 they do not leave the remainder 3.

Again check the option (c) instead of (d) because we are required to find out the smallest possible number.

89. $13^{31} > 31^{13}$

$\frac{13^{31}}{13^{13}} > \frac{31^{13}}{13^{13}}$

$13^{18} > (2.4)^{13}$

Hence it is correct.

Again $10^{100} < 100^{10}$

$10^{100} < (10^2)^{10}$

$10^{100} < 10^{20}$ which is wrong.

Again, $2^{32} < 32^2$

$2^{32} < (2^5)^2$

$2^{32} < 2^{10}$ which is also wrong.

Hence (d) is the correct option.

90. Since it is not clear that which particular numbers are odd and which are even.

So we can't say about option (a), (c) and (d). Again in option (b) there are 1 more than half of the total numbers, so we can infer that there must be atleast one even number. Further we know that the product with even number is always even

i.e. even × odd = even

and even × even = even

Thus option (b) is confirm.

91. (43 and 387) and (129, 301)

$43k + 43l = 430$

$\Rightarrow 43(k + l) = 430$

$\Rightarrow k + l = 10$

but k, l must be coprimes.

So $(k, l) = (1, 9)$ and $(3, 7)$

92. $2^{73} - 2^{72} - 2^{71} = 2^{71}(2^2 - 2^1 - 1)$

$= 2^{71}(4 - 2 - 1) = 2^{71}$

93. Since we know that if $a + b + c = 0$, then

$a^3 + b^3 + c^3 = 3abc$

Hence $55^3 + 17^3 - 72^3 = 3 \times 55 \times 17 \times (-72)$

$= -(3 \times 5 \times 11 \times 17 \times 2^3 \times 3^2)$

Thus the given number is divisible by 3, 17, 40, 11 and 15.

Hence (d) is the most appropriate answer.

94.

$$
\begin{array}{r|l}
13 & 999999 \\
 & 91 \\
 & 89 \\
 & 78 \\
 & 119 \\
 & 117 \\
 & 29 \\
 & 26 \\
 & 39 \\
 & 39 \\
 & \times
\end{array}
\quad 76923
$$

Thus $abcde = 76923$.

$\therefore a + b + c + d + e = 7 + 6 + 9 + 2 + 3 = 27$

95. $n + (n + 2) + (n + 4) = 3n + 6 = 3(n + 2)$,

where $n = 2, 4, 6, \ldots$

So it is always divisible by 12.

Hence (d).

96. Since we know that $(a^3 + b^3) = (a + b)(a^2 + ab + b^2)$ which is divisible by $(a + b)$ hence leaves no any remainder.

97. $N = n(n + 1)(n + 2)(n + 3)(n + 4)$

at $n = 1$, $N = 120 = 1 \times 2 \times 3 \times 4 \times 5$

$n = 2$, $N = 720 = 2 \times 3 \times 4 \times 5 \times 6$

$n = 3$, $N = 2520 = 3 \times 4 \times 5 \times 6 \times 7$

$n = 4$, $N = 6720 = 4 \times 5 \times 6 \times 7 \times 8$ etc.

Hence the possible number is 120.

98. $(x - y)^2 = x^2 + y^2 - 2xy = 25 - 24$

$\Rightarrow (x - y) = \pm 1$

Similarly $(x + y) = \pm 7$

So, solving for x and y, we get

$x = -3, -4, 3$ and 4

and $y = -4, -3, 4$ and 3

Thus $x^{-1} + y^{-1} = \frac{1}{x} + \frac{1}{y} = \frac{7}{12}$ and $\frac{-7}{12}$

Hence (d).

99. $\frac{75^{75^{75}}}{37} = \frac{1^{75^{75}}}{37} \rightarrow$ Remainder is 1.

100. $\frac{p^2 + 17}{12} \rightarrow \frac{(p^2 + 5)}{12} \rightarrow$ Now since $p^2 = 12m + 1$.

Therefore $\frac{p^2 + 5}{12} \rightarrow \frac{(12m + 1) + 5}{12} \rightarrow \frac{12m + 6}{12}$

Hence the remainder is 6.

101. The unit digit of $(12345k)^{72}$ is 6.

Means the unit digit of k^{72} is 6.

Now, go through options and verify

$6^{72} \rightarrow$ unit digit is 6

$8^{72} \rightarrow$ unit digit is 6

$2^{72} \rightarrow$ unit digit is 6

Hence (d).

102. **Go through option.** If you subtract 2, 8 or 25 from 369, then you will not obtain a perfect cube number. So (b) is the correct answer.

Alternatively : If you write down the nearest perfect cube such that $k \leq 369$, where k is a perfect cube, then

$7^3 = 343$, which is just below 369.

So $369 - 343 = 26$

Scanned by CamScanner

yourSmahboob.wordpress.com

103. $n(n+2) = 624$

$\therefore$ from options $24 \times 26 = 624$

or find the roots of quadratic equation $n^2 + 2n - 624 = 0$.

104. $\frac{1719 \times 1715 \times 1713}{17} \to \frac{2 \times 15 \times 13}{17} \to \frac{30 \times 13}{17} \to \frac{13 \times 13}{17}$

$\to \frac{169}{17} \to 16$, is the required remainder.

105. $\frac{12.5}{1/6} = \frac{12.5 \times 6}{1} = 75$

106. $32k - 23k = 315$

$\Rightarrow \quad 9k = 315 \Rightarrow k = 35$

$\therefore$ The original product $= 23 \times 35 = 805$

107. Let the fraction be $\frac{x}{y}$, then

$$\left(\frac{x}{y}\right)^2 = \frac{x^2}{y^2}$$

then $$\frac{\frac{2}{3}x^2}{\frac{1}{5}y^2} = \frac{10x^2}{3y^2}$$

Thus $$\frac{10x^2}{3y^2} = 2\frac{x}{y}$$

$\Rightarrow$ $$\frac{x}{y} = \frac{3}{5}$$

Hence $x + y = 3 + 5 = 8$

108. The required number

= H.C.F. of (221–104), (377–221) and (377–104)

= H.C.F. of 117, 156, 273 = 39

109. $(ab^2)^{1/3} = 125 = 5^3$

$\Rightarrow \quad ab^2 = (5^3)^3$

$ab^2 = 5^9$

Now since $a \neq b \neq 1$ and $(a, b) > 1$.

Therefore a and b must be equal to the some power of 5.

Again since $a > b$, so check the option (b).

Consider $a = b^4$

$\therefore \quad ab^2 = 5^9$

$b^6 = 5^9$

$\Rightarrow \quad b^2 = 5^3$

then $a = b^4 = 5^6$

$\therefore \quad ab^2 = 5^6 \times 5^3 = 5^9$, which is correct.

Thus the presumed option (b) is correct.

Option (a) is clearly wrong and option (c) is also wrong.

Because $a^{3/2} = b^{2/3} \Rightarrow a^{9/6} = b^{4/6} \Rightarrow a < b$, which is inadmissible.

110. $24 = 8 \times 3$, so the given number must be divisible by both 8 & 3.

Now for 8, $n = 1, 5, 9$

Again for 3, when $n = 1$ then $m = 3, 6, 9$

and when $n = 5$ then $m = 2, 5, 8$

and when $n = 9$ then $m = 1, 4, 7$

Thus there are total 9 combinations of m and n.

111. Let the fraction be $\frac{x}{y}$, then its reciprocal be $\frac{y}{x}$,

$\therefore \quad \frac{\frac{x}{y}}{\frac{y}{x}} = \frac{x^2}{y^2}$

Now $\frac{x^2}{y^2} \times \frac{x}{y} = \frac{x^3}{y^3} = \frac{512}{125} = \frac{8^3}{5^3}$

$\Rightarrow \quad \frac{x}{y} = \frac{8}{5}$

$\therefore \quad \frac{y}{x} = \frac{5}{8}$

$\therefore \quad \frac{x}{y} - \frac{y}{x} = \frac{8}{5} - \frac{5}{8} = \frac{64 - 25}{40} = \frac{39}{40}$

112. Consider the values as $441 - 41 = 400$

$441 + 43 = 484$

So, $41 + 43 = 84$, which is divisible by 4.

113. $(11)^a = (19)^b = (209)^c = z$

$\Rightarrow \quad 11 = z^{1/a}, 19 = z^{1/b}, 209 = z^{1/c}$

Therefore $11 \times 19 = 209$

$z^{1/a} \times z^{1/b} = z^{1/c} = z^{(1/a + 1/b)} = z^{1/c}$

$\Rightarrow \quad \frac{1}{a} + \frac{1}{b} = \frac{1}{c}$

$\Rightarrow \quad c(a + b) = ab$

114. $\frac{2^{54} - 1}{9} = \frac{(2^6)^9 - 1}{9} = \frac{(64)^9 - 1}{9}$

$\Rightarrow \quad \frac{(1)^9 - 1}{9} \Rightarrow 0$

Hence there will be no any remainder.

115. 64 is the only number which is both a perfect square and a perfect cube.

So $6 + 4 = 10$.

116. The only possible number is 729 which is the cube of 9 and square of 27.

So $7 \times 2 \times 9 = 126$

117. In order to N be a least possible number $c < b < a$.

But $c \neq 1$, since $a \neq b \neq c$.

So the least possible value of $c = 2$, then

$c^8 = 2^8 = 256 = 4^4 = 16^2$

Thus $a = 16$, $b = 4$ and $c = 2$ the required number is 256.

118. Go through option.

119. There are only 4 digits whose square also gives the same unit digit which are 0, 1, 5 and 6.

But the number whose unit digit is 0 (zero), this number after squaring makes the tense digit zero also. Again it means the tens digit of the original number be zero. Now if we square such a number whose tens and unit digits are zero, this number gives 4 zeros (at least) on the end of the square which is not possible since 000 can not be considered a relevent number. Thus zero cannot be the unit digit.

Now, if we consider unit digit 1, and any digit except zero.

Scanned by CamScanner

yoursmahboob.wordpress.com

NOTE Zero shows the same behaviour as in the first case), then unit digit remains the same on being squared the given number but tens digit gets changed so, 1 as a unit digit is also impossible. Now if we consider 6 as probable unit digit similar behaviour is seen with 6 also.
Thus, if we consider 5 as a unit we always get 5 as a unit digit after squaring any number whose unit digit is 5. Also we always get the 2 as the tens digit when we square any number whose unit digit is 5. Now to maintain the tens digit '2' we consider a number whose tens and unit digits be respectively 2, 5. Now if we square to 25, we get a three digit number 625. It means if it is possible, then the three digit given number must be 625.

Now, $(625)^2 = 390625,$

which satisfies the given conditions.

Now $3 \times 9 \times 0 \times 6 \times 2 \times 5 = 0$

Hence (a) is correct.

120. $3^{6n} + 4^{6n} \to 9^{3n} + 16^{3n}$

Now $9^{3n} + 16^{3n}$ is divisible by $25\ (= 9 + 16)$

Since $(a^n + b^n)$ is divisible by $(a + b)$ only when 'n' is odd.

Hence n must be odd.

121.

5	100	
5	20 →	24
	4 →	

Number of zeros = 24

122.

3	41	
3	13 →	
3	4 →	18
	1 →	

$41! = 3^{18} \times k^a \times l^b$

123. Go through options

$$36 = 4 \times 9 = (2)^2 \times (3)^2$$

3, 6, 9 are in G.P.; $9 = (3 + 6)$

$$36 + 27 = 63$$

124. $7777 + 7777 \times 7777 \times (5 \div 77) \times (11 \div 35)$

$$= 7777 + 7777 \times 7777 \times \frac{5}{77} \times \frac{11}{35}$$

$$= 7777 + 1111 \times 1111$$

$$= 7777 + 1234321 = 1242098$$

Hence (d) is the answer.

125. Go through options

$$\frac{7}{8} + \frac{8}{7} = \frac{113}{56}$$

and $$\frac{8}{7} - \frac{7}{8} = \frac{15}{56}$$

Alternatively $$a + \frac{1}{a} = \frac{113}{56}$$

and $$a - \frac{1}{a} = \frac{15}{56}$$

Solve these equations.

126. Let $\frac{x}{y}$ be the fraction, then

$$\frac{x+4}{y} = \frac{1}{3}$$

and $$\frac{x}{y+3} = \frac{1}{6}$$

$\Rightarrow$ $3x + 12 = y$

and $6x = y + 3$

$\Rightarrow$ $x = 5$ and $y = 27$

Thus $x + y = 32$

127. Go through options and subtract the reasonable value from 7777 and see that whether the resultant number is a perfect square.

Alternatively : $n^2 \le 777 \Rightarrow n^2 = 7744$

Hence 33 (= 7777 – 7744) chairs are required to remove from that place.

128. $$p^r \cdot p^{-1} \cdot p^s = (\sqrt{p^3})^2$$

$\Rightarrow$ $$p^{r+s-1} = p^3$$

$\Rightarrow$ $$r + s - 1 = 3$$ ...(1)

$\Rightarrow$ $$r + s = 4$$

Again $$p^{3/2} \cdot p^r = p^s \cdot p^{-1/2}$$

$\Rightarrow$ $$p^{r+3/2} = p^{s-1/2}$$

$\Rightarrow$ $$r + \frac{3}{2} = s - \frac{1}{2}$$

$\Rightarrow$ $$r - s = -2$$ ...(2)

$\Rightarrow$ $r = 1$ and $s = 3$

Thus $(r + s)^{r+s} = (4)^4 = 256$

Hence (d).

129. $$5^{-k} = \frac{1}{l} \Rightarrow l = 5^k$$

$$5^{3k} = (5^k)^3 = (l)^3$$

Hence (c) is correct.

130. $$5^{x-1} + 5^x + 5^{x+1} = 775$$

$\Rightarrow$ $$5^{x-1}(1 + 5 + 5^2) = 775$$

$\Rightarrow$ $$5^{x-1}(31) = 775$$

$\Rightarrow$ $$5^{x-1} = 25 \Rightarrow 5^2$$

$\Rightarrow$ $$x - 1 = 2 \Rightarrow x = 3$$

131. The perfect square digits are 1, 4 and 9.
So the number formed by using any of these two digits which is also a perfect square is 49.

where $(4 \times 9) + (4 + 9) = 49$

$36 + 13 = 49$

$49 = 49$

So, $94 - (9 + 4) = 81$

132. Consider some consecutive values.

133. $25930800 = 2^4 \times 3^3 \times 5^2 \times 7^2$

So, if this number is divided by 3, then we get the quotient as a perfect square.

134. Let the Arun has x books and Prabhat has y books with them, then

$$2(x - 3) = (y + 3)$$

$$2x - 6 = y + 3$$

$\Rightarrow$ $$2x - y = 9$$ ...(1)

and $$(x + 2) = (y - 2)$$

$\Rightarrow$ $$x - y = -4$$ ...(2)

Solving equations (1) and (2), we get $x = 13$ and $y = 17$ thus $x + y = 30$.

Alternatively : Go through option.

Consider Option (c) :



(Solve in reverse)

Scanned by CamScanner

yoursmahboob.wordpress.com

136. Weight of Bottle + Total volume of water = 1600 gm

Weight of Bottle + $\frac{1}{3}$ volume of water = 900 gm

$\Rightarrow \frac{2}{3}$ volume of water = 700 gm

$\Rightarrow$ total volume of water = $700 \times \frac{3}{2} = 1050$ gm

$\therefore$ The weight of empty bottle = 550 gm

$= (1600 - 1050)$

137. $(10a + b) \times (10c + d) - (10b + a) \times (10d + c)$

$= (100a.c + 10b.c + 10a.d + b.d)$

$- (100b.d + 10b.c + 10a.d + a.c)$

$= 99\,(a.c - b.d)$

Now, inorder to the difference be maximum so $a \times c$ will be maximum and $b.d$ will be minimum, thus $a \times c = 9 \times 8 = 72$

and $b \times d = 1 \times 2 = 2$

Hence $99\,(ac - bd) = 99\,(72 - 2) = 99 \times 70 = 6930$

138. $12600 = 2^3 \times 3^2 \times 5^2 \times 7$

Required value $= 2^{(n-1)} = 2^{(4-1)} = 2^3 = 8$

where $n \rightarrow$ number of prime factors.

Here 2, 3, 5, 7 are total 4 prime factors.

139. Go through options.

140. $(2^{123} - 2^{122} - 2^{121}) \times (3^{234} - 3^{233} - 3^{232})$

$= 2^{121}\,(2^2 - 2 - 1) \times 3^{232}\,(3^2 - 3 - 1)$

$= 2^{121}\,(1) \times 3^{232} \times 5$

$= 2^{121} \times 3^{232} \times 5^1$

Therefore there will be only one zero at the end of the product.

LEVEL 2

1. Since these bells tolls 18 times in 24 hrs

So the min. time interval when they toll together $= \frac{24}{18}$

$= 80$ minutes

So the required number of bells

= total number of different factors of 80

Now since $80 = 2^4 \times 5$

$\therefore$ Total number of factors $= (4 + 1)(1 + 1) = 10$

Thus the maximum number of bells = 10

NOTE The time interval of all the bells individually will be the factor of 80.

2. Consider the following relation and compare with $p^q = q^r$

$2^4 = 4^2 \Rightarrow p = 2,\ q = 4,\ r = 2$

$\Rightarrow q > r$

Again $4^2 = 2^4 \Rightarrow p = 4,\ q = 2,\ r = 4$

$\Rightarrow q < r$

So we can't say exactly whether $q < r$ or $q > r$.

NOTE If we know the relation between p and q then only we can say about q and r.

3. By Hit and trial plus your intelligence and familiarity with the numbers will help you in finding the following relation.

Now follow the given directions :

$7^3 - 3^5 = (7 + 3)^{5-3}$

$343 - 243 = 10^2$

$100 = 100$

Hence $p + q + r = 7 + 5 + 3 = 15$.

Thus (c) is correct.

4. Given that $a^2 + b^2 + c^2 + d^2 = 1$

Now, the maximum value of $a.b.c.d$ will be only when

$a = b = c = d = k$

Then $a^2 + b^2 + c^2 + d^2 = 4k^2 = 1$

$\Rightarrow k = \pm \frac{1}{2}$

Now $a.b.c.d = k^4 = \left(\pm \frac{1}{2}\right)^4 = \frac{1}{16}$

Hence (c) is correct.

5. $n^2 - 2\,(n!) + n = 0$

$\Rightarrow n^2 + n = 2\,(n!)$

$\Rightarrow n\,(n + 1) = 2\,(n!)$

Now, going through options, we see that 1 and 3 are the two possible values hence (d).

6. Try and find the following suitable values for the given relation

$3^6 = 9^3 = (6!) + 9$

$729 = 729 = 720 + 9$

$729 = 729 = 729$

where $m = 3,\ n = 6$ and $p = 9$

$\therefore m.n.p = 162$

7. $n + (n - 1) + (n - 2) = n\,(n - 1)(n - 2)$

$\Rightarrow 3n - 3 = n\,(n - 1)(n - 2)$

$\Rightarrow 3\,(n - 1) = n\,(n - 1)(n - 2)$

$\Rightarrow n\,(n - 2) = 3$

$\Rightarrow n = 3, -1$

But the only possible values is $n = 3$.

Hence $(n!)^n = (3!)^3 = (6)^3 = 216$

8. $n^3 - n^2 - n = n$

$\Rightarrow n^3 - n^2 - 2n = 0$

$\Rightarrow n\,(n^2 - n - 2) = 0$

$\Rightarrow n = 0$ or $(n^2 - n - 2) = 0$

Now, if $(n^2 - n - 2) = 0$

$\Rightarrow n = -1, 2$

$\therefore n = -1, 0, 2$ Hence (c).

9. $\frac{12}{3} = 4$

First of all you should know that if $n_1 + n_2 + n_3 + \ldots = 0$

$\Rightarrow n_1 = n_2 = n_3 \ldots = 0$

Again, each term is the product of three quantities (or numbers). So only one number which is equal to zero is enough to make the product zero. Thus a particular single number, which is equal to zero can make three terms zero, because it present in three consecutive terms.

For example if $k_3 = 0$, then $k_1k_2k_3 = k_2k_3k_4 = k_3k_4k_5 = 0$

and if $k_6 = 0$, then $k_4k_5k_6 = k_5k_6k_7 = k_6k_7k_8 = 0$

and if $k_9 = 0$, then $k_7k_8k_9 = k_8k_9k_{10} = k_9k_{10}k_{11} = 0$

and if $k_{12} = 0$, then $k_{10}k_{11}k_{12} = k_{11}k_{12}k_{13} = k_{12}k_{13}k_{14} = 0$ etc.

Scanned by CamScanner

yoursmahboob.wordpress.com

10. $3^2 + 3^4 = (3^2 + 1)^2 - (3^2 + 1)$

$9 + 81 = 100 - 10$

$90 = 90$

and $1^0 + 1^2 = (1^2 + 1)^2 - (1^2 + 1)$

$1 + 1 = 4 - 2$

$2 = 2$

Alternatively : $n^{(n-1)} + n^{(n+1)} = (n^2 + 1)^2 - (n^2 + 1)$

$\Rightarrow \quad n^{(n-1)}(1 + n^2) = (n^2 + 1)[(n^2 + 1) - 1]$

$n^{(n-1)} = [n^2]$

$\Rightarrow \quad n - 1 = 2 \Rightarrow n = 3$

and if $n = 1$, then $1^0 = 1^2 = 1$

Thus $n = 1, 3$.

11. $1^3 + (12)^3 = (10)^3 + (9)^3$

$1 + 1728 = 1000 + 729$

$1729 = 1729$

12. $8^6 - 5^6 = (8^2)^3 - (5^2)^3 = (64)^3 - (25)^3$

$= (64 - 25)(64^2 + 25^2 + 64 \times 25) = 39 \times 6321$

$= 13 \times 3 \times 3 \times 7 \times 7 \times 43$

So it can be divided by $13 \times 7 = 91$, $7 \times 7 = 49$, $3 \times 43 = 129$

Hence, all of these are possible.

13. Since the product of 4 prime factors = 1365

$= 3 \times 5 \times 7 \times 13$

and the sum of the 3 prime factors = $25 = (5 + 7 + 13)$

Now, total number of factors of the required number $N = 24$

$= 2^3 \times 3 \Rightarrow (1 + 1)(1 + 1)(1 + 1)(2 + 1)$

Let N can be expressed as $N = 3^p \times 5^q \times 7^r \times 13^s$

Thus, in order to N will be greatest possible number in the above expressed form, the power of the greatest prime factors will be greater.

So $N = 3 \times 5 \times 7 \times 13^2$

$= 105 \times 169 = 17745$

14. Obviously (as per the given options) no any odd digit will appear as the last (or unit digit).

Hence (d) since even × even = even.

15. $\dfrac{R(135)}{R(100, 35)} = \dfrac{(135)!}{100 \times 101 \times 102 \times 103 \times \ldots \times 135}$

$= \dfrac{1 \times 2 \times 3 \times \ldots \times 99 \times 100 \times 101 \times 102 \times \ldots \times 135}{100 \times 101 \times 102 \times \ldots \times 135}$

$= 1 \times 2 \times 3 \times \ldots \times 99 = (99)!$

16. $R(17) . R(19, 62)$

$= (1 \times 2 \times 3 \times 4 \times 5 \times 6 \times \ldots \times 17) \times (19 \times 20 \times 21 \times 22 \times \ldots \times 81)$

$= \dfrac{(1 \times 2 \times 3 \times \ldots \times 81)}{18} = \dfrac{81!}{18}$

17. $R(2, 995) = 2 \times 3 \times 4 \times \ldots \times \ldots \times 995 \times 996 \times 997$

$R(996, 1) = 996 \times 997$

$\therefore$ L.C.M. of $R(2, 995)$ and $R(996, 1)$

$= 1 \times 2 \times 3 \times \ldots \times 997 = 997!$

18. $R(139, 2) = 139 \times 140 \times 141$

$R(141) = 1 \times 2 \times 3 \times \ldots \times 141$

$\therefore$ H.C.F. of $R(139, 2)$ and $R(141) = 139 \times 140 \times 141$

$= 2743860$

19. Since $abc \times 1001 = abcabc$

Thus the number $abcabc$ is always divisible by 1001 and its all factors. So (d) is the best option. Since $1001 = 7 \times 11 \times 13$.

20. Numbers divisible by 5 upto 1155 = 231

Numbers divisible by 7 upto 1155 = 165

Numbers which are divisible by both 5 and 7 (*i.e.*, 35) upto 1155 = 33

$\therefore$ Numbers which are exactly divisible by 5 or 7 = (231 + 165) − 33 = 363

Numbers which are divisible by 5 and 11 both (*i.e.*, 55) = 21

Numbers which are divisible by 7 and 11 both (*i.e.*, 77) = 15

Numbers which are divisible by 5, 7 and 11 simultaneously = 3

$\therefore$ Numbers which are only divisible by either 5 and 11 or 7 and 11

$= 21 + 15 - 3 = 33$

Hence, the total number of numbers which are divisible by 5 or 7 but not by 11 = 363 − 33 = 330.

21. $4x + 7y = 3$

$\Rightarrow \quad y = \dfrac{3 - 4x}{7}; \quad x, y \in I$

Now, in the given range of x and y, the least possible value of x is − 99 and then $y = 57$.

Again the largest possible value of x is 97 and the corresponding value of y is −55. So in this range there are total 29 solution sets are possible.

(Since the possible values of x are −99, −92, −85, ... 99 and the possible values of y are 57, 53, 49, ... −51, −55)

22. See the following pattern :

$N_1 \times N_2 \rightarrow$ Unit digit	$N_1 \times N_2 \rightarrow$ Unit digit
$1 \times 3 \rightarrow 3$	$10 \times 12 \rightarrow 0$
$2 \times 4 \rightarrow 8$	$11 \times 13 \rightarrow 3$
$3 \times 5 \rightarrow 5$	$12 \times 14 \rightarrow 8$
$4 \times 6 \rightarrow 4$	$13 \times 15 \rightarrow 5$
$5 \times 7 \rightarrow 5$	$14 \times 16 \rightarrow 4$
$6 \times 8 \rightarrow 8$	$15 \times 17 \rightarrow 5$
$7 \times 9 \rightarrow 3$	$16 \times 18 \rightarrow 8$
$8 \times 10 \rightarrow 0$	$17 \times 19 \rightarrow 3$
$9 \times 11 \rightarrow 9$	$18 \times 20 \rightarrow 0$ etc.

Except to first column in all the rest columns the least occuring unit digits are 9 and 4, and they occur same number of times. But in the first column 9 is not occuring. Thus finally '9' as the unit digit occurs least number of times *i.e.*, one times less as '4' occurs.

23. Except the first column the sum of all the unit digits

$= 99 (9 + 0 + 3 + 8 + 5 + 4 + 5 + 8 + 3 + 0)$

$= 99 (45) = 4455$

and the sum of all the unit digits of first column

$= (3 + 8 + 5 + 4 + 5 + 8 + 3 + 0) = 36$

Thus the sum of all the unit digits = 4455 + 36 = 4491

Hence (a).

24. Since a cube has to be cut from three sides (*i.e.*, along 3 dimensions). Hence the number of cuts will be equal to the sum of the 3 factors of 960, when 960 is expressed as the product of 3 factors.

Scanned by CamScanner

yoursmahboob.wordpress.com

Again since the number of cuts to be applied are minimum. Hence the sum of these 3 factors of 960 must be minimum. So, in order to be the sum of 3 factors of 960 be minimum we have to have the minimum possible difference between the 3 factors of 960.

Thus $960 = 8 \times 10 \times 12$

Hence the minimum possible number of cuts

$$= (8 + 10 + 12) = 30$$

Now, if we want to maximize the product of any 3 factors whose sum is constant i.e., 30, then it is possible only when all the 3 factors be equal. Thus a, b, c be the three factors such that :

$$a + b + c = 30$$

Then Maximum $(a \times b \times c) = 10 \times 10 \times 10 = 1000$

So, the maximum number of 1000 identical pieces can be formed by applying the same number of n cuts.

25. Since $45000 = 10 \times 4500$

So, the sum of all the factors of 45000 which are the multiples of 10 will be same as sum of all the factors of 4500 multiplied by 10.

Now, $4500 = 2^2 \times 3^2 \times 5^3$

Therefore the sum of all the factors of

$$4500 = \frac{(2^3 - 1) \times (3^3 - 1)(5^4 - 1)}{(2-1)(3-1)(5-1)}$$

$$= \frac{7 \times 26 \times 624}{1 \times 2 \times 4} = 14196$$

Hence the sum of all the products of 45000 which are the multiples of $10 = 10 \times 14196 = 141960$.

26. The unit digit of $(1!)^{1!} = 1$

The unit digit of $(2!)^{2!} = 4$

The unit digit of $(3!)^{3!} = 6$

The unit digit of $(4!)^{4!} = 6$

The unit digit of $(5!)^{5!} = 0$

Now since we know that 5!, 6!, 7!, 8!, ... all have their unit digits zero.

Thus the sum of all the unit digits = 7

(Since $1 + 4 + 6 + 6 + 0 = 17$)

27. To know the remainder, when any number is divided by 5, we just need to know the unit digit of the dividend. Further from the previous question, we know that the unit digit of the sum of the whole expression is 7.

So divide 7 by 5 and get 2 as the remainder.

28. The last two digits of $(1!) = 01$

The last two digits of $(2!)^2 = 04$

The last two digits of $(3!)^3 = 16$

The last two digits of $(4!)^4 = 76$

The last two digits of $(5!)^5 = 00$

Now, we can conclude that the last two digits of the higher numbers *e.g.*, $(6!)^6$, $(7!)^7$, $(8!)^8$ ... etc. are "00". So the last two digits of the whole expression = 9

(Since $01 + 04 + 16 + 76 + 00 = 97$)

29. Let the two parts be x and y then

$$x^2 - y^2 = 50\,(x - y)$$

$$\Rightarrow \quad (x + y) = 50$$

Hence the number is 50.

30. If $p = 3$, then $n = 5$ (Since $n > 2$)

If $p = 10$, then $n = 5$ also

If $p = 17$, then $n = 5$ also etc.

Hence $n = 5$.

31. Go through options :

	Anjali	Bhagwat	
Total Shots →	45	45	= 90
Total Hits →	36	30	= 66
Total miss shots →	9	15	

Since, $\frac{36}{9} = 4$ and $\frac{30}{15} = 2$, $\frac{4}{2} = 2$,

Hence, the presumed option is correct.

32. This is possible only when $n = 4, 10, 16, 22, 28, 34, \ldots$ hence the remainder will be 3 when $(n - 1)$ will be divided by 6.

33. Option (b) is obvious, as 2222 and 7777 both numbers are divisible by 101.

Now we know that if the sum of the remainders of two or more numbers are divisible by the given divisor then the required expression is also divisible by the divisor. The remainder when $(2222)^{7777}$ is divided by 13 is 12 and the remainder when $(7777)^{2222}$ is divided by 13 is 9.

Hence the given expression is not divisible by 13.

(Since $(12 + 9) \neq 13m$ for any positive integer m)

Again the remainder when $(2222)^{7777}$ is divided by 99 is 44 and the remainder when $(7777)^{2222}$ is divided by 99 is 77.

Hence the whole expression cannot be divided by 99.

(Since $44 + 77 = 121$ which is not divisible by 99.)

34. Let there be x students, then

$$\frac{x}{2} + \frac{x}{3} + \frac{x}{4} = 91$$

$$\Rightarrow \quad \frac{6x + 4x + 3x}{12} = 91$$

$$\Rightarrow \quad \frac{13x}{12} = 91$$

$$\Rightarrow \quad x = 84 \text{ students}$$

35. Best way is to go through convenient options.

$$1 + \frac{1}{4} \times 1 = \frac{5}{4} \qquad \left(\because \frac{1}{4} \to 25\%\right)$$

$$\frac{5}{4} + \frac{1}{2} \times \frac{5}{4} = \frac{15}{8} \qquad \left(\frac{1}{2} \to 50\%\right)$$

Hence option (c) is correct.

Alternatively : Let the first time rise in salary be x%, and the original salary be k then

$$k + \frac{kx}{100} = \frac{k\,(100 + x)}{100}$$

Again $\frac{k\,(100 + x)}{100} + \frac{k\,(100 + x)}{100} \times \frac{2x}{100} = \frac{k \times 15}{8}$

$$\frac{k\,(100 + x)}{100}\left[\frac{(100 + 2x)}{100}\right] = \frac{15k}{8}$$

$$\Rightarrow \quad \frac{(100 + x)}{100}\,\frac{(100 + 2x)}{100} = \frac{15}{8}$$

So simplify and solve the quadratic equation and get the values of x, then twice the value of x will be the required value.

Scanned by CamScanner

yoursmahboob.wordpress.com

36. $5^{72}\times 8^{27} = 5^{72}\times 2^{81} = (5^{72}\times 2^{72})\times 2^9$
$= 512\times 10^{72}$

Therefore there are total 75 (= 3 + 72) digits in the above expression.

37. Find the sum of n natural numbers which is just greater than 500. So if we consider that he had to be added 32 natural numbers then the ideal answer would have been 528. It means he had missed 28 during the process.

NOTE For clarification of the concept just write the natural numbers in sequence and then add up them one by one but not as the child did, then you will must get the lucid explanation of this problem.

38. Total distance to be covered
= total horizontal movement
+ total upward movement
$= (20\times 2 - 1) + (20)$
$= 39 + 20 = 59$ feet



39.

	Paltry	Sundry
Fired shots	5	7
Hit shots	2	3
Missed shots	3	4

When Sundry missed 32 shots, it means Paltry missed 24 shots.
When Paltry missed 24 shots, it means Paltry hit 16 shots.

40. It can be solved easily by options :
As consider option (a), then

$$90\times\frac{5}{6} = 75$$

$$75 - 5 + 2 = 72$$

Again $$90\times\frac{4}{5} = 72$$

Hence, the assumed option is correct.

41. See the figure and visualise the actual situation.



42. Go through options and check the option (b).

Thus at $y = -2$ and $y = 4$, $p = \frac{1}{0}$, which is undefined.

43. $\frac{1}{1\times 2}+\frac{1}{2\times 3}+\frac{1}{3\times 4}+\frac{1}{4\times 5}+\ldots+\frac{1}{100\times 101}$

$$=\left(\frac{1}{1}-\frac{1}{2}\right)+\left(\frac{1}{2}-\frac{1}{3}\right)+\left(\frac{1}{3}-\frac{1}{4}\right)+\left(\frac{1}{4}-\frac{1}{5}\right)+\ldots+\left(\frac{1}{100}-\frac{1}{101}\right)$$

$$=1-\frac{1}{101}=\frac{100}{101}$$

44.

$$\left.\begin{array}{l} R\to x+10 \\ L\to x+6 \\ B\to x+5 \\ H\to x+4 \\ A\to x \end{array}\right] \begin{array}{c} x \\ x \\ x \\ x \\ x \end{array} + \left(25\right) \left.\begin{array}{c} x+5 \\ x+5 \\ x+5 \\ x+5 \\ x+5 \end{array}\right] \begin{array}{c} \textcircled{5}^{+} \\ \textcircled{1}^{+} \\ \textcircled{1}^{-} \\ \textcircled{5}^{-} \end{array}$$

Thus total 6 coins have to be transferred.

45. As per the given expression the value of $f(x) = f\left(\frac{1}{x}\right)$

Try to put $\left(\frac{1}{x}\right)$ in place of x.

Thus the value of $f\left(\frac{1}{2}\right) = f(2) = 1081.58$

46. The unit digit of each pair is 4, and there are 50 such pairs which are mutually multiplied together. Thus finally we get 6 as unit digit. As

$$\underset{\text{digit}}{\text{Unit}}\quad \underbrace{4\times 9^2}_{4}\times\underbrace{4^3\times 9^4}_{4}\times\underbrace{4^5\times 9^6}_{4}\times\ldots\times\underbrace{4^{99}\times 9^{100}}_{4}$$

Again $4\times 4\times 4\times 4\ldots 4$ (upto 50 times)
i.e., the unit digit of 4^{50}, which is 6
[Since unit digit of 4^{2n} is 6 for $n = 1, 2, 3, \ldots$ etc.]

47. The unit digit of each pair is 5 and there are total 50 such pairs.

$$\underset{\text{digit}}{\text{Unit}}\quad \underbrace{4+9^2}_{5}+\underbrace{4^3+9^4}_{5}+\underbrace{4^5+9^6}_{5}+\ldots+\underbrace{4^{99}+9^{100}}_{5}$$

Thus $5 + 5 + 5 + \ldots$ 5 (50 times)
Hence the unit digit = 0
[Since $5\times 50 = 250 \to$ unit digit is zero.]

48. Consider some appropriate values :
As $p = 3.99,\quad q = 4.99,\quad r = 6.99$
$A = [p + q + r] = [3.99 + 4.99 + 6.99] = [15.97] = 15$
$B = [p] + [q] + [r] = [3.99] + [4.99] + [6.99]$
$= 3 + 4 + 6 = 13$
Hence $A - B = 2$

49. Options (a), (b) and (c) are irrelevent.
as $(25)^2 = (5)^2\times 25$
or $(27)^2 = (9)^2\times 9$
or $(6)^2 = (4)^2\times 9$
or $(6)^2 = (3)^2\times 4$ etc.
Hence (d) is correct.

NOTE If $a = b.c$ then $a^2 = b^2.c^2$
$a^2 = b^2.k$
Thus k must be a perfect square.

50. Since odd × even = even
even × even = even
even × even = even
It means when the odd numbers are added even number of times the resultant is always an even number for example :
$3 + 5 = 8 \to$ even
$3 + 5 + 9 = 17 \to$ odd
$3 + 5 + 9 + 13 = 30 \to$ even etc.
Again, even + even = even
and odd + even = odd,
so the sum of odd numbers cannot be odd in order to be the resultant sum be an even number.

51. Go through options

$$1 + 2 + 3 + \ldots + k = N^2 \qquad \text{(a perfect square)}$$

$$\frac{k(k+1)}{2} = N^2$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\frac{1\times 2}{2} = (1)^2 \rightarrow$ a perfect square number,

$\frac{8\times 9}{2} = 4\times 9 = (2\times 3)^2 \rightarrow$ a perfect square number,

and $\frac{49\times 50}{2} = 49\times 25 = (7\times 5)^2 \rightarrow$ a perfect square number.

52. Check through options consider some appropriate values.

$(17 + 15)$ and $(17 - 15)$

32 and 2, have a common factor 2.

$(7 + 4)$ and $(7 - 4)$

11 and 3, have no any common factor.

Hence options (a) and (b) are wrong and option (c) is correct.

53. If a and b be two such numbers, then

$$(ab)^{1/2} = 35 \Rightarrow ab = 1225$$

and $$\left(\frac{a+b}{2}\right) = 43\frac{3}{4} \Rightarrow (a+b) = \frac{175}{2}$$

$$\therefore \quad (a-b)^2 = (a+b)^2 - 4ab$$

$$(a-b)^2 = \frac{30625}{4} - 4900$$

$$(a-b) = \sqrt{\frac{30625 - 19600}{4}}$$

$$(a-b) = \frac{105}{2}$$

Now solving $(a+b) = \frac{175}{2}$

and $(a-b) = \frac{105}{2}$

we get $a = 70$ and $b = \frac{35}{2}$

Hence (c) is correct.

Alternatively : From option

$$\sqrt{70\times x} = 35$$

$$\Rightarrow \quad x = \frac{35}{2}$$

and $$\frac{70 + \frac{35}{2}}{2} = 43\frac{3}{4}$$

Hence (c) is the right answer.

54. Such a least possible number = [L.C.M. of 1, 2, 3, ..., n] $- 1$

Now if the L.C.M. of $(1, 2, 3, \ldots, n) = L$

then the next higher number $= (m.L) - 1$

and $m.L = n!$ for a suitable value of m; $m \in N$

Hence option (b) is most appropriate.

55. Let $n + (n+2) + (n+4) + (n+6) = k$

$$\therefore \quad 3n = 2(n+4)$$

$$\Rightarrow \quad n = 8$$

$$\therefore \quad k = 8 + 10 + 12 + 14$$

$$k = 44$$

56. Go through option and match the conditions.

Alternatively : Let there be k number of benches.

$$5k + 4 = 11\,(k-4)$$

$$\Rightarrow \quad 6k = 48$$

$$\Rightarrow \quad k = 8$$

Hence $5k + 4 = 44$

Thus there are 8 benches and 44 students.

57. $$\frac{m}{n} = 25\left(\frac{n}{m}\right)$$

$$\Rightarrow \quad \left(\frac{m}{n}\right)^2 = 25 \Rightarrow \frac{m}{n} = \frac{5}{1} = 5$$

58. 3^{3322} and 33^{332}

$$\Rightarrow \quad (3^4)^{830}\times 3^2 \text{ and } 33^{332}$$

Thus $(81)^{830}\times 3^2 > 33^{332}$

Again 3^{3322} and 333^{22}

$$\Rightarrow \quad (3^6)^{553}\times 3^4 \text{ and } (333)^{22}$$

Thus $(729)^{553}\times 3^4 > (333)^{22}$

Again 3^{3322} and 22^{333}

$$\Rightarrow \quad (3^3)^{1107}\times 3 \text{ and } 22^{333}$$

Thus $(27)^{1107}\times 3 > 22^{333}$

Hence (a).

59. $$a\times b = 25$$

$$(-1)\times(-25) = 25$$

Thus the minimum required value of $a + b = (-1) + (-25)$

$$= -26$$

Hence (d).

60. The least value of $p.q = 5\times(-10) = -50$

The least value of $p.q^6 = 4\times(-9)^6 = 4\times(729)^2$

The least value of $p^6.q = 5^6\times(-10) = (-156250)$

The least value of $(pq)^5 = [5\times(-10)]^5 = (-312500000)$

Hence (d) is the correct option.

61. Please remember that all the factorial numbers greater than or equal to n are divisible by n. Hence 7!, 8!, 9!, 10!, ... etc. are divisible by 7. So we have to check only $1! + 2! + 3! + 4! + 5! + 6!$

Hence $1! + 2! + 3! + 4! + 5! + 6!$

$$= 1 + 2 + 6 + 24 + 120 + 720 = 873$$

Thus 873 leaves a remainder of 5 when divided by 7.

Therefore $1! + 2! + 3! + 4! + 5! + \ldots + 77!$ leaves remainder 5.

62. It does not satisfy options a, b, c. Therefore option (d) is correct.

63. For one digit number $1\times 9 = 9$

for two digit numbers $2\times 90 = 180$

for three digit numbers upto $500 = 3\times 401 = 1203$

Thus the required value $= 9 + 180 + 1203 = 1392$

64. If a, b, c, d, e, f all the six forms of an A.P. can have only 9 values hence the common difference of the A.P. must be 1. (Since common difference cannot be greater than 1.)

$\therefore$ If $a = 1$, then

$1^2\times 3^4\times 5^6 \rightarrow$ unit digit is 5

If $a = 2$, then

$2^3\times 4^5\times 6^7 \rightarrow$ unit digit is 2

If $a = 3$, then

$3^4\times 5^6\times 7^8 \rightarrow$ unit digit is 5

If $a = 4$, then

$4^5\times 6^7\times 8^9 \rightarrow$ unit digit is 2

Scanned by CamScanner

yoursmahboob.wordpress.com

65. The greatest possible number
= H.C.F. of (1313 – 17) and (621 – 9)
= H.C.F. of 1296 and 612 = 36
Now the total number of factors of 36 = (2 + 1)(2 + 1) = 9
(Since $36 = 2^2 \times 3^2$)

66. Except to $x = 0$ and $x = 5$ all the values are acceptible, hence the range of x is $R - \{0, 5\}$ where R represents all the real numbers.

67. $p_1 + p_2 + p_3 + p_4 = 204$ ...(1)

$p_1 + p_4 = p_2 + p_3$ ...(2)

$\Rightarrow$ $p_2 - p_1 = p_4 - p_3$ ...(3)

and $p_3 - p_2 = 2(p_2 - p_1)$

$= 2(p_4 - p_3)$

$\Rightarrow$ $p_1 + x = p_2$

$p_2 + 2x = p_3$ ...(4)

$p_3 + x = p_4$

Also $\left(\frac{p_1 + p_2 + p_3 + p_4}{4}\right) = 51 = 17 \times 3$

Thus from the relation 2, we can deduce that

$p_1 + p_4 = p_2 + p_3 = 102$

Thus by hit and trial we will find the only possible values of p_1, p_2, p_3 and $p_4 = 31, 41, 61$ and 71 respectively.

NOTE The unit digits of (p_1 and p_4) or (p_2 and p_3) can be only (1 and 1), (3 and 9), but not necessarily in the order. So consider only those two digit prime number which satisfy all the given conditions.

68. Let the price of Sim card be x and instrument be y

then $x + y = 5000$

and $x = y - 4000$

$\Rightarrow$ $(y - 4000) + y = 5000$

$\Rightarrow$ $2y = 9000 \Rightarrow y = 4500$

Alternatively : Go through option

Instrument	Sim card
4500 + 500 = 5000	
4500 – 500 = 4000	

69. At $x = 0$ or $y = 0$, we get infinite number of ordered solutions set.

70. $l = \frac{292k + 7}{23}$

Therefore at $k = 1$, $l = 13$

Hence (d).

71. Since a, c are neither prime nor composite it means $a = c = 1$ and $b = 2, 3, 5, 7$ and $d = 2, 3, 5, 7$ but $b \neq d$.

Thus from $ab + 4 = cd$

$\Rightarrow$ $ab = 13$ and $cd = 17$, the only possible combination.

$\therefore$ $ba = 40 = dc$

$\Rightarrow$ $31 + 40 = 71$

Therefore $\frac{ab + ba}{cd + dc} = \frac{13 + 31}{17 + 71} = \frac{44}{88} = \frac{1}{2}$

72. The best way to go through options.
Let there are initially 3 boxes then,

1st customer gets $= \frac{3}{2} + \frac{1}{2} = 2$

Remaining boxes $= 3 - 2 = 1$

2nd customer gets $= \frac{1}{2} + \frac{1}{2} = 1$

Remaining boxes = 0

Hence presumed option (b) is correct.

73. $123454321 = (11111)^2$
Hence (d).

74. $1^2 - 2^2 + 3^2 - 4^2 + 5^2 - 6^2 + \ldots - 198^2 + 199^2$

$= (1^2 - 2^2) + (3^2 - 4^2) + (5^2 - 6^2) + \ldots + (197^2 - 198^2) + 199^2$

$= (-3) + (-7) + (-11) + (-15) + \ldots + (-395) + (199)^2$

$= \left[-\left(\frac{3 + 395}{2}\right) \times 99\right] + 39601$

$= (-199 \times 99) + 39601$

$= (-19701) + 39601 = 19900$

75. The G.P. is as following :

$a, ar, ar^2, ar^3, \ldots$ etc.

then LCM of this G.P. $= ar^{n-1}$

and HCF of this G.P. $= a$

$\therefore$ $\frac{\text{LCM}}{\text{HCF}} = \frac{ar^{n-1}}{a} = r^{n-1}$

76. From option (a)
Total number of brothers and sisters = 4
Also there are two brothers and 2 sisters.

77. $(4 @ 5) = (4 \# 5) = \frac{4}{5}$ $\because 4 < 5$

and $(6 @ 5) = (5 \# 6) = \frac{5}{6}$ $\because 6 > 5$

and $\left(\frac{4}{5}\right) @ \frac{5}{6} = \frac{\frac{4}{5}}{\frac{5}{6}}$ $\because \frac{4}{5} < \frac{5}{6}$

$\therefore$ $(4 @ 5) @ (6 @ 5) = \frac{\frac{4}{5}}{\frac{5}{6}} = \frac{24}{25}$

78. The only possible values of p, q, r are 1, 2, 4
So $s = 5$, $t = 6$, $u = 7$.
Hence the number is 124567 therefore
$p + q + r + s + t + u = 25$

79. $4^{1111} \times 5^{2222} = 2^{2222} \times 5^{2222} = 1 \times 10^{2222}$
Hence there will be 2223 number of digits.

80. Since N is always even. Thus p is always odd
[As even + odd = odd]

81. Let $\frac{p}{q} = -7$ and $\frac{r}{s} = 3$

then $\left|\frac{p}{q}\right| = 7$ and $\left|\frac{r}{s}\right| = 3$

Thus $\left|\frac{p}{q}\right| > \left|\frac{r}{s}\right|$.

Again if $\frac{p}{q} = 4$ and $\frac{r}{s} = 7$ then $\left|\frac{p}{q}\right| > \left|\frac{r}{s}\right|$, hence (d).

Scanned by CamScanner

yoursmahboob.wordpress.com

82. Since all the numbers u, v, w, x are negative, but when $u^v + v^w + w^x = 0$, then u^v it means there must be some terms whose value will be positive and thus it adding up with negative value makes the expression zero.

e.g., $(k) + (-k) = 0$

Hence we can say that there must be some even integers which converts a negative number into a positive number. Further we know that an even number when multiplied with any other (even or odd) number it finally makes an even number.

Explanation : $u^v + v^w + w^x = 0$

$\Rightarrow \quad (-u)^{-v} + (-v)^{-w} + (-w)^{-x} = 0 \quad (\because u, v, w, x \in I^-)$

Again, if $k + l + m = 0$

$\Rightarrow \quad k + l = m \quad$ or $\quad k + m = l \quad$ or $\quad l + m = k$

i.e., half of the numerical value will be positive and half of the numerical value will be negative since there are every non zero integer.

Now, if $(-k)^{\text{even}} \rightarrow$ positive value

So, if there exists some even integer n, then

$k \times l \times m \times n \rightarrow$ even (though k, l, m can be odd).

83. The unit digit of 2^{3^4} is 2.

The unit digit of 3^{4^5} is 1.

The unit digit of 4^{5^6} is 4.

The unit digit of 5^{6^7} is 5.

The unit digit of 6^{7^8} is 6.

The unit digit of 7^{8^9} is 1.

Therefore the unit digit of :

$$2^{3^4} \times 3^{4^5} \times 4^{5^6} \times 5^{6^7} \times 6^{7^8} \times 7^{8^9} = 0$$

(Since $2 \times 1 \times 4 \times 5 \times 6 \times 1 = 240$)

Alternatively : 5 always gives unit digit 5 irrespective of its (positive) power and similarly 6 also gives 6 as a unit digit irrespective of its power.

So, $5 \times 6 = 30$. Hence you will get the unit digit zero without solving the complete expression.

84. In order to be a, b, c be least, then

$$(a-7) = (b-10) = (c-12)$$

Again $\quad (a-7)(b-10)(c-12) = 1000$

$\Rightarrow \quad 10 \times 10 \times 10 = 1000$

$\Rightarrow \quad a = 17, \quad b = 20 \quad$ and $\quad c = 22$

Therefore $(a + b + c) = 59$.

85. $\dfrac{23^{32} - 9}{16} \rightarrow \left(\dfrac{23^{32}}{16} - \dfrac{9}{16}\right) \rightarrow \left(\dfrac{7^{32}}{16} - \dfrac{9}{16}\right)$

$$\rightarrow \left[\frac{(7^2)^{16}}{16} - \frac{9}{16}\right] \rightarrow \left[\frac{1^{16}}{16} - \frac{9}{16}\right]$$

$$\rightarrow \frac{1-9}{16} \rightarrow \frac{-8}{16} \rightarrow \frac{16-8}{16} \rightarrow \frac{8}{16} \rightarrow 8$$

86. Very similar to the problem number 84.

Hence $\quad (x-5) = (y+6) = (z-8) = 11$

$\Rightarrow \quad x = 16, \; y = 5, \; z = 19$

Thus $\quad (x + y + z) = 40.$

87. $(x-6)(y+7)(z-4)$ will be maximum only when $(x-6) = (y+7) = (z-4) = k$ (say) for a given value of $(x + y + z) = 21$

$\Rightarrow \quad x = k + 6$

$\quad\quad y = k - 7$

$\quad\quad z = k + 4$

$\therefore \quad x + y + z = 21$

$\Rightarrow \quad (k+6) + (k-7) + (k+4) = 21$

$\Rightarrow \quad 3k + 3 = 21$

$\Rightarrow \quad k = 6$

Therefore, $\quad (x-6).(y+7)(z-4) = k^3 = (6)^3 = 216$

88. $\dfrac{3^{37} + 4^{37}}{7} \rightarrow \left(\dfrac{3^{37}}{7} + \dfrac{4^{37}}{7}\right) \rightarrow \left[\dfrac{(3^2)^{18} \times 3}{7} + \dfrac{(4^2)^{18} \times 4}{7}\right]$

$$\rightarrow \left(\frac{2^{18} \times 3}{7} + \frac{2^{18} \times 4}{7}\right) \rightarrow \left(\frac{(2^3)^6 \times 3}{7} + \frac{(2^3)^6 \times 4}{7}\right)$$

$$\rightarrow \left(\frac{3}{7} + \frac{4}{7}\right) = \left(\frac{7}{7}\right) \rightarrow \text{Remainder zero.}$$

Alternatively : $a^n + b^n$ is divisible by $(a + b)$ if n is odd. Hence $(3^{37} + 4^{37})$ is divisible by 7 $(= 3 + 4)$. Hence leaves no remainder.

89. $7^{74} - 4^{74}$ is divisible by 3

since $a^n - b^n$ is divisible by $(a - b)$ and

Again $7^{74} - 4^{74} = (7^2)^{37} - (4^2)^{37} = 49^{37} - 16^{37}$

Now, since $a^n - b^n$ is divisible by $(a - b)$ if n is odd, then $7^{74} - 4^{74}$ (*i.e.*, $49^{37} - 16^{37}$) is divisible by 11.

Hence (d).

90. Try to find out 11^2 in less than 22!.

You can't find. So (a) is the correct choice.

91. The number of zeros at the end of $2^3 \times 3^4 \times 4^5 \times 5^6 = 6$

The number of zeros at the end of $3^5 \times 5^7 \times 7^9 \times 8^{10} = 7$

The number of zeros at the end of $4^5 \times 5^6 \times 6^7 \times 7^8 = 6$

The number of zeros at the end of $10^2 \times 15^3 \times 20^4 = 7$

So the number of zeros at the end of the whole expression = 6.

93. Min. (1, 2, 3) + Max. (1, 2, 3)

$$= \text{Min. } (2, 6, 3) + \text{Max. } (1, 8, 3) = 2 + 8 = 10$$

94. Labh [Hani (1, 2, 3), Hani (2, 3, 4), Hani (3, 4, 5)]

$$= \text{Labh } [4, 5, 6] = \frac{4 + 5 + 6}{3} = 5$$

95. Min. [Hani (1, 2, 3), Hani (2, 3, 4), Hani (3, 4, 5)]

+ Max. [Labh (1, 2, 3), Labh (2, 3, 4), Labh (3, 4, 5)]

= Min. [4, 5, 6] + Max. [2, 3, 4]

= Min. (20, 30, 24) + Max. (8, 81, 16)

= 20 + 81 = 101

96. $\therefore \quad (55)_{10} = (25)_{25}$

25	55
25	2 → 5
	0 → 2

97. $Q = 4, 8$

$P = 3, 6, 9, 1, 4, 7;$ since $P, Q > 0$

So there are total 6 values of (P, Q).

Scanned by CamScanner

yoursmahboob.wordpress.com

98. Total number of 6's = Number of actual 6's + Number of wrong 6's

Number of Actual 6's = 20 (as unit digits) + 20 (at tens digit) + 100 (as hundreds digit) = 140 6's

Number of wrong 6's (which are at the place of 8's) = 20 (at unit's place) + 20 (at tens place) = 40

Hence total number of 6's = 180

99. If $p^2 - pq = 0 \Rightarrow p(p-q) = 0 \Rightarrow p = 0$ or $p = q$, but since $p \neq q$, then $p = 0$ is only possible solution.

100. $15990 = 2 \times 3 \times 5 \times 13 \times 41$

$= 2 \times 3 \times 13 \times 5 \times 41 = 78 \times 205$

Hence the only possible option is (d).

101. $n = 1, 2, 3, \ldots, 7$.

102. If you go through option, then you will find option (c) is correct. Since divisor is always greater than remainder.

Alternatively : $\frac{A}{D} \rightarrow$ Remainder 13

$\frac{B}{D} \rightarrow$ Remainder 31

$\frac{A+B}{D} \rightarrow$ Remainder should be 44

But it is given that the remainder is 4.
Hence, the divisor must be 40 (= 44 − 4).

103. Since $(N)^{2p} \rightarrow$ unit digit 6

and $(N)^{(2p+1)} \rightarrow$ unit digit 4

It means every even power of N has unit digit 6 and every odd power has unit digit 4. It means the unit digit of N is 4. Hence the largest two digit number is 94, whose unit digit is 4.

104. Just replace x by $(x+1)$ and simplify or consider some numerical value of x then check through options.

105. $$60 = \pm \begin{bmatrix} 1 \times 60 \\ 2 \times 30 \\ 3 \times 20 \\ 4 \times 15 \\ 5 \times 12 \\ 6 \times 10 \end{bmatrix}$$

$$\Rightarrow \quad a + b = \begin{Bmatrix} = (-4) + (-15) & = -19 \\ = 5 + 12 & = 17 \\ = 2 + 30 & = 32 \end{Bmatrix}$$

106. To find the required unit digit just add up the single unit digits of the two previous consecutive numbers successively and you will find that every 15th term of this sequence has unit digit zero. Hence the unit digit of the 75th term of this sequence is 0.

107. Every nth term has its unit digit 5 if n is divisible by 5 but it has unit digit zero (0) if n is divisible by 15. Since we have to find out the unit digit of 55th term. So here 55 is divisible by 5 but not by 15, hence the unit digit will be 5.

108. The unit digit of the sum of the 88th term plus 89th term will be equal to the unit digit of 90th term. Hence it will be zero. (See the question number 106).

109. Always 5. Since when we multiply a number whose unit digit is 5 with any odd number the unit digit of the resultant number is 5.

111. The least possible product of any 3 numbers can be found by multiplying numerically greatest possible number, but at least one number must be negative.

Thus the required product $= (-5) \times (24) \times (25) = (-3000)$

Hence (c).

112. Since $q - p = r - q = 2$

Therefore p, q, r are in A.P.

But the least possible value of p, q, r can be 1. So if $p = 1$, then $q = 3$ and $r = 5$.

Hence $(p+q)(q+r)(r+p) = 4 \times 8 \times 6 = 192$

114. Check for any value of R.

116. Option (a) and (b) are wrong since the maximum cost of total pens is nearly Rs. 745. Now, to maximize the number of pens of Rs. 5, we have to minimize the number of pens of Rs. 3 and the total cost cannot exceed Rs. 745.6

So by hit and trial get the required result. As :

Number of pens of Rs. 3 each	Number of pens of Rs. 5 each	Total Cost
$1 \times 3 = 3$	$149 \times 5 = 745$	748
$2 \times 3 = 6$	$148 \times 5 = 740$	746
$3 \times 3 = 9$	$147 \times 5 = 735$	744

Hence the maximum number of pens of Rs. 5 is 147.

117. The last digit of this number is 9.

Since $(1 \times 9) + (2 \times 50) = 109$

i.e., there are 9 digits of one digit number and 100 digits are of 50 numbers of 2 digit.

Again the 50th two digit number is 59, hence the last digit of the given number is 9.

Now, if we add 1 to this number it will become divisible by both 2 and 5.

118. If the sum of all the 109 digits of the given number is divisible by 3, then the given number itself is divisible by 3.

Now, the sum of all the 109 digits

= [sum of all the unit digits of all the 59 numbers + sum of all the tens digit of all the 2 digit numbers upto 59]

$= 6 \times (45) + 5 \times (15)$

$= 270 + 75 = 345$

Now since the sum of all the digits is 345. Hence it is divisible by 3.

Again a number is divisible by 11 if the difference of sum of all the digits at even places and sum of all the digits at odd places is divisible by 11 or it is zero.

Now, 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 ... 575859.

The sum of all the digits at odd places

$= 5 \times (45) + (9 + 7 + 5 + 3 + 1) = 250$

[Counted from right side]

The sum of all the digits at even places

$= 10 \times (1 + 2 + 3 + 4 + 5) + (8 + 6 + 4 + 2)$

$= 150 + 20 = 170$

Scanned by CamScanner

yoursmahboob.wordpress.com

Thus the required difference = 250 – 170 = 80

But if we subtract the least possible number *i.e.*, 3 from the given number (1 2 3 4 5 ... 5859) the new number will become (1 2 3 4 5 ... 5856)

Now the required difference = 247 – 170 = 77

Since 77 is divisible by 11 hence the given number is also divisible by 11.

Again, the number (12345 ... 5856) is also divisible by 3. Since if a number is divisible by 3 and we subtract a multiple of 3 from this number then the resultant number is also divisible by 3.

119. Since $F < B < G < A$

Now, if $F = 1$, then $1 < 2 < 3 < 4$, adultas cannot be 4 in one family.

if $F = 2$, then $2 < 3 < 4 < 5$, adultas cannot be 5 in 2 families.

if $F = 3$, then $3 < 4 < 5 < 6$, not possible since one family has only one adult.

Again, if $F = 4$ then $4 < 5 < 6 < 7$, possible since

$$(3 \times 2) + (1 \times 1) = 7$$

120. $$A = 3^{3^{3^3}} = 3^{3^{27}}$$

and $$C = 3^{3^{33}} = 3^{3^{33}}$$

Hence $C > A$.

Hence either (b) or (d) option is correct.

Now $$A = 3^{3^{3^3}} = 3^{3^{27}}$$

and $$D = 3^{333}$$

Hence $A > D$ (Since $3^{27} > 333$)

Thus the correct relation is $C > A > B > D$.

Hence, option (b) is correct.

121. $\frac{A}{D} \rightarrow$ Remainder 23

and $\frac{B}{D} \rightarrow$ Remainder 3

$$\frac{A+B}{D} \rightarrow \text{Remainder } 26$$

Therefore it is clear that the divisor D cannot less than or equal to 26. Thus the possible values of D are greater than 26.

122. $a^2 - b^2 = (a+b)(a-b) = m \times n$

$$\Rightarrow \quad a = \frac{m+n}{2} \text{ and } b = \frac{m-n}{2}$$

Now, $729 = 1 \times 729 \Rightarrow a = 365, b = 364$

$3 \times 243 \Rightarrow a = 123, b = 120$

$9 \times 81 \Rightarrow a = 45, b = 36$

$27 \times 27 \Rightarrow a = 27, b = 0$

Thus we can express it in 4 ways, Hence (a).

Alternatively : The required answer is always equal to the number of ways in which a given product can be expressed as the product of two factors.

123. $2310 = 2 \times 3 \times 5 \times 7 \times 11$, Now since 2310 has to be expressed as a product of 3 factors, as $2310 = a \times b \times c$. Now, we exclude one prime factor say a then we find the rest part as a product of 2 factors.

Thus when $a = 1$, then $b \times c$ can be expressed as

$$\frac{(1+1)(1+1)(1+1)(1+1)(1+1)}{2} = 16 \text{ ways}$$

Now, if $a = 2$, then

$$b \times c = \frac{(1+1)(1+1)(1+1)(1+1)}{2} = 8 \text{ ways}$$

when $a = 3$, then

$$b \times c = \frac{(1+1)(1+1)(1+1)(1+1)}{2} = 8 \text{ ways}$$

similarly when $a = 5, 7, 11$ the value of $b \times c = 8$ ways

But when $a = 2$, then the $(b \times c) = 8 - 1 = 7$ since one way of expression has been included in the case of $a = 1$.

Similarly when $a = 3, 5, 7$ and 11 then the number of ways will be 6 (= 8 – 2), 5 (= 8 – 3), 4 (= 8 – 4), 3 (= 8 – 5) respectively.

Thus the total number of ways in which 729 can be expressed as the product of 3 factors = 16 + 7 + 6 + 5 + 4 + 3 = 41 ways.

Final Round

1. $120 = 4 \times 5 \times 6$ (Since minimum number of cuts are possible only when all the three factors are very close)

Again $125 = 5 \times 5 \times 5$

But since 4 + 5 + 6 = 5 + 5 + 5 = 15, hence the same number of cuts are required as previously. Hence '*n*' number of cuts are required to get 125 identical pieces.

2. Note that the first element of *n*th term of the given sequence is $\left(\frac{n^2 - n + 2}{2}\right)$ and the last element of the *n*th element is $\frac{n(n+1)}{2}$.

So the last element of the 21st term of the sequence

$$= \frac{21 \times 22}{2} = 231$$

Now to find the sum of first 21 term we have to find the sum of first 231 natural numbers.

Hence $\frac{231 \times 232}{2} = 231 \times 116 = 26796$

Hence the last digit is 6 and tens digit is 9.

3. The elements of the set

$S_{19} = \{172, 173, 174, 175, ..., 190\}$

Now $175 = 5^2 \times 7$

$180 = 5 \times 36$

$185 = 5 \times 37$

$190 = 5 \times 38$

Therefore the number of 5's contained in the product of the element of the set is 5. Note that the number of 2's are more than the number of 5's. So the total number of zeros at the end of the product of the element is 5.

4. Note the number of zeros in the product of S_{19} and S_{20} will depend upon the number of 5's contained in S_{19} and S_{20}.

Now, the $S_{20} = \{191, 192, 193, 194, 195, ..., 210\}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Thus $195 = 5 \times 39$
$200 = 5 \times 5 \times 8$
$205 = 5 \times 41$
$210 = 5 \times 42$

Therefore the total number of 5's contained in $S_{20} = 5$ hence the number of zeros at the end of the product is 5. Thus the number of zeros at the end of the product of S_{19} and $S_{20} = 10$. Thus the largest power of 10 is 10, which can exactly divide the product of S_{19} and S_{20}.

5. $S = \{2, 4, 6, 8, 10, 12, 14, 16, 18, \ldots, 96, 98, 100\}$
If the product of any 3 elements contains 4 or more than 4 two's then it will be divisible by 16 (since $16 = 2^4$) otherwise it will not be divisible. Hence remove those elements which are multiples of either 4 or 8 or 16 or 32 or 64 in the given set.
Since $(2k \times 2l \times 2m)$ is not divisible by 16 if k, l, m are odd numbers.
Thus there are only 25 elements in p.
As $P = \{2, 6, 10, 14, 18, 22, 26, 30, \ldots, 94, 98\}$

6. Since $51 = 17 \times 3$
$85 = 17 \times 5$
$102 = 17 \times 6$
Thus the minimum possible number of cubes $= 3 \times 5 \times 6 = 90$
The total surface area of non-red faces
= (Total surface area of all the cubes
− total surface area of cuboid)
$= (90 \times 6 \times 17 \times 17) - 2 \times (51 \times 85 + 85 \times 102 + 102 \times 51)$
$= 90 \times 6 \times 289 - 2 \times 289\,(15 + 30 + 18)$
$= 90 \times 6 \times 289 - 2 \times 289\,(63)$
$= 289 \times 18\,(5 \times 6 - 7)$
$= 289 \times 18 \times 23 = 119646\ \text{cm}^2$

7. Go through option
$$\frac{6p + 7q}{42} \to \frac{6p}{42} + \frac{7q}{42}$$
Since p is divisible by 7 and q is divisible by 6 thus
$$\frac{6p}{42} + \frac{7q}{42} \to \frac{6 \times 7m + 7 \times 6n}{42}$$
$$= \frac{42(m + n)}{42} = (m + n)$$

8. $p^q - q^r = (p + q)^{r-q}$; $11 > p > r > q \in$ Prime numbers.
$7^3 - 3^5 = (7 + 3)^{5-3}$
$100 = 100$
$\therefore \quad (p + q) = 7 + 3 = 10$
$= 5(5 - 3) = r(r - q)$

9. Since there are 25 prime numbers upto 100 also 1 is not divisible by any number.
Hence there are only 26 seats available on the front row for the mathematicians.

10.

Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
1	2	3	4	5	6	7
8	9	10	11	12	13	14

$\frac{88}{7}$ = Remainder is 4.
So the 4th day in the week is Thursday.

11. Since Thursday will fall on those dates which can be expressed as $7k + 4$; $k = 0, 1, 2, 3, \ldots$
Now since 64 can't be expressed as $7k + 4$.
Hence (d) is the required answer.

12. According to the septarion calendar there are exactly 364 days and each day occurs equal number of times in whole year.

13. Find the pattern
hence, $(89)^{91} \to (89^{10})^9 \times 89^1$
$(89)^{91} \to 01 \times 89$
$(89)^{91} \to 89$
Thus the last two digits of $(1989)^{91}$ are 8 and 9.

Since		
	$(89)^1 \to 89$	$(89)^{11} \to 89$
	$(89)^2 \to 21$	$(89)^{12} \to 21$
	$(89)^3 \to 69$	$(89)^{13} \to 69$
	... ...	... ...
	... ...	... ...
	$89^{10} \to 01$	$(89)^{20} \to 01$

NOTE To find the last 'n' digits we find the pattern for last 'n' digits.

14. Step 1. | 2 | 7 | 3 | 5 | → No any digit is placed at the right place.

Step 2. | 5 | 2 | 7 | 3 | → No any digit is correctly placed.

Step 3. | 3 | | | | → This digit is not acceptable at this place.

It means the first digit will be 7, since, 2, 5 and 3 are inadmissible.

7			

Again since 5 and 3 are not acceptable at unit digit place and 7 is correctly filled up as the first digit, hence only one digit i.e., '2' is left for the unit digit place.

7			2

Now, since 3 and 7 are not acceptable and 2 has been used, hence only one digit *i.e.*, '5' is left for the tens place.

7		5	2

Thus, we can complete the password as

7	3	5	2

Alternatively : Go through options.

15. $(888!)^{999} = (1 \times 2 \times 3 \times 4 \times \ldots \times 76 \times 77 \times 78 \times \ldots \times 888)^{999}$
Since it has a factor as 77. Thus it has no remainder.

16. The middle most pages of the magazines are shown in the figure numbered as 42 and 43.
Did you notice that the front pages on the left side of the magazine (as shown in figure) are divisible by 2 and the odd numbers are on the back side of these numbers ? Note that I am talking about the left side of the magazine when it is open as shown in figure.



Scanned by CamScanner

yoursmahboob.wordpress.com

So the missing page numbers with 29 will be 30 and the corresponding number in the right side will be 51 and 52.

Alternatively : Since the magazine has 84 pages it means there are 21 sheets of paper, which are folded in middle. Now see the pattern of page numbers :

Left side	Right side
1, 2	83, 84
3, 4	81, 82
5, 6	79, 80
7, 8	77, 78
9, 10	75, 76
⋮ ⋮	⋮ ⋮
29, 30	55,56
⋮ ⋮	⋮ ⋮
41, 42	43, 44



(i)



(ii)

Thus we can say that the sum of the page numbers on a sheet in one side is always 85. Hence the page numbers printed on the sheet of paper is 29, 30 and 55, 56.

17. Let there be six locks *A, B, C, D, E* and *F*.
Then we need maximum 5 attempts to know the right key for '*A*'. Again we need maximum 4 attempts to know the right key for '*B*'. Similarly we need 3, 2 and 1 attempts to know the proper key for the locks *C, D* and *E*. Now 1 key is automatically left for the lock '*F*'. Thus the total number attempts required

$$= 5 + 4 + 3 + 2 + 1 = 15$$

18. $\dfrac{51n^2 + 17n + 6}{n} = 51n + 17 + \dfrac{6}{n}$

Here the first two terms are divisible for any value of n, but the last term is divisible by only 1, 2, 3 and 6 *i.e.*, only 4 values, which are actually the factors of 6.

19. $V >> S >> P$

$V >> L >> P$

$V >> L > S$

Therefore, $V >> L > S >> P$

Thus the worst player can be Plexur.

20. Obviously $(n-1)$. Since if the Winner first picks up $(n-1)$ sticks then there will be only one stick left, which must be picked up by the Loser and hence the last player will lose it.

21. The last ten digits of $1^1 \times 2^2 \times 3^3 \times 4^4 \times 5^5$ is (00,86,40,00,00)
The last ten digits of $1^6 \times 2^7 \times 3^8 \times 4^9 \times 5^{10}$ is (00,00,00,00,00)
The last ten digits of $1^{11} \times 2^{12} \times 3^{13} \times 4^{14} \times 5^{15}$ is (00,00,00,00,00)
The last ten digits of $1^{96} \times 2^{97} \times 3^{98} \times 4^{99} \times 5^{100}$ is (00,00,00,00,00)
Thus the sum of the last tens digits of the expression is (00,86,40,00,00)
Hence the sum of the last ten digits of the sum of the expression = 18. ($\because$ 8 + 6 + 4 = 18)

22. Initially Ravi Shankar has only Rs. 2 with him. Since we know that the Ravi Shankar can pay the sum in rupees only it means he cannot pay in paise. Therefore he must have purchased initially the flowers of exactly Re. 1.
Now from the options : Consider option (c).
The number of flowers he has purchased for Re. 1 = 4.
Later on he could purchased the number of flowers for total Rs. 2 = 4 + 6 = 10.
Thus the initial cost of one dozen flowers = Rs. 3
and the changed cost of one dozen flowers = Rs. 2.40
Thus he could gain 60 paise per dozen. Hence the presumed option (c) is correct.

NOTE The initial number of flowers must be less than 6, for Re. 1 only then he can get the benefit by purchasing 6 flowers for the next Re. 1.

23. See the figure there are 31 pencils of equal length.



15 vertically and 16 horizontally.
Thus there are 12 small squares of the dimension of equivalent to 1 pencil and 6 squares of dimension of equivalent to 2 pencil and 2 squares of dimensions of equivalent to 3 pencils. Therefore total number of squares = 12 + 6 + 2 = 20.

24. Let she did x number of pages on the first day. It means second, third, fourth, ..., nineth and tenth day she did $(x+3)(x+6)(x+9)\ldots(x+24)$ and $(x+27)$ passages.
Now since $(x+24) = 4(x+3)$
$\Rightarrow$ $3x = 12$
$\Rightarrow$ $x = 4$
Therefore the number of passages she did on the last day
$= x + 27 = 31$.

25. Total number of passages
$= x + (x+3) + (x+5) + \ldots + (x+27)$
$= (4 \times 10) + (3 + 6 + 9 + \ldots + 27)$
$= 40 + 3(1 + 2 + 3 + \ldots + 9)$
$= 40 + 135 = 175$

26. Let there be x people in the village then there must be $4x$ sheep.
Now the number of persons live = $(x - 8)$
and the number of sheep to be carried with the survived people = $4x - (47 + 21) = 4x - 68$
Since we know that each person has carried only one sheep with him. Therefore
$(x - 8) = 4x - 68$
$\Rightarrow$ $3x = 60$
$\Rightarrow$ $x = 20$
$\Rightarrow$ $4x = 80$
Hence there were total 80 sheep.

Scanned by CamScanner

yoursmahboob.wordpress.com

27. (123) (234) (345) (456) (567) (678) (789)
(135) (246) (357) (468) (579)
(147) (258) (369)
(159)
Thus there are total 16 such numbers.

28. $(2^2 + 4^2 + 6^2 + 8^2 + \ldots + 100^2) - (1^2 + 3^2 + 5^2 + \ldots + 99^2)$
$= (2^2 + 4^2 + 6^2 + \ldots + 100^2)$
$-[(1^2 + 2^2 + 3^2 + 4^2 + \ldots + 99^2 + 100^2)$
$- (2^2 + 4^2 + 6^2 + \ldots + 100^2)]$
$= 2(2^2 + 4^2 + \ldots + 100^2) - (1^2 + 2^2 + 3^2 + \ldots + 100^2)$
$= 8(1^2 + 2^2 + 3^2 + \ldots + 50^2)$
$- (1^2 + 2^2 + 3^2 + 4^2 + \ldots + 100^2)$
$= 8\left(\frac{50 \times 51 \times 101}{6}\right) - \left(\frac{100 \times 101 \times 201}{6}\right)$
$= \frac{101 \times 100}{6}(51 \times 4 - 201) = \frac{10100}{6} \times (3) = 5050$, hence (b).

Alternatively :
$(2^2 + 4^2 + 6^2 + 8^2 + \ldots + 100^2) - (1^2 + 3^2 + 5^2 + \ldots + 99^2)$
$= (4 + 16 + 36 + 64 + \ldots + 10000)$
$- (1 + 9 + 25 + \ldots + 9801)$
$= [(4 - 1) + (16 - 9) + (36 - 25) + \ldots + (10000 - 9801)]$
$= 3 + 7 + 11 + 15 + \ldots + 199 = \left(\frac{3 + 199}{2}\right) \times 50$
$= \frac{202 \times 50}{2} = 101 \times 50 = 5050$

29. Consider some proper values.

30. $S_n = 3^0 + 3^1 + 3^2 + \ldots + 3^{200}$
$S_n = \frac{3^0(3^{201} - 1)}{(3 - 1)} = \frac{(3^{201} - 1)}{2}$
Now, $\frac{(3^{201} - 1)}{2} = \frac{(3^3)^{67} - 1^3}{2} = \frac{[(27)^{67} - 1]}{2}$
Now since $a^n - b^n$ is divisible by $(a - b)$ therefore $[(27)^{67} - 1]$ is divisible by $(27 - 1) = 26$.
Hence it is also divisible by 13.
Thus the remainder is zero since the given expression is divisible by 13.

31. Let the sum of the expression be S_n then
$S_n = 4^0 + 4^1 + 4^2 + 4^3 + \ldots + 4^{40}$
$\Rightarrow \quad S_n = (1 + 4 + 16 + 64) + 4^4(1 + 4 + 16 + 64) + \ldots$
$+ 4^{36}(1 + 4 + 16 + 64) + 4^{40}$
Since $(1 + 4 + 16 + 64) = 85$ is divisible by 17, hence except 4^{40} remaining expression is divisible by 17.
$\therefore \quad \frac{4^{40}}{17} \to \frac{(4^4)^{10}}{17} \to \frac{(1)^{10}}{17}$,
hence the required remainder is 1.

32. Let $S_n = 4^0 + 4^1 + 4^2 + 4^3 + 4^4 + 4^5 + \ldots + 4^{40}$
$\Rightarrow \quad S_n = (1 + 4 + 16) + 4^3(1 + 4 + 16)$
$+ 4^6(1 + 4 + 16) + \ldots + 4^{40}$
$\Rightarrow \quad S_n = 21 + 4^3(21) + 4^6(21) + 4^9(21) + \ldots$
$+ 4^{36}(21) + (4^{39} + 4^{40})$
Here we can see that except $(4^{39} + 4^{40})$ remaining expression is divisible by 7.

Now $\frac{(4^{39} + 4^{40})}{7} \to \frac{4^{39}(5)}{7} \to \frac{(4^3)^{13} \times 5}{7} \to \frac{5}{7}$
Hence the required remainder is 5.

33. The total distance which a monkey has to overcome is 35 metre.
Since the monkey first climbs up 5 metre and then he slips down by 2 metre, it means he climbs up only 3 metre in one round of 2 (= 1 + 1) minutes.
Now, note that if the monkey has to just climbup 5 metre then he will not be slipped back. Thus he will cover the 30 metre height in 10 rounds and the rest 5 metre height of the top will covere in only one attempt. Since when he will touch (or reach) the top of the pole he will not be slipped back.
Thus total number of attempts required = 11 (= 10 + 1).

NOTE In this type of question subtract the height which he/she climbs up in first attempt (*i.e.*, 5 metre in this question) then assuming the resultant height and solve it as usual. Now the length of the top will be covered in only one attempt of upward direction and then addup all the results obtained.

34. Since first he covers 30 metres in 20 minutes and the rest height of 5 metre (at the top) covers in only one minute.
Hence total time = 20 + 1 = 21 minutes.

35. Since the actual height is 36 metre.
Therefore 36 – 5 = 31, which is not divisible by 3.
Hence he will climb 33 (= 3 × 11) metre in 11 attempts taking 22 (= 11 × 2) minutes.
Now the rest height of 3 metre will be covered in $\frac{3}{5}$ minute
i.e., 36 seconds.
Hence total time taken to cover 36 metre height is 22 minutes 36 seconds.

36. $1^3 + 2^3 + 3^3 + 4^3 + \ldots + 1000^3$
$= \left[\frac{1000(1001)}{2}\right]^2 \left\{\because 1^3 + 2^3 + \ldots + n^3 = \left[\frac{n(n+1)}{2}\right]^2\right\}$
$= (500 \times 1001)^2 = 250000 \times 1001 \times 1001$,
which is divisible by 13. Hence the remainder is zero.

37. $(22)^3 + (23)^3 + (24)^3 + \ldots + (87)^3 + (88)^3$
$= (22^3 + 88^3) + (23^3 + 87^3) + (24^3 + 86^3)$
$+ (25^3 + 85^3) + \ldots + (54^3 + 56^3) + 55^3$
Now since we know that $a^n + b^n$ is divisible by $(a + b)$ when n is an odd number. Therefore all the terms, except $(55)^3$, is divisible by 110.
Now the remainder when $(55)^3$ is divided by 110 is 55.
Hence the required remainder of the whole expression is 55.

38. The value of nth term = Sum of n terms – Sum of $(n - 1)$ term
Therefore value of 6th term = Sum of 6 terms
– Sum of 5 terms
$= (6! + 6^2) - (5! + 5^2) = (720 + 36) - (120 + 25) = 611$

39. The smallest possible number which is divisible by either 3, 5 or 7 is 105. Now we express it in binary representation, then

2	105		
2	52	→ 1	→ LSB
2	26	→ 0	
2	13	→ 0	
2	6	→ 1	
2	3	→ 0	
2	1	→ 1	
	0	→ 1	→ MSB

Scanned by CamScanner

yoursmahboob.wordpress.com

Thus $(105)_{10} = (1101001)_2$.

Hence the minimum 7 digits are required to represent it.

40. Go through option

$S_n = 1 + 3 + 5 + 7 + \ldots + 22221$

$S_{11111} = (11111)^2$ $[\because S_n = n^2]$

Hence it is divisible by 11111. Thus option (b) is correct.

41. Go through options

Anjuli had chocolates = 12

She gave to Amit $= \frac{12}{2} - 1 = 5$

Now she is left with 7 chocolates
then she gave 3 chocolates to Bablu
Now she has 4 chocolates
then she gave 2 chocolates to Charles
Now she has only two chocolates.
Then she gave 1 chocolate to Deepak
and she is finally left with one chocolate.

Alternatively : Solve the problem in reverse.

Anjuli's chocolate = 1 (Finally)
Before she has given to Deepak = 2 chocolates
Before she has given to Charles = 4 chocolates
Before she has given to Bablu = 7 chocolates
Before she has given to Amit = 12 chocolates.

Alternatively : By forming the equation assuming any variable x as the original number of chocolates which Anjuli had.

42. Since $a_1b_1c_1$, $a_2b_2c_2$, $a_3b_3c_3$, ... etc. are consecutive 3 digit numbers. Hence $c_1, c_2, c_3, \ldots$ etc. must be the consecutive unit digits. Hence there will be all the 10 digits (*viz.*, 0, 1, 2, ..., 9) 10 times as unit digits.

It means the required unit digit is equal to the sum of all the unit digits.

Thus $[(1)^{100} + (2)^{100} + (3)^{100} + \ldots (9)^{100} + (10)^{100}] \times 10$

$= [1 + 6 + 1 + 6 + 5 + 6 + 1 + 6 + 1 + 0] \times 10$

$= [3] \times 10 = 0$

Thus the unit digit of the whole expression is 0 (zero).

43. $P(x, y) + Q(x, y)$

$= (f(x, y) + g(x, y)) + (f(x, y) - g(x, y))$

$= 2f(x, y) = 2 \times ([x] + \{y\})$

$= 2 \times ([16] + \{25\}) = 2 \times (16 + 25)$

$= 2 \times 41 = 82$

44. $P(x, y) \cdot Q(x, y) = (f(x, y) + g(x, y)) \cdot (f(x, y) - g(x, y))$

Now since $f(x, y) = [x] + \{y\} = [\pm 4] + \{\pm 5\}$

$f(\pm 4, \pm 5) = \pm 9$ or ± 1

and $g(x, y) = [x] - \{y\} = [\pm 4] - \{\pm 5\}$

$g(\pm 4, \pm 5) = \pm 9$ or ± 1

Now since there are too many combinations of $f(x, y)$ and $g(x, y)$.

So there is no unique value of $P(x, y) \cdot Q(x, y)$.

45. Since $P(x, y) + Q(x, y) = 2f(x, y)$

So the required value is always an even number.

46. $(50^2 - 1) = (50 + 1)(50 - 1) = (17 \times 3) \times (7 \times 7)$

hence divisible by 17.

and $(729)^5 - 729 = 729(729^4 - 1)$

$= 729(729^2 - 1)(729^2 + 1)$

$= (729)(729 - 1)(729 + 1)(729^2 + 1)$

$= 729 \times 728 \times 730 \times (729^2 + 1)$

Hence it is divisible by 5.

Alternatively : $(a^p - a)$ is divisible by p if p is a prime number.

47. Let there be n rows, then the number of soldier in each row $= \frac{36}{n}$

(Since the number of soldier in each row is same)

Now the number of bullets he gave to the first row

= 1 bullet × number of soldiers

and the number of bullets he gave to the second row,

= 2 bullets × number of soldiers

and the number of bullets he gave to the third row

= 3 bullets × number of soldiers

Hence total number of bullets

$= 1 \times \frac{36}{n} + 2 \times \frac{36}{n} + 3 \times \frac{36}{n} + \ldots + n \times \frac{36}{n}$

$180 = \frac{36}{n}(1 + 2 + 3 + \ldots + n)$

or $180 = \frac{36}{n} \times \frac{n(n+1)}{2}$

or $180 = \frac{36(n+1)}{2}$

$\Rightarrow (n + 1) = 10$

$\Rightarrow n = 9$

Thus the number of soldiers in each row $= \frac{36}{9} = 4$

Hence, there are 4 soldiers in 8th row.

48. Given that $(n - 5)$ is divisible by 17 and let $(n - 5) = k = 17m$

So $(n + 12) \times (n + 29) = (n - 5 + 17) \times (n - 5 + 34)$

$= [(n - 5) + 17] \times [(n - 5) + 34]$

$= (k + 17) \times (k + 34)$

$= k^2 + 51k + 2(17)^2$

Now since k is divisible by 17 so,

$k^2 + 51k + 2.(17)^2 = (17m)^2 + 51 \times 17m + 2.(17)^2$

$= 17^2 (m^2 + 3m + 2)$

Now the least possible value of $m = 1$, therefore $(n + 12) \times (n + 29)$ is divisible by $(17)^2 \times 6 = 1734$.

49. Go through option :

$(3^{96} - 1) = (3^{48} + 1)(3^{48} - 1)$

$= (3^{48} + 1)(3^{24} + 1)(3^{24} - 1)$

Thus if any number 'n' can divide $(3^{24} - 1)$ it will certainly divide $(3^{96} - 1)$.

50. $(5^{28} - 1) = (5^{14} + 1)(5^{14} - 1)$

and $(5^{42} - 1) = (5^{14})^3 - 1$

$= (5^{14} - 1)(5^{28} + 1 + 5^{14}.1)$

Hence both (a) and (b). Thus the appropriate answer is (d).

51. Check through some values.

Alternatively : $T_1 = 1^2 + 1$

$T_2 = 2^2 + 2$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$T_3 = 3^3 + 3$$
.....
.....
$$T_n = n^2 + n$$

$$S_n = T_1 + T_2 + T_3 + \ldots + T_n$$
$$= (1^2 + 1)(2^2 + 2)(3^2 + 3) + \ldots + (n^2 + n)$$
$$= (1^2 + 2^2 + 3^2 + \ldots + n^2) + (1 + 2 + 3 + \ldots + n)$$
$$= \frac{n(n+1)(2n+1)}{6} + \frac{n(n+1)}{2}$$
$$= \frac{n(n+1)}{2}\left[\frac{2n+1}{3} + 1\right] = \frac{n(n+1)}{2}\left[\frac{2n+4}{3}\right]$$
$$S_n = \frac{n(n+1)(n+2)}{3}$$

52. The number of zeros at the end of $222^{111} \times 35^{53}$ is 53.
The number of zeros at the end of $(71)^{61} \times (101)^{51}$ is 960.
The number of zeros at the end of $42^{42} \times 25^{25}$ is 42.
Thus the number of zeros at the end of the whole expression is 42.

53. $\frac{12345}{12346} + \frac{12346}{12347} + \frac{12347}{12345}$
$$= 1 - \frac{1}{12346} + 1 - \frac{1}{12347} + 1 + \frac{2}{12345}$$
$$= 3 + \frac{2}{12345} - \frac{1}{12346} - \frac{1}{12347} = 3$$

54. The sum of all the elements of $S_n = n^3$
Therefore the sum of all the element of $S_{10} = (10)^3 = 1000$

55. The middle most element of any odd number of set
$$S_n = n^2$$
Therefore the 11th (*i.e.*, the mid/most) element of
$$S_{21} = (21)^2 = 441$$

56. The sum of the first and last elements of the odd number of set $S_n = 2n^2$.
Therefore the required answer $= 2 \times (51)^2$
$$= 2 \times 2601 = 5202$$

57. $k = 13 + 17 + 31 + 2$
$$= (9 + 3) + (9 + 7) + (9 + 9 + 9 + 1) + 2$$
$$= 9 + 9 + 9 + 9 + 9 + 7 + 2 + 3 + 1$$
$$= 9 + 9 + 9 + 9 + 9 + 9 + 4 = 64$$
$[\because 9 + 9 = 19, 19 + 9 = 29, 29 + 9 = 39, 39 + 9 = 49,$
$49 + 9 = 59, 59 + 4 = 64]$

58. $4 + 16 - 5 + 12 = 12 + 4 + 16 - 5$
$$= 16 + 11 = (9 + 6) + (9 + 1)$$
$$= 9 + 9 + 7 = 27$$

59. Check for options (a), (b) and (c) then you will find distinct unit digits. Now consider $x = 10^4$.
The unit digit of $(7)^4 = 1$ $[\because \log_{10}(10^4) = 4]$
and the unit digit of $(3)^{10000}$ is 1.
Hence (d).

60. $(1 + 2 + 3 + 4 + 7)^{x^2 + x}$ and $(11 \times 11 \times 13)^x$
$$(17)^{x^2 + x} \text{ and } (1573)^x$$
at $x = 2$, $x^2 + x = 6$
$\therefore$ The unit digit of $(17)^6$ is 9 and the unit digit of $(1573)^2$ is 9
Hence (b) is correct.

61. For example

	Remainder
$\frac{3^2}{8} \to$	1
$\frac{3^4}{8} \to$	1
$\frac{5^6}{8} \to$	1
$\frac{7^2}{8} \to$	1
$\frac{11^2}{8} \to$	1 etc.

62.

	Wednesday
	2
	9
Thus $(23 - 2) = 21$, will	16
fall on Monday.	23
	30

63.

	Wednesday
	2
	8
21 will fall on Thursday.	14
	20
	26

64. Eldest said → Equal number of brothers and sisters (excluding eldest one)
⇒ 3 brothers and 3 sisters (excluding eldest one)
Youngest said → Twice the number of sisters as the number of brothers
⇒ 4 sisters and 2 brothers (excluding youngest)
It means there are 3 male and 4 female persons.
Now, as the youngest said that there are 4 sisters and 2 brothers engaged in work. Therefore it is obvious that the youngest person itself is a male. Hence it can be inferred that the brother of *S* is youngest.

	F	*F*	*F*	*F*	*M*	*M*	*M*
As :	*S*	*T*	*R*	*A*	*N*	*G*	*E*
	↑						↑
	Eldest						Youngest

65. Since $(10x + y) - (x + y) = 9x$
$(100x + 10y + z) - (x + y + z) = 9(11x + y)$
$(1000w + 100x + 10y + z) - (w + x + y + z)$
$= 9(111w + 11x + y)$ etc.
Hence all these numbers are divisible by 9.

66. $$y + \frac{7}{x} + \frac{y}{13} = 6\frac{3}{143}$$
$$\Rightarrow \quad \frac{14y}{13} + \frac{7}{x} = \frac{861}{143}$$
Now, the value of x can be only 11 or 143 or its multiples, inorder to satisfy the relation.
Let $x = 11$, then
$$\frac{14y}{13} = \frac{861}{143} - \frac{7}{11}$$
$$\Rightarrow \quad \frac{14y}{13} = \frac{770}{143}$$
$$\Rightarrow \quad y = 5$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Therefore $x - y = 7 - 5 = 2$

Again, $x = 143$, then

$$\frac{14y}{13} = \frac{861}{143} - \frac{7}{143} \Rightarrow \frac{14y}{13} = \frac{854}{143}$$

$\Rightarrow y = \frac{61}{11}$, which is not a natural number.

Therefore it is clear that when $x \neq 143$, then the multiples of 143 are also not acceptable.

Thus the only acceptable value is $x = 7$ and $y = 5$.

Hence $x - y = 2$, is the correct answer.

67. In the first subset, the number of elements

Divisible by 3 → (3, 9, 15, 21, ..., 99) ⇒ 17
Divisible by 9 → (9, 27, 45, ... 99) ⇒ 6
Divisible by 27 → (27, 81) ⇒ 2
Divisible by 81 is 162 only ⇒ 1
} 26

In the second subset, the number of elements

divisible by 3 → {102, 108, ..., 198} ⇒ 17
divisible by 9 → {108, 126, ..., 198} ⇒ 6
divisible by 27 → (108, 162) ⇒ 2
divisible by 81 is 162 only ⇒ 1
} 26

Hence the greatest power of 3 is 52 which can divide the product of all the elements of the given set.

68. In the first subset, the number of elements

divisible by 5 → {5, 15, 25, ..., 95} ⇒ 10
divisible by 25 → (25, 75) ⇒ 2
} 12

In the second subset, the number of elements

divisible by 5 → {110, 120, 130, ..., 200} ⇒ 10
divisible by 25 → {150, 200} ⇒ 2
} 12

Thus the highest power of 5 is 24 that can divide the product of all the elements of the set.

69. In the first subset, the number of elements

divisible by 5 → (10, 20, 30, 40, 50) → 5
divisible by 25 → (50) → 1

In the second subset, the number of elements

divisible by 5 → (55, 60, 65, 70, ...) → 10
divisible by 25 → (75, 100) → 2

(Note, that in the whole set the number of 2's are greater than the number of 5's)

Hence the number of zeros at the end of the product of the element is 18. Hence (a).

70. Since the 5th number is 10,
10th number is 20
15th number is 30
20th number is 40
25th number will be 100

71. Since in normal one hour this watch completes 5 hours. So in normal 3 hours this watch will completes 15 hours hence it will show 3 o'clock As, 15 = 12 + 3.

72.
$$T_1 = 5 \times 1 + 1$$
$$T_2 = 5 \times 2 + 1$$
$$T_3 = 5 \times 3 + 1$$
$$\ldots\ldots\ldots\ldots$$
$$\ldots\ldots\ldots\ldots$$
$$T_n = 5 \times n + 1$$

$\therefore S_n = 5(1 + 2 + 3 + \ldots + n) + (1 + 1 + \ldots + n \text{ times})$

$$= 5\left[\frac{n(n+1)}{2}\right] + n = \frac{5n^2 + 7n}{2} = \frac{n}{2}(5n + 7)$$

73. Go through options or solve similarly as Q. No. 72.

74. Let the original dimension of a square be x unit then the area will be x^2, hence total area of paper = $144x^2$

Again the area of reduced square = $(x - 2)(x - 2) = (x - 2)^2$

therefore the total area of paper = $400\,(x - 2)^2$

Thus $144x^2 = 400\,(x - 2)^2$

$\Rightarrow 9x^2 = 25\,(x - 2)^2$

$\Rightarrow 9x^2 = 25x^2 + 100 - 100x$

$\Rightarrow 16x^2 - 100x + 100 = 0$

$\Rightarrow x = 5$ cm

$\therefore$ Area of paper $= 5 \times 5 \times 144 = 3600$

Alternatively : $\frac{3600}{114} \rightarrow 25 \rightarrow$ side of square = 5 cm

$\frac{3600}{400} \rightarrow 9 \rightarrow$ side of new square = 3 cm

Hence option (c) is correct.

75. $(ab)^2 = bcb$, where ab is a two digit number and bcb is a three digit number.

Now 'b' can be equal to 0, 1, 5 or 6, which are probable values of b as a unit digit.

at $b = 0$, bcb is not a three digit number.

at $b = 1$ either $a = b$ or $b = c$ or $b \neq b$, which is not possible.

at $b = 5$, c is always 2 and $b \neq b$, hence not possible.

at $b = 6$ and $a = 2$, $(ab)^2 = bcb$ *i.e.*, $(26)^2 = 676$, the only possible value.

Thus $a = 2, b = 6, c = 7$.

Since b, c, d are in AP hence $d = 8$

Therefore $(dd)^2 = (88)^2 = 7744 = ccff$

$\Rightarrow f = 4$

76. $A = 555! = 1 \times 2 \times 3 \times 4 \times \ldots \times 277 \times 278 \times 279 \times \ldots \times 554 \times 555$

$= (1 \times 555) \times (2 \times 554) \times (3 \times 553) \times (4 \times 552) \times \ldots$

$\times (277 \times 279) \times (278)$

and $B = (278)^{555} = (278 \times 278) \times (278 \times 278)$

$\times (278 \times 278) \ldots (278)$

Hence $A < B$.

77. The last element of nth set $= \frac{n(n+1)}{2}$

Therefore last element of $S_{24} = \frac{24 \times 25}{2} = 300$

78. The middlemost element of any odd number set is $\frac{n^2 + 1}{2}$

Therefore the middlemost element of the set S_{15} is

$$\frac{15^2 + 1}{2} = 113$$

79. The sum of all the elements of an odd numbered set

$S_n = n \times$ (middlemost term)

Therefore, the sum of all the elements of set

$$S_{25} = 25 \times \left(\frac{25^2 + 1}{2}\right) = 25 \times 313 = 7825$$

80. Write the elements and then find out.

S_9, S_{12}, S_{13} have maximum number of prime number elements equally.

81. The sum of all the elements of the set S_n is even if n is divisible by 4. Hence (c) is the required answer.

Thus sum of all the elements of S_{72} is even since 72 is divisible by 4.

Scanned by CamScanner

yoursmahboob.wordpress.com

82. Check the options.

83. The last element of the set $S_n = n^2 + n - 1$
Therefore the last element of the set $S_{100} = 10099$

84. The middlemost element of an odd number set $S_n = n^2$
Therefore the middlemost element of $S_{125} = (125)^2 = 15625$

85. The sum of all the elements of any set $S_n = n^3$
Therefore the required sum of the set

$$S_{101} = (101)^3 = 1030301$$

86. $S = \frac{1}{1.2} + \frac{1}{2.3} + \frac{1}{3.4} + \ldots + \frac{1}{99.100}$

$$= \left(\frac{1}{1} - \frac{1}{2}\right) + \left(\frac{1}{2} - \frac{1}{3}\right) + \left(\frac{1}{3} - \frac{1}{4}\right) + \ldots + \left(\frac{1}{99} - \frac{1}{100}\right)$$

$$= 1 - \frac{1}{100} = \frac{99}{100}$$

87. $\frac{P}{D} \rightarrow$ Remainder 18

$\frac{Q}{D} \rightarrow$ Remainder 11

$\frac{P+Q}{D} \rightarrow$ Remainder 29, but the remainder is 4.

Hence, the divisor = (29 − 4) = 25.

88. Note $1 \times 2 \times 3 \times 4 \times \ldots \times (n-1).\ n = n!$
Now if n = 240, 241, 242, 243, 244 (5 values)
then the number of zeros in the end of the product of $n!$ is 68.
Alternatively : The number of zeros in the given expression will depend on number of 5's (but do not depend on number of 2's). Now, since you know that the number of 5's changed at the interval of 5 consecutive numbers. Then there will be no any change in the number of zeros (since number of 5's) for the five consecutive values of n.

89. Since $\frac{6}{10} \rightarrow$ Remainder is 6.

$\frac{6^6}{10} \rightarrow$ Remainder is 6

$\frac{6^{6^6}}{10} \rightarrow$ Remainder is 6

90. Since we know that if $(a + b + c) = 0$, then

$$a^3 + b^3 + c^3 = 3abc$$

Therefore $53^3 - 46^3 - 7^3 = 3 \times 53 \times 46 \times 7$

91. Let the original number in base 'n' be $(xy)_n$ then its reverse number be $(yx)_n$

Again $2(nx + y) = (ny + x)$

$$\Rightarrow \quad \frac{x}{y} = \frac{n-2}{2n-1}$$

So at $n = 3$, $\frac{x}{y} = \frac{1}{5}$

at $n = 4$, $\frac{x}{y} = \frac{2}{7}$

and at $n = 5$ $\frac{x}{y} = \frac{3}{9} = \frac{1}{3}$

and at $n = 8$ $\frac{x}{y} = \frac{6}{15} = \frac{2}{5}$

but the values of x, y cannot be equal to or greater than their respective bases. Hence there are only two values of n are possible *viz.*, $n = 5$ and $n = 8$.

Now since the greatest possible value of n is 8. Hence the numbers in base n = 8 are 25 and 52. Again when we convert them into base 10, then the numbers are 21 and 42.
Thus the sum of these numbers in decimal system is 63.

92. $n = 5, 8$. Hence (b).

93. $7^0 + 7^1 + 7^2 + 7^3 + \ldots + 7^{365} = \frac{1(7^{366} - 1)}{(7-1)} = \frac{(7^{366} - 1)}{6}$,

its divisible since $(a^n - b^n)$ is divisible by $(a - b)$.

Now $\frac{(7^{366} - 1)}{5} \rightarrow \frac{(2^{366} - 1)}{5} \rightarrow \frac{(4)^{183} - 1}{5} \rightarrow \frac{4-1}{5} \rightarrow \frac{3}{5}$

Since the remainder is 3.
Hence Krishna will receive 3 hens.

94. These numbers are 1 and 81.

95. $\frac{\text{Actual number of boys}}{\text{Actual number of girls}} = \frac{1}{1}$

Since $\frac{2}{3}$rd girls didnot go to picnic.

Hence the ratio of boys to the girls at picnic = 3 : 1.
Now, let there be k samosas to be distributed among boys or girls equally then

$\frac{k}{3x} \rightarrow$ Remainder 39

and $\frac{k}{x} \rightarrow$ Remainder 12

Now, since $39 - 12 = 27$

Thus x = 27, or 3, or 9 [$\because 27 = 1 \times 27$ or $27 = 3 \times 9$]

but since x cannot be less than 12

hence $x = 27$

Thus the number of boys = $3x = 81$
and the number of girls = $3x = 81$
Hence total number of students = 162

96. In any box the maximum number of fruits can be packed is 15 and since not more than 5 boxes contain same number of fruits. So the number of fruits in this case = $5 \times 15 = 75$
Again we can put 14 fruits in other 5 boxes = $5 \times 14 = 70$
Similarly 13 fruits in each of the 5 boxes can be contained

$$= 5 \times 13 = 65$$

Since the minimum number of fruits we have to put in a box = 10
So the total number of fruits which can be put

$$= 5 \times 15 + 5 \times 14 + 5 \times 13 + 5 \times 12 + 5 \times 11 + 5 \times 10$$
$$= 5(10 + 11 + 12 + 13 + 14 + 15) = 375$$

97. To maximize the contents in the boxes first we fill up 15–15 fruits in maximum possible number (*i.e.*, 7) of boxes.

7	15	15	15	15	15	15	15
7	14	14	14	14	14	14	14
7	13	13	13	13	13	13	13
7	12	12	12	12	12	12	12
5	11	11	11	11	11		

Then we fill up 14, 13, 12, in 7–7 boxes. Thus we filled up 28 boxes containing maximum number of fruits. Now in the rest 5 boxes we fill up 11 fruits in each box to its maximum possible capacity. Now we see that there are at least 5 boxes in which the number of fruits are same.

Scanned by CamScanner

yoursmahboob.wordpress.com

98. $(19)^n - (23)^n - (43)^n + (47)^n$

$= [(47)^n + (19)^n] - [(43)^n + (23)^n]$

$= (47 + 19)\,k - (43 + 23)\,l$

[since $a^n + b^n$ is divisible by $(a + b)$ if n is odd]

$= 66\,[k - l]$

Hence, it is divisible by 2, 3, 6, 11, 22, 33 and 66.

Again $(47)^n - (23)^n - (43)^n + (19)^n$

$= (47)^n - (23)^n - [(43)^n - (19)^n]$

$= (47 - 23)\,(k) - (43 - 19)\,(l) = 24\,(k - l)$

[$\because$ since $(a^n - b^n)$ is divisible by $(a - b)$]

Therefore it is divisible by 2, 12, 3, 8, 4, 6.

Thus the whole expression is divisible by 264.

Since $264 = 11 \times 24$.

99. $1\cdot(1)^2\left(1-\frac{0}{1}\right) + 2\cdot 2^2\left(1-\frac{1}{2}\right) + 3\cdot 3^2\left(1-\frac{2}{3}\right) + 4\cdot 4^2\left(1-\frac{3}{4}\right)$

$= 1\cdot(1)^2\cdot 1 + 2\cdot(2)^2\cdot\frac{1}{2} + 3\cdot(3)^2\cdot\frac{1}{3} + 4\cdot(4)^2\cdot\frac{1}{4} + \ldots$

$= 1^2 + 2^2 + 3^2 + 4^2 + \ldots + n^2$

$= \frac{n\,(n+1)(2n+1)}{6}$

100. These numbers are (101, 102) (111, 112) (121, 122)



(131, 132) (141, 142) ... (202, 203) (212, 213) ... (303, 304) (313, 314) ... (808, 809) ... (898, 899, 900) ... (909, 910) (919, 920) ... (989, 990).

Thus there are total $20 \times 7 + 21 + 18 = 179$, mile stones which are red, because the hundreds digit on next mile stone is same as the unit of previous mile stone.

101. $(18^2 - 1) = (17)(18 + 1)$

$(18^4 - 1) = (18^2 + 1)(18^2 - 1)$

$= (18^2 + 1)(18 + 1)(18 - 1)$

$(18^6 - 1) = (18^3)^2 - 1$

$= (18^3 + 1)(18^3 - 1) = 17 \times k$ etc.

Hence there will only 9 times 17 in the whole expression.

102. $\frac{M}{28} \to$ Remainder 24 $\Rightarrow$ $M = 28k + 24$

and $\frac{M}{22} \to$ Remainder 12 $\Rightarrow$ $M = 22l + 12$

$\Rightarrow$ $M = 28k + 24 = 22l + 12$

$\Rightarrow$ at $k = 9$, $l\,(= 12)$, is an integer, for the least solution.

Hence, $M = 276$ ...(1)

and higher such numbers can be obtained as

$M' = 308p_1 + 276$ ...(2)

Again $\frac{N}{28} \to$ Remainder 16 $\Rightarrow$ $N = 28m + 16$

and $\frac{N}{22} \to$ Remainder 12 $\Rightarrow$ $N = 22n + 12$

$\Rightarrow$ $N = 28m + 16 = 22n + 12$

at $m = 3$, $n\,(= 4)$ is an integer, for the least solution.

Hence $N = 100$

and higher such numbers can be obtained as

$N' = 308p_2 + 100$

Now, $28 + 22 = 50$, hence $(M' + N')$ must be divisible by 5.

So $M' + N' = 308\,(p_1 + p_2) + 376$

Inorder that $M' + N'$ must be divisible by 50, either $p_1 = 1$ and $p_2 = 2$ or $p_1 = 2$ and $p_2 = 1$, for the least possible solution.

Hence, $M' + N' = 308 \times 3 + 376 = 1300$.

103. Since $M' + N' = 308\,(p_1 + p_2) + 376$

As we can observe that the values of p_1 and p_2 are not constant so we cannot determine uniquely the ratio of $M' : N'$.

104. In each set of 100 numbers, there are 10 numbers whose tens digit and unit digit are same. Again in the same set there are 10 numbers whose hundreds and tens digits are same. But there is one number in each set of 100 numbers whose Hundreds, Tens and Unit digit are same as 111, 222 etc. Hence there are exactly $(10 + 10 - 1) = 19$ numbers in each set of 100 numbers. Further there are 9 such sets of number. Hence total required number = 171.

Alternatively :

H	T	U
9	10	10

$-$

H	T	U
9	9	9

$900 - 729 = 171$

105. $(1 + p)^{256} \times (1 + p^{128}) \times \ldots \times (1 + p^2)(1 + p) \times \frac{(1 - p)}{(1 - p)}$

$= \frac{(1 + p^{256})(1 - p^{256})}{1 - p} = \frac{(1 - p^{512})}{1 - p}$

106. Let the length and breadth of the given perimeter be l and b respectively. Then

$2\,(l + b) = 50$

$\Rightarrow$ $l + b = 25$

Now $(b, l) = (1, 24), (2, 23), (3, 22), (4, 21), (5, 20), (6, 19), (7, 18), (8, 17), \ldots, (12, 13)$

Therefore the required number of rectangles = 12

107. The product of prime factors $= 30 = 2 \times 3 \times 5$

Now the total number of prime factors = 24

$= 2 \times 2 \times 6$ $\Rightarrow$ $(1 + 1)(1 + 1)(5 + 1)$

So the least possible number $= 2^5 \times 3^1 + 5^1 = 480$

and the greatest possible number $= 2^1 \times 3^1 \times 5^5 = 18750$

So the ratio of $= \frac{480}{18750} = \frac{2^4}{5^4}$

$\therefore$ The square root $= \frac{2^2}{5^2} = \frac{4}{25}$

108. Let the powers of 2, 3, 5 be a, b, c respectively then the total number of factors = 24

$= (a + 1)(b + 1)(c + 1) = 24$

So if $(a + 1) = k$, $(b + 1) = l$, $(c + 1) = m$, then

$k \times l \times m = 24$, where $k, l, m \geq 2$

$2 \times 2 \times 6$
$2 \times 3 \times 4$
$2 \times 6 \times 2$
$2 \times 4 \times 3$
$3 \times 2 \times 4$
$3 \times 4 \times 2$
$4 \times 2 \times 3$
$4 \times 3 \times 2$
$6 \times 2 \times 2$

Hence there are total 9 numbers possible.

Scanned by CamScanner

yoursmahboob.wordpress.com

109. The best way is to go through options. You will find that when you consider 150 question you can not get 75 marks any how.

Alternatively : Since 75 is an integer, hence he must have to do $(75 + 4x)$ problems, where x is a whole number. Now put the values of x and satisfy the given options.

Explanation : Since he gets the net marks in integers it means when he does $3n$ questions wrong , he loses actually $4n$ marks. For more classification see the table below :

Total Questions	Correct	Marks	Wrong	Marks	Net marks
75	75	75	0	0	75
79	76	76	3	−1	75
83	77	77	6	−2	75
87	78	78	9	−3	75

110. Solve it through options

	Total given coins	Rest coins
$(25-1)\times\frac{1}{2}=24\times\frac{1}{2}=12$	13	12
$(12-2)\times\frac{1}{2}=10\times\frac{1}{2}=5$	7	5
$(5-3)\times\frac{1}{2}=2\times\frac{1}{2}=1$	4	1

Hence he must have been stolen 25 coins.

111. Let $y=\log_2 7 \Rightarrow 2^y=7$ $\quad(\because x^y=a\Rightarrow \log_x a=y, x\neq 1)$

[Clearly y neither can be an integer nor a fraction]

Now if y is a rational number, we can write as

$$y=\frac{p}{q};\ q\neq 0$$

Thus $\quad 2^{p/q}=7 \ \Rightarrow\ 2^p=7^q.$

Since in L.H.S. the quantity is even while in the right hand side the given quantity is odd. Thus, y can't be a rational number.

112. Let us consider $2\times\frac{1}{2}=1,$

then $\quad 2+\frac{1}{2}=2\cdot 5$

Thus the option (a) and (b) are ruled out.

Again, let us take some different values

viz., $\quad \frac{1}{3}\times\frac{3}{2}\times 2=1$

then, $\quad \frac{1}{3}+\frac{3}{2}+2=\frac{23}{6}\neq 3+\frac{1}{3}\left(=\frac{10}{3}=\frac{20}{6}\right)$

hence option (c) is ruled out.

Finally, option (d) is correct, as can be seen from the above illustrations.

Alternatively : Let $a_1, a_2, a_3, \ldots, a_n$ be n positive real numbers such that $a_1 . a_2 \ldots a_n = 1$.

Now, we know that A.M. ≥ G.M. for some given quantities.

So $\quad \frac{(a_1+a_2+a_3+\ldots+a_n)}{n}\geq (a_1 . a_2 . a_3 \ldots a_n)^{1/n}=1$

$\Rightarrow \quad (a_1+a_2+a_3+\ldots+a_n)\geq n$

Hence option (d) is correct choice.

113. Let $S=1+n+n^2+\ldots+n^{127}$

$$=\frac{1(n^{128}-1)}{(n-1)} \qquad \left[\because S_n=\frac{a(r^n-1)}{r-1};\ r>1\right]$$

$$=\frac{n^{128}-1}{(n-1)}=\frac{(n^{64}-1)(n^{64}+1)}{(n-1)}$$

Thus at $m = 64$ the given expression is divisible by $(n^m + 1)$.

Hence (c).

114. We have $240 = 2^4 \times 3 \times 5$

∴ Number of divisors

$= 5 \times 2 \times 2 = 20$, which are given below :

1	2	4	8	16
3	6	12	24	48
5	10	20	40	80
15	30	60	120	240

Thus only 4 divisors are of the form $4n + 2$

Hence option (a) is correct.

115. We know that if a number is divisible by 5, then its unit digit must be either 0 or 5.

Again, the unit digits of $7^1 = 7$

$7^2 = 9$

$7^3 = 3$ and $7^4 = 1$

i.e., we can get only 7, 9, 3, 1 as unit digits.

Now, the combinations of 7, 9, 3, 1 never gives unit digit 5, but $7 + 3 = 9 + 1 = 10$, these two combinations gives us unit digit zero.

So $7^m + 7^n$ is divisible where

case (i) $m = 1, 5, 9, \ldots, 97$ correspondingly $n = 3, 7, 11, \ldots, 99$

case (ii) $m = 2, 6, 10, \ldots, 98$ correspondingly $n = 4, 8, 12, \ldots, 100$

or the values of m and n can be reversed in each case mutually but then we get the same values.

Hence total distinct numbers so formed, divisible by 5, are

$$1250 = 25 \times 25 + 25 \times 25$$

Hence option (a) is correct.

116. Let us assume the values of a, b, c, d such that

$$a+b+c+d=2$$

i.e., $\quad \frac{1}{3}+\frac{2}{3}+\frac{1}{4}+\frac{3}{4}=2$

then $\quad M=(a+b)(c+d)=\left(\frac{1}{3}+\frac{2}{3}\right)\left(\frac{1}{4}+\frac{3}{4}\right)=1$

Hence option (c) and (d) are ruled out.

now, if a, b, c, d be $\frac{1}{3}, \frac{1}{4}, \frac{2}{3}, \frac{3}{4}$, then

$$M=(a+b)(c+d)=\left(\frac{1}{3}+\frac{1}{4}\right)\left(\frac{2}{3}+\frac{3}{4}\right)=\frac{119}{144}<1$$

Hence option (b) is also ruled out. Thus only option (a) is correct.

Alternatively : Let $a + b = P$ and $c + d = Q$,

$$P + Q = 2 \quad \text{and} \quad PQ > 0$$

(Since P and Q are positive real numbers)

Further we know that

$$\text{AM} \geq \text{GM} \ \Rightarrow\ \frac{P+Q}{2}\geq\sqrt{PQ}$$

$$\Rightarrow \quad 1\geq\sqrt{PQ} \ \Rightarrow\ 1\geq PQ$$

$$\therefore \quad PQ = M \leq 1$$

Hence option (a) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

2 AVERAGES

In MAT, CET, FMS and other entrance exams the questions are directly asked from this chapter and they are very moderate, but in CAT this chapter constitutes a very low proportion of questions *i.e.*, they are rarely asked based on direct formula. As in last 10-12 years on an average 1 question per year has appeared in CAT and each question was almost of applied nature and blended with the logical reasoning.

So, when we said that on an average there was 1 question was asked per year in the last decade (*i.e.*, 10 years), it means we can conclude that almost 10 questions were asked by CAT in the last 10 years.

In general average is the central value of the given data. For example if the heights of three persons *A*, *B* and *C* be 90 cm, 110 cm and 115 cm respectively, then the average height of *A*, *B* and *C* together will be $\frac{90+110+115}{3} = 105$ cm.

So we can say that the height of each person *viz.* *A*, *B* and *C* is near about 105 cm. Thus in layman's language it can be said that every one is almost 105 cm tall.

Basically the average is the arithmetic mean of the given data. For example if the $x_1, x_2, x_3, x_4 \ldots x_n$ be any '*n*' quantities (*i.e.*, data), then the average (or arithmetic mean) of these '*n*' quantities

$$= \frac{x_1 + x_2 + x_3 + \ldots x_n}{n}$$

PROPERTIES OF AVERAGES

1. The average of any two or more quantities (or data) necessarily lies between the lowest and highest values of the given data. *i.e.*, if x_l and x_h be the lowest and highest (or greatest) values of the given data $(x_1, x_2, \ldots x_l, \ldots x_h, \ldots x_n)$ then $x_l < \text{Average} < x_h$; $x_l \neq x_h$

$$i.e., \quad x_l < \frac{(x_1 + x_2 + x_3 + x_l \ldots + x_h \ldots + x_n)}{n} < x_h$$

EXAMPLE 1 *The average of 8, 9, 12, 13, 15, 9 is :*
(a) 11 *(b) 6* *(c) 16* *(d) 18*

SOLUTION From the above mentioned property (1) we can say that options (b), (c) and (d) are invalid since 6, 16, and 18 are out of range *i. e.*, either below 8 (which is the least value) or above 15 (which is the highest value of the data).
So, option (a) can be acceptable only.
Alternatively :

$$\text{Average} = \frac{8+9+12+13+15+9}{6} = \frac{66}{6} = 11$$

EXAMPLE 2 *A has 8 pencils, B has 10 pencils and C has 15 pencils, then the average number of pencils with them :*
(a) 8 *(b) 10*
(c) 15 *(d) lies between 9 and 15*

SOLUTION Average number of pencils $= \frac{8+10+15}{3} = 11$

So, option (d) is correct.

2. If each quantity is increased by a certain value '*K*' then the new average is increased by *K*.

EXAMPLE 3 *A, B, C, D, E are the five electronic shops in the Nazaa market, which have 20, 30, 60, 80 and 50. T.V. sets with them respectively, then the average number of T.V. sets in each shop is :*
(a) 24 *(b) 48* *(c) 50* *(d) 60*

SOLUTION Average number of T.V. sets

$$= \frac{20+30+60+80+50}{5}$$

$$= 48$$

So option (b) is correct.

EXAMPLE 4 *In the previous example, if each of A, B, C, D and E have imported 12 new T.V. sets, then the average number of T.V. sets is:*
(a) 50 *(b) 56* *(c) 60* *(d) 144*

SOLUTION Average number of T.V. sets

$$= \frac{(20+12)+(30+12)+(60+12)+(80+12)+(50+12)}{5}$$

$$= \frac{300}{5} = 60$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively :

$$\frac{(20+30+60+80+50)+(12+12+12+12+12)}{5}$$

$$=\frac{(240)+(5\times 12)}{5}=48+12=60$$

Thus, the new average will be 60.

EXAMPLE 5 *The average number of shirts with Salman, Ambani and Dalmiya is 60, if all of them reached a shopping mall (AMBI) in Gurgaon and purchased 6 shirts each of them then the average number of shirts each of them now has :*

(a) 66 *(b) 63*
(c) 62 *(d) can't be determined*

SOLUTION Required average = Old average + New average
$= 60 + 6 = 66$

3. If each quantity is decreased by a certain value K, then the new average is also decreased by K.

EXAMPLE 6 *A, B, C, D, E, F are the only six families in Indira nagar. A, B, C, D, E and F has 7, 8, 10, 13, 6, and 10 members in their families respectively.*
If 1 member from all the six families left their respective families to accomodate themselves in the hostel of IIM Lucknow, then the average number of members now in each family of Indira nagar is :

(a) 8 *(b) 9* *(c) 10* *(d) 13*

SOLUTION Required average =

$$\frac{(7-1)+(8-1)+(10-1)+(13-1)+(6-1)+(10-1)}{6}$$

$$=\frac{(7+8+10+13+6+10)}{6}-\frac{(6\times 1)}{6}$$

$$=9-1=8$$

EXAMPLE 7 *Last year Sahara, Tata, Singhania and Birla each has 250 industries. This year everyone has sold out 10 factories due to the recession of the economy and poor turnout. The average number of industries which each of them now has :*

(a) 260 *(b) 240*
(c) 25 *(d) none of these*

SOLUTION Required average = Old average – New average
$= (250) - (10) = 240$

4. If each quantity is multiplied by a certain value K, then the new average is the product of old average with K.

EXAMPLE 8 *In a flower shop there were 6 flowers in each bouquet. If the seller has doubled the number of flowers in each bouquet then the new average of flowers in each bouque is :*

(a) 12 *(b) 8*
(c) 3 *(d) none of these*

SOLUTION Now required average = Old average × Multiplicand
$= 6 \times 2 = 12$

5. If each quantity is divided by a certain quantity 'K', then the new average becomes $\frac{1}{K}$ times of the initial average, where $K \neq 0$.

EXAMPLE 9 *The average of 100, 200, 300, 400, ..., 1000 is 550. If each number is divided by 5, then the new average will be equal to :*

(a) 450 *(b) 45*
(c) 55 *(d) none of these*

SOLUTION Actual average

$$=\frac{(100+200+300+\ldots+1000)}{10}=550$$

the new average $=\frac{550}{5}=110$

Hence, (d) is correct.

6. If 'A' be the average of $x_1, x_2, x_m, \ldots y_1, y_2, \ldots y_n$ where $x_1, x_2, \ldots, x_m$ be the below A and $y_1, y_2, y_3, \ldots y_n$ be the above A, then

$$(A-x_1)+(A-x_2)+\ldots(A-x_m)$$
$$=(y_1-A)+(y_2-A)+\ldots(y_n-A)$$

i.e., the surplus above the average is always equal the net deficit below average.

EXAMPLE 10 *The salary of A, B, C, D, E is Rs. 8000. Rs. 5000, Rs. 11000, Rs. 7000, Rs. 9000 per month respectively, then the average salary of A, B, C, D and E per month is :*

(a) Rs. 7000 *(b) Rs. 8000*
(c) Rs. 8500 *(d) Rs. 9000*

SOLUTION Average salary

$$=\frac{8000+5000+11000-7000+9000}{5}$$

$= \text{Rs. } 8000$

NOTE The average salary = Rs. 8000
and the sum of salaries above Rs. 8000

Therefore, the average surplus = $\frac{20000}{2}$

again, the sum of salaries below Rs. 8000

Therefore, the average deficit = $8000 - \left(\frac{12000}{2}\right) = 2000$

Hence the surplus above the average
= deficit below the average = 2000

Alternatively : Let the average be 10,000
Then,

10,000 – 8,000 = 2,000
10,000 – 5,000 = 5,000
10,000 – 7,000 = 3,000 and 11,000 – 10,000 = 1,000
10,000 – 9,000 = 1,000 Surplus = 1,000
Deficit → 11000

∴ Net difference = Surplus – deficit
$= 1{,}000 - 11{,}000 = -10{,}000$

∴ Average variation $=\frac{-10{,}000}{5}=-2000$

Hence, the actual average = assumed average + average variation
$= 10{,}000 - 2{,}000 = 8{,}000$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 11 *The average of 6 numbers 13, 17, 25, 11, 26, 10 is :*

(a) 20 *(b) 17* *(c) 15* *(d) 25*

SOLUTION Let the average be 20.

then
$20 - 13 = 7$
$20 - 17 = 3$
$20 - 11 = 9$
$20 - 10 = 10$
$\overline{29}$ (deficit)

and

$20 - 25 = 5$
$20 - 26 = 6$
$\overline{11}$
(Surplus)

The net difference (surplus − deficit) = (11 − 29) = − 18

Therefore average variation = $\frac{-18}{6} = -3$

Hence, the actual average = 20 + (−3) = 17

NOTE This method is very helpful in Data Interpretation section where there are very large values are to be calculated and most of the time we need just the lumpsum value.

7. Weighted average : When the average of groups or sets, instead of individuals, having different number of elements is being calculated, then it is called the weighted average. Since in this case the number of elements is different for the different sets thus they carry different weightage. If the number of elements in n different groups be $K_1, K_2, K_3, K_4, \ldots, K_n$ and the averages of the respective groups be $A_1, A_2, A_3, A_4 \ldots A_n$ then the

$$\text{weighted average} = \frac{K_1A_1 + K_2A_2 + K_3A_3 + \ldots K_nA_n}{K_1 + K_2 + K_3 + \ldots K_n}$$

EXAMPLE 12 *The average salary of 12 employees of STAR plus is Rs. 18,000 per month and 15 employees of NDTV is Rs. 16,000 per month. The average salary of all the 27 employees is :*

(a) Rs. 17,000 *(b) Rs. 16,500*
(c) Rs. 16,888.88 *(d) none of these*

SOLUTION Required average salary =

$$\frac{12 \times 18{,}000 + 15 \times 16{,}000}{12 + 15} = \frac{4{,}56{,}000}{27} = \text{Rs. } 16{,}888.88$$

EXAMPLE 13 *The number of students at i4 IIM in morning batch, evening batch and weekends batch is 30, 40 and 60 respectively and their respective averages ages (in years) are 22, 21 and 25, then the average age of all the students (combined) is :*

(a) $22\frac{1}{13}$ *years* *(b)* $23\frac{1}{13}$ *years*
(c) 24.5 years *(d) none of these*

SOLUTION $\frac{30 \times 22 + 40 \times 21 + 60 \times 25}{130} = \frac{3000}{130} = 23\frac{1}{13}$ years

8. Problems based on ages :

(i) If the average age of 'n' members of a family is x years then K years back, the average age of the family is $(x - K)$ years, provided that no any person is expired or born in K years period.

(ii) If the present age of 'n' members of a family is x years then K years later the average age of the same family will be $(x + K)$ years.

EXAMPLE 14 *The average age of 7 members of Patel's family is 25 years. The average age of the same family 3 years ago was :*

(a) 21 years *(b) 22 years*
(c) 25 years *(d) none of these*

SOLUTION Present average age of family = 25 years

3 years ago average age of family = 25 − 3 = 22 years

EXAMPLE 15 *The average age of all the 16 professors of Lucknow University is 52 years. Four years later the average age of all the 16 professors will be, if there is no any retirement or recruitment :*

(a) 68 *(b) 64*
(c) 56 *(d) none of these*

SOLUTION Present average age = 52 years

4 years later the average age = 52 + 4 = 56 years

EXAMPLE 16 *6 months ago the present age of the student of class 10th was 14 years. 6 months hence, the age of the same students will be :*

(a) 15 years *(b)* $15\frac{1}{2}$ *years*
(c) 20 years *(d) none of these*

SOLUTION Since the time difference between two dates is 1 year, hence the average age will be increased by 1 year.

Thus the average age of the class 6 months hence will be 15 years.

EXAMPLE 17 *The average age of Priyambada's family consisting of 5 members 3 years ago was 35 years. One year ago a new baby was born in this family. Three years hence the average age of the family will be :*

(a) 36 years *(b)* $34\frac{5}{6}$ *years*
(c) $35\frac{4}{5}$ *years* *(d) none of these*

SOLUTION 3 years ago total age of 5 members

= 5 × 35 = 175 years

At the time of birth of new baby the total age of family

= 175 + (2 × 5)

= 185 years

The present age of family = 185 + (1 × 6) = 191 years

3 years hence, the average age of family

$$= \frac{191 + (3 \times 6)}{6} = 34\frac{5}{6} \text{ years}$$

EXAMPLE 18 *10 years ago the average age of all the 25 teachers of the Girls college was 45 years. 4 years ago, the principal has retired from her post at the age of 60 year. So after one year a new principal whose age was 54 years recruited from outside. The present average age of all the teachers is, if principal is also considered as a teacher :*

(a) $54\frac{18}{25}$ *years* *(b)* $55\frac{17}{25}$ *years*
(c) $49\frac{1}{2}$ *years* *(d) none of these*

SOLUTION 10 years ago average age of 25 teachers = 45 years

4 years ago (just before the reteriment of principal) average age of 25 teachers = 45 + 6 = 51 years

and the same time total age of 25 teachers = 51 × 25

= 1275 years

Scanned by CamScanner

yoursmahboob.wordpress.com

and the total age of remaining 24 teachers when just the principal has retired

$= 1275 - 60 = 1215$ years

1 year later (i.e., 3 years ago from present) total age of 24 teachers (just before the recruitment of new principal)

$= 1215 + (1 \times 24) = 1239$ years

and the total age of 25 teachers including new principal just after the recruitment

$= 1239 + 54 = 1293$ years

Thus the present age of all the 25 teachers

$= 1293 + (3 \times 25) = 1368$ years

Hence, the present average age of the 25 teachers

$= \frac{1368}{25} = 54\frac{18}{25}$ years

Alternatively : 10 years ago, the average age of 25 teachers $= 45$ years

Let us assume that the principal has not retired from her post then the present average age of all the 25 teachers,

$= 45 + 10 = 55$ years

Thus the total age of all the 25 teachers

$= 55 \times 25 = 1375$ years

Now assume that the new principal has replaced the old principal 4 years ago instead of 3 years ago, when the age of new principal would have been 53 years. Thus the age of new principal was 7 years less than the age of old principal, which results in the reduction of total age of the group of 25 teachers by 7 years.

Thus the actual total age of the 25 teachers (presently)

$= 1375 - 7 = 1368$ years

Hence, the present average age of the 25 teachers

$= \frac{1368}{25} = 54\frac{18}{25}$ years

EXAMPLE 19 *The ratio of the ages of the father and the daughter at present is 3 : 1. Four years ago the ratio was 4 : 1. The average age of the father and daughter 2 years hence will be :*

(a) 24 (b) 26 (c) 25 (d) 36

SOLUTION Let the present ages of father be $3x$ and daughter be x.

So the 4 years ago father's age and daughter's age was $(3x - 4)$ and $(x - 4)$

Therefore $\left(\frac{3x-4}{x-4}\right) = \frac{4}{1}$

$\Rightarrow \quad x = 12$ years and $3x = 36$ years

Hence, the present average age of father and daughter $= 24$ years and the average age 2 years hence will be 26 years.

9. Problems based on income/salary

Income = Expenditure + Savings

EXAMPLE 20 *The average salary of Rajesh, Bahadur and Amir is Rs. 8000 per month. The average expenditure of the Rajesh, Bahadur and Amir per month is Rs. 5000. The average savings of all the 3 persons per month is :*

(a) Rs. 3000 (b) Rs. 5000
(c) Rs. 2500 (d) Rs. 9000

SOLUTION Average saving

= Average Income − Average Expenditure

$= 8000 - 5000 = 3000$

EXAMPLE 21 *The average salary of A, B and C is Rs. 10,000 and average expenditure of A is Rs. 6000 then the average savings of B and C is :*

(a) Rs. 5500 (b) Rs. 4500
(c) Rs. 4000 (d) can't be determined

SOLUTION Total income = Total Expenditure + Total savings

We can not find the average savings of B and C, since data is insufficient.

EXAMPLE 22 *The average salary of A, B is Rs. 6000 and that of C, D and E is Rs. 8000. The average salary of all the 5 people is :*

(a) Rs. 7200 (b) Rs. 7000
(c) Rs. 7500 (d) can't be determined

SOLUTION Required average salary $= \frac{6000 \times 2 + 8000 \times 3}{(2+3)} = \frac{36000}{5} = \text{Rs. } 7200$

EXAMPLE 23 *The average salary of all the 60 employees in an office is Rs. 12,000 per month. If the number of executives is twice the number of non executive employees, then the average salary of all the non executive employees is :*

(a) Rs. 9000 (b) Rs. 8000
(c) Rs. 6000 (d) can't be determined

SOLUTION $\frac{\text{No. of executives}}{\text{No. of non-executives}} = \frac{2}{1}$

Therefore number of executives $= 40$

and number of non-executive employees $= 20$

Now, go through the options

Total salary $= 40 \times$ salary of executive $+ 20 \times$ salary of non-executive

$60 \times 12000 = 40 \times k + 20 \times l$, here k, l are unknowns

So we can't determine the required average salary.

EXAMPLE 24 *In the above problem, if the average salary of non-executives be $\frac{2}{5}$th of the average salary of executives, then the average salary of non-executive employees is :*

(a) Rs. 9000 (b) Rs. 8000
(c) Rs. 6000 (d) data insufficient

SOLUTION By options : $60 \times 12000 = 20 \times 6000 + 40 \times 15000$

Hence option (c) is correct.

Alternatively : $60 \times 12000 = 20 \times x + 40 \times \frac{5}{2}x$

$\Rightarrow \quad x = 6000$

10. Problems based on speed, time and distance :

Case 1: When the distance travelled in different time slots or parts is same *i.e.*, if a person or vehicle moves x km at a speed of u km/hr and further he goes or comes back the same distance x km at a speed of v km/hr. Then the average speed $= \frac{2uv}{(u+v)}$.

If there are 3 parts of distance x km travelled with 3 different speeds *i.e.*, if a person goes first x km @ speed of u km/hr and next x km @ v km/hr and the last x km @ w km/hr. Then the average speed $= \frac{3uvw}{(uv + vw + wu)}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

NOTE In this type of questions the average speed is independent of the distance travelled.

General Formula : Average speed $= \dfrac{\text{Total distance}}{\text{Total time}}$

The above two formulae are derived with the help of the general formula of average speed.

Proportion Method : If the half of the distance is covered at u km/hr and the rest half of the journey is covered at v km/hr then the average speed can be found as follows :

Step 1. Divide the difference of u and v in the ratio of $u : v$ (where $u < v$)

Step 2. $u + \dfrac{(u \sim v) \times u}{(u + v)}$

or $v - \dfrac{(u \sim v)\, v}{u + v}$

Case 2. When the distances travelled at different speeds are different then we calculate the average speed with the help of general formula of average speed. *e.g.*, A person first goes x_1 km at the speed of u km/hr and x_2 km at the speed of v km/hr and x_3 km at the speed of w km/hr and so on, then the

$$\text{Average speed} = \frac{\text{Total distance}}{\text{Total time}} = \frac{x_1 + x_2 + x_3 + \ldots}{t_1 + t_2 + t_3 + \ldots} = \frac{x_1 + x_2 + x_3 + \ldots}{\frac{x_1}{u} + \frac{x_2}{v} + \frac{x_3}{w} + \ldots}$$

EXAMPLE 25 *Einstien goes from Ahmedabad to Lucknow at the speed of 40 km/hr and returned at the speed of 60 km/hr. The average speed of Einstien during the whole journey is :*

(a) 48 km/hr *(b) 24 km/hr*
(c) 50 km/hr *(d) none of these*

SOLUTION $\dfrac{2 \times 40 \times 60}{(40 + 60)} = \dfrac{4800}{100} = 48$ km/hr

Alternatively: $40 \xleftarrow{(20)} 60$
$\downarrow 2 \qquad \downarrow 3$

So the average speed $= 40 + \dfrac{2}{5}(20) = 48$ km/hr

or Average Speed $= 60 - \dfrac{3}{5}(20) = 48$ km/hr

EXAMPLE 26 *Sri Krishna took the chariot and started his journey from Mathura to Gokul by his chariot at the speed of 40 km/hr and then, the same distance he travelled on his foot at the speed of 10 km/hr from Gokul to Brindaban. Then he returned from Brindaban to Mathura via Gokul at the speed of 24 km/hr riding on the horse. The average speed of the whole trip is :*

(a) 20 km/hr *(b) 25 km/hr*
(c) 19.2 km/hr *(d) 18.5 km/hr*

SOLUTION Since the distance from Mathura to Gokul is same as that of Gokul to Brindaban.

So the average speed from Mathura to Brindaban

$$= \frac{2 \times 40 \times 10}{(40 + 10)} = 16 \text{ km/hr}$$

Again since he returned on the same path, so the distance from Mathura to Brindaban is same in both the directions. Thus the required average speed $= \dfrac{2 \times 16 \times 24}{(16 + 24)} = 19.2$ km/hr

EXAMPLE 27 *Anoop travels first $\frac{1}{3}$rd of the total distance at the speed of 10 km/hr and the next $\frac{1}{3}$rd distance at the speed of 20 km/hr and the last $\frac{1}{3}$rd distance at the speed of 60 km/hr. The average speed of Anoop is :*

(a) 15 km/hr *(b) 18 km/hr*
(c) 25 km/hr *(d) 30 km/hr*

SOLUTION Since all the three distances are same, hence the average speed

$$= \frac{3 \times 10 \times 20 \times 60}{(200 + 1200 + 600)} \qquad \left(= \frac{3uvw}{uv + vw + wu}\right)$$

$$= \frac{36000}{2000} = 18 \text{ km/hr}$$

EXAMPLE 28 *Columbus started his journey from Lucknow to Kolkata, which is 200 km, at the speed of 40 km/hr then he went to Bangalore which is 300 km, at the speed of 20 km/hr. Further he went to Ahmedabad which is 500 km, at the speed of 10 km/hr. The average speed of Columbus is :*

(a) $14\frac{2}{7}$ *km/hr* *(b)* $14\frac{5}{7}$ *km/hr*
(c) 15.6 km/hr *(d) none of these*

SOLUTION Average speed $= \dfrac{\text{Total distance}}{\text{Total time}}$

$$= \frac{(200 + 300 + 500)}{\left(\frac{200}{40} + \frac{300}{20} + \frac{500}{10}\right)} = \frac{1000}{70} = \frac{100}{7} = 14\frac{2}{7} \text{ km/hr}$$

$= 14.2857$ km/hr

11. Some Important Concepts

1. $a + b = k$ and $b + c = l$ and $a + b + c = m$
then $[(a + b) + (b + c)] - (a + b + c) = (k + l) - m$
or $b = k + l - m$

2. $a + b = k$, $d + e = l$ and $a + b + c + d + e = m$
then $c = (a + b + c + d + e) - [(a + b) + (d + e)]$
$= m - [k + l]$

EXAMPLE 29 *The average weight of all the 11 players of Indian cricket team is 50 kg. If the average of first six lightest weight players is 49 kg and that of the six heaviest players is 52 kg. The average weight of the player which lies in the sixth position in the list of players when all the 11 players are arranged in the order of increasing or decreasing weights :*

(a) 56 kg *(b) 52 kg*
(c) 51 kg *(d) none of these*

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION Let $A, B, C, D, E, F, G, H, I, J, K$ be the 11 players in the order of increasing weight then,

$$A + B + C + D + E + F = 49 \times 6 = 294$$
$$F + G + H + I + J + K = 52 \times 6 = 312$$
and $$A + B + C + D + E + F + G + H + I + J + K = 50 \times 11 = 550$$
Therefore $F = (A + B + C + D + E + F) + (F + G + H + I + G + K) - (A + B + C + D + \ldots J + K)$
$$= 294 + 312 - 550 = 56$$

Hence the average weight of $F = 56$ kg.

EXAMPLE 30 *The average presence of students in a class on Monday, Tuesday and Wednesday is 30 and on the Wednesday, Thursday, Friday and Saturday is 28 then number of students who attended the class on Wednesday is, if the average number of students on all the six days is 27 :*

(a) 24 (b) 25 (c) 20 (d) 40

SOLUTION Since $W = (M + T + W) + (W + Th + F + S) - (M + T + W + Th + F + S)$
$$= (30 \times 3) + (28 \times 4) - (27 \times 6)$$
$$= 202 - 162 = 40$$

EXAMPLE 31 *The average age of A, B, C, D and E is 40 years. The average age of A and B is 35 years and the average age of C and D is 42 years. The average age of E is :*

(a) 46 (b) 48
(c) 32 (d) none of these

SOLUTION $A + B + C + D + E = 40 \times 5 = 200$
$$A + B = 35 \times 2 = 70$$
$$C + D = 42 \times 2 = 84$$
Therefore $E = (A + B + C + D + E) - [(A + B) + (C + D)]$
$$= 200 - (70 + 84) = 46$$

Thus the average age of $E = 46$ years.

EXAMPLE 32 *The average temperature on Monday, Tuesday and Wednesday is 38°C. The average temperature on Tuesday, Wednesday and Thursday is 43°C. If the average temperature on Monday and Thursday is 18.5°C. The average temperature on Monday is :*

(a) 11°C (b) 21°C (c) 35°C (d) 27°C

SOLUTION $(M + T + W) = 38 \times 3 = 114$ ...(i)
$(T + W + Th) = 43 \times 3 = 129$ ...(ii)
Therefore $Th - M = 15$ [(ii) – (i)]
and $Th + M = 37$

Thus the temperature on Monday is 11°C and on Thursday is 26°C.

12. Average of Some Important Series of Numbers :

(i) Average of first 'n' natural numbers $= \frac{n+1}{2}$

(ii) Average of first 'n' even numbers $= (n + 1)$

(iii) Average of first 'n' odd numbers $= n$

(iv) If there are $(p + q)$ elements in a set or group but the average of p elements is r and the average of q elements is s, then the average of all the elements of the set (or group) is $\frac{(pr + sq)}{(p + q)}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. The average weight of a class of 20 students is 45 kgs. A new student whose weight is 40 kgs replaces an old student of this class. Hence, the average weight of the whole class decreases by 1 kg. The weight of the replaced student is :
(a) 55 kgs (b) 50 kgs
(c) 60 kgs (d) none of these

2. The average length of first 3 fingers is 3 inches and the average length of the other 2 fingers *i. e.*, thumb and the index finger is 2.8 inches. If the length of the index fingers is 3 inches then the length of the thumb is :
(a) 2 inches (b) 2.6 inches
(c) 3 inches (d) none of these

3. Three types of rice whose rates are Rs. 38, Rs. 43 and Rs. 49 per kg are blended together to make a 15 kg of new blend of rice in which there are 8 kgs, 4 kgs 3 kgs of the respective types of rice. The average price of the new blend of rice is :
(a) Rs. 41.53 (b) Rs. 43
(c) Rs. 40 (d) Rs. 43.3

4. Pankaj went to the post-office at the speed of 60 km/hr while returning for his home he covered the half of the distance at the speed of 10 km/hr, but suddenly he realized that he was getting late so he increased the speed and reached the home by covering rest half of the distance at the speed of 30 km/hr. The average speed of the Pankaj in the whole length of journey is :
(a) 5.67 km/hr (b) 24 km/hr
(c) 22.88 km/hr (d) 5.45 km/hr

5. 123 typists typed 984 papers in 1/15 hour. The number of papers typed per minute by an average typist is :
(a) 1 (b) 2
(c) 3 (d) 5

6. The cost of the Red, Green and Blue colours per kg is Rs. 20, Rs. 15 and Rs. 18 respectively. Rang Mahal is a renowned building in which these three colours are being used in the ratio of 3 : 2 : 4. The average cost of all the three colours used per kg is :
(a) 18 (b) 20
(c) 17.66 (d) can't be determined

7. Rajeev earns 3/2 times in January, April, July and October than his average earning of Rs. 600 per month in the rest of the months. So his savings in the January, April, July and October goes to 5/4 times that of the rest months saving of Rs. 400 per month in the year. The average expenditure of per month is :
(a) Rs. 266.66 (b) Rs. 250
(c) Rs. 233.33 (d) Rs. 433.33

8. The average of 3 prime numbers lying between 47 and 74 is 191/3. The greatest possible difference between any two out of the 3 prime numbers is :
(a) 12 (b) 14
(c) 18 (d) can't be determined

9. The average of 9 numbers is 11. If each of these 9 numbers is multiplied by 5 and then 5 is added to each of these resultant numbers, then the new average is :
(a) 20 (b) 30
(c) 60 (d) 50

10. The average score of Dhoni after 48 innings is 48 and in the 49th innings Dhoni scores 97 runs. In the 50th innings the minimum number of runs required to increase his average score by 2 than it was before the 50th innings :
(a) 99 (b) 149
(c) 151 (d) can't be determined

11. The average age of Sachin and Ganguli is 35 years. If Kaif replaces Sachin, the average age becomes 32 years and if Kaif replaces Ganguli, then the average age becomes 38 years. If the average age of Dhoni and Irfan be half of the average age of Sachin, Ganguli and Kaif, then the average age of all the five people is :
(a) 28 years (b) 32 years
(c) 25 years (d) none of these

12. Out of these five people (in question no. 11) whose age is the greatest?
(a) Sachin (b) Ganguli
(c) Kaif (d) can't be determined

13. In a village the average age of n people is 42 years. But after the verification it was found that the age of a person had been considered 20 years less than the actual age, so the new average, after the correction, increased by 1. The value of n is :
(a) 21 (b) 20
(c) 22 (d) none of these

14. The average rainfall in the months of January and February is 6 cm and in the months of March to June is 5 cm and July to October is 10 cm and in the November and December, it is 6 cm. The average rainfall for the whole year is :
(a) 7 (b) 5.5
(c) 7.5 (d) none of these

15. On an average 300 people watch the movie in Sahu Cinema hall on Monday, Tuesday and Wednesday and the average number of visitors on Thursday and Friday is 250. If the average number of visitors per day in the week be 400, then the average number of people who watch the movie in weekends (*i. e.*, on Saturday and Sunday) is :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 500 (b) 600
(c) 700 (d) none of these

16. The average weight of 11 players of Indian cricket team is increased by 1 kg, when one player of the team weighing 55 kg replaced by a new player. The weight of the new player is :
(a) 55 kg (b) 64 kg
(c) 66 kg (d) none of these

17. The average age of a family of 6 members 4 year ago was 25 years. Mean while a child was born in this family and still the average age of the whole family is same today. The present age of the child is :
(a) 2 years (b) $1\frac{1}{2}$ years
(c) 1 year (d) data insufficient

18. Amitabh's average expenditure for the January to June is Rs. 4200 and he spends Rs. 1200 in January and Rs 1500 in July. The average expenditure for the months of February to July is :
(a) Rs. 4250 (b) Rs. 4520
(c) Rs. 4060 (d) none of these

19. The average of a, 11, 23, 17 is 15 and the average of a, b, 12, 25 is 16. The value of $\frac{a}{b}$ is :
(a) 1/3 (b) 1/2
(c) 2/3 (d) 3/4

20. The average salary is being paid to all its employees by the Biotech corporation is Rs. 15,500. The average salary of the senior employees is Rs. 18000 per month and the average salary of the junior employees is Rs. 12,000 per month. If there are only two levels of employees viz junior and senior level, then what fraction of the total employees is the junior level employees are :
(a) $\frac{7}{10}$ (b) $\frac{5}{12}$
(c) 5/10 (d) none of these

21. The average of any 5 consecutive odd numbers a, b, c, d, e is :
(a) $\frac{(abcde)}{5}$ (b) $\frac{bd}{3}$
(c) $\left(\frac{a+c+e}{5}\right)$ (d) none of these

22. The average age of 30 students of a class is 30 years. When the average age of class teacher is also included, the average age of the whole class increases by 1 year. The age of the class teacher is :
(a) 31 years (b) 60 years
(c) 61 years (d) none of these

23. There were five sections in MAT paper. The average score of Pooja in first 3 sections was 83 and the average in the last 3 sections was 97 and the average of all the sections (i. e., whole paper) was 92, then her score in the third section was :
(a) 85 (b) 92
(c) 88 (d) none of these

24. The average age of 18 pupils of Dronacharya was 25 years. If the age of Dronacharya was also included, the average age of 19 people becomes 26 years. The average age of the Dronacharya at that time was :
(a) 33 (b) 44
(c) 50 (d) 51

25. The average of 7 consecutive odd numbers if the smallest of those numbers is denoted by k :
(a) $k+4$ (b) $k+7$
(c) $k+6$ (d) $7k$

26. If the average marks of $\frac{1}{4}$th class is 85% and that of $\frac{1}{3}$rd class is 70% and the average marks of the rest class is 56%, then the average of the whole class is (for the given subjects) :
(a) 67.916% (b) 72.33%
(c) 69.165% (d) can't be determined

27. The average length of any four fingers of my left hand is 600 mm. Then the average length of all the five fingers of my left hand is :
(a) 800 mm (b) 750 mm
(c) 480 mm (d) can't be determined

28. The average of $4\frac{3}{5}, 2\frac{2}{3}, 6\frac{8}{9}, 7\frac{7}{15}, 3\frac{5}{9}$ is :
(a) $5\frac{3}{225}$ (b) $5\frac{8}{225}$
(c) $6\frac{3}{45}$ (d) $25\frac{8}{45}$

29. The average of 1000.0001, 100.001, 10.01, 1.1 is :
(a) 277.777 (b) 322.222
(c) 11.11 (d) 233.333

30. The average of 7 consecutive numbers which are positive integers is 10. The average of lowest and highest such numbers is :
(a) 7 (b) 10
(c) 15 (d) data insufficient

31. The average of first 100 natural number is :
(a) 100 (b) 50
(c) 50.50 (d) 55

32. The average of first 50 odd natural numbers is :
(a) 50 (b) 55
(c) 51 (d) 101

33. The average of first 99 even numbers is :
(a) 9999 (b) 100
(c) 9801 (d) 9009

34. The average of a, b and c is 79 and the average of a and c is also 79. Then the value of b is :
(a) 0 (b) 79
(c) −79 (d) none of these

35. The average value of property of Mittal, Ambani and Singhania is Rs. 11111 crore. The property of Singhania is as less as the property of Mittal is greater than the average property of both the Singhania and Mittal. The value of property of Ambani is :
(a) Rs. 111 crore (b) Rs. 11111 crore
(c) Rs. 3703.7 crore (d) can't be determined

36. I went to Delhi @ speed of 200 km/hr but suddenly I returned to the same place @ speed of 600 km/hr. What is my average speed :
(a) 300 km/hr (b) 400 km/hr
(c) 366.66 km/hr (d) none of these

37. The average of A and B is 400 and the average of C and D is 600 the average of A, B, C and D is :
(a) 500 (b) 450
(c) 525 (d) 625

Scanned by CamScanner

yourshanbobb.wordpress.com

38. The average weight of liquid in 100 bottles is 500 gm. The total weight of all the bottles is 20 kg. The average weight of a bottle with liquid is :
(a) 0.65 kg (b) 0.7 kg
(c) 70 ml (d) none of these

39. The average score of Sehwag in 10 innings was 77 runs. In the 11^{th} innings he had scored zero runs. The overall average score of Sehwag in all the 11 innings was :
(a) 77 (b) 7.7
(c) 11 (d) none of these

40. The average age of 3 children of Arihant Singh is 12 years and their ratio of ages is 3 : 4 : 5. The average age of the youngest and eldest child is if he had only 3 children :
(a) 12 (b) 21
(c) 8 (d) 9

41. The average income of all the Infosys employees is Rs. 20,000 per month. Recently the company announced the increment of Rs. 2,000 per month for all the employees. The new average of all the employees is :
(a) Rs. 22,000 (b) Rs. 40,000
(c) Rs. 22,00 (d) data insufficient

42. The average age of 10 students in a class is 20 years, if a new student is also included, then the new average age of all the students increases by 1 year. The age of the new student is :
(a) 21 years (b) 30 years
(c) 31 years (d) none of these

43. The average weight of 20, four wheelers is 180 kg. If an old car is removed from this group of four wheelers, the new average weight decreases by 2 kg. The weight of the removed car is :
(a) 220 (b) 218
(c) 182 (d) none of these

44. The average price of 3 diamonds of same weights is Rs. 5 crore, where the average price of the two costliest diamonds is double the price of the cheapest diamond. The price of the cheapest diamond is :
(a) 3 crore (b) 5 crore
(c) 1.66 crore (d) can't be determined

45. In the previous question, the price of the costliest diamond is :
(a) 5 crore (b) 6 crore
(c) 8 crore (d) can't be determined

46. Praveen gets 40 marks out of 50 in Computer Science, 70 out of 100 in Manufacturing science and 142 out of 150 in proffessional communication. The average marks of Praveen (in percent) in all the three subjects is :
(a) 84% (b) 76%
(c) 71% (d) 60%

47. The average of all the prime and composite numbers upto 100 is :
(a) 51 (b) 49.50
(c) 50.50 (d) 55

48. The average of all the perfect squares upto 100 is :
(a) 38.5 (b) 1000
(c) 100 (d) 385

49. The average of all the non-negative integers upto 99 is :
(a) 50.49 (b) 49.50
(c) 50.50 (d) 99

50. The average of 7, 14, 21, 28 ... 77 is :
(a) 7 (b) 11
(c) 42 (d) 66

51. The average weight of A, B, C and D is 40 kg. A new person E is also included in the group, then the average weight of the group is increased by 1 kg. Again a new person F replaces A, then the new average of 5 persons becomes 42. The average weight of B, C, D, F is :
(a) 42 (b) 41.25
(c) 42.5 (d) none of these

52. The average of 3 consecutive natural numbers (which are in increasing order) is k. If two more consecutive number, just next the first set of numbers, is added, then the new average becomes :
(a) $k + 2$ (b) $k + 1$
(c) $\frac{2k+1}{2}$ (d) $2k - 1$

53. The average of any 5 consecutive odd natural numbers is k. If two more such numbers, just next to the previous 5 numbers are added, the new average becomes :
(a) $\frac{2}{7}(k + 1)$ (b) $2k - 3$
(c) $2k + 1$ (d) $k + 2$

54. The average weight of the 5 officers of a regiment is 42 kg. If a senior officer was replaced by a new officer and thus the average increased by 500 gm, the weight of the new officer is :
(a) 44.5 kg (b) 45 kg
(c) 42.5 kg (d) none of these

55. The average age of 6 servants in my farm house is 28 years. A new and young servant replaces an old servant, then the new average reduces by 1 year, the age of the new servant is :
(a) 26 years (b) 22 years
(c) 35 years (d) can't be determined

56. In the above question (no. 55) if the age of the replaced servant was 31 years, then the age of the new servant is :
(a) 25 years (b) 35 years
(c) 24 years (d) none of these

57. The average income of A, B and C is Rs. 12,000 per month and the average income of B, C and D is Rs. 15,000 per month. If the average salary of D be twice that of A, then the average salary of B and C is (in Rs.) :
(a) 8,000 (b) 18,000
(c) 13,500 (d) 9,000

58. The average price of 80 computers in an electronic shop is Rs. 30,000. If the highest and lowest price computers are sold out then the average price of the remaining 78 computers is Rs. 29,500. The cost of the highest price computer is Rs. 80,000. The cost of lowest price computer is :
(a) Rs. 19,000 (b) Rs. 20,000
(c) Rs. 29,000 (d) can't be determined

59. A has 50 coins of 10 paise denominations. While B has 10 coins of 50 paise denominations. C has 20 coins of 25 paise denominations while D has 25 coins of 20 paise denominations. The average number of paise per person is :
(a) 450 paise (b) 500 paise
(c) 600 paise (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

60. A travel agency has three types of vehicles viz. four seater, autorickshaw, 10 seater maxi cab and 20 seater minibus. The rate of each passanger (irrespective of its age or weight or seniority) for the auto rickshaw is Rs. 12 and for the maxicab is Rs. 15 and for the minibus is Rs. 8 for the one round. The average occupancy of the seats is 100%, 80% and 75% respectively. If he has only one vehicle of each kind, then the average earning for one round of each vehicle is :

(a) Rs. 96 (b) Rs. 90
(c) Rs. 86 (d) Rs. 70

LEVEL 2

1. A train normally covers a certain distance at a speed of 60 km/hr. However, if it were to halt for a fixed time interval in each hour its average speed reduced to 50 km/hr. What is the time interval for which the train halt in each hour?

(a) 10 minutes (b) 20 minutes
(c) 6 minutes (d) 12 minutes

2. If p, q, r be three positive numbers such that $p > q > r$ when the smallest number is added to the difference of the rest two numbers, then the average of the resultant number and the original numbers except to the smallest number is 21 more than the average of all the three original numbers. The value of $(p - q)$ is :

(a) 7 (b) 14
(c) 63 (d) 42

3. Progressive express left for New Delhi, increasing its speed in each hour. It started its journey from Lucknow, but after four hours of its journey it met with accident. Its speed in the fourth hour was $\frac{7}{5}$ times that of the third hour and the speed in the third hour was $\frac{10}{7}$ times that of the second hour and in the second hour it was $\frac{7}{5}$ times that of the first hour. If it would have been travelled with the half of the speed that of the third hour, then it would have gone 160 km less in the same time (i. e., in four hours). The average speed of the train during the journey of 4 hours was :

(a) 50 km/hr (b) 90 km/hr
(c) 80 km/hr (d) can't be determined

4. In a Mock CAT 123 students appeared and the average score obtained was 120. But later it was found that the top three students were repeaters, so their score has been eliminated and then the new average score was found to be decreased by 1.5. Also, it is known that all the students obtained the marks in integers and the scores of the toppers were distinct. If the second highest topper has scored more than 185 marks, then the highest possible score of the third highest topper is :

(a) 166 (b) 167
(c) 168 (d) 170

5. The average age of all the 100 employees in an office is 29 years, where $\frac{2}{5}$ employees are ladies and the ratio of average age of men to women is 5 : 7. The average age of female employees is :

(a) 18 years (b) 35 years
(c) 25 years (d) none of these

6. There are two houses in Parliament. One is Lok Sabha and the other one is Rajya Sabha and the member of Parliaments (MPs) in both the houses is 300 and 200 respectively. The average age of the members of Lok Sabha and Rajya Sabha is 40 years and 50 years respectively. A member of the Rajya Sabha when elected for the Lok Sabha also, he left the Rajya Sabha and becomes the member of the Lok Sabha. Thus the average age of both the houses increases. Which one of the following statements is true?

(a) The age of this member is greater than 50 years
(b) The age of this member is less than 40 years
(c) The age of this member is greater than 40 but less than 50 years
(d) none of these

Directions for questions 7, 8 and 9 : Eight years ago there were 5 members in the Arthur's family and then the average age of the family was 36 years. Mean while Arthur got married and gave birth to a child. Still the average age of his family is same now.

7. The present age of his wife is :

(a) 25 years (b) 26 years
(c) 32 years (d) data insufficient

8. The age of his wife at the time of his child's birth was. If the difference between the age of her child and herself was 26 years :

(a) 25 years (b) 26 years
(c) 20 years (d) can't be determined

9. The age of Arthur at the time of his marriage was :

(a) 22 years (b) 23 years
(c) 26 years (d) can't be determined

10. Eleven years earlier the average age of a family of 4 members was 28 years. Now the age of the same family with six members is yet the same, even when 2 children were born in this period. If they belong to the same parents and the age of the first child at the time of the birth of the younger child was same as there were total family members just after the birth of the youngest members of this family, then the present age of the youngest member of the family is :

(a) 3 years (b) 5 years
(c) 6 years (d) none of these

11. Mr. Patel walked 6 km to reach the station from his house, then he boarded a train whose average speed was 60 km/hr and thus he reached his destination. In this way he took total of 3 hours. If the average speed of the entire journey was 32 km/hr then the average speed of walking is :

(a) 3 km/hr (b) 4.5 km/hr
(c) 4 km/hr (d) none of these

Directions for question numbers 12 and 13: During the winter session all the women which constitutes $\frac{1}{5}$th strength of the Lok Sabha, left the house (i.e., parliament) due to the

Scanned by CamScanner

yoursmahboob.wordpress.com

rejection of their demand. Actually they were asking for the 50% reservation of seats for the women in the Lok Sabha. Thus the average age of the remaining members of the house (i.e., the Lok Sabha) increases by $\frac{1}{4}$th than it was earlier when all the members (i.e., men and women) were present.

12. The total strength of the Lok Sabha is :
(a) 300 MPs (b) 475 MPs
(c) 526 MPs (d) none of these

13. If the average age of women be 30 years then the average age of male members in the Lok Sabha will be :
(a) 26 (b) 34
(c) 40 (d) none of these

14. An artist in a circus moves along the hexagonal path of each side 20 metres in such a way that for the first 20 metres he goes with a speed of 20 m/s and the next 20 metres with a speed of 10 m/s. Similarly he continues for the rest of the hexagonal path with the same alternating speeds *i. e.*, 20 m/s and 10 m/s. The average speed of the artist per round of the circus is :
(a) 13.33 m/s (b) 23.66 m/s
(c) $39\frac{1}{3}$ m/s (d) 15 m/s

15. The average of 26, 29, n, 35 and 43 lies between 25 and 35. If n is always an integer and greater than the average of the given integers then the value of n is :
(a) $33 < n < 47$ (b) $34 < n < 43$
(c) $33 < n < 42$ (d) none of these

16. The average of 4 distinct prime numbers a, b, c, d is 35, where $a < b < c < d$. a and d are equidistant from 36 and b and c are equidistant from 34 and a, b are equidistant from 30 and c and d are equidistant from 40. The difference between a and d is :
(a) 30 (b) 14
(c) 21 (d) can't be determined

17. There are four numbers whose product is 9261000 and each of these four numbers is formed by 3 distinct prime numbers. The average of all the four numbers is :
(a) 61.75 (b) 67.25
(c) 82.33 (d) data insufficient

18. A number is such that when it is multiplied by 8, it gives another number which is as much above from 270 as the original number (itself) is below 270. The average of the original number and the resultant number is :
(a) 33.75 (b) 190
(c) can't be determined (d) none of these

19. In the above question (no. 18) the average of the original no. and 270 is :
(a) 165 (b) 185
(c) 135 (d) none of these

20. In a particular week the average number of people who visited the Tajmahal is 40. If we exclude the holidays then the average is increased by 16. Further if we exclude also the day on which the maximum number of 112 people visited the Tajmahal, then the average becomes 42. The number of holidays in the week is :
(a) 1 (b) 2
(c) 3 (d) data insufficient

21. The average age of all the 20 students of a class is 24. The minimum age of a student is 18 and the maximum age of another student in the same class is 30 years. When the two students whose average age was 26 years resticated from the class but later on one of the resticated student was readmitted. Now the average age of the class is :
(a) 23.89 years (b) 28.39 years
(c) 25 years (d) can't be determined

22. In a set of prime and composite numbers, the composite numbers are twice the number of prime numbers and the average of all the numbers of the set is 9. If the number of prime numbers and composite numbers are exchanged then the average of the set of numbers is increased by 2. If during the exchange of the numbers the average of the prime numbers and composite numbers individually remained constant, then the ratio of the average of composite numbers to the average of prime numbers (initially) was :
(a) $\frac{7}{13}$ (b) $\frac{13}{7}$
(c) 9/11 (d) none of these

23. The total age of all the guests in the party was 540 years. If a South Indian couple (guests) left the party, then the average of the remaining guests still remained unchanged, where the age of both the husband and wife (the South Indian couple) was same, then the average age of this couple and the total number of guests in the party, respectively, can be :
(a) 18, 27 (b) 20, 27
(c) 15, 38 (d) can't be determined

24. In the command hospital Lucknow the sum of the ages of all the 29 people *i. e.*, physicians, surgeons and nurses is 696. If the age of each physician, each surgeon and each nurse be 1 year, 6 years and 3 years more, then the average age of the whole staff would have been 3 years more. If the number of surgeon is a square root of a two digit number which is also a perfect cube, then the number of nurses in the hospital is :
(a) 12 (b) 15
(c) 16 (d) none of these

25. The average expenditure of Sarvesh for the January to June is Rs. 4200 and he spents Rs. 1200 in January and Rs. 1500 in July. The average expenditure for the months of February to July is :
(a) 4250 (b) 4520
(c) 4060 (d) none of these

26. The average marks of Sameer decreased by 1, when he replaced the subject in which he has scored 40 marks by the other two subjects in which he has just scored 23 and 25 marks respectively. later he has also included 57 marks of Computer Science, then the average marks increased by 2. How many subjects were there initially?
(a) 6 (b) 12
(c) 15 (d) can't be determined

27. In a combined family the average age of 4 males and 7 females is 42 and 20 years respectively. If two persons whose average age is 13 years have left the family and other three

Scanned by CamScanner

yoursmahboob.wordpress.com

people joined the family whose respective ages are 11, 15 and 28 years, then the average age of the new family is increased by :

(a) 4 years (b) 1 year
(c) 3 years (d) none of these

28. A teacher gave sum to his class to find the average of n numbers viz. 1, 2, 3, 4, 5, 6 ... etc. But when the teacher checked the solution, he has found that during the calculation a student just missed a number for the addition thus his average of the n numbers was 15. The value of n is :

(a) 30 (b) 26
(c) 31 (d) not unique

29. The average earning of a group of persons is Rs. 50 per day. The difference between the highest earning and lowest earning of any two persons of the group is Rs. 45. If these two people are excluded the average earning of the group decreases by Re. 1. If the minimum earning of the person in the group lies between 42 and 47 and the number of persons initially in the group was equal to a prime number, with both its digits prime. The number of persons in the group initially was :

(a) 29 (b) 53
(c) 31 (d) none of these

30. There are three categories of jobs A, B and C. The average salary of the students who got the job of A and B categories is 26 lakh per annum. The average salary of the students who got the job of B and C category is 44 lakh per annum and the average salary of those students who got the job of A and C categories is 34 lakh per annum. The most appropriate (or closest) range of average salary of all the three categories (if it is known that each student gets only one category of jobs *i. e.*, A, B and C) :

(a) lies between 30 and 44 (b) lies between 28 and 34
(c) lies between 34 and 43 (d) lies between 29 and 48

31. Out of the five integral numbers C is the average of A and D. B is greater than C and less than D. Also B is the average of A and E. The middle most number in the sequence is :

(a) A (b) B
(c) C (d) D

32. The average age of Donald, his wife and their two children is 23 years. His wife is just 4 year younger than Donald himself and his wife was 24 years old when his daughter was born. He was 32 years old when his son was born. The average age of Donald and his daughter is :

(a) 25 years (b) 22.5 years
(c) 26 years (d) can't be determined

33. There are only five people in the Aman Verma's family. Aman, his wife, a son and two daughters. The younger daughter's age is $\frac{4}{5}$th of the elder daughter's age. The age of eldest daughter is $\frac{3}{8}$ times that of her father Aman and the age of the son is $\frac{1}{5}$th that of his father Aman. 4 years ago the age of her wife was 8 times that of his son and now the sum of the ages of the younger daughter and wife is same as the sum of the ages of Aman and his son. The average age of the family is :

(a) 22.22 years (b) 25.4 years
(c) 21.2 years (d) none of these

34. The average weight of a political party is decreased by 1, when some new politicians joined the party, whose strength is $\frac{1}{4}$th of the existing (or old) politicians and the total weight of the new politicians is 209 kgs. What is the new average weight of all the politicians if it is known that the number of politicians always must be greater than 50 but less than 100 :

(a) 15 kgs (b) 16 kgs
(c) 18 kgs (d) 19 kgs

35. Ravi went to Kanpur from Lucknow by his four wheeler. During the journey he had to use the spare wheel (i.e. stepney). Thus he finished his 160 km journey. The average distance covered by the wheels of his car is :

(a) 40 km (b) 120 km
(c) 128 km (d) 48 km

36. There are 6 consecutive odd numbers in increasing order. The difference between the average of the squares of the first 4 numbers and the last four numbers is 64. If the sum of the squares of the first and the last element (*i. e.*, odd numbers) is 178, then the average of all the six numbers is :

(a) 7 (b) 8
(c) 9 (d) 10

37. The average age of board of directors of a company, having 10 directors was 48 years. Coincidentally when a director aged 53 resigned from the board of directors, another director died on the same day. So a new director joined the board of directors aged 34. Next year in the same month the average age of all the 9 directors was found to be 46 years. The age of the late (*i. e.*, dead) director at the time of his death was :

(a) 56 years (b) 53 years
(c) 57 years (d) 61 years

38. In an office the average weight of 24 employees is 60 kg. If n employees were included whose average weight was 54 kg, then the total number of employees in the office, (given that the new average weight of all the $(24 + n)$ employees is a whole number) :

(a) 36 (b) 30
(c) 34 (d) 25

39. The average age of 100 nurses in a nursing home in 1982 was 50 years. In 1984, 20 nurses retired from their job, whose average age was 60 years. After a huge gap in 1987, 40 nurses were employed whose average age was 38 years. The average age of all the nurses in 1990 was :

(a) 53 years (b) 51 years
(c) 48.5 years (d) data insufficent

✍ ***Directions for question numbers 40, 41, 42, 43 and 44:*** *Bhartiya Idol is a talent search programme launched and run by TV Tarana. In this programme each participating candidate has to appear for the audition in such a manner that a candidate will play the Antakchhary with its aspiring opponent until he fails, otherwise he can continue and become winner. If a candidate fails on his part, he will have to leave*

Scanned by CamScanner

yoursmahboob.wordpress.com

the contest and in place of it another candidate will start off with the same existing opponent. The number of points a candidate scores is equal to the number of times he responds correctly to his opponents. The candidate who finishes the game (or who wins over the last opponent) will be declared as a winner, even if he/she has scored less points and started as the last participant. The points scored individually by all the 10 candidates are as shown below. Besides if a person loses the contest only if he/she responds incorrectly.

	Participant	Points
1.	Rajesh	8
2.	Radhe	10
3.	Harish	7
4.	Prajakta	12
5.	Aditya	25
6.	Rahul	24
7.	Shekhar	18
8.	Amit Tandon	23
9.	Amit Sana	29
10.	Abhijeet	30

40. The average score of all the 10 participants is :
(a) 21.5 (b) 18.6
(c) 18.3 (d) none of these

41. A candidate can face maximum 'n' opponents. The value of 'n' is :
(a) 3 (b) 4
(c) 1 (d) can't be determined

42. The average score of five participants who started earlier :
(a) 23 (b) 12
(c) 19.5 (d) cant't be determined

43. If Abhijeet has not started off earlier and he is the winner then the minimum number of participants who has lost the game before he has started off :
(a) 4 (b) 6
(c) 5 (d) none of these

44. For the above question the maximum possible average of the opponents of Abhijeet could be :
(a) 13.5 (b) 9.25
(c) 13.0 (d) 17.5

45. In an NGO, the daily average wages of 20 illiterate employees is decreased from Rs. 25 to Rs. 10, thus the average salary of all the literate (educated) and illiterate employees is decreased by Rs. 10 per day. The number of educated employees working in the NGO is :
(a) 15 (b) 20
(c) 10 (d) data insufficient

46. Mr. Tyagi while going from Meerut to Saharanpur covered half the distance by train at the speed of 96 km/hr then he covered half of the rest distance by his scooter at the speed of 60 km/hr and finally he covered the rest distance at the speeed of 40 km/hr by car. The average speed at which Mr Tyagi completed his journey is :
(a) 64 km/hr (b) 56 km/hr
(c) 60 km/hr (d) 36 km/hr

47. There are four types of candidates in our coaching preparing for the CAT. The number of students of Engineering, Science, Commerce and Humanities is 40, 60, 50 and 30 respectively and the respective percentage of students who qualified the CAT is 80%, 75%, 60% and 50% respectively the overall percentage of successful candidates in our institute is :
(a) 67.77% (b) 66.66%
(c) 68.5% (d) none of these

48. Mr. Manmohan calculated the average of 10, 'three digit numbers'. But due to mistake he reversed the digits of a number and thus his average increased by 19.8. The difference between the unit digit and hundreds digit of that number is :
(a) 8 (b) 4
(c) 2 (d) can't be determined

49. Once my peon went to the office of SKYLINE COURIER with 4 different envelopes. The clerk in the office measured the weights in all possible pairs. The weights obtained are 59 gm, 61 gm, 62 gm, 63 gm, 64 gm and 66 gm. The weight of the heaviest envelope is :
(a) 35 gm (b) 36 gm
(c) 34 gm (d) can't be determined

50. The average expenditure of the hotel when there are 10 guests is Rs. 60 per guests and the average expenditure is Rs. 40 when there are 20 guests. If it is known that there are some fixed expenses irrespective of the number of guests then the average expenditure per guest when there are 40 guests in the hotel :
(a) Rs. 30 (b) Rs. 25
(c) Rs. 20 (d) can't be determined

Final Round

✍ ***Directions for question numbers 1 to 15:*** *There are 3 sets of natural numbers 1 to 100. Set A contains all the natural numbers which are prime, upto 100. Set B contains all the non-prime even natural numbers upto 100. Set C contains all the non-prime odd natural numbers upto 100 i.e.,*
$A = \{2, 3, 5, 7, 11, \ldots 89, 97\}$
$B = \{4, 6, 8, 10, 12, \ldots 98, 100\}$
$C = \{1, 9, 15, 21, 25, 27, 33 \ldots 95, 99\}$

1. The average of all the elements of A, B and C is :
(a) 49.50 (b) 50.50
(c) 55 (d) none of these

2. The average of all the elements of B is :
(a) 52 (b) 48
(c) 49 (d) none of these

3. If the average (factually correct) of the set A is 42.46, then the average of the Set C is :
(a) 52 (b) 49.87
(c) 55.46 (d) can't be determined

4. The average of the elements of the Set A and C combined is :
(a) 49.0588 (b) 49.0372
(c) 50 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

5. If an element less than 50 belongs to Set A is transferred to Set B, then the average of Set B :
(a) increases (b) decreases
(c) remains constant (d) can't say

6. If any two elements, greater than 50, belong to Set A are transferred to Set C, then the average of Set C :
(a) remains constant (b) decreases
(c) increases (d) can't say

7. Any 10 elements of the Set A are transferred to the Set B, then the average of Set B :
(a) increases (b) decreases
(c) remains constant (d) can't say

8. If a least and a greatest element of Set C are transferred from Set C to Set A then the average of Set A :
(a) increases (b) decreases
(c) remains constant (d) can't be determined

9. If a smallest and a greatest element of the Set B is transferred to Set A, then the averages of A, B, C respectively :
(a) decreases, decreases, increases
(b) decreases, constant and increased
(c) increases, constant, constant
(d) can't be determined

10. If an element 2 is also included in the Set B, then the average of B :
(a) decreases by 3 (b) increases by 2
(c) decreases by 1 (d) can't be determined

11. The average of all the perfect squares of the Set C is :
(a) 35 (b) 33
(c) 30.5 (d) none of these

Directions for question number 12, 13, 14: 5 elements below 25 from the Set A are transferred to Set B, and 10 elements lying between 25 and 50 from the Set B are transferred to Set C and 15 elements above 50 from the Set C are transferred to Set A.

12. The overall average of all the elements of A, B and C is :
(a) 39.8 (b) 50.50
(c) 71.2 (d) can't be determined

13. The maximum increase in the average of set :
(a) A (b) B
(c) C (d) can't say

14. When we intended to minimise the loss in average of Set B then the new average of Set B is :
(a) 54.4772 (b) 45.74
(c) 51.84 (d) can't be determined

15. If 10-10 elements are transferred from Set A to Set B, then Set B to Set C and then from Set C to Set A but the received elements can not be transferred to the next set, *e.g.* the elements obtained from Set A can not be transferred to C through Set B. The average of which Set is maximum :
(a) A (b) B
(c) C (d) can't say

Directions for question numbers 16 and 17: In the following graph the relation between speed and distance is given :



16. The average speed for the first 200 kms. (in km/hr)
(a) 24 (b) 25
(c) 26 (d) 40

17. The average speed for the first 150 km :
(a) 15 (b) 18
(c) 25 (d) none of these

18. Abhay working in Tele Bharti as a salesperson. His monthly salary is just Rs. 200. But he gets the bonus as per the given rule. If he sells the simcards of Rs. x then his bonus will be Rs. $\left[\left(\frac{x}{100}\right)^2 + 10\right]$. In the first quarter of the year his average sale was Rs. 3000 per month. In the next 5 months his average sale was Rs. 5000 per month. In the last four months his average sale was Rs. 8000 per month. What is the average earning per month for the whole year?
(a) Rs. 3350 (b) Rs. 3610
(c) Rs. 3560 (d) none of these

19. The price of Shirts at Sahara Ganj is defined as Rs. $(100 + 10x^2)$, where x is the number of shirts. Mallika purchased 5 shirts from the above shop. The average price of a shirt is :
(a) Rs. 70 (b) Rs. 50
(c) Rs. 75 (d) none of these

20. In the above question if the sister of Mallika purchased k shirts but the average price was same as that of Mallika. The value of k could be :
(a) 6 (b) 4
(c) 2 (d) none of these

21. There are 10 compartments in passenger train which carries on an average 20 passengers per compartment. If atleast 12 passengers were sitting in each compartment and no any compartment has equal number of passengers then maximum how many passengers can be accomodated in any compartment :
(a) 64 (b) 45
(c) 56 (d) none of these

22. There are twice the number of two wheelers as there are three wheelers and the number of 4 wheelers are equal to the number of two wheelers. The average number of wheel per vehicle is :
(a) 3 (b) 4
(c) 5 (d) none of these

23. Sone lal has 'n' magical eggs whose average weight is 'k' gm. Each of the 'n' eggs produces 'n' eggs next day such that the average weight of 'n' eggs produced is same as that of the parental (previous generation) egg for each 'n' groups individually *i.e.*, each egg produces 'n' eggs in its next generation and the average weight of all the 'n' eggs of next generation is same as the weight of the mother egg. This process is continued without any change in pattern. What is the total weight of all the eggs of r^{th} generation, where the initial number of eggs with Sone Lal are considered as the eggs of first generation :
(a) rnk (b) $n^r k$
(c) nk^r (d) $n^{r+1}k$

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions for question numbers 24 to 27: *A CAT training institute was established on January 1, 2004 with 3, 4, 5 and 6 faculty members in the Logical Reasoning (LR), Data Interpretation (DI), English Language and Quantitative Analysis (QA) areas respectively, to start with. No faculty member retired or joined the institute in the first three months, of the year 2004. In the next four years, the institute recruited one faculty member in each of the four areas. All these new faculty members, who joined the institute subsequently over the years were 25 years old at the time of their joining the institute. All of them joined the institute on April 1. During these four years, one of the faculty members retired at the age of 60. The following diagram gives the area-wise average age (in terms of number of completed years) of faculty members as on April 1 of 2004, 2005, 2006 and 2007.*

Faculty	2004	2005	2006	2007
LR	49.33	44	45	46
DI	50.5	51.5	52.5	47.8
English	50.2	49	45	46
Quants	45	43	44	45

24. In which year did the new faculty member join as the faculty of English?
(a) 2004 (b) 2005
(c) 2006 (d) 2007

25. What was the age of the new faculty member, who joined the faculty of QA, as on April 1, 2007?
(a) 25 (b) 26
(c) 27 (d) 28

26. From which area did the faculty member retire?
(a) English (b) LR
(c) DI (d) Quants

27. Professors Sarvesh and Manish, two faculty members in the LR area, who have been with the Institute since its inception, share a birthday, which falls on 30th November. One was born in 1951 and the other one in 1954. On April 1, 2009, what was the age of the third faculty member, who has been in the same area since inception?
(a) 47 (b) 50
(c) 51 (d) 52

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

LEVEL-1

1 (c)	2. (b)	3. (a)	4. (b)	5. (b)	6. (a)	7. (a)	8. (c)	9. (c)	10. (b)
11. (a)	12. (a)	13. (b)	14. (a)	15. (c)	16. (c)	17. (c)	18. (a)	19. (b)	20. (b)
21. (d)	22. (c)	23. (d)	24. (b)	25. (c)	26. (a)	27. (b)	28. (b)	29. (a)	30. (b)
31. (c)	32. (a)	33. (b)	34. (b)	35. (b)	36. (a)	37. (a)	38. (b)	39. (d)	40. (a)
41. (a)	42. (c)	43. (b)	44. (a)	45. (d)	46. (a)	47. (a)	48. (a)	49. (b)	50. (c)
51. (b)	52. (b)	53. (d)	54. (d)	55. (d)	56. (a)	57. (c)	58. (a)	59. (b)	60. (a)

LEVEL-2

1 (a)	2. (c)	3. (b)	4. (b)	5. (b)	6. (c)	7. (d)	8. (b)	9. (d)	10. (a)
11. (c)	12. (d)	13. (d)	14. (a)	15. (c)	16. (b)	17. (a)	18. (d)	19. (a)	20. (b)
21. (d)	22. (a)	23. (b)	24. (d)	25. (a)	26. (c)	27. (d)	28. (d)	29. (d)	30. (a)
31. (b)	32. (a)	33. (a)	34. (a)	35. (c)	36. (b)	37. (a)	38. (a)	39. (b)	40. (b)
41. (b)	42. (d)	43. (c)	44. (a)	45. (c)	46. (a)	47. (a)	48. (c)	49. (c)	50. (a)

FINAL ROUND

1 (b)	2. (a)	3. (c)	4. (a)	5. (b)	6. (c)	7. (d)	8. (a)	9. (c)	10. (c)
11. (b)	12. (b)	13. (a)	14. (c)	15. (d)	16. (a)	17. (d)	18. (b)	19. (a)	20. (c)
21. (c)	22. (a)	23. (b)	24. (c)	25. (c)	26. (a)	27. (d)			

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1. Initially the total weight = $20 \times 45 = 900$
Now, the total weight when a student has been replaced $= 20 \times 44 = 880$
It means the weight of the new student is 20 kgs less than the replaced student. Hence the weight of the replaced student $= 40 + 20 = 60$ kgs
Alternatively: Since you know that there are total 20 students and when their average weight decreases by 1, it means on an average 1 kg weight is reduced from each of the students. Thus there is 20 kg weight loss, in total. Again this happens due to the student whose weight is 40 kg replaces an old student. Thus we can say that the weight of the old (or existing) student of the class was 60 kg, which is reduced by a 40 kg student.

2. The only useful data is that the average length of the thumb and index finger is 2.8 and the length of index finger is 3 inches.
Now the total length of index finger and thumb
$$= 2.8 \times 2 = 5.6 \text{ inches}$$
Thus the length of thumb is $(5.6 - 3) = 2.6$ inches.

3. The average price of the new mixture
$$= \frac{(38 \times 8) + (43 \times 4) + (49 \times 3)}{15} = 41.53$$

4. Average speed when Pankaj was returning
$$= \frac{2 \times 10 \times 30}{40} = 15 \text{ km/hr}$$
Now the average speed of the whole journey
$$= \frac{2 \times 15 \times 60}{75} = 24 \text{ km/hr}$$

5. Use unitary method :
In $\frac{1}{15}$ hours, 123 typists can type 984 papers
In 1 minute, 123 typists can type $\frac{984}{4} = 246$ papers
In 1 minute, 1 typist can type $\frac{246}{123} = 2$ papers
(Hint : $\frac{1}{15}$ hours $= 4$ minutes)

6. Average cost $= \frac{20 \times 3x + 15 \times 2x + 18 \times 4x}{9x} = 18$

7. Earning in the 8 months $= 600 \times 8 = 4800$
Earning in the 4 months $= \left(600 \times \frac{3}{2}\right) \times 4 = 3600$
Total earning = Rs. 8400
Saving in 8 months $= 400 \times 8 = 3200$
Saving in 4 months $= \left(400 \times \frac{5}{4}\right) \times 4 = 2000$
Total savings = 5200
Total expenditure for 12 months
$= 8400 - 5200 = 3200$
Therefore average saving per month $= \frac{3200}{12} = 266.66$

8. There are 6 prime numbers between 47 and 74 as given below:
53, 59, 61, 67, 71, 73
There are only two combinations whose average is $\frac{191}{3}$ or whose total sum is 191.
These are, {53, 67, 71} and {59, 61, 71}
We observe that in the first set the difference between greatest and smallest prime number is 18.
Hence choice (c) is correct.

9. Go back to the fundamentals and see the property number 4 and 2 of averages.
Hence required average $= 11 \times 5 + 5 = 60$

10. The average score after 48th innings = 48
The average score after 49th innings = 49
Since $\frac{(48 \times 48 + 97)}{49} = 49$
Now the requirement of runs $= 49 + (50 \times 2) = 149$
or $(50 \times 51) - (49 \times 49) = 149$

11.

		Average	Total
$S + G$	$\rightarrow$	35	70
$K + G$	$\rightarrow$	32	64
$S + K$	$\rightarrow$	38	76
$S + K + G$	$\rightarrow$	35	105
$D + I$	$\rightarrow$	$\frac{35}{2}$	35

$\therefore \quad \frac{S + K + G + D + I}{5} = \frac{105 + 35}{5} = 28$

12. Kaif $\rightarrow$ 35
Sachin $\rightarrow$ 41
Ganguli $\rightarrow$ 29
Dhoni < 35 and Irfan < 35
Hence Sachin is the senior person

13. It is the same as a person with 20 years more age replaces an existing person of the group (or village)
Since the total age of the village having n persons, is being increased by 20 years and the average age of village is being increased by 1 year, hence there are total 20 people in the village.
Alternatively : $(n \times 42) + 20 = (n \times 43)$
$\Rightarrow \quad n = 20$

14. Average rainfall $= \frac{2 \times 6 + 4 \times 5 + 4 \times 10 + 2 \times 6}{12} = 7$

15. $400 \times 7 = (300 \times 3) + (250 \times 2) + (n \times 2) \Rightarrow 700$

16. The new player must be 11 kg heavier than the replaced one.
Hence the weight of the new person = 55 + 11 = 66 kg.

Scanned by CamScanner

yoursmahboob.wordpress.com

17.

	No. of family members	Average age	Total age
4 years ago	6	25	150
Presently	6	29	174

But the no. of family members (presently) = 7
and average age (presently) = 25
Therefore the total age = 25 × 7 = 175
Hence, the age of child = 175 – 174 = 1 year

18. Amitabh's total expenditure for Jan-June = 4200 × 6 = 25200
Expenditure for Febuary-June = 25200 – 1200 = 24000
Expenditure for the months of Febuary-July
= 24,000 + 1500 = 25,500
The average expenditure = $\frac{25,500}{6} = 4250$

19. Total value of $a + 11 + 23 + 17 = 60 \Rightarrow a = 9$
again $a + b + 12 + 25 = 64 \Rightarrow b = 18$
therefore $\frac{a}{b} = \frac{1}{2}$

20. By the method of Alligation



Therefore the ratio of number of Jun. level employee to the senior level employee = 5 : 7
Hence the required fraction = $\frac{5}{(5+7)} = \frac{5}{12}$

Alternatively: Go through options

$$\frac{J}{J+S} = \frac{5x}{12x}$$

$$\Rightarrow \quad \frac{J}{S} = \frac{5x}{7x}$$

Therefore $15,500 \times 12x = 12,000 \times 5x + 18,000 \times 7x$
L.H.S. = R.H.S., Hence correct

21. None of a, b, c is correct.
The correct answer can be $\frac{a+b+c+d+e}{5}$
or $\frac{a+e}{2} = \frac{b+d}{2} = c$
where a, b, c, d, e are consecutive odd numbers.

22. $31 \times 31 - 30 \times 30 = 61$ years

23. $a + b + c + d + e = 5 \times 92 = 460$
$a + b + c = 3 \times 83 = 249$
$c + d + e = 3 \times 97 = 291$
$\therefore \quad c = (a + b + c) + (c + d + e) - (a + b + c + d + e)$
or $\quad c = 540 - 460 \quad$ or $\quad c = 80$

24. $19 \times 26 - 18 \times 25 = 44$ years

25. $\frac{k + k + 2 + k + 4 + k + 6 + k + 8 + k + 10 + k + 12}{7} = k + 6$

26. $\frac{\frac{x}{4} \times \frac{85}{100} + \frac{x}{3} \times \frac{70}{100} + \frac{5x}{12} \times \frac{56}{100}}{x} \times 100 = 67.916$

Here, x is the total number of students in the whole class.

27. Since there are five possibilities or combinations (as ${}^5C_4 = 5$)
therefore average = $\frac{5 \times 600}{4} = 750$ mm

28. $\frac{\frac{23}{5} + \frac{8}{3} + \frac{62}{9} + \frac{112}{15} + \frac{32}{9}}{5} = 5\frac{8}{225}$

29. $\frac{1000.0001 + 100.001 + 10.01 + 1.1}{4} = \frac{1111.1111}{4} = 277.777$

30. $\frac{7 + 8 + 9 + 10 + 11 + 12 + 13}{7} = 10$

$\Rightarrow \quad \frac{7 + 13}{2} = 10$

31. $\frac{\left(1 + 2 + 3 + \ldots 100\right)}{100} = \frac{\left(\frac{100 \times 101}{2}\right)}{100} = 50.50$

32. $\left(\frac{1 + 3 + 5 + 7 + \ldots 99}{50}\right) = \left(\frac{50 \times 50}{50}\right) = 50$

33. $\frac{2 + 4 + 6 + \ldots 198}{99} = \frac{99 \times 100}{99} = 100$

34. $a + b + c = 237$
$a + c = 158$
$\Rightarrow \quad b = 79$

35. $\frac{M + A + S}{3} = 11111$
also $\quad \frac{S + M}{2} = 11111 \quad (\because M - 11111 = 11111 - S)$
$\Rightarrow \quad A = 11111$

36. $\frac{2 \times 200 \times 600}{800} = 300$ km/hr

37. $\frac{A + B + C + D}{4} = \frac{400 \times 2 + 600 \times 2}{4} = 500$

38. Average weight = $\frac{20 + 50}{100} = 0.7$ kg ($\because$ 1 kg = 1000 gm)

39. Average = $\frac{770}{11} = 70$

40. $\frac{3x + 4x + 5x}{3} = 12 \Rightarrow x = 3$
$\therefore$ The ages are 9, 12 and 15 years
and the required average = $\frac{9 + 15}{2} = 12$

41. Since the salary of each employee is being increased therefore the average salary will also increased by Rs. 2000. Thus the required average = 22,000.

42. $11 \times 21 - 10 \times 20 = 31$

43. $20 \times 180 - 19 \times 178 = 218$

44. Let the price of $A > B > C$
then $\frac{A + B}{2} = 2C$
$A + B = 4C$
Now, $A + B + C = 5 \times 3 = 15$ crore
$\Rightarrow \quad 5C = 15$ crore
$\Rightarrow \quad C = 3$ crore

45. Since we don't know about the price of B.

Scanned by CamScanner

yoursmanboob.wordpress.com

46. $\left(\frac{40+70+142}{50+100+150}\right)\times 100 = 84\%$

47. Since 1 is neither prime nor composite number. Thus there are only 99 number viz. 2, 3, 4, 5, 6, ... 99, 100.

Hence $\left(\frac{2+3+4+5+6+\ldots 100}{99}\right)$

$=\left(\frac{(1+2+3+4+\ldots 100)-1}{99}\right)$

$=\frac{5050-1}{99}=\frac{5049}{99}=51$

48. $\frac{1+4+9+16+\ldots 100}{10}$

$=\left(\frac{10\times 11\times 21}{6\times 10}\right)$

$\left[\because 1^2+2^2+\ldots n^2=\frac{n(n+1)(2n+1)}{6}\right]$

$= 38.5$

49. The non-negative integers upto 99 are 0, 1, 2, 3, ... 99.

Therefore average $=\left(\frac{0+1+2+3+\ldots 99}{100}\right)$

$=\frac{\left(99\times\frac{100}{2}\right)}{100}$ $\left[\because 1+2+3+\ldots n=\frac{n(n+1)}{2}\right]$

$= 49.5$

50. $\frac{7+14+21+\ldots 77}{11}=\frac{7(1+2+\ldots 11)}{11}$

$=\frac{7\times 11\times 12}{11\times 2}=42$ $\left[\because 1+2+3\ldots n=\frac{n(n+1)}{2}\right]$

Alternatively: Since all the numbers are in A.P. Further there are odd number of numbers (*i. e.*, 11) in the sequence. Thus the middle most term is the average of the sequence, which is 42.

51.

	Average	Total
A, B, C, D	40	160
A, B, C, D, E	41	205
F, B, C, D, E	42	210

Thus $E = 205 - 160 = 45$

Hence $F, B, C, D = 210 - 45 = 165$

Therefore average of $F, B, C, D = 41.25$

52. Three consecuntive natural numbers whose average is k are $(k-1), (k), (k+1)$

The next two numbers will be $(k+2)$ and $(k+3)$

Therefore average of $(k-1), (k), (k+1)(k+2)$ and $(k+3)$ is $(k+1)$

Alternatively: Consider any 3 conseculitive natural number *eg.* 4, 5, 6 the average is 5

Again 4, 5, 6, 7, 8 the average is 6.

To verify it consider some different numbers *eg.* 10, 11, 12 average = 11 and 10, 11, 12, 13, 14 average = 12

Hence, proved that the average is increased by 1.

53. The 5 consevtive odd numbers whose average is k are $(k-4)(k-2), k, (k+2)(k+4)$

Again the average of $(k-4), (k-2), (k), (k+2), (k+4), (k+6), (k+8)$ is $(k+2)$

Alternatively: Consider some appropriate numbers.

54. The increase in weight = $(5\times 42.5)-(5\times 42) = 2.5$ kg

But we don't know the weight of the replaced officer. So we can't determine.

55. The decrease in age = $6\times(28-27) = 6$ years

But we don't know the age of the old servant which is being replaced. So we cannot determine the average age of new servant.

56. The age of new servant = 31 – 6 = 25 years

57. $A+B+C = 12{,}000\times 3$

$B+C+D = 15{,}000\times 3$

$\Rightarrow \quad D-A = 3000\times 3$

$D-A = 9000$

also $D = 2A$

$\Rightarrow \quad D = 18{,}000$ and $A = 9000$

Therefore average salary of B and $C = \frac{(45{,}000-18{,}000)}{2}$

$= 13{,}500$

58. The price of the costliest and cheapest computer

$= (80\times 30{,}000)-(78\times 29{,}500) = 99{,}000$

Therefore the price of the cheapest computer

$= 99{,}000 - 80{,}000 = 19{,}000$

59. $\frac{10\times 50+50\times 10+20\times 25+25\times 20}{4}=500$

60.

	Auto Rickshaw	Maxi. cab	Mini. Bus
No. of seats	4	10	20
No. of seats occupied	4	8	15
Rate per seat	12	15	8
Total amount (in Rs.)	48	120	120

Therefore average earning $=\frac{48+120+120}{3}=96$

LEVEL 2

1. For this type of questions take the LCM of speeds and assume the LCM as the distance

then the time taken @ speed of 60 km/hr $=\frac{300}{60}=5$ hrs

again the time taken @ speed of 50 km/hr $=\frac{300}{50}=6$ hrs

Thus we see that in place of 5 hrs train takes 6 hours. It means the train takes 1 hour extra and this one hour is stopping period in the total time of 6 hours. Thus in 6 hour train halts for 1 hour. So in 1 hour train will stop for $\frac{1}{6}$ hours or 10 minutes.

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively : (short cut)

Halting (or stopping) time $= \left(1 - \frac{\text{slower speed}}{\text{faster speed}}\right)$ hours

$= 1 - \frac{50}{60} = \frac{10}{60} = \frac{1}{6}$ hours

$= 10$ minutes

($\because$ 1 hour = 60 minutes)

2. $\frac{[r + (p - q)] + p + q}{3} = 21 + \frac{p + q + r}{3}$

$\Rightarrow \quad \frac{2p + r}{3} - 21 = \frac{p + q + r}{3}$

$\Rightarrow \quad \frac{p - q}{3} = 21$

$\Rightarrow \quad p - q = 63$

3. Let the speed for the first hour be x km/hr

then the speed for the second hour be $\frac{7}{5}x$ km/hr

then the speed for the third hour be $\frac{10}{7} \times \frac{7}{5}x = 2x$ km/hr

then the speed for the fourth hour be $2x \times \frac{7}{5} = \frac{14x}{5}$ km/hr

Therefore total distance in four hours $= x + \frac{7}{5}x + 2x + \frac{14x}{5}$

$= \frac{36x}{5}$ km

$\therefore$ Average speed $= \frac{\text{Total Distance}}{\text{Total Time}} = \frac{\left(\frac{36x}{5}\right)}{4} = \frac{9x}{5}$ km/hr

Again the distance in 4 hours @ speed of x km/hr which is half of the third hour's speed is $4x$ km

Hence $\frac{36x}{5} - 4x = 160$ km

$\Rightarrow \quad x = 50$

Hence, the average speed $= \frac{9 \times 50}{5} = 90$ km/hr

4. The total score of 3 toppers $= 123 \times 120 - 120 \times 118.5 = 540$

The highest possible score of the third highest topper is possible when the score of other two toppers was minimum

So,

1st rankers score = 187 (minimum)
2nd rankers score = 186 (minimum)
3rd rankers score = 167 (maximum)
} 540

5. Go through options : $40 \times 35 + 60 \times 25 = 29 \times 100$

Since there are 40 ladies and 60 gents

Alternatively: $40 \times 7x + 60 \times 5x = 29 \times 100$

$\Rightarrow \quad x = 5 \quad \therefore \quad 7x = 35$

6.

	Lok Sabha	Rajya Sabha
No. of MPs	300	200
Ave. Age	40	50

Since when a member of Rajya Sabha joins the Lok Sabha and the average age of both the houses increases, it means the average age of this member must lie between 40 and 50. When the age of this member is greater than 40, then the average age of the Lok Sabha increases.

Again when the age of this member is less than 50, then after leaving it, the average age of the Rajya Sabha increases.

Solutions for question numbers 7, 8 and 9:

	No. of family members	Average	Total
8 years ago →	5	36	180
Presently →	(if) 5	(36 + 8) = 44	220
	7	36	252

7. From the above explanation we have no any clue about his wife's age.

8. Since we know that the difference between the age of any two persons remains always constant, while the ratio of their ages gets changed as the time changes.

So, if the age of his child be x (presently)

Then the age of wife be $x + 26$ (presently)

Thus, the total age $= x + (x + 26) = 32$ [$\because$ 252 – 220 = 32]

$\Rightarrow \quad x = 3$

Therefore the age of her child is 3 years and her self is 29 years. Hence her age at the time of the birth of her child was 26 years.

Alternatively: As we have mentioned above that the age difference remains always constant. Therefore her age at the time of her child's birth was 26 years.

9. Since there is no clue. So we can't determine.

10.

	No. of family members	Average	Total
Eleven years earlier	4	28	112
Presently	if 4	39	156
	6	28	168

Since it is obvious that just after the birth of the youngest member (*i.e.*, child) was 6 family members in the family. Therefore at the time of the birth of the youngest child the elder child's age was 6 years.

Now the sum of their ages $= x + (x + 6) = 12 = (168 - 156)$

$\Rightarrow \quad x = 3$ and $(x + 3) = 9$

11. Go through options

$\frac{6}{4} = 1.5$ hour, when he was walking

Therefore time of journey by train $= 3 - 1.5 = 1.5$

Now, the distance travelled by train $= 1.5 \times 60 = 96 - 6 = 90$

Hence correct.

Alternatively: Total distance $= 32 \times 3 = 6 + 60 \times x$

$\Rightarrow \quad x = 1.5$ hours

Thus, the speed of walking $= \frac{6}{1.5} = 4$ km/hr

12. Let the number of total Mps = n and their average age be x then

$$n \times x = \frac{4}{5}n \times \frac{5}{4}x + \frac{n}{5} \times y$$

$\Rightarrow \quad$ either $n = 0$ or $y = 0$

[Since there are only 80% MPs remained in the house which

Scanned by CamScanner

yoursmahboob.wordpress.com

is equal to $\frac{4}{5}n$ and the increase in average age = 20% = $\frac{5}{4}x$]

Thus, there cannot be any possible value of n.

13. $nx = \frac{4}{5}n \times \frac{5}{4}x + \frac{n}{5} \times 30$

$\Rightarrow \quad n = 0$ which is impossible

So, there is no any woman MP in the Lok Sabha

14. Average speed = $\frac{\text{Total distance}}{\text{Total time}}$

$= \frac{6 \times 20}{9} = 13.33$ m/s



Hexagonal path has six sides

15. Average of 26, 29, 35 and 43 is 33.25. Also the average of 26, 29, n, 35 and 43 lies between 25 and 35 *i. e.*,

$$25 < \frac{26 + 29 + n + 35 + 43}{5} < 35$$

$\Rightarrow \quad 125 < 26 + 29 + n + 35 + 43 < 175$

$\Rightarrow \quad 125 < 133 + n < 175$

$\Rightarrow \quad n < 42$

Since the value of n is an integer and greater than 33.25 then $33 < n < 42$, for every integer n.

16. Given that $a < b < c < d$



The only possible prime number between 30 and 34 is 31

Hence $b = 31$, therefore $a = 29$

Similarly $c = 37$ and $d = 43$

Therefore $d - a = 43 - 29 = 14$

17. $9261000 = 2^3 \times 3^3 \times 5^3 \times 7^3$

$= (2 \times 3 \times 5) \times (2 \times 3 \times 7) \times (2 \times 5 \times 7) \times (3 \times 5 \times 7)$

$= 30 \times 42 \times 70 \times 105$

Therefore the average of 30, 42, 70 and 105 is 61.75.

18. Since the number is as below 270 as its multiple is as above 270. It means these two numbers are equidistant from 270. Hence their average is 270.

Alternatively : Let the number be x then.

$$270 - x = 8x - 270$$

$\Rightarrow \quad x = 60$ and $8x = 480$

Therefore the average of 60 and 480 is 270.

19. The average of 60 and 270 is 165

20. Number of days in a week = 7

Average number of visitors = 40

Total visitors = 280 (= 7 × 40)

Now, if n be the number of holidays in a week then

$(7 - n) \times 56 = 280$ (40 + 16 = 56)

$\Rightarrow \quad n = 2$

The rest data is redundant or useless, since our problem is solved here without using it.

Alternatively : Go through options

$40 \times 7 = 280 = 56 \times 5$ hence proved.

21. Since we don't know their ages individually so we cannot calculate the average of the class when a student of unknown age readmitted in the class.

22. Let the average of prime numbers be P and average of composite numbers be C.

Again the number of prime numbers be x, then the number of composite numbers be $2x$.

Then $\frac{Px + 2Cx}{3x} = 9 \Rightarrow P + 2C = 27$ ...(1)

and $\frac{2Px + Cx}{3x} = 11$

$\Rightarrow \quad 2P + C = 33$ ...(2)

on adding eq. (1) and (2)

we get $P + C = 20$

and on subtracting eq. (1) from (2)

we get $P - C = 6$

Therefore $P = 13$ and $C = 7$

Thus $\frac{C}{P} = \frac{7}{13}$

23. Solve through option $\frac{540}{27} = 20$

$$\frac{540 - (2 \times 20)}{25} = \frac{500}{25} = 20$$

Hence option (b) is correct.

24. Number of members in the staff × average age = Total age

$29 \times 24 = 696$

$29 \times 27 = 783$

hence change in total age = 87

	Physician	Surgeon	Nurse
No. of members	$(21 - x)$	8	x
Increase in average age	1	6	3
Increase in total age	$(21 - x)$	48	$3x$

Since $P + S + N = 29$

therefore if there would be x nurses then there must be $(21 - x)$ physicians.

Again total change (or increase) in age

$= (21 - x) + 48 + 3x = 87$

$\Rightarrow \quad x = 9$

25. Total exp. Jan-June = 4200 × 6 = Rs. 25200

Total exp. Feb-June = 25200 − 1200 = Rs. 24000

Total exp. Feb-July = 24000 + 1500 = Rs. 25500

The average expenditure Feb-July = $\frac{25500}{6} = 4250$

26. Let the number of subjects be n and average marks be x, then, total marks = nx

Again $(n + 1)(x - 1) = (nx - 40) + (23 + 25)$

$\Rightarrow \quad x - n = 9$ ...(1)

Further $(n + 2)(x + 1) = (nx - 40) + (23 + 25) + 57$

$\Rightarrow \quad nx + 2x + n + 2 = nx + 65$

$\Rightarrow \quad 2x + n = 63$ ...(2)

Solving equations (1) and (2), we get

$n = 15$ and $x = 24$

27. Initially, the total age of family = $4 \times 42 + 7 \times 20 = 308$

and the average age = $\frac{308}{11} = 28$

Scanned by CamScanner

yoursmahboob.wordpress.com

Now, the total age of family = 308 − (2 × 13) + (11 + 15 + 28)
= 308 + 28 = 336

Now, the new average of the family = $\frac{336}{12} = 28$

Since the average age of the original family and that of new family is same (i.e., 28)
Hence, the average age of the new family is increased by 0 year.

28. Let there be n number and he missed a number k, then the average (which he has calculated) = $\frac{\left(\frac{n(n+1)}{2} - k\right)}{n} = 15$

$\Rightarrow \quad n^2 - 29n = 2k$

$\Rightarrow \quad n(n - 29) = 2k$

Thus at $n = 29$ or $n < 29$, the expression is invalid since the value of k is neither zero nor negative, which is actually a natural number. So for the least possible valued of $n = 30$

$k = 15$

and for $n = 31, k = 31$

Again for $n > 31$, k is beyound the range *i. e.*, greater than n. Since k can not be greater than n. Hence there are only two values of k. So there is no unique value of n.

29. Let there be n people (initially) in the group, then the total earning of the group = $n \times 50$

Again $n \times 50 = (n - 2) \times 49 + (2x + 45)$

$\Rightarrow n = 2x - 53$; where x is the lowest earning of any person.

Now, since $42 < x < 47$ and $n \in$ prime numbers

Then the only possible value of $n = 37$ for $x = 45$

30. Let the number of students who got the jobs of A, B and C categories is a, b and c respectively,

then the total salary = $\frac{26(a + b) + 44(b + c) + 34(c + a)}{2(a + b + c)}$

$= \frac{60a + 70b + 78c}{2(a + b + c)}$

$= \frac{30(a + b + c) + (5b + 9c)}{a + b + c}$

= 30 + some positive value

So the minimum salary must be Rs. 30 lakh and the maximum salary can not exceed 44, which is the highest of the three.

31. $D - C - A$ ...(1)

$D > B > C$ ...(2)

from (1) and (2)

$D > B > C > A$ ...(3)

Again $E - B - A$

but $B > A$, from (3)

So $E > D > B > C > A$

[Since B is the average of E and A so it is equidistant from both E and A.]

32. Let Donald be denoted by H (Husband)
His wife be denoted by W (Wife)
His daughter be denoted by D (Daughter)
His son be denoted by S (Son)

The average age of 4 persons = $\frac{(H + W + D + S)}{4} = 23$

$\Rightarrow \quad H + W + D + S = 92$

Again $H = W + 4$

So

	H		W	D	S
At the time when daughter is born	28	← (+4)	24	0	×
↓					
At the time when son is born	32	→ (−4)	28	4	0

So at the time of birth of his son, total age of his family = 64 years (32 + 28 + 4 + 0 = 64)
and presently the total age of his family = 92 years
It means total increase in age of the whole family = 28 years
Thus the average increase in age = $\frac{28}{4} = 7$ years

It means the age of Donald = 39 years
and age of his daughter = 11 years
Therefore the average age of Donald and his daughter is 25 years.

33.

Aman	Wife	Son	El. D	Yg. D
$5x$ ◄——►	x		$5z$ ◄——►	$4z$
$8y$ ◄——————►		$3y$		
⇒ 40 K	(W)	8K	15K	12K

Again since Yg. $D + W = A + S$ $(K = x.y)$

$\Rightarrow \quad 12K + W = 40K + 8K \quad W \rightarrow$ Age of wife

$\Rightarrow \quad W = 36K$

Thus 4 years ago

$(36K - 4) = 8(8K - 4)$

$\Rightarrow \quad 28K = 28 \Rightarrow K = 1$

Therefore, the age of Aman = 40
Wife = 36
Son = 8
Elder daughter = 15
Younger daughter = 12

Hence, the average age of the family = $\frac{111}{5} = 22.22$ years

34. Let there be n politicians (initially) in the party and their average weight be x kg, then

$nx + 209 = \frac{5}{4} n(x - 1)$

$\frac{n}{4}(x - 5) = 209$

$\Rightarrow \quad x = \frac{209 \times 4}{n} + 5$

$x = \frac{4 \times 11 \times 19}{n} + 5$

So the possible value of n is 76 (= 19 × 4)
Thus $x = 16$
Therefore the average weight of all the politicians is 15 kg.

35. Total distance covered by all the wheels = 4 × 160
Number of wheels used = 5
Therefore average distance covered by each wheel

$= \frac{4 \times 160}{5} = 128$ km

Scanned by CamScanner

yoursmahboob.wordpress.com

36. Let the numbers be $(a-5), (a-3), (a-1), (a+1), (a+3), (a+5)$
then their average
$$= \frac{(a-5)+(a-3)+(a-1)(a+1)(a+3)(a+5)}{6} = a$$
Again the value of 'a' can be found by using the last statement
i.e., $(a-5)^2 + (a+5)^2 = 178$
$\Rightarrow$ $a^2 = 64 \Rightarrow a = 8$

37.

	No. of Directors	Average Age	Total Age
Just before death and resignation	10	48	480
Just after death and resignation	9		{480 – (53 + x) + 34}
One year later	9	46	414

So one year later, after the incident
total age $= \{480 - (53 + x) + 34\} + 9 \times 1 = 414$
$\Rightarrow$ $x = 56$ years
where x is the age of the dead person at the time of his death.

38. Go through options $= \frac{24 \times 60 + 12 \times 54}{(24 + 12)}$
$= 58$, which is a whole number.

39.

	Year/ Time	No. of Nurses	Average Age	Total Age
	1982	100	50	5000
Just before retirement	1984	100	52	5200
Just after retirement	1984	80	50	(5200 – 20 × 60) = 4000
Just before recruitment	1987	80	53	4240
Just after recruitment	1987	(80 + 40) = 120	48	(4240 + 38 × 40) = 5760
	1990	120	51	6120

40. Average score
$$= \frac{8+10+7+12+25+24+18+23+29+30}{10} = \frac{186}{10} = 18.6$$

41. The candidate who has scored maximum (means continuing for long time and number of responses were maximum) can be such a required person.
Now, consider Abhijeet, whose score was 30.
Again consider Rajesh, Radhe, Harish and one more candidate
since $8 + 10 + 7 < 30 \Rightarrow 25 < 30$
So there are exactly 3 persons which can be full time opponents. Further there are 5 (= 30 – 25) more chances. So these chances can be utilised by any other candidate but he or she must be in the beginning or in the ending of the Abhijeet, since the score of all the candidates is greater than 5. Hence there can be maximum 3 + 1 = 4 opponents of Abhijeet.

42. There is no such an information.

43. The minimum number of participants who have lost the game before Abhijeet started will be possible only when the number of participant with Abhijeet be maximum, which is 4. Hence excluding these 4 players (opponents of Abhijeet) and Abhijeet himself there are 5 people left. So minimum 5 players have lost the game (or contest).

44. The opponents of Abhijeet (as per the requirement) are Rajesh, Radhe, Harish and Amit Sana
So, the average score $= \frac{8+10+7+29}{4} = 13.5$

45. Go through options
or Total employs $= \frac{(25-10)\times 20}{10} = 30$
Hence number of educated employees = 30 – 20 = 10

46. Average speed of the later half journey
$$= \frac{2 \times 40 \times 60}{100} = 48 \text{ km/hr}$$
Now the average speed of the whole journey
$$= \frac{2 \times 48 \times 96}{144} = 64 \text{ km/hr}$$

47. $\frac{40 \times 0.8 + 60 \times 0.75 + 50 \times 0.6 + 30 \times 0.5}{180} \times 100$
$= \frac{122}{180} \times 100 = 67.777 \ldots \%$

48. Remember $\frac{abc - cba}{99(a-c)}$
where abc and cba are the three digit numbers and $(a, c) \neq 0$
Again since the difference in average = 19.8
Therefore the difference in total = 19.8 × 10 = 198
Thus, $99 \times (a - c) = 198$
$\Rightarrow$ $(a - c) = 2$

49. If the highest weight be 35 gm, then the second highest weight will be 31 gm. Again if the second highest will be 31, then the third highest will be 33 which is inadmissible, since then 35 + 33 = 68 which is not the greatest possible combination. Hence wrong.
Similarly 36 (i.e., option b) is also invalid

Highest	Sec. Highest	Third Highest	
36	30	34	

Thus 36 + 34 = 70 > 66, hence wrong.
The greatest possible combination can not be greater than 66.
Now, consider option (c)

Highest	Sec. Highest	Third Highest	
34	32	32 ✗	(since weights are different)
	32	31 ✗	(since 65 is not a combination)
	32	30 ✓	

So, the highest weight 34
Sec. highest weight 32
Third highest weight 30
Lowest weight 29
Since, all the weights obtained give all the 6 different combinations, hence 34 is the highest possible weight of an envelope.

50. Let the fixed expenditure of the hotel be Rs. x and the variable expenditure (which is dependent on the guest) is Rs. y, then
$x + 10y = 600$ ...(1)
$x + 20y = 800$ ...(2)
$\Rightarrow$ $10y = 200$
$y =$ Rs. 20 and $x = 400$
hence the total expenditure when there are 40 guests
$= 400 + 40 \times 20 = 1200$
Therefore average expenditure $= \frac{1200}{40} =$ Rs. 30

Scanned by CamScanner

yoursmahboob.wordpress.com

1. Since all the total 100 elements of Sets A, B, C are the natural numbers upto. Thus the average of these first 100 natural numbers is the required average.

$$\therefore \text{ Average} = \frac{1+2+3+4\ldots 100}{100} = \frac{100\times 101}{2\times 100} = 50.50$$

2. Except to 2 there are all the even numbers upto 100

So, the required average $= \frac{(2+4+6+\ldots 100)-2}{49}$

$$= \frac{50\times 51-2}{49} = \frac{2548}{49} = 52$$

NOTE There are only 49 elements in the Set B. Apply the formula of sum of first even numbers. Also use the property of AP.

3. The total value of all the 25 elements of the Set A

$$= 25\times 42.4 = 1060$$

Since, there are 25 prime numbers upto 100 in the Set A Again in the Set A and C there are 50 odd numbers and one even number. So the sum of all the elements of A and C

$$= (1+3+5+7+\ldots 99)+2$$
$$= (50)^2+2 = 2502$$

Therefore the sum of all the elements of Set C

$$= 2502-1060 = 1442$$

Hence, the average of the Set C $= \frac{1442}{26} = 55.4615$

4. The average of all the elements of the Set A and C

$$= \frac{2502}{51} = 49.0588$$

Solutions for question number 5 to 15 :

Set	No. of elements	Average	Least element	Greatest element
A	25	42.4	2	97
B	49	52	4	100
C	26	55.46	1	99

5. Since the value of element which is transferred to Set B is less than 50, which in turn less than the average of Set B, hence the average of Set B decreases.

NOTE If a quantity which is less than the average of the group introduces from outside then the new average of the group decreases.

6. The least possible numbers of Set A which are greater than 50 are 53 and 59 whose average is always greater than the average of C. Hence the average of C will necessarily increases.

7. Can't say, since we don't know which 10 numbers are being transferred. Whether their average is greater, less or equal to the average of B.

8. Definitily increases, since the average of those numbers (*viz.* 1 and 99) is 50 which is greater than the average of Set A.

9. The average of those numbers (*viz.* 4 and 100) is 52. Hence average of A will increase and average of B will remain constant and the average of C remains unaffected because Set C is not involved.

NOTE If an element or average of some elements is equal to the average of the group then this element (or subset of elements) does not change the average of the group, when it joins the group or leaves the group.

10. After the insertion of new element *viz.* 2 in the Set B the new average $= \frac{2+4+6+\ldots 100}{50} = 51$

Hence, the new average of Set B decreases by 1.

11. The perfect square number of the Set C are 1, 9, 25, 49, 81

Hence, the average of these number $= \frac{165}{5} = 33$

12. Since there is no net change (*i. e.*, all the elements even after being transferred are same). Hence their average is also same as in question no. 1.

13. Obviously A. Since the average of all those 15 elements which are joining the Set A is greater than the average of all those 5 elements which are leaving the Set A and this difference in average is largest in companision to Set B or Set C. Even in Set C there is decrease in average.

14. To minimize the loss in average of Set B, we have to transfer the least possible values of the given range and have to bring the highest possible values from the Set A to the Set B.

Thus the absolute decrease in Set B

$$= (26+28+30+32\ldots 44)-(23+19+17+13+11)$$
$$= 350-83 = 267$$

Hence, the decrease in total value of Set B

$$= 2548-267 = 2281$$

Therefore, new average $= \frac{2281}{44} = 51.84$

NOTE Now there are only 44 elements in Set B.

15. There is no relevent information regarding the numbers which are being transferred from one set to another set.

16. Average speed $= \frac{\text{Total distance}}{\text{Total time}}$

$$= \frac{200}{\left(5+\frac{10}{3}\right)} = \frac{200\times 3}{25} = 24 \text{ km/hr}$$

Since for the first 100 km time required is $\frac{100}{20} = 5$ hrs and for the last 100 km time required $= \frac{100}{30} = \frac{10}{3}$ hours

17. The average speed $= \frac{150}{5+\frac{5}{3}} = \frac{150\times 3}{20} = 22.5$ km/hr

18. Average bonus for the first 3 months $= \left(\frac{3000}{100}\right)^2 + 10 = 910$

Average bonus for the next 5 months $= \left(\frac{5000}{100}\right)^2 + 10 = 2510$

Average bonus for the last 4 months $= \left(\frac{8000}{100}\right)^2 + 10 = 6410$

His average bonus for the whole year

$$= \frac{910\times 3+2510\times 5+6410\times 4}{12} = \text{Rs. } 3410$$

Hence his average earning per month

$$= 3410+200 = \text{Rs. } 3610$$

19. Total price of 5 shirts $= \text{Rs}\,[100+10\times(5)^2] = \text{Rs. } 350$

Hence, the average price $= \frac{350}{5} = \text{Rs. } 70$

Scanned by CamScanner

yoursmahboob.wordpress.com

20. Check the option (c).

$$\text{Total price} = 100 + 10 \times (2)^2 = \text{Rs. } 140$$

$$\text{Average price} = \frac{140}{2} = \text{Rs. } 70$$

Hence, the average price is same as that of Mallika.

21. Total number of passengers = $10 \times 20 = 200$

In the 9 compartments the total number of passangers

$= 144 (= 12 + 13 + 14 + 15 + 16 + 17 + 18 + 19 + 20)$

So the no. of passengers in the 10^{th} coach = $200 - 144 = 56$

22.

	No. of 2 wheelers	No. of 3 wheelers	No. of 4 wheelers
No. of wheels	$2x$	x	$2x$
	$2 \times 2x = 4x$	$3 \times x = 3x$	$2x \times 4 = 8x$

Therefore average number of wheels = $\frac{4x + 3x + 8x}{5x} = 3$

23. The average weight of eggs of first generation is k gm and the no. of eggs is 'n'.

Let $a_1, a_2, a_3, \ldots a_n$ be the weights of n eggs of the first generation

$$\therefore \quad k = \frac{a_1 + a_2 + a_3 + \ldots a_n}{n}$$

$$\therefore \quad nk = a_1 + a_2 + a_3 + \ldots a_n \qquad \ldots(1)$$

where a_1 is the average weight of its 'n' child eggs, a_2 is the average weight of its own 'n' child eggs and so on. child egg is referred to the egg of next generation produced by its mother egg.

$$\therefore \quad a_1 = \frac{a_1 + b_1 + c_1 + \ldots n_1}{n}$$

$$a_2 = \frac{a_2 + b_2 + c_2 + \ldots n_2}{n}$$

$$a_3 = \frac{a_3 + b_3 + c_3 + \ldots n_3}{n} \text{ etc.}$$

Substituting the values of $a_1, a_2, a_3 \ldots$ in equation ...(1)

$$nk = \left(\frac{a_1 + b_1 + c_1 + \ldots}{n}\right) + \left(\frac{a_2 + b_2 + c_2 + \ldots}{n}\right) + \left(\frac{a_3 + b_3 + c_3 + \ldots}{n}\right) + \ldots \left(\frac{a_n + b_n + c_n + \ldots}{n}\right)$$

$$\therefore nk = \frac{(a_1 + b_1 + c_1) + (a_2 + b_2 + c_2 + \ldots) + (a_3 + b_3 + c_3 + \ldots)}{n}$$

$\Rightarrow$ Therefore n^2k is the total weight of all the eggs of second generation.

Similarly, each of $a_1, b_1, c_1, a_2, b_2, c_2 \ldots$ are the average weights of n eggs of their child eggs. Hence in the third generation total weight will be n^3k. Thus the total weight of all the eggs of r^{th} generation is n^rk.

Solutions for question number 24 to 27 : Before going for the final solution we need to look for the fundamental concept of averages i.e., if a person of higher age than the average age of the group leaves the group, then the average age of the group decreases. Also if a person of less age than the average age of the existing group joins the group, then the average age of the group decreases.

Besides it we also know that the average age of the same group after k years increases by K years.

Faculty of LR :

Year	No. of faculty	Average age	Total age
2004	3	49.33	148
2005	4	44	$176 = 148 + 3 + 25$
2006	4	45	$180 = 176 + 4$
2007	4	46	$184 = 180 + 4$

$176 = 148 + 3 + 25$, *implies that due to 3 existing professors their total age will be increased by 3 years after one year time period and 25 years age will be added due to a new entrant in the faculty of LR.*

Faculty of DI :

Year	No. of faculty	Average age	Total age
2004	4	50.5	202
2005	4	51.5	$206 = 202 + 4$
2006	4	52.5	$210 = 206 + 4$
2007	5	47.8	$239 = 210 + 4 + 25$

Faculty of English :

Year	No. of faculty	Average age	Total age
2004	5	50.2	251
2005	4	49	$196 = 251 + 5 - 60$
2006	5	45	$225 = 196 + 4 + 25$
2007	5	46	$230 = 225 + 5$

Faculty of Quants :

Year	No. of faculty	Average age	Total age
2004	6	45	270
2005	7	43	$301 = 270 + 6 + 25$
2006	7	44	$308 = 301 + 7$
2007	7	45	$315 = 308 + 7$

24. In the year 2006, a new faculty member joined the English faculty.

25. The new faculty member who joined on April 1, 2005 became 27 years old on April 1, 2007.

26. From the faculty of English a professor retired on April 1, 2005.

27. Age of Sarvesh on April 1, 2004 = 52 years + 4 months $\approx$ 52 years

Similarly age of Manish on April 1, 2004

= 49 years + 4 months $\approx$ 49 years

$\therefore$ Age of the third professor on April 1, 2004

$= 148 - (52 + 49) = 47$ years

Hence the age of the third professor on April 1, 2009

$= 47 + 5 = 52$ years

Scanned by CamScanner

yoursmahboob.wordpress.com

3 ALLIGATIONS

As we have studied the normal average in the previous chapter, so here we study particularly weighted average. In this chapter we will learn to find the average of two different groups with different number of elements which is known as weighted average. So alligation method is the simplified technique to solve the complex average problems. In this chapter, various kinds of problems will be discussed, since this chapter works as a means not as an end for.

Basically in the entrance tests or competitive exams like CAT, the problems are not directly asked from this chapter, rather the techniques used in this chapter are applied for the higher level problems of CAT. As the alligation plays a vital role as a time saving method in solving the problems of Ratio Proportion, S.I., C.I. Profit Loss and some other topics, so we need to emphasize on the concept of Alligation and its applications extensively applied.

Remember, in some exams like MAT, IRMA, CET etc., the problems of this chapter are directly asked which you need to solve within seconds, even orally.

EXAMPLE 1 *The average weight of a class of 40 students is 30 and the average weight of a class of 20 students is 15. Find the average weight of both the combined classes :*

(a) 20 (b) 25 (c) 17.5 (d) 15

SOLUTION To find the solution of this problem, we can use two widely used techniques :

1. Weighted average method

$$\text{The required average} = \frac{40 \times 30 + 20 \times 15}{(40 + 20)} = 25$$

2. Alligation method :



In this graphical representation of the solution, x is the weighted average where 15 and 30 are the averages of different class. So remember that the weighted average is always written in middle and the individual averages are written at the top, the smaller one in the left and the greater one in the right just for convenience and the number of elements (or the fixed quantities) are written below correspondingly.

Now, the difference between the two averages is divided in the inverse ratio of the quantities written below. As in the above problem, the difference 15 (= 30 - 15) will be divided in the ratio of 2:1 (as 40 : 20) but not in the ratio of 1 : 2, which must be clear from the arrows indicating cross proportion.

So, the value of $x = 15 + \frac{2}{3} \times (30 - 15) = 25$

or $x = 30 - \frac{1}{3} \times (30 - 15) = 25$

Therefore, the average weight of both the classes is 25.

EXAMPLE 2 *If the average weight of a class of students is 15 and the average weight of another class of students is 30, then find the ratio of the students of the first class to the another class of 30 students when the average weight of both the classes is 25 :*

(a) 1 : 2 (b) 2 : 1 (c) 1 : 3 (d) 3 : 4

SOLUTION Let the ratio of the students with 15 students to 30 students be $x : y$, then



Here we know that the averages of individual classes is 15 and 30. Again we know that the averages of both the combined classes is 25. So the difference between 25 and 15 *i. e.*, 10 and 30 & 25, *i.e.*, 5 is written diagonally opposite.

Thus the required ratio $= \frac{5}{10} = \frac{1}{2}$

EXAMPLE 3 *The average weight of girls is 15 and the average weight of boys is 30 and the average weight of boys and girls both is 25. If the number of boys are 12, then the number of girls is :*

(a) 4 (b) 6 (c) 10 (d) 18

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION



Since the ratio of girls to boys is $\frac{5}{10} = \frac{1}{2}$

Hence if there are 12 boys, so there will be 6 girls.

EXAMPLE 4 *The ratio of number of girls to number of boys is 1 : 2. If the average weight of the boys is 30 kg and the average weight of both the boys and girls be 25 kg, then the average weight of the girls is :*

(a) 15 kg (b) 20 kg (c) 35 kg (d) 40 kg

SOLUTION

$$\Rightarrow \quad \left(\frac{30-25}{25-G} = \frac{x}{2x}\right)$$

So $$\frac{(30-25)}{(25-G)} = \frac{1}{2} \Rightarrow G = 15$$

Therefore, the average weight of the girls is 15 kg. In general, if the average of group 1 be A_1 and the number of the elements be n_1 and the average of the group 2 be A_2 & the number of element be n_2 then the weighted average

$$A_w = \frac{n_1A_1 + n_2A_2}{n_1 + n_2}$$

$$\Rightarrow \quad n_1A_w + n_2A_w = n_1A_1 + n_2A_2$$

$$\Rightarrow \quad n_1(A_w - A_1) = n_2(A_2 - A_w)$$

$$\Rightarrow \quad \frac{n_1}{n_2} = \frac{(A_2 - A_w)}{(A_w - A_1)}$$

(known as Alligation Equation)

So this can be represented in the graphical form as given below



So all these problems concerned to the topic can be solved either by the formula of weighted average or Alligation equation or graphical representation method, as discussed above.

EXAMPLE 5 *Two varieties of soda water with different prices is mixed in the ratio of 2 : 3. The price of first soda water is Rs. 10 per litre while the price of second soda water is Rs. 15 per litre, respectively. The average price of the mixture (per litre) is :*

(a) Rs. 12 (b) Rs. 13 (c) Rs. 14 (d) Rs. 15

SOLUTION

$$\Rightarrow \quad \frac{(x-10)}{(15-x)} = \frac{3}{2}$$

$$\Rightarrow \quad 2(x-10) = 3(15-x)$$

$$\Rightarrow \quad x = 13$$

EXAMPLE 6 *5 kg of superior quality of sugar is mixed with 25 kg of inferior quality sugar. The price of superior quality and inferior quality sugar is Rs. 18 and Rs. 12 respectively. The average price per kg of the mixture is :*

(a) Rs. 13 (b) Rs. 15 (c) Rs. 18 (d) Rs. 21

SOLUTION



$$\frac{(x-12)}{(18-x)} = \frac{5}{25}$$

$$\Rightarrow \quad x = 13$$

SHORTCUT The corresponding ratio is 25 : 5 = 5 : 1

Now reverse the ratio, which is 1 : 5

Now divide the differences of 12 and 18 in the ratio of 1 : 5 *i. e.*, divide 6 into two parts in the ratio of 1 : 5

then the average price of mixture is 12 + 1 = 13

or 18 – 5 = 13

EXAMPLE 7 *16 litres of kerosene is mixed with 5 litres of petrol. The price of kerosene is Rs. 12 per litre and the price of petrol is Rs. 33 per litre. The average price of the mixture per litre is :*

(a) Rs. 15 (b) Rs. 17 (c) Rs. 23 (d) Rs. 27

SOLUTION



Now divide the difference of 12 and 33 in the ratio of 5 : 16 (not in the ratio of 16 : 5)

Here, the difference of 33 and 12 = 21

Again on dividing 21 in the ratio of 5 : 16, we get the first part = 5 and second part = 16

So, the average price = 12 + 5 = 17

or = 33 – 16 = 17

NOTE This cross among the numbers written above shows that the difference between x and 12 is 5 and the difference between 33 and x is 16.

EXAMPLE 8 *Amit travels 30 minutes at the speed of 25 km/hr. Further he travels 20 minutes at the speed of 40 km/hr. Find his average speed.*

(a) 25 km/hr (b) 30 km/hr
(c) 31 km/hr (d) none of these

SOLUTION



Since the actual ratio is 3 : 2, so reverse it, *i.e.*, the required ratio is 2 : 3.

Now divide the difference of both the speeds *i.e.*, 25 and 40 in the ratio of 2 : 3.

i.e., $(40-25)\times\frac{2}{5} = 6$ and $(40-25)\times\frac{3}{5} = 9$

So the average speed is 25 + 6 = 31

or 40 – 9 = 31

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 9 *A milkman has two types of milk. In the first container the percentage of milk is 80% and in the second container the percentage of milk is 60%. If he mixes 28 litres of milk of the first container to the 32 litres of milk of the second container, then the percentage of milk in the mixture is :*

(a) 63.99 (b) 69.33 (c) 72.5 (d) 75.2

SOLUTION

8 : 7

7 : 8 (reversed ratio)

So $(80 - 60) \times \frac{7}{7+8} = 20 \times \frac{7}{15} = 9.33$

Thus the required percentage = 60 + 9.33 = 69.33

EXAMPLE 10 *Modern electronic shop sold the 30% hardware at the profit of 50% and 90% software at the profit of 10%. The average profit percent of the Modern electronic shop is, if it sells only these two kinds of things :*

(a) 15 (b) 20 (c) 25 (d) 45

SOLUTION



The actual ratio is 3 : 1.

So the reversed ratio is 1 : 3.

Now divide the difference of 10 and 50 in the ratio of 1 : 3 then add the first part to the 10 or subtract the second part from the 50.

i.e., Required average $= 10 + (50 - 10) \times \frac{1}{4}$

$= 10 + 10 = 20$

or $50 - (50 - 10) \times \frac{3}{4} = 20$

NOTE All the problems discussed above can be solved in any way, *i.e.*, either by using the formula of weighted average or Alligation Equation. But we have emphasised on the graphical (cross proportion) method. Since this technique is quite handy, *i.e.*, some times you need not to calculate on paper.

EXAMPLE 11 *Avinash covered 150 km distance in 10 hours. The first part of his journey he covered by car, then he hired a rickshaw. The speed of car and rickshaw is 20 km/hr and 12 km/hr respectively. The ratio of distances covered by car and the rickshaw respectively are :*

(a) 2 : 3 (b) 4 : 5

(c) 1 : 1 (d) none of these

SOLUTION The average speed of Avinash $= \frac{150}{10} = 15$ km/hr



It means the rickshaw took 5/8 and car took 3/8 of the total time

i. e., the ratio of time taken by rickshaw to car is 5 : 3

So the ratio of distances covered by rickshaw to car is

$5 \times 12 : 3 \times 20 \Rightarrow 1 : 1$

NOTE

1. In this calculation (*i.e.*, In alligation method) distance never involves directly. Only time and speeds are involved.
2. Since we have to find generally the average speed (not the average time) so speeds are written on the top and corresponding time taken is written below.

EXAMPLE 12 *A mixture of rice is sold at Rs. 3.00 per kg. This mixture is formed by mixing the rice of Rs. 2.10 and Rs. 2.52 per kg. What is the ratio of price of cheaper to the costlier quality in the mixture if the profit of 25% is being earned.*

(a) 5 : 2 (b) 2 : 7 (c) 2 : 5 (d) 15 : 8

SOLUTION Let the cost price of the mixture be Rs. x per kg, then selling price $= x + \frac{25 \times x}{100} = 3$

$\Rightarrow \quad 1.25x = 3$

$\Rightarrow \quad x = 2.4$

Now the average cost price of mixture = Rs. 2.4



Therefore, the ratio of cheaper to costlier rice is 12 : 30, *i.e.*, 2 : 5.

NOTE Re 1 = 100 paise. There is no change in the ratio when we change the rupees into paise, just for our convenience in calculation.

EXAMPLE 13 *A milkman has 20 litres of milk. If he mixes 5 litres of water, which is freely available, in 20 litres of pure milk. If the cost of pure milk is Rs. 18 per litre, then the profit of the milkman, when he sells all the mixture at cost price, is :*

(a) 20% (b) 25% (c) 33.33% (d) 18%

SOLUTION When the water is freely available and all the water is sold at the price of the milk, then the water gives the profit on the cost of 20 litres of milk.

Therefore, profit percentage $= \frac{5}{20} \times 100 = 25\%$

Since, the profit % $= \frac{\text{profit}}{\text{cost price}} \times 100$

NOTE Here the milkman cheats his customer by false practise of creating illusion that instead of 20 litres milk, there is 25 litres of milk. So this extra 5 litres of milk (actually water) is the part of profit.

EXAMPLE 14 *In what ratio should water and wine be mixed so that after selling the mixture at the cost price a profit of 33.33% is made?*

(a) 1 : 4 (b) 1 : 3 (c) 2 : 3 (d) 3 : 4

SOLUTION 33.33% profit means there is one part water and 3 part is pure wine. So the required ratio of water and wine in the mixture is 1 : 3.

NOTE The above problem (No. 14) and the previous problem are basically related to the topics of ratio and profit-loss.

EXAMPLE 15 *In what ratio should freely available water be mixed with the wine worth Rs. 60 per litre so that after selling the mixture at Rs. 50 per litre, the profit will be 25%?*

(a) 1 : 2 (b) 2 : 3 (c) 3 : 4 (d) 4 : 5

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION Selling price = Rs. 50

Therefore, the cost price

= Rs. 40, which is the average price.

It means the wine, worth Rs. 60 becomes worth Rs. 40 when the water was mixed in it. So we can conclude that in the mixture of Rs. 60, there is wine worth Rs. 40 and the rest is water. Therefore, the ratio of water and wine is 20 : 40 i.e., 1 : 2 :

Alternatively :



⇒ 1 : 2

EXAMPLE 16 *A mixture of water and milk contains 80% milk. In 50 litres of such a mixture, how many litres of water is required to increase the percentage of water to, 50%?*

(a) 20 *(b) 15*

(c) 30 *(d) none of these*

SOLUTION Total amount of mixture is 50 litre



Note that, in this process the quantity of milk remains constant but its percentage decreases as the quantity (and percentage) of water increases.

Initially we have 40 litre milk and 10 litre water. Now we are required to have 50% water and remaining 50% milk in the new mixture. So we have to have 40 litre water, equal to the amount of pure milk (which is constant) available in the mixture. Thus we have to add up 30 litre (= 40 − 10) water in the original mixture.

EXAMPLE 17 *In a 50 litre mixture of water and milk, water is only 20%. The milkman gives 10 litres 'of this' mixture to a customer and then he adds up 10 litres of pure water in the remaining mixture. The percentage of water in the final mixture is :*

(a) 84% *(b) 74%* *(c) 26%* *(d) 36%*

SOLUTION Total quantity of mixture = 50 litre



See the chart for the solution.

Initially there is 40 litres (80%) milk in the 50 litres mixture. When 10 litres of mixture is drawn out, it means 8 litres of milk is drawn out. Now when the 10 litres of water is added, it means in the 50 litres of mixture, there is only 32 litres of milk, i.e., 64%. Hence the percentage of water is 36%.

EXAMPLE 18 *There are three types of milk, Parag, Amul and Nestle. The ratio of fat to the non-fat contents in milk is 4 : 5, 5 : 6, 6 : 7 respectively. If all these three types of milk is mixed in equal quantity, the ratio of fat to the non-fat contents in the mixture will be :*

(a) 1751 : 2110 *(b) 175 : 543*

(c) 3 : 5 *(d) 10 : 18*

SOLUTION In this type of questions, we consider only one item (*viz.*, either fat or non-fat) as the fraction of the total quantity. Again we equate the denominators.

Let us consider fraction of 'fat'.

	Parag	Amul	Nestle
Fraction of fat →	$\frac{4}{9}$	$\frac{5}{11}$	$\frac{6}{13}$
	$\frac{4\times11\times13}{9\times11\times13}$	$\frac{5\times9\times13}{11\times9\times13}$	$\frac{6\times9\times11}{13\times9\times11}$
	$\frac{572}{1287}$	$\frac{585}{1287}$	$\frac{594}{1287}$

So the total fat in the total mixture

$$= \frac{572+585+594}{1287+1287+1287} = \frac{1751}{3861}$$

Hence, the ratio of fat to the non-fat contents in the mixture

= 1751 : 2110 ∵ (3861 − 1751 = 2110)

EXAMPLE 19 *Sharabi Chand purchased two different kinds of alcohol. In the first mixture the ratio of alcohol to water is 3 : 4 and in the second mixture it is 5 : 6. If he mixes the two given mixtures and makes a third mixture of 18 litres in which the ratio of alcohol to water is 4 : 5, the quantity of first mixture (whose ratio is 3 : 4) is required to make the 18 litres of the third kind of mixture is :*

(a) 6 *(b) 7* *(c) 8* *(d) 9*

SOLUTION The fraction of alcohol in the different mixtures is as follows :

$$\text{First mixture } \frac{3}{7} = \frac{297}{693}$$

$$\text{Second mixture } \frac{5}{11} = \frac{315}{693}$$

$$\text{Final mixture } \frac{4}{9} = \frac{308}{693}$$

Therefore



Hence the ratio of first mixture is to second mixture is 7 : 11. Thus he has to mix 7 litres of first type of alcohol to make 18 litres of required mixture.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 20 *Some amount out of Rs. 6000 was lent out at 10% per annum and the rest amount @ at 20% per annum and thus in 4 years the total interest from both the amounts collected was Rs. 3400. What is the amount which was lent out @ 10% per annum?*

(a) Rs. 2500 *(b) Rs. 2800*
(c) Rs. 3200 *(d) Rs. 3500*

SOLUTION The total interest of one year

$$= \text{Rs. } 850 = \left(\frac{3400}{4}\right)$$

Therefore, the average rate of interest $= 14\frac{1}{6}\% = \frac{85}{6}\%$

Thus,



Hence the ratio of amount which is lent @ 10% per annum to the amount lent @ 20% per annum is 35 : 25, *i.e.*, 7 : 5.

Therefore, the amount which is lent out @ 10% per annum is Rs. 3500.

EXAMPLE 21 *From the 50 litres of milk, 5 litres of milk is taken out and after it 5 litres of water is added to the rest amount of milk. Again 5 litres of mixture of milk and water is drawn out and it was replaced by 5 litres of water. If this process is continued similarly for the third time, the amount of milk left after the third replacement :*

(a) 45 L *(b) 36.45 L* *(c) 40.5 L* *(d) 42.5 L*

SOLUTION

Milk	Water	
50 L	0 L	50 litre (initially)
− 5 L	− 0 L	withdrawn amount
45 L	0 L	50 litre (after first replacement)
+ 0 L	+ 5 L	
− 4.5 L	− 0.5 L	withdrawn amount
40.5 L	4.5 L	50 litre (after second replacement)
+ 0 L	+ 5 L	
− 4.05 L	− 0.95 L	withdrawn amount
36.45 L	8.55 L	50 litre (after third replacement)
	+ 5 L	

SHORTCUT $50 \times \left(1 - \frac{5}{50}\right) \times \left(1 - \frac{5}{50}\right) \times \left(1 - \frac{5}{50}\right)$

$$= 50 \times \frac{45}{50} \times \frac{45}{50} \times \frac{45}{50} = 50 \times \left(\frac{45}{50}\right)^3 = 50 \times \left(\frac{9}{10}\right)^3$$

$$= 36.45 \text{ L}$$

GENERAL FORMULA

Final or reduced concentration = Initial concentration $\left(1 - \frac{\text{amount being replaced in each operation}}{\text{total amount}}\right)^n$

where n is the number of times the same operation is being repeated. The "amount being replaced" could be pure or mixture as per the case. Similarly, "total amount" could also be either pure or mixture. Here amount being replaced denotes the quantity which is to be withdrawn in each time.

EXAMPLE 22 *From a tank of petrol, which contains 200 litres of petrol, the seller replaces each time with kerosene when he sells 40 litres of petrol (or its mixture). Everytime he sells out only 40 litres of petrol (pure or impure). After replacing the petrol with kerosene 4th time, the total amount of kerosene in the mixture is :*

(a) 81.92 l *(b) 96 l*
(c) 118.08 l *(d) none of these*

SOLUTION The amount of petrol left after 4 operations

$$= 200 \times \left(1 - \frac{40}{200}\right)^4 = 200 \times \left(\frac{4}{5}\right)^4$$

$$= 200 \times \frac{256}{625} = 81.92 \text{ litres}$$

Hence the amount of kerosene = 200 − 81.92 = 118.08 litres

EXAMPLE 23 *From a container of wine, a thief has stolen 15 litres of wine and replaced it with same quantity of water. He again repeated the same process. Thus in three attempts the ratio of wine and water became 343 : 169. The initial amount of wine in the container was :*

(a) 75 litres *(b) 100 litres*
(c) 150 litres *(d) 120 litres*

SOLUTION $\frac{\text{wine (left)}}{\text{water (added)}} = \frac{343}{169}$

It means $\frac{\text{wine (left)}}{\text{wine (initial amount)}} = \frac{343}{512}$ $(\because 343 + 169 = 512)$

Thus, $343x = 512x\left(1 - \frac{15}{K}\right)^3$

$\Rightarrow$ $\frac{343}{512} = \left(\frac{7}{8}\right)^3 = \left(1 - \frac{15}{K}\right)^3$

$\Rightarrow$ $\left(1 - \frac{15}{K}\right) = \frac{7}{8} = \left(1 - \frac{1}{8}\right)$

$\Rightarrow$ $K = 120$

Thus the initial amount of wine was 120 litres.

EXAMPLE 24 *A jar was full with honey. A person used to draw out 20% of the honey from the jar and replaced it with sugar solution. He has repeated the same process 4 times and thus there was only 512 gm of honey left in the jar, the rest part of the jar was filled with the sugar solution. The initial amount of honey in the jar was :*

(a) 1.25 kg *(b) 1 kg*
(c) 1.5 kg *(d) none of these*

SOLUTION Let the initial amount of honey in the jar was K, then

$$512 = K\left(1 - \frac{1}{5}\right)^4 \qquad \left(\because 20\% = \frac{20}{100} = \frac{1}{5}\right)$$

or $512 = K\left(\frac{4}{5}\right)^4$

$\Rightarrow$ $K = \frac{512 \times 625}{256}$

$\therefore$ $K = 1250$

Hence initially the honey in the jar = 1.25 kg.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

1. How much Pepsi at Rs. 6 a litre is added to 15 litre of 'dew' at Rs. 10 a litre so that the price of the mixture be Rs. 9 a litre?
(a) 5 (b) 8
(c) 10 (d) none of these

2. In a municipal parking there are some two wheelers and rest are 4 wheelers. If wheels are counted, there are total 520 wheels but the incharge of the parking told me that there are only 175 vehicles. If no vehicle has a stepney, then the no. of two wheelers is :
(a) 75 (b) 100
(c) 90 (d) 85

3. In my pocket there are Rs. 25 consisting of only the denominations of 20 paise and 50 paise. Thus there are total 80 coins in my pocket. The no. of coins of the denomination of 50 paise is :
(a) 30 (b) 70
(c) 50 (d) 25

4. There are some shepherds and their sheep in a grazing field. The no. of total heads are 60 and total legs are 168 including both men and sheep. The no. of sheep is :
(a) 18 (b) 26
(c) 24 (d) 36

5. In the 75 litres of mixture of milk and water, the ratio of milk and water is 4 : 1. The quantity of water required to make the ratio of milk and water 3 : 1 is :
(a) 1 litre (b) 3 litres
(c) 4 litres (d) 5 litres

6. In my office the average age of all the female employees is 21 years and that of male employees is 32 years, where the average age of all the (male and female) employees is 28 years. The total no. of employees in my office could be :
(a) 35 (b) 78
(c) 231 (d) 90

7. A car agency has 108 cars. He sold some cars at 9% profit and rest at 36% profit. Thus he gains 17% on the sale of all his cars. The no. of cars sold at 36% profit is :
(a) 25 (b) 32
(c) 35 (d) 75

8. Rs. 69 were divided among 115 students so that each girl gets 50 paise less than a boy. Thus each boy received twice the paise as each girl received. The no. of girls in the class is :
(a) 92 (b) 42
(c) 33 (d) 23

9. In what proportion water be mixed with spirit to gain 12.5% by selling it at cost price?
(a) 3 : 5 (b) 1 : 8
(c) 2 : 7 (d) 1 : 9

10. A butler stole wine from a butt of sherry containing 50% of spirit, then he replenished it by different wine containing 20% spirit. Thus there was only 30% strength (spirit) in the new mixture. How much of the original wine did he steal?
(a) 1/3 (b) 2/3
(c) 1/2 (d) 1/4

11. Mr. Mittal purchased two steel factories, one in India and other one in Malaysia for total Rs. 72 crores. Later on he sold the Indian factory at 16% profit and Malasian factory at 24% profit. Thus he gained a total profit of 19%. The selling price of Indian factory is :
(a) 45 crore (b) 52.2 crore
(c) 8.55 crore (d) can not be determined

12. In a 25 litre mixture of milk and water, the water is only 20%. How many litres of water is required to increase the percentage of water to 90%?
(a) 45 litre (b) 70 litre
(c) 115 litre (d) 175 litre

13. A milkman sells the milk at the cost price but he mixes the water (freely available) in it and thus he gains 9.09%. The quantity of water in the mixture of 1 litre is :
(a) 83.33 mL (b) 90.90 mL
(c) 99.09 mL (d) can't be determined

14. The price of petrol is Rs. 60 per litre and the price of spirit is Rs. 40 per litre. In what ratio the petrol and spirit be mixed such that the profit after selling the mixture at Rs. 75 per litre be 25%?
(a) 1 : 1
(b) 3 : 2
(c) 5 : 1
(d) such a mixture is not possible

15. A trader sells total 315 TV sets. He sells black and white TV sets at a loss of 6% and colour TV sets at a profit of 15%. Thus he gains 9% on the whole. The no. of B/W TV sets, which he has sold, is :
(a) 126 (b) 216
(c) 135 (d) 90

16. In a class of 30 students, the average weight of boys is 20 kg and the average weight of the girls is 25 kg. The fraction of boys out of the total students of the class is :
(a) $\frac{4}{5}$ (b) $\frac{5}{6}$
(c) $\frac{3}{4}$ (d) data insufficient

17. Baniya sells two types of tea *viz.* Desi Chai and Videshi Chai. He sells Desi Chai at Rs. 18 per kg and incurs a loss of 10% whereas on selling the Videshi Chai at Rs. 30 per kg, he gains

Scanned by CamScanner

yoursmahboob.wordpress.com

20%. In what proportion should the Desi Chai and Videshi Chai be mixed such that he can gain a profit of 25% by selling the mixture at Rs. 27.5 per kg?

(a) 3 : 2 (b) 2 : 3
(c) 2 : 5 (d) 3 : 5

18. The average age of boys in class is 16.66, while the average age of girls is 18.75. Thus the average age of all the 40 students of the class is 17.5. If the difference between the no. of boys and girls is 8, then the no. of girls in the class is :

(a) 12 (b) 16
(c) 18 (d) data insufficient

19. The ratio of water and alcohol in two different containers is 2 : 3 and 4 : 5. In what ratio we are required to mix the mixtures of two containers in order to get the new mixture in which the ratio of alcohol and water be 7 : 5?

(a) 7 : 3 (b) 5 : 3
(c) 8 : 5 (d) 2 : 7

20. The average marks of the students in four sections *A*, *B*, *C* and *D* together is 60%. The average marks of the students of *A*, *B*, *C* and *D* individually are 45%, 50%, 72% and 80% respectively. If the average marks of the students of sections *A* and *B* together is 48% and that of the students of *B* and *C* together is 60%. What is the ratio of number of students in sections *A* and *D*?

(a) 2 : 3 (b) 4 : 3
(c) 5 : 3 (d) 3 : 5

21. The diluted wine contains only 8 litres of wine and the rest is water. A new mixture whose concentration is 30%, is to be formed by replacing wine. How many litres of mixture shall be replaced with pure wine if there was initially 32 litres of water in the mixture ?

(a) 4 (b) 5
(c) 8 (d) none of these

22. The average weight of boys in a class is 30 kg and the average weight of girls in the same class is 20 kg. If the average weight of the whole class is 23.25 kg, what could be the possible strength of boys and girls respectively in the same class ?

(a) 14 and 26 (b) 13 and 27
(c) 17 and 27 (d) none of these

23. The shopkeeper mixed 40 kg refined oil with vegetable oil worth Rs. 60 per kg. Thus he gains Rs. 10 after selling the mixture of the two oils. The price of the first oil is :

(a) 20 (b) 25
(c) 45 (d) can't be determined

24. In a mixture of milk and water, there is only 26% water. After replacing the mixture with 7 litres of pure milk, the percentage of milk in the mixture become 76%. The quantity of mixture is :

(a) 65 litre (b) 91 litre
(c) 38 litre (d) none of these

25. The ratio of expenditure and savings is 3 : 2. If the income increases by 15% and the savings increases by 6%, then by how much per cent should his expenditure increases?

(a) 25 (b) 21
(c) 12 (d) 24

26. 4 kg of a metal contains $\frac{1}{5}$ copper and rest is zinc. Another 5 kg of metal contains $\frac{1}{6}$ copper and rest is zinc. The ratio of copper and zinc into the mixture of these two metals :

(a) 49 : 221 (b) 39 : 231
(c) 94 : 181 (d) none of these

27. 450 litres of a mixture of milk and water contain the milk and water in the ratio 9 : 1. How much water should be added to get a new mixture containing milk and water in the ratio 3 : 1?

(a) 54 (b) 90
(c) 45 (d) 63

28. The ratio of petrol and kerosene in the container is 3 : 2 when 10 litres of the mixture is taken out and is replaced by the kerosene, the ratio becomes 2 : 3. The total quantity of the mixture in the container is :

(a) 25 (b) 30
(c) 45 (d) cannot be determined

29. From a container, 6 litres milk was drawn out and was replaced by water. Again 6 litres of mixture was drawn out & was replaced by the water. Thus the quantity of milk and water in the container after these two operations is 9 : 16. The quantity of mixture is :

(a) 15 (b) 16
(c) 25 (d) 31

Answers

1. (a)	**2.** (c)	**3.** (a)	**4.** (c)	**5.** (d)	**6.** (c)	**7.** (b)	**8.** (a)	**9.** (b)	**10.** (b)
11. (b)	**12.** (d)	**13.** (a)	**14.** (d)	**15.** (d)	**16.** (d)	**17.** (a)	**18.** (b)	**19.** (b)	**20.** (b)
21. (b)	**22.** (b)	**23.** (d)	**24.** (b)	**25.** (b)	**26.** (a)	**27.** (b)	**28.** (b)	**29.** (a)	

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

1. Let x litre pepsi is required.



Therefore $\frac{x}{15} = \frac{1}{3}$

$\Rightarrow$ $x = 5$ litre

Alternatively : Go through options.

2. Go through options :

$$90 \times 2 + 85 \times 4 = 520$$

If 2 wheelers be 90 then the four wheelers will be

$$85 = (175 - 90)$$

Alternatively : The average number of wheels per vehicle $= \frac{520}{175}$



$\Rightarrow$ 180 : 170

$\Rightarrow$ 90 : 85

$\Rightarrow$ 18 : 17

Therefore the ratio of two wheelers to four wheelers is 18 : 17.
Hence there are 90 "two wheelers".

3. Go through options :

$$30 \times 50 + 50 \times 20 = 2500 \text{ paise}$$

Alternatively : Since the average price of a coin

$$= \frac{2500}{80} = 31.25 \text{ paise}$$



So the ratio of no. of 20 paise coins to the no. of 50 paise coins

$$= 18.75 : 11.25$$

$$= 75 : 45 = 5 : 3$$

Therefore, the no. of coins of the denominations of 50 paise is 30.

4. Go through option :

$$24 \times 4 + 36 \times 2 = 168$$

Alternatively :



$\Rightarrow$ 3 : 2

Therefore, the ratio of men and sheep is 3 : 2

Alternatively : Suppose there are only men, then the no. of legs $= 60 \times 2 = 120$.
Now since there are $48 = (168 - 120)$ legs extra, it means there are $24 = \left(\frac{48}{2}\right)$ sheep, since a sheep has 2 extra legs than a man has.

5. Total quantity of mixture = 75 litre

Therefore



6. Since the ratio of no. of female and male employees is 4 : 7, so the total no. of employees must be the multiples of 11. Hence the possible answer is 231.



7. Since the ratio of cars sold at profit of 9% to the 36% is 19 : 8, hence the no. of cars sold at 36% profit is 32.



8. Here each girl receives 50 paise and each boy receives 100 paise and the average receiving of each student

$$= \frac{6900}{115} = 60 \text{ paise}$$



$\Rightarrow$ (G) 4 : (B) 1

Thus the no. of girls = 92 [Number of boys = 23]

9. Profit = 12.5% = $\frac{1}{8}$

Hence the ratio of water to spirit is 1 : 8

since profit % = $\frac{\text{profit}}{\text{cost}} \times 100$.

10.



Since the ratio of 20% wine to 50% wine is 2 : 1, it means there is $\frac{2}{3}$ wine which is replaced with wine in which the concentration of spirit is 20%.

Scanned by CamScanner

yoursmahboob.wordpress.com

11. 16 — 24 — 19 — 5 — 3

Thus the cost price of Indian factory is Rs. 45 crore.
Therefore, the selling price of Indian factory is

$$= 45 + \frac{45 \times 16}{100} = 52.2 \text{ crore}$$

12.

Milk		Water
80%		20%
4	:	1
20 L		5 L
20 L		180 L (+ 175 L)
10%		90%
1	:	9

13. Profit (%) = 9.09% = $\frac{1}{11}$

Since the ratio of water and milk is 1 : 11,
Therefore the ratio of water is to mixture = 1 : 12
Thus the quantity of water in mixture of 1 litre

$$= 1000 \times \frac{1}{12} = 83.33 \text{ mL}$$

14. The selling price of mixture = Rs. 75

∴ The cost price of mixture = Rs. 60

Now we know that if he mixes the spirit (worth Rs. 40) with petrol (worth Rs. 60), the cost price of mixture must be less than Rs. 60, which is impossible. Hence there is no spirit with the petrol.

15. −6 — 15 — 9 — 6 — 15

⇒ 2 : 5

Thus the ratio of B/W TV sets to the no. of colour TV sets

$$= 2 : 5$$

Therefore, no. of B/W TV sets = 90

16. Since we do not know either the average weight of the whole class or the ratio of no. of boys to girls.

17. The S.P. of Desi Chai = Rs. 18
The S.P. of Videshi Chai = Rs. 30
The C.P. of Desi Chai = Rs. 20
The C.P. of Videshi Chai = Rs. 25
The S.P. of mixture = Rs. 27.5
The C.P. of mixture = Rs. 22

20 — 25 — 22 — 3 — 2

Therefore, the ratio of Desi Chai is to Videshi Chai is 3 : 2

18. 16.66 — 18.75 — 17.5 — (Boys) x — y (Girls)

$\frac{50}{3} \times \frac{4}{4}$ — $\frac{75}{4} \times \frac{3}{3}$ — $\frac{35}{2} \times \frac{6}{6}$ — x — y

$\frac{200}{12}$ — $\frac{225}{12}$ — $\frac{210}{12}$ — $\frac{15}{12}$ — $\frac{10}{12}$

⇒ 3 : 2

Thus the no. of girls = 16 and no. of boys = 24

19.

$W_1 : A_1$	$W_2 : A_2$	$W_N : A_N$
2 : 3	4 : 5	5 : 7
$\frac{W_1}{W_1 + A_1} = \frac{2}{5}$	$\frac{W_2}{W_2 + A_2} = \frac{4}{9}$	$\frac{W_N}{W_N + A_N} = \frac{5}{12}$
$= \frac{72}{180}$	$= \frac{80}{180}$	$= \frac{75}{180}$

$\frac{72}{180}$ — $\frac{80}{180}$ — $\frac{75}{180}$ — $\frac{5}{180}$ — $\frac{3}{180}$

⇒ 5 : 3

Therefore, the ratio is 5 : 3.

20. Since the average marks of sections B and C together are equal the average marks of all the four sections (*i.e.*, A, B, C and D), therefore the average marks of the remaining two sections A and D together will also be equal *i.e.*, 60%.

45 — 80 — 60 — 20 — 15

⇒ 4 : 3

Hence, the required ratio is 4 : 3.

21.

Wine		Water
8 L		32 L
1	:	4
20%		80% (original ratio)
30%		70% (required ratio)

In this case, the percentage of water being reduced when the mixture is being replaced with wine.

So the ratio of **left quantity** to the initial quantity is 7 : 8.

Therefore $\frac{7}{8} = \left[1 - \frac{K}{40}\right] \Rightarrow \frac{7}{8} = \left[\frac{40 - K}{40}\right]$

$\Rightarrow$ $K = 5$ litre

Alternatively : Go through options.

22. Therefore no. of boys : Number of girls = 13 : 27

20 — 30 — 23.25 — 6.75 — 3.25

27 : 13

Scanned by CamScanner

yoursmahboob.wordpress.com

23. Since there is insufficient data.

24. Milk Water

74% 26% (Initially)

76% 24% (after replacement)

$$\text{Left amount} = \text{Initial amount}\left(1 - \frac{\text{replaced amount}}{\text{total amount}}\right)$$

$$24 = 26\left(1 - \frac{7}{K}\right)$$

$$\Rightarrow \quad \frac{12}{13} = \left(1 - \frac{7}{K}\right)$$

$$\Rightarrow \quad \frac{1}{13} = \frac{7}{K}$$

$$\Rightarrow \quad K = 91 \text{ litre}$$

NOTE In case of replacement, the initial (pure) amount is equal to the amount of final mixture.

25.



Therefore $x = 21\%$

26. Copper in $4 \text{ kg} = \frac{4}{5} \text{ kg}$

and Zinc in $4 \text{ kg} = 4 \times \frac{4}{5} = \frac{16}{5} \text{ kg}$

Copper in $5 \text{ kg} = 5 \times \frac{1}{6} = \frac{5}{6} \text{ kg}$

Zinc in $5 \text{ kg} = 5 \times \frac{5}{6} = \frac{25}{6} \text{ kg}$

Therefore, Copper in mixture $= \frac{4}{5} + \frac{5}{6} = \frac{49}{30} \text{ kg}$

and Zinc in the mixture $= \frac{16}{5} + \frac{25}{6} = \frac{221}{30} \text{ kg}$

Therefore, the required ratio = 49 : 221.

27.



28. Petrol : Kerosene

3 : 2 (initially)

2 : 3 (after replacement)

$$\frac{\text{Remaining (or left) quantity}}{\text{Initial quantity}} = \left(1 - \frac{\text{replaced quantity}}{\text{total quantity}}\right)$$

$$\text{(for petrol)} \quad \frac{2}{3} = \left(1 - \frac{10}{K}\right)$$

$$\Rightarrow \quad \frac{1}{3} = \frac{10}{K}$$

$$\Rightarrow \quad K = 30 \text{ litre}$$

Therefore, the total quantity of the mixture in the container is 30 litre.

29.

$$\frac{9}{25} = \left(1 - \frac{6}{K}\right)^2$$

$$\Rightarrow \quad \frac{3}{5} = \left(1 - \frac{6}{K}\right)$$

$$\Rightarrow \quad K = 15 \text{ litre}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

4 RATIO, PROPORTION & VARIATION

The basic applications of the concepts involved in this chapter are comparisons of two or more quantities and changes in their magnitudes, *e.g.*, comparison of the ages, weights income, savings, heights, volume, density, temperature etc.

So this chapter is very useful in solving the problems of Data interpretation. Also each and every year one or two problems from this chapter is/are asked in CAT, either directly or application based for QA section. Last but not the least, the concepts of ratio, proportion and variations are very useful in solving the maximum arithmetic problems. That's why these problems are usually asked in most of the competitive exams like FMS, IIFT, MAT, SYMBIOSIS etc.

RATIO

The comparison between two quantities in terms of magnitude is called the ratio, *i.e.*, it tells us that the one quantity is how many times the other quantity.

For example, Amit has 5 pens and Sarita has 3 pens. It means the ratio of number of pens between Amit and Sarita is 5 is to 3. It can be expressed as '5 : 3'.

NOTE It should be noted that in a ratio, the order of the terms is very important. For example, in the above illustration the required ratio is 5 : 3 while 3 : 5 is wrong.

So the ratio of any two quantities is expressed as $\frac{a}{b}$ or $a : b$.

The numerator 'a' is called the **antecedent** and denominator 'b' is called as **consequent**.

Rule of Ratio

The comparison of two quantities is meaningless if they are not of the same kind or in the same units (of length, volume or currency etc). We do not compare 8 boys and 6 cows or 15 litres and 5 toys or 5 metres and 25 centimetres. Therefore, to find the ratio of two quantities (of the same kind), it is necessary to express them in same units.

NOTE

1. We do not compare 8 boys and 6 cows, but we can compare the number (8) of boys and number (6) of cows. Similarly, we cannot compare the number (15) of litres and the number (5) of toys etc.
2. Ratio has no units.

PROPERTIES OF RATIOS

1. The value of a ratio does not change when the numerator and denominator both are multiplied by same quantities *i.e.*,

$$\frac{a}{b} = \frac{ka}{kb} = \frac{la}{lb} = \frac{ma}{mb} \text{ etc.}$$

e.g., $\frac{3}{4} = \frac{6}{8} = \frac{9}{12}$ ... etc. have the same ratio.

2. The value of a ratio does not alter (or change) when the numerator and denominator both are divided by same quantities *i.e.*,

$$\frac{a}{b} = \frac{a/k}{b/k} = \frac{a/l}{b/l} = \frac{a/m}{b/m} \text{ etc.}$$

e.g., $\frac{3}{4} = \frac{3/2}{4/2} = \frac{3/3}{4/3} = \frac{3/4}{4/4}$ ... etc are same ratio.

3. The ratio of two fractions can be expressed in ratio of integers. *e.g.*,

$$\frac{3/4}{5/4} = \frac{3}{4} \times \frac{4}{5} = \frac{3}{5}$$

Since $\frac{a/b}{c/d} = \frac{a}{b} \times \frac{d}{c}$ (Refer to the **fractions** in Fundamentals)

4. When two or more than two ratios are multiplied with each other, then it is called as compounded ratio *e.g.*, $\frac{2}{3} \times \frac{4}{5} \times \frac{6}{7} = \frac{16}{35}$ is the compounded ratio of $\frac{2}{3}, \frac{4}{5}, \frac{6}{7}$

So, $\frac{a}{b} \times \frac{c}{d} \times \frac{e}{f} \ldots = \frac{k}{l}$ (compounded ratio)

5. When the ratio is compounded with itself, it is called as duplicate, triplicate ratios etc. *e.g.*,

$\frac{a}{b} \times \frac{a}{b} = \frac{a^2}{b^2} = \left(\frac{a}{b}\right)^2$ is called as duplicate ratio of $\frac{a}{b}$

and $\frac{a}{b} \times \frac{a}{b} \times \frac{a}{b} = \left(\frac{a}{b}\right)^3$ is called as triplicate ratio of $\frac{a}{b}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

Similarly, $\sqrt{\left(\frac{a}{b}\right)}=\left(\frac{a}{b}\right)^{1/2}$ is called as sub-duplicate ratio and $\sqrt[3]{\left(\frac{a}{b}\right)}=\left(\frac{a}{b}\right)^{1/3}$ is called as sub-triplicate ratio of $\frac{a}{b}$.

6. $\frac{a}{b}=\frac{c+am}{d+bm}$ if and only if $\frac{c}{d}=\frac{a}{b}$

i.e., $\frac{30}{40}=\frac{30+3m}{40+4m}=\frac{33}{44}=\frac{36}{48}$ ... etc at $m=1,2,\ldots$

This property is very useful when we compare two fractions

e.g., to compare between $\frac{10}{20}$ and $\frac{12}{22}$

We see that $\frac{10}{20}=\frac{1}{2}$

Now if $\frac{10}{20}$ and $\frac{12}{22}$ are equal then $\frac{12}{22}=\frac{10+m}{22+2m}$

Now putting $m=2$, we don't get the required fraction.

So $\frac{12}{22}\neq\frac{10}{20}$ for any value of m, $\frac{12}{22}\neq\frac{10}{20}$ (in terms of ratio)

7. $\frac{a+k}{b+k}<\frac{a}{b}$ if for every positive k, $\frac{a}{b}>1$

and $\frac{a-k}{b-k}>\frac{a}{b}$

8. $\frac{a+k}{b+k}>\frac{a}{b}$ if for every positive k, $\frac{a}{b}<1$ and $\frac{a-k}{b-k}<\frac{a}{b}$

9. $\frac{a+c}{b+d}>\frac{a}{b}$ if $\frac{c}{d}>\frac{a}{b}$

10. $\frac{a+c}{b+d}<\frac{a}{b}$ if $\frac{c}{d}<\frac{a}{b}$

11. If $\frac{a}{b}=\frac{c}{d}=\frac{e}{f}=\frac{g}{h}=\ldots=k$

then $\frac{a+c+e+g+\ldots}{b+d+f+h+\ldots}=k$

12. Let $\frac{a}{b},\frac{c}{d},\frac{e}{f},\frac{g}{h}\ldots$ be some different ratios, then the value of $\left(\frac{a+c+e+g+\ldots}{b+d+f+h+\ldots}\right)$ must lies between the lowest and highest ratios.

13. If $a:b$ and $b:c$ are given, then

$$a:b:c=\overset{a}{\underset{b}{\downarrow}}\swarrow\overset{b}{\underset{c}{\downarrow}}=(a\cdot b):(b\cdot b):(b\cdot c)$$

14. If the ratios between $a:b$, $b:c$, $c:d$, $d:e$ are given individually, then the combined ratio of $a:b:c:d:e$

$$\begin{matrix}a:b\\b:c\\c:d\\d:e\end{matrix}\quad\begin{matrix}a\\b\\c\\d\end{matrix}\Big|\;:\;\begin{matrix}b\\b\\c\\d\end{matrix}\Big|\;:\;\begin{matrix}b\\c\\c\\d\end{matrix}\Big|\;:\;\begin{matrix}b\\c\\d\\d\end{matrix}\Big|\;:\;\begin{matrix}b\\c\\d\\e\end{matrix}\Big|$$

i.e., $a:b:c:d:e=(a.b.c.d):(b.b.c.d)$
$:(b.c.c.d):(b.c.d.d):(b.c.d.e)$

EXAMPLE 1 *Find the ratio of 25 to 40.*

SOLUTION $\frac{25}{40}=\frac{5\times5}{5\times8}=\frac{5}{8}$

NOTE To get the ratio, we rationalize the fractions by cancelling out the common factors of numerator and denominator.

EXAMPLE 2 *Find the ratio of 90 cm to 1.5 m.*

SOLUTION 1.5 m = 150 cm (units must be same)

So, the required ratio $=\frac{90}{150}=\frac{3}{5}$

EXAMPLE 3 *The number of boys and girls in a school are 576 and 480 respectively. Express the ratio of the number of boys to that of girls in the simplest form.*

SOLUTION Required ratio $=\frac{576}{480}=\frac{6}{5}$ $\left(\because\frac{576}{480}=\frac{96\times6}{96\times5}\right)$

EXAMPLE 4 *Shukla earns Rs. 14,000 per month and Mishra earns Rs. 18,000 per month. Find the ratio of Shukla's salary to Mishra's salary.*

SOLUTION Required ratio $=\frac{14{,}000}{18{,}000}=\frac{7}{9}$

EXAMPLE 5 *Out of 144 persons working in an office, 56 are men and the remaining are women. Find the ratio of number of women to number of men.*

SOLUTION Ratio $=\frac{88}{56}=\frac{11}{7}$ (∵ number of women = 144 − 56)

EXAMPLE 6 *In a club having 100 members, 20 play carrom, 24 play table-tennis and 16 play cricket and the remaining members do not play any game. No member plays more than one game. Find the ratio of the number of members who play.*

(a) *Carrom to the number of those who play table-tennis.*
(b) *Cricket to the number of those who play carrom.*
(c) *Cricket to the number of those who do not play any game.*
(d) *Table-tennis to the number of those who do not play any game.*
(e) *Some game to the number of those who do not play any game.*

SOLUTION Total members = 100
Carrom = 20
Table-tennis = 24
Cricket = 16
No any game = 40

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $\frac{20}{24}=\frac{5}{6}$ (b) $\frac{16}{20}=\frac{4}{5}$

(c) $\frac{16}{40}=\frac{2}{5}$ (d) $\frac{24}{40}=\frac{3}{5}$

(e) $\frac{60}{40}=\frac{3}{2}$

EXAMPLE 7 *A person earns Rs. 1200 per day and spends Rs. 800. Find the ratio of his savings to expenditure.*

SOLUTION $\frac{400}{800}=\frac{1}{2}$ (Savings = Income – Expenditure)

$= 1 : 2$

EXAMPLE 8 *Simplify the following ratios :*

(a) $\frac{1}{6}:\frac{1}{8}$ (b) $2\frac{1}{3}:3\frac{1}{2}$ (c) $\frac{5}{6}:\frac{3}{8}:3\frac{3}{4}$

SOLUTION (a) $\frac{1}{6}:\frac{1}{8}=\frac{1/6}{1/8}=\frac{1}{6}\times\frac{8}{1}=\frac{4}{3}$ or $4:3$

Alternatively: $\frac{1}{6}:\frac{1}{8}=\frac{48}{6}:\frac{48}{8}$ $\left(\text{or } \frac{24}{6}:\frac{24}{8}\right)$

$= 8 : 6 = 4 : 3$

NOTE In case of fractions, convert them to whole numbers by multiplying each term by the L.C.M. of their denominators.

(b) $2\frac{1}{3}:3\frac{1}{2}=\frac{7}{3}:\frac{7}{2}=\frac{7/3}{7/2}=\frac{2}{3}$ or $2:3$

NOTE In case of two fractions if numerators are same, then the required ratio is the inverse ratio of the fractions.

(c) $\frac{5}{6}:\frac{3}{8}:3\frac{3}{4}=\frac{5}{6}:\frac{3}{8}:\frac{15}{4}=\frac{5}{6}\times24:\frac{3}{8}\times24:\frac{15}{4}\times24$

$= 20 : 9 : 90$ {∵ LCM of 6, 8 and 4 is 24}

EXAMPLE 9 *Divide 14 toffees among Ankita and Anshul in the ratio 5 : 2*

SOLUTION According to the question, if there are 7 toffees then Ankita will have 5 and Anshul will have 2 toffees but since there are 14 toffees, which is twice of 7. So Ankita will have 10 toffees and Anshul will have 4 toffees.

SHORTCUT

Ankita	:	Anshul
5	:	2
$14\times\frac{5}{(5+2)}$	:	$14\times\frac{2}{(5+2)}$
10	:	4

EXAMPLE 10 *Three boys are aged 2 years, 4 years and 8 years. They want to divide seventy rupees in the ratio of their ages. How much money would each get?*

SOLUTION The ratio of their ages = $A : B : C = 2 : 4 : 8 = 1 : 2 : 4$

A	:	B	:	C
1	:	2	:	4
$70\times\frac{1}{1+2+4}$	:	$70\times\frac{2}{1+2+4}$	:	$70\times\frac{4}{1+2+4}$
10	:	20	:	40

So A gets Rs. 10, B gets Rs. 20 and C gets Rs. 40 if the ratio of their ages is $2 : 4 : 8$.

EXAMPLE 11 *An amount of Rs. 100 is being divided among two persons in the ratio* $\frac{1}{10}:\frac{1}{15}$. *How much money does each get?*

SOLUTION $\frac{1}{10}:\frac{1}{15}=\frac{1}{10}\times30:\frac{1}{15}\times30=3:2$ (here 30 is the LCM of 10 and 15)

So, the ratio of amount of money $=\frac{3}{5}\times100:\frac{2}{5}\times100$

$= 60$ and 40

EXAMPLE 12 *The lengths of sides of a triangle are in the ratio 2 : 3 : 4. If the perimeter of the triangle is 63 cm, find the lengths of the sides of the triangle.*

SOLUTION Let the sides of triangle be $2x$, $3x$ and $4x$, then $2x + 3x + 4x = 63$

$\Rightarrow \quad 9x = 63 \Rightarrow x = 7$

∴ The sides of triangle $= 2x, 3x, 4x = 14, 21, 28$

Alternatively:

$63\times\frac{2}{(2+3+4)}$ and $63\times\frac{3}{(2+3+4)}$ and $63\times\frac{4}{(2+3+4)}$

$= 14, 21$ and 28.

EXAMPLE 13 *Divide 1224 into three parts such that first part be double that of second part and second part be* $\frac{1}{3}$ *of the third part.*

SOLUTION Let A, B, C be three parts respectively, then

$A : B = 2 : 1$

and $B : C = 1 : 3$

$\therefore A : B : C = 2 : 1 : 3$

$A = 1224\times\frac{2}{6}=408$

$B = 1224\times\frac{1}{6}=204$

$C = 1224\times\frac{3}{6}=612$

EXAMPLE 14 *If* $A : B = 3 : 4$, $B : C = 5 : 2$ *then find the value of* $A : B : C$.

SOLUTION $A : B = 3 : 4$

and $B : C = 5 : 2$

$A : B : C = (3\times5) : (4\times5) : (4\times2)$

or $A : B : C = 15 : 20 : 8$

$\begin{bmatrix}3 & : & 4\\ \downarrow & & \downarrow\\ 5 & : & 2\end{bmatrix}$

EXAMPLE 15 *The ratio of* $A : B = 1 : 3$, $B : C = 2 : 5$, $C : D = 2 : 3$. *Find the value of* $A : B : C : D$.

SOLUTION $A : B = 1 : 3$

$B : C = 2 : 5$

$C : D = 2 : 3$

$A : B : C : D = (1\times2\times2) : (3\times2\times2) : (3\times5\times2) : (3\times5\times3)$

$A : B : C : D = 4 : 12 : 30 : 45$

Scanned by CamScanner

yoursmartboob.wordpress.com

EXAMPLE 16 *There are two types of mixtures of milk and water. In the first mixture, out of 12 litres of mixture, 5 litre is milk only and in the second mixture, 6 litre is milk and 12 litre is water. Which one mixture is better in terms of milk's strength?*

SOLUTION

First Mixture	Second Mixture	
$\frac{5}{12}$	$\frac{6}{18}$	$(6+12=18)$
$\frac{5}{12}\times 36$	$\frac{6}{18}\times 36$	(milk + water = mixture)
15	12	

So the first mixture has more milk in comparison to water.

EXAMPLE 17 *The ratio of salary of $A:B=1:2$, $B:C=3:4$, $C:D=5:6$ and $D:E=7:8$. What is the ratio of salary of A and E?*

SOLUTION

$A:B \quad 1:2$
$B:C \quad 3:4$
$C:D \quad 5:6$
$D:E \quad 7:8$

$A:B:C:D:E=(1\times3\times5\times7):(2\times3\times5\times7)$
$:(2\times4\times5\times7):(2\times4\times6\times7):(2\times4\times6\times8)$

or $A:B:C:D:E=105:210:280:336:384$

So the ratio of salary of $A:E=105:384=35:128$

NOTE In every next step, we leave the left term and adopt right term.

EXAMPLE 18 *If $\frac{a}{b}=\frac{3}{4}$, then find the value of $7a-4b:3a+b$.*

(a) 7 : 1 (b) 5 : 13
(c) 12 : 1 (d) none of these

SOLUTION Simply substitute the value of a and b as 3 and 4 in the given algebraic ratio

as $(7\times3-4\times4):(3\times3+4)=5:13$

EXAMPLE 19 *If $a:b=3:2$ and $b:c=6:5$ then $a:b:c$ is equal to*

(a) 9 : 6 : 5 (b) 9 : 6 : 10
(c) 3 : 3 : 5 (d) 3 : 6 : 5

SOLUTION

$a:b=3:2$
$b:c=6:5$

$a:b:c=(3\times6):(2\times6):(2\times5)$
$=18:12:10=9:6:5$

EXAMPLE 20 *The sum of two natural numbers is 64. Which of the following can not be the ratio of these two numbers?*

(a) 3 : 5 (b) 1 : 3 (c) 7 : 9 (d) 3 : 4

SOLUTION Let the numbers be $3x$ and $5x$, then

$3x+5x=64 \Rightarrow 8x=64$

$\Rightarrow x=8$, which is possible

The numbers are 24, 40.

Take another option:

$x+3x=64 \Rightarrow x=16$

The numbers are 16 and 48.

Check for option (c) :

$7x+9x=64 \Rightarrow 16x=64$

$\Rightarrow x=4$

The numbers are 28 and 36.

Check for option (d)

$3x+4x=64 \Rightarrow 7x=64$

$x=\frac{64}{7}$

Numbers are $\frac{3\times64}{7}$ and $\frac{4\times64}{7}$ or $\frac{192}{7}$ and $\frac{256}{7}$

which are not the natural numbers.

Hence option (d) is the required answer.

EXAMPLE 21 *Monthly incomes of A and B are in the ratio of 4 : 3 and their savings are in the ratio of 3 : 2. If the expenditure of each will be Rs. 600, then the monthly incomes of each are :*

(a) 1800, 2400 (b) 2400, 1600
(c) 2400, 1800 (d) 1600, 1200

SOLUTION Income = Exp. + Savings

$A \rightarrow 4x=3y+600$

$B \rightarrow 3x=2y+600$

Therefore, $4x-3y=600$ and $3x-2y=600$

$\Rightarrow 4x-3y=3x-2y \Rightarrow x=y$

$\therefore 4x-3x=600 \Rightarrow x=600$

Then, the income of $A=4\times600=2400$

and income of $B=3\times600=1800$

Alternatively: Check the options. Consider (c)

Income	A		B	
	2400		1800	
	(4)	:	(3)	$\Rightarrow$ correct
Again,	2400		1800	
	− 600		− 600	
Savings	1800		1200	
	(3)	:	(2)	$\Rightarrow$ correct

Hence, option (c) is correct. If you check other options, the ratio will not match.

EXAMPLE 22 *A, B and C have 40, x and y balls with them respectively. If B gives 20 balls to A, he is left with half as many balls as C. If together they had 60 more balls, each of them would have had 100 balls on an average. What is value of $x:y$?*

(a) 3 : 2 (b) 4 : 6 (c) 2 : 1 (d) 3 : 4

SOLUTION From the last statement

$\frac{100+x+y}{3}=100$

$\Rightarrow x+y=200$ ...(1)

Again from first statement, $\frac{x-20}{y}=\frac{1}{2}$

$\Rightarrow 2x-y=40$ ...(2)

Solving equations (1) and (2), we get

$x=80$ and $y=120$

Therefore, required ratio of $x:y=2:3$

Hence, option (b) is correct.

Alternatively: After forming the equation (1), we can go through the options. Let us assume option (b).

$x+y=200$

$\because x:y=4:6$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow \quad x = 80$ and $y = 120$

Now from the first statement, $\frac{x-20}{y} = \frac{1}{2}$

So $\frac{80-20}{120} = \frac{1}{2}$ (verified)

hence option (b) is correct.

EXAMPLE 23 *The incomes of A, B, C are in the ratio of 12 : 9 : 7 and their spendings are in the ratio 15 : 9 : 8. If A saves 25% of his income. What is the ratio of the savings of A, B and C?*

SOLUTION Income = Expenditure + Saving

$A \rightarrow \quad 12x = 15y + 3x \qquad (3x = 25\% \text{ of } 12x)$

$B \rightarrow \quad 9x = 9y + (9x - 9y)$

$C \rightarrow \quad 7x = 8y + (7x - 8y)$

Therefore, $12x - 3x = 15y$

$\Rightarrow \quad \frac{x}{y} = \frac{5}{3}$

$\Rightarrow \quad y = \frac{3x}{5}$

Therefore, savings = (income − expenditure)

$A = 12x - 9x = 3x$

$B = 9x - \frac{27}{5}x = \frac{18}{5}x$

$C = 7x - \frac{24}{5}x = \frac{11}{5}x$

i.e., the ratio of savings of $A : B : C = 3x : \frac{18}{5}x : \frac{11}{5}x$

$= 15x : 18x : 11x$

$= 15 : 18 : 11$

EXAMPLE 24 *There are total 100 coins consisting of 20 paise, 50 paise and Re 1 in the ratio of 7 : 8 : 5. What is the no. of coins of 50 paise if the difference between the amount yielded by 20 paise and Re. 1 coin is 18?*

(a) 32 *(b) 40* *(c) 26* *(d) 56*

SOLUTION $(20 \times 7x) - (100 \times 5x) = 1800$ (Rs. 18 = 1800 paise)

$(140x) - (500x) = 1800$

$\Rightarrow \quad 360x = 1800$

$\Rightarrow \quad x = 5$

Therefore, number of coins of 50 paise $= 8 \times 5 = 40$

Alternatively: Let there be 40 coins of 50 paise denomination, then

The no. of coins of $A, B, C = 7x : 8x : 5x = 35 : 40 : 25$

Therefore, the amount from 20 paise coins = 35×20 = Rs. 7

and amount from Re 1 coins = 1×25 = Rs. 25

Hence difference = Rs. 18 (25 − 7)

Thus the presumed option is correct.

EXAMPLE 25 *There are 43800 students in 4 schools of a city. If half of the first, two-third of the second, three-fourth of the third and four-fifth of the fourth are the same number of students, then find the ratio of number of students of A and D if A, B, C and D be the first, second, third and fourth schools respectively.*

SOLUTION $\frac{A}{2} = \frac{2B}{3} = \frac{3C}{4} = \frac{4D}{5}$

Therefore, $\frac{A}{B} = \frac{4}{3}$ and $\frac{B}{C} = \frac{9}{8}$ and $\frac{C}{D} = \frac{16}{15}$

$\therefore \quad A : B = 4 : 3$

$B : C = 9 : 8$

$C : D = 16 : 15$

$\therefore \quad A : B : C : D = (4 \times 9 \times 16) : (3 \times 9 \times 16)$

$: (3 \times 8 \times 16) : (3 \times 8 \times 15)$

$A : B : C : D = 576 : 432 : 384 : 360$

Therefore, the ratio of number of students of A and D = 576 : 360 = 8 : 5

Alternatively: $\frac{A}{2} = \frac{2}{3}B = \frac{3}{4}C = \frac{4}{5}D = k$

then $A : B : C : D = 2k : \frac{3}{2}k : \frac{4}{3}k : \frac{5}{4}k$

$= 24k : 18k : 16k : 15k$

$\therefore \quad A : B : C : D = 24 : 18 : 16 : 15$

$\therefore \quad A : D = 24 : 15 = 8 : 5$

PROPORTION

An equality of two ratios is called a proportion and we say that the four numbers are in proportion.

i.e., if $\frac{a}{b} = \frac{c}{d}$, or $a : b = c : d$, then we say that a, b, c and d are in proportions and written as $a : b :: c : d$, where the symbol '::' indicates proportion and it is read as 'a is to b as c is to d'.

Here a and d are called **"extremes"** (or extreme terms) and b and c are called as **"means"** (or middle terms). Thus four numbers are said to be in proportion, if the ratio of the first to the second number is equal to the ratio of the third to the fourth number. *e.g.*, 2 : 3 :: 4 : 6. Some important results are derived from the discussion of proportion, which are very important for clear understanding.

Properties of Proportion

1. If four numbers (quantities) are in proportion then product of the extremes is equal to the product of the means and if these are not in proportion, then product of extremes is not equal to the product of the means.

   i.e., if $a : b :: c : d$,

   then $a \times d = b \times c$

   Thus it is clear that if three out of four terms of a proportion are given, then we can find the fourth term by dividing the product of means (or extremes) by the remaining term.

2. If a, b and c are three numbers such that $a : b = b : c$ then these numbers a, b, c are said to be in **continued proportion** or simply in proportion.

Scanned by CamScanner

yoursmahboob.wordpress.com

i.e., $a : b = b : c \Rightarrow b^2 = ac$

Here b is said to be the **mean proportional** between a and c, and c is said to be the **third proportional** to a and b. *e.g.*, $3 : 9 :: 9 : 27$

Here $9 \times 9 = 3 \times 27$ which are in continued proportion.

NOTE Sometimes the above idea is also expressed by saying that the three numbers are in the ratio 3 : 9 : 27. Thus if three quantities are proportionals, the first is to the third as the duplicate ratio of the first to the second.

i.e., if $a : b :: b : c$
then $a : c = a^2 : b^2$

$$\left[\because \frac{a}{b} = \frac{b}{c} \Rightarrow \frac{a^2}{b^2} = \frac{ab}{bc} \Rightarrow \frac{a^2}{b^2} = \frac{a}{c} \Rightarrow a : c = a^2 : b^2\right]$$

Some Facts about Proportion

(a) Invertendo: If $\frac{a}{b} = \frac{c}{d} \Rightarrow \frac{b}{a} = \frac{d}{c}$

(b) Alternando: If $\frac{a}{b} = \frac{c}{d} \Rightarrow \frac{a}{c} = \frac{b}{d}$

NOTE Each of the two results (a) and (b) can be obtained by cross product.

(c) Componendo: If $\frac{a}{b} = \frac{c}{d} \Rightarrow \left(\frac{a+b}{b}\right) = \left(\frac{c+d}{d}\right)$

(d) Dividendo: If $\frac{a}{b} = \frac{c}{d} \Rightarrow \left(\frac{a-b}{b}\right) = \left(\frac{c-d}{d}\right)$

(e) Componendo and Dividendo: If $\frac{a}{b} = \frac{c}{d}$

$$\Rightarrow \left(\frac{a+b}{a-b}\right) = \left(\frac{c+d}{c-d}\right)$$

NOTE The result (e) can be obtained by dividing result (c) by result (d).

EXAMPLE 1 *The first, second and fourth terms of a proportion are 5, 15 and 90 respectively. Find the third term.*

SOLUTION Let the third term be x, then 5, 15, x, 90 are in proportion *i. e.*, $5 : 15 :: x : 90$

$\Rightarrow$ $5 \times 90 = 15 \times x$ (by the I[st] property)

$\Rightarrow$ $x = 30$

EXAMPLE 2 *The ratio of length to width of a rectangular sheet of paper is 5 : 3 If the width of the sheet is 18 cm, find its length.*

SOLUTION Let the length of sheet of paper be x cm. Then the ratio of length to width $= x : 18$

Thus $x : 18 = 5 : 3$

$\Rightarrow$ $x \times 3 = 18 \times 5$

$\Rightarrow$ $x = 30$

Hence the length of paper = 30 cm.

EXAMPLE 3 *If 81, x, x, 256 are in proportion, find x.*

SOLUTION $81 : x :: x : 256$

$\Rightarrow$ $81 \times 256 = x \times x \Rightarrow x = 144$

EXAMPLE 4 *The ratio between the number of men and women in an office is 5 : 7. If the number of women working in the office is 56, find the number of men working in the office.*

SOLUTION $5 : 7 = x : 56$ (suppose number of men = x)

$\Rightarrow$ $x = 40$ (by the first property)

Therefore, number of men in the office = 40

EXAMPLE 5 *The age of Chandi and Radhika are in the ratio 5 : 3 If Chandi's age is 20 years, find the age of Radhika.*

SOLUTION $5 : 3 = 20 : x$

$\Rightarrow$ $x = \frac{3 \times 20}{5}$ (by the first property)

$\Rightarrow$ $x = 12$

Hence the age of Radhika is 12 years.

EXAMPLE 6 *The ratio of the number of boys to that of girls in a school is 9 : 11. If the number of girls in the school is 2035, find :*
(a) number of boys in school
(b) number of students in school.

SOLUTION (a) $9 : 11 = x : 2035$

$\Rightarrow$ $x = \frac{9 \times 2035}{11}$

$x = 1665$ (number of boys)

(b) number of students
= number of boys + number of girls = 3700

EXAMPLE 7 *What is the least possible number which must be subtracted from 16, 19 and 23 so that the resulting numbers are in continued proportion?*
(a) 2 *(b) 4* *(c) 6* *(d) 7*

SOLUTION Going through options, we find option (d) is correct.

Alternatively:

$(16 - x) : (19 - x) :: (19 - x) : (23 - x)$

$\Rightarrow$ $(19 - x)^2 = (16 - x)(23 - x)$

By solving the above equation, we get $x = 7$

EXAMPLE 8 *If $(a + b) : (a - b) = 15 : 1$, then the value of $a^2 - b^2$ is:*
(a) 56 *(b) 15* *(c) 112* *(d) 8*

SOLUTION $\frac{(a+b)}{(a-b)} = \frac{15}{1}$

$\Rightarrow$ $\frac{a}{b} = \frac{8}{7}$ (by componendo and dividendo)

therefore $a^2 - b^2 = 64 - 49 = 15$

EXAMPLE 9 *The mean proportional between 8 and 98 is :*
(a) 16 *(b) 53* *(c) 112* *(d) 28*

SOLUTION $8 : x :: x : 98$

$x^2 = 8 \times 98$

$\Rightarrow$ $x = 28$

Hence (d) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 10 *The students in three classes are in the ratio of 2 : 3 : 4. If 40 students are added in each class, the ratio becomes 4 : 5 : 6. Find the total number of students in all the three classes is :*
(a) 270 (b) 180 (c) 126 (d) 135

SOLUTION
$2x + 40 = 4y$ ...(i)
$3x + 40 = 5y$ ...(ii)
$4x + 40 = 6y$ ...(iii)
Therefore $2x = 40$
$\Rightarrow$ $x = 20$
Hence, total number of students $= 2x + 3x + 4x = 9x$
$= 9 \times 20 = 180$

Alternatively: It can be solved through options also.

EXAMPLE 11 *The dimensions of a photograph are 4 and 1.8 cms. If the breadth of the enlarged photo is 4.5 cm and it was enlarged proportionally then what is the new length of new photograph?*
(a) 6 (b) 5.4 (c) 10 (d) 9

SOLUTION
$4 : 1.8 = x : 4.5$
$\Rightarrow$ $x = 10$
Thus, the length of new photograph is 10 cm.

EXAMPLE 12 *Two equal containers are filled with the mixture of milk and water. The concentration of milk in each of the containers is 20% and 25% respectively. What is the ratio of water in both the containers respectively?*
(a) 15 : 16 (b) 16 : 15 (c) 4 : 5 (d) 5 : 4

SOLUTION

Milk	20%	25%
Water	80%	75%

Thereofre, required ratio $= \frac{80}{75} = \frac{16}{15}$ or 16 : 15

EXAMPLE 13 *A cat takes 7 steps for every 5 steps of a dog, but 5 steps of a dog are equal to 6 steps of cat. What is the ratio of speed of cat to that of dog?*
(a) 24 : 25 (b) 42 : 25 (c) 24 : 19 (d) 25 : 42

SOLUTION

	CAT	DOG
Given speed	7 steps	5 steps

but the length of 5 steps of dog = length of 6 steps of cat
it means the ratio of length covered by dog is to cat $= \frac{6}{5}$
Therefore, in each step a dog will cover $\frac{6}{5}$ times distance than that of a cat.
Thus the ratio of actual speed of cat is to dog
$= 7 : 5 \times \frac{6}{5} = 7 : 6$

SHORTCUT Actual speed of $A : B$
$= \frac{\text{Given speed of } A}{\text{no. of steps of } A \text{ in terms of length}} : \frac{\text{Given speed of } B}{\text{no. of steps of } B \text{ in terms of length}}$
$= \text{CAT} : \text{DOG}$
$= \frac{7}{6} : \frac{5}{5} = 7 : 6$

EXAMPLE 14 *A camel pursue an elephant and takes 5 leaps for every 7 leaps of the elephant, but 5 leaps of elephant are equal to 3 leaps of camel. What is the ratio of speeds of camel and elephant?*

SOLUTION Ratio of speed of camel and elephant
$= \frac{5}{3} : \frac{7}{5} = \frac{5}{3} \times 15 : \frac{7}{5} \times 15$
$= 25 : 21$

UNITARY METHOD

A method in which the value of a quantity is first obtained to find the value of any required quantity is called unitary method.

In solving problems based on unitary method.

Direct Proportion

Two quantities are said to be directly proportional if the increase (or decrease) in one quantity causes the increase (or decrease) in the other quantity by same proportion. *e.g.,*

(i) The cost of articles varies directly to the number of articles. More articles more cost, less articles less cost.

(ii) The work done varies directly to the number of men (work force) at work. More men at work, more work done in same time. Less men, less work done in same time.

Inverse Proportion

Two quantities are said to vary inversely if the increase (or decrease) in one quantity causes the decrease (or increase) in the other quantity by same proportion *e.g.,* The time taken to finish a work varies inversely to the number of men at work.

More men at work, less time taken to finish the same work. Less men at work, more time taken to finish the same work.

EXAMPLE 1 *If 6 note books cost Rs. 45, how much would 8 notebooks cost?*

SOLUTION More note books more cost; less note books, less cost

Note books	Cost
6	45
1	45/6
8	$\frac{8 \times 45}{6} = 60$

Hence 8 note books cost Rs. 60.

EXAMPLE 2 *If 45 students can consume a stock of food in 2 months, find for how many days the same stock of food will last for 27 students?*

SOLUTION More students, less days; less students, more days

Students	Days
45	60
1	60×45
27	$\frac{60 \times 45}{27} = 100$ days

Scanned by CamScanner

yourSmartboob.wordpress.com

EXAMPLE 3 *A man working 8 hours a day takes 5 days to complete a project. How many hours a day must he work to complete it in 4 days?*

SOLUTION 'More days, less hours; less days, more hours'

Days	Hours
5	8
1	5×8
4	$\frac{5 \times 8}{4} = 10$ hours a day

VARIATION

When two or more quantities are dependent upon each other and then if any one of them is changed, the other (dependent) quantity is also changed.

For example :

(i) When the salary of a person increases, then its savings/expenditure increases.

(ii) When the number of guests in a hotel/number of students in a hostel/number of employees changes, their respective expenses increases.

Basically, as it happens in direct proportion and inverse proportion, there are two types of variation :

(i) Direct variation (ii) Inverse variation

Direct Variation

A quantity A is said to vary directly if the increase (or decrease) in B yields increase (or decrease) in A but not in proportion. It is expressed as

$$A \propto B \Rightarrow A = KB,$$

where K is called proportionality constant

$$\Rightarrow \quad K = \frac{A}{B}$$

Inverse Variation

A quantity A is said to vary inversely if the increase (or decrease) in B yields decrease (or increase) in A but not in same proportion. It is expressed as

$$A \propto \frac{1}{B} \Rightarrow A = \frac{K}{B}$$

or $K = AB$, K is called as proportionality constant.

NOTE

1. If it is not mentioned that a particular quantity is inversely variable, then it means the given quantity is directly variable.
2. A quantity sometimes vary jointly *i.e.*, directly on any quantity and inversely on another quantity.

e.g., $A \propto B$ and $A \propto \frac{1}{C}$

It means $A \propto \frac{B}{C} \Rightarrow A = \frac{KB}{C}$

Here A varies directly as B but inversely as C.

Also it can vary as only directly or inversely as more than one quantities.

e.g., $A \propto BC \Rightarrow A = KBC$

and $A \propto \frac{1}{BC} \Rightarrow A = \frac{K}{BC}$

EXAMPLE 1 *A varies directly as B and inversely as C. A is 12 when B is 6 and C is 2. What is the value of A when B is 12 and C is 3?*

SOLUTION $A \propto B$ and $A \propto \frac{1}{C}$

$$\Rightarrow \quad A \propto \frac{B}{C} \Rightarrow A = K\frac{B}{C}$$

when $A = 12, B = 6, C = 2$, then

$$12 = K\frac{6}{2} \Rightarrow K = 4$$

Again $A = K\frac{B}{C} = 4 \times \frac{12}{3} = 16$

$$\Rightarrow \quad A = 16$$

EXAMPLE 2 *The value of a coin varies directly to the square of its radius, when its thickness is constant. The radius of a coin is 1.5 cm and its value is Rs. 2. What will be the radius of a coin if its value is Rs. 5?*

SOLUTION $V \propto r^2$

$$\Rightarrow \quad V = Kr^2$$

$$2 = K \times (1.5)^2$$

$$\Rightarrow \quad K = \frac{2}{2.25}$$

$$K = \frac{8}{9}$$

Again $5 = \frac{8}{9} \times r^2$

$$\Rightarrow \quad r^2 = \frac{5 \times 9}{8}$$

$$\therefore \quad r = \frac{3}{2} \times \sqrt{\frac{5}{2}}$$

$$= 1.5 \times \sqrt{2.5} = 1.5 \times 1.6$$

$$r \approx 2.4 \text{ cm}$$

Hence, required radius = 2.4 cm

PROBLEMS BASED ON AGES

This article is very suitable as an appendix of Ratio-proportion, since most of the questions based on ages involve the concept of ratio-proportion. *e.g.*, the age of Ravi is 16 years and the age of her mother is twice etc. or the ratio of the ages of the father and son at present is 3 : 1. 4 years, earlier the ratio was 4 : 1. What is the present ages of the father and son etc.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *The ratio of ages of Krishna and Balram is 3 : 4. Four years earlier the ratio was 5 : 7. Find the present ages of Krishna and Balram :*

(a) 15 years, 20 years *(b) 24 years, 32 years*

(c) 16 years, 20 years *(d) 32 years, 24 years*

SOLUTION Let the present age of Krishna and Balram be $3x$ and $4x$, then

four years ago their ages be $(3x - 4)$ and $(4x - 4)$

So $$\frac{(3x-4)}{(4x-4)} = \frac{5}{7}$$

$$\Rightarrow \quad 7(3x - 4) = 5(4x - 4)$$

$$\Rightarrow \quad 21x - 28 = 20x - 20$$

$$\Rightarrow \quad x = 8$$

$\therefore$ Present age of Krishna $= 3x = 24$ years

and age of Balram $= 4x = 32$ years

EXAMPLE 2 *The ratio of age of Aman and her mother is 3 : 11. The difference of their ages is 24 years. What will be the ratio of their ages after 3 years?*

SOLUTION Let the present age of Aman and her mother be $3x$ and $11x$ then 3 years later their ages will be $(3x + 3)$ and $(11x + 3)$ respectively.

Again $11x - 3x = 24$

$$\Rightarrow \quad 8x = 24 \Rightarrow x = 3$$

Therefore the ratio of their ages 3 years after

$$= \frac{3x+3}{11x+3} = \frac{12}{36} = \frac{1}{3}$$

EXAMPLE 3 *The age of Sachin is 4 times that of his son. Five years ago Sachin was nine times as old as his son was at that time. The present age of the Sachin is :*

(a) 25 years *(b) 36 years*

(c) 32 years *(d) 48 years*

SOLUTION Let the age of son is x years, then the age of Sachin will be $4x$ years.

$$\therefore \quad (4x - 5) = 9(x - 5) \Leftrightarrow x = 8$$

$\therefore$ Age of Sachin is 32 years.

EXAMPLE 4 *The ratio of Varun's age and his mother's age is 5 : 11. The difference of their ages is 18 years. The ratio of their ages after 5 years will be :*

(a) 19 : 59 *(b) 2 : 3* *(c) 37 : 75* *(d) 10 : 19*

SOLUTION Let their ages be $5x$ and $11x$.

$$11x - 5x = 18 \Leftrightarrow x = 3$$

So their present ages are 15 and 33 years. Therefore, ratio of their ages after 5 years $= 20 : 38 = 10 : 19$.

PARTNERSHIP

When two or more than two people run a business jointly by investing their money/resources, then it is called a joint venture or the business in partnership.

All these people, who have invested their resources, are called as Partners.

Partners are basically of two types

(i) **Working partner:** A partner who is directly involved with day-to-day activities of business is called as working partner.

(ii) **Sleeping partner:** A partner who just invests his or her money is called as sleeping partner.

General rules of partnership :

(i) If the partners invest different amounts for the same period of time, then the profits of all the partners are shared in the ratio of their investments.

(ii) If the partners invest same amount for the different time periods, then the profits of all the partners are shared in the ratio of time periods for which their amounts were invested.

(iii) If the partners invest different amounts for different time periods, then their profits are shared in the ratio of products of respective investments with the time period for each partner, individually.

Thus gain or loss is divided in the ratio of 'money-time' capitals.

NOTE Sometimes different problems are solved on the basis of partnership to find the expenses.

EXAMPLE 1 *Bhanu and Shafeeq started a business by investing Rs. 36,000 and Rs. 63,000. Find the share of each, out of an annual profit of Rs. 5,500.*

SOLUTION Ratio of shares of Bhanu and Shafeeq

$= 36000 : 63,000 = 4 : 7$

$\therefore$ Share of Bhanu $= 5500 \times \frac{4}{11} =$ Rs. 2000

and Share of Shafeeq $= 5500 \times \frac{7}{11} = 3500$

EXAMPLE 2 *A starts some business with Rs. 50,000. After 3 months B joins him with Rs. 70,000. At the end of the year, in what ratio should they share the profits?*

SOLUTION Ratio of amount of A and $B = 50,000 : 70,000$

Ratio of time periods for A and $B = 12 : 9$

$\therefore$ Ratio of their money-time capital

Investments $= 50000 \times 12 : 70000 \times 9 = 20 : 21$

EXAMPLE 3 *Harsh Vardhan started a business by investing Rs. 36,000. After 4 months Gyan Vardhan joined him with some investment. At the end of the year, the total profit was divided between them in the ratio of 9 : 7. How much capital was invested by Gyan Vardhan in the business?*

SOLUTION $$\frac{36,000 \times 12}{x \times 8} = \frac{9}{7}$$

$$\Rightarrow \quad x = 42,000$$

$\therefore$ Gyan Vardhan invested Rs. 42,000 for 8 months only.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 4 *A started some business with Rs. 26,000. After 3 months B joined him with Rs. 16,000. After some more time C joined them with Rs. 25,000. At the end of the year, out of a total profit of Rs. 15,453, C gets Rs. 3825 as his share. How many months after B joined the business did C join?*

SOLUTION Ratio (of share) of profits

$= 26,000 \times 12 : 16000 \times 9 : 25000 \times C$

$= 312 : 144 : 25C$

Now C's share $= \frac{25C}{456 + 25C} = \frac{3825}{15453}$

$\Rightarrow \quad C = 6$

$\therefore$ Therefore C joined 3 months later than B joined.

EXAMPLE 5 *A, B and C started a business with their investments in the ratio 1 : 2 : 4. After 6 months A invested the half amount more as before and B invested twice the amount as before while C withdrew $\frac{1}{4}$th of the their investments. Find the ratio of their profits at the end of the year.*

SOLUTION Let us assume their initial investments were x, $2x$ and $4x$ respectively.

Therefore, ratio of their investments during the whole year

$= (x \times 6 + \frac{3x}{2} \times 6) : (2x \times 6 + 4x \times 6) : (4x \times 6 + 3x \times 6)$

$= 15x : 36x : 42x$

$= 5x : 12x : 14x$

$= 5 : 12 : 14$

$\therefore$ Ratio of their profits $= 5 : 12 : 14$

EXAMPLE 6 *A started a business with Rs. 52,000 and after 4 months B joined him with Rs. 39,000. At the end of the year, out of the total profits B received total Rs. 20,000 including 25% of the profits as commission for managing the business. What amount did A receive?*

SOLUTION Profit's share of A and B

$= 52,000 \times 12 : 39,000 \times 8 = 2 : 1$

Let the profit be Rs. x, then B receives 25% as commission for managing business, the remaining 75% of the total profit x is shared between A and B in the ratio 2 : 1. Hence B will get $\frac{1}{3}$rd part of this in addition to his commission. Hence his total earning

$= 0.25x + \frac{1}{3} \times 0.75x$

$= 0.5x = 20,000$

$\Rightarrow \quad x = 40,000$

So, the remaining profit goes to A, hence the profit of A is Rs. 20,000.

EXAMPLE 7 *A working partner gets 20% as his commission of the profit after his commission is paid. If the working partner's commission is Rs. 8000, then what is the total profit in the business?*

SOLUTION Let the total profit be Rs. x. The remaining profit after paying 20% working partner's commission $= (x - 8000)$. Again since 20% of this is working partner's commission,

therefore $\frac{20}{100} \times (x - 8000) = 8000$

$\Rightarrow \quad x = 48,000$

$\therefore$ The total profit in the business is Rs. 48,000.

UNITARY METHOD

INTRODUCTORY EXERCISE-4.1

1. If 40 articles cost Rs. 180, the cost of 18 articles is :
   (a) Rs. 18 (b) Rs. 36
   (c) Rs. 81 (d) Rs. 40.5
2. If 20 persons can do a piece of work in 7 days, then the number of persons required to complete the work in 28 days :
   (a) 4 (b) 5
   (c) 14 (d) 10
3. If 20 men can reap a field in 38 days, in how many days will 19 men reap the field?
   (a) 21 days (b) 19 days
   (c) 76 days (d) 40 days
4. A rope makes 260 rounds of a cylinder with base radius 20 cm. How many times can it go round a cylinder with base radius 26 cm?
   (a) 130 (b) 300
   (c) 200 (d) 150
5. A garrison of 750 men has provision for 20 weeks. If at the end of 4 weeks they are reinforced by 450 men, how long will the remaining provision last?
   (a) 10 weeks (b) 11 weeks
   (c) 15 weeks (d) 16 weeks
6. 40 men can build a wall 20 m high in 15 days. The number of men required to build a similar wall 25 m high in 6 days will be :
   (a) 100 (b) 125
   (c) 150 (d) 200
7. Cost of erecting a fence round a square field of 625 hectares at 15 paise per metre is :
   (a) Rs. 500 (b) Rs. 750
   (c) Rs. 100 (d) Rs. 1500
8. 56 workers can reap a field in 8 days. If the work is to be completed in 7 days, the extra workers needed are :
   (a) 7 (b) 8
   (c) 14 (d) 16
9. If 5 persons weave 180 shawls in 12 days, how many shawls will 6 persons weave in 15 days?
   (a) 260 (b) 370
   (c) 270 (d) 360

Scanned by CamScanner

yoursmahboob.wordpress.com

10. 15 men take 42 days of 4 hours each to do a piece of work. How many days of 6 hours each would 21 women take if 3 women do as much work as 2 men?
(a) 15 (b) 22
(c) 25 (d) 30

11. 10 engines consume 80 litres diesel when each is running 9 hours a day., How much diesel will be required for 10 engines, each running 15 hours a day, whereas 6 engines of the former type consume as much as 5 engines of latter type?
(a) 160 litre (b) 75 litre
(c) 80 litre (d) $111\frac{1}{9}$ litre

12. If $\frac{3}{5}$th of a cistern is filled in 30 minutes, how much more time will be required to fill the rest of it?
(a) 50 minutes (b) 20 minutes
(c) 15 minutes (d) 45 minutes

AGE RELATED PROBLEMS

INTRODUCTORY EXERCISE-4.2

1. Amit is as much younger to Barkha as he is older to Chaman. If the sum of the ages of Barkha and Chaman is 48 years, what is the present age of Amit?
(a) 18 years (b) 36 years
(c) 24 years (d) 28 years

2. Bipin is 6 times old as Alok. Bipin's age will be twice of Chandan's age after 10 years. If Chandan's 7th birthday was celebrated 3 years ago, what is Alok's present age?
(a) 15 years (b) 12 years
(c) 5 years (d) none of these

3. Renuka got married 8 years ago. Today her age is $1\frac{1}{3}$ times her age at the time of marriage. Her daughter's age is 1/8 times her age. Her daughter's age is :
(a) 3 years (b) 4 years
(c) 6 years (d) 8 years

4. Ten years ago *B* was twice of *A* in age. If the ratio of their present ages is 4 : 3, what is the sum of their present ages?
(a) 25 years (b) 30 years
(c) 40 years (d) 35 years

5. The sum of the ages of Aryabhatta and Shridhar is 45 years. Five years ago the product of their ages was 4 times the Aryabhatta's age at that time. The present ages of Aryabhatta and Shridhar respectively are :
(a) 25 and 20 (b) 35 and 10
(c) 36 and 9 (d) 40 and 5

PARTNERSHIP

INTRODUCTORY EXERCISE-4.3

1. A company make a profit of Rs. 9,00,000, 20% of which is paid as taxes. If the rest is divided among the partners *P*, *Q* and *R* in the ratio of $1 : 1\frac{1}{2} : 2$, then the shares of *P*, *Q* and *R* are respectively :
(a) 2,40,000; 3,20,000; 1,60,000
(b) 3,20,000; 2,40,000; 1,60,000
(c) 1,60,000; 3,20,000; 2,40,000
(d) 1,60,000; 2,40,000; 3,20,000

2. We have to divide a sum of Rs. 13,950 among three persons *A*, *B* and *C*. *B* must get the double of *A*'s share and *C* must get Rs. 50 less than the double of *B*'s share. The share of *A* will be :
(a) Rs. 1950 (b) Rs. 1981.25
(c) Rs. 2000 (d) Rs. 2007.75

3. *A* started business with Rs. 45,000 and *B* joined afterward with Rs. 30,000. If the profits at the end of one year were divided in the ratio 2 : 1 respectively, then *B* would have joined *A* for business after :
(a) 1 month (b) 2 months
(c) 3 months (d) 4 months

4. *A* and *B* are partners in a business. They invest in the ratio 5 : 6, at the end of 8 months *A* withdraws. If they receive profits in the ratio of 5 : 9, find how long *B*'s investment was used?
(a) 12 months (b) 10 months
(c) 15 months (d) 14 months

5. Four milkmen rented a pasture. *A* put to graze 16 cows for 3 months, *B* 20 cows for 4 months, *C* 18 cows for 6 months and *D* 42 cows for 2 months. If *A*'s share of rent be Rs. 2400, the rent paid by *C* is :
(a) Rs. 3200 (b) Rs. 4200
(c) Rs. 4000 (d) Rs. 5400

6. *A*, *B* and *C* subscribe Rs. 47000 for a business. If *a* subscribes Rs. 7000 more than *B* and *B* Rs. 5000 more than *C*, then out of total profit of Rs. 4700, *C* receives :
(a) Rs. 1200 (b) Rs. 4500
(c) Rs. 1000 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

RATIO AND PROPORTION

INTRODUCTORY EXERCISE-4.4

1. If $A:B = 4:5$, $B:C = 3:4$, $C:D = 7:11$, then $A:D$ is :
   (a) 3 : 4 (b) 21 : 55
   (c) 21 : 44 (d) 7 : 5

2. Mean proportional between 17 and 68 is :
   (a) 51 (b) 24
   (c) 4 (d) 34

3. Third proportional between 16 and 36 is :
   (a) 64 (b) 144
   (c) 81 (d) 49

4. If $a:b = 2:3$, then $(5a + b):(3a + 2b)$ is :
   (a) 13 : 12 (b) 15 : 17
   (c) 12 : 13 (d) 13 : 11

5. $a = 2b = 3c = 4d$, then $a:b:c:d$ is :
   (a) 12 : 3 : 6 : 4 (b) 3 : 4 : 6 : 12
   (c) 6 : 12 : 4 : 3 (d) 12 : 6 : 4 : 3

6. The fourth proportional to 4, 7 and 20 is :
   (a) 28 (b) 21
   (c) 18 (d) 35

7. If $\sqrt{2}:(1+\sqrt{3}) :: \sqrt{6}:x$, then x is equal to :
   (a) $1+\sqrt{3}$ (b) $\sqrt{3}-1$
   (c) $\sqrt{3}+3$ (d) $2\sqrt{3}$

8. If $\frac{a}{3} = \frac{b}{4} = \frac{c}{5}$ then $\frac{a+b+c}{b} = ?$
   (a) 2 (b) 3
   (c) 4 (d) 5

9. If $\frac{a}{b} = \frac{c}{d}$, then :
   (a) $\frac{a+b}{a-b} = \frac{c+d}{c-d}$ (b) $\frac{a+b}{a^2} = \frac{c+d}{d^2}$
   (c) $\frac{a+b}{a^2} = \frac{c+d}{c^2}$ (d) $ac = bd$

10. If $a:b = b:c = c:d$ then $\frac{a}{b}, \frac{b}{c}, \frac{c}{d}$ are :
    (a) in AP
    (b) in continued proportion
    (c) in GP
    (d) both (b) and (c)

11. If $(a+b):(a-b) = 3:2$, the $(a^2-b^2):(a^2+b^2)$ equals :
    (a) 5 : 13 (b) 12 : 13
    (c) 9 : 4 (d) none of these

12. Two whole numbers, whose sum is 64, can not be in the ratio :
    (a) 1 : 7 (b) 3 : 5
    (c) 5 : 11 (d) 1 : 2

13. Two numbers are in the ratio 3 : 4. The difference between their squares is 28. Find the greater number :
    (a) 12 (b) 8
    (c) 24 (d) 16

14. If a, b, c, d, e, f, g are in continued proportion, then the value of $a.b.c.e.f.g$ is :
    (a) d^3 (b) d^7
    (c) d^6 (d) none of these

15. If A and B shared Rs. 1300 in the ratio 1 : 12, how much did A get?
    (a) 120 (b) 1200
    (c) 100 (d) 1000

16. Rs. 3960 are divided among A, B and C so that half of A's part, one-third of B's part and one-sixth of C's part are equal. Then C's part is :
    (a) 720 (b) 2160
    (c) 1080 (d) 810

17. A sum of Rs. 21000 is divided among A, B, C such that shares of A and B are in the ratio of 2 : 3 and those of B and C are in the ratio 4 : 5. The amount received by A is :
    (a) Rs. 6000 (b) Rs. 4500
    (c) Rs. 4800 (d) Rs. 8400

18. A certain amount was divided between A and B in the ratio 7 : 9. If B's share was Rs. 7200, the total amount was :
    (a) Rs. 1280 (b) Rs. 6300
    (c) Rs. 5600 (d) Rs. 12800

19. Rs. 11250 are divided among A, B and C so that A may receive one-half as much as B and C together receive and B receives one-fourth of what A and C together receive. The share of A is more than that of B by :
    (a) Rs. 2500 (b) Rs. 1500
    (c) Rs. 1800 (d) Rs. 650

20. A girl 1.2 metre tall casts a shadow 1.1 m at the time when a building casts a shadow 6.6 m long. The height of the building is :
    (a) 2.7 m (b) 7.2 m
    (c) 6.0 m (d) 5.5 m

21. The prices of Bajaj Scooter and Bajaj Pulser are in the ratio of 4 : 9. If the Bajaj Pulser costs Rs. 30,000 more than a Bajaj Scooter, the price of Bajaj Pulser is :
    (a) Rs. 63,000 (b) Rs. 45,000
    (c) Rs. 54,000 (d) Rs. 60,000

22. What is the ratio whose terms differ by 40 and the measure of which is 2/7?
    (a) 16 : 56 (b) 14 : 49
    (c) 15 : 36 (d) 16 : 72

23. Two numbers are in the ratio 3 : 5. If 9 be subtracted from each, then they are in the ratio of 12 : 23. The second number is :
    (a) 53 (b) 54
    (c) 55 (d) 52

24. Consider the following statements :
    (1) If both the terms of a ratio are multiplied or divided by the same natural number, then the ratio remains unaltered.

Scanned by CamScanner

yoursmahboob.wordpress.com

(2) A statement which states that two ratios are equivalent is called proportion.

(3) If 4 quantities are in proportion, the product of extremes is not equal to the means.

(4) The mean proportion between any two numbers is equal to the square root of their product. The wrong one statements is/are :

(a) 1 (b) 3
(c) 3 and 4 (d) 1 and 4

25. In a mixture of 120 litres, the ratio of milk and water is 2 : 1. If the ratio of milk and water is 1 : 2, then the amount of water (in litres) is required to be added is :

(a) 20 (b) 40
(c) 80 (d) 120

26. A quantity x varies inversely as the square of y. Given that $x = 4$, when $y = 3$, the value of x when $y = 6$ is :

(a) 1 (b) 2
(c) 3 (d) 4

27. Suppose y varies as the sum of two quantities of which one varies directly as x and the other inversely as x. If $y = 6$ when $x = 4$ and $y = 3\frac{1}{3}$ when $x = 3$, then the relation between x and y is :

(a) $x = y + 4$ (b) $y = 2x + \frac{8}{x}$
(c) $y = 2x - \frac{8}{x}$ (d) $y = 2x - \frac{4}{x}$

28. The time period of a pendulum is proportional to the square root of the length of the pendulum. Consider the following statements :

(1) If the length of the pendulum is doubled, then the time period is also doubled.

(2) If the length is halved, then time period becomes one-fourth of the original time period.

The correct assertions are :

(a) 1 (b) 2
(c) neither 1 nor 2 (d) both 1 and 2

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. Four numbers are in proportion. The sum of the squares of the four numbers is 50 and the sum of the means is 5. The ratio of first two terms is 1 : 3. What is the average of the four numbers?
(a) 2 (b) 3
(c) 5 (d) 6

2. A naughty student breaks the pencil in such a way that the ratio of two broken parts is same as that of the original length of the pencil to one of the larger part of the pencil. The ratio of the other part to the original length of pencil is :
(a) $1 : 2\sqrt{5}$ (b) $2 : (3 + \sqrt{5})$
(c) $2 : \sqrt{5}$ (d) can't be determined

3. If $\frac{x+y}{x-y} = \frac{5}{3}$ and $\frac{x}{(y+2)} = 2$, the value of (x, y) is :
(a) (4, 1) (b) (2, 8)
(c) (1, 4) (d) (8, 2)

4. If $a^3 + b^3 : a^3 - b^3 = 133 : 117$; find $a : b$:
(a) 2 : 3 (b) 5 : 4
(c) 5 : 2 (d) none of these

5. A student obtained equal marks in History and Sociology. The ratio of marks in Sociology and Geography is 2 : 3 and the ratio of marks in History and Philosophy is 1 : 2. If he has scored an aggregate of 55% marks. The maximum marks in each subject is same. In how many subjects did he score equal to or greater than 60% marks?
(a) 1 (b) 2
(c) 3 (d) none of these

6. The ratio of income of Anil and Mukesh is 2 : 3. The sum of their expenditure is Rs. 8000 and the amount of savings of Anil is equal to the amount of expenditure of Mukesh. What is the sum of their savings?
(a) 22,000 (b) 4,000
(c) 16,000 (d) 12,000

7. Hutch and Essar entered into a partnership just 5 months ago. The ratio of profit claimed by Hutch and Essar is 6 : 17. If Essar had just started his business 12 months ago with Rs. 1275, what is the amount contributed by Hutch?
(a) Rs. 980 (b) Rs. 1080
(c) Rs. 1200 (d) Rs. 998

8. A child has three different kinds of chocolates costing Rs. 2, Rs. 5 and Rs. 10. He spends total Rs. 120 on the chocolates. What is the minimum possible number of chocolates, he can buy, if there must be atleast one chocolate of each kind?
(a) 22 (b) 19
(c) 17 (d) 15

9. In the previous problem (no. 8) what is the maximum possible no. of chocolates?
(a) 52 (b) 53
(c) 55 (d) 60

10. Mr. Teremere and Mr. Meretere have 5 chocolates and 3 chocolates with them respectively. Meanwhile Mr. Khabbu Singh joined them and all 8 chocolates were distributed equally among all these three people. In turn Khabbu Singh gave Rs. 16 to Mr. Teremere and Mr. Meretere, since Khabbu Singh did not has any chocolate. What is the difference of amounts received by Teremere and Meretere? Given that the amount was shared in proportion of chocolates received by Khabbu Singh.
(a) Rs. 8 (b) Rs. 12
(c) Rs. 14 (d) Rs. 15

11. Rs. 4536 is divided among 4 men, 5 women and 2 boys. The ratio of share of a man, a woman and a boy is 7 : 4 : 3. What is the share of a woman?
(a) Rs. 336 (b) Rs. 498
(c) Rs. 166 (d) Rs. 256

12. The concentration of petrol in three different mixtures (petrol and kerosene) is $\frac{1}{2}$, $\frac{3}{5}$ and $\frac{4}{5}$ respectively. If 2 litres, 3 litres and 1 litre are taken from these three different vessels and mixed. What is the ratio of petrol and Kerosene in the new mixture?
(a) 4 : 5 (b) 3 : 2
(c) 3 : 5 (d) 2 : 3

13. Time period (T) of pendulum is directly proportional to the square root of length of string by which bob is attached to a fixed point and inversely proportional to the square root of gravitational constant 'g'. Time period of a bob is 3 seconds when the gravitational constant g is 4 m/sec^2 and length of string is 9 metre, what is the time period of a bob having a string of length 64 metre and gravitational constant 16 m/sec^2?
(a) 4 seconds (b) 12 seconds
(c) 16 seconds (d) 10 seconds

14. In a milk shoppe there are three varieties of milk, 'Pure', 'Cure' and 'Lure'. The 'Pure' milk has 100% concentration of milk. The ratio of milk is to water in the 'Cure' is 2 : 5 and in the Lure it is 3 : 8 respectively. Sonali purchased 14 litres of Cure and 22 litres of Lure milk and mixed them. If she wanted to make the concentration of milk in the mixture of purchased milk to 50%. How many litres of 'Pure' milk she is needed?
(a) 6 litres (b) 8 litres
(c) 16 litres (d) 18 litres

Scanned by CamScanner

yoursmahboob.wordpress.com

15. In the squadron of Indian Air Force the ratio of Sukhoi is to Mig and Jaguar together is 5 : 7 and the ratio of Jaguar is to Sukhoi and Mig together is 1 : 2. Find the ratio of Sukhoi and Mig :
(a) 2 : 7 (b) 3 : 5
(c) 3 : 1 (d) 5 : 3

16. During our campaign against child labour we have found that in three glass making factories *A*, *B* and *C* there were total 33 children aged below 18 were involved. The ratio of male to female in *A*, *B* and *C* was 4 : 3, 3 : 2 and 5 : 4 respectively. If the no. of female children working in the factories *B* and *C* be equal then find the no. of female children working in factory *A* :
(a) 5 (b) 2
(c) 8 (d) 6

17. The value of a diamond is directly proportional to the square of its weight. A diamond unfortunately breaks into three pieces with weights in the ratio of 3 : 4 : 5 thus a loss of Rs. 9.4 lakh is incurred. What is the actual value of diamond :
(a) 28.8 lakh (b) 13.5 lakh
(c) 14.4 lakh (d) 18.8 lakh

18. In the Ruchika's wallet there are only Rs. 16, consisting of 10 paise, 20 paise and Re. 1 coins. The ratio of no. of coins of 10 paise and 20 paise is 6 : 1. The minimum no. of Re 1 coin is :
(a) 5 (b) 12
(c) 4 (d) 8

19. There are two vessels containing the mixture of milk and water. In the first vessel the water is 2/3 of the milk and in the second vessel water is just 40% of the milk. In what ratio these are required to mix to make 24 litres mixture in which the ratio of water is to milk is 1 : 2?
(a) 4 : 3 (b) 5 : 7
(c) 5 : 2 (d) 7 : 5

20. Nehru Ji had '*n*' chocolates. He distributed them among 4 children in the ratio of $\frac{1}{2} : \frac{1}{3} : \frac{1}{5} : \frac{1}{8}$. If he gave them each one a complete chocolate, the minimum no. of chocolates that he had :
(a) 139 (b) 240
(c) 278 (d) none of these

21. The ratio of working efficiency of *A* and *B* is 5 : 3 and the ratio of efficiency of *B* and *C* is 5 : 8. Who is the most efficient ?
(a) *A* (b) *B*
(c) *C* (d) can't be determined

22. If $4A = 5B$ and $3A = 2C$, the ratio of $B : C$ is :
(a) 4 : 3 (b) 5 : 8
(c) 8 : 15 (d) 10 : 15

23. Equal quantities of three mixtures of milk and water are mixed in the ratio of 1 : 2, 2 : 3 and 3 : 4. The ratio of water and milk in the mixture is :
(a) 193 : 122 (b) 122 : 193
(c) 61 : 97 (d) 137 : 178

24. The ratio of age of *A* and *B* is 8 : 9 and the age of *B* is 2/3 of *C*'s age and age of *C* is $\frac{9}{13}$ times the age of *D*. If the age of *B* is 18 years then the age of *C* is :
(a) 36 years (b) 39 years
(c) 27 years (d) 54 years

25. A milk man has a mixture of milk in which ratio of milk and water is 5 : 3. He sells 40 litres of milk *i. e.*, mixture then he adds up 15 litres of pure water. Now the ratio of milk and water is 5 : 4. What is the new quantity of mixture?
(a) 72 litres (b) 270 litres
(c) 135 litres (d) data insufficient

26. *A* and *B* are two alloys of copper and tin prepared by mixing the respective metals in the ratio of 5 : 3 and 5 : 11 respectively. If the alloys *A* and *B* are mixed to form a third alloy *C* with an equal proportion of copper and tin, what is the ratio of alloys *A* and *B* in the new alloy *C*?
(a) 3 : 5 (b) 4 : 5
(c) 3 : 2 (d) 2 : 3

27. A hotel incurs two types of expenses, one which is fixed and others depend upon no. of guests. When there are 10 guests, total expenses of hotel are Rs. 6000. Also when there are 25 guests average expenses per guests are Rs. 360? What is the total expenses of hotel when there are 40 guests?
(a) Rs. 8,000 (b) Rs. 12,000
(c) Rs. 15,500 (d) none of these

28. The ratio of third proportional to 21 and 42 and mean proportional to 16 and 49 is :
(a) 3 : 1 (b) 2 : 3
(c) 4 : 3 (d) 1 : 3

29. The period of the pendulum is directly proportional to the square root of the length of the string. The period of such a pendulum with string of length 16 cm is 52 seconds. Find the length of the string if the period is 65 seconds :
(a) 4.5 cm (b) 5 cm
(c) 6 cm (d) none of these

30. For any two numbers *m*, *n*; $(m + n) : (m - n) : mn = 7 : 1 : 60$ Find the value of $\frac{1}{m} : \frac{1}{n}$
(a) 4 : 3 (b) 8 : 6
(c) 3 : 4 (d) 7 : 8

31. Rs. 960 were distributed among *A*, *B*, *C* and *D* in such a way that *C* and *D* together gets half of what *A* and *B* together gets and *C* gets one-third amount of *B*. Also *D* gets $\frac{5}{3}$ times as much as *C*. What is the amount of *A*?
(a) Rs. 240 (b) Rs. 280
(c) Rs. 320 (d) data insufficient

32. Find the value of $\frac{p^2 + q^2}{r^2 + s^2}$, if $p : q :: r : s$.
(a) $\frac{1}{4}$ (b) $\frac{1}{9}$
(c) $\frac{ps}{rq}$ (d) $\left(\frac{p-q}{r-s}\right)^2$

33. Find the value of $\frac{p^2 + q^2}{r^2 + s^2}$, if $p : q :: r : s$.
(a) $\frac{1}{4}$ (b) $\frac{pq}{rs}$
(c) $\left(\frac{p+q}{r+s}\right)^2$ (d) both (b) and (c)

34. The speeds of rickshaw, car and scooter are in the ratio of 3 : 5 : 6. What is the ratio of time taken by each one of them for the same distance?
(a) 6 : 5 : 3 (b) 10 : 6 : 5
(c) 12 : 7 : 6 (d) data insufficient

Scanned by CamScanner

yoursmahboob.wordpress.com

35. Divide Rs. 6940 in such a way that A gets $\frac{2}{3}$rd of what B gets and B gets $\frac{3}{5}$th of what C gets? What is the share of A and B together?
(a) Rs. 1982 (b) Rs. 1388
(c) Rs. 3470 (d) none of these

36. The ratio of age of A and B is $x : y$. If A's age is increased by 3 years and B's age is increased by 2 years then new ratio of their ages becomes 24 : 25. Given that the sum of their actual ages is 93 years. Find the actual ratio of their ages.
(a) 21 : 22 (b) 42 : 45
(c) 45 : 48 (d) can't be determined

37. $a : b = 4 : 9$ if 4 is added to both of the numbers then the new ratio becomes 21 : 46. What is the difference between a and b?
(a) 80 (b) 100
(c) 125 (d) 130

38. The ratio of ages of Rahul and Deepesh is 3 : 5. 10 years later this ratio becomes 5 : 7. What is the present age of Deepesh?
(a) 20 years (b) 50 years
(c) 25 years (d) 40 years

39. When 5 is added to the numerator and denominator both of a (positive) fraction, then the new ratio of numerator to denominator becomes 11 : 15. What is the original ratio?
(a) 17 : 25 (b) 3 : 5
(c) 28 : 40 (d) none of these

40. Five numbers a, b, c, d and e are in the ratio of 2 : 3 : 5 : 8 : 9 and their sum is 162. Find the average of all these numbers :
(a) 27 (b) 30
(c) 32.4 (d) can't be determined

41. 6 pumps of Kirlosker can fill a tank in 7 days and 2 similar pumps of USHA can fill the same tank in 18 days. What is the ratio of the efficiency of a Kirlosker pump and a USHA pump?
(a) 6 : 7 (b) 7 : 6
(c) 7 : 54 (d) can't be determined

42. 16 persons can reap $\frac{1}{5}$th field in 6 days. How many persons (with same efficiency) are required to reap rest of the field in 8 days?
(a) 27 (b) 54
(c) 48 (d) 64

43. The LCM of two numbers is 210 and their ratio is 2 : 3. The sum of these numbers is :
(a) 210 (b) 175
(c) 315 (d) can't be determined

44. What number must be subtracted from each of the numbers 53, 21, 41, 17 so that the remainders are in proportion?
(a) 1 (b) 3
(c) 5 (d) none of these

45. The angles of a triangle are in the ratio of 2 : 3 : 4. Find the measurement of greatest angle :
(a) 30° (b) 60°
(c) 100° (d) 80°

46. In a wallet the ratio of 25 paise, 50 paise and Re 1 coins are in the ratio of 12 : 4 : 3, which amounts to Rs. 600. Find the no. of coins of 25 paise :
(a) 200 (b) 225
(c) 275 (d) none of these

47. $(x-a):(x-b):(x-c) = 11 : 9 : 5$, where $x = \frac{a+b+c}{2}$.
What is the ratio of a, b, c?
(a) 10 : 8 : 7 (b) 3 : 5 : 9
(c) 7 : 8 : 10 (d) 6 : 5 : 3

48. Petrol is 7 times heavy than Kerosene and Castrol mobil is 18 times as heavy as Kerosene. What should be the ratio of petrol and mobil in the new mixture to get the mixture which must be 11 times as heavy as kerosene?
(a) 3 : 4 (b) 7 : 4
(c) 9 : 19 (d) 9 : 10

49. A girl buys 2 pigeons for Rs. 182. She sells one at a loss of 5% and another at a profit if 8%. But she neither gains nor loses on the whole. Find the price of pigeon which has sold at a profit :
(a) Rs. 112 (b) Rs. 85
(c) Rs. 70 (d) can't be determined

50. The ratio of prices of Cello and Rotomac pens in 2000 were in the ratio of 3 : 5. In 2005 the price of Cello pen trebles itself and the price of Rotomac pen is increased by Rs. 100, then the new ratio of prices of the same pens becomes 4 : 5. What was the original price of the Rotomac pen in 2000?
(a) Rs. 60 (b) Rs. 80
(c) Rs. 100 (d) Rs. 120

51. A goldsmith has 361 rings of gold. He sells some of them at a loss of 4% and rest at a profit of 15% making overall profit of 8%. Find the no. of rings sold at a profit of 15% :
(a) 171 (b) 133
(c) 218 (d) 228

52. Michel travelled from New York to New Jersey covering total distance of 250 miles in 8 hr. partly by car at 30 miles/hr. and rest by train at 35 miles/hr. The distance travelled by car is :
(a) 150 miles (b) 80 miles
(c) 220 miles (d) 180 miles

53. A rabit takes 22 leaps for every 17 leaps of cat and 22 leaps of a rabit are equal to 17 leaps of the cat. What is the ratio of the speeds of rabit and cat?
(a) 1 : 1 (b) 484 : 289
(c) 17 : 22 (d) none of these

54. Rs. 171 are divided among four friends in the ratio of $\frac{1}{3}:\frac{1}{4}:\frac{1}{5}:\frac{1}{6}$. What is the amount of the person who got the greatest share?
(a) 14 (b) 40
(c) 36 (d) 60

55. 10 years ago the age of Karishma was $\frac{1}{3}$rd of the age of Babita. 14 years hence the ratio of ages of Karishma and Babita will be 5 : 9. Find the ratio of their present ages :
(a) 13 : 29 (b) 11 : 27
(c) 29 : 17 (d) 13 : 25

Scanned by CamScanner

yoursmahboob.wordpress.com

56. The ratio of numerator to a denominator of a fraction is $\frac{1}{5}$ when x and $5x$ are added to the numerator and denominator respectively to the given fraction then the ratio of the new fraction will be :
(a) 1 : 1 (b) 1 : 25
(c) 1 : 5 (d) 2 : 7

57. x varies directly as y and x varies inversely as the square of z. When $y = 75$ and $x = 6$, then $z = 5$. Find the value of x when $y = 24$ and $z = 4$:
(a) 1 (b) 2
(c) 3 (d) 4

58. x varies directly as $(y^2 + z^2)$. At $y = 1$ and $z = 2$, the value of x is 15. Find the value of z, when $x = 39$ and $y = 2$:
(a) 2 (b) 3
(c) 4 (d) 6

59. Weight of a sumo is jointly varies as his height and his age. When height is 1.2 m and age is 20 years his weight is 48 kg. Find the weight of the sumo when his height is 1.5 metre and age is 30 years :
(a) 60 kg (b) 72 kg
(c) 90 kg (d) 58 kg

60. If $(a + b) : (b + c) : (c + a) = 5 : 6 : 9$ and $a + b + c = 10$. What is the value of c :
(a) 2 (b) 3
(c) 5 (d) 7

61. A, B, and C have amounts in the ratio of 3 : 4 : 5. First B gives $\frac{1}{4}$th to A and $\frac{1}{4}$th to C then C gives $\frac{1}{6}$th to A. Find the final ratio of amount of A, B and C, respectively :
(a) 4 : 3 : 5 (b) 5 : 4 : 3
(c) 6 : 4 : 2 (d) 5 : 2 : 5

LEVEL 2

1. A tin contains a mixture of Dew and Sprite in the ratio of 7 : 3 and another tin contains the Dew and Sprite in the ratio of 5 : 4. In what proportion should the solution of two tins be mixed to achieve a perfect proportion of 2 : 1 (in which Dew is 2 times that of sprite).
(a) 10 : 3 (b) 4 : 1
(c) 3 : 10 (d) 3 : 1

2. There are two containers A and B filled with mentha oil with different prices and their volumes are 140 litres and 60 litres respectively. Equal quantities are drawn from both A and B in such a manner that the oil drawn from A is poured into B and the oil drawn from B is poured into A. The price per litre becomes equal in both A and B. How much oil is drawn from each of A and B :
(a) 40 litre (b) 21 litre
(c) 42 litre (d) can't be determined

3. A three digit number is such that this number itself is divisible by the sum of its digits. The sum of hundreds and unit digit is 6 while the sum of the tens and unit digit is 5. What is the ratio of unit and tens digit :
(a) 1 : 2 (b) 2 : 3
(c) 3 : 4 (d) 2 : 7

4. Sachin bought 1.5 kg fresh grapes. The ratio of water is to pulp was 4 : 1. When his naughty child crushed these grapes, then some water get wasted. Now the ratio of water is to pulp is 3 : 2. What is the total amount of the crushed grapes?
(a) 0.5 kg (b) 1 kg
(c) 0.75 kg (d) none of these

5. A man bought 9 mangoes for a rupee and sold them at 6 mangoes for a rupee. What is the ratio of profit to the cost price?
(a) $\frac{3}{10}$ (b) $\frac{3}{2}$
(c) 1/2 (d) none of these

6. Half of the volume of Petrol and kerosene mixture of ratio 7 : 5 is converted into a mixture of ratio 3 : 1 by the substitution (or replacement) method. While the mixture of ratio 7 : 5 was formed from the mixture of 7 : 3 by adding the Kerosene in it. If 240 litres petrol is required in the replacement method, what is the total amount of Kerosene was added to prepare the mixture of 7 : 5?
(a) 100 litres (b) 400 litres
(c) 50 litres (d) 200 litres

7. Sometimes ago in a Cinema hall a blockbuster movie was being shown. Due to excessive demand of the show, manager of the Cinema hall increased the prices of tickets in all the three categories. 25% in first class, 12.5% in special class and 40% in balcony. If the collection of one show was Rs. 218925, then find the collection from the balcony only given that the ratio of price of ticket (increased price) for first class, special class and balcony is 5 : 9 : 14 :
(a) 109462.5 (b) 58800
(c) 14400 (d) data insufficient

8. In a mixture of petrol and Kerosene petrol is only 99 litres. if this same quantity of petrol would be presented in another mixture of petrol and Kerosene where total volume would be 198 litres less than the actual mixture then the concentration of petrol in the actual mixture would have been 13.33% point less than that of the new mixture. What is the concentration of petrol in actual mixture?
(a) 20% (b) 16.66%
(c) 26.66% (d) 8.33%

9. A drum of 20 litres is filled with milk. A milkman has only two measuring vessels of 3 litres and 5 litres without any calibration. He has to measure four litres of milk for a customer without using anyother vessel. Minimum how many operations are required for this work, where an operation is counted if the milk is transferred from one vessel to another vessel?
(a) 5 (b) 6
(c) 8 (d) 11

10. The ages of Vinay, Varsha, Veera and Vikram are in arithmetic progression, but not in order. The ratio of ages of Vinay and Varsha is 6 : 5 and Veera is to Vikram is 7 ; 8. Two years later

Scanned by CamScanner

yoursmahboob.wordpress.com

the age of Varsha and Vikram will be 2 : 3. Find the ratio of ages of Vinay and Veera :
(a) 7 : 6 (b) 5 : 8
(c) 6 : 7 (d) 8 : 9

11. A container is filled with the mixture of milk and water. The ratio of milk and water is same. Bobby and Sunny increases the concentration to 60%. Bobby makes it by adding the milk and Sunny makes it by replacing the mixture with milk. What is the percentage of milk added by Bobby to that of milk replaced by Sunny :
(a) 100% (b) 120%
(c) 133.33% (d) none of these

12. There are two vessels A and B containing 25 litres each of pure milk and pure water respectively. 5 litres of milk from A is taken and poured into B, then 6 litres of mixture from B is taken and poured in A. What is the ratio of water in A and B respectively :
(a) 4 : 5 (b) 1 : 4
(c) 5 : 4 (d) 2 : 3

13. The ratio of age between A and B is 6 : 5 and the age of each C and D is $\frac{9}{10}$ times that of B. Age of F is less than A but greater than B. The ratio of ages between B and E is 2 : 3 also age of A is 3 years less than E. What is the ratio of ages of A and F if all the ages are in integers?
(a) 12 : 11 (b) 9 : 7
(c) 24 : 19 (d) 12 : 13

14. The ratio of students in a coaching preparing for B.Tech and MBA is 4 : 5. the ratio of fees collected from each of B. Tech and MBA student is 25 : 16. If the total amount collected from all the students is 1.62 lakh, what is the total amount collected from only MBA aspirants?
(a) Rs. 62,000 (b) Rs. 72,000
(c) Rs. 80,000 (d) none of these

15. The cost of the marble varies directly with square of its weight. Marble is broken into 3 parts whose weights are in the ratio 3 : 4 : 5. If marble had been broken into three equal parts by weight then there would have been a further loss of Rs. 1800. What is the actual cost of the original (or unbroken) marble?
(a) Rs. 3600 (b) Rs. 10,800
(c) Rs. 2160 (d) none of these

Directions for 16 and 17: Four friends A, B, C and D have some money among them one day they decided to equate the money, so first A gave B what B had initially, then B gave C what C had initially. Again C gave D what D had initailly and finally D had doubled the money of A. Thus each of them had equal sum of Rs. 48.

16. What was the initial amount of B?
(a) Rs. 36 (b) Rs. 54
(c) Rs. 45 (d) Rs. 42

17. What was the amount with C after second transaction?
(a) Rs. 45 (b) Rs. 69
(c) Rs. 72 (d) Rs. 84

18. Hari and Murli have 24 cows and 30 cows respectively. Both of them together hired a grazing field for the whole month of November. Initially Hari's cows used for grazing then for the remaining days of the month Murli's cows grazed it. If Hari has paid Rs. 3500 and Murli has paid Rs. 5000 for grazing then for how many days Hari used the grazing field :
(a) 14 (b) 16
(c) 21 (d) 20

19. The speeds of scooter, car and train are in the ratio of 1 : 4 : 16. If all of them covers equal distance then the ratio of time taken/velocity for the each of the vehicle is :
(a) 256 : 16 : 1 (b) 1 : 4 : 16
(c) 16 : 4 : 1 (d) 16 : 1 : 4

20. Radhika purchased one dozen bangles. One day she slipped on the floor fell down. What can not be the ratio of broken to unbroken bangles :
(a) 1 : 2 (b) 1 : 3
(c) 2 : 3 (d) 1 : 5

21. If $\frac{a}{b}=\frac{c}{d}=\frac{e}{f}$, then the value of $\left(\frac{a^n p+c^n q+e^n r}{b^n p+d^n q+f^n r}\right)^{1/n}$:
(a) $\frac{ad}{bc}$ (b) $\frac{af}{be}$
(c) $\frac{ck}{dk}$ (d) none of these

22. At a casino in Mumbai, there are 3 tables A, B and C. The pay-offs at A is 10 : 1, at B is 20 : 1 and at C is 30 : 1. If a man bets Rs. 200 at each table and win at two of the tables, what is the maximum and minimum difference between his earnings can be?
(a) Rs. 2500 (b) Rs. 2000
(c) Rs. 4000 (d) none of these

23. If $m=\frac{4pq}{p+q}$, then the value of $\frac{m+2p}{m-2p}+\frac{m+2q}{m-2q}$:
(a) 2 (b) 4
(c) $\frac{2mpq}{(p+q)}$ (d) none of these

24. The ratio of volumes of two cubes is 8 : 27. What is the ratio of surface area of these cubes respectively?
(a) 2 : 3 (b) 4 : 9
(c) 8 : 19 (d) 9 : 4

25. Dudheri Lal has two jars. Jar A is completely filled with milk and another jar B is totally empty. Before selling the milk in a town he transferred some milk in to the empty jar B then he fill the jar A with water. Once again he transferred the mixture of milk from A to B so that B is completely filled. Which one of the following is correct?
(a) Concentration of milk in B cannot be less than 75%
(b) Concentration of milk in B cannot be greater than 75%
(c) Concentration of milk is always 75%
(d) none of the above

26. In ABC corporation there are some management trainees. These trainees are divided into 3 groups A, B and C for 3 different projects in the ratio of 3 : 4 : 5 respectively, where P, Q, R are the projects-in-charge of A, B, C respectively. The difference between the no. of trainees in A and C is not greater than 3. Also P, Q, R belongs to the group of trainees. The no. of assistant of Q is less than the no. of assistance of R by :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 33.33% (b) 20%
(c) 25% (d) 16.66%

27. If $\frac{a}{b}=\frac{b}{c}=\frac{c}{d}=\frac{d}{e}=\frac{e}{f}=\frac{1}{3}$, find the value of $\left(\frac{a+b+c+d+e}{b+c+d+e+f}\right)$:

(a) $\frac{1}{81}$ (b) $\frac{1}{27}$
(c) $\frac{1}{3}$ (d) 1

28. An engine can move at the speed of $\frac{20}{3}$ m/s without any wagon attached. Reduction in the speed of the train is directly proportional to the square root of the no. of wagons attached to the engine. When there are only four wagons attached its speed is $\left(\frac{50}{9}\right)$ m/s. The greatest no. of wagons with which the engine can move is :

(a) 144 (b) 143
(c) 12 (d) none of these

29. Mrs. Annapurna per day sells exactly four quintal sugar at Rs. 2000 per quintal getting the profit of Rs. 25%. Since she mixes two varities of sugar, one costs Rs. 14 per kg and another costs Rs. 22 per kg. One day due to huge demand in market she had only 3 quintal of the required mixture so she purchased the sugar costs Rs. 17 per kg at Rs. 18 per kg from the wholeseller on that day and then she mixed 300 kg mixture with 100 kg sugar costing Rs. 18 per kg to fullfill the demand of the market selling at the same price. How much percent less does she gain that she would have gained, if she had sufficient quantity of usual mixture of sugar?

(a) 12.5% (b) 18.18%
(c) 62.5% (d) can't be determined

30. Two vessels P and Q contain 'a' litres of petrol and 'b' litres of Kerosene respectively. 'c' litres of petrol and same quantity of Kerosene is taken out and then transferred to Q and P respectively. This process is repeated several times. If after the first operation the quantity of petrol or Kerosene in either of P and Q does not change. What is the value of 'c'?

(a) $\frac{ab}{(a-b)}$ (b) $\frac{2ab}{(a+b)}$
(c) $\frac{ab}{(a+b)}$ (d) $\left(\frac{a}{b}\right)^2$

31. Arvind Singh purchased a 40 seater bus. He started his services on route no. 2 (from Terhipuliya to Charbagh with route length of 50 km). His profit (P) from the bus depends upon the no. of passangers over a certain minimum number of passangers 'n' and upon the distance travelled by bus. His profit is Rs. 3600 with 29 passangers in the bus for a journey of 36 km and Rs. 6300 when there are 36 passengers. travelled for 42 km. What is the minimum no. of passangers are required so that he will not suffer any loss?

(a) 12 (b) 20
(c) 18 (d) 15

32. Three cats are roaming in a zoo in such a way that when cat A takes 5 steps, B takes 6 steps and cat C takes 7 steps. But the 6 steps of A are equal to the 7 steps of B and 8 steps of C. What is the ratio of their speeds :

(a) 140 : 144 : 147 (b) 40 : 44 : 47
(c) 15 : 21 : 28 (d) 252 : 245 : 240

33. In a family there were n people. The expenditure of rice per month in this family is directly proportional to the 5 times the square of no. of people in the family. If the elder son left the family to study in USA there was decrease in consumption of 95 kg rice per month. What is the value of n?

(a) 5 (b) 12
(c) 9 (d) 10

34. One day in summer I wanted to chill me out, I went to a cool corner. I gave him a note of Rs. 10 and asked for a coke costing Rs. 5 per jar and he did so, but he returned me Rs. 5, in the denomination of Re. 1, 50 paise and 25 paise. What could be the ratio of no. of coins of Re. 1, 50 paise and 25 paise respectively :

(a) 2 : 3 : 1 (b) 1 : 7 : 2
(c) 6 : 1 : 3 (d) 2 : 1 : 2

35. If $\frac{a}{b+c}=\frac{b}{c+a}=\frac{c}{a+b}$ and $a+b+c\neq 0$ then the value of $\frac{b}{a+b+c}$ is :

(a) $\frac{1}{2}$ (b) $\frac{1}{3}$
(c) $\frac{1}{4}$ (d) 1

36. The ratio of the density of 3 kinds of petrol P_1, P_2 and P_3 is 9 : 7 : 5. The density of P_1 is 18 gm/cc and P_1, P_2, P_3 are mixed in the ratio of 6 : 5 : 4 by weight. If a litre of P_3 cost Rs. 40, then find the cost of P_3 in 450 kg of mixture of P_1, P_2 and P_3 :

(a) Rs. 380 (b) Rs. 480
(c) Rs. 355 (d) Rs. 448

37. Three persons Amar, Akbar and Anthony agree to pay their hotel bills in the ratio of 3 : 4 : 5. Amar pays the first day's bill which amounts to Rs. 26.65, Akbar pays the second days bill which amounts to Rs. 42.75 and C pays the third day's bill which amounts to Rs. 53.00. When they settle their accounts, which of the following happens?

(a) Amar gives Rs. 3 to C
(b) Akbar gives Rs. 2 to Amar
(c) Amar gives Akbar Rs. 1.95 and Rs. 2 to Anthony
(d) none of the above

38. Find the value of x if $(14x-4):(8x-1)=(3x+8):(9x+5)$:

(a) 1 (b) 1/2
(c) 3/4 (d) none of these

39. Pooja, Shipra and Monika are three sisters. Pooja and Shipra are twins. The ratio of sum of the ages of Pooja and Shipra is same as that of Monika alone. Three years earlier the ratio of age of Pooja and Monika was 2 : 7. What will be the age of Shipra 3 years hence?

(a) 21 years (b) 16 years
(c) 8 years (d) 12 years

40. A couple got married 9 years ago when the age of wife was 20% less than her husband. 6 years from now the age of wife will be only 12.5% less than her husband. Now they have six

Scanned by CamScanner

yoursmahboob.wordpress.com

children including single, twins and triplets and the ratio of their ages is 2 : 3 : 4 respectively. What can be the maximum possible value for the present age of this family?
(a) 110 years (b) 103 years
(c) 105 years (d) 83 years

41. The price of a necklace varies directly as the no. of pearls in it. Also, it varies directly as the square root of radius of a pearl. The price of a necklace was Rs. 150. When it had 75 pearls each of radius 1 cm. Find the radius of the pearl of a necklace having 100 pearls whose cost is Rs. 600.
(a) 2 (b) 9
(c) 3 (d) 4

42. The price of a book varies directly as the no. of pages in it and inversely as the time periods in years that have elapsed since the date of purchasing. Two books cost the same, however, the no. of pages in the first book is triple of the second book. if the first book is sold on 18 years ago, how long ago was the second book sold?
(a) 54 years (b) 9 years
(c) 6 years (d) 3 years

43. Akbar and Birbal who purchased the shares for the cost of their basic salaries which are in the ratio of 5 : 6. later on company gave them 40 additional shares to each, due to which the ratio changed to 7 : 8. If the worth of each share is Rs. 75, what is the basic salary of the person who got less shares?
(a) Rs. 10500 (b) Rs. 7500
(c) Rs. 8800 (d) Rs. 9000

44. Distance covered by a train is directly proportional to the time taken and also it varies directly as the square root of fuel used and varies inversely as the no. of wagons attached to it. A train coveres 192 km journey in 20 hours when there are 10 wagons attached to it and total fuel consumption was 256 litre of diesel. Find the consumption of fuel per km when a train goes 200 km in 25 hours with 15 wagons attached to it :
(a) 1.5 *l*/km (b) 2 *l*/km
(c) 2.8 *l*/km (d) 20 *l*/km

45. At Sahara shopping centre, a person can purchase as much articles at a time as his or her age that is a person of n years age can purchase only n similar articles at a time. Amisha is younger to her elder brother who has just entered into his twenties. One day Amisha went to the Sahara shopping centre, she purchased same toffees at a particular rate on the ground floor. But when she reached on third floor she found that she could purchase double the no. of toffees with the same amount as she had spent on the ground floor. Also to purchase the same no. of toffees on the third floor she had to spend Rs. 2 less than that of on the first floor. How many toffees did she buy?
(a) 6 (b) 12
(c) 18 (d) 15

46. A contractor deployed some men to plant 1800 trees in a certain no. of days. But in $\frac{1}{3}$rd of the planned time 120 plants could be less planted so to ful fill the target for the rest of the days every day 20 more plants were planted. Thus it saved one day out of the initially planned no. of days. How many plants he planned to plant each day initially?
(a) 180 (b) 100
(c) 120 (d) 160

47. A and B have to write 810 and 900 pages respectively in the same time period. But A completes his work 3 days ahead of time and B completes 6 days ahead of time. How many pages did A write per hour if B wrote 21 pages more in each hour?
(a) 45 (b) 72
(c) 54 (d) 100

48. Three friends A, B and C decided to share the soda water with D, who had no soda water. A contributed 2 tumbler more than that of B and B contributed 1 tumbler more than that of C and then all of them had equal amount of soda water. In turn D paid money, which was divided among A, B and C in the ratio of their contribution to D. Thus A had gotten thrice as much money as B had gotten. The price of each tumbler of soda water was Rs. 15 and each transaction was integral in numbers either the sharing of money or contribution of soda water. What was the sum of money that B had gotten?
(a) Rs. 15 (b) Rs. 18
(c) Rs. 22.5 (d) none of these

49. In Maa Yatri Temple every devotee offers fruits to the orphans. Thus every orphan receives bananas, oranges and grapes in the ratio of 3 : 2 : 7 in terms of dozen. But the weight of a grape is 24 gm and weight of a banana and an orange are in the ratio of 4 : 5, while the weight of an orange is 150 gm. Find the ratio of all the three fruits in terms of weight, that an orphan gets :
(a) 90 : 75 : 42 (b) 180 : 150 : 82
(c) 75 : 42 : 90 (d) none of these

Final Round

1. In two alloys the ratio of Iron and copper is 4 : 3 and 6 : 1 respectively. If 14 kg of the first alloy and 42 kg of the second alloy are mixed together to form a new alloy, then what will be the ratio of copper to iron in the new alloy :
(a) 11 : 3 (b) 11 : 8
(c) 8 : 11 (d) none of these

2. In a zoo, there are rabbits and pigeons. If heads are counted, there are 340 heads and if legs are counted there are 1060 legs. How many pigeons are there?
(a) 120 (b) 150
(c) 180 (d) 170

3. 6 litre is taken out from a vessel full of Kerosene and substituted by pure petrol. This process is repeated two more times. Finally the ratio of petrol and Kerosene in the mixture becomes 1701 : 27. Find the volume of the original solution :
(a) 14 litre (b) 16 litre
(c) 8 litre (d) 42 litre

Scanned by CamScanner

yoursmahboob.wordpress.com

4. In three vessels, each of 25 litres capacity, mixture of milk and water is filled. The ratio of milk and water are 3 : 1, 2 : 3, 4 : 3 in the respective vessels. If all the three vessels are emptied into a single large vessel, then what will be the ratio of water to milk in the resultant mixture?
(a) 179 : 241 (b) 197 : 214
(c) 219 : 117 (d) 179 : 234

5. Two liquids are mixed in the ratio 4 : 3 and the mixture is sold at Rs. 20 with a profit of $33\frac{1}{3}\%$. If the first liquid is costlier than the second by Rs. 7. Find the sum of costs of both the liquids :
(a) Rs. 11 (b) Rs. 29
(c) Rs. 35 (d) Rs. 70

6. Two alloys made up of copper and tin. The ratio of copper and tin in the first alloy is 1 : 3 and in the second alloy it is 2 : 5. In what ratio the two alloys should be mixed to obtain a new alloy in which the ratio of tin and copper be 8 : 3?
(a) 3 : 5 (b) 4 : 7
(c) 3 : 8 (d) 5 : 11

7. Three vessels having volumes in the ratio of 2 : 3 : 5 are full of a mixture of water and milk. In the first vessel ratio of water and milk is 1 : 3, in second 2 : 3 and in third vessel, 2 : 5. If all the three vessels were poured out in a large container, what is the resulting ratio of milk and water?
(a) 43 : 96 (b) 438 : 962
(c) 348 : 962 (d) 962 : 438

8. The number of oranges in three baskets are in the ratio of 3 : 4 : 5. In which ratio the no. of oranges in first two baskets must be increased so that the new ratio becomes 5 : 4 : 3?
(a) 1 : 3 (b) 2 : 1
(c) 3 : 4 (d) 2 : 3

9. A vessel of capacity 2 litre has 25% alcohol and another vessel of capacity 6 litre had 40% alcohol. The total liquid of 8 litre was poured out in a vessel of capacity 10 litre and thus the rest part of the vessel was filled with the water. What is the new concentration of mixture?
(a) 31% (b) 71%
(c) 49% (d) 29%

10. Alloy A contains 40% gold and 60% silver. Alloy B contains 35% gold and 40% silver and 25% copper. Alloys A and B are mixed in the ratio of 1 : 4. What is the ratio of gold and silver in the newly formed alloy is?
(a) 20% and 30% (b) 36% and 44%
(c) 25% and 35% (d) 49% and 36%

11. Dia and Urea are two chemical fertilizers. Dia is consists of N, P and K and Urea conists of only N and P. A mixture of Dia and Urea is prepared in which the ratio of N, P and K is 26%, 68% and 6% respectively. The ratio of N, P and K in Dia is 20%, 70% and 10% respectively. What is the ratio of N and P in the Urea?
(a) 27% and 63% (b) 33% and 67%
(c) 35% and 65% (d) 70% and 30%

12. The ratio of copper and nickel by weight in the two alloys X and Y are 2 : 7 and 5 : 4. How many kilogram of the alloy X and Y are required to make 42 kg of new alloy Z in which the ratio of copper and nickel is same?
(a) 6 kg and 36 kg (b) 10 kg and 32 kg
(c) 7 kg and 35 kg (d) none of these

13. There are two alloys made up of copper and aluminium. In the first alloy copper is half of the aluminium and in the second alloy copper is thrice as much as aluminium. How many times the second alloy must be mixed with first alloy to get the new alloy in which copper is twice as that of aluminium?
(a) 2 (b) 3
(c) 4 (d) 5

14. There are 90 litres castrol and 150 litres CRB mobil oils. The price of castrol is Rs. 80 per litre and price of CRB is Rs. 75 per litre. Equal amount of castrol and CRB is taken out and then CRB is poured out in the vessel of castrol and castrol is poured out in the vessel of CRB. Now the rate of both the mixtures is same. What is the amount of mobil oil taken out from each of the vessel?
(a) 45 litres (b) 56.25 litres
(c) 24.5 litres (d) 36 litres

15. There are two containers, the first contain, 1 litre pure water and the second contains 1 litre of pure milk. Now 5 cups of water from the first container is taken out is mixed well in the second container. Then, 5 cups of this mixture is taken out and is mixed in the first container. Let A denote the proportion of milk in the first container and B denote the proportion of water in the second container then :
(a) $A < B$ (b) $A = B$
(c) $A > B$ (d) can't be determined

16. Mitthu Bhai sells rasgulla (a favorite indian sweets) at Rs. 15 per kg. A rasgulla is madeup of flour and sugar in the ratio of 5 : 3. The ratio of price of sugar and flour is 7 : 3 (per kg). Thus he earns $66\frac{2}{3}\%$ profit. What is the cost price of sugar?
(a) Rs. 10/kg (b) Rs. 9/kg
(c) Rs. 18/kg (d) Rs. 14/kg

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-4.1

1. (c)	2. (b)	3. (d)	4. (c)	5. (a)	6. (b)	7. (d)	8. (b)	9. (c)	10. (d)
11. (a)	12. (b)								

INTRODUCTORY EXERCISE-4.2

1. (c)	2. (c)	3. (b)	4. (d)	5. (c)					

INTRODUCTORY EXERCISE-4.3

1. (d)	2. (c)	3. (c)	4. (a)	5. (d)	6. (c)				

INTRODUCTORY EXERCISE-4.4

1. (b)	2. (d)	3. (c)	4. (a)	5. (d)	6. (d)	7. (c)	8. (b)	9. (a)	10. (d)
11. (b)	12. (d)	13. (b)	14. (c)	15. (c)	16. (b)	17. (c)	18. (d)	19. (b)	20. (b)
21. (c)	22. (a)	23. (c)	24. (b)	25. (d)	26. (a)	27. (c)	28. (c)		

LEVEL-1

1. (b)	2. (b)	3. (d)	4. (c)	5. (b)	6. (d)	7. (b)	8. (c)	9. (b)	10. (b)
11. (a)	12. (b)	13. (a)	14. (c)	15. (d)	16. (d)	17. (c)	18. (c)	19. (b)	20. (a)
21. (a)	22. (c)	23. (a)	24. (c)	25. (c)	26. (c)	27. (b)	28. (a)	29. (d)	30. (c)
31. (b)	32. (d)	33. (d)	34. (b)	35. (c)	36. (c)	37. (b)	38. (c)	39. (d)	40. (c)
41. (a)	42. (c)	43. (b)	44. (c)	45. (d)	46. (d)	47. (c)	48. (b)	49. (c)	50. (b)
51. (d)	52. (d)	53. (a)	54. (d)	55. (a)	56. (c)	57. (c)	58. (b)	59. (c)	60. (c)
61. (d)									

LEVEL-2

1. (a)	2. (c)	3. (b)	4. (c)	5. (c)	6. (d)	7. (d)	8. (a)	9. (c)	10. (c)
11. (d)	12. (b)	13. (a)	14. (b)	15. (d)	16. (c)	17. (d)	18. (a)	19. (a)	20. (c)
21. (c)	22. (c)	23. (a)	24. (b)	25. (a)	26. (c)	27. (c)	28. (b)	29. (a)	30. (c)
31. (d)	32. (a)	33. (d)	34. (b)	35. (b)	36. (b)	37. (c)	38. (b)	39. (c)	40. (b)
41. (b)	42. (c)	43. (b)	44. (b)	45. (b)	46. (b)	47. (c)	48. (a)	49. (a)	

FINAL ROUND

1. (d)	2. (b)	3. (c)	4. (a)	5. (b)	6. (b)	7. (d)	8. (b)	9. (d)	10. (b)
11. (c)	12. (c)	13. (c)	14. (b)	15. (b)	16. (d)				

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1. $a : b :: c : d$

$a^2 + b^2 + c^2 + d^2 = 50$

$b + c = 5$

and $a : b = 1 : 3$

If consider $a : b = 1 : 3$ as it is, then

$c = 2$ $(5 - 3 = 2)$

and $d = 6$ $(\because a : b :: c : d)$

$a^2 + b^2 + c^2 + d^2 = 1^2 + 3^2 + 2^2 + 6^2 = 50$

Hence, the presumed values are correct.

Thus, the average of a, b, c and $d = \dfrac{a+b+c+d}{4}$

$= \dfrac{1+3+2+6}{4} = 3$

Hence (b) is correct.

Alternatively: Assume option (b)

$\because \quad \dfrac{a+b+c+d}{4} = 3$

$\Rightarrow \quad a + b + c + d = 12$

Now $\because \quad b + c = 5$

$\Rightarrow \quad a + d = 7$

Again $a : b = 1 : 3$

$\Rightarrow \quad c : d = 2 : 6$

Now verify that $a^2 + b^2 + c^2 + d^2 = 50$. Since it is correct.

Hence option (b) is correct.

NOTE It can also be solved by forming quadratic equations.

2. $\dfrac{a}{b} = \dfrac{a+b}{a}$

$\Rightarrow \quad a^2 = ab + b^2$

$\Rightarrow \quad a^2 - b^2 - ab = 0$

Let $b = 1$, then $a : b = a : 1$ (by putting $b = 1$)

$\therefore \quad a^2 - a - 1 = 0$

$\Rightarrow \quad a = \dfrac{1 \pm \sqrt{5}}{2}$ (Solving quadratic equation by Sridharacharya's formula)

$\therefore a = \dfrac{1+\sqrt{5}}{2}$ (negative value can't be considered)

$a : b = \dfrac{1+\sqrt{5}}{2} : 1$

or $a : b = (1 + \sqrt{5}) : 2$

Therefore, $\dfrac{b}{a+b} = \dfrac{2}{1+\sqrt{5}+2} = \dfrac{2}{3+\sqrt{5}}$

Hence option (b) is correct.

3. The best way is to go through options

$\dfrac{x+y}{x-y} = \dfrac{8+2}{8-2} = \dfrac{10}{6} = \dfrac{5}{3}$ (verified)

Again $\dfrac{x}{y+2} = \dfrac{8}{2+2} = 2$ (verified)

Hence option (d) is correct.

4. Best way is to go through options

and $\dfrac{a^3+b^3}{a^3-b^3} = \dfrac{5^3+2^3}{5^3-2^3} = \dfrac{125+8}{125-8} = \dfrac{133}{117}$

Hence option (c) is correct.

5. $H : S = 1 : 1$

and $S : G = 2 : 3$

$H : P = 1 : 2$

$\therefore \quad H : S : G : P = 2 : 2 : 3 : 4$

$= 2x : 2x : 3x : 4x$

Therefore $\dfrac{2x+2x+3x+4x}{4} = \dfrac{11x}{4} = 55$

$\Rightarrow \quad x = 20$

Marks in History = 40

Sociology = 40

Geography = 60

Philosophy = 80

Hence, only in two subjects he scored 60% or above.

Hence option (b) is correct.

6. Let the incomes of A and M is $2x$ and $3x$

Let the savings of A be K, then the expenditure of M be K

Also expenditure of $A = 2x - K$

Given $(2x - K) + K = 8000 \Rightarrow x = 4000$

$\therefore$ Total income of

A and $B = 2x + 3x = 5x = 5 \times 4000 = 20000$

$\therefore$ Total savings of A and $B = 20{,}000 - 8000 = \text{Rs. } 12{,}000$

7. $\dfrac{\text{Profit of Hutch}}{\text{Profit of Essar}} = \dfrac{\text{time period} \times \text{amount of Hutch invested}}{\text{time period} \times \text{amount of Essar invested}}$

$\dfrac{6}{17} = \dfrac{5 \times K}{12 \times 1275}$

$\Rightarrow \quad K = \dfrac{6 \times 12 \times 1275}{17 \times 5} = 1080$

8. Minimum number of chocolates are possible when he purchases maximum number of costliest chocolates.

Thus $2 \times 5 + 5 \times 2 = \text{Rs. } 20$

Now Rs. 100 must be spend on 10 chocolates as $100 = 10 \times 10$.

Thus minimum number of chocolates $= 5 + 2 + 10 = 17$

9. Maximum number of chocolates are possible only when he purchases minimum number of costlier chocolates and maximum number of cheaper chocolates

$\therefore \quad 2 \times 5 + 1 \times 10 = \text{Rs. } 20$

Now Rs. 100 must be spend on 50 chocolates as $100 = 2 \times 50$.

Thus maximum number of possible chocolates

$= 2 + 1 + 50 = 53$

Scanned by CamScanner

yoursmahboob.wordpress.com

10. Meretere → M, Teremere → T and Khabbu Singh → K

$\frac{5+3}{3} = 2.66$ (since all the 8 chocolates were shared by 3)

It means M has given $5 - 2.66 = 2.33$ chocolates to K and T has given $3 - 2.66 = 0.33$ chocolates to K

Thus M and T will receive the amount in the ratio of donations (i.e., share of chocolates)

M	:	T
2.33	:	0.33
$2\frac{1}{3}$	:	$\frac{1}{3}$
$\frac{7}{3}$	:	$\frac{1}{3}$
7	:	1

So the M receives Rs. 14 and T receives Rs. 2

Thus the difference = Rs. 12

11. Share of a man, a woman and a boy = $7x$, $4x$ and $3x$

then the share of 4 men = $4 \times 7x = 28x$

then the share of 5 women = $5 \times 4x = 20x$

then the share of 2 boys = $2 \times 3x = 6x$

Now, the share of all women = $\frac{20x}{(28x + 20x + 6x)} \times 4536$

$= \frac{20}{54} \times 4536 = \text{Rs. } 1680$

Hence, the share of one woman = $\frac{1680}{5} = 336$

12. Concentration of petrol in

A	B	C
$\frac{1}{2}$	$\frac{3}{5}$	$\frac{4}{5}$

Quantity of petrol taken from A = 1 litre out of 2 litre

Quantity of petrol taken from B = 1.8 litre out of 3 litre

Quantity of petrol taken from C = 0.8 litre out of 1 litre

Therefore total petrol taken out from

A, B and $C = 1 + 1.8 + 0.8 = 3.6$ litre

So, the quantity of Kerosene = $(2 + 3 + 1) - (3.6) = 2.4$ litre

Thus, the ratio of petrol to Kerosene = $\frac{3.6}{2.4} = \frac{3}{2}$

13. $T \propto \frac{\sqrt{l}}{\sqrt{g}} \Rightarrow T = k\sqrt{\frac{l}{g}}$

Therefore, $3 = K\sqrt{\frac{9}{4}}$ or $3 = K\frac{3}{2} \Rightarrow K = 2$

Again $T = K\sqrt{\frac{l}{g}} = 2 \times \sqrt{\frac{64}{16}} = 4$

$T = 4$ seconds

14.

Pure	Cure	Lure
100%	40%	37.5%
$\frac{1}{1}$	$\frac{2}{5}$	$\frac{3}{8}$

	Milk	Water	Mixture
Cure	$4l$	$10l$	$14l$
Lure	$6l$	$16l$	$22l$
New mixture	Milk	Water	
	$10l$	$26l$	
	$16l$		
	$26l$	$26l$	

Required mixture 1 : 1

Since in the required mixture the ratio of milk and water is 1 : 1 so she has to add up 16 litre of more milk (pure) to get it, for the fixed quantity of water.

15. $S : (M + J) = 5 : 7 \Rightarrow 7S = 5M + 5J$ ...(1)

$J : (S + M) = 1 : 2 \Rightarrow 2J = S + M$ ...(2)

By solving equations (1) and (2), we get

$S : M : J = 5 : 3 : 4$

so $S : M = 5 : 3$

16.

	Male		Female
A	$4x$	:	$3x$
B	$3y$	:	$2y$
C	$5z$	:	$4z$

but $2y = 4z$

$\therefore$

	Male		Female
A	$4x$	:	$3x$
B	$6z$	:	$4z$
C	$5z$	:	$4z$

Therefore, $7x + 19z = 33$

but z can assume only one value i.e., $z = 1$

Hence, $7x + 19 = 33 \Rightarrow x = 2$

Thus the no. of female children in factory $A = 3x = 6$.

17. The ratio of broken parts (by weight) = $3x : 4x : 5x$

Therefore value of broken parts of diamond

$= (3x)^2 + (4x)^2 + (5x)^2 = 50x^2$

The value of original diamond = $(3x + 4x + 5x)^2 = 144x^2$

Therefore, loss in value = $144x^2 - 50x^2 = 9.4$ lakh

$\Rightarrow 94x^2 = 9.4$ lakh

$\Rightarrow 94x^2 = 940000$

$\Rightarrow x^2 = 10000$

Hence, the actual value of the diamond = $144x^2$

$= 144 \times 10000$

$= 14.4$ lakh

18. $10x + 20y + 100z = 1600$

Again since $x : y = 6 : 1$

$\therefore 60y + 20y + 100z = 1600$

$\Rightarrow 80y + 100z = 1600$

$\Rightarrow 4y + 5z = 80$

Putting $z = 1, 2, 3, 4, 5 \ldots$, we get at $z = 4$, $y = 15$ (an integer)

Hence, min. 4 coins of Re. 1 will be there

19. Concentration of water in first vessel = $\frac{2}{5} = 40\%$

concentration of water in second vessel = $\frac{2}{7} = 28.57\%$

By alligation

$\frac{2}{7}$ $\quad$ $\frac{2}{5}$

$\frac{1}{3}$

$\left(\frac{2}{5} - \frac{1}{3}\right)$ $\quad$ $\left(\frac{1}{3} - \frac{2}{7}\right)$

$\frac{1}{15}$	:	$\frac{1}{21}$
21	:	15
7	:	5

Therefore, ratio of first mixture to the second mixture = 5:7

Scanned by CamScanner

yoursmahboob.wordpress.com

20. LCM of 2, 3, 5, 8 = 120

Therefore, $\frac{1}{2} \times 120 = 60$

$\frac{1}{3} \times 120 = 40$

$\frac{1}{5} \times 120 = 24$

$\frac{1}{8} \times 120 = 15$

Therefore, minimum number of chocolates

$= 60 + 40 + 24 + 15 = 139$

21. $A : B = 5 : 3$

$B : C = 5 : 8$

$\therefore \quad A : B : C = 25 : 15 : 24$

So, A is the most efficient.

22. $A : B = 5 : 4 \Rightarrow 10 : 8$

$A : C = 2 : 3 \Rightarrow 10 : 15$

$\therefore \quad A : B : C = 10 : 8 : 15$

$\therefore \quad B : C = 8 : 15$

23.

	A		B		C
(Proportion of milk in mixture)	$\frac{1}{3}$	:	$\frac{2}{5}$	:	$\frac{3}{7}$
or	$\frac{35}{105}$	:	$\frac{42}{105}$	:	$\frac{45}{105}$

quantity of milk in new mixture $= 35 + 42 + 45 = 122l$

quantity of water in new mixture $= (105 \times 3) - 122 = 193l$

Therefore, ratio of water is to milk = 193 : 122

24. $A : B = 8 : 9$

$B : C = 2 : 3$

$C : D = 9 : 13$

$A : B : C : D = 144x : 162x : 243x : 351x$

But we need not to solve this, since we already know that

$B : C = 2x : 3x$

$\therefore \quad 2x : 3x :: 18 : k \Rightarrow k = 27$ years

25.

Milk		Water	
$5x$		$3x$	(initially)
$-25l$		$-15l$	
$5x - 25$		$3x - 15$	(after selling 40l mixture)
		$+15l$	
$5x - 25$		$3x$	(after adding 15l water)
5	:	4	

$\therefore \quad \frac{5x - 25}{3x} = \frac{5}{4} \Rightarrow x = 20$

$\therefore$ New quantity of mixture $= (5x - 25) + 3x = 135$ litre

26.

A	B
$C : T$	$C : T$
5 : 3	5 : 11

Concentration of copper in $A = \frac{5}{8}$

Concentration of copper in $B = \frac{5}{16}$

By alligation



$\frac{2}{16} \quad : \quad \frac{3}{16}$

$2 \quad : \quad 3$

So, the required ratio of $A : B = 3 : 2$ (Since $B : A = 2 : 3$)

27. $k + 10x = 6000$

$k + 25x = 9000$ ($\because 25 \times 360 = 9000$)

$\Rightarrow \quad 15x = 3000$

$\Rightarrow \quad x = 200$ and $k = 4000$

$\therefore \quad k + 40x = 4000 + 40 \times 200 = 12{,}000$

where k is the fixed expenditure.

28. Third proportional of 21 and 42 is 84 and mean proportional to 16 and 49 is 28.

Therefore required ratio $= \frac{84}{28} = \frac{3}{1}$ or 3 : 1

29. $P \propto \sqrt{l} \Rightarrow P = k\sqrt{l}$

$\therefore \quad 52 = k\sqrt{16}$

$\Rightarrow \quad k = 13$

Again, $P = k\sqrt{l}$

$65 = 13\sqrt{l}$

$\Rightarrow \quad l = 25$ cm

30. $\frac{m+n}{m-n} = \frac{7x}{x} \Rightarrow \frac{m}{n} = \frac{4x}{3x}$

Again $mn = 4x \times 3x = 12x^2$

and $mn = 60x$

So $60x = 12x^2$

$\Rightarrow \quad x = 5$

$\therefore \quad m = 20$ and $n = 15$

Hence, $\frac{1}{m} : \frac{1}{n} = \frac{1}{20} : \frac{1}{15} = 3 : 4$

Alternatively: $\frac{m}{n} = \frac{4x}{3x}$

$\frac{1}{m} : \frac{1}{n} = 3 : 4$

31. $\underbrace{A + B}_{2} : \underbrace{C + D}_{1}$

and $\frac{B}{3} : \frac{C}{1}$ and $\frac{C}{3} : \frac{D}{5}$

$\Rightarrow \quad B : C : D$

$9 : 3 : 5$

Again $A + B : C + D$

$\underbrace{7 + 9}_{16} \quad \underbrace{3 + 5}_{8}$

Thus $A + B = 16 \Rightarrow A = 7$ when $B = 9$

$\therefore$ Therefore share of $A = \frac{7}{24} \times 9600 =$ Rs. 280

Scanned by CamScanner

yoursmahboob.wordpress.com

32. The best way is to consider some values in the proportion and verify the option, but care should be taken that in this type of question you are required to verify a possible correct option atleast with 2-3 times with different values.

Since, if you consider

$$p:q::r:s \Rightarrow 1:2::3:6$$

you will find answer (b) is also correct, but for only particular values. So it is not the general solution. Finally you will realize that option (d) is the most appropriate answer.

33. Solve by componendo and dividendo or as mentioned in the previous solution.

34. Since for the constant distance time is inversely proportional to the speed. So, the required ratio of time taken by each of the rickshaw, car and scooter is

$$\frac{1}{3}:\frac{1}{5}:\frac{1}{6} \Rightarrow 10:6:5$$

$$\left[\frac{1}{3}\times\frac{10}{10}:\frac{1}{5}\times\frac{6}{6}:\frac{1}{6}\times\frac{5}{5}=\frac{10}{30}:\frac{6}{30}:\frac{5}{30}=10:6:5\right]$$

35. $A:B=2:3$ and $B:C=3:5$

$\Rightarrow A:B:C=2:3:5$

$\therefore (A+B):C=5:5=1:1$

Hence, Share of $(A+B)=\frac{1}{2}\times 6940=3470$

36. $x+y=93$ ...(1)

and $\frac{x+3}{y+2}=\frac{24}{25}$

$\Rightarrow 25x-24y=(-27)$ ...(2)

From equations number (1) and (2)

$x=45$ and $y=48$

Alternatively: Go through options.

37. $\frac{a}{b}=\frac{4x}{9x}$ and $\frac{a+4}{b+4}=\frac{21}{46}$

$\Rightarrow a=80$ and $b=180$

$\therefore b-a=100$

38. $\frac{R}{D}=\frac{3x}{5x}$ and $\frac{R}{D}\Rightarrow\frac{3x+10}{5x+10}=\frac{5}{7}$

$\Rightarrow x=5$

Hence, $\frac{R}{D}=\frac{15}{25}$

Alternatively: Go through options.

39. Let the fraction be $\frac{x}{y}$ then

$$\frac{x+5}{y+5}=\frac{11}{15} \Rightarrow 11y-15x=20$$

Since, we have only one equation in two variables, so we cannot find the solution.

40. $\frac{2x+3x+5x+8x+9x}{5}=\frac{162}{5}=32.4$

41. The number of days required by a single Kirlosker pump to fill the tank $=6\times7=42$ days and the number of days required by a single USHA pump to fill the same tanks $=2\times18=36$ days. Now, since efficiency is inversely proportional to the number of days. Hence,

$$\frac{\text{Efficiency of one K-pump}}{\text{Efficiency of U-pump}}=\frac{36}{42}=\frac{6}{7}$$

42. $\frac{1}{5}$th field can be reaped by 96 man days

$\therefore \frac{4}{5}$th field can be reaped by $96\times4=384$ man days

Now, since there are only 8 days so reqired

number of men $=\frac{384}{8}=48$ men

43. $210=2\times3\times5\times7$

Therefore, $\frac{N_1}{N_2}=\frac{2k\times5\times7}{3k\times5\times7}$

since, $N_1:N_2=2:3$

Therefore, $N_1=70$ and $N_2=105$

$\therefore N_1+N_2=70+105=175$

44. $\frac{(53-x)}{(21-x)}=\frac{(41-x)}{(17-x)} \Rightarrow x=5$

Alternatively : Go through options.

45. $2x+3x+4x=180$

$\Rightarrow x=20 \therefore 4x=80$

46. $(25\times12x)+(50\times4x)+(100\times3x)=800x=60000$

$\Rightarrow x=75$

$\therefore$ number of coins of 25 paise $=12x=12\times75=900$

Alternatively : Go through options, choices (a), (b) and (c) are eliminated since neither of 200, 225, 275 is divisible by 12. Hence choice (d) is correct.

47. Go through options.

Alternatively : $\frac{(x-a)}{11}=\frac{(x-b)}{9}=\frac{(x-c)}{5}=k$

$\Rightarrow a=x-11k$

$b=x-9k$

$c=x-5k$

$$\therefore x=\frac{(x-11k)+(x-9k)+(x-5k)}{2}$$

$2x=3x-25k \Rightarrow x=25k$

$a=14k \Rightarrow b=16k$ and $c=20k$

$\therefore a:b:c=14:16:20=7:8:10.$

48. If the weight of kerosene be k kg/unit volume, then
weight of petrol $=7k$/unit volume
weight of castrol $=18k$/unit volume
required weight of the mixture $=11k$/unit volume

By Alligation



The required ratio is 7 : 4.

49. **By Alligation**



The ratio of price of pigeons sold at loss and profit respectively are in the ratio of 8 : 5

$\therefore$ Cost price of profitable pigeon $=\frac{5}{8+5}\times182=$ Rs. 70.

Scanned by CamScanner

yoursmahboob.wordpress.com

50. $\frac{C}{R} = \frac{3x}{5x}$

Again $\frac{C}{R} = \frac{(3x)3}{(5x+100)} = \frac{4}{5}$

$\Rightarrow$ $x = 16$

$\therefore$ Price of Rotomac pen in 2000 was Rs. 80.

51. By Alligation



Now, we get the ratio of no. of rings sold at a loss and profit is 7 : 12

$\therefore$ Number of rings sold at profit $= \frac{12}{19} \times 361 = 228$

Alternatively : Go through options.

52. Best way is to go through options.

consider option (d)

$$\frac{180}{30} + \frac{70}{35} = 6 + 2 = 8 \text{ hrs}$$

Hence, (d) is correct.

Alternatively : $\frac{x}{30} + \frac{250 - x}{35} = 8$

$\Rightarrow$ $x = 180$ miles

Alternatively : Since the Average Speed

$$= \frac{\text{Total Distance}}{\text{Total Time}} = \frac{250}{8} \text{ miles/hr}$$

$\therefore$ **By Alligation**



Therefore, the ratio of time taken @ 30 m/hr and @ 35 m/hr is in the ratio of 3 : 1. It means he has travelled @ 30 m/hr for 6 hr.

Therefore, the distance travelled by car is 180.

($\because$ Distance = Speed $\times$ Time).

53. $\frac{22}{22} : \frac{17}{17} = 1 : 1$

54. $\frac{1}{3} : \frac{1}{4} : \frac{1}{5} : \frac{1}{6}$

$\Rightarrow$ $\frac{20}{60} : \frac{15}{16} : \frac{12}{60} : \frac{10}{60}$ (by taking LCM)

$\Rightarrow$ $20 : 15 : 12 : 10$

$\therefore$ Largest share $= \frac{20}{(20+15+12+10)} \times 171$

$= \frac{20}{57} \times 171 = 60.$

55. Let the present age of Karishma and Babita be x and y then,

$$\frac{x-10}{y-10} = \frac{1}{3} \quad \ldots(1)$$

Again $\frac{x+14}{y+14} = \frac{5}{9}$ ...(2)

By solving (1) and (2) we get $x = 26$ and $y = 58$

56. Let the fraction be $\frac{k}{5k}$

then, $\frac{k+x}{5k+5x} = \frac{(k+x)}{5(k+x)} = \frac{1}{5}$

57. $x \propto y$ and $x \propto \frac{1}{z^2}$

$x \propto \frac{y}{z^2} \Rightarrow x = k\frac{y}{z^2}$

$6 = k \times \frac{75}{(5)^2} \Rightarrow k = 2$

Again $x = 2 \times \frac{24}{(4)^2} \Rightarrow x = 3$

58. $x \propto (y^2 + z^2) \Rightarrow x = k(y^2 + z^2)$

$15 = k(1^2 + 2^2) \Rightarrow k = 3$

again $39 = 3 \times (2^2 + z^2)$

$\Rightarrow$ $13 = (4 + z^2) \Rightarrow z = 3$

59. $W \propto HA \Rightarrow W = K \times H \times A$

Now, $48 = K \times 1.2 \times 20 \Rightarrow K = 2$

Again $W = 2 \times 1.5 \times 30$

$\therefore$ $W = 90$

60. $(a+b) : (b+c) : (c+a) = 5x : 6x : 9x$

and $a + b + c = 10$

$\Rightarrow$ $(a+b) + (b+c) + (c+a) = 20x$

$\Rightarrow$ $a + b + c = 10x$

$\Rightarrow$ $a + b + c = 10$ ($\because x = 1$)

$\therefore$ $c = (a+b+c) - (a+b)$

or $c = 10 - 5 = 5$

61.

A	B	C	
$3x$	$4x$	$5x$	
$(3x + x)$	$2x$	$(5x + x)$	(B gives $\frac{1}{4}$ to A and $\frac{1}{4}$ to C)
$= 4x$	$2x$	$6x$	
$(4x + x)$	$2x$	$(5x)$	(C gives $\frac{1}{6}$ to A)
$5x$	$2x$	$5x$	
5	: 2	: 5	

Scanned by CamScanner

yousmahboob.wordpress.com

LEVEL (2)

1.

M_1	M_2
$D : S$	$D : S$
$7 : 3$	$5 : 4$

New Mixture

D		S
2	:	1

proportion of Dew in $M_1 = \frac{7}{10}$

proportion of Dew in $M_2 = \frac{5}{9}$

proportion of new mixture $= \frac{2}{3}$ (required)

By alligation rule

$\frac{7}{10}$ $\quad$ $\frac{5}{9}$

$\frac{2}{3}$

$\left(\frac{2}{3} - \frac{5}{9}\right)$ $\quad$ $\left(\frac{7}{10} - \frac{2}{3}\right)$

$\frac{3}{27}$ $\quad$ $\frac{1}{30}$

or $\frac{1}{9} : \frac{1}{30}$

or $10 : 3$

2. The ratio of quantities $= 140 : 60 = 7 : 3$

$\therefore$ The quantity to be exchanged $= \frac{(140 \times 3) + (60 \times 7)}{2(7+3)}$

$= 42$ litre

NOTE In this question individual prices are not required. You can solve it by forming equation.

Alternatively : Go through options by assuming some prices.

3. Let the number be $100x + 10y + z$, then

$x + z = 6$ and $y + z = 5$

Also, from the given options only option (b) is suitable

i.e., $y + z = 5$

or $3 + 2 = 5$

4.

Water	Pulp
$4x$	x
$3y$	$2y$

but $x = 2y$ since pulp remains contant

	Water	Pulp
$5y$ = loss in water →	$8y$	$2y$
	$3y$	$2y$

but $10y\ (= 8y + 2y) = 1.5$ kg

$\therefore$ $5y\ (= 3y + 2y) = 0.75$ kg

5.

Cost price	:	Selling price
$\frac{1}{9}$	:	$\frac{1}{6}$
2	:	3

or CP : SP = 2 : 3

since profit = SP − CP

$\therefore$ Profit = 3 − 2 = 1

$\therefore$ Profit : CP = 1 : 2

6. Flow Chart :

$P : K$

$7x : 3x$ → + Kerosene by addition

Step 1 → $7x : 5x$ ← by replacement

Step 2 → $3x : x$ ←

By the replacement formula from alligation chapter

$$\frac{1}{4} = \frac{5}{12}\left(1 - \frac{240}{12x}\right)$$

$$\Rightarrow \quad \frac{3}{5} = \left(1 - \frac{240}{12x}\right)$$

$$\Rightarrow \quad \frac{2}{5} = \frac{20}{x}$$

$$\Rightarrow \quad x = 50$$

Therefore, half of the initial amount = (350 + 150) litres then, the required amount of kerosene

$= 5x - 3x = 2x = 100$ litres

But for the whole amount required kerosene to be added = 200 litres

7. Data insufficient. Since we don't know that how many persons bought ticket of all the categories individually

i.e., $5x + 9y + 14z = 213925$

but we don't know anything about x, y and z

8.

Petrol	Kerosene	Total Mixture
99	x	$99 + x$
99	$(x - 198)$	$(x - 99)$

Again $\frac{99}{(x-99)} \times 100 - \frac{99}{(x+99)} \times 100 = 13.33$

or $9900\left(\frac{x + 99 - x + 99}{x^2 - 99^2}\right) = 13.33$

or $\frac{9900\,(198)}{x^2 - 99^2} = \frac{40}{3}$

$\Rightarrow \quad x^2 - 99^2 = 99^2 \times 15$

$\Rightarrow \quad x^2 = (99)^2 \times (16)$

$\Rightarrow \quad x = 99 \times 4 = 396$ litres

Therefore the actual concentration of petrol

$= \frac{99}{(99 + 396)} = 20\%$

Scanned by CamScanner

yoursmahboob.wordpress.com

9. Do it yourself.

10. Varsha : Vinay = 5 : 6 = 5x : 6x

Veera : Vikram = 7 : 8 = 7y : 8y

But their ages are in A.P.

Therefore, $6x - 5x = 8y - 7y$

$\Rightarrow \quad x = y$

Again, $\dfrac{5x+2}{8y+2} = \dfrac{2}{3}$

$\Rightarrow \quad \dfrac{5x+2}{8x+2} = \dfrac{2}{3}$

$\Rightarrow \quad x = 2$

Therefore, the ages of Varsha, Vinay, Veera and Vikram are 10, 12, 14 and 16 years respectively.

Therefore, the ratio of ages of Vinay and Veera = 6 : 7

11.

Bobby			Sunny		
Milk	:	Water	Milk	:	Water
1		1	1		1
50% ②		50% ②	50%		50%
60% ③	:	40% ②			

It means bobby will add up 1 litre of milk, in 4 litre of initial mixture, to prepare 5 litres mixture in the ratio of 3 : 2

By replacement method

$\dfrac{2}{5} = \dfrac{2}{4}\left(1 - \dfrac{k}{4}\right)$

$\Rightarrow \quad \dfrac{4}{5} = \left(1 - \dfrac{k}{4}\right)$

$\Rightarrow \quad \dfrac{1}{5} = \dfrac{k}{4}$

$\Rightarrow \quad k = \dfrac{4}{5}$

It means Sunny will replace $\frac{4}{5}$ litre of initial mixture by the same quantity of pure milk.

Hence, the percentage of milk added by Bobby to that of replaced by Sunny $= \dfrac{1}{4/5} \times 100 = 125\%$

12.

	A		B	
	Milk	Water	Milk	Water
After first operation	25l	0	0	25l
	20l	0 →	5l	25l
			1 : 5	
After second operation	21l	5l ←	4l	20l

Therefore, the ratio of water in A and B is 1 : 4

13. $B = \dfrac{5}{6}A$ ...(i)

and $C = D = \dfrac{9}{10}B$ ...(ii)

also $B = \dfrac{2}{3}E$ ...(iii)

and $E - A = 3$ ...(iv)

From (i) and (iii) $\dfrac{A}{E} = \dfrac{4}{5}$ or $E = \dfrac{5}{4}A$ ...(v)

$\therefore \quad E - A = \dfrac{5A}{4} - A = 3$ from (iv) and (v)

$\Rightarrow \quad A = 12$ and $E = 15$ and $B = 10$

Also $C = D = 9$ and $F = 11$, since $B < F < A$ and F is integer

$\therefore \quad A : F = 12 : 11$

14. The ratio of fees collected from B.Tech : MBA

$= 4x \times 25y : 5x \times 16y$

$= 100xy : 80xy$

$= 5xy : 4xy = 5k : 4k$

The amount collected only from MBA students

$= \dfrac{4}{9} \times 1.62 \text{ lakh}$

= Rs. 72,000

15. $C \propto (W)^2$

$W_1 : W_2 : W_3 = 3 : 4 : 5$

cost $= (3x)^2 + (4x)^2 + (5x)^2 = 50\,(x)^2$

Again $W_1 : W_2 : W_3 = 4 : 4 : 4$ (when weights are equal)

cost $= (4x)^2 + (4x)^2 + (4x)^2 = 48x^2$

loss $= 50x^2 - 48x^2 = 2x^2$

$1800 = 2x^2$

$x = 30$

$\therefore$ Actual cost of unbroken marble $= (4x + 4x + 4x)^2$

$= (12x)^2 = 144x^2$

$= 144 \times x^2$

$= 144 \times 900 = 129600$

Solutions for 16 and 17 :

	A	B	C	D
Initially	69	45	42	36
$A \to B$	24	90	42	36
$B \to C$	24	48	84	36
$C \to D$	24	48	48	72
$D \to A$	48	48	48	48

Solve it in reverse order (*i.e.*, from the result side)

18. Ratio of price paid by Hari and Murli = 7 : 10

or $(24 \times x) : 30 \times (30 - x) = 7 : 10$

$\Rightarrow \quad x = 14$

or go through options.

19. Since distance is constant. Therefore ratio of speeds of scooter, car and train = 1 : 4 : 16

and therefore, ratio of time taken = 16 : 4 : 1

Therefore, required ratio $= \dfrac{16}{1} : \dfrac{4}{4} : \dfrac{1}{16}$

$= 16 : 1 : \dfrac{1}{16} = 256 : 16 : 1$

20. Since there are 12 bangles, then the no. of broken to unbroken bangles can not be 2 : 3, since $5x = (2x + 3x)$ can not divide 12 for any integral value of x *i.e.*, all the sum of ratios which are the factors of 12 can possibly be the ratio of broken to unbroken.

Scanned by CamScanner

yoursmahboob.wordpress.com

21.

$$\frac{a}{b}=\frac{c}{d}=\frac{e}{f}=k$$

$$\Rightarrow \quad \frac{a^n}{b^n}=\frac{c^n}{d^n}=\frac{e^n}{f^n}=k^n$$

$$\Rightarrow \quad \frac{a^n p}{b^n p}=\frac{c^n q}{d^n q}=\frac{e^n r}{f^n r}=k^n$$

$$\therefore \quad \frac{a^n p+c^n q+e^n r}{b^n p+d^n q+f^n r}=(k^n)$$

$$\therefore \quad \left(\frac{a^n p+c^n q+e^n r}{b^n p+c^n q+f^n r}\right)^n=(k^n)^{1/n}$$

$$\therefore \quad \left(\frac{a^n p+c^n q+e^n r}{b^n p+d^n q+f^n r}\right)^{1/n}=k=\frac{a}{b}=\frac{c}{d}=\frac{e}{f}$$

Hence (c) is the possible answer.

22. Maximum earning will be only when he will won on the maximum yielding table.

$A \rightarrow 10:1$

$B \rightarrow 20:1$

$C \rightarrow 30:1$

i.e., he won on B and C but lost on A

$$20\times200+30\times200-1\times200=9800$$

minimum earning will be when he won on table A and B and lose on that table 3.

$$\therefore \quad 10\times200+20\times200-1\times200$$

$$6000-200=5800$$

Therefore, difference $= 9800 - 5800 = 4000$

Alternatively the difference

$$=[(30+20-1)-(10+20-1)]\times200$$

$$=20\times200=\text{Rs. } 4000.$$

23. $\dfrac{m+2p}{m-2p}+\dfrac{m+2q}{m-2q}$

$=\dfrac{m}{2p}+\dfrac{m}{2q}$ (by componendo and dividendo)

$=m\left(\dfrac{p+q}{2pq}\right)$

$=\left(\dfrac{4pq}{p+q}\right)\left(\dfrac{p+q}{2pq}\right)$ substituting the value of $m=\dfrac{4pq}{p+q}=2$

24. Volume of a cube $= (\text{side})^3 = (a)^3$

surface area of a cube $= 6(a)^2$ ($a \rightarrow$ side)

$$a_1^3 : a_2^3 = 8:27$$

$$\Rightarrow \quad a_1 : a_2 = 2:3$$

$$\Rightarrow \quad a_1^2 : a_2^2 = 4:9$$

$$\Rightarrow \quad 6a_1^2 : 6a_2^2 = 4:9$$

25. Clearly it can not be less than 75%. For clarification of concept consider some values and then verify it.

26.

$$A:B:C=3x:4x:5x$$

but $\quad C-A=5x-3x\le 3$

or $\quad C-A=2x\le 3 \Rightarrow x=1$

$\Rightarrow \quad C-A=2$

$\therefore \quad A:B:C=3:4:5$

Therefore, number of assistant trainee (except project in charge) of $Q = 3$ and assistant trainee of $R = 4$

Therefore, required percentage $=\dfrac{4-3}{4}\times100$

$$=\frac{1}{4}\times100=25\%$$

27. $b=3a$

$c=3b=9a$

$d=3c=9b=27a$

$e=3d=9c=27b=81a$ and $f=3e=243a$

put the values and simplify.

or we know that $\dfrac{a}{b}=\dfrac{c}{d}=\dfrac{e}{f}\ldots=\dfrac{a+c+e}{b+d+f}$

28. Let w be the number of wagons and s be the speed of engine

without wagon $=\dfrac{20}{3}$ m/s $= 24$ km/hr.

then speed of the train $= s - k\sqrt{w}$

$$\therefore \quad 20=24-k\sqrt{4} \qquad [\because \tfrac{50}{9}\text{ m/s} = 20\text{ km/hr}]$$

$$\therefore \quad k=2$$

when train will stop its speed becomes zero

$$0=24-2\sqrt{w} \qquad (\because k=2)$$

$$\Rightarrow \quad w=144$$

since at 144 wagons train will stop, so at 143 wagons train just can move with its least possible speed having maximum possible wagons.

29. Cost of 1 kg (mixture) of sugar = Rs. 16/kg

since selling price is Rs. 20/kg

Therefore, ratio of quantity of sugar costing Rs. 14 and Rs. 22 per kg = 3 : 1



So, the available stock of mixture costing Rs. 16 = 3 quintal and the required stock of sugar costing Rs. 18 = 1 quintal

Therefore, the new price of mixture costing 3 quintal of sugar @ Rs. 16/kg and 1 quintal of sugar @ Rs. 18 per kg



$\therefore \quad x = \text{Rs. } 16.5$ per kg

New price = Rs. 16.5 per kg

Now, original profit = 20 − 16 = Rs. 4 per kg

New profit = 20 − 16.5 = Rs. 3.5 per kg

$\therefore$ Percentage reduction in profit $=\dfrac{4-3.5}{4}\times100=12.5\%$

30.

	P	Q
Initial amounts	a (petrol)	b (kerosene)
After one operation	$a-c$ (petrol) c (kerosene)	$b-c$ (kerosene) c (petrol)

Scanned by CamScanner

yoursmahboob.wordpress.com

Since there is no change in concentration in the second, third... etc operations.

In the vessel P;

The fraction of kerosene in P is $\frac{c}{a}$

In the vessel Q;

The fraction of kerosene in Q is $\left(\frac{b-c}{b}\right)$

$$\therefore \quad \left(\frac{b-c}{b}\right) = \frac{c}{a}$$

$$\Rightarrow \quad c(a+b) = ab$$

$$\Rightarrow \quad c = \frac{ab}{a+b}, \qquad \text{Hence (c)}$$

Since at this moment the concentration in both vessels is same.

31. The minimum number of passengers n, at which there is no loss and number of passengers travelling $= m$ and let the distance travelled is d, then

$$P \propto (m-n)d$$

or $\quad p = k(m-n)d$; k is a constant.

when $P = 3600$, $m = 29$ and $d = 36$, then

$$3600 = k(29-n) \times 36 \qquad \ldots(1)$$

Again, when $p = 6300$, $m = 36$, $d = 42$ km

$$6300 = k(36-n) \times 42 \qquad \ldots(2)$$

Dividing equation (2) by (1)

$$\frac{6300}{3600} = \frac{k}{k}\frac{(36-n)\times 42}{(29-n)\times 36}$$

$$\Rightarrow \quad \frac{(36-n)}{(29-n)} = \frac{9}{6}$$

$$\Rightarrow \quad 3n = 45 \Rightarrow n = 15$$

Hence to avoid loss, minimum number of 15 passengers are required.

32. Frequency of step of $A : B : C = 5 : 6 : 7$

but it terms of size of step, $6A = 7B = 8C$

$\therefore$ Ratio of speeds of A, B and $C = \frac{5}{6} : \frac{6}{7} : \frac{7}{8}$

$$= 280 : 288 : 294$$

$$= 140 : 144 : 147$$

33. Expenditure $= 5$ (no. of family members)^2

$$\Rightarrow \quad E_1 = 5(n)^2 \qquad \ldots(1)$$

again $\quad E_2 = 5(n-1)^2 \qquad \ldots(2)$

but $\quad E_1 - E_2 = 95$

$$\therefore \quad 5[n^2 - (n-1)^2] = 95$$

$$5[n^2 - (n^2 + 1 - 2n)] = 95$$

$$n^2 - n^2 - 1 + 2n = 19$$

$$\Rightarrow \quad 2n = 20 \Rightarrow n = 10$$

34. Finally I have Rs. 5

Consider option (a)

$$2 \times 100 + 3 \times 50 + 1 \times 25 = 375 \text{ paise}$$

Its integer multiple can not give the value equals to 500. So can not be true.

Consider option (b)

$1 \times 100 + 7 \times 50 + 2 \times 25 = 500$ paise, can be true

but we also check the option (c) and (d) now when you check the choices (c) and (d) you will find wrong as choice (a). So, only choice be could be the best answer.

35. By componendo and dividendo :

$$\frac{a}{b+c} = \frac{b}{c+a}$$

$$\frac{a+b+c}{a-b-c} = \frac{b+c+a}{b-c-a}$$

$$\Rightarrow \quad a-b-c = b-c-a$$

$$\Rightarrow \quad a = b$$

similarily $\quad a = b = c$

$$\therefore \quad \frac{b}{a+b+c} = \frac{1}{3}$$

36. Density of P_1, P_2 and P_3 are 18, 14 and 10 gm/cc

$$\text{again since volume} = \frac{\text{weight}}{\text{density}}$$

now the weight of P_3 in 450 kg mixture $= \frac{450 \times 4}{15} = 120$ kg

now the volume of $P_3 = \frac{120}{10} = 12$ litre

$\therefore$ The cost of 12 litre P_3 petrol $= 12 \times 40 =$ Rs. 480

37. $26.65 + 42.75 + 53 = 122.40$

Proportionate amount of Amar, Akbar and Anthony in the ratio of 3 : 4 : 5 is Rs. 30.60, Rs. 40.80 and Rs. 51 respectively.

Now	Amar	Akbar	Anthony
	30.60	40.80	51.00
	26.65	42.75	53.00

So, Amar pays Rs. 1.95 to Akbar and Rs. 2 to Anthony.

38. The best way is to go through options

Alternatively: Solve by cross product rule and componendo.

39. Since Pooja and Shipra are twins so their ages be same. Let their ages be x and age of Monika be y, then,

$$x + x = y \qquad \ldots(1)$$

and $\quad \frac{(x-3)}{(y-3)} = \frac{2}{7}$

$$\Rightarrow \quad 7x - 2y = 15$$

Now, from equation (1),

$$7x - 4x = 15 \Rightarrow x = 5$$

So the age of Shipra 3 years hence will be $5 + 3 = 8$ years.

40. $\frac{H-9}{W-9} = \frac{5}{4}$ and $\frac{H+6}{W+6} = \frac{8}{7}$

$\therefore$ Thus the present age of Husband is 34 and present age of his wife is 29 years.

Now, the maximum age of any child must be less than 9 years. Hence their ages can be 2, 3 and 4 years or 4, 6 and 8 years. So the max. possible sum of age of this family

$$= 34 + 29 + (1 \times 4 + 2 \times 6 + 3 \times 8)$$

$$= 103 \text{ years}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

41. $P \propto n\sqrt{r} \Rightarrow P = kn\sqrt{r}$

where P is the price of necklace, n is number of pearls and r is the radius of a pearl.

Now $150 = k \times 75 \times \sqrt{1}$

$\Rightarrow$ $k = 2$

again $600 = 2 \times 100 \times \sqrt{r}$

$\Rightarrow$ $\sqrt{r} = 3 \Rightarrow r = 9$ cm

42. $P \propto \frac{N}{T} \Rightarrow P = K\frac{N}{T}$

$P \rightarrow$ Price of a book, $N \rightarrow$ Number of Pages, $T \rightarrow$ Time period

$$P_1 = P_2$$

$$\therefore K\frac{N_1}{T_1} = K\frac{N_2}{T_2}$$

$$\Rightarrow \frac{3N}{18} = \frac{N}{T}$$

$$T = 6 \text{ years}$$

43. $\frac{5x + 40}{6x + 40} = \frac{7}{8} \Rightarrow \frac{\text{Akbar}}{\text{Birbal}}$

$\Rightarrow$ $x = 20$

$\therefore$ The actual number of shares of less salaried person

$= 100$ $\because (5 \times 20 = 100)$

$\therefore$ The salary of Akbar $= 100 \times 75 = 7500$

44. $D \propto \frac{\sqrt{F} \times T}{W}$, $D \rightarrow$ Distance, $F \rightarrow$ Fuel, $T \rightarrow$ Time, $W \rightarrow$ No. of wagons

$$D = k\frac{\sqrt{F} \times T}{W}$$

$$192 = k\frac{\sqrt{256} \times 20}{10}$$

$\Rightarrow$ $k = 6$

again $200 = \frac{6 \times \sqrt{F} \times 25}{15}$

$\Rightarrow$ $\sqrt{F} = 20 \Rightarrow F = 400$ litre

$\therefore$ fuel used per km $= \frac{400}{200} = 2 l/\text{km}$

45. Just go through option and factorize the product into two factors such that the given conditions must satisfy.

e.g., $6 = 1 \times 6$

2×3

3×2

6×1

It is not true.

Again consider option (b)

$12 = 1 \times 12$

2×6

$3 \times 4 \rightarrow 3 \times 4 = 12$

4×3

$6 \times 2 \rightarrow 6 \times 2 = 12$

12×1

Now you can see that the rate is being half from 4 to 2 so she can purchase double number of toffees as she was already purchasing on the ground floor. Again to purchase the same number of toffees she had to spend Rs. 2 less than the spending on the ground floor :

Rate		Number of toffee/Re		Total Number of toffee
4	×	3	=	12
2	×	6	=	12

and if you check other options (c) and (d) they will not satisfy the given conditions.

46. Go through options.

	Total no. of plants		No. of plants	Days
Previous scheme $\Rightarrow$	1800	=	100	× 18

Again after $\frac{1}{3}$rd days, remaining plants

$$= \frac{1800 \times 2}{3} + 120 = 1320$$

$$1320 = (100 + 20) \times 11$$

This shows that in the second case 1 day was saved than the planned no. of day.

47. Go through options.

$$\frac{810}{54} - \frac{900}{75} = 3 = (6 - 3 = 3)$$

$$15 - 12 = 3$$

$$3 = 3$$

Hence choice (c) is correct.

i.e., if A writes 54 page, then B writes 75 (= 54 + 21) pages per hour.

48.

	A	B	C	D
Initial amount of soda water	$(x + 3)$	$(x + 1)$	(x)	0
final amount of soda water	$\left(\frac{3x}{4} + 1\right)$	$\left(\frac{3x}{4} + 1\right)$	$\left(\frac{3x}{4} + 1\right)$	$\left(\frac{3x}{4} + 1\right)$

Therefore to be the integral value x must be $4m$; $m = 1, 2, 3...$

So at $m = 1$

Hence option (a) is correct since B had contributed 1 tumbler.

	A	B	C	D
Initial amount	7	5	4	0
Final amount	4	4	4	4
	3	1	0	
		2	1	

49. Ratio of fruits (by dozen) = 3 : 2 : 7

Ratio of fruits by weight = 120 : 150 : 24

$\therefore$ Ratio of fruits (combined) by weight

$= 3 \times 120 : 2 \times 150 : 7 \times 24$

$= 30 : 25 : 14$

Scanned by CamScanner

yoursmahboob.wordpress.com

Final Round

1.

	1st Alloy		2nd Alloy	
	Iron	Copper	Iron	Copper
	4	3	6	1
Proportion of iron in the alloys	$\frac{4}{7}$ ⇩ $\frac{8}{14}$ (×2)		$\frac{6}{7}$ ⇩ $\frac{36}{42}$ (×6)	

So in the new alloy total iron will be 44 kg and copper will be 12 kg.

$\therefore$ Iron = 8 + 36 = 44

and Copper = (14 + 42) − (8 + 36) = 12

$\therefore$ Ratio of copper to iron = 12 : 44 = 3 : 11, hence (d)

2. Suppose there are all the pigeons then total no. of heads are 340 and total no. of legs are 680. Now since 380 (= 1060 − 680) legs are extra, it means there will be $190\left(=\frac{380}{2}\right)$ rabbits. As we know a rabbit has 2 extra legs than that of a pigeon who has only two legs.

Therefore, number of rabbits = 190

and number of pigeons = 340 − 190 = 150

Alternatively : go through options and consider choice (b)

	Pigeons	Rabbits
Heads (340)	150 (×2)	190] 340 (×4)
Legs (1060)	300	760] 1060

Alternatively : $P + R = 340$ ...(1)

and $2P + 4R = 1060$ ...(2)

Solve these two equations and you will get the answer.

Alternatively : It can be solved through alligation rule.

3. By the replacement formula

Decreased amount

$$= \text{Original amount}\left(1 - \frac{\text{replacing amount}}{\text{original amount}}\right)^{\text{no. of times } (n)}$$

Now, since the ratio of petrol and kerosene is 1701 and 27 it means initially there was (1701 + 27) = 1728 unit of kerosene and the decreased amount of kerosene is 27 unit.

$$\therefore \quad 27 = 1728\left(1 - \frac{6}{k}\right)^3 \Rightarrow k = 8 \text{ litre}$$

NOTE Here 27 : 1728 just show the ratio not the exact amount.

4. The ratio of milk in 3 vessels

$$= \frac{3}{4} \times \frac{5\times7}{5\times7} : \frac{2}{5} \times \frac{4\times7}{4\times7} : \frac{4}{7} \times \frac{4\times5}{4\times5}$$

$$= \frac{105}{140} : \frac{56}{140} : \frac{80}{140}$$

Remember, The value of 25 litre does not matter, the basic thing is that the amount of mixture in all the three quantities is same.

So the total quantity of milk in mixture = 105 + 56 + 80 = 241

So the total amount of water in mixture

$$= [(3\times140) - 241] = 179 \text{ litre}$$

Therefore ratio of water to milk in the new mixture

$$= 179 : 241$$

5. $\because$ Profit = $33\frac{1}{3}\%$, it means cost price = Rs. 15

Now, by alligation

$$\frac{(x+7)-15}{(15-x)} = \frac{3}{4}$$



$$\Rightarrow \quad x = 11$$

$\therefore \quad x = 11$ and $(x + 7) = 18$

Thus the total value of both the prices = 11 + 18 = 29

6.

A_1		A_2	
C	T	C	T
1	3	2	5
Copper → $\frac{1}{4}$		Copper → $\frac{2}{7}$	

Required copper → $= \frac{3}{11}$

So, the required ratio is 4 : 7

Since it is clear from the above values

(1 + 2 → 3 and 4 + 7 → 11)

Alternatively : By Alligation



$$\frac{1}{77} : \frac{1}{44}$$

$$\Rightarrow \quad \frac{1}{7} : \frac{1}{4}$$

$$4 : 7$$

7. Ratio of W_1 M_1 W_2 M_2 W_3 M_3

1 : 3 2 : 3 2 : 5

Proportion of water $\frac{1}{4} : \frac{2}{5} : \frac{2}{7}$

$$\Rightarrow \quad \frac{1}{4} \times \frac{5\times7}{5\times7} : \frac{2}{5} \times \frac{4\times7}{4\times7} : \frac{2}{7} \times \frac{4\times5}{4\times5}$$

$$\Rightarrow \quad \frac{35}{140} : \frac{56}{140} : \frac{40}{140}$$

Now since all these three mixtures are mixed in the ratio of 2 : 3 : 5

Therefore new ratio $= \frac{35}{140} \times \frac{2}{2} : \frac{56\times3}{140\times3} : \frac{40\times5}{140\times5}$

$$= \frac{70}{280}, \frac{168}{420}, \frac{200}{700}$$

Now, the amount of water = 70 + 168 + 200 = 438

$\therefore$ The amount of milk = (280 + 420 + 700) − 438 = 962

$\therefore$ Ratio of milk to water = 962 : 438

Scanned by CamScanner

yoursmahboob.wordpress.com

8. $B_1 : B_2 : B_3 = 3x : 4x : 5x$

again $B_1 : B_2 : B_3 = 5y : 4y : 3y$

Since there is increase in no. of oranges in first two basket only, it means the no. of oranges remains constant in the third basket

$\therefore \quad 5x = 3y$

Hence $3x : 4x : 5x$

$\Rightarrow \quad \frac{9y}{5} : \frac{12y}{5} : \frac{15y}{5} = 9y : 12y : 15y$

and $5y : 4y : 3y \Rightarrow 25y : 20y : 15y$

Therefore, increase in first basket = 16

and increase in second basket = 8

$\therefore$ the required ratio = 2 : 1

9. Amount of alcohol in first vessel = $0.25 \times 2 = 0.5$ litre

amount of alcohol in second vessel = $0.4 \times 6 = 2.4$ litre

Total amount of alcohol out of 10 litres of mixture is $0.5 + 2.4 = 2.9$ litre

Hence, the concetration of the mixture is 29% $\left(= \frac{2.9}{10} \times 100\right)$

10. Assume the weight of Alloy A is 100 kg

$\therefore$ The weight of Alloy B is 400 kg

		Gold	Silver	Copper
$\therefore$	A	40 kg	60 kg	0 kg
	B	140 kg	160 kg	100 kg
$\therefore$	total →	180 kg	220 kg	100 kg

$\therefore$ Ratio of Gold and Silver in new alloy $= \frac{180}{500} : \frac{200}{500}$

$= 36\% : 44\%$

11.

Urea			Dia		
N	P	K	N	P	K
x	y	0	20%	70%	10%

Mixture		
N	P	K
26%	68%	6%

This 6% of K is obtained only from Dia.

$\therefore$

Urea			Dia		
N	P	K	N	P	K
x	y	0	120	420	60

Mixture		
N	P	K
260	680	60

$N_U + N_D = N_M \Rightarrow N_U + 120 = 260$

$N \rightarrow$ Nitrogen, $P \rightarrow$ Phosphorus

and $P_U + P_D = P_M \Rightarrow P_U + 420 = 680$

$U, D, M \rightarrow$ Urea, Dia and mixture

$\therefore$ Amount of Nitrogen in Urea = 140

and amount of Phosphorus in Dia = 260

$\therefore$ Ratio of $N : P = 7 : 13 \Rightarrow 35 : 65$

12.

X		Y	
C	N	C	N
2	7	5	4

Copper → $\frac{2}{9} = \frac{4}{18}$ Copper → $\frac{5}{9} = \frac{10}{18}$

$\therefore$ **By alligation**



$\therefore$ amount of $X = \frac{1}{6} \times 42 = 7$ kg

and amount of $Y = \frac{5}{6} \times 42 = 35$ kg

13.

	First	Alloy	Second	Alloy
	C	Al	C	Al
	1	2	3	1

$\therefore$	Required	alloy
	C	Al
	2	1

$\therefore$ Copper in first alloy $= \frac{1}{3}$

copper in second alloy $= \frac{3}{4}$

copper in required alloy (mixture) $= \frac{2}{3}$

Now, **by alligation**



$\Rightarrow \quad 1 : 4$

Therefore, second alloy be mixed 4 times the first alloy.

14. Note in this type of question individual prices does not matter. To prove this solve it algebrically.

$$\text{Exchanged amount} = \frac{3 \times 150 + 5 \times 90}{2(3+5)}$$

$$= \frac{450}{8} = 56.25 \text{ litre}$$

Here 3 and 5 are obtained from the ratio of amounts *i.e.*, from 90 and 150.

15. Here the ratio of mixtures (*i.e.*, milk, water) does not matter. But the important point is that whether the total amount (either pure or mixture) being transferred is equal or not. Since the total amount (*i.e.*, 5 cups) being transferred from each one to another, hence $A = B$.

HINT You can verify it very easly by considering a simple example.

16. CP. of rasgulla = Rs. 9 (since profit is 66.66%)

Now by alligation



$\frac{(9-3x)}{(7x-9)} = \frac{3}{5} \Rightarrow x = 2$

$\therefore$ Price of sugar = $7x$ = Rs. 14 per kg.

Scanned by CamScanner

yoursmahboob.wordpress.com

5 PERCENTAGES

It is one of the most important chapters which is the backbone of calculations either involved in commercial arithmetic or in real life. Personally I do maximum arithmetical calculation using percentage and others too. So in the context of calculation it is necessary to know the clear concepts of percentage which plays a very vital role in Data Interpretation besides quantitative Aptitude section. On an average two problems *i.e.*, nearly 4–5 % problems in QA only, are being asked in CAT every year.

In other entrance/competitive exams like MAT, XAT and UPMCAT, etc there are too many questions asked from this chapter.

PERCENTAGE AND ITS APPLICATION

A fraction with denominator 100 is called a per cent. Per cent is an abbreviation for the latin word "percentum" meaning "per hundred " or "hundredhs" and is denoted by symbol %.

NOTE A fraction with denominator 10 is called as decimal.

Since per cent is a form of fraction, we can express per cent as fractions (or decimals) and *vice-versa*.

CONVERSION OF A FRACTION INTO PERCENTAGE

To convert a fraction into a percentage, multiply the fraction by 100 and put "%" sign.

EXAMPLE 1 *Convert the following fractions into percentages:*

(i) $\frac{1}{2}$ *(ii)* $\frac{3}{4}$ *(iii)* $\frac{4}{5}$ *(iv)* $\frac{7}{8}$

SOLUTION (i) $\frac{1}{2} \to \frac{1}{2} \times 100 = 50\%$

(ii) $\frac{3}{4} \to \frac{3}{4} \times 100 = 75\%$

(iii) $\frac{4}{5} \to \frac{4}{5} \times 100 = 80\%$

(iv) $\frac{7}{8} \to \frac{7}{8} \times 100 = 87.5\%$

CONVERSION OF A PERCENTAGE INTO A FRACTION

To convert a percentage into a fraction, replace the % sign with $\frac{1}{100}$ and reduce the fraction to simplest form.

EXAMPLE 2 *Express the following percentage as fraction*

(i) 20% *(ii)* 30% *(iii)* 45% *(iv)* $5\frac{1}{8}$ %

(v) 155%

SOLUTION (i) $20\% = \frac{20}{100} = \frac{1}{5}$

(ii) $30\% = \frac{30}{100} = \frac{3}{10}$

(iii) $45\% = \frac{45}{100} = \frac{9}{20}$

(iv) $5\frac{1}{8}\% = \frac{41}{8 \times 100} = \frac{41}{800}$

(v) $155\% = \frac{155}{100} = \frac{31}{20} = 1\frac{11}{20}$

CONVERSION OF A PERCENTAGE INTO A RATIO

To convert a percentage into a ratio, first convert the given percentage into a fraction in simplest form and then to a ratio.

EXAMPLE 3 *Solve the following :*

(i) 38% *(ii) 25%* *(iii) 66.66%*

SOLUTION (i) $38\% = \frac{38}{100} = \frac{19}{50} = 19:50$

(ii) $25\% = \frac{25}{100} = \frac{1}{4} = 1:4$

(iii) $66.66\% = 66\frac{2}{3}\% = \frac{200}{3 \times 100} = \frac{2}{3} = 2:3$

CONVERSION OF A RATIO INTO A PERCENTAGE

To convert a ratio into a percentage, first convert the given ratio into a fraction then to a percentage.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 4 *Express the following ratios as percentage :*
(i) 1 : 5 (ii) 2 : 3 (iii) 4 : 9

SOLUTION (i) $1:5=\frac{1}{5}=\frac{1}{5}\times100=20\%$

(ii) $2:3=\frac{2}{3}=\frac{2}{3}\times100=66.66\%$

(iii) $4:9=\frac{4}{9}=\frac{4}{9}\times100=44.44\%$

CONVERSION OF A PERCENTAGE INTO A DECIMAL

To convert a percentage into a decimal remove the % sign and move the decimal point two places to the left.

EXAMPLE 5 *Convert the following percentages into decimals :*
(i) 36% (ii) 250% (iii) 57.5% (iv) $17\frac{1}{5}\%$ (v) 7%

SOLUTION (i) $36\% = 0.36$

(ii) $250\% = 2.50 = 2.5$

(iii) $57.5\% = 0.575$

(iv) $17\frac{1}{5}\% = 17.2\% = 0.172$

(v) $7\% = 0.07$

CONVERSION OF A DECIMAL INTO A PERCENTAGE

To convert a decimal into a percentage, move the decimal point two place to the right (adding zeros if necessary) and put % sign.

EXAMPLE 6 *Convert the following decimals into percentages :*
(i) 0.35 (ii) 8.12 (iii) 0.018

SOLUTION (i) $0.35 = 35\%$

(ii) $8.12 = 812\%$

(iii) $0.018 = 1.8\%$

- Work out some more examples so that all these thing rest on your fingure tips.

Remember $\frac{1}{2}=\frac{2}{4}=\frac{3}{6}=\frac{4}{8}=\ldots=50\%$ etc.

Learn and practice all the values given below.

CONVERSION OF FRACTION INTO PERCENTAGE

NUMERATORS

DENOMINATORS	1	2	3	4	5	6	7	8	9	10	11	12
1	100	200	300	400	500	600	700	800	900	1000	1100	1200
2	50	100	150	200	250	300	350	400	450	500	550	600
3	33.33	66.66	100	133.33	166.66	200	233.33	266.66	300	333.33	366.60	400
4	25	50	75	100	125	150	175	200	225	250	275	300
5	20	40	60	80	100	120	140	160	180	200	220	240
6	16.66	33.33	50	66.66	83.33	100	116.66	133.33	150	166.66	183.33	200
7	14.28	28.56	42.85	57.13	71.42	85.71	100	114.28	128.56	142.85	157.13	171.42
8	12.5	25	37.5	50	62.5	75	87.5	100	112.5	125	137.5	150
9	11.11	22.22	33.33	44.44	55.55	66.66	77.77	88.88	100	111.11	122.22	133.33
10	10	20	30	40	50	60	70	80	90	100	110	120
11	9.09	18.18	27.27	36.36	45.45	54.54	63.63	72.72	81.81	90.9	100	109.09
12	8.33	16.66	25	33.33	41.66	50	58.33	66.66	75	83.33	91.66	100
15	6.66	13.33	20	26.66	33.33	40	46.66	53.33	60	66.66	73.33	80

(PERCENTAGE-FRACTION CONVERSION TABLE)

Remember : $\frac{1}{7}=14.28\%$ and $\frac{1}{14}=7.14\%$

$\frac{1}{6}=16.66\%$ and $\frac{1}{15}=6.66\%$

$\frac{1}{9}=11.11\%$ and $\frac{1}{11}=9.09\%$

$\frac{1}{15}=6.66\%$ and $\frac{1}{16}=6.25\%$

$\frac{1}{3}=33.33\%$ and $\frac{3}{10}=30\%$

99.99% is equivalent to 100% (in calculation)

SOME OTHER TYPICAL VALUES

$\frac{1}{13}=7.69\%\approx7.7\%$, $\frac{1}{17}=5.88\%$, $\frac{1}{19}=5.26\%$,

$\frac{1}{21}=4.76\%$, $\frac{1}{23}=4.35\%$, $\frac{1}{24}=4.166\%$

Learnings from the table :

(i) This table is a first hand support as a percentage values of some frequently used fractions.

(ii) All the percentage values whose decimal part is 0.33, 0.66, 0.00 contain the denominator 3 in the fraction.

(iii) Similarly if there is 0.16, 0.33, 0.50, 0.66, 0.83, 0.00 it means there is a 6 in the denominator of the fraction.

Scanned by CamScanner

yoursmahboob.wordpress.com

(iv) Similarly if there is 0.28, 0.56, 0.85, 0.13, 0.42, 0.71 it means there is a 7 as denominator.

(v) If there is 0.11, 0.22, 0.33, 0.44 ... 0.99 etc. It means there is 9 as the denominator of the fraction.

(vi) If there is 0.09, 0.18, 0.27 ... it means there is 11 as the denominator of the fraction.

(viii) If two percentage values have different decimal values (there must be different denominators) then their addition or subtraction results always in decimal *i.e.*, never as an integer.

PERCENTAGE OF A QUANTITY

EXAMPLE 1 *Find the no. of male students (i.e., boys), if there are 42% male students in the school and the total no. of students in the school is 1000.*

SOLUTION Required number of male students

$$= 42\% \text{ of } 1000$$

$$= \frac{42}{100} \times 1000 = 420$$

EXAMPLE 2 *A student scored 85% marks. Total marks were 400. How much did he score?*

SOLUTION Marks scored = 85% of 400

$$= \frac{85}{100} \times 400$$

$$= 340$$

EXAMPLE 3 *In an orchard $16\frac{2}{3}\%$ of the trees are mango trees. If the total number of trees in the orchard is 360, find the number of other types of trees in the orchard.*

SOLUTION Total number of trees = 360

Number of mango trees = $16\frac{2}{3}\%$ of 360

$$= \frac{50}{3 \times 100} \times 360 = 60$$

Therefore, the number of other trees = 360 − 60 = 300

Alternatively: Number of mango trees = $16\frac{2}{3}\%$

It means no. of other types of trees = $\left(100 - 16\frac{2}{3}\right)\%$

$$= 83\frac{1}{3}\%$$

Thus number of other types of trees = $83\frac{1}{3}\%$ of 360 = 300

INTRODUCTORY EXERCISE-5.1

1. Find the value of :
   (i) 25% of 200 (ii) 30% of 180
   (iii) 37.5% of 300 (iv) 83.33% of 480
   (v) 100% of 2 quintal (vi) 165% of 330 litre
   (vii) $5\frac{1}{2}\%$ of Rs. 1600 (viii) 10% of 1 hour
   (ix) 66.66% of 300
   (x) 20% of 1 million rupees.
2. Mr. Arvind Vidyarthi spends 30% of his money on education and he has total Rs. 15,000. How many rupees he spends on education?
3. Sonia purchased 80 metres of cloth, out of which 35% was used for making trousers. How much cloth was used by her for making trousers?
4. The total no. of students in the school are 1250. 40% of the students are girls. Find the number of boys.
5. William's monthly salary was Rs. 1140 . His salary is increased by 16.66%. How much increase has he gotten? Also find the salary if his salary increased by 33.33%.
6. The population of Vatican city is 700. If it increases by 7.14% per annum (*i.e.*, every year). Find the population of the Vatican city after one year.
7. The speed of a car is 85 km/hr. It is increased by 20%. Find the increased speed of the car?
8. A shopkeeper announces a reduction of 8.33% on all its prices after new year. If a wrist watch was earlier for Rs. 2400. How much would it costs now?
9. 44% of the students in a class are females and the number of male students is 42. Find the total no. of students in the class.
10. 30% of a number is 225. Find the number.
11. A horse costing Rs 80,000 one year ago now costs 25% less. Find the changed price.
12. 1700 students took an exam 85% students passed it. Find the number of students who failed in the exam.

CAT Tips Now I would like to suggest you that all the problems mentioned in the exercise must be done using fractions instead of percentage, in order to make the calculation simple and handy.

For example see the solution of question 2 :

$15000 \times 0.3 = 4500$ $\left[\text{Recall } \frac{x \times 30}{100} = 0.3x\right]$

Solution for question 5 : Since $16.66\% = \frac{1}{6}$

So the new salary will increase by $\frac{1}{6}$ it means the absolute value of new salary will be $\frac{7}{6}\left(= 1 + \frac{1}{6}\right)$ times of the original salary.

So the increase in salary = $1140 \times \frac{1}{6}$ = Rs. 190

and increased salary = original salary + increase in salary

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= 1 + \frac{1}{6} = \frac{7}{6} = \frac{7}{6} \times 1140 = \text{Rs.}1330$$

Similarly if the salary is increased by 33. ›3% it means

$$33.33\% = \frac{1}{3}$$

Therefore new salary $= 1 + \frac{1}{3} = \frac{4}{3} = \frac{4}{3} \times 1140 = 1520$

Solution for question 6: Since $7.14\% = \frac{1}{14}$

So the new population of the city $= 700 \times \left(1 + \frac{1}{14}\right)$

$$= 700 \times \frac{15}{14} = 750$$

Solution for question 8: The reduced price of the watch

$$= 2400\left(1 - \frac{1}{12}\right) \qquad \left\{\because 8.33\% = \frac{1}{12}\right\}$$

$$= 2400 \times \frac{11}{12} = 2200$$

EXPRESSING ONE QUANTITY AS A PERCENTAGE OF ANOTHER QUANTITY

EXAMPLE 1 *What per cent is number 3 of number 20 ?*

SOLUTION As per cent means out of 100. Then by unitary method

out of $20 \rightarrow 3$

out of $1 \rightarrow \frac{3}{20}$

out of $100 \rightarrow \frac{3}{20} \times 100 = 15\%$

Hence to find what per cent the first number is of second number, we divide the first number by the second number and multiply the result by 100.

EXAMPLE 2 *Ravi obtained 325 marks out of a maximum of 400 marks. Find the percentage of marks obtained by him.*

SOLUTION Required percentage of marks $= \frac{325}{400} \times 100 = 81.25\%$

EXAMPLE 3 *In a factory of 150 workers, 18 were absent in a day what percentage were present?*

SOLUTION Present $= 150 - 18 = 132$

$$\text{Percentage presence} = \frac{132}{150} \times 100 = 88\%$$

EXAMPLE 4 *Kurla obtained 480 marks out of 600 and Birla obtained 560 marks out of 800. Whose performance is better?*

SOLUTION % marks of Kurla $= \frac{480}{600} \times 100 = 80\%$

$$\% \text{ marks of Birla} = \frac{560}{800} \times 100 = 70\%$$

So, obviously Kurla's performance is better than that of Birla even though getting less absolute marks.

INTRODUCTORY EXERCISE-5.2

1. What per cent is :
   (i) 30 out of 600 ?
   (ii) 25 out of 160 ?
   (iii) 75 out of 225 ?
   (iv) 36 kg of 150 kg ?
   (v) 90 cm of 4.5 metre.
   (vi) 60 litres of 40 litres
   (vii) 800 shirts out of 1200 shirts?
   (viii) 875 m of 2 km. ?
2. Express:
   (i) 20 as a percentage of 500.
   (ii) 60 kg as a per cent age of 80 kg .
   (iii) 350 ml as a percentage of 5.6 litre.
   (iv) Rs. 13 as a percentage of Rs. 39.
   (v) 15 seconds as a percentage of 1 hour.
   (vi) 27° as a percentage of 360°.
3. Manu scored 384 marks out of 450. What per cent marks did she get?
4. In an election, out of 60,000 eligible voters 42000 cast their vote. Calculate the percentage of voters casting their votes.
5. A tin contains 24 litres of milk. Due to leakage, 720 ml is lost. What per cent of milk is still present in the tin?
6. Price of an item increased from 16.50 to Rs. 41. 25. Find the percentage increase in price.
7. The excise duty on a certain item has been reduced to Rs. 3480 from Rs. 5220 . Find the percentage reduction in the excise duty for that item.
8. Out of total production of 6450 tonnes of a coalmine a quantity of 645 tonnes was lost during extraction. What per cent of the total production was the net coal extracted?
9. A cricket team played 24 matches. The team won 9 matches and lost 3 matches. 12 matches ended in draw. What per cent of the total matches did the team lose?
10. In a particular month, Rs. 10,000 were allocated for the food items in a hostel out of total Rs. 50,000 budget. Further Rs. 2000 is allocated for the fruits out of Rs.10,000 (allocated for food items) what per cent of total budget is spend on fruits only?

Scanned by CamScanner

yoursmahboob.wordpress.com

SOME MOST IMPORTANT VALUES

$\frac{1}{2} \to 50\%$, $\frac{1}{3} = 33.33\%$,

$\frac{2}{3} = 66.66\%$, $\frac{1}{4} \to 25\%$,

$\frac{3}{4} \to 75\%$, $\frac{1}{5} \to 20\%$,

$\frac{2}{5} \to 40\%$, $\frac{3}{5} \to 60\%$,

$\frac{1}{6} \to 16.66\%$, $\frac{5}{6} \to 83.33\%$

NOTE The application of percentage is very diverse in nature *e.g.* profit and loss, Simple and compound interest etc. All these are exactly based on the percentage increase/decrease of the original (or actual) value.

Percentage increase/decrease in a quantity

$$= \left(\frac{\text{change in quantity}}{\text{original quantity}} \times 100\right)\%$$

EXAMPLE 1 *The height of Abhimanyu some times ago was 110 cm. Now his height is 120 cm. Find the percentage change in his height.*

SOLUTION $\frac{120-110}{110} \times 100 = 9.09\%$

SHORTCUT $\frac{10}{110} \to \frac{1}{11} \to 9.09\%$

Alternatively: $\frac{12}{11} \to 109.09\%$, so increase = 9.09%

EXAMPLE 2 *The total expenses of a hostel were Rs. 8000 per month. Some students left the hostel due to which the new expenses come down by Rs. 1000. Find the percentage decrease in expenses of the hostel.*

SOLUTION $\frac{1000}{8000} \to \frac{1}{8} \to 12.5\%$

EXAMPLE 3 *Salary of Raja is Rs. 9000 per month and salary of Rani is Rs. 10,000 per month.*

(i) What per cent is the salary of Rani to that of Raja ?

(ii) What per cent is the salary of Raja to that of Rani?

SOLUTION (i) $\frac{10,000}{9,000} \times 100 = 111.11\%$

Alternatively:

$\frac{10}{9} \to \frac{9}{9} + \frac{1}{9} \to 100\% + 11.11\% \to 111.11\%$

(ii) $\frac{9}{10} \to 90\%$ $\left(\because \frac{1}{10} \to 10\%\right)$

Hence, salary of Raja is 90% to the salary of Rani.

PERCENTAGE CHANGE AND PERCENTAGE POINT CHANGE

Last year Abhijeet's salary was Rs. 10,000 and Sonu's salary was Rs. 8,000. This year Abhijeet's salary is Rs. 12,000 while Sonu's salary is Rs. 10,000.

1. (i) What is the percentage increase of Abhijeet's salary?

(ii) What is the percentage increase of Sonu's salary?

(iii) Percentage increase in Sonu's salary is how much percent greater than the percentage increase in Abhijeet's salary?

(iv) What is the percentage point change in the salary of Sonu and Abhijeet?

SOLUTION (i) $\frac{12,000-10,000}{10,000} \times 100 = 20\%$

or $\frac{2}{10} \to \frac{1}{5} \to 20\%$

(ii) $\frac{2}{8} \to \frac{1}{4} \to 25\%$

(iii) Percentage increase of Sonu's salary = 25

Percentage increase of Abhijeet's salary = 20

So the required percentage $= \frac{25-20}{20} \times 100 = 25\%$

It means percentage increase of Sonu's salary is 25% greater than the percentage increase of Abhijeet's salary.

(iv) Percentage point change

= (Percentage increase in Sonu's salary

− Percentage increase in Abhijeet's salary)

= 25 − 20 = 5 percentage point

Infact percentage point change is the difference between two percentage values.

ADVANCED CONCEPT OF PERCENTAGE CHANGE

(A) If a value p is increased by $x\%$, then we have to decrease the resultant value by $\left(\frac{x}{x+100} \times 100\right)\%$ to get back to the original value p.

Original value p $\xrightarrow{\text{increasing value}}$ $\underset{\text{increasing value}}{\frac{p \times x}{100}}$ $\longrightarrow$ Increased value $\left(p + \frac{px}{100}\right)$

$$= p\left(\frac{100+x}{100}\right)$$

Now the percentage decrease

$$= \frac{\left[p\left(\frac{100+x}{100}\right) - p\right]}{p\left(\frac{100+x}{100}\right)} \times 100 = \left(\frac{x}{100+x} \times 100\right)\%$$

In other words (*i.e.*, in terms of fraction) if a value is increased by $\frac{n}{d}$ then to get back the same number p from the resultant value, we have to decrease the increased value by $\left(\frac{n}{d+n}\right)$.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *Salary of Rajeev Ratan in 2001 was $100 per day and his salary in 2002 was $ 125 per day. Again in 2003 his salary was $ 100 per day.*

(i) What is the percentage increase in his salary in 2002?

(ii) What is the percentage decrease in his salary in 2003 over 2002?

SOLUTION (i) $\frac{125-100}{100}\times 100 = 25\%$

(ii) $\frac{125-100}{125}\times 100 = 20\%$

In fact there is same absolute change but percentage change is different due to different denominator (i.e., base change). So the base change is as much important as the numerator or absolute change in quantity.

EXAMPLE 2 *Age of Ravi is 20 years. If the Shyam's age is 25% greater than that of Ravi then how much per cent Ravi's age is less than Shyam's age ?*

SOLUTION Age of Ravi Age of Shyam

$$20 \underset{(-20\%)}{\overset{(+25\%)}{\rightleftarrows}} 25$$

Solution using percentage change formula

Here $x = 25$, then

percentage decrease (or less) $= \frac{25}{125}\times 100 = 20\%$

Solution using fractional change formula

Since increase $= \frac{1}{4}$ $\quad\because \left(25\% = \frac{1}{4}\right)$

Therefore decrease $= \frac{1}{4+1} = \frac{1}{5} \to 20\%$

EXAMPLE 3 *Gautam has 33.33% more pencils than Rahul has. By how much per cent less pencils Rahul has than that of Gautam?*

SOLUTION

$$33.33\% \to \frac{1}{3}$$

Rahul ⇄ Gautam

$$-25\% = \frac{1}{4} = \frac{1}{3+1}$$

So Rahul has 25% less pencils than Gautam has.

EXAMPLE 4 *Height of Amitabh is 50% greater than the height of Amir Khan. Height of Amir Khan is how much per cent less than that of Amitabh?*

SOLUTION

$$+50\% \to \frac{1}{2}$$

Amir ⇄ Amitabh

$$-33.33\% = \frac{1}{3} = \frac{1}{2+1}$$

Thus the height of Amir is 33.33% less than Amitabh.

Explanation of Concept : Assume A has 10 apples and B has 20 apples, then we say that B has 100% more apples than A has. Again we can say that A has 50% less apples than B has.

To calculate the percentage change :

$$100\% \to \frac{1}{1}$$

$A \rightleftarrows B$

$$-50\% = \frac{1}{2} = \frac{1}{1+1}$$

Consider another example : Let us assume A has 6 chocolates and B has 10 chocolates then we can say that B has 66.66% more chocolates than A. So again we can also say that A has 40% less chocolates than B.

$$66.66\% \to \frac{2}{3}$$

$A \rightleftarrows B$

$$-40\% = \frac{2}{5} = \frac{2}{3+2}$$

Remember the percentage change graphic is almost 70–80% better in giving quick and simple results. So instead of using the percentage formula, use the percentage change graphic method. For this you are just required to know the percentage fraction conversion table.

(B) If a value P is first decreased by $x\%$ then to get back the original value P, we have to increase the decreased (resultant) value by $\left(\frac{x}{100-x}\times 100\right)$

$$\underset{P}{\text{original value}} \xrightarrow[\frac{Px}{100}]{\text{(decreasing value)}} \underbrace{\left(P-\frac{Px}{100}\right)}_{\text{decreased value}} = P\left(1-\frac{x}{100}\right)$$

Now, the per cent increase $= \frac{\left[P-P\left(1-\frac{x}{100}\right)\right]}{P\left(1-\frac{x}{100}\right)}\times 100$

$$= \frac{x}{100-x}\times 100$$

In terms of fraction, if a value P is first decreased by n/d then to get back the original number P. We have to increase the decreased (or resultant) value by $\frac{n}{d-n}$.

EXAMPLE 5 *Due to irregular working habits of Ramachandran, his salary was reduced by 20% but after some months his salary was increased to the original salary. What is the percentage increase in salary of Ramachandran?*

SOLUTION Let initial salary be Rs. 100

$$100 \underset{+25\%}{\overset{-20\%}{\rightleftarrows}} 80$$

Alternatively : Here $x = 20$

then % increase $= \frac{20}{(100-20)}\times 100 = 25\%$

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively:



Hence his salary will be incresed by 25%

EXAMPLE 6 *Kajol usually wears saree, which is 16.66% less than the actual length of the saree. By how much per cent the actual length of the saree is greater than the length of saree which kajol usually wears?*

SOLUTION



So the actual length of the saree is 20% greater than the usually used saree.

NOTE
(1) If a value X is first increased by p% to Y then Y is again decreased to X by q% then p is always greater than q (for positive values)
(2) If a value X is first decreased by p% to Y and then Y is increased by q% to X, then p is always less than q.
(3) If a value A is increased by p% then again by q% once again it is increased by r%, then the final value will be same as if you change the order of p, q, r *i.e.*, A can be first increased by r% then by q% and then by p% still the result will be same.
(4) The rule 3 is also applicable for the decreasing of the values. A value 'A' is first decreased by p%, then by q% and then by r% and so on, the resultant value will be same as when A is first decreased by q% then by p% and then by r% etc.
Note : In case 3 and 4 we are discussing the successive increase or decrease in the value.
(5) A value 'A' is first increased by p% then by q% and then it is reduced by r% will give the same results as when A is first decreased by r%, then increased by q% and then by p% etc.

EXAMPLE 7 *Initially Ms. Rakhi Sawant has Rs. 200 in her wallet then she increased it by 20%. Once again she increased her amount by 25%. The final value of money in her wallet will be how much per cent greater than the initial amount.*

SOLUTION $200 \xrightarrow{+20\%} 240 \xrightarrow{+25\%} 300$

So the required % increase $= \dfrac{300-200}{200} \times 100 = 50\%$

EXAMPLE 8 *The age of B is 50% greater than the age of A. The age of C is 20% less than the age of B. By how much percentage the age of C is greater than the age of A.*

SOLUTION $\underset{100}{A} \xrightarrow{+50\%} \underset{150}{B} \xrightarrow{-20\%} \underset{120}{C}$

So the required percentage change $= \dfrac{20}{100} \times 100$

$= 20\%$

CONCEPT OF PRODUCT CONSTANCY

It is the same as we know the inverse proportion in the chapter of Ratio, Proportion and Variation.

e.g., When the rate of a pencil is Rs. 1.25 then we can purchase 16 pencils by paying Rs. 20. If the rate of a pencil is decreased by Rs. 0.25 then we can purchase 20 pencils by paying Rs. 20.

Explanation : Rate × No. of pencils = Price

$$1.25 \times 16 = 20$$
$$1.00 \times 20 = 20$$

So you can see that here the product (20) is constant in both the cases. Thus it is clear that if we reduce the price of a pencil to Rs. 0.50, then we can purchase 40 pencils in Rs. 20.

Some more examples of product constancy :
(i) speed × time = distance
(ii) rate × time = cost
(iii) efficiency × time = work
(iv) length × breadth = area
(v) average × no of elements = total value
(vi) rate × quantity = price (or expenditure)

e.g., The price of sugar is increased by 25% then by how much per cent should a customer reduce the consumption (*i.e.*, quantity used) of sugar so that he has not to increase his expenses on sugar.

price × quantity = expenditure

$$100 \times 100 = 10{,}000$$
$$125 \times x = 10{,}000$$

$\Rightarrow x = \dfrac{10{,}000}{125} = 80$. Therefore % reduction = 20%

or $1 \times 1 = 1$

$1.25 \times k = 1 \Rightarrow k = 0.8$

thus there will be 20% decrease in the consumption of sugar in order to maintain the same expenditure on sugar.

PRODUCT CONSTANCY CONDITIONS

- When one factor of a product is increased by p% then the other factor will be decreased by $\left(\dfrac{p}{100+p} \times 100\right)$%

  It means when one factor of a product is increased by $\dfrac{n}{d}$ then the other factor is decreased by $\dfrac{n}{(d+n)}$.

- When one factor of a product is decreased by p% then the other factor will be increased by $\left(\dfrac{p}{100-p} \times 100\right)$%

  It means when one factor of a product is decreased by $\dfrac{n}{d}$ then the other factor will must be increased by $\dfrac{n}{(d-n)}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *If the price of a commodity be raised by 20% then by how much per cent a house holder reduce his consumption of the same commodity so that his expenditure does not increase.*

SOLUTION Since here product (i.e., expenditure) is constant
rate × consumption = expenditure

$$\text{initially} \rightarrow 1 \times 1 = 1$$

After change $1.2 \times x = 1$

$\Rightarrow x = 0.833 \therefore$ decrease in value = 16.66%

Alternatively:

Increase in rate		Decrease in consumption
$+20\% = +\frac{1}{5}$	$\longrightarrow$	$-16.66\% = -\frac{1}{6}$

EXAMPLE 2 *If the price of petrol falls down by 20% by how much per cent must a person increase its consumption, so as not to decrease the expenditure on this item?*

SOLUTION Since product is constant

decrease by		increase by	
$20\% = \frac{1}{5}$	$\longrightarrow$	$\frac{1}{4} = 25\%$	$\left[\because \frac{n}{d} \rightarrow \frac{n}{(d-n)}\right]$

EXAMPLE 3 *Due to 50% increase in the price of rice . We purchased 5 kg less rice with the same amount of Rs. 60. What is the new price of rice?*

(a) Rs. 4.66 (b) Rs. 5
(c) Rs. 4 (d) Rs. 6

SOLUTION

Increase in price		Decrease in amount
$50\% = \frac{1}{2}$	$\longrightarrow$	$\frac{1}{3} = 33.33\%$

Since the new quantity of rice decreases by 33.33% which is equal to 5 kg it means initially there was 15 kg rice to be used.

So, the initial price = Rs. 4 $\quad \because \left(\frac{60}{15} = 4\right)$

and final price = Rs. 6 $\quad \because \left(\frac{60}{10} = 6\right)$

Alternatively: From the options.
Let us consider choice (d).

Therefore $[6 \times 10 = 60]$ (finally)

Hence $[4 \times 15 = 60]$ (initialy)

EXAMPLE 4 *The length of a plot is decreased by 33.33%. By how much % the breadth of the plot will be increased so that the area remains constant?*

SOLUTION

(Decrease)		(Increase)	
$33.33 = \frac{1}{3}$	$\longrightarrow$	$\frac{1}{2} = 50\%$	$\left[\frac{1}{2} = \frac{1}{3-1}\right]$

CONCEPT OF 'BY' AND 'TO'

Please note that there is a clear difference between "by" and "to". *e.g.*, the income is reduced by 40% it means the new income is 60% of the original and the income is reduced to 40% means the new income is 40% of the original value. Thus "by" represents difference and "to" represents final value.

e.g., The income of Sarika is increased by 20% means its new income is 100 + 20 = 120 % of the original income. The income of Sarika is increased to 120% means the new income of Sarika is 120% of the original income.

EXAMPLE 1 *In an election between two candidates, the candidate who got 57% valid votes won by a majority of 420 votes. Find the total no. of valid votes.*

SOLUTION

Winner	Loser	
$0.57x$	$0.43x$	$[100 - 57 = 43]$
$0.14x$		$[57 - 43 = 14]$

$0.14x = 420$

$x = 3000$

Hence total valid votes = 3000

EXAMPLE 2 *Due to fall in manpower, the production in the factory decreases by 60% By what per cent should the working hour be increased to restore the original production in the factory?*

SOLUTION Manpower × Working hours = Production

$$(-60\%) = \frac{3}{5} \longrightarrow \frac{3}{2} = (+150\%) \quad \left[\frac{3}{5} \rightarrow \frac{3}{5-3} = \frac{3}{2}\right]$$

Hence by 150% working hours will be increased. It means the new working hours will be 2.5 times (not 1.5 times) of the original time.

EXAMPLE 3 *Two numbers are respectively 25% and 40% less than a third number. What per cent is the second of the first ?*

SOLUTION Consider A, B, C three numbers and assume $C = 100$ (as a base)



Now $\frac{60}{75} \times 100 = 80\%$

EXAMPLE 4 *A person gives 10% to his wife 10% of the remaining to a hospital (as a donation) again 10% of the remaining to prime minister's relief Fund. Then he has only 7290 Rs. with him. What was the initial sum of money with that person?*

SOLUTION Since he gives 10% so he is left with 90% of the original sum and since he does the same with the remaining (or left) amount. So it forms a chain.

$\therefore$ Remaining amount $= (x) \times 0.9 \times 0.9 \times 0.9$

$= 0.729x = 7290$

$\Rightarrow x = 10{,}000$, where x is supposed to be initial amount.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 5 *Initially a shopkeeper had n chocolates. A customer bought 10% chocolate from n then another customer bought 20% of the remaining chocolates, after that one more customer purchased 25% of the remaining chocolates. Finally shopkeeper is left with 270 chocolates in his shop. How many chocolates were there initially in his shop?*

(a) 300 *(b) 450* *(c) 500* *(d) 600*

SOLUTION $n \times 0.9 \times 0.8 \times 0.75 = 270$

$$n = \frac{270 \times 10{,}000}{9 \times 8 \times 75}$$

$$n = 500$$

NOTE These type of problems (see example no. 4 and 5) can be solved with a great convenience if we solve in reverse order, with the aid of given choices.

Let us consider option (c)

$500 \times 0.9 = 450$

$450 \times 0.8 = 360$

$360 \times 0.75 = 270$

Hence presumed option is correct.

POPULATION RELATED MATHEMATICAL PROBLEMS

If the original population of a locality (*i.e.*, region) be P and the annual growth rate be $r\%$. The population after n years

$$= P\left(1 + \frac{r}{100}\right)^n$$

change (or increase) in the population

$$= P\left[\left(1 + \frac{r}{100}\right)^n - 1\right]$$

If there is decrease in population be $r\%$ then,

total population after n years $= P\left(1 - \frac{r}{100}\right)^n$

and decrease in population $= P\left[1 - \left(1 - \frac{r}{100}\right)^n\right]$

EXAMPLE 1 *If the annual increase in the population be 20% and the present population be 10,000. What will be the population after 3 years hence?*

(a) 16,000 *(b) 17,280*

(c) 14,400 *(d) 1,728*

SOLUTION $10{,}000\left(1 + \frac{20}{100}\right)^3 = 10{,}000\left(\frac{6}{5}\right)^3$

$$= 10{,}000 \times (1.2)^3 = 17{,}280$$

Hence (b) is correct.

EXAMPLE 2 *The population of a town in the first year increases by 10% in the next year it decreases by 10% Once again in the third year it increase by 10% and in the fourth year it decrease by 10%. If the present population be 20,000 then the population after four years will be :*

(a) 16,902 *(b) 19,602*

(c) 20,000 *(d) none of these*

SOLUTION $20{,}000\left(1 + \frac{10}{100}\right)\left(1 - \frac{10}{100}\right)\left(1 + \frac{10}{100}\right)\left(1 - \frac{10}{100}\right)$

$$= 20{,}000\,(1.1)\,(0.9)\,(1.1)\,(0.9)$$

$$= 20{,}000 \times 1.21 \times 0.81 = 19{,}602$$

Thus option (b) is correct.

NOTE If the value of a number is first increased by $x\%$ and then decreased by $x\%$, the net change is always a decreases (or loss) in original value.

Hence, $\%\ \text{loss} = \left(\frac{x}{10}\right)^2\%$

EXAMPLE 1 *Shweta is a very expert in bargaining. Once she went to a nearby shop. When Shweta asked the price of Shampoo Sachet the shopkeeper told her the price by increasing 15% of the original cost. But Shweta insisted to decrease the price by 15% so the shopkeeper sold it by decreasing the price by 15% What is the loss or profit of shopkeeper and by how much percent?*

(a) no loss *(b) profit of 1.5%*

(c) loss of 2.25% *(d) none of these*

SOLUTION Let the actual price be 100

$$100 \xrightarrow{+15\%} 115 \xrightarrow{-15\%} 97.75 \quad \text{(loss of 2.25\%)}$$

Alternatively: $\text{loss}\% = \left(\frac{15}{10}\right)^2 = 2.25\%$

There is always a loss.

EXAMPLE 2 *If the length and breadth of a rectangle are changed by + 20% and − 10% What is the percentage change in area of rectangle?*

(a) 8% *(b) 10.8%*

(c) 20% *(d) data insufficient*

SOLUTION $l \times b = \text{area}$

$1 \times 1 = 1$

$1.2 \times 0.9 = 1.08$

So there is 8% increase in the area of rectangle.

EXAMPLE 3 *The salary of A is 20% lower than B's salary and the salary of C is 56.25% greater than A's salary. By how much percent the salary of B is less than the salary of C.*

SOLUTION $A \quad B \quad C$

$80 \xleftarrow{(-20\%)} 100 \quad 125$ (Consider the salary of $B = 100$)

$+56.25\%$

The required value $= \frac{25}{125} \times 100 = 20\%$

Remember: Percentage change

$$= \left(\frac{\text{difference between original value and new value}}{\text{original value}}\right) \times 100$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$\text{Percentage increase} = \frac{\text{increased value} - \text{original value}}{\text{original value}} \times 100$$

$$\text{Percentage decrease} = \frac{\text{original value} - \text{decreased value}}{\text{original value}} \times 100$$

NOTE (1) There is a huge difference between "decreased value" and "decrease in value" and between "increased value" and "increase in value".

For example : Initial value = 70

Final value = 90

it means increased value is = 90

but increase in value is 20

and % increase = $\frac{90-70}{70} \times 100 = 28.57\%$

(2) If there is increase of $\frac{x}{y}$ in any value P then the increased value will be $P\left(1+\frac{x}{y}\right)$.

(3) If there is decrease of $\frac{x}{y}$ in any value, then the decreased value will be $P\left(1-\frac{x}{y}\right)$.

EXAMPLE 1 *Nishith is now 20 years old. Some years later his age will increase by 50% of himself. What will be the new age at that time?*

SOLUTION $20\left(1+\frac{1}{2}\right) = 30$ years $\left[\because 20 + 20 \times \frac{1}{2} = 20\left(1+\frac{1}{2}\right)\right]$

EXAMPLE 2 *The average salary of Purushottam in Infosys is 20% less than that was in Microsoft. If the salary of Purushottam in Microsoft be $ 80,000 per month then what is the salary of Purushottam in Infosys?*

SOLUTION $20\% = \frac{1}{5}$

So new salary $= 80{,}000\left(1-\frac{1}{5}\right)$

$= 80{,}000 \times \frac{4}{5} = \$\,64{,}000$

NOTE Remember this type of problems can also be solved exactly through percentages.

As $80{,}000 \times 0.8$ $(100 - 20 = 80\%)$

$= 64{,}000$

but the technique given above is not less important. Some where it becomes very necessary to solve through fractions. So, keep your eyes open mind focussed and use your wits to solve the problems intelligently as per the situation.

EXAMPLE 3 *Which one of the following is greatest* $\frac{3}{4}, \frac{7}{8}, \frac{16}{19}, \frac{13}{15}$?

SOLUTION

$\frac{3}{4} = 75\%$

$\frac{7}{8} = 87.5\%$

$\frac{16}{19} = 84.21\%$

$\frac{13}{15} = 86.66\%$

So, $\frac{7}{8}$ is the greatest fraction (or rational number)

INTRODUCTORY EXERCISE-5.3

1. What per cent of $\frac{3}{7}$ is $\frac{1}{105}$?
   (a) 10% (b) 2.22%
   (c) 45% (d) 450%
2. What per cent is 3% of 15%?
   (a) 15% (b) 20%
   (c) 40% (d) 66.66%
3. If the cost of a calculator worth Rs 250 is increased by Rs. 100, the rate of increase is
   (a) 100% (b) 40%
   (c) 25% (d) none of these
4. A number increased by 37.5% gives 99 the number is
   (a) 140 (b) 61.5
   (c) 72 (d) 48
5. When 40% of a number is added to 42, the result is the number itself. The number is:
   (a) 105 (b) 72
   (c) 70 (d) 82
6. In an examination 52% of the candidates failed in Science 42% in Mathematics and 17% in both. The no. of those who passed in both the subjects, is :
   (a) 83% (b) 64%
   (c) 23% (d) 55.55%
7. The price of an item is increased by 20% and then decreased by 20%. The final price as compared to original price
   (a) 4% more (b) 20% more
   (c) 20% less (d) 4% less
8. Two candidates fought an election. One got 65% of the votes and won by 600 votes. The total no. of votes polled is:
   (a) 12,000 (b) 10,000
   (c) 2,000 (d) 8,000
9. Out of a no. of electronic items, a person purchases 60% coloured TVs 5% of these were found to be defective. The percentage of defective TVs in all is
   (a) 3% (b) 6%
   (c) 12% (d) can't be determined
10. A's salary is half that of B. If A got a 50% rise in his salary and B got a 25% rise in his salary, then the percentage increase in combined salaries of both is
    (a) 30% (b) 33.33%
    (c) 55% (d) 28%

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. In our Singapore office there are 60% female employees. 50% of all the male employees are computer literate. If there are total 62% employees computer literate out of the total 1600 employees, then the no. of female employees who are computer literate :
(a) 690 (b) 672
(c) 960 (d) can't be determined

2. The price of a car depreciates in the first year by 25% in the second year by 20% in the third year by 15% and so on. The final price of the car after 3 years, if the present cost of the car is Rs. 10,00,000 :
(a) 7,80,000 (b) 5,10,000
(c) 6,90,000 (d) 1,70,000

3. A shopkeeper charges sales tax of x% up to Rs. 2,000 and above it he charges y%. A customer pays total tax of Rs 320, when he purchases the goods worth Rs. 6,000 and he pay's the total tax of Rs. 680 for the goods worth Rs. 12,000. The value of $(x - y)$ is :
(a) 0 (b) – 2
(c) – 4 (d) 5

4. 40% of a number when added to the square of the same number, then it is increased to 4040% of itself the actual number is :
(a) 175 (b) 400
(c) 40 (d) 120

5. In my office there are 30% female employees and 30% of these earn greater than Rs. 8,000 per month and 80% of male employees earn less than Rs. 8,000 per month. What is the percentage of employees who earn more than Rs. 8,000 per month?
(a) 30% (b) 23%
(c) 60% (d) can't be determined

6. 600 students took the test on physics and chemistry. 35% students failed in Physics and 45% students failed in chemistry and 40% of those who passed in chemistry also passed in Physics, then how many students failed in both :
(a) 162 (b) 138
(c) 60 (d) none of these

7. In an examination 70% of the candidates passed in History and 50% in Geography and 20% students failed in both the subjects. If 500 students passed in both the subjects, then how many candidates appeared for the exam ?
(a) 1,000 (b) 1,500
(c) 2,500 (d) none of these

8. My salary is Rs. 12,345 per month. The salary of my brother is 10% greater than that of mine. The salary of my only sister is 9.09% greater than my only brother. The salary of my wife is $56\frac{12}{23}$% less than the total salary of my brother and sister together, then the salary of my wife is :
(a) greater than my sister's salary
(b) $33\frac{11}{23}$% less than my sister's salary
(c) equal to my salary
(d) $44\frac{11}{23}$% greater than my own salary

9. MDTV is a very popular TV channel. It telecasts the programmes from 8 : 00 a.m. to 12 : 00 p.m. It telecasts 60 advertisements each of 8 seconds and 16 advertisements each of 30 seconds. What is the percentage of time devoted in a day for the advertisements?
(a) 1.5% (b) 1.66%
(c) 2% (d) 2.5%

10. Lagaan is levied on the 60% of the cultivated land. The revenue department collected total Rs. 3,84,000 through the lagaan from the village of Sukhiya. Sukhiya, a very rich farmer, paid only Rs. 480 as lagaan. The percentage of total land of Sukhiya over the total taxable land of the village is :
(a) 0.15% (b) 15%
(c) 0.125% (d) none of these

11. The actual area of a rectangle is 60 cm^2, but while measuring its length a student decreases it by 20% and the breadth increases by 25%. The percentage error in area, calculated by the student is :
(a) 5% (b) 25%
(c) can't be determined (d) none of these

12. The cost of packaging of the mangoes is 40% the cost of fresh mangoes themselves. The cost of mangoes increased by 30% but the cost of packaging decreases by 50%, then the percentage change of the cost of packed mangoes, if the cost of packed mangoes is equal to the sum of the cost of fresh mangoes and cost of packaging :
(a) 14.17% (b) 7.14%
(c) 6.66% (d) none of these

13. Abhinav scores 80% in Physics and 66% in chemistry and the maximum marks of both the papers are 100. What per cent does he score in maths which is of 200 marks, if he scores 80% marks in all the three subjects :
(a) 74% (b) 84%
(c) 87% (d) 83%

14. In the New York Stock Exchange there are 45% female employees and thus the number of male employees is exceeded by 72. Hence the total no. of employees in the New York Stock Exchange is :
(a) 540 (b) 720
(c) 7200 (d) 550

Scanned by CamScanner

yoursmahboob.wordpress.com

15. Three candidates *A*, *B* and *C* contested an election. Out of the total votes on a voter list 25% did not vote and 6.66% votes polled were invalid. *C* got 2450 valid votes, which were 40% more than that of *B*. If *A* got only 40% of the total votes, then who is the winner?
(a) A (b) B
(c) C (d) can't be determined

16. The cost of a car is 400% greater than the cost of a bike. If there is an increase in the cost of the car is 15% and that of bike is 20%. Then the total increase in the cost of the 5 cars and 10 bikes is :
(a) 17.5% (b) $16\frac{3}{7}\%$
(c) 18.5% (d) 18.25%

17. The square of a positive number is 2,000% greater than the number itself, then the square of that number is :
(a) 1762 (b) 1635
(c) 441 (d) 139

18. The monthly salary of Shahid and Kareena together is $ 28,000. The salary of Shahid and Kareena is increased by 25% and 12.5% respectively then the new salary of Kareena becomes 120% of the new salary of Shahid. The new (or increased) salary of Shahid is :
(a) $ 15,000 (b) $ 18,000
(c) $ 14,000 (d) $ 16,000

19. 80% of a smaller number is 4 less than 40% of a larger number. The larger number is 85 greater than the smaller one. The sum of these two numbers is :
(a) 325 (b) 425
(c) 235 (d) 500

20. 220% of a number '*X*' is 44. What is 44% of '*X*'?
(a) 88 (b) 8.8
(c) 66 (d) data insufficient

21. The shopkeeper increased the price of a product by 25% so that customer finds it difficult to purchase the required amount. But somehow the customer managed to purchase only 70% of the required amount. What is the net difference in the expenditure on that product ?
(a) 10% more (b) 5% more
(c) 12.5% less (d) 17.5% less

22. In the previous government, party *Q* was in the opposition. Now increasing the seats by 33.33% Q is the ruling party and thus party Q enjoys twice the majority than that of party *P* in the previous government. If there were only two parties *P* and *Q* and the fix no. of seats be 500 in the parliament of Hum-Tum, then the no. of seats of the Q in the new government is :
(a) 225 (b) 200
(c) 275 (d) 300

23. In an examination a candidate got 30% marks and failed by 30 marks. If the passing marks are 60% of the total marks, then the maximum marks will be :
(a) 450 (b) 600
(c) 300 (d) 100

24. In a school there are 1800 students. Last day except 4% of the boys all the students were present in the school. Today except 5% of the girls all the students are present in the school, but in both the days no. of students present in the school, were same. The no. of girls in the school is :
(a) 1200 (b) 800
(c) 1000 (d) 600

25. In a library 60% of the books are in Hindi, 60% of the remaining are in English and rest of the books are in Urdu. If there are 3600 books in English, then the total no. of books in Urdu are :
(a) 2400 (b) 2500
(c) 3000 (d) none of these

26. In a test there are total *n* questions. Bhanu answers 20 out of 25 questions correctly in the first section. In the second section he answers 60% question correct and thus his total score is 66.66% in the test. Given that all the questions carry equal marks, without any negative marking. The total no. of question in the test is :
(a) 50 (b) 60
(c) 75 (d) 100

27. In a class of MBA students 16.66% students are from Science background and 12.5% students are from commerce background and 6.66% students from arts background and rest are from Engineering background. The minimum possible students of engineering background are :
(a) 45 (b) 77
(c) 100 (d) 120

28. An alloy contains the copper and aluminium in the ratio of 7 : 4. While making the weapons from this alloy, 12% of the alloy got destroyed. If there is 12 kg of aluminium in the weapon, then the weight of the alloy required is :
(a) 48 kg (b) 40 kg
(c) 37.5 kg (d) 14.4 kg

29. Hariharan goes to a shop to buy an FM radio costing Rs. 1404 including sales tax at 8%. He asks the shopkeeper to reduce the price of radio so that he can save the amount equal to the sales tax. The reduction of the price of the radio is :
(a) Rs. 108 (b) Rs.104
(c) Rs. 112.32 (d) none of these

30. The average weight of a class of students is 67.5 kg. The weight of the class teacher is 25% more than the average weight of the class. The average weight of the class is less than the class teacher by *x*%. The value of *x* is :
(a) 33.33% (b) 25%
(c) 20% (d) can't be determined

31. Last year in CAT, each section of the question paper had different weightage. The weightage of QA, DI and VA/RC sections was 8, 9 and 10 respectively. The maximum marks in all the three sections together were 810. Wrong answer did not carry negative marks as a penalty. If Padma had gotten 20% more marks in QA and 8% more marks in DI and 7.14...% more marks in VA/RC, then she must had gotten 100% marks in all the three sections. The total marks that Padma had scored :
(a) 730 (b) 700
(c) 750 (d) 775

32. A salesman gets commission on total sales at 9%. If the sale is exceeded Rs. 10,000 he gets an additional commission as bonus of 3% on the excess of sales over Rs. 10,000. If he gets total commission of Rs. 1380, then the bonus he received is :
(a) Rs. 180 (b) Rs. 120
(c) Rs. 480 (d) data insufficient

33. In Veeru Bhai Pvt. limited company 60% of the employees are men and 48% of the employees are Engineer and 66.6% of these are men. The percentage of women who are not engineers :
(a) 33.33% (b) 60%
(c) 52% (d) 46.66%

Scanned by CamScanner

yoursmahboob.wordpress.com

34. Initially Veer had 60% more love letters than that of Zara. In the last month the no. of love letters of Veer increased by 25% and that of Zara decreased by 25%. Again in the present month the no. of love letters of Veer decreased to 60% and that of Zara increased by 60%. Then which of the following statements is correct regarding the present no. of love letters :
(a) Veer has 40% more letters than that of Zara
(b) Zara has 20% less letters than that of Veer
(c) Veer and Zara have equal no of letters
(d) Zara has 37.5% less letters than that of Veer.

35. The charges per hour of internet surfing is increased by 25% then find the percentage decrease in the time period of surfing of a user (a net savy) who can afford only a 10% increase in expenditure :
(a) 22% (b) 12%
(c) 15% (d) 9.09%

36. The average earning of each member of the Ambani family is 20% less than the average earning of each member of the Sahara family and the total earning of Ambani's family is 20% more than the total earning of Saharas's family. The no. of family members in the Sahara is what per cent of the no. of family members of Ambani :
(a) 25% (b) 20%
(c) 66.66% (d) none of these

37. From 2000 onwards, till 2003 the price of computers increased every year by 10%. After that due to government subsidy the price of computers decreases every year by 10%. The price of a computer in 2006 will be approx. how much per cent less than the price in 2000 if the same pattern of price is continued :
(a) 2 (b) 3
(c) 4 (d) none of these

38. A book consists of 30 pages, 25 lines on each page and 35 characters on each line. If this content is written in another note book consisting of 30 lines and 28 characters per line, then the required no. of pages will how much per cent greater than the previous pages?
(a) 4.16% (b) 5%
(c) 6.66% (d) none of these

39. The rate of increase of the price of sugar is observed to be two per cent more than the inflation rate expressed in percentage. The price of sugar on January 1, 2004 is Rs. 20 per kg. The inflation rates of the years 2004 and 2005 are expected to be 8% each. The expected price of sugar on January 1, 2006 would be :
(a) Rs. 23.60 (b) Rs. 24.00
(c) Rs. 24.20 (d) Rs. 24.60

40. A club has raised 75% of the amount it needs for a new building by receiving an average donation of Rs. 600 from the people already solicited. The people already solicited represents 60% of the people the club will ask for donations. If the club is to raise exactly the amount needed for the new building, what should be the average donation from the remaining people to be solicited?
(a) 250 (b) 300
(c) 400 (d) 600

41. A number x is mistakenly divided by 10 instead of being multiplied by 10. What is the percentage error in the result?
(a) – 99% (b) + 99%
(c) – 100% (d) + 100%

42. What is the percentage change in the result when we add 50 to a certain number x, instead of subtracting 50 from the same number x ?
(a) 50% (b) 100%
(c) 300% (d) can't be determined

43. In the Regional Science Centre, Lucknow the rate of ticket is increased by 50% to increase the revenue, but simultaneously 20% of the visitors decreased. What is percentage change in the revenue of Regional Science Centre. If it is known that the centre collects the revenue only from the visitors and it has no other financial supports :
(a) + 20% (b) – 25%
(c) + 30% (d) can't be determined

44. Recently when I visited a show room of shoes shopkeeper told me that he could reduce the price of Bata shoes by 49% and if I were to purchase woodland shoes he could reduce the price to 51% of the original price. If the marked price (*i.e.*, printed price) of both the shoes was same, then which shoes was cheap to buy :
(a) Wood land (b) Bata
(c) both (d) can't say

45. Selling price of a shirt and a coat is Rs. 4000. The cost price of a shirt is 58.33% of the cost price of a coat and so amount of profit on both the shirt and coat is same, then the price of the shirt could be :
(a) Rs 2100 (b) Rs. 2525
(c) Rs. 2499 (d) Rs. 1120

46. On the April 1, 2005 my salary increased from Rs. 10,000 to Rs. 16,000. Simultaneously the rate of income tax decreased by 37.5% , So the amount of income tax paid by me remains constant what is the value of income tax paid by me :
(a) Rs. 3000 (b) Rs. 6000
(c) Rs. 1600 (d) can't be determined

47. In the previous question, if the difference in the rate of income tax be 9 (in percent) then the income tax paid by me :
(a) Rs. 2000 (b) Rs. 2400
(c) Rs. 1600 (d) none of these

48. The average of a set of whole numbers is 27.2. When the 20% of the elements (ie numbers) are eliminated from the set of numbers then the average becomes 34. The number of elements in the new set of numbers can be :
(a) 27 (b) 35
(c) 52 (d) 63

49. In a class, the no. of boys is more than the no. of girls by 12% of the total strength. The ratio of boys to girls is :
(a) 15 :11 (b) 11 : 14
(c) 14 :11 (d) 8 : 11

50. The population of a village is 5000 and it increases at the rate of 2% every year. After 2 years, the population will be :
(a) 5116 (b) 5202
(c) 5200 (d) 5204

51. A customer asks for the production of x number of goods. The company produces y number of goods daily. Out of which z% are unfit for sale. The order will be completed in :
(a) $\frac{x}{100\,y\,(1-z)}$ days (b) $\frac{100\,yz}{x}$ days
(c) $\frac{100\,x}{y\,(100-z)}$ days (d) $\frac{100}{y\,(z-1)}$ days

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL (2)

1. In the Awadh school Gomti Nagar, there are 500 students. 60% of the students are boys, 40% of whom play hockey and the girls don't play hockey, 75% of girls play badminton. There are only two games to be played. The number of students who don't play any game is :
(a) 10% (b) 36%
(c) 46% (d) can't be determined

2. A fraction in reduced form is such that when it is squared and then its numerater is increased by 25% and the denominator is reduced to 80% it results in 5/8 of the original fraction. The product of the numerator and denominator is :
(a) 6 (b) 12
(c) 10 (d) 7

3. In the Chidambaram's family the ratio of expenses to the savings is 5 : 3. But his expenses is increased by 60% and income increases by only 25% thus there is a deficit of Rs. 3500 in the savings. The increased income of Mr. Chidambaram's family is :
(a) Rs. 35,000 (b) Rs. 28,000
(c) Rs. 25,000 (d) Rs. 18,500

4. In the Presidency College two candidates contested a presidential election. 15% of the voters did not vote and 41 votes were invalid. The elected contestant got 314 votes more than the other candidate. If the elected candidate got 45% of the total eligible votes, which is equal to the no. of all the students of the college. The individual votes of each candidate are :
(a) 2250 and 1936 (b) 3568 and 3254
(c) 2442 and 2128 (d) 2457 and 2143

5. The annual earning of Mr. Sikkawala is Rs. 4 lakhs per annum for the first year of his job and his expenditure was 50%. Later on for the next 3 years his average income increases by Rs. 40,000 per annum and the saving was 40%, 30% and 20% of the income. What is the percentage of his total savings over the total expenditure if there is no any interest is applied on the savings for these four years :
(a) $49\frac{37}{87}\%$ (b) $41\frac{73}{83}\%$
(c) 53% (d) none of these

6. In an election only two candidates contested 20% of the voters did not vote and 120 votes were declared as invalid. The winner got 200 votes more than his opponents thus he secured 41% votes of the total voters on the voter list. Percentage votes of the defeated candidate out of the total votes casted is :
(a) 47.5% (b) 41%
(c) 38% (d) 45%

Directions for questions 7, 8 and 9: Pujari ji, the chief of a temple's trust, has a beautiful daughter Nirjala and a son in law, Radhey. Pujarin, the wife of Pujari ji, lives her own life by receiving the alms from the devotees and receives 9.09% earning of her husband and the daughter together. The earning of Nirjala in each month is Rs. 8000 less than her husband Radhey. The earning of Pujari ji and Radhey together is Rs. 30,000 per month. The earning of Radhey and Nirjala together is Rs. 133.33% greater than that of Pujari ji.

7. The average earning of each Pujari ji. Nirjala and Radhey is:
(a) Rs. 13333.33 (b) Rs. 888.88
(c) Rs. 15,000 (d) none of these

8. What is the earning of Pujarin from the alms?
(a) Rs. 1800 (b) Rs. 2000
(c) Rs. 3600 (d) can't be determined

9. The earning of Radhey is how much per cent greater than that of his wife?
(a) 50% (b) 80%
(c) $47\frac{11}{13}\%$ (d) none of these

10. A sales executive gets 20% bonus of the total sales value and 10% commission besides the bonus on the net profit after charging such commission. If the total sales value be Rs. 10 lakh per annum and the total profit of the company be Rs. 1.32 lakh, then his total earning per annum will be, given that he is not entitled to receive any fixed salary from the company :
(a) 2.3 lakh (b) 3.2 lakh
(c) 2.32 lakh (d) 2.12 lakh

11. Mr Scindia after selling 5.5% stock at Rs. 92 realizes Rs. 32200. Then he invested $\frac{1}{3}$ of the amount in 4.5% stock at Rs. 92, $\frac{2}{5}$ of the amount at Rs. 115 in 5% stock and the remaining in 6% stock at Rs. 56. The change in his income is :
(a) Rs. 56 loss (b) Rs. 78 profit
(c) Rs. 80 profit (d) Rs. 70 loss

12. Each edge of a cube is increased by 20% then the percentage increase in surface area of the cube is :
(a) 144% (b) 40%
(c) 44% (d) 72.8%

Directions for question number 13 and 14: Pati, Patni and Woh (the three persons) were playing a game. At the begining of the game Pati and Patni together had 100% more money than Woh. Patni and Woh together had 300% more than Pati. By the end of the game Pati and Patni together had 100% more money than Woh had and Pati had 12.5% less money than Patni and Woh together had. Finally Pati gained Rs. 800 by the end of the game.

13. Who has suffered the loss?
(a) Patni (b) Woh
(c) Patni and Woh both (d) can't be determined

14. The percentage change of money of Patni is :
(a) 40% (b) 30%
(c) 57.1428% (d) 42.857%

15. The raw material and manufacturing cost formed individually 70% and 30% of the total cost and the profit percentage is 14.28% of the raw material. If the cost of raw material increase by 20% and the cost of manufacturing is increased by 40% and the selling price is increased by 80%, then the new profit percentage is :
(a) 57% (b) 65.8%
(c) 60% (d) can't determined

Scanned by CamScanner

yoursmahboob.wordpress.com

16. A, B, C and D purchased a cine-multiplex for Rs. 56 lakhs. The contribution of B, C and D together is 460% that of A, alone. The contribution of A, C and D together is 366.66% that of B's contribution and the contribution of C is 40% that of A, B and D together. The amount contributed by D is :
(a) 10 lakh (b) 12 lakh
(c) 16 lakh (d) 18 lakh

17. In a village three people contested for the post of village Pradhan. Due to their own interest, all the voters voted and no one vote was invalid. The losing candidate got 30% votes. What could be the minimum absolute margin of votes by which the winning candidate led by the nearest rival, if each candidate got an integral per cent of votes?
(a) 4 (b) 2
(c) 1 (d) none of these

18. Every day a mango seller sells half his stock, 10% of the stock overnight gets spoiled. If 1983 mangoes rotted over 3 nights then how many did he start with on the first day?
(a) 25,000 (b) 24,000
(c) 30,000 (d) 32,000

19. A man lost half of his initial amount in the gambling after playing 3 rounds. The rule of gambling is that if he wins he will receive Rs. 100, but he has to give 50% of the total amount after each round. Luckily he won all the three rounds. The initial amount with which he had started the gambling was :
(a) $\frac{500}{3}$ (b) $\frac{700}{3}$
(c) 300 (d) 600

20. In a factory there are three types of Machines M_1, M_2 and M_3 which produces 25% , 35%, and 40% of the total products respectively. M_1, M_2 and M_3 produces 2%, 4% and 5% defective products, respectively. What is the percentage of non-defective products?
(a) 89% (b) 97.1%
(c) 96.1% (d) 86.1%

21. A company has 12 machines of equal efficiency in its factory. The annual manufacturing expenses are Rs. 24,000 and the establishment charges are Rs. 10,000. The annual output of the company is Rs. 48,000. The annual output and manufacturing costs are directly proportional to the no. of machines while the share holders get the 10% profit, which is directly proportional to the annual output of the company. If 8.33% machines remained close throughout the year. Then the percentage decrease in the amount of Share holders is :
(a) 16.66% (b) 14.28%
(c) 8.33% (d) none of these

22. In every month Ravindra consumes 25 kg rice and 9 kg wheat. The price of rice is 20% of the price of wheat and thus he spends total Rs. 350 on the rice and wheat per month. If the price of wheat is increased by 20% then what is the percentage reduction of rice consumption for the same expenditure of Rs. 350? Given that the price of rice and consumption of wheat is constant :
(a) 36% (b) 40%
(c) 25% (d) 24%

23. My friend Siddhartha Ghosh is working in the life insurance Corporation of India (LIC). He was hired on the basis of commission and he got the bonus only on the first years commission. He got the policies of Rs. 2 lakh having maturity period of 10 year. His commission in the first second, third, fourth and for the rest of the years is 20%, 16% 12% 10% and 4% respectively. The bonus is 25% of the commission. If the annual premium is Rs. 20,000 then what is his total commission if the completion of the maturity of all the policies is mandatory :
(a) Rs. 174,00 (b) RS. 23, 600
(c) Rs. 15,000 (d) Rs. 15,500

Directions for question number 24 and 25: DELL Computer has two branches : One in Ohio and second in Texas : The total no. of employees in Ohio office grew this year by 25% to 750 but the ratio of male to female employees is same as in the previous year. The no. of employees in the Texas office grew this year by 9.09% to 1200. The ratio of male to female employees last year in the Texas office was 5 : 6 and the no. of male employees in the Ohio office was 20% less than that of Texas office.

24. The total no. of female employees this year in both the offices is :
(a) 654 (b) 546
(c) 950 (d) can't be determined

25. The total no. of employees in both the offices last year was :
(a) 1500 (b) 1700
(c) 1650 (d) can't be determined

26. A shepherd had n goats in the year 2000. In 2001 the no. of goats increased by 40%. In 2002 the no. of goats declined to 70%. In 2003 the no. of goats grew by 30%. In 2004, he sold 10% goats, then he had only 34,398 goats. The percentage increase of the no. of goats in this duration was :
(a) 14.66% (b) 16.66%
(c) 20% (d) 33.33%

27. In the above question in which year the no. of goats was minimum?
(a) 2000 (b) 2001
(c) 2002 (d) 2004

Directions for questions number 28, 29 and 30: In the IGNOU (Indira Gandhi National Open University) there are total 16,000 students pursuing MBA, which offers the specialization only in Finance, HR and Marketing. IGNOU accepts only Science, Commerce and Engineering students for the two years course of MBA. The number of science, students is 166.66% of the Commerce students. Number of Engineering students is equal to the number of Science and Commerce students together. Each student can specialize in only one of the marketing, HR and Finance. 20% of Science students opted the Finance, which is 16.66% less than the no. of Commerce students who opted Finance. The total Finance students is equal to 18% the total strength of the MBA students. 32% of Science students opted HR. Commerce students who opted HR is equal to 25% of total students specializing in Finance and Engineering students equal to 6.5% of the total strength of the MBA students opted HR.

Scanned by CamScanner

yoursmahboob.wordpress.com

28. The number of Engineering students who opted marketing is :

(a) 7850 (b) 7500
(c) 8850 (d) none of these

29. The percentage of Commerce students who opted HR over the total strength of the MBA students is :

(a) 6.6% (b) 42.5%
(c) 4.5% (d) 62.5%

30. The most preferable course among the MBA students is :

(a) Finance (b) HR
(c) Marketing (d) I. T and systems

31. P% of the students of a class passed the exam. g% of the passed students are girls and b% of the fail students are boys. The percentage of passed boys over the failed girls is :

(a) $\left(\frac{bg}{p} \times 100\right)$ (b) $\frac{100(100-g)p}{(100-p)(100-b)}$

(c) $\frac{(100-g)(100-b)}{(100-p)}$ (d) none of these

32. In the Polo hospital some patients who were suffering from the Hepatites-B were admitted for the treatment , but 9% of the patients were died within half an hour. After treatment, the percentage of patients cured out of the remaining was only 80%. Out of these patients only 70% are completely cured out and the remaining were partially cured out which were equal to 153 patients. The no. of patients (approx.) who were admitted for the treatment for the same was :

(a) 400 (b) 678
(c) 560 (d) 700

33. The total cost of setting up a sugar cane factory is Rs. 1 crore, which produces 5000 ton per annum. Sugar is being sold at Rs. 18 per kg. Manufacturing cost including raw material is Rs. 3.2 per kg, labour and packing charges are Rs. 1.8 per kg. Maintenance and utilities expenses are Rs. 2 per kg and the general expenses (ie all the rest charges) are Rs. 3 per kg, 20% taxes are being paid of the gross annual earnings, then the net profit of the production of the factory per annum is :

(a) Rs. 4.2 crore (b) Rs. 3.2 crore
(c) 5.4 crore (d) none of these

34. A student appeard in the Mock CAT. The test paper contained 3 sections namely QA, DI and VA. The percentage marks in VA was equal to the average of the percentage marks in all the 3 sections. Coincidentally, if we reverse the digits of the percentage marks of QA we get the percentage marks of DI. The percentage marks in VA scored by the student could be :

(a) 48 (b) 66
(c) 69 (d) 81

35. The pressure of a definite mass of a gas is directly proportional to the temperature and inversely proportional to the volume under the given conditions. If temperature is increased by 40% and the volume is decreased by 20% then the new pressure will:

(a) be increased by 75% (b) reduce to 25%
(c) be increase by 20% (d) increase by 28%

36. A computer typist types a page with 20 lines in 10 minutes but he leaves 8% margin on the left side of the page. Now he has to type 23 pages with 40 lines on each page which he leaves 25% more margin than before. How much time is now required to type these 23 pages

(a) $7\frac{1}{2}$ hrs (b) $7\frac{2}{3}$ hrs

(c) $23\frac{1}{2}$ hrs (d) 3.916 hrs

37. A company made a cuboidal box of size $16 \times 12 \times 5$ to sell the ice cream, but later on it was found that the capacity of the box was 14.28% less than the required capacity while the height of the box was correct, which is 5 inches. As per the requirement he had to increase the length and breadth of the box in equal amount then the percentage increase in the area of the base of the box is

(a) 12.5% (b) 6.66%
(c) 16.66% (d) none of these

38. In Sabarmati Express, there are as many wagons as there are the no. of seats in each wagon and not more than one passanger can have the same berth (seat). If the middlemost compartment carrying 25 passangers is filled with 71.428% of its capacity, then find the maximum no. of passangers in the train that can be accommodated if it has minimum 20% seats always vacant

(a) 500 (b) 786
(c) 980 (d) can't be determined

39. The prepaid card of Reliance Infocom gives 19% less talktime than the prepaid card of Tata Indicom, having same price. Again the post-paid card of same price of Tata Indicom gives 10% less talktime than its prepaid card.
Similarly the post paid card of same price of Reliance gives 11.11% less talk time than its prepaid card. How much percent less talk time we get from the Reliance post paid card than the post paid card of Tata Indicom?

(a) 21.11% (b) 20%
(c) 30.11% (d) none of these

40. In the half yearly exam only 70% of the students were passed. Out of these (passed in half yearly) only 60% student are passed in annual exam. Out of those who did not pass the half yearly exam, 80% passed in annual exam. What per cent of the students passed the annual exam ?

(a) 42% (b) 56%
(c) 66% (d) none of these

41. The marks obtained by the students of a school is given below : maximum marks are 50.

Marks	Percentage of Students
< 10	15%
< 20	32%
< 30	40%
< 40	70%
< 50	100%

The ratio of no. of boys to no. of girls who passed the exam is 7 : 6. It is known that a student can pass the exam only when he obtained at least 20 marks in the exam. The total no. of students in the school if the no. of girls who are passed is 408 :

(a) 1100 (b) 1200
(c) 1300 (d) 1430

Scanned by CamScanner

yoursmahboob.wordpress.com

Direction for question number 42 to 45: *After defeating Ravana, Ram and his family won a lot of valuable assets in the war. It consists of horses, chariots and some land of Ravans's kingdom. The cost of each horse and chariot was Rs. 20,000 and Rs. 8,000 respectively while the cost of 1 acre land was Rs. 5000. All the property was shared among the four persons in such a way that Ram and Sita got together the same wealth as Laxman and Urmila got together. Ram got more than Sita and Laxman got more than Urmila. Ram got $\frac{1}{3}$rd horses and 20% chariots while Laxman received 50%chariots as the 50% of his total wealth. The no. of horses that Ram and Sita got together was 50% more than that of Laxman and Urmila together had. Sita got 8 horses and Urmila got 7 horses but the Ram and Sita got equal no. of Chariots and Urmila got 20 chariots less than that of Laxman. Urmila got twice the land than that of Sita but 20% less than Laxman.*

42. What is the difference between the wealth of Ram and wealth of Urmila?
(a) 1.2 lakh (b) 1 lakh
(c) 1.4 lakh (d) can't be determined

43. If Laxman wanted to exchange all his chariots with the horses, then who can exchange with his/her horses in terms of wealth :
(a) Ram (b) Sita
(c) Urmila (d) can't be determined

44. The wealth of Urmila is how many per cent less than that of Laxman :
(a) 42% (b) 45%
(c) 35% (d) none of these

45. The wealth due to land and chariot together is how much greater, in per cent, than the wealth due to horses.
(a) 25% (b) 20%
(c) 33.33% (d) none of these

46. A big cube is formed by rearranging the 160 coloured and 56 non-coloured similar cubes in such a way that the exposure of the coloured cubes to the outside is minimum. The percentage of exposed area that is coloured is:
(a) 25.9% (b) 44.44%
(c) 35% (d) none of these

47. Selection into IIMs (Indian Institutes of Management) is quite simple. In our coaching institute some students qualified CAT (The first stage of entrance into IIMs) but coincidentally the no. of boys who qualified the CAT was equal to the no. of girls. Besides these boys and girls got the calls from only IIM Ahamedabad and IIM Bangalore, but each of these from both the IIMs. 60% of the boys failed in the group discussion (the second phase of the selection process) and thus equal no of boys (but distinct) appeared for the personnel interview of IIM-A and IIM-B (interview is the third and final stage of selection of a candidate) but 20% of the boys who appeared for the interview of IIM-A and 60% of the boys who appeared for the interview of IIM-B failed. If it is possible that a candidate can receive the calls from more than one IIMs but he/ she can face the interview of only one IIM. Given that only 24 boys from our coaching institute were selected by the IIM-A and IIM-B also a candidate can appear for the next stage only if he/she qualifies the previous stage of the exam, then find the no. of girls who qualified the CAT (Common Admission Test).
(a) 100 (b) 250
(c) 300 (d) 600

48. In an office there were initially n employees. The HR manager first hired P% employees then after a month q% employees left the office, then there were finally n employees remained in the office, the value of $p-q$ is :
(a) pq (b) $\frac{pq}{100}$
(c) $\frac{p}{q}$ (d) none of these

49. In the Garbar Jhala, Aminabad a shopkeeper first raises the price of a Jewellery by x% then he decreases the new price by x%. After one such up down cycle, the price of a Jewellery decreased by Rs. 21025.After a second updown cycle the jewellery was sold for Rs. 484416. What was the original price of the jewellery.
(a) Rs. 5,00,000 (b) Rs. 6,00,625
(c) Rs. 525625 (d) RS. 5,26,000

50. The amount of work in a leather factory is increased by 50%. By what per cent is it necessary to increase the number of workers to complete the new amount of work in previously planned time, if the productivity of the new labour is 25% more.
(a) 60% (b) 66.66%
(c) 40% (d) 33.33%

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions for question number 1, 2 and 3: *The bar graph shown below reveals the data about the no. of students in different disciplines of MBA at a prominent Business School in India.*



1. The growth rate of Finance compared to that of marketing is:
   (a) less (b) equal
   (c) greater (d) none of these
2. Total no. of MBA students in the session of 2004-05 if the no. of students in 2004-2005 is increasing by 9.09% over the previous year :
   (a) 555 (b) 600
   (c) 777 (d) none of these
3. In the session of 2002-03 what percentage of MBA students are studying International Business?
   (a) 13.33% (b) 25%
   (c) 6.66% (d) 24%

Directions for question number 4 to 7: *The following table gives the sales details of the books for CAT written by Sarvesh.*

Year	Quant. Aptitude	Data Interpretation	Verbal Ability	Log. Reasoning
2000	4000	3750	4140	4350
2001	4200	3870	4260	4400
2002	4370	3990	4255	4500
2003	4268	3868	5371	4690
2004	4750	4900	5476	4710
2005	4800	5000	5500	4800

4. What is the growth rate of sales of Quantitative Aptitude from 2000 to 2005?
   (a) 8% (b) 25%
   (c) 20% (d) 40%
5. Which of the categories shows the lowest growth rate from 2000 to 2005?
   (a) Q.A (b) DI
   (c) VA (d) LR
6. Which category had the highest growth rate in the period?
   (a) QA (b) DI
   (c) VA (d) LR
7. Which of the categories had either a consistent growth or consistent decline in the period shown?
   (a) QA (b) DI
   (c) VA (d) LR

Directions for question number 8 to 10: *In India there were only three bicycle making companies in the given period. The following table shows the production of units (in 000)*

Year	HERO	ATLAS	AVON
1990	2.97	1.75	3.77
91	4.22	2.48	4.55
92	5.95	3.14	4.5
93	6.28	3.01	4.76
94	6.33	4.12	4.74
95	8.50	4.21	4.26

UPTREND IN BICYCLES PRODUCTION IN INDIA

8. The simple average rate of growth of production of Hero cycles from 1990-95 :
   (a) 37% (b) 42%
   (c) 27% (d) 31.5%
9. Which of the following statements is/are correct ?
   (i) Atlas cycles have recorded the fastest growth rate.
   (ii) Total bicycles production was the highest in 1993
   (iii) Hero cycles on an average account for 48% of total bicycles production
   (a) I only (b) II only
   (c) III only (d) none of these
10. Atlas cycles on an average account for what percentage of the total bicycles production :
    (a) 15% (b) 23.4%
    (c) 34.5% (d) 29%

Directions for question number 11 to 14 : *Answer the questions based on the following information, which gives data about certain butter producer companies in India.*

Name of the Company	Production ('000) tonnes	Capacity Utilisation (%)	Sales ('000) tonnes	Total sales value (in crore)
Amul	1.54	59.35	1.47	17.45
Nestle	1.64	64.80	1.26	15.25
Parag	2.48	71.20	2.03	26.75
Amrit	2.97	76.50	2.55	31.15
Total (including others)	11.60	61.30	10.67	132.80

11. What is the maximum production capacity (in '000 tonnes) of Nestle for Butter?
    (a) 2.53 (b) 2.07
    (c) 2.84 (d) 2.97
12. Which company out of the four companies mentioned above has the maximum unutilised capacity in ('000 tonnes)?
    (a) Amul (b) Nestle
    (c) Parag (d) Amrit

Scanned by CamScanner

yoursmahboob.wordpress.com

13. What is the approximate total production capacity (in '000 tonnes) for butter in India?
(a) 7.8 (b) 18.9
(c) 11.60 (d) data insufficient

14. What per cent of the total market share (by sales value) is controlled by others?
(a) 32% (b) 83%
(c) 67% (d) data insufficient

Directions for (Q. no. 15 to 19): The following pie chart shows the hourly distribution of all the major activities of a student.



15. The percentage of time which he spends in school is :
(a) 38% (b) 30%
(c) 40% (d) 25%

16. How much time (in per cent) he spends in games in comparison to sleeping?
(a) 30% (b) 40%
(c) 25% (d) none of these

17. If he spends the time in games equal to the home work and remains constant in other activities, then the percentage decrease in time of sleeping :
(a) 15% (b) 12.5%
(c) 20% (d) none of these

18. What is the difference in time (in hours) spends in school and in home work :
(a) 2 (b) 3
(c) 4 (d) 8

19. If he spends $\frac{1}{3}$ rd time of home work in Mathematics then the no. of hours spends in rest of the subjects in homework :
(a) 1 (b) 2
(c) 3 (d) 4

Directions for question number 20 to 23 : The two pie charts show the market share of different companies which produces TV and Refrigerator (both) in the first quarter of 2005-06.



T.V.



REFRIGERATOR

NOTE The graph is not shown to scale.

20. The difference in the angle subtended by Sony TV. and refrigerator is :
(a) 7.2° (b) 14.4°
(c) 21.6° (d) none of these

21. If the turn over of Samsung TV is Rs. 31 crores and of Samsung refrigerator is Rs. 9 crore, then what is the overall market share of Electrolux TV and refrigerater combined?
(a) 33.33% (b) 28%
(c) 16.7% (d) 65%

22. If the turnover in the first quarter of 2005-06 of Electrolux TV and Refrigerator is Rs. 42 crores and Rs. 6 crores respectively, then what is the average annual turnover of Godrej and Aiwa in both the product categories together?
(a) Rs. 304 crores
(b) Rs. 284 crores
(c) RS. 178 crores
(d) none of the above

23. Which of the following cann't be deduced from the given data :
(a) The angular difference between Samsung TV and Electrolux refrigerator is 3.6°.
(b) Sony is the market leader in the TV and Refrigerator segment combined.
(c) For every Rs. 100 turnover of Whirlpool Refrigerator, the difference in the turnover of Electrolux and Samsung Refrigerator is Rs. 33.34 crore
(d) none of the above

Directions for question number 24 to 28 : Number of different colleges in India in different years is given in the graph below. Distribution of different colleges in the years 1980 and 1990 shown in the pie charts below :



Scanned by CamScanner

yoursmahboob.wordpress.com



(1980)



(1990)

NOTE General courses include all the courses except Medical, Engineering and management

24. What is percentage increase in the number of colleges from 1960 to 1990?
(a) 1000% (b) 940%
(c) 1040% (d) 470%

25. The growth rate in no. of medical colleges in 1980 to 1990 is :
(a) 33% (b) 52%
(c) 36% (d) 39%

26. By what percentage did the no. of Engineering colleges go up from 1960 to 1970?
(a) 38% (b) 28%
(c) 42% (d) cann't of be determind

27. Till 1990 what was the highest increase in the number of colleges in any decade?
(a) 150% (b) 166.66%
(c) 200% (d) 140%

28. If the projected increase in the number of colleges in 2000 over 1990 is to be the same in all the categories of colleges, the percentage of Medical colleges in 2000 will be :
(a) 9% (b) 11%
(c) 7% (d) 13%

Directions for question number 29 to 33 : *Answer the questions based on the following information. The following table gives the tariff (in paise per kilo-litre) levied by the Lucknow jal Nigam in 2003-04 in four sectors and the region within them. (Each sector is divided in 5 regions). The table gives the percentage change in the tariff as compared to 2000-01.*

	Region 1		Region 2		Region 3		Region 4		Region 5	
	P/kl	%	P/kl	%	P/kl	%	P/kl	%	P/kl	%
Sector 1	1000	+ 25	400	+ 14.28	250	– 16.66	625	+ 4.166	720	+ 20%
Sector 2	800	+ 33.33	375	+ 7.14	350	– 12.5	750	+ 7.14	360	– 10
Sector 3	625	– 16.66	525	– 12.5	400	+ 14.28	240	– 4%	320	– 20
Sector 4	575	– 4.166	800	– 20%	500	– 16.66	360	+ 20%	400	– 11.11

29. If the amount of water consumed by the various regions in sector 1 is the same, then as compared to 2000-01 the net tariff in 2003-04 :
(a) increased by 20% (b) increased by 13%
(c) decreased by 12% (d) decreased by 20%

30. What was the approximate average tariff in region 2 in 2000-01?
(a) 450 (b) 675
(c) 575 (d) 525

Additional direction for question 31-33 : *The Lucknow Jal Nigam supplies the water under four categories : Urban (25%) rural (15%) domestic (40%) industrial (20%). In 2003-04, the total water supplied by the Lucknow Jal Nigam was 20,000 kilo-litres.*

31. If in 2003-4, there was a 20% decrease in the domestic consumption of water as compared to that in 2000-01 what was the consumption of water in the industrial sector in 2000-01?
(a) 5,000 kl (b) 7500 kl
(c) 10,000 kl (d) 6000 kl

32. In the given two years, what is the total tariff paid by the Urban sector?
(a) Rs. 16,000 (b) Rs. 48,000
(c) Rs. 23,000 (d) can't be determined

33. Which of the following statements is true?
(a) The average tariff in region 2 is 625
(b) The average tariff in region 4 is greater than the average tariff in region 5
(c) In 2000-01 the industrial sector contributed about 30% of the total revenue from water supply
(d) none of the above

Directions for question 34-37 : *A marketing company conducted a survey among 10,000 person in Kanpur :*



Scanned by CamScanner

yoursmahboob.wordpress.com

Percentages



It was observed that some people have more than one bike but from only one company i.e., a particular person can have more than one bike of HeroHonda, but not from bajaj etc. and vice versa. Thus there were total 12,000 bikes with 10,000 persons used for survey. There are only four companies operating in this market.

34. If each of Students, Govt. Servants and housewives use a Hero Honda bike (motorcycle), what per cent of the remaining people drive Hero Honda bike?
(a) 15% (b) 25%
(c) 20% (d) none of these

35. If the number of people who drive one, two and three bikes are in the ratio 15 : 3 : 1 what is the number of people in the survey who do not drive even a single bike?
(a) 750 (b) 400
(c) 600 (d) 500

36. If all the persons driving more than one bike drive only Hero Honda what is the number of people who drive single Hero Honda bike (the data can be used from previous question if necessary)?
(a) 2400 (b) 2100
(c) 4200 (d) 2600

37. If 20% of the persons who drive Bajaj's bike also drive another bike. What is the number of people who drive only Bajaj' bike ?
(a) 2400 (b) 2500
(c) 2660 (d) none of these

Directions for question 38-42 : A table below shows the production and imports of crude oil (in '000 tonnes). Domestic production of crude oil is total of on-shore and off-shore production, which is supplemented by imports to meet the total demand of crude oil in the country.

Year	2001	2002	2003
On shore	12,000	11,500	11,000
Off shore	11,000	19,000	16,000
Imports	21,000	24,000	30,000

(in '000 tonnes)

38. What was the percentage of domestic production of crude oil over imports in 2001?
(a) 80% (b) 140%
(c) 109.52% (d) none of these

39. What was the percentage change in domestic production of crude oil from 2001-2003 ?
(a) 14% (b) 27%
(c) 17.4% (d) – 10%

40. What is the average of total demand of crude oil over the period?
(a) 185 million tonnes (b) 52 million tonnes
(c) 18.5 million tonnes (d) 35 million tonnes

41. What was the approx-percentage increase in imports of crude oil from 2001 to 2003 :
(a) 49% (b) 65%
(c) 43% (d) none of these

42. If in the year 2004, off-shore production declines by 12.5% production on-shore remains the same and total demand increases by 2% what will be the imports of crude oil in 2004 ?
(a) 33.14 million tonnes (b) 63 million tonnes
(c) 39 million tonnes (d) 25 million tonnes.

Directions : (Q. no. 43 to 50) Solve the following question on the basis of given data in the following table :

Production of Rice in India

Year	Quantity (in tonnes)	Percentage change over the previous year
1920-21	1,34,300	+ 06.25%
1930-31	10,97,172	+ 12.50%
1940-41	2,64,280	+ 11.11%
1950-51	1,27,890	– 09.09%
1960-61	2,01,924	+ 20.00%
1970-71	1,12,325	– 16.66%
1980-81	2,13,465	– 25.00%
1990-91	1,69,368	+ 33.33%
2000-01	100,956	+ 50.00%
2010-11	23,800	– 83.33%

43. What is the production of rice in 1959-60?
(a) 1,84,250 (b) 1,68,270
(c) 242308.8 (d) none of these

44. What is the production of rice in 1949-50?
(a) 116263.6 3 (b) 1,23,460
(c) 1,40,679 (d) none of these

45. What is the total production of rice in 1919-20and 1929-30 and 1939-40 ?
(a) 13,26,400 (b) 13,39,516
(c) 1142693.75 (d) can't be determined

46. The production of rice in 2000-01 forms what percentage of total production out of the given years?
(a) 3.12% (b) 3.23%
(c) 4.128% (d) 6.45%

47. What is the difference in production of rice in 1969-70 and 1979-80 ?
(a) 149830 (b) 175752
(c) 53,890 (d) none of these

48. The percentage decrease in production of rice from 1929-30 to 1949-50
(a) 88.3% (b) 85.57%
(c) 66.66% (d) none of these

49. The production of rice in 1959-60 is what percentage of rice in 1960-61.
(a) 86.66% (b) 75.6%
(c) 83.33% (d) 16.66%

50. Out of the given years which year has shown least increase (in amount) over the previous year :
(a) 1940-41 (b) 1960-61
(c) 1920-21 (d) 2000-01

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-5.1

1. (i) 50, (ii) 54, (iii) 112.5, (iv) 400, (v) 2 quintal, (vi) 544.5, (vii) 88, (viii) 6 minutes, (ix) 200, (x) 2 lakh rupees
2. Rs. 4,500 **3.** 28 metres **4.** 750 **5.** 190 and 1520 **6.** 750 **7.** 102 km/hr **8.** Rs. 2200 **9.** 75 **10.** 750
11. 60000 **12.** 255

INTRODUCTORY EXERCISE-5.2

1. (i) 5%, (ii) 15.625, (iii) 33.33%, (iv) 24%, (v) 20%, (vi) 150%, (vii) 66.66%, (viii) 43.75%
2. (i) 4%, (ii) 75%, (iii) 6.25%, (iv) 33.33%, (v) 0.4166%, (vi) 7.5%
3. 85.33% **4.** 70% **5.** 97% **6.** 150% **7.** $33\frac{1}{3}\%$ **8.** 90% **9.** 12.5% **10.** 4%

INTRODUCTORY EXERCISE-5.3

1 (b)	2. (b)	3. (b)	4. (c)	5. (c)	6. (c)	7. (d)	8. (c)	9. (a)	10. (b)

LEVEL-1

1 (b)	2. (b)	3. (b)	4. (c)	5. (d)	6. (d)	7. (d)	8. (c)	9. (b)	10. (d)
11. (d)	12. (b)	13. (c)	14. (b)	15. (a)	16. (b)	17. (c)	18. (a)	19. (c)	20. (b)
21. (c)	22. (d)	23. (d)	24. (b)	25. (a)	26. (c)	27. (b)	28. (c)	29. (b)	30. (c)
31. (a)	32. (b)	33. (b)	34. (c)	35. (b)	36. (c)	37. (b)	38. (c)	39. (c)	40. (b)
41. (a)	42. (d)	43. (a)	44. (c)	45. (d)	46. (d)	47. (b)	48. (c)	49. (c)	50. (b)
51. (c)									

LEVEL-2

1 (d)	2. (c)	3. (a)	4. (d)	5. (d)	6. (d)	7. (a)	8. (d)	9. (b)	10. (d)
11. (c)	12. (c)	13. (a)	14. (c)	15. (a)	16. (d)	17. (c)	18. (b)	19. (b)	20. (c)
21. (b)	22. (a)	23. (a)	24. (d)	25. (b)	26. (a)	27. (c)	28. (d)	29. (c)	30. (c)
31. (b)	32. (d)	33. (b)	34. (b)	35. (a)	36. (a)	37. (c)	38. (c)	39. (b)	40. (c)
41. (c)	42. (a)	43. (a)	44. (c)	45. (b)	46. (b)	47. (a)	48. (b)	49. (c)	50. (c)

FINAL ROUND

1 (a)	2. (b)	3. (a)	4. (c)	5. (d)	6. (b)	7. (d)	8. (a)	9. (d)	10. (b)
11. (a)	12. (a)	13. (b)	14. (a)	15. (b)	16. (c)	17. (b)	18. (c)	19. (b)	20. (b)
21. (c)	22. (a)	23. (b)	24. (b)	25. (a)	26. (d)	27. (b)	28. (b)	29. (b)	30. (c)
31. (a)	32. (d)	33. (b)	34. (a)	35. (d)	36. (b)	37. (a)	38. (c)	39. (c)	40. (b)
41. (c)	42. (a)	43. (b)	44. (c)	45. (b)	46. (c)	47. (a)	48. (b)	49. (c)	50. (c)

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1.

F	M	
$60x$	$40x$	
$42x$	$20x$	(comp. lit.)

$62x$

$\therefore$ Female comp. literate $1600 \times \frac{42}{100} = 672$

2. $(10,00,000) \times 0.75 \times 0.80 \times 0.85 =$ Rs.5,10,000

3. $2000 \times \frac{x}{100} + 4000 \times \frac{y}{100} = 320$

and $2000 \times \frac{x}{100} + 10,000 \times \frac{y}{100} = 680$

$\therefore$ $x = 4$ and $y = 6$

$\therefore$ $x - y = -2$

4. Go through option $(40 \times 0.4) + (40)^2 = 1616$

$\left(100 \times \frac{1616}{40} = 4040\right)$

Alternatively: $(x \times 0.4) - x^2 = \frac{x \cdot 4040}{100}$

$\Rightarrow$ $x^2 = 40x \Rightarrow x = 40$

5. Can't be determined. We don't that whether there are some male employees who have exactly Rs. 8000 per month as their salary or not.

6.

	Physics	Chemistry
Failed	35%	45%
Passed	65%	55%

Passed in both = 22% of total student

Percentage of students who are passed in any of the Physics or Chemistry or both = (65 + 55) − 22 = 98%

So, the percentage of students who are failed in both = 2%

Therefore total failed (in both the subject) students = 12

7.

	History	Geography
Pass	$70x$	$50x$
Fail	$30x$	$50x$

both $20x$

$\therefore$ Total failed candidates = $(30x + 50x) - 20x = 60x$

Passed in both = $(100x - 60x) = 40x = 500$

Therefore total students = $100x = 1250$ $\because x = \frac{25}{2}$

8. My salary = 100

Salary of my brother = 110

Salary of my sister = 120

Salary of my wife = $230 - \left(230 \times \frac{1300}{23 \times 100}\right) = 100$

$\because$ $56\frac{12}{23} = \frac{1300}{23}$

9. $\frac{60 \times 8 + 16 \times 30}{16 \times 60 \times 60} \times 100 = 1.66\%$

10. Total land of Sukhiya $= \frac{480x}{0.6} = 800x$

$\therefore$ Cultivated land of village = $384000x$

$\therefore$ Required percentage $= \frac{800x}{384000} \times 100 = 0.20833$

11. Area = $l \times b$

$1 = 1 \times 1$

$1 = 0.8 \times 1.25$

So the area remained constant

12. Cost of fresh Mangoes + Packaging cost = Total cost

$1 + 0.4 = 1.4$

$1.3 + 0.2 = 1.5$

Percentage increase in cost = $\frac{0.1}{1.4} \times 100 = 7.14\%$

13. $\frac{80}{100} - \frac{66}{100} = \frac{x}{200} - \frac{320}{400}$

$\Rightarrow$ $x = 174 \Rightarrow 87\%$

14.

Male	Female
$55x$	$45x$

$\Rightarrow$ $10x = 72$

$x = 7.2$

$100x = 7.2 \times 100$

15. Let the total votes be x,

Polled votes = $0.75x$

valid votes = $0.70x$

$A - B - C = 0.70x$

2450

1750

$0.4x$

It means $B + C = 0.3x$ since given that $A = 0.4x$

Hence A is the winner.

16.

Bike	Car
x	$5x$
$1.2x$	$5.75x$

Initially total cost $= 25x + 10x = 35x$

Changed cost = $28.75x + 12x = 40.75x$

Percentage change = $\frac{5.75}{35} \times 100 = 16\frac{3}{7}\%$

18. Go through option

S	K	
15,000	18,000	Going in the reverse direction.
12,000	16,000	

Hence, the presumed option is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively:

	Sahid	Kareena
25%	$4x$	$\frac{48x}{9}$
	$5x$	$6x$
	$+120\%$	

$\Rightarrow$ Initially $S : K = 4x : \frac{48x}{9} = 3 : 4$

$\Rightarrow$ Sahid's initial salary = 12,000
Sahid's changed salary = 15000

19. Let the smaller number be x and larger number be y

$$0.8x + 4 = 0.4y$$
$\Rightarrow$ $$4y - 8x = 40$$
and $$y - x = 85$$
$\Rightarrow$ $$x = 75 \text{ and } y = 160$$
$\therefore$ $$x + y = 235$$

20. $$\frac{x \times 220}{100} = 44$$

$\Rightarrow$ $$x = 20 \text{ So } \frac{20 \times 44}{100} = 8.8$$

21. Quantity × Rate = Price

$$1 \times 1 = 1$$
$$0.7 \times 1.25 = 0.875$$

$\therefore$ Decrease in price $= \frac{0.125}{1} \times 100 = 12.5\%$

22. Go through options

	P	Q	
In the Ist government	275	225	Difference = 50
In the 2nd government	200	300	Difference = 100

Hence, the presumed option (d) is correct

NOTE It can also be solved through the equation and variables

23. Passing marks are $0.6x$

So $0.3x + 30 = 0.6x \Rightarrow x = 100$

24. Go through options

Girls	Boys
800	1000

Now, $0.95 \times 800 + 1000 = 0.96 \times 1000 + 800$
Hence the presumed option is correct.

25.

H	E	U
$0.6x$	$0.24x$	$0.16x$
	3600	2400

$(\because E : U = 24 : 16 = 3 : 2)$

26. Go through option

75 → 25, 50; 50 → (60%); 25 → 20; 50 → 30

$$\frac{50}{75} \times 100 = 66.66\%$$

Hence, the presumed option is correct.

27.

Science	Commerce	Arts	Engineering
$\frac{x}{6}$	$\frac{x}{8}$	$\frac{x}{15}$	K

No. of Engineering student $= 1 - \left(\frac{x}{6} + \frac{x}{8} + \frac{x}{15}\right) = k = \frac{77x}{120}$

When $x = 120$ (the least possible number)
then the no of Engineering students = 77

28.

Copper		Aluminium	
7	:	4	
21 kg		12 kg	→ 33 kg

Required total alloy $= \frac{33}{0.88} = 37.5$ kg

29. $$1.08x = 1404$$
$$x = 1300$$

Therefore reduction in price = 1404 − 1300 = Rs. 104

$\left[\text{Since } 1300 + 1300 \times \frac{8}{100} = 1404\right]$

So you can solve it by using options.

30. Very fundamental question.

31. $$8x + 9x + 10x = 810$$
$\Rightarrow$ $$x = 30$$
Total marks in QA ⟶ 240
DI ⟶ 270
VA/RC ⟶ 300

Now her score in QA ⟶ $\frac{240}{1.2} = 200$

Her score in DI $= \frac{270}{1.08} = 250$

Her score in $\frac{VA}{RC} = \frac{300}{1.0714} = 280$

Her total score = 200 + 250 + 280 = 730

32. Commission up to 10000 $= 10000 \times \frac{9}{100} = 900$

Again after 10000,

Commission	:	Bonus
9	:	3
$3x$	:	x

$\Rightarrow$
$\therefore$ Bonus $= (1380 - 900) \times \frac{1}{4} =$ Rs. 120

33.

Men	Women
$600x$	$400x$

Total Engineer $= 480x$

Male Engineer $= 480x \times 0.66 = 320x$

$\therefore$ Women who are Engineers $= 160x$

$\therefore$ Women who are not Engineers $= 400x - 160x = 240x$

Required percentage $= \frac{240}{400} \times 100 = 60\%$

34.

	Veer	Zara
In the last month	160	100
After the first change	200	75
After final change	120	120

Scanned by CamScanner

yoursmahboob.wordpress.com

Time × Rate = Total charges

35. $1 \times 1 = 1$

$x \times 1.25 = 1.1$

$x = \frac{1.1}{1.25} \times 100 = 88\%$

Thus decrease in time = 12%

36.

	Ambani	Sahara
Average earning	$4x$	$5x$
No. of family members	k	l
Total earning	$6y$	$5y$

Average earning × Number of family members = Total earning

$l = \frac{5y}{5x} = \frac{y}{x}$

$k = \frac{6y}{4x}$

Required percentage $= \frac{l}{k} \times 100 = \frac{\frac{y}{x}}{\frac{6y}{4x}} \times 100$

$= \frac{4}{6} \times 100 = 66.66\%$

Alternatively : After some steps you can use the options.

37.

Year	Value
2000	100
2001	110
2002	121
2003	133.1
2004	119.79
2005	107.811
2006	97.0299

HINT $(100) \times 1.1 \times 1.1 \times 1.1 \times 0.9 \times 0.9 \times 0.9 = 97.0299$

Now, $\frac{100 - 97.0299}{100} \times 100 \approx 3\%$

38. $30 \times 25 \times 35 = x \times 30 \times 28$

$\Rightarrow \quad x = 31.25$

It means 32 pages.

So, the percentages increase in the no. of pages

$= \frac{2}{30} \times 100 = 6.66\%$

39. Rate of increase of the price

= (rate of inflation + 2)% = 8 + 2 = 10%

Jan 2004	Jan 2005	Jan 2006	
20	20	22	24.2
	+2	+2.2	

Alternatively: Expected price after 2 years

$= 20 \times 1.1 \times 1.1 = 24.2$

40. Let the total number of people = x

then the amount donated by $0.6x$ people

$= 600 \times 0.6x = 360x$

Now since Rs. $360x$ is equal to 75% of the required amount. Hence we need only 25% more amount from the rest of the people *i.e.*, from $0.4x$ people

Hence average requirement $= \frac{120x}{0.4x} = 300$

Alternatively: $(600 \times 0.6 + k \times 0.4)\frac{3}{4} = 600 \times 0.6$

$\Rightarrow \quad k = 300$

41. By mistake $= \frac{x}{10}$

Actual value $= x \times 10$

% change $= \frac{10x - \frac{x}{10}}{10x} \times 100 = \frac{99}{100} \times 100$

= 99% (negative)

Since actual value is greater than the wrong value

Alternatively :

Actual result $= 10 \times 10 = 100$ (suppose $x = 10$)

wrong result $= \frac{10}{10} = 1$

% change $= \frac{100 - 1}{100} \times 100 = 99\%$

NOTE Percentage error is always calculated on the basis of actual (*i.e.*, correct) value.

42. Use some different values for x then verify.

Let $x = 150$ then % error $= \frac{200 - 100}{100} \times 100 = 100\%$

Again if $x = 100$ then % error $= \frac{150 - 50}{50} \times 100 = 200\%$

Hence, we cannot determine.

43. Number of visitors × Rate = Revenue collected

$$(-20\%)\ 1 \times 1 = 1\ (+50\%)$$
$$0.8 \times 1.5 = 1.2$$

Therefore percentage change in the revenue

$= \frac{1.2 - 1}{1} \times 100 = 20\%$

44.

	Bata	Woodland
M.P	100	100
S.P.	51	51

(Since the marked prices are same)

NOTE M.P. → Marked price, S.P. → Selling price
decreased by 49% = reduced to 51%

45. Selling price = cost price + profit

Shirt = $7y + x$

Coat = $12y + x$

Since, the profit is same, so the selling price of shirt will certainly be less than Rs. 2000 (which is half of the total value) as it is clear that cost price of shirt is less than the cost price of coat.

NOTE If selling price of shirt is equal to or greater than the selling price of coat then the C.P. of coat will be equal to or less than the C.P. of shirt which is wrong. Hence the only possible choice is (d).

46. Since we don't have sufficient data. Further any value is possible as the required income tax.

Scanned by CamScanner

yoursmahboob.wordpress.com

47. $2004 \longrightarrow 10000 \times x\% = k$

$2005 \longrightarrow 16000 \times \frac{5}{8} x\% = k$

but $x - \frac{5}{8}x = 9 \Rightarrow x = 24\%$

So, the income tax = 2400.

48. Only (c) is correct since it is divisible by 4.

Let the original number of element be x then the new no. of elements will be

$$\frac{4x}{5} = K$$

So K must be divisible by 4

Since, $x = \frac{K \times 5}{4}$

49. Go throught option

Boys	Girls	Total
14	11	25
56	44	100

(12)

Since out of 100 students no. of boys are greater than the no. of girls by 12 *i.e.*, 12% Hence correct.

Alternatively :

Let the no. of boys and girls be x and y respectively

then $(x - y) = \frac{12 \times (x + y)}{100}$

$\Rightarrow \frac{x}{y} = \frac{14}{11}$

50. Population after 2 years $= 5000\left(1 + \frac{2}{100}\right)^2$

$$5000 \times \frac{51}{50} \times \frac{51}{50} = 5202$$

51. Daily supply $= (100 - z)\%$ of $y = \frac{(100 - z)y}{100}$

$\therefore$ Required no. of days $= \frac{x \times 100}{(100 - z)y}$

LEVEL 2

1.



Since we do not have information that whether the rest of the boys playing badminton or not. So we can not determine the total no. of students who are not playing any of the two games.

2. Go through option. Let us assume option (c)

$$10 = 2 \times 5 = 5 \times 2 = 1 \times 10 \times 10 \times 1$$

Consider the proper fraction $= \frac{2}{5}$

[Since the given percentage values are 25% and 20% that's why we have picked up option (c)].

$$\frac{2}{5} \rightarrow \frac{4}{25} \rightarrow \frac{5}{20}$$

To verify : $\frac{2}{5} \times \frac{5}{8} = \frac{1}{4} = \frac{5}{20}$

Hence presumed option is correct

Alternatively: $\frac{x}{y} \rightarrow \frac{x^2}{y^2} \rightarrow \frac{1.25x^2}{0.8y^2} = \frac{25}{16}\frac{x^2}{y^2}$

Now since $\frac{25x^2}{16y^2} = \frac{5}{8}\left(\frac{x}{y}\right)$

$\Rightarrow \frac{x}{y} = \frac{2}{5}$

3. Income = Expenditure + Savings

$$\begin{pmatrix} 8x = \\ 10x = \end{pmatrix} \begin{pmatrix} 5x + 3x \\ 8x + 2x \end{pmatrix} - x$$

Now the deficit $= (3x - 2x) = x = 3500$

and $\therefore$ the new salary $= 10x = 35{,}000$

Alternatively : Go through options.

4. Go through options

$2457 - 2143 = 314$ (True)

Again $(2457 + 2143) + 41 = 4641$

Now $\frac{4641}{0.85} \rightarrow 5460$

Again $\frac{5460 \times 45}{100} = 2457$ (True)

Hence the presumed option is correct.

Alternatively: Let there be total x eligible voters, and the no. of votes goes to loser is k then

$0.85x - 41 = 2k + 314$ ...(1)

$k + 314 = 0.45x$ ...(2)

Therefore $x = 5460$

then, $5460 \times 0.85 = 4641$

Again $4641 - 41 = 4600$

Again $k + (k + 314) = 4600$

$\Rightarrow k = 2143$ (loser)

and $k + 314 = 2457$ (winner)

5.

Income →	4	4.4	4.8	5.2]	18.4	lakh
Saving →	2	1.76	1.44	1.04]	6.24	lakh
Exp. →	2	2.64	3.36	4.16]	12.16	lakh

So, $\frac{6.24}{12.16} \times 100 = 51\frac{6}{19}\%$

6. Let there be x voters and k votes goes to loser then

$0.8x - 120 = k + (k + 200)$

$k + 200 = 0.41x$

$\Rightarrow k = 1440$

and $(k + 200) = 1640$

Therefore $\frac{1440}{3200} \times 100 = 45\%$

Scanned by CamScanner

yoursmahboob.wordpress.com

Solutions for 7 – 9 :

$$P + R = 30{,}000 \quad ...(1)$$

$$N = R - 8000 \quad ...(2)$$

$$(R + N) = 233.3\,(P)$$

$$\Rightarrow \quad 3(R + N) = 7P \quad ...(3)$$

$$\Rightarrow \quad 6R - 7P = 24{,}000 \quad ...(4)$$

$$\therefore \quad R = 18{,}000$$

and $P = 12{,}000$

and $N = 10{,}000$

7. $\dfrac{P + R + N}{3} = \dfrac{40{,}000}{3} = 1333.33$

8. Can't be determined

9. $\dfrac{8}{10} \times 100 = 80\%$

10. (Bonus) Commission $= \dfrac{20 \times 10{,}00{,}000}{100} = 2$ lakh

but total profit = net profit + $\dfrac{10}{100}$ × net profit

$\Rightarrow$ 1.32 lakh = 1.1 × net profit

$\Rightarrow$ net profit = 1.2 lakh = 1,20,000

$\therefore$ commission = total profit – net profit

= 1,32,000 – 1,20,000 = 12,000

hence total earning = 2,00,000 + 12,000 = 2,12,000

11. Let Mr. Scindia has x shares of 5.5%

$$x \times 92 = 32{,}200$$

$\Rightarrow$ $x = 350$ shares

Income = 350 × 5.5 = 1925

Now, after investment his income is

$$\left(\frac{1}{3} \times \frac{32200}{92} \times 4.5\right) + \left(\frac{2}{5} \times \frac{32200}{115} \times 5\right) + \left(\frac{4}{15} \times \frac{32{,}200}{56} \times 6\right)$$

$$= 525 + 560 + 920 = 2005$$

Profit = 2005 – 1925 = Rs. 80

12. The surface area of a cube = $6a^2 = 6 \times (\text{side})^2$

New surface area = $6 \times 1.44\,a^2$

$\therefore$ $\dfrac{0.44\,a^2}{a^2} \times 100 = 44\%$

Solution for 13 and 14 :

Pati → *Pt*, *Patni* → *Pn*, *Woh* → *W*

$$(Pt + Pn) = 2W \quad ...(i)$$

$$(Pn + W) = 4\,Pt \quad ...(ii)$$

Solving equation (i) and (ii) we get

$$\frac{Pn}{W} = \frac{7}{5} \quad \textit{and} \quad \frac{Pt}{W} = \frac{3}{5}$$

$\Rightarrow$ $Pt : Pn : W = 3 : 7 : 5$

Again $(Pt + Pn) = 2W \quad ...(iii)$

and $(Pn + W) \times 7 = 8 \times Pt \quad ...(iv)$

Therefore $\dfrac{Pn}{W} = \dfrac{3}{5}, \quad \dfrac{Pt}{W} = \dfrac{7}{5}$

$\Rightarrow$ $Pt : Pn : W = 7 : 3 : 5$

Gain of Pati = $7x - 3x = 4x = 800$

$\Rightarrow$ $x = 200$

	Pati	*Patni*	*Woh*
Amount at the begining of Game =	600	1400	1000
Amount at the end of the game =	1400	600	1000

13. Only Patni has suffered the loss

14. $\dfrac{1400 - 600}{1400} \times 100 = 57.1428\%$

15. RM + MC = Total cost

Total cost + Profit = Sale price

$70 + 30 = 100 \quad 100 + 10 = 110$

$84 + 42 = 126 \quad 126 + 72 = 198$ ← + 80%

Therefore profit % = $\dfrac{72}{126} \times 100 = 57.14\%$

16. $A + B + C + D = 56$

$B + C + D = 4.6A$

$\Rightarrow$ $A + B + C + D = 5.6A$ (adding A in both sides)

56 lakh = $5.6A$

$\Rightarrow$ $A = 10$ lakh

Similarly $A + C + D = \dfrac{11}{3} B$

$\Rightarrow$ $A + B + C + D = \dfrac{14}{3} B$

$\Rightarrow$ $B = 12$ lakh

Similarly $4\,(A + B + D) = C$

$\Rightarrow$ $A + B + D = 2.5C$

$\Rightarrow$ $A + B + C + D = 3.5C$

$\Rightarrow$ $C = 16$ lakh

Therefore $D = (A + B + C + D) - (A + B + C) = 18$ lakh

17. Losing candidate = $0.3\,x$

$\therefore$ Other two candidates = $0.7\,x$

The share of winning candidate = $0.36\,x$

and the second ranker = $0.34\,x$

$\therefore$ Margin (min. possible) = $0.02\,x$

$\Rightarrow$ 2% of x

Let the minimum possible voters be 50 then

$$\frac{2 \times 50}{100} = 1$$

Hence the minimum possible margin of votes = 1

18.

Day	Initial amount	Sales	Remaining over night	Rotten	Stock for next day
I	x	$0.5x$	$0.5x$	$0.05x$	$0.45x$
II	$0.45x$	$0.225x$	$0.225x$	$0.0225x$	$0.2025x$
III	$0.2025x$	$0.10125x$	$0.10125x$	$0.010125x$	

$\therefore$ Total rotten amount = $0.082625x = 1983$

$\Rightarrow$ $x = 24{,}000$

Scanned by CamScanner

yoursmahboob.wordpress.com

19. Check through option

Alternatively : Let the initial amount be x (with gambler), then

$$\left(\left((x+100)\frac{1}{2}+100\right)\frac{1}{2}+100\right)\frac{1}{2}=\frac{x}{2}$$

$$\Rightarrow \quad x=\frac{700}{3}$$

20. Non-defective products

$$\frac{25\times 0.98+35\times 0.96+40\times 0.95}{100}\times 100=96.1$$

21.

No. of Machines	Output	Manf. cost	Est. cost	Total cost	Profit
12	48,000	24,000	10,000	34,000	14,000
11	44,000	22,000	10,000	32,000	12,000

Profit = out put − Total cost

= 44,000 − 32,000 = 12,000

Initial value of share holders $= 14{,}000\times\frac{10}{100}=1400$

Changed value of share holders $= 12{,}000\times\frac{10}{100}=1200$

$$\%\text{ decrease}=\frac{200}{1400}\times 100=14.28\%$$

22.

Rice	Wheat
25	9
$\times x$	$\times 5x$
$25x$	$45x$

$$70x=350$$

$$\Rightarrow \quad x=5$$

Hence the price of Rice = Rs. 5 per kg

Price of wheat = Rs. 25 per kg

Now, the price of wheat = Rs. 30 per kg

Let the new amount of Rice be M kg, then

$$M\times 5+9\times 30=350$$

$$M=16$$

Hence decrease (in%) of amount of rice

$$=\frac{25-16}{25}\times 100=36\%$$

23.

Year	Rate of Commission	Commission in values
1	20%	$0.2\times 20{,}000=4000$
	25% (bonus)	$0.25\times 4000=1000$
2	16%	$0.16\times 20{,}000=3200$
3	12%	$0.12\times 20{,}000=2400$
4	10%	$0.1\times 20{,}000=2000$
5–10	4%	$6\times 0.04\times 20{,}000=4800$

Total commission

= (4000 + 3200 + 2400 + 2000 + 48 00) + (1000) = 17,400

Solution for 24-25

	OHIO	TEXAS
Last year :	$600 \xleftarrow[(2:1)]{(M:F)}$	$\xrightarrow[(5:6)]{(M:F)} 1100$
This year :	$750 \xleftarrow{(2:1)}$	$\xrightarrow{\text{(unknown)}} 1200$

24. Since we don't know the number of female employees in the Texas office this year so we can't determine

25. 1100 + 600 = 1700

26. There is no need to use the no. of goats *i.e.*, (34, 398) let initially there be 1000 goats then

$$1000\to 1400\to 980\to 1274\to 1146.6$$

Thus the % increase $=\frac{1146.6-1000}{1000}\times 100=14.66\%$

27. In 2002 (980 goats) as per the flow chart

Optional	Science	Commerce	Engineering	Total
	5000	3000	8000	16,000
Finance	1000	1200	680	2880
HR	1600	720	1040	3360
Marketing	2400	1080	6280	9760

28. 6280 Students of Engineering opted marketing

29. $\frac{720}{16{,}000}\times 100=4.5\%$

30. Marketing, since maximum students have opted marketing.

31. Consider some values and then verify the option.

32. Go through option :

700 ↓ 91% = (100 − 9)% ↓ 637 ↓ 80% ↓ 509.6 ≈ 510 persons ↓ 70% (completely cured out) ↓ 357 ↓ (Partially cured) 153 = (510 − 357)

Hence, the presumed option is corret

33. Total expenditure per kg

= 3.2 + 1.8 + 2 + 3 = 10 = cost price

Selling price = Rs. 18 (per kg)

Gross profit = Rs. 8 per kg = (18 − 10)

Net profit $= 8\times\frac{80}{100}$ (since 20% is tax) = Rs. 6.4

Hence the net profit of the factory = 6.4 × 50,00,000

= Rs. 3,20,00,000 = Rs. 3.2 crore

34. Let the percentage marks in QA = $(10a+b)\%$

Let the percentage marks in DI = $(10b+a)\%$

Let the percentage marks in VA = $x\%$

then $\frac{(10a+b)+x+(10b+a)}{3}=x$

$$\Rightarrow \quad 11a+11b+x=3x$$

$$\Rightarrow \quad x=\frac{11}{2}(a+b)$$

Thus the percentage of the VA section is a multiple of 11.

Scanned by CamScanner

yoursmahboob.wordpress.com

35. $P_1 = k\frac{T}{V}$

$$P_2 = k\frac{1.4T}{0.8} = K\frac{7T}{4V}$$

$$\frac{P_2 - P_1}{P_1} = \frac{\frac{7}{4}\frac{T}{V} - \frac{T}{V}}{\frac{T}{V}} = \frac{\frac{3}{4}\frac{T}{V}}{\frac{T}{V}} = \frac{3}{4}$$

Hence, the new pressure will be increased by 75%.

36. $20 \times 0.92 \Rightarrow$ 10 minutes.

$$\frac{23 \times 40 \times 0.90}{20 \times 0.92} = 45$$

Thus the required time is 45 times than the previous time

Hence, 450 minutes $= 7\frac{1}{2}$ hrs.

37. Original volume $= 16 \times 12 \times 5 = 960\ (\text{inch})^3$

Required capacity $= 1120\ (\text{inch})^3$

Increase in area $= \frac{1120}{5} - 16 \times 12$

$= 224 - 192 = 32\ (\text{inch})^2$

$$\% \text{ increase} = \frac{32}{192} \times 100 = 16.66\%$$

38. The total passengers in each compartment $= 25 \times \frac{7}{5} = 35$

Total no. of seats $= (35)^2 = 1225$

Maximum available capacity $= 1225 \times \frac{80}{100} = 980$ seats

39.

	Tata	Reliance
Prepaid	100	81
Postpaid	90	72

Thus the % decrease in talk time $= \frac{90 - 72}{90} \times 100 = 20\%$

40. **Half yearly exam**



Annual exam

$$\underbrace{\frac{70 \times 0.6}{42}} + \underbrace{\frac{30 \times 0.8}{24}}$$

∴ Total pass in annual exam $= 42 + 24 = 66$

41. Percentage of passed students $= 68\%$ [100 − 32]%

Number of girls passed the exam $= 408$

Number of boys passed the exam $= 476$

Total passed students $= 884$

Therefore total no. of students $= \frac{884}{68} \times 100 = 1300$

Solution for 42- 45 :

Name	Horse	Chariot	Land	Total (in Rs.)
Ram	2 lakh (10)	80,000 (10)	20 acre = 1 lakh	3.8 lakh
Sita	1.6 lakh (8)	80,000 (10)	8 acre = 40,000	2.8 lakh
Laxman	1 lakh (5)	2 lakh (25)	20 acre = 1 lakh	4 lakh
Urmila	1.4 lakh (7)	40,000 (5)	16 acre = 80,000	2.6 lakh

1. $R + S = L + U$ *and* $R > S$ *and* $L > U$

2. Horses $\rightarrow (R + S) : (L + U) = 3x : 2x = 18x : 12x$

Again Ram have $\frac{1}{3}$ *rd horses*

Therefore $30x \times \frac{1}{3} = 10x$

Therefore the horse of Sita $= 18x - 10x = 8x$

$\Rightarrow \quad x = 1$

Therefore the horse of Ram $= 10$ *and Laxman* $= 5$

No. of chariots of Sita = No. of chariots of Ram $= \frac{K}{5}$

and *no. of chariots of Laxman* $= \frac{K}{2}$

Hence the no. of chariots of Urmila $= K - \left(\frac{K}{5} + \frac{K}{5} + \frac{K}{2}\right) = \frac{K}{10}$

Again $\frac{k}{2} - \frac{k}{10} = 20 \Rightarrow k = 50$ *chariots*

Now the 50% property of Laxman $= 25$ *chariots* $= 2{,}00{,}000$

Hence the total property of Laxman $= 4{,}00{,}000$

Thus the area of Land of Laxman $= \frac{2{,}00{,}000 - 5 \times 20{,}000}{5000}$

$= 20$ acre $= (1$ lakh$)$

Total property of Urmila

$= 1{,}40{,}000 + 40{,}000 + 80{,}000 = 2{,}60{,}000$

Thus the total property of Laxman and Urmila $= 6.6$ *lakh*

42. $3.8 - 2.6 = 1.2$ lakh

43. Value of chariots of Laxman $= 2$ lakh

Now since only Ram has the horses of worth Rs. 2 lakh. So only Ram can exchange with Laxman.

45. $\frac{7.2 - 6.0}{6.0} \times 100 = 20\%$

46. Total cubes $160 + 56 = 216$

Therefore the side of cube $= 6$ unit

No. of cubes without any exposure $= (6 - 2)^3 = 64$

Thus 64 cubes will be inside of the big cube

Now rest of the cubes $= 160 - 64 = 96$

Again the no. of cubes with one face outside

$= 6 \times (4 \times 4) = 96$

Hence the required percentage $= \frac{96}{216} \times 100 = 44.44\%$

Scanned by CamScanner

yoursmahboob.wordpress.com

47.

(Qualified CAT)
↓
x boys and x girls
↓
(Qualified G.D)
↓
$0.4x$ boys
↓
(Interview)

IIM-A	IIM-B	
[$0.2x$	$0.2x$]	appeared
↓	↓	
Qualified	Qualified	
↓	↓	
$0.8 \times 0.2x$	$0.4 \times 0.2x$	
$= 0.16x$	$= 0.08x$	

Total boys qualified the final stage = 0.24%

Thus $0.24x = 24$

$\Rightarrow$ $x = 100$

48. Go through option and consider some appropriate values

Alternatively : $\frac{p}{100+p} = \frac{q}{100}$

$\Rightarrow$ $100(p-q) = pq$

$\Rightarrow$ $(p-q) = \frac{pq}{100}$

49. Let the original price be P, then the decrease in value of P after one cycle

$$= p\left(\frac{x}{100}\right)^2 = 21025 \quad \ldots(i)$$

Again the final value after second cycle

$$\Rightarrow P\left(1+\frac{x}{100}\right)\left(1-\frac{x}{100}\right)\left(1+\frac{x}{100}\right)\left(1-\frac{x}{100}\right) = 484416$$

$$\Rightarrow P\left[1-\left(\frac{x}{100}\right)^2\right]^2 = 484416 \quad \ldots(ii)$$

Dividing equation (ii) by equation (i)

$$\frac{\left[1-\left(\frac{x}{100}\right)^2\right]^2}{\left(\frac{x}{100}\right)^2} = \frac{484416}{21025} = \frac{2304}{100}$$

$$\Rightarrow \frac{1-\left(\frac{x}{100}\right)^2}{\left(\frac{x}{100}\right)} = \sqrt{\frac{2304}{100}} = \frac{48}{10}$$

Let $\frac{x}{100} = k$, then

$$\frac{1-k^2}{k} = \frac{48}{10}$$

$\Rightarrow$ $10k^2 + 48k - 10 = 0$

$\Rightarrow$ $5k^2 - 24x - 5 = 0$

$\Rightarrow$ $k = 5$ or $k = -\frac{1}{5}$ (inadmissible value)

So $x = 20\%$

Hence, $P\left(\frac{x}{100}\right)^2 = 21025$

$\Rightarrow$ $P = 525625$

50. Men × Time = Work

100 × 1 = 100 unit

150 × 1 = 150 unit

Extra man power required = 50

but since new workers are $\frac{5}{4}$ times as efficient as existing workers.

$\therefore$ Actual no. of workers $= \frac{50}{5/4} = 40$ men

Hence, required percentage $= \frac{40}{100} \times 100 = 40\%$

Final Round

1. Growth rate of Finance

$$= \frac{125-75}{75} \times 100 = \frac{2}{3} \times 100 = 66.66\%$$

Growth rate of Marketing $= \frac{250-100}{100} \times 100 = 150\%$

2. Total no. of students in 2003-04 is

$= (250 + 125 + 100 + 75) = 550$

No. of student in 2004-05

$$= 550\left(1+\frac{1}{11}\right) = 600 \text{ students}$$

3. $\frac{50}{(150+100+75+50)} \times 100 = \frac{50}{375} \times 100 = 13.33\%$

4. $\frac{4800-4000}{4000} \times 100 = 20\%$

5. $\frac{450}{4350} \times 100 = 10.34\%$, which is lowest in comparison to others

Thus the growth rate of logical reasoning book is lowest.

6. DI $\rightarrow \frac{5000-3750}{3750} \times 100 = 33.33$

and VA $\rightarrow \frac{5500-4140}{4140} \times 100 = 32.85\%$

7. Only LR has consistent growth, others have been fluctuated (QA – 2003, DI – 2003, VA – 2002)

8. $\frac{\left[\frac{8.5-2.97}{2.97} \times 100\right]}{5} = 37.23\%$

9. Growth rate of Hero = 37.23%

Growth rate of Atlas = 28.1%

Avon is least which is clear from the data.

Total bicycle production is highest in 95 hence false

Hero cycle's share $= \frac{2.97 + 4.22 + \ldots 8.5}{79.84} = 43\%$

Hence, (d) since none of (a), (b) and (c) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

10. $\frac{1.75+2.48+\ldots 4.21}{79.84}=23.4\%$

11. $\frac{1.64}{64.8}\times 100=2.53$

12. Amul has max. unutilised capacity

HINT $\left(\frac{1.54}{59.35}\times 100\right)-1.54=1.05$

Similarly for others can also be find out

13. $\frac{11.6}{61.3}\times 100\approx 18.9$

14. $\frac{42.20}{132.8}\times 100=31.81\%$

15. $\frac{105}{360}\times 100=\frac{7}{24}\times 100=29.166\%$

16. $\frac{30}{120}\times 100=25\%$

17. $\frac{15}{120}\times 100=12.5\%$

18. $105-45=60°=4$ hours

19. $15°=1$ hour (Maths)
$30°=2$ hour (other subjects)

20. Sony TV → 19%
Sony Refrigerator → 15%
difference = 4% = 14.4° (Since 1% = 3.6°)

21. 12% → Samsung TV = 31 crore
18% → Electrolux TV = 46.5 crore
100% → Total market = 258 crore

11% → Samsung Refrg. = 9 crore
13% → Electrolux Refrg. = 10.6 crore
100% → Total market = 81.8 crore

$$\text{Market share}=\frac{46.5+10.6}{258+81.8}\approx 16.7\%$$

22. 18% = Rs. 42 crores, so 27% (= 16 + 11) = Rs. 63 crore
13% = Rs. 6 crore, so 28% (= 12 + 16) = Rs. 13 crore
Total Rs. 76 crores
∴ Annual approx. turnover = 4 × 76 = Rs. 304 crores

23. (a) (13 − 12) = 1% = 3.6
(b) We don't know the turnover of TV and refrigerator market for each brand.
(c) 6% total refrigerator market = 100 crore
⇒ Total refrigerator market ≅ 1667 crore
∴ Difference = 2% of 1667 = 33.34 crore
Thus, (b) can't be inffered.

24. $\frac{52,000-5,000}{5000}\times 100=9.4\times 100=940\%$

25. Medical college in $1980=\frac{11}{100}\times 32,000=3520$

$$1990=\frac{9}{100}\times 52,000=4680$$

$$\therefore\quad \frac{4680-3520}{3520}\times 100=32.95$$

26. We don't have the information about the proportion (share) of Engineering colleges in the given years.

27. $\frac{32,000-12,000}{12,000}\times 100=166.66\%$

28. Number of medical colleges in 1990

$$=\frac{52,000\times 9}{100}=4680$$

Increase in the total no. of colleges

$$=60,000-52000=8000$$

Increase in the no. of medical colleges $=\frac{8000}{4}=2000$

Therefore, percentage of medical colleges in 2000

$$=\frac{4680+2000}{60,000}\times 100=11\%$$

29. If the amount of water consumed of sector 1 is the same then we can directly compare the tariffs to the two years.

	Tariff 2003–04	% change	Tariff 2000–01
Region 1	1000	+ 25%	800
Region 2	400	+ 14.28%	350
Region 3	250	–16.66%	300
Region 4	625	+ 4.166%	600
Region 5	720	+ 20%	600
	2995		**2650**

$$\frac{2995-2650}{2650}\times 100=\frac{345}{2650}\times 100$$

$$=13.01\%$$

30.

	Tariff 2003–04	% change over 2000-01	Tariff 2000–01
Sector 1	400	+ 14.28%	350
Sector 2	375	+ 7.14%	350
Sector 3	525	–12.5%	600
Sector 4	800	–20%	1000
	2100		**2300**

$$\text{Average tarrif}=\frac{2300}{4}=575$$

31. In 2003-04 the water consumed by various secters out of 20,000 kilo-litres can be given as follow:

Category	Percentage	Consumption in 2003–04
Domestic	40	8,000
Urban	25	5,000
Rural	15	3,000
Industrial	20	4,000
		20,000

Since there was a 20% decrease in the domestic consumption in 2003-04 the domestic consumption in

2000-01 $=\frac{8,000}{0.8}=10,000$

Scanned by CamScanner

yoursmahboob.wordpress.com

But this constitutes 40% of total water consumed in 2000-01 and the industrial consumption constitutes 20% of total water in 2000-01. Hence in 2000-01 the industrial consumption $= 10{,}000 \times \frac{20}{40} = 5{,}000$ kilo-liters

32. We do not know the category-wise break up of tariffs ie the rates of Urban sector is unknown.

33. The average of Region $2 = \frac{400 + 375 + 525 + 800}{4} = 525$

Average tariff in region $4 = \frac{62.5 + 750 + 240 + 360}{4} = 487.5$

Average tariff in region $5 = \frac{220 + 360 + 320 + 400}{4} = 450$

Statements (c) can not be determined

34. Total number of people = 10,000

Business men	10%	1000
Govt. Servant	13%	1300
Professionals	30%	3000
Students	45%	4500
Housewives	2%	200

LML	1200
SUZUKI	1200
BAJAJ	3000
HERO HONDA	6600

The total number of Hero Honda bikes = 6600

Total numbers of Government servants housewives and students = 6000

Total no. of Businessmen and professional = 4000

∴ Percentage of remaining (*i.e.*, Businessmen and prof.) driving Hero Honda $= \frac{600}{4000} \times 100 = 15\%$

35. Let the no. of people who drive one two and three bikes be $15k$, $3k$ and k respectively.

Number of bikes which are being driven

$$= 15k + 2(3k) + 3(k) = 24k$$

Since LML and Suzuki can not be driven by same person and a person can drive maximum 3 bikes.

Total bikes which are being used to drive = 12,000

$$\therefore \quad 24k = 12{,}000 \Rightarrow k = 500$$

Total number of people driving the bikes

$$= 15k + 3k + k = 19k = 9500$$

∴ Number of people who do not drive any bike

$$= 10{,}000 - 9500 = 500$$

36. From the previous solution, number of people who drive more than 1 bike *i.e.*, 2 bikes and 3 bikes are 1500 and 500 respectively.

These people have total 4500 bikes

$$(= 1500 \times 2 + 500 \times 3)$$

Hence, the remaining Hero Honda bikes

$$= 6600 - 4500 = 2100$$

Thus, the number of persons who drive single Hero Honda

$$= 2100$$

37. Since 20% drive other bikes 80% drive only bajaj bike number of people who drive only Bajaj bike

$$= 0.8 \times 3000 = 2400$$

38. $\frac{11000 + 12000}{21{,}000} \times 100 = 109.52\%$

39. $\frac{27{,}000 - 23{,}000}{23{,}000} \times 100 = 17.4\%$

40. Demand = Domestic Production + Imports

Average demand $= \frac{44 + 54.5 + 57}{3} \approx 52$ million tonnes

41. (c) $\frac{30{,}000 - 21{,}000}{21{,}000} \times 100 \approx 43\%$

42. Offshore production in 2004 $= 16{,}000 \times 0.875$

$= 14{,}000$ thousand tonnes

Onshore production = 11,000 thousand tonnes

Demand in 2004 $= 57{,}000 \times 1.02 = 5814$ thousand tonnes

imports = 33.14 million tonnes ($\because$ 1 million $\approx 10^6$)

43. $201924 \times \frac{5}{6} = 33654 \times 5 = 168270$

44. $127890 \times \frac{11}{10} = 140679$

45. $126400 + 975264 + 237852 = 1339516$

46. $\frac{100956}{2445480} \times 100 = 4.128\%$

Alternatively: $\frac{1}{24} \times 100 \approx 4.16\%$

47. 1969 – 70 → 134790
1979 – 80 → 284620] 149830

48. 1929 – 30 → 9,75,264

1949 – 50 → 1,40,679

% decrease $= \frac{975264 - 140679}{975264} \times 100 = 85.57\%$

49. 1959 – 60 ⟶ 1960 – 61

$168020 \xrightarrow{+20\%} 201924$

Therefore $\frac{168020}{201924} \times 100 = 83.33\%$

Alternatively: From percentage charge graphic

Increase	Decrease
20%	16.66%
1/5	1/6

∴ The required value = 83.33% (100 – 16.66%)

Alternatively: $x \times \frac{6}{5} = k$

$$\Rightarrow \quad x = \frac{5k}{6}$$

$$(x)\% = \frac{5k}{6} \times 100 = 83.33\% \text{ of } k$$

50. Only 7,900 tonnes increase over the 1919 – 20.

Scanned by CamScanner

yoursmahboob.wordpress.com

6 PROFIT, LOSS AND DISCOUNT

This chapter is as much important as other chapters in the arithmetic section, since it is a chapter of applications by which we calculate profit, loss, discount in day-to-day business. So in the entrance exams of MBA it plays a crucial role in determining the selection of an aspirant. Particularly in CAT the questions asked in QA are very logical in nature, apart from the simple application in Data interpretation (D.I.) and Data sufficiency (D.S.). Entrance exams like FMS, IIFT, NIFT and MAT ask plethora of questions. Infact a normal question paper seems to be incomplete without having the problems based on profit, loss and discount.

THEORY AND CONCEPTS

In day-to-day life we sell and purchase the things as per our requirement. A customer can get things in the following manner :

Manufacturer (or producer) → Whole-saler (dealer) → (Shopkeeper) Retailer (or sales person) → Customer

TERMINOLOGY

Cost price (CP) : The money paid by the shopkeeper to the manufacturer or whole-saler to buy the goods is called the cost price (CP) of the goods purchased by the shopkeeper.

NOTE If an article is purchased for some amount and there are some additional expenses on transportation labour, commission etc., these are to be added in the cost price. Such expenses are called overhead expenses or overheads.

Selling Price (SP) : The price at which the shopkeeper sells the goods is called the selling price (SP) of the goods sold by the shopkeeper.

Profit : If the selling price of an article is more than its cost price, then the dealer (or shopkeeper) makes a profit (or gain)

i.e., Profit = SP – CP; SP > CP

Loss : If the selling price of an article is less than its cost price, then the dealer suffers a loss.

i.e., loss = CP – SP; CP > SP

Important Formulae

(i) Profit = SP – CP

(ii) Loss = CP – SP

(iii) $\text{Profit percentage} = \frac{\text{profit}}{\text{cost price}} \times 100$

(iv) $\text{Loss percentage} = \frac{\text{loss}}{\text{cost price}} \times 100$

(v) $SP = \left(\frac{100 + \text{gain}\%}{100} \times CP\right) = \left(\frac{100 - \text{loss}\%}{100} \times CP\right)$

(vi) $CP = \left(\frac{100}{100 + \text{gain}\%} \times SP\right) = \left(\frac{100}{100 - \text{loss}\%} \times SP\right)$

(vii) SP = (100 + k)% of CP; when profit = k% of CP

(viii) SP = (100 – k)% of CP; when loss = k% of CP

NOTE Profit or loss is always calculated on the basis of cost price unless otherwise mentioned in the problem.

EXAMPLE 1 *A fruit seller buys 300 oranges at 5 for Rs. 8 and sold at 2 for Rs. 5. Find :*

(i) the cost price of each orange

(ii) the selling price of each orange

(iii) profit or loss on selling one orange

(iv) his total profit or loss on selling all the oranges.

SOLUTION (i) Since the cost price of 5 oranges = Rs. 8

∴ Cost price of one (or each) orange = Rs. $\frac{8}{5}$ = Rs. 1.60

(ii) Since the selling price of 2 oranges = Rs. 5

∴ the selling price of one orange = Rs. $\frac{5}{2}$ = Rs. 2.50

(iii) Since SP is more than CP, there is a profit.

So profit on selling one orange = SP – CP

= 2.5 – 1.6 = Re. 0.90

(iv) Profit on selling all the oranges

= Rs. (0.90 × 300) = Rs. 270

Hence the total profit on selling all oranges = Rs. 270

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 2 *A shopkeeper buys 100 eggs at Rs. 1.20 per piece. Unfortunately 4 eggs got spoiled during transportation. The shopkeeper sells the remaining eggs at Rs. 15 a dozen. Find his profit or loss.*

SOLUTION Cost price of all eggs = Rs. 100×1.2 = Rs. 120

Selling price of one egg = $\frac{15}{12}$ = Rs. 1.25

$\therefore$ Selling price of 96 eggs = $96 \times \frac{15}{12}$ = Rs. 120

HINT After spoiling 4 eggs, only 96 eggs are left.

Now, since the total selling price and total cost price is same, the shopkeeper neither makes a profit nor suffers a loss.

EXAMPLE 3 *Aviral purchased a computer for Rs. 47,000. He had to sell it for Rs. 45,800. Find his profit or loss per cent.*

SOLUTION Since SP < CP, there will be loss

$$\text{loss (\%)} = \frac{\text{loss}}{\text{CP}} \times 100 = \frac{47000 - 45800}{47000} \times 100$$

$$= \frac{1200}{47000} \times 100 = 2\frac{26}{47}\%$$

EXAMPLE 4 *A dealer sold 600 quintals of sugar at a profit of 7%. If a quintal of sugar cost him Rs. 1600, find his total profit and the selling price.*

SOLUTION CP = 1600×600 = Rs. 9,60,000

Rate of Profit = 7%

$$\text{Profit} = 9{,}60{,}000 \times \frac{7}{100} = \text{Rs. } 67200$$

$\therefore$ SP = CP + Profit = Rs. 9,60,000 + Rs. 67,200

= Rs. 1027200

Thus profit = Rs. 67200 and selling price = Rs. 10,27,200

EXAMPLE 5 *A dealer buys 200 quintals of wheat at Rs. 1200 a quintal. He spends Rs. 10,000 on transportation and storage. Then he sells the wheat at Rs. 13 per kg. Find his profit or loss. Also calculate it as a percentage.*

SOLUTION CP = 1200×200 = Rs. 2,40,000

Transportation and storage cost = Rs. 10,000

Total CP = 2,40,000 + 10,000

= Rs. 2,50,000

Total SP = $13 \times 200 \times 100$

= Rs. 2,60,000

$\therefore$ Now, since SP > CP, hence there will be profit.

Profit = SP − CP = Rs. (2,60,000 − 2,50,000) = Rs. 10,000

$$\text{Profit (\%)} = \frac{\text{Profit}}{\text{CP}} \times 100$$

$$= \frac{10{,}000}{2{,}50{,}000} \times 100 = 4\%$$

EXAMPLE 6 *Find the cost price of an article which is sold for Rs. 220 at a loss of 12%.*

SOLUTION SP = Rs. 220, Loss = 12%

Let CP = Rs. x

then SP = 88% of CP

$$220 = \frac{88}{100} \times x$$

$\Rightarrow$ $x = 250$

Therefore cost price = Rs. 250

EXAMPLE 7 *By selling a colour TV for Rs. 23520, a dealer suffers a loss of 4%. What is the cost price of the colour TV? At what price should he sell it to gain 8%?*

SOLUTION SP = 96% of CP $\because$ (loss is 4%)

$\therefore$ $23520 = \frac{96}{100} \times \text{CP}$

CP = 24500

Now gain % = 8%

$\therefore$ New selling price = (100 + 8)% of CP

$$= \frac{108}{100} \times 24500 = \text{Rs. } 26460$$

INTRODUCTORY EXERCISE-6.1

1. A towel is sold for Rs. 198 at a gain of 10%. What is the cost price of the towel? At what price must it be sold to gain 25%?
2. A man sold a watch at Rs. 6000, at a loss of $33\frac{1}{3}\%$. Find the cost price?
3. By selling a shirt for Rs. 285 a shopkeeper loses 5%. At what price should he sell the shirt so as to gain 15%?
4. Sufyan bought 1200 eggs at Rs. 16 a dozen. At what price per hundred must he sell the eggs so as to earn a profit of 15%?
5. Ram Singh purchased two camels for Rs. 18,000 and Rs. 15,000 respectively. He sold them at a loss of 15% and a gain of 19% respectively. Find the selling price of each of the camels. Also find the overall gain or loss per cent in the transaction.

MARK UP AND DISCOUNT

Marked price: Basically to avoid loss due to bargaining by the customer and to get the profit over the cost price trader increases the cost price by a certain value, this increase in value over cost price is known as markup and the increased price (*i.e.*, CP + Markup) is called the marked price or printed price or list price of the goods.

Scanned by CamScanner

yoursmahboob.wordpress.com

Marked price = CP + Markup
Marked price = CP + (% markup on CP)

Generally goods are sold at marked price, if there is no further discount, then in this case selling price equals to marked price.

Discount : Discount means reduction of marked price to sell at a lower rate or literally discount means concession. Basically it is calculated on the basis of marked price.

∴ Selling price = Marked price – Discount
or Selling price = Marked price (MP) – (% discount on MP)

Since marked price = CP + % markup on CP

Remember **markup** is calculated on the basis of CP while **discount** is calculated on the basis of MP.

In general, CP < SP < MP at profit
CP = SP < MP at no profit no loss
SP < CP < MP at loss

Also

and

NOTE You will find wide application of percentage calculation, percentage change graphic etc. so to move further you must know the concepts of percentages.

EXAMPLE 8 *If the cost price of an article is Rs. 300 and the per cent markup is 20%. What is the marked price?*

SOLUTION MP = CP + % markup on CP

$= 300 + 300 \times \frac{20}{100}$

MP = Rs. 360

Alternatively : SP = 300 × 1.2 = 360

EXAMPLE 9 *If the marked price of an article is Rs. 450 and markup percentage is 12.5%, what is the cost price?*

SOLUTION MP = 112.5 of CP

$\therefore \quad 450 = \frac{112.5}{100} \times CP$

$450 = \frac{9}{8} \times CP$

$\Rightarrow \quad CP = Rs.\ 400$

Alternatively : Change your outlook to visulize the problem differently for smarter calculation.

You can see that MP is 12.5% (*i.e.*, $\frac{1}{8}$ times) greater than CP.

So CP will be $\frac{1}{9}$ times less than MP. This percentage (or fraction) change rule has been throughly discussed through different illustrations in percentage chapter. In my opinion if you change your observation *i.e.*, you mould your thinking in a CAT oriented approach you will not change only your attitude and aptitude but the whole scenario will be changed. So look this problem like me :



$\left(\frac{n}{d+n}\right)$ $n \rightarrow$ numerator, $d \rightarrow$ denominator

So, the CP will be $\frac{1}{9}$ times less than MP, which is rather too much easier to calculate than the traditional method given at the beginning of the solution.

EXAMPLE 10 *If the marked price of an article is Rs. 660 and the discount is 10%, then what is the selling price of the article?*

SOLUTION **General Solution :**

SP = MP – Discount

$SP = 660 - 660 \times \frac{10}{100}$

SP = 594

Alternatively: SP = 90% of MP

SP = 0.9 × 660

SP = 594

Alternatively: We can see that when SP is 10% (*i.e.*, $\frac{1}{10}$) less than MP, it means MP is $\frac{1}{9}$ times greater than SP.

Therefore $MP = \frac{10}{9} SP \quad \left(1 + \frac{1}{9} = \frac{10}{9}\right)$

Ultimately I would like to say that you should see the core of the problem and solution both, instead of taking help from any formula. In other words formulae make you logically blind particularly in context of CAT where your intelligence is tested rather than your memory and theory of the maths.

EXAMPLE 11 *If the markup percentage of an article is 50% and discount percentage is also 20%, then the profit percentage will be :*
(a) 10% (b) 0% (c) 30% (d) 20%

SOLUTION See the smartest calculation technique and follow me to be smarter.



Therefore profit = 20% $\left(\frac{120-100}{100} \times 100 = 20\%\right)$

Explanation: MP = 150% of CP (∵ markup is 50%)
SP = 80% of MP (∵ discount is 20%)

Once again I am reiterating on the gist of this chapter. What is that gist? The gist is that this chapter test nothing but your grip on the concepts of percentage change. I think CP, SP, MP etc., are just the words, the crux is that how CP, SP and MP etc., change with respect to each other. So those students who have grasped and internalised the most important concept of percentage change, they will not find any difficulty in understanding the concept of the profit-loss problems. Believe me when your visualisation will be improved, you will be master on this chapter. So try to have a different approach.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 12 *A trader markup the goods by 10% and then gives a discount of 10%. What is the profit or loss percentage?*

SOLUTION

CP → SP → MP

100 → 99 → 110

So there is a loss of 1%.

Explanation: MP = 110% of CP (10% markup)

SP = 90% of MP (10% discount)

EXAMPLE 13 *Successive discount of 10% and 5% is equivalent to :*

(a) 16.5% *(b) 15%*

(c) 15.5% *(d) 14.5%*

SOLUTION

100 ↓ (–10%) 90 ↓ (–5%) 85.5

14.5

NOTE There is no difference in two different cases *i.e.*, either you decrease 100 at first by 10% and then by 5% or decrease 100 at first by 5% and then by 10%.

100 ↓ (–5%) 95 ↓ (–10%) 85.5

14.5

Explanation : $100 \times 0.9 \times 0.95 = 85.5$

∴ Single discount equivalent to 10% and 5% is 14.5%

(100 – 85.5)%

or $(100 \times 0.95 \times 0.9 = 85.5)$

Some Important Concepts

(1) When two articles are sold at same price but one of them at a profit and another at a loss and the percentage profit is the same as the percentage loss. In this case there is always a loss.

$$\text{loss (\%)} = \left(\frac{\text{Common gain or loss}}{10}\right)^2$$

EXAMPLE 14 *A man sells two wrist watches one at a profit of 10% and another at a loss of 10%, but the selling price of each watch is Rs. 200. Find the :*

(1) percentage profit or loss

(2) net amount of profit or loss

SOLUTION (1) Since there is always loss.

(Logic: To get the logic you should refer the percentage chapter)

Now, $\text{loss \%} = \left(\frac{\text{Common gain or loss}}{10}\right)^2 \%$

$$\text{loss \%} = \left(\frac{10}{10}\right)^2 \% = 1\%$$

(2) Amount of loss.

Total SP = Rs. 400 (200 + 200)

again, total SP = 99% of CP (1% loss)

$$400 = \frac{99}{100} \times \text{CP}$$

$$\Rightarrow \quad \text{CP} = \text{Rs. } 404.04$$

$$\therefore \quad \text{loss} = \text{CP} - \text{SP} = \text{Rs. } 4.04 \qquad (= 404.04 - 400)$$

EXAMPLE 15 *There were two articles and the sum of cost prices of these articles is Rs. 500. One of them was sold at a profit of 20% and another at a loss of 20%. Besides if the selling prices of both the articles were same. Find the amount of overall loss.*

SOLUTION

$$x \times \frac{120}{100} = (500 - x)\frac{80}{100}$$

$$\Rightarrow \quad x = 200$$

So, the CP of profit yielding article = Rs. 200

and the CP of loss giving article = Rs. 300 (500 – 200)

and the common SP = Rs. 240 = (200 × 1.2 = 300 × 0.8)

So the loss = CP – SP

$$= 500 - 2 \times 240 = \text{Rs. } 20$$

(2) When the selling price of 'm' articles is same as the cost price of 'n' similar articles.

EXAMPLE 16 *If the cost price of 15 apples is same as the selling price of 20 apples. What is the gain or loss per cent?*

SOLUTION CP of 15 apples = SP of 20 apples

$$\Rightarrow \quad \text{CP} \times 15 = \text{SP} \times 20$$

$$\Rightarrow \quad \frac{\text{CP}}{\text{SP}} = \frac{4}{3}$$

So you can see that CP > SP, therefore, there will be loss.

Now consider CP = 4, then SP = 3

$$\therefore \quad \text{loss} = 1$$

$$\text{loss (\%)} = \frac{\text{loss}}{\text{CP}} \times 100$$

$$= \frac{1}{4} \times 100 = 25\%$$

$$\therefore \quad \text{loss} = 25\%$$

EXAMPLE 17 *If the selling price of 10 CDs is the same as the cost price of 12 CDs. What is the profit or loss per cent?*

SOLUTION SP of 10 CDs = CP of 12 CDs

$$\Rightarrow \quad \text{SP} \times 10 = \text{CP} \times 12$$

$$\Rightarrow \quad \frac{\text{SP}}{\text{CP}} = \frac{12}{10} = \frac{6}{5}$$

⇒ SP > CP, therefore there will be a profit

$$\text{Profit (\%)} = \frac{(\text{SP} - \text{CP})}{\text{CP}} \times 100$$

$$= \frac{(6-5)}{5} \times 100 = 20\% \text{ (profit)}$$

(3) When a person recovers the cost price of 'm' articles by selling 'n' articles ($n < m$), then

$$\text{Profit (\%)} = \frac{\text{goods left}}{\text{goods sold}} \times 100$$

$$= \frac{m-n}{n} \times 100$$

Scanned by CamScanner

yoursmahboob.wordpress.com

In this case money is equated in terms of no. of (or amount) articles.

For your convenience always assume the CP of an article as Re 1. (or Rs. 100)

EXAMPLE 18. *A dealer by selling 12 oranges gets the cost price of 15 oranges. What is the percentage profit?*

SOLUTION $\text{Profit (\%)} = \frac{\text{goods left}}{\text{goods sold}} \times 100 = \frac{15-12}{12} \times 100 = 25\%$

Alternatively : Suppose CP of one orange = Re. 1

then CP of 12 oranges = Rs. 12

and SP of 12 oranges = CP of 15 oranges = Rs. 15

$\therefore$ $\text{profit} = \frac{15-12}{12} \times 100 = 25\%$

EXAMPLE 19. *By selling 8 bananas, a fruit seller gains the selling price of 1 banana. Calculate his gain per cent.*

SOLUTION Let the SP of one banana = Re. 1

then SP of 8 bananas = Rs. 8

and profit = Re. 1

$\therefore$ CP = 8 − 1 = Rs. 7

$\therefore$ $\text{profit \%} = \frac{1}{7} \times 100 = 14\frac{2}{7}\%$

EXAMPLE 20. *By selling 18 chocolates, a vendor loses the selling price of 2 chocolates. Find his loss per cent.*

SOLUTION Let the SP of 1 chocolate = Re. 1

$\therefore$ SP of 18 chocolate = Rs. 18

and loss = Rs. 2

$\therefore$ CP = SP + loss

= 18 + 2 = Rs. 20

$\therefore$ $\text{Percentage loss} = \frac{\text{loss}}{\text{CP}} \times 100$

$= \frac{2}{20} \times 100 = 10\%$

EXAMPLE 21. *A trader sell all his articles at the cost price but gives 10% less amount as he should give. What is his percentage profit?*

SOLUTION $\text{Profit (\%)} = \frac{\text{goods left}}{\text{goods sold}} \times 100$

$= \frac{10}{90} \times 100 = 11\frac{1}{9}\%$

Since if we assume that the CP of 1 article is Re. 1.

Now since he gives only 90% article instead of 100% and save 10% article. So his profit will be the equal to the remaining articles (over the sold articles).

It means when he sells the articles (actually) worth Rs. 90 then he gains by articles worth Rs. 10.

Hence profit % $= \frac{10}{90} \times 100 = 11\frac{1}{9}\%$

(The selling price $= \frac{100}{90} = \frac{10}{9}$ = Rs. 1.11

EXAMPLE 22. *A trader by means of his false balance defrauds to the extent of 10% in buying goods and also defrauds to 10% in selling. Find his gain per cent.*

SOLUTION Let the actual CP of an article be Re. 1, then the effective CP $= \frac{100}{110} = \frac{10}{11}$

(Since he purchases 110 articles by paying Rs. 100)

$\text{again SP} = \frac{100}{90} = \frac{10}{9}$

(Since he sells only 90 articles charging the CP of 100 articles)

$\therefore$ $\text{Gain \%} = \frac{\text{SP} - \text{CP}}{\text{CP}} \times 100 = \frac{\frac{10}{9} - \frac{10}{11}}{\frac{10}{11}} \times 100$

$= \frac{20}{99} \times \frac{11}{10} \times 100$

$= \frac{200}{9} = 22\frac{2}{9}\%$

INTRODUCTORY EXERCISE-6.2

1. The cost price of a scooter is Rs. 20,000 and the profit percent is 12%. What is the selling price?
   (a) 2400 (b) 22040
   (c) 2600 (d) 22400
2. The SP of an article is Rs. 3200 and the profit per cent is $33\frac{1}{3}\%$. Find the cost price.
   (a) Rs. 20000 (b) Rs. 2000
   (c) Rs. 2400 (d) Rs. 3000
3. The CP of an article is 5/6th of the SP. What is the percentage profit or loss?
   (a) 20% loss (b) 16.66% profit
   (c) 16.66% loss (d) 20% profit.
4. The MP of a camera is 3/2 of the CP and SP is 9/10 of MP. Find the percentage profit or loss.
   (a) 25% profit (b) 35% profit
   (c) 33.33% loss (d) none of these
5. The MP of an article is 30% higher than its CP and 20% discount is allowed on this article then the profit percentage :
   (a) 10% (b) 14%
   (c) 4% (d) 26%
6. An article is sold for Rs. 1980 at 10% profit. What is the cost price?
   (a) Rs. 198 (b) Rs. 1800
   (c) Rs. 1900 (d) Rs. 1600

Scanned by CamScanner

yoursmahboob.wordpress.com

7. On selling an article for Rs. 576 a trader loses 4%. In order to gain $4\frac{1}{6}$%, he must sell that article for :
(a) Rs. 636 (b) Rs. 676
(c) Rs. 625 (d) can't be determined

8. The per cent profit made when an article is sold for Rs. 56 is thrice as when it is sold for Rs. 42. The cost price of the article is :
(a) Rs. 48 (b) Rs. 49
(c) Rs. 50 (d) Rs. 35

9. A shopkeeper uses a weight of 460 g instead of 500 g and sells the articles at the cost price. What is the profit percentage?
(a) 40% (b) 23%
(c) $8\frac{16}{23}$% (d) 20%

10. A trader uses a weight of 920 g instead of 1 kg and sells the articles at the marked price which is 15% above the cost price. Find the profit percentage.
(a) 20% (b) 23%
(c) 25% (d) can't be determined

11. If a gift pack is sold at a gain of 6% instead of at a loss of 6%, then the seller gets Rs. 6 more. The cost price of the article is :
(a) Rs. 60 (b) Rs. 66
(c) Rs. 50 (d) Rs. 36

12. A man sells a bicycle at a gain of 10%. If he had bought it at 10% less and sold it for Rs. 132 less, he would have still gained 10%. The cost price of the article is :
(a) Rs. 1000 (b) Rs. 1200
(c) Rs. 1500 (d) Rs. 1320

13. An item costing Rs. 600 is being sold at 20% loss. If the price is further reduced by 12.5%, the selling price will be :
(a) Rs. 400 (b) Rs. 380
(c) Rs. 420 (d) Rs. 525

14. While selling an electric fan, a dealer gives a discount of 5%. If he gives a discount of 8%, he earns Rs. 36 less as profit. The marked price of the fan is :
(a) Rs. 1000 (b) Rs. 1200
(c) Rs. 800 (d) none of these

15. If a commission of 10% is given on the marked price of a book, the publisher gains 20%. If the commission is increased to 15%, the gain of publisher is :
(a) 13.33% (b) 15%
(c) 18% (d) data insufficient

16. A retailer buys a cellphone at a discount of 15% and sells it for Rs. 5865. Thus, he makes a profit of 15%. The discount is :
(a) Rs. 200 (b) Rs. 850
(c) Rs. 750 (d) Rs. 900

17. At what per cent above the cost price must an articles be marked so as to gain 17% after allowing a discount of 10%?
(a) 34% (b) 70%
(c) 30% (d) 27%

18. A merchant marks his goods at Rs. 900 and allows a discount of 25%. If he still gain 12.5%, then the cost price of the article is :
(a) Rs. 500 (b) Rs. 600
(c) Rs. 720 (d) can't be determined

19. A vendor buys oranges @ Rs. 2 for 3 oranges and sells them at a rupee each. To make a profit of Rs. 10, he must sell :
(a) 10 oranges (b) 20 oranges
(c) 30 oranges (d) 40 oranges

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. Abhishek and Bhanu both are dealers of KML scooters. The price of a KML Scooter is Rs. 28,000. Abhishek gives a discount of 10% on whole, while Bhanu gives a discount of 12% on the first Rs. 20,000 and 8% on the rest Rs. 8000. What is the difference between their selling prices?
(a) Rs. 240 (b) Rs. 420
(c) Rs. 640 (d) none of these

2. A trader sells two articles, one at a loss of 10% and another at a profit of 15% but finally there is no loss or gain. If the total sale price of these two articles is Rs. 30,000, find the difference between their cost prices :
(a) Rs. 5000 (b) Rs. 6000
(c) Rs. 7500 (d) none of these

3. A milkman purchases the milk at Rs. x per litre and sells it at Rs. $2x$ per litre still he mixes 2 litres water with every 6 litres of pure milk. What is the profit percentage?
(a) 116% (b) 166.66%
(c) 60% (d) 100%

4. 60% goods are sold at 5% loss while rest are sold at 10% profit. If there is a total profit of Rs. 100, then the worth of goods sold is :
(a) Rs. 6000 (b) Rs. 5000
(c) Rs. 10000 (d) none of these

5. A retailer bought 20 kg tea at a discount of 10%. Besides 1 kg tea was freely offered to him by the wholesaler at the purchase of 20 kg tea. Now he sells all the tea at the marked price to a customer. What is profit percentage of retailer?
(a) 30% (b) 12%
(c) 16.66% (d) none of these

6. Two articles are sold at the same price. One at a profit of 75% and another one at a loss of 30%. What is the overall profit or loss?
(a) 22.5% profit (b) 57.5 profit
(c) $13\frac{2}{7}$% loss (d) none of these

7. What is percentage profit in selling an article at a discount of 20% which was earlier being sold at a 40% profit?
(a) 20% (b) 14%
(c) 28% (d) 12%

8. A man bought 18 oranges for a rupee and sold them at 12 oranges for a rupee. What is the profit percentage?
(a) 33.33% (b) 50%
(c) 66.66% (d) none of these

9. A dealer buys a product at Rs. 1920, He sells at a discount of 20% still he gets the profit of 20%. What is the selling price of that product?
(a) Rs. 2304 (b) Rs. 1536
(c) Rs. 2200 (d) it is not possible

10. Tinkawala purchased the articles for Rs. 123684. He sold 60% of those at a profit of 16.66% and rest at a loss. Find the loss percentage on the remaining if the overall loss is 14%?
(a) 20% (b) 30%
(c) 60% (d) 66.66%

11. What should be the minimum markup percentage such that after giving a discount of $66\frac{2}{3}$%, there will not be a loss?
(a) 200% (b) 133.33%
(c) 100% (d) 150%

12. The ratio of cost price and marked price of an article is 2 : 3 and ratio of percentage profit and percentage discount is 3 : 2. What is the discount percentage?
(a) 16.66% (b) 20%
(c) 25% (d) 33.33%

13. A dealer gives as much discount (in per cent) as the markup (in per cent) above the cost price. What is the profit or loss per cent?
(a) 10% (b) 1%
(c) 4% (d) can't be determined

14. In the above problem, what is the markup percentage when there is a loss in percentage be half of the percentage markup?
(a) 20% (b) 40%
(c) can't be determined (d) none of these

15. A shopkeeper sold 12 cameras at a profit of 20% and 8 cameras at a profit of 10%. If he had sold all the 20 cameras at a profit of 15%, then his profit would have been reduced by Rs. 36. What is the cost price of each camera?
(a) 100 (b) 150
(c) 180 (d) 220

16. Mr. Mittal purchased a car for Rs. 3,00,000 and a bike for his son for Rs. 1,00,000. He sold the car at a profit of 10% and bike at a loss of 20%. What is the net gain or loss?
(a) 2% gain (b) 1.5% loss
(c) 2.5% loss (d) 2.5% gain

17. A trader sells 20 kg of sugar at Rs. 400. A customer asks 20% discount and he agrees to it but instead of 1 kg he gives 4% less sugar. What is the effective discount that the customer gets?
(a) 16% (b) 16.66%
(c) 15.5% (d) 19.6%

18. The profit percentage on the three articles A, B and C is 10%, 20% and 25% and the ratio of the cost price is 1 : 2 : 4. Also the ratio of number of articles sold of A, B and C is 2 : 5 : 2, then the overall profit percentage is :
(a) 18.5% (b) 21%
(c) 75% (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

19. The marked price of an article is increased by 25% and the selling price is increased by 16.66%, then the amount of profit doubles. If the original marked price be Rs. 400 which is greater than the corresponding cost price by 33.33%, what is the increased selling price?
(a) 240 (b) 360
(c) 420 (d) 600

20. A shopkeeper calculated his profit per cent on the selling price which comes out to be 30%. If it had been calculated as usual on the cost price then what is the required percentage profit?
(a) $42\frac{6}{7}\%$ (b) $4\frac{7}{27}\%$
(c) $7\frac{6}{42}\%$ (d) none of these

21. An item was sold after giving two successive discount of 20% and 10% respectively. If the item was sold for Rs. 468. The marked price of that item is :
(a) Rs. 600 (b) Rs. 500
(c) Rs. 575 (d) Rs. 650

22. The cost price of an article 'A' is Rs. 160 and selling price of another article 'B' is Rs. 240. If the selling price of *A* will be equal to the cost price of *B*, then the profit after selling *A* is 20%. What is the profit on 'B'?
(a) 16.66% (b) 50%
(c) 25% (d) none of these

23. A single discount equivalent to three successive discounts of 5%, 10%, 20% is :
(a) 68.4% (b) 35%
(c) 31.6% (d) 32%

24. Ragini purchases oranges at Rs. 10 per dozen and sells them at Rs. 12 for every 10 oranges. What is the profit percentage?
(a) 40% (b) 44%
(c) 60% (d) 48%

25. A trader uses a weighing balance that shows 1250 g for a kilogram. He further marks-up his cost price by 20%. What is the profit percentage?
(a) 5% (b) 45%
(c) 50% (d) 30%

26. On selling an article for Rs. 240, a trader loses 4%. In order to gain 10% he must sell that article for :
(a) Rs. 275 (b) Rs. 340
(c) Rs. 320 (d) Rs. 264

27. A merchant marks his goods at Rs. 300 and allows a discount of 25%. If he still gains 12.5%, then the cost price of article is :
(a) Rs. 220 (b) Rs. 200
(c) Rs. 240 (d) Rs. 260

28. An item costing Rs. 200 is being sold at 10% loss. If the price is further reduces by 5%, the selling price will be :
(a) Rs. 170 (b) Rs. 171
(c) Rs. 180 (d) Rs. 181

29. A person sold two cows each for Rs. 9900. If he gained 10% on one and lost 20% on the other, then which of the following is true?
(a) He gained Rs. 200
(b) He lost Rs. 200
(c) He neither gained nor lost
(d) None of the above

30. Two third of a consignment was sold at a profit of 5% and the remainder at a loss of 2%. If the total profit was Rs. 400, the value of the consignment (in rupees) was :
(a) 15000 (b) 20000
(c) 10000 (d) 12000

31. A fruit seller declares that he sells fruits at the cost price. However, he uses a weight of 450 g instead of 500 g. His percentage profit is :
(a) 10% (b) $11\frac{1}{9}\%$
(c) 12% (d) $12\frac{2}{9}\%$

32. A person loses Rs. 20 by selling some bananas at the rate of Rs. 3 per banana and gains Rs. 30, if he sells them at Rs. 3.25 per banana. The number of bananas sold by him :
(a) 100 (b) 200
(c) 120 (d) 2400

33. Due to an increase of 30% in the price of eggs, 3 eggs less are available for Rs. 9.10. The present rate per egg is :
(a) 91 paise (b) 78 paise
(c) 48 paise (d) 84 paise

34. By selling 12 apples for a rupee, a man loses 20%. How many for a rupee should he sell to gain 20%?
(a) 8 (b) 10
(c) 15 (d) 16

35. A dealer buys a washing machine, listed at Rs. 10000 and gets 10% and 20% successive discounts. He spends 10% of his CP on transport. At what price (in rupees) should he sell the washing machine to earn a profit of 10%?
(a) 8722 (b) 7892
(c) 8712 (d) 8840

36. 6% more is gained by selling a coat for Rs. 1425 than by selling it for Rs. 1353. The cost price of the coat is :
(a) Rs. 1000 (b) Rs. 1250
(c) Rs. 1500 (d) Rs. 1200

37. By selling a wrist watch at Rs. 405 the shopkeeper incurs a loss of 10%. What is the gain or loss percentage if he sells the same watch at Rs. 465?
(a) profit of 10% (b) loss of 6%
(c) profit of 3.33% (d) no profit no loss

38. Titan sells a wrist watch to a wholesaler making a profit of 10%. The wholeseler, in turn, sells it to the retailer making a profit of 10%. A customer purchases it by paying Rs. 990. Thus the profit of retailer is $2\frac{3}{11}\%$. What is the cost incurred by the Titan to produce it?
(a) 768 (b) 750
(c) 800 (d) 820

39. Pepsi and Coke, there are two companies, selling the packs of cold-drinks. For the same selling price Pepsi gives two successive discounts of 10% and 25%. While Coke sells it by giving two successive discounts of 15% and 20%. What is the ratio of their marked price?
(a) 143 : 144 (b) 19 : 11
(c) 136 : 135 (d) 73 : 77

40. When a shopkeeper reduces the selling price from 1080 to 1026 its loss increases by 4 percentage point. What is the selling price of this same article when it fetches a profit of 4%?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) Rs. 1392 (b) Rs. 1404
(c) Rs. 1450 (d) Rs. 1350

41. The difference between CP and SP of a table fan is Rs. 175 when it gives the profit of 14%. What is the selling price of that fan?
(a) 1225 (b) 1450
(c) 1425 (d) 1275

42. A company instead of raising the mark-up by 20% discounted the cost price by 20% while stiching the price tag on its product. Further the company offers a discount of 6.25% to its customer. In this process company incurs a loss of Rs. 37.5 on a single article. What is the selling price of that article?
(a) 417.5 (b) 112.5
(c) 365.5 (d) none of these

43. When an article is sold for Rs. 703 loss incurred is 25% less than the profit earned on selling it at Rs. 836. What is the selling price of the article when it earns a profit of 20%?
(a) 912 (b) 1576
(c) 1532 (d) 1092

44. Arun bought toffees at 6 for a rupee. How many for a rupee he should sell to gain 20%?
(a) 3 (b) 4
(c) 5 (d) can't be determined

45. A scientific calculator is available at Universal Shoppe in Hazratganz at 20% discount and the same is available at only 15% discount at Universal Shoppe Bhootnath Market. Ms. Agrawal has just sufficient amount of Rs. 800 to purchase it at Universal Shoppe Hazratganz. What is the amount that Ms. Agrawal has less than the required amount to purchase it at Universal Shoppe Bhootnath?
(a) Rs. 70 (b) Rs. 50
(c) Rs. 100 (d) data insufficient

46. A balance of a trader weighs 10% less than it should be. Still the trader marks-up his goods to get the overall profit of 20%. What is the markup on the cost price?
(a) 40% (b) 8%
(c) 25% (d) 16.66%

47. ITC sells one product at a profit of 20% another at a loss of 20% at the same selling price. What is the loss incurred by ITC?
(a) 1% (b) 2%
(c) 4% (d) 0%

48. In the previous question, if SP of each article be Rs. 200, what is the amount of loss?
(a) Rs. 10 (b) Rs. 16
(c) Rs. 16.66 (d) none of these

49. The cost price of 19 articles is same as the selling price of 29 articles. What is the loss %?
(a) 35% (b) 34.48%
(c) 52.63% (d) none of these

50. The selling price of 13 articles is same as the cost price of 23 articles. What is the profit percentage?
(a) 43.47% (b) 74.83%
(c) 78% (d) 76.92%

51. A trader can procure 34 pencils by selling 28 pencils. What is the ratio of cost price to the selling price of a pencil?
(a) 2 : 3 (b) 14 : 17
(c) 9 : 7 (d) 4 : 7

52. At style cloth emporium the shopkeeper measures 20% less for every metre of cloth also he marks-up goods by 20%. What is the profit percentage?
(a) 50% (b) 80%
(c) 75% (d) none of these

53. A bookseller procures 40 books for Rs. 3200 and sells them at a profit equal to the selling price of 8 books. What is the selling price of one dozen books, if the price of each book is same?
(a) 720 (b) 960
(c) 1200 (d) 1440

54. The profit percentage of A and B is same on selling the articles at Rs. 1800 each but A calculates his profit on the selling price while B calculates it correctly on the cost price which is equal to 20%. What is the difference in their profits?
(a) Rs. 360 (b) Rs. 60
(c) Rs. 540 (d) Rs. 450

55. Each of A and B sold their article at Rs. 1818 but A incurred a loss of 10% while B gained by 1%. What is the ratio of cost price of the articles of A to that of B?
(a) 101 : 90 (b) 85 : 89
(c) 81 : 75 (d) none of these

56. A trader sold an article at a loss of 5% but when he increased the selling price by Rs. 65 he gained 3.33% on the cost price. If he sells the same article at Rs. 936, what is the profit percentage?
(a) 15% (b) 16.66%
(c) 20% (d) data insufficient

57. Even after a discount of q% on marked price a trader gains by p%. What is the markup percentage over the cost price?
(a) $\frac{p+q}{(q-p)} \times 100$ (b) $\frac{p+q}{(100-p)} \times 100$
(c) $\frac{p+q}{(100-q)} \times 100$ (d) not possible

58. A milkman mixes 10% water in pure milk but he is not content with it so he again mixes 10% more water in the previous mixture. What is the profit percentage of milkman if he sells it at cost price :
(a) 11.11% (b) 20%
(c) 21% (d) 12.1%

59. A person sold an electronic watch at Rs. 96 in such a way that his percentage profit is same as the cost price of the watch. If he sells it at twice the percentage profit of its previous percentage profit then the new selling price will be :
(a) Rs. 132 (b) Rs. 150
(c) Rs. 192 (d) Rs. 180

60. A trader mixes 25% kerosene to his petrol and then he sells the whole mixture at the price of petrol. If the cost price of kerosene be 50% of the cost price of petrol, what is the net profit percentage?
(a) $11\frac{1}{9}\%$ (b) $12\frac{1}{9}\%$
(c) $9\frac{1}{11}\%$ (d) 20%

Scanned by CamScanner

yoursmahboob.wordpress.com

61. A retailer cheats both to his whole-seller and his customer by 10% by his faulty balance i.e., he actually weighs 10% more while purchasing from wholesaler and weighs 10% less while selling to his customer. What is his net profit percentage, when he sells at CP?
(a) $22\frac{2}{11}\%$ (b) $22\frac{2}{9}\%$
(c) 20% (d) 21%

62. A trader procures his goods from a wholesaler, whose balance reads 1200 g for 1000 g. The trader sells all the procured goods to a customer after marking up the goods at 20% above the cost price. What is his overall percentage profit or loss in the whole transaction?
(a) 38% profit
(b) 50% profit
(c) no profit no loss
(d) none of the above

63. A person wants to reduce the trade tax so he calculates his profit on the sale price instead of on the cost price. In this way by selling a article for Rs. 280 he calculates his profit as $14\frac{2}{7}\%$. What is his actual profit percentage?
(a) 20% (b) 16.66%
(c) 25% (d) data insufficient

64. A vendor sells his articles at a certain profit percentage. If he sells his articles at 1/3 of his actual selling price, then he incurs a loss of 40%. What is his actual profit percentage?
(a) 72% (b) 120%
(c) 80% (d) none of these

65. A retailer increases the selling price by 25% due to which his profit percentage increases from 20% to 25%. What is the percentage increase in cost price?
(a) 20% (b) 30%
(c) 25% (d) 50%

66. Abhinav saves Rs. 25 by getting 6.66% discount on a textbook. What is the amount of money (in Rs.) paid by him?
(a) 450 (b) 350
(c) 225 (d) 375

67. At kul-kul petrol pump the operator gives 5% less petrol but he sells it at the cost price. What is his profit in this way?
(a) 5% (b) 5.6%
(c) 5.26% (d) 4.78%

68. Due to reduction of 25% in price of oranges a customer can purchase 4 oranges more for Rs. 16. What is original price of an orange?
(a) Re 1 (b) Rs. 1.33
(c) Rs. 1.5 (d) Rs. 1.6

69. A reduction of 20% in the price of sugar enables a housewife to purchase 6 kg more for Rs. 240. What is the original price per kg of sugar?
(a) Rs. 10 per kg (b) Rs. 8 perkg
(c) Rs. 6 per kg (d) Rs. 5 per kg

70. A wholesaler sells toys at a profit of 20% to a retailer and retailer sells these toys to its customer at a profit of 25%. What is the profit percentage of the retailer?
(a) 5% (b) 80%
(c) 20% (d) 25%

LEVEL 2

1. An automobile agency launched a scheme that if a customer purchases two Jabaaj Discover bikes, one extra Jabaaj Discover will be free and if he purchases 3 Jabaaj Pulser he will get one extra Jabaaj Pulser free. If the cost price of 3 Jabaaj Discover and 4 Jabaaj Pulser be Rs. 67500 and Rs. 232500 respectively. If a customer purchases 2 bikes of Jabaaj Discover and 3 bikes of Jabaaj Pulser as per scheme he availed 1 bike free of each category, then at what price these bikes should be sold so that the agency can get overall profit of 17.5% :
(a) 235250 (b) 352500
(c) 368000 (d) 268000

2. Rahul went to purchase a Nokia mobile handset, the shopkeeper told him to pay 20% tax if he asked the bill. Rahul manages to get the discount of 5% on the actual saleprice of the mobile and he paid the shopkeeper Rs. 3325 without tax. Besides he manages to avoid to pay 20% tax on the already discounted price, what is the amount of discount that he has gottten?
(a) 750 (b) 375
(c) 875 (d) 525

3. When a bicycle manufacturer reduced its selling price by 50%, the number of bicycles sold radically increased by 600%. Initially the manufacturer was getting only 140% profit. What is the percentage increase of his profit?
(a) 10% (b) 14%
(c) 0% (d) can't be determined

4. A trader marks his goods such that he can make 32% profit after giving 12% discount. However a customer availed 20% discount instead of 12%. What is the new profit percentage of trader?
(a) 20% (b) 44%
(c) 30% (d) 28.8%

5. A retailer bought 3850 Linc pens and 1848 Cello pens at the same price. He sells Linc pens in such a way that he can buy 650 Linc pens with the sale price of 481 Linc pens. Again he can buy only 408 Cello pens with the sale price of 629 pens. What is the overall percentage of profit of the retailer?
(a) 4.8% (b) 9.6%
(c) 13% (d) none of these

6. The ratio of selling price of 3 articles *A*, *B* and *C* is 8 : 9 : 5and the ratio of percentage profit is 8 : 7 : 14 respectively. If the profit percentage of *A* is 14.28% and the cost price of *B* is Rs. 400, what is the overall percentage gain?
(a) 14.28% (b) 14.87%
(c) 16.66% (d) none of these

7. Anna sold his car to Boney at a profit of 20% and Boney sold it to Chakori at a profit of 10%. Chakori sold it to mechanic at a loss of 9.09%. Mechanic spent 10% of his purchasing price and then sold it at a profit of 8.33% to Anna once again. What is the loss of Anna?
(a) 23% (b) 29%
(c) 50% (d) 40%

Scanned by CamScanner

yoursmahboob.wordpress.com

8. In an office the number of employees reduces in the ratio of 3 : 2 and the wages increases in the ratio of 20 : 27. What is the profit percentage of employees over the previous wages?
(a) 10% (b) 9.09%
(c) 11.11% (d) none of these

9. I asked the shopkeeper the price of a wristwatch. I found that I had just the required sum of money. When the shopkeeper allowed me a discount of 25%, I could bought another watch worth Rs. 940 for my younger sister. What is the price which I have paid for my own watch?
(a) Rs. 2700 (b) Rs. 1800
(c) Rs. 2820 (d) Rs. 3760

10. *A* and *B* are two partners and they have invested Rs. 54,000 and Rs. 90,000 in a business. After one year *A* recieved Rs. 1800 as his share of profit out of total profit of Rs. 3600 including his certain commission on total profit since he is a working partner and rest profit is received by *B*. What is the commission of *A* as a percentage of the total profit?
(a) 20% (b) 10%
(c) 5% (d) 25%

11. A trader sells goods to a customer at a profit of *k*% over the cost price, besides it he cheats his customer by giving 880 g only instead of 1 kg. Thus his overall profit percentage is 25%. Find the value of *k*?
(a) 8.33% (b) 8.25%
(c) 10% (d) 12.5%

12. A trader sells two brands of petrol; one is Extra Premium (EP) and other one is 'Speed' (SP). He mixes 12 litres of EP with 3 litres of speed and by selling this mixture at the price of EP he gets the profit of 9.09%. If the price of Extra Premium be Rs. 48 per litre, then the price of Speed (SP) is :
(a) Rs. 38 per litre (b) Rs. 42 per litre
(c) Rs. 28 per litre (d) none of these

13. *A*, *B* and *C* invest in the ratio of 3 : 4 : 5. The percentage of return on their investments are in the ratio of 6 : 5 : 4. Find the total earnings, if *B* earns Rs. 250 more than *A* :
(a) Rs. 6000 (b) Rs. 7250
(c) Rs. 5000 (d) none of these

14. Ajay bought a motor cycle for Rs. 50,000. 2 years later he sold it to Bijoy at 10% less of the cost price. Bijoy spend 5% of the purchasing price on its maintenance. Later Bijoy displayed the sale price of his motorcycle Rs. 50,000. Chetan wanted to purchase it at 15% discount but Bijoy gave him two successive discounts of 10% and 5% instead of 15% in one time. What is the actual discount availed by Chetan?
(a) 15% (b) 15.5%
(c) 14.5% (d) none of these

15. Kamal bought a house in Sushant city, whose sale price was Rs. 8 lakh. He availed 20% discount as an early bird offer and then 10% discount due to cash payment. After that he spent 10% of the cost price in interior decoration and lawn of the house. At what price should he sell the house to earn a profit of 25%?
(a) Rs. 9 lakh (b) Rs. 7.99 lakh
(c) Rs. 7.92 lakh (d) none of these

16. I wanted to purchase 10 chairs for the class room whose cost was Rs. 200 each. The trader offered me a discount if I were to purchase a set of 12 chairs. So I calculated that if I assume the normal price of 10 chairs then we can purchase 2 extra chairs which cost me only Rs. 80 each of two chairs at the cost price of 12 chairs after discount. What is the percentage discount?
(a) 6% (b) 8%
(c) 12% (d) 10%

17. The cost of servicing of a Maruti car at Maruti care Pvt. Ltd. is Rs. 400. Manager of service centre told me that for the second service within a year a customer can avail a 10% discount and further for third and fourth servicing he can avail 10% discount of the previous amount paid, within a year. Further if a customer gets more than 4 services within a year he has to pay just 60% of the servicing charges on these services. A customer availed 5 services from the same servicing station, what is the total percentage discount fetched by the customer?
(a) 19.42% (b) 18.5%
(c) 17.6% (d) 26%

18. The cost price of an article is *C* and the selling price of the same article is *S*, where *Z* is the profit or loss percentage. If the cost price and selling price both are increased by same amount then which of the following is true :
(a) *Z* increases (b) *Z* decreases
(c) remains constant (d) none of these

19. Cost price of 12 oranges is equal to the selling price of 9 oranges and the discount on 10 oranges is equal to the profit on 5 oranges. What is the percentage point difference between the profit percentage and discount percentage?
(a) 20 (b) 22.22
(c) 16.66 (d) 15

20. A car mechanic purchased four old cars for Rs. 1 lakh. He spent total 2 lakh in the maintenance and repairing of these four cars. What is the average sale price of the rest three cars to get 50% total profit if he has already sold one of the four cars at Rs. 1.2 lakh?
(a) 1.5 lakh (b) 1.1 lakh
(c) 1.2 lakh (d) 1.65 lakh

21. The cost of setting up a magazine is Rs. 2800. The cost of paper and ink etc is Rs. 80 per 100 copies and printing cost is Rs. 160 per 100 copies. In the last month 2000 copies were printed but only 1500 copies could be sold at Rs. 5 each. Total 25% profit on the sale price was realized. There is one more resource of income from the magazine which is advertising. What sum of money was obtained from the advertising in magazine?
(a) Rs. 1750 (b) Rs. 2350
(c) Rs. 1150 (d) Rs. 1975

22. DSNL charges a fixed rental of Rs. 350 per month. It allows 200 calls free per month. Each call is charged at Rs. 1.4 when the number of calls exceeds 200 per month and it charges Rs. 1.6 when the number of calls exceeds 400 per month and so on. A customer made 150 calls in February and 250 calls in March. By how much per cent the each call is cheaper in March than each call in February?
(a) 28% (b) 25%
(c) 18.5% (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

23. In the Bargain Bazar everyone purchases with a fair bargaining, so the traders markup the prices too much. A trader marked up an article at Rs. M expected huge profit if it is sold on the marked price. But a customer purchased it at $M/2$ with his fine bargaining skills, so the expected profit of the trader diminished by 66.66%. What is the percentage discount fetched by the customer through bargaining?
(a) 33.33% (b) 50%
(c) 66.66% (d) none of these

24. Tika Chand has a weighing balance in which there is a technical fault. The right pan of his balance measures always 200 g more than its left pan. Tika Chand as usual misutilise this balance in his business. While purchasing the articles he puts goods in the left pan and weight in the right pan while selling he reverse the order *i.e.*, goods in the right pan and weight in the left pan. He uses only 2 kg weight for the measurement and to measure $2n$ kg weight he measures n times by 2-2 kg but he sells goods at cost price. What is his profit percentage?
(a) 20% (b) $22\frac{2}{9}\%$
(c) $18\frac{2}{11}\%$ (d) none of these

25. Akram Miya has two types of grapes. One is the fresh grapes containing 80% water and dry grapes containing 25% water. He sells 20 kg dry grapes, by adding water to the dry grapes, at cost price. What is the total profit percentage when after adding water the weight of 20 kg dry grapes increased in the proportion of water in fresh grapes?
(a) 275% (b) 200%
(c) 80% (d) 125%

26. Pankaj and Sushil invested some amount of money in the ratio of 3 : 5 for the same period in a business. They decided that at the end of year 20% profit was to be given to AIDS Control Society of India as a donation. Out of the remaining, 75% was to be reinvested and the rest of the profit was to be divided as interest on their capitals. If the difference in their shares is Rs. 1200. Find the total profit?
(a) Rs. 18000 (b) Rs. 24000
(c) Rs. 20000 (d) none of these

27. Jagran group launched a new magazine in January 2004. The group printed 10000 copies initially for Rs. 50000. It distributed 20% of its stock freely as specimen copy and 25% of the rest magazines are sold at 25% discount and rest at 16.66% discount whose printing price was Rs. 12 per copy. What is the overall gain or loss in the first month's issue of magazine, if the magazine could not realize the income from advertisements or other resources?
(a) 56% profit (b) 27% loss
(c) 16.66% profit (d) 38% profit

28. Teenagers shoe company sells the shoes whose prices *i.e.*, cost prices and selling prices are the multiples of either 13, 14, 15, 16, 17, 18 or 19, starting from Rs. 399 to Rs. 699 (i.e., $399 \le CP/SP \le 699$). What can be the maximum profit of the company?
(a) Rs. 292 (b) RS. 398
(c) Rs. 298 (d) Rs. 300

29. Jhun Jhunwala makes 1000 toys and incurs a cost of Rs. 1.2 for each toy. He marks-up the price in such a way that if he sells only 70% of the manufactured toys he will realize 16.66% overall profit. He sells only 750 articles at the marked price since rest of the toys are found to be defective so can't be sold. What is the net profit or loss of Jhun Jhunwala?
(a) 14.44% loss (b) 25% profit
(c) 33.33% profit (d) none of these

30. Anupam sells a painting to Bhargava at 4/5th the rate of profit at which Bhargava sells it to Chaudhary. Further Chaudhary sells it to Dara Singh at half the rate of profit at which Anupam sold it to Bhargava. If Chaudhary earns a profit of 10% by selling it to Dara Singh for Rs. 2805. What is the cost price of painting for Bhargava?
(a) 1896 (b) 2040
(c) 1680 (d) 2000

31. A dishonest retailer cheats his wholesaler and customer both. He purchases 19% more from the wholesaler and sells 15% less while selling to its customer. What is profit percentage by selling the goods at cost price?
(a) 36.78% (b) 34%
(c) 40% (d) 36.85%

32. Rotomac produces very fine quality of writing pens. Company knows that on an average 10% of the produced pens are always defective so are rejected before packing. Company promises to deliver 7200 pens to its wholesaler at Rs. 10 each. It estimates the overall profit on all the manufactured pens to be 25%. What is the manufacturing cost of each pen?
(a) Rs. 6 (b) Rs. 7.2
(c) Rs. 5.6 (d) Rs. 8

33. Pratibha printers prepares diaries expecting to earn a profit of 40% by selling on the marked price. But during transportation 8% diaries were got spoiled due to at random rain and 32% could be sold only at 75% of the cost price. Thus the remaining 60% diaries could be sold at the expected price. What is the net profit or loss in the whole consignment?
(a) 6% (b) 10%
(c) 8% (d) can't be determined

34. Radhey Lal markup the prices of sweets by 40% and he sold only 40% of those at this price. He sells half of the rest at $14\frac{2}{7}\%$ discount and rest at 25% discount. What is the net profit of Radhey Lal?
(a) 26.5% (b) 23.5%
(c) 30% (d) 28.6%

35. The price of an article reduces to 576 after two successive discounts. The markup is 80% above the cost price of Rs. 500. What is the new profit percentage if instead of two successive discounts the markup price was further increased successively two times by the same percentage?
(a) 259.2% (b) 59.2%
(c) 159.2% (d) can't be determined

36. A trader marks-up his goods by 80% and gives discount of 25%. Besides it he weighs 10% less amount while selling his goods. What is the net profit of trader?
(a) 50% (b) 35%
(c) 45% (d) 55%

Scanned by CamScanner

yoursmahboob.wordpress.com

37. A dishonest trader marks up his goods by 80% and gives discount of 25%. Besides he gets 20% more amount per kg from wholesaler and sells 10% less per kg to customer. What is the overall profit percentage?
(a) 80% (b) 60%
(c) 70% (d) none of these

38. A dishonest dealer purchases goods at 20% discount of the cost price of Rs x and also cheats his wholesaler by getting 20% extra through false weighing, per kg. Then he marks up his goods by 80% of x, but he gives a discount of 25% besides he cheats his customer by weighing 10% less than the required. What is his overall profit percentage?
(a) 125% (b) 100%
(c) 98.66% (d) 120%

39. Anjuli, Bhoomika and Chawla went to market to purchase the rings whose costs were same. But each ring was available with two successive discounts. Anjuli availed two successive discounts of 5% and 20%. Bhoomika availed two successive discounts 10% and 15% while Chawla availed two successive discounts of 12% and 13%. Who gets the maximum possible discount?
(a) Anjuli (b) Bhoomika
(c) Chawla (d) all of these

40. An egg seller sells his eggs only in the packs of 3 eggs, 6 eggs, 9 eggs, 12 eggs etc., but the rate is not necessarily uniform. One day Raju (which is not the same egg seller) purchased at the rate of 3 eggs for a rupee and the next hour he purchased equal number of eggs at the rate of 6 eggs for a rupee. Next day he sold all the eggs at the rate of 9 eggs for Rs. 2. What is his percentage profit or loss?
(a) 10% loss (b) 11.11% loss
(c) 3% loss (d) 2.5% profit

41. Virendra and Gurindra purchased one camera each at the same prices. Later on Amrendra purchased both cameras at equal prices from Virendra and Gurindra. But the profit percentage of Virendra was P while the same of Gurindra was Q since Gurindra calculated his profit on the selling price. Thus $Q = 41\frac{2}{3}\%$ of P. If Amrendra sells one of the camera to Dholakiya at $P\%$ profit then what is the cost price for Dholakiya, while Amrendra purchased each of the camera at Rs. 240?
(a) Rs. 676 (b) Rs. 500
(c) Rs. 576 (d) none of these

42. A merchant earns 25% profit in general. Once his 25% consignment was abducted forever by some goondas. Trying to compensate his loss he sold the rest amount by increasing his selling price by 20%. What is the new percentage profit or loss?
(a) 10% loss (b) 12.5% loss
(c) 12.5% profit (d) 11.11% loss

43. A milkman purchases 10 litres of milk at Rs. 7 per litre and forms a mixture by adding freely available water which constitutes 16.66% of the mixture. Later on he replaced the mixture by some freely available water and thus the ratio of milk is to water is 2 : 1. He then sold the new mixture at cost price of milk and replaced amount of mixture at twice the cost of milk then what is the profit percentage?
(a) 68% (b) 34%
(c) 40% (d) none of these

44. Profit on selling 10 candles equals selling price of 3 bulbs. While loss on selling 10 bulbs equals selling price of 4 candles. Also profit percentage equals to the loss percentage and cost of a candle is half of the cost of a bulb. What is the ratio of selling price of candle to the selling price of a bulb?
(a) 5 : 4 (b) 3 : 2
(c) 4 : 5 (d) 3 : 4

45. Cost price of two motorcycles is same. One is sold at a profit of 15% and the other for Rs. 4800 more than the first. If the net profit is 20%. Find the cost price of each motorcycle :
(a) Rs. 48000 (b) Rs. 52000
(c) Rs. 36000 (d) Rs. 42500

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-6.1

1. Rs. 180 and Rs. 225 **2.** Rs. 9000 **3.** Rs. 345 **4.** Rs. $153\frac{1}{3}$ per hundred **5.** Rs. 15300, Rs. 17850, gain = $\frac{S}{11}$ %

INTRODUCTORY EXERCISE-6.2

1 (d)	2. (c)	3. (d)	4. (b)	5. (c)	6. (b)	7. (c)	8. (d)	9. (c)	10. (c)
11. (c)	12. (b)	13. (c)	14. (b)	15. (a)	16. (d)	17. (c)	18. (b)	19. (c)	

LEVEL-1

1 (a)	2. (b)	3. (b)	4. (c)	5. (c)	6. (d)	7. (d)	8. (b)	9. (a)	10. (c)
11. (a)	12. (a)	13. (d)	14. (d)	15. (c)	16. (d)	17. (b)	18. (b)	19. (c)	20. (a)
21. (d)	22. (c)	23. (c)	24. (b)	25. (c)	26. (a)	27. (b)	28. (b)	29. (d)	30. (a)
31. (b)	32. (b)	33. (a)	34. (a)	35. (c)	36. (d)	37. (c)	38. (c)	39. (c)	40. (b)
41. (c)	42. (b)	43. (a)	44. (c)	45. (b)	46. (b)	47. (c)	48. (c)	49. (b)	50. (d)
51. (b)	52. (a)	53. (c)	54. (b)	55. (a)	56. (c)	57. (c)	58. (c)	59. (a)	60. (a)
61. (b)	62. (c)	63. (b)	64. (c)	65. (a)	66. (b)	67. (c)	68. (b)	69. (a)	70. (d)

LEVEL-2

1 (b)	2. (c)	3. (c)	4. (a)	5. (d)	6. (d)	7. (a)	8. (a)	9. (c)	10. (a)
11. (c)	12. (c)	13. (b)	14. (c)	15. (c)	16. (d)	17. (a)	18. (b)	19. (b)	20. (b)
21. (d)	22. (a)	23. (b)	24. (b)	25. (a)	26. (b)	27. (a)	28. (c)	29. (b)	30. (b)
31. (c)	32. (b)	33. (c)	34. (b)	35. (c)	36. (a)	37. (a)	38. (a)	39. (a)	40. (b)
41. (c)	42. (c)	43. (a)	44. (b)	45. (a)					

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1. Abhishek Bhanu

Discount → 2800 2400 + 640 = 3040

The difference in selling price is same as difference in discount which Rs. 240 (= 3040 – 2800)

2. ∵ 10 % x = 15% of y, where $x + y = 30000$

$$\Rightarrow \quad \frac{x}{y} = \frac{3k}{2k}$$

Hence, the difference = k = 6000

3. Let the cost price of 1 litre pure milk be Re. 1, then

$$\left.\begin{matrix} 6 \text{ litres (milk)} \rightarrow \text{CP} = \text{Rs. } 6 \\ 2 \text{ litres (water)} \rightarrow \text{CP} = \text{Rs. } 0 \end{matrix}\right\} \rightarrow \text{CP} = \text{Rs. 6 only.}$$

and 8 litre mixture → SP → 8 × 2 = Rs. 16

$$\text{Profit} = \frac{16-6}{6} \times 100 = \frac{1000}{6} = 166.66\%$$

4. $\left.\begin{matrix} \text{SP of } 60\% \text{goods} = 0.6x \times 0.95 = 0.57x \\ \text{SP of } 40\% \text{goods} = 0.4x \times 1.1 = 0.44x \end{matrix}\right\}$ Total SP = $1.01x$

$$\text{Profit} = 0.01x = 100$$

$$\Rightarrow \quad x = 10000$$

Alternatively: From option (c)

10000

6000 4000

loss = 300 gain = 400

net gain = 400 – 300 = Rs. 100,

Hence, option (c) is correct.

5. Let the MP of 1 kg tea be Re. 1, then CP of 20 kg with discount = 20 × 0.9 = Rs. 18

also 1 kg tea is free. So the retailer gets tea worth Rs. 21 by paying Rs. 18 only.

$$\text{Profit \%} = \frac{\text{goods left}}{\text{goods sold}} \times 100$$

$$= \frac{21-18}{18} \times 100 = 16.66\%$$

(Since the retailer earns Rs. 3 on each Rs. 18)

6. Let the CP of profit yielding article be Rs. 100 then

$$\left.\begin{matrix} & & & & 250 & \text{CP} \\ & & & & \downarrow & \\ 75\%\text{profit} & \left\{\begin{matrix} \text{SP} & 175 & \leftrightarrow & 175 & \text{SP} \\ & \uparrow & & & \\ \text{CP} & 100 & & & \end{matrix}\right. & & & & \end{matrix}\right\} 30\% \text{ loss}$$

Total CP = 350, Total SP = 350

So there is no profit no gain.

Alternatively: $1.75x = 0.7y$

$$\Rightarrow \quad \frac{x}{y} = \frac{2}{5}$$

again $[2 \times 1.75 = 3.5]$

and $[5 \times 0.7 = 3.5]$

Total cost price = 2 + 5 = Rs. 7

Total selling price = 3.5 + 3.5 = Rs. 7

Hence, no loss no gain.

7.

	CP	SP	MP	
Initially	: 100	140	×	(since profit = 40%)
New prices :	100	112	140	
		profit = 12%	discount = 20%	

8. $$\frac{\text{CP}}{\text{SP}} = \frac{2}{3}$$

$$\therefore \quad \text{profit (\%)} = \frac{1}{2} \times 100 = 50\%$$

Alternatively: $$\text{CP} = \frac{100}{18} = 5.55 \text{ paise}$$

$$\text{SP} = \frac{100}{12} = 8.33 \text{ paise}$$

$$\text{Profit} = \frac{8.33 - 5.55}{5.55} \times 100 = 50\%$$

9.

CP	SP	MP
100	120	150
	20% profit	20% discount

But it can be directly solved as SP = 1.2 CP = Rs. 2304

NOTE There is no role of discount.

10. **Note:** There is no role of cost price of article (Rs. 123684)

(Consider) CP → 100

60 40

16.66% of profit + 10 −24 60% loss

70 16

(100 −14) = SP 86

Since, the overall % loss = 14%

Thus option (c) is correct.

Alternatively: $0.6x + k \times 0.4x = 0.86x$

$$\Rightarrow \quad 0.4kx = 0.16x$$

$$\Rightarrow \quad k = 0.4$$

Therefore loss = 1 – 0.4 = 0.6 i.e., 60%

Scanned by CamScanner

yourSmahboob.wordpress.com

11. Go through options



NOTE When there is no loss, CP = SP.

Alternatively: CP = SP, MP



From percentage change graphic :

Decrease	Increase
$\frac{2}{3}\downarrow$	$\frac{2}{3-2}=\frac{2}{1}\uparrow$
$= 66.66\%$	$= 200\%$

So, when CP = 100, markup % = 200, MP = 300

$$\text{Discount} = 66\frac{2}{3}\% = 200,\ \text{SP} = 100 = \text{CP}$$

Alternatively : $(\text{CP} = \text{SP}) = \frac{1}{3}\text{MP}$

$\Rightarrow$ $(\text{CP} = \text{SP}) : \text{MP} = 1 : 3$

12. $\text{CP} : \text{MP} = 2x : 3x$

$\Rightarrow$ Profit $= x$

(%) profit : (%) discount = 3 : 2

Let CP = 200, SP = 300

But $\frac{3x}{100} \times 200 + \frac{2x}{100} \times 300 = 100$

$\Rightarrow$ $x = 8.33\%$

Discount $2x = 16.66\%$

13. It is dependent upon the markup (%) or discount (%)

Since,



loss = 4%

Again



loss = 25%

Hence we can't determine.

14. CP → Profit (%) → MP

$100 \to x\% \to 100 + \frac{100x}{100} = (100 + x)$

Again, MP → discount → SP

$(100 + x) \to x\% \to (100 + x) - (100 + x)\frac{x}{100}$

$$= (100 + x)\left(1 - \frac{x}{100}\right)$$

Now $\frac{(100 + x)}{(100 + x)\left(1 - \frac{x}{100}\right)} = \frac{2}{1}$

$\Rightarrow$ $\left(1 - \frac{x}{100}\right) = \frac{1}{2} \Rightarrow x = 50\%$

This can be observed in the solution of the previous problem.

15. Go through option

$180 \times 12 \times 1.2 + 180 \times 8 \times 1.1 = 180\,[14.4 + 8.8]$

$= 180\,(23.2) = 4176$

and $180 \times 20 \times 1.15 = 4140$

Therefore loss = 4176 − 4140 = 36

Hence option (c) is correct.

16. Gain = 30000

loss = 20000

net gain = 10000 over Rs. 4 lakh

Hence, $\text{profit} = \frac{10000}{400000} \times 100 = 2.5\%$

17. Let the MP = Re 1 per kg then

Weight	MP	Rate
100	100	1
96	80	$\frac{80}{96}$
	SP	

Effective discount $= 1 - \frac{80}{96} = \frac{16}{96}$

$$\%\ \text{discount} = \frac{16}{96} \times 100 = 16.66\%$$

18. CP of $A + B + C = 2x \times y + 5x \times 2y + 2x \times 4y = 20xy$

Profit of $A = 0.2xy$

Profit of $B = 2xy$

Profit of $C = 2xy$

Total profit $= 4.2xy$

$$\%\ \text{profit} = \frac{4.2xy}{20xy} \times 100 = 21\%$$

19. Initially

CP	Profit	SP	MP
100	x	$(100 + x)$	133.33

After change

CP	Profit	SP
100	$2x$	$(100 + x)\frac{7}{6}$

Now, since $(100 + x)\frac{7}{6} - 100 = 2x$

$\Rightarrow$ $x = 20\%$

	CP	Profit	SP	MP
	100	20	120	133.33
So,	300	60	360	400
Again	300	120	420	

So the increased selling price = Rs. 420

20. From percentage change graphic



Scanned by CamScanner

yoursmahboob.wordpress.com

$$\text{Decrease} = \frac{3}{10}\downarrow = 30\%$$

$$\text{Increase} = \frac{3}{(10-3)} = \frac{3}{7}\uparrow = 42\frac{6}{7}\%$$

21. Let the price be x, then

$$x \times 0.8 \times 0.9 = 468$$

$\Rightarrow x = 650$, therefore marked price = Rs. 650

Alternatively: $650 \times 0.8 \times 0.2 = 468$

Hence option (d) is correct.

22.



23. Reduced price = $100 \times 0.95 \times 0.90 \times 0.80 = 68.40$

$\therefore$ Single discount = $(100 - 68.4)\% = 31.6\%$

24. $\text{CP} = \frac{10}{12}$, $\text{SP} = \frac{12}{10}$

$$\text{Profit (\%)} = \frac{\frac{12}{10} - \frac{10}{12}}{\frac{10}{12}} \times 100 = 44\%$$

25. Let the cost price of one gram be Re. 1, then the markup price be Rs. 1.2 per g.

Now he sells 1000 g which seems to be 1250 g so he charges to a customer $1250 \times 1.2 =$ Rs. 1500 for 1000 g (or Rs. 1000)

$$\text{Thus his profit \%} = \frac{1500 - 1000}{1000} \times 100 = 50\%$$

26. Let the CP be Rs. x, then SP be $0.96x$

$$\therefore \quad 0.96x = 240 \quad \Rightarrow \quad x = 250$$

Now the new SP = $250 \times 1.1 = 275$

27.

CP	SP	MP
x	$112.5x = 225$	300
	(−25%)	

$\therefore x = 200$, hence the cost price be Rs. 200.

NOTE It can also be solved by using option. First of all find the SP by decreasing MP by 25% then this SP will be equal to 112.5% (12.5% is the profit) of the cost price so the CP can be find as given above.

28.

CP	$\xrightarrow{(-10\%)}$	$(SP)_1$	$\xrightarrow{(-5\%)}$	$(SP)_2$
200		180		171

29. The CP of profitable cow = $\frac{9900}{1.1} = 9000$

and profit = Rs. 900

The CP of loss yielding cow = $\frac{9900}{0.8} = 12375$

and loss = Rs. 2475

So, the net loss = $2475 - 900 = 1575$

30. The best way is to go through option. Consider option (a)

15000

$\left(\frac{2}{3}\right)$ $\left(\frac{1}{3}\right)$

10000 5000

(5% profit) ↓ ↓ 2% loss

500 100

Net gain = Rs. 400 (= 500 − 100)

Hence, option (a) is correct.

Alternatively: $\left[\left(1.05 \times \frac{2x}{3} + 0.98\,\frac{x}{3}\right) - x\right] = 400$

$\Rightarrow \quad x = 15000$

31. $\text{Profit (\%)} = \frac{\text{goods left}}{\text{goods sold}} \times 100 = \frac{50}{450} \times 100 = 11\frac{1}{9}\%$

Alternatively: Suppose CP of 1 g is Re. 1 then he sells goods worth Rs. 450 only and charges Rs. 500. So the profit is Rs. 50 over the sale price of Rs. 450.

32. Go through options. Consider option (b)

$200 \times 3.25 - 200 \times 3 =$ Rs. $50 (= 30 + 20)$

Hence, option (b) is correct.

Alternatively: Rs. 0.25 is the difference on 1 banana

$\therefore$ Re 1 is the difference on $\frac{1}{0.25} = 4$ bananas

$\therefore$ Rs. 50 is the difference on $4 \times 50 = 200$ bananas

33. By percentage change (or fraction change) graphic

increase decrease

$30\% = \frac{3}{10}\uparrow$ $\frac{3}{13}\downarrow$ [Since product *i.e.*, price is constant]

It means now $\frac{3}{13}$ times less eggs are available which is equal to 3 eggs.

i.e., $\frac{3x}{13} = 3$

$\Rightarrow \quad x = 13$ eggs (initially)

Now available eggs on the same price = $13 - 3 = 10$

Thus, the new price = $\frac{910}{10} = 91$ paise

Alternatively : Go through options.

New or changed	No. of eggs	Rate	= total prices
	$\oplus 3$ 10	× 91	= 910 paise
Initial →	13	× 70	(+30%) = 910 paise

Therefore option (a) is correct.

34. $\text{SP} = \frac{100}{12}$ paise

$$\text{CP} = x, \ \text{SP} = 0.8x = \frac{100}{12} \quad \Rightarrow \quad x = \frac{100}{9.6} \text{ paise}$$

Therefore, $\text{CP} = \frac{100}{9.6}$ paise

Thus, the new SP (with 20% profit) = $\frac{100}{9.6} \times 1.2 = \frac{100}{8}$ paise

Hence, 8 apples can be purchased for Re. 1 to gain 20%.

Scanned by CamScanner

yoursmahboob.wordpress.com

35. $10000 \xrightarrow{-10\%} 9000 \xrightarrow{-20\%} 7200 \xrightarrow{+10\%} 7920 \xrightarrow{+10\%} 8712$

36. $1425 - 1353 = 72 = 6\%$ of CP

$\Rightarrow$ CP = 1200

37. $CP = \frac{405}{0.9} = 450$

New SP = Rs. 465

Profit (%) $= \frac{465 - 450}{450} \times 100 = 3.33\%$

38. $\left[((x \times 1.1) \times 1.1) \times \frac{1125}{1100}\right] = 990$

$\Rightarrow$ $x = 800$

Alternatively: Go through options or by the reverse process.

39. Best way is to go through option

Alternatively : $P \times 0.9 \times 0.75 = C \times 0.85 \times 0.80$

$\Rightarrow$ $\frac{P}{C} = \frac{136}{135}$

40. Let the CP be x then

$0.04x = 54 (= 1080 - 1026)$

$\Rightarrow$ $x = \frac{54}{0.04} = 1350$ (CP)

CP = 1350

SP = $1350 \times 1.04 = 1404$

41. SP − CP = 175 = 14% of CP

$\Rightarrow$ CP = 1250

$\therefore$ SP = 1250 + 175 = 1425

42. CP = 100, then

Tag price = 80

SP, after discount = 75

Total loss = 25

$\because$ Rs. 25 are being less at CP of Rs. 100

$\therefore$ Rs. 37.5 are being less at CP of Rs. $\frac{100}{25} \times 37.5 = 150$

Hence, SP = 150 − 37.5 = 112.5

Alternatively: 112.5 + 37.5 = 150 = CP

Again $150 \times 0.8 \times .9375 = 112.5 = SP$

Hence, option (b) is correct.

43. $CP + 4k = SP_1$ (gives profit)

$CP - 3k = SP_2$ (gives loss)

since loss ($3k$) is 25% less than profit ($4k$)

$\therefore$ $SP_1 - SP_2 = 7k = 836 - 703 = 133$

$\Rightarrow$ $k = 19$

$\therefore$ $CP = SP_1 - 4k = SP_2 + 3k = 760$

Therefore required SP = $760 \times 1.2 = 912$

44. You can go through options.

$CP = \frac{100}{6} = 16.66$ paise

$SP = \frac{100}{5} = 20$ paise

profit (%) $= \frac{20 - 16.66}{16.66} \times 100 = \frac{3.33}{16.66} \times 100$

$= \frac{1}{5} \times 100 = 20\%$

Hence, option (c) is correct.

Alternatively: $CP = \frac{100}{6}$

$SP = \frac{100}{6} \times 1.2 = \frac{100}{5}$

Hence, he should sell 5 toffees for Re. 1 (= 100 paise)

45. CP MP

$800 = 0.8x$ x

20% discount

$\Rightarrow$ x = Rs. 1000 = MP

SP at Hazratganz = Rs. 800

SP at Bhootnath = $1000 \times 0.85 = 850$

So, she requires Rs. 50 more to purchase the same calculator at Bhootnath.

46. Let the CP be Re. 1 per g

but he weighs 900 g for every 1000 g

$\therefore$ Value of goods sold = 900

Now, let the markup be x%

$\therefore$ $MP = 1000 + \frac{1000x}{100} = (1000 + 10x)$

but since MP = SP, $\therefore$ $SP = (1000 + 10x)$

Hence, profit (%) $= \frac{(1000 + 10x) - 900}{900} \times 100 = 20$

$\Rightarrow$ $x = 8$

Thus the markup = 8%.

47. Loss % $= \left(\frac{\text{common gain or loss}}{10}\right)^2 \%$

$= \left(\frac{20}{10}\right)^2 \% = 4\%$

48. Since loss = 4%

Now assume total CP of both articles be x, then

$SP = 0.96x = 400$

$\Rightarrow$ $x = \frac{400}{0.96} = CP$

$\therefore$ loss = 4% of CP

$\frac{4}{100} \times \frac{400}{0.96} =$ Rs. 16.66

49. $\frac{CP}{SP} = \frac{29x}{19x}$

loss % $= \frac{29x - 19x}{29x} \times 100 = 34.48\%$

(To understand the concept assume CP of each article Rs. 29 and SP of each article = Rs. 19)

Scanned by CamScanner

yoursmahboob.wordpress.com

50. $\frac{CP}{SP} = \frac{13}{23}$

$\text{profit (\%)} = \frac{23-13}{13} \times 100 = \frac{10}{13} \times 100 = 76.92\%$

51. $\frac{CP}{SP} = \frac{28}{34} = \frac{14}{17}$

52. MP = Rs. 1.2, if CP = Re. 1
But he gives the cloth worth Rs. 0.8 instead of Re. 1.

Therefore profit $\% = \frac{1.2-0.8}{0.8} = \frac{0.4}{0.8} \times 100 = 50\%$

53. CP = Rs. 80 $\left(=\frac{3200}{40}\right)$

Now SP of 40 books = CP of 40 books + SP of 8 books

$\Rightarrow$ SP of 32 books = 3200

$\Rightarrow$ SP of 1 book = Rs. 100

$\therefore$ Required SP of 1 dozen books = Rs. 1200

54. Profit of $A = 1800 \times \frac{20}{100}$ = Rs. 360

$$\text{CP of } B = \frac{1800}{1.2} = 1500$$

$\therefore$ Profit of B = Rs. 300 (= 1800 – 1500)

$\therefore$ Difference in profit of A and B = Rs. 60

55. $$\text{CP of } A = \frac{1818}{0.9} = 2020$$

$$\text{CP of } B = \frac{1818}{1.01} = 1800$$

$$\frac{\text{CP of } A}{\text{CP of } B} = \frac{2020}{1800} = \frac{101}{90}$$

56. 103.33 CP – 0.95 CP = 65

$\Rightarrow$ CP = Rs. 780

$$\text{Profit (\%)} = \frac{936-780}{780} \times 100 = 20\%$$

57. Best way is to assume some proper values then verify it.

58. Let us assume initially he has 100 l of milk
So, after 10% of water addition new amount of
mixture = 110 l
Again adding 10% more then the final amount of
mixture = 121 l

$$\text{Profit \%} = \frac{21}{100} \times 100 = 21\%$$

59. $$SP = x + \frac{x \times x}{100} = 96\%$$

$\Rightarrow$ $x = 60$

New, $SP = 60 + \left(\frac{60 \times 120}{100}\right)$ = Rs. 132

60. $K \rightarrow 1$ litre, price of $K \rightarrow 1$
$P \rightarrow 4$ litre, price of $P \rightarrow 2$
Price of total (new) mixture $= 1 \times 1 + 4 \times 2$ = Rs. 9
Price of pure petrol of same quantity = 5×2 = Rs. 10
Percentage profit $= \frac{1}{9} \times 100 = 11\frac{1}{9}\%$

61. Amount purchased = 1100 g
Amount sold = 900 g

$$\text{Profit \%} = \frac{200}{900} \times 100 = 22\frac{2}{9}\%$$

62. If CP be Re. 1 per g, then he pays Rs. 1200 for 1000 g
Again he obtains Rs. 1200 for 1000 g (by selling at 20% profit). Thus there is no loss no gain.

63.

CP	SP
240	280

$\left(-14\frac{2}{7}\%\right)$

Actual profit (%) $= \frac{40}{240} \times 100 = 16.66\%$

NOTE Here you can apply base change concept.

Increase	decrease
16.66%	$14\frac{2}{7}\%$
$\frac{1}{6}\uparrow$	$\frac{1}{7}\downarrow$

64. Go through options :

$$100 \xrightarrow{80\%} 180$$

$$\text{New SP} = \frac{180}{3} = 60$$

Percentage loss = 40% (100 – 60)
Hence, (c) is correct choice.

65.

CP	Profit	SP	
100	20	120	+25%
x	25	150	

$x \times 1.25 = 150 \Rightarrow x = 120$

$$\text{\% change} = \frac{120-100}{100} \times 100 = 20\%$$

66. 6.66% of MP = 25

$\Rightarrow$ MP = 375

$\therefore$ SP = MP – 25 = 350

67. Profit $\% = \frac{5}{95} \times 100 = 5.26\%$

68. Recall it is based on inverse proportion or product constancy concept.

Reduction in price	increase in amount
$25\%\left(\frac{1}{4}\right)\downarrow$	$\uparrow\left(\frac{1}{3}\right)33.33\%$ = 4 oranges

It means original number of oranges = $4 \times 3 = 12$

$\therefore$ Original price of oranges $= \frac{16}{12}$ = Rs. 1.33

69.

Reduction in price	increase in amount
$20\%\left(\frac{1}{5}\right)\downarrow$	$\frac{1}{4}\uparrow(25\%) = 6$ kg

It means original amount of sugar needed = $6 \times 4 = 24$ kg

$\therefore$ Original price of the sugar $= \frac{240}{24}$ = Rs. 10 per kg.

70. Just a sitter. Don't be bogged down. Its simple *i.e.*, 25%, nothing else, which is very obvious.

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL 2

1. Just a sitter but a logical problem.

CP of 5 bikes = 67500 + 232500 = 300000

Now, since we require 17.5% profit, so SP = $300000 \times \frac{117.5}{100}$

= Rs. 352500

2. CP = 100, SP (with tax) = 120

New SP = 100 − 5 = 95

∴ Effective discount = 120 − 95 = 25

So, at SP of 95 → discount = 25

and at SP of 3325 → discount = $\frac{25}{95} \times 3325 = 875$

3. Let the CP of a bicycle = Rs. 100

Now, since profit 140%

∴ SP = 240

Now, 7 bicycles are being sold instead if 1 bicycle, but the sale price of new bicycle = Rs. 120

Therefore total sale price of new sale of bicycles

$= 7 \times 120 = 840$

and the CP = $7 \times 100 = 700$

So, the new profit = 840 − 700 = Rs. 140

Since the initial profit is same as the new so there is no increase in percentage.

4. CP SP MP

100 —32%→ 132 —$\frac{12}{88}$↑→ 150

−12% $\left(=\frac{12}{100}\right)$↓ [from percentage change graphic]

NOTE In this case first of all find the SP, after adding profit percentage to CP then find the MP through SP.

Now, CP SP MP

100 —+20%→ 120 —−20%→ 150

Here first of all we subtract discount from the MP then the resultant value will be SP.

5.

Linc pens	Cello pens
CP : SP	CP : SP
37 : 50	37 : 24

Profit % = $\frac{13}{37} \times 100$

and Loss% = $\frac{13}{37} \times 100$

Since Profit = loss

Hence option (d) is correct.

6.

	A		B		C
SP	$\frac{1}{7}\binom{8}{7}\frac{1}{8}$	:	$\frac{1}{8}\binom{9}{8}\frac{1}{9}$	:	$\frac{1}{4}\binom{5}{4}\frac{1}{5}$

Since $14.28\% = \frac{1}{7}$

So, the ratio of profit percentage of

A		B		C	
8	:	7	:	14	(Given)
↓		↓		↓	
$\frac{1}{7}$		$\frac{1}{8}$		$\frac{1}{4}$	

Thus the ratio of CP of $A : B : C$

$7 : 8 : 4$

Therefore % profit = $\frac{(8+9+5)-(7+8+4)}{(7+8+4)} \times 100$

$= \frac{3}{19} \times 100 = 15.78\%$

7.

	A	B	C	M
CP →	100	120	132	(120 + 12) = 132
SP →	120	132	120	143
CP →	143	←		

Loss of A = 143 − 120 = 23

% loss of $A = \frac{23}{100} \times 100 = 23\%$

8. Total wages = no. of employees × wage per employee

$60xy = 3x \times 20y$

$54xy = 2x \times 27y$

Profit (%) = $\frac{60-54}{60} \times 100 = 10\%$

9. If I had Rs. 100

Discount = 25 = cost of my sister's watch

then cost of my own watch = 75

Thus the ratio of cost of my own watch to that of my sister's watch = 3 : 1

10. Ratio of profit of $A : B$ (excluding commission of A)

$= 3 : 5$ (∵ 54 : 90 = 3 : 5)

Now the share of profit of B = 3600 − 1800 = Rs. 1800

So the share of profit of A (excluding commission) = Rs. 1080

So the commission of A = 1800 − 1080 = 720

Therefore the required percentage = $\frac{720}{3600} \times 100 = 20\%$

11. Profit % = $\frac{25}{100} = \frac{120+k}{880}$ (Profit)/(Sale) ⇒ $k = 100$

Therefore, net profit % = $\frac{100}{1000} \times 100 = 10\%$

12. $SP = \frac{12}{11}$ of CP

$48 = \frac{12}{11}$ of CP ⇒ CP = 44

Now, by alligation

48		k
	44	
12		3
4	:	1

∴ $k = 28$

Thus the price of speed brand is Rs. 28/litre.

Scanned by CamScanner

yoursmahboob.wordpress.com

13.

	A	B	C
Investment	$3x$	$4x$	$5x$
Rate of return	$6y\%$	$5y\%$	$4y\%$
Return	$\frac{18xy}{100}$	$\frac{20xy}{100}$	$\frac{20xy}{100}$

$$\text{Total} = (18 + 20 + 20) = \frac{58xy}{100}$$

$$B\text{'s earnings} - A\text{'s earnings} = \frac{2xy}{100} = 250$$

$$\text{Total earning} = \frac{58xy}{100} = 7250$$

14. MP → after first discount → after second discount

100 → 90 → 85.5

So, the net discount = 100 − 85.5 = 14.5%

15. MP → CP → Total CP

100 → 80 → 72 → 79.2

(−20%, −10%, +10%)

SP = 125% of CP

$SP = 1.25 \times 79.2$

$SP = 99$

So, initially marked price = 100 ⇒ 8,00,000

Final sale price = 99 ⇒ 7,92,000

16. Price of 10 chairs = $10 \times 200 = 2000$

Price of 12 chairs (without discount) = $12 \times 200 = 2400$

Price of 12 chairs with discount = $10 \times 200 + 2 \times 80 = 2160$

therefore discount = 2400 − 2160 = 240

Hence discount % = $\frac{240}{2400} \times 100 = 10\%$

17. Amount paid in Ist service = 100 (suppose)

Amount paid in IInd service = 90

Amount paid in IIIrd service = 81

Amount paid in IVth service = 72.9

Amount paid in Vth service = 60

Total amount paid = 403.9

Discount = 500 − 403.9 = 96.1

Discount % = $\frac{96.1}{500} \times 100 = 19.42\%$

18. Consider some proper values and then check out.

19. CP : SP

3 : 4

Profit on 3 apples = Re 1 (consider CP = Re 1)

Profit = 33.33%

and discount = 11.11%

Since CP → SP → MP

3 → 4 → 4.5

(1) (0.5)

Profit is double that of discount

So, the percentage point difference = 33.33% − 11.11%

= 22.22% point

20. Total cost of 4 cars = 1 + 2 = 3 lakh

Total SP of 4 cars = $3 \times 1.5 = 4.5$ lakh

SP of 1 car = 1.2 lakh

SP of rest 3 cars = 4.5 − 1.2 = 3.3 lakh

Average SP of all the 3 cars = 1.1 lakh

21. Setup cost = Rs. 2800

Paper etc. = Rs. 1600

Printing cost = Rs. 3200

Total cost = Rs. 7600

Total sale price = $1500 \times 5 = 7500$

Let the amount obtained from advertising is x then

$(7500 + x) - (7600) = 25\%$ of 7500

$x = 1975$

22. Charge of 1 call in February = $\frac{350}{150} = \frac{7}{3}$

Charge of 1 call in March = $\frac{350 + 50 \times 1.4}{250}$

$= \frac{420}{250} = \frac{42}{25}$

% cheapness of a call in March = $\frac{\frac{7}{3} - \frac{42}{25}}{\frac{7}{3}} \times 100 = 28\%$

23. Let the CP be 100 and % markup be k% then

$$MP = 100 + k$$

$$100 \xrightarrow{k\%} (100 + k) \text{ MP (also expected SP)}$$

$$\text{but actual SP} = \frac{100 + k}{2}$$

$$\therefore \quad \frac{\left[\left(\frac{100 + k}{2}\right)\right]}{k} = \frac{200}{3 \times 100} \; (= 66.66\%)$$

$$\Rightarrow \quad k = 300$$

Therefore CP MP (initially)

100 400

$$\text{Finally SP} = \frac{400}{2} = 200$$

$$\therefore \quad \text{Discount} = \frac{200}{400} \times 100 = 50\%$$

Alternatively: $MP \to M$

$$SP \to \frac{M}{2}$$

$$\text{Discount (\%)} = \frac{M/2}{M} \times 100 = 50\%$$

24. Let the CP and SP of 1 g = Re 1, then

He spends Rs. 2000 and purchase 2200 g

and he charges Rs. 2000 and sells 1800 g

$$\text{profit (\%)} = \frac{\text{goods left}}{\text{goods sold}} \times 100$$

$$= \frac{400}{1800} \times 100 = 22\frac{2}{9}\%$$

Scanned by CamScanner

yoursmahboob.wordpress.com

25.

Fresh grapes

Water		Pulp
80%		20%
4	:	1

Dry grapes

Water		Pulp
25%		75%
1	:	3
5 kg		15 kg] out of 20 kg dry grapes

+ (55 kg) → 60 kg

80%	20%
4	1
60 kg	15 kg

Required proportion of water and pulp

Thus to make dry grapes similar to the fresh grapes, Akram requires 55 kg water with 20 kg of dry grapes.

So, the profit (%) $= \frac{55}{20} \times 100 = 275\%$

26. Let the total profit be 100
Amount left after donation = 80
Amount left after reinvestment = 20

Now, $\frac{5x}{8} - \frac{3x}{8} = 1200$

where x is the amount left after reinvestment

$$\frac{2x}{8} = 1200 \Rightarrow x = 4800$$

Therefore, total profit $= 4800 \times 5 = 24000$

Alternatively: Go through options.

27. Total cost = Rs. 50,000
Total sale price (or revenue) $= 2000 \times 9 + 6000 \times 10 = 78{,}000$

$$\text{profit (\%)} = \frac{28000}{50000} \times 100 = 56\%$$

28. The maximum possible profit
= maximum possible difference in SP and CP.
It means SP be maximum and CP be minimum

$CP_{(min)}$ = Rs. 399 $\quad 19m = 399$

where m is an integer.
Again $SP_{(max)}$ = Rs. 697, which is very close to 699
Here $697 = 17k$; k is a positive integer.
So, the maximum profit = 697 − 399 = Rs. 298

29. Total cost price $= 1000 \times 1.2 =$ Rs. 1200
Expected selling price $= 700 \times x = 1200 \times 1.1666 = 1400$

$\Rightarrow$ x = Rs. 2 per toy

Now the real selling price $= 750 \times 2 =$ Rs. 1500

$\therefore$ Profit = Rs. 300 (= 1500 − 1200)

$\therefore$ Profit % $= \frac{300}{1200} \times 100 = 25\%$

30. Chaudhary's profit = 10%
Anupam's profit = 20%
Bhargava's profit = 25%

i.e., A $\xrightarrow{20\%}$ B $\xrightarrow{25\%}$ C $\xrightarrow{10\%}$ D
100 → 120 → 150 → 165

Now

B	D
120	165
17 times	17 times
2040	2805

31. From the statements it is clear that he purchases 119 g instead of 100 g and he sells 85 g instead of 100 g. Therefore in this whole transaction he saves 19 + 15 = 34 g

Thus the profit $= \frac{34}{85} \times 100 = \left(\frac{\text{Goods left}}{\text{Goods sold}} \times 100\right) = 40\%$

NOTE In this type of question always equate either money or weight for simple solution.

32. You must know that the company is able to deliver only 90% of the manufactured pens. So let K be the manufacturing price of a pen, then
total income (including 25% profit) $= (8000 \times K) \times 1.25$
also this same income is obtained by selling 90% manufactured pens at Rs. 10 which is equal to 7200×10
Thus $(8000 \times K)\,1.25 = 7200 \times 10$

$\Rightarrow$ K = Rs. 7.2 (90% of 8000 = 7200)

33. Let the number of diaries (produced) be 100 and the cost price of a diary be Re 1 then
Total cost incurred $= 100 \times 1 = 100$
Total sale price $= 32 \times 0.75 + 60 \times 1.4 = 108$
Therefore profit = Rs. 8
Thus there is 8% profit

NOTE Marked price (*i.e.*, expected) = 40% above the cost price.

34. Let the number of sweets be 100 and the cost price of one piece of sweet = Re. 1
then, total cost price $= 100 \times 1 =$ Rs. 100
Total sale price $= 40 \times 1.4 + 30 \times 1.2 + 30 \times 1.05 = 123.5$
$\therefore$ profit (%) = 23.5% (= 123.5 − 100)

35.

CP	SP	MP
500	576	900

Again $SP = MP\left[\left(1 - \frac{r}{100}\right)^2\right]$ [$r \rightarrow$ rate of discount in %]

$\Rightarrow$ $576 = 900\left(1 - \frac{r}{100}\right)^2$

$\Rightarrow$ $\frac{24}{30} = \left(1 - \frac{r}{100}\right) \Rightarrow r = 20\%$

Again, new $SP = MP\left(1 + \frac{r}{100}\right)^2 = 900\left(1 + \frac{20}{100}\right)^2 = 1296$

New, profit percentage $= \frac{SP - CP}{CP} \times 100$

$= \frac{1296 - 500}{500} \times 100 = 159.2\%$

36. Consider actual price of 1 g goods = Re. 1 then
he sells the product equals to Rs. 90 only (10% less weighing)
Again MP = Rs. 1.8 and SP = 1.35 for 1 g.
Thus he gives the goods worth Rs. 90 and charges Rs. 135 after 25% discount. Thus the profit %

$$= \frac{135 - 90}{90} \times 100 = 50\%$$

37. $CP = \frac{100}{120} = \frac{10}{12}$

(since he purchases 120 g and pays Rs. 100, by assumption actual CP of 1 g = Re. 1)

Scanned by CamScanner

yoursmahboob.wordpress.com

$$SP = \frac{135}{90} = \frac{3}{2} = \frac{18}{12}$$

(Since actual MP = 180, actual SP = 135, with 25% discount and he sells only 90 g instead of 100 g)

$$\text{profit (\%)} = \frac{\frac{18}{12} - \frac{10}{12}}{\frac{10}{12}} \times 100 = 80\%$$

38. Let the actual cost price of an article be Re 1 (in place of x)
Now he purchases goods worth Rs. 120 and pays Rs. 80, since 20% discount is allowed.
So the $CP = \frac{80}{120} = \frac{2}{3}$

Again MP = 180, SP = 135 (since 25% discount)
Thus the trader sells goods worth Rs. 90 instead of 100 g and charges Rs. 135. Therefore the effective $SP = \frac{135}{90} = \frac{3}{2}$

$$\therefore \quad \text{profit (\%)} = \frac{\frac{3}{2} - \frac{2}{3}}{2/3} \times 100 = 125\%$$

39.

Anjuli		Bhoomika		Chawla
100		100		100
↓ – 20%		↓ – 15%		↓ – 12%
24 ← 80		23.5 ← 85		23.44 ← 88
↓ – 5%		↓ – 10%		↓ – 13%
76		76.5		76.56

Thus it is clear from the graphical solution that the maximum discount is availed by Anjuli.

NOTE It does not matter that we first decrease by 20% and then by 5% or *vice-versa*. This concept has been already illustrated in percentage chapter. Try to do it for your concept clarification.

40. CP of one egg (in first case) $= \frac{1}{3} = 33.33$ paise

CP of one egg (in second case) $= \frac{1}{6} = 16.66$ paise

Average CP of one egg $= \frac{(33.33 + 16.66)}{2} = 25$ paise

SP of one egg $= \frac{200}{9}$ (Re. 1 = 100 paise)

$$\text{profit-loss} = \frac{25 - \frac{200}{9}}{25} \times 100 \qquad \left(\text{loss\%} = \frac{CP - SP}{CP} \times 100\right)$$

$= 11.11\%$ loss

41. This question is based on fundamental concept of percentage change.

$$\text{Virendra} = CP_V \xrightarrow{\rightarrow P\%} SP_V$$

$$\text{Gurindra} = CP_G \xrightarrow{Q\% \leftarrow} SP_G$$

Here, $CP_V = CP_G$ and $SP_V = SP_G$
But $P \neq Q$
also, $P\%$ of $CP_V = Q\%$ of SP_G
also $Q = 41\frac{2}{3}\%$ of $P = \frac{125}{3} \times \frac{P}{100}$

and $Q = \frac{P}{100 + P} \times 100$

(From the concept of percentage change)

$$\therefore \quad \frac{P}{100 + P} \times 100 = \frac{125}{3} \times \frac{P}{100} \qquad \left(41\frac{2}{3} = \frac{125}{3}\right)$$

$$\Rightarrow \quad P = 140$$

$\therefore$ CP = 100 when SP = 240

Where $CP = CP_V = CP_G$ and $SP = SP_V = SP_G$

Again SP for Amrindra = 240 + 140% of 240 = 576

42. Let the CP of one article be Rs. 1
then the SP be Re. 1.25
Again the new SP be $(1.25) \times 1.2 = 1.5$
Now, if he sell initially 100 articles, then

CP = 100 × 1 = Rs. 100

SP = 100 × 1.25 = Rs. 125

New SP = 75 × 1.5 = 112.5 (since 25% articles were abducted)

$\therefore$ New profit percentage = 12.5%

43. **Note :** First of all the price of milk does not matter. You can assume any convenient price. Besides it instead of 10 l of milk you can consider 100 l of milk to avoid calculations in decimal.
Now, since water is 16.66% in the mixture of milk, therefore with 100 l pure milk 20 l water is added. Again note that in replacement method the quantity of mixture does not increase except to the variation in ratio of contents.
Again by replacement formula

$$\frac{80}{120} = \frac{100}{120}\left(1 - \frac{K}{120}\right) \quad \Rightarrow \quad K = 24\,l$$

Thus he replaces 24 l of mixture with water.
(Note the required ratio of milk is to water is 2 : 1. It means in 3 l of new mixture, there will be 2 l of water)
Thus if the price of new mixture be Re 1, then the price of replaced mixture be Rs. 2.
Therefore, total SP = 120 × 1 + 24 × 2 = 168
and CP = 100 × 1 = 100
$\therefore$ Profit % = 68%

44.

	Candle	Bulb
CP	a	c
SP	b	d

and $c = 2a$

Profit = 10 $(b - a) = 3d$

and Loss = 10 $(c - d) = 4b$

$$\text{Profit (\%)} = \frac{3d}{10a} \times 100$$

and $$\text{Loss (\%)} = \frac{4b}{10c} \times 100$$

Again $$\frac{3d}{10a} \times 100 = \frac{4b}{10c} \times 100$$

$$\Rightarrow \quad \frac{3d}{a} = \frac{4b}{c} \Rightarrow \frac{3d}{a} = \frac{4b}{2a} \qquad (\because c = 2a)$$

$$\Rightarrow \quad \frac{b}{d} = \frac{3}{2}$$

45. Let the CP of each motorcycle be Rs. x, then

$$2(1.15x) + 4800 = 2(1.2x)$$

$$\Rightarrow \quad 0.x = 4800 \Rightarrow x = 48000$$

Scanned by CamScanner

yoursmahboob.wordpress.com

7 CI/SI/INSTALMENTS

The concept of simple interest and compound interest is one of those concepts which are widely used in Business and Banking etc. Questions are rarely asked in CAT from this chapter, but it is important for the purpose of Data interpretation. Since the questions based on the concept of 'interest' are rather easy so it is common that MAT, FMS, CET etc. asked enough questions from this chapter. The questions of this chapter are so easy that 95% questions can be solved orally or using unitary methods *i.e.*, sometimes you don't need to apply the given formula and I think that is essential.

Simple interest is nothing but the fix percentage of the principal (invested/borrowed amount of money)

Some key words used in the concept of interest.

Principal :(P) It is the sum of money deposited/loaned etc. also known as **capital.**

Interest : It is the money paid by borrower, calculated on the basis of **Principal.**

Time (T/n) : This is the duration for which money is lent/borrowed.

Rate of Interest (r/R) : It is the rate at which the interest is charged on principal.

Amount (A) = Principal + Interest

Simple Interest : When the interest is calculated uniformly only on the principal for the given time period.

Compound Interest : In this case for every next period of time the interest is charged on the total previous amount (which is the sum of principal and interest charged on it so far.) *i.e.*, every time we calculate successive increase in the previous amount.

IMPORTANT FORMULAE

Simple Interest (SI)

$$SI = \frac{P \times r \times t}{100}$$

P = Principal

r = rate of interest (in %)

t = time period (yearly, half yearly etc.)

$$\text{Amount } (A) = P + \frac{Prt}{100} = P\left(1 + \frac{rt}{100}\right)$$

NOTE Out of the five variables A, SI, P, r, t we can find any one of these, if we have the requisite information.

CONVERSION OF TIME PERIOD-RATE OF INTEREST

Given (r%)	Given (t)	Required (r%)	Required (t)
r% annual	t years	$\frac{r}{2}$(%) half-yearly	$2t$
r% annual	t years	$\frac{r}{4}$% quarterly	$4t$
r% annual	t years	$\frac{r}{12}$% monthly	$12t$

Compound Interest (CI)

1. CI = $A - P$ [A is the amount including interest and principal (P) both]

2. Amount $(A) = P\left(1 + \frac{r}{100}\right)^t$

3. When rate of interest is half-yearly

$$A = P\left(1 + \frac{(r/2)}{100}\right)^{2t}$$

4. When the rate of interest is quarterly

$$A = P\left(1 + \frac{r/4}{100}\right)^{4t}$$

Difference between CI and SI for two years

(also in second year) $= P\left(\frac{r}{100}\right)^2$

Difference between CI and SI for three years

$$= P\left(\frac{r}{100}\right)^2\left(\frac{r}{100} + 3\right)$$

Depreciation : It is known that the prices of some articles depriciates in their values over a time period. When the value in terms of currency decreases, we say that the value of the article is depreciating.

$$V_f = V_i\left(1 - \frac{r}{100}\right)^t$$

Scanned by CamScanner

yoursmahboob.wordpress.com

V_i = initial value of the article

V_f = final (depreciated) value of article

r, is the rate of interest by which the price of article decreases over the time period 't'.

Population : It has been observed that the population of a particular locality/nation etc. increases or decreases successively over its previous value *i.e.*, it increases or decreases as compound interest for the money. Thus we use similar formulae for the calculation of population.

$$\text{(Total population) } P = P_0\left(1+\frac{r}{100}\right)^n,$$

when population increases

$$\text{(Total population) } P = P_0\left(1-\frac{r}{100}\right)^n,$$

when population decreases.

Instalments : When a borrower paid the sum in parts (*i.e.*, not in a single amount) then we say that he/she is paying in instalments. For example A borrowed Rs. 100 from B and he pays back it to B in several parts *i.e.*, Rs. 20 in 5 times or Rs. 50 in 2 times etc. But the important point is that borrower has to also pay the interest for using the borrowed sum/or purchased article. In general the value of each instalment is kept constant even when the interest charged on each instalment vary for each instalment.

For Simple Interest

$$A = \left[x+\left(x+\frac{x\times r\times 1}{100}\right)+\left(x+\frac{x\times r\times 2}{100}\right)+\left(x+\frac{x\times r\times 3}{100}\right)+\ldots\right]$$

A = Total amount paid

x = Value of each instalment

Also, $$\boxed{A = P+\frac{P\times n\times r}{100}}$$

P is the principal

n is the number of instalments

r is the rate of interest

For Compound Interest

(loan amount)

$$P = \left[\frac{x}{\left(1+\frac{r}{100}\right)}+\frac{x}{\left(1+\frac{r}{100}\right)^2}+\frac{x}{\left(1+\frac{r}{100}\right)^3}+\ldots+\frac{x}{\left(1+\frac{r}{100}\right)^n}\right]$$

$x \to x$ is the value of each instalment.

$$\text{Total amount paid in instalments } (A) = P\left(1+\frac{r}{100}\right)^n$$

n is the number of instalments.

Difference between CI and SI for n^{th} year

$$= \frac{Pr}{100}\left[\left(1+\frac{r}{100}\right)^{n-1}-1\right]$$

For Compound Interest

$$\frac{\text{increase in amount in } n^{\text{th}} \text{ year}}{\text{increase in amount in } (n+1)^{\text{th}} \text{ year}} = \frac{100}{(100+r)}$$

Similarly,

$$\frac{\text{decrease in amount in } n^{\text{th}} \text{ year}}{\text{decrease in amount in } (n+1)^{\text{th}} \text{ year}} = \frac{100}{(100-r)}$$

where r is rate of interest.

EXAMPLE 1. *Find the simple interest on Rs. 1000 at 12% per annum for 5 years.*

SOLUTION $\text{SI} = \frac{Prt}{100} = \frac{1000\times 12\times 5}{100} = \text{Rs. } 600$

{Total amount = P + SI = 1000 + 600 = Rs. 1600}

EXAMPLE 2. *Find the simple interest on Rs. 800 at 7% per annum and on Rs. 700 at 16% p.a. and on Rs. 500 at 4% p.a. for 2 years.*

SOLUTION $$\text{SI} = \frac{P_1 r_1 t_1}{100}+\frac{P_2 r_2 t_2}{100}+\frac{P_3 r_3 t_3}{100}$$

$$= \frac{800\times 7\times 2}{100}+\frac{700\times 16\times 2}{100}+\frac{500\times 4\times 2}{100}$$

$$= 112+224+40$$

$$= \text{Rs. } 376$$

EXAMPLE 3. *A sum of money (P) doubles in 10 years. In how many years it will be treble at the same rate of simple interest?*

SOLUTION $A = 2P$

$\therefore$ $\text{SI} = P$ $\quad (\text{SI} = 2P - P)$

$$P = \frac{P\times r\times 10}{100}$$

$\Rightarrow$ $r = 10\%$

So, the new amount = $3P$

But the new SI = $2P = (3P - P)$

$$2P = \frac{P\times 10\times t}{100} \quad (r = 10\%)$$

$t = 20$ years

EXAMPLE 4. *A sum of money in 3 years becomes 1344 and in 7 years it becomes Rs. 1536. What is the principal sum where simple rate of interest is to be charged ?*

(a) 4000 (b) 1500 (c) 1200 (d) 2800

SOLUTION It would be very time saving if we do it by unitary method.

1536 – 1344 = Rs. 192

Scanned by CamScanner

yoursmahboob.wordpress.com

Rs. 192 is the interest for 4 years

So, Rs. 48 is the interest for 1 year

It means Rs. 144 is the interest for 3 years at actual principal.

$\therefore$ Principal = 1344 – 144 = Rs. 1200

EXAMPLE 5. *A certain sum of money amounts to Rs. 15900 at simple rate of interest at 6% p.a. in 1 year. What is the value of principal sum ?*

(a) 12000 *(b) 18000*
(c) 15000 *(d) 14000*

SOLUTION Best way is to go through option as $\frac{15000 \times 6 \times 1}{100} = 900$

So the total amount = 15900, hence (c) is correct.

EXAMPLE 6. *A sum of money becomes 3 times in 12 years. In how many years it will become 5 times at the same rate of simple interest?*

(a) 20 years *(b) 16 years*
(c) 24 years *(d) 30 years*

SOLUTION In this type of question consider only SI not the amount. So,

(in first case) SI = 2P for principal P.

(in second case) SI = 4P for principal P.

Now since SI is directly proportional to the time at fixed rate of interest.

Therefore to make SI two times it will require 12 years

So to make SI four times it will require 24 years

Thus to make an amount 5 times of the principal requires 24 years at the given rate of interest as per question.

EXAMPLE 7. *What will be the amount when Rs. 10000 is deposited in a bank at 10% per annum compounded annually for 3 years?*

SOLUTION $A = P\left(1 + \frac{r}{100}\right)^n = 10000\left(1 + \frac{10}{100}\right)^3$

$= 10000 \times (1.1)^3$

$=$ Rs. 13310

EXAMPLE 8. *A sum of amount at r% compound interest doubles in 3 years. In 9 years it will be k times of the original principal. What is the value of k?*

(a) 10 *(b) 9* *(c) 6* *(d) 8*

SOLUTION $A = P\left(1 + \frac{r}{100}\right)^n$

1st case $2P = P\left(1 + \frac{r}{100}\right)^3$

$\Rightarrow$ $2 = \left(1 + \frac{r}{100}\right)^3$

2nd case $(2)^3 = \left[\left(1 + \frac{r}{100}\right)^3\right]^3 = \left(1 + \frac{r}{100}\right)^9$

$\Rightarrow$ $k = (2)^3 = 8$ times.

EXAMPLE 9. *Rs. 20000 is being compounded at 20% p.a. If the rate of interest is charged half yearly. What will be the amount after 2 years ?*

(a) 28292 *(b) 27292*
(c) 29282 *(d) 22358*

SOLUTION $20000\left(1 + \frac{20/2}{100}\right)^{2\times 2} = 20000\left(1 + \frac{10}{100}\right)^4$

$= 20000\,(1.1)^4$

$= 20000 \times 1.4641$

$=$ Rs. 29282

EXAMPLE 10. *If the rate of interest is 10% p.a. and Rs. 12000 lent at the compound interest, half yearly. What is the equivalent simple rate of interest for first year?*

SOLUTION $A = P\left(1 + \frac{r}{100}\right)^n = 12000\,(1.05)^2$

$= 12000 \times 1.1025$

$=$ Rs. 13230

Again SI = 13230 – 12000 = 1230

$\therefore$ $1230 = \frac{12000 \times r \times 2}{2 \times 100}$

$\Rightarrow$ $r = 10.25\%$

EXAMPLE 11. *Rs. 1000 is being charged at 50% per annum. What is the interest for 3rd year at compound interest ?*

(a) 1122 *(b) 1025* *(c) 1125* *(d) 625*

SOLUTION Total amount for two years = $1000\,(1.5)^2 = 2250$

Now, interest for third year = $\frac{2250 \times 50 \times 1}{100} = 1125$

Hence (c) is correct.

EXAMPLE 12. *CI and SI for a certain sum at certain rate of interest are Rs. 220 and Rs. 200. What is the principal for these interests?*

(a) Rs. 2200 *(b) Rs. 200*
(c) Rs. 500 *(d) Rs. 2000*

SOLUTION 220 – 200 = 20

Rs. 20 is the interest on the interest of the first year, which is Rs. $100 = \left(\frac{200}{2}\right)$

Thus the rate of interest = 20% $\left(20 = \frac{100 \times r \times 1}{100}\right)$

So the actual principal = P = 500

$\left(\text{since } 100 = \frac{P \times 20 \times 1}{100} \Rightarrow P = 500\right)$

Hence (c) is correct.

EXAMPLE 13. *The population of UP increases very rapidly @ 12% p.a. and 3 years ago its population was 1 million. What is present population?*

SOLUTION $A = 1000000\,(1.12)^3 = 1404928$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 14. *Jadeja purchased a maruti car 3 years ago for Rs. 2 lakh. Its value depreciated each year @ 25% p.a. What is the present value of the car ?*

SOLUTION $200000\left(1-\frac{25}{100}\right)^3 = 200000\times\left(\frac{3}{4}\right)^3$

$= 84{,}375$

EXAMPLE 15. *The difference between CI and SI for 3 years @ 20% p.a. is Rs. 152. What is the principal lent in each case ?*

(a) 1200 (b) 1155
(c) 1187.5 (d) none of these

SOLUTION Difference between CI and SI for 3 years = Rs. 152

$$P\left(\frac{r}{100}\right)^2\left(\frac{r}{100}+3\right)=152$$

$$P\left(\frac{1}{25}\right)\left(\frac{16}{5}\right)=152$$

$$P=\frac{152\times25\times5}{16}$$

$$P = 9.5\times25\times5 = 1187.5$$

EXAMPLE 16. *A sum is being lent at 20% p.a. compound interest. What is the ratio of increase in amount of 4th year to 5th year?*

(a) 4 : 5 (b) 5 : 4
(c) 5 : 6 (d) can't be determined

SOLUTION $$\frac{P\left(1+\frac{r}{100}\right)^4}{P\left(1+\frac{r}{100}\right)^5}=\frac{1}{\left(1+\frac{r}{100}\right)}$$

$$=\frac{100}{100+r}=\frac{100}{120}=\frac{5}{6}$$

EXAMPLE 17. *Rs. 12000 amounts to Rs. 20736 in 3 years at r% p.a. of compound interest. What is the value of r?*

(a) 10% (b) 25% (c) 12% (d) 20%

SOLUTION $$A = P\left(1+\frac{r}{100}\right)^3$$

$$20736 = 12000\left(1+\frac{r}{100}\right)^3$$

$$\Rightarrow \quad \frac{20736}{12000}=\left(1+\frac{r}{100}\right)^3$$

$$\Rightarrow \quad \frac{1728}{1000}=\left(1+\frac{r}{100}\right)^3$$

$$\Rightarrow \quad \left(\frac{12}{10}\right)^3=\left(1+\frac{r}{100}\right)^3$$

$$\Rightarrow \quad \left(1+\frac{2}{10}\right)^3=\left(1+\frac{r}{100}\right)^3$$

$$\Rightarrow \quad r = 20\%$$

Alternatively : The best way for this problem is to go through options.

$12000\times1.2 \Rightarrow 14400\times1.2 \Rightarrow 17280\times1.2 \Rightarrow 20736$

EXAMPLE 18. *A certain sum amounts to Rs. 14641 in 4 years @ 10% p.a. compounded annualy. What is the value of principal?*

(a) Rs. 6000 (b) Rs. 12000
(c) Rs. 10000 (d) data insufficient

SOLUTION $$14641 = P\left(1+\frac{10}{100}\right)^4$$

$$14641 = P\left(\frac{11}{10}\right)^4$$

$$P = 14641\times\left(\frac{10}{11}\right)^4$$

$$= 10000$$

EXAMPLE 19. *A sum of Rs. 10000 is borrowed at 8% p.a. compounded annualy which is paid back in 3 equal annual instalments. What is the amount of each instalments?*

SOLUTION $$10000 = x\left[\frac{25}{27}+\left(\frac{25}{27}\right)^2+\left(\frac{25}{27}\right)^3\right]$$

$$= x\times\frac{25}{27}\left[1+\frac{25}{27}+\frac{625}{729}\right]$$

$$=\frac{25x}{27}\left[\frac{2029}{729}\right]$$

$$\Rightarrow \quad x = \text{Rs. } 3880.335$$

Alternatively :

$$10000\,(1.08)^3 = x\,[1+(1.08)+(1.08)^2]$$

$$\Rightarrow \quad x = 3880.335$$

EXAMPLE 20. *A scooty is sold by an automobile agency for Rs. 19200 cash or for Rs. 4800 cash down payment together with five equal monthly instalments. If the rate of interest charged by the company is 12% per annum find each instalment.*

SOLUTION Balance of the price to be paid through instalments = Rs. 14400

Rate of interest (r) = 12% p.a.

$$\therefore \left(14400+\frac{14400\times12\times5}{100\times12}\right)=\left[x+\left(x+\frac{12x}{1200}\right)+\left(x+\frac{12x\times2}{12\times100}\right)+\ldots+\left(x+\frac{12x\times4}{12\times100}\right)\right]$$

$\Rightarrow x = \text{Rs. } 2964.70$, where x is the value of each instalment.

NOTE In the left hand side and right hand side given amounts are equal. Each amount is equal to the total amount payable after 5 months.

Important : For quick and smooth calculation to the problems of this chapter you can remember the following values :

Scanned by CamScanner

yoursmahboob.wordpress.com

Rate of Interest	For Rs. 100, amount				
	after one year	after 2 years	after 3 years	after 4 years	after 5 years
5%	105	110.25	115.7625	121.550625	127.62815625
6%	106	112.36	119.1016	126.247696	133.82255776
8%	108	116.64	125.9712	136.048896	146.93280768
10%	110	121.00	133.1000	146.4100	161.051
12%	112	125.44	140.4928	157.351936	176.23416832
15%	115	132.25	152.0875	174.900625	201.13571875
20%	120	144.00	172.80	207.36	248.832
25%	125	156.25	195.3125	244.140625	305.17578125
30%	130	169.00	219.70	285.61	371.293
50%	150	225.00	337.50	506.25	759.375

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. A man borrows Rs. 4000 and pays back after 5 years at 15% simple interest. The amount paid by the man is :
   (a) Rs. 1800 (b) Rs. 4800
   (c) Rs. 7500 (d) Rs. 7000

2. What is the time period for which Rs. 8000 amounts to Rs. 12000 at 20% p.a. of simple interest?
   (a) 4 years (b) 2.5 years
   (c) 3.25 years (d) 6 years

3. What is the rate of simple interest at which Rs. 14,000 gives interest of Rs. 1960 in two years?
   (a) 4% (b) 5%
   (c) 7% (d) 10%

4. What is the sum of amount which gives Rs. 6300 as interest @ 7% per annum of simple interest in $7\frac{1}{2}$ years?
   (a) 36000 (b) 24000
   (c) 63000 (d) 12000

5. If the rate of simple interest is 12% per annum, the amount that would fetch interest of Rs. 6000 per annum is :
   (a) Rs. 7200 (b) Rs. 48000
   (c) Rs. 50000 (d) Rs. 72000

6. A sum was put at simple interest at a certain rate for 2 years. Had it been put at 4% higher rate, it would have fetched Rs. 112 more. The sum is :
   (a) 1120 (b) 1400
   (c) 1200 (d) 8000

7. In what time will a sum of money double itself @ 20% per annum (p.a.) simple interest?
   (a) 10 years (b) 5 years
   (c) 2 years (d) 4 years

8. At r% per annum a sum doubles after 20 years. The rate of interest per annum is :
   (a) 4% (b) 5%
   (c) 8% (d) 10%

9. A sum of money trebles (i.e., 3 times) in 15 years at r% of simple interest per annum. What is the value of r?
   (a) 12% (b) $\frac{40}{3}$%
   (c) $\frac{50}{3}$% (d) can't be determined

10. A sum of money doubles itself in 12 years. In how many years would it treble itself?
    (a) 36 years (b) 18 years
    (c) 24 years (d) 15 years

11. Out of a sum of Rs. 625, a part was lent at 5% SI and the other at 10% SI. If the interest on the first part after 2 years is equal to the interest on the second part after 4 years, then the second sum (in Rs.) is :
    (a) 250 (b) 300
    (c) 125 (d) 275

12. A sum of Rs. 2500 is lent out in two parts; one at 12% p.a. and another at 12.5% p.a. for one year. If the total annual income is Rs. 306, the money lent at 12% is :
    (a) 1000 (b) 1200
    (c) 1500 (d) 1300

13. Akul lent Rs. 6000 to Bakul for 2 years and Rs. 1500 to camlin for 4 years and received altogether from both Rs. 900 as simple interest. The rate of interest is :
    (a) 4% (b) 8%
    (c) 10% (d) 5%

14. A person takes a loan of Rs. 200 at 5% simple interest. He returns Rs. 100 at the end of one year. In order to clear his dues at the end of 2 years, he would pay :
    (a) 125.50 (b) 110
    (c) 115.50 (d) none of these

15. A lends a sum of money for 10 years at 5% SI. B lends double the amount for 5 years at the same rate of interest. Which of the following statements is true in this regard?
    (a) A will get twice the amount of interest that B would get
    (b) B will get twice the amount of interest that A would get
    (c) A will get the same amount of interest that B would get
    (d) B will get four times the amount of interest that A would get

16. Consider the following statements.
    If a money is loaned at simple interest then the :
    (i) money gets doubled in 5 years if the rate of interest is $16\frac{2}{3}$%.
    (ii) money gets doubled in 5 years if the rate of interest is 20%.
    (iii) money becomes four times in 10 years if it gets doubled in 5 years.
    of these statements :
    (a) (i) and (iii) are correct (b) (iii) alone is correct
    (c) (ii) alone is correct (d) (ii) and (iii) are correct

17. Pratibha invests an amount of Rs. 15,860 in the names of her three daughters A, B and C in such a way that they get the same interest after 2, 3 and 4 years respectively. If the rate of simple interest is 5% p.a., then the ratio of the amounts invested among A, B and C will be :
    (a) 5 : 10 : 12 (b) $\frac{1}{10} : \frac{1}{15} : \frac{1}{20}$
    (c) 6 : 7 : 8 (d) 6 : 5 : 4

18. What annual payment will discharge a debt of Rs. 580 in 5 years, the rate being 8% p.a.?
    (a) 120 (b) 100
    (c) 80 (d) 78

Scanned by CamScanner

yoursmahboob.wordpress.com

19. Find the amount of Rs. 2500 invested at 12% during the period from 4th February, 2005 to 18 April 2005 :
(a) Rs. 3000 (b) Rs. 3800
(c) Rs. 2560 (d) Rs. 2600

20. Find the amount of Rs. 1700 invested at 16% half yearly at simple interest for one year :
(a) 2100 (b) 2244
(c) 2200 (d) 2500

21. The compound interest on Rs. 1000 at 10% p.a. in 3 years is :
(a) 331 (b) 1331
(c) 133 (d) 300

22. The compound interest on Rs. 10000 at 20% p.a. in 4 years :
(a) 10736 (b) 736
(c) 20736 (d) 7280

23. The compound interest on Rs. 4000 at 25% p.a. in 3 years :
(a) 1235 (b) 5625
(c) 3812.5 (d) 3750.5

24. The compound interest on Rs. 5000 at 30% per annum for 4 years :
(a) 4280.5 (b) 6700
(c) 9280.5 (d) 3857.5

25. A sum of Rs. 400 would become Rs. 441 after 2 years at r% compound interest, find the value of 'r' :
(a) 10% (b) 5%
(c) 15% (d) 20%

26. At compound interest, if a certain sum of money doubles in n years, then the amount will be four fold in :
(a) n^2 years (b) $2n^2$ years
(c) $2n$ years (d) $4n$ years

27. Rs. 6000 amounts to Rs. 7986 in 3 years at CI. The rate of interest is :
(a) 20% (b) 10%
(c) 6% (d) 7.5%

28. The least number of complete years in which a sum of money put at 20% CI will be more than doubled is :
(a) 4 (b) 5
(c) 6 (d) 8

29. The CI on Rs. 5000 for 3 years at 8% for first year, 10% for second year and 12% for third year will be :
(a) Rs. 1750 (b) Rs. 1652.80
(c) Rs. 1575 (d) Rs. 1685.20

30. A sum of Rs. 2400 deposited at CI, doubled after 5 years. After 20 years it will become :
(a) Rs. 24000 (b) Rs. 38400
(c) Rs. 19200 (d) can't be determine

31. A sum of Rs. 550 was taken as a loan. This is to be paid back in two equal annual instalments. If the rate of interest be 20% compounded annually, then the value of each instalments is :
(a) 300 (b) 360
(c) 250 (d) none of these

32. The difference between CI and SI on a sum of money lent for 2 years at 10% is Rs. 40. The sum is :
(a) 1600 (b)
(c) 4000 (d) none of these

33. The difference between simple and compound interest on Rs. 6000 for 1 year at 20% per annum reckoned half yearly is :
(a) 120 (b) 60
(c) 180 (d) 72

34. A certain sum amounts to Rs. 8988.8 in two years and to Rs. 9528.128 in three years, at compound interest per annum. What is the principal and rate of interest?
(a) Rs. 12,000, 5% (b) Rs. 6,000, 8%
(c) Rs. 8,000, 6% (d) Rs. 10,000, 8.5%

35. The compound interest and the simple interest for two years on a certain sum of money at a certain rate of interest are Rs. 2257.58, Rs. 2100 respectively. Find the principal and rate percent :
(a) 6000, 7% (b) 7500, 8%
(c) 14000, 10% (d) 7000, 15%

36. The compound interest on a certain sum at a certain rate of interest for the second year and third year is Rs. 21780 and Rs. 23958 respectively. What is the rate of interest?
(a) 6% (b) 12%
(c) 10% (d) 15%

37. Amit borrowed Rs. 800 at 10% rate of interest. He repaid Rs. 400 at the end of first year. What is the amount required to pay at the end of second year to discharge his loan which was calculated at compound interest?
(a) 420 (b) 440
(c) 450 (d) 528

38. A sonata watch is sold for Rs. 440 cash or for Rs. 200 cash down payment together with Rs. 244 to be paid after one month. Find the rate of interest charged in the instalment scheme :
(a) 10% (b) 15%
(c) 20% (d) 25%

39. A cellphone is available for Rs. 600 or for 300 cash down payment together with Rs. 360 to be paid after two months. Find the rate of interest charged under this scheme :
(a) 20% (b) 50%
(c) 120% (d) none of these

40. Abhinav purchases a track suit for Rs. 2400 cash or for Rs. 1000 cash down payments and two monthly instalments of Rs. 800 each. Find the rate of interest :
(a) 75% (b) 120%
(c) 50% (d) none of these

41. Indicom cell-phone is available for Rs. 2500 cash or Rs. 520 cash down payments followed by 4 equal monthly instalments. If the rate of interest charged is 25% per annum, calculate the monthly instalment :
(a) 520 (b) 480
(c) 550 (d) none of these

42. An article is sold for Rs. 500 cash or for Rs. 150 cash down payments followed by 5 equal monthly instalments. If the rate of interest charged is 18% p.a., compute the monthly instalment :
(a) 63.07% (b) 37.06%
(c) 75.0% (d) 73.06%

43. A sum of Rs. 390200 is to be paid back in three equal annual instalments. How much is each instalment, if the rate of interest charged is 4% per annum compounded annually?
(a) Rs. 140608 (b) Rs. 120560
(c) Rs. 10000 (d) Rs. 18000

44. Purnima borrowed a sum of money and returned it in three equal quarterly instalments of Rs. 17576 each. Find the sum borrowed, if the rate of interest charged was 16% per annum compounded quarterly. Find also the total interest charged :
(a) 46900 and 4700 (b) 48775 and 3953
(c) 68320 and 1200 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

45. Sunidhi borrowed Rs. 10815, which is to be paid back in 3 equal half yearly instalments. If the interest is compounded half yearly at $\frac{40}{3}$% per annum, how much is each instalment?
(a) 2048 (b) 3150
(c) 4096 (d) 5052

46. Sapna borrowed some money on compound interest and returned it in three years in equal annual instalments. If the rate of interest is 15% per annum and annual instalment is Rs. 466680, find the sum borrowed :
(a) 1112220 (b) 1111200
(c) 1122000 (d) none of these

47. P and Q invest some amount under SI and CI repectively but for the same period at 6% per annum. Each gets a total amount of Rs. 65,000 at the end of 6 years. Which of the following is definitely true?
(i) Q's initial principal is less than that of P
(ii) Q's initial principal is equal to that of P
(iii) P's percentage earning is less than that of Q
(a) (i) only (b) (ii) only
(c) (iii) only (d) (i) and (iii) only

48. In the above (i.e., previous) problem, what is the ratio of P's final amount to that of Q, if P and Q invest the same amounts?
(a) $(1.06)^6$ (b) $\frac{136}{100} \times \left(\frac{100}{106}\right)^6$
(c) $\frac{100}{136} \times \left(\frac{106}{100}\right)^6$ (d) none of these

49. Mr. Lala Ram has lent some money to Aaju at 6% p.a. and the Baaju at 8% p.a. At the end of the year he has gain the overall interest at 7% per annum. In what ratio has he lent the money to Aaju and Baaju?
(a) 2 : 3 (b) 1 : 1
(c) 5 : 6 (d) 4 : 3

50. The difference between simple and compound interest for the fourth year is Rs. 7280 at 20% p.a. What is the principal sum?
(a) 10000 (b) 50000
(c) 1 lakh (d) 40000

51. The simple interest on certain sum at 5% for 9 month is Rs. 10 greater than the simple interest on the same sum @ 3% for 14 months. What is the sum of interest in both the cases (i.e., total sum of interest)?
(a) Rs. 130 (b) Rs. 290
(c) Rs. 120 (d) Rs. 330

52. Mr. Bajaj invested $\frac{1}{7}$ of his total investment at 4% and $\frac{1}{2}$ at 5% and rest at 6% for the one year and received total interest of Rs. 730. What is the total sum invested?
(a) Rs. 70000 (b) Rs. 14000
(c) Rs. 24000 (d) Rs. 38000

53. The rate of interest in two banks DNB and HBI are in the ratio of 7 : 8. If a person invested some amount in both the banks and received equal amounts from both the banks in two year. The ratio of amount invested in DNB and HBI respectively is :
(a) 15 : 1 (b) 8 : 7
(c) 7 : 8 (d) 108 : 107

54. The ratio of CI for 3 years and SI for 1 year for a fixed amount at a rate of r% is 3.64. What is the value of r?
(a) 10% (b) 15%
(c) 20% (d) none of these

55. A sum of money becomes 13/5 times of itself in 32 years at r% of SI. What is the value of r?
(a) 6% (b) 7%
(c) 5% (d) 18%

56. The difference between interest received by A and B is Rs. 18 on Rs. 1500 for 3 year. What is the difference in rate of interest?
(a) 1% (b) 2.5%
(c) 0.5% (d) 0.4%

LEVEL 2

1. The compound interest on a certain sum for 2 years is Rs. 756 and SI (simple interest) is Rs. 720. If the sum is invested such that the SI is Rs. 900 and the number of years is equal to the rate per cent per annum, find the rate per cent :
(a) 4 (b) 5
(c) 6 (d) 1.0

2. Jalela and Dalela have to clear their respective loans by paying 3 equal annual instalments of Rs. 30000 each. Jalela pays @ 10% per annum of simple interest while Dalela pays 10% per annum compound interest. What is the difference in their payments?
(a) Rs. 300 (b) Rs. 425
(c) Rs. 245 (d) Rs. 333.33

3. Akbar lends twice the interest received from Birbal to Chanakya at the half of the interest at which he lent to Birbal. If Akbar lent Rs. P @ r% per annum for 1 year to Birbal then the interest received by Akbar from Chanakya is :
(a) $\frac{Pr^2}{100}$ (b) $\left(\frac{Pr}{10}\right)^2$
(c) $P\left(\frac{r}{10}\right)^2$ (d) $P\left(\frac{r}{100}\right)^2$

4. Equal amounts of each Rs. 43892 is lend to two persons for 3 years. One @ 30% SI and second @ 30% CI annually. By how much per cent the CI is greater than the simple interest received in this 3 years duration?
(a) 23% (b) 33%
(c) 33.33% (d) none of these

5. Rs. 3500 was lent partly @ 4% and partly @ 6% SI. The total interest received after 3 years is 498. What is the amount lent @ 4% SI?
(a) Rs. 1300 (b) Rs. 1800
(c) Rs. 200 (d) Rs. 2200

6. The population of vultures in a particular locality is decreases by a certain rate of interest (compounded annually). If the current population of vultures be 29160 and the ratio of decrease in population for second year and 3rd year be 10 : 9. What was the population of vultures 3 years ago?
(a) 30000 (b) 35000
(c) 40000 (d) 50000

7. The ratio of the amount for two years under CI annually and for one year under SI is 6 : 5. When the rate of interest is same, then the value of rate of interest is :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 12.5% (b) 18%
(c) 20% (d) 16.66%

8. A bicycle can be purchased on cash payment of Rs. 1500. The same bicycle can also be purchased at the down payment (initial payment, at the time of purchasing) of Rs. 350 and rest can be paid in 3 equal installments of Rs. 400 for next 3 months. The rate of SI per annum charged by the dealer is :

(a) $23\frac{9}{17}\%$ (b) $17\frac{9}{23}\%$
(c) $13\frac{9}{17}\%$ (d) none of these

9. Data Ram lends equal sum of money at the same rate of interest to *A* and *B*. The money lends to *A* becomes twice of the original amount in just four years at simple interest. While Data Ram lends to *B* for the first two years at compound interest and for the rest two years at simple interest. If the difference between the amount of *A* and *B* after 4 years is Rs. 2750. What is the amount of money that Data Ram lends to each one?

(a) Rs. 40000 (b) Rs. 6000
(c) Rs. 8000 (d) Rs. 80000

10. Akram Ali left an amount of Rs. 340000 to be divided between his two sons aged 10 years and 12 years such that both of them would get an equal amount when each attain 18 years age. What is the share of elder brother if the whole amount was invested at 10% simple interest :

(a) 12000 (b) 16000
(c) 160000 (d) 180000

11. Satyam took loan from IDIDI Bank for his 2 years course of MBA at IMD. He took the loan of Rs. 6 lakh such that he would be charged at 8% per annum at CI during his course and at 10% CI after the completion of course. He returned half of the amount which he had to be paid on the completion of his studies and remaining after 2 years. What is the total amount returned by Satyam ?

(a) Rs. 7.73323 lakh (b) Rs. 7.58 lakh
(c) Rs. 7.336 lakh (d) none of these

12. We had 1000 goats at the beginning of year 2001 and the no. of goats each year increases by 10% by giving birth (compounded annually). At the end of each year we double the no. of goats by purchasing the same no. of goats as there is the no. of goats with us at the time. What is the no. of goats at the beginning of 2004?

(a) 10600 (b) 10648
(c) 8848 (d) 8226

13. Rs. 100000 was invested by Mohan in a fixed deposit @ 10% per annum at CI. However every year he has to pay 20% tax on the compound interest. How much money does Mohan has after 3 year?

(a) 128414 (b) 108000
(c) 126079.2 (d) none of these

14. A property dealer bought a rectangular plot (of land) in Noida 5 years ago at the rate of Rs. 1000 per m^2. The cost of plot is increases by 5% in every 6 years and the worth of a rupee falls down at a rate of 2% in every 5 years. What is the approximate value of the land per meter^2 25 years hence?

(a) Rs. 995 (b) Rs. 1134
(c) Rs. 1500 (d) Rs. 1495

15. *A* and *B* run a joint venture in which the profit earned by *A* and *B* are in the ratio 28 : 15. A invest his share at the start of the year and *B* joins in after 9 months of the same year. What is the ratio of their initial investment respectively?

(a) 7 : 15 (b) 8 : 13
(c) 5 : 17 (d) 15 : 7

16. In the previous problem if *A* gets a profit of Rs. 4200 the amount invested by *B* is :

(a) 2250 (b) 2600
(c) 1350 (d) can't be determined

17. Arvind and Govind each invested Rs. 15000 for 3 years at the same rate of interest but Arvind's investment is compounded annually while Govind's investment is charged on simple interest. What amount did Arvind receive more than Govind?

(a) Rs. 680 (b) Rs. 3450
(c) data insufficient (d) none of these

18. Shyam Lal takes a loan of Rs. 10500 at 10% p.a. compounded annually which is to be repaid in two equal annual instalments. One at the end of one year and the other at the end of the second year. The value of each instalments is :

(a) 5987 (b) 6050
(c) 6352.5 (d) 5678.5

19. Hari Lal and Hari Prasad have equal amounts. Hari Lal invested all his amount at 10% compounded annually for 2 years and Hari Prasad invested 1/4 at 10% compound interest (annually) and rest at r% per annum at simple interest for the same 2 years period. The amount received by both at the end of 2 year is same. What is the value of *r*?

(a) 14% (b) 12.5%
(c) 10.5% (d) 11%

20. The annual sales of a company in the year 2000 was Rs. 1000 and in the year 2005 was Rs. 2490. Find the compounded annual growth rate (CAGR) of sales in the given period of the same company :

(a) 14.289% (b) 10%
(c) 15% (d) 20%

21. HDFC lends 1 million to HUDCO at 10% simple interest p.a. for 2 years and HUDCO lends the same amount to SAHARA STATES HOUSING corporation at 10% p.a. of compound interest for 2 years. What is the earning of HUDCO in this way?

(a) Rs. 133100 (b) Rs. 33100
(c) Rs. 131000 (d) no profit no loss

22. ICICI lent Rs. 1 lakh to captain Ram Singh @ 6% per annum of simple interest for 10 years period. Meanwhile ICICI offered a discount in rate of interest for armed forces. Thus the rate of interest ICICI decreased to 4%. In this way Ram Singh had to pay total amount 1.48 lakh.

After how many year Ram Singh got the discount in rate of interest?

(a) 3 years (b) 4 years
(c) 6 years (d) 5 years

23. Sanjay purchased a hotel worth Rs. 10 lakh and barkha purchased a car worth Rs. 16 lakh. The value of hotel every year increases by 20% of the previous value and the value of car every year depreciates by 25%. What is the difference between the price of hotel and car after 3 years?

(a) Rs. 925000 (b) Rs. 10,53,000
(c) remains constant (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

1 (d)	2. (b)	3. (c)	4. (d)	5. (c)	6. (b)	7. (b)	8. (b)	9. (b)	10. (c)
1. (c)	12. (d)	13. (d)	14. (c)	15. (c)	16. (c)	17. (b)	18. (b)	19. (c)	20. (b)
1. (a)	22. (a)	23. (c)	24. (c)	25. (b)	26. (c)	27. (b)	28. (a)	29. (b)	30. (b)
1. (b)	32. (c)	33. (b)	34. (c)	35. (d)	36. (c)	37. (d)	38. (c)	39. (c)	40. (b)
1. (a)	42. (d)	43. (a)	44. (b)	45. (c)	46. (b)	47. (d)	48. (b)	49. (b)	50. (b)
1. (b)	52. (b)	53. (b)	54. (c)	55. (c)	56. (d)				

VEL-2

1 (b)	2. (a)	3. (d)	4. (b)	5. (d)	6. (c)	7. (c)	8. (d)	9. (c)	10. (d)
11. (a)	12. (b)	13. (d)	14. (b)	15. (a)	16. (d)	17. (c)	18. (b)	19. (c)	20. (a)
21. (c)	22. (b)	23. (b)							

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL (1)

1. $4000 + (4000 \times 5 \times 0.15) = \text{Rs. } 7000$

2. $(12000 - 8000) = \dfrac{8000 \times t \times 20}{100}$

$\Rightarrow \quad t = \dfrac{5}{2}$ years

3. $1960 = \dfrac{14000 \times r \times 2}{100} \Rightarrow r = 7\%$

4. $6300 = \dfrac{P \times 7 \times 15}{100 \times 2}$

$\Rightarrow \quad P = \text{Rs. } 12000$

5. $6000 = \dfrac{P \times 12 \times 1}{100}$

$\Rightarrow \quad P = 50000$

6. In my opinion this question should be solved by unitary method instead of making complex solution

Years	Rate of Interest	Interest
2	4%	112
2	1%	28
1	1%	(14)

It means the principal sum is Rs. 1400

Alternatively: $\dfrac{P}{100} \times 2[(r+4) - r] = 112$

$\Rightarrow \quad P = 1400$

7. $SI = 2P - P = P$ (Interest = Amount − Principal)

$P = \dfrac{P \times 20 \times t}{100} \Rightarrow t = 5$ years

8. $P = \dfrac{P \times r \times 20}{100}$ (Interest = Amount − Principal)

$\Rightarrow \quad r = 5\%$ p.a.

9. $2P = \dfrac{P \times 15 \times r}{100}$ $(2P = 3P - P)$

$r = \dfrac{40}{3}\%$ p.a.

10. $P = \dfrac{P \times r \times 12}{100} \Rightarrow r = \dfrac{100}{12}\%$ p.a.

Now, $2P = \dfrac{P \times 100 \times t}{12 \times 100} = 24$ years

Shortcut (for SI) Since SI in second case is double the SI in first case, so the time period will also be double since SI is directly proportional to the time period, provided that rate of interest be same and principal as well.

11. $\dfrac{P_1 \times 5 \times 2}{100} = \dfrac{P_2 \times 10 \times 4}{100}$

$\Rightarrow \quad P_1 : P_2 = 4 : 1$

Therefore second principal is Rs. $125 \left(= 625 \times \dfrac{1}{5}\right)$

Alternative: Go through options.

12. Best way is to go through option

So, $1300 \times 0.12 + 1200 \times 0.125 = 306$

Hence, (d) is the correct option.

Alternatively: Solve through alligation

Therefore the ratio of first principal to the second principal is 13 : 12.



$306 = \dfrac{2500 \times r \times 1}{100}$

$r = \dfrac{306}{25} = 12.24$

13. $\left(\dfrac{6000 \times 2 + 1500 \times 4}{100}\right) r = 900$

$\Rightarrow \quad r = 5\%$

14. Amount to be paid in first year $= \dfrac{200 \times 5 \times 1}{100} + 200 = 210$

Amount left as a principal for the second year

$= 210 - 100 = 110$

$\therefore$ Amount paid in second year $= 110 + \dfrac{110 \times 5 \times 1}{100} = 115.5$

15.

A	B
$P_A = P$	$P_B = 2P$
$r_A = 5\%$	$r_B = 5\%$
$t = 10$ years	$t = 5$ years
Interest of $A = \dfrac{P \times 5 \times 10}{100} = \dfrac{P}{2}$	Interest of $B = \dfrac{2P \times 5 \times 5}{100} = \dfrac{P}{2}$

Hence (c) is correct

16. **Statement (I)** $\dfrac{P \times 5 \times 50}{100 \times 3} \neq P$, hence wrong

Statement (II) $SI = \dfrac{P \times 5 \times 20}{100} = P$, hence correct

Statement (III) $P = \dfrac{P \times 5 \times r}{100} \Rightarrow r = 20\%$

Again $SI = \dfrac{P \times 10 \times 20}{100} = 2P$ hence wrong

17. $\dfrac{P_1 \times 2 \times 5}{100} = \dfrac{P_2 \times 3 \times 5}{100} = \dfrac{P_3 \times 4 \times 5}{100}$

$\Rightarrow \quad 10P_1 = 15P_2 = 20P_3$

$\Rightarrow \quad P_1 : P_2 : P_3 = 30 : 20 : 15 = \dfrac{1}{10} : \dfrac{1}{15} : \dfrac{1}{20}$

Scanned by CamScanner

yoursmahboob.wordpress.com

18. $580 = \left[(x) + \left(x + \frac{x \times 1 \times 8}{100}\right) + \left(x + \frac{x \times 2 \times 8}{100}\right) + \left(x + \frac{x \times 3 \times 8}{100}\right) + \left(x + \frac{x \times 4 \times 8}{100}\right)\right]$

$$580 = 5x + \frac{8x}{10} = \frac{58x}{10}$$

$$\Rightarrow \quad x = 100$$

19. Time period = Feb 24 + March 31 + April 18

$$= 73 \text{ days} = \frac{1}{5} \text{ year}$$

$$\therefore \quad 2500 + \frac{2500 \times 12 \times 1}{100 \times 5} = \text{Rs. } 2560$$

20. $1700 + \frac{1700 \times 16 \times 2}{100} = \text{Rs. } 2244$

21. $A = P\left(1 + \frac{r}{100}\right)^n$

$$A = 1000\left(1 + \frac{10}{100}\right)^3$$

$$A = 1000 \times (1.1)^3$$

$$A = 1331$$

$$\therefore \quad CI = A - P = 1331 - 1000 = 331$$

22. $A = 10000 \times (1.2)^4$

$$A = 10000 \times 2.0736$$

$$A = 20736$$

$$CI = A - P$$

$$CI = 20736 - 10000 = 10736$$

23. $CI = [4000 \times (1.25)^3] - (4000)$

$$= 4000 \times 1.953125 - 4000$$

$$= 4000 \times 0.953125$$

$$= 3812.5$$

24. $CI = 5000 \times (1.3)^4 - 5000$

$$= 5000 \times 2.8561 - 5000$$

$$= 5000\,(1.8561)$$

$$= 9280.5$$

25. $441 = 400\left(1 + \frac{r}{100}\right)^2$

$$\Rightarrow \quad \frac{21}{20} = 1 + \frac{r}{100}$$

$$\Rightarrow \quad r = 5\%$$

26. Since, $A = 2P$, then

$$2P = P\left(1 + \frac{r}{100}\right)^n$$

$$\Rightarrow \quad 2 = \left(1 + \frac{r}{100}\right)^n$$

$$\Rightarrow \quad 4 = (2)^2 = \left[\left(1 + \frac{r}{100}\right)^n\right]^2 = \left[\left(1 + \frac{r}{100}\right)^{2n}\right]$$

$$\Rightarrow \quad \text{time period} = 2n \qquad \{\because (a^m)^n = a^{m.n}\}$$

(This question can be easily done by considering some appropriate values)

27. $7986 = 6000\left(1 + \frac{r}{100}\right)^3$

$$\frac{7986}{6000} = \left(1 + \frac{r}{100}\right)^3$$

$$\Rightarrow \quad \frac{1331}{1000} = \left(1 + \frac{r}{100}\right)^3$$

$$\Rightarrow \quad \frac{11}{10} = \left(1 + \frac{r}{100}\right)$$

$$\Rightarrow \quad r = 10\%$$

Alternatively: Go through options.

$$6000 \xrightarrow{+10\%} 6600 \xrightarrow{+10\%} 7260 \xrightarrow{+10\%} 7986$$

Hence, assumed option is correct.

28. Go through option

$$1 \times (1.2) = 1.2$$

$$1 \times (1.2)^2 = 1.44$$

$$1 \times (1.2)^3 = 1.728$$

$$1 \times (1.2)^4 = 2.0736$$

Hence minimum 4 years are required to double the sum.

29. $A = P\left(1 + \frac{R_1}{100}\right)\left(1 + \frac{R_2}{100}\right)\left(1 + \frac{R_3}{100}\right)\ldots$

$$A = 5000\,(1.08)\,(1.1)\,(1.12)$$

$$A = 6652.8$$

$$CI = 1652.8 = (6652.8 - 5000)$$

30. $2P = P\left(1 + \frac{r}{100}\right)^5$

$$\Rightarrow \quad 2 = \left(1 + \frac{r}{100}\right)^5$$

Now, $(2)^4 = \left(\left(1 + \frac{r}{100}\right)^5\right)^4 = \left(1 + \frac{r}{100}\right)^{20}$

$\Rightarrow$ The amount becomes 16 $(= 2^4)$ times

$\therefore$ Hence (b) is correct, $\because (2400 \times 16 = 38400)$

31. $550 = x\left[\left(\frac{1}{1.2}\right) + \left(\frac{1}{1.2}\right)^2\right]$

$$\Rightarrow \quad 550 = x\left[\frac{2.2}{1.44}\right]$$

$$\Rightarrow \quad x = \text{Rs. } 360$$

32. Difference between CI and SI for 2 years $= P\left(\frac{r}{100}\right)^2$

$$40 = P\left(\frac{10}{100}\right)^2 \quad \Rightarrow \quad P = 4000$$

Alternatively: Go through options

	First year	Second year	
SI	400	400	40
CI	400	440	

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively: Go back in the reverse process.
Rs. 40 at 10% implies that the principal for this interest was Rs. 400. Again by the same logic Rs. 400 as interest obtained at the principal of Rs. 4000 at 10%.

33. $6000\left(\frac{10}{100}\right)^2 = 60$

34. $$\frac{P\left(1+\frac{r}{100}\right)^3}{P\left(1+\frac{r}{100}\right)^2} = \left(1+\frac{r}{100}\right)$$

$$\therefore \quad \frac{9528.128}{8988.8} = \left(1+\frac{r}{100}\right)$$

$$\Rightarrow \quad \left(1+\frac{84270}{1404500}\right) = \left(1+\frac{r}{100}\right)$$

$$\Rightarrow \quad \left(1+\frac{6}{100}\right) = \left(1+\frac{r}{100}\right)$$

$$\Rightarrow \quad r = 6\%$$

So, $$8988.8 = P\left(1+\frac{6}{100}\right)^3$$

$$\Rightarrow \quad P = 8000$$

Alternatively: Best way is to go through options.

35. Difference between CI and SI for 2 years will be equal to the interest on SI for first year.

Hence, $6000 \times 0.07 \Rightarrow 420 \times 0.07 = 29.4 \neq 157.5$

and $7500 \times 0.08 \Rightarrow 600 \times 0.08 = 48 \neq 157.5$

and $14000 \times 0.1 \Rightarrow 1400 \times 0.1 = 140 \neq 157.5$

and $7000 \times 0.15 \Rightarrow 1050 \times 0.15 = 157.5 = 157.5$

Thus option (d) is correct.

36. $$\frac{P\left(1+\frac{r}{100}\right)^3}{P\left(1+\frac{r}{100}\right)^2} = \left(1+\frac{r}{100}\right)$$

$$\frac{23958}{21780} = \left(1+\frac{r}{100}\right)$$

$$1+\frac{2178}{21780} = 1+\frac{r}{100}$$

$$\boxed{r = 10\%}$$

Alternatively: Remember the difference between compound interest of any two consecutive years will be same as the interest on the amount of total previous years.

So, $23958 - 21780 = 2178$

Now $$r = \frac{2178}{21780} \times 100$$

$$r = 10\%$$

37. Amount to be paid at the end of 2 year

$$= \frac{800 \times 10 \times 2}{100} + 800 = 880$$

Amount left as principal for the second year

$$= 480 = (880 - 400)$$

Amount to be paid after 2nd year $= 480 + \frac{480 \times 10}{100}$

$$= \text{Rs. } 528$$

38. Principal for next month = 440 – 200 = 240

Amount paid after next month = 244

Therefore interest charged at Rs. 240 = 4

$$\therefore \quad 4 = \frac{240 \times r \times 1}{12 \times 100}$$

$$r = 20\% \text{ per annum}$$

39. Amount as a principal for first and second month = 600 – 300 = Rs. 300

Now, interest = 360 – 300 = Rs. 60

$$\therefore \quad 60 = \frac{300}{100} \times \frac{2}{12} \times r$$

$$r = 120\%$$

40. Amount as a principal for 2 month = 2400 – 1000 = 1400
At the rate of r% per annum after 2 months, Rs. 1400 will amount to

$$\text{Rs.}\left(1400 + \frac{1400 \times r \times 2}{100 \times 12}\right) \quad \ldots(i)$$

Again total amount for the 2 instalments at the end of second month will be

$$\text{Rs}\left[800 + \left(800 + \frac{800 \times r \times 1}{100 \times 12}\right)\right] \quad \ldots(ii)$$

from (i) and (ii), we get

$$1400 + \frac{2800r}{1200} = 1600 + \frac{800r}{1200}$$

$$\frac{2000r}{1200} = 200$$

$$\Rightarrow \quad r = 120\%$$

41. Balance price to be paid in instalments = 1980
At the rate of r% per annum after 4 months, Rs. 1980 will amount to Rs. $\left(1980 + \frac{1980 \times 4 \times 25}{12 \times 100}\right) = \text{Rs. } 2145$ ...(i)

Now, the total amount for the 4 instalments at the end of fourth month will be

$$\left[x + \left(x + \frac{25x \times 1}{12 \times 100}\right) + \left(x + \frac{25x \times 2}{12 \times 100}\right) + \left(x + \frac{25 \times 3x}{12 \times 100}\right)\right]$$

$$= 4x + \frac{25x}{1200}(1 + 2 + 3)$$

$$= \frac{33x}{8} \quad \ldots(ii)$$

from (i) and (ii) $\frac{33x}{8} = 2145$

$$\boxed{x = 520}$$

42. Balance price to be paid in instalments = 350
At the rate of r% per annum after 5 months, Rs. 350 will amount to

$$\text{Rs.}\left(350 + \frac{350 \times 18 \times 5}{12 \times 100}\right) = \left(350 + \frac{1750 \times 18}{1200}\right) \quad \ldots(i)$$

Again, total amount for the 5 instalments at the end of 5th month will be

Scanned by CamScanner

yoursmahboob.wordpress.com

$$\text{Rs.}\left[x+\left(x+\frac{18x\times1}{1200}\right)+\left(x+\frac{18x\times2}{12\times100}\right)+\left(x+\frac{18x\times3}{12\times100}\right)+\left(x+\frac{18x\times4}{12\times100}\right)\right]$$

$$=\left[5x+\frac{18x}{1200}(1+2+3+4)\right]$$

$$=5x+\frac{180x}{1200}=\left(\frac{6180x}{1200}\right) \quad \ldots(ii)$$

from (i) and (ii), we get

$$\left(350+\frac{1750\times18}{1200}\right)=\frac{6180x}{1200}$$

$$\Rightarrow \quad x=73.058$$

43. Let each instalments be Rs. x
The amount to be paid instalments = 390200
The total value of all the three instalments is

$$\text{Rs.}\left[x\left(\frac{25}{26}\right)+x\left(\frac{25}{26}\right)^2+x\left(\frac{25}{26}\right)^3\right]$$

and this must be equal to Rs. 390200

Hence, $x\times\frac{25}{26}\left[1+\frac{25}{26}+\frac{625}{676}\right]=390200$

$$x=\text{Rs. } 140608$$

44. Rate of interest = 16% annum
Actual rate of interest = 4% per quarter
Principal of all three instalments

$$=\left[17576\left(\left(\frac{25}{26}\right)+\left(\frac{25}{26}\right)^2+\left(\frac{25}{26}\right)^3\right)\right]$$

$$=\frac{17576\times25\times1951}{26\times676}$$

$$=48775$$

Total amount paid = Rs. $17576\times3=52728$

Interest charged = $52728-48775=3953$

45. Rate of interest $=\frac{40/3}{2}\%=\frac{20}{3}\%$ half yearly

$$\therefore \quad 10815=x\left[\frac{15}{16}+\left(\frac{15}{16}\right)^2+\left(\frac{15}{16}\right)^3\right]$$

$$\Rightarrow \quad x=4096$$

46. $$P=486680\left[\frac{20}{23}+\left(\frac{20}{23}\right)^2+\left(\frac{20}{23}\right)^3\right]$$

$$\Rightarrow \quad P=\left[486680\times\frac{20}{23}\left(1+\frac{20}{23}+\frac{400}{529}\right)\right]$$

$$P=1111200$$

47.



Obviously $P_S > P_C$, therefore percentage gain of P_C is greater than P_S.

48. $$A_S=P+\frac{P\times6\times6}{100}=P\left(\frac{136}{100}\right)$$

$$A_C=P\left(1+\frac{6}{100}\right)^6=P\left(\frac{106}{100}\right)^6$$

$$\therefore \quad \frac{A_S}{A_C}=\frac{136}{100}\times\left(\frac{100}{106}\right)^6$$

49.



50. Difference between CI and SI for n^{th} year

$$=\frac{Pr}{100}\left[\left(1+\frac{r}{100}\right)^{n-1}-1\right]$$

$$7280=\frac{P\times20}{100}[(1.2)^3-1]$$

$$\Rightarrow \quad P=50000$$

Alternatively:

	Initially	Ist year	IInd year	IIIrd year	IVth year
SI	10000	12000	14000	16000	18000
CI	10000	12000	14400	17280	20736

CI for 4th year = 20736 − 17280 = 3456

SI for 4th year = 2000

Difference between CI and SI = 1456 for Rs. 10000
So, the difference of Rs. 7280 is for Rs. 50000

51. $$\frac{P\times5\times9}{100\times12}-\frac{P\times14\times3}{100\times12}=10$$

$$\Rightarrow \quad P=\text{Rs. } 4000$$

Now, $\frac{4000}{100\times12}[5\times9+14\times3]=\text{Rs. } 290$

52. Let the principal be x, then

$$\frac{\left(\frac{x}{7}\times4+\frac{x}{2}\times5+\frac{5x}{14}\times6\right)}{100}=730$$

$$\Rightarrow \quad x=14000$$

Alternatively: Go through suitable options.
Choose any middlemost option so that if the chosen option is not correct, then you can determine that whether you have to increase or decrease the value of the choices given.

53. $$\frac{P_1\times2\times7x}{100}=\frac{P_2\times2\times8x}{100}$$

$$\Rightarrow \quad \frac{P_1}{P_2}=\frac{8}{7}$$

54. $$\frac{P\left[\left(1+\frac{r}{100}\right)^3-1\right]}{\frac{pr}{100}}=\frac{\left(1+\frac{r}{100}\right)^3-1}{\frac{r}{100}}=3.64$$

Now go through options and verify

Scanned by CamScanner

your smartbook.wordpress.com

$$\frac{\left(1+\frac{20}{100}\right)^3-1}{\frac{20}{100}}=\frac{(1.2)^3-1}{0.2}$$

$$=\frac{0.728}{0.2}=3.64$$

Hence (c) is correct.

55. $\frac{13p}{5}-p=\frac{8p}{5}$

Now, $\frac{8}{5}P=\frac{P\times r\times 32}{100}$

$\Rightarrow$ $r=5\%$

56. $\frac{1500\times 3}{100}(r_1-r_2)=18$

$\Rightarrow$ $r_1-r_2=0.4$

LEVEL 2

1. CI for 2 years = Rs. 756
SI for 2 years = Rs. 720
It means the interest on the interest of the first year = Rs. 36 (= 756 – 720)
This implies that the rate of interest is 10%

as $\frac{36}{360}\times 100=10\%$

It means the principal for first year was Rs. 3600

$\because$ $\frac{P\times 10\times 1}{100}=360$

$\Rightarrow$ $P=3600$

Now, $\frac{P\times k\times k}{100}=\text{SI}$, where $r=t=k$

$\frac{3600\times k^2}{100}=900$

$\Rightarrow$ $k=5$

2. $30000(1+1.1+(1.1)^2)-30000(1+1.1+1.2)$

$\Rightarrow$ Rs. 300

$$30{,}000\left(1+\frac{10}{100}\right)^2-\frac{30{,}000\times 10\times 2}{100}$$

$\Rightarrow$ Rs. 300

3. Interest received from Birbal = $\frac{Pr}{100}$

Interest received from Chanakya = $\frac{\left(2\frac{Pr}{100}\right)\times\frac{r}{2}}{100}$

$=P\left(\frac{r}{100}\right)^2$

4. $100(1.3)^3=219.7$

$\Rightarrow$ CI = 119.7

and $\text{SI}=\frac{100\times 3\times 30}{100}=90$

$\therefore$ CI is greater than SI by Rs. 29.7 (119.7 – 90)

$\therefore$ % increase = $\frac{29.7}{90}\times 100=33.0\%$

5. The best way is to go through options

$$\frac{2200\times 4\times 3}{100}+\frac{1300\times 6\times 3}{100}=\text{Rs. }498$$

Hence the presumed option is correct.

NOTE When we consider Rs. 2200 for 4%, then the rest amount *i.e.*, Rs. 1300 = (3500 – 2200) will be considered automatically for 6%.

Alternatively: Average % rate = $\frac{166}{35}\%$

$\left[\because 498=\frac{3500\times r\times 3}{100}\right]$ $\Rightarrow$ $r=\frac{166}{35}\%$

$\therefore$ $\frac{35}{35}\times 4$ — $\frac{166}{35}$ — $6\times\frac{35}{35}$

$\frac{44}{35}$: $\frac{26}{35}$

22 : 13

Thus the ratio of principal at 4% and 6% will be in the ratio of 22 : 13 respectively.

6. $\frac{\text{Decreases in second year}}{\text{Decreases in third year}}=\frac{100}{100-r}=\frac{10}{9}$

$\Rightarrow$ $r=10\%$

Let the population of vultures 3 years ago be P, then

$$P\left(1-\frac{10}{100}\right)^3=29160$$

$\Rightarrow$ $P=40000$

7. On the second year (in terms of CI) is

$$\frac{P\left(1+\frac{r}{100}\right)^2}{\left(P+\frac{Pr}{100}\right)}=\frac{6}{5}\quad\Rightarrow\quad\left(1+\frac{r}{100}\right)=\frac{6}{5}$$

$\Rightarrow$ $r=20\%$

8. Balance price to be paid in instalments = Rs. 1150 ...(i)

$\because$ $(1500-350)=1150$

Now, the total amount for the next 3 instalments at the end of 3rd month will be

$$\left(1150+\frac{1150\times r\times 3}{12\times 100}\right)=$$

$$\left[400+\left(400+\frac{400\times r\times 1}{100\times 12}\right)+\left(400+\frac{400\times r\times 2}{100\times 12}\right)\right]$$

$$\left(\frac{46000+115r}{40}\right)=\left(1200+\frac{400\times 3r}{1200}\right)$$

$\Rightarrow$ $r=\frac{80}{3}=26.66\%$ ...(ii)

9. A: $P=\frac{P\times 4\times r}{100}$

$\Rightarrow$ $r=25\%$

B: $P\left(1+\frac{25}{100}\right)^2=\frac{25P}{16}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Again $\frac{25P}{16} \times \frac{2 \times 25}{100} = \frac{25P}{32}$

Therefore total amount of A after 4 years $= 2P$

and total amount of B after 4 years $= \frac{25P}{16} + \frac{25P}{32} = \frac{75P}{32}$

Therefore difference in amount $= \frac{75P}{32} - 2P = \frac{11P}{32} = 2750$

$\Rightarrow$ $P = 8000$

10. Go through options

$$1.8 + \frac{1.8 \times 6 \times 10}{100} = 1.6 + \frac{1.6 \times 8 \times 10}{100},$$

Hence (d) is correct.

Alternatively: $P_1 + \frac{P_1 \times 6 \times 10}{100} = P_2 + \frac{P_2 \times 8 \times 10}{100}$

$\Rightarrow$ $\frac{P_1}{P_2} = \frac{9}{8}$

11. Amount which is to be returned on completion of studies

$= 600000 \times (1.08)^2$

$= 699840$

But only half of 699840 is returned which is equal to Rs. 349920

∴ Amount which is returned after two year of completion of studies

$$= 349920\left(1 + \frac{10}{100}\right)^2$$

$= 423403.2$

Total amount returned

$= 349920 + 423403.2 = 773323.2$

$=$ Rs. 7.73323 lakh

12.



13. Note that, ultimately 8% interest is charged.
So the net value after 3 years = 125971.2

14. Total time $= 25 + 5 = 30$ years

Again no. of time periods for cost increment $= \frac{30}{6} = 5$

and no. of time periods for rupee depreciation $= \frac{30}{5} = 6$

Now, the net value of the plot $= 1000 \times (1.05)^5 \times (0.98)^6$

$\approx$ Rs. 1130

15. $\frac{A}{B} = \frac{12 \times x}{3 \times y} = \frac{28}{15}$

$\Rightarrow$ $\frac{A}{B} = \frac{7}{15}$

16. We can find the profit of B but not investment.

17. We don't know the rate of interest.

18. $10500 = x\left[\frac{10}{11} + \left(\frac{10}{11}\right)^2\right]$

$\Rightarrow$ $x = 6050$

19. Let the amount of investment with each one be Rs. 400, then

Hari Lal Hari Prasad

$$[400\ (1.1)^2] = [100\ (1.1)^2] + \left[300 + \frac{300 \times r \times 2}{100}\right]$$

$\Rightarrow$ $r = 10.5\%$

20. Best way is to go through options

$1000 \times (1.2)^2 = 2488.32 \approx 2490$

21. Amount earned by HDFC $= 1000000 + \frac{1000000 \times 10 \times 2}{100}$

$= 1200000$

Amount earned by HUDCO $= 1000000\ (1.1)^3 = 1331000$

Net earning of HUDCO $= 1331000 - 1200000 = 131000$

22. Interest paid by Ram Singh = Rs. 48000
Now go through option

$$48000 = \frac{100000}{100}[6 \times 4 + 4 \times 6]$$

$48000 = 48000$

Hence proved that option (b) is correct. It means Ram Singh availed the discount after 4 years of loaning.

23. Worth of hotel after 3 years $= 1000000\ (1.2)^3$

$= 1728000$

Worth of car after 3 years $= 1600000\left(\frac{3}{4}\right)^3$

$=$ Rs. 6,75,000

So, the difference in their worth (pertaining to hotel and car) is

$= 1728000 - 675000 = 10,53,000$

❑❑❑

Scanned by CamScanner

yourshahboob.wordpress.com

8. TIME AND WORK

This chapter is one of the easiest chapter for the students. Even an average student can perform better than in other chapters. There is basically one concept is involved in this chapter *i.e.*, concept of efficiency. So most of the problems are very similar in their basic characteristic. Almost every aptitude exam ask the problems from this chapter. On an average 2-3 problems from this chapter have been asked in past years in CAT.

As it is very clear to all of us that the work is directly related with time. As one can say if a particular person or machine works for more time then more work will be done and if it devotes less time then it yields less work *i.e.*, output of a machine or person is directly proportional to time, provided that he/she maintains his/her efficiency during the work.

CONCEPT OF EFFICIENCY

Suppose a person can complete a particular work in 2 days then we can say that each day he does half of the work or 50% work each day. Thus it is clear that his efficiency is 50% per day. Efficiency is generally considered with respect to the time. The time can be calculated either in days, hours, minutes or months etc. So if a person completes his work in 4 days, then his efficiency (per day) is 25%. Since each day he works 1/4th of the total work (*i.e.*, 25% of the total work).

I would like to mention that the calculation of percentage and conversion of ratios and fractions into percentage and vice versa is the prerequisite for this chapter.

Now, if a person can complete a work in n days then his one day's work $= \frac{1}{n}$

and this one day's work in terms of percentage is called his efficiency.

Also if a person can complete $\frac{1}{n}$ work in one day, then he can complete the whole work in n days.

Relation between work of 1 unit of time and percentage efficiency.

A person can complete his work in n days, then his one day's work $= \frac{1}{n}$, his percentage efficiency $= \frac{1}{n} \times 100$

No. of days/hours etc. required to complete the whole work	Work of 1 day/hour	Percentage efficiency
n	$1/n$	$100/n$
1	1/1	100%
2	1/2	50%
3	1/3	$33.33\% = 33\frac{1}{3}\%$
4	1/4	25%
5	1/5	20%
6	1/6	$16.66\% = 16\frac{2}{3}\%$
7	1/7	$14.28\% = 14\frac{2}{7}\%$
8	1/8	12.5%
9	1/9	$11.11\% = 11\frac{1}{9}\%$
10	1/10	10%

This table is very similar to the percentage fraction table given in the chapter of percentage. This table just manifests as a model for efficiency conversion.

Basically for faster and smarter calculation you have to have your percentage calculation very smart.

All the problems of this chapter can be solved through two methods :

1. Unitary method
2. Percentage efficiency

Unitary method is generally obsolete in respect to high level aptitude exam of CAT since it involves typical calculation of LCM each and every time. But when the problems are solved through percentage efficiency it becomes inevitable to save the time which in turn helps to do some more problems within the stipulated time. I admit that initially it might be difficult to solve for those students who are not so good and confident in percentage and fraction calculation, but a little bit of extra Practice will yield an unexpected result in quicker calculations. Now I have some good examples to show you both the methods of solving the same problems.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *A can do a job in 12 days and B can do the same job in 6 days, in how many days working together they can complete the job?*

SOLUTION A's 1 day's work $= \frac{1}{12}$

B's 1 day's work $= \frac{1}{6}$

$\therefore (A + B)$'s 1 day's work $= \frac{1}{12} + \frac{1}{6} = \frac{3}{12} = \frac{1}{4}$

$\therefore$ Time taken by both to finish the whole work $= \frac{1}{1/4} = 4$ days

Alternatively :

efficiency of $A = \frac{100}{12} = 8.33\%$

and efficiency of $B = \frac{100}{6} = 16.66\%$

Combined efficiency of A and B both $= 8.33 + 16.66 = 25\%$

$\therefore$ Time taken by both to finish the work (working together) $= \frac{100}{25} = 4$ days

NOTE As per my experience, I have found that in this chapter only selected (numerals) numbers are always used and thus there are almost 20 – 25 numbers are frequently used. So one can very easily remember (and calculate) the percentage efficiency but with different combinations to calculate the LCM becomes a very tedious job. Still you can choose your own method, which is comfortable to you.

EXAMPLE 2 *A can do a job in 10 days, B can do the same job in 12 days and C can do the same job in 15 days. In how many days they will finish the work together?*

SOLUTION A's 1 day's work $= \frac{1}{10}$

B's 1 day's work $= \frac{1}{12}$

C's 1 day's work $= \frac{1}{15}$

$(A + B + C)$'s one day's work $= \frac{1}{10} + \frac{1}{12} + \frac{1}{15} = \frac{15}{60} = \frac{1}{4}$

Since they can complete $\frac{1}{4}$ work in 1 day. So they will finish the whole work in $\frac{1}{1/4} = 4$ days.

Alternatively : A's efficiency $= 10\%$

B's efficiency $= 8.33\%$

C's efficiency $= 6.66\%$

Combined efficiency of A, B and $C = 10 + 8.33 + 6.66 = 25\%$

Hence, they will take $\frac{100}{25} = 4$ days to finish the job working together

(Since in one day they complete 25% work)

RELATION BETWEEN EFFICIENCY AND TIME

Efficiency is inversely proportional to the time (*i.e.*, number of days, hours, minutes) etc.

For example if A is twice efficient as B, it means, A takes half the time to finish the same job as B requires working alone.

EXAMPLE 1 *A takes 16 days to finish a job alone, while B takes 8 days to finish the same job. What is the ratio of their efficiency and who is less efficient.*

SOLUTION Since A takes more time than B to finish the same job hence A is less efficient or

efficiency of $A = \frac{100}{16} = 6.25\%$

and efficiency of $B = \frac{100}{8} = 12.5\%$

ratio of efficiency of $A : B = \frac{1}{16} : \frac{1}{8} = 1 : 2$

Hence, B is twice efficient as A.

EXAMPLE 2 *A is thrice efficient as B and A takes 20 days to do a job, then in how many days B can finish the same job?*

SOLUTION Ratio of efficiency of $A : B = 3 : 1$

$\therefore$ Ratio of required days of $A : B = \frac{1}{3} : \frac{1}{1} = 1 : 3$

Now since A takes 20 days. So B will take 60 days to finish the same job.

NOTE Ratio of number of days is equal to the ratio of the reciprocals of efficiency and *vice-versa*.

EXAMPLE 3 *P is thrice as efficient as Q and is therefore able to finish a piece of work in 60 days less than Q. Find the time in which P and Q can complete the work individually.*

SOLUTION Efficiency of $P : Q = 3 : 1$

Required number of days of $P : Q = 1 : 3$

i.e., if P requires x days then Q requires $3x$ days

but $3x - x = 60$

$\Rightarrow$ $2x = 60$

$\Rightarrow$ $x = 30$ and $3x = 90$

Thus P can finish the work in 30 days and Q can finish the work in 90 days.

EXAMPLE 4 *A is twice as good a workman as B and is therefore able to finish a piece of work in 30 days less than B. In how many days they can complete the whole work; working together?*

SOLUTION Ratio of efficiency $= 2 : 1$ $(A : B)$

Ratio of required time $= 1 : 2$ $(A : B)$ $\Rightarrow$ $x : 2x$

but $2x - x = 30$

$\Rightarrow$ $x = 30$ and $2x = 60$

now efficiency of $A = 3.33\%$

and efficiency of $B = 1.66\%$

Scanned by CamScanner

yoursmahboob.wordpress.com

Combined efficiency of A and B together = 5%

$\therefore$ time required by A and B working together to finish the work

$$= \frac{100}{5} = 20 \text{ days.}$$

NOTE

$$\text{Efficiency} \propto \frac{1}{\text{number of time units}}$$

$\therefore$ Efficiency × time = constant work

Hence $$\text{Required time} = \frac{\text{work}}{\text{efficiency}}$$

Whole work is always considered as 1, in terms of fraction and 100%, in terms of percentage.

In general, number of day's or hours $= \frac{100}{\text{efficiency}}$

EXAMPLE 5 *A can do a works in x days while B can do the same work in y days then in how many days will they complete the work, working together?*

SOLUTION A's one day's work $= \frac{1}{x}$

B's one day's work $= \frac{1}{y}$

So, both A and B completes $\frac{1}{x} + \frac{1}{y} = \frac{x+y}{xy}$ work in one day.

Now, **by Unitary method**

$\frac{x+y}{xy}$ work can be completed in 1 day

$\therefore$ 1 (means complete) work will be finished in $\frac{1}{\frac{(x+y)}{xy}}$ days

$$= \frac{xy}{x+y} \text{ days.}$$

$\left(\because \text{Required time to complete the work} = \frac{1}{\text{one day's work}}\right)$

CONCEPT OF NEGATIVE WORK

In this case one person works but another destroyes it or cancells it. For example Sonu can write 20 pages per hour but his younger sister Rimjhim erases 10 pages per hour which Sonu writes.

It means finally Sonu writes 10 pages per hour since each hour his sister erases 10 pages out of 20 written pages. Take an other example :

EXAMPLE 1 *A tub can be filled in 20 minutes but there is a leakage in it which can empty the full tub in 60 minutes. In how many minutes it can be filled?*

SOLUTION Filling efficiency = 5% $\left(\because 5 = \frac{100}{20}\right)$

emptying efficiency = 1.66% $\left(\because 1.66 = \frac{100}{60}\right)$

Net efficiency = 5 − 1.66 = 3.33%

$\therefore$ Required time to fill the tub $= \frac{100}{3.33} = 30$ minutes

Alternatively : In 1 minute tub is filling $= \frac{1}{20}$

In 1 minute tub is emptying $= \frac{1}{60}$

$\therefore$ In 1 minute, effective filling of tub $= \frac{1}{20} - \frac{1}{60}$

$$= \frac{2}{60} = \frac{1}{30}$$

Since $\frac{1}{30}$ part of tub is filled in 1 minute.

Therefore complete tub will be filled in $\frac{1}{1/30} = 30$ minutes

APPLICATION OF INVERSE PROPORTION (OR PRODUCT CONSTANCY)

As I have already discussed thoroughly the concept of inverse proportion and product constancy in ratio-proportion and it has been widely used in profit loss chapter also.

Since the efficiency or rate of work done in one unit of time (mentioned) is inversely proportional to the time *i.e.*, if the rate of work done is greater then the time required will be less and if the rate of work done is less then the time required for the same amount of work will be more.

This product constancy method is limited to the constant work, if the amount of work gets changed, then it does not work, then we have to take help from the unitary method.

When more than one man/machine work on a particular work/project, the rate of work is calculated as the strength of workers working in a particular time. So the amount of work is defined in terms of man-days or man-hours or man-days-hours.

EXAMPLE 1 *If 20 persons can do a piece of work in 7 days then calculate the number of persons required to complete the work in 28 days*

SOLUTION Number of persons × days = work

$20 \times 7 = 140$ man-days

Now, $x \times 28 = 140$ man-days

$\Rightarrow$ $x = 5$

Therefore in second case the required number of person is 5.

Second Method : Since work is constant, therefore

$M_1 \times D_1 = M_2 \times D_2 =$ work done

$20 \times 7 = M_2 \times 28$

$\Rightarrow$ $M_2 = 5$

Scanned by CamScanner

yoursmahboob.wordpress.com

Third Method : Men × days = work, which is constant

$$\downarrow \frac{3}{4}\begin{pmatrix} 20 & 7 \\ 5 & 28 \end{pmatrix} 3\uparrow$$

Since number of days is increased by 3 times (*i.e.*, 300%). So the number of men will be decreased by $\frac{3}{4}$ times (*i.e.*, 75%)

(remember percentage change graphic)

EXAMPLE 2 *If 25 men can do a piece of work in 36 days working 10 hours a day, then how many men are required to complete the work working 6 hours a day in 20 days?*

SOLUTION $M_1 \times D_1 \times H_1 = M_2 \times D_2 \times H_2$

$$25 \times 36 \times 10 = M_2 \times 20 \times 6$$

$$\Rightarrow \quad M_2 = 75 \text{ persons}$$

Alternatively :

$$\begin{matrix} & \text{Men} & \times & \text{Time} & \\ 2\uparrow & \begin{pmatrix} 25 \\ 75 \end{pmatrix} & & \begin{pmatrix} 360 \\ 120 \end{pmatrix} & \frac{2}{3}\downarrow \end{matrix}$$

[Since product (work) is constant]

By percentage change graphic, when time is decreased by $\frac{2}{3}$ (i.e., 66.66%), number of men is increased by 2 times (i.e., 200%)

EXAMPLE 3 *A contractor employed 30 men to complete the project in 100 days. But later on he realised that just after 25 days only 20% of the work had been completed.*

(a) How many extra days, than the scheduled time are required?

(b) To complete the work on the scheduled time how many men he has to increase?

(c) If the amount of work is also increased by 20% of the actual work, then how many extra days are required (in comparison with scheduled time) but the number of men remained constant.

(d) How many men should be increased so that the work will be completed in 25 days less than the scheduled time.

SOLUTION (a) Men × days = work done

$$30 \times 25 = 750 = 20\% \text{ of the actual work}$$

Now, the work to be done is 4 times than the work done but the number of days is only 3 times. So he is required 4 times the number of days, thus he has to work for extra 25 days.

(b) $M_1 D_1 = M_2 D_2$

$$4\,(30 \times 25) = M_2 \times 75$$

$$\Rightarrow \quad M_2 = 40$$

(Since, the work to be done is 4 times of the work done. Hence he requires 4 times man-days.)

Alternatively : Since the new product (*i.e.*, work) is 4 times of the original product (*i.e.*, work). But the new product is being multiplied by 3. Thus to make it 4 times we have to multiply it by 4/3. Thus without changing number of days we get the new value of number of men which is 40 (being multiplied by 4/3)

Therefore he has to increase 10 more men.

(c) New work = 3750 man-days

and the available number of men = 30

$$\therefore \quad \text{number of days required} = \frac{3750}{30} = 125$$

So, he has to work for extra 50 days where

$$50 = (125 - 75)$$

(d) Work = 3000 unit (man days)

number of available days = 50 (75 – 25)

$$\therefore \quad \text{number of men required} = \frac{3000}{50} = 60$$

Thus he has to increase (60 – 30) = 30 more men.

EXAMPLE 4 *16 workers working 6 hours a day can build a wall of length 150 metres, breadth 20 m and height 12 m in 25 days. In how many days 12 workers, working 8 hours a day can build a wall of length 800 m, breadth 15 m and height 6 m.*

SOLUTION Here work is the volume of the wall. So the work force should be increased/decreased in the ratio of volume of the work. Therefore

$$\frac{L_1 B_1 H_1}{L_2 B_2 H_2} = \frac{M_1 D_1 T_1}{M_2 D_2 T_2}$$

where L, B, H are length, breadth and height of the wall respectively and M, D, T are men, days and time in hours per day, respectively. 1 indicates the first case, while 2 indicates second case. So the ratio of work force remains constant as the ratio of volume and work.

$$\therefore \quad \frac{150 \times 20 \times 12}{800 \times 15 \times 6} = \frac{16 \times 6 \times 25}{12 \times 8 \times D_2}$$

$$\Rightarrow \quad D_2 = 50$$

hence the required number of days = 50

Please notice that the volume of work becomes twice (in the second case) so the work force will also be twice to the previous work force.

RELATION BETWEEN EFFICIENCIES

In this case the efficiencies of different persons are different but when they work in a group, so the efficiency of the group is required to know the time taken. For example 3 men can do a work in 4 days while 12 boys can do the same work in 3 days. It means we need $3 \times 4 = 12$ man-days *i.e.*, 12 men can finish the job in 1 day.

Similarly we need $12 \times 3 = 36$ boys days *i.e.*, 36 boys can finish the same job in 1 day.

Here we can see that to finish the work in only 1 day 12 men are needed while 36 boys are needed. Thus we can conclude that work of 12 men is equal to the work of 36 boys. Therefore efficiency of 12 men is equal to 36 boys *i.e.*, we can say the efficiency of 1 man is equal to 3 boys. Thus a man is thrice efficient as a boy or we can say that a man is two times more efficient than a boy.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *6 boys and 8 women finish a job in 6 days and 14 boys and 10 women finish the same job in 4 days. In how many days working together 1 boy and 1 woman can finish the work?*

SOLUTION In this kind of questions we find the work force required to complete the work in 1 day (or given unit of time) then we equate the work force to find the relationship between the efficiencies (or work rate) between the different workers.

Therefore $6B + 8W = 6$ days

$\Rightarrow$ $6(6B + 8W) = 1$ day (inversely proportional)

$\Rightarrow$ $36B + 48W = 1$ (by unitary method)

Again $14B + 10W = 4$ days

$\Rightarrow$ $56B + 40W = 1$

So, here it is clear that either we employ $36B$ and $48W$ to finish the work in 1 day or $56B$ and $40W$ to finish the same job in 1 day. Thus, we can say

$\Rightarrow$ $36B + 48W = 56B + 40W$

$\Rightarrow$ $20B = 8W$

$\Rightarrow$ $W = 2.5B$

Thus a woman is 2.5 times as efficient as a boy.

Now, since $36B + 48W = 1$

$\Rightarrow$ $36B + 48 \times (2.5B) = 1$

$\Rightarrow$ $156B = 1$

i.e., to finish the job in 1 day 156 boys are required or the amount of work is 156 boys-days.

Again $1W + 1B = 2.5B + 1B = 3.5B$

Now, since 156 boys can finish the job in 1 day

So 1 boy can finish the job in 1×156 days

$\therefore$ 3.5 boys can finish the job in $\frac{1 \times 156}{3.5} = 44\frac{4}{7}$ days

NOTE There is a great difference between 'and' & 'or'
For example 4 men and 8 women can do a piece of work in 10 days : means it is unknown that who is faster or slower (*i.e.*, we don't know the relation between efficiencies of a man and a woman)
Again, 4 men or 8 women can do a piece of work in 10 days : means 4 men are equal to 8 women. Hence a man is twice efficient as a woman.

EXAMPLE 2 *6 men and 8 women can do a job in 10 days. In how many days can 5 men and 9 women do the same job?*

SOLUTION Since we don't know the relation between work rate (or efficiency) between a man and that of a woman so we can't find the required number of days.

EXAMPLE 3 *6 men and 8 women can do a job in 10 days. In how many days can 3 men and 4 women finish the same job working together?*

SOLUTION Notice here we don't know the relation of efficiencies but we can solve the problem due to clear relation between the work force.

Since $6M + 8W = 10$ days

$2(3M + 4W) = 10$ days

$\Rightarrow$ $(3M + 4W) = 20$ days

Since, the work force has become half of the original force so number of days must be double.

Thus required number of days = 20

EXAMPLE 4 *A can complete a work in 12 days, B in 15 days. Find the time taken by them :*

(a) when A and B worked together.

(b) when A and B worked alternatively started by A.

(c) when A and B worked alternatively started by B.

(d) if A started two days later, in comparison to B.

(e) if B started two days later, in comparison to A.

(f) if A leaves two days before the actual completion of the work.

(g) if B leaves two days before the actual completion of the work.

(h) if A leaves two days before the scheduled completion of the work.

(i) if B leaves two days before the scheduled completion of the work.

(j) if B does negative work with his same work rate.

SOLUTION (a) A's efficiency = 8.33%

B's efficiency = 6.66%

Combined efficiency = 15%

So, the required time $= \frac{100}{15} = 6\frac{2}{3}$ days.

(b) In every two days A and B work 15%. So in 12 days they will complete 90% work. Now on the 13th day, A will finish 8.33% of the remaining (*i.e.*, 10% work) and the rest 1.66% will be finished by B on 14th day by taking time $= \frac{1.66}{6.66} = \frac{1}{4}$ day.

Thus, total required time $= 12 + 1 + \frac{1}{4} = 13\frac{1}{4}$ days.

See the chart below :

Day	1	2	3	4	5	6	7	8	9	10	11	12	13	14
Work	8.33	6.66	8.33	6.66	8.33	6.66	8.33	6.66	8.33	6.66	8.33	6.66	8.33	1.66
	15		15		15		15		15		15			
	$15 \times 6 = 90\%$												10%	

(c) Here the difference is in the last day/days only.

See the chart below :

Day	1	2	3	4	5	6	7	8	9	10	11	12	13	14
Work	6.66	8.33	6.66	8.33	6.66	8.33	6.66	8.33	6.66	8.33	6.66	8.33	6.66	3.33
	15		15		15		15		15		15		10	
	$15 \times 6 = 90\%$												10%	

So, after the completion of 90% work in 12 days, on the 13th day 6.66% work will be finished by B and then 3.33% (the last part of the work) will be finished by A by taking time $= \frac{3.33}{8.33} = \frac{2}{5}$ day.

Thus, the required time $= 12 + 1 + \frac{2}{5} = 13\frac{2}{5}$ days.

(d) It means B worked for 2 days more than A has worked for. Now, since B completes $2 \times 6.66 = 13.33\%$ work in two days. So the remaining work will be done by A and B together.

Scanned by CamScanner

yoursmahboob.wordpress.com

Therefore the time taken by A and B, working together

$$= \frac{86.66}{15} \frac{\text{(remaining work)}}{\text{(combined efficiency)}} = 5\frac{7}{9} \text{ days}$$

Thus the total required time to finish the whole work

$$= 2 + 5\frac{7}{9} = 7\frac{7}{9} \text{ days.}$$

(e) It means A alone worked for 2 days which is equal to

$$8.33 \times 2 = 16.66\%$$

So, the remaining (83.33%) work will be done by A and B together.

$$\therefore \quad \text{Time taken together} = \frac{83.33}{15} = 5\frac{5}{9} \text{ days}$$

Thus, the total required time $= 2 + 5\frac{5}{9} = 7\frac{5}{9}$ days.

(f) 'A leaves two days before the actual completion of the work' means in the last two days B has worked alone which is $6.66 \times 2 = 13.33\%$

Therefore the remaining work *i.e.*, 86.66% work was only done by A and B together in $\frac{86.66}{15} = 5\frac{7}{9}$ days

Thus, the required time $= 2 + 5\frac{7}{9} = 7\frac{7}{9}$ days.

NOTE This case is exactly same as part (d) of the same example. The difference is only in order of days. In part (d) B worked alone initially for 2 days and in part (f) B worked alone in the last 2 days.

(g) Applying the same concept as above we can calculate the required number of days which is same as in case (e)



(h) 'A leaves two days before the scheduled completion of the work' means A works with B only for $4\frac{2}{3}$ days since the scheduled time is $6\frac{2}{3}$ [see the case (a)]

Scheduled time is the time in which work could be finished by working together without any change in efficiency or work force.

Now since both A and B have worked together for $4\frac{2}{3}$ days it means the last 2 days work (scheduled) which is equal to 30% (since if A and B working together can finish 30% work in 2 days) will be done by B only.

$\therefore$ required time to complete 30% work by B alone

$$= \frac{30}{6.66} = 4.5 \text{ days}$$

Thus the total required time to finish the whole work

$$= 4\frac{2}{3} + 4\frac{1}{2} = 9\frac{1}{6} \text{ days.}$$

(i) Very similar to the case (h) A and B worked only for 4 days (2 days less than the scheduled time $6\frac{2}{3}$ days)

(It is obvious that in $4\frac{2}{3}$ days A and B, working togethe completes 70% work, but we can directly calculate that they ca complete 30% if they work together, in 2 days)

Thus 30% work is done by A alone

$$\therefore \quad \text{time taken} = \frac{30}{8.33} = 3\frac{3}{5} \text{ days}$$

Thus, the total time $= 4\frac{2}{3} + 3\frac{3}{5} = 8\frac{4}{15}$ days.

(j) Combined efficiency of A and $B = (8.33) + (-6.66)$

$= 1.66\%$

$\therefore$ Time required by A and B working together

$$= \frac{100}{1.66} = 60 \text{ days}$$

(Negative work means, B works against A)

EXAMPLE 5 *A can complete a work in 10 days, B in 12 days and C in 15 days. All of them began the work together, but A had to leave the work after 2 days of the start and B 3 days before the completion of the work. How long did the work last?*

SOLUTION See the diagram and then interpret the language of the question.



Since initially for 2 days all of them A, B and C work together so they complete the 50% work

and for the last 3 days only C works which is equal to 20% work.

Thus, the remaining work $= 30\%[100 - (50 + 20)]$

This 30% work was done by B and C in 2 days $= \left(\frac{30}{15}\right)$.

NOTE

Efficiency of $A = 10\%$

Efficiency of $B = 8.33\%$

Efficiency of $C = 6.66\%$

So, the total number of required days $= 2 + 2 + 3 = 7$ days.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. *A* can finish a piece of work in 12 days while *B* can do it in 15 days. If both work at it together, what time will they take to do the work?
(a) 6 days (b) 8 days
(c) $6\frac{2}{3}$ days (d) $10\frac{1}{5}$ days

2. *A* can do a piece of work in 10 days, *B* can do it in 12 days and *C* can do it in 15 days. In how many days they can complete the work, working together?
(a) 6 (b) 4
(c) 5 (d) 10

3. *A* can do a piece of work in 5 days, *B* can do it in 10 days. With the help of *C*, they finish the work in 2 days. In how many days *C* alone can do the whole work?
(a) 3 (b) 4
(c) 5 (d) 6

4. *A* can do a piece of work in 8 days, *B* can do it in 16 days, while *C* can do it in 80 days. In how many days they can complete the whole work, working together?
(a) 5 (b) 6
(c) $8\frac{2}{3}$ (d) $20\frac{2}{5}$

5. *A* can do a piece of work in 10 days, *B* can do it in 15 days working together they can finish the work in :
(a) 9 (b) 8
(c) 10 (d) 6

6. *A* can do a piece of work in 24 days, while *B* can do it in 30 days. With the help of *C* they can finish the whole work in 12 days. How much time is required for *C* to complete the work, alone?
(a) 100 days (b) 120 days
(c) 125 days (d) 72 days

7. *A* can do a piece of work in 10 days. *B* can do it in 24 days. If *C* also works with them then it takes only 6 days to complete the whole work. In how many days *C* alone can complete the whole work?
(a) 25 (b) 40
(c) 50 (d) 75

8. *A* can do a piece of work in 14 days while *B* can do it in 21 days. In how many days, working together they will complete the whole work?
(a) 10.5 (b) 8
(c) 8.4 (d) 9

9. *A* can do a piece of work in 24 days. If *B* is 60% more efficient than *A*, then the number of days required by *B* to do the same piece of work is :
(a) 10 (b) 15
(c) 12 (d) 9.6

10. *A* is twice as good a workman as *B* and together they finish a piece of work in 14 days. In how many days can *A* alone finish the work?
(a) 18 (b) 20
(c) 21 (d) 24

11. *A* is twice as good a workman as *B* and together they finish a piece of work in 7 days. In how many days can *A* alone finish the work?
(a) 10 (b) 10.5
(c) 12 (d) 11

12. *A* is thrice as good a workman as *B* and takes 10 days less to do a piece of work than *B* takes. The number of days taken by *B* to finish the work is :
(a) 9 (b) 18
(c) 15 (d) 12

13. *A* is twice as good a workman as *B* and therefore *A* takes 6 days less than *B* to finish the work individually. If *A* and *B* working together complete the work in 4 days, then how many days are required by *B* to complete the work alone?
(a) 12 (b) 18
(c) 8 (d) 6

14. *A* is thrice efficient as *B* and *C* is twice as efficient as *B*. What is the ratio of number of days taken by *A*, *B* and *C*, when they work individually?
(a) 2 : 6 : 3 (b) 2 : 3 : 6
(c) 1 : 2 : 3 (d) 3 : 1 : 2

15. Ajit is 3 times as efficient as Bablu, then the ratio of number of days required by each to work alone, completely?
(a) 3 : 1 (b) 1 : 3
(c) 6 : 3 (d) 3 : 6

16. *X* is 4 times more efficient as *Y*, then the number of days taken by *X* and *Y* are in the ratio :
(a) 8 : 1 (b) 1 : 5
(c) 6 : 8 (d) 5 : 1

17. If *A* takes 4/5 days as *B* takes and working together they require $\frac{20}{3}$ days to complete the whole work. What is the efficiency of *B* ?
(a) $6\frac{2}{3}\%$ (b) 16%
(c) 5.55% (d) $8\frac{1}{3}\%$

18. *A* is thrice as efficient as *B*. Working together they complete the work in 3 days. If *B* takes 8 days more than *A*, what is the number of days taken by *A* to finish the whole work, alone?
(a) 4 (b) 2
(c) 12 (d) 16

Scanned by CamScanner

yoursmahboob.wordpress.com

19. A and B can do a piece of work in 8 days, B and C can do the same work in 12 days and A and C complete it in 8 days. In how many days A, B and C can complete the whole work, working together?
(a) 4 (b) 6
(c) 12 (d) 9

20. A and B can do a piece of work in 12 days, B and C in 15 days C and A in 20 days. In how many days can C alone do it?
(a) 60 (b) 50
(c) 25 (d) 24

21. Ganga, Jamuna and Saraswati can do a piece of work, working together, in 1 day. Ganga is thrice efficient as Jamuna and Jamuna takes the twice the number of days as Saraswati takes to do it alone. What is the difference between the number of days taken by Ganga and Saraswati?
(a) 1 (b) 2
(c) 3 (d) 4

22. A can finish a work in 12 days and B can do it in 15 days. After A had worked for 3 days, B also joined A to finish the remaining work. In how many days, the remaining work will be finished?
(a) 3 (b) 4
(c) 5 (d) 6

23. Raja can do a piece of work in 14 days, while Rani can do the same work in 21 days. They started the work together but 3 days before the completion of the work, Raja left the work. The total number of days to complete the work is :
(a) 7 (b) 8.5
(c) 5 (d) $10\frac{1}{5}$

24. A and B can complete a task in 30 days when working together after A and B have been working together for 11 days, B is called away and A, all by himself completes the task in the next 28 days. Had A been working alone, the number of days taken by him to complete the task would have been :
(a) $33\frac{3}{19}$ (b) $19\frac{6}{25}$
(c) $44\frac{4}{19}$ (d) none of these

25. Sonu can do a piece of work in 20 days. He started the work and left after some days, when 25% work was done. After it Abhijeet joined and completed it working for 10 days. In how many days Sonu and Abhijeet can do the complete work, working together?
(a) 6 (b) 8
(c) 10 (d) 12

26. Efficiency of Asha is 25% more than Usha and Usha takes 25 days to complete a piece of work. Asha started a work alone and then usha joined her 5 days before actual completion of the work. For how many days Asha worked alone?
(a) 9 (b) 11
(c) 10 (d) 15

27. Krishna can do a work in 10 days while Mohan can do the same work in 20 days. They started work together. After 3 days Krishna left the work and Mohan completed it. For how many days Mohan worked alone more than the number of days required when both worked together?
(a) $4\frac{1}{3}$ (b) $3\frac{1}{4}$
(c) $2\frac{3}{5}$ (d) $3\frac{2}{3}$

28. Kareena can do a piece of work in 9 days and Karishma can do the same work in 18 days. They started the work. After 3 days Shahid joined them, who can complete alone the same whole work in 3 days. What is the total number of days in which they had completed the work?
(a) 12 (b) 8
(c) 4 (d) 6

29. Kavita, Babita and Samita started a work. 5 days later Samita left the work and Babita left the work after working 8 days. In how many more days Kavita would have completed the rest work if they take 20, 60 and 30 days individually to finish a work?
(a) 4 (b) 5
(c) 6 (d) 8

30. The ratio of efficiency of A is to C is 5 : 3. The ratio of number of days taken by B is to C is 2 : 3. A takes 6 days less than C, when A and C completes the work individually. B and C started the work and left after 2 days. The number of days taken by A to finish the remaining work is :
(a) 4.5 (b) 5
(c) 6 (d) $9\frac{1}{3}$

31. Anand can do a piece of work in 45 days, but Bahuguna can do the same work in 5 days less, than Anand, when working alone. Anand and Bahuguna both started the work together but Bahuguna left after some days and Anand finished the remaining work in 56 days with half of his efficiency but he did the work with Bahuguna with his complete efficiency. For how many days they had worked together?
(a) 6 (b) 8
(c) 9 (d) 12

32. Chandni and Divakar can do a piece of work in 9 days and 12 days respectively. If they work for a day alternatively, Chandni beginning, in how many days, the work will be completed?
(a) $10\frac{1}{4}$ (b) $9\frac{1}{5}$
(c) 11.11 (d) 10

33. Fatima and Zahira can do a piece of work in 12 days and 15 days respectively. If they work for alternate day and Fatima starts the work first, then in how many days the work will be completed?
(a) $12\frac{1}{5}$ (b) $13\frac{1}{4}$
(c) $13\frac{1}{5}$ (d) 15

34. In the previous question (number 33) if Zahira starts first then in how many days, the work will be completed?
(a) $14\frac{1}{5}$ (b) 14
(c) $13\frac{1}{5}$ (d) $13\frac{2}{5}$

35. The number of days required by A, B and C to work individually is 6, 12 and 8 respectively. They started a work doing it alternatively. If A has started then followed by B and so on, how many days are needed to complete the whole work?
(a) 8 (b) 7.5
(c) 8.5 (d) $9\frac{1}{2}$

Scanned by CamScanner

yoursmahboob.wordpress.com

36. In the previous question if the order of working days be as B, C, A, B, C, A ... (starting with B and followed by C and A respectively), then in how many days the work will be completed?
(a) $7\frac{3}{4}$ (b) 8
(c) $8\frac{1}{4}$ (d) 9

37. A takes 6 days less than B to do a certain job and 2 days more than C. A and B together can do the work in the same time as C. In how many days B alone can do the complete work?
(a) 10 (b) 14
(c) 12 (d) 16

38. A and B undertook a work for Rs. 350. A got Rs. 150 more than that of B, when they worked together. B takes 9 days more than A, when they work individually. In how many days A and B working together can do the whole work :
(a) 5 (b) $4\frac{2}{7}$
(c) $4\frac{5}{7}$ (d) $5\frac{4}{7}$

39. Alen and Border can do a work individually in 21 and 42 days respectively. In how many days they can complete the work, working alternatively?
(a) 14 (b) 28
(c) 42 (d) 35

40. C takes twice the number of days to do a piece of work than A takes. A and B together can do it in 6 days while B and C can do it in 10 days. In how many days A alone can do the work?
(a) 60 (b) 30
(c) 6 (d) 7.5

41. When A, B and C are deployed for a task, A and B together do 70% of the work and B and C together do 50% of the work. Who is most efficient?
(a) A (b) B
(c) C (d) can't be determined

42. Colonel, Major and General started a work together for Rs. 816. Colonel and Major did $\frac{8}{17}$ of the total work, while Major and General together did $\frac{12}{17}$ of the whole work. What is the amount of the least efficient person?
(a) Rs. 256 (b) Rs. 144
(c) Rs. 85 (d) can't be determined

43. Sharma is 20% less efficient than Kelkar. If Kelkar can do a piece of work in 24 days. The number of days required by Sharma to complete the same work alone?
(a) 20 (b) 30
(c) 28.8 (d) can't be determined

44. 30 persons can do a piece of work in 24 days. How many more people are required to complete the work in 20 days?
(a) 4 (b) 5
(c) 6 (d) none of these

45. 12 women can do a piece of work in 20 days. If the 4 women deny to work, then how many more days are required?
(a) 6 (b) 10
(c) 15 (d) none of these

46. 35 boys can do a piece of work in 15 days. The work w completed in 25 days. How many boys did not turn up for t job?
(a) 14 (b) 20
(c) 6 (d) 7

47. 24 men can complete a job in 40 days. The number of m required to complete the job in 32 days is :
(a) 30 (b) 40
(c) 25 (d) 50

48. 16 men finished one-third work in 6 days. The number additional men are required to complete the job in next days :
(a) 10 (b) 8
(c) 16 (d) 32

49. If 10 persons can do a job in 20 days, then 20 person wit twice the efficiency can do the same job in :
(a) 5 days (b) 40 days
(c) 10 days (d) 20 days

50. A certain job was assigned to a group of men to do in 20 days. But 12 men did not turn up for the job and the remaining men did the job in 32 days. The original number of men in the group was :
(a) 32 (b) 36
(c) 42 (d) 40

51. 30 workers can finish a work in 20 days. After how many days should 9 workers leave the job so that the work is completed in total 26 days :
(a) 12 (b) 10
(c) 6 (d) none of these

52. 25 men can complete a job in 30 days. After how many days should the strength of work force be increased by 50 men so that the work will be completed in $\frac{2}{3}$rd of the actual time :
(a) 15 (b) 10
(c) 18 (d) 5

53. A group of workers can complete a job in 120 days. If there were 4 more such workers then the work could be finished in 12 days less. What was the actual strength of workers?
(a) 30 workers (b) 40 workers
(c) 42 workers (d) 36 workers

54. Mr. Modi can copy 40 pages in 10 minutes, Mr Xerox and Mr. Modi both working together can copy 250 in 25 minutes. In how many minutes Mr. Xerox can copy 36 pages?
(a) 5 minutes (b) 6 minutes
(c) 3 minutes (d) 12 minutes

55. 20 persons completed $\frac{1}{3}$rd of the work in 12 days. How many more person are required to finish the rest work in next 12 days?
(a) 20 (b) 12
(c) 18 (d) 40

56. A contractor undertook a work to complete in 60 days. But just after 20 days he observed that only $\frac{1}{5}$th of the project work had been completed. To complete the work in time (*i.e.*,

Scanned by CamScanner

yoursmahboob.wordpress.com

in rest days) minimum how many workers he had to increase, if there were initially 75 workers were deployed for the task?
(a) 25 (b) 50
(c) 75 (d) can't be determined

57. 6 men or 10 women can reap a field in 15 days, then the number of days that 12 men and 5 women will take to reap the same field is :
(a) 5 (b) 6
(c) 8 (d) 12

58. If 2 men or 3 women or 4 boys can do a piece of work in 52 days, then the same piece of work will be done by 1 man, 1 woman and 1 boy in :
(a) 48 days (b) 36 days
(c) 45 days (d) none of these

59. 2 men or 5 women or 7 boys can finish a work in 469 days, then the number of days taken by 7 men, 5 women and 2 boys to finish the work is :
(a) 134 (b) 106
(c) 100 (d) 98

60. 6 children and 2 men complete a certain piece of work in 6 days. Each child takes twice the time taken by a man to finish the work. In how many days will 5 men finish the same work?
(a) 6 (b) 8
(c) 9 (d) 15

61. 2 men and 3 women finish 25% of the work in 4 days, while 6 men and 14 women can finish the whole work in 5 days. In how many days will 20 women finish it?
(a) 20 (b) 25
(c) 24 (d) 88

Directions : For question number 62 and 63:
A can do a work in 15 days and B can do it in 18 days. With the help of C, all of them complete the work in 6 days.

62. How long will it take C to finish the work alone?
(a) 30 days (b) 22 days
(c) $\frac{45}{2}$ days (d) 25 days

63. A, B and C received total Rs. 27,000 for the whole work. What is the share of C, if the money is distributed in the ratio of amount of work done, individually?
(a) 2700 (b) 7200
(c) 14400 (d) 6300

Directions : Solve the following questions individually.

64. 314 weavers weaves 6594 shawls in $\frac{1}{6}$ hours. What is the number of shawls weaved per hour by an average weaver?
(a) 42 (b) 21
(c) 102 (d) 126

65. Three men and two women can do a piece of work in 4 days, while two men and three women can do the same work in 5 days. Rs 44 is given to a woman for her contribution towards work, per day. What is the amount received by a man per day?
(a) Rs. 88 (b) Rs. 144
(c) Rs. 154 (d) can't be determined

66. 30 girls can finish a work in 40 days. After how many days should 10 girls leave the work so that it may be finished in 46 days, if all the 30 girls started the work?
(a) 18 days (b) 28 days
(c) 22 days (d) 30 days

67. If 8 women collect 200 kg of tea leaves in 10 hours. How many more (in kg) of tea leaves will 12 women collect in 8 hours?
(a) 24 kg (b) 40 kg
(c) 50 kg (d) 100 kg

68. 450 man-days of work can be completed by a certain number of men in some days. If the number of people (men) are increased by 27, then the number of day required to complete the same work is decreased by 15. The number of days are required to complete the three times work (than the previous/actual work) by 27 men?
(a) 50 (b) 60
(c) 54 (d) 45

69. 4 boys and 5 girls can do a piece of work in 10 days. 6 boys and 6 girls can do the same work in 7 days. In how many days can 2 boys and 7 girls complete the same work, working together?
(a) 15 days (b) 14 days
(c) 21 days (d) 18 days

70. If 20 engineers and 20 workers can together construct a 20 km road in 20 days. 40 engineers and 40 workers together construct 40 km road in how many days?
(a) 10 (b) 20
(c) 40 (d) can't be determined

71. $(x-2)$ men can do a piece of work in x days and $(x+7)$ men can do 75% of the same work in $(x-10)$ days. Then in how many days can $(x+10)$ men finish the work?
(a) 27 days (b) 12 days
(c) 25 days (d) 18 days

72. A man, a woman and a girl worked for a contractor for the same period. A man is twice efficient as a woman and a woman is thrice efficient as a girl Rs. 10000 were given to all of them. What is the sum of money received by a woman and a girl together?
(a) Rs. 5500 (b) Rs. 4500
(c) Rs. 4000 (d) Rs. 6000

73. 33 men can do a job in 30 days. If 44 men started the job together and after every day of the work, one person leaves. What is the minimum number of days required to complete the whole work?
(a) 21 (b) 42
(c) 45 (d) none of these

74. Abhishek can do a piece of work in 40 days. He alone worked at it for 8 days and then Bacchhan completed alone the rest work in 24 days. In how many days they will complete the whole work, working together?
(a) $17\frac{1}{7}$ days (b) $18\frac{1}{7}$ days
(c) $9\frac{1}{6}$ days (d) 14 days

Scanned by CamScanner

yoursmahboob.wordpress.com

75. C is twice efficient as A. B takes thrice as many days as C. A takes 12 days to finish the work alone. If they work in pairs (i.e., AB, BC, CA) starting with AB on the first day then BC on the second day and AC on the third day and so on, then how many days are required to finish the work?

(a) $6\frac{1}{5}$ days (b) 4.5 days

(c) $5\frac{1}{9}$ days (d) 8 days

76. Ahluwalia and Bimal together take 6 days to finish the work. Bimal and Jalan together take 10 days to finish the work. What is the difference between number of days taken by Ahluwalia and Jalan when they worked alone to complete the whole work?

(a) 12 days (b) 16 days

(c) 15 days (d) can't be determined

77. B is twice efficient as A and A can do a piece of work in 15 days. A started the work and after a few days B joined him. They completed the work in 11 days, from the starting. For how many days they worked together?

(a) 1 day (b) 2 days

(c) 6 days (d) 5 days

78. A, B and C can complete a piece of work in 15, 30 and 40 days respectively. They started the work together and A left 2 days before the completion of the work and B left 4 days before the completion of the work. In how many days was the work completed?

(a) $7\frac{3}{10}$ (b) $10\frac{2}{15}$

(c) $10\frac{7}{30}$ (d) none of these

79. There was a leakage in the container of the refined oil. If 11 kg oil is leaked out per day then it would have lasted for 50 days, if the leakage was 15 kg per day, then it would have lasted for only 45 days. For how many days would the oil have lasted, if there was no leakage and it was completely used for eating purpose?

(a) 80 days (b) 72 days

(c) 100 days (d) 120 days

80. A contractor undertook to complete the work in 40 days and he deployed 20 men for his work. 8 days before the scheduled time he realised that $\frac{1}{3}$rd of the work was still to be done. How many more men were required to complete the work in stipulated time?

(a) 16 (b) 15

(c) 20 (d) 25

81. 7 Indian and 4 Chinese finish a job in 5 days. 7 Japanese and 3 Chinese finish the same job in 7 days. Given that the efficiency of each person of a particular nationality is same but different from others. One Indian, one Chinese and one Japanese will complete the work in :

(a) $18\frac{3}{13}$ days (b) $20\frac{5}{12}$ days

(c) $21\frac{6}{14}$ days (d) $20\frac{7}{12}$ days

82. A, B and C are three book binders. A takes 8 minutes, B takes 12 minutes and C takes 16 minutes to bind a book. If they work each day for 12 hours, then on an average, how many books each one bind per day?

(a) 65 (b) 52

(c) 48 (d) 70

83. A piece of work can be completed by 10 men and 6 women in 18 days. Men works 9 hours per day while women works 7.5 hours per day. Per hour efficiency of a woman is $\frac{2}{3}$rd of a man's efficiency. In how many days 10 men and 9 women complete the work?

(a) 16 days (b) 20 days

(c) 30 days (d) 25 days

84. B and C are equally efficient, but the efficiency of A is half of each B and C. A and B started a work and 3 days later C joined them. If A alone can do the work in 14 days, then in how many more days the work will be completed?

(a) 1 (b) 2

(c) 3 (d) 4.5

85. A can do a piece of work in 10 days, B in 15 days. They work together for 5 days, the rest of the work is finished by C in two more days. If they get Rs. 3000 as wages for the whole work, what are the daily wages of A, B and C respectively (in Rs.):

(a) 200,250,300 (b) 300,200,250

(c) 200,300,400 (d) none of these

86. A can do a piece of work in 2 hours, B can do thrice the work in 8 hours and 'C' can do the same work as A in 8 hours. If all of them work together, how long it would take them to complete the work :

(a) 1 hour (b) 2 hours

(c) 3 hours (d) 4 hours

87. A is twice efficient as B and together they do the same work in as much time as C and D together. If C and D can complete the work in 20 and 30 days respectively, working alone, then in how many days A can complete the work individually :

(a) 12 days (b) 18 days

(c) 24 days (d) 30 days

88. 4 men and 2 boys can finish a piece of work in 5 days. 3 women and 4 boys can finish the same work in 5 days. Also 2 men and 3 women can finish the same work in 5 days. In how many days 1 man, 1 woman and one boy can finish the work, at their double efficiency?

(a) $4\frac{8}{13}$ (b) $4\frac{7}{13}$

(c) $3\frac{7}{13}$ (d) none of these

89. If m men can do a work in r days, then the number of days taken by $(m + n)$ men to do it is :

(a) $\frac{m+n}{mn}$ (b) $\frac{m+n}{mr}$

(c) $\frac{mr}{(m+n)}$ (d) $\frac{(m+n)r}{mn}$

90. Pipe A can fill a tank in 36 minutes and pipe B can fill it in 45 minutes. If both the pipes are opened to fill an empty tank, in how many minutes will it be full?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 15 (b) 18
(c) 20 (d) 25

91. Tap A can fill the empty tank in 12 hours, but due to a leak in the bottom it is filled in 15 hours. If the tank is full and then tap A is closed then in how many hours the leak can empty it?
(a) 45 hours (b) 48 hours
(c) 52 hours (d) 60 hours

92. Pipe A and B can fill a cistern in 10 hours and 15 hours respectively. When a third pipe C which works as an outlet pipe is also open then the cistern can be filled in 18 hours. The outlet pipe can empty a full cistern in :
(a) 12 hours (b) 8 hours
(c) 9 hours (d) 14 hours

93. A cistern has a leak which would empty it in 6 hours. A tap is turned on which fills the cistern @ 10 liters per hour and then it is emptied in 15 hours. What is the capacity of the cistern?
(a) 100 litres (b) 166.66 litres
(c) 60.66 litres (d) none of these

94. Tap a fills a tank in 10 hours and B can fill it in 15 hours. Both are opened simultaneously. Sometimes later tap B was closed, then it takes total 8 hours to fill up the whole tank. After how many hours B was closed?
(a) 2 (b) 3
(c) 4 (d) 5

95. Tap A can fill a tank in 20 hours, B in 25 hours but tap C can empty a full tank in 30 hours. Starting with A, followed by B and C each tap opens alternatively for one hour period till the tank gets filled up completely. In how many hour the tank will be filled up completely?
(a) $51\frac{11}{15}$ (b) $52\frac{2}{3}$
(c) $24\frac{4}{11}$ (d) none of these

96. If one pipe A can fill a tank in 20 minutes, then 5 pipes, each of 20% efficiency of A, can fill the tank in :
(a) 80 min (b) 100 min
(c) 20 min (d) 25 min

97. Pipe A basically used as inlet pipe and pipe B is used as outlet pipe. Pipes A and B both are opened simultaneously, all the time. When pipe A fills the tank and B empty the tank, it will take double the time than when both the pipe fill the tank. When pipe B is used for filling the tank, its efficiency remains constant. What is the ratio of efficiency of pipe A and pipe B respectively?
(a) 3 : 1 (b) 5 : 2
(c) 1 : 3 (d) 3 : 2

98. Pipe A can fill the tank in 4 hours, while pipe B can fill it in 6 hours working separately. Pipe C can empty whole the tank in 4 hours. He opened the pipe A and B simultaneously to fill the empty tank. He wanted to adjust his alarm so that he could open the pipe C when it was half-filled, but he mistakenely adjusted his alarm at a time when his tank would be 3/4th filled. What is the time difference between both the cases, to fill the tank fully :
(a) 48 min. (b) 54 min.
(c) 30 min. (d) none of these

99. Two pipes A and B can fill a cistern in 15 hours and 10 hours respectively. A tap C can empty the full cistern in 30 hours. All the three taps were open for 2 hours, when it was remembered that the emptying tap had been left open. It was then closed. How many hours more would it take for the cistern to be filled?
(a) 30 min. (b) 1.2 hours
(c) 24 min. (d) 35 min.

100. Pipe A can fill an empty tank in 30 hours while B can fill it in 45 hours. Pipe A and B are opened and closed alternatively *i.e.*, first pipe A is opened, then B, again A and then B and so on for 1 hour each time without any time lapse. In how many hours the tank will be filled when it was empty, initially?
(a) 36 (b) 54
(c) 48 (d) 60

LEVEL (2)

1. A, B and C three weavers have to supply an order of 100 shawls. A can weave a shawl in 2 hours, B in 3 hours and C in 4 hours respectively. It is known that even being a joint contract each one weaves his own shawl completely *i.e.*, no other weaver help to the rest weavers. In how many hours they will complete the order irrespective of day or night?
(a) 93 hours (b) 100 hours
(c) $92\frac{4}{13}$ hours (d) 94 hours

2. Arun and Satyam can complete a work individually in 12 working days and 15 working days respectively with their full efficiencies. Arun does work only on Monday, Wednesday and Friday while Satyam does the work on Tuesday, Thursday and Saturday. Sunday is always off. But Arun and Satyam both works with half of their efficiencies on Friday and Saturday respectively. If Arun started the work on Ist January which falls on Monday followed by Satyam on the next day and so on (*i.e.*, they work collectively in alternate days), then on which day work will be completed?
(a) Tuesday (b) Wednesday
(c) Thursday (d) Friday

3. Kaushalya can do a work in 20 days, while Kaikeyi can do the same work in 25 days. They started the work jointly. Few days later Sumitra also joined them and thus all of them completed the whole work in 10 days. All of them were paid total Rs. 700. What is the share of Sumitra?
(a) Rs. 130 (b) Rs. 185
(c) Rs. 70 (d) can't be determined

4. A and B can complete the work individually in 24 days and 30 days respectively, working 10 hours a day. Work is to be done in two shift. Morning shift lasts for 6 hours and evening shift lasts for 4 hours. On the first day A works in the morning shift while B works in the evening shift. Next day A works in the evening shift while B works in the morning shift and so on. It means they work alternatively with respect to their shifts. Thus they work on this pattern till the work is completed. On which day the work got completed?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 26th day (b) 27th day
(c) 28th day (d) 30th day

5. In the previous question what per cent of the time of the morning shift was utilised?
(a) 33.33% (b) 60%
(c) 100% (d) none of these

6. Working together B and C take 50% more number of days than A, B and C together take and A and B working together, take $\frac{8}{3}$ more number of days than A, B and C take together. If A, B and C all have worked together till the completion of the work and B has received Rs. 120 out of the total earning of Rs. 450, then in how many days did A, B and C together complete the whole work?
(a) 10 (b) 6
(c) 4 (d) 2

7. At Technosys Pvt Ltd. there are some engineering students employed as trainee engineers, belong to two eminent institutions of India. One group belong to MIT and another to NIT. Each student of MIT works for 10 hours a day till 60 days and each student of NIT works for 8 hours till 80 days on the two same projects. The ratio of number of students of MIT and that of NIT is 4 : 5 respectively. Students of which institution is slower in work and by how much?
(a) Each student of MIT is 20% less efficient than that of NIT
(b) Each student of NIT is 33.33% less efficient than that of MIT
(c) Each student of NIT is 25% less efficient than that of MIT
(d) Each student of MIT is 33.33% less efficient than that of NIT.

Directions for questions 8, 9 and 10 : At Arihant Prakashan every book goes through 3 phases (or stages) typing, composing and binding. There are 16 typists, 10 composers and 15 binders. A typist can type 8 books in each hour, a composer can compose 12 books in each hour and a binder can bind 12 books in each hour. All of the people at Arihant Prakashan works for 10 hours a day and each person is trained to do only the job of 1 category.

8. How many books can be prepared in each day?
(a) 1500 (b) 1200
(c) 1440 (d) 1380

9. If company has hired 12 more people, who can do any of the three jobs, then maximum how many books can be prepared in each day?
(a) 1500
(b) 1680
(c) 1800
(d) more than 2000

10. If company wanted to reduce the number of employees by 3, then from which category it reduces the number of employees without reducing the amount of production of books?
(a) It should reduce two binders and 1 typist
(b) It should reduce three binders only
(c) It should reduce 1 typist, 1 composer and 1 binder
(d) both (a) and (b) are possible

11. Bunty and Babli working together completed a job in 8 days. If Bunty worked twice efficiently as he actually did and Babli worked $\frac{1}{3}$ as efficiently as she actually did, the work would have been completed in 6 days. Find the time taken by Bunty to complete the job alone :
(a) 8 days (b) $\frac{38}{35}$ days
(c) $\frac{15}{2}$ days (d) $13\frac{1}{3}$ days

12. A single reservoir supplies the petrol to the whole city, while the reservoir is fed by a single pipeline filling the reservoir with the stream of uniform volume. When the reservoir is full and if 40,000 litres of petrol is used daily, the supply fails in 90 days. If 32,000 litres of petrol is used daily, it fails in 60 days. How much petrol can be used daily without the supply ever failing?
(a) 64000 litres (b) 56000 litres
(c) 78000 litres (d) 60000 litres

13. Railneer is packaged in a water bottling plant, with the help of two machines M_1 and M_2. M_1 and M_2 produces 400 and 600 bottles per minute. One day's production can be processed by M_1 operating alone for 9 hours, by M_2 operating alone for 6 hours or by both M_1 and M_2 operating simultaneously for 3 hours and 36 minutes. If one days production is processed by M_1 operating alone for $\frac{1}{3}$ of the time and M_1 and M_2 simultaneously operating for $\frac{2}{3}$ of the time, then in how many hours total production of one day will be completed?
(a) 2 (b) 3
(c) 4.5 (d) 4.8

Directions for questions 14 and 15 : A contractor employed a certain number of workers to finish constructing a road in a certain scheduled time. Sometime later, when a part of work had been completed, he realised that the work would get delayed by three-fourth of the scheduled time, so he at once doubled the number of workers and thus he managed to finish the road on the scheduled time.

14. How much work he had been completed, before increasing the number of workers?
(a) 10%
(b) $14\frac{2}{7}\%$
(c) 20%
(d) can't be determined

15. Some-time after the new workers were introduced, all of the newly introduced workers left the work due to heavy rain and the efficiency of the remaining workers reduced by 20% due to which the work finally got completed by delay of 60% of the scheduled time then how much work still remained incomplete by the end of the scheduled time?
(a) $17\frac{3}{5}\%$ (b) 21%
(c) $27\frac{5}{7}\%$ (d) 28%

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions for questions 16 to 20 : Mr. Stenley employed a certain number of typists for his project. 8 days later 20% of the typist left the job and it was found that it took as much time to complete the rest work from then as the entire work needed with all the employed typists. The average speed of a typist is 20 pages/hour.

16. How many typists left the work?
(a) 10 (b) 5
(c) 16 (d) can't be determined

17. Minimum how many typist could be employed?
(a) 10 (b) 5
(c) 15 (d) 4

18. What could be the number of typists remained at work when 20% of the employed typists left the job?
(a) 15 (b) 18
(c) 68 (d) 78

19. What is the actual number of days required, when it is done with actual work force, through out the completion :
(a) 32 days (b) 48 days
(c) 40 days (d) can't be determined

20. 16 days after the 20% typist left the job it was decided to complete the work on time by increasing the work-force again. By how much percentage increase in work-force is required?
(a) 100% (b) 50%
(c) 200% (d) none of these

21. Five tailors *A*, *B*, *C*, *D* and *E* stich 1800 shirts in 90 days working alternatively. Find the minimum possible number of shirts that can be stiched in a single day by working together :
(a) 100 (b) 20
(c) 50 (d) 4

Directions for question number 22, 23 : 8 men and 5 women working 6 hours a day can complete a work in 4 days. Also 4 men and 5 women working for 8 hours a day can complete the same job in 5 days. Similarly 5 boys working 8 hours a day can complete the same job in 30 days.

22. If 4 men, 3 women and 4 boys worked together everyday for 5 hours, then in how many days they have completed the work?
(a) 3 (b) 4
(c) 8 (d) 6

23. If women and children (boys) can't be employed, then minimum how many men are required to complete the job in 6 days if the working hours per day cannot exceed 9?
(a) 4 (b) 5
(c) 6 (d) 7

24. Eklavya can do the 6 times the actual work in 36 days while Faizal can do the one-fourth of the original work in 3 days. In how many days will both working together complete the 3 times of the original work?
(a) 6 (b) 10
(c) 12 (d) 15

25. Progressive Company Pvt. Ltd. hired some employees in a fix pattern. On the first day it hired one person, on the second day one more joined him. On the third, fourth etc (*i.e.*, every next day) one more person increased in this group. The capacity of each person was same. The whole work was completed on the 24th day then out of total Rs. 5000, maximum how much a person had earned?
(a) Rs. 500 (b) Rs. 400
(c) Rs. 200 (d) Rs. 250

26. Two persons having different productivity of labour, working together can reap a field in 2 days. If one-third of the field was reaped by the first man and rest by the other one working alternatively took 4 days. How long did it take for the faster person to reap the whole field working alone?
(a) 12 (b) 8
(c) 6 (d) 3

27. The total number of men, women and children working in a factory is 18. They earn Rs. 4000 in a day. If the sum of the wages of all men, all women and all children is in the ratio of 18 : 10 : 12 and if the wages of an individual man, woman and child is in the ratio 6 : 5 : 3, then how much a woman earn in a day?
(a) Rs. 400 (b) Rs. 250
(c) Rs. 150 (d) Rs. 120

28. A group of workers was put on a job. From the second day onwards, one worker was withdrawn each day. The job was finished when the last worker was withdrawn. Had no worker been withdrawn at any stage, the group would have finished the job in 55% of the time. How many workers were there in the group?
(a) 50 (b) 40
(c) 45 (d) 10

29. Two workers undertake to do a job. The second worker started working 2 hours after the first. Five hours after the second worker has begun working there is still $\frac{9}{20}$ of the work to be done. When the assignment is completed, it turns out that first worker has done 60% of the work, while second worker has done rest of the work. How many hours would it take each one to do the whole job individually?
(a) 10 hours and 12 hours
(b) 15 hours and 10 hours
(c) 20 hours and 25 hours
(d) 18 hours and 20 hours

30. A group of men decided to do a job in 4 days. But since 20 men dropped out every day, the job completed at the end of the 7th day. How many men were there at the beginning?
(a) 240 (b) 140
(c) 280 (d) 150

31. Brahma, Vishnu and Mahesh are three friends with different productivity. Brahma working alone needs as much time as Vishnu and Mahesh working together, while Vishnu himself needs 8 hours more working alone than when he works with Mahesh. Brahma working alone needs 8 hours less than Vishnu needs working alone. In how much time Brahma, Vishnu and Mahesh working together can complete the job?
(a) 4 hours (b) 5 hours
(c) 6 hours (d) 8 hours

Scanned by CamScanner

yourSmartbook.wordpress.com

32. Milinda takes $8\frac{1}{3}$ hours more when she works alone in comparison of when she works with Bill. While Bill takes $5\frac{1}{3}$ hours more when he work alone in comparison to the time, when he works with Milinda. How long it will take Bill to complete the work alone?

(a) 10 hours (b) 15 hours
(c) 18 hours (d) 12 hours

33. Pascal and Rascal are two workers. Working together they can complete the whole work in 10 hours. If the Pascal worked for 2.5 hours and Rascal worked for 8.5 hours, still there was half of the work to be done. In how many hours Pascal working alone, can complete the whole work?

(a) 24 hours (b) $17\frac{1}{7}$ hours
(c) 40 hours (d) can't be determined

34. Boston, Churchill and David are three workers, employed by a contractor. They completed the whole work in 10 days. Initially all of them worked together, but the last 60% of the work was completed by only Churchill and David together. Boston worked with Churchill and David only for initial two days then he left the work due to his poor health. Also Churchill takes 20% less time to finish the work alone than that of David working alone. If they were paid Rs. 3000 for the entire work, then what is the share of least efficient person?

(a) Rs. 900 (b) Rs. 1200
(c) Rs. 1000 (d) none of these

35. There are three boats B_1, B_2 and B_3 working together they carry 60 people in each trip. One day an early morning B_1 carried 50 people in few trips alone. When it stopped carrying the passengers B_2 and B_3 started carrying the people together. It took a total of 10 trips to carry 300 people by B_1, B_2 and B_3. It is known that each day on an average 300 people cross the river using only one of the 3 boats B_1, B_2 and B_3. How many trips it would take to B_1 to carry 150 passengers alone?

(a) 15 (b) 30
(c) 25 (d) 10

36. Three men and 5 women together can finish a job in 3 days. Working on the same job 3 women take 5 days more than the time required by 2 men. What is the ratio of efficiency of a man to a woman?

(a) 2 : 1 (b) 3 : 2
(c) 5 : 2 (d) 4 : 1

37. Henry and Ford are two different persons, but when they worked together, they complete it in 10 days. Had Henry worked at half of his efficiency and Ford at five times of his efficiency it would have taken them to finish the job in 50% of the scheduled time. In how many days Ford can complete the job working alone?

(a) 12 (b) 24
(c) 15 (d) 30

38. Anne, Benne and Cenne are three friends. Anne and Benne are twins. Benne takes 2 days more than Cenne to complete the work. If Anne started a work and 3 days later Benne joins him, then the work gets completed in 3 more days. Working together Anne, Benne and Cenne can complete thrice the original work in 6 days. In how many days Benne can complete twice the original work with double the efficiency working alone?

(a) 2 (b) 3
(c) 4 (d) 6

39. Three typists A, B and C working together 8 hours per day can type 900 pages in 20 days. In a day B types as many pages more than A as C types as many pages more than B. The number of pages typed by A in 4 hours equal to the number of pages typed by C in 1 hour. How many pages C types in each hour?

(a) 1 (b) 2
(c) 3 (d) 4

Directions for question number 40 and 41: Four pipes A, B, C and D can fill a cistern in 20, 25, 40 and 50 hours respectively.

40. The first pipe A was opened at 6:00 am, B at 8:00 am, C at 9:00 am and D at 10:00 am. When will the cistern be full?

(a) 4:18 pm (b) 3:09 pm
(c) 12:15 pm (d) 11:09 am

41. If A and B are opened as inlet pipe into the cistern and C and D are opened as outlet pipes from the cistern and all the four pipes are opened simultaneously, how many hours will it take to fill the cistern completely?

(a) 20 hours (b) $11\frac{1}{9}$ hours
(c) $22\frac{2}{9}$ hours (d) 45 hours

42. A tank is connected with four pipes A, B, C and D of which two are filling the tank and other two are emptying it. The time taken by A, B, C and D to finish their jobs are 10 hours, 15 hours, 20 hours and 30 hours respectively. All four pipes are opened. When the tank was empty, it took 12 hours to fill it completely. Which two are the outlet pipes?

(a) A and B (b) C and D
(c) A and C (d) B and D

43. Two pipes A and B can fill a tank in 24 hours and $\frac{120}{7}$ hours respectively. Harihar opened the pipes A and B to fill an empty tank and some times later he closed the taps A and B, when the tank was supposed to be full. After that it was found that the tank was emptied in 2.5 hours because an outlet pipe 'C' connected to the tank was open from the beginning. If Harihar closed the pipe C instead of closing pipes A and B the remaining tank would have been filled in :

(a) 2 hours (b) 8 hours
(c) 6 hours (d) 4 hours

44. Pipe A can fill a tank in 12 hours and pipe B can fill it in 15 hours, separately. A third pipe C can empty it in 20 hours. Initially pipe A was opened, after one hour pipe B was opened and then after 1 hour when pipe B was opened pipe C was also opened. In how many hours the tank will be full?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $9\frac{2}{3}$ hours (b) $6\frac{2}{3}$ hours
(c) 10 hours (d) none of these

Directions for question number 45 and 46: A tank has an inlet and outlet pipe. The inlet pipe fills the tank completely in 2 hours when the outlet pipe is plugged. The outlet pipe empties the tank completely in 6 hours when the inlet pipe is plugged.

45. If both pipes are opened simultaneously at a time when the tank was one-third filled, when will the tank fill thereafter?
(a) $\frac{3}{2}$ hours (b) $\frac{2}{3}$ hour
(c) 2 hours (d) $1\frac{2}{3}$ hours

46. If there is a leakage also which is capable of draining out the liquid from the tank at half of the rate of outlet pipe, then what is the time taken to fill the empty tank when both the pipes are opened?
(a) 3 hours (b) $3\frac{2}{3}$ hours
(c) 4 hours (d) none of these

47. An inlet pipe can fill a tank in 5 hours and an outlet pipe can empty the same tank in 36 hours, working individually. How many additional number of outlet pipes of the same capacity are required to be opened, so that the tank never over flows?
(a) 3 (b) 6
(c) 8 (d) 7

Directions for question number 48 and 49: In a public bathroom there are n taps 1, 2, 3... n. Tap 1 and tap 2 take equal time to fill the tank while tap 3 takes half the time taken by tap 2 and tap 4 takes half the time taken by tap 3. Similarly each next number of tap takes half the time taken by previous number of tap i.e., K^{th} tap takes half the time taken by $(K-1)^{th}$ tap.

48. If the 10th tap takes 2 hours to fill the tank alone then what is the ratio of efficiency of 8th tap and 12th tap, respectively?
(a) 4 : 1 (b) 5 : 3
(c) 16 : 1 (d) 1 : 16

49. If the 8th tap takes 80 hours to fill the tank then the 10th and 12th taps working together take how many hours to fill the tank?
(a) 2 hours (b) 4 hours
(c) 6 hours (d) none of these

50. Pipe *A* takes 3/4 of the times required by pipe *B* to fill the empty tank individually. When an outlet pipe *C* is also opened simultaneously with pipe *A* and pipe *B*, it takes 3/4 more time to fill the empty tank than it takes, when only pipe *A* and pipe *B* are opened together. If it takes to fill 33 hours when all the three pipes are opened simultaneously, then in what time pipe *C* can empty the full tank operating alone?
(a) 66 hours (b) 50 hours
(c) 44 hours (d) can't be determined

Directions for question number 51, 52 and 53: A contractor undertook a project to complete it, in 20 days which needed 5 workers to work continuously for all the days estimated. But before the start of the work the client wanted to complete it earlier than the scheduled time, so the contractor calculated that he needed to increase 5 additional men every 2 days to complete the work in the time the client wanted it :

51. How many men were working on the day the project was completed as per the date of client wanted to complete it?
(a) 5 (b) 10
(c) 20 (d) none of these

52. Find the number of days in which client wanted to complete his work.
(a) 15 (b) 10
(c) 8 (d) can't be determined

53. If the work was further increased by 50% but the contractor continues to increase the 5 workers on every 2 days then how many more days are required over the initial time specified by the client?
(a) 1 day (b) 2 days
(c) 5 days (d) none of these

54. A tank is connected with 8 pipes. Some of them are inlet pipes and rest work as outlet pipes. Each of the inlet pipe can fill the tank in 8 hours, individually, while each of those that empty the tank *i.e.*, outlet pipe, can empty it in 6 hours individually. If all the pipes are kept open when the tank is full, it will take exactly 6 hours for the tank to empty. How many of these are inlet pipes?
(a) 2 (b) 4
(c) 5 (d) 6

55. A tank has two inlet pipes which can fill the empty tank in 12 hours and 15 hours working alone and one outlet pipe which can empty the full tank in 8 hours working alone. The inlet pipes are kept open for all the time but the outlet pipe was opened after 2 hours for one hour and then again closed for 2 hours then once again opened for one hour. This pattern of outlet pipe continued till the tank got completely filled. In how many hours the tank has been filled, working on the given pattern?
(a) 8 hours 24 minutes (b) 10 hours 15 minutes
(c) 9 hours 10 minutes (d) 9 hours 6 minutes

Final Round

Directions for question number 1 to 5 : In a nut-bolt factory 180 workers are working for 6 hours a day. Out of 180 workers there are some men, some women and rest are boys. All the workers can produce either nut or bolt or both of them. A man can produce 60 nuts and 80 bolts in each hour and a woman can produce 30 nuts and 60 bolts per hour. A man is thrice as efficient as a boy and 3/2 times as efficient as a woman. Given that all men, all women and all boys produce equal number of articles of one kind (i.e., either nut or bolt) per hour.

Scanned by CamScanner

yoursmahboob.wordpress.com

1. Working 6 hours a day, how many nuts they can produce with 52500 bolt in each day?
(a) 17500 (b) 26250
(c) 50850 (d) can't be determined

2. In how many hours can 15 men, 12 women and 8 boys can produce 12000 nuts and 8200 bolts?
(a) 3 (b) 5
(c) 6 (d) none of these

3. If 30 women and 50 boys can produce 5400 bolts in one hour then to produce equal number of nuts in one hour how many men are required?
(a) 30 (b) 40
(c) 50 (d) none of these

4. If the efficiency of each boy is doubled then what is the increase in production per hour?
(a) 100% (b) 50%
(c) 33.33% (d) none of these

5. If the manager of factory wanted equal number of men, women and boys in his factory but the efficiency of a man, woman and a boy remains constant, then the change in production is :
(a) increased by 10% (b) decreased by 10%
(c) increased by 8.33% (d) none of these

6. Ram Lal is a renowned packager of fruits in Varanasi. He packs 70 mangoes or 56 guavas every day working 7 hours per day. His wife also helps him. She packs 30 mangoes or 24 guavas working 6 hours per day. Ram Lal has to pack 3300 mangoes and 2400 guavas with the help of his wife. They work alternatively, each day 10 hours. His wife started packaging on the first day and works on every alternate days. Similarly Ram Lal started his work on second day and worked alternatively till the completion of the work. In how many days the work will be finished?
(a) 85 days (b) $85\frac{2}{5}$ days
(c) 84 days (d) none of these

Directions for question number 7 to 11 : *A company produces three products. The products are processed on 3 different machines. The time required to manufacture one unit of each the three products and the daily capacity of three machines are given in the table below :*

Machine	Time per unit (in min.)			Machine capacity (min./day)
	Product 1	Product 2	Product 3	
M_1	2	2	3	450
M_2	2	5	–	410
M_3	3	–	4	480

7. How many units of product 1 can be produced in one day?
(a) 160 (b) 205
(c) 225 (d) 64

8. If minimum 20 units of P_1 and 30 units of P_2 have to be produced, then what is the maximum units of P_3 that can be produced in a day?
(a) 116 (b) 105
(c) 205 (d) 220

Directions for questions 9, 10 and 11 : *Read the following additional data for question number 9, 10 and 11. The profit per unit for product 1, 2 and 3 is Rs. 3, Rs. 4 and Rs. 5.*

9. What combination of P_1, P_2 and P_3 will yield maximum profit, under the manufacturing constraints?
1. $P_1 - 25$, $P_2 - 50$, $P_3 - 100$
2. $P_1 - 20$, $P_2 - 60$, $P_3 - 80$
3. $P_1 - 100$, $P_2 - 0$, $P_3 - 50$
4. $P_1 - 0$, $P_2 - 80$, $P_3 - 100$
(a) 4 (b) 2
(c) 3 (d) 1

10. Which of the machine if it breaks down will affect profitability the least?
(a) Machine 1 (b) Machine 2
(c) Machine 3 (d) Machine 1 or 3

11. If no production of product 2 is scheduled today and it is decided to only produce one type of product today, then what is the maximum profits that can be had today?
(a) Rs. 480 (b) Rs. 750
(c) Rs. 600 (d) none of these

Directions for question number 12-15 : *Ready Tailoring Services is very well known in its quality and time bound services. The company (Ready Tailoring Services) received a large order for stiching military uniforms. It has two different orders to prepare the shirts one for Officers and second for Jawans (non-officers). It has three cutters who will cut the fabric. Six tailors who will do the stiching and 3 assistant to stich the buttons and iron the shirts. Each of these 12 persons will work for exactly 8 hours a day. Each of the Officers uniform requires 20 minutes for cutting the fabric, 1 hour for stiching and 20 minutes for stiching buttons and ironing the shirts. Whereas the Jawan's uniform requires 15 minutes for cutting the fabric and 60 minutes for stiching and 10 minutes for buttons and ironing.*

12. If the company has to supply 40 officers uniforms only and no other on a particular day, how many man-hours are utilised on that day?
(a) $33\frac{1}{3}$ hours (b) $66\frac{2}{3}$ hours
(c) 40 hours (d) 60 hours

13. If the number of tailors will be increased by 50% then maximum how many uniforms for officers can be completed in one day?
(a) 48 (b) 50
(c) 60 (d) 72

14. If the company can increase maximum 3 employees of any category then for which category should it hire to get maximum increase in production capacity, assuming that it needs to stich only officer's uniform :
(a) cutter (b) tailor
(c) assistant (d) can't be determined

15. If the company has to produce the shirts for only one category then of which category it can produce maximum number of uniforms?
(a) Officers (b) Jawans
(c) either (a) or (b) (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

LEVEL-1

1 (c)	2. (b)	3. (c)	4. (a)	5. (d)	6. (b)	7. (b)	8. (c)	9. (b)	10. (c)
11. (b)	12. (c)	13. (a)	14. (a)	15. (b)	16. (b)	17. (a)	18. (a)	19. (b)	20. (a)
21. (a)	22. (c)	23. (d)	24. (c)	25. (b)	26. (b)	27. (a)	28. (c)	29. (c)	30. (c)
31. (b)	32. (a)	33. (b)	34. (d)	35. (a)	36. (c)	37. (c)	38. (b)	39. (b)	40. (d)
41. (a)	42. (b)	43. (b)	44. (c)	45. (b)	46. (a)	47. (a)	48. (c)	49. (a)	50. (a)
51. (c)	52. (a)	53. (d)	54. (b)	55. (a)	56. (c)	57. (b)	58. (a)	59. (d)	60. (a)
61. (a)	62. (c)	63. (b)	64. (d)	65. (c)	66. (b)	67. (b)	68. (a)	69. (b)	70. (b)
71. (b)	72. (c)	73. (d)	74. (a)	75. (c)	76. (d)	77. (b)	78. (b)	79. (b)	80. (c)
81. (b)	82. (a)	83. (a)	84. (a)	85. (b)	86. (a)	87. (b)	88. (d)	89. (c)	90. (c)
91. (d)	92. (c)	93. (a)	94. (b)	95. (a)	96. (c)	97. (a)	98. (b)	99. (c)	100. (a)

LEVEL-2

1 (a)	2. (c)	3. (c)	4. (b)	5. (c)	6. (c)	7. (c)	8. (b)	9. (c)	10. (d)
11. (d)	12. (b)	13. (c)	14. (b)	15. (c)	16. (d)	17. (b)	18. (c)	19. (c)	20. (d)
21. (a)	22. (c)	23. (b)	24. (c)	25. (b)	26. (d)	27. (b)	28. (d)	29. (c)	30. (b)
31. (c)	32. (d)	33. (b)	34. (c)	35. (a)	36. (c)	37. (d)	38. (d)	39. (c)	40. (b)
41. (c)	42. (b)	43. (b)	44. (a)	45. (c)	46. (c)	47. (d)	48. (d)	49. (b)	50. (c)
51. (c)	52. (c)	53. (b)	54. (b)	55. (c)					

FINAL ROUND

1 (c)	2. (b)	3. (a)	4. (c)	5. (c)	6. (c)	7. (a)	8. (b)	9. (d)	10. (b)
11. (c)	12. (b)	13. (d)	14. (b)	15. (c)					

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1. Efficiency of $A = \frac{100}{12} = 8.33\%$

Efficiency of $B = \frac{100}{15} = 6.66\%$

Combined efficiency of A and $B = 8.33 + 6.66 = 15\%$

Number of days taken by A and B, when worked together

$$= \frac{100}{15} = 6\frac{10}{15} = 6\frac{2}{3} \text{ days}$$

NOTE Efficiency × Time period = Fixed amount of work

Also, in terms of percentage total work to be done is considered as 100% (in fraction it is 1), unless otherwise stated.

Alternatively : It can be done through unitary method, also.

2. Efficiency of $A = \frac{100}{10} = 10\%$

Efficiency of $B = \frac{100}{12} = 8.33\%$

Efficiency of $C = \frac{100}{15} = 6.66\%$

Combined efficiency of A, B and $C = 10 + 8.33 + 6.66 = 25\%$

$\therefore$ Required number of days, when A, B and C worked together

$$= \frac{100}{25} = 4 \text{ days}$$

3. Efficiency of $A = 20\%\left(= \frac{100}{5}\right)$

Efficiency of $B = 10\%\left(= \frac{100}{10}\right)$

Efficiency of A, B and $C = 50\%\left(= \frac{100}{2}\right)$

$\therefore$ Efficiency of C = (Efficiency of A, B and C) − (Efficiency of A and B)

$$= (50) - (20 + 10) = 20\%$$

$\therefore$ Number of days required by C to work alone $= \frac{100}{20} = 5$ days

Alternatively : Go through options and satisfy the values.

	A	B	C	$(A + B + C)$
Days →	5	10	5	2
Efficiency →	20%	10%	20%	50%

Consider option (c)

4. Efficiency of $A = 12.5\%$

Efficiency of $B = 6.25\%$

Efficiency of $C = 1.25\%$

Efficiency of $(A + B + C) = 20\%\ (= 12.5 + 6.25 + 1.25)$

Required number of days $= \frac{100}{20} = 5$ days

5. Efficiency of $A = 10\%$

Efficiency of $B = 6.66\%$

$\therefore$ Required number of days $= \frac{100}{16.66} = 6$ days

6. Efficiency of $A = \frac{100}{24} = 4.16\%$

Efficiency of $B = \frac{100}{30} = 3.33\%$

Efficiency of $(A + B + C) = \frac{100}{12} = 8.33\%$

$\therefore$ Efficiency of $C = (8.33) - (4.16 + 3.33) = 0.83\%$

$\therefore$ Number of days required by C to complete the work alone

$$= \frac{100}{0.83} = \frac{100}{5/6} = 120 \text{ days}$$

NOTE $\frac{5}{6} = 0.833$

7. Efficiency of $A = 10\%$

Efficiency of $B = 4.16\%$

Efficiency of $(A + B + C) = 16.66\%$

$$\left\{\begin{array}{l} \frac{100}{10} = 10 \\ \frac{100}{24} = 4.16 \\ \frac{100}{6} = 16.66 \end{array}\right.$$

Efficiency of $C = (16.66) - (10 + 4.16) = 2.5\%$

Number of days required by C alone to finish the work

$$= \frac{100}{2.5} = 40 \text{ days}$$

8. Efficiency of $A = 7.14\%$

Efficiency of $B = 4.76\%$

Efficiency of $A + B = 11.9\%$

$\therefore$ Number of days required by A and B, working together

$$= \frac{100}{11.9} = 8.4 \text{ days}$$

HINT You can see that there is only one option between 8 and 9 which is 8.4 hence (c) is the correct choice.

Explanation : For 8 days denominator should be 12.5 and for 9 days denominator should be almost 11.

Alternatively : One day's work of A and B

$$= \frac{1}{14} + \frac{1}{21} = \frac{5}{42}$$

$\therefore$ Required number of days $= \frac{42}{5} = 8.4$ days

Scanned by CamScanner

yoursmahboob.wordpress.com

9. Efficiency of $A = 4.16\%$

Efficiency of $B = 1.6 \times 4.16 = 6.66\%$

$\therefore$ Number of days required by $B = \dfrac{100}{6.66} = 15$ days

Alternatively :

		A	B
Efficiency	$\rightarrow$	x	$1.6x$
Days	$\rightarrow$	$1.6k$	k

(Since number of days are inversely proportional to efficiency)

Now $1.6k = 24 \Rightarrow k = 15$ day

Alternatively : A's one day's work $= \dfrac{1}{24}$

$\therefore$ B's one day's work $= 160\%$ of $\dfrac{1}{24} = \dfrac{1}{15}$

$\therefore$ Required number of days $= 15$

10. Efficiency of $A + B = \dfrac{100}{14} = 7.14\%$

Again the ratio of efficiency of A and $B = 2:1$

$\therefore$ Efficiency of $A = \dfrac{2}{3} \times 7.14 = 4.76\%$

$\therefore$ required number of days by $A = \dfrac{100}{4.76} = 21$ days

NOTE Only choice (c) lies between 20 and 24.

Explanation : For 20 days denominator should be 5 and for 24 days, denominator should be 4.16 also the only choice (c) gives a value which is multiple of 7 and very close to the answer (as appears).

Alternatively : One day's work of

$$A \text{ and } B = \frac{1}{x} + \frac{1}{2x} = \frac{1}{14}$$

$$\Rightarrow \quad x = 21$$

Since A is twice efficient as B so A will take half of the days taken by B.

11. Efficiency of $A + B = 14.28\% \left(= \dfrac{100}{7}\right)$

Now, since the ratio of efficiency of A and B is $2:1$

So, the efficiency of $A = \dfrac{2}{3} \times 14.28 = 9.52\%$

$\therefore$ Number of days required by $A = 10.5$ days

HINT Only choice (b) is correct since there is no other value (In option) lies between 10 and 11.

Explanation : For 10 days, denominator should be 10 and for 11 days, denominator should be 9.09.

Alternatively : Let A takes x days and then B takes $2x$ days

then 1 day's work of A and $B = \dfrac{1}{x} + \dfrac{1}{2x} = \dfrac{1}{7}$

$$\Rightarrow \quad x = 10.5$$

Thus A takes 10.5 days.

12.

		A		B
Efficiency	$\rightarrow$	3	:	1
Days	$\rightarrow$	1	:	3

(Since number of days are inversely proportional to the efficiency)

Now if A requires x days, so B requires $3x$ days

$\therefore$ Difference of required days $(= 3x - x) = 2x = 10$

$$\Rightarrow \quad x = 5$$

Hence the number of days required by $B = 3x = 3 \times 5 = 15$ days

13.

		A		B
Efficiency	$\rightarrow$	2	:	1
Days	$\rightarrow$	1	:	2

$\left(\text{Days} \propto \dfrac{1}{\text{Efficiency}}\right)$

Now, let A requires x days, then B requires $2x$ days

$\therefore$ difference in number of days $(= 2x - x) = x = 6$

$$\Rightarrow \quad x = 6$$

$\therefore$ B requires $2x = 2 \times 6 = 12$ days

Alternatively : If A takes x days, then B takes $x + 6$ days

Now, A's 1 day's work $= \dfrac{1}{x}$

B's 1 day's work $= \dfrac{1}{x+6}$

$$\therefore \quad \frac{1/x}{\frac{1}{x+6}} = \frac{2}{1}$$

(Since A does twice the work as B does)

$$\Rightarrow \quad x = 6$$

$\therefore$ B takes $2x = 12$ days.

Alternatively : $\dfrac{1}{x} + \dfrac{1}{(x+6)} = \dfrac{1}{4}$

$\Rightarrow$ $x = 6$ and $2x = 12$ days (required by B)

Alternatively : Go through option and satisfy all the conditions.

14.

	A	:	B	:	C
Ratio of efficiency	3	:	1	:	2
Ratio of number of days	$\left\{\frac{1}{3}\right.$	:	$\frac{1}{1}$	:	$\left.\frac{1}{2}\right\}$
or	2	:	6	:	3

Hence, (a) is correct $\left[\because \text{Time} \propto \dfrac{1}{\text{Efficiency}}\right]$

15.

	Ajit		Bablu
Efficiency	3	:	1
No. of days	1	:	3

16.

	X		Y
Efficiency	5	:	1
No. of days	1	:	5

17. Efficiency of $A + B = \dfrac{100}{\frac{20}{3}} = 15\%$

	A		B
No. of days	4	:	5
Efficiency	5	:	4

$\therefore$ Efficiency of $B = \dfrac{4}{9} \times 15 = \dfrac{20}{3} = 6\dfrac{2}{3}\%$

Scanned by CamScanner

yoursmahboob.wordpress.com

18. Efficiency of $A + B = 33.33\% \left(= \frac{100}{3}\right)$

Ratio of efficiency of A and $B = 3 : 1$

$\therefore$ Efficiency of $A = \frac{3}{4} \times 33.33 = 25\%$

$\therefore$ Number of days taken by $A = 4 \left(= \frac{100}{25}\right)$

Alternatively :

	A		B
Efficiency	3	:	1
No. of days	1 (x)	:	3 (x)

$\therefore$ Difference in days $= 2x = 8$

$\Rightarrow$ $x = 4$ and $3x = 12$

Therefore number of days taken by A, working alone = 4 days

Alternatively : $\frac{1}{x} + \frac{1}{(x+8)} = \frac{1}{3}$

Now, you can use the options, or solve the equations to get the value of x which is equal to 4.

19. Efficiency of $(A + B) = 12.5\%$

Efficiency of $(B + C) = 8.33\%$

Efficiency of $(C + A) = 12.5\%$

$\therefore$ Efficiency of $[(A + B) + (B + C) + (C + A)] = 33.33\%$

$\therefore$ Efficiency of $(A + B + C) = 16.66\%$

$\therefore$ Number of days required by A, B and C together = 6 days $\left(= \frac{100}{16.66}\right)$

20. Efficiency of $(A + B) = 8.33\%$

Efficiency of $(B + C) = 6.66\%$

Efficiency of $(C + A) = 5.00\%$

$\therefore$ Efficiency of $A + B + C = \frac{1}{2}(8.33 + 6.66 + 5) = 10\%$

$\therefore$ Efficiency of C = Efficiency of $[(A + B + C) - (A + B)]$

$= (10 - 8.33) = 1.66\%$

$\therefore$ Number of days required by C alone $= \frac{100}{1.66} = 60$ days

21. Remember $\text{Time} \propto \frac{1}{\text{Efficiency}}$

Now,

		Ganga	:	Jamuna	:	Saraswati
Efficiency	$\rightarrow$	3	:	1	:	2
No. of days	$\rightarrow$	2	:	6	:	3

Again, efficiency of Ganga, Jamuna and Saraswati

$= \frac{100}{1} = 100\%$

$\therefore$ Efficiency of Ganga $= \frac{3}{6} \times 100 = 50\%$

Efficiency of Saraswati $= \frac{2}{6} \times 100 = 33.33\%$

Now, number of days taken by Ganga $= \frac{100}{50} = 2$

Number of days taken by Saraswati $= \frac{100}{33.33} = 3$

$\therefore$ Difference in number of days taken by Ganga and Saraswati

$= 3 - 2 = 1$ day

22. Day 1 2 3 4 5 6 7 8

A A A $(A + B)$ $(A + B)$ $(A + B)$ $(A + B)$ $(A + B)$

$3 \times \frac{1}{12} = \frac{3}{12} = 25\%$ work completed

Remaining work $= 75\% = (100 - 25)$

Now, efficiency of $A + B = 15\% = (8.33 + 6.66)$

$\therefore$ Number of days required by $A + B = \frac{75}{15} = 5$ to complete rest work (= 75%)

23. '3 days before the completion of the work Raja left the work' means in last 3 days only Rani has worked alone.

So, in last 3 days worked done by Rani $= 3 \times \frac{1}{21} = \frac{1}{7}$

So, the rest $\left(1 - \frac{1}{7}\right) = \frac{6}{7}$ work was done by Raja and Rani both.

Number of days in which Raja and Rani worked together

$= \frac{6/7}{5/42} = \frac{36}{5} = 7\frac{1}{5}$ days

NOTE Work done by Raja and Rani in one day $= \frac{1}{14} + \frac{1}{21} = \frac{5}{42}$

$\left(\text{Also, number of days} = \frac{\text{Total work to be done}}{\text{Work to be done in one day}}\right)$

24. Work done in 11 days $= \frac{11}{30}$

Rest work $= \frac{19}{30}$

1 day's work of $A = \frac{19/30}{28} = \frac{19}{30 \times 28} = \frac{19}{840}$

Total number of days required to complete the whole work alone

$= \frac{1}{19/840} = \frac{840}{19} = 44\frac{4}{19}$ days

25. Efficiency of Sonu $= 5\% = \left(\frac{100}{20}\right)$

Rest work = 75%

$\therefore$ Efficiency of Abhijeet $= \frac{75}{10} = 7.5\%$

$\therefore$ Combined efficiency of Sonu and Abhijeet

$= 12.5\% = (7.5 + 5)$

$\therefore$ Number of days required by Sonu and Abhijeet, to work together

$= \frac{100}{12.5} = 8$ days

26.

	Asha	Usha
Efficiency	5	4
No. of days	$4x$	$5x = 25$

$\therefore$ Number of days required by Asha to finish the work alone

$= 20$ $\quad \because (4x = 4 \times 5)$

Scanned by CamScanner

yoursmahboob.wordpress.com

(Alternatively, from percentage change graphic, number of days taken by Asha will be 20% less than Usha, if efficiency of Asha is 25% more than Usha)

Now, since Asha and Usha did work together for last 5 days

$= 5 \times 9 = 45\%$

(Since efficiency of Asha = 5% and Usha's efficiency = 4%)

It means Asha completed 55% work alone

∴ Number of days taken by Asha to complete 55% work

$= \frac{55}{5} = 11$ days

27. Krishna's efficiency = 10%

Mohan's efficiency = 5%

Work done by Krishna and Mohan together in 3 days

$= 15 \times 3 = 45\%$

Now, number of days in which B completed rest (55%) work alone $= \frac{55}{5} = 11$

Total number of days in which B worked = 3 + 11 = 14

Now number of days required by B, when A and B both worked together $= \frac{100}{15} = 6\frac{2}{3}$

∴ Required difference in number of days $= (11) - \left(6\frac{2}{3}\right)$

$= \frac{13}{3} = 4\frac{1}{3}$ days

28. Efficiency of Kareena and Karishma

$= 11.11 + 5.55 = 16.66\%$

Work done in 3 days $= 3 \times 16.66 = 50\%$

Rest work done by Kareena, Karishma and Shahid $= \frac{50}{50} = 1$ day

(Since efficiency of Shahid = 33.33%)

Thus in 4 (= 3 + 1) days they have completed the work.

29. Efficiency of Kavita = 5%

Efficiency of Babita = 1.66%

Efficiency of Samita = 3.33%

Work done in 5 days by $K + B + S = 5 \times (10) = 50\%$

Work done in 3 days by $K + B = 3 \times (6.66) = 20\%$

Remaining work (30%) done by Kavita alone $= \frac{30}{5} = 6$ days

30.

	A	:	B	:	C
Efficiency →	10	:	9	:	6
No. of days →	$9x$	:	$10x$	:	$15x$

Now, $15x - 9x = 6$

$\Rightarrow x = 1$

∴ Number of days taken by $A = 9$

Number of days taken by $B = 10$

Number of days taken by $C = 15$

Work done by B and C in initial 2 days $= \frac{2 \times 1}{6} = \frac{1}{3}$

rest work $= \frac{2}{3}$

Number of days required by A to finish $\frac{2}{3}$ work $= \frac{2/3}{1/9} = 6$ days

31.

	Anand	Bahuguna
No. of days	45	40
Efficiency	$2.22\%\left(=\frac{1}{45}\right)$	$2.5\%\left(=\frac{1}{40}\right)$

Anand did the work in 56 days $= 56 \times \frac{1}{45 \times 2} = \frac{28}{45}$

∴ Rest work $\left(\frac{17}{45}\right)$ was done by Anand and Bahuguna

$= \frac{17/45}{17/360} = 8$ days

(Since Anand and Bahuguna do the work in one day $= \frac{1}{45} + \frac{1}{40} = \frac{17}{360}$)

32. Efficiency of Chandni = 11.11%

Efficiency of Divakar = 8.33%

They do 19.44% work in 2 days

∴ They need 10 days to do 97.22% work,

Now the rest work (2.78) was done by Chandni in $\frac{2.78}{11.11} = \frac{1}{4}$ day

Therefore total number of days required $= 10 + \frac{1}{4} = 10\frac{1}{4}$ days

Alternatively : Chandni's one day's work $= \frac{1}{9}$

Divakar's one day's work $= \frac{1}{12}$

Chandni's and Divakar's (1 + 1) = 2 day's work $= \frac{1}{9} + \frac{1}{12} = \frac{7}{36}$

So, in 10 days they do $= \frac{7 \times 5}{36} = \frac{35}{36}$ work

So, the remaining $\frac{1}{36}\left(=1 - \frac{35}{36}\right)$ work will be done by Chandni $= \frac{1/36}{1/9} = \frac{1}{4}$ day

Thus total number of required days $= 10 + \frac{1}{4} = 10\frac{1}{4}$ days

HINT

Day	1	2	3	4	5	6	7	8	9	10	11
Turn	C	D	C	D	C	D	C	D	C	D	C
Work	$\frac{1}{9}$	$\frac{1}{12}$	$\frac{1}{9}$	$\frac{1}{12}$	$\frac{1}{9}$	$\frac{1}{12}$	$\frac{1}{9}$	$\frac{1}{12}$	$\frac{1}{9}$	$\frac{1}{12}$	$\frac{1}{36}$
	7/36		7/36		7/36		7/36		7/36		
	35/36										1/36

33.

Day	1	2	3	4	5	6	7	8	9	10	11	12	13	14
	F	Z	F	Z	F	Z	F	Z	F	Z	F	Z	F	Z
	$\frac{1}{12}$	$\frac{1}{15}$	$\frac{1}{12}$	$\frac{1}{15}$	$\frac{1}{12}$	$\frac{1}{15}$	$\frac{1}{12}$	$\frac{1}{15}$	$\frac{1}{12}$	$\frac{1}{15}$	$\frac{1}{12}$	$\frac{1}{15}$	$\frac{1}{12}$	$\frac{1}{60}$
	9/60		9/60		9/60		9/60		9/60		9/60			
	54/60												6/60	

In two days Fatima and Zahira do $= \frac{1}{12} + \frac{1}{15} = \frac{9}{60}$ work. In 12 days they do $= \frac{6 \times 9}{60} = \frac{54}{60}$ work

So, the remaining work $= \frac{6}{60} = \frac{1}{10}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Now, $\frac{1}{12}$ work will be done by Fatima in 13th day

So, the remaining work $= \frac{1}{10} - \frac{1}{12} = \frac{1}{60}$

This $\frac{1}{60}$ work will be done by Zahira $= \frac{1/60}{1/15} = \frac{1}{4}$ day

Thus the total number of days required

$$= 12 + 1 + \frac{1}{4} = 13\frac{1}{4} \text{ days}$$

Alternatively : A's efficiency = 8.33%, B's efficiency = 6.66%] 15%

Thus in 12 days 90% work will be done and in 13th day 8.33% more work will be done so the rest work 1.66% will be done by Zahira

$$= \frac{1.66}{6.66} = \frac{1}{4} \text{ day}$$

Thus, total number of required days $= 12 + 1 + \frac{1}{4} = 13\frac{1}{4}$

34. The difference will arise only on the last two days only. The work done on 13th day $= \frac{1}{15}$

$$\text{rest work} = \frac{1}{10} - \frac{1}{15} = \frac{1}{30}$$

This rest work $\left(\frac{1}{30}\right)$ will be done by Fatima $= \frac{1/30}{1/12} = \frac{2}{5}$ day

Thus total number of required days $= 12 + 1 + \frac{2}{5} = 13\frac{2}{5}$ days.

35.

1	2	3	4	5	6	7	8
A	B	C	A	B	C	A	B
1/6	1/12	1/8	1/6	1/12	1/8	1/6	1/12
3/8			3/8			1/4	

$$\frac{6}{8} = \frac{3}{4}$$

In 3 days A, B, C do $\frac{3}{8}$ work

In 6 days A, B, C do $\frac{3}{4}$ work

Rest work $= \frac{1}{4}$, which is less than $\frac{3}{8}$

On the 7th day, $\frac{1}{6}$ more work will be done by A

Now rest work $= \frac{1}{4} - \frac{1}{6} = \frac{1}{12}$

Now, this rest work $\left(\frac{1}{12}\right)$ will be done by B in 1 complete day.

Thus, total number of days $= 6 + 1 + 1 = 8$ days

Alternatively : Efficiency of $A = 16.66\%$

Efficiency of $B = 8.33\%$

Efficiency of $C = 12.5\%$

Efficiency of $A + B = 25\%$

Efficiency of $A + B + C = 37.5\%$

In 3 days A, B, C completes 37.5% work

In 6 days A, B, C completes 75% work

Rest work = 25%

This 25% work will be completed by A and B in next 2 days

Thus total $6 + 2 = 8$ days are needed.

36. From the previous solution 75% work will be completed in 6 days. In the next two days (*i.e.*, on 7th and 8th day) B and C will complete 20.83% (12.5+ 8.33) more work.

So the remaining work = 4.16%

This 4.16% work will be completed by $A = \frac{4.16}{16.66} = \frac{1}{4}$ day

So, the total number of required days $= 6 + 2 + \frac{1}{4} = 8\frac{1}{4}$ days.

37. Let B takes x days to complete the work individually.

Then, the B's 1 day's work $= \frac{1}{x}$

A's 1 day's work $= \frac{1}{x-6}$

C's 1 day's work $= \frac{1}{x-8}$

$$\therefore \quad \frac{1}{x-6} + \frac{1}{x} = \frac{1}{x-8}$$

Now either solve the equation or satisfy the equation from the choices given in the question.

Thus option (c) is correct.

Alternatively : Select an appropriate option and then solve through % efficiency.

38. A's share = Rs. 250

B's share = Rs. 100

It means the ratio of efficiency of $A : B = 250 : 100 = 5 : 2$

$\therefore$ Ratio of days taken by A and $B = 2x : 5x$

Now, $5x - 2x = 9 \Rightarrow x = 3$

$\therefore$ Number of days taken by $A = 6$ (efficiency = 16.66%)

Number of days taken by $B = 15$ (efficiency = 6.66%)

Therefore number of days taken by A and B, working together

$$= \frac{100}{23.33} = \frac{300}{70} = 4\frac{2}{7} \text{ days}$$

39. Alen's one day's work $= \frac{1}{21}$

Border's one day's work $= \frac{1}{42}$

(working alternatively) Alen and Border's two days work

$$= \frac{1}{21} + \frac{1}{42} = \frac{1}{14}$$

So, Alen and Border do $\frac{1}{14}$ work in 2 days

So, they complete the work in $14 \times 2 = 28$ days.

40. Efficiency of A and $B = 16.66\%$

Efficiency of B and $C = 10\%$

But efficiency of A is twice that of C

$\because$ Therefore, $A = 2C$

Now $A + B = 16.66$ and $B + C = 10$

$\Rightarrow$ $2C + B = 16.66$ ...(1)

and $C + B = 10$ ...(2)

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore$ from eq. (1) and (2) $C = 6.66\%$

$$A = 13.33\%$$

$\therefore$ Number of days taken by A to complete the work alone

$$= \frac{100}{13.33} = 7\frac{1}{2} \text{ days}$$

41. $A + B = 70\%$

$B + C = 50\%$ $\quad [\because A + B + B + C - (A + B + C) = B$, $70 + 50 - 100 = 20\%]$

$\Rightarrow$ $B = 20\%$

$A = 50\%$

and $C = 30\%$

Hence, A is most efficient.

42. $$C + M = \frac{8}{17}$$

$$M + G = \frac{12}{17}$$

$\Rightarrow$ $$M = \frac{3}{17}$$

$[\because (C + M + M + G) - (C + M + G) = M]$

$$\left[\left(\frac{8}{17} + \frac{12}{17}\right) - 1 = \frac{3}{17}\right]$$

$\therefore$ $$C = \frac{5}{17}$$

$$G = \frac{9}{17}$$

So the whole amount will be distributed in the ratio of 5 : 3 : 9 among C, M and G respectively.

Now since M is least efficient so he get his own share

$$= \frac{3}{17} \times 816 = \text{Rs. } 144$$

43.

	Sharma	Kelkar
Efficiency	$0.8x$	x
Number of day	k	$0.8k = 24$

$\because$ $0.8k = 24 \Rightarrow k = 30$

Thus Sharma requires 30 days, to complete the work, alone.

44.

	Man	Days	
$\frac{1}{5}\uparrow$	30	24	$\frac{1}{6}\downarrow$
	36	20	

Applying product constancy method.

For a constant work when days are reduced by $\frac{1}{6}$, then number of men is increased by $\frac{1}{5}$. Hence 6 men will increase.

Alternatively : $24 \times 30 = 20 \times x$

$\Rightarrow$ $$x = 36$$

Therefore 6 more men are required.

45.

	Women	Days	
$\downarrow\frac{1}{3}$	12	20	$\frac{1}{2}\uparrow$
	8	30	

Thus 10 more days are required.

Alternatively : $12 \times 20 = 8 \times x$

$\Rightarrow$ $$x = 30$$

$\therefore$ 10 more days are required.

46.

	Boys	Days	
$\frac{2}{5}\downarrow$	35	15	$\frac{2}{3}\uparrow$
	21	25	

Thus 14 boys did not turn up for the job.

Alternatively : $35 \times 15 = 25 \times x$

$\Rightarrow$ $$x = 21$$

$\therefore$ $35 - 21 = 14$ boys did not turn up for the job.

47. $x \times 32 = 24 \times 40$ $\quad (M_1D_1 = M_2D_2)$

48. $$M \times D = W$$

$$16 \times 6 = \frac{1}{3}W$$

$$\text{Rest work} = \frac{2}{3}W$$

For double work in same time we need double men. So 16 more men are required.

Alternatively : $2 \times (16 \times 6) = 6 \times M$

$\Rightarrow$ $$M = 32$$

$\therefore$ 16 more men are required.

49. $M \times D = 10 \times 20 = 200$ Man-days

New Man-days $= (20 \times 2) \times x$

$$200 = 20 \times 2 \times x$$

$$x = 5 \text{ days}$$

or $$M_1D_1 = M_2D_2$$

$$10 \times 20 = (20 \times 2) \times x$$

$\Rightarrow$ $$x = 5$$

50. $$M_1D_1 = M_2D_2$$

$$M_1 \times 20 = (M_1 - 12) \times 32$$

$\Rightarrow$ $$M_1 = 32$$

Also, using the above concept you can go through options.

51. Go through options. Consider option (c)

$$30 \times 20 = 30 \times 6 + 21 \times 20$$

$600 = 600$, hence presumed option is correct.

Alternatively : $30 \times 20 = 30 \times x + 21 \times (26 - x)$

$\Rightarrow$ $$x = 6$$

52. Go through options. Consider choice (a)

$25 \times 30 = 25 \times 15 + 75 \times 5$

$750 = 750$, hence choice (a) is correct.

Alternatively : $25 \times 30 = 25 \times x + 75 \times (20 - x)$

$\because \left[30 \times \frac{2}{3} = 20\right]$

53. Go through options. Consider choice (d)

$$36 \times 120 = 40 \times 108$$

$$4320 = 4320$$

Hence, choice (d) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively :

	Men	Days	
$\frac{1}{9}\uparrow$	x	120	$\left(\frac{1}{10}\right)\downarrow$
	$\downarrow$	$\downarrow$	
	$\left(x\times\frac{10}{9}\right)$	(12)	

From percentage change (product constancy) graphic when number of days are decreased by $\frac{1}{10}$ then the number of men are increased by $\frac{1}{9}$ and $\frac{1}{9}$ is equivalent to 4 men so the actual number of men are $9\times4=36$.

Alternatively : $M_1\ D_1 = M_2\ D_2$

$$x\times120=(x+4)\times108$$

$$\Rightarrow \quad x=36$$

54. Efficiency (per minute) of Modi = 4 copies/min

Efficiency of Modi and Xerox together = 10 pages/min

$\therefore$ Efficiency of Xerox alone = 10 – 4 = 6 pages/min

$\therefore$ Mr. Xerox needs 6 minutes to copy 36 pages.

55. $$\text{Work done}=\frac{1}{3}$$

$$\text{Remaining work}=\frac{2}{3}$$

$$2\times(20\times12)=12\times x$$

$$\Rightarrow \quad x=40$$

So, 20 men will be increased.

56. $$\text{Work done}=\frac{1}{5}$$

$$\text{remaining work}=\frac{4}{5}$$

$$\therefore \quad 4\,(20\times75)=40\times x$$

$$x=150$$

Therefore 75 men should be increased.

57. Work done by 6 men = Work done by 10 women.

$\Rightarrow$ Work done by 1 man = work done by $\frac{10}{6}=\frac{5}{3}$ women

$\therefore$ 12 men + 5 women $=12\times\frac{5}{3}+5=25$ women

$\therefore$ $W_1\times D_1=W_2\times D_2$, W = women, D = days

$$10\times15=25\times D_2$$

$$D_2=6$$

58. Work done by 2 men = 3 women = 4 boys

$\therefore$ 1 man = 2 boys

$$1\text{ woman}=\frac{4}{3}\text{ boys}$$

$\therefore$ boys × days = 4 × 52 (boys-days)

Again 1 man + 1 woman + 1 boy $=2+\frac{4}{3}+1=\frac{13}{3}$ boys

$B_1\times D_1=B_2\times D_2$, B = boys, D = days

$$4\times52=\frac{13}{3}\times D_2$$

$$D_2=48\text{ days}$$

59. 2 men = 7 boys $\Rightarrow$ 1 man $=\frac{7}{2}$ days

5 women = 7 boys $\Rightarrow$ 1 woman $=\frac{7}{5}$ boys

7 men + 5 women + 2 boys $=7\times\frac{7}{2}+5\times\frac{7}{5}+2=\frac{67}{2}$ boys

Now, $B_1\times D_1=B_2\times D_2$

$$7\times469=\frac{67}{2}\times D_2$$

$$\Rightarrow \quad D_2=98\text{ days}$$

60. $$6C+2M=6\text{ days}$$

$$\Rightarrow \quad 36C+12M=1\text{ days}$$

Again $1M=2C$

$\therefore$ $36+12\times2=1$ day

60 children can do the work in 1 day

Now, 5 men = 10 children

$\therefore$ 10 children can do the work in 6 days.

61. $$8M+12W=4\text{ days (whole work)}$$

$$\Rightarrow \quad 32M+48W=1\text{ day} \qquad \ldots(1)$$

Again $6M+14W=5$ days

$$\Rightarrow \quad 30M+70W=1\text{ day} \qquad \ldots(2)$$

From eq. (1) and (2)

$$32M+48W=30M+70W$$

$$\Rightarrow \quad 2M=22W$$

$$\Rightarrow \quad 1M=11W$$

Now, $30M+70W=1$ day

$$(30\times11+70)W=1\text{ day}$$

Therefore $400W$ requires 1 day to complete the whole work.

Thus $20W$ needs 20 days to complete the whole work.

62. Efficiency of A = 6.66%

Efficiency of B = 5.55%

Efficiency of $A+B+C$ = 16.66%

$\therefore$ Efficiency of C = 4.44%

Now, number of days required by

$$C=\frac{100}{4.44}=\frac{100}{(10\times4)/9}=\frac{45}{2}\text{ days}$$

63. Ratio of efficiencies of A, B and C = 6 : 5 : 4

$\therefore$ Share of $C=\frac{4}{15}\times27000=7200$

64. In 1 hour 314 weavers weave = 6594 × 6 shawls

In 1 hour 1 weaver weaves $=\frac{6594\times6}{314}$ shawls = 126 shawls

65. $$3M+2W=4\text{ days}$$

$$\Rightarrow \quad 12M+8W=1\text{ day} \qquad \ldots(1)$$

Again, $2M+3W=5D$

$$\Rightarrow \quad 10M+15W=1D \qquad \ldots(2)$$

From eq. (1) and (2)

$$12M+8W=10M+15W$$

$$\Rightarrow \quad 2M=7W$$

Scanned by CamScanner

yourmathbook.wordpress.com

$$\Rightarrow \quad \frac{M}{W} = \frac{7}{2}$$

Since the ratio of efficiency of women : men = 2 : 7
So, the amount of a man per day = Rs. 154

$$\left[\left(\frac{7}{2} \times 44\right) = 154\right]$$

66. Go through options.
Alternatively :

$$30 \times 40 = 30 \times x + 20 \times (46 - x)$$

$$\Rightarrow \quad x = 28 \text{ days}$$

67. Women × hours = 8 × 10 = 80 women hours
Now, women × hours = 12 × 8 = 96 women hours
Since new work force is 20% greater than previous work force.
So, the new quantity of tea leaves will be increased by 20% which is equal to $200 \times \frac{20}{100} = 40$ kg, hence (b)

68. New work = 3 × 450 man-day

$$\therefore \quad 3 \times 450 = 27 \times x$$

$$x = 50 \text{ days}$$

69.

$$4B + 5G = 10$$

$$\Rightarrow \quad 40B + 50G = 1 \qquad \ldots(1)$$

Again,

$$6B + 6G = 7$$

$$\Rightarrow \quad 42B + 42G = 1 \qquad \ldots(2)$$

Comparing eq. (1) and (2)

$$40B + 50G = 42B + 42G$$

$$\Rightarrow \quad 2B = 8G \quad \Rightarrow \quad 1B = 4G$$

Now, $(42 \times 4 + 42)$ girls = 1 day
210 girls can do a work in 1 day
Again $2B + 7G = 15$ girls
So, 15 girls require $\frac{210}{15} = 14$ days

70. Equate the man-days
For 20 km road, 20 × 20 = 400 man-days are required
∴ For 40 km road 800 man-days are required

So, $800 = 40 \times x$

$$\Rightarrow \quad x = 20 \text{ days}$$

71.

$$\frac{3}{4} \times (x - 2)\, x = (x + 7)(x - 10)$$

$$\Rightarrow \quad x^2 - 6x - 280 = 0$$

$$\Rightarrow \quad x = 20 \quad \text{and} \quad x = -14$$

So, the acceptable values is $x = 20$
∴ Total work = $(x - 2) \times x = 18 \times 20 = 360$ unit
Now $360 = 30 \times k \qquad \because (30 = 20 + 10)$

$$\Rightarrow \quad k = 12 \text{ days}$$

72. Efficiency of a man : woman : girl = 6 : 3 : 1

$$\therefore \text{ Share of a woman and girl} = \frac{(3+1)}{(6+3+1)} \times 10{,}000$$

$$= \frac{4}{10} \times 10000 = \text{Rs. } 4000$$

73. Total work = 33 × 30 = 990 man-days

$$\text{First day's work} = \frac{1}{990} \times 44$$

$$\text{Second day's work} = \frac{1}{990} \times 43$$

$$\text{Third day's work} = \frac{1}{990} \times 42 \text{ and so on}$$

$$\text{So, the total work in 44 days} = \frac{1}{990}(44 + 43 + 42 + \ldots)$$

$$= \frac{1}{990} \times \frac{44 \times 45}{2} = 1$$

Hence in 44 days total work will be completed.

74. Efficiency of Abhishek = 2.5% = $\left(\frac{100}{40}\right)$

Work done in 8 days = 20%
Rest work = 80%

$$\text{Efficiency of Bacchhan} = \frac{80}{24} = 3.33\%$$

$$\therefore \text{ Required number of days} = \frac{100}{(2.5 + 3.33)}$$

$$= \frac{100}{5.83} = \frac{100 \times 6}{35} = 17\frac{1}{7}$$

HINT $0.83 = \frac{5}{6}$, so, $5.83 = 5 + \frac{5}{6} = \frac{35}{6}$

75.

	A		B		C
Efficiency	3	:	2	:	6
Number of days	2	:	3	:	1

∴ Number of days taken by $A = 12$
Number of days taken by $B = 18$
Number of days taken by $C = 6$

$$1 \text{ day's work of } (A + B) = \frac{5}{36}$$

$$1 \text{ day's work of } (B + C) = \frac{8}{36}$$

$$1 \text{ day's work of } (C + A) = \frac{9}{36}$$

Day →	1	2	3	4	5	6
Work →	5/36	8/36	9/36	5/36	8/36	
	35/36					1/36

In 5 days total work done = $\frac{35}{36}$

Now, the rest work (1/36), which is done by AC.
∴ Number of days taken by AC for the rest work

$$= \frac{1/36}{9/36} = \frac{1}{9}$$

Therefore, total time = $5 + \frac{1}{9} = 5\frac{1}{9}$ days

76. Efficiency of $A + B = 16.66$
Efficiency of $B + J = 10$
We have no further relevent informations, so we cannot determine.

Scanned by CamScanner

yourSmartbook.wordpress.com

77.

	A	B
Efficiency	x	$2x$
Number of days	15	15/2

$$A\text{'s one day's work} = \frac{1}{15}$$

$$B\text{'s one day's work} = \frac{2}{15}$$

$$(A+B)\text{'s one day's work} = \frac{3}{15}$$

Now, let us assume B joined A after $(11-x)$ days, then

$$\frac{(11-x)}{15} + \frac{x \times 3}{15} = 1$$

$$\Rightarrow \quad (11-x) + 3x = 15$$

$$\Rightarrow \quad x = 2$$

It means they worked together for 2 days.

Alternatively: Go through options and check easily with the percentage efficiency.

$$9 \times 6.66 + 2 \times 20 = 100\%$$

78. Efficiency of $A = 6.66\%$

Efficiency of $B = 3.33\%$

Efficiency of $C = 2.5\%$

Work done in last two days (only C do it) $= 2 \times 2.5 = 5\%$

Work done in the 3rd and 4th day from the last day (only A and C do it)

$$= 2 \times 9.16 = 18.33\%$$

Remaining work $= 100 - (5 + 18.33) = 76.66\%$

This 76.66% work was done by all of A, B and C.

$\therefore$ Number of days taken by them $= \frac{76.66}{12.5} = \frac{460}{75} = 6\frac{2}{15}$

$\therefore$ Total time required $= 6\frac{2}{15} + 2 + 2 = 10\frac{2}{15}$ days

79. Let x kg of oil is used for eating purpose, daily, then

$$(x + 11) \times 50 = (x + 15) \times 45$$

$$x = 25$$

$\therefore$ Total quantity of oil $= (25 + 11) \times 50 = 1800$

$\therefore$ Required number of days $= \frac{1800}{25} = 72$ days

80. Work done $= \frac{2}{3}$

Remaining work $= \frac{1}{3}$, which is half of $\frac{2}{3}$

$$\therefore \quad \frac{1}{2} \times (20 \times 32) = 8 \times x$$

$$\Rightarrow \quad x = 40 \text{ men}$$

Therefore, 20 more men were required.

81. One day's work of 7 Indian with 4 Chinese $= \frac{1}{5}$

and one day's work of 7 Japanese and 3 Chinese $= \frac{1}{7}$

Therefore, one day's work of 7 Indian, 7 Chinese and 7 Japanese

$$= \frac{1}{5} + \frac{1}{7} = \frac{12}{35}$$

Therefore, one day's work of 1 Indian, 1 Chinese and 1 Japanese

$$= \frac{12}{35} \times \frac{1}{7} = \frac{12}{35 \times 7}$$

Therefore, number of days required by 1 Indian, 1 Chinese and 1 Japanese

$$= \frac{1}{12/(35 \times 7)} = \frac{35 \times 7}{12} = 20\frac{5}{12} \text{ days}$$

82. In 1 minute A, B and C bind $= \frac{1}{8} + \frac{1}{12} + \frac{1}{16} = \frac{13}{48}$ book

In 12 hours A, B and C bind $= 12 \times 60 \times \frac{13}{48} = 195$ books

$\therefore$ Average number of books bind by each $= \frac{195}{3} = 65$ books

83. Work of a man for 1 hour $= \frac{3}{2}$ women's work for 1 hour

Again, work of a man for 1 day

$$= \left(\frac{3}{2} \times \frac{9}{7.5}\right) \text{ women's work for 1 hour}$$

$\Rightarrow$ Work of a man for 1 day $= \frac{9}{5}$ women's work for 1 day

$$\Rightarrow \quad 1 \text{ man} = \frac{9}{5} \text{ women}$$

$$\therefore \quad 10 \text{ men} + 6 \text{ women} = 10 \times \frac{9}{5} + 6 = 24 \text{ women}$$

$$\therefore \quad 10 \text{ men} + 9 \text{ women} = 10 \times \frac{9}{5} + 9 = 27 \text{ women}$$

Now, $\quad D_1 \times W_1 = D_2 \times W_2$

$$18 \times 24 = D_2 \times 27$$

$$\Rightarrow \quad D_2 = 16 \text{ days}$$

84. Number of days taken by A to complete work alone $= 14$ days

Number of days taken by B to complete work alone $= 7$ days

Number of days taken by C to complete work alone $= 7$ days

$$\text{One day's work of } A \text{ and } B = \frac{1}{14} + \frac{1}{7} = \frac{3}{14}$$

and one day's work of A, B and $C = \frac{1}{14} + \frac{1}{7} + \frac{1}{7} = \frac{5}{14}$

$$3 \text{ day's work of } A \text{ and } B = 3 \times \frac{3}{14} = \frac{9}{14}$$

$$\text{remaining work} = \frac{5}{14} \qquad \left(1 - \frac{9}{14}\right)$$

This remaining work will be done by A, B and C

$$= \frac{5/14}{5/14} = 1 \text{ day}$$

85. A's 5 days work $= 50\%$

B's 5 days work $= 33.33\%$

C's 2 days work $= 16.66\%$ $\qquad [100 - (50 + 33.33)]$

Ratio of contribution of work of A, B and $C = 50 : 33\frac{1}{3} : 16\frac{2}{3}$

$$= 3 : 2 : 1$$

Scanned by CamScanner

yoursmahboob.wordpress.com

A's total share = Rs. 1500

B's total share = Rs. 1000

C's total share = Rs. 500

A's one day's earning = Rs. 300

B's one day's earning = Rs. 200

and C's one day's earning = Rs. 250

86. Efficiency of A = 50% $\left(\frac{100}{2}\right)$

Efficiency of B = 37.5% $\left(\frac{100}{8/3}\right)$

Efficiency of C = 12.5% $\left(\frac{100}{8}\right)$

Combined efficiency of A, B and C = 100%

So, they complete the work in 1 hour.

87.

	A	+	B	=	C	+	D
	↓		↓		↓		↓
Ratio of efficiency	$\underbrace{10x}_{15x}$	+	$5x$		$\underbrace{9x}_{15x}$	+	$6x$

Therefore, ratio of efficiency of $A : C = 10 : 9$

Therefore, ratio of days taken by $A : C = 9 : 10$

Therefore, number of days taken by A = 18 days

88. Efficiency of 4 men and 2 boys = 20%

Efficiency of 3 women and 4 boys = 20%

Efficiency of 2 men and 3 women = 20%

∴ Efficiency of 6 men, 6 women and 6 boys = 60%

∴ Efficiency of 1 man, 1 woman and 1 boy = 10%

Now, since they will work at double their efficiency

∴ Efficiency of 1 man, 1 woman and 1 boy = 20%

∴ Required number of days = 5

89. $M_1 \times D_1 = M_2 \times D_2$

$$m \times r = (m + n) \times D_2$$

$$D_2 = \frac{mr}{(m + n)}$$

90. Efficiency of A = 2.77%

Efficiency of B = 2.22%

∴ Combined efficiency of A and B = 5%

= (2.77 + 2.22)

Thus, it will take total of 20 minutes $\left(\because 20 = \frac{100}{5}\right)$

91. Efficiency of A = 8.33%

Effective efficiency = 6.66%, when there is leakage

∴ Efficiency of leakage = 1.66% = (8.33 – 6.66)

It means due to leakage a full tank will be empty in 60 hours.

92. Efficiency of $A + B$ = 10 + 6.66 = 16.66%

Efficiency of $A + B + C$ = 5.55%

∴ Efficiency of C (outlet pipe) = 16.66 – 5.55

= 11.11%

It means outlet pipe C can empty in 9 hours.

93. Efficiency of only leakage = 16.66%

Effective efficiency of leakage = 6.66%

It means the capacity of filling pipe = 10%

Therefore, the inlet pipe can fill the tank in 10 hours hence the capacity of tank = 100 l.

94. Efficiency of tap A and B = 16.66% = (10 + 6.66)

$$\therefore \quad 16.66x + 10 \times (8 - x) = 100\%$$

$$\Rightarrow \quad x = 3$$

95. Efficiency of A = 5%

Efficiency of B = 4%

Efficiency of C = – 3.33%

It means in every 3 consecutive hours tops A, B and C can fill 5.66% (= 5 + 4 – 3.33)

Therefore in 51 hours (= 3 × 17) tops A, B and C can fill 96.33% (= 5.66 × 17)

∴ the remaining part i.e., 3.66% (= 100 – 96.33) can be filled up by A in $\frac{11}{15}$ hours $\left(= \frac{3.66}{5}\right)$, since it is now A's turn.

Hence, the total time required = $51 + \frac{11}{15} = 51\frac{11}{15}$

97. Efficiency when both pipes used to fill = $A + B$

and efficiency when pipe A is used to fill and pipe B is used to empty the tank = $A - B$

$$\therefore \quad \frac{A + B}{A - B} = \frac{2}{1}$$

$$\Rightarrow \quad \frac{A}{B} = \frac{3}{1} \qquad \text{(By componendo and dividendo)}$$

Thus, the ratio of efficiency of pipe A and B = 3 : 1.

98. In ideal case:

Time taken to fill the half tank by A and $B = \frac{50}{41.66} = \frac{6}{5}$ hours

Time taken by A, B and C to fill rest half of the tank

$$= \frac{50}{16.66} = 3 \text{ hours}$$

Total time = $\frac{6}{5} + 3 = 4$ hours 12 minutes

In second case:

Time taken to fill $\frac{3}{4}$ tank by A and $B = \frac{75}{41.66} = \frac{9}{5}$ hours

Time taken by A, B and C to fill rest $\frac{1}{4}$ tank = $\frac{25}{16.66} = \frac{3}{2}$ hours

Total time = $\frac{9}{5} + \frac{3}{2} = 3$ hours 18 minutes

Therefore, difference in time = 54 minutes

99. Time taken by pipes A and B to fill the whole tank = $\frac{100}{16.66}$

= 6 hours

Capacity filled in 2 hours by pipes A, B and C = 2 × 13.33

= 26.66%

Remaining capacity = 73.33%

This remaining capacity can be filled by A and B

Scanned by CamScanner

yoursmahboob.wordpress.com

$= \frac{73.33}{16.66} = 4\frac{2}{5}$ hours

So, the total time required $= 2 + 4\frac{2}{5} = 6$ hours 24 minutes

Thus, in this case 24 minutes extra are required.

100. In one hour pipe A can fill $= \frac{1}{30}$ part of the tank

In one hour pipe B can fill $= \frac{1}{45}$ part of the tank

In two hour pipes A and B can fill $= \frac{1}{18}$ part of the tank

Therefore in 36 hours the tank will be completely filled.

Alternatively: Efficiency of pipe $A = 3.33\%$

Efficiency of pipe $B = 2.22\%$

and Combined efficiency $= 5.55\%$

Therefore in 2 hours pipe A and B fill 5.55%.

Thus to fill 100% tank, these pipe will take 36 hours.

LEVEL (2)

1. LCM of 2, 3 and 4 = 12

In 12 hours A will make 6 shawls
" " " B will make 4 shawls
" " " C will make 3 shawls
} 13 shawls

i.e., in 12 hours they will weave 13 shawls

so, in 84 hours they will weave 91 shawls

Now, in 9 hours A will make 4 shawls
in 9 hours B will make 3 shawls
in 9 hours C will make 2 shawls
} 9 shawls

So, they will complete 100 shawls in 93 hours.

NOTE Since, they cannot share each-others work so B will take completely 9 hours to make 3 shawls, even when A and C stay idle for the last 1 hour till B completes his own work.

2.

	M	T	W	Th	F	S
	A	S	A	S	A	S
Work →	15%		15%		7.5%	

37.5%

{This pattern continued for total 2 weeks only till 75% work got completed.}

Thus in 2 weeks they will complete 75% work.

Now 15% of the remaining (25% of the work) will be done in the third week in Monday and Tuesday. Again 10% work remained undone. Out of this 8.33% work will be done by Arun on Wednesday and remaining 1.66% work will be completed on Thursday by Satyam.

Final week

M	T	W	Th
A	S	A	S
15%		8.33%	1.66%

25%

3. Efficiency of Kaushalya = 5%

Efficiency of Kaikeyi = 4%

Thus, in 10 days working together they will complete only 90% of the work.

$[(5 + 4) \times 10] = 90$

Hence, the remaining work will surely done by Sumitra, which is 10%.

Thus, Sumitra will get 10% of Rs. 700, which is Rs. 70.

✍ ***Solutions for question number 4 and 5:***

	1st day	*2nd day*
Morning shift}	*A*	*B*
Evening shift}	*B*	*A*

It is clear that in two days finally they work very similar to the alternate days i.e., finally A work for 10 hours and B also works for 10 hours.

Thus in every two days they will complete 7.5% work. So, in 26 days they will complete 97.5% of the total work.

Now, the remaining work = 2.5%

Now, this is the turn of A,

Since A does 4.16% work in 10 hours.

So, he will do 2.5% work in 6 hours.

4. Thus, the work will be finished on 27th day.

5. Since, A does 2.5% work in 6 hours, which is the actual duration of morning shift. So 100% time of the morning shift was utilised.

6. **From the first statement :**

	$(B + C)$	$(A + B + C)$
Efficiency	$2x$	$3x$
Days	$3y$	$2y$

Thus, we can say that efficiency of A is $\frac{1}{3}$ the efficiency of $(A + B + C)$.

From the last statement:

Share of B out of total amount $= \frac{120}{450} = \frac{4}{15}$

From these two results we can conclude that:

		A	:	B	:	C
Ratio of efficiency		$\frac{5}{15}\left(=\frac{1}{3}\right)$	:	$\frac{4}{15}$	:	$\frac{6}{15}$
	$\Rightarrow$	5	:	4	:	6
Ratio of number of days	$\Rightarrow$	$\frac{1}{5}$	:	$\frac{1}{4}$	:	$\frac{1}{6}$
	$\Rightarrow$	$12x$	:	$15x$	:	$10x$

One day's work of A and $B = \frac{1}{12x} + \frac{1}{15x} = \frac{9}{60x}$

$\therefore$ A and B will take $\frac{60x}{9}$ days to complete the whole work,

Again one day's work of A, B and C

$= \frac{1}{12x} + \frac{1}{15x} + \frac{1}{10x} = \frac{15}{60x}$

$\therefore$ A, B and C working together complete the work in $\frac{60x}{15}$ days

$\therefore$ $\frac{60x}{9} - \frac{60x}{15} = \frac{8}{3}$

Scanned by CamScanner

yoursmahboob.wordpress.com

(Since, A and B take $\frac{8}{3}$ days more than A, B and C)

$$\Rightarrow \quad x = 1$$

$\therefore$ Number of days required to complete the whole work by A, B and $C = 4x = 4 \times 1 = 4$ days

Alternatively: You can solve through option.

Alternatively: Ratio of efficiencies of A, B and $C = 5x : 4x : 6x$

$\therefore$ Number of days required by A and $B = \frac{100}{9x}$ ...(1)

and number of days required by A, B and $C = \frac{100}{15x}$ ...(2)

$$\therefore \quad \frac{100}{9x} - \frac{100}{15x} = \frac{8}{3} \Rightarrow x = \frac{5}{3}$$

From eq. (2) number of days required by A, B and C working together

$$= \frac{100}{15x} = \frac{100}{15 \times \frac{5}{3}} = \frac{100}{25} = 4 \text{ days}$$

7.

MIT	NIT
$4 \times 10 \times 60 \times E_1$	$= 5 \times 8 \times 80 \times E_2$

$$\Rightarrow \quad \frac{E_1}{E_2} = \frac{4}{3}$$

where E_1 and E_2 are the respective working efficiencies per hour.

$\therefore$ Each engineer from NIT is 25% less efficient than each engineer from MIT.

8.

T	C	B	
16	10	15	
8	12	12	
128	120	180	← in one hour
1280	1200	1800	← in 10 hour

Since, restriction is imposed by composers *i. e.*, since only 1200 books can be composed in 10 hours so not more than 1200 books can be finally prepared.

9. To maximise the production we locate 5 persons for composing and 7 persons for typing. Only then we can maximise our production which is 1800 books per day.

T	C	B
(16 + 7)	(10 + 5)	15
8	12	12
184	180	180
1840	1800	1800

10. **1st case**

T	C	B
15	10	13
8	12	12
120	120	156
1200	1200	1560

No change in critical value

2nd case

T	C	B
16	10	12
8	12	12
128	120	144

No change in critical value*

*Critical value means the minimum amount of job which creates the restriction.

NOTE In third case it will reduce the production below 1200 books per day (or 120 books per hour)

So, option (d) is correct.

11. Efficiency of Bunty and Babli (jointly) = 12.5%

Now, go through options and satisfy the conditions.

Consider option (d).

	Bunty		Babli
Efficiency	7.5%	→	5%
Days	$\frac{40}{3}$		20

Now, the new efficiency of Bunty = 15%

and the new efficiency of Babli = $\frac{5}{3}$%

$\therefore$ Combined efficiency = $\frac{50}{3}$%

$\therefore$ Number of days taken by them = $\frac{100}{50/3} = 6$ days

Hence, the presumed option (d) is correct.

NOTE Without solving the complete problem we can say that only option (d) is true since other 3 options gives the efficiency of Bunty equal to or more than 12.5% which is inadmissible *i.e.*, cannot be equal to or greater than the combined efficiency of both persons together.

12. Let x litre be the per day filling and v litre be the capacity of the reservoir, then

$$90x + v = 40000 \times 90 \quad \text{...(1)}$$

and $$60x + v = 32000 \times 60 \quad \text{...(2)}$$

Solving eq. (1) and (2), we get

$$x = 56000$$

Hence, 56000 litres per day can be used without the failure of supply.

13. One day's production = $400 \times 9 \times 60 = 2160000$ bottles per day

Ratio of time utilised by M_1 and $(M_1 + M_2) = 1 : 2$

Now, the production of bottles by M_1 in 1 minute = 400

and the production of bottles by M_1 and M_2 together in 2 minutes = 2000

Thus total 2400 bottles can be processed in 3 minutes

$\therefore$ 216000 bottles can be processed in

$$216000 \times \frac{3}{2400} = 4.5 \text{ hours}$$

14. Let he initially employed x workers which works for D days and he estimated 100 days for the whole work and then he doubled the worker for $(100 - D)$ days.

$$D \times x + (100 - D) \times 2x = 175x$$

$$\Rightarrow \quad D = 25 \text{ days}$$

NOTE $175 = 100 + \frac{3}{4} \times 100$, since required number of days are 75% $\left(i.e., \frac{3}{4}\right)$ more than the estimated number of days.

Now, the work done in 25 days = $25x$

Total work = $175x$

$\therefore$ Work done before increasing the number of workers

$$= \frac{25x}{175x} \times 100 = 14\frac{2}{7}\%$$

Scanned by CamScanner

yoursmahboob.wordpress.com

15. **Note:** For easier calculation consider some convenient value of x (i.e., number of workers). Let initially there were 20 workers employed.

It means work done till 25 days

$$= 25 \times 20 = 500 \text{ man-days}$$

Now, since delay in works is 60%.

It means the work was completed in 160 days. Let the increased workers worked for k days then

$$40 \times k + 16 \times (135 - k) = 75 \times 40$$

$$\Rightarrow \quad k = 35 \text{ days}$$

$\therefore$ 40 workers work for only 35 days

Here 40 means twice the work force of 20

and 16 means 80% efficiency of the original work-force

and 135 means (160 – 25) days

and 75 means (100 – 25) days

Since, number of days are increased by 60 in which only 16 workers work.

$\therefore$ Remaining work after 100 days $= 60 \times 16 = 960$

$$= \frac{960}{3500} \times 100 = 27\frac{5}{7}\%$$

Solutions for 16–20: *Let the actual number of typists be n required to work for D days, then*

$$nD = (n \times 8) + \left(\frac{4n}{5} \times D\right)$$

$$\Rightarrow \quad D = 40$$

16. Since, the above equation is independent of n (i. e., number of typists) so cannot be calculated. It means there are many possible values.

17. Since 20% $\left(i.e., \frac{1}{5}\right)$ typists left the job. So, there can be any value which is multiple of 5 *i. e.*, whose 20% is always an integer. Hence, 5 is the least possible value.

18. The remaining value must be divisible by 4.

Since, $\frac{4x}{5} = k$ $\quad x \rightarrow$ actual number of typists

$$\Rightarrow \quad x = \frac{k \times 5}{4} \quad k \rightarrow \text{remaining number of typists}$$

So, k must be divisible by 4, since a person cannot be a fraction. Hence, option (c) could be the possible answer.

19. Since, $D = 40$

20. Work done in 8 days $= 8x$

Work done in further 16 days $= 16 \times \frac{4}{5}x = \frac{64x}{5}$

Remaining work $= 40x - \left(8x + \frac{64x}{5}\right) = \frac{96x}{5}$

Remaining number of days $= 40 - (8 + 16) = 16$

$\therefore$ New work-force $= \frac{96x/5}{16} = \frac{6x}{5}$

$\therefore$ Change (or increase) in work-force

$$= \frac{\left(\frac{6x}{5}\right) - x}{x} \times 100 = 20\%$$

21. Let A, B, C, D and E stiches a, b, c, d and e shirts per day then

$$\frac{1}{a} + \frac{1}{b} + \frac{1}{c} + \frac{1}{d} + \frac{1}{e} = \frac{90}{1800} = \frac{1}{20}$$

when $a = b = c = d = e$, we get the minimum value

$\therefore$ $\quad 5 \times \frac{1}{a} = \frac{1}{20}$

$\Rightarrow$ $\quad a = 100 = b = c = d = e$

22. $(8M + 5W) \times 6 \times 4 = (4M + 5W) \times 8 \times 5$

$\Rightarrow$ $\quad 4M = 10W$

$\Rightarrow$ $\quad 1M = 2.5W$

Now, substituting the value M by W, we get total work-done

Work $= (8 \times 2.5 + 5) \times 6 \times 4 = 600$ women-days-hours

$= 240$ man-days-hours

Again work $= 5 \times 8 \times 30 = 1200$ boy-days-hours

$\therefore$ $\quad 1M = 2.5W = 5B$

$4M + 3W + 4B = 30$ boys

$\therefore$ Required number of days $= \frac{1200}{30 \times 5} = 8$ days

23. $9 \times 6 \times M = 240$

$$M = \frac{240}{6 \times 9} = 4.4 \text{ men}$$

Therefore, minimum 5 men are required.

24. Efficiency of Eklaya = 16.66%

Efficiency of Faizal = 8.33%

Total efficiency of Eklaya and Faizal = 25%

So, they can do actual work in 4 days

$\therefore$ 3 times work requires 12 days.

25. $1 + 2 + 3 + 4 + 5 + \ldots + 24 = \frac{24 \times 25}{2} = 300$

Total work = 300 man-days

But, the person who started the work on the first day works for 24 days. Hence, his share will be maximum which is equal to $\frac{24}{300} = \frac{2}{25}$.

Thus, he will receive $5000 \times \frac{2}{25} =$ Rs. 400.

26. Total efficiency of two persons = 50%

Ratio of efficiencies of first person to the second person = 1 : 2

Therefore, efficiency of second person = 33.33%

Hence, he will take 3 days to complete the work alone.

27. Ratio of number of men, women and children

$$= \frac{18}{6} : \frac{10}{5} : \frac{12}{3} = 3x : 2x : 4x$$

$\therefore$ $\quad (3x + 2x + 4x) = 18$

$\therefore$ $\quad x = 2$

Therefore, number of women = 4

Share of all women $= \frac{10}{40} \times 4000 =$ Rs. 1000

$(\because 18 + 10 + 12 = 40)$

$\therefore$ Share of each woman $= \frac{1000}{4} =$ Rs. 250

Scanned by CamScanner

yoursmahboob.wordpress.com

28. It can be solved easily through option.

$$(10 + 9 + 8 + \ldots + 1) = 10 \times \left(10 \times \frac{55}{100}\right)$$

$$55 = 55$$ Hence correct.

Alternatively: $\frac{n(n+1)}{2} = n \times \frac{55n}{100}$

$$\Rightarrow \quad n = 10$$

In both cases total work is 55 man-days.

29. Go through option. Consider choice (c).

Efficiency of first worker = 5%

Efficiency of second worker = 4%

∴ In 7 hours first worker completed 35% work

In 5 hours second worker completed 20% work

Thus, work completed = 55%

Remaining work = 45%

Hence, one condition is satisfied.

Again, they will take 5 more hours to complete 45% work

$$\left[\frac{45}{4+5} = 5\right]$$

Thus, first person completes $7 \times 5 + 5 \times 5 = 60\%$ work

and second person completes $5 \times 4 + 5 \times 4 = 40\%$ work

Hence, second condition is also satisfied. Hence, correct option is (c).

30. Go through option

$$140 \times 4 = (140 + 120 + 100 + \ldots + 20)$$

$$560 = 560$$

Alternatively: Let n be the initial number of worker then

$$n \times 4 = n + (n - 20) + (n - 40) + \ldots + (n - 120)$$

$$4n = 7n - 420$$

$$\Rightarrow \quad 3n = 420$$

$$\Rightarrow \quad n = 140 \text{ workers}$$

31. **From the first statement**

	B		$(V + M)$
Number of days	x	=	x
Efficiency	1	:	1

From the second statement

	V	$(V + M)$
Number of days →	$(K + 8)$	K

From the third statement

	B	V
Number of days →	$(n - 8)$	n

Now, go through option and consider option (c).

Efficiency of $(B + V + M) = 16.66\%$ (number of days = 6)

∴ Efficiency of $B = 8.33\%$ (number of days = 12)

and Efficiency of $(V + M) = 8.33\%$ (number of days = 12)

Therefore, B will take 12 days.

Now, from third statement V will take 20 days.

Hence, the efficiency of V is 5%.

Therefore, V will take 20 days. Hence, second statement is also true. Thus, the presumed option (c) is correct.

32. Consider option (d)

Time taken by Bill = 12 hours

Efficiency of Bill = 8.33%

Therefore, time taken by Bill and Milinda working together

$$= 6\frac{2}{3} \text{ hours}$$

Hence, the efficiency of Milinda and Bill = 15%

Therefore efficiency of Milinda = 15 – 8.33 = 6.66%

Thus, the number of days taken by Milinda = 15, which is $8\frac{1}{3}$ days more than when both work together.

Hence, all the conditions satisfied.

		M	$B + M$	B
Efficiency	→	6.66%	15%	8.33%
Number of days	→	15	$6\frac{2}{3}$	12

33. Efficiency of Pascal and Rascal = 10%

Pascal worked for 2.5 hours and Rascal worked separately 8.5 hours. Which means it can be considered that Pascal and Rascal worked together for 2.5 hours and Rascal worked alone for 6 hours.

Thus, Pascal and Rascal in 2.5 hours can complete 25% work.

It means the remaining (50 – 25) = 25% of the work was done by Rascal in 6 hours.

Therefore, Rascal can do 100% work in 24 hours. It means the efficiency of Rascal = 4.16%

Therefore, efficiency of Pascal = (10 – 4.16) = 5.83%

Thus, Pascal require $\frac{100}{5.83} = 17\frac{1}{7}$ hours to complete the work alone.

Alternatively: Go through option.

34.



From the above diagram it is clear that efficiency of C and D is 7.5%, since C and D complets 60% work in 8 days and efficiency of B, C and D is 20%. It means efficiency of B alone is 12.5% = (20 – 7.5).

Now

	C	:	D
Number of days	$4x$	:	$5x$
Efficiency	$5y$	:	$4y$

∴ Efficiency of $C = \frac{5}{9} \times 7.5 = 4.16\%$

and Efficiency of $D = \frac{4}{9} \times 7.5 = 3.33\%$

Thus, D is the least efficient person.

Now share of work done by David

$$(D) = 3.33\% \times 10 = 33.33\%$$

Hence, his share of amount = 33.33% of Rs. 3000 = Rs. 1000

35. Combined efficiency of all the three boats = 60 passenger/trip

Now, consider option (a).

15 trips and 150 passengers means efficiency of $B_1 = 10\frac{p}{t}$ which means in carrying 50 passengers B_1 must has taken 5 trips. So the rest trips equal to 5 (10 – 5 = 5) in which B_2 and B_3 together carried remaining 250 (300 – 50) passengers.

Scanned by CamScanner

yoursmahboob.wordpress.com

Therefore the efficiency of B_2 and $B_3 = \frac{250}{5} = 50\frac{p}{t}$

Since, the combined efficiency of B_1, B_2 and B_3 is 60. Which is same as given in the first statement hence option (a) is correct.

Alternatively: It can be solved by framing quadratic equation.

36. Efficiency of 3 men + 5 women = 33.33%

Required number of days by 2 men = x

∴ Required number of days by 3 women = $x + 5$

Now, consider option (c).

Therefore, $3M + 5W = 3M + 2M = 5$ men

Therefore, efficiency of a man = 6.66%

Hence, a man needs 15 days to finish the job, working alone.

Again $3M + 5W = 7.5W + 5W = 12.5W$

Therefore, efficiency of a woman = 2.66%

Therefore, a woman needs 37.5 days.

Thus, 2 men needs 7.5 days to work alone $\because \left(7.5 = \frac{15}{2}\right)$

and 3 women needs 12.5 days to work alone $\because \left(12.5 = \frac{37.5}{3}\right)$

Hence, the difference in number of days = 5 which is same as given in the problem. Hence correct option is (c).

37. Efficiency of Henry and Ford (combined) = 10%

Consider option (d).

Efficiency of Ford = 3.33% (30 days)

Therefore, Efficiency of Henry = 6.66%

Now, the new efficiency of Ford = 16.66%

and the new efficiency of Henry = 3.33%

Therefore, newly combined efficiency of H and F = 20%

Therefore, required number of days by Henry and Ford working together = 5

Since 5 is half of 10, hence the option (d) is correct.

38. From the last statement:

Efficiency of Anne (A), Benne (B) and Cenne (C) = 50%

From the first statement: Number of days taken by B is 2 more than C.

From the second statement: Anne had worked for 6 days and Benne had worked for 3 days only. Now, consider option (d).

Number of days taken by B = 6,

Efficiency = 16.66%

It means Benne had completed $16.66 \times 3 = 50\%$ work in 3 days.

Therefore Anne had completed 50% work in 6 days.

Thus, the efficiency of Anne = $8.33\%\left(\frac{50}{6}\right)$

Hence, the efficiency of Cenne = $50 - (16.66 + 8.33) = 25\%$

Thus B takes 6 days (∵ efficiency = 16.66%)

and C takes 4 days (∵ efficiency = 25%)

which is true according to the first statement, hence option (d) is correct.

39. Number of pages typed by A, B and C together per day = 45

Now let the number of pages typed by B is x

then the number of pages typed by $A = x - d$

and the number of pages typed by $C = x + d$

$\Rightarrow \quad (x - d) + (x) + (x + d) = 45$

$\Rightarrow x = 15$ pages per day.

Again let C types k pages per day then A types $\frac{k}{4}$ pages per day.

Therefore, the ratio of typing of pages per day of A and C = 1 : 4

∴ Number of pages typed by C in one day

$= \frac{4}{5} \times 30 = 24$ pages $\quad (30 = 45 - 15)$

∴ Number of pages typed by C per hour $= \frac{24}{8} = 3$ pages/hour

40. Efficiency of P = 5%

Efficiency of Q = 4%

Efficiency of R = 2.5%

Efficiency of S = 2%

Till 10 am pipe P filled 20%
Till 10 am pipe Q filled 8%
Till 10 am pipe R filled 2.5%
} 30.5%

Thus, at 10 am pipe P, Q and R filled 30.5% of the cistern.

Now, the time taken by P, Q, R and S together to fill the remaining capacity of the cistern

$= \frac{69.5}{13.5} = \frac{139}{27} = 5$ hours and 9 minutes (approx)

Therefore, total time = 4 hours + 5 hours 9 minutes

= 9 hours and 9 minutes

It means cistern will be filled up at 3 : 09 pm

41. Efficiency of $P + Q = 9\%$ (inlet pipes)

Efficiency of $R + S = 4.5\%$ (outlet pipes)

Net efficiency = 4.5%

So, the time taken = $\frac{100}{4.5} = 22\frac{2}{9}$ hours

42. Efficiency of A = 10%

Efficiency of B = 6.66%

Efficiency of C = 5%

Efficiency of D = 3.33%

Efficiency of $A + B + C + D = 8.33$ (time = 12 hours)

Now, go through options and consider A and B as inlet pipes and C and D as outlet pipes, then

$(10 + 6.66) - (5 + 3.33) = 8.33$

which is required hence it is certain that C and D are outlet pipes.

NOTE There is no any other such combination.

43. Efficiency of inlet pipe $A = 4.16\%$ $\left(\frac{100}{24}\right)$

Efficiency of inlet pipe $B = 5.83\%$ $\left(\frac{100}{120/7}\right)$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore$ Efficiency of A and B together $= 10\%$ $\therefore$ (time $= 10$ hours)

Now, if the efficiency of outlet pipe be $x\%$ then in 10 hours the capacity of tank which will be filled $= 10 \times (10 - x)$

Now, since this amount of water is being emptied by C at $x\%$ per hour, then

$$\frac{10 \times (10 - x)}{x} = 2.5 \text{ hours} \Rightarrow x = 8\%$$

Therefore in 10 hours 20% tank is filled only. Hence, the remaining 80% of the capacity will be filled by pipes A and B in $\frac{80}{10} = 8$ hours.

44. Efficiency of pipe $A = 8.33\%$

Efficiency of pipe $B = 6.67\%$

Efficiency of pipe $C = 5\%$

When tap C was opened pipe A filled 16.66% capacity

When tap C was opened pipe B filled 6.67% capacity

Therefore rest capacity of the tank to be filled

$$= 100 - 23.34 = 76.66\%$$

Now, the net efficiency of A, B and $C = 10\%$

Hence, pipes A, B and C will take $= \frac{76.66}{10} = 7.66 = 7\frac{2}{3}$ hours

$\therefore$ Total time $= 2$ hours $+ 7\frac{2}{3}$ hours $= 9\frac{2}{3}$ hours

45. Efficiency of inlet pipe $= 50\%$

Efficiency of outlet pipe $= 16.66\%$

Net efficiency of pipes A and $B = 33.33\%$

Capacity of tank to be filled up $= 66.66\%$

Hence, required time $= \frac{66.66}{33.33} = 2$ hours

46. Rate of leakage $= 8.33\%$ per hour

Net efficiency $= 50 - (16.66 + 8.33) = 25\%$

Time required $= \frac{100}{25} = 4$ hours

47. Since, an inlet pipe is 7.2 times efficient than an outlet pipe. Therefore, in order to tank never overflow we will need total 8 outlet pipes.

Thus we need only 7 more $(8 - 1 = 7)$ outlet pipes.

48. Time taken by 8th tap $= 2 \times 2 \times 2 = 8$ hours

and time taken by 12th tap $= 2 \times \frac{1}{2} \times \frac{1}{2} = \frac{1}{2}$ hour

Ratio of time taken by 8th tap and 12th tap $= 8 : \frac{1}{2} = 16 : 1$

$\therefore$ Ratio of efficiencies of 8th tap and 12th tap $= 1 : 16$

49. Time taken by 10th tap $= 80 \times \frac{1}{2} \times \frac{1}{2} = 20$ hours

Time taken by 12th tap $= 80 \times \frac{1}{2} \times \frac{1}{2} \times \frac{1}{2} \times \frac{1}{2} = 5$ hours

Thus 10th tap and 12th tap together will take 4 hours.

50. Let pipe A fill the tank in $3x$ hours then pipe B fill it in $4x$ hours.

Therefore, in 1 hour they will fill $= \frac{1}{3x} + \frac{1}{4x} = \frac{7}{12x}$

i.e., they will take $\frac{12x}{7}$ hours

When an inlet pipe C is also opened then it takes

$$= \frac{12x}{7} + \frac{12x}{7} \times \frac{3}{4}$$

$$= \frac{12x}{7}\left(\frac{7}{4}\right) = 3x \text{ hours}$$

Now, in one hour pipe A, B and C working together fill

$$= \frac{1}{3x} + \frac{1}{4x} - \frac{1}{C} = \frac{1}{3x}$$

$$\Rightarrow \quad \frac{7}{12x} - \frac{1}{C} = \frac{1}{3x}$$

$$\Rightarrow \quad \frac{1}{C} = \left(\frac{1}{12x} - \frac{1}{3x}\right)$$

$$\Rightarrow \quad C = 4x$$

Hence in $4x$ hours pipe C can empty the whole tank.

Now, since $3x = 33 \Rightarrow x = 11$

$\therefore$ $4x = 4 \times 11 = 44$ hours

51. Total work $= 5 \times 20 = 100$ man-days.

Let the client needed to complete it in n days then

$$(5 \times 2) + (10 \times 2) + (15 \times 2) + (20 \times 2) = 100$$

Hence, in 8 days all the work will be completed as per the requirement of client.

And on the 8th day 20 men were working.

52. It requires total 8 days by adding the work force successively.

53. Total work $= 100 + 50 = 150$ man-days

In 8 days 100 man-days work has been completed. Now on 9th and 10th day there will be 25 workers. So in 2 days they will complete additional 50 man-days work. Thus the work requires 2 more days.

54. Let there be 'n' inlet pipes then there must be $(8 - n)$ outlet pipes.

Therefore $(8 - n)\frac{1}{6} - n \times \frac{1}{8} = \frac{1}{6} \Rightarrow n = 4$

Alternatively: $(8 - n)16.66 - n \times 12.5 = 16.66$

$$\Rightarrow \quad n = \frac{116.66}{29.16} = \frac{700}{175} = 4$$

Alternatively: It can be solve through options very easily.

55. Efficiency of two inlet pipes A and $B = 8.33 + 6.66 = 15\%$

Efficiency of two inlet pipes A and B along with an outlet pipe

$$C = 8.33 + 6.66 - 12.5 = 2.5\%$$

Hours	1	2	3	4	5	6	7	8	9	10
Efficiency →	15	15	2.5	15	15	2.5	15	15	2.5	
	32.5			32.5			32.5			
	97.5%									2.5%

In 9 hours 97.5% tank will be completely filled. On the 10th hour 2.5% (remaining capacity) will be fill by pipe A, B with its 15% efficiency.

Thus, A will take $= \frac{2.5}{15} = \frac{1}{6}$ hour $= 10$ minutes

Therefore, total time $= 9$ hours and 10 minutes.

Scanned by CamScanner

yoursmahboob.wordpress.com



9 TIME, SPEED AND DISTANCE

It is sure and certain that it is one of the most important chapter, which includes various fundamental and logical concepts and therefore most of the problems are complex in their nature. Every year 4-6 problems are generally asked in CAT. Besides CAT almost every aptitude exam contains the questions pertaining to the concepts of TSD.

This chapter includes the following :

(a) Motion in a straight line
(b) Circular motion and races
(c) Problems based on trains, boats, river and clocks etc.

CONCEPT OF MOTION

When a body moves from a point A to another point B at a distance of D, then it requires some time (T) to cover a distance (D) with a particular speed (S).

The relation between T, S and D is as follows:

$$T \times S = D$$

i.e., Time × Speed = Distance

Therefore, when D is constant,

$$T \propto \frac{1}{S}$$

and when T is constant,

$$D \propto S$$

and when S is constant,

$$D \propto T$$

NOTE This relation of proportionality is very important.

Formulae : Distance = Speed × Time

$$\text{Speed} = \frac{\text{Distance}}{\text{Time}}$$

$$\text{Time} = \frac{\text{Distance}}{\text{Speed}}$$

NOTE To solve the problem, all the units involved in the calculation must be uniform *i.e.*, either all of them be in metres and seconds or in kilometres and hours etc.

Conversion of unit:

$$1 \text{ km/h} = \frac{5}{18} \text{ m/s}$$

$$1 \text{ m/s} = \frac{18}{5} \text{ km/h}$$

[1 km = 1000 m, 1 h = 60 min, 1 min = 60 s]

HINT Try to find these relations by unitary method.

1 mile = 1609.30 m = 1.6093 km

and 1 km = 0.621 mile

1 yard = 0.9144 m

and 1 m = 1.0936 yards

and 1 m = 39.4 inches

$$\textbf{Average speed} = \frac{\text{Total distance}}{\text{Total time taken}}$$

When distances are equal :

$$\text{Average speed} = \frac{2xy}{x+y} \quad \text{(speeds } x, y\text{)}$$

and $$\text{Average speed} = \frac{3xyz}{xy+yz+zx} \quad \text{(speeds } x, y, z\text{)}$$

EXAMPLE 1 *Abhishek drives his bike at the speed of 150 km/h. What is the distance covered by him in 3 hours.*

SOLUTION $D = S \times T = 150 \times 3 = 450$ km

EXAMPLE 2 *Udai travels half of his journey by train at the speed of 120 km/h and rest half by car at 80 km/h. What is the average speed?*

SOLUTION Let the total distance be $2D$ km, then

Total time = Time taken by train + Time taken by car

$$= \frac{D}{120} + \frac{D}{80}$$

$$\therefore \quad \text{Average speed} = \frac{2D}{\frac{D}{120} + \frac{D}{80}}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$\frac{2D}{D\left(\frac{1}{120}+\frac{1}{80}\right)} = \frac{2}{\left(\frac{2+3}{240}\right)} = 96 \text{ km/h}$$

Alternatively: Consider the distance in numerals (since it is independent of the distance) as the LCM of the speeds.

Then, the total distance = LCM of 120 and 80 = 240

Therefore, time taken by train $= \frac{120}{120} = 1$ h

and time taken by car $= \frac{120}{80} = \frac{3}{2}$ h

$\therefore$ Average speed $= \frac{\text{Total distance}}{\text{Total time taken}}$

$$= \frac{240}{1+\frac{3}{2}} = 96 \text{ km/h}$$

Alternatively: Average speed $= \frac{2(xy)}{(x+y)}$

where x and y are the speeds.

$\therefore$ Average speed $= \frac{2 \times 120 \times 80}{120+80} = 96$ km/h

NOTE This formula is applicable only when the distances travelled at the speed of x km/h and y km/h are same.

Alternatively: Solve through alligations.

EXAMPLE 3 *Speed of Karan is 40 km/h and speed of Arjun is 60 km/h. What is the ratio of time taken by each to cover the same distance?*

SOLUTION

	Karan		Arjun
Speed	40	:	60
$\Rightarrow$	2	:	3
$\therefore$ Time	3	:	2

Alternatively: Time taken $= \frac{1}{40} : \frac{1}{60} = 3 : 2$

NOTE For the constant distance covered, the ratio of time taken by each person is the ratio of the reciprocal of their speeds and *vice-versa*.

If the ratio of speeds of A, B, C, D be $a : b : c : d$, then the ratio of time taken by A, B, C and D to cover the same distance

$$= \frac{1}{a} : \frac{1}{b} : \frac{1}{c} : \frac{1}{d}$$

and if the time taken by A, B, C and D be $p : q : r : s$, then the ratio of their speeds

$$= \frac{1}{p} : \frac{1}{q} : \frac{1}{r} : \frac{1}{s}$$

EXAMPLE 4 *A car takes half of the time taken by truck to go from Lucknow to Bombay. A truck takes 20 hours to go for the same journey. What is the speed of truck, if the speed of car be 120 km/h.*

SOLUTION

	Car		Truck
Time $\rightarrow$	1	:	2
Speed $\rightarrow$	2	:	1

Therefore, speed of the truck = 60 km/h

EXAMPLE 5 *A cycle covers 75 km distance in 5 hours. What is the distance covered by the cycle in 6 hours?*

SOLUTION $\text{Speed} = \frac{\text{Distance}}{\text{Time}}$

$\therefore$ $\text{Speed} = \frac{75}{5} = 15$ km/h

Now, distance covered in 6 hours at the speed of 15 km/h

$= 15 \times 6 = 90$ km

EXAMPLE 6 *The distance of the college and the home of Rajeev is 80 km. One day he was late by 1 hour than the normal time to leave for the college, so he increased his speed by 4 km/h and thus he reached to college at the normal time. What is the changed (or increased) speed of Rajeev?*

(a) 28 km/h *(b) 30 km/h*
(c) 40 km/h *(d) 20 km/h*

SOLUTION Let the normal speed be x km/h, then

$$\frac{80}{x} - \frac{80}{(x+4)} = 1$$

$\Rightarrow$ $x^2 + 4x - 320 = 0$

$\Rightarrow$ $x(x+20) - 16(x+20) = 0$

$(x+20)(x-16) = 0$

$x = 16$ km/h

$\therefore$ $(x+4) = 20$ km/h

Therefore increased speed = 20 km/h

Alternatively: If t_1 and t_2 be the original and changed time and S_1 and S_2 be the original and changed speeds, then

$$S_1 \times S_2 = \frac{\text{Distance} \times (S_1 \sim S_2)}{(t_1 \sim t_2)}$$

Also, $\boxed{t_1 \times t_2 = \frac{\text{Distance} \times (t_1 \sim t_2)}{(S_1 \sim S_2)}}$

$\therefore$ $S_1 \times S_2 = \frac{80}{1} \times 4 = 320$

$\therefore$ $S_1 \times S_2 = 320$

or $S_1 \times (S_1 + 4) = 320$

$\Rightarrow$ $S_1 = 16$ and $S_2 = 20$

NOTE Here you need not to solve necessarily quadratic equation. You can just try and find two factors of 320 in such a way that (in this particular problem) one factor must be greater than the other factor by 4.

Alternatively: Go through options. Consider 20

$$t_2 = \frac{80}{20} = 4$$

$$t_1 = 4 + 1 = 5$$

$\therefore$ $S_1 = \frac{80}{5} = 16$

Since, S_1 is 4 km/h less than S_2. Hence, option (d) is correct.

Alternatively: If you find yourself comfortable then factorise 80 in two factors and check the correct combinations.

$$80 = \begin{matrix}\textcircled{-1}\\ \\ \\ \\ \end{matrix}\begin{bmatrix} 1 \times 80 \\ 2 \times 40 \\ 4 \times 20 \\ 5 \times 16 \\ 8 \times 10 \end{bmatrix}\begin{matrix}\\ \\ \\ \\ +\textcircled{4}\end{matrix}$$

So, the increased speed = 20 km/h.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 7 *Shweta when increases her speed from 24 km/h to 30 km/h she takes one hour less than the usual time to cover a certain distance. What is the distance usually covered by Shweta?*

(a) 160 km (b) 240 km (c) 120 km (d) 90 km

SOLUTION Let the original time be t hours, then

$$24t = 30 \times (t-1) = D \quad \text{(distance)}$$

then $t = 5$

$\therefore$ Distance $= 24 \times 5 = 120$ km

Alternatively: Go through options.

$\frac{120}{24} = 5$ h

$\frac{120}{30} = 4$ h } 1 hour less

Hence, the option (c) is correct.

Alternatively: Since distance (D) is constant.

Therefore, $D = S_1 \times t_1 = S_2 \times t_2$

It means here we can apply product constancy

Speed	Time	
$\frac{1}{4}\uparrow$	$\frac{1}{5}\downarrow$	= 1 hour

$\therefore$ Original time taken $= 5 \times 1 = 5$ hours

Therefore, Distance = Original speed × Original time

$= 24 \times 5 = 120$ km

NOTE In the given exercise or in the whole chapter you have to solve maximum problems through product constancy concept described in the chapter of ratio proportion and variation. Solving through product constancy gives faster results.

Alternatively: Let the distance be D, then

$$\frac{D}{24} - \frac{D}{30} = 1$$

$\Rightarrow$ $D = 120$ km

EXAMPLE 8 *Kriplani goes to school at 20 km/h and reaches the school 4 minutes late. Next time, she goes at 25 km/h and reaches the school 2 minutes earlier than the scheduled time. What is the distance of her school?*

SOLUTION Increase in speed = 5 km/h

Decrease in time = 6 min (4 + 2)

By product constancy :

Speed	Time	
$\frac{1}{4}\uparrow$	$\frac{1}{5}\downarrow$	= 6 min

It means original time = 30 min $\left(\because \frac{x}{5} = 6 \Rightarrow x = 30\right)$

$\therefore$ Total distance = Original speed × Original time

$= 20 \times \frac{30}{60} = 10$ km

EXAMPLE 9 *Amit covers a certain distance with his own speed, but when he reduces his speed by 10 km/h his time duration for the journey increases by 40 hours, while if he increases his speed by 5 km/h from his original speed he takes 10 hours less than the original time taken. Find the distance covered by him.*

SOLUTION

$\left.\begin{matrix} S & & T \\ -10 & \times & +40 \end{matrix}\right\}$ $40S - 10T = |-400|$ ...(i)

$\left.\begin{matrix} S & & T \\ +5 & \times & -10 \end{matrix}\right\}$ $-10S + 5T = |-50|$ ...(ii)

Solving eq. (i) and (ii), we get

$S = 25$ and $T = 60$

$\therefore$ Distance $(D) = S \times T$

$= 25 \times 60 = 1500$ km

where $D \rightarrow$ Distance, $S \rightarrow$ Speed, $T \rightarrow$ Time

'+' means increase in value.

and '–' means decrease in value.

Alternatively: Let distance be x km and usual speed be y km/h.

$$\frac{x}{(y-10)} - \frac{x}{y} = 40$$

$\Rightarrow$ $x\left[\frac{10}{y(y-10)}\right] = 40$

$\Rightarrow$ $x = 4y\,(y-10)$ ...(i)

and $\frac{x}{y} - \frac{x}{(y+5)} = 10$

$\Rightarrow$ $x = 2y(y+5)$ ...(ii)

from eq. (i) and (ii)

$4y(y-10) = 2y\,(y+5)$

$2y - 20 = y + 5$

$y = 25$ km/h

$x = 1500$ km

EXAMPLE 10 *A train met with an accident 60 km away from Anantpur station. It completed the remaining journey at $\frac{5}{6}$th of the previous speed and reached the Baramula station 1 hour 12 min late. Had the accident taken place 60 km further, it would have been only 1 hour late.*

(a) What is the normal speed of the train?

(b) What is the distance between Anantpur and Baramula?

SOLUTION **Case I.** Since the speed is decreased by $\frac{1}{6}$. So, the time will be increased by 1/5, which is equal to 1 hour 12 minutes.

It means the normal time required for this remaining part (x) of the journey is 5×72 min = 360 min = 6 h.

($\because$ 1 h 12 min = 72 min)



P is the place of accident.

Case II. When accident is supposed to be happened at Q.



Since, the speed is decreased by $\frac{1}{6}$, hence, the time will be increased by $\frac{1}{5}$, which is equal to 1 hour, hence the normal time required for this remaining part $(x - 60)$ of journey $= 5 \times 1 = 5$ hours.

Scanned by CamScanner

yoursmahboob.wordpress.com

Thus, it is clear that when the train runs 60 km of its normal speed it takes 1 hour less, which implies that in 1 hour the train can run 60 km with its normal speed. Thus, the normal speed of the train is 60 km/h.

(b) Since the train requires 6 hours at its normal speed of 60 km/h for the x km. Hence,

$$x = 6 \times 60 = 360 \text{ km}$$

Thus, the total distance = Distance travelled before accident + Distance travelled after accident

$$= 60 \times 1 + 60 \times 6 = 420 \text{ km}$$

EXAMPLE 11 *A and B started simultaneously towards each other from P and Q respectively. The distance between P and Q is 600 km and the ratio of speeds of A is to B is 5 : 7. If they meet at a point M:*

(i) Find the ratio of PM : QM.

(ii) Find the distance PM.

SOLUTION (i) Since the time is constant so, the distance covered by A and B is directly proportional to the speeds of A and B.

Hence, $PM : QM = 5 : 7$

(ii) Since, the ratio of their speeds (or their distances covered) is 5 : 7. Hence, A will cover $\frac{5}{12}$ of the total length.

$$\therefore \quad PM = \frac{5}{12} \times 600 = 250 \text{ km}$$

(Similarly $QM = \frac{7}{12} \times 600 = 350$ km)

RELATIVE MOTION WITH TWO OR MORE BODIES

(i) When two bodies move in the same direction: If the speeds of the two bodies A and B be S_A and S_B, then their relative speed = $S_A - S_B$ or $S_B - S_A$ *i.e.*, in the same direction the relative speed or effective speed between two bodies is the difference of their speeds. (The difference is always considered as positive)

(ii) When two bodies move in the opposite direction: If the speeds of the two bodies A and B be S_A and S_B, then their relative speed = $S_A + S_B$.

i.e., in the opposite direction the relative speed or effective speed between two bodies is the sum of their speeds.

EXAMPLE 12 *The distance between two places P and Q is 700 km. Two persons A and B started towards Q and P from P and Q simultaneously. The speed of A is 30 km/h and speed of B is 40 km/h. They meet at a point M which lies on the way from P to Q.*

(i) How long will they take to meet each other at M?

(ii) What is the ratio of PM : MQ?

(iii) What is the distance MQ?

(iv) What is the extra time needed by A to reach at Q than to reach at P by B?

(v) What is the ratio of time taken by A and B to reach their respective destinations after meeting at M?

(vi) In how many hours will they be separated by only 560 km before meeting each other.

(vii) How long will it take to separate them by 280 km from each other when they cross M (time to be considered after their meeting)?

SOLUTION



(i) Since, they are coming towards each other from opposite ends, therefore the relative speed will be the sum of their speeds = 30 + 40 = 70 km/h.

Thus, the required time to meet at M

= Time required to cover 700 km (combined)

$$= \frac{700}{70} = 10 \text{ h}$$

Thus in 10 hours they will meet each other at M.

(ii) The ratio of their distances covered to meet at M

= Ratio of their speeds = 3 : 4

(Since, time is constant *i. e.*, same for each)

Thus $PM : MQ = 3 : 4$

(iii) $MQ = \frac{4}{7} \times 700 = 400$ km

(iv) Time required by A to reach at $Q = \frac{700}{30} = \frac{70}{3}$ h

Time required by B to reach at $P = \frac{700}{40} = \frac{70}{4}$ h

$\therefore$ Extra time required by $A = \frac{70}{3} - \frac{70}{4}$

$$= 70 \times \frac{1}{12} = 5 \text{h } 50 \text{ min}$$

(v) Time required by A to cover $MQ = \frac{400}{30}$

and time required by B to cover $MP = \frac{300}{40}$

$\therefore$ Required ratio $= \frac{400/30}{300/40} = \frac{16}{9}$

Remember: If speed of A is S_A and speed of B is S_B and A takes t_A time to cover MQ and B takes t_B time to cover MP, then

$$\frac{S_A}{S_B} = \sqrt{\frac{t_B}{t_A}}$$

(vi) It means they have to cover (700 − 560) = 140 km. Thus, the required time to cover 140 km distance

$$= \frac{140}{70} = 2 \text{ h}$$

(vii) Since in each hour they separate by 70 km from each other. Hence, to separate by 280 km, time required

$$= \frac{280}{70} = 4 \text{ h}$$

EXAMPLE 13 *Two places P and Q are 800 km apart from each other. Two persons start from P towards Q at an interval of 2 hours. Whereas A leaves P for Q before B. The speeds of A and B are 40 km/h and 60 km/h respectively. B overtakes (or catches or meets) A at M, which is on the way from P to Q.*

Scanned by CamScanner

yoursmahboob.wordpress.com

(i) *How long will B take to overtake?*
(ii) *What is the distance from P, where B overtakes A (i.e., PM)?*
(iii) *What is the ratio of time taken by A and B to meet at M?*
(iv) *What is the extra time required by A to reach at Q?*
(v) *How many hours late A will reach at Q than that of B?*
(vi) *After how many hours A and B will be separated by 50 km before M, when both are moving?*
(vii) *How many hours does B require to advance himself, by 100 km, in comparison to A?*

SOLUTION



(i) Since A moves 2 hours earlier than B at the speed of 40 km/h, so in 2 hours A will cover 80 km. Thus A will be 80 km away from B.
Now, since they are moving in the same direction therefore their relative speed will be $(60 - 40) = 20$ km/h *i.e.*, with respect to A, B moves at 20 km/h. It means either they reduce (or create) the difference of 20 km in each hour between themselves.
Thus, the required time to overtake (or reduce the difference upto zero from 80 km)

$$= \frac{\text{Distance advanced}}{\text{Relative speed}} = \frac{80}{20} = 4 \text{ h}$$

(ii) The distance between P and M
= (Time required to overtake × Speed of the faster body)
$= 4 \times 60 = 240$ km
Since, B has to move for 4 hours at 60 km/h. Hence, distance covered = 240 km.

(iii) Time taken by B to reach at $M = 4$ h
Time taken by A to reach at $M = (4 + 2) = 6$ h
Thus, the ratio of time taken by A and $B = 6 : 4 = 3 : 2$
(Since, A has left 2 hours earlier)

(iv) Time taken by A to reach at $Q = \frac{800}{40} = 20$ h

Time taken by B to reach at $Q = \frac{800}{60} = 13$ h 20 min

Hence, A takes 6 hrs 40 min extra to reach at Q.

(v) Since, A leaves 2 hrs earlier, thus he will reach at Q only 4 hours 40 min late.
Since, A takes 6 hrs 40 min extra to reach at Q,

(vi) When B starts to move towards Q the difference between A and B is 80 km.
The required difference between A and $B = 50$ km
Hence, they have to reduce it by 30 km.

Thus, the required time $= \frac{(80 - 50)}{20} = 1.5$ h

$= 1$ h 30 min

Thus, after 3/2 hrs A will be only 50 metres ahead of B.

(vii) When B starts to follow A (towards Q) A was 80 km ahead of B. Also B wants to overtake A and further go ahead of A by 100 km. Thus, the net difference (required) = 180 km.

$\therefore$ Required time

$$= \frac{(\text{Distance advanced} + \text{Required difference})}{\text{Relative speed}}$$

$$= \frac{80 + 100}{20} = \frac{180}{20} = 9 \text{ h}$$

Thus, after 9 hrs (when B starts moving) B will be 100 km ahead of A *i.e.*, they will be separated by 100 km from each other after crossing M.

TO AND FRO MOTION IN A STRAIGHT LINE

This concept is just the extension of the previous concepts of relative motion between more than one dynamic (or moving) bodies.

(a) When two bodies start moving towards each other

(i) To meet each other they cover the distances in the ratio of their individual speeds.
(ii) If the initial distance (or gaping) between two bodies A and B is D, then A and B together have to cover D unit of distance for the first meeting.
(iii) For the next number of meeting (*e.g.*, second, third, fourth meeting and so on) both A and B together have to cover $2D$ distance more from the previous meeting *i.e.*, to meet for the fourth time they have to cover together $D + (3 \times 2D) = 7D$ unit of distances. Similarly for seventh meeting they have to cover together $D + (6 \times 2D) = 13D$ units of distance. Thus for each subsequent meeting they have to cover $2D$ distance extra from the previous one.

NOTE Individually they will cover the distances in the ratio of their speeds for any number of meeting.
Thus, the total distance covered for the n^{th} meeting $= (2n - 1)D$.

(b) When two bodies start moving towards the same direction

(i) For the first meeting after they start to move they have to cover $2D$ distance, if the distance between two particular points (or places) be D unit.
Since, the faster body reaches the next (or opposite) end first than the slower body and the faster body starts returning before the slower body reaches the same opposite end and thus the two bodies meet somewhere between the two ends covering individually the distances in their respective speeds.
(ii) For every subsequent meeting they have to cover together $2D$ unit distance more from the previous meeting.
Thus, for n^{th} meeting they have to cover together $(n \times 2D)$ unit of distance.
(iii) At any point of time the distances covered by the bodies will be equal to the ratio of their speeds.

Scanned by CamScanner

yoursmartbook.wordpress.com

EXAMPLE 14 *The distance between P and Q is 100 m and the speeds of A and B are 20 m/s and 30 m/s respectively. Initially A and B are at P. They move between P and Q. Calculate:*

(i) the distance covered by A in first meeting.
(ii) the time required for the second meeting.
(iii) the distance covered by B to meet for the third time.
(iv) the ratio of distances covered by A and B till the fourth meeting.
(v) the distance between P and the place of fifth meeting.
(vi) the distance between Q and the point of third meeting.

SOLUTION

Meeting	Total distance covered by A and B together	Distance covered by A	Distance covered by B	Point of meeting from P	Point of meeting from Q	Time (in second)
1st	200 m	80 m	120 m	80 m	20 m	4
2nd	400 m	160 m	240 m	40 m	60 m	8
3rd	600 m	240 m	360 m	40 m	60 m	12
4th	800 m	320 m	480 m	80 m	20 m	16
5th	1000 m	400 m	600 m	0 m (at P)	100 m	20

(i) The distance covered by A in the first meeting = 80 m

(ii) Time required for the second meeting = $\frac{400}{50} = 8$ s

(iii) The distance covered by B for the third time meeting = $12 \times 30 = 360$ m

(iv) It is always (for any moment, after the starting of movement) will be in the ratio of their respective speeds.
So, the required ratio of distances covered by A and B = 20 : 30 = 2 : 3 *i. e.*,

$$A : B = 20 : 30 = 2 : 3$$

(v) Since for the fifth meeting they have to cover $50 \times 20 = 1000$ m.

(vi) 60 m.

EXAMPLE 15 *The distance between two points P and Q is 100 m. A is initially at P and B is at Q. The speeds of A and B is 20 m/s and 30 m/s. They move between P and Q to and fro :*

(i) Find the time required for the first meeting.
(ii) Distance covered by A till the third meeting.
(iii) Distance covered by B till the fifth meeting.
(iv) The distance between P and the place of fourth meeting.
(v) The distance between Q and the place of fifth meeting.
(vi) The ratio of distances covered by each one till the third meeting.

SOLUTION

No. of meeting	Distance covered by A and B together	Time (in second)	Distance covered by A	Distance covered by B	Distance between P and point of meeting	Distance between Q and point of meeting
1st	100 m	2	40 m	60 m	40 m	60 m
2nd	300 m	6	120 m	180 m	80 m	20 m
3rd	500 m	10	200 m	300 m	at P	at P
4th	700 m	14	280 m	420 m	80 m	20 m
5th	900 m	18	360 m	540 m	40 m	60 m

(i) 2 second $\left(\text{Time} = \frac{100}{50} = 2\right)$

(ii) 200 m (Distance = Speed × Time = $20 \times 10 = 200$ m)

(iii) 540 m ($D = 18 \times 30 = 540$ m)

(iv) 80 m

(v) 60 m

(vi) 2 : 3 always equal to the ratio of respective speeds.

EXAMPLE 16 *A and B are two friends. A lives at a place P and B lives at another place Q. Everyday A goes to Q to meet B at 120 km/h. Thus, he takes 3 hours. On a particular day B started to meet A so he moved towards P. On that day A took only 2 hours to meet B on the way instead at Q.*

(i) What is the ratio of speeds of A is to B?

(ii) What is the speed of B?

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION Distance between P and $Q = 120 \times 3 = 360$ km

Let the speed of B be S_B, then

$$\text{Time} = \frac{\text{Distance}}{\text{Speed}}$$

$$2 = \frac{360}{(120 + S_B)}$$

$$\Rightarrow \quad S_B = 60 \text{ km/h}$$

Here, A and B are moving towards each other. So, the relative speed will be the sum of the speeds of A and B both.

Therefore, ratio of speeds of $A : B = 2 : 1$.

(i) 2 : 1 (ii) 60 km/h

NOTE In this case ratio of speeds of

$$A : B = \frac{\text{Actual time required when } B \text{ is also moving}}{\text{Time difference when } B \text{ is also moving}}$$

$$= \frac{(3-1)}{1} = \frac{2}{1}$$

EXAMPLE 17 *A lives at P and B lives at Q. A usually goes to meet B at Q. He covers the distance in 3 hours at 150 km/h. On a particular day B started moving away from A. While A was moving towards Q thus A took total 5 hours to meet B.*

(i) What is the speed of B?

(ii) What is the ratio of speeds of A : B ?

SOLUTION Distance $= 3 \times 150 = 450$ km

$$\text{Time} = \frac{\text{Distance}}{\text{Relative speed}}$$

$$5 = \frac{450}{(150 - S_B)} \qquad S_B \rightarrow \text{Speed of } B$$

$$\Rightarrow \quad S_B = 60 \text{ km/h}$$

Ratio of speeds of $A : B = \frac{150}{60} = \frac{5}{2} = 5 : 2$

(i) 60 km/h (ii) 5 : 2

In this case ratio of speeds of

$$A : B = \frac{\text{Actual time required when } B \text{ is also moving}}{\text{Time difference}}$$

$$= \frac{5}{2}$$

EXAMPLE 18 *A train approaches a tunnel AB. Inside the tunnel a cat located at a point i. e., $\frac{5}{12}$ of the distance AB measured from the entrance A. When the train whistles, the cat runs. If the cat moves to the entrance of the tunnel A, the train catches the cat exactly at the entrance. If the cat moves to the exit B, the train catches the cat at exactly the exit. The speed of the train is greater than the speed of the cat by what order?*

SOLUTION Train CAT



Let the speed of train be u and the speed of cat be v and train whistles at a point T, x km away from A, then

$$\frac{u}{v} = \frac{x}{5k} = \frac{x + 12k}{7k}$$

$$\Rightarrow \quad 7x = 5(x + 12k)$$

$$\Rightarrow \quad \frac{x}{k} = \frac{30}{1}$$

$$\therefore \quad \frac{u}{v} = \frac{30}{5 \times 1} = \frac{6}{1}$$

Alternatively: $\frac{u}{v} = \frac{7k + 5k}{7k - 5k} = \frac{6}{1}$

NOTE Since time is constant, therefore distances covered by train and cat will be in the ratio of their respective speeds.

CONCEPT BASED ON TRAINS

(i) When two trains (or bodies) are moving in opposite direction, their relative speed will be equal to the sum of their individual speeds.

(ii) When two trains are moving in the same direction their relative speed will be equal to the difference of their speeds.

(iii) Distance to be covered to cross each other is always equal to the sum of their individual lengths.

(iv) Distance to be covered such as bridge, platform etc., is always equal to the sum of the length of train and the length of the particular object such as bridge, platform etc.

(v) Distance to be covered such as pole, man, tree etc, is always equal to the length of the train only.

(vi) If a man is travelling in a train, then this man has to cover the distance to cross another train is equal to the length of the train which is passing or crossing him. In this case the relative speed of both the trains will be considered.

EXAMPLE 19 *A train crosses a tree in 10 seconds. If the length of the train be 150 m, then find the speed of the train.*

SOLUTION Distance = Length of train

= Speed of train × Time

$$150 = \text{Speed} \times 10$$

$$\Rightarrow \quad \text{Speed} = 15 \text{ m/s}$$

$$\text{Speed} = 15 \times \frac{18}{5} = 54 \text{ km/h}$$

NOTE A train starts to cross a stationary thin object (of inconsiderable thickness) when the engine of the train meets the object and it completes the crossing when the last wagon (or backend) of the train just crosses the object.

EXAMPLE 20 *A train crosses a man coming from the opposite direction in 7.5 seconds. If the speed of man be 10 m/s and speed of train is 20 m/s, find the length of the train.*

SOLUTION Length of train = Time × Relative speed

$$= 7.5 \times (10 + 20) = 7.5 \times 30 = 225 \text{ m}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 21 *A train of length 250 m crosses a bridge of length 150 m in 20 seconds. What is the speed of train?*

SOLUTION (Length of train + Length of bridge)

= Speed of train × Time

$(250 + 150) = 20 \times \text{Speed}$

$$\text{Speed} = \frac{400}{20} = 20 \text{ m/s} = 72 \text{ km/h}$$

EXAMPLE 22 *Two trains coming from the opposite sides crosses each other in 10 seconds if the lengths of first train and second train be 125 m and 175 m respectively, also the speed of first train be 36 km/h, find the speed of second train.*

SOLUTION Speed of first train = 36 km/h = 10 m/s

Now, $\text{Time} = \dfrac{\text{Sum of length of the two trains}}{\text{Sum of their speeds}}$

$$10 = \frac{125 + 175}{(10 + x)}$$

$$\Rightarrow \quad x = 20 \text{ m/s} = 72 \text{ km/h}$$

EXAMPLE 23 *A fast moving superfast express crosses another passenger train in 20 seconds. The speed of faster train is 72 km/hr and speeds of slower train is 27 km/h. Also the length of faster train is 100 m, then find the length of the slower train if they are moving in the same direction.*

SOLUTION $\text{Time} = \dfrac{\text{Sum of length of the two train}}{\text{Difference in speeds}}$

$$20 = \frac{(100 + x)}{25/2}$$

$$\Rightarrow \quad x = 150 \text{ m}$$

NOTE Relative speed = (72 – 27) = 45 km/h

$$= 45 \times \frac{5}{18} = \frac{25}{2} \text{ m/s}$$

CONCEPT BASED ON BOATS AND RIVERS (OR STREAMS)

(i) When the boat and stream (or current) of river move in the same direction, then the relative speed of the boat is the sum of the individual speeds of boat and river. It is known as **downstream speed**.

(ii) When the boat moves against the current of the river (*i.e.*, in opposite direction), then the relative speed of the boat is the difference of the speeds of the boat and stream (of the river). It is known as **upstream speed**.

Let the speed of boat in still water be B and speed of current of river be C then,

$$\begin{cases} \text{Downstream speed} = (B + C) \\ \text{Upstream speed} = (B - C) \end{cases} ; \qquad B > C$$

$$\begin{cases} \text{Speed of the boat in still water} = \dfrac{(D + U)}{2} \\ \text{Speed of current (or stream)} = \dfrac{(D - U)}{2} \end{cases}$$

where $D \rightarrow$ downstream speed of the boat

and $U \rightarrow$ upstream speed of the boat

When the distance covered by boat in downstream (*i.e.*, with the flow of water) is same as the distance covered by boat in upstream (against the flow of the water) then,

$$\frac{\text{Time taken by boat in DS}}{\text{Time taken by boat in US}} = \frac{\text{Upstream speed}}{\text{Downstream speed}}$$

DS → Downstream, US → Upstream

EXAMPLE 24 *A boat can move at 5 km/h in still water (i.e., when water is not flowing). The speed of stream of the river is 1 km/h. A boat takes 80 minutes to go from a point A to another point B and return to the same point.*

(i) What is the distance between the two points?

(ii) What is the ratio of downstream speed and upstream speed?

(iii) What is the ratio of time taken in downstream speed to the upstream speed?

SOLUTION Downstream speed of boat = (5 + 1) = 6 km/h

Upstream speed of boat = (5 – 1) = 4 km/h

Therefore, $\dfrac{\text{Downstream speed}}{\text{Upstream speed}} = \dfrac{\text{Upstream time}}{\text{Downstream time}}$

$$\frac{6}{4} = \frac{3}{2} = \frac{\text{Time taken in upstream direction}}{\text{Time taken in downstream direction}}$$

$\therefore$ Time taken in downstream $= \dfrac{2}{5} \times 80 = 32$ min

and time taken in upstream direction $= \dfrac{3}{5} \times 80 = 48$ min

$\therefore$ Distance between two points = DS speed × DS time

= US speed × US time

where DS → Downstream and US → Upstream

$$D = \frac{6 \times 32}{60} = 3.2 \text{ km}$$

or $$D = 4 \times \frac{48}{60} = 3.2 \text{ km}$$

(i) 3.2 km (ii) 3 : 2 (iii) 2 : 3

EXAMPLE 25 *A man can row 9 km/h in still water. It takes him twice as long as to row up as to row down. Find the rate of stream of the river.*

SOLUTION $\dfrac{\text{Time taken in upstream}}{\text{Time taken in downstream}} = \dfrac{2}{1}$

$$\therefore \quad \frac{\text{Downstream speed}}{\text{Upstream speed}} = \frac{2}{1} \quad \text{where} \quad \frac{B + R}{B - R} = \frac{2}{1}$$

$B \rightarrow$ Speed of boat in still water

$R \rightarrow$ Speed of current

$$\Rightarrow \quad \frac{B}{R} = \frac{3}{1} \qquad \text{(By componendo and dividendo)}$$

$$\Rightarrow \quad \frac{9}{R} = \frac{3}{1} \Rightarrow R = 3 \text{ km/h}$$

Scanned by CamScanner

yourshahbaab.wordpress.com

RACES

Terminology

(i) **Startup or headstart:** When a runner allows to another runner to stay ahead in the same race, then it is said that there is a startup in the race.
For example if A allows B to go ahead before starting the race, then it is said that A gives startup to B and B has the startup. If before starting the race B goes ahead of x metre, then we can say A gives x metre startup to B or B has startup (or headstart) of x metre.

(ii) **Dead heat:** When the runners reach the finishing line (or the final post) then it is said that these runners finish (or end) the race in dead heat.

SOME MORE USEFUL CONCEPTS

(i) When it is said that A can give B a start of x metre in y metre race, then it means in y metre race B runs x metre less than A in the same time.

NOTE There is a great difference between 'can' and 'gives'.

(ii) When A beats B by t seconds in a race of y metre then it means B is the loser and A is the winner and when A reaches the finishing line B is still some distance back to A. Thus B takes t seconds to cover the remaining distance. Hence, we can calculate the speed of loser (B).

(iii) Throughout the race there is always a certain relationship among runners *i.e.*, they always maintain the ratio of speeds. I think this is the nub of all the problems pertaining to the races. Go ahead...

EXAMPLE 1 *A can give B a 200 m startup and C a 300 m startup in a race of 1 km. How many metres startup can B gives to C in a 1 km race.*

SOLUTION



Ratio of speeds of $A : B = 1000 : 800 = 5 : 4$

Ratio of speeds of $A : C = 1000 : 700 = 10 : 7$

Ratio of speeds of $B : C = 800 : 700 = 8 : 7$

Since, when B moves 8 m, C moves 7 metre. Therefore, when B moves 1000 m, C moves 875 metre. Thus, B can give C a start of $1000 - 875 = 125$ m.

Alternatively: Since C is 12.5% slower than B. So, C will cover 12.5% less distance than B in the same time.

(Since when time is constant, they cover the distances in the ratio of their speeds.)

Thus, in 1000 m (or 1 km) when B runs 1000 m, C will run 125 m less than B.

Hence, B can give a start of 125 m to C in a 1 km race.

EXAMPLE 2 *In a one km race A gives B a start of 100 m and in a one km race B gives a start of 80 m to C. In a 1 km race who will win and by how much distance from the worst performer between two losers?*

SOLUTION Ratio of speeds of $A : B = 1000 : 900 = 100 : 90$

Ratio of speeds of $B : C = 1000 : 920 = 100 : 92$

Therefore, when A moves 1000 m, B moves 900 m and when B moves 900 m, C moves 828 m.

Thus,



Since, C moves 8% less than B in the same time. Thus, C is the worst performer and A will win by him by 172 m.

EXAMPLE 3 *In a 4 km race A wins by 600 m over B. B can give start of 200 m to C in a 4 km race. By how much distance C gets start up so that the race between A and C ends in dead heat in the same race of 4 km?*

SOLUTION



Ratio of speeds of $A : B = 20 : 17$

and Ratio of speeds of $B : C = 20 : 19$

$\therefore$ Ratio of speeds of $A : B : C = 400 : 340 : 323$

Therefore, in 4000 m race A run 4000 m, B run 3400 m and C run 3230 m. Thus C can get 770 m start up from A.

EXAMPLE 4 *In a 1500 m race A wins over B by 350 m and in 1500 m race C can give a startup of 250 m to B. By how much distance A give start up to C, so that A beats C by 50 metres?*

SOLUTION Ratio of speeds of $A : B = 30 : 23$

Ratio of speeds of $B : C = 5 : 6$

$\therefore$ Ratio of speeds of $A : B : C = 150 : 115 : 138$

So, when A moves 1500 m, B moves 1150 m and C moves 1380 m. Thus C moves 120 m less than A. To win A just by 50 m over C, A should give $120 - 50 = 70$ m startup to C.

EXAMPLE 5 *In a race of 2500 m, A beats B by 500 m and in a race of 2000 m, B beats C by 800 m. By what distance A gives startup to C so that they will end up with dead heat in 3 km race. Also find that by what distance A will win over C in a 1 km race?*

SOLUTION Ratio of speeds of $A : B = 5 : 4$

Ratio of speeds of $B : C = 5 : 3$

$\therefore$ Ratio of speeds of $A : B : C = 25 : 20 : 12$

Scanned by CamScanner

yoursmahboob.wordpress.com

In 3 km race A run 3000 m, B run 2400 m, C run 1440 m, so to end up the race in dead heat A should give C the startup of 1560 m and therefore in 1 km the same will be 520 m.

EXAMPLE 6 *A gives B, a start of 30 m or 10 seconds and end up the race of 1 km in dead heat. What is the ratio of speeds of A and B?*

SOLUTION



Since, either B has the startup of 30 m or 10 seconds. It means B runs 30 m in 10 seconds. Hence, the speed of B is 3 m/s.

NOTE Don't be confused that A's speed = 3 m/s.

Also, it is very simple when A moves 1000 m, B moves 970 m. Since, the ratio of speeds is equal to the ratio of distances covered by A and B in the same time. Thus, the speed of

$$A : B = 1000 : 970 = 100 : 97$$

EXAMPLE 7 *In a 1 km race A wins over B by 80 m or 20 seconds. B can give a start of 100 m to C in 1 km race. Find out that by how much time A will win over C? Also, find the ratio of speeds of B and C.*

SOLUTION Ratio of speeds of $A : B = 100 : 92$

Ratio of speeds of $B : C = 10 : 9$

$\therefore$ Ratio of speeds of $A : B : C = 1000 : 920 : 828$

Also, Speed of $B = \frac{80}{20} = 4$ m/s

Therefore, Speed of $C = 3.6$ m/s

Now, C has to cover 172 m distance in extra time. So, the time taken by C to cover the remaining distance $= \frac{172}{3.6} = 47.77$ s.

Ratio of speeds of $B : C$ = Ratio of distances covered by $B : C$

$$= 1000 : 900 = 10 : 9$$

$$\therefore \quad \frac{\text{Speed of } B}{\text{Speed of } C} = \frac{10}{9}$$

EXAMPLE 8 *A can win B by 250 m in a 2 km race. What should be the change in distance of startup? So, that B must cover 20% less distance than that by A in the same time.*

SOLUTION

$$\frac{\text{Distance covered by } A}{\text{Distance covered by } B} = \frac{5}{4}$$

$$\therefore \quad \frac{\text{Speed of } A}{\text{Speed of } B} = \frac{5}{4}$$

So, when A moves 2000 m, B should move 1600 m. But since initially B moves 1750 m. Therefore the new startup will be increased by 150 m.

EXAMPLE 9 *The ratio of speeds of A and B is 4 : 7 and A loses the race by 270 m, then what is the length of the race course?*

SOLUTION When B moves 7 m, A moves only 4 m. Hence, A loses the race by 3 m.

Now, since B loses by 3 m in the race of 7 m.

$\therefore$ B will lose 270 m in the race of 630 m.

EXAMPLE 10 *The ratio of time taken to run a certain distance by Pythagorus and Hawkins is 4 : 3 and thus Hawkins wins the race by 360 m. What is the distance of race course?*

SOLUTION

$$\frac{\text{Time taken by Pythagorus}}{\text{Time taken by Hawkins}} = \frac{4}{3}$$

$$\frac{\text{Speed of Pythagorus}}{\text{Speed of Hawkins}} = \frac{3}{4}$$

$$= \frac{\text{Distance covered by P}}{\text{Distance covered by H}}$$

Now, when Hawkins runs 4 m, Pythagorus runs 3 m and thus Hawkins wins by 1 m.

So, when Hawkins wins the race by 1 m, race course is 4 m.

when Hawkins wins the race by 360 m, race course is

$$360 \times 4 = 1440 \text{ m}$$

Alternatively : 360 = 25% of the total length of race.

$\therefore$ length of race course = 1440 m.

EXAMPLE 11 *In a race of D km, A wins over B by 0.2 D and in the same length of race B wins over C by 0.25 D. What should be the head- start to C, So that A and C finish the race at the same time.*

SOLUTION **Note:** Instead of solving the problem using 'D' as a distance convert it into 100 *i. e*, suppose $D = 100$.

(It is just for your convenience.)

Now,



Now, Speed of $A : B = 100 : 80 = 5 : 4$

Speed of $B : C = 4 : 3$

$\therefore$ Speed of $A : B : C = 20 : 16 : 12$

$$= \underbrace{100 : 80 : 60}_{\{40\}}$$

So, A can give 'C' a start of 40 m in 100 m race. Therefore, A can give 0.4 D. Start to 'C' in the race of D unit.

EXAMPLE 12 *In a 3 km race the speeds of A and B are in the ratio of 6 : 5 and A wins by 10 seconds. What is the time taken by B to finish the race. Also, to end the race in dead heat what per cent of total distance A should give the startup to B?*

SOLUTION Ratio of distances covered by A and B when A just reaches the finishing line = 6 : 5.

Thus, B has to cover 500 m distance in extra time and this 500 m distance is covered by B in 10 seconds. So, the speed of B = 50 m/s.

Thus, the total time required by B to complete the 3 km race

$$= \frac{3000}{50} = 60 \text{ s} = 1 \text{ min}$$

Since, B coveres 16.66% distance less than A covers in the same time, so A should give 16.66% of the total distance as a startup to B.

EXAMPLE 13 *In a 1 km race A gives B a startup of 5 seconds and still wins over B by 15 seconds. The ratio of speeds of A and B is 2 : 1. Find the time taken by A to finish 2.5 km race.*

Scanned by CamScanner

yoursmanboob.wordpress.com

SOLUTION

$$\frac{\text{Speed of } A}{\text{Speed of } B} = \frac{2}{1}$$

$$\frac{\text{Time taken by } A}{\text{Time taken by } B} = \frac{1}{2}$$

$$\frac{t}{(t+20)} = \frac{1}{2}$$

$$\Rightarrow \quad t = 20 \text{ s}$$

Thus, A needs 20 seconds to cover 1 km. Thus, to cover 2.5 km race he needs $20 \times 2.5 = 50$ seconds.

EXAMPLE 14 *X can beat Y by 200 m in a race of 2000 m. Y can beat Z by 100 m in a race of 2500 m. By how many metres can X beat Z in a race of 1000 m.*

SOLUTION Ratio of speeds of X and $Y = 10 : 9$ (2000 : 1800)

Ratio of speeds of Y and $Z = 25 : 24$ (2500 : 2400)

Ratio of speeds of X, Y and $Z = 250 : 225 : 216$

Since in a race of 250 m, X beats Z by 34 m.

So, in a race of 1000 m, X will beat Z by 136 m.

EXAMPLE 15 *In a 6 km race B has 250 m headstart and C has 500 m headstart by A, still A beats C and B by 235 m and 350 m respectively. How many metres startup can B give to C so as to end up the race at the same time with C in the race of 6 km. Also find the ratio of speeds of $A : B : C$.*

SOLUTION When A runs 6000 m, B runs 5400 m only and C runs 5265 m only.

So, when B runs 6000 m, C will run 5850 m. So, B can give 150 m startup to C.

Ratio of speeds of $A : B : C = 6000 : 5400 : 5265$

$= 1200 : 1080 : 1053$

$= 400 : 360 : 351$

EXAMPLE 16 *A can run 1 km in 2 min 20 second and B can run the same distance in 3 min. What is the distance travelled by B in the same time as A travels, when they start simultaneously in the race of 4.5 km.*

SOLUTION

$$\frac{\text{Time taken by } A}{\text{Time taken by } B} = \frac{140 \text{ s}}{180 \text{ s}} = \frac{7}{9}$$

$$\therefore \quad \frac{\text{Speed of } A}{\text{Speed of } B} = \frac{\text{Distance travelled by } A}{\text{Distance travelled by } B} = \frac{9}{7}$$

Therefore, B travels $\frac{7}{9} \times 4.5 = 3.5$ km.

EXAMPLE 17 *Shahrukh takes 4 min to cover the same distance for which Urmila takes 6 min 30 sec. What is the ratio of distances covered by Shahrukh and Urmila in the race of 2.6 km and by what distance Shahrukh wins over Urmila?*

SOLUTION

$$\frac{\text{Time taken by Shahrukh}}{\text{Time taken by Urmila}} = \frac{240}{390} = \frac{8}{13}$$

$$\frac{\text{Distance covered by Shahrukh}}{\text{Distance covered by Urmila}} = \frac{13}{8}$$

Hence, Shahrukh will win the race by 1 km.

EXAMPLE 18 *A runs at the speed of $\frac{7}{4}$ times the speed of B. By calculation B finds that she has to run 300 m after A reaches to the winning post. What is the total distance of race?*

SOLUTION

$$\frac{\text{Speed of } A}{\text{Speed of } B} = \frac{7}{4}$$

$$\frac{\text{Distance of } A}{\text{Distance of } B} = \frac{7}{4}$$

So, the total distance of race = 700 m.

$(\because 7x - 4x = 300 \Rightarrow 7x = 700)$

EXAMPLE 19 *Time taken by A is 5/7 of B's time for the same length of race. The speed of A is 84 m/s and A beats B by 240 m. What is the length of race course?*

SOLUTION

$$\frac{\text{Speed of } A}{\text{Speed of } B} = \frac{\text{Time taken by } B}{\text{Time taken by } A} = \frac{7}{5}$$

Now since, $7x - 5x = 240$

$$\Rightarrow \quad 7x = 840 \text{ m}$$

EXAMPLE 20 *In a race of 5000 m, Michal beats Nicholas by 600 m and Nicholas in a race of 2000 m beats Oscar by 600 m. In a 1 km race by how much distance Michal beats Oscar?*

SOLUTION Ratio of speeds of $M : N : O = 100 : 80 : 56$

So, Michal (M) beats Oscar (O) by 440 m in 1 km race.

EXAMPLE 21 *In a race of 500 m, President runs at 5 m/s. If president gives chairman a start of 20 m and still beats him by 20 seconds, what is the chairman's speed?*

SOLUTION Chairman has to cover only 480 m. He takes total

$$100 + 20 = 120 \text{ s}$$

Therefore, speed of chairman $= \frac{480}{120} = 4$ m/s

EXAMPLE 22 *In a race of 800 m Dholakiya gives Preetam a start of 200 m and then loses the race by 20 seconds. What is the speed of Preetam and Dholakiya respectively? If the ratio of respective speeds be 3 : 2.*

SOLUTION Let the speed of Dholakiya be S_D and speed of Preetam be S_P and let the time taken by Preetam be t second then,

$$\frac{S_D}{S_P} = \frac{\frac{800}{(t+20)}}{\frac{600}{t}} = \frac{2}{3}$$

$$\frac{800}{600} \times \frac{t}{(t+20)} = \frac{2}{3}$$

$$t = 20 \text{ s}$$

$$\therefore \quad \text{Speed of Preetam} = \frac{600}{20} = 30 \text{ m/s}$$

and speed of Dholakiya $= \frac{800}{40} = 20$ m/s

EXAMPLE 23 *In race of 1 km Sahara gives Birla a startup of 250 m still Sahara wins by 150 m. What is the ratio of speeds of Sahara and Birla?*

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION When Sahara covers 1000 m, Birla covers only 600 m.
So, the ratio of speeds of Sahara and Birla
$= 1000 : 600 = 5 : 3$

EXAMPLE 24 *Priyambda wins the race over Kokilaben by 150 m in a race of 1 km but when she gives a startup of 5 seconds to Kokilaben she wins by 65 m. Find the speed of Kokilaben.*

SOLUTION In 5 seconds Kokilaben runs 85 m.
So, the speed of Kokilaben = 17 m/s.

CIRCULAR MOTION

(i) When the bodies are moving in the opposite direction, their relative speed becomes equal to the sum of their individual speed.

(ii) When two bodies are moving in the same direction their relative speed becomes equal to the difference of the individual speeds.

First Meeting

(i) Let A and B be two runners. Time taken by them to meet for the first time

$$= \frac{\text{Length of the circular track}}{\text{Relative speed}}$$

(ii) When there are more than two runners, then suppose A is the fastest runner and A meets B for the first time in t_{AB} seconds/hours and A meets C for the first time in t_{AC} seconds/hours and A meets D for the first time in t_{AD} seconds/hours and so on. Then time taken by all of them to meet for the first time is the LCM of t_{AB}, t_{AC}, t_{AD} etc.

First Meeting at the Starting Point

Let A takes t_A time to complete one round and B takes t_B time and C takes t_C time and so on, then the time taken to meet for the first time at the starting point = LCM of t_A, t_B, t_C etc.

EXAMPLE 1 *Arjun and Bhishma are running on a circular track of length 600 m (i.e., circumference of the track). Speed of Arjun is 30 m/s and that of Bhishma is 20 m/s. They start from the same point at the same time in the same direction. When will they meet again for the first time?*

SOLUTION
$$\text{Time} = \frac{\text{Circumference}}{\text{Relative speed}}$$
$$= \frac{600}{10} = 60\text{ s}$$

Actually Arjun (faster one) has to make a lead of 600 m, because when Arjun will be 600 m ahead (or extra distance) of Bhishma, they will be together again as a person when completes the total length (or circumference) it starts retracing the same path and thus Arjun and Bhishma can be together again.

Since, they make a difference (or Arjun makes a lead) of 10 m in 1 second. So, he will create 600 m difference in 60 second.

EXAMPLE 2 *In the previous problem if they move in opposite direction, then what is the time taken by them to meet again for the first time?*

SOLUTION
$$\text{Time} = \frac{\text{Circumference}}{\text{Relative speed}}$$
$$= \frac{600}{50} = 12\text{ s} \qquad (30 + 20 = 50)$$

EXAMPLE 3 *Arjun and Bhishma run at the speed 30 m/s and 20 m/s respectively on the circular track of 600 m, as its circumference, when would the Arjun and Bhishma meet for the first time at the starting point if they start simultaneously from the same point?*

SOLUTION Time taken by Arjun to complete one round
$$= \frac{600}{30} = 20\text{ s}$$
Time taken by Bhishma to complete one round $= \frac{600}{20} = 30\text{ s}$

Hence, after every 20 second, Arjun would be at the starting point and after every 30 second. Bhishma would be at the starting point. Thus the time taken by both to be at the starting point again for the first time
$$= \text{LCM of } 20 \text{ and } 30 = 60\text{ s}$$

Thus, every 60 seconds they would be together at the starting point.

NOTE The required time for the bodies to meet for the first time at the starting point is immaterial to the direction of bodies *i.e.*, whether they move in the same direction or in opposite direction.

EXAMPLE 4 *Arjun, Bhishma and Nakul run on the circular path at the speed of 20 m/s, 30 m/s and 50 m/s respectivley in the same direction. The circumference of the track (or path) is 600 m.*
(i) When will they be together again for the first time?
(ii) When will they be together again for the first time at the starting point?

SOLUTION (i) Nakul meets Arjun after every $= \frac{600}{(50-20)} = 20\text{ s}$

Nakul meets Bhishma after every $= \frac{600}{(50-30)} = 30\text{ s}$

Therefore, all of the three would meet after every 60 seconds. (60 = LCM of 20 and 30).
Hence, they would all meet for the first time after 60 seconds.

(ii) Arjun takes $\frac{600}{20} = 30\text{ s}$ to complete one round

Bhisma takes $\frac{600}{30} = 20\text{ s}$ to complete one round

and Nakul takes $\frac{600}{50} = 12\text{ s}$ to complete one round

Hence, they would meet for the first time at the starting point after 60 seconds.

HINT 60 = LCM of 30, 20 and 12.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 5 *A tortoise can complete a full round on the circular track in 8 min, while the rabbit can do the same on the same circular track in 5 min. A, B, C and D are the four consecutive points on the circular track which are equidistant from each other. A is opposite to C and B is opposite to D.*

(i) After how many minutes will they meet together for the first time, when both have started simultaneously from the same point in the same direction?

(ii) After how many minutes will they meet together for the first time at the starting point, when both have started simultaneously from the same point in the same direction?

(iii) If they start from a point A, simultaneously in the same direction then after how many minutes will they meet at C which is just opposite to A?

(iv) If tortoise has a lead of 5 min, when would they meet for the first time, where they have started from the same point in the same direction?

SOLUTION (i) Ratio of time of rabbit and tortoise = 5 : 8

$\therefore$ Ratio of the speed of rabbit and tortoise = 8 : 5

Let the length of the circular track be 40 m, then the speed of rabbit = 8 m/min and speed of tortoise = 5 m/min.

(40 is the LCM of 8 and 5, taken just for convenience in calculation)

Now, the time when they will be together for the first time

$$= \frac{\text{Circumference}}{\text{Relative speed}} = \frac{40}{3} \text{ min}$$

(ii) Time taken by rabbit to complete one round = 5 min

Time taken by tortoise to complete one round = 8 min

$\therefore$ They will meet at the starting point, for the first time

= LCM of 5 and 8 = 40 min

(iii) Rabbit reaches point C in $\frac{20}{8} = 2.5$ min.

Rabbit reaches the same point C in 7.5, 12.5, 17.5, 22.5 min etc. Tortoise reaches after 4 min, 12 min, 20 min, ... etc. They will never meet at C since time cannot coincide as time taken by rabbit is the decimal number and time taken by tortoise is a natural number.

(iv) In 5 min tortoise travels 25 m. Now, rabbit starts chasing tortoise @ 8 m/min.

$\therefore$ Time taken by rabbit to overtake tortoise

$$= \frac{25}{(8-5)} = \frac{25}{3} \text{ min}$$

EXAMPLE 6 *Alfred and Bernard run on the circular track of 600 m. Speeds of Alfred and Bernard are 30 m/s and 20 m/s respectively. Initially they are diametrically opposite to each other.*

(i) When will they meet for the first time if both move in the same direction?

(ii) If both of them move in opposite directions, when will they meet for the second time?

SOLUTION (i) Relative speed of Alfred = 30 – 20 = 10 m/s

Bernard is 300 m ahead in the race.

So, time taken by Alfred to catch Bernard $= \frac{300}{10} = 30$ s

(ii) To meet for the second time they have to cover

= 300 + 600 = 900 m

there relative speed = 30 + 20 = 50 m/s

(since direction is opposite)

$\therefore$ Time taken to meet for the second time $= \frac{900}{50} = 18$ s

EXAMPLE 7 *A, B and C run on a circular track of 800 m. Speeds of A, B and C are 20 m/s, 26 m/s and 33 m/s.*

(i) When will they meet for the first time?

(ii) What is the ratio of distances covered by each one to meet for the first time.

SOLUTION (i) Time taken by C to meet A for the first time

$$= \frac{800}{33-20} = \frac{800}{13} \text{ s}$$

Time taken by C to meet B for the first time

$$= \frac{800}{33-26} = \frac{800}{7} \text{ s}$$

LCM of $\frac{800}{13}$ and $\frac{800}{7} = 800$ s.

Therefore, all of them (i.e., A, B and C) meet after 800 seconds = 13 min 20 sec.

(ii) The ratio of distances = ratio of speeds

= 20 : 26 : 33

INTRODUCTORY EXERCISE-9.1

1. P and Q starts running on the circular track in opposite directions. They start from a point A and meet for the first, second and third time at B, C and A respectively. What is the ratio of speeds of P and Q?
   (a) 2 : 1 (b) 3 : 1
   (c) 4 : 1 (d) none of these
2. P and Q run on a circular track of 100 m. Speed of P is 250 m/s and that of Q is 400 m/s. In how many points on a circular track will they meet if they start from the same point, simultaneously in the same direction?
   (a) 1 (b) 2
   (c) 3 (d) 4
3. A, B and C start to walk around a circular track. A completes one round in 91/6 seconds, B completes in 65/4 seconds and C completes in 56/3 seconds respectively. After how many seconds will they meet to each other at the starting point again?
   (a) 3460 s (b) 1820 s
   (c) 3640 s (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

CLOCKS

Actually the movement of hour-hand and minute-hand follows the relative motion. The dial of the clock behaves like a circular track and where minute-hand is a faster runner and hour-hand is a slower one.

For better understanding with the clocks, assume 60 minutes shown on the dial as 60 points. Here we give an arbitrary new unit of distance as 'point'.

So, minute-hand (MH) runs on the circular track of 60 points at 60 points per hour and hour-hand (HH) runs at 5 points per hour. Now we become familiar with the relative motion of two hands of a clock.

Here, 1 point = 6° and 60 point = 360°

also 1 point = 6° = 1 min

EXAMPLE 1 *How many times minute-hand coincides with hour-hand in 12 hours?*

SOLUTION Time taken by minute-hand to meet hour-hand for the first time $= \frac{60}{55} = \frac{12}{11}$ hours.

(Assume initially both hands are at 12 *i.e.*, 12 O' clock is shown by them.)

Therefore, after every 12/11 hours-minute hand and hour-hand meet each other (or coincide or overtake).

Now, since in $\frac{12}{11}$ hours they coincide 1 time

So, in 12 hours they will coincide

$$= \frac{12}{12/11} = \frac{12}{12} \times 11 = 11 \text{ times}$$

Remember: Between 11 O'clock and 1 O'clock, two hands coincide only one time, that's why they coincide with each other only 11 times in 12 hours.

NOTE In every $\frac{12}{11}$ hours (or 65 $\frac{5}{11}$ min) two hands of a clock coincide.

EXAMPLE 2 *In 12 hours how many times the two hands of clock will be just opposite to each other i.e., they make a straight line having the difference of 180° between them?*

SOLUTION 180° = 30 points

For the first time minute-hand and hour-hand will be separated in $\frac{30}{55}$ h $\left(\text{Time} = \frac{\text{Required distance}}{\text{Relative speed}}\right)$ and for every next time they will take $\frac{60}{55}$ minutes more to occur as opposite to each other.

(Since in 60/55 hours they complete one round of clock's dial *i.e.*, 60 points undergoing the relative motion, we have total 12 hours.)

Thus, $\frac{30}{55} + \frac{60}{55} + \frac{60}{55} + \frac{60}{55} + \ldots = 12$

$\Rightarrow$ $\frac{30}{55} + \frac{60}{55} + \frac{60}{55} + \ldots = \frac{12 \times 55}{55}$

$\Rightarrow$ $6 + 12 + 12 + \ldots = 12 \times 11 = 132$

$\Rightarrow$ $6 + 12n = 132$

$\Rightarrow$ $12n = 126 \Rightarrow n = 10$

only integral value is admissible.

Thus, total 10 + 1 = 11 times both hands of a clock will be opposite to each other.

Remember: Between 5 O'clock and 7 O'clock the two hands make 180° angle only one time, that's why they make 180° angle only 11 times in 12 hours, *i.e.*, at exactly 6 O'clock they are 180° apart.

EXAMPLE 3 *In 12 hours how many times a minute-hand and hour-hand of a clock makes 90° between them or becomes perpendicular to each other?*

SOLUTION 90° = 15 points

This problem can be solved in two parts.

(i) When minute-hand goes ahead of hour-hand.

(ii) When hour-hand goes ahead of minute-hand.

(i) For the first time minute-hand and hour-hand will make 90° (or 15 points) difference in $\frac{15}{55}$ hours.

$\left(\text{time} = \frac{\text{distance}}{\text{relative speed}}\right)$

Now, after every $\frac{60}{55}$ hours they will occur at 90°. Since, in every $\frac{60}{55}$ hours they create a difference of 360° or 60 points (as the circumference of dial).

Now, we have 12 hours,

$\therefore$ $\frac{15}{55} + \frac{60}{55} + \frac{60}{55} + \ldots = 12\text{h} = 12 \times \frac{55}{55}$

$\Rightarrow$ $\frac{3}{11} + \frac{12}{11} + \frac{12}{11} + \ldots = \frac{12 \times 11}{11}$

$\Rightarrow$ $\frac{3}{11} + \left(\frac{12}{11}n\right) = \frac{12 \times 11}{11}$

$\Rightarrow$ $3 + 12n = 132$

$\Rightarrow$ $n = \frac{129}{12} = 10$

(only integral value of n is acceptable)

Therefore, 10 + 1 = 11 times in 12 hours minute-hand makes 90° angle between the two hands, but when minute hand is ahead of hour-hand.

(ii) For the first time minute-hand and hour-hand will make 90° (or 15 points) difference in $\frac{60-15}{55} = \frac{45}{55}$ hours.

Since, in this case minute-hand goes till it appears to be 15 points behind of hour-hand (consider initially they are showing 12 O'clock) then you will see that at 12 : 49 : 05 two hand are making 90° angle between them, while it appears to be hour-hand is ahead of minute-hand.

Now, for every next time after $\frac{60}{55}$ hours they will show the same situation.

we have 12 hours.

So, $\frac{45}{55} + \frac{60}{55} + \frac{60}{55} + \frac{60}{55} + \ldots = 12\text{h} = 12 \times \frac{55}{55}$

Scanned by CamScanner

yoursmanboob.wordpress.com

$$\Rightarrow \quad \frac{3}{11}+\frac{4}{11}+\frac{4}{11}\ldots=\frac{4\times 11}{11}$$

$$\Rightarrow \quad 3+4+4+\ldots=44$$

$$\Rightarrow \quad 3+4n=144$$

$\Rightarrow n=\frac{41}{4}=10$, consider only integral value.

Thus, total $10+1=11$ times they will make 90° angle.

Hence, in 12 hours both hands make 90° angle $(11+11)=22$ times in different positions.

Remember: At 3 O'clock and 9 O'clock they are at right angled. Since, except between 2–4 O'clock and 8–10 O'clock in each hour both hands make 90° angle 4 times while in the 2–4 O'clock and 8–10 O'clock two hands makes three-three times in every two hour.

EXAMPLE 4 *Between 2 O'clock and 3 O'clock when two hands of a clock overlap each other?*

SOLUTION To overlap or overtake minute-hand has to reduce the gap of 10 points. Since at 2 O'clock two hands are 10 point apart.

$$\therefore \quad \text{Time}=\frac{\text{Distance advanced}}{\text{Relative speed}}$$

$$=\frac{10}{55}\text{h}=\frac{10}{55}\times 60\text{ min}$$

$$=10\text{ min }54\text{ s}$$

Thus, at 2 : 10 : 54 both hands of a clock coincide.

EXAMPLE 5 *Between 6 am and 7 am when the two hands of a clock coincide.*

SOLUTION $\text{Time}=\frac{30}{55}\text{h}=\frac{30}{55}\times 60\text{ min}=32\text{ min }43\text{ s}$

(Distance advanced $=6\times 5=30$ points)

Thus at 6 : 32 : 43 two hands of a clock coincide.

EXAMPLE 6 *Between 11 O'clock and 12 O'clock when will they coincide.*

SOLUTION Distance advanced at 11 O'clock = 55 points

Relative speed = 55 point/h

$$\therefore \quad \text{Time}=\frac{55}{55}=1\text{ h}$$

Hence, they will coincide at $(11+1)=12$ O'clock.

EXAMPLE 7 *Between 3 O'clock and 4 O'clock when will the two hands make 36° angle between them:*

(i) when hour-hand is ahead of minute-hand.

(ii) when minute-hand is ahead of hour-hand.

SOLUTION (i) 36° = 6 points

Now, at 3 O'clock two hands are separated by exactly 15 points to which we have to reduce upto 6 points. Thus, we have to reduce $15-6=9$ points distance, with the relative speed of 55 point/h.

$$\therefore \quad \text{Time required}=\frac{9}{55}\text{ h}=\frac{9}{55}\times 60$$

$$=9\text{ min }49\text{ s}$$

Thus at 3 : 09 : 49 they are 36° apart from each other.

(ii) At 3 O'clock both hands are 15 points apart so to make them 6 points apart minute-hand has to move for $(15+6)=21$ points, since minute-hand has to go 6 points ahead of hour hand, after crossing the hour-hand.

$$\therefore \quad \text{Time}=\frac{21}{55}\text{ h}=\frac{21}{55}\times 60\text{ min}=22\text{ min }54\text{ s}$$

Thust at 3 : 22 : 54, both hands will be 6 points (or 36°) apart from each other.

Did you notice something?

The same angle can be formed in two situations, one when hour-hand is ahead of minute-hand and when minute-hand is ahead of hour-hand.

Thus, you can find the required time by dividing the required difference of points (which you have to either create or reduce) by the relative speed.

EXAMPLE 8 *What is the angle between the two hands at 3 : 10 am?*

SOLUTION Assume 60th point (*i.e.*, when it is 12 O'clock) as the origin.

Step 1. Find the distance of minute-hand from the origin.

Step 2. Find the distance of hour-hand from the origin.

Step 3. Take the difference between two values obtained in step 1 and step 2.

$\therefore$ **Step 1.** 10 point = 60°

Step 2. 90° + 5° = 95° (In 10 min hour-hand moves 5°)

Step 3. 95° – 60° = 35°

Thus, at 3 : 10 am two hands are 35° apart.

EXAMPLE 9 *What is the angle between two hands of a clock at 7 : 35?*

SOLUTION **Step 1.** At 7 : 35, minute-hand is $35\times 6=210°$ away from origin.

Step 2. At 7 : 35 hour-hand is $7\times 30+35\times\frac{1}{2}=210+17.5$ = 227.5° away from the origin.

Step 3. 227.5 – 210 = 17.5°

Thus at 7 : 35, both hands make 17.5° angle between them.

NOTE A minute-hand moves 6° in one minute while a hour-hand moves $\left(\frac{1}{2}\right)°$ in one minute.

Scanned by CamScanner

yoursmahboob.wordpress.com



LEVEL 1

1. 'A' goes 10 km distance with average speed of 6 km/h while rest 20 km he travels with an average speed of 15 km/h. What is the average speed of '*A*' **during** the whole journey?
(a) 10 km/h (b) 12 km/h
(c) 13 km/h (d) 14.5 km/h

2. *A* covers half of his distance with 20 km/h and rest with 30 km/h. What is the average speed during the whole journey?
(a) 20 km/h (b) 24 km/h
(c) 25 km/h (d) 26 km/h

3. *A* covers 1/3rd of his journey at the speed of 10 km/h and half of the rest at the speed of 20 km/h and rest at the speed of 30 km/h. What is the average speed of *A*?
(a) $6\frac{2}{11}$ km/h (b) $16\frac{4}{11}$ km/h
(c) $16\frac{4}{11}$ m/s (d) none of these

4. *A* covers 1/4th of his journey at 20 km/h and 1/3rd of the rest at 25 km/h and half of the rest at 30 km/h and rest at the speed of 40 km/h. What is the average speed of *A*?
(a) $13\frac{78}{89}$ km/h (b) 12 km/h
(c) $26\frac{86}{89}$ km/h (d) 28 km/h

5. *A* covered half of his journey at 20 km/h and rest at x km/h, then his average speed is 24 km/h. What is the value of x?
(a) 30 (b) 32
(c) 36 (d) 40

6. A man covered half of the distance at $3x$ km/h and rest at $5x$ km/h. What is the average speed of the man?
(a) $4x$ km/h (b) $3.5x$ km/h
(c) $3.75x$ km/h (d) none of these

7. A person goes to his office at 1/3rd of the speed at which he returns from his office. If the average speed during the whole trip (i.e., one round) is 12 km/h. What is the speed of the person while he was going to his office?
(a) 10 (b) 6
(c) 8 (d) can't be determined

8. A person *X* starts from Lucknow and another persons *Y* starts from Kanpur to meet each other. Speed of *X* is 25 km/h, while speed of *Y* is 35 km/h. If the distance between Lucknow and Kanpur be 120 km and both *X* and *Y* start their journey at the same time, when will they meet?
(a) 1 h later (b) 2 h later
(c) $\frac{1}{2}$ h later (d) 3 h later

9. In the above question (no. 8), what is the distance from Lucknow where they meet?
(a) 50 km (b) 60 km
(c) 100 km (d) 80 km

10. Two persons *A* and *B* started from two different places towards each other. If the ratio of their speeds be 3 : 5, then what is the ratio of distance covered by *A* and *B* respectively till the point of meeting?
(a) 1 : 2 (b) 3 : 4
(c) 3 : 5 (d) 5 : 3

Directions for question number 11 to 16: A person P is at X and another person Q is at Y. The distance between X and Y is 100 km. The speed of P is 20 km/h. While the speed of Q is 60 km/h?

11. If they first time meet at point *Z* somewhere between *X* and *Y* then the distance between *X* and *Z* is :
(a) 20 km (b) 40 km
(c) 25 km (d) 30 km

12. If they continue to move to and fro between *X* and *Y* then what is the distance covered by *P* when they meet second time?
(a) 105 km (b) 100 km
(c) 80 km (d) 75 km

13. If they continue to move to and fro between *X* and *Y* then what is the distance travelled by *Q*, when they meet each other for the third time?
(a) 375 km (b) 225 km
(c) 350 km (d) 445 km

14. If *P* and *Q* continue to move between *X* and *Y* in the given manner and if they meet for the fourth time at a place *M* somewhere between *X* and *Y*, then the distance between *X* and *M* is :
(a) 10 km (b) 90 km
(c) 75 km (d) 25 km

15. If *P* and *Q* continue to move between *X* and *Y*, then the ratio of distances covered by *P* and *Q* when they meet for the 5th time?
(a) 1 : 4 (b) 1 : 3
(c) 2 : 3 (d) 3 : 4

16. If *P* and *Q* continue to move between *X* and *Y*, then the distance covered by *P* and *Q* together between any two consecutive meeting?
(a) 100 (b) 300
(c) 200 (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

✍ ***Directions for questions number 17, 18 and 19:*** *A persons P starts his journey from A and another person Q starts his journey from B, towards each other. The speeds of P and Q are 16 km/h and 25 km/h respectively and they meet at point M somewhere between A and B when they start their journey simultaneously.*

17. What is the ratio of time taken by P and Q to reach at M?
(a) 1 : 4 (b) 1 : 1
(c) 4 : 5 (d) 16 : 25

18. What is the ratio of time taken by P and Q to reach B and A respectively?
(a) 16 : 25 (b) 1 : 1
(c) 25 : 16 (d) 4 : 5

19. What is the ratio of time taken by P and Q after meeting each other at M to reach B and A respectively?
(a) 25 : 16 (b) 625 : 256
(c) 16 : 25 (d) 4 : 5

20. The speeds of Vimal and Kamal are 30 km/h and 40 km/h. Initially Kamal is at a place L and Vimal is at a place M. The distance between L and M is 650 km. Vimal started his journey 3 hours earlier than Kamal to meet each other. If they meet each other at a place P somewhere between L and M, then the distance between P and M is :
(a) 220 km (b) 250 km
(c) 330 km (d) 320 km

21. In the above question (no. 20) what is the distance between L and P ?
(a) 220 km (b) 320 km
(c) 330 km (d) none of these

✍ ***Directions for questions number 22 to 27:*** *There are two places X and Y, 200 km apart from each other. Initially two persons P and Q both are at 'X'. The speed of P is 20 km/h and speed of Q is 30 km/h. Later on they starts to move to and fro between X and Y.*

22. If they starts to move between X and Y, then for the first time when they will meet each other?
(a) after 12 hours (b) after 24 hours
(c) after 30 hours (d) after 8 hours

23. If they meet first time at a point M somewhere between X and Y, then what is the distance travelled by P?
(a) 160 km (b) 150 km
(c) 200 km (d) 210 km

24. If they meet second time each other at a point N somewhere between X and Y, then the distance travelled by Q is :
(a) 240 km (b) 480 km
(c) 360 km (d) none of these

25. If they meet third time each other at a point C, somewhere between X and Y, then the ratio of distances CX and CY is :
(a) 3 : 2 (b) 1 : 3
(c) 2 : 3 (d) 2 : 5

26. If they meet fourth time each other at a point D somewhere between X and Y, then what is the distance between D and X?
(a) 75 (b) 80
(c) 150 (d) 160

27. After starting their race, they meet each other for the n^{th} time at point X, then what is the minimum possible value of n?
(a) 1 (b) 2
(c) 3 (d) 5

✍ ***Directions for questions number 28 to 33:*** *A person X started 3 hours earlier at 40 km/h from a place P, then another person Y followed him at 60 km/h, started his journey at 3 O'clock, afternoon.*

28. At what time will they meet to each other (or at what time Y will overtake X)?
(a) 4:30 pm (b) 5 pm
(c) 6 pm (d) 9 pm

29. At what time the difference between X and Y was 30 km, but before Y overtakes X?
(a) 6:30 pm (b) 7:30 pm
(c) 8:75 pm (d) none of these

30. At what time Y will be 30 km ahead of X, after overtaking it?
(a) 6:45 pm (b) 7:30 pm
(c) 10:30 pm (d) 8 pm

31. What is the distance travelled by Y to overtake X?
(a) 180 km (b) 420 km
(c) 320 km (d) 360 km

32. What distance should Y cover so that he may reach 360km ahead of X?
(a) 1440 km (b) 1200 km
(c) 920 km (d) 750 km

33. What is difference in time when X was 30 km ahead of Y and when Y was 30 km ahead of X?
(a) 2 (b) 3
(c) 3.5 (d) 4.25

34. A postman goes with a speed of 36 km/h what is the speed of postman in m/s?
(a) 4.5 m/s (b) 6 m/s
(c) 10 m/s (d) can't be determined

35. In the above question (no. 34) what is the speed in m/min?
(a) 325 (b) 432
(c) 360 (d) 600

36. In the above question (no. 34) what is the speed of postman in mile/h?
(a) 22.37 (b) 30.08
(c) 28.30 (d) 38.12

37. A train goes with a speed of 20 m/s. What is the speed of train in km/h?
(a) 57 km/h (b) 72 km/h
(c) 80 km/h (d) 120 km/h

38. As per the question (no. 37) what is the speed of train in km/min?
(a) 1.2 (b) 12
(c) 1200 (d) 120

39. A is twice fast as B and B is thrice as fast as C. The journey covered by C in 78 minutes will be covered by A in :
(a) 12 min (b) 13 min
(c) 15.5 min (d) none of these

40. The ratio of speeds of A is to B is 2 : 3 and therefore A takes 20 minutes less time than B takes. What is the ratio of time taken by A and B?
(a) 2 : 3 (b) 2 : 5
(c) 3 : 2 (d) 3 : 5

41. What is the time taken by A (in the above question)?
(a) 1 h (b) 1.2 h
(c) 0.6 h (d) 30 min

Scanned by CamScanner

yoursmahboob.wordpress.com

42. A certain distance is covered at a certain speed. If half of this distance is covered in double the time, the ratio of the two speeds is :
(a) 1 : 16 (b) 4 : 1
(c) 2 : 1 (d) 2 : 8

43. Two runner start runing together for a certain distance, one at 5 km/h and another at 3 km/h. The former arrives one and half an hour before the latter. The distance (in km) is :
(a) 12 (b) 20
(c) 25 (d) 36

44. The ratio between the rates of walking of *A* and *B* is 2 : 3. If the time taken by *B* to cover a certain distance is 48 minutes, the time taken (in minutes) by *A* to cover the distance is :
(a) 52 min (b) 68 min
(c) 72 min (d) 32 min

45. Two trains starting at the same time from two stations 300 km apart and going in opposite directions, cross each other at a distance of 160 km from one of them. The ratio of their speeds is :
(a) 7 : 9 (b) 16 : 20
(c) 8 : 7 (d) 8 : 12

46. *A* and *B* travel the same distance at 9 km/h and 10 km/h respectively. If *A* takes 20 minutes longer than *B*, the distance travelled by each is :
(a) 16 (b) 20
(c) 30 (d) none of these

47. Abhinav leaves Mumbai at 6 am and reaches Bangalore at 10 am Praveen leaves Bangalore at 8 am and reaches Mumbai at 11:30 am. At what time do they cross each other?
(a) 10 am (b) 8:32 am
(c) 8:56 am (d) 9:20 am

48. Two persons, Alif and Laila start at the same time from Allahabad and Lucknow and proceed towards each other at 45 km/h and 54 km/h respectively. When they meet, it is found that one of them has travelled 72 km more than the other. The distance between the places (in km) is :
(a) 729 (b) 792
(c) 540 (d) none of these

49. Walking at 4/5 of his normal speed, Dewang is 15 minutes late in reaching his club. What is the usual time taken by him to cover the distance?
(a) 1 h (b) 1 h 20 min
(c) 45 min (d) none of these

50. Walking at 3/4 of her normal speed Malleshwari takes 2 hours more than the normal time. What is the normal time?
(a) 4 h (b) 5 h
(c) 6 h (d) 8 h

51. Walking at 3/2 of his normal speed Shekhawat takes 40 minutes less than the usual time? What is the changed (new) time taken by Shekhawat?
(a) 1 h (b) 1.2 h
(c) 3 h (d) 2 h

52. A man reduces his speed from 20 km/h to 18 km/h. So, he takes 10 minutes more than the normal time. What is the distance travelled by him?
(a) 30 km (b) 25 km
(c) 50 km (d) 36 km

53. Osaka walks from his house at 5 km/h and reaches his office 10 minutes late. If this speed had been 6 km/h he would have reached 15 minutes early. The distance of his office from his house is :
(a) 15 km (b) 12.5 km
(c) 10.5 km (d) 18 km

54. Sachin and Mongiya starting from the same place walk at the rate of 7.5 km/h and 9 km/h respectively. What time will they take to be 7.5 km apart, if they walk in the same direction?
(a) 3 h (b) 4 h
(c) 5 h (d) none of these

55. Two aeroplanes start from the same place in opposite directions. One goes towards east at 320 km/h and the other goes towards west at 400 km/h what time will they take to be 720 km apart?
(a) 4 h (b) 3 h
(c) 1 h (d) 1.5 h

56. A man covers a certain distance by his own car. Had he moved 6 km/h faster he would have taken 4 hours less. If he had moved 4 km/h slower, he would have taken 4 hours more. The distance (in km) is :
(a) 240 km (b) 640 km
(c) 480 km (d) none of these

57. If Deepesh had walked 20 km/h faster he would have saved 1 hour in the distance of 600 km. What is the usual speed of Deepesh?
(a) 100 (b) 120
(c) 150 (d) none of these

58. Harsha takes 3 hours more than Ashok, who drives his car 5 km/h faster than Harsha drives, to cover 180 km distance. What is the speed of Harsha?
(a) 12 km/h (b) 15 km/h
(c) 30 km/h (d) 40 km/h

59. A minibus takes 6 hours less to cover 1680 km distance, if its speed is increased by 14 km/h? What is the usual time taken by minibus?
(a) 15 h (b) 24 h
(c) 25 h (d) 30 h

60. The driver of an ambulance sees a school bus 40 m ahead of him. After 20 second, the school bus is 60 metre behind. If the speed of the ambulance is 30 km/h, what is the speed of the school bus?
(a) 10 km/h (b) 12 km/h
(c) 15 km/h (d) 22 km/h

61. A postman riding a bicycle at 15 km/h can reach a village in 4 hours. If he is delayed by 1 hour at the start, then in order to reach his destination in time, he should ride with a speed of:
(a) 20 km/h (b) 16 km/h
(c) 14 km/h (d) 12 km/h

62. What is the time required by a train of length of 350 m to cross an electric pole with a speed of 70 m/s?
(a) 3 s (b) 3.5 s
(c) 5 s (d) 10 s

63. A train 270 m long is running over a bridge of length of 130 m with a speed of 40 m/s. What is the time taken by this train to cross the bridge?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 6 s (b) 16 s
(c) 10 s (d) none of these

64. If a train 225 m long passes a telegraphic pole in 9 seconds, then the time taken (in seconds) by it to cross a tunnel 450 m long is :
(a) 8 s (b) 10 s
(c) 27 s (d) none of these

65. A train 350 m long is running at the speed of 36 km/h. If it crosses a tunnel in 1 minute, then the length of the tunnel (in metres) is :
(a) 200 m (b) 250 m
(c) 150 m (d) none of these

66. If a 250 m long train crosses a platform of the same length as that of the train in 25 seconds, then the speed of the train is :
(a) 150 m/s (b) 200 m/s
(c) 20 km/h (d) 72 km/h

67. Sabarmati express takes 18 seconds to pass completely through a station 162 m long and 15 seconds through another station 120 m long. The length of the Sabarmati express is :
(a) 132 m (b) 100 m
(c) 80 m (d) 90 m

68. A train 200 m long travels at the speed of 72 km/h. A man is running at 3.6 km/h in the same direction in which the train is going. The train will pass the man in :
(a) 10 s (b) $12\frac{3}{19}$ s
(c) $10\frac{10}{19}$ s (d) none of these

69. A train 350 m long is moving at the speed of 20 km/h. It will cross a man coming from the opposite direction at the speed of 1 km/h in :
(a) 27 s (b) 35 s
(c) 45 s (d) 60 s

70. The length of Lucknow mail is 120 m and that of Punjab mail is 80 m. These two trains are running in the same direction with velocities of 40 km/h and 50 km/h respectively. The time taken by them to cross each other is :
(a) 8 s (b) 72 s
(c) 11.5 s (d) 12.5 s

71. In the above question if the trains are running in opposite directions. The time taken by them to cross each other is :
(a) 8 s (b) 72 s
(c) 12.5 s (d) none of these

72. A train passes an electric pole in 10 seconds and a platform 120 m long in 18 seconds. Its length in metres is :
(a) 150 m (b) 130 m
(c) 240 m (d) 180 m

73. A 175 m long train crosses a man walking at a speed of 9 km/h in the opposite direction in 10 sec. The speed of the train (in km/h) is :
(a) 45 (b) 54
(c) 72 (d) 68

74. A train of length 100 m takes 1/6 minute to pass over another train 150 m long coming from the opposite direction. If the speed of first train is 60 km/h, the speed of the second train is :
(a) 45 km/h (b) 28 km/h
(c) 30 km/h (d) none of these

75. A train overtakes two girls who are walking in the opposite direction in which the train is going at the rate of 3 km/h and 6 km/h and passes them completely in 36 seconds and 30 seconds respectively. The length of the train (in metres) is :
(a) 120 m (b) 150 m
(c) 125 m (d) none of these

76. A coolie standing on a railway platform observes that a train going in one direction takes 4 seconds to pass him. Another train of same length going in opposite direction takes 5 seconds to pass him. The time taken (in seconds) by the two trains to cross each other will be :
(a) 35 (b) 36.5
(c) $\frac{40}{9}$ (d) none of these

77. Pushpak express leaves Lucknow at 6 am and two hours later another train Bhopal express leaves Lucknow. Both trains arrive Bhopal at 4 pm on the same day. If the difference between their speeds be 10 km/h, what is the average speeds of both the trains over entire route :
(a) 40 km/h (b) $44\frac{4}{9}$ km/h
(c) $42\frac{3}{5}$ km/h (d) none of these

Directions for question number 78, 79: Two trains leave Meerut at the difference of 4 hours. The first train leaves at 8 am at 40 km/h and the faster train leaves later at 60 km/h in the same direction.

78. When the faster train will overtake the slower train?
(a) 4 pm (b) 2 pm
(c) 8 pm (d) 6:30 pm

79. What is the distance from Meerut, where one train overtakes another train?
(a) 480 km (b) 420 km
(c) 360 km (d) 250 km

80. The distance between Lucknow and Delhi is 700 km. Rajdhani express starts from Delhi for the Lucknow at 60 km/h. 50 minutes later Lucknow express leaves Lucknow for Delhi on the parallel tracks at 70 km/h. How far from Lucknow will they cross each other?
(a) 250 km (b) 360 km
(c) 350 km (d) 475 km

81. Patna express travels first 560 km in 7 hours and rest 360 km in 9 hours. What is the average speed of the train?
(a) 39 km/h (b) 43 km/h
(c) 63 km/h (d) 57.5 km/h

82. Jammutavi express leaves Jammu for Kanya Kumari at 120 km/h and returns to Jammu at 80 km/h. What is the average speed of the train during the whole journey?
(a) 47.5 km/h (b) 96 km/h
(c) 38 km/h (d) 57.5 km/h

83. In the above question if the total time taken by the train is 25 hours, what is the distance between these two places?
(a) 1365.5 km (b) 1369 km
(c) 1200 km (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

84. Roorkee express normally reaches its destination at 50 km/h in 30 hours. Find the speed at which it travels to reduce the time by 10 hours?
(a) 38 km/h (b) 76 km/h
(c) 75 km/h (d) 60 km/h

85. Two trains *A* and *B* start simultaneously in the opposite direction from two points *P* and *Q* and arrive at their destinations 16 and 9 hours respectively after their meeting each other. At what speed does the second train *B* travel if the first train travels at 120 km/h per hour :
(a) 90 km/h (b) 160 km/h
(c) 67.5 km/h (d) none of these

86. There are two trains running on two parallel tracks. Length of each train is 120 m. When they are running in opposite directions, they cross each other in 4 seconds and when they are running in the same direction they cross in 12 seconds. What is the speed of the faster train?
(a) 80 km/h (b) 72 km/h
(c) 120 km/h (d) 144 km/h

87. Two trains are travelling in the same direction at 22.5 km/h and 7.5 km/h respectively. The faster train crosses a man in the slower train in 18 seconds. What is length of the faster train?
(a) 87.5 m (b) 75 m
(c) 122.5 m (d) none of these

88. A train covers a certain distance moving at a speed of 60 km/h. However if it were to halt for a fixed time every hour, its average speed comes out to be 50 km/h. For how much time does the train halt for every hour?
(a) 6 min (b) 10 min
(c) 12 min (d) none of these

89. Two horses start trotting towards each other, one from *A* to *B* and another from *B* to *A*. They cross each other after one hour and the first horse reaches *B*, 5/6 hour before the second horse reaches *A*. If the distance between *A* and *B* is 50 km. What is the speed of the slower horse?
(a) 30 km/h (b) 15 km/h
(c) 25 km/h (d) 20 km/h

90. Pankaj walked at 5 km/h for certain part of the journey and then he took an auto for the remaining part of the journey travelling at 25 km/h. If he took 10 hours for the entire journey. What part of journey did he travelled by auto if the average speeed of the entire journey be 17 km/h :
(a) 750 km (b) 100 km
(c) 150 km (d) 200 km

91. A car travelled first 36 km at 6 km/h faster than the usual speed, but it returned the same distance at 6 km/h slower than the usual speed. If the total time taken by car is 8 hours, for how many hours does it travelled at the faster speed?
(a) 4 (b) 3
(c) 2 (d) 1

92. A dog starts chasing to a cat 2 hours later. It takes 2 hours to dog to catch the cat. If the speed of the dog is 30 km/h, what is the speed of cat?
(a) 10 km/h (b) 15 km/h
(c) 20 km/h (d) can't be determined

93. Prachi starts from Barabanki at 6 am at constant speed of 60 km/h. She halts at Lucknow for half an hour and then drives at 40 km/h. If she reaches Kanpur at 9 : 30 am, which is 160 km from Barabanki, how far is Barabanki from Lucknow?
(a) 75 km (b) 80 km
(c) 100 km (d) 120 km

94. Two trains whose respective lengths are 200 m and 250 m cross each other in 18 s, when they are travelling in opposite direction and in 1 min, when they are travelling in the same direction. What is the speed of the faster train (in km/h)?
(a) 38.5 (b) 48.5
(c) 54 (d) 58.5

95. Abhinav started for the station half a km from his home walking at 1 km/h to catch the train in time. After 3 minutes he realised that he had forgotten a document at home and returned with increased, but constant speed to get it succeded in catching the train. Find his latter speed in km/h :
(a) 1.25 (b) 1.1
(c) $\frac{11}{9}$ (d) 2

Directions for question number 96-97: The ratio of speeds at which Anil and Mukesh walk is 3 : 4. Anil takes 30 minutes more than the time taken by Mukesh in reaching the destination.

96. If Anil drives the car at twice the speed of his walking then the time required to reach his destination by car is :
(a) 45 min (b) 60 min
(c) 1.5 h (d) 1 h 20 min

97. What is the total distance travelled by each of them, if the average of speeds of Anil and Mukesh is 28 km/h?
(a) 48 (b) 60
(c) 17 km (d) 70

98. Train *X* starts from point *A* for point *B* at the same time that train *Y* starts from *B* to *A*. Point *A* and *B* are 300 km apart. The trains are moving at a constant speed atleast at 25 km/h. The trains meet eachother 3 hours after they start. If the faster train takes atleast 2 more hours to reach the destination. By which time will the slower train have definitely reached its destination? (Ignoring the length of trains in crossing)
(a) 4 hours after the start
(b) 7.5 hours after the start
(c) 6 hours after the start
(d) none of the above

99. In reaching the Purnagiri a man took half as long again to climb the second third as he did to climb the first third and a quarter as long again for the last third as for the second third. He took altogether 5 hs 50 minutes. Find the time he spent on the first third of the journey?
(a) 72 min (b) 80 min
(c) 81 min (d) 88 min

100. Walking at four fifth of his usual speed Vijay Malya reaches his office 15 minutes late on a particular day. The next day, he walked at 5/4 of his usual speed. How early would he be to the office when compared to the previous day?
(a) 27 min (b) 32 min
(c) 30 min (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

101. Abdul starts in a car from Ahmedabad towards Bangalore. After sometime he realises that he will cover only 75% of the distance in the scheduled time and he therefore doubles his speed immediately and thus manages to reach Bangalore exactly on time. Find the time after which Abdul changed his speed, given that he could have been late by 3 hours if he had not changed his speed :
(a) 3 h (b) 4 h
(c) 5 h (d) 6 h

102. A man travels the first part of his journey at 20 km/h and the next at 70 km/h, covering the entire journey at an average speed of 50 km/h. What is the ratio of the distance that he covered at 20 km/h to that he covered at 70 km/h?
(a) 4 : 21 (b) 3 : 22
(c) 1 : 4 (d) 3 : 5

103. Anjali fires two bullets from the same place at an interval of 6 minutes but Bhagwat sitting in a car approaching the place of firing hears the second fire 5 minute 32 seconds after the first firing. What is the speed of car, if the speed of sound is 332 m/s?
(a) 56 m/s (b) 102 m/s
(c) 28 m/s (d) 32 m/s

104. A car crosses a man walking at 6 km/h. The man can see the things upto 450 m only in one direction due to fog. He sees the car which was going in the same direction for 4.5 minutes. What is the speed of the car?
(a) 9 km/h (b) 12 km/h
(c) 12.5 km/h (d) 15 km/h

105. A man takes 4 h 20 minutes in walking to a certain place and riding back. If he walk on both sides he loses 1 h. The time he would take by riding both ways is :
(a) 2 h 20 min (b) 3 h 20 min
(c) 2 h (d) 4 h 40 min

106. A train met with an accident 120 km from station *A*. It completed the remaining journey at 5/6 of its previous speed and reached 2 hours late at station *B*. Had the accident taken place 300 km further, it would have been only 1 hour late? What is the speed of the train?
(a) 100 km/h (b) 120 km/h
(c) 60 km/h (d) 50 km/h

107. For the above question what is the total distance between *A* and *B* ?
(a) 480 km (b) 520 km
(c) 600 km (d) 720 km

108. The wheel of an engine of 300 cm in circumference makes 10 revolutions in 6 seconds. What is the speed of the wheel (in km/h)?
(a) 18 (b) 20
(c) 27 (d) 36

109. A man can row downstream at 12 km/h and upstream at 8 km/h. What is the speed of man in still water?
(a) 12 km/h (b) 10 km/h
(c) 8 km/h (d) 9 km/h

110. A man can row upstream at 15 km/h and downstream at 21 km/h. The speed of water current of the river is :
(a) 8 km/h (b) 6 km/h
(c) 3 km/h (d) 5 km/h

111. A boat moves downstream at 1 km in 5 minutes and upstream at 1 km in 12 minutes. What is the speed of current?
(a) 4.5 km/h (b) 3.5 km/h
(c) 2 km/h (d) 2.5 km/h

112. A man rows downstream 60 km and upstream 36 km, taking 4 hours each time. The speed of the man is :
(a) 15 km/h (b) 16 km/h
(c) 8 km/h (d) 12 km/h

113. A man can row 5 km/h in still water. If the rate of current is 1 km/h, it takes $\frac{5}{4}$ hours to row to a place and back. How far is the place?
(a) 2 km (b) 2.5 km
(c) 3 km (d) 4 km

114. A man can swim 5 km/h in still water. If the speed of current be 3 km/h, the time taken by him to swim to a place 16 km upstream and back is :
(a) 8 h (b) 7.5 h
(c) 6.66 h (d) 10 h

115. A boat covers 48 km upstream and 72 km downstream in 12 hours, while it covers 72 km upstream and 48 km downstream in 13 hours. The speed of stream is :
(a) 2 km/h (b) 2.2 km/h
(c) 2.5 km/h (d) 4 km/h

116. A motor boat takes 2 hours to travel a distance of 9 km downstream and it takes 6 hours to travel the same distance against the current. The speed of the boat in still water and that of the current (in km/h) respectively are :
(a) 6, 5 (b) 3, 1.5
(c) 8, 5 (d) 9, 3

117. A man can row 15 km/h in still water and he finds that it takes him twice as much time to row up than as to row down the same distance in the river. The speed of the current (in km/h) is :
(a) 6 km/h (b) 6.5 km/h
(c) 4.5 km/h (d) 5 km/h

118. A motor boat takes 12 hours to go downstream and it takes 24 hours to return the same distance. What is the time taken by boat in still water?
(a) 15 h (b) 16 h
(c) 8 h (d) 20 h

119. The speed of a boat in upstream is 2/3 that of downstream. Find the ratio of speed of boat in still water and to the average speed of boat in downstream and upstream?
(a) $\frac{24}{25}$ (b) $\frac{25}{24}$
(c) $\frac{5}{12}$ (d) none of these

120. The difference between downstream speed and upstream speed is 3 km/h and the total time taken during upstream and downstream is 3 hours. What is the downstream speed, if the downstream and upstream distance are 3 km each?
(a) 2.5 km/h (b) 4.33 km/h
(c) 4 km/h (d) 3.3 km/h

Scanned by CamScanner

yoursmahboob.wordpress.com

121. A boat which sails at 10 km/h in still water starts chasing, from 10 km behind, another one which sails at 4 km/h in the upstream direction. After how long will it catchup if the stream is flowing at 2 km/h :
(a) 4 h (b) 2.5 h
(c) 2 h (d) 3.5 h

Directions for question number 122 and 123 : *A motor boat went downstream for 120 km and immediately returned. It took the boat 15 hours to complete the round trip. If the speed of the river were twice as high, the trip downstream and back would take 24 hours.*

122. What is the speed of the boat in still water?
(a) 20 km/h (b) 18 km/h
(c) 15 km/h (d) 16 km/h

123. What is the speed of the stream?
(a) 3.5 km/h (b) 4 km/h
(c) 6 km/h (d) 8 km/h

124. A boat sails 15 km of a river towards upstream in 5 hours. How long will it take to cover the same distance downstream, if the speed of current is one-fourth the speed of the boat in still water :
(a) 1.8 h (b) 3 h
(c) 4 h (d) 5 h

125. A boat takes 5 hours more while going back in upstream than in downstream. If the distance between two places is 24 km and the speed of boat in still water be 5.5 km/h. What must be the speed of boat in still water so that it can row donwstream, 24 km, in 4 hours?
(a) 1.5 km/h (b) 3.5 km/h
(c) 4.5 km/h (d) 3 km/h

126. A boat takes 7 hours to go from P to R, through a midpoint Q, but it takes 8 hours to go from P to Q and then return from Q to P. How long it would take to go from R to P?
(a) 7 h (b) 8 h
(c) 9 h (d) none of these

127. Mallah can row 40 km upstream and 55 km downstream in 13 h and 30 km upstream and 44 km downstream in 10 hours. What is the speed of Mallah in still water?
(a) 6 km/h (b) 12 km/h
(c) 3 km/h (d) 8 km/h

Directions for question number 128-129 : *In a kilometre race, A can give B a start of 20 m and also in a half kilometre race C beats A by 50 m.*

128. If A, B and C run a 2 km race, what is the difference between the distances covered by the two losers, when the winner finishes the race?
(a) 64 m (b) 36 m
(c) 32 m (d) 58 m

129. B and C run a half km race, who should give a start to the slower runner and of how many metres so that they both finish the race at the same time?
(a) C, 59 m (b) B, 34 m
(c) C, 48 m (d) B, 56 m

130. In a 1600 m race, A beats B by 80 m and C by 60 m. If they run at the same time then by what distance will C beat B in a 400 m race?
(a) $5\frac{15}{77}$ m (b) $5\frac{20}{76}$ m
(c) $15\frac{5}{77}$ m (d) none of these

131. Aman can run a distance in 190 seconds and Shakti can run the same distance in 200 seconds. If they start together, by what distance Aman can beat Shakti in 1 km race?
(a) 48 m (b) 25 m
(c) 24 m (d) 50 m

132. A runs $\frac{7}{4}$ times as fast as B. If A gives B a start of 300 m, how far must the winning post be if both A and B have to end the race at same time?
(a) 1400 m (b) 700 m
(c) 350 m (d) 210 m

133. A beats B by 100 m in a race of 1200 m and B beats C by 200 m in a race of 1600 m. Approximately by how many metres can A beat C in a race of 9600 m?
(a) 1600 m (b) 1800 m
(c) 1900 m (d) 2400 m

134. In a 1000 m race Ameesha gives a headstart of 100 m to Bipasha and beats her by 200 m. In the same race Ameesha gives a headstart of 100 m to Celina and beats her by 300 m. By how many metres would Bipasha beat Celina in a 50 m race?
(a) 6.66 m (b) 7.143 m
(c) 8 m (d) none of these

135. In a 1000 metres race Ravi gives Vinod a start of 40 m and beats him by 19 seconds. If Ravi gives a start of 30 seconds then Vinod beats Ravi by 40 m. What is the ratio of speed of Ravi to that of Vinod?
(a) 4 : 5 (b) 6 : 5
(c) 3 : 8 (d) 5 : 4

136. In a race, the man who came two places ahead of the last man finished one place ahead of the man who came three places behind the man just ahead of the one who stood second. How many men finished the race?
(a) 6 (b) 5
(c) 4 (d) 8

137. Vinay and Versha run a race with their speeds in the ratio of 5 : 3. They prefer to run on a circular track of circumference 1.5 km. What is the distance covered by Vinay when he passes Versha for the seventh time?
(a) 25.25 km (b) 26.25 km
(c) 132 m (d) none of these

138. A gives both B and C a start of 60 m in a 1500 m race. However, while B finishes with him, C is 15 m behind them when A and B cross the finishing line. How much start can B give C for the 1500 m race course?
(a) $7\frac{6}{23}$ m (b) $15\frac{5}{8}$ m
(c) $7\frac{11}{16}$ m (d) $5\frac{5}{24}$ m

139. In a 600 m race Prabhat has a start of 200 m and the ratio of speeds of Prabhat and Nishith is 4 : 5, then the distance by which Prabhat wins by :
(a) 100 m (b) 80 m
(c) 120 m (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

140. In the game of billiards, *A* can give *B*, 20 points in 80 and *B* can give *C*, 16 points in 80. How many points can *A* give *C* in a game of 200?
(a) 64 (b) 72
(c) 80 (d) none of these

141. In a day how many times the minute and hour-hands coincide (or overlap or come together)?
(a) 12 (b) 20
(c) 22 (d) 24

142. In a day how many times the minute-hand and hour-hand make right angle between them?
(a) 12 (b) 20
(c) 22 (d) 44

143. In a day how many times the minute-hand and hour-hand are opposite to each other?
(a) 12 (b) 24
(c) 11 (d) 22

144. The relative speed of minute-hand with respect to hour-hand is :
(a) $\left(5\frac{1}{2}\right)^\circ$ per minute
(b) $\left(\frac{11}{12}\right)$ minute per minute
(c) 6° per minute
(d) both (a) and (b)

145. When do the hands of a clock coincide between 5 and 6?
(a) 5 : 30 (b) 5 : 27 : 16
(c) 5 : 32 : 16 (d) 5 : 28 : 56

146. What is the angle between hour-hand and minute-hand at 2 : 25 pm?
(a) 77.5° (b) 68°
(c) 67.5° (d) none of these

147. When do the two hands of a clock of just after 3 pm make 30° angle between them?
(a) 3 : 15 : 00 (b) 3 : 10 : 54
(c) 3 : 01 : 59 (d) none of these

148. At what time are the hands of clock together between 7 pm and 8 pm?
(a) 7 : 45 : 54 (b) 7 : 36 : 27
(c) 7 : 37 : 49 (d) 7 : 38 : 11

149. What is the angle between the hands of a clock when the time is 15 minutes past 6?
(a) 97.5° (b) 87.5°
(c) 77° (d) none of these

150. What are the possible times when a clock shows 35° angle between two hands between 3 pm and 4 pm?
(a) 20 min 25 sec (b) 25 min 20 sec
(c) 22 min 43 sec (d) none of these

LEVEL 2

Directions for question number 1–4 : Aishwarya is going to cover a distance of 360 km from Ambala to Khandala. The first one-third of the distance she covers on a cycle. The second one-third she covers by an auto-rickshaw and the remaining distance she travels by car. The average speed of the journey by a car is 5 times the average speed by cycle and 20 km/h more than the average speed by auto-rickshaw, but she took 1 hour more by auto-rickshaw than by car.

1. What is the average speed of the whole journey?
(a) 15 km/h (b) 24 km/h
(c) 20 km/h (d) none of these

2. What is the time taken in the whole journey?
(a) 10 h (b) 12 h
(c) 15 h (d) none of these

3. What is the distance covered by her in last five hours of her journey?
(a) 250 km (b) 240 km
(c) 200 km (d) can't be determined

4. Instead of travelling the first one-third by cycle if she travels by same auto-rickshaw with the same average speed, then what is the percentage decrease/increase in time taken during the entire journey?
(a) 46.66% (b) 33.33%
(c) 50% (d) 25%

5. Bipasha and Mallika leave towns Kolkata and Ambala at 6 am and travel towards Ambala and Kolkata respectively. Speed of Bipasha is 60 km/h and speed of Mallika is 120 km/h. Rani leaves Kolkata for Ambala sometime later and travels at a speed of 90 km/h. If the distance between Kolkata and Ambala is 1080 km and all three meet at the same point on the way, at same time, then at what time did Rani leave Kolkata?
(a) 7 am (b) 8 am
(c) 7:30 am (d) 10 am

6. A passenger sitting in a train of length *l* m, which is running with speed of 60 km/h passing through two bridges, notices that he crosses the first bridge and the second bridge in time intervals which are in the ratio of 7 : 4 respectively. If the length of first bridge be 280 m, then the length of second bridge is :
(a) 490 m (b) 220 m
(c) 160 m (d) can't be determined

7. Pathik and Rahi started from two places Andheri and Bhavnagar towards Bhavnagar and Andheri respectively at 8 : 20 am. The speeds of Pathik and Rahi are in the ratio of 4 : 5. They meet at Chandni Chowk, somewhere between Andheri and Bhavnagar, spent some-time together enjoyed coffee and burger and then both started towards their destination at 9 : 27 am. If Pathik reaches Bhavnagar at 10 : 32 am, how much time did they spend together?
(a) 8 min (b) 12 min
(c) 15 min (d) can't be determined

8. A train with 120 wagons crosses Arjun who is going in the same direction, in 36 seconds. It travels for half an hour from the time it starts overtaking the Arjun (he is riding on the horse) before it starts overtaking Srikrishna (who is also riding on his horse) coming from the opposite direction in 24 seconds. In how much time (in seconds) after the train has crossed the Srikrishna do the Arjun meets to Srikrishna?
(a) 3560 sec (b) 3600 sec
(c) 3576 sec (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

9. Kareena and Shahid start from Kurla and Worli towards Worli and Kurla respectively, at the same time. After they meet at Shantakruz on the way from Kurla to Worli, Kareena reduces her speed by 33.33% and returns back to Kurla and Shahid increases his speed by 33.33% and returns back to Worli. If Kareena takes 2 hours for the entire journey, what is the time taken by Shahid for the entire journey?
(a) 96 min (b) 84 min
(c) 168 min (d) can't be determined

10. Due to the technical snag in the signal system two trains start approaching each other on the same rail track from two different stations, 240 km away from each other. When the train starts a bird also starts moving to and fro between the two trains at 60 km/h touching each time each train. The bird is initially sitting on the top of the engine of one of the trains and it moves so till these trains collide. If these trains collide one and a half hour after the start, then how many kilometres bird travells till the time of collision of trains?
(a) 90 km (b) 130 km
(c) 120 km (d) none of these

11. Einstein walks on an escalator at a rate of 5 steps per second and reaches the other end in 10 seconds. While coming back, walking at the same speed he reaches the starting point in 40 seconds. What is the number of steps on the escalator?
(a) 40 (b) 60
(c) 120 (d) 80

12. A girl while walking diametrically across a semicircular playground, takes 3 minutes less than if she had kept walking round the circular path from A to B. If she walks 60 metres a minute, what is the diameter of the play ground :
(a) 60 m (b) 48 m
(c) 84 m (d) 315 m

13. Two trains start simultaneously from two stations Howrah and Bandra, respectively towards each other on the same track. The distance between the two stations is 560 km and the speed of trains are 30 and 40 km/h.
Simultaneously with the trains, a sparrow sitting on the top of one of the train starts towards the other and reverses its direction on reaching the other train and so on. If the speed of sparrow is 80 km/h then the distance that the sparrow flies before being crushed between the train is :
(a) 70 km (b) 560 km
(c) 640 km (d) 650 km

14. A surveillance plane is moving between two fixed places Pukhwara and Kargil at 120 km/h. The distance between two places is 600 km. After 18 hour what will be the distance between the Kargil and its position if it is starts moving from Pukhwara?
(a) 360 km (b) 300 km
(c) 240 km (d) none of these

15. The speed of a car during the second hour of its journey is thrice that in the first hour. Also its third hours speed is the average speed of the first two hours. Had the car travelled at the second hours speed during all the first three hours, then it would have travelled 150 km more. Find the percentage reduction in time in the second case for the first three hours :
(a) $33\frac{1}{3}\%$ (b) 40%
(c) 25% (d) 50%

16. There are three runners Tom, Dick and Harry with their respective speeds of 10 km/h, 20 km/h and 30 km/h. They are initially at P and they have to run between the two points P and Q which are 10 km apart from each other. They start their race at 6 am and end at 6 pm on the same day. If they run between P and Q without any break, then how many times they will be together either at P and Q during the given time period?
(a) 5 (b) 7
(c) 4 (d) 12

Directions for question number 17 and 18 : Arjun and Srikrishna go by chariot from Mathura to Kurukshetra which is on the way to Hastinapur. Abhimanyu goes from Hastinapur to Kurukshetra. The distance between Mathura to Hastinapur is 700 km and the distance between Hastinapur and Kurukshetra is 300 km. Speed of Arjun and Srikrishna's chariot is 25 km/h and speed of Abhimanyu is 10 km/h. All the three persons start their journey at 10 am. After travelling some miles Srikrishna sees Duryodhan going (by riding on his horse) at 20 km/h to Kurukshetra. Arjun and Srikrishna go ahead meet Abhimanyu and pick him up. Then they return immediately to Kurukshetra and thus all the four reach at the same time.

17. What is the total distance travelled by Arjun?
(a) 400 (b) 500
(c) 600 (d) can't be determined

18. What is the total time taken to reach Kurukshetra?
(a) 10 h (b) 15 h
(c) 18 h (d) 24 h

19. Priyanka, Akshay and Salman started out on a journey to watch the newly released movie "Mujhse Shaadi Karogi", which was being shown at wave cine-multiplex. The multiplex was 120 km away from their starting point of journey. Priyanka and Salman went by car at the speed of 50 km/h, while Akshay travelled by Tonga (horse cart) at 10 km/h. After a certain distance Salman got off and travelled the rest distance by another Tonga at 10 km/h, while Priyanka went back for Akshay and reached the destination at the same time that Salman arrived. The number of hours required for the trip was :
(a) 4 h (b) 5 h
(c) 4.8 h (d) can't be determined

Directions for question number 20 and 21 : Ajai and Kajol start towards each other at the same time from Barabanki and Fatehpur for their destinations Fatehpur and Barabanki respectively which are 300 km apart. They meet each other 120 km away from Barabanki.

20. Shahrukh starts from Barabanki to Fatehpur, 1 hour after Ajai starts. Shahrukh meets Kajol 1.5 hours after Shahrukh starts. If the speed of Shahrukh is atleast 20 km/h faster than the speed of Kajol.
Which of the following statements is true?

Scanned by CamScanner

yourshabbab.wordpress.com

(a) The minimum possible speed of Ajai is 45 km/h
(b) The maximum possible speed of Ajai is 45 km/h
(c) The minimum possible speed of Kajol is 60 km/h
(d) The maximum possible speed of Kajol is 60 km/h

21. What is the minimum speed of Shahrukh to overtake Ajai, before he meets Kajol? (Use the data from previous question, if necessary)
(a) 30 (b) 40
(c) 60 (d) none of these

Directions for question number 22-24 : *Raghupati goes at a speed of 60 km/h. Raghav goes at a speed of 36 km/h. Raja Ram can go from Azamgarh to Barelley in 2 hours. The distance between Azamgarh to Barelley is equal to the distance between Azamgarh to Chandoli. Raghav takes the same time travelling from Barelley to Azamgarh as from Barelley to Chandoli at his regular speed which is twice the speed of Raja Ram.*

22. What is the distance between Azamgarh and Chandoli?
(a) 60 km (b) 27 km
(c) 36 km (d) 18 km

23. How much time will Raghupati take to complete a round trip of the three cities?
(a) 1 h 12 min (b) 1 h 48 min
(c) 1 h 30 min (d) 1 h 36 min

24. If Raghupati and Raja Ram travel towards each other from Barelley and Chandoli respectively, how far from Barelley will they meet each other?
(a) $\frac{60}{13}$ (b) $27\frac{9}{13}$ km
(c) $37\frac{9}{13}$ (d) $\frac{360}{9}$

Directions for question number 25-26 : *Mohan, Namit and Pranav travel from Shantipur to Hulchulpur. They have a two seeter bike which can be driven by only Mohan. It is known that due to very stringent traffic rules only two persons can ride at a time. Hulchulpur is 180 km away from Shantipur. All of them can walk at 6 km/h, but reach to Hulchulpur simultaneously also they started their journey simultaneously.*

25. If the speed of the bike is 36 km/h, then what is the total distance that the bike travels?
(a) 400 km (b) 380 km
(c) 200 km (d) 320 km

26. If the speed of the bike is 42 km/h, then what is the shortest possible time in which all three of them can complete the journey?
(a) $7\frac{1}{3}$ h (b) $9\frac{4}{7}$ h
(c) $9\frac{3}{7}$ h (d) can't be determined

27. While walking down on the pavements of New York city. I notice that every 20 minute there is a city bus coming in the opposite direction and every 30 minute there is a city bus overtaking me from behind. What is the time gap between one city bus passing a stationary point known as Local Bus Stop beside the route and the immediately next city bus in the same direction passing the same stationary point?
(a) 27 min (b) 24 min
(c) 25 min (d) can't determined

28. Abhinav and Brijesh start from Allahabad and Barabanki respectively with uniform velocities. Abhinav is headed towards Barabanki and Brijesh towards Allahabad and both cities are 600 km apart. Abhinav rests whenever Brijesh is on the move and Brijesh rest whenever Abhinav is on the move. Abhinav's speed is 25 km/h and Brijesh's speed is 30 km/h. If Abhinav starts first and reaches Barabanki in 36 hours, then find the least time that Brijesh would take to reach his destination after Abhinav makes a start :
(a) 20 h (b) 36 h
(c) 44 h (d) none of these

29. A man can cross a downstream river by steamer in 40 minutes and same by boat in 1 hour. If the time of crossing the river in upstream direction by steamer is 50% more than downstream time by the steamer and the time required by boat to cross the same river by boat in upstream is 50% more than the time required in downstream by boat. What is the time taken for the man to cross the river downstream by steamer and then return to same place by boat half the way and by steamer the rest of the way?
(a) 85 min (b) 115 min
(c) 120 min (d) 125 min

Directions for question number 30 and 31 : *Awadh express and Bokaro express start simultaneously from Lucknow and Jamshedpur towards each other and continuously shuttle between these two places. Every time these trains meet each other, they turn back after exchanging their respective speeds, the initial ratio of their speeds is 2 : 1.*

30. What is the number of distinct places at which they will meet?
(a) 1 (b) 2
(c) 5 (d) none of these

31. Let these two trains first time meet at Patna, then what is the ratio of distances covered by Awadh express and Bokaro express till they meet for the third time at the same place Patna :
(a) 1 : 1 (b) 14 : 13
(c) 10 : 11 (d) none of these

32. Mahindra starts a journey for his office, which is in the north east of his home. An hour after starting meets with a minor accident. He takes one hour in resuming his journey. After that he proceeds at 5/6th of his former speed and arrives at the office 1 hour 36 minutes late than the scheduled time. Had the accident occurred 80 kms further from the actual place of accident, he would have arrived 1 hour 20 minutes beyond the scheduled time. What is the distance between his office and his home?
(a) 180 km (b) 240 km
(c) 250 km (d) 300 km

33. A soldier fired two bullets at an interval of 335 seconds moving at a uniform speed v_1. A terrorist who was running ahead of the soldier in the same direction, hears the two shots at an interval of 330 seconds? If the speed of sound is 1188 km/h, then who is the faster and by how much?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) Soldier, 22 km/h (b) Terrorist, 25 km/h
(c) Soldier, 18 km/h (d) Terrorist, 20 km/h

34. A hunter fired two shots from the branch of a tree at an interval of 76 seconds. A tiger separating too fast hears the two shots at an interval of 83 seconds. If the velocity of the sound is 1195.2 km/h, then find the speed of tiger?
(a) 112.8 km/h (b) 100.8 km/h
(c) 80.16 km/h (d) none of these

35. A man goes to the fair in Funcity with his son and faithful dog. Unfortunately man misses his son which he realises 20 minutes later. The son comes back towards his home at the speed of 20 m/min and man follows him at 40 m/min. The dog runs to the son (child) and comes back to the man (father) to show him the direction of his son. It keeps moving to and fro at 60 m/min between son and father, till the man meets the son. What is the distance travelled by the dog in the direction of the son?
(a) 800 m (b) 1675 m
(c) 848 m (d) 1000 m

36. Amarnath express left Amritsar for Gorakhpur. Two hours later Gorakhnath express left from Amritsar to Gorakhpur. Both trains reached Gorakhpur simultaneously. If Amarnath express had started from Amritsar and Gorakhnath express had started from Gorakhpur at the same time and travelled towards each other they would meet in 1 h 20 min. Find the time taken by Amarnath express to travel from Amritsar to Gorakhpur (in hours) :
(a) 2 (b) 4
(c) 5 (d) 6

37. Akbar and Birbal setout at the same time to walk towards eachother respectively from Agra and Banaras 144 km apart. Akbar walks at the constant speed of 8 km/h, while Birbal walks 4 km in the first hour, 5 km in the second hour, 6 km in the third hour and so on. Then the Akbar and Birbal will meet :
(a) in 6 h
(b) in 8 h
(c) midway between Agra and Banaras
(d) 80 km away from Banaras

38. A tiger is 50 of its own leaps behind a deer. The tiger takes 5 leaps per minute to the deer's 4. If the tiger and the deer cover 8 m and 5 m per leap respectively, what distance will the tiger have to run before it catches the deer?
(a) 600 m (b) 700 m
(c) 800 m (d) 1000 m

39. Soniya and Priyanka started from Amethi and Bellari for Bellari and Amethi, which are 645 km apart. They meet after 15 hours. After their meeting, Sonia increased her speed by 3 km/h and Priyanka reduced her speed by 3 km/h, they arrived at Bellari and Amethi respectively at the same time. What is their initial speeds?
(a) 24 km/h and 30 km/h (b) 25 km/h and 18 km/h
(c) 18 km/h and 21 km/h (d) 20 km/h and 23 km/h

40. Den Bosch and Eastbourne are two famous cities 300 km apart. Maradona starts from Den Bosch at 8 : 24 am. An hour later Pele starts from Den Bosch. After travelling for 1 hour, Pele reaches Nottingham that Maradona had passed 40 minutes earlier. Nottingham falls on the way from Den Bosch to Eastbourne. If Pele and Maradona just reaches Eastbourne at the same time, what are the speeds of the Maradona and Pele respectively?
(a) 100 km/h, 125 km/h (b) 60 km/h, 80 km/h
(c) 60 km/h, 75 km/h (d) 75 km/h, 100 km/h

41. A thief sees a jeep at a distance of 250 m, coming towards him at 36 km/h. Thief takes 5 seconds to realise that there is nothing but the police is approaching him by the jeep and start running away from police at 54 km/h. But police realise after 10 seconds, when the thief starts running away, that he is actually a thief and gives chase at 72 km/h. How long after thief saw police did police catchup with him and what is the distance police had to travel to do so?
(a) 50 s, 1000 m (b) 65 s, 1150 m
(c) 65 s, 1300 m (d) 45 s, 1050 m

42. Inspired by the 'Golden quadrilateral project' UP Government recently accomplished a diamond triangular project. Under this project the State Government laid down 6 lane roads connecting three cities Ayodhya, Banaras and Chitrakoot, which are equally separated from each other *i. e.*, in terms of geometry they form an equilateral triangle. Angad and Bajrang start simultaneously from Ayodhya and Banaras respectively, towards Chitrakoot. When Angad covers 100 kms, Bajrang covers such a distance that the distance betweeen Angad and Bajrang makes 90° angle with the road joining Banaras and Chitrakoot. When Bajrang reaches Chitrakoot, Angad is still 150 km away from Chitrakoot. What is the distance between Ayodhya and Banaras?
(a) 250 km (b) 450 km
(c) 300 km (d) none of these

43. Two trains Ajanta express and Barouni express simultaneously started on two parallet tracks from Meerut to Nagpur, which are 390 km apart. The ratio of the speed of Ajanta express and Barouni express is 6 : 7. After how long (in kms) travelling, Barouni express exchanges the speed with Ajanta express so that both the trains reach at their destination simultaneously :
(a) 150 km (b) 190 km
(c) 210 km (d) can't be determined

44. In a circus there was a leopard and a tiger walking in the two different rings of same radii. There I observed that when leopard moved 3 steps, tiger moved 5 steps in the same time, but the distance traversed by leopard in 5 steps is equal to the distance traversed by tiger in 4 steps. What is the number of rounds that a leopard made when tiger completed 100 rounds?
(a) 120 (b) 48
(c) 75 (d) none of these

✍ ***Directions for question number 45-48 :*** *In the following figure the route is shown which is followed by Professor Jai and Professor Jaya, who are visting faculty at IIM-A and IIM-B respectively. A, B denote IIM-A and IIM-B respectively and C denotes the residence of Prof. Jai and Prof. Jaya. They leave home for classes at the same time and their driving speeds are* $\frac{500}{13}$ *km/h and* $\frac{1200}{13}$ *km/h respectively. Also they finish the classes at the same time to reach home.*

Scanned by CamScanner

yoursmahboob.wordpress.com



The path adopted by Jai and Jaya is CADC and CBDC respectively. Prof. Jai and Prof. Jaya are husband and wife respectively.

45. If both of them start and finish the classes at the same time, then who returned home earlier than other, if no one of them halts for anywhere in the route and they just leave the institution as soon as they finish the lectures?
(a) Prof. Jai
(b) Prof. Jaya
(c) Return at the same time
(d) Can't be determined

46. In the shown figure *N* and *D* denotes Noida and Delhi respectively, who returned home late and by how much time, if Jaya turned from Noida instead of Delhi :
(a) Jai, 9 h 10 min (b) Jaya, 9 h 50 min
(c) Jai, 2 h 55 min (d) Jai, 16 h 10 min

47. In the above question how many per cent time Jaya saved in going via Noida of the total time taken previously :
(a) 10% (b) 25%
(c) 50% (d) 17%

48. If Mrs. Jaya wants to watch the premier show of a movie at Wave Cinema in Noida while returning from institute through BNC. When will she return home given that she spends total time 3 hours at wave cinema?
(a) at the same time as normal
(b) 5 min late than her husband
(c) at the same time when her husband returns
(d) can't be determined

49. Preetam and Devi start running a race on the given track as shown in figure.



Where *AC* and *BC* are mutually perpendicular and *CD* is the median of triangular paths *ABC*. *BC* is 100 km longer than that of *AC*, again *CD* is 250 km. The speeds of Preetam and Devi are 30 km/h and 40 km/h, initially and their respective paths of running are *CADC* and *CBDC*. After how much time they reverse their speeds so that they return *C* at the same time?
(a) $\frac{50}{7}$ h (b) $\frac{120}{7}$ h
(c) $\frac{80}{11}$ h (d) none of these

Directions for question number [illegible] markets $M_1, M_2, M_3, \ldots$ etc of Vyapar [illegible] are circular paths $P_1, P_2, P_3, \ldots$ etc. All [illegible] are concentric at centre 'O' and their distances are 1 km, 2 km, 3 km, ... etc from the centre 'O' respectively. At the centre 'O' there is a "Khoob Khao" tiffin agency which supplies the tiffins to all the markets $M_1, M_2, M_3, \ldots$ etc. A tiffin carrier starts from 'O' goes directly east of the shop and then on reaching the circular path it moved 1 km in counter clock direction on it. After completing its 1 km distance on P_1 the carrier moves to P_2 in the radial direction. Then it goes 2 km on P_2. Similarly 3 km on P_3 and 4 km on P_4 etc in counter clock direction moving radially from P_2 to P_3 and P_3 to P_4 etc and motion of the carrier continued in this manner till it reaches exactly in the east direction.

50. After reaching east of the shop it can't move on further than the given distance on the current path. For how many markets can it supply its tiffins directly?
(a) 4 (b) 5
(c) 7 (d) can't be determined

51. The total distance covered by the carriers in providing the tiffins from centre 'O' to the last point in one way only is :
(a) 30 km (b) 28 km
(c) 35 km (d) none of these

52. The ratio of distances covered on the circular path P_2 to that on the last path, where the carrier reaches directly eastward of its shop is :
(a) 1 : 1 (b) 2 : 7
(c) 2 : π (d) none of these

Directions for question number 53-57 : A train enters into a tunnel AB at A and exits at B. A jackal is sitting at O in another by passing tunnel AOB, which is connected to AB at A and B, where OA is perpendicular to OB. A cat is sitting at P inside the tunnel AB making the shortest possible distance between O and P, such that AO : PB = 30 : 32. When a train before entering into the tunnel AB makes a whistle (or siren) somewhere before A, the jackal and cat run towards A, they meet with accident (with the train) at the entrance A. Further if the cat moves towards B instead of A it again meets with accident at the exit of the tunnel by the same train coming from the same direction.

53. What is the ratio of speeds of jackal and cat?
(a) 4 : 3 (b) 5 : 3
(c) 1 : 1 (d) can't be determined

54. The ratio of speeds of jackal is to train is :
(a) 5 : 1 (b) 3 : 5
(c) 1 : 5 (d) can't be determined

55. If jackal moves towards *OPA*, it will meet with train at M_1 then AM_1 is :
(a) 20 km (b) 16 km
(c) 10 km (d) can't be determined

56. If jackal moves towards *OPB* and cat moves towards *POA* who will not meet with accident with the train?
(a) Jackal (b) Cat
(c) Both (a) and (b) (d) Can't be determined

57. The ratio of time taken by cat and jackal in moving *OAPO* and *PBOP* respectively given that they do not meet with accident :
(a) 1 : 1 (b) 3 : 4
(c) 5 : 4 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

58. A candle of 6 cm long burns at the rate of 5 cm in 5 h and another candle of 8 cm long burns at the rate of 6 cm in 4 h. What is the time required by each candle to remain of equal lengths after burning for some hours, when they start to burn simultaneously with uniform rate of burning?
(a) 1 h (b) 1.5 h
(c) 2 h (d) none of these

59. Two boats start at the same instant to cross a river W metre wide. The faster boat reaches the other bank and returns back immediately. What are the distances travelled by them when they meet, where the speeds of these boats are b_1 & b_2?
(a) $\frac{2W}{(b_1 + b_2)}, \frac{2W}{(b_1 - b_2)}$
(b) $\frac{2W}{(b_1 + b_2)} b_1$ and $\frac{2W}{(b_1 + b_2)} b_2$
(c) $\frac{W}{(b_1 + b_2)} b_1, \frac{W}{(b_1 + b_2)} b_2$
(d) data insufficient

60. Mariya was travelling in her boat when the wind blew her hat off and the hat started floating back downstream. The boat continued to travel upstream for twelve more minutes before Mariya realized that her hat had fallen off and turned back downstream. She caught up with that as soon as it reached the starting point. Find the speed of river if Mariya's hat flew off exactly 3 km from where she started :
(a) 5 km/h (b) 6 km/h
(c) 7.5 km/h (d) can't be determined

61. Akbar, Birbal and Chanakya run around a circular track of length 500 m. Akbar and Birbal run with the speeds of 15 m/s and 20 m/s in the same direction respectively and Chanakya being very intelligent run in the opposite direction with a speed of 25 m/s. If all three of them start at the same time, then :
(a) Akbar meets Chanakya more frequently than Birbal does
(b) Akbar and Chanakya meets as frequently as Birbal and Chanakya
(c) Akbar meets Birbal least frequently
(d) Nothing can be concluded

62. Arun and Barun run with the speeds of 30 m/s and 20 m/s around a circular track of 600 m. They participate in a 3000 m race. What is the distance covered by Arun when he passes Barun for the 5th time?
(a) 2200 m (b) 2250 m
(c) 2850 m (d) none of these

63. Akkal and Bakkal are running on a circular track of radius 175 metres. Akkal can complete a round in 100 seconds and the speed of Bakkal is twice the speed of Akkal. They started simultaneously towards each other from two points 350 metres diametrically opposite on the circular path. If they first meet at a point they called it love point, which is between the two points P and Q from where they have started their race, after how much time from the start do they meet at love point for the third time?
(a) $218\frac{2}{5}$ s (b) $216\frac{2}{3}$ s
(c) 221 s (d) none of these

64. Arti and Barkha start swimming towards each other from the deep end and shallow end respectively of a swimming pool in Funcity. They start their swimming simultaneously in the length of 300 m pool. The ratio of their speeds is 1 : 2 respectively. Each swimmer rests for 6 seconds once she reaches the other end and starts swimming back. Where will they meet for the second time in the still water of swimming pool?
(a) 30 m from the shallow end
(b) at the shallow end
(c) at the deepend
(d) can't be determined

65. A and B runs around a circular track. A beats B by one round or 10 minutes. In this race, they had completed 4 rounds. If the race was only of one round, find the A's time over the course :
(a) 8 min (b) 7.5 min
(c) 12.5 min (d) 12 min .

66. A, B and C participated in a race. A covers the same distance in 49 steps, as B covers in 50 steps and C in 51 steps. A takes 10 steps in the same time as B takes 9 steps and C takes 8 steps. Who is the winner of the race?
(a) A (b) B
(c) C (d) can't be determined

67. Shambhu drives his car very fast at 360 m/s. Moving ahead for some hours he finds some problem in headlights of the car. So he takes 20 seconds in changing the bulb of the headlight by stopping the car. Mean while he notices that another car which was 400 m back is now 200 m ahead of his car. What is the speed of this car?
(a) 100 km/h (b) 92 km/h
(c) 108 km/h (d) 300 km/h

68. Two persons start from the opposite ends of a 90 km straight track and run to and fro between the two ends. The speed of first person is 30 m/s and the speed of other is 125/6 m/s. They continue their motion for 10 hours. How many times they pass each other?
(a) 10 (b) 9
(c) 12 (d) none of these

69. At what time after 3 : 10 am, the acute angle made by the minute and hour-hand is double to that of at 3 : 10 am, for the first time?
(a) 4 h 43 min (b) 3 h 48 min
(c) $3\text{ h }\frac{320}{11}$ min (d) none of these

70. If the two incorrect watches are set at 12 : 00 noon at correct time, when will both the watches show the correct time for the first time given that the first watch gains 1 min in 1 hour and second watch loses 4 min in 2 hours :
(a) 6 pm, 25 days later
(b) 12 : 00 noon, 30 days later
(c) 12 noon, 15 days later
(d) 6 am 45 days later

71. Rajeev and Sanjeev are too close friends Rajeev's watch gains 1 minute in an hour and Sanjeev's watch loses 2 minutes in an hour. Once they set both the watches at 12 : 00 noon, with my correct watch. When will the two incorrect watches of Rajeev and Sanjeev show the same time together?
(a) 8 days later (b) 10 days later
(c) 6 days later (d) can't be determined

72. At a railway station a 24 hour watch loses 3 minutes in 4 hours. If it is set correctly on Sunday noon when will the watch show the correct time?
(a) 6 pm after 40 days (b) 12 noon after 75 days
(c) 12 pm after 100 days (d) 12 noon after 80 days

Scanned by CamScanner

yoursmahboob.wordpress.com

73. A swiss watch is being shown in a museum which has a very peculiar property. It gains as much in the day as it loses during night between 8 pm to 8 am. In a week how many times will the clock show the correct time?
(a) 6 times (b) 14 times
(c) 7 times (d) 8 times

74. A wrist watch which is running 12 minutes late on a Sunday noon is 16 minutes ahead of the correct time at 12 noon on the next Sunday. When is the clock 8 minutes ahead of time?
(a) Thursday 10 am (b) Friday noon
(c) Friday 8 pm (d) Tuesday noon

75. A clock loses 2 minutes in an hour and another clock gains 2 minutes in every 2 hours. Both these clocks are set correctly at a certain time on Sunday and both the clocks stop simultaneously on the next day with the time shown being 9 am and 10 : 06 am. What is the correct time at which they stopped?
(a) 9 : 54 am (b) 9 : 44 pm
(c) 9 : 46 am (d) 9 : 44 am

76. David sets his watch at 6 : 10 am on Sunday, which gains 12 minutes in a day. On Wednesday if this watch is showing 2 : 50 pm. What is the correct time?
(a) 1 : 50 pm (b) 2 : 10 pm
(c) 2 : 30 pm (d) 3 : 30 pm

77. Ramu purchased a second hand Swiss watch which is very costly. In this watch the minute-hand and hour hand coincide after every $65\frac{3}{11}$ minutes. How much time does the watch lose or gain per day?
(a) 4 min (b) 5 min
(c) 4 min, 20 sec (d) none of these

78. My watch was 8 minutes behind at 8 pm on Sunday but within a week at 8 pm on Wednesday it was 7 minutes ahead of time. During this period at which time this watch has shown the correct time :
(a) Tuesday 10 : 24 am
(b) Wednesday 9 : 16 pm
(c) It cannot show the correct time during this period
(d) None of the above

79. Out of the following four choices which does not show the coinciding of the hour hand and minute-hand :
(a) 3 : 16 : 2 (b) 6 : 32 : 43
(c) 9 : 59 : 05 (d) 5 : 27 : 16

80. Kumbhakarna starts sleeping between 1 am and 2 am and he wakes up when his watch shows such a time that the two hands (*i.e.*, hour-hand and minute-hand) interchange the respective places. He wakes up between 2 am and 3 am on the same night. How long does he sleep?
(a) $55\frac{5}{13}$ min (b) $110\frac{10}{13}$ min
(c) $54\frac{6}{13}$ min (d) none of these

SPEED TEST (TSD)

Directions for question number 1 to 3: Arun took part in a triathlon, an athletic event. He had to swim, run and bicycle to 10 km, 24 km and 30 km, respectively and return the same way. Arun's average speed for the triathelon is 4 km/h. He took a total of 4 min for swimming and 20 min for bicycling in the triathelon.

1. His speed of running is:
(a) 5 km/min (b) 6 km/min
(c) 7.5 km/min (d) $\frac{8}{3}$ km/min

2. He finishes race in:
(a) 16 min (b) 23 min
(c) 32 min (d) 35 min

3. How much time he took while returning for the bicycle if the time taken for the return of each phase (i. e., each event) is 50% greater than that of taken initially:
(a) 12 min (b) 11 min
(c) $11\frac{1}{9}$ min (d) none of these

Directions for question number 4 to 5: A, B and C start running a race from the same point P in the same direction. A runs around a path which is an equilateral triangle PQX and B runs around a square path PQYZ and C runs on the regular hexagonal path PQRSTU. Where the one side PQ of each path is common.

4. If all of them complete one equal round at the same time then which of the following is true?
(a) Speed of *C* is twice that of *B*
(b) Speed of *A* is half that of *C*
(c) Speed of *B* is 50% more than that of *A*
(d) none of the above

5. If each of them run at a same constant speed, what is the maximum number of rounds anyone of them would have completed when they meet for the first time?
(a) 1 (b) 2 (c) 3 (d) 4

Directions for the question number 6 to 9: City X and City Y are connected to a straight road. A and B start moving simultaneously towards each other. After travelling some distance, B takes a 60° turn to his left. Two hours later after B turns, A takes a 60° turn to his right. A travels 60 km after turning, before he meets B. A and B meet 10 hours after they start their journey. A and B together travel 200 km before turning and they arrive at the meeting point simultaneously.

6. How many hours after turning does *A* meet *B* ?
(a) 1 (b) 3 (c) 4 (d) 5

7. What distance does *A* travel before turning 60 degree to his right?
(a) 140 km (b) 150 km
(c) 160 km (d) 170 km

8. If *A* and *B* had not turned, after how many hours would they have met?
(a) $7\frac{1}{8}$ h (b) $9\frac{1}{8}$ h (c) $6\frac{1}{8}$ h (d) $8\frac{1}{8}$ h

9. What is *B*'s speed?
(a) 10 km/h (b) 12.5 km/h
(c) 12 km/h (d) 15 km/h

10. Chetak and Ashwa, two horses, start galloping from Patna to Ranchi which are 80 km apart. The speed of Chetak is 160 km/h and that of Ashwa is 150 km/h. They start galloping simultaneously, from Patna to Ranchi. Chetak reached to Ranchi and returned to Patna but Ashwa returned from Jamshedpur (which is somewhere between Patna and Ranchi) to Patna at the same time. What is the ratio of distances between Patna and Jamshedpur and Jamshedpur and Ranchi?
(a) 15 : 1 (b) 3 : 25
(c) 15 : 2 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-9.1

1 (a)	2. (c)	3. (c)							

LEVEL-1

1 (a)	2. (b)	3. (b)	4. (c)	5. (a)	6. (c)	7. (c)	8. (b)	9. (a)	10. (c)
11. (c)	12. (d)	13. (a)	14. (d)	15. (b)	16. (c)	17. (b)	18. (c)	19. (b)	20. (c)
21. (b)	22. (d)	23. (a)	24. (b)	25. (c)	26. (d)	27. (d)	28. (d)	29. (b)	30. (c)
31. (d)	32. (a)	33. (b)	34. (c)	35. (d)	36. (a)	37. (b)	38. (a)	39. (b)	40. (c)
41. (a)	42. (b)	43. (b)	44. (c)	45. (c)	46. (c)	47. (c)	48. (b)	49. (a)	50. (b)
51. (b)	52. (a)	53. (b)	54. (c)	55. (c)	56. (c)	57. (a)	58. (b)	59. (d)	60. (b)
61. (a)	62. (c)	63. (c)	64. (c)	65. (b)	66. (d)	67. (d)	68. (c)	69. (d)	70. (a)
71. (a)	72. (a)	73. (b)	74. (c)	75. (b)	76. (c)	77. (b)	78. (c)	79. (a)	80. (c)
81. (d)	82. (b)	83. (c)	84. (c)	85. (b)	86. (d)	87. (b)	88. (b)	89. (d)	90. (c)
91. (c)	92. (b)	93. (d)	94. (d)	95. (c)	96. (b)	97. (a)	98. (b)	99. (b)	100. (a)
101. (d)	102. (a)	103. (c)	104. (b)	105. (b)	106. (c)	107. (d)	108. (a)	109. (b)	110. (c)
111. (b)	112. (d)	113. (c)	114. (d)	115. (a)	116. (b)	117. (d)	118. (b)	119. (b)	120. (b)
121. (b)	122. (b)	123. (c)	124. (b)	125. (b)	126. (c)	127. (d)	128. (b)	129. (a)	130. (a)
131. (d)	132. (b)	133. (c)	134. (b)	135. (b)	136. (b)	137. (b)	138. (b)	139. (a)	140. (c)
141. (c)	142. (d)	143. (d)	144. (d)	145. (b)	146. (a)	147. (b)	148. (d)	149. (a)	150. (c)

LEVEL-2

1 (b)	2. (c)	3. (b)	4. (a)	5. (b)	6. (c)	7. (c)	8. (c)	9. (b)	10. (a)
11. (d)	12. (d)	13. (c)	14. (c)	15. (a)	16. (b)	17. (c)	18. (d)	19. (c)	20. (b)
21. (d)	22. (c)	23. (b)	24. (b)	25. (b)	26. (c)	27. (b)	28. (c)	29. (b)	30. (b)
31. (c)	32. (b)	33. (c)	34. (b)	35. (d)	36. (b)	37. (c)	38. (c)	39. (d)	40. (d)
41. (b)	42. (c)	43. (c)	44. (b)	45. (c)	46. (c)	47. (d)	48. (b)	49. (b)	50. (c)
51. (a)	52. (a)	53. (b)	54. (c)	55. (c)	56. (b)	57. (c)	58. (d)	59. (b)	60. (c)
61. (c)	62. (d)	63. (b)	64. (b)	65. (b)	66. (a)	67. (c)	68. (c)	69. (c)	70. (b)
71. (b)	72. (d)	73. (d)	74. (b)	75. (d)	76. (b)	77. (a)	78. (a)	79. (c)	80. (a)

SPEED TEST-1

1 (b)	2. (c)	3. (b)	4. (b)	5. (d)	6. (b)	7. (a)	8. (d)	9. (c)	10. (a)

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1. Average speed $= \dfrac{\text{Total distance}}{\text{Total time}} = \dfrac{10+20}{\frac{10}{6}+\frac{20}{15}}$

$= \dfrac{30}{\left(\frac{90}{30}\right)} = \dfrac{30}{3} = 10$ km/h

2. Average speed (when distances are same) $= \dfrac{2uv}{u+v}$

$= \dfrac{2\times 20\times 30}{(20+30)} = 24$ km/h

where u, v are the different speeds.
(or use the general formula–Total distance/Total time)

3. Average speed $= \dfrac{3uvw}{uv+vw+uw}$

$= \dfrac{3\times 10\times 20\times 30}{200+600+300} = \dfrac{18000}{1100}$

$= 16\dfrac{4}{11}$ km/h

Alternatively: Suppose the total distance 3 times the LCM of the given speeds, then solve by general formula.

Total distance = 180 km (say)

then Total time $= \dfrac{60}{10}+\dfrac{60}{20}+\dfrac{60}{30}$

$= 6+3+2 = 11$ h

$\therefore$ Average speed $= \dfrac{180}{11} = 16\dfrac{4}{11}$ km/h

Alternatively: Suppose the total distance equals to $3x$ km then solve as above.

4. Suppose the total distance equals to 4 times the LCM of the speeds.

$\therefore$ Total distance = 2400 km

$\therefore$ Total time $= \dfrac{600}{20}+\dfrac{600}{25}+\dfrac{600}{30}+\dfrac{600}{40}$

$= 30+24+20+15 = 89$ h

$\therefore$ Average speed $= \dfrac{2400}{89} = 26\dfrac{86}{89}$ km/h

5. $\dfrac{2\times 20\times x}{(20+x)} = 24$

$\Rightarrow \quad x = 30$ km/h

Alternatively: Go through options.

6. Average speed $= \dfrac{2uv}{u+v}$

$= \dfrac{2\times 3x\times 5x}{(3x+5x)} = 3.75x$ km/h

7. $u = k, \quad v = 3k$

$\therefore \quad \dfrac{2uv}{u+v} \Rightarrow \dfrac{2\times k\times 3k}{(k+3k)} = 12$

$\Rightarrow \quad 1.5k = 12$

$\Rightarrow \quad k = 8$ km/h

Alternatively: Go through options.
Alternatively: Solve through alligations.

8. Effective speed = 25 + 35 = 60 km/h

Total distance to be covered = 120 km

$\therefore$ Time taken $= \dfrac{120}{60} = 2$ h

HINT Since in each hour X and Y together covers 60 km.



9. Since they take 2 hours to meet each other. Thus in 2 h X is 50 km away from Lucknow.
Alternatively: Both X and Y will cover the respective distances in the ratio of their speeds.

So, distance from Lucknow $= \dfrac{5}{12}\times 120 = 50$ km

10. When time is constant the distances covered by A and B will be in the ratio of their speeds, respectively.

11.



To meet each other they have to cover 100 km distance together and the ratio of distances covered by each one is directly proportional to the ratio of their speeds, respectively. Since the time taken by each one is same (i. e., constant).

Hence, $\dfrac{XZ}{YZ} = \dfrac{20}{60} = \dfrac{1}{3}$

$\therefore \quad XZ = \dfrac{1}{4}\times 100 = 25$ km

12. To meet the second time they have to cover 300 km distance together [for n^{th} time distance $= (2n-1)d$]
Time taken by them to meet each other, for the second time

$= \dfrac{300}{80} = 3\dfrac{3}{4}$ h

Distance covered by P $= 20\times 3\dfrac{3}{4} = 75$ km

Alternatively: The ratio of distance covered = Ratio of their speeds

$\therefore$ Distance covered by $P = \dfrac{1}{4}\times 300 = 75$ km

Scanned by CamScanner

yoursmahboob.wordpress.com

13. The ratio of distances covered by each of them
= Ratio of their respective speeds

$\therefore$ Distance covered by Q for the third meeting $= \frac{3}{4} \times 500$

$= 375$ km

14. Consider the distance travelled by any one of them, then find the distance between X and M, where they meet.

$\therefore$ The distance travelled by P for the fourth meeting

$$= \frac{1}{4} \times 700 = 175 \text{ km}$$

Therefore P will be 75 km from Y. It means P will be 25 km away from X.



15. This is constant for any number of meeting and is equal to the ratio of their speeds. Hence, 1 : 3.

16. It is always twice the length of race course. Hence, between any two consecutive meeting they have to cover total 200 km distance to meet each other for the next meeting.

HINT For the first meeting they will cover 100 km.
For the second meeting they will cover 300 km.
For the third meeting they will cover 500 km.
For the fourth meeting they will cover 700 km and so on.

17. To meet each other they will take equal time since they start their journey simultaneously.

18. To reach their destination the time taken by A and B is equal to the ratio of reciprocal to their speeds. Since when distance is constant time is inversely proportional to the respective speeds.

Hence, time taken by A and $B = \frac{1}{16} : \frac{1}{25} = 25 : 16$

19. $\frac{A\text{'s speed}}{B\text{'s speed}} = \sqrt{\frac{\text{Time taken by } B\ (t_B)}{\text{Time taken by } A\ (t_A)}}$

$$\frac{16}{25} = \sqrt{\frac{t_B}{t_A}}$$

$$\Rightarrow \quad \frac{t_B}{t_A} = \frac{256}{625} \Rightarrow \frac{t_A}{t_B} = \frac{625}{256}$$

20.



(Kamal) 40 km/h — (Vimal) 30 km/h

In the first 3 hours Vimal covers 90 km.

So, the rest distance = 560 km

Now, Kamal and Vimal both travels together, towards each other.

So, the time $= \frac{\text{Distance}}{\text{Speed}} = \frac{560}{70} = 8$ h

Thus, Vimal travels total = 3 + 8 = 11 h

Thus, the distance travelled by Vimal = 11 × 30 = 330 km

21. The distance covered by Kamal = 8 × 40 = 320 km

22.



To meet the first time they have to cover 200 × 2 = 400 km

Now, the time taken to meet each other $= \frac{400}{50} = 8$ h

23. Distance travelled by $P = 20 \times 8 = 160$ km

24. Distance travelled by $Q = 30 \times \frac{800}{50} = 480$ km

25. Distance travelled by $P = 20 \times \frac{1200}{50} = 480$ km

So, P will be 80 km away from X. Therefore ratio of distances

$$= \frac{80}{120} = \frac{2}{3}$$

26. The distance travelled by $P = \frac{1600}{50} \times 20 = 640$ km

Thus, P will be 160 km away from X.
[Since 640 = (200 × 2) + 240]
$\therefore$ Distance between D and X is 160 km.

27. This is possible only when the distance covered by P in n round be the multiple of 400.

28. X started at 12 : 00 noon
Y started at 3 pm

$$\text{Required time} = \frac{\text{Distance advanced in 3 h}}{\text{Relative speed}}$$

$$= \frac{40 \times 3}{20} = 6 \text{ h} \qquad (20 = 60 - 40)$$

Hence, Y will overtake X at 9 pm. $(3 + 6 = 9)$

29. $$\text{Required time} = \frac{\text{Distance advance} - \text{Required difference}}{\text{Relative speed}}$$

$$= \frac{120 - 30}{20} = \frac{90}{20} = 4.5 \text{ h}$$

Thus, at 7 : 30 pm X and Y will be 30 km apart.

30. $$\text{Required time} = \frac{\text{Distance advanced} + \text{Required difference}}{\text{Relative speed}}$$

$$= \frac{120 + 30}{20} = \frac{150}{20} = 7.5 \text{ h}$$

Thus at 10 : 30 pm X and Y will be 30 km apart.

31. Distance travelled by Y to overtake X

= Time taken × Speed of Y

= 6 × 60 = 360 km

Thus, Y will overtake X at a distance of 360 km from P.

32. Required distance

$$= \left(\frac{\text{Distance advanced} + \text{Required difference}}{\text{Relative speed}}\right) \times (\text{Speed of } Y)$$

$$= \frac{120 + 360}{20} \times 60 = 1440 \text{ km}$$

33. Time (when X was 30 km ahead of Y) $= \frac{120 - 30}{20} = 4.5$ h

Time (when Y was 30 km ahead of X) $= \frac{120 + 30}{20} = 7.5$ h

Thus, required difference in time = 3 h

Scanned by CamScanner

yoursmahboob.wordpress.com

34. Speed = 36 km/h

$$= 36 \times \frac{5}{18} = 10 \text{ m/s}$$

35. Since in 60 minutes postman goes 36000 metre.

So in 1 minute postman goes $\frac{36000}{60} = 600$ metre

Thus, his required speed = 600 m/min

36. 1 mile = 1609.3 m = 1.6093 km

$\therefore$ 1 km $= \frac{1}{1.6093}$ mile = 0.6213882 mile

$\therefore$ Required speed = 36×0.6213882 mile/h

= 22.37 mile/h

37. Speed = 20 m/s = $20 \times \frac{18}{5} = 72$ km/h

38. In one hour train goes 72 km. So in one minute train will go $\frac{72}{60}$.

$\therefore$ Speed $= \frac{6}{5} = 1.2$ km/min

39. The ratio of speeds of $A, B, C = 6 : 3 : 1$

$\therefore$ The ratio of time taken by $A, B, C = 1 : 2 : 6$

$\therefore$ Time taken by $A = 13$ min

40.

	A	:	B
Speed	2	:	3
Time	$3x$	:	$2x$

41. $\because$ $3x - 2x = 20 \Rightarrow x = 20$

$\therefore$ $3x = 60$ min = 1 h

42. Let the original speed be S_1 and time t_1 and distance be D

Now, $\frac{D/2}{2t_1} = S_2$

$\therefore$ $S_2 = \frac{D}{4t_1}$ and $S_1 = \frac{D}{t_1}$

$\therefore$ $\frac{S_1}{S_2} = \frac{D/t_1}{D/4t_1} = \frac{4}{1}$

43. You can go through options to check the required difference.

Alternatively: Required distance

$$= \frac{S_1 S_2}{(S_1 \sim S_2)} \times \text{Time difference}$$

$$= \frac{5 \times 8}{3} \times \frac{3}{2} = 20 \text{ km}$$

Alternatively: Take the LCM of distances then solve by unitary method.

$\therefore$ LCM of 5, 8 = 40

Now, consider 40 km as a distance, then there is a 3 hours difference in 40 km. So, 3/2 hours difference will be in 20 km.

Alternatively: Let x be the distance, then

$$\frac{x}{5} - \frac{x}{8} = \frac{3}{2}$$

$\Rightarrow$ $x = 20$ km

44.

	A	:	B
Speed	2	:	3
Time	3	:	2

$\because$ B takes 48 minutes so A will take 72 minutes

= 1 h 12 min

45. The ratio of distances = 160 : 140 = 8 : 7

$\therefore$ The ratio of speeds = 8 : 7

46. $\frac{x}{9} - \frac{x}{10} = \frac{20}{60}$

$x = 30$ km

47. Time taken by Abhinav = 4 h

Time taken by Praveen = 3.5 h

For your convenience take the product of times taken by both as a distance.

Then the distance = 14 km

Since, Abhinav covers half of the distance in 2 hours (i.e., at 8 am)

Now, the rest half (*i.e.*, 7 km) will be covered by both Praveen and Abhinav.

Time taken by them $= \frac{7}{7.5} = 56$ min

Thus, they will cross each other at 8 : 56 am.

48. 9 km difference arises in the 99 km distance.

$\therefore$ 72 km difference will arise in the 792 km distance.

49. Apply the product constancy concept

Speed	Time	
$\frac{1}{5}\downarrow$	$\frac{1}{4}\uparrow$	= 15 min

Since, $\frac{x}{4} = 15$ min $\Rightarrow$ $x = 60$ min = 1 h

So, the original (or usual) time = 60 min = 1 h

50.

Speed	Time	
$\frac{1}{4}\downarrow$	$\frac{1}{3}\uparrow$	= 2 h

$\Rightarrow$ Usual time = $2 \times 3 = 6$ h

51.

Speed	Time	
$\frac{1}{2}\uparrow$	$\frac{1}{3}\downarrow$	= 40 min

$\Rightarrow$ Usual time = $3 \times 40 = 120$ min = 2 h

52.

Speed	Time	
$\frac{2}{20} = \frac{1}{10}\downarrow$	$\frac{1}{9}\uparrow$	= 10 min

$\Rightarrow$ Usual time = $9 \times 10 = 90$ min $= \frac{3}{2}$ h

$\therefore$ Distance travelled = Speed $\times$ Time

$= 20 \times \frac{3}{2} = 30$ km

53. Increase in speed = 1 km

Change in time = 25 min

Speed	Time	
$\frac{1}{5}\uparrow$	$\frac{1}{6}\downarrow$	= 25

Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow$ Usual (normal) time $= 6 \times 25 = 150 \text{ min} = \frac{5}{2}\text{h}$

$\therefore$ Distance = Normal speed × Normal time

$= 5 \times \frac{5}{2} = 12.5 \text{ km}$

54. Since, they are 1.5 km apart in each hour.
$\therefore$ 7.5 km apart they will be in 5 hours.
(Since, in the same direction speeds are subtracted)

55. In each hour they will be 720 km apart.
(Since in opposite direction speeds are added)

56. Let the distance = x km and usual rate = y km/h

$$\therefore \quad \frac{x}{y} - \frac{x}{(y+6)} = 4 \text{ h} \qquad \ldots(i)$$

$$\frac{x}{(y-4)} - \frac{x}{y} = 4 \qquad \ldots(ii)$$

From Eqs. (i) and (ii), we get

$$\frac{x}{y} - \frac{x}{(y+6)} = \frac{x}{(y-4)} - \frac{x}{y}$$

$$\Rightarrow \quad y = 24$$

Now putting the value of $y = 24$ in Eq (i), we get

$$x = 480$$

Alternatively:

$$\begin{matrix} S & & T \\ & \times & \\ +6 & & -4 \end{matrix} \Rightarrow -4S + 6T = |-4 \times 6|$$

$$\begin{matrix} S & & T \\ & \times & \\ -4 & & +4 \end{matrix} \Rightarrow 4S - 4T = |-4 \times 4|$$

$$\therefore \quad -4S + 6T = 24 \qquad \ldots(i)$$

$$4S - 4T = 16 \qquad \ldots(ii)$$

$\therefore$ Solving these two equations, we get

$$T = 20 \quad \text{and} \quad S = 24$$

$\therefore$ Distance = Speed × Time

$= 24 \times 20 = 480 \text{ km}$

57. Let the original speed be x km/h, then

$$\frac{600}{x} - \frac{600}{(x+20)} = 1$$

$$\Rightarrow \quad 600\left(\frac{x+20-x}{x(x+20)}\right) = 1$$

$$\Rightarrow \quad x^2 + 120x - 12000 = 0$$

$$\Rightarrow \quad (x-120)(x-100) = 0$$

$$\Rightarrow \quad x = 100 \quad \text{and} \quad x = 120$$

$\therefore$ Original speed = 100 km/h

Alternatively:

$$S_1 \times S_2 = \text{Distance} \times \frac{\text{Difference in speed}}{\text{Difference in time}}$$

$$= 600 \times \frac{20}{1} = 600 \times 20 = 12000$$

$$\Rightarrow \quad S_1 \times S_2 = 12000$$

$$\therefore \quad S_1 = 100 \quad \text{and} \quad S_2 = 120$$

(Factorise 12000 in such a way that the difference be 20) S_1 is the original speed and S_2 is the changed speed.

58. Very similar to question number 57.

$$180 \times \frac{5}{3} = 60 \times 5$$

$$S_1 \times S_2 = 300 = 15 \times 20$$

$$S_1 = 15 \text{ km/h}$$

and $\quad S_2 = 20 \text{ km/h}$

Alternatively: $\quad S_1 \times (S_1 + 5) = 300$

$$\Rightarrow \quad S_1 = 15 \text{ km/h}$$

59. Very similar to previous problems

$$t_1 \times t_2 = \text{Distance} \times \frac{\text{Difference in time}}{\text{Difference in speed}}$$

$$\Rightarrow \quad t_1 \times t_2 = 1680 \times \frac{6}{14}$$

$$t_1 \times t_2 = 120 \times 6 = 720 = 30 \times 24$$

$$\Rightarrow \quad t_1 = 30 \quad \text{and} \quad t_2 = 24$$

[since $t_2 = (t_1 - 6) \Rightarrow t_1 \times (t_1 - 6) = 720 \Rightarrow t_1 = 30$]

Therefore, usual time = 30 h

60. Relative speecd $= \frac{\text{Total distance}}{\text{Total time}}$

$$= \frac{60+40}{20} = 5 \text{ m/s}$$

$$\therefore \quad 5 \text{ m/s} = 5 \times \frac{18}{5} = 18 \text{ km/h}$$

Now, Relative speed = 18 km/h

= Speed of ambulance − Speed of school bus

18 = 30 − speed of school bus

Speed of school bus = 12 km/h

61.

Time	Speed
$\frac{1}{4}\downarrow$	$\frac{1}{3}\uparrow$

Since he has to increase his speed by $\frac{1}{3}$rd of the original speed.

So, the new speed = 15 + 5 = 20 km/h

Alternatively: $\quad 15 \times 4 = 3 \times x$

$$\Rightarrow \quad x = 20 \text{ km/h}$$

62. Time (required) $= \frac{\text{Length of train}}{\text{Speed of train}} \qquad \left(T = \frac{D}{S}\right)$

$$= \frac{350}{70} = 5 \text{ s}$$

63. Time taken to cross the bridge $= \frac{\text{Total length}}{\text{Speed of train}}$

$$= \frac{270+130}{40} = \frac{400}{40}$$

$$= 10 \text{ s}$$

64. Speed of train $= \frac{225}{9} = 25 \text{ s}$

Now, Time taken to cross the tunnel $= \frac{225+450}{25} = 27 \text{ s}$

65. Let the length of the tunnel be x m, then

$$\text{Time} = \frac{\text{Length of train} + \text{Length of tunnel}}{\text{Speed}}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$60 = \frac{350 + x}{10} \qquad \left(\text{Speed} = 36 \times \frac{5}{18} = 10 \text{ m/s}\right)$$

$\Rightarrow$ $x = 250$ m

66. Speed of train $= \frac{\text{Length of train + Length of platform}}{\text{Time}}$

$$= \frac{250 + 250}{25} = 20 \text{ m/s}$$

$$= 72 \text{ km/h}$$

67. Let the length of the Sabarmati express is x metre then,

$$\frac{x + 162}{18} = \frac{x + 120}{15} \text{ Speed of train}$$

$\Rightarrow$ $x = 90$ m

68. Time $= \frac{\text{Length of train}}{\text{Relative speed}}$

$$= \frac{200}{19} = 10\frac{10}{19} \text{ s}$$

(Relative speed $= 72 - 3.6 = 68.4$ km/h $= 19$ m/s)

69. Time $= \frac{\text{Length of train}}{\text{Relative speed}}$

$$= \frac{350}{35} \times 6 = 60 \text{ s}$$

(Relative speed $= 20 + 1 = 21$ km/h $= 21 \times \frac{5}{18} = \frac{35}{6}$ m/s)

70. Relative speed $= 50 - 40 = 10$ km/h $= \frac{50}{18}$ m/s

$\therefore$ Time taken $= \frac{\text{Sum of length of the trains}}{\text{Relative speed}}$

$$= \frac{200}{50} \times 18 = 72 \text{ s}$$

71. Relative speed $= 50 + 40 = 90$ km/h

$$= 90 \times \frac{5}{18} = 25 \text{ m/s}$$

$\therefore$ Time taken $= \frac{\text{Sum of lengths of train}}{\text{Relative speed}} = \frac{200}{25} = 8 \text{ s}$

72. Let the length of train be x m, then

$$\frac{x}{10} = \frac{120 + x}{18}$$

$\Rightarrow$ $x = 150$ m

73. Let the speed of train be x km/h, then

$$\frac{175}{10} = (9 + x) \times \frac{5}{18}$$

$\Rightarrow$ $x = 54$ km/h

74. Relative speed = Sum of speeds of two trains

$$= (60 + x)$$

$$\text{Time} = \frac{\text{Sum of length of two trains}}{\text{Relative speed}}$$

$$10 = \frac{250}{(60 + x) \times 5} \times 18$$

$$(60 + x) = 90$$

$$x = 30 \text{ km/h}$$

75. Let the length of the train be x metre, and let the speed of train be y km/h, then

$$x = (y + 3)\frac{5}{18} \times 36 \quad \text{...(i)}$$

and $$x = (y + 6) \times \frac{5}{18} \times 30 \quad \text{...(ii)}$$

From Eq. (i) and (ii), we get

$$(y + 3) \times 36 = (y + 6) \times 30$$

$$y = 12 \text{ km/h}$$

$\therefore$ $$x = (y + 3) \times \frac{5}{18} \times 36$$

or $$x = 15 \times \frac{5}{18} \times 36$$

or $$x = 150 \text{ m}$$

76. Let the length of each train be x m, then

$S_1 = \frac{x}{4}$ and $S_2 = \frac{x}{5}$; S_1 and S_2 are speeds

Now, required time $= \frac{2x}{\frac{x}{4} + \frac{x}{5}} = \frac{40}{9}$ s

77.

	Pushpak		Bhopal
Time $\rightarrow$	10	:	8
Speed $\rightarrow$	8	:	10
$\Rightarrow$	$4x$	:	$5x$

Since, $5x - 4x = 10$

$\Rightarrow$ $5x = 50$ and $4x = 40$

$\therefore$ Average speed $= \frac{2 \times 40 \times 50}{40 + 50} = 44\frac{4}{9}$ km/h

78. Required time $= \frac{\text{Distance advanced}}{\text{Relative speed}} = \frac{4 \times 40}{20} = 8$ h

Thus, the faster train will overtake at 8 pm.

79. Required distance = Time taken in overtaking $\times$ Faster's speed

$= 8 \times 60 = 480$ km from Meerut

80. In 50 minute Rajdhani express can cover 50 km. So, the rest distance = 650 km, which will be jointly covered by both trains.

$\therefore$ Time taken $= \frac{650}{(60 + 70)} = 5$ h

Distance from Lucknow $= 5 \times 70 = 350$ km

81. Average speed $= \frac{\text{Total distance}}{\text{Total time}}$

$$= \frac{560 + 360}{16} = 57\frac{1}{2} \text{ h}$$

82. Average speed $= \frac{2 \times 80 \times 120}{200} = 96$ km/h

83. Distance = Average speed $\times$ Average time

or Distance $= 96 \times \frac{25}{2}$

or Distance $= 1200$ km

84. $50 \times 30 = x \times 20$

$\Rightarrow$ $x = 75$ km/h

Scanned by CamScanner

yoursmahboob.wordpress.com

85. $$\frac{S_1}{S_2} = \sqrt{\frac{t_2}{t_1}}$$

$$\frac{120}{S_2} = \sqrt{\frac{9}{16}} = \frac{3}{4}$$

$$\Rightarrow \quad S_2 = 160 \text{ km/h}$$

86. $$S_1 + S_2 = \frac{240}{4} = 60$$

$$S_1 - S_2 = \frac{240}{12} = 20$$

$$\therefore \quad S_1 = 40 \text{ m/s} \quad \text{and} \quad S_2 = 20 \text{ m/s}$$

$$\therefore \quad S_1 = 40 \times \frac{18}{5} = 144 \text{ km/h}$$

87. Time taken to cross the man $= \dfrac{\text{Length of the faster train}}{\text{Relative speed}}$

$$18 = \frac{x}{15 \times \frac{5}{18}} \quad \Rightarrow \quad x = 75 \text{ m}$$

88. Suppose the total distance be 300 km (LCM of 50 and 60) then in the first case it takes only 5 hours and in the second case it takes 6 hours.
Thus, in 6 hours trains halts for 1 hour.
Therefore in 1 hour train halts for 1/6 hour = 10 m

Alternatively: Difference in speeds = 10 km/h

Faster speed = 60 km/h

$\therefore$ Required time per hour $= \dfrac{10}{60} = \dfrac{1}{6}$ h = 10 min

89. If the speed of faster horse be f_S and that of slower horse be s_S, then

$$f_S + s_S = \frac{50}{1} = 50$$

and $$\frac{50}{s_S} - \frac{50}{f_S} = \frac{5}{6}$$

Now, you can go through options.
The speed of slower horse is 20 km/h.

Since, $$20 + 30 = 50$$

and $$\frac{50}{20} - \frac{50}{30} = \frac{5}{6}$$

90. Let he walked for x hours, then

$$5x + 25(10 - x) = 17 \times 10$$

$$\Rightarrow \quad x = 4$$

$$\therefore \quad 10 - x = 6 \text{ h}$$

Hence, distance travelled by auto = $25 \times 6 = 150$ km.

91. Let the original speed be x km/h then,

$$\frac{36}{(x-6)} + \frac{36}{(x+6)} = 8$$

Now, you can go though options or solve it as follows

$$\frac{(x+6+x-6)}{(x^2-36)} = \frac{8}{36}$$

$$\Rightarrow \quad x = 12 \quad \text{and} \quad x = -3$$

Thus, the possible value of $x = 12$

$\therefore$ Time taken by faster speed = 2 h

92. $$\text{Time} = \frac{\text{Distance advanced}}{\text{Relative speed}}$$

$$2 = \frac{2 \times x}{(30 - x)}$$

$$\Rightarrow \quad x = 15 \text{ km/h}$$

93. Prachi travels only for 3 hours, since half an hour she halts at Lucknow.

Now, the average speed (except the halt) $= \dfrac{160}{3}$ km/h

Therefore, by alligation



$$\Rightarrow \quad 1 : 2$$

Therefore, the ratio of time taken at 40 km/h and at 60 km/h is 1 : 2.
Thus, the distance between Lucknow and Kanpur

$$= 2 \times 60 = 120 \text{ km}$$

94. Let the speed of the faster train be f_S and slower train be s_S, then

$$f_S + s_S = \frac{200 + 250}{18} = 25 \text{ m/s}$$

and $$f_s - s_S = \frac{200 + 250}{60} = \frac{450}{60} = 7.5 \text{ m/s}$$

$$\therefore \quad f_S = 16.25 \text{ m/s}$$

$$= 16.25 \times \frac{18}{5} = 58.5 \text{ km/h}$$

95. Distance covered in 3 minutes $= 3 \times \dfrac{1000}{60} = 50$ m

Now he has to cover (500 + 50) metres in (30 – 3) minutes

$$\therefore \quad \text{New speed} = \frac{550/1000}{27/60} = \frac{11}{9} \text{ km/h}$$

96.

	Anil		Mukesh
Speed →	3	:	4
Time →	4	:	3

But $$4x - 3x = \frac{1}{2} \text{ h}$$

$$\Rightarrow \quad 4x = 2 \text{ h} \quad \text{and} \quad 3x = 1.5 \text{ h}$$

Now, since Anil doubles the speed so time will be half of the actual time. Hence, new time will be 1 hour.

97. Average speed of Anil and Mukesh $= \dfrac{3x + 4x}{2} = 28$

$$\Rightarrow \quad x = 8$$

$$\therefore \quad \text{Speed of Sameer} = 3 \times 8 = 24 \text{ km/h}$$

$$\therefore \quad \text{Distance travelled} = 2 \times 24 = 48 \text{ km}$$

98. Let the speed of X and Y be the x km/h and y km/h respectively. Since they meet after 3 hours, so $x + y = 100$.
Since, the faster train takes atleast 3 + 2 = 5 hours to complete the 300 km journey. Hence, minimum possible speed for the slower train = 40 km/h at which speed it will take 7.5 h to complete the journey. $\left(7.5 = \dfrac{300}{40}\right)$

Scanned by CamScanner

yourshanboob.wordpress.com

99. Let the time taken in first third part of the journey be x minutes, then the time required in second third part of the journey is $\frac{3x}{2}$ and in the last third part of the journey time required is $\frac{15x}{8}$.

Therefore, $x + \frac{3x}{2} + \frac{15x}{8} = 350$ min

$\Rightarrow$ $x = 80$ min

100.

Speed	Time	
$\frac{1}{5}\downarrow$	$\frac{1}{4}\uparrow$	$= 15$ min

Therefore usual time $= 4 \times 15 = 60$ min

Now,

Speed	Time	
$\frac{1}{4}\uparrow$	$\frac{1}{5}\downarrow$	$= 12$ min

(Since original time = 60 min)

Therefore he will be 15 + 12 = 27 minutes early in comparison to the previous day.

101. Let the original speed be s km/h and scheduled time $= t$ hours

and total distance $= D$ km

then $s \times t = \frac{3}{4}D$ ...(i)

and $s \times (t + 3) = D$ ...(ii)

From Eq. (i) and (ii), we get

$st = \frac{3}{4}[s(t + 3)] \Rightarrow t = 9$ h

and let $s = 1$ km/h, then $D = 12$ km

Again, since he doubles his speed after k hours then,

$s_1t_1 + s_2t_2 = D$

$1 \times k + 2 \times (9 - k) = 12$

$\Rightarrow$ $k = 6$ h

102. By alligation rule



Ratio of time = 2 : 3

$\therefore$ Ratio of distances $= 2 \times 20 : 3 \times 70 = 4 : 21$

Alternatively: $\frac{x}{20} + \frac{y}{70} = \frac{x + y}{50}$

$\Rightarrow$ $\frac{76x + 20y}{1400} = \frac{x + y}{50}$

$\Rightarrow$ $42x = 8y \Rightarrow \frac{x}{y} = \frac{4}{21}$

103. $\frac{\text{(Speed of wind)}}{\text{(Speed of car)}} = \frac{\text{(Time utilised)}}{\text{(Time saved)}}$

$\frac{332}{x} = \frac{332}{28}$

$\Rightarrow$ $x = 28$ m/s

104. Time $= \frac{\text{Total distance}}{\text{Relative speed}}$

$\frac{4.5}{60} = \frac{450/1000}{x} \Rightarrow x = 6$ km/h

Relative speed = Speed of car − Speed of man

$6 = x - 6$

$\Rightarrow$ $x = 12$ km/h

105. $W + R \rightarrow 4$ h 20 min

$W + W \rightarrow 5$ h 20 min

$\therefore R + R \rightarrow 3$ h 20 min

106.



$P_1 \rightarrow$ Place of accident

$P_2 \rightarrow$ Imaginary place of accident

For the distance x

Speed	Time	
$\frac{1}{6}\downarrow$	$\frac{1}{5}\uparrow$	$= 1$ h

Thus, the usual time required for the distance x km is $5 \times 1 = 5$ hours.

For the distance $(x + 300)$

Speed	Time	
$\frac{1}{6}\downarrow$	$\frac{1}{5}\uparrow$	$= 2$ h

Thus, the usual time required for the distance $(x + 300)$ km is $5 \times 2 = 10$ h.

It means he covers 300 km distance in 5 h

$\therefore$ Speed $= \frac{300}{5} = 60$ km/h (normal speed)

107. Since, he can cover x km at 60 km/h in 5 h it means $x = 300$ km.

Therefore, total distance = (120 + 300 + 300) = 720 km.

108. Circumference means one revolution.

Therefore, distance covered in 10 revolutions $= 300 \times 10 = 30$ m

i.e., 30 metre in 6 seconds.

$\therefore$ Speed of wheel $= \frac{30}{6}$ m/s $= 5$ m/s

$\therefore$ 5 m/s $= 5 \times \frac{18}{5} = 18$ km/h

109. Speed of man in still water $= \frac{S_D + S_U}{2}$

$= \frac{12 + 8}{2} = 10$ km/h

$S_D \rightarrow$ Speed in downstream (= Boat + River)

$S_U \rightarrow$ Speed in upstream (=Boat − River)

110. Speed of water current $= \frac{S_D - S_U}{2} = \frac{21 - 15}{2} = 3$ km/h

111. $S_D = 12$ km/h

$S_U = 5$ km/h

Speed of current $= \frac{12 - 5}{2} = 3.5$ km/h

Scanned by CamScanner

yoursmahboob.wordpress.com

112. $S_D \rightarrow 15$ km/h
$S_S \rightarrow 9$ km/h

$$\text{Speed of man} = \frac{15+9}{2} = 12 \text{ km/h}$$

113. Let the required distance be D km, then

$$\frac{D}{6} + \frac{D}{4} = \frac{5}{4}$$

$$D\left(\frac{10}{24}\right) = \frac{5}{4}$$

$$\Rightarrow \quad D = 3 \text{ km}$$

114. $\frac{16}{8} + \frac{16}{2} = 10$ h

115. Let the downstream speed be D and upstream speed be U, then

$$\frac{48}{U} + \frac{72}{D} = 12$$

and $$\frac{48}{D} + \frac{72}{U} = 13$$

$$\therefore \quad 48m + 72n = 12 \quad \ldots(i)$$

and $$48n + 72m = 13 \quad \ldots(ii)$$

Solving Eq. (i) and (ii), we get

$$m + n = \frac{5}{24} \quad \text{and} \quad m - n = \frac{1}{24}$$

$$\therefore \quad D = 12 \text{ km/h} \quad \text{and} \quad U = 8 \text{ km/h}$$

$$\therefore \quad \text{Speed of current} = 2 \text{ km/h}$$

116.
$$D_S = \frac{9}{2} = 4.5 \text{ km/h}$$

$$U_S = \frac{9}{6} = 1.5 \text{ km/h}$$

$$\therefore \text{ Speed of boat in still water} = \frac{4.5+1.5}{2} = 3 \text{ km/h}$$

and Speed of river in still water $= \frac{4.5-1.5}{2} = 1.5$ km/h

117. $\frac{D_T}{U_T} = \frac{1}{2} \Rightarrow \frac{D_S}{U_S} = \frac{2}{1} \Rightarrow \frac{B+S}{B-S} = \frac{2}{1} \Rightarrow \frac{B}{S} = \frac{3}{1}$

HINT: D_T and U_T are the downstream and upstream times and D_S and U_S are the downstream and upstream speeds. Here we can use componendo and dividendo.

$$\because \quad \frac{\text{Speed of boat}}{\text{Speed of stream}} = \frac{3}{1} = \frac{15}{x}$$

$$\therefore \quad \text{Speed of stream} = 5 \text{ km/h}$$

118. If t_1 and t_2 are the upstream and downstream times. Then time taken in still water is given by

$$\frac{2 \times t_1 \times t_2}{t_1 + t_2} = \frac{2 \times 12 \times 24}{36} = 16 \text{ h}$$

Alternatively: $D = (B + S) \times 12$

and $D = (B - S) \times 24$

where $(B + S)$ is downstream speed
$(B - S)$ is upstream speed

$$\Rightarrow \quad \frac{B+S}{B-S} = \frac{2}{1}$$

$$\Rightarrow \quad \frac{B}{S} = \frac{3}{1} \quad \text{(By componendo and dividendo)}$$

Now $D = 4S \times 12 = 48S$

$D = 48S = 16B$ (Distance = Time × Speed)

$\therefore$ Required time = 16 h

119. $\frac{D_S}{U_S} = \frac{B+S}{B-S} = \frac{3}{2}$

where $B \rightarrow$ Speed of boat in still water
$S \rightarrow$ Speed of current/stream

$$\Rightarrow \quad \frac{2B}{2S} = \frac{5}{1} \quad \text{(By componendo and dividendo)}$$

$$\Rightarrow \quad \frac{B}{S} = \frac{5/2}{1/2} \Rightarrow B = \frac{5}{2}$$

Average speed of downstream and upstream $= \frac{2 \times 3 \times 2}{3+2} = \frac{12}{5}$

$$\therefore \quad \text{Required ratio} = \frac{5/2}{12/5} = \frac{25}{24}$$

120. Let x be the upstream speed, then the downstream speed will be $(x + 3)$.

$$\therefore \quad \frac{3}{x} + \frac{3}{x+3} = 3$$

$$\Rightarrow \quad x^2 + x - 3 = 0$$

$$\Rightarrow \quad x = \frac{-1 + \sqrt{13}}{2}$$

$$= \frac{-1 + 3.6}{2} = 1.3 \text{ km/h}$$

$$\therefore \quad (x + 3) = 4.3 \text{ km/h}$$

121. Upstream speed of first boat = 8 km/h

Upstream speed of second boat = 4 km/h

$$\therefore \quad \text{Relative speed} = 4 \text{ km/h} \quad (= 8 - 4)$$

$$\therefore \quad \text{Required time} = \frac{10}{4} = 2.5 \text{ h}$$

122. Downstream speed $= B + S$ $\quad B \rightarrow$ Speed of boat

Upstream speed $= B - S$ $\quad S \rightarrow$ Speed of stream

$$\therefore \quad \frac{120}{B+S} + \frac{120}{B-S} = 15$$

$$\Rightarrow \quad \frac{B}{B^2 - S^2} = \frac{1}{16} \quad \ldots(i)$$

Again $$\frac{120}{B+2S} + \frac{120}{B-2S} = 24$$

$$\Rightarrow \quad \frac{B}{B^2 - 4S^2} = \frac{1}{10} \quad \ldots(ii)$$

From Eq. (i) and (ii), we get

$$B = (B^2 - S^2)16$$

and $$B = (B^2 - 4S^2)10$$

$$\Rightarrow \quad 10B^2 - 40S^2 = 16B^2 - 16S^2$$

$$\Rightarrow \quad \frac{B^2}{S^2} = 9 \Rightarrow \frac{B}{S} = 3$$

i.e., $$B : S = 3 : 1$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Now, you can go through options or solve by equations. Since now you know the ratio of speeds of boat and stream. The correct choice is (b).

124. Upstream speed $= B - S$

Downstream speed $= B + S$

$$B - S = \frac{15}{5} = 3 \text{ km/h}$$

Again $B = 4S$

$\therefore$ $B - S = 3 = 3S$

$\Rightarrow$ $S = 1$ and $B = 4$ (km/h)

$\therefore$ $B + S = 5$ km/h

$\therefore$ Time during downstream $= \frac{15}{5} = 3$ h

125. $\frac{24}{(5.5 - R)} - \frac{24}{(5.5 + R)} = 5$

$\Rightarrow$ $R = 2.5$ km/h; $R \rightarrow$ Speed of river/current

Again $(B_2 + R) = \frac{24}{4} = 6$

$\Rightarrow$ $(B_2 + 2.5) = 6 \Rightarrow B_2 = 3.5$ km/h

126.



$PQ = QR$

$P \rightarrow Q \rightarrow R$ (7 h)

It means $P \rightarrow Q$ (3.5 h)

Again $\{P \rightarrow Q$ and $Q \rightarrow P\}$ (8 h)

It means $Q \rightarrow P$ (4.5 h)

Therefore $R \rightarrow Q$ (4.5 h)

Thus, from R to P boat will take 9 hours.

HINT $P \rightarrow R$ (Downstream)
$R \rightarrow P$ (Upstream)

127. $\frac{40}{(B - S)} + \frac{55}{(B + S)} = 13$

$\frac{30}{(B - S)} + \frac{44}{(B + S)} = 10$

HINT Go though options for quicker answer and prefer the value which can help in dividing 44 and 55.

Solutions for question number 128 and 129: *B is 2% slow than A and A is 10% slow than C. Therefore, in 1 km race.*



128. Since in 1000 m (1 km) race difference between A and B is 18 m.

So in 2 km race it will be 36 m.

129. In a 1 km race C can give B a start of 118 m. Therefore in a half km race C can give B a start of 59 m.

130. In a 1600 m race



$C \rightarrow 1540$, $B \rightarrow 1520$

The ratio of speeds of $C : B$ is 77 : 76. It means in 77 m race C beats B by 1 m. So, in 400 m race C will beat B by

$$400 \times \frac{1}{77} \text{ m} = 5\frac{15}{77} \text{ m}$$

131.

	Aman	Shakti
Time	190	200
Speed	$20x$	$19x$

$\because$ $20x = 1000$ m

$\Rightarrow$ $x = 50$ m

Again $20x - 19x = x = 50$ m

So, Aman can beat Shakti by 50 m.

132.

	A	:	B	
Speed	7	:	4	
Time	4	:	7	
Distance	4	:	7	(Since distance $\propto$ time)

Now, $7x - 4x = 300$

$3x = 300$

$\Rightarrow$ $x = 100$

$\therefore$ $7x = 700$

Thus, the winning post be 700 m away from the starting point.

133. Ratio of speeds of $A : B = 12 : 11$

and ratio of speeds of $B : C = 8 : 7$

Therefore ratio of speeds of $A : B : C = 96 : 88 : 77$

So in 9600 m race A will beat C by 1900 m.

134. When Ameesha runs 1000 m, then Bipasha runs only 700 m [1000 – (100 + 200)]

when Ameesha runs 1000 m, then Celina runs only 600 m [1000 – (100 + 300)]

Therefore,



Now, since in 700 m race Bipasha beats Celina by 100 m. So, in 50 m race Bipasha will beat Celina by

$$50 \times \frac{100}{700} = 7.14 \text{ m}$$

Alternatively: Bipasha beats Celina by 14.28% of the distance then in 50 m race Bipasha will beat Celina by 7.14 m.

135.

		Distance	Time
Case I:	Ravi	1000	t_1
	Vinod	960	$t_1 + 19$
Case II:	Ravi	960	t_2
	Vinod	1000	$t_2 + 30$

Therefore, $\frac{1000}{t_1} = \frac{960}{t_2}$ = Speed of Ravi

$\Rightarrow$ $t_1 = \frac{25}{24} t_2$

Also $\frac{960}{t_1 + 19} = \frac{1000}{t_2 + 30}$ = Speed of Vinod

$\therefore$ $(t_2 + 30)\, 24 = 25\left[\frac{25}{24} t_2 + 19\right]$

$\Rightarrow$ $49t_2 = 5880$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow$ $t_2 = 120$ s

$\therefore$ Required ratio $= \dfrac{960/t_2}{1000/t_2 + 30} = \dfrac{6}{5}$

137. Since, the speeds of Vinay and Versha are in the ratio of 5 : 3 *i.e.*, when Vinay covers 5 rounds, then Versha covers 3 rounds, but first time Vinay and Versha meet when Vinay completes $2\frac{1}{2}$ round and Versha completes $1\frac{1}{2}$ round.

For Vinay to pass Versha 7th time, Vinay would have completed $7 \times 2\frac{1}{2}$ rounds. Since, each round is $1\frac{1}{2}$ km, the distance covered by Vinay is

$$7 \times 2\frac{1}{2} \times 1\frac{1}{2} = 7 \times \frac{5}{2} \times \frac{3}{2} = 26\frac{1}{4} \text{ km}$$

138.



In the same time, when A covers 1500 m, B covers 1440 m and C covers 1425 m.

So, in 1440 m race B can give a start of 15 m.

$\therefore$ In 1500 m race B will give a start of

$$\frac{15}{1440} \times 1500 = 15\frac{5}{8} \text{ m}$$

139. In 600 m race Prabhat can have only start of 120 m. Now since he has more than 200 m start up so he will win the race.



Now, when Prabhat will cover 400 m distance, then in the same time Nishith will cover only 500 m. So, Prabhat will win by 100 m.

140. B is 25% slower than A and C is 20% slower than B.

Therefore in a game of 200 points B can have 150 points and C can have 120 points.

Thus, A can give C 80 points.

141. Since between 11 am and 1 pm and 11 pm and 1 am two hands of a clock coincide only once, each time.

142. Since between 2 am and 3 am (2 pm and 3 pm) and 8 am and 10 am (8 pm and 10 pm) two hands of a clock make 90° angle only 3 times in rest of the each hour two hands make 90° angle 2 times.

143. Since between 5 am and 7 am (5 pm and 7 pm) this happens only once. In rest each of the hours it happens one time.

144. Both (a) and (b) are correct.

Relative speed = Speed of minute-hand − Speed of hour-hand

$$= 6° - \frac{1}{2}° = 5\frac{1}{2}°$$

and $1 \text{ min} - \dfrac{1}{12} \text{ min} = \dfrac{11}{12} \text{ min}$

145. $\dfrac{5 \times 30}{11/2} = \dfrac{300}{11} = 27\dfrac{3}{11}$ min = 27 min 16 s

Therefore, required time = 5 : 27 : 16

146. The angle made by minute-hand = $5 \times 30 = 150°$

The angle made by hour-hand = $2 \times 30 + 25 \times \dfrac{1}{2} = 72.5°$

Hence, required angle = $150 - 72.5 = 77.5°$

147. $\dfrac{90° - 30°}{5.5} = \dfrac{60}{11} \times 2 = \dfrac{120}{11} = 10\dfrac{10}{11}$ minute

$= 10$ min 54 s

$\therefore$ Required time = 3 : 10 : 54

148. $\dfrac{210}{5.5} = \dfrac{210}{11} \times 2 = \dfrac{420}{11} = 38\dfrac{2}{11}$ min = 38 min 11 s

Therefore, required time = 7 : 38 : 11

149. The angle made by minute-hand = 90°

The angle made by hour-hand = $6 \times 30 + 15 \times \dfrac{1}{2} = 187.5°$

$\therefore$ Required difference = 97.5°

150. $\dfrac{90 - 35}{5.5} = \dfrac{55}{11} \times 2 = 10$ min

So, the required time = 3 : 10 : 00

Again $\dfrac{90 + 35}{5.5} = \dfrac{125}{11} \times 2 = \dfrac{250}{11} = 22\dfrac{8}{11}$ min

$= 22$ min 43 s

LEVEL 2

1.

	Cycle	Auto	Car	
Speed	x	$(5x - 20)$	$5x$	
Time		$(t + 1)$	t	
Distance	120	120	120	(in km)

$\therefore$ $\dfrac{120}{(5x - 20)} - \dfrac{120}{5x} = 1$

$\Rightarrow$ $x^2 - 4x - 96 = 0$

$\Rightarrow$ $x = 12$

$\therefore$ Average speed $= \dfrac{360}{(10 + 3 + 2)} = 24$ km/h

2. Time taken by cycle $= \dfrac{120}{12} = 10$ h

Time taken by auto $= \dfrac{120}{40} = 3$ h

Time taken by car $= \dfrac{120}{60} = 2$ h

Total time = 15 h

3. In last 5 hours she covers 240 km (120 + 120)

4. New time = 3 + 3 + 2 = 8 h

Hence, decrease in time = 7 h (15 − 8

$\therefore$ Percentage change $= \dfrac{7}{15} \times 100 = 46.66\%$

Scanned by CamScanner

yoursmartbook.wordpress.com

5. Time taken to meet Bipasha and Mallika $= \frac{1080}{(60+120)} = 6$ h

So, in 6 hours Bipasha covers 360 km and this 360 km distance Rani covers in $\frac{360}{90} = 4$ h.

Hence, Rani leaves Kolkata 2 hours later than Bipasha *i. e.*, at 8 am. Rani leaves Kolkata.

NOTE The distance 360 covered by Bipasha to meet Mallika can also be calculated by the ratio of their speeds.

6. Note here the length of the train in which passenger is travelling is not considered since we are concerned with the passenger instead of train. So, the length of the bridge will be directly proportional to the time taken by the passenger respectively.

Therefore, $\frac{t_1}{t_2} = \frac{l_1}{l_2}$ $t \rightarrow$ Time, $l \rightarrow$ Length of bridge

$$\frac{7}{4} = \frac{280}{x}$$

$$\Rightarrow \quad x = 160 \text{ m}$$

7.



Note that the distances covered by them to meet at C are in the direct ratio of their speeds. Therefore

$$AC : BC = 4x : 5x$$

Now, for any particular person (say Pathik) the time required to cover different distances is directly proportional to the different distances. So, time taken by Pathik to cover AC and BC are the ratio of 4 : 5 (excluding staying or halt time at Chandni Chowk).

Thus time required to cover AC is 52 minutes only since he covers BC in 65 minutes.

But since he leaves Chandni Chowk for Bhavnagar at 9 : 27 am *i. e.*, 67 minutes later, when he left Andheri. It means he must have stayed at C for (67 − 52) = 15 minutes.

8. Let the length of the train be L metres and speeds of the train Arjun and Srikrishna be R, A and K respectively, then

$$\frac{L}{R-A} = 36 \qquad \ldots(i)$$

and $$\frac{L}{(R+K)} = 24 \qquad \ldots(ii)$$

From eq. (i) and (ii)

$$3(R-A) = 2(R+K)$$

$$\Rightarrow \quad R = 3A + 2K$$

In 30 minutes (i. e., 1800 seconds), the train covers $1800R$ (distance) but the Arjun also covers $1800A$ (distance) in the same time.

Therefore distance between Arjun and Srikrishna, when the train has just crossed Srikrishna

$$= 1800(R-A) - 24(A+K)$$

$$\therefore \quad \text{Time required} = \frac{1800(R-A) - 24(A+K)}{(A+K)}$$

$$= (3600 - 24) = 3576 \text{ s}$$

(Since $R = 3A + 2K$)

9.



Let the time taken by Kareena in going from K to S is x minutes and the time taken by Shahid in going from Worli to Shantakruj be y min.

Since, the new speed of Kareena is $\frac{2}{3}$, therefore time taken in returning $= \frac{3}{2}x$.

$$\therefore \quad x + \frac{3}{2}x = 120$$

$$\Rightarrow \quad x = 48 \text{ min}$$

but $$x = y$$

Again since the new speed of Shahid is $\frac{4}{3}$, therefore the time taken in returning $= \frac{3}{4}y$.

$$\therefore \quad \text{Total time} = y + \frac{3}{4}y$$

$$= 48 + 36 = 84 \text{ min}$$

10. Time taken to collide the two trains $= \frac{3}{2}$ h

So, in $\frac{3}{2}$ h bird travels $\frac{3}{2} \times 60 = 90$ km

11. Let there be l steps in the escalator and x be the speed (in steps/second)of escalator, then

$$\frac{l}{(5+x)} = 10 \quad \text{and} \quad \frac{l}{(5-x)} = 40$$

then $$\frac{5+x}{(5-x)} = \frac{40}{10} \Rightarrow x = 3$$

$\therefore$ Number of steps in the escalator $= l = 8 \times 10 = 80$

12. Let the radius be r, then difference in the distance

$$= (\pi r - 2r) = r(\pi - 2)$$

$$= r\left(\frac{22}{7} - 2\right) = 60 \times 3$$



$$\Rightarrow \quad 2r = 315 \text{ m}$$

[$\pi r \rightarrow$ semiperimeter and $2r \rightarrow$ diameter]

13. Time taken by trains to collide $= \frac{560}{70} = 8$ h

In 8 h sparrow will cover $8 \times 80 = 640$ km

14.



In 18 h plane will cover $18 \times 120 = 2160$ km

Now, $2160 = (600 \times 2) + 600 + 360$

So, the plane will be 360 km away from Kargil it means it will be 240 km (600 − 360) away from Pukhwara.

15.

	First hour	Second hour	Third hour	Total
Initial speed	x	$3x$	$2x$	$6x$
New speed	$3x$	$3x$	$3x$	$9x$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore$ Percentage increase in speed $= \frac{3x}{6x} \times 100 = 50\%$

Since speed is increased by (50%) $\frac{1}{2}$.

Therefore, time will reduce by (33.33%) $\frac{1}{3}$.

16. P ——— Q

They will be together at every two hours. Therefore in 12 h they will be (6 + 1) = 7 times together at P and they will never meet altogether at Q.

17.

Mathura — Kurukshetra — Hastinapur

400 km | 300 km

700 km

Consider only one person either Arjun or Srikrishna since their speed is same and move together.

Now, the distance covered by Arjun and Abhimanyu is in the ratio of their speeds. So, Arjun will cover 500 km to meet Abhimanyu and thus Arjun has to return back 100 km for Kurukshetra. Therefore, Arjun will cover total 600 km distance.

18. Total time $= \frac{600}{25} = 24$ h

19.

A ——— C

A ——— B

D ——— C

D ——— (direction)

A is the starting point of journey.

B is the destination.

$C \rightarrow$ where Salman has got off.

$D \rightarrow$ where Priyanka picks up Akshay

Let $AD = l$ and $BC = k$ and $CD = x$

then $$\frac{CD + DB}{BC} = \frac{50}{10}$$

$$\frac{2x + k}{k} = \frac{5}{1}$$

$$\Rightarrow \quad \frac{x}{k} = \frac{2}{1}$$

Again $$\frac{AC + CD}{AD} = \frac{50}{10}$$

$$\frac{2x + l}{l} = \frac{5}{1}$$

$$\Rightarrow \quad \frac{x}{l} = \frac{2}{1}$$

$$\Rightarrow \quad x = 2k = 2l \quad \text{or} \quad k = l = \frac{x}{2}$$

$$\therefore \quad k + x + l = 120$$

$\Rightarrow$ $k = 30$ km, $x = 60$ km and $l = 30$ km

Total distance travelled $= AC + CD + DB$

$$= l + x + x + x + k = 240 \text{ km}$$

$\therefore$ Time (required) $= \frac{240}{50} = 4.8$ h

20.

Barabanki ——— Fatehpur

300

120 | 180

Let the speeds of Ajai, Kajol and Shahrukh be x, y and z respectively, then

$$\frac{y}{x} = \frac{180}{120} \Rightarrow x = \frac{2y}{3}$$

Note Kajol is faster since she covers 180 km while Ajai covers only 120 km in the same time.

Shahrukh meets Kajol 1.5 hours after Shahrukh himself starts and 2.5 hours after Kajol starts.

Hence, $$2.5y + 1.5z = 300$$

$$\Rightarrow \quad z = \frac{600 - 5y}{3}$$

Since $z \geq (y + 20) \Rightarrow \frac{600 - 5y}{3} \geq (y + 20)$

$$\Rightarrow \quad y \leq 67.5$$

or $$x \leq 45 \text{ km/h}$$

21. Let t be the time after Kajol starts, when she meets Ajai, then

$$t = \frac{300}{(x + y)}$$

This should be less than 2.5 or $(x + y) > 120$

Since $$y = \frac{3x}{2} \Rightarrow y > 72$$

This $(y > 72)$ is greater than 67.5 km/h and hence Shahrukh will always overtake Ajai before he meets Kajol.

22. Speed of Raghupati $(R_P) = 60$ km/h

Speed of Raghav $(R_V) = 36$ km/h

Speed of Raja Ram $(RR) = 18$ km/h



$AB = AC = BC$

Time taken to cover AB by (RR) is 2 hours

$\therefore$ Time taken to cover AB by Raghav is 1 hour

$\therefore$ Time taken to cover AB by Raghupati = 36 min

$$\left(t_{RP} : t_{RV} : t_{RR} = \frac{1}{S_{RP}} : \frac{1}{S_{RV}} : \frac{1}{S_{RR}}\right)$$

$t \rightarrow$ Time, $S \rightarrow$ Speed

$$AB = 2 \times 18 = 36 \text{ km}$$

23. Time $= \frac{3 \times 36}{60} = \frac{9}{5}$ h $= 1$ h 48 min

24. Distance from Barelley $= \frac{60}{(60 + 18)} \times 36$

$$= \frac{360}{13} = 27\frac{9}{13} \text{ km}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

25.



Since the speed of bike and walking are different. So, two people partially travelled by bike and rest by walking since all the three persons take equal time to reach the destination. It means initially Mohan will carry either Namit or Pranav to a point A, then this person reach to H by walking and Mohan return to B where he will pick up the third person and reach at H at the same time as the second person.

Let $SB = k$, $AB = x$ and $AH = l$

Now, $$\frac{SA + AB}{SB} = \frac{36}{6}$$

$$\frac{2x + k}{k} = \frac{6}{1}$$

$$\Rightarrow \quad \frac{x}{k} = \frac{5}{2}$$

and $$\frac{AB + BH}{AH} = \frac{36}{6}$$

$$\Rightarrow \quad \frac{2x + l}{l} = \frac{6}{1}$$

$$\Rightarrow \quad \frac{x}{l} = \frac{5}{2}$$

$$\therefore \quad x : k : l = 5 : 2 : 2$$

$$\Rightarrow \quad x + k + l = 180$$

$$\Rightarrow \quad x = 100, \quad k = 40 \quad \text{and} \quad l = 40 \text{ km}$$

Total distance travelled by bike $= SA + AB + BH$

$$= k + 3x + l = 380 \text{ km}$$

26. $$\frac{2x + k}{k} = \frac{42}{6} = \frac{7}{1}$$

$$\Rightarrow \quad \frac{x}{k} = \frac{3}{1}$$

Similarly $$\frac{x}{l} = \frac{3}{1}$$

$$\therefore \quad x : k : l = 3 : 1 : 1$$

$$\therefore \quad x = 108, \quad k = 36, \quad l = 36 \text{ km}$$

Total distance travelled $= k + 3x + l = 396$ km

$$\therefore \quad \text{Required time} = \frac{396}{42} = 9\frac{3}{7} \text{ h}$$

27. Let the buses leave from both the stations at time intervals of T, then the distance between any two consecutive buses coming opposite to me = the distance betwen any two consecutive buses coming in the same direction as me = VT. (where V is the velocity of the buses)

Let the speed of walking be W, then

$$\frac{VT}{V + W} = 20 \quad \text{and} \quad \frac{VT}{V - W} = 30$$

$$\therefore \quad \frac{V + W}{V - W} = \frac{30}{20} = \frac{3}{2}$$

$$\Rightarrow \quad \frac{V}{W} = \frac{5}{1}$$

$$\therefore \quad \frac{VT}{V + W} = 20$$

$$\Rightarrow \quad \frac{5}{6} \times T = 20$$

$$\Rightarrow \quad T = 24 \text{ min}$$

28. Time taken by Abhinav = 36 h

Ideal time required by Abhinav $= \frac{600}{25} = 24$ h

It means Abhinav rests for $(36 - 24) = 12$ h

Now, the required time for Brijesh $= \frac{600}{30} = 20$ h

But Brijesh utilised those 12 hours in which Abhinav rests, so he needs only $(20 - 12) = 8$ hours extra.

Thus, the total time taken by Brijesh $= 36 + 8 = 44$ h

29. Downstream (Steamer) = 40 min

Downstream (Boat) = 60 min

Upstream (Steamer) = 60 min

Upstream (Boat) = 90 min

Required time = 40 + 30 + 45 = 115 min

30.



These two trains meet only at P and L i. e., there are only two points.

31. For the first meeting they have to cover only $2x + x = 3x$ distance and for the further meeting for each next meeting they have to cover $6x$ distance together.

Distance covered by A	$2x$	$2x$	$4x$	$2x$
Distance covered by B	x	$4x$	$2x$	$4x$
Point of meeting	P	L	P	P
Total distance travelled	$3x$	$6x$	$6x$	$6x$

when A and B meet at P for the third time A goes $10x$ and B goes $11x$.

Thus, the required ratio = 10 : 11

32.



1 hr

Speed	Time
$\frac{1}{6}\downarrow$	$\frac{1}{5}\uparrow = 36$ min

$\Rightarrow$ actual time required to cover x km is $5 \times 36 = 180$ min



1 hr

Speed	Time
$\frac{1}{6}\downarrow$	$\frac{1}{5}\uparrow = 20$

$\Rightarrow$ actual time required for $(x - 80)$ km $= 5 \times 20 = 100$ min

It means he can move $= x - (x - 80) = 80$ km in

Scanned by CamScanner

yourSmartbook.wordpress.com

$$(180 - 80) = 80 \text{ min}$$

It means his actual speed = 60 km/h

Thus, the total distance from his home to his office

$$= 60 \times 1 + 60 \times 3 = 240 \text{ km}$$

NOTE Since 1 hour he lost at the place of accident, so the actual delay due to reduced speed is always 1 hour less than it is found to be in both the cases.
It means due to reduced speed he becomes late only 36 minutes and 20 minutes in respective cases.

33. $$\frac{\text{Speed of wind (Sound)}}{\text{Relative speed of soldier and terrorist}} = \frac{\text{Time utilised}}{\text{Difference in time}}$$

$$\frac{1188}{x} = \frac{330}{5}$$

$$\Rightarrow \quad x = 18 \text{ km/h}$$

34. In case of increasing gap between two objects.

$$\frac{\text{Speed of sound}}{\text{Speed of tiger}} = \frac{\text{Time utilised}}{\text{Difference in time}}$$

$$\frac{1195.2}{x} = \frac{83}{7}$$

$$\Rightarrow \quad x = 100.8 \text{ km/h}$$

35. In 20 minutes the difference between man and his son

$$= 20 \times 20 = 400 \text{ m}$$

Distance travelled by dog when he goes towards son

$$= \frac{400}{40} \times 60$$

= 600 m and time required is 10 minutes

In 10 minutes the remaining difference between man and son.

$$400 - (20 \times 10) = 200 \text{ m}$$

NOTE Relative speed of dog with child is 40 km/h and the same with man is 100 km/h.

Time taken by dog to meet the man $= \frac{200}{100} = 2$ min

In 2 min the remaining distance between child and man

$$200 - (2 \times 20) = 160 \text{ m}$$

Now, the time taken by dog to meet the child again

$$= \frac{160}{40} = 4 \text{ min}$$

In 4 minutes he covers $4 \times 60 = 240$ m distance while going towards the son.

In 4 minute the remaining distance between man and child

$$= 160 - (4 \times 20) = 80 \text{ m}$$

Time required by dog to meet man once again

$$= \frac{80}{100} = 0.8 \text{ min}$$

In 0.8 min remaining distance between man and child

$$= 80 - (0.8 \times 20) = 64 \text{ m}$$

Now, time taken by dog to meet the child again

$$= \frac{64}{40} \times \frac{8}{5} \text{ min}$$

$$\therefore \quad \text{Distance travelled by dog} = \frac{8}{5} \times 60 = 96 \text{ m}$$

Thus, we can observe that every next time dog just go 2/5th of the previous distance to meet the child in the direction of child.

So, we can calculate the total distance covered by dog in the direction of child with the help of GP formula.

Here, first term (a) = 600 and common ratio (r) $= \frac{2}{5}$

$\because$ Sum of the infinite GP $= \frac{a}{1-r}$

$$= \frac{600}{\left(1 - \frac{2}{5}\right)} = \frac{600}{3/5} = 1000 \text{ m}$$

36. Let Amarnath express takes x hours, then Gorakhnath express takes $(x - 2)$ hours.

$$\therefore \quad \frac{1}{x} + \frac{1}{(x-2)} = \frac{60}{80}$$

$$\Rightarrow \quad x = 4 \text{ h}$$

37. Distance travelled by them in first hour = 12 km

Distance travelled by them in second hour = 13 km

Distance travelled by them in third hour = 14 km and so on

Thus, in 9 hours they will cover exactly 144 km and in 9 h each will cover half-half the total distance.

$(8 \times 9 = 72$ and $4 + 5 + 6 + 7 + 8 + 9 + 10 + 11 + 12 = 72)$

38. Speed of tiger = 40 m/min

Speed of deer = 20 m/min

Relative speed = 40 − 20 = 20 m/min

Difference in distances = $50 \times 8 = 400$ m

$\therefore$ Time taken in overtaking (or catching) $= \frac{400}{20} = 20$ min

$\therefore$ Distance travelled in 20 min = $20 \times 40 = 800$ m

39. The sum of their speeds $= \frac{615}{15} = 43$ km/h

Notice that they are actually exchanging their speeds. Only then they can arrive at the same time at their respective destinations. It means the difference in speeds is 3 km/h.

Thus, $\quad x + (x + 3) = 43$

$\Rightarrow \quad x = 20$ and $x + 3 = 23$

The concept is very similar to the case when after meeting each other they returned to their own places of departure. It can be solved through option also.

40. Let Pele covers x km in 1 hour. So Maradona takes (2 h − 40 min) = 1 h 20 min to cover x km. Let speed of Maradona and Pele be M and P respectively than

$$x = M \times \frac{4}{3} \quad \text{and} \quad x = P \times 1$$

$$\Rightarrow \quad \frac{M}{P} = \frac{3}{4}$$

Again $\quad \frac{300}{M} - \frac{300}{P} = 1$

Scanned by CamScanner

yoursmanboob.wordpress.com

$\Rightarrow \quad \frac{300}{3k} - \frac{300}{4k} = 1$

$\Rightarrow \quad k = 25$

$\Rightarrow \quad M = 3k = 75$ km/h

and $\quad P = 4k = 100$ km/h

(Through option it is very easy to solve.)

41. Initial speed of police = 10 m/s
Increased speed of police = 20 m/s
Speed of thief = 15 m/s
Initial difference between thief and police = 250 m
After 5 seconds difference between thief and police

$= 250 - (5 \times 10) = 200$ m

After 10 seconds more the difference between thief and police $= 200 + (5 \times 10) = 250$ m.
Now, the time required by police to catch the thief

$= \frac{250}{5} = 50$ s

Distance travelled $= 50 \times 20 = 1000$ m

Total time $= 50 + 15 = 65$ s

Total distance $= 1000 + (15 \times 10) = 1150$ m

42.



$\frac{100 + \frac{x}{2}}{100} = \frac{100 + x}{(100 + x - 150)}$

$= \frac{\text{Speed of Bajrang}}{\text{Speed of Angad}}$

$\frac{200 + x}{200} = \frac{(100 + x)}{(x - 50)}$

$\Rightarrow \quad (200 + x)(x - 50) = 200(100 + x)$

$\Rightarrow \quad x^2 + 150x - 10000 = 20000 + 200x$

$\Rightarrow \quad x^2 - 50x - 30000 = 0$

$\Rightarrow \quad (x - 200)(x + 150) = 0$

$\Rightarrow \quad x = 200$ km

Therefore distance between Ayodhya and Banaras is 300 km since $AB = BC = AC$.
(With the help of trigonometry we can find the value of PC in terms of x i. e., $\cos 60° = \frac{PC}{QC} = \frac{1}{2}$. Hence $PC = \frac{x}{2}$)

43. Basically they will exchange their speeds just after half of the time required for the whole journey. It means after covering 210 km distance they will exchange their speeds.
Check it out graphically for more clarification.

44. The ratio of speeds
= The ratio of distances, when time is constant
∴ The ratio of distances covered by leopard to the tiger = 12 : 25
Again, ratio of rounds made by leopard to the tiger = 12 : 25
Hence, leopard makes 48 rounds, when tiger makes 100 rounds.

45. Length of $DC = \frac{6000}{13}$ (for this, refer geometry section)

Total distance covered in the returning by Jai

$= AD + CD$

$= \frac{2500}{13} + \frac{6000}{13} = \frac{8500}{13}$ km

Required time $= \frac{8500/13}{500/13} = 17$ h

Total distance covered by Jaya while returning

$= BD + DC$

$= \frac{14400}{13} + \frac{6000}{13}$

∴ Required time $= \frac{20400/13}{1200/13} = 17$

Hence, both will reach at the same time.
Alternatively: Since the ratio of speeds is same as that of distances. So, they will take same time to reach the home.

46. The distance of route $ADC = \frac{8500}{13}$

and the distance of route $BNC = 1300$

and the time taken by Jai is $\frac{8500/13}{500/13} = 17$ h

and the time taken by Jaya is $\frac{1300}{1200/13} = \frac{169}{12}$ h $= 14\frac{1}{12}$ h

$= 14$ h 05 min

Hence, option (c) is correct.

47. Time saved in percentage $= \frac{175}{1020} \times 100 = 17.15\%$

48. Husband takes 17 hours and she takes 14 h 05 min + 3h
$= 17$ h 05 min
So, she becomes late by 05 min than her husband.

49. $x^2 + (x + 100)^2 = (500)^2$ (Using Pythagorus theorem)

$\Rightarrow \quad x = 300$ km

Now, let they change their speeds after t_1 hours and then the rest time is t_2 then

$30t_1 + 40t_2 = 800$ ...(i)

$40t_1 + 30t_2 = 900$ ...(ii)

Solving Eq. (i) and (ii), we get

$t_1 = \frac{120}{7}$ and $t_2 = \frac{50}{7}$

50. Since it moves only one radian on every path and it has to move 2π radian to reach directly eastward. Hence, it has to run on more than 6 paths i. e., the last path is 7th one (or P_7)
(∵ $n \times 1$ radian $\geq 2\pi$ radian)

$\Rightarrow \quad n \geq 2\pi$

Scanned by CamScanner

yoursmahboob.wordpress.com

or $n = 7$, for interger values

Hence, option (c) is correct.

51. Since it stops directly eastward of the shop so the total distance covered so for

$$= 7 + (1 + 2 + 3 + 4 + 5 + 6 + 2) = 30 \text{ km}$$

NOTE Total radial movement = 7 km
Again on the last path it will move only 2 km.

Actually it has to cover total 2π radian distance but on 6 paths it covers only 6 radian hence the remaining distance which will be covered on the 7th path i. e., $2\pi - 6$

$$= 2 \times \frac{22}{7} - 6 = \frac{2}{7} \text{ radian}$$

But, the radius of the last path (i. e., P_7) = 7 km

Hence, the distance covered in km $= \frac{2}{7} \times 7 = 2$ km

$$\left(\theta = \frac{\text{Arc}}{\text{Radius}}\right)$$

Thus, on the last path it moves only 2 km. Hence, (a) is the correct choice.

52. The ratio of distance covered on P_2 and $P_7 = \frac{2}{2} = \frac{1}{1}$

53. Since it is clear from the statement itself that ΔAOB is a right angle triangle and further OP must be perpendicular to AB then we can find that $AO = 30$ km and $BO = 40$ km by using Pythogorus theorem and its corrollaries.



HINT

$$OP^2 = OA^2 - AP^2$$

$$\therefore \quad OP^2 = 900 - x^2$$

and $$OB^2 = OP^2 + BP^2$$

$$\therefore \quad OB^2 = 900 - x^2 + 1024$$

and $$AB^2 = OA^2 + OB^2$$

$$\therefore \quad (x + 32)^2 = 900 + 900 - x^2 + 1024$$

$$\Rightarrow \quad x = 18 \text{ km}$$

Hence, $AP = 18$, $OA = 30$ and $OB = 40$ and $OP = 24$ km

Now, since jackal and cat reaches A at the same time, so the ratio of speeds = ratio of distances covered by them.

$$\therefore \quad \frac{\text{Speed of Jackal}}{\text{Speed of cat}} = \frac{30}{18} = \frac{5}{3}$$

54. Again, since jackal and train both arrive at A at the same time and let the train was x km away from A, before entering into the tunnels, *i.e.*, when it makes a whistle then the ratio of distances covered by train and jackal.

$$= \frac{x}{30} = \frac{x + 50}{40}$$

$$\Rightarrow \quad x = 150 \text{ km}$$

Thus, the ratio of speeds of Jackal is to train is 1 : 5.

55. Since, when the train arrive at A, the jackal can move 30 km. So, at the time when train is at A the jackal will cover 6 km from P on PA in addition to 24 km at OP. Now, the rest distance at AP is 12 km this remaining distance will be covered by train and jackal according to their respective speeds.

So, distance covered by train $= 12 \times \frac{5}{6} = 10$ km

and distance covered by jackal $= 12 \times \frac{1}{6} = 2$ km

Hence, jackal will meet with train at M_1 which is 10 km away from A (inside AB).

NOTE It can be solved using options in lesser time.

56. It is obvious from the path of cat that if cat moves in the POA direction it will never meet with accident and now jackal follows the path OPB. Again when the train is at A then jackal will cover 30 km (*i. e.*, 24 (OP) + 6 km on PB).
So, the ratio of distances covered by jackal is to train = ratio of their respective speeds.
Now let the jackal and train meet each other at AB, $(6 + x)$ km away from P towards B, then

$$\frac{x}{24 + x} = \frac{1}{5}$$

$$\Rightarrow \quad 4x = 24 \quad \Rightarrow \quad x = 6$$

Hence, train meets with jackal at $(18 + 6 + 6) = 30$ km away from A.

Alternatively: $\frac{150 + 18 + 6 + x}{30 + x} = \frac{5}{1} \Rightarrow x = 6$

Hence, $18 + 6 + 6 = 30$ km.
Thus, option (b) is correct.

57. The ratio of time taken by cat and jackal $= \frac{72/3}{96/5} = \frac{5}{4}$

Hence, option (c) is correct.

58.

$$(6 - x) = (8 - 1.5x)$$

$$\Rightarrow \quad x = 4 \text{ cm}$$

So, it will take 4 hours to burn in such a way that they remain equal in length.

59. Total distance covered by them when they meet = $2W$

and $$\text{Total time} = \frac{2W}{b_1 + b_2}$$

$$\therefore \quad d_1 = \frac{2W}{(b_1 + b_2)} b_1 \quad \text{and} \quad d_2 = \frac{2W}{(b_1 + b_2)} b_2$$

60. Let the speed of boat be B and that of river be R. In 12 minutes the distance between boat and hat

$$= 12(B - R) + 12R = 12B$$

Now time taken by boat to reach to the hat

$$= \frac{12B}{(B + R) - R} = 12 \text{ min}$$

Total time = 24 min

Scanned by CamScanner

yourshanboob.wordpress.com

In 24 minutes had flown off = 3 km

$\therefore \quad \frac{24}{60} \times R = 3$

$\Rightarrow \quad R = 7.5$ km/h

61. Akbar meets Birbal once $\frac{500}{20-15} = 100$ s

Birbal meets Chanakya once $= \frac{500}{20+25} = 11\frac{1}{9}$ s

Akbar meets Chanakya once $= \frac{500}{15+25} = 12.5$ s

62. Time taken by them to meet $= \frac{600}{30-20} = 60$ s

Time taken to meet 5th time $= 5 \times 60 = 300$ s

Total duration of race $= \frac{3000}{30} = 100$ s

So, they will not meet 5th time in the race of 3000 metre.

63. Length of the track $= 2 \times \frac{22}{7} \times 175 = 1100$ m

Distance to be covered for the first meeting = 550 m

Speed of Akkal $= \frac{1100}{100} = 11$ m/s

Speed of Bakkal $= \frac{1100}{50} = 22$ m/s

Time taken from the start of the first meeting

$= \frac{550}{(11+22)} = \frac{50}{3}$ s

Time taken for Akkal and Bakkal to meet again at Love point = LCM of times taken by them to go around the track once.

= LCM of $\frac{1100}{11}$ and $\frac{1100}{22}$

= LCM of 100 and 50

= 100 s

So, the total required time $= \frac{50}{3} + 100 + 100$

$= \frac{650}{3} = 216\frac{2}{3}$ s

64. Since both rest for 6 seconds so when B is just about to start the journey A reaches there at the shallow end so they meet at they shallow end.

65. B runs around the track in 10 min.

i. e., Speed of B = 10 min per round

$\therefore$ A beats B by 1 round

Time taken by A to complete 4 rounds

= Time taken by B to complete 3 rounds

= 30 min

$\therefore$ A's speed $= \frac{30}{4}$ min per round

= 7.5 min per round

Hence, if the race is only of one round A's time over the course = 7 min 30 sec.

66. The ratio of speeds of $A, B, C = \frac{10}{49} : \frac{9}{50} : \frac{8}{51}$

Hence, A is the fastest.

67. Speed of this car $= \frac{400+200}{20} \times \frac{18}{5}$ km/h

= 108 km/h

68. The speeds of two persons is 108 km/h and 75 km/h. The first person covers 1080 km in 10 hours and thus he makes 12 rounds. Thus, he will pass over another person 12 times in any one of the direction.

69. Angle between two hands at 3 : 10 am

$= (90 + 5) - 60 = 35°$

So, the required angle = 70°, after 3 : 10 am

Total time required to make 70° angle when minute-hand is ahead of hour-hand.

$= \frac{90+70}{11/2} = \frac{320}{11}$ min

So, at 3 h $\frac{320}{11}$ min the required angle will be formed.

Alternatively: Check through options.

70. For the first watch: When a watch creates the difference of 12 hours, it shows correct time.

So to create the difference of 12 h required time

$= \frac{60 \times 12}{24} = 30$ days

For the second watch: To create the difference of 12 h required time

$= \frac{30 \times 12}{24} = 15$ days

So, after 30 days at the same time both watches show the correct time.

HINT Take the LCM of 30 and 15.

71. To show the same time together the difference between two watches must be 12 h.

Now, since they create 3 min differnce in 1 h

So they will create 12 h differnce in $\frac{1}{3} \times \frac{12 \times 60}{24}$

= 10 days later

72. To show the correct time again, watch must create 24 h difference. (Since in one round hour-hand covers 24 h.)

So, the required time $= \frac{4}{3} \times \frac{60 \times 24}{24} = 80$ day

73. $(n + 1)$ times in $n$days

74. Actually the watch gains (12 + 16)

= 28 min in $7 \times 24 \times 60$ min.

Thus, it gains 1 min in 360 minutes.

Therefore, it will gain (12 + 8) min in $\frac{20 \times 360}{60 \times 24} = 5$ day

Hence, (h) is the correct choice.

Scanned by CamScanner

yoursmahboob.wordpress.com

75. Actually they create a difference of 3 min per hour and the two watches are showing a difference of 66 minutes. Thus, they must have been corrected 22 hours earlier.
Now, the correct time can be found by comparing any one of the watch.
Since, second watch gains 1 min in 1 hour so it will must show 22 min extra than the correct time in 22 hours.
Hence, the correct time can be found by subtracting 22 min from 10 : 06.
Hence, (d) is the correct answer.

NOTE For quick answer go through options.

76. Incorrect watch covers 1452 min in 1440 min

So, it will cover 1 min in $\frac{1440}{1452}$ min

Therefore it will cover 4840 min in $\frac{1440}{1452} \times 4840$

$= 4800$ min

$= 80$ h

Therefore 80 h = 3 days and 8 h.

77. You must know that a correct watch coincide just after $65\frac{5}{11}$ min.

Therefore in every $65\frac{5}{11}$ hours the watch gains $\frac{2}{11}$.

Hence, in 24 hours it will gain $\frac{2}{11} \times \frac{11}{720} \times 24 \times 60 = 4$ min

78. In 72 hours my watch gains $(8 + 7) = 15$ min. To show the correct time watch must gain 8 minutes.
Since the watch gains 15 min in 72×60 min.
Therefore, the watch will gain 8 min in $\frac{72 \times 60 \times 8}{15}$ min

$$= \frac{72 \times 60 \times 8}{15} = 38 \text{ h } 24 \text{ min}$$

Hence, (a) is the correct choice.

80. To exchange the position both hands to cover 360° together.
In one minute, hour-hand moves $\frac{1^\circ}{2}$ and in one minute, minute-hand moves 6°. Let the required time be t min, then

$$6t + \frac{1}{2}t = 360$$

$$\Rightarrow \quad t = \frac{360}{13} \times 2 = \frac{720}{13} = 55\frac{5}{13} \text{ min}$$

❑❑❑

Scanned by CamScanner

yoursmahboob.wordpress.com

10 MENSURATION

It is one of the easiest chapters which contributes almost 6-8% problems in Quantitative Aptitude Section of CAT. Besides there are several other aptitude tests which includes plethora of questions from this topic itself. Therefore it is advised that those students who are not so good in other sections such as algebra or sort of logical questions they must emphasise on this chapter. Even the questions asked from this chapter are not as much complex as in Geometry.

Definition : Mensuration is a science of measurement of the lengths of lines, areas of surfaces and volumes of solids.

Planes : Planes are two dimensional *i.e.* these two dimensions are namely length and breadth. These occupy surface.

Solids : Solids are three dimensional, namely length, breadth and height. These occupy space.

CONVERSION OF SOME IMPORTANT UNITS

1 km = 10 hectometre = 100 decametre
= 1000 metre = 10,000 decimetre
= 1,00,000 centimetre = 10,00,000 millimetre
1 hectare = 10,000 square metre
1 are = 100 square metre
1 square hectometre = 100 square decametre
1 square decametre = 100 square metre
1 square metre = 100 square decimetre
1 square decimetre = 100 square centimetre
1 square centimetre = 100 square millimetre

$\sqrt{2} = 1.414$, $\sqrt{3} = 1.732$,
$\sqrt{5} = 2.236$, $\sqrt{6} = 2.45$

Weight = Volume × density

2-D Figures (Plane figures)

S. No.	Name	Figure	Nomenclature	Area	Perimeter
1.	Rectangle		$l \rightarrow$ length $b \rightarrow$ breadth	$l \times b = lb$	$2l + 2b = 2(l + b)$
2.	Square		$a \rightarrow$ side $d \rightarrow$ diagonal $d = a\sqrt{2}$	(i) $a \times a = a^2$ (ii) $\frac{d^2}{2}$	$a + a + a + a = 4a$
3.	Triangle (Scalene)		a, b and c are three sides of triangle and s the semiperimeter, where $s = \left(\frac{a+b+c}{2}\right)$ b is the base and h is the altitude of triangle	(i) $\frac{1}{2} \times b \times h$ (ii) $\sqrt{s(s-a)(s-b)(s-c)}$ (Hero's formula)	$a + b + c = 2s$

Scanned by CamScanner

yoursmahboob.wordpress.com

S. No.	Name	Figure	Nomenclature	Area	Perimeter
4.	Equilateral triangle		$a \rightarrow$ side $h \rightarrow$ height or altitude $h = \frac{\sqrt{3}}{2}a$	(i) $\frac{1}{2} \times a \times h$ (ii) $\frac{\sqrt{3}}{4}a^2$	$3a$
5.	Isosceles triangle		$a \rightarrow$ equal sides $b \rightarrow$ base $h \rightarrow$ height or altitude $h = \frac{\sqrt{4a^2 - b^2}}{2}$	(i) $\frac{1}{2} \times b \times h$ (ii) $\frac{1}{4} \times b \times \sqrt{4a^2 - b^2}$	$2a + b$
6.	Right angled triangle		$b \rightarrow$ base $h \rightarrow$ altitude/height $d \rightarrow$ diagonal $d = \sqrt{b^2 + h^2}$	$\frac{1}{2} \times b \times h$	$b + h + d$
7.	Isosceles right angled triangle		$a \rightarrow$ equal sides $d \rightarrow$ diagonal $d = a\sqrt{2}$	$\frac{1}{2}a^2$	$2a + d$
8.	Quadrilateral		AC is the diagonal and h_1, h_2 are the altitudes on AC from the vertices D and B respectively	$\frac{1}{2} \times AC \times (h_1 + h_2)$	$AB + BC + CD + AD$
9.	Parallelogram		a and b are sides adjacent to each other. $h \rightarrow$ distance between the parallel sides	$a \times h$	$2(a + b)$
10.	Rhombus		$a \rightarrow$ each equal side of rhombus d_1 and d_2 are the diagonals $d_1 \rightarrow BD$ $d_2 \rightarrow AC$	$\frac{1}{2} \times d_1 \times d_2$	$4a$
11.	Trapezium		a and b are parallel sides to each other and h is the perpendicular distance between parallel sides	$\left(\frac{a+b}{2}\right) \times h$	$AB + BC + CD + AD$

Scanned by CamScanner

yoursmahboob.wordpress.com

S. No.	Name	Figure	Nomenclature	Area	Perimeter
12.	Regular hexagon		$a \rightarrow$ each of the equal side	$\frac{3\sqrt{3}}{2}a^2$	$6a$
13.	Regular octagon		$a \rightarrow$ each of equal side	$2a^2(1+\sqrt{2})$	$8a$
14.	Circle		$r \rightarrow$ radius of the circle $\pi = \frac{22}{7} = 3.1416$ (approx)	πr^2	$2\pi r$ (called as circumference)
15.	Semicircle		$r \rightarrow$ radius of the circle	$\frac{1}{2}\pi r^2$	$\pi r + 2r$
16.	Quadrant		$r \rightarrow$ radius	$\frac{1}{4}\pi r^2$	$\frac{1}{2}\pi r + 2r$
17.	Ring or circular path (shaded region)		$R \rightarrow$ outer radius $r \rightarrow$ inner radius	$\pi(R^2 - r^2)$	(outer) $\rightarrow 2\pi R$ (inner) $\rightarrow 2\pi r$
18.	Sector of a circle		$O \rightarrow$ centre of the circle $r \rightarrow$ radius $l \rightarrow$ length of the arc $\theta \rightarrow$ angle of the sector $l = 2\pi r\left(\frac{\theta}{360^\circ}\right)$	(i) $\pi r^2\left(\frac{\theta}{360^\circ}\right)$ (ii) $\frac{1}{2} r \times l$	$l + 2r$
19.	Segment of a circle		$\theta \rightarrow$ angle of the sector $r \rightarrow$ radius $AB \rightarrow$ chord $ACB \rightarrow$ arc of the circle	Area of segment ACB (minor segment) $= r^2\left(\frac{\pi\theta}{360^\circ} - \frac{\sin\theta}{2}\right)$	$2r\left[\frac{\pi\theta}{360^\circ} + \sin\left(\frac{\theta}{2}\right)\right]$
20.	Pathways running across the middle of a rectangle		$l \rightarrow$ length $b \rightarrow$ breadth $w \rightarrow$ width of the path (road)	$(l + b - w)\,w$	$2(l+b) - 4w$ $= 2[l + b - 2w]$

Scanned by CamScanner

yoursmahboob.wordpress.com

S. No.	Name	Figure	Nomenclature	Area	Perimeter
21.	Outer pathways		$l \rightarrow$ length $b \rightarrow$ breadth $w \rightarrow$ widthness of the path	$(l+b+2w)2w$	(inner) $\rightarrow 2(l+b)$ (outer) $\rightarrow 2(l+b+4w)$
22.	Inner path		$l \rightarrow$ length $b \rightarrow$ breadth $w \rightarrow$ widthness of the path	$(l+b-2w)2w$	(outer) $\rightarrow 2(l+b)$ (inner) $\rightarrow 2(l+b-4w)$

RECTANGLES AND SQUARES

1. Area of a rectangle = Length × breadth = $l \times b$

2. Area of a square = $(\text{side})^2 = \frac{1}{2}(\text{diagonal})^2$

$= \frac{1}{2}d^2 = a^2$

3. Diagonal of a rectangle

$= \sqrt{(\text{length})^2 + (\text{breadth})^2} = \sqrt{l^2 + b^2}$

4. Diagonal of a square

$= \sqrt{\text{side}^2 + \text{side}^2} = \text{side}\sqrt{2} = a\sqrt{2}$

5. Perimeter of a rectangle

$= 2(\text{length} + \text{breadth}) = 2(l+b)$

6. Perimeter of a square $= 4 \times \text{side} = 4a$

7. Area of four walls of a room $= 2(l+b) \times h$

EXAMPLE 1 *The length and breadth of a rectangular room are 15 m and 8 m respectively :*

(a) Find the perimeter of room.

(b) Find the area of the floor of room.

(c) Find the maximum possible length of the rod that can be put on the floor.

SOLUTION (a) Perimeter $= 2(15+8) = 46$ m

(b) Area of floor $= 15 \times 8 = 120$ m^2

(c) Length of diagonal $= \sqrt{(15)^2 + (8)^2} = 17$ m

NOTE The maximum possible length of any rod that can be placed on a rectangular floor is equal to the diagonal of the floor of the room.



Here $d > l$

EXAMPLE 2 *The side of a square shaped garden is 20 m. Find the :*

(a) area of the garden

(b) perimeter (or boundary) of the garden

(c) maximum possible distance between any two corners of the garden.

SOLUTION (a) Area $= (\text{side})^2 = (20)^2 = 400$ m^2 (square metre)

(b) Perimeter $= 4 \times \text{side} = 4 \times 20 = 80$ m

(c) Diagonal $= \text{side}\sqrt{2} = 20 \times \sqrt{2}$

$= 20 \times 1.414 = 28.28$ m

EXAMPLE 3 *One side of a rectangular lawn is 12 m and its diagonal is 13 m. Find the area of the field.*

SOLUTION $d = \sqrt{l^2 + b^2} \Rightarrow 13 = \sqrt{12^2 + b^2}$

$\Rightarrow b = 5$ m

$\therefore$ Area $= l \times b = 12 \times 5 = 60$ m^2

EXAMPLE 4 *The length of a rectangle is 1 cm more than its breadth. The diagonal is 29 cm. Find the area of the rectangle.*

(a) 481 cm^2 *(b) 841 cm^2*

(c) 420 cm^2 *(d) 870 m^2*

SOLUTION $l = (b+1)$

and $d = \sqrt{l^2 + b^2} = \sqrt{(b+1)^2 + b^2} = 29$

$\Rightarrow b^2 + b = 420$

$\Rightarrow b = 20$

$\therefore l = 21$

$\therefore$ Area $= l \times b = 420$ cm^2

EXAMPLE 5 *The length of a wall is 5/4 times of its height. If the area of the wall be 180 m^2. What is the sum of the length and height of the wall?*

SOLUTION Let the length be $5x$ and height be $4x$

then $l \times h = 180 = 5x \times 4x = 20x^2$

$\Rightarrow x = 3$

$\therefore l + h = 15 + 12 = 27$

Alternatively : $1.25h^2 = 180$

Scanned by CamScanner

yourshahbaab.wordpress.com

$\therefore \Rightarrow \quad h = 12$ m

$\therefore \quad l = 15$ m

$l + h = 27$ m

EXAMPLE 6 *A rectangular grassy lawn is 18 m by 12 m. It has a gravel path 1.5 m wide all around it on the outside. What is the area of the path.*

SOLUTION Area of path (outside the lawn) $= (l + b + 2w)\,2w$

$= (18 + 12 + 3)\,3$

$= 99$ m^2



Alternatively :

Area of lawn $= 18 \times 12 = 216$ m^2

Total area (lawn + path) $= (18 + 3) \times (12 + 3)$

$= 21 \times 15 = 315$ m^2

$\therefore$ Area of path (only) $= 315 - 216 = 99$ m^2

EXAMPLE 7 *Find the cost of carpeting a room 17 m long and 9 m wide with a carpet 60 cm broad at 40 paise per metre.*

SOLUTION Area of carpet = Area of room

$l \times 0.6 = 17 \times 9$ (60 cm = 0.6 m)

$\Rightarrow \quad l = 255$ m

$\therefore$ Cost of carpeting the floor = rate × length of carpet

$= 0.4 \times 255 =$ Rs. 102.00

EXAMPLE 8 *The dimensions of a lawn are in the ratio 4 : 1 and its area is 1/4 hectares. What is the length of the lawn?*

SOLUTION $l \times b = 4x \times x = \frac{1}{4} \times 10{,}000$

$\Rightarrow \quad x = 25$

$\Rightarrow$ length $= 4x = 100$ m

EXAMPLE 9 *A room is 16 m long, 7 m broad and 8 m high. Find the cost of white washing the four walls of room at Rs. 7.5 per m^2, white washing is not to be done on the doors and windows, which occupy 65 m^2.*

SOLUTION Area of 4 walls of a room $= 2(16 + 7) \times 8 = 368$ m^2

Net area of 4 walls $= 368 - 65 = 303$ m^2

$\therefore$ Cost of white washing $= 303 \times 7.5 =$ Rs. 2272.5

EXAMPLE 10 *The ratio between the sides of a room is 5 : 3. The cost of white washing the ceiling of the room at 50 P per square m is Rs. 270 and the cost of papering the walls at 10 P per square metre is Rs. 48. The height of the room is :*

(a) 6 m (b) 8 m (c) 5 m (d) 10 m

SOLUTION Area of ceiling $= \frac{\text{Total cost}}{\text{cost of 1 sq. unit}}$

$= \frac{270}{0.5} = 540$ sq. m

Now since $l : b = 5x : 3x$

$\Rightarrow \quad l \times b = 15x^2 = 540$ m^2

$\Rightarrow \quad l = 30$ and $b = 18$ m

Now, Area of the 4 walls $= \frac{\text{Total cost}}{\text{Cost of 1 sq. unit}} = \frac{48}{0.1} = 480$ m^2

$\therefore \quad$ Height $= \frac{480}{2(30 + 18)} = 5$ m

INTRODUCTORY EXERCISE-10.1

1. A rectangular field has its length and breadth in the ratio of 16 : 9. If its perimeter is 750 cm. What is its area?
   (a) 7500 cm^2 (b) 32400 cm^2
   (c) 14400 cm^2 (d) 14000 cm^2
2. A rectangular field costs Rs. 110 for levelling at 50 paise per square metre. If the ratio of length : breadth is 11 : 5. Find the length of the field :
   (a) 16 m (b) 21 m
   (c) 22 m (d) none of these
3. A room is half as long again as it is wide. The cost of carpeting it at 62 paise per square metre is Rs. 2916.48. Find the cost of white washing the ceiling at 30 paise per metre :
   (a) Rs. 2211.5 (b) Rs. 1114.2
   (c) Rs. 1411.2 (d) can't be determined
4. The length of a rectangular plot of ground is four times its breadth and its area is 4 hectares. How long will it take to a dog to walk round it at the rate of 3 km/hr?
   (a) 12 min (b) 20 min
   (c) 21 min (d) 18.5 min
5. Find the length of the wire required to fence a square field 6 times having its area 5 hectares and 76 ares :
   (a) 5760 m (b) 6760 m
   (c) 52500 m (d) 11760 m
6. A room is 19 m long and 3.50 m broad. What will be the cost of covering its floor with a carpet of 70 cm wide at 95 paise per metre?
   (a) Rs. 90.25 (b) Rs. 99.25
   (c) Rs. 90.75 (d) none of these
7. Find the cost of paving a courtyard 316.8 m × 65 m with stones measuring 1.3 m × 1.1 m at Rs. 0.5 per stone :
   (a) Rs. 1440 (b) Rs. 7200
   (c) Rs. 72,000 (d) none of these
8. A rectangular garden 63 m long and 54 m broad has a path 3 m wide inside it. Find the cost of paving the path at Rs. 37/2 per square metre :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) Rs. 12321 (b) Rs. 11100
(c) Rs. 74000 (d) none of these

9. If the length of a rectangular field is doubled and its breadth is halved (*i.e.*, reduced by 50%). What is percentage change in its area?
(a) 0% (b) 10%
(c) 25% (d) 33.33%

10. A path of uniform width runs all around the inside of rectangular field 116 m by 68 m and occupies 720 sq. m. Find the width of the path :
(a) 1 m (b) 1.5 m
(c) 2 m (d) 4 m

11. A drawing room is 7.5 m long 6.5 m broad and 6 m high. Find the length of paper 2.5 dm wide to cover its walls allowing 8 sq. m for doors :
(a) 368 m (b) 640 m
(c) 625 m (d) 888 m

12. A square field of 2 sq. km is to be divided into two equal parts by a wall which coincides with a diagonal. Find the length of the wall :
(a) $\sqrt{2}$ km (b) 1 km
(c) 4.2 km (d) 2 km

13. There are two square fields. Of the two square fields one contains 1 hectare area while the other is broader by 11 per cent. Find the difference in area expressed in sq. m :
(a) 2321 sq. m (b) 1210 sq. m
(c) 2121 sq. m (d) 7700 sq. m

14. The expenses of carpeting a half of the floor were Rs. 759, but if the length had been 6 m less than it was, the expenses would have been Rs. 561. What is the length?
(a) 21 m (b) 23 m
(c) 45 m (d) 27 m

15. If a roll of paper 1 km long has area 1/25 hectare, how wide is the paper?
(a) 4 m (b) 40 cm
(c) 40 dm (d) 25 cm

16. The diagonal and one side of a rectangular plot are 289 m and 240 m respectively. Find the other side :
(a) 237 m (b) 181 m
(c) 161 m (d) 159 m

17. How many tiles 20 cm by 40 cm will be required to pave the floor of a prayer hall of a room 16 m long and 9 m wide :
(a) 18000 (b) 2700
(c) 1800 (d) 14400

18. If the area of a square be 22050 sq. cm. Find the length of diagonal :
(a) 201 cm (b) 220 cm
(c) 211 cm (d) 210 cm

19. If requires 90 g paint for painting a door 12 cm × 9 cm, how much paint is required for painting a similar door 4 cm × 3 cm?
(a) 30 g (b) 27 g
(c) 10 g (d) 45 g

20. The area of a rectangular foot ball field is 24200 sq. m. It is half as broad as it is long. What is the approx minimum distance a man will cover if he wishes to go from one corner to the opposite one?
(a) 283 m (b) 246 m
(c) 576 m (d) 289 m

21. The area of the four walls of a room is 2640 sq. m and the length is twice the breadth and the height is given as 11 m. What is the area of the ceiling?
(a) 2800 m^2 (b) 3200 m^2
(c) 320 m^2 (d) none of these

22. If the perimeter of a square and a rectangle are the same, then the areas A and B enclosed by them would satisfy the inequality :
(a) $A > B$ (b) $A \geq B$
(c) $A < B$ (d) $A \leq B$

23. If the perimeter of a rectangle and a square each is equal to 80 cm and the difference of their areas is 100 sq. cm, the sides of the rectangle are :
(a) 25 cm, 15 cm (b) 28 cm, 12 cm
(c) 30 cm, 10 cm (d) 35 cm, 15 cm

24. The number of square shaped tin sheets of side 25 cm that can be cut off from a square tin sheet of side 1 m, is :
(a) 4 (b) 40
(c) 16 (d) 400

25. The length and breadth of a rectangular field are 120 m and 80 m respectively. Inside the field, a park of 12 m width is made around the field. The area of the park is :
(a) 2358 m^2 (b) 7344 m^2
(c) 4224 m^2 (d) 3224 m^2

26. A 5m wide lawn is cultivated all along the outside of a rectangular plot measuring 90m × 40 m. The total area of the lawn is :
(a) 1441 m^2 (b) 1400 m^2
(c) 2600 m^2 (d) 420 m^2

27. The length of a rectangle is 2 cm more than its breadth. The perimeter is 48 cm. The area of the rectangle (in cm^2) is :
(a) 96 (b) 128
(c) 143 (d) 144

28. The area of a rectangular field is 52000 m^2. This rectangular area has been drawn on a map to the scale 1 cm to 100 m. The length is shown as 3.25 cm on the map. The breadth of the rectangular field is :
(a) 210 m (b) 150 m
(c) 160 m (d) 123 m

29. If the length of diagonal BD of a square $ABCD$ is 4.8 cm, the area of the square $ABCD$ is :
(a) 9.6 cm^2 (b) 11.52 cm^2
(c) 12.52 cm^2 (d) 5.76 cm^2

30. If the side of square is increased by 20%, then how much per cent does its area get increased :
(a) 40% (b) 20%
(c) 44% (d) 24%

Scanned by CamScanner

yourSmartBook.wordpress.com

31. The ratio of the area of a square to that of the square drawn on its diagonal is :

(a) 1 : 1 (b) 1 : 2
(c) 1 : 3 (d) 1 : 4

32. The length and breadth of a square are increased by 60% and 40% respectively. The area of the resulting rectangle exceeds the area of the square by :

(a) 224% (b) 24%
(c) 124% (d) 100%

TRIANGLES

(1) Area of a triangle $= \frac{1}{2} \times$ base $\times$ height (General formula)

(2) Area of an scalene triangle

$$= \sqrt{s(s-a)(s-b)(s-c)}$$

where s is the semiperimeter of the triangle and a, b and c are the three sides of the triangle, $\left(s = \frac{a+b+c}{2}\right)$

(Scalene triangle : A triangle whose all sides are different in length)

(3) Area of a right angle triangle $= \frac{1}{2} \times$ base $\times$ height

(Right angle triangle : A triangle in which two sides are perpendicular)

Also, Hypotenuse $= \sqrt{(\text{base})^2 + (\text{height})^2}$

(4) Area of an equilateral triangle

$$= \frac{1}{2} \times \text{side} \times \left(\frac{\sqrt{3}}{2}\text{side}\right) = \frac{\sqrt{3}}{4} \times (\text{side})^2$$

(Equilateral triangle : A triangle in which all the three sides are equal also all the three internal angles are equal)

Height of an equilateral triangle $(h) = \frac{\sqrt{3}}{2} \times$ side

An important property : In an equilateral Δ perpendiculars drawn from all the three vertices intersect each other in the ratio of 2 : 1 from the vertex to the base.



$$\therefore \quad \frac{AO}{OR} = \frac{BO}{OP} = \frac{CO}{OQ} = \frac{2}{1} = \frac{r_2}{r_1}$$

$OP = OQ = OR$, all are the inradii

$OA = OB = OC$, all are the circumradii

NOTE Radii means more than one radius.



O is the centre of two circles. Circle PQR is called as incircle (touching the sides) and circle ABC is called as circumcircle (touching the vertices)

$$\therefore \quad \text{Inradius} = \frac{\text{side}}{2\sqrt{3}}$$

and $$\text{Circumradius} = \frac{\text{side}}{\sqrt{3}}$$

EXAMPLE 1 *The base of a right angled triangle is 8 cm and hypotenuse is 17 cm. Find its area.*

SOLUTION Hypotenuse $= \sqrt{(\text{base})^2 + (\text{altitude})^2}$

$$(17) = \sqrt{64 + (x)^2}$$

$$\Rightarrow \quad 289 = 64 + x^2$$

$$\Rightarrow \quad x^2 = 225$$

$$\Rightarrow \quad x = 15\text{cm}$$



$$\therefore \quad \text{Area} = \frac{1}{2} \times \text{base} \times \text{altitude}$$

(height is called altitude also)

$$= \frac{1}{2} \times 8 \times 15$$

$$= 60 \text{ cm}^2$$

EXAMPLE 2 *Find the area of an equilateral triangle whose side is $4\sqrt{3}$ cm.*

SOLUTION Area of an equilateral triangle $= \frac{\sqrt{3}}{4} \times (\text{side})^2$

$$= \frac{\sqrt{3}}{4} \times (4\sqrt{3})^2$$

$$= \frac{\sqrt{3}}{4} \times 48 = 12\sqrt{3} \text{ cm}^2$$

EXAMPLE 3 *The area of a right angled triangle is 24 cm^2 and the length of its hypotenuse is 10 cm. The length of the shorter leg is :*

(a) 5 cm (b) 4 cm (c) 6 cm (d) 3 cm

SOLUTION $H^2 = A^2 + B^2 = 100 \text{ cm}^2$

$$\text{Area} = \frac{1}{2} \times A \times B$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow \quad \frac{1}{2} A \times B = 24 \text{ cm}^2$

$\Rightarrow \quad A \times B = 48 \text{ cm}^2$

$\Rightarrow \quad (A+B)^2 = A^2 + B^2 + 2AB$

$\therefore \quad (A+B)^2 = 196$

$A + B = 14 \quad \ldots(1)$

$\Rightarrow$

Again $\quad (A-B)^2 = A^2 + B^2 - 2AB$

$\Rightarrow \quad (A-B)^2 = 4$

$\Rightarrow \quad A - B = 2 \quad \ldots(2)$

Therefore by solving equation (1) and (2) we get

$A = 8 \quad$ and $\quad B = 6$

Therefore the shorter leg is 6 cm.

Alternatively : Go through options.

$\because \quad \frac{1}{2} \times A \times B = 24$

$\Rightarrow \quad A \times B = 48$

Let us assume $B = 6$, then $A = \frac{48}{6} = 8$

Now, $\quad A^2 + B^2 = 100$

$(8)^2 + (6)^2 = 100$

$100 = 100$

Hence choice (c) is correct.

EXAMPLE 4 *Find the area and perimeter of a triangle whose sides are 17 cm, 8 cm and 15 cm long.*

SOLUTION Since $\quad 8^2 + 15^2 = 17^2$

$64 + 225 = 289$

$289 = 289$

Hence it is a right angled triangle.

$\therefore \quad$ Area $= \frac{1}{2} \times b \times h$

$= \frac{1}{2} \times 15 \times 8$

$= 60 \text{ cm}^2$

and $\quad$ perimeter $= 8 + 15 + 17 = 40$ cm

EXAMPLE 5 *Find the area and perimeter of an isosceles triangle whose equal sides are 5 cm each and base is 6 cm.*

SOLUTION Area of an isosceles triangle

$= \frac{b}{4} \sqrt{4a^2 - b^2}$

$= \frac{6}{4} \sqrt{4 \times 25 - 36}$

$= \frac{3}{2} \times \sqrt{64} = 12 \text{ cm}^2$

Alternatively : We know that the altitude CD bisects the base AB in the isosceles triangle ABC.

$\therefore \quad AD = BD = 3$ cm

Using Pythagorus theorem in ΔADC we have,

$CD^2 = AC^2 - AD^2$

$\therefore \quad CD = 4$ cm

$\therefore \quad$ Area of triangle $= \frac{1}{2} \times$ base $\times$ height

$= \frac{1}{2} \times 6 \times 4 = 12 \text{ cm}^2$

Also, the perimeter of triangle $= 5 + 5 + 6 = 16$ cm

INTRODUCTORY EXERCISE-10.2

1. What is the area of the triangle whose sides are 84 m, 80 m and 52 m?
   (a) 1620 sq. m (b) 2016 sq. m
   (c) 1818 sq. m (d) none of these
2. Two poles 15 m and 30 m high stand upright in a play ground. If their feet be 36 m apart, find the distance between their tops.
   (a) 41 m (b) 36 m
   (c) 39 m (d) none of these
3. The sides of a triangle are 25 m, 39 m and 56 m respectively. Find the perpendicular distance from the vertex opposite to the side 56 m.
   (a) 15 m (b) 16.5 m
   (c) 18.6 m (d) 21 m
4. ABC is a triangle and D, E, F are the mid-points of the sides BC, CA, AB respectively. The ratio of the areas of ΔABC and ΔDEF is :
   (a) 4 : 1 (b) 5 : 1
   (c) 3 : 1 (d) can't be determined
5. The integral base of an isosceles triangle can be whose area is 60 cm^2 and the length of one of the equal sides is 13 cm :
   (a) 20 cm (b) 10 cm
   (c) 16 cm (d) data insufficient
6. A ladder is resting with one end in contact with the top of a wall of height 60 m and the other end on the ground is at a distance of 11 m from the wall. The length of the ladder is :
   (a) 61 m (b) 71 m
   (c) 87 m (d) none of these
7. The base of a triangular field is three times its height. If the cost of cultivating the field is Rs. 36.72 per hectare is Rs. 495.72, find the height and base of the triangular field :
   (a) 480 m, 1120 m (b) 400 m, 1200 m
   (c) 300 m, 900 m (d) 250 m, 650 m
8. If every side of a triangle is doubled, then increase in area of the triangle is :
   (a) 200% (b) 300%
   (c) 400% (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

9. If the altitude of an equilateral triangle is $2\sqrt{3}$, then its area is :
(a) $4\sqrt{3}$ cm^2 (b) $12\sqrt{3}$ cm^2
(c) $\frac{8}{\sqrt{3}}$ cm^2 (d) none of these

10. If the perimeter of an equilateral triangle and a square are same and the area of equilateral triangle is P and area of square is Q, then :
(a) $P < Q$ (b) $P \le Q$
(c) $P > Q$ (d) $P \ge Q$

PARALLELOGRAM, RHOMBUS AND TRAPEZIUM

1. (a) Area of parallelogram = base (b) × height (h)
(b) Area of parallelogram
= product of any two adjacent side × sine of the included angle
2. Perimeter = 2 (sum of any two adjacent sides)
3. (a) Area of rhombus $= \frac{1}{2} \times$ (product of diagonals)
$= \frac{1}{2} \times d_1 d_2$
(b) Area of rhombus = product of adjacent sides × sine of the angle included by them
4. Perimeter of rhombus = 4 × side
5. Area of a trapezium $= \frac{1}{2} \times$ sum of parallel sides × height
height → distance between the two parallel sides
6. Perimeter of trapezium = sum of all the four sides

7. (a) Area of quadrilateral $= \frac{1}{2} \times$ product of diagonal × sine of the angle between them ($AC = d_1$ and $BD = d_2$)



$\therefore$ Area $= \frac{1}{2} d_1 d_2 \sin\theta_1$
$= \frac{1}{2} d_1 d_2 \sin\theta_2$

(b) Area $= \frac{1}{2} \times$ diagonal × sum of the perpendiculars drawn from the opposite vertices on it.



$= \frac{1}{2} d \times (h_1 + h_2)$

where, $MD = h_1$ and $BN = h_2$
$AC = d$

INTRODUCTORY EXERCISE-10.3

1. The adjacent sides of a parallelogram are 6 cm and 8 cm and the angle between them is 30°. What is the area of the parallelogram?
(a) 24 cm^2 (b) 12 cm^2
(c) 40 cm^2 (d) $24\sqrt{3}$ cm^2

2. A parallelogram has sides 30 cm and 20 cm and one of its diagonal is 40 cm long. Then its area is :
(a) $75\sqrt{5}$ cm^2 (b) 245 cm^2
(c) $150\sqrt{15}$ cm^2 (d) 300 cm^2

3. The distance of a 24 cm long side of a parallelogram from the opposite side is 22 cm. The area of the parallelogram is :
(a) 264 cm^2 (b) 246 cm^2
(c) 460 cm^2 (d) 528 cm^2

4. The two adjacent sides of a parallelogram are 25 cm and 40 cm respectively. The altitude drawn on the longer side is 18 cm, then the area of the parallelogram is :
(a) 450 cm^2 (b) 720 cm^2
(c) 500 cm^2 (d) none of these

5. In the adjoining figure, the ratio of the areas of the parallelogram $ABCD$ and that of triangle ABN is :



(a) 6 : 1 (b) 5 : 1
(c) 4 : 1 (d) 8 : 1

6. If the perimeter of a rhombus is $4p$ and lengths of its diagonals are a and b, then its area is :
(a) $\frac{a}{b}$ (b) $\frac{ab}{2}$
(c) ab/p (d) $p(a^2 + b^2)$

7. The ratio of the lengths of the diagonal of a rhombus is 2 : 5. Then, the ratio of the area of the rhombus to the square of the shorter diagonal :
(a) 5 : 4 (b) 5 : 2
(c) 2 : 5 (d) none of these

8. Area of a rhombus is 256 cm^2. One of the diagonal is half of the other diagonal. The sum of the diagonals is :
(a) 38 cm (b) 48 cm
(c) 28 cm (d) 56 cm

Scanned by CamScanner

yoursmahboob.wordpress.com

9. The lengths of two parallel sides of a trapezium are 30 cm and 50 cm and its height is 16 cm. Its area is :
(a) 460 cm^2 (b) 750 cm^2
(c) 320 cm^2 (d) 640 cm^2

10. $ABCD$ is a trapezium in which $AB \parallel CD$ and $AB = 2CD$. If its diagonals intersect each other at O, then ratio of areas of triangles AOB and COD is :
(a) 1 : 4 (b) 1 : 2
(c) 4 : 1 (d) 2 : 1

11. The area of a trapezium is 441 cm^2 and the ratio of parallel sides is 5 : 9. Also the perpendicular distance between them is 21 cm, the longer of parallel sides is :
(a) 36 cm (b) 27 cm
(c) 18 cm (d) 28 cm

12. The cross-section of a canal is in the shape of a trapezium and the area of cross-section is 360 m^2. If the canal is 12 m wide at the top and 8 m wide at the bottom the depth of the canal is :
(a) 36 m (b) 180 m
(c) 45 m (d) none of these

13. The area of a hexagon whose one side is 4 m, is :
(a) $6\sqrt{3}$ m^2 (b) $24\sqrt{3}$ m^2
(c) $42\sqrt{3}$ m^2 (d) 24 m^2

14. $ABCD$ is a quadrilateral $AC = 19$ cm. The lengths of perpendiculars from B and D on AC are 5 cm and 7 cm respectively. Then, the area of $ABCD$ (in cm^2) is :
(a) 162 (b) 144
(c) 228 (d) 114

15. $ABCD$ is a square, $AC = BD = 4\sqrt{2}$ cm, $AE = DE = 2.5$ cm. Find the area of the adjoining figure $ABCDE$:
(a) 19 cm^2
(b) 22 cm^2
(c) 17 cm^2
(d) none of the above



CIRCLES

1. Area of a circle $= \pi R^2$ ($R \rightarrow$ radius of the circle)
2. Circumference of the circle $= 2\pi R$
3. Length of an arc $= 2\pi R\left(\frac{\theta}{360°}\right)$
4. Area of a sector $= \pi R^2\left(\frac{\theta}{360°}\right) = \frac{1}{2}(\text{arc} \times R)$
5. Area of segment $= \pi R^2\left(\frac{\theta}{360°}\right) - \frac{R^2}{2}\sin\theta$

Diameter $= 2 \times$ radius



$OB = OA \rightarrow$ radius
$AB \rightarrow$ diameter

EXAMPLE 1 *The radius of a circular wheel is* $1\frac{3}{4}$ *m. How many revolutions will it make in travelling 11 km?*

SOLUTION Total distance (travelled) = 11 km = 11000 m

Distance travelled in one revolution

= circumference of the wheel

$= 2 \times \pi \times r = 2 \times \frac{22}{7} \times \frac{7}{4} = 11$ m

$\therefore$ number of revolutions in 11 km $= \frac{11000}{11}$

= 1000 revolution

EXAMPLE 2 *It takes 13.5 mL to paint the surface of the circular sheet of radius 17 cm. How much paint is required to paint a similar circular sheet with double the radius?*

SOLUTION Ratio of radii = 1 : 2

$\therefore$ Ratio of areas = 1 : 4

$$\left(\text{Since } \frac{\text{Area of } C_1}{\text{Area of } C_2} = \frac{\pi r_1^2}{\pi r_2^2} = \frac{1 \times 1}{2 \times 2} = \frac{1}{4}\right)$$

$\therefore$ Quantity of required paint is 4 times
Thus we need $4 \times 13.5 = 54$ mL paint.

EXAMPLE 3 *A circular road runs round a circular garden. If the difference between the circumference of the outer circle and the inner circle is 44 m. Find the width of the road.*

SOLUTION Let R and r be radii of outer circle and inner circle respectively

$\therefore$ Width of the road $= R - r$

$\therefore$ $2\pi R - 2\pi r = 44$ m

$\Rightarrow$ $2\pi(R - r) = 44$ m

$\Rightarrow$ $(R - r) = 7$ m $\quad \left(\because \pi = \frac{22}{7}\right)$

EXAMPLE 4 *The radius of a circle is 5 m. What is the radius of another circle whose area is 25 times that of the first?*

SOLUTION Ratio of areas = (ratio of radii)^2

$$\frac{25}{1} = (\text{ratio of radii})^2$$

$\Rightarrow$ ratio of radii $= \frac{5}{1}$

Therefore radius of another circle is 5 times

Hence the required radius = 25 m

EXAMPLE 5 *What is the radius of a circle whose area is equal to the sum of the areas of two circles whose radii are 20 cm and 21 cm.*

Scanned by CamScanner

yoursmartbook.wordpress.com

SOLUTION

$$\pi R^2 = \pi r_1^2 + \pi r_2^2$$
$$\pi R^2 = \pi (r_1^2 + r_2^2)$$
$$R^2 = (400 + 441)$$
$$R^2 = 841$$
$$\Rightarrow \quad R = 29 \text{ cm}$$

EXAMPLE 6 *In a circle of radius 28 cm, an arc subtends an angle of 108° at the centre.*

(a) Find the area of the sector.

(b) Find the length of the arc.

SOLUTION (a) Area of the sector $= \pi r^2 \left(\frac{\theta}{360^\circ}\right)$

$$= \frac{22}{7} \times 28 \times 28 \times \frac{108^\circ}{360^\circ}$$
$$= 22 \times 4 \times 28 \times \frac{3}{10}$$
$$= 739.2 \text{ cm}$$

(b) Length of the arc $= 2\pi r \left(\frac{\theta}{360^\circ}\right)$

$$= 2 \times \frac{22}{7} \times 28 \times \frac{108}{360^\circ} = 52.8 \text{ cm}$$

INTRODUCTORY EXERCISE-10.4

1. If the circumference of a circle is 704 cm, then its area is :
   (a) 49324 m^2 (b) 39424 m^2
   (c) 3672 cm^2 (d) 39424 cm^2

2. If the circumference of a circle is 4.4 m, then the area of the circle (in m^2) is :
   (a) $49/\pi$ (b) 49π
   (c) 4.9π (d) none of these

3. A circular wire of radius 4.2 m is cut and bent in the form of a rectangle whose longer side is 20% more than its shorter side. The longer side of the rectangle is :
   (a) 7.2 m (b) 72 cm
   (c) 8 m (d) none of these

4. The inner circumference of a circular path around a circular lawn is 440 m. What is the radius of the outer circumference of the path, if the path is 14 m wide?
   (a) 96 m (b) 84 m
   (c) 70 m (d) 88 m

5. The sum of the radius and the circumference of a circle is 51 cm. The area of the circle is :
   (a) 151 cm (b) 152 cm
   (c) 154 cm (d) data insufficient

6. The difference between the circumference and the diameter of the circle is 15 m. What is the area of the circle?
   (a) 225 m^2 (b) 165 m^2
   (c) 156 m^2 (d) none of these

7. The radius of a circle is increased by 2 cm from 5 cm to 7 cm. What is the percentage change in area of the circle?
   (a) 96% (b) 35%
   (c) 70% (d) 74%

8. If the circumference of a circle is increased by 20%, then its area will be increased by :
   (a) 44% (b) 32%
   (c) 40% (d) none of these

9. The area of a circular field is 124.74 hectares. The cost of fencing it at the rate of 80 paise per metre is :
   (a) Rs. 3168 (b) Rs. 1584
   (c) Rs. 1729 (d) none of these

10. Eldeco Housing Pvt. Ltd purchased a circular plot of land for Rs. 158400 at the rate of 1400 per sq. metre. The radius of the plot is :
    (a) 5 m (b) 6 m
    (c) 7 m (d) 14 m

11. A figure consists of a square of side 'a' m with semicircles drawn on the outside of the square. The area (in m^2) of the figure so formed will be :
    (a) $a^2(\pi + 1)$ (b) $a^2\left(\pi + \frac{1}{4}\right)$
    (c) $a^2 + \frac{\pi a^2}{2}$ (d) none of these

12. The length of a rope by which a buffalo must be tethered so that she may be able to graze a grassy area of 2464 sq. m is :
    (a) 35 m (b) 27 m
    (c) 24 m (d) 28 m

13. A circle of radius 'a' is divided into 6 equal sectors. An equilateral triangle is drawn on the chord of each sector to lie outside the circle. Area of the resulting figure is :
    (a) $3a^2(\pi + \sqrt{3})$ (b) $3\sqrt{3}\,a^2$
    (c) $3(a^2\sqrt{3} + \pi)$ (d) $\frac{3\sqrt{3}\pi a^2}{2}$

14. In the following figure, the area in (cm^2) is :
    (a) 115.5
    (b) 228.5
    (c) 154
    (d) none of the above



15. If a piece of wire 25 cm long is bent into an arc of a circle subtending an angle of 75° at the centre, then the radius of the circle (in cm) is :
    (a) $\frac{\pi}{120}$ (b) $\frac{60}{\pi}$
    (c) 60π (d) none of these

16. Four horses are tethered at four corners of a square plot of 42 m so that they just cannot reach one another. The area left ungrazed is :
    (a) 378 m^2 (b) 438 m^2
    (c) 786 m^2 (d) none of these

Scanned by CamScanner

yoursmanboob.wordpress.com

17. The circumference of the following figure is :



(a) $(20 + 10\pi)$ (b) 20π
(c) 10π (d) 30π

18. The area of a minor sector subtending the central angle at the centre 40° is 8.25 cm^2. What is the area of the remaining part (*i.e.*, major sector) of the circle?
(a) 82.5 cm^2 (b) 74.25 cm^2
(c) 66 cm^2 (d) none of these

19. The area of a sector of a circle of radius 8 cm, formed by an arc of length 5.6 cm, is :
(a) 22.4 cm^2 (b) 2.24 cm^2
(c) 56 cm^2 (d) none of these

20. How long will a man take to go, walking at 13.2 km/h, round a circular garden of 700 m radius?
(a) 12 minute (b) 30 minute
(c) 20 minute (d) none of these

21. What is the radius of circular field whose area is equal to the sum of the areas of three smaller circular fields of radii 8 m, 9 m and 12 m respectively?
(a) 17 m (b) 20 m
(c) 21 m (d) 29 m

22. A rope by which a calf is tied is decreased from 23 m to 12 m. What is the decrease in area to be grazed by it?
(a) 1110 m^2 (b) 1210 m^2
(c) 1120 m^2 (d) 1221 m^2

23. A wire is bent in the form of a square of side 66 m. It is cut and again bent in the form of a circle. The diameter of this circle is :
(a) 42 m (b) 84 m
(c) 21 m (d) none of these

24. A wire is in the form of a circle of radius 42 m is cut and again bent in the form of a square. What is the diagonal of the square?
(a) 66 m (b) $66\sqrt{3}$ m
(c) $66\sqrt{2}$ m (d) none of these

25. If the driving wheel of a bicycle makes 560 revolutions in travelling 1.1 km. Find the diameter of the wheel :
(a) 31:5 cm (b) 30.5 cm
(c) 62.5 cm (d) none of these

3-D FIGURES (SOLIDS)

S. No.	Name	Figure	Nomenclature	Volume	Curved/Lateral surface area	Total surface area
1.	Cuboid		$l \rightarrow$ length $b \rightarrow$ breadth $h \rightarrow$ height	lbh	$2(l+b)h$	$2(lb+bh+hl)$
2.	Cube		$a \rightarrow$ edge/side	a^3	$4a^2$	$6a^2$
3.	Right circular cylinder		$r \rightarrow$ radius of base $h \rightarrow$ height of the cylinder	$\pi r^2 h$	$2\pi rh$	$2\pi r(h+r)$
4.	Right circular cone		$r \rightarrow$ radius $h \rightarrow$ height $l \rightarrow$ slant height $l = \sqrt{r^2 + h^2}$	$\frac{1}{3}\pi r^2 h$	πrl	$\pi r(l+r)$

Scanned by CamScanner

yoursmahboob.wordpress.com

S. No.	Name	Figure	Nomenclature	Volume	Curved/Lateral surface area	Total surface area
5.	Right triangular prism		—	area of base × height	perimeter of base × height	lateral surface area + 2 (area of base)
6.	Right pyramid		—	$\frac{1}{3}$ × area of the base × height	$\frac{1}{2}$ × perimeter of the base × slant height	lateral surface area + area of the base
7.	Sphere		$r \rightarrow$ radius	$\frac{4}{3}\pi r^3$	—	$4\pi r^2$
8.	Hemisphere		$r \rightarrow$ radius	$\frac{2}{3}\pi r^3$	$2\pi r^2$	$3\pi r^2$
9.	Spherical shell		$r \rightarrow$ inner radius $R \rightarrow$ outer radius	$\frac{4}{3}\pi[R^3 - r^3]$	—	$4\pi[R^2 + r^2]$
10.	Frustum of a cone		—	$\frac{\pi}{3}h(r^2 + Rr + R^2)$	$\pi(r + R)\,l$	lateral surface area + $\pi[R^2 + r^2]$

CUBOID AND CUBE

Cuboid : A cuboid has 6 faces, 12 edges, 8 vertices and 4 diagonals.



Faces : *ABCD, EFGH, ABEH, CFGD, BCFE, ADGH*

Edges : *AB, BC, CD, AD, EF, FG, GH, EH, BE, CF, DG, AH*

Vertices : *A, B, C, D, E, F, G, H*

Diagonals : *AF, BG, CH, DE*

Formulae : Volume $= l \times b \times h$

($l \rightarrow$ length, $b \rightarrow$ breadth, $h \rightarrow$ height)

Total surface area $= 2(lb + bh + hl)$

Diagonal $(d) = \sqrt{l^2 + b^2 + h^2}$

Cube : A cube has 6 equal faces, 12 equal edges, 8 vertices and 4 equal diagonals

Formulae :

Volume : $(a)^3$

Total surface area $= 6(a)^2$

($a \rightarrow$ edge of the cube)

Diagonal $(d) = a\sqrt{3}$



Euler's Theorem $\rightarrow (V + F) = (E + 2)$; where $V \rightarrow$ no. of vertices, $F \rightarrow$ no. of faces, $E \rightarrow$ no. of edges

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *The dimensions of a cuboid are 16 cm, 18 cm and 24 cm. Find :*
(a) volume (b) surface area (c) diagonal

SOLUTION (a) Volume $= l \times b \times h = 16 \times 18 \times 24 = 6912 \text{ cm}^3$

(b) Surface area $= 2(lb + bh + hl)$
$= 2(16 \times 18 + 18 \times 24 + 24 \times 16)$
$= 2208 \text{ cm}^2$

(c) Diagonal $= \sqrt{l^2 + b^2 + h^2}$
$= \sqrt{16^2 + 18^2 + 24^2} = \sqrt{1156} = 34 \text{ cm}$

EXAMPLE 2 *Edge of a cube is 5 cm. Find :*
(a) volume (b) surface area (c) diagonal

SOLUTION Volume $= a^3 = (5)^3 = 125 \text{ cm}^3$
Surface area $= 6a^2 = 6 \times (5)^2 = 150 \text{ cm}^3$
Diagonal $= a\sqrt{3} = 5\sqrt{3} = 8.660 = 8.66 \text{ cm}$

EXAMPLE 3 *Three cubes of volumes, 1 cm³, 216 cm³ and 512 cm³ are melted to form a new cube. What is the diagonal of the new cube?*

SOLUTION Volume of new cube $= 1 + 216 + 512 = 729 \text{ cm}^3$
$\therefore$ Edge of new cube $= \sqrt[3]{729} = 9 \text{ cm}$
$\therefore$ Surface area $= 6a^2 = 6 \times (9)^2 = 486 \text{ cm}^2$
$\therefore$ Diagonal of the new cube $= a\sqrt{3} = 9\sqrt{3}$
$= 15.6 \text{ cm (approx)}$

EXAMPLE 4 *The surface area of a cube is 864 cm². Find its volume.*

SOLUTION $6a^2 = 864 \Rightarrow a^2 = 144 \Rightarrow a = 12 \text{ cm}$
$\therefore a^3 = (12)^3 = 1728 \text{ cm}^3$

EXAMPLE 5 *Find the length of the longest pole that can be placed in a room 30 m long, 24 m broad and 18 m high.*

SOLUTION $d = \sqrt{l^2 + b^2 + h^2}$
$d = \sqrt{900 + 576 + 324}$
$d = 30\sqrt{2} \text{ m}$

EXAMPLE 6 *A brick measures 20 cm × 10 cm × 7.5 cm. How many bricks will be required for a wall 20 m × 2 m × 0.75 m?*

SOLUTION Number of bricks $= \dfrac{\text{total volume of a wall}}{\text{volume of one brick}}$
$= \dfrac{20 \times 2 \times 0.75 \times 100 \times 100 \times 100}{20 \times 10 \times 7.5}$
$= 20{,}000$

INTRODUCTORY EXERCISE-10.5

1. A cube of metal, each edge of which measures 4 cm, weighs 400 kgs. What is the length of each edge of a cube of the same metal which weighs 3200 kg?
(a) 64 cm (b) 8 cm
(c) 2 cm (d) none of these

2. The length of a tank is thrice that of breadth, which is 256 cm deep and holds 3000 L water. What is the base area of the tank? (1000 L = 1 cubic metre)
(a) 111775 m^2 (b) 1171.875 m^2
(c) 1.171875 m^2 (d) none of these

3. The three co-terminus edges of a rectangular solid are 36 cm, 75 cm and 80 cm respectively. Find the edge of a cube which will be of the same capacity :
(a) 60 cm (b) 52 cm
(c) 46 cm (d) none of these

4. A tank 10 m long and 4 m wide is filled with water. How many litres of water must be drawn off to make the surface sink by 1 m. (1000 L = 1 cubic metre)
(a) 20 kilolitre (b) 40 kilolitre
(c) 50 kilolitre (d) none of these

5. How many cubes each of surface area 24 sq. dm can be made out of a metre cube, without any wastage :
(a) 75 (b) 250
(c) 125 (d) 62

6. Three cubes of metal, whose edges are 3 cm, 4 cm and 5 cm respectively are melted to form a new cube. What is the surface area of the new cube?
(a) 216 cm^2 (b) 56 cm^2
(c) 36 cm^2 (d) none of these

7. A lid of rectangular box of sides 39.5 cm by 9.35 cm is sealed all around with tape such that there is an overlapping of 3.75 cm of the tape. What is the length of the tape used?
(a) 111.54 cm (b) 101.45 cm
(c) 110.45 cm (d) none of these

8. A cistern from inside is 12.5 m long, 8.5 m broad and 4 m high and is open at top. Find the cost of cementing the inside of a cistern at Rs. 24 per sq. m :
(a) Rs. 6582 (b) Rs. 8256
(c) Rs. 7752 (d) Rs. 8752

9. 250 men took a dip in a water tank at a time, which is 80 m × 50 m. What is the rise in the water level if the average displacement of 1 man is 4 m^3?
(a) 22 cm (b) 25 cm
(c) 18 cm (d) 30 cm

10. The edge of a cube is increased by 100%, the surface area of the cube is increased by :
(a) 100% (b) 200%
(c) 300% (d) 400%

Scanned by CamScanner

yoursmahboob.wordpress.com

11. The edge of a cube is doubled. What will be the new volume?
(a) 2 times (b) 3 times
(c) 4 times (d) 8 times

12. The external dimensions of a wooden box closed at both ends are 24 cm, 16 cm and 10 cm respectively and thickness of the wood is 5 mm. If the empty box weighs 7.35 kg, find the weight of 1 cubic cm of wood :
(a) 10 g (b) 12.5 g
(c) 27 g (d) 15 g

13. The internal dimensions of a tank are 12 dm, 8 dm and 5 dm. How many cubes each of edge 7 cm can be placed in the tank with faces parallel to the sides of the tank. Find also, how much space is left unoccupied?
(a) 35; 113 dm^3 (b) 1313; 31.13 dm^3
(c) 1309; 31.013 dm^3 (d) 1309; 13.31 dm^3

14. The length, breadth and height of box are 2 m, 1.5 m and 80 cm respectively. What would be the cost of canvas to cover it up fully, if one square metre of canvas costs Rs. 25.00?
(a) Rs. 260 (b) Rs. 290
(c) Rs. 285 (d) none of these

15. Three cubes each of edge 3 cm long are placed together as shown in the adjoining figure. Find the surface area of the cuboid so formed :



(a) 182 sq. cm (b) 162 sq. cm
(c) 126 sq. cm (d) none of these

16. A room is 36 m long, 12 m wide and 10 m high. It has 6 windows, each 3 m × 2.5 m; one door 9.5 m × 6 m and one fire chimney 4 m × 4.5 m. Find the expenditure of papering its walls at the rate of 70 paise per metre, if the width of the paper is 1.2 m :
(a) Rs. 490 (b) Rs. 690
(c) Rs. 1000 (d) none of these

17. A school hall has the dimensions 30 m, 12 m by 6 m. Find the number of children who can be accommodated, if each child should get 8 m^3 of space :
(a) 240 (b) 270
(c) 250 (d) 150

18. When each side of a cube is increased by 2 cm, the volume is increased by 1016 cm^3. Find the side of the cube. If each side of it is decreased by 2 cm, by how much will the volume decrease?
(a) 12 cm, 729 cm^3 (b) 8 cm, 512 cm^3
(c) 9 cm, 729 cm^3 (d) 12 cm, 728 cm^3

19. Three equal cubes are placed adjacently in a row. Find the ratio of the total surface area of the resulting cuboid to that of the sum of the total surface areas of the three cubes :
(a) 5 : 7 (b) 7 : 9
(c) 9 : 7 (d) none of these

20. A hollow square shaped tube open at both ends is made of iron. The internal square is of 5 cm side and the length of the tube is 8 cm. There are 192 cm^3 of iron in the tube. Find its thickness :
(a) 2 cm (b) 0.5 cm
(c) 1 cm (d) can't be determined

21. A cube of 11 cm edge is immersed completely in a rectangular vessel containing water. If the dimensions of base are 15 cm and 12 cm. Find the rise in water level in the vessel :
(a) 6.85 cm (b) 7 cm
(c) 7.31 cm (d) 7.39 cm

22. A rectangular tank 25 cm long and 20 cm wide contains water to a depth of 5 cm. A metal cube of side 10 cm is placed in the tank so that one face of the cube rests on the bottom of the tank. Find how many litres of water must be poured into the tank so as to just cover the cube?
(a) 1 L (b) 1.5 L
(c) 2 L (d) 2.5 L

23. A rectangular block has length 10 cm, breadth 8 cm and height 2 cm. From this block, a cubical hole of side 2 cm is drilled out. Find the volume and the surface area of the remaining solid :
(a) 152 cm^3, 512 cm^2 (b) 125 cm^3, 215 cm^2
(c) 152 cm^3, 240 cm^2 (d) 125 cm^3, 512 cm^2

24. A rectangular tank of dimensions 24 m × 12 m × 8 m is dug inside a rectangular field 600 m long and 200 m broad. The earth taken out is evenly spread over the field. By how much will the level of the field rise?
(a) 1.925 cm (b) 0.02 m
(c) 0.2 cm (d) none of these

25. How many bricks (number near to next hundred) will be required to build a wall 30 m long, 30 cm thick and 5 m high with a provision of 2 doors, each 4 m × 2.5 m and each brick being 20 cm × 16 cm × 8 cm when one-ninth of the wall is filled with lime?
(a) 13500 bricks (b) 13600 bricks
(c) 20050 bricks (d) 18500 bricks

26. A rectangular water reservoir is 15 m by 12 m at the base. Water flows into it through a pipe whose cross-section is 5 cm by 3 cm at the rate of 16 m per second. Find the height to which the water will rise in the reservoir in 25 minutes :
(a) 0.2 m (b) 2 cm
(c) 0.5 m (d) none of these

27. Which of the following pairs is not correctly matched :

Geometrical objects	Number of vertices
(A) Tetrahedron	4
(B) Pyramid with rectangular base	5
(C) Cube	6
(D) Triangle	3

(a) (A) (b) (B)
(c) (C) (d) (D)

Scanned by CamScanner

yourshamboob.wordpress.com

28. If the length of diagonal of a cube is $6\sqrt{3}$ cm, then the length of its edge is :
(a) 2 cm (b) 3 cm
(c) 6 cm (d) $\frac{36}{\sqrt{3}}$ cm

29. The length of longest pole that can be placed on the floor of a room is 12 m and the length of longest pole that can be placed in the room is 15 m. The height of the room is :
(a) 3 m (b) 6 m
(c) 9 m (d) none of these

30. The sum of length, breadth and depth of a cuboid is 12 cm and its diagonal is $5\sqrt{2}$ cm. Its surface area is :
(a) 152 cm^2 (b) 94 cm^2
(c) 108 cm^2 (d) $60\sqrt{2}$ cm^2

31. The volume of a wall, 3 times as high as it is broad and 8 times as long as it is high, is 36.864 m^3. The height of the wall is :
(a) 1.8 m (b) 2.4 m
(c) 4.2 m (d) none of these

32. If the areas of 3 adjacent sides of a cuboid are x, y, z respectively, then the volume of the cuboid is :
(a) xyz (b) $\sqrt{xyz}$
(c) $3xyz$ (d) none of these

CYLINDER AND CONE

Cylinder :

Volume = base area × height
$= \pi r^2 h$

Curved surface area
= perimeter × height
$= 2\pi rh$

Total surface of the cylinder
= curved surface area + 2 (base area)
$= 2\pi rh + 2\pi r^2 = 2\pi r(h + r)$

Volume of a hollow cylinder $= \pi h (R^2 - r^2)$





Cone :



Volume $(V) = \frac{1}{3} \times$ base area × height $= \frac{1}{3}\pi r^2 h$

Curved surface area $= \pi rl$

Total surface area $= \pi rl + \pi r^2 = \pi r (l + r)$

Frustum of a cone :

Volume of the frustum of a cone
$= \frac{\pi}{3} h (r^2 + Rr + R^2)$

Curved/Lateral surface area of the frustum of cone
$= \pi l (r + R)$



EXAMPLE 1 *The base radius of a cylinder is 14 cm and its height is 30 cm. Find :*
(a) volume *(b) curved surface area*
(c) total surface area

SOLUTION (a) Volume of cylinder $= \pi r^2 \times h = \frac{22}{7} \times 14 \times 14 \times 30$
$= 18480 \text{ cm}^3$

(b) Curved surface area $= 2\pi rh = 2 \times \frac{22}{7} \times 14 \times 30$
$= 2640 \text{ cm}^2$

(c) Total surface area $= 2\pi r (h + r)$
$= 2 \times \frac{22}{7} \times 14 (30 + 14)$
$= 2 \times \frac{22}{7} \times 14 \times 44 = 3872 \text{ cm}^2$

EXAMPLE 2 *How many cubic metres of earth must be dug to make a well 14 m deep and 4 m in diameter?*

SOLUTION Earth to be dugout from the well
= volume of the cylindrical well
$= \pi r^2 h = \frac{22}{7} \times 2 \times 2 \times 14$
$= 176 \text{ m}^3$

EXAMPLE 3 *A hollow cylindrical tube open at both ends is made of iron 2 cm thick. If the external diameter be 50 cm and the length of the tube is 210 cm, find the number of cubic cm of iron in it.*

SOLUTION External radius $(R) = 25$ cm
Internal radius $(r) = (25 - 2) = 23$ cm
Volume of iron $= \pi h (R^2 - r^2)$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{22}{7} \times 210 \times (25^2 - 23^2)$$

$$= 63360 \text{ cm}^3$$

EXAMPLE 4 *A well with 14 m inside diameter is dugout 15 m deep. The earth taken out of it has been evenly spread all around it to a width of 21 m to form an embarkment. What is the height of the embarkment?*

SOLUTION Area of embarkment × height of embarkment = volume of earth dugout

$$\pi (R^2 - r^2) \times h = \pi \times 7 \times 7 \times 15$$

$$\Rightarrow \quad (28^2 - 7^2)\, h = 7 \times 7 \times 15$$

$$\Rightarrow \quad (35 \times 21) \times h = 7 \times 7 \times 15$$

$$\Rightarrow \quad h = 1 \text{ m}$$

EXAMPLE 5 *A cylindrical cistern whose diameter is 21 cm is partly filled with water. If a rectangular block of iron 14 cm in length, 10.5 cm in breadth and 11 cm in thickness is wholly immersed in water, by how many centimetres will the water level rise?*

SOLUTION Volume of the block $= 14 \times 10.5 \times 11 \text{ cm}^3$

Radius of the tank $= \frac{21}{2} = 10.5$ cm

Volume of the cylinder $= \pi r^2 h = \frac{22}{7} \times \frac{21}{2} \times \frac{21}{2} \times h$

$$\therefore \quad \frac{22}{7} \times \frac{21}{2} \times \frac{21}{2} \times h = 14 \times 10.5 \times 11$$

$$h = \frac{14}{3} = 4\frac{2}{3} \text{ cm}$$

EXAMPLE 6 *If the radius of cylinder is doubled, but height is reduced by 50%. What is the percentage change in volume?*

SOLUTION $\frac{r_1}{r_2} = \frac{r}{2r}$ and $\frac{h_1}{h_2} = \frac{h}{h/2}$

$\therefore$ Actual volume $= \pi r^2 h$

New volume $= \pi(2r)^2 \times \frac{h}{2} = 2\pi r^2 h$

Therefore new volume is the twice of the original volume.

Hence the change in volume $= \frac{2-1}{1} \times 100 = 100\%$

EXAMPLE 7 *The radius of the base of a right cone is 35 cm and its height is 84 cm. Find :*

(a) slant height *(b) curved surface area*
(c) total surface area *(d) volume*

SOLUTION (a) Slant height $(l) = \sqrt{r^2 + h^2}$

($r \rightarrow$ radius of the circular base)

$= \sqrt{35^2 + 84^2}$ ($h \rightarrow$ height of the cone)

$= \sqrt{1225 + 7056}$

$= \sqrt{8281} = 91$ cm

(b) Curved surface area $= \pi r l = \frac{22}{7} \times 35 \times 91$

$= 10010 \text{ cm}^2$

(c) Total surface area = lateral surface area + base area

$= \pi r l + \pi r^2 = \pi r (l + r)$

$= \frac{22}{7} \times 35 (91 + 84)$

$= 110 \times 175 = 19250 \text{ cm}^2$

(d) Volume $= \frac{1}{3} \pi r^2 h$

$= \frac{1}{3} \times \frac{22}{7} \times 35 \times 35 \times 84$

$= 107800 \text{ cm}^3$

EXAMPLE 8 *Find the area of the iron sheet required to prepare a cone 20 cm high with base radius 21 cm.*

SOLUTION $r = 21$ cm, $h = 20$ cm

$\therefore \quad l = \sqrt{r^2 + h^2} = 29$ cm

$\therefore$ Area of the sheet = total surface area of the cone

$= \pi r l + \pi r^2$

$= \pi r (l + r) = \frac{22}{7} \times 21 [29 + 21]$

$= 3300 \text{ cm}^2$

EXAMPLE 9 *A solid metallic cylinder of base radius 3 cm and height 5 cm is melted to make n solid cones of height 1 cm and base radius 1 mm. Find the value of n.*

SOLUTION $n = \frac{\text{volume of cylinder}}{\text{volume of one cone}}$

$= \frac{\pi \times 3 \times 3 \times 5}{\frac{1}{3} \pi \times \frac{1}{10} \times \frac{1}{10} \times 1} = 13500$

INTRODUCTORY EXERCISE-10.6

1. How many cubic metres of water fill a pipe which is 3500 m long and 0.08 m in diameter?
   (a) 17.5 m^3 (b) 17.6 m^3
   (c) 21 m^3 (d) 35 m^3
2. A cube of metal, whose edge is 10 cm, is wholly immersed in water contained in cylindrical tube whose diameter is 20 cm. By how much will the water level rise in the tube?
   (a) 3.3 cm (b) $6\frac{3}{11}$ cm
   (c) $3\frac{2}{11}$ cm (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

3. Find the height of the cylinder whose volume is 511 m^3 and the area of the base is 36.5 m^2 :
(a) 7 m (b) 10.5 m
(c) 14 m (d) none of these

4. The lateral surface area of a cylinder is 1056 cm^2 and its height is 16 cm. What is its volume?
(a) 5566 cm^3 (b) 4455 cm^3
(c) 5544 cm^3 (d) none of these

5. There is a cubical block of wood of side 2 cm. If the cylinder of the largest possible volume is carved out from it. Find the volume of the remaining wood :
(a) $\frac{7}{12}$ cm^2 (b) $\frac{12}{7}$ cm^3
(c) $5\frac{5}{7}$ cm^3 (d) none of these

6. The amount of concrete required to build a cylindrical pillar whose base has a perimeter of 8.8 m and whose curved surface area is 17.6 m^2 :
(a) 12.32 m^3 (b) 12.23 m^3
(c) 9.235 m^3 (d) 8.88 m^3

7. If the diameter of the base of a closed right circular cylinder be equal to its height 'h', then its whole surface area is :
(a) $\frac{2}{3}\pi h^2$ (b) $\frac{3}{2}\pi h^3$
(c) $\frac{3}{2}\pi h^2$ (d) πh^3

8. A right circular cylindrical tunnel of diameter 4 m and length 10 m is to be constructed from a sheet of iron. The area of the iron sheet required :
(a) $\frac{280}{\pi}$ (b) 40 π
(c) 80 π (d) none of these

9. The ratio between curved surface area and total surface area is 2 : 3. If the total surface area be 924 cm^2, find the volume of the cylinder :
(a) 2156 cm^3 (b) 1256 cm^3
(c) 1265 cm^3 (d) none of these

10. If the volume and curved surface area of a cylinder are 269.5 cm^3 and 154 cm^2 respectively, what is the height of the cylinder?
(a) 6 (b) 3.5
(c) 7 (d) can't be determined

11. If the curved surface area of a cylinder is 1320 cm^2 and its base radius is 21 cm, then its total surface area is :
(a) 4092 cm^2 (b) 2409 cm^2
(c) 4920 cm^2 (d) none of these

12. The ratio between the radius of the base and the height of a cylindrical pillar is 3 : 4. If its volume is 4851 m^3, the curved surface area of the pillar is :
(a) 924 m^2 (b) 1617 m^2
(c) 425 m^2 (d) none of these

13. If the ratio of total surface area to the curved surface area of a cylinder be 4 : 1, what is the ratio of radius to the height?
(a) 4 : 1 (b) 2 : 3
(c) 3 : 2 (d) 3 : 1

14. The circumference of the base of a right cylinder is 33 cm and height is 330 cm. What is the volume of this cylinder?
(a) 28586.25 cm^3 (b) 3344 cm^3
(c) 4433 cm^3 (d) 3456 cm^3

15. The radius of an iron rod decreased to one-fourth. If its volume remains constant, the length will become :
(a) 2 times (b) 8 times
(c) 4 times (d) 16 times

16. The total surface area of the cylinder is 2640 m^2 and the sum of height and radius of base of cylinder is 30 m. What is the ratio of height and radius of the cylinder?
(a) 7 : 9 (b) 9 : 7
(c) 8 : 7 (d) 3 : 7

17. The radii of two cylinders are in the ratio of 3 : 5 and their heights are in the ratio 4 : 3. The ratio of their volumes is :
(a) 12 : 25 (b) 13 : 25
(c) 4 : 5 (d) 5 : 4

18. The heights of two cylinders are in the ratio of 3 : 1. If the volumes of two cylinders be same, the ratio of their respective radii are :
(a) $\sqrt{3}$:1 (b) 1 : $\sqrt{3}$
(c) 1 : 9 (d) none of these

19. The ratio of heights of two cylinders is 3 : 2 and the ratio of their radii is 6 : 7. What is the ratio of their curved surface areas?
(a) 9 : 7 (b) 1 : 1
(c) 7 : 9 (d) 7 : 4

20. A hollow garden roller 42 cm wide with a girth of 132 cm is made of iron 3 cm thick. The volume of the iron of the roller is :
(a) 15544 cm^3 (b) 15444 cm^3
(c) 15545 cm^3 (d) none of these

21. A conical vessel has a capacity of 15 L of milk. Its height is 50 cm and base radius is 25 cm. How much milk can be contained in a vessel in cylindrical form having the same dimensions as that of the cone?
(a) 15 L (b) 30 L
(c) 45 L (d) none of these

22. The height of a cone is 30 cm. A small cone is cut off at the top by a plane parallel to the base. If its volume be $\frac{1}{27}$ of the volume of the given cone, at what height above the base is the section made?
(a) 20 cm (b) 18 cm
(c) 27 cm (d) 15 cm

23. A tent is in the form of right circular cone 10.5 m high, the diameter of the base being 13 m. If 8 men are in the tent, find the average number of cubic metres of air space per man :
(a) $32\frac{3}{58}$ (b) 59.75
(c) $36\frac{9}{13}$ (d) $58\frac{3}{32}$

Scanned by CamScanner

yoursmanboob.wordpress.com

24. The radius and height of a right circular cone are in the ratio of 5 : 12. If its volume is $314\frac{2}{7}$ m^3, its Slant height is :
(a) 26 m (b) 19.5 m
(c) 13 m (d) none of them

25. The volume and height of a right circular cone are 1232 cm^3 and 24 cm respectively, the area of its curved surface (in cm^2) is :
(a) 1100 (b) 225
(c) 616 (d) 550

26. The circumference of the base of a right circular cone is 220 cm^3 and its height 84 cm. The curved surface area of the cone is :
(a) 20020 cm^2 (b) 2020 cm^2
(c) 2200 cm^2 (d) 10010 cm^2

27. How many metres of cloth 10 m wide will be required to make a conical tent with base radius of 14 m and height is 48 m?
(a) 110 m (b) 55 m
(c) 77 m (d) 220 m

28. A cone of height 2.8 cm has a lateral surface area 23.10 m^2. The radius of the base is :
(a) 3.5 cm (b) 2 cm
(c) 2.1 cm (d) 4 cm

29. The radii of two cones are equal and their slant heights are in the ratio 3 : 2. If the curved surface area of the smaller cone is 300 cm^2, then the curved surface area of the bigger cone (in cm^2) is :
(a) 250 (b) 450
(c) 150 (d) 200

30. The ratio of the volume of a right circular cylinder and a right circular cone of the same base and height will be :
(a) 2 : 3 (b) 1 : 3
(c) 3 : 1 (d) 9 : 1

31. If the diameter of the base of right circular cone is equal to 8 cm and its slant height is 5 cm, then the area of its axial section is :
(a) 9 cm^2 (b) 12 cm^2
(c) 20 cm^2 (d) 40 cm^2

32. If the base radius and the height of a right circular cone are increased by 40% then the percentage increase in volume (approx) is :
(a) 175% (b) 120%
(c) 64% (d) 540%

33. From a circular sheet of paper of radius 25 cm, a sector area 4% is removed. If the remaining part is used to make a conical surface, then the ratio of the radius and height of the cone is :
(a) 16 : 25 (b) 9 : 25
(c) 7 : 12 (d) 24 : 7

34. If the radius of the base is doubled, keeping the height constant, what is the ratio of the volume of the larger cone to the smaller cone?
(a) 2 : 1 (b) 3 : 1
(c) 4 : 1 (d) 4 : 3

35. A largest posible cone is cut out from a cube of volume 1000 cm^3. The volume of the cone is :
(a) 280 cm^3 (b) 261.9 cm^3
(c) 269.1 cm^3 (d) 296.1 cm^3

36. If the height and the radius of a cone are doubled, the volume of the cone becomes :
(a) 2 times (b) 8 times
(c) 16 times (d) 4 times

37. A conical tent has 60° angle at the vertex. The ratio of its radius and slant height is :
(a) 3 : 2 (b) 1 : 2
(c) 1 : 3 (d) can't be determined

38. Water flows at the rate of 5 m per min from a cylindrical pipe 8 mm in diameter. How long will it take to fill up a conical vessel whose radius is 12 cm and depth 35 cm?
(a) 315 s (b) 365 s
(c) 5 min (d) none of these

39. A reservoir is in the shape of a frustum of a right circular cone. It is 8 m across at the top and 4 m across at the bottom. It is 6 m deep its capacity is :
(a) 224 m^3 (b) 176 m^3
(c) 225 m^3 (d) none of these

40. A conical vessel whose internal radius is 10 cm and height 72 cm is full of water. If this water is poured into a cylindrical vessel with internal radius 30 cm, the height of the water level rises in it is :
(a) $2\frac{2}{3}$ cm (b) $3\frac{2}{3}$ cm
(c) $5\frac{2}{3}$ cm (d) none of these

SPHERE, PRISM AND PYRAMID

Sphere :



$$\text{Volume} = \frac{4}{3}\pi r^3$$

$$\text{Surface area} = 4\pi r^2$$

Hemisphere :



$$\text{Volume} = \frac{2}{3}\pi r^3$$

$$\text{Curved surface area} = 2\pi r^2$$

$$\text{Total surface area} = 3\pi r^2 \quad (2\pi r^2 + \pi r^2)$$

Spherical shell :

$$\text{Volume} = \frac{4}{3}\pi(R^3 - r^3)$$

$$\text{Total surface area} = 4\pi(R^2 + r^2)$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Prism :

Volume = Base area × height



Lateral surface area
= perimeter of the base × height



Pyramid :

Volume = $\frac{1}{3}$ × base area × height



Lateral surface area
= $\frac{1}{2}$ × perimeter of the base × slant height

Total surface area = lateral surface area + base area





EXAMPLE 1 *Find the volume and surface area of a sphere of radius 3.5 cm.*

SOLUTION Volume = $\frac{4}{3}\pi r^3$

$= \frac{4}{3} \times \frac{22}{7} \times 3.5 \times 3.5 \times 3.5 = 179.66 \text{ cm}^3$

Surface area = $4\pi r^2$

$= 4 \times \frac{22}{7} \times 3.5 \times 3.5 = 154 \text{ cm}^2$

EXAMPLE 2 *Find the volume, curved surface area and total surface area of a hemisphere of diameter 7 cm.*

SOLUTION Volume = $\frac{2}{3}\pi r^3$

$= \frac{2}{3} \times \frac{22}{7} \times \frac{7}{2} \times \frac{7}{2} \times \frac{7}{2} = 89.833 \text{ cm}^3$

Curved surface area = $2\pi r^2$

$= 2 \times \frac{22}{7} \times \frac{7}{2} \times \frac{7}{2} = 77 \text{ cm}^2$

Total surface area = $3\pi r^2$

$= 3 \times \frac{22}{7} \times \frac{7}{2} \times \frac{7}{2} = 115.5 \text{ cm}^2$

EXAMPLE 3 *How many bullets can be made from a sphere of 8 cm radius. The radius of each bullet must be 0.2 cm.*

SOLUTION Number of bullets = $\frac{\text{volume of sphere}}{\text{volume of 1 bullet}}$

$= \frac{\frac{4}{3}\pi \times 8 \times 8 \times 8}{\frac{4}{3}\pi \times 0.2 \times 0.2 \times 0.2} = 64000$

EXAMPLE 4 *A sphere has the same curved surface as a cone of height 12 cm and base radius 5 cm. Find the radius to the nearest cm.*

SOLUTION $4\pi r^2 = \pi \times 5 \times 13$

$\Rightarrow \quad r^2 = \frac{65}{4}$

$\Rightarrow \quad r = 4 \text{ cm}$ (approx)

INTRODUCTORY EXERCISE-10.7

1. A spherical ball of lead 6 cm in radius is melted and recast into three spherical balls. The radii of two of these balls are 3 cm and 4 cm. What is the radius of the third sphere?
   (a) 4.5 cm (b) 5 cm
   (c) 6 cm (d) 7 cm
2. The radius of a copper sphere is 12 cm. The sphere is melted and drawn into a long wire of uniform circular cross-section. If the length of the wire is 144 cm, the radius of wire is :
   (a) 1 cm (b) 2 cm
   (c) 4 cm (d) none of these
3. A hemispherical bowl of internal radius 6 cm contains alcohol. This alcohol is to be filled into cylindrical shaped small bottles of diameter 6 cm and height 1 cm. How many bottles will be needed to empty the bowl?
   (a) 36 (b) 27
   (c) 16 (d) 4

Scanned by CamScanner

yoursmahboob.wordpress.com

4. A hemisphere of lead of diameter 14 cm is cast into a right circular cone of height 14 cm. The radius of the base of the cone is :
(a) 7 cm (b) 14 cm
(c) 21 cm (d) none of these

5. The volume of a spherical shell whose external and internal diameters are 14 cm and 10 cm respectively :
(a) 42π cm^3 (b) $\frac{872}{3}\pi$ cm^3
(c) 118π cm^3 (d) 86π cm^3

6. A solid metal ball of diameter 16 cm is melted and cast into smaller balls, each of radius 1 cm. The number of such balls is :
(a) 256 (b) 2048
(c) 512 (d) 4096

7. If a hemispherical dome has an inner radius 21 cm then its volume (in m^3) is :
(a) 4910 m^3 (b) 18354 m^3
(c) 19404 m^3 (d) none of these

8. A sphere of radius 9 cm is dropped into a cylindrical vessel partly filled with water. The radius of the vessel is 12 cm. If the sphere is submerged completely, then the surface of the water rises by :
(a) 27.5 cm (b) 27 cm
(c) 12 cm (d) 6.75 cm

9. If the height of a cone is half the radius of a sphere then the radius of the base of the cone, which has the same volume as a sphere of radius 7 cm is :
(a) 14 m (b) $\frac{14}{\sqrt{2}}$ cm
(c) $14\sqrt{2}$ cm (d) none of these

10. From a solid sphere of radius 15 cm, a right circular cylindrical hole of radius 9 cm whose axis passing through the centre is removed. The total surface area of the remaining solid is :
(a) 1188π cm^2 (b) 108π cm^2
(c) 1170π cm^2 (d) 144π cm^2

11. The volume of a pyramid of base area 25 cm^2 and height 12 cm is :
(a) 200 cm^3 (b) 100 cm^3
(c) 400 cm^3 (d) 800 cm^3

12. If the base of right rectangular prism remains constant and the measures of the lateral edges are halved, then its volume will be reduced by :
(a) 50% (b) 33.33%
(c) 66.66% (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

MISCELLANEOUS

1. If the side of an equilateral triangle is r, then the area of the triangle varies directly as :
   (a) $\sqrt{r}$ (b) r
   (c) r^2 (d) r^3

2. The length of the minute hand of the clock is 6 cm. The area swept by the minute hand in 30 minutes is :
   (a) $\frac{1}{36\pi}$ cm^2 (b) $\frac{1}{18\pi}$ cm^2
   (c) 18π cm^2 (d) 36π cm^2

3. If the diagonals of a rhombus are 18 cm and 24 cm respectively, then its perimeter is :
   (a) 15 cm (b) 42 cm
   (c) 60 cm (d) 70 cm

4. If the ratio of diagonals of two squares is 3 : 2 then the ratio of the areas of two squares is :
   (a) 4 : 5 (b) 6 : 5
   (c) 9 : 4 (d) $\sqrt{3} : \sqrt{2}$

5. In the given figure, $ABCD$ is a trapezium in which the parallel sides AB, CD are both perpendicular to BC. Find the area of the trapezium :
   (a) 140 m^2
   (b) 168 m^2
   (c) 180 m^2
   (d) 156.4 m^2



6. One cubic metre piece of copper is melted and recast into a square cross-section bar, 36 m long. An exact cube is cut off from this bar. If cubic metre of copper cost Rs. 108, then the cost of this cube is :
   (a) 50 paisa (b) 75 paisa
   (c) one rupee (d) 1.50 rupee

7. If 'h' be the height of a pyramid standing on a base which is an equilateral triangle of side 'a' units, then the slant height is :
   (a) $\sqrt{h^2 + a^2/4}$ (b) $\sqrt{h^2 + a^2/8}$
   (c) $\sqrt{h^2 + a^2/3}$ (d) $\sqrt{h^2 + a^2}$

8. The area of the square base of a right pyramid is 64 cm^2. If the area of each triangle forming the slant surface is 20 cm^2, then the volume of the pyramid is :
   (a) 64 cm^3 (b) $\frac{128}{3}$ cm^3
   (c) $\frac{64}{3}\sqrt{3}$ cm^3 (d) $64\sqrt{2}$ cm^3

9. If the surface areas of two spheres are in the ratio 4 : 9, then the ratio of their volumes is :
   (a) 8 : 25 (b) 8 : 26
   (c) 8 : 27 (d) 8 : 28

10. The side of a rhombus are 10 cm and one of its diagonal is 16 cm. The area of the rhombus is :
   (a) 96 cm^2 (b) 95 cm^2
   (c) 94 cm^2 (d) 93 cm^2

11. In the adjoining figure $PQRS$ is a rectangle 8 cm × 6 cm, inscribed in the circle. The area of the shaded portion will be :
   (a) 48 cm^2
   (b) 42.50 cm^2
   (c) 32.50 cm^2
   (d) 30.5 cm^2



12. In the adjoining figure $AB = CD = 2BC = 2BP = 2CQ$. In the middle, a circle with radius 1 cm is drawn. In the rest figure all are the semicircular arcs. What is the perimeter of the whole figure?



   (a) 4π (b) 8π
   (c) 10π (d) none of these

13. In a shower 10 cm of rain fall the volume of water that falls on 1.5 hectares of ground is :
   (a) 1500 m^3 (b) 1400 m^3
   (c) 1200 m^3 (d) 1000 m^3

14. The base of a prism is a right angle triangle and the two sides containing the right angle are 8 cm and 15 cm. If its height is 20 cm, then the volume of the prism is :
   (a) 1600 cc (b) 300 cc
   (c) 1200 cc (d) 600 cc

15. A conical circus tent is to be made of canvas. The height of the tent is 35 m and the radius of the base is 84 m. If $\pi = \frac{22}{7}$, then the canvas required is :
   (a) 24000 m^2 (b) 24004 m^2
   (c) 24014 m^2 (d) 24024 m^2

16. The radius of base and the volume of a right circular cone are doubled. The ratio of the length of the larger cone to that of the smaller cone is :
   (a) 1 : 4 (b) 1 : 2
   (c) 2 : 1 (d) 4 : 1

17. A cone and a hemisphere have equal base diameter and equal volumes. The ratio of their heights is :
   (a) 3 : 1 (b) 2 : 1
   (c) 1 : 2 (d) 1 : 3

18. A hollow sphere of internal and external diameters 4 cm and 8 cm respectively is melted to form a solid cylinder of base diameter 8 cm. The height of the cylinder is approximately :
   (a) 4.5 cm (b) 4.57 cm
   (c) 4.67 cm (d) 4.7 cm

Scanned by CamScanner

yourSmartbook.wordpress.com

19. The perimeter of the figure given below correct to one decimal place is :



(a) 56 m
(b) 56.6 m
(c) 57.2 m
(d) 57.9 m

20. The sum of the radii of the two circle is 140 cm and the difference between their circumference is 88 cm. The radius of the larger circle is :
(a) 60 cm (b) 70 cm
(c) 63 cm (d) 77 cm

21. If the lateral surface of a right circular cone is 2 times its base, then the semi-vertical angle of the cone must be :
(a) 15° (b) 30°
(c) 45° (d) 60°

22. There is a pyramid on a base which is a regular hexagon of side $2a$. If every slant edge of this pyramid is of length $\frac{(5a)}{2}$ then the volume of this pyramid must be :
(a) $3a^3$ (b) $3a^3\sqrt{2}$
(c) $3a^3\sqrt{3}$ (d) $6a^3$

23. The slant height of a conical tent made of canvas is $\frac{14}{3}$ m. The radius of tent is 2.5 m. The width of the canvas is 1.25 m. If the rate of canvas per metre is Rs. 33, then the total cost of the canvas required for the tent (in Rs.) is :
(a) 726 (b) 950
(c) 960 (d) 968

24. A hemispherical basin 150 cm in diameter holds water one hundred and twenty times as much a cylindrical tube. If the height of the tube is 15 cm, then the diameter of the tube (in cm) is :
(a) 23 (b) 24
(c) 25 (d) 26

25. If BC passes through centre of the circle, then the area of the shaded region in the given figure is :



(a) $\frac{a^2}{2}(3-\pi)$
(b) $a^2\left(\frac{\pi}{2}-1\right)$
(c) $2a^2(\pi-1)$
(d) $\frac{a^2}{2}\left(\frac{\pi}{2}-1\right)$

26. A river 3 m deep and 60 m wide is flowing at the rate of 2.4 km/h. The amount of water running into the sea per minute is :
(a) 6000 m^3 (b) 6400 m^3
(c) 6800 m^3 (d) 7200 m^3

27. A cone whose height is 15 cm and radius of base is 6 cm is trimmed sufficiently to reduce it to a pyramid whose base is an equilateral triangle. The volume of the portion removed is :
(a) 330 cm^3 (b) 328 cm^3
(c) 325 cm^3 (d) 331 cm^3

28. If a solid right circular cylinder is made of iron is heated to increase its radius and height by 1% each, then the volume of the solid is increased by :
(a) 1.01% (b) 3.03%
(c) 2.02% (d) 1.2%

29. The base of a prism is a regular hexagon. If every edge of the prism measures 1 m, then the volume of the prism is :
(a) $\frac{3\sqrt{2}}{2}$ m^3 (b) $\frac{3\sqrt{3}}{2}$ m^3
(c) $\frac{6\sqrt{2}}{5}$ m^3 (d) $\frac{5\sqrt{3}}{2}$ m^3

30. If the side of a square is 24 cm, then the circumference of its circumscribed circle (in cm) is :
(a) $24\sqrt{3}\pi$ (b) $24\sqrt{2}\pi$
(c) $12\sqrt{2}\pi$ (d) 24π

31. An isosceles right triangle has area 112.5 m^2. The length of its hypotenuse (in cm) is :
(a) 21.213 (b) 21.013
(c) 21.113 (d) 21.313

32. Two circles of unit radii, are so drawn that the centre of each lies on the circumference of the other. The area of the region, common to both the circles, is :
(a) $\frac{(4\pi-3\sqrt{3})}{12}$ (b) $\frac{(4\pi-6\sqrt{3})}{12}$
(c) $\frac{(4\pi-3\sqrt{3})}{6}$ (d) $\frac{(4\pi-6\sqrt{3})}{6}$

33. If the right circular cone is separated into three solids of volumes V_1, V_2 and V_3 by two planes which are parallel to the base and trisects the altitude, then $V_1 : V_2 : V_3$ is :
(a) 1 : 2 : 3 (b) 1 : 4 : 6
(c) 1 : 6 : 9 (d) 1 : 7 : 19

34. Water flows at the rate of 10 m per minute from a cylindrical pipe 5 mm in diameter. A conical vessel whose diameter is 40 cm and depth 24 cm is filled. The time taken to fill the conical vessel is :
(a) 50 min (b) 50 min. 12 sec.
(c) 51 min. 12 sec (d) 51 min. 15 sec

35. The length of four sides and a diagonal of the given quadrilateral are indicated in the diagram. If A denotes the area and l the length of the other diagonal, then A and l are respectively :



(a) $12\sqrt{6}, 4\sqrt{6}$
(b) $12\sqrt{6}, 5\sqrt{6}$
(c) $6\sqrt{6}, 4\sqrt{6}$
(d) $6\sqrt{6}, 5\sqrt{6}$

36. If a regular square pyramid has a base of side 8 cm and height of 30 cm, then its volume is :
(a) 120 cc (b) 240 cc
(c) 640 cc (d) 900 cc

37. A cylinder circumscribes a sphere. The ratio of their volumes is :
(a) 1 : 2 (b) 3 : 2
(c) 4 : 3 (d) 5 : 6

38. In triangle ABC, $BC = 8$ cm, $AC = 15$ cm and $AB = 17$ cm. The length of the altitude drawn from B on AC is :
(a) 6 cm (b) 7 cm
(c) 8 cm (d) 10 cm

39. The area of the largest possible square inscribed in a circle of unit radius (in square unit) is :
(a) 3 (b) 4
(c) $2\sqrt{3}\pi$ (d) 2

Scanned by CamScanner

yoursmahboob.wordpress.com

40. The area of the largest triangle that can be inscribed in a semicircle of radius r is :
(a) r^2 cm^2 (b) $\left(\frac{r}{3}\right)^2$ cm^2
(c) $r\sqrt{2}$ cm^2 (d) $3\sqrt{3}r$ cm^2

41. If a regular hexagon is inscribed in a circle of radius r, then its perimeter is :
(a) $6\sqrt{3}r$ (b) $6r$
(c) $3r$ (d) $12r$

42. If a regular hexagon circumscribes a circle of radius r, then its perimeter is :
(a) $4\sqrt{3}r$ (b) $6\sqrt{3}r$
(c) $6r$ (d) $12\sqrt{3}r$

43. In the adjoining figure there are three semicircles in which $BC = 6$ cm and $BD = 6\sqrt{3}$ cm. What is the area of the shaded region (in cm) :



(a) 12π (b) 9π
(c) 27π (d) 28π

44. Area of a rhombus is 144 cm^2 and the ratio of length of two diagonals is 1 : 2. The sum of lengths of its diagonals are :
(a) 72 cm (b) 40 cm
(c) 36 cm (d) $18\sqrt{2}$ cm

45. Find the area of the shaded region in the given figure of square $ABCD$:



(a) 128 cm^2
(b) 192 cm^2
(c) 148 cm^2
(d) 168 cm^2

46. In the following figure $AB = BC$ and $AC = 84$ cm. The radius of the inscribed circle is 14 cm. B is the centre of the largest semi- circle. What is the area of the shaded region?



(a) 335 cm^2 (b) 770 cm^2
(c) 840 cm^2 (d) 650 cm^2

47. A tank 4 m long and 2.5 m wide and 6 m deep is dug in a field 10 m long and 9 m wide. If the earth dugout is evenly spread over the field, the rise in level of the field will be :
(a) 80 cm (b) 75 cm
(c) 60 cm (d) 30 cm

48. An open box is made of wood 2 cm thick. Its internal length is 86 cm, breadth 46 cm and height is 38 cm. The cost of painting the outer surface of the box at Rs. 10 per m^2 is :
(a) Rs. 18.5 (b) Rs. 8.65
(c) Rs. 11.65 (d) Rs. 17.50

49. A rectangular tin sheet is 22 m long and 8 m broad. It is rolled along its length to form a cylinder by making the opposite edges just to touch each other. The volume of the cylinder (in m^3) is :
(a) 385 (b) 204
(c) 280π (d) 308

50. The lateral surface of a cylinder is developed into a square whose diagonal is $2\sqrt{2}$ cm. The area of the base of the cylinder (in cm^2) is :
(a) 3π (b) $1/\pi$
(c) π (d) 6π

51. If from a circular sheet of paper of radius 15 cm, a sector of 144° is removed and the remaining is used to make a conical surface, then the angle at the vertex will be :
(a) $\sin^{-1}\left(\frac{3}{10}\right)$ (b) $\sin^{-1}\left(\frac{6}{5}\right)$
(c) $2\sin^{-1}\left(\frac{3}{5}\right)$ (d) $2\sin^{-1}\left(\frac{4}{5}\right)$

52. A right circular cone of radius 4 cm and slant height 5 cm is carved out from a cylindrical piece of wood of same radius and height 5 cm. The surface area of the remaining wood is :
(a) 84π (b) 70π
(c) 76π (d) 50π

53. If h, s, V be the height, curved surface area and volume of a cone respectively, then $(3\pi Vh^3 \div 9V^2 - s^2h^2)$ is equal to :
(a) 0 (b) π
(c) $\frac{V}{sh}$ (d) $\frac{36}{V}$

54. If a cone is cut into two parts by a horizontal plane passing through the mid point of its axis, the ratio of the volumes of the upper part and the frustum is :
(a) 1 : 1 (b) 1 : 2
(c) 1 : 3 (d) 1 : 7

55. A cone, a hemisphere and a cylinder stand on equal bases of radius R and have equal heights H. Their whole surfaces are in the ratio :
(a) $(\sqrt{3}+1):3:4$ (b) $(\sqrt{2}+1):7:8$
(c) $(\sqrt{2}+1):3:4$ (d) none of these

56. If a sphere is placed inside a right circular cylinder so as to touch the top, base and the lateral surface of the cylinder. if the radius of the sphere is R, the volume of the cylinder is :
(a) $2\pi R^3$ (b) $8\pi R^3$
(c) $\frac{4}{3}\pi R^3$ (d) none of these

57. A cylinder is circumscribed about a hemisphere and a cone is inscribed in the cylinder so as to have its vertex at the centre of one end and the other end as its base. The volumes of the cylinder, hemisphere and the cone are respectively in the ratio of :
(a) $3:\sqrt{3}:2$ (b) 3 : 2 : 1
(c) 1 : 2 : 3 (d) 2 : 3 : 1

58. The base of a pyramid is a rectangle 40 m long and 20 m wide. The slant height of the pyramid from the mid-point of the shorter side of the base to the apex is 29 m. What is the volume of pyramid?
(a) 5600 m^3 (b) 400 m^3
(c) 6500 m^3 (d) $1753\sqrt{110}$ m^3

59. A copper wire when bent in the form of a square, encloses an area of 121 m^2. If the same wire is bent to form a circle, the area enclosed by it would be :
(a) 122 m^2 (b) 112 m^2
(c) 154 m^2 (d) 308 m^2

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL 1

1. The perimeter of a parallelogram with one internal angles 150° is 64 cm. Find the length of its sides when its area is maximum :
   (a) 16, 16 (b) 15, 17
   (c) 14, 18 (d) can't be determined

2. A sphere of 30 cm radius is dropped into a cylindrical vessel of 80 cm diameter, which is partly filled with water, then its level rises by x cm. Find x :
   (a) 27.5 cm (b) 22.5 cm
   (c) 18.5 cm (d) none of these

3. Amit walked 12 m toward east, then he turned to his right and walked 18 m. He then turned to his right and walked 12 m. He again turned to his right and walked 28 m then he again turned to his right and walked 24 m. At what distance is he from the starting point and in which direction?
   (a) 23 m north-east (b) 26 m north-east
   (c) 26 m west (d) 34 m north-east

4. Find the inradius of triangle if its area is 30 cm^2 and hypotenuse is 13 cm :
   (a) 1 cm (b) 2 cm
   (c) 2.5 cm (d) $2\sqrt{2}$ cm

5. Which of the following figure will have maximum area if the perimeter of all figures is same?
   (a) Square (b) Octagon
   (c) Circle (d) Hexagon

6. $ABCD$ is a trapezium with $\angle A = 90°$ and AB parallel to CD. Then $\angle B$ is :
   (a) 90° (b) $90° - \angle C$
   (c) $360° - \angle C$ (d) $180° - \angle C$

7. A square $ABCD$ has an equilateral triangle drawn on the side AB (interior of the square). The triangle has vertex at G. What is the measure of the angle CGB ?
   (a) 60° (b) 80°
   (c) 75° (d) 90°

8. There are two concentric circles whose areas are in the ratio of 9 : 16 and the difference between their diameters is 4 cm. What is the area of the outer circle?
   (a) 32 cm^2 (b) 64π cm^2
   (c) 36 cm^2 (d) 48 cm^2

9. A square and rhombus have the same base. If the rhombus is inclined at 60°, find the ratio of area of square to the area of the rhombus :
   (a) $2\sqrt{3} : 3$ (b) $1 : \sqrt{3}$
   (c) $\sqrt{3} : 2$ (d) none of these

10. Four isosceles triangles are cut off from the corners of a square of area 400 m^2. Find the area of new smaller square (in m^2) :
   (a) $200\sqrt{2}$ (b) $\frac{200}{\sqrt{2}}$
   (c) 200 (d) $100\sqrt{2}$

11. Altitude and base of a right angle triangle are $(x + 2)$ and $(2x + 3)$ (in cm). If the area of the triangle be 60 cm^2, the length of the hypotenuse is :
   (a) 21 cm (b) 13 cm
   (c) 17 cm (d) 15 cm

12. Find the area of a regular octagon with each side 'a' cm :
   (a) $2a^2 (1 + \sqrt{2})$ (b) $\sqrt{2}a (1 + \pi)$
   (c) $a^2 (\sqrt{2} + 2)$ (d) none of these

13. $ABCD$ is a square, 4 equal circles are just touching each other whose centres are the vertices A, B, C, D of the square. What is the ratio of the shaded to the unshaded area within square?



   (a) $\frac{8}{11}$ (b) $\frac{3}{11}$
   (c) $\frac{5}{11}$ (d) $\frac{6}{11}$

14. $ABCD$ is a trapezium, in which $AD \parallel BC$, E and F are the mid-points of AB and CD respectively, then EF is :



   (a) $\frac{(AD + BC)}{2}$
   (b) $\frac{(AB + CD)}{2}$
   (c) $\frac{DF \times CF}{AE \times BE}$
   (d) $\frac{AD + EF + BC}{2}$

15. A right circular cone resting on its base is cut at $\frac{4}{5}$th its height along a plane parallel to the circular base. The height of original cone is 75 cm and base diameter is 42 cm. What is the base radius of cut out (top portion) cone?
   (a) 4.2 cm (b) 2.8 cm
   (c) 3.5 cm (d) 8.4 cm

16. l, b are the length and breadth of a rectangle respectively. If the perimeter of this rectangle is numerically equal to the area of the rectangle. What is the value of $l - b$ (where $l > b$)?
   (a) 1 (b) 2
   (c) 3 (d) can't be determined

17. In the adjoining figure ABC is an equilateral triangle and C is the centre of the circle, A and B lie on the circle. What is the area of the shaded region, if the diameter of the circle is 28 cm?



   (a) $\left(102\frac{2}{3} - 49\sqrt{3}\right)$ cm^2
   (b) $\left(103\frac{2}{3} - 98\sqrt{3}\right)$ cm^2
   (c) $(109 - 38\sqrt{3})$ cm
   (d) none of the above

Scanned by CamScanner

yoursmahboob.wordpress.com

18. l_1, b_1 and l_2, b_2 are the lengths and breadths of the two rectangles respectively, but the areas of the rectangles are same. l_1 is increased by 25% and b_1 is decreased by 25%. Similarly l_2 is decreased by 25% and b_2 is increased by 25%. If A_1 and A_2 is the new areas of the two rectangles respectively, then :

(a) $A_1 > A_2$ (b) $A_1 < A_2$
(c) $A_1 = A_2$ (d) can't be determine

19. An acute angle made by a side of parallelogram with other pair of parallel sides is 60°. If the distance between these parallel sides is $6\sqrt{3}$, the other side is :

(a) 12 cm (b) $12\sqrt{3}$ cm
(c) $15\sqrt{3}$ cm (d) none of these

20. A solid sphere is melted and recast into a right circular cone with a base radius equal to the radius of the sphere. What is the ratio of the height and radius of the cone so formed?

(a) 4 : 3 (b) 2 : 3
(c) 3 : 4 (d) none of these

21. In the given figure there are 3 semicircles, the radii of each smaller circle is equal. If the radius of the larger circle be 22 cm, then the area of the shaded region is :



(a) $363\frac{\pi}{4}$ (b) $363\frac{\pi}{3}$
(c) 236.5π (d) 363π

22. A rectangular lawn 60 m × 40 m has two roads each 5 m wide running in the middle of it, one parallel to length and the other parallel to breadth. The cost of gravelling the roads at 80 paise per sq. m is :

(a) Rs. 380 (b) Rs. 385
(c) Rs. 400 (d) none of these

23. There are two rectangular fields of same area. The length of first rectangular field is x% less than the length of the second field and breadth of the first field is $(5x)$% greater than the breadth of the second field. What is the value of x?

(a) 15 (b) 25
(c) 50 (d) 80

24. In the adjoining figure ACB is a quadrant with radius 'a'. A semicircle is drawn outside the quadrant taking AB as a diameter. Find the area of shaded region :



(a) $\frac{1}{4}(\pi - 2a^2)$
(b) $\left(\frac{1}{4}\right)(\pi a^2 - a^2)$
(c) $\frac{a^2}{2}$
(d) can't be determined

25. Ravi made an error of 5% in excess while measuring the length of rectangle and an error of 8% deficit was made while measuring the breadth. What is the percentage error in the area?

(a) – 3% (b) – 40%
(c) – 3.4% (d) can't be determined

26. In the adjoining figure the cross-section of a swimming pool is shown. If the length of the swimming pool is 120 m then the amount of water it can hold is :



(a) 5760 m^3
(b) 9600 m^3
(c) 7200 m^3
(d) none of these

27. Around a circular garden a circular road is to be repair which costs Rs. 22176 at the rate of Rs. 1 per sq. m. If the inner radius is 112 m, find the width of the circular road :

(a) 18 m (b) 28 m
(c) 14 m (d) none of these

28. An equilateral triangle is cut from its three vertices to form a regular hexagon. What is the percentage of area wasted?

(a) 20% (b) 50%
(c) 33.33% (d) 66.66%

29. ABC is an equilateral triangle and $PQRS$ is a square inscribed in the triangle in such a way that P and Q lie on AB and R, S lie on BC and AC respectively. What is the value of $RC : RB$?



(a) $1 : \sqrt{2}$
(b) $1 : \sqrt{3}$
(c) $\sqrt{3} : 2$
(d) 1 : 2

30. The area of a square and circle is same and the perimeter of square and equilateral triangle is same, then the ratio between the area of circle and the area of equilateral triangle is :

(a) $\pi : 3$ (b) $9 : 4\sqrt{3}$
(c) $4 : 9\sqrt{3}$ (d) none of these

31. Adjoining figure shows a square $ABCD$ in which O is the point of intersection of diagonals AC and BD. Four squares of maximum possible area are formed inside each four triangles AOB, BOC, COD and AOD. What is the total area of these 4 squares?



(a) 400 cm^2 (b) 100 cm^2
(c) 80 cm^2 (d) none of these

32. What is the ratio of the area of circumcircle of equilateral triangle to the area of square with the same side length as the equilateral triangle?

(a) $\pi : 3$ (b) $\pi : \sqrt{3}$
(c) $\sqrt{3} : 2$ (d) none of these

33. It is required to construct a big rectangular hall that can accommodate 400 people with 25 m^3 space for each person. The height of the wall has been fixed at 10 m and the total inner surface area of the walls must be 1300 m^2. What is the length and breadth of the hall (in metres)?

Scanned by CamScanner

yourmahboob.wordpress.com

(a) 30, 20 (b) 45, 20
(c) 40, 25 (d) 35, 30

34. The perimeter of a rectangle and an equilateral triangle are same. Also, one of the sides of the rectangle is equal to the side of the triangle. The ratio of the areas of the rectangle and the triangle is :
(a) $\sqrt{3}:1$ (b) $1:\sqrt{3}$
(c) $2:\sqrt{3}$ (d) $4:\sqrt{3}$

35. If l, b, p be the length, breadth and perimeter of a rectangle and b, l, p are in GP (in order), then l/b is :
(a) 2 : 1 (b) $(\sqrt{3}-1):1$
(c) $(\sqrt{3}+1):1$ (d) $2:\sqrt{3}$

36. A spherical steel ball was silver polished then it was cut into 4 similar pieces. What is ratio of the polished area to the non polished area :
(a) 1 : 1 (b) 1 : 2
(c) 2 : 1 (d) can't be determined

37. What is the total surface area of the identical cubes of largest possible size that are cut from a cuboid of size 85 cm × 17 cm × 5.1 cm?
(a) 26010 cm^2 (b) 21600 cm^2
(c) 26100 cm^2 (d) none of these

38. 125 identical cubes are cut from a big cube and all the smaller cubes are arranged in a row to form a long cuboid. What is the percentage increase in the total surface area of the cuboid over the total surface area of the cube?
(a) $234\frac{2}{3}\%$ (b) $235\frac{1}{3}\%$
(c) $134\frac{2}{3}\%$ (d) none of these

39. In the adjoining figure a parallelogram $ABCD$ is shown. $AB = 24$ cm and $AO = BO = 13$ cm. Find BC :



(a) 8 cm (b) 10 cm
(c) 11 cm (d) none of these

40. There are two circles intersecting each other. Another smaller circle with centre O, is lying between the common region of two larger circles. Centres of the circle (i.e., A, O and B) are lying on a straight line. $AB = 16$ cm and the radii of the larger circles are 10 cm each. What is the area of the smaller circle?



(a) 4π cm^2 (b) 2π cm^2
(c) $\frac{4}{\pi}$ cm^2 (d) $\frac{\pi}{4}$ cm^2

41. $ABCD$ is a square, inside which 4 circles with radius 1 cm, each are touching each other. What is the area of the shaded region?



(a) $(2\pi - 3)$ cm^2
(b) $(4 - \pi)$ cm^2
(c) $(16 - 4\pi)$ cm^2
(d) none of these

42. $ABCD$ is a square, E is a point on AB such that $BE = 17$ cm. The area of triangle ADE is 84 cm^2. What is the area of square?



(a) 400 cm^2
(b) 625 cm^2
(c) 729 cm^2
(d) 576 cm^2

43. If the volume of a sphere, a cube, a tetrahedron and a octahedron be same then which of the following has maximum surface area?
(a) Sphere (b) Cube
(c) Octahedron (d) Tetrahedron

44. In a rectangle the ratio of the length is to breadth is same as that of the sum of the length and breadth to the length. If l and b be the length and breadth of the rectangle then which of the following is true?
(i) $\frac{l}{b} = \frac{l^2}{b^2} + 1$ (ii) $\frac{b}{l-b} = \frac{l+b}{l}$
(iii) $lb = (l + b)(l - b)$
(a) only (i) is true
(b) only (ii) is true
(c) only (ii) and (iii) are true
(d) only (i) and (ii) are true

45. Three circle of equal radii touch each other as shown in figure. The radius of each circle is 1 cm. What is the area of shaded region?



(a) $\left(\frac{2\sqrt{3}-\pi}{2}\right)$ cm^2
(b) $\left(\frac{3\sqrt{2}-\pi}{3}\right)$ cm^2
(c) $\frac{2\sqrt{3}}{\pi}$ cm^2
(d) none of the above

46. How many spheres of radius 1.5 cm can be cut out of a wooden cube of edge 9 cm?
(a) 216 (b) 81
(c) 27 (d) can't be determined

47. Kaurav and Pandav have a rectangular field of area 20,000 sq. m. They decided to divide it into two equal parts by dividing it with a single straight line. Kaurav wanted to fence their land immediately, so they incurred total expenses for the fencing all the four sides alone at Rs. 2 per metre. What is the minimum cost that Kaurav had to incur?
(a) Rs. 800 (b) Rs. 1600
(c) Rs. 1200 (d) Rs. 600

Scanned by CamScanner

yoursmahboob.wordpress.com

48. There is a cone of height 12 cm, out of which a smaller cone (which is the top portion of the original cone) with the same vertex and vertical axis is cut out. What is the ratio of the volume of the larger (actual) cone to the remaining part (frustum) of the cone, if the height of the smaller cone is 9 cm?
(a) 3 : 1 (b) 9 : 1
(c) 64 : 37 (d) 16 : 7

49. Radhey can walk along the boundary of a rectangular field and also along the diagonals of the field. His speed is 53 km/h. The length of the field is 45 km. Radhey started from one corner and reached to the diagonally opposite corner in 1 hour. What is the area of the field?
(a) 860 km^2 (b) 1260 km^2
(c) 1060 km^2 (d) can't be determined

50. Charles has a right circular cylinder which he inserted completely into a right circular cone of height 30 cm. The vertical angle of the cone is 60° and the diameter of the cylinder is $8\sqrt{3}$ cm. What is the volume of the cone?
(a) $\frac{3000}{7}\pi$ cm^3 (b) 3000π cm^3
(c) 4860π cm^3 (d) can't be determind

51. There are six faces in a cube. Rajeev fix one cube on each of the faces. The dimensions of all the cubes are same. What is the ratio of total surface area of the newly formed solid to the area of a single cube?
(a) 7 : 1 (b) 6 : 1
(c) 5 : 1 (d) 41 : 9

52. If the ratio of diagonals of two cubes is 3 : 2 then the ratio of the surface areas of the two cubes respectively is :
(a) 5 : 4 (b) 9 : 5
(c) 9 : 4 (d) can't be determind

53. *ABCDEF* is a regular hexagon of side 6 cm. What is the area of triangle *BDF*?



(a) $32\sqrt{3}$ cm^2 (b) $27\sqrt{3}$ cm^2
(c) 24 cm^2 (d) none of these

Directions for question number 54 and 55 : *King Dashratha of Ayodhya had a rectangular plot of area 9792 m^2. He divided it into 4 square shaped plots by fencing parallel fences to the breadth of the rectangular plot. All the four sons got each square shaped plot. However, some area of plot was still left which could not be formed as a square shaped. So, four more square shaped plots were formed by fencing parallel to the longer side of the original plot. The king gave one smaller square shaped plot to each of his wives and one of the smaller square shaped plot retained with himself and then nothing left to divide.*

54. What is the ratio of the area of larger square shaped plot to the area of the smaller square shaped plot?
(a) 17 : 1 (b) 25 : 9
(c) 16 : 1 (d) can't be determined

55. What are dimensions of the original plot?
(a) 288 m, 34 m (b) 102 m, 96 m
(c) 306 m, 32 m (d) 204 m, 48 m

LEVEL 2

Directions for question number 1, 2 and 3 : *Each edge of an equilateral triangle is 'a' cm. A cone is formed by joining any two sides of the triangle.*

1. What is the radius and slant height of the cone?
(a) $a, \frac{a}{2\pi}$ (b) $\frac{a}{\pi}, \frac{a}{2}$
(c) $\frac{a}{2\pi}, a$ (d) $2a, \frac{a}{\pi}$

2. What is the volume of the cone?
(a) $\frac{a^2}{24\pi^3}\sqrt{4-\pi^2}$ (b) $\frac{a^3}{24\pi^2}\sqrt{4\pi^2-1}$
(c) $\frac{a^3}{8\pi^2}\sqrt{1-4\pi^2}$ (d) $\frac{a}{\sqrt{3}}\pi^2\left(1-\frac{2}{\pi}\right)$

3. If the cone is cut along its axis from the middle, the new shape we obtain after opening the paper is :
(a) isosceles triangle (b) equilateral triangle
(c) right angle triangle (d) none of these

4. If the sum of the radius and the height of a closed cylinder is 35 cm and the total surface area of the cylinder is 1540 cm^2, then the circumference of the base of the cylinder is :
(a) 66 cm (b) 44 cm
(c) 56 cm (d) can't be determined

5. An iron pillar has some part in the form of a right circular cylinder and remaining in the form of a right circular cone. The radius of base of cone, as well as cylinder is 21 cm. The cylindrical part is 80 cm high and conical part is 16 cm high. Find the weight of the pillar, if 1 cm^3 of iron weighs 8.45 g :
(a) 999.39 kg (b) 111 kg
(c) 1001 kg (d) 989 kg

6. *ABCD* is a square of side *a* cm. *AB*, *BC*, *CD* and *AD* all are the chords of circles with equal radii each. If the chords subtends an angle of 120° at their respective centres, find the total area of the given figure, where arcs are part of the circles :



(a) $\left[a^2+4\left(\frac{\pi a^2}{9}-\frac{a^2}{3\sqrt{2}}\right)\right]$ (b) $\left[a^2+4\left(\frac{\pi a^2}{9}-\frac{a^2}{4\sqrt{3}}\right)\right]$
(c) $[9a^2-4\pi+3\sqrt{3}a^2]$ (d) none of these

7. A rectangle has a perimeter of 26. How many combinations of integral valued length are possible?
(a) 4 (b) 8
(c) 6 (d) 12

Scanned by CamScanner

yoursmahboob.wordpress.com

8. A hollow sphere of outer diameter 24 cm is cut into two equal hemisphere. The total surface area of one of the hemisphere is $1436\frac{2}{7}$ cm^2. Each one of the hemisphere is filled with water. What is the volume of water that can be filled in each of the hemisphere?

(a) $3358\frac{2}{3}$ cm^3 (b) $3528\frac{2}{3}$ cm^3

(c) $2359\frac{2}{3}$ cm^3 (d) $9335\frac{2}{3}$ cm^3

9. A big cube of side 8 cm is formed by rearranging together 64 small but identical cubes each of side 2 cm. Further, if the corner cubes in the topmost layer of the big cube are removed, what is the change in total surface area of the big cube?

(a) 16 cm^2, decreases
(b) 48 cm^2, decreases
(c) 32 cm^2, decreases
(d) remains the same as previously

10. A large solid sphere of diameter 15 m is melted and recast into several small spheres of diameter 3 m. What is the percentage increase in the surface area of the smaller spheres over that of the large sphere?

(a) 200% (b) 400%
(c) 500% (d) can't be determined

11. A cone is made of a sector with a radius of 14 cm and an angle of 60°. What is total surface area of the cone?

(a) 119.78 cm^2 (b) 191.87 cm^2
(c) 196.5 cm^2 (d) none of these

12. Kishan Chand is a very labourious farmer, he erected a fence around his paddy field in a square shape. He used 26 poles in each side, each at a distance of 4 m. What is the area of field?

(a) 1.6 hectare (b) 2.6 hectare
(c) 5.76 hectare (d) 1 hectare

13. A rectangular lawn is surrounded by a path of width 2 m on all sides. Now if the length of the lawn is reduced by 2 m the lawn becomes a square lawn and the area of path becomes 13/11 times, what is the length of the original lawn?

(a) 8 m (b) 9 m
(c) 10 m (d) 12 m

Directions for question number 14, 15 : A cylinder with height and radius 2 : 1 is filled with soft drink and then it is tilted so as to allow some soft drink to flow off to an extent where the level of soft drink just touches the lowest point of the upper mouth.

14. If the 2.1 L soft drink is retained in the cylinder, what is the capacity of the cylinder?

(a) 3.6 L (b) 4 L
(c) 1.2 L (d) 4.2 L

15. If the quantity of soft drink left is poured into a conical flask whose height and base radius are same as that of the cylinder so as to fill the conical flask completely, the quantity of soft drink left in the cylinder as a fraction of its total capacity is :

(a) $\frac{1}{3}$ (b) $\frac{1}{6}$

(c) $\frac{1}{9}$ (d) $\frac{1}{10}$

16. An elephant of length 4 m is at one corner of a rectangular cage 16 m × 30 m and facing towards the diagonally opposite corner. If the elephant starts moving towards the diagonally opposite corner it takes 15 seconds to reach the opposite corner. Find the speed of the elephant :

(a) 1 m/s (b) 2 m/s
(c) 1.87 m/s (d) can't be determined

17. What is the height of the cone which is formed by joining the two ends of a sector of circle with radius r and angle 60°?

(a) $\frac{\sqrt{35}}{6}r$ (b) $\frac{\sqrt{25}}{6}r$

(c) $\frac{r^2}{\sqrt{3}}$ (d) none of these

18. If a cube of maximum possible volume is cut off from a solid sphere of diameter d, then the volume of the remaining (waste) material of the sphere would be equal to :

(a) $\frac{d^3}{3}\left(\pi - \frac{d}{2}\right)$ (b) $\frac{d^3}{3}\left(\frac{\pi}{2} - \frac{1}{\sqrt{3}}\right)$

(c) $\frac{d^2}{4}(\sqrt{2} - \pi)$ (d) none of these

19. In the adjoining figure $PQRS$ is a square and $MS = RN$ and A, P, Q and B lie on the same line. Find the ratio of the area of two circles to the area of the square. Given that $AP = MS$:



(a) $\frac{\pi}{3}$ (b) $\frac{2\pi}{3}$

(c) $\frac{3\pi}{2}$ (d) $\frac{6}{\pi}$

20. $ABCD$ is a rectangle and there are four equilateral triangles. Area of ΔASD equals to area of ΔBQC and area of ΔDRC equals to area of ΔAPB. The perimeter of the rectangle is 12 cm. Also the sum of the areas of the four triangles is $10\sqrt{3}$ cm^2 then the total area of the figure thus formed :



(a) $2(4 + 5\sqrt{3})$ cm^2 (b) $5(4 + 2\sqrt{3})$ cm^2
(c) $42\sqrt{3}$ cm^2 (d) none of these

21. $ABCD$ and $EFGA$ are the squares of side 4 cm, each. In square $ABCD$, DMB and PMQ are the arcs of circles with centres at A and C respectively. In square $AEFG$, the shaded region is enclosed by two arcs of circles with centres at A and F, respectively. What is the ratio of the shaded regions of the squares $ABCD$ and $AEFG$ respectively :



Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $\frac{2+\pi(\sqrt{2}-2)}{(\pi-2)}$ (b) $\frac{(\pi-2)}{2(\sqrt{2}+1-\pi)}$

(c) $\frac{4}{3}$ (d) none of these

22. In the adjoining figure $\frac{AB}{BC}=\frac{AD}{DF}$, where $EBCF$ is a square. Find the ratio of $\frac{AE}{EF}$:



(a) $\frac{(1\pm\sqrt{7})}{3}$ (b) $\frac{(1-\sqrt{7})}{2}$

(c) $\frac{(1+\sqrt{5})}{2}$ (d) $\frac{(1\pm\sqrt{5})}{2}$

Direction for question number 23–25 : In the adjoining figure ABCD is a square. A circle ABCD is passing through all the four vertices of the square. There are two more circles on the sides AD and BC touching each other inside the square, AD and BC are the respective diameters of the two smaller circles. Area of the square is 16 cm².



23. What is the area of region 1?

(a) 2.4 cm² (b) $\left(2-\frac{\pi}{4}\right)$ cm²

(c) 8 cm² (d) $(4\pi-2)$ cm²

24. What is the area of region 2?

(a) $3(\pi-2)$ cm² (b) $(\pi-3)$ cm²

(c) $(2\pi-3)$ cm² (d) $4(\pi-2)$ cm²

25. What is the area of region 3?

(a) $(4-4\pi)$ cm² (b) $4(4-\pi)$ cm²

(c) $(4\pi-2)$ cm² (d) $(3\pi+2)$ cm²

26. In the adjoining figure $ABCD$ is a square. Four equal semicircles are drawn in such a way that they meet each other at 'O'. Sides AB, BC, CD and AD are the respective diameters of the four semicircles. Each of the side of the square is 8 cm. Find the area of the shaded region :



(a) $32(\pi-2)$ cm² (b) $16(\pi-2)$ cm²

(c) $(2\pi-8)$ cm² (d) $\left(\frac{3}{4}\pi-4\right)$ cm²

27. $ABCD$ is a square. Another square $EFGH$ with the same area is placed on the square $ABCD$ such that the point of intersection of diagonals of square $ABCD$ and square $EFGH$ coincide and the sides of square $EFGH$ are parallel to the diagonals of square $ABCD$. Thus a new figure is formed as shown in the figure. What is the area enclosed by the given figure if each side of the square is 4 cm :



(a) $32(2-\sqrt{2})$ (b) $16\left(\frac{3+\sqrt{2}}{2+\sqrt{2}}\right)$

(c) $32\left(\frac{2+\sqrt{2}}{3+\sqrt{2}}\right)$ (d) none of these

28. A piece of paper is in the form of a right angle triangle in which the ratio of base and perpendicular is 3 : 4 and hypotenuse is 20 cm. What is the volume of the biggest cone that can be formed by taking right angle vertex of the paper as the vertex of the cone?

(a) 45.8 cm³ (b) 56.1 cm³

(c) 61.5 cm³ (d) 48 cm³

29. In a particular country the value of diamond is directly proportional to the surface area (exposed) of the diamond. Four thieves steel a cubical diamond piece and then divide equally in four parts. What is the maximum percentage increase in the value of diamond after cutting it?

(a) 50% (b) 66.66%

(c) 100% (d) none of these

Directions for question number 30 and 31 : In the figure shown square II is formed by joining the mid-points of square I, square III is formed by joining the mid-points of square II



and so on. In this way total five squares are drawn. The side of the square I is 'a' cm.

30. What is the perimeter of all the five squares?

(a) $\frac{(4\sqrt{2}+1)a}{(\sqrt{2}+1)}$ (b) $\frac{(4\sqrt{2}-1)a}{(\sqrt{2}+1)}$

(c) $\frac{5}{6}a$ (d) $(7+3\sqrt{2})a$

31. What is the total area of all the five squares?

(a) $\frac{(4\sqrt{2}-1)a^2}{(4\sqrt{2}-1)}$ (b) $\frac{(4\sqrt{2}-1)a^2}{4(\sqrt{2}-1)}$

(c) $\frac{31}{16}a^2$ (d) none of these

Directions for question number 32-35 : Each edge of a cube is equally divided into n parts, thus there are total n^3 smaller cubes. Let,

N_0 → Number of smaller cubes with no exposed surfaces

Scanned by CamScanner

yourSmartbook.wordpress.com

$N_1 \rightarrow$ *Number of smaller cubes with one exposed surfaces*
$N_2 \rightarrow$ *Number of smaller cubes with two exposed surfaces*
$N_3 \rightarrow$ *Number of smaller cubes with three exposed surfaces*

32. What is the number of unexposed smaller cubes (N_0)?
(a) $(n-2)^3$ (b) n^3
(c) $n!$ (d) 8

33. What is the number of smaller cubes with one exposed surface (N_1)?
(a) $4(n-3)^3$ (b) $6(n-2)^2$
(c) $(n-3)^2$ (d) $(n+1)^2$

34. What is the value of (N_2)?
(a) $8(n-2)^2$ (b) $6(n-2)$
(c) $12(n-2)$ (d) $3(n-3)^2$

35. What is the value of N_3?
(a) $(n-1)!$ (b) $(n-2)^2$
(c) $\frac{n(n+1)}{2}$ (d) 8

36. In a bullet the gun powder is to be filled up inside the metallic enclosure. The metallic enclosure is made up of a cylindrical base and conical top with the base of radius 5 cm. The ratio of height of cylinder and cone is 3 : 2. A cylindrical hole is drilled through the metal solid with height two-third the height of metal solid. What should be the radius of the hole, so that the volume of the hole (in which gun powder is to be filled up) is one-third the volume of metal solid after drilling?
(a) $\sqrt{\frac{88}{5}}$ cm (b) $\sqrt{\frac{55}{8}}$ cm
(c) $\frac{55}{8}$ cm (d) 33π cm

37. A sector of the circle measures 19° (see the figure). Using only a scale, a compass and a pencil, is it possible to split the circle into 360 equal sectors of 1° central angle?



(a) Yes
(b) No
(c) Yes, only if radius is known
(d) can't be determined

38. A circular paper is folded along its diameter, then again it is folded to form a quadrant. Then it is cut as shown in the figure, after it the paper was reopened in the original circular shape. Find the ratio of the original paper to that of the remaining paper? (The shaded portion is cut off from the quadrant. The radius of quadrant *OAB* is 5 cm and radius of each semicircle is 1 cm) :



(a) 25 : 16 (b) 25 : 9
(c) 20 : 9 (d) none of these

39. A cubical cake is cut into several smaller cubes by dividing each edge in 7 equal parts. The cake is cut from the top along the two diagonals forming four prisms. Some of them get cut and rest remained in the cubical shape. A complete cubical (smaller) cake was given to adults and the cut off part of a smaller cake is given to a child (which is not an adult). If all the cakes were given equally each piece to a person, total how many people could get the cake?
(a) 343 (b) 448
(c) 367 (d) 456

Directions for question number 40-42 : *A square is inscribed in a circle then another circle is inscribed in the square. Another square is then inscribed in the circle. Finally a circle is inscribed in the innermost square. Thus there are 3 circles and 2 squares as shown in the figure. The radius of the outer-most circle is R.*



40. What is the radius of the inner-most circle?
(a) $\frac{R}{2}$ (b) $\frac{R}{\sqrt{2}}$
(c) $\sqrt{2}R$ (d) none of these

41. What is the sum of areas of all the squares shown in the figure?
(a) $3R^2$ (b) $3\sqrt{2}R^2$
(c) $\frac{3}{\sqrt{2}}R^2$ (d) none of these

42. What is the ratio of sum of circumferences of all the circles to the sum of perimeters of all the squares?
(a) $(2+\sqrt{3})\pi R$ (b) $(3+\sqrt{2})\pi R$
(c) $3\sqrt{3}\pi R$ (d) none of these

Directions for question number 43-45 : *A regular hexagon is inscribed in a circle of radius R. Another circle is inscribed in the hexagon. Now another hexagon is inscribed in the second (smaller) circle.*



43. What is the sum of perimeters of both the hexagons?
(a) $(2+\sqrt{3})R$ (b) $3(2+\sqrt{3})R$
(c) $3(3+\sqrt{2})R$ (d) none of these

44. What is the ratio of area of inner circle to the outer circle?
(a) 3 : 4 (b) 9 : 16
(c) 3 : 8 (d) none of these

45. If there are some more circles and hexagons inscribed in the similar way as given above, then the ratio of each side of outermost hexagon (largest one) to that of the fourth (smaller one) hexagon is (fourth hexagon means the hexagon which is inside the third hexagon from the outside) :
(a) $9 : 3\sqrt{2}$ (b) 16 : 9
(c) $8 : 3\sqrt{3}$ (d) none of these

Directions for question number 46-47 : *Five spheres are kept in a cone in such a way that each sphere touch each other and also touch the lateral surface of the cone, this is due to increasing radius of the spheres starting from the vertex of the cone. The radius of the smallest sphere is 16 cm.*



Scanned by CamScanner

yoursmahboob.wordpress.com

46. If the radius of the fifth (i.e., largest) sphere be 81 cm, then find the radius of the third (i.e., middlemost) sphere :
(a) 25 cm (b) $25\sqrt{3}$ cm
(c) 36 cm (d) data insufficient

47. What is the least distance between the smallest sphere and the vertex of the cone?
(a) 64 cm (b) 80 cm
(c) 26 cm (d) none of these

48. Saumya has a pencil box of volume 60 cm^3. What can be the maximum length of a pencil that can be accommodated in the box. Given that all the sides are integral (in cm) and different from each other?
(a) $7\sqrt{2}$ cm (b) $\sqrt{905}$ cm
(c) $\sqrt{170}$ cm (d) $\sqrt{3602}$ cm

49. There are two concentric hexagons. Each of the side of both the hexagons are parallel. Each side of an internal regular hexagon is 8 cm. What is the area of the shaded region, if the distance between corresponding parallel sides is $2\sqrt{3}$ cm :



(a) $120\sqrt{3}$ cm^2
(b) $148\sqrt{3}$ cm^2
(c) 126 cm^2
(d) none of the above

50. $ABCD$ is a square. A circle is inscribed in the square. Also taking A, B, C, D (the vertices of square) as the centres of four quadrants, drawn inside the circle, which are touching each other on the mid-points of the sides of square. Area of square is 4 cm^2. What is the area of the shaded region?



(a) $\left(4 - \frac{3\pi}{2}\right)$ cm^2 (b) $(2\pi - 4)$ cm^2
(c) $(4 - 2\pi)$ cm^2 (d) none of these

51. In a factory there are two identical solid blocks of iron. When the first block is melted and recast into spheres of equal radii 'r', then 14 cc of iron was left, but when the second block was melted and recast into sphere each of equal radii '$2r$', then 36 cc of iron was left. The volumes of the solid blocks and all the spheres are in integers. What is the volume (in cm^3) of each of the larger spheres of radius '$2r$'?
(a) 176 (b) 12π
(c) 192 (d) data insufficient

52. There is a vast grassy farm in which there is a rectangular building of the farm-house whose length and breadth is 50 m and 40 m respectively. A horse is tethered at a corner of the house with a tether of 80 m long. What is the maximum area that the horse can graze?
(a) 5425π (b) 5245π
(c) 254π (d) none of these

53. A cube of side 6 cm is painted on all its 6 faces with red colour. It is then broken up into 216 smaller identical cubes. What is the ratio of $N_0 : N_1 : N_2$.
Where, $N_0 \rightarrow$ number of smaller cubes with no coloured surface.
$N_1 \rightarrow$ number of smaller cubes with 1 red face.
$N_2 \rightarrow$ number of smaller cubes with 2 red faces :
(a) 3 : 4 : 6 (b) 3 : 4 : 5
(c) 4 : 6 : 3 (d) can't be determined

54. Assume that a mango and its seed, both are spherical, now if the radius of seed is 2/5 of the thickness of the pulp. The seed lies exactly at the centre of the fruit. What per cent of the total volume of the mango is its pulp?
(a) $63\frac{3}{5}\%$ (b) 97.67%
(c) $68\frac{2}{3}\%$ (d) none of these

55. In the adjoining diagram $ABCD$ is a square with side 'a' cm. In the diagram the area of the larger circle with centre 'O' is equal to the sum of the areas of all the rest four circles with equal radii, whose centres are P, Q, R and S. What is the ratio between the side of square and radius of a smaller circle?



(a) $(2\sqrt{2} \div 3)$ (b) $(2 \div 3\sqrt{2})$
(c) $(4 \div 3\sqrt{2})$ (d) can't be determined

56. Initially the diameter of a balloon is 28 cm. It can explode when the diameter becomes 5/2 times of the initial diameter. Air is blown at 156 cc/s. It is known that the shape of balloon always remains spherical. In how many seconds the balloon will explode?
(a) 1078 s (b) 1368 s
(c) 1087 s (d) none of these

57. The radius of a cone is $\sqrt{2}$ times the height of the cone. A cube of maximum possible volume is cut from the same cone. What is the ratio of the volume of the cone to the volume of the cube?
(a) 3.18π (b) 2.25π
(c) 2.35 (d) can't be determined

58. Raju has 64 small cubes of 1 cm^3. He wants to arrange all of them in a cuboidal shape, such that the surface area will be minimum. What is the diagonal of this larger cuboid?
(a) $8\sqrt{2}$ cm (b) $\sqrt{273}$
(c) $4\sqrt{3}$ cm (d) $\sqrt{129}$ cm

59. The volume of a cylinder is 48.125 cm^3, which is formed by rolling a rectangular paper sheet along the length of the paper. If a cuboidal box (without any lid i.e., open at the top) is made from the same sheet of paper by cutting out the quare of side 0.5 cm from each of the four corners of the paper sheet, then what is the volume of this box?
(a) 20 cm^3 (b) 38 cm^3
(c) 19 cm^3 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions for question number 60-62 : *Consider a cylinder of height h cm and radius $r = \frac{4}{\pi}$ cm as shown in the figure. A string of certain length when wound on its cylindrical surface, starting at point A, gives a maximum of n turns.*

60. What is the vertical spacing (in cm) between two consecutive turns?



(a) $\frac{h}{n}$

(b) $\frac{\sqrt{h}}{n}$

(c) $\frac{h^2}{n}$

(d) can't be determined

61. If there is no spacing between any two courecutive turns and the width of string be x cm, then the required length of the string is :

(a) $\frac{8x}{h}$ cm (b) $\frac{8h}{x}$ cm

(c) $8hx$ cm (d) $2\sqrt{2}\frac{h}{x}$ cm

62. If the string is wound on the exterior four walls of a cube of side a cm starting at point C and ending at point D exactly above C, making equally spaced 4 turns. The side of the cube is :

(a) $a = \frac{2n}{\sqrt{255}}$ (b) $a = \frac{(n)^2}{16}$

(c) $a = \frac{8n}{\sqrt{257}}$ (d) $a = 2\sqrt{15}n$

63. A blacksmith has a rectangular iron sheet 10 ft long. He has to cut out 7 circular discs from this sheet. What is the minimum possible width of the iron sheet if the radius of each disc is 1 ft?

(a) $2\sqrt{3}$ ft (b) $(2+\sqrt{3})$ ft

(c) $(3+\sqrt{2})$ ft (d) $(2+2\sqrt{3})$ ft

64. The perimeter of a square, a rhombus and a hexagon are same. The area of square, rhombus and hexagon be s, r, h, respectively then which of the following is correct :

(a) $r > s > h$ (b) $s > h > r$

(c) $h > s > r$ (d) data insufficient

65. In the adjoining figure ABC is an equilateral triangle inscribing a square of maximum possible area. Again in this square there is an equilateral triangle whose side is same as that of the square. Further the smaller equilateral triangle inscribes a square of maximum possible area. What is the area of the innermost square if the each side of the outermost triangle be 0.01 m?



(a) $(873 - 504\sqrt{3})$ cm^2 (b) $(738 - 504\sqrt{3})$ cm^2

(c) $(873 - 405\sqrt{2})$ cm^2 (d) none of these

66. A blacksmith has a rectangular sheet of iron. He has to make a cylindrical vessel both circular ends are closed. When he minimises the wastage of the sheet of iron, then what is the ratio of the wastage to the utilised area of sheet?

(a) $\frac{1}{11}$ (b) $\frac{2}{17}$

(c) $\frac{3}{22}$ (d) none of these

67. Barun needs an open box of capacity 864 m^3. Actually where he lives, the rates of paints are soaring high so he wants to minimize the surface area of the box keeping the capacity of the box same as required. What is the base area and height of such a box?

(a) 36 m^2, 24 m (b) 216 m^2, 4 m

(c) 144 m^2, 6 m (d) none of these

68. There are two cylindrical containers of equal capacity and equal dimensions. If the radius of one of the container is increased by 12 ft and the height of another container is increased by 12 ft, then the capacity of both the container is equally increased by K cubic ft. If the actual heights of each of the container be 4 ft, then find the increased volume of each of the container :

(a) 1680 π cu ft (b) 2304 π cu ft

(c) 1480 π cu ft (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

Test of Your Learning

1. Three equal circles each of radius 1 cm are circumscribed by a larger circle. Find the perimeter of the circumscribing circle :



(a) $\frac{\sqrt{3}}{2}(2-\sqrt{3})\pi$ cm

(b) $\left(\frac{2+\sqrt{3}}{\sqrt{3}}\right)$ cm

(c) $\frac{2}{\sqrt{3}}(2+\sqrt{3})\pi$ cm

(d) none of the above

2. Three circular rings of equal radii of 1 cm each are touching each other. A string runs all around the set of rings very tightly. What is the minimum length of string required to bind all the three rings in the given manner?



(a) $\frac{6}{\pi}$ cm (b) $2(3+\pi)$ cm

(c) $\frac{\pi}{6}$ cm (d) can't be determined

3. An equilateral triangle circumscribes all the three circles each of radius 1 cm. What is the perimeter of the equilateral triangle?



(a) $6(\sqrt{3}+1)$ cm

(b) $\sqrt{3}(8+\sqrt{2})$ cm

(c) $15(\sqrt{3}-1)$ cm

(d) none of the above

4. Six circles each of unit radius are being circumscribed by another larger circle. All the smaller circles touch each other. What is the circumference of the larger circle?



(a) $\left(\frac{\sqrt{3}+4}{\sqrt{2}}\right)\pi$ cm

(b) $4\sqrt{3}\pi$ cm

(c) $2\left(\frac{4+\sqrt{3}}{\sqrt{3}}\right)\pi$ cm

(d) can't be determined

5. There are six circular rings of iron, kept close to each other. A string binds them as tightly as possible. If the radius of each circular iron ring is 1 cm. What is the minimum possible length of string required to bind them?



(a) $2(6+3\sqrt{3}+\pi)$ cm

(b) $6(2+\sqrt{3})\pi$ cm

(c) $2(6+\pi)$ cm

(d) none of the above

6. An equilateral triangle circumscribes all the six circles, each with radius 1 cm. What is the perimeter of the equilateral triangle?

(a) $6(2+\sqrt{3})$ cm

(b) $3(\sqrt{3}+2)$ cm

(c) $12(\sqrt{3}+4)$ cm

(d) none of the above



7. A cube of maximum possible volume is cut from the sphere of diameter $3\sqrt{3}$ cm. What is the ratio of volume of the sphere to that of cube?

(a) $\frac{4\sqrt{3}}{\pi}$ (b) $\frac{\sqrt{3}}{2}\pi$

(c) $\frac{4}{\sqrt{3}}\pi$ (d) none of these

8. A cube of maximum possible volume is cut from the solid right circular cylinder. What is the ratio of volume of cube to that of cylinder if the edge of a cube is equal to the height of the cylinder?

(a) $\frac{11}{7}$ (b) $\sqrt{2}\frac{\pi}{7}$

(c) $\frac{7}{11}$ (d) none of these

9. In a right angle triangle ABC, what is the maximum possible area of a square that can be inscribed when one of its vertices coincide with the vertex of right angle of the triangle?



(a) $\frac{a}{b}$ (b) $\frac{ab}{a+b}$

(c) $\frac{a+b}{ab}$ (d) $\left(\frac{ab}{a+b}\right)^2$

10. In the adjoining figure a square of maximum possible area is circumscribed by the right angle triangle ABC in such a way that one of its side just lies on the hypotenuse of the triangle. What is the area of the square?



(a) $\left(\frac{abc}{a^2+b^2+ab}\right)^2$ (b) $\frac{a^2+b^2+c^2}{abc}$

(c) $\frac{abc}{a^2+b^2+c^2}$ (d) none of these

11. In the adjoining figure $PQRS$ is a square of maximum possible area which is circumscribed by the semicircle. Points R and S lie on the diameter AB. What is the area of the square if the radius of the circle is 'r'?



Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $\frac{\sqrt{3}}{4}r^2$ (b) $\frac{4}{5}r^2$

(c) $\frac{3}{5}r^2$ (d) $\frac{\sqrt{5}}{4}r^2$

12. In the adjoining figure a quadrant (of circle) inscribes a square of maximum possible area. If the radius of the circle be 'r' then what is the area of the square?



(a) $\frac{r^2}{2}$ (b) $\frac{3r^2}{5}$

(c) $\frac{r^2}{\sqrt{3}}$ (d) $2\sqrt{6}r$

13. In the adjoining figure, *AB* is the diameter of a semicircle which inscribes a circle of maximum possible area. If the radius of the larger circle (i. e., semicircle) is *r*, the area of the inscribed circle is :



(a) $\frac{5r^2}{\pi}$ (b) $\frac{2\pi}{\sqrt{3}}r^2$

(c) $\frac{\pi r^2}{4}$ (d) none of these

14. In a quadrant (of a circle) a circle of maximum possible area is given. If the radius of the circumscribing quadrant be *r*, then what is the area of the inscribed circle?



(a) $(2+3\sqrt{2})r^2$ (b) $\frac{\pi r^2}{(3+2\sqrt{2})}$

(c) $\left(\frac{3+2\sqrt{2}}{r^2}\right)\pi$ (d) none of these

15. A cylindrical chocobar has its radius *r* unit and height '*h*' unit. If we wish to increase the volume by same unit either by increasing its radius alone or its height alone, then how many unit we have to increase the radius or height?

(a) $\frac{r^2+2r}{h}$ (b) $\frac{r^2-2rh}{h}$

(c) $\frac{2r^2-rh}{h^2}$ (d) $\frac{\pi r^2}{2h}$

16. A 12 cm long wire is bent to form a triangle with one of its angle as 60°. Find the sides of the triangle (in cm) when its area is largest?

(a) 3, 4, 5 (b) 2, 4, 6

(c) 4, 4, 4 (d) 2.66, 3.66, 4.66

17. Let $S_1, S_2, \ldots, S_n$ be the squares such that for each $n > 1$, the length of a side of S_n equals the length of the diagonal of $S_{(n+1)}$. If the length of a circle of S_1 is 10 cm, then for which of the following values of *n* the area of S_n is less than 1 square cm?

(a) 4 (b) 8

(c) 6 (d) 7

18. Area of a regular hexagon and a regular octagon is same. Which one of the two has larger perimeter?

(a) Hexagon (b) Octagon

(c) can't be determined (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-10.1

1. (b)	2. (c)	3. (c)	4. (b)	5. (a)	6. (a)	7. (b)	8. (a)	9. (a)	10. (c)
11. (b)	12. (d)	13. (a)	14. (b)	15. (b)	16. (c)	17. (c)	18. (d)	19. (c)	20. (b)
21. (b)	22. (a)	23. (c)	24. (c)	25. (c)	26. (b)	27. (c)	28. (c)	29. (b)	30. (c)
31. (b)	32. (c)								

INTRODUCTORY EXERCISE-10.2

1. (b)	2. (c)	3. (a)	4. (a)	5. (d)	6. (a)	7. (c)	8. (b)	9. (a)	10. (a)

INTRODUCTORY EXERCISE-10.3

1. (a)	2. (c)	3. (d)	4. (b)	5. (d)	6. (b)	7. (a)	8. (b)	9. (d)	10. (c)
11. (b)	12. (a)	13. (b)	14. (d)	15. (a)					

INTRODUCTORY EXERCISE-10.4

1. (d)	2. (d)	3. (a)	4. (b)	5. (c)	6. (d)	7. (a)	8. (a)	9. (a)	10. (b)
11. (c)	12. (d)	13. (b)	14. (a)	15. (b)	16. (a)	17. (a)	18. (c)	19. (a)	20. (c)
21. (a)	22. (b)	23. (b)	24. (c)	25. (c)					

INTRODUCTORY EXERCISE-10.5

1. (b)	2. (c)	3. (a)	4. (b)	5. (c)	6. (a)	7. (b)	8. (a)	9. (b)	10. (c)
11. (d)	12. (a)	13. (c)	14. (b)	15. (c)	16. (a)	17. (b)	18. (d)	19. (b)	20. (c)
21. (d)	22. (b)	23. (c)	24. (a)	25. (b)	26. (a)	27. (c)	28. (c)	29. (c)	30. (b)
31. (b)	32. (b)								

INTRODUCTORY EXERCISE-10.6

1. (b)	2. (c)	3. (c)	4. (c)	5. (b)	6. (a)	7. (c)	8. (b)	9. (a)	10. (c)
11. (a)	12. (a)	13. (d)	14. (a)	15. (d)	16. (c)	17. (a)	18. (b)	19. (a)	20. (b)
21. (c)	22. (a)	23. (d)	24. (c)	25. (d)	26. (d)	27. (d)	28. (c)	29. (b)	30. (c)
31. (b)	32. (a)	33. (d)	34. (c)	35. (c)	36. (b)	37. (b)	38. (a)	39. (b)	40. (a)

INTRODUCTORY EXERCISE-10.7

1. (b)	2. (c)	3. (c)	4. (a)	5. (b)	6. (c)	7. (c)	8. (d)	9. (c)	10. (c)
11. (b)	12. (a)								

MISCELLANEOUS

1. (c)	2. (c)	3. (c)	4. (c)	5. (c)	6. (a)	7. (c)	8. (a)	9. (c)	10. (a)
11. (d)	12. (c)	13. (a)	14. (c)	15. (d)	16. (b)	17. (b)	18. (c)	19. (b)	20. (d)
21. (b)	22. (c)	23. (d)	24. (c)	25. (d)	26. (d)	27. (d)	28. (b)	29. (b)	30. (b)
31. (a)	32. (c)	33. (d)	34. (c)	35. (a)	36. (c)	37. (b)	38. (c)	39. (d)	40. (a)
41. (b)	42. (a)	43. (c)	44. (c)	45. (a)	46. (b)	47. (b)	48. (c)	49. (d)	50. (b)
51. (c)	52. (c)	53. (a)	54. (d)	55. (c)	56. (a)	57. (b)	58. (a)	59. (c)	

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL-1

1 (a)	2. (b)	3. (b)	4. (b)	5. (c)	6. (d)	7. (c)	8. (b)	9. (a)	10. (c)
11. (c)	12. (a)	13. (b)	14. (a)	15. (a)	16. (c)	17. (a)	18. (c)	19. (a)	20. (d)
21. (b)	22. (a)	23. (d)	24. (c)	25. (c)	26. (a)	27. (b)	28. (c)	29. (c)	30. (b)
31. (d)	32. (a)	33. (c)	34. (c)	35. (c)	36. (a)	37. (a)	38. (a)	39. (b)	40. (a)
41. (b)	42. (d)	43. (d)	44. (c)	45. (a)	46. (c)	47. (a)	48. (c)	49. (b)	50. (b)
51. (c)	52. (c)	53. (b)	54. (c)	55. (d)					

LEVEL-2

1 (c)	2. (b)	3. (c)	4. (b)	5. (a)	6. (b)	7. (c)	8. (a)	9. (d)	10. (b)
11. (a)	12. (d)	13. (c)	14. (d)	15. (b)	16. (b)	17. (a)	18. (b)	19. (b)	20. (a)
21. (a)	22. (c)	23. (c)	24. (d)	25. (b)	26. (a)	27. (a)	28. (b)	29. (c)	30. (d)
31. (c)	32. (a)	33. (b)	34. (c)	35. (d)	36. (b)	37. (a)	38. (a)	39. (b)	40. (a)
41. (a)	42. (d)	43. (b)	44. (a)	45. (c)	46. (c)	47. (a)	48. (b)	49. (a)	50. (b)
51. (a)	52. (a)	53. (c)	54. (b)	55. (b)	56. (a)	57. (b)	58. (c)	59. (a)	60. (a)
61. (b)	62. (c)	63. (b)	64. (c)	65. (a)	66. (a)	67. (c)	68. (b)		

TEST OF YOUR LEARNING

1 (c)	2. (b)	3. (a)	4. (c)	5. (c)	6. (a)	7. (b)	8. (c)	9. (d)	10. (a)
11. (b)	12. (a)	13. (c)	14. (b)	15. (c)	16. (c)	17. (b)	18. (a)		

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 10.1

1. $2(16x + 9x) = 750$; $l = 16x$ and $b = 9x$

2. $$\text{Area} = \frac{110}{0.5} = 220 \text{ sq. m}$$
   and $$11x \times 5x = 220$$

3. Length : breadth = 3 : 2
   Also, area of floor = area of roof

   and 30 is almost 50% of 62. So you need not to solve just look out for the appropriate option thus 1411.2 is almost 50% of 2916.48 and rest of the options are not satisfactory.

4. 1 hectares = 10000 m^2, find length and breadth, then perimeter
   Perimeter = 1000 m = 1 km
   $$\therefore \quad \text{Time} = \frac{\text{distance}}{\text{speed}} = \frac{1}{3} \text{ hrs} = 20 \text{ min}$$

5. 5 hectares and 76 ares = 57600 m^2, find perimeter then multiply it by 6.

6. $l \times 0.7 = 19 \times 3.5 \Rightarrow l = 95$ m (70 cm = 0.7 m)
   Also $(95)^2 = 9025$
   So $95 \times 0.95 = 90.25$

7. $$\text{Number of stones} = \frac{\text{Area of courtyard}}{\text{Area of one stone}} = 14400$$
   Cost = Rate × number of stones
   $= (0.5 \times 14400)$

8. Area $= (63 + 54 - 6) \times 6$ [$\because$ Area $= (l + b - 2w)\, 2w$]
   Area $= (111 \times 6)$
   and $$\text{Rate} = \frac{37}{2} = \frac{37 \times 3}{2 \times 3} = \frac{111}{6}$$
   $$\therefore \quad \text{Cost} = (111 \times 6) \times \frac{111}{6}$$
   $$= 111 \times 111 = 12321$$

9. Original area $= l \times b$
   New area $= 2l \times \frac{b}{2} = l \times b$
   Hence, no change.

10. $(116 + 68 - 2w)\, 2w = 720$
    Solve through quadratic equation.
    Alternatively: Go through options and put $w = 2$ from option (c) you will find that both sides are equal. So the presumed choice is correct.

11. Net area = Total area of 4 walls – $8 m^2$
    and Area of 4 walls $= 2(l + b) \times h$

12. $$d^2 = 2 \times \text{area} \qquad \left(\because \text{Area} = \frac{d^2}{2}\right)$$
    $$d^2 = 2 \times 2 \Rightarrow d = 2 \text{ km}$$

13. $100 \times 100 = 10000 \ m^2 = 1$ hectare
    $111 \times 111 = 12321 \ m^2$
    $\therefore$ Difference in area = 2321 m^2

14. $$\text{Rate} = \frac{759 - 561}{6} = \text{Rs. } 33 \text{ per metre}$$

15. $$l \times b = \frac{1}{25} \times 10000 = 1000 \times b$$
    $$\Rightarrow \quad b = 0.4 \text{ m}$$

16. $$\text{Side} = \sqrt{(289)^2 - (240)^2}$$

17. $$\frac{1600 \times 900}{40 \times 20} = 1800$$

18. $$\text{Area} = \frac{d^2}{2}$$

19. $$\frac{1}{3} \times \frac{1}{3} = \frac{1}{9}$$
    $$\therefore \quad 90 \times \frac{1}{9} = 10 \text{ g} \qquad \text{(It depends upon area)}$$

20. $l : b = 2 : 1$
    $2x^2 = 24200$, find diagonal.
    $\sqrt{(110)^2 + (220)^2} = 110\sqrt{1^2 + 2^2}$
    $= 110 \times \sqrt{5}$
    $= 110 \times 2.236 = 246$ m

21. $2(2x + x) \times 11 = 2640$, find $2x \times x = ?$

22. Consider some appropriate values.

    e.g., 

    $4a = 16$ cm $\qquad 2(l + b) = 16$ cm
    but $a^2 = 16 \text{ cm}^2$ and $l \times b = 12 \text{ cm}^2$
    $\Rightarrow \quad a^2 > l \times b$

    Remember, when $a + b$ is constant, then the maximum value of $a \times b$ is at when $a = b$.
    So, area of square (i. e., $l \times b = a \times a$) is always greater than area of rectangle with same perimeter.
    Alternatively: Let each side of a square be a and length and breadth of the rectangle be l and b, then
    $$4a = 2(l + b) \Rightarrow a = \left(\frac{l + b}{2}\right)$$
    $\therefore$ Area of the rectangle $= l \times b$
    and Area of the square $= a^2 = \frac{1}{4}(l + b)^2$
    But since we know that for any (different) certain values
    AM > GM
    $$\therefore \quad \frac{l + b}{2} > \sqrt{l \times b}$$
    $$\Rightarrow \quad \left(\frac{l + b}{2}\right)^2 > l \times b$$
    $\Rightarrow$ Area of square > Area of rectangle

Scanned by CamScanner

yoursmahboob.wordpress.com

23. Best way is to go through options and verify the result.

Alternatively: $2(l+b)=4a=80$

$\Rightarrow \quad l+b=40$ and $a=20 \Rightarrow a^2=400$

Also $a^2-lb=100$

$\Rightarrow \quad 400-lb=100$

$\Rightarrow \quad lb=300$

Now $(l-b)^2=(l+b)^2-4lb$

$(l-b)^2=1600-1200$

$\Rightarrow \quad l-b=20$

(Solving $l+b=40$ and $l-b=20$)

$\therefore \quad l=30$ and $b=10$

24. $\frac{100\times100}{25\times25}=16$ (1 m = 100 cm)

25. $(120+80-24)\times24=176\times24=4224$

26. $(90+40+10)\times10=1400$

27. $2[(x+2)+x]=48 \Rightarrow x=11$ cm

$\therefore \quad (x+2)=13$ cm

28. $\frac{52000}{325}=160$

3.25 cm means 325 m, as per scale.

29. Area $=\frac{d^2}{2}$; $d \rightarrow$ diagonal

30. $1.2\times1.2=1.44 \Rightarrow$ 44% increase

31. $a^2:(a\sqrt{2})^2=1:2$

32. $1.6\times1.4=2.24 \Rightarrow$ increase $=1.24 \Rightarrow 124\%$

INTRODUCTORY EXERCISE 10.2

1. Use Hero's formula:

Area of scalene triangle $=\sqrt{s(s-a)(s-b)(s-c)}$

2.



$AM=BC=36$ m

$MD=CD-MC=30-15 \quad (\because MC=AB=15\text{ m})$

$\therefore \quad MD=15$ m

Now using Pythagorus theorem

$AD^2=AM^2+MD^2$, find AD

3. Find the area, using Hero's formula, then

$\text{Area}=\frac{1}{2}\times b\times h$

$=\frac{1}{2}\times56\times AD$



4. All the triangles are similar to each other.

$\therefore \quad \frac{\text{Area of } \Delta ABC}{\text{Area of } \Delta DEF}=\frac{4}{1}$

(Since in ΔABC there are 4 similar triangles having same area as ΔDEF.)



5. $60=\frac{b}{4}\sqrt{4a^2-b^2}$

$\Rightarrow \quad 60=\frac{b}{4}\sqrt{676-b^2}$

$\Rightarrow \quad 57600=b^2(676-b^2)$

By solving the above equation we can get the value of b.

Alternatively: You can go through option.

6. Use pythagorus theorem

$x^2=(60)^2+(11)^2$

[Pythagorus theorem : (Hypotenuse)^2 = (base)^2 + (height)^2]



7. Area of field $=\frac{495.72}{36.72}$

$=13.5$ hectare $=135000$ m^2

Now, if $h=x, \quad b=3x$

$\therefore \quad \frac{1}{2}\times b\times h=135000$

8. Area of triangle $=\frac{1}{2}\times b\times h$

Let initially area of triangle $=1\times1=1$ unit

Now, the area of triangle $=2\times2=4$ unit

Increase in area $=\frac{4-1}{1}\times100=300\%$

(For your convenience assume any value of b and h.)

9. Height of an equilateral triangle $=\frac{\sqrt{3}}{2}\times$ side

$\therefore \quad 2\sqrt{3}=\frac{\sqrt{3}}{2}\times$ side

$\Rightarrow \quad$ Side $=4$ cm

$\therefore$ Area of an equilateral triangle $=\frac{\sqrt{3}}{4}\times(\text{side})^2$

$=\frac{\sqrt{3}}{4}\times4\times4=4\sqrt{3}$ cm^2

10. Let the each side of a square be $3x$ and each side of an equilateral triangle be $4x$

then perimeter of square $=4\times3x=12x$

and perimeter of equilateral triangle $=3\times4x=12x$

Now area of square $=(3x)^2=9x^2$

Area of equilateral triangle $=\frac{\sqrt{3}}{4}\times(4x)^2=4\sqrt{3}x^2$

Since $9x^2>4\sqrt{3}x^2 \Rightarrow 9>4\sqrt{3}$

Hence area of square is greater than area of equilateral triangle, when the perimeter of each is same.

Alternatively: Consider any suitable values and verify.

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 10.3

1. Area $= 6 \times 8 \sin 30°$

$= 6 \times 8 \times \frac{1}{2} = 24 \text{ cm}^2$ $\left(\sin 30° = \frac{1}{2}\right)$

2. To find the area of parallelogram, first find the area of ΔABC by Hero's formula then double it.



Since, area of $ABCD = 2 \times$ Area of ΔABC

$= 2 \times$ Area of ΔACD

3. Area $= 22 \times 24 = 528 \text{ cm}^2$



4. Area $= 40 \times 18 = 720 \text{ cm}^2$



5. $\frac{\text{Area of parallelogram } ABCD}{\text{Area of triangle } ABN} = \frac{BC \times AN}{\frac{1}{2} \times BN \times AN} = \frac{2 \times 4x}{x} = \frac{8}{1}$

6. Area of rhombus $= \frac{1}{2} \times$ product of diagonals

$= \frac{1}{2} \times a \times b = \frac{ab}{2}$

7. Area of rhombus $= \frac{1}{2} \times 2x \times 5x = \frac{10x^2}{2} = 5x^2$

and square of the shorter diagonal $= (2x)^2 = 4x^2$

$\therefore \quad \frac{5x^2}{4x^2} = \frac{5}{4}$

8. $\frac{1}{2} \times x \times 2x = 256$

$\Rightarrow \quad x^2 = 256$

$\Rightarrow \quad x = 16$

$\therefore \quad 2x = 32$

Hence, $x + 2x = 16 + 32 = 48$

9. Area $= \frac{1}{2} \times (30 + 50) \times 16 = 640 \text{ cm}^2$

10. $\frac{\text{Area of } \Delta AOB}{\text{Area of } \Delta COD} = \frac{\frac{1}{2} \times AB \times OQ}{\frac{1}{2} \times CD \times PO}$



$= \frac{AB \times OQ}{CD \times PO}$

$= \frac{2CD \times 2OP}{CD \times OP} = \frac{4}{1}$ $\left(\because \begin{matrix} AB = 2CD \\ \text{and } OQ = 2PO \end{matrix}\right)$

This is due to the similarity of triangles AOB and COD.

11. Area of trapezium $= 441$

$\frac{1}{2}(5x + 9x) \times 21 = 441$

$\Rightarrow \quad 14x = 42 \Rightarrow x = 3$

$\therefore \quad 9x = 27 \text{ cm}$

12. $\frac{1}{2} \times (12 + 8) \times h = 360$

$\Rightarrow \quad h = 36 \text{ m}$

13. $6 \times \frac{\sqrt{3}}{4} \times (\text{Side})^2 = \frac{3\sqrt{3}}{2} (\text{Side})^2$

$= \frac{3\sqrt{3}}{2} \times 4 \times 4 = 24\sqrt{3} \text{ m}^2$

14. Area of quadrilateral $= \frac{1}{2} \times 19 \times (5 + 7) = 114 \text{ cm}^2$

15. $AB = BC = CD = AD = 4 \text{ cm}$ $\left(\because \text{Side} = \frac{\text{Diagonal}}{\sqrt{2}}\right)$

and $EF = 1.5 \text{ cm}$ (By Pythagorus theorem)

$\therefore$ Area of $ABCDE$ = Area of $ABCD$ + Area of AED

$= (4)^2 + \frac{1}{2} \times 4 \times 1.5 = 19 \text{ cm}^2$

INTRODUCTORY EXERCISE 10.4

1. $2\pi r = 704 \Rightarrow r = 112$

$\therefore \quad \pi r^2 = \frac{22}{7} \times 112 \times 112 = 39424 \text{ cm}^2$

2. $2\pi r = 4.4 \Rightarrow r = \frac{7}{10} \text{ m}$

$\therefore \quad \pi r^2 = 0.49\pi \text{ m}^2$

3. $2\pi r = 2 \times \frac{22}{7} \times 4.2$

$= 26.4 \text{ metre}$

$26.4 = 2(6x + 5x)$

$\Rightarrow \quad 6x = 7.2 \text{ m}$

Scanned by CamScanner

yoursmahboob.wordpress.com

4. $2\pi r = 440 \Rightarrow r = 70$ m



$\therefore$ $R = 70 + 14 = 84$ m

5. $r + 2\pi r = 51 \Rightarrow r\left(1 + \frac{44}{7}\right) = 51 \Rightarrow r = 7$,

Find area.

6. $(2\pi r - 2r) = 15 \Rightarrow 2r\left(\frac{22}{7} - 1\right) = 15 \Rightarrow r = \frac{7}{2}$

$\therefore$ $\pi r^2 = \frac{22}{7} \times \frac{7}{2} \times \frac{7}{2} = 38.5\ m^2$

7. $\frac{\text{New area}}{\text{Original area}} = \frac{\pi \times 7 \times 7}{\pi \times 5 \times 5} = \frac{49}{25}$

Change in area $= \frac{24}{25} \times 100 = 96\%$

8. $\frac{\text{New circumference}}{\text{Original circumference}} = \frac{6}{5} = \frac{\text{New radius}}{\text{Original radius}}$

$\therefore$ $\frac{\text{New area}}{\text{Original area}} = \left(\frac{6}{5}\right)^2 = \frac{36}{25}$

$\therefore$ Change in area $= \frac{11}{25} \times 100 = 44\%$

Alternatively: Change $= (1.2 \times 1.2) - (1 \times 1) = 0.44$

$\therefore$ Change $= 44\%$

9. $\pi r^2 = 124.74$ hectare

$\pi r^2 = 1247400\ m^2$

$\Rightarrow$ $r = 630$ m

$\therefore$ $2\pi r = 3960$

$\therefore$ Cost $= 3960 \times 0.8 = 3168$

10. $\pi r^2 = \frac{158400}{1400} \Rightarrow r^2 = 36 \Rightarrow r = 6$ m

11.



Area of square $= a^2$

Area of circular parts $= 4 \times \frac{1}{2} \pi \left(\frac{a}{2}\right)^2 = \frac{\pi a^2}{2}$

$\therefore$ Total area $= a^2 + \frac{\pi a^2}{2} = a^2\left(1 + \frac{\pi}{2}\right)$

12. $\pi r^2 = 2464 \Rightarrow r = 28$ m

13. Basically there are 12 equilateral triangles each of side a.



Fig. (I)



Fig. (II)

$\therefore$ $12 \times \frac{\sqrt{3}}{4} \times (a)^2 = 3\sqrt{3}a^2$

14. $\frac{1}{2} \times \pi \times (7)^2 + 2\left[\frac{1}{2} \times \pi \times \left(\frac{7}{2}\right)^2\right]$

Area of larger semicircle + 2 (area of smaller semicircle)

15. $2\pi \times R \times \frac{75}{360} = 25 \Rightarrow R = \frac{60}{\pi}$

16. Ungrazed area = Area of square − 4 (area of quadrants)



$= (42)^2 - 4 \times \frac{1}{4} \times \pi\ (21)^2 = (21)^2\ [4 - \pi] = 378$

17. $20 + \frac{1}{2} \times [2\pi \times 10] = 20 + 10\pi$

18. $\frac{40}{360} = \frac{1}{9}$ $\therefore$ $\frac{(360 - 40)}{360} = \frac{8}{9}$

$\therefore$ Area of major sector $= 8 \times 8.25 = 66\ cm^2$

19. Area of a sector $= \frac{1}{2} \times$ arc $\times$ radius $= \frac{1}{2} \times 8 \times 5.6 = 22.4\ m^2$

20. $2\pi r = 2 \times \frac{22}{7} \times 700 = 4400$ m $= 4.4$ km

Time $= \frac{\text{Distance}}{\text{Speed}} = \frac{4.4}{13.2} = \frac{1}{3}$ h $= 20$ minute

21. $\pi R^2 = \pi [r_1^2 + r_2^2 + r_3^2]$, find R.

22. $\pi [23^2 - 12^2] = \frac{22}{7} \times [529 - 144] = 1210$

23. $4a = 4 \times 66 = 264 = 2\pi r \Rightarrow r = 42$

$\therefore$ $d = 2r = 84$ m

24. $r = 42$ $\therefore$ $2\pi r = 264 = 4a \Rightarrow a = 66$

$\therefore$ $d = a\sqrt{2} = 66\sqrt{2}$

25. Circumference $= \frac{1100}{560} = \frac{110}{56} = 2\pi r$

$\therefore$ $2r = \frac{110}{56} \times \frac{7}{22} = \frac{5}{8}$ m $= 62.5$ cm

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 10.5

1. Volume of original cube = $(4)^3 = 64$ cm^3
and its weight = 400 kg
Since weight of the larger cube is 8 times the weight of smaller cube. Hence, the volume of new cube will be 8 times the volume of smaller cube.
Hence volume of required cube = $8 \times 64 = (8)^3$
$\therefore$ Edge of this cube = 8 cm

2. Volume of the tank = 3 m^3
$\therefore$ Base area × height = 3 m^3
$\Rightarrow$ Base area $= \frac{3}{2.56} = 1.171875$ m^2
[$\because$ Volume of cuboid = $(l \times b) \times h$ = (base area) × height]

3. Volume of cube = Volume of cuboid
$a^3 = lbh$
$\Rightarrow$ $a^3 = 36 \times 75 \times 80 = 216000$
$\Rightarrow$ $a = 60$ cm

4. Base area × height = Volume
$10 \times 4 \times 1 = 40$ m^3
But 1 m^3 = 1000 litre = 1 kilolitre
$\therefore$ 40 m^3 = 40,000 litre = 40 kilolitre

5. Volume of smaller (required) cube = 8 (dm)^3 = 0.008 m^3
$\therefore$ Number of required cubes $= \frac{\text{Volume of larger cube}}{\text{Volume of each smaller cube}}$
$= \frac{1}{0.008} = 125$

6. Volume of new cube = $(3)^3 + (4)^3 + (5)^3 = 216$ cm^3
$\therefore$ Each edge of the new cube = 6 cm
and hence, surface area = $6 \times (a)^2 = 216$ cm^2

7. Total length of tape = $2(l + b) + 3.75$
$= 2(39.5 + 9.35) + 3.75$
$= 101.45$ cm

8. Area of surface to be cemented = $2 \times (l + b) \times h + (l \times b)$
i.e., area of four walls + area of floor
$= 2 \times (21) \times 4 + (106.25)$
$= 274.25$ m^2
$\therefore$ Cost of cementing = 24×274.25 = Rs. 6582

9. Total volume of water displaced by 250 men
$= 250 \times 4 = 1000$ m^3
$\therefore$ Rise in water level (h) $= \frac{\text{Volume}}{\text{Base area}}$
$= \frac{1000}{80 \times 50} = 25$ cm

10. Let each edge of smaller cube = 1 m
$\therefore$ Each edge of larger cube = 2 m
and Surface area of smaller cube = $6 \times (1)^2 = 6$ m^2
$\therefore$ Surface area of larger cube = $6 \times (2)^2 = 24$ m^2
$\therefore$ % increase in surface area $= \frac{24 - 6}{6} \times 100 = 300\%$

NOTE It can be determined by using variables *e.g., x* (edge of cube) instead of solving by assuming some numerals.

Alternatively : $\frac{S_2}{S_1} = \left(\frac{e_2}{e_1}\right)^2 \Rightarrow \frac{S_2}{S_1} = \frac{4}{1}$
$\therefore$ Percentage increase in surface area $= \frac{4 - 1}{1} \times 100 = 300\%$
where S = surface area, e = edge of cube.

11. $\frac{V_2}{V_1} = \left(\frac{e_2}{e_1}\right)^3$ $\{\because V = (e)^3\}$ {e = edge of cube}
$\therefore$ $\frac{V_2}{V_1} = \left(\frac{2}{1}\right)^3 = \frac{8}{1}$
$\therefore$ $V_2 = 8V_1$

12. External volume of the box = $24 \times 16 \times 10 = 3840$ cm^3
Thickness of the wood = 5 mm = 0.5 cm
$\therefore$ Internal length of box = $24 - 2 \times 0.5 = 23$ cm
Internal breadth of box = $16 - 2 \times 0.5 = 15$ cm
Internal height of box = $10 - 2 \times 0.5 = 9$ cm
$\therefore$ Internal volume of the box = $23 \times 15 \times 9 = 3105$ cm^3
$\therefore$ Volume of the wood = $3840 - 3105 = 735$ cm^3
Now, total weight of wood = Volume × weight of 1 cm^3 wood
$7350 = 735 \times$ weight of 1 cm^3 wood
$\therefore$ Weight of 1 cm^3 wood = 10 gm

13. Length of tank = 120 cm
But since, $\frac{120}{7} = 17\frac{1}{7}$, hence 17 cubes can be placed along length and breadth of tank = 80 cm
But since, $\frac{80}{7} = 11\frac{3}{7}$, hence 11 cubes can be placed along breadth and height of tank = 50 cm.
But since, $\frac{50}{7} = 7\frac{1}{7}$, hence only 7 cubes can be placed along height of the tank.
$\therefore$ Total volume occupied by these cubes = $(7)^3 \times 17 \times 11 \times 7$
$= 448987$ cm^3
Total volume of the tank = $120 \times 80 \times 50 = 480000$ cm^3
$\therefore$ Area of unoccuppied space = $480000 - 448987$
$= 31013$ cm^3 = 31.013 dm^3

14. Surface area of the cuboid = $2(lb + bh + hl) = 11.6$ m^3
$\therefore$ Cost of canvas = 11.6×25 = Rs. 290

15. Required surface area = $2(9 \times 3 + 3 \times 3 + 3 \times 9) = 126$ cm^2

16. Area of 4 walls = $2(36 + 12) \times 10 = 960$ m^2
Total area of (windows + door + chimney) = 120 m^2
$\therefore$ Net area for papering = $960 - 120 = 840$ m^2
$\therefore$ Length of required paper $= \frac{840}{1.2} = 700$ m
Hence, cost of papering = 700×0.7 = Rs. 490

17. Number of children × Space required for one child
= Volume of room
$\therefore$ Number of children $= \frac{30 \times 12 \times 6}{8} = 270$

Scanned by CamScanner

yoursmahboob.wordpress.com

18. $(x+2)^3 - x^3 = 1016$

$\Rightarrow \quad x = 12$ cm

and $\quad x^3 - (x-2)^3 = (12)^2 - (10)^2 = 728$

19. You can see the figure shown in the question number 15. Now let us consider that surface area of each face of the cube 1 cm^3.

$\therefore$ Total surface area of the cuboid = 14 cm^2

and Total surface area of the 3 cubes = 18 cm^2

Hence, required ratio = 14 : 18 = 7 : 9

NOTE In the arrangement of cuboid there are only 14 faces visible to us.

20. Iron used in the tube

= Difference in external and internal volumes of the tube



$\therefore \quad 192 = 8x^2 - 8(5)^2$

$\Rightarrow \quad x = 7$ cm

Hence, the thickness of the tube $= \frac{7-5}{2} = 1$ cm

21. Base area of vessel × rise in water level = Volume of cube

$15 \times 12 \times h = 11 \times 11 \times 11$

$\Rightarrow \quad h = 7.39$ cm

22. (Initial volume of water + required volume of water + volume of cube)

= Base area of vessel × 10

$\therefore 25 \times 20 \times 5 +$ required volume of water $+ 1000 = 25 \times 20 \times 10$

$\Rightarrow$ Required volume of water = 1500 cm^3 = 1.5 litre

23. Net volume = $(10 \times 8 \times 2) - (2 \times 2 \times 2) = 152$ cm^3

Net surface area = $2(10 \times 8 + 8 \times 2 + 2 \times 10) + 4(2 \times 2) - 2(2 \times 2)$

= 240 cm^2

24. Available area for spreading the earth

$= (600 \times 200) - (24 \times 12)$

$= 119712$ m^2

Volume of the earth = 119712 × rise in level

$24 \times 12 \times 8 = 119712 \times h$

$\Rightarrow \quad h = \frac{2304}{119712}$

$= 0.01924$ m $= 1.92$ cm

25. Net volume of the wall

= Total volume − Volume taken away due to doors

$= (30 \times 0.3 \times 5) - 2(4 \times 2.5 \times 0.3) = 39$ m^3

Volume of the bricks $= 39 \times \frac{8}{9}$

(Since $\frac{1}{9}$ part is lime in the wall)

$\therefore$ Number of bricks $= \frac{39 \times 8}{9 \times 0.2 \times 0.16 \times 0.08}$

$= 13541.66 \approx 13600$

26. Volume of water which flow in 25 minutes

$= 25 \times 60 \times 0.05 \times 0.03 \times 16 = 36$ m^3

$\therefore$ Rise in water level $= \frac{36}{15 \times 12} = \frac{1}{5}$ m $= 0.2$ m

27. A tetrahedron is a pyramid with triangular base hence it has total $(3+1) = 4$ vertices.

(See the figure shown after exercise 10.6)

28. $a\sqrt{3} = 6\sqrt{3} \Rightarrow a = 6$ cm

29. $\sqrt{l^2 + b^2} = 12 \Rightarrow l^2 + b^2 = 144$

and $\quad \sqrt{l^2 + b^2 + h^2} = 15$

$\Rightarrow \quad l^2 + b^2 + h^2 = 225$

$\Rightarrow \quad h^2 = 81 \Rightarrow h = 9$ m

30. $l + b + h = 12$ cm, $\sqrt{l^2 + b^2 + h^2} = 5\sqrt{2}$

$\Rightarrow \quad l^2 + b^2 + h^2 = 50$

Now, $\quad (l+b+h)^2 = l^2 + b^2 + h^2 + 2(lb + bh + hl)$

$\Rightarrow \quad 144 = 50 + 2(lb + bh + hl)$

$\Rightarrow \quad 2(lb + bh + hl) = 94$ cm^2

31. $h : b = 3 : 1$ and $l : h = 8 : 1$

$\Rightarrow \quad l : h : b = 24 : 3 : 1$

$\therefore \quad 24x \times 3x \times x = 36.864$

$\Rightarrow \quad x^3 = 0.512 \Rightarrow x = 0.8$

$\therefore \quad h = 3x = 2.4$ m

32. $lb = x, \quad bh = y, \quad hl = z$

$\therefore \quad lb \times bh \times hl = xyz$

$\Rightarrow \quad (lbh)^2 = xyz \Rightarrow lbh = \sqrt{xyz}$

INTRODUCTORY EXERCISE 10.6

1. Required volume of water $= \frac{22}{7} \times (0.04)^2 \times 3500$

$= 17.6$ m^3

2. $h = \frac{10 \times 10 \times 10}{\pi \times 10 \times 10} = 3\frac{2}{11}$ cm

3. $h = \frac{511}{36.5} = 14$ m

4. $2\pi rh = 1056$ cm^2

$\Rightarrow \quad r = \frac{33}{\pi}$ cm

$\therefore \quad \pi r^2 h = \pi \times \left(\frac{33}{\pi}\right)^2 \times 16$

$\Rightarrow \quad$ Volume = 5544 cm^3

Scanned by CamScanner

yoursmahboob.wordpress.com

5. Diameter of the cylinder = edge of the cube = 2 cm

Height of the cylinder = edge of the cube

$\therefore$ Required volume $= (2)^3 - \pi \times (1)^2 \times 2$

$= 8 - \left(\frac{44}{7}\right) = \frac{12}{7}$ cm^3

6. $h = \frac{2\pi rh}{2\pi r} = \frac{17.6}{8.8} = 2$ m

and $2\pi r = 8.8 \Rightarrow r = 1.4$ m

$\therefore$ $\pi r^2 h = \frac{22}{7} \times (1.4)^2 \times 2 = 12.32$ m^3

7. $2r = h \Rightarrow r = \frac{h}{2}$

$\therefore$ $2\pi r(h + r) = 2\pi \times \frac{h}{2}\left(h + \frac{h}{2}\right) = \frac{3}{2}\pi h^2$

8. $2\pi rh = 2 \times \pi \times 2 \times 10 = 40\pi$ m^2

9. $\frac{2\pi rh}{2\pi r(h + r)} = \frac{2}{3} \Rightarrow \frac{h}{h + r} = \frac{2}{3} \Rightarrow \frac{h}{r} = \frac{2}{1}$

$\therefore$ $2\pi r(h + r) = 924$

$\therefore$ $2\pi rh = 924 \times \frac{2}{3} = 616$ cm^2

$\Rightarrow$ $2 \times \pi \times x \times 2x = 616$

$\Rightarrow$ $x = 7$ $\therefore r = 7$ cm and $h = 14$ cm

$\therefore$ $\pi r^2 h = \frac{22}{7} \times (7)^2 \times 14 = 2156$ cm^3

10. $\frac{\pi \times r \times r \times h}{2 \times \pi \times r \times h} = \frac{269.5}{154}$

$\Rightarrow$ $r = 3.5$ cm

Now, $2\pi \times 3.5 \times h = 154$

$\Rightarrow$ $h = 7$ cm

11. $2\pi rh = 1320 \Rightarrow h = 10$ cm

$\therefore$ $2\pi r(h + r) = 2 \times \frac{22}{7} \times 21 \times 31 = 4092$ cm^2

12. $\frac{r}{h} = \frac{3x}{4x}$, $\pi r^2 h = 4851 \Rightarrow x = 3.5$

$\therefore$ $r = 10.5$ m and $h = 14$ m

$\therefore$ $2\pi rh = 2 \times \frac{22}{7} \times 10.5 \times 14 = 924$ m^2

13. $\frac{2\pi r(h + r)}{2\pi rh} = \frac{4}{1} \Rightarrow \frac{h + r}{h} = \frac{4}{1}$

$\Rightarrow$ $\frac{r}{h} = \frac{3}{1}$

Alternatively : Go through options.

14. $2\pi r = 33 \Rightarrow r = \frac{21}{4}$

$\therefore$ Volume $= \pi r^2 h = \frac{22}{7} \times \left(\frac{21}{4}\right)^2 \times 330$

$= 28586.25$ cm^3

15. $\frac{r_1}{r_2} = \frac{4x}{x}$, but $V_1 = V_2$

$\therefore$ $\pi (4x)^2 \times h_1 = \pi (x)^2 h_2$

$\Rightarrow$ $h_2 = 16h_1$

16. $2\pi r(h + r) = 2640$

$\Rightarrow$ $2\pi r(30) = 2640$

$\Rightarrow$ $r = 14$ m

$\Rightarrow$ $h = 16$ m $(\because r + h = 30$ m$)$

$\therefore$ $h : r = 8 : 7$

17. $\frac{V_1}{V_2} = \frac{\pi (r_1)^2 h_1}{\pi (r_2)^2 h_2} = \frac{3 \times 3 \times 4}{5 \times 5 \times 3} = \frac{12}{25}$

18. $\frac{V_1}{V_2} = \frac{1}{1}$

$\left(\frac{r_1}{r_2}\right)^2 \times \frac{h_1}{h_2} = \frac{1}{1} \Rightarrow \left(\frac{r_1}{r_2}\right)^2 \times \frac{3}{1} = \frac{1}{1}$

$\Rightarrow$ $\left(\frac{r_1}{r_2}\right)^2 = \frac{1}{3} \Rightarrow \frac{r_1}{r_2} = \frac{1}{\sqrt{3}}$

19. $\frac{2\pi r_1 h_1}{2\pi r_2 h_2} = \frac{3}{2} \times \frac{6}{7} = \frac{9}{7}$

20. $h = 42$ cm, $2\pi R = 132$ cm

$\Rightarrow$ $R = 21$ cm

$\therefore$ $r = 21 - 3 = 18$ cm

$\therefore$ Required volume $= \pi (R^2 - r^2) h$

$= \frac{22}{7}[(21)^2 - (18)^2] \times 42$

$= 15444$ cm^3

21. Since radius and height of the cylinder are same as that of cone. Therefore cylinder can contain $15 \times 3 = 45$ litre of milk.

HINT Volume of cone $= \frac{1}{3}\pi r^2 h$ and volume of cylinder $= \pi r^2 h$.

22. Best way is to go through option.

Alternatively : $\frac{V_1}{V_2} = \frac{1}{27}$

$\frac{(r_1)^2 h_1}{(r_2)^2 h_2} = \frac{1}{27}$

$\Rightarrow$ $\frac{x_1^3}{x_2^3} = \frac{(1)^3}{(3)^3} \Rightarrow \frac{x_1}{x_2} = \frac{1}{3}$

$\Rightarrow$ $\frac{h_1}{h_2} = \frac{1}{3}$

$\therefore$ $h_1 = \frac{h_2}{3} = \frac{30}{3} = 10$ cm



Hence, cone is cut off at $(30 - 10 =)$ 20 cm above the base.

HINT For more clarification of the concept seek help from geometry. (Similarity of triangles)

23. Volume of conical tent $= \frac{1}{3} \times \frac{22}{7} \times \frac{13}{2} \times \frac{13}{2} \times 10.5$

$\therefore$ Average space per man $= \frac{\text{Volume of tent}}{8} = 58\frac{3}{32}$

24. $\frac{1}{3} \times \pi \times (5x)^2 \times (12x) = 314\frac{2}{7} = \frac{2200}{7}$

$\Rightarrow$ $x = 1$

$\therefore$ $r = 5$ and $h = 12$

$\therefore$ $l = 13$ m

Scanned by CamScanner

yoursmahboob.wordpress.com

25. $\frac{1}{3} \times \frac{22}{7} \times r^2 \times 24 = 1232$

$\Rightarrow \quad r = 7$ cm

$\therefore \quad \pi r l = \frac{22}{7} \times 7 \times 25 = 550 \text{ cm}^2 \quad (\because l = \sqrt{r^2 + h^2})$

26. $2\pi r = 220 \Rightarrow r = 35$ cm

$\therefore \quad l = \sqrt{r^2 + h^2} = 91$ cm

$\therefore \quad \pi r l = \frac{22}{7} \times 35 \times 91 = 10010 \text{ cm}^2$

27. Area of cloth $= \pi r l = \frac{22}{7} \times 14 \times 50 = 2200 \text{ m}^2$

$\therefore \quad$ Length of cloth $= \frac{2200}{10} = 220$ m

28. $\pi r l = 23.10$

$\Rightarrow \quad r l = 2.1 \times 3.5$

Now, we know that $h = 2.8$. So we can assume the value of r from the given option.

at $\quad r = 2.1, \quad l = 3.5 \quad (\because l = \sqrt{r^2 + h^2})$

Alternatively : $r^2 (r^2 + h^2) = (2.1 \times 3.5)^2$

$\Rightarrow \quad r^4 + (2.8)^2 r^2 = (7.35)^2$

$\Rightarrow \quad r^4 + 7.84 r^2 = 54.0225$

$\Rightarrow \quad k^2 + 7.84k - 54.0225, \quad k = r^2$

Now, solve the above quadratic equation, if you can else substitute the value of r from the given choices.

29. $\frac{\pi r_1 l_1}{\pi r_2 l_2} = \frac{3}{2} \quad (\because r_1 = r_2)$

$\therefore \quad \frac{A_1}{A_2} = \frac{3}{2} \Rightarrow \frac{A_1}{300} = \frac{3}{2}$

$\therefore \quad A_1 = 450 \text{ cm}^2$

30. $\frac{\text{Volume of cylinder}}{\text{Volume of cone}} = \frac{\pi r^2 h}{\left(\frac{1}{3}\right) \pi r^2 h} = \frac{1}{\left(\frac{1}{3}\right)} = \frac{3}{1}$

31. By Pythagorus theorem

$AD = 3$ cm

$\therefore$ Area of axial section

$= \frac{1}{2} \times 8 \times 3$

$= 12 \text{ cm}^2$



32. $\frac{V_2}{V_1} = \frac{(1.4)^3}{(1)^3} = \frac{2.744}{1}$

$\therefore$ % increase in volume $= \left[\frac{2.744 - 1}{1}\right] \times 100 = 174.4\%$

33. Area of circular sheet $= 625\pi$

Since length of arc and area of sector are directly proportional to the central angle.

Therefore, length of remaining arc $= \frac{96}{100} \times 2 \times \pi \times 25 = 48\pi$

But the remaining arc is equal to the circumference of the base of circular cone.

$\therefore \quad 2\pi R = 48\pi \Rightarrow R = 24$ cm

Now, since the slant height of cone is equal to the radius of the original circular sheet.

Hence, $\quad l = 25$ cm

$h = 7$ cm $\quad (\because l = \sqrt{r^2 + h^2})$

$\therefore \quad \frac{\text{Radius}}{\text{Height}} = \frac{24}{7}$

34. $\frac{V_2}{V_1} = \frac{(r_2)^2 h_2}{(r_1)^2 h_1} = \frac{(2r)^2}{(r)^2} \quad (\because h_1 = h_2)$

$\Rightarrow \quad \frac{V_2}{V_1} = \frac{4}{1}$

35. Each edge of cube= 10 cm

Radius of base of cone = 5 cm

Height of cone = 10 cm

$\therefore$ Volume of cone $= \frac{1}{3} \times \frac{22}{7} \times 25 \times 10 = 261.9 \text{ cm}^2$

36. $\frac{V_2}{V_1} = \frac{r_1^2 \times h_1}{r_2^2 \times h_2} = \frac{2 \times 2 \times 2}{1 \times 1 \times 1} = \frac{8}{1}$

37. $\frac{BD}{AB} = \cos 60°$

$\frac{BD}{AB} = \frac{1}{2}$



$BD = CD$, are the radii of the base and $AB = AC$ are the slant heights of the cone. A is the vertex and BC is the base.

38. Volume of cone $= \frac{1}{3} \pi \times 144 \times 35$

Volume of water flowing per second $= \pi \times (0.8)^2 \times \frac{500}{60}$

$\therefore \quad$ Required time $= \frac{\left(\frac{\pi}{3}\right) \times 144 \times 35}{\pi \times 0.64 \times \left(\frac{500}{60}\right)}$

$= 315$ seconds

39. Use the given formula :

$$\text{Volume} = \frac{\pi}{3} h (r^2 + Rr + R^2)$$

where $\pi = \frac{22}{7}, \quad h = 6, \quad R = 4 \quad$ and $\quad r = 2$

40. $\frac{1}{3} \pi \times (10)^2 \times 72 = \pi \times (30)^2 \times h$

$\Rightarrow \quad h = \frac{8}{3} = 2\frac{2}{3}$ cm

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 10.7

1. $\frac{4}{3}\pi(r_1^3 + r_2^3 + r_3^3) = \frac{4}{3}\pi(6)^3$

$\Rightarrow \quad 27 + 64 + r_3^3 = 216$

$\Rightarrow \quad r_3^3 = 125$

$\Rightarrow \quad r_3 = 5\text{ cm}$

2. $\pi r^2 \times 144 = \frac{4}{3}\pi \times (12)^3$ (∵ Volume remains constant)

$\Rightarrow \quad r = 4\text{ cm}$

3. Number of bottles × Volume of each bottle = Volume of hemisphere

$n \times \pi \times (3)^2 \times 1 = \frac{2}{3}\pi \times (6)^3$

$\Rightarrow \quad n = 16$

4. $\frac{1}{3}\pi \times (r)^2 \times 14 = \frac{2}{3}\pi \times (7)^3$

5. Volume of the spherical shell $= \frac{4}{3}\pi(R^3 - r^3)$

$= \frac{4}{3}\pi(7^3 - 5^3)$

$= \frac{872}{3}\pi$

6. Since volume is constant

$\therefore \quad n \times \frac{4}{3}\pi(1)^3 = \frac{4}{3}\pi \times (8)^3$

$\Rightarrow \quad n = 512$

7. Volume of hemisphere $= \frac{2}{3}\pi r^3$

$= \frac{2}{3} \times \frac{22}{7} \times (21)^3 = 19404\text{ m}^3$

8. Change in height (or level) of water $= \frac{\text{Volume of sphere}}{\text{Base area of cylinder}}$

$= \frac{\frac{4}{3}\pi \times (9)^3}{\pi \times (12)^2} = \frac{27}{4}\text{ cm}$

9. Volume of cone = Volume of sphere

$\frac{1}{3}\pi r^2 \times \frac{7}{2} = \frac{4}{3}\pi(7)^3$

$\Rightarrow \quad r = 14\sqrt{2}\text{ cm}$

10. **Note:** The exact value of the required surface area cannot be found using the general formula. For the exact value of total surface area we have to solve it with the help of calculus. In the following solution we are calculating lumpsum value of total surface area.

Now, $OA = \sqrt{(OP)^2 - (AP)^2}$

$= \sqrt{(15)^2 - (9)^2} = 12\text{ cm}$

$\therefore \quad AB = 2 \times OA = 24\text{ cm}$



$\therefore$ Height of cylinder = 24 cm

$\therefore$ Required area = Surface area of sphere − 2 (area of each end of cylinder) + curved surface area of cylinder

$= 900\pi - 2(81\pi) + 432\pi = 1170\pi\text{ cm}^2$

11. Volume of pyramid $= \frac{1}{3} \times$ base area × height

$= \frac{1}{3} \times 25 \times 12 = 100\text{ cm}^3$

12. Volume of prism = Base area × height

Since base area is constant and height is being halved therefore volume will also be halved. Hence, its volume will be reduced by 50%.

Scanned by CamScanner

yoursmakbooks.wordpress.com

LEVEL 1

1. With the given perimeter the area of parallelogram will be maximum when it will be a rhombus.
Hence (a) is correct.
Alternatively :



$$\text{Perimeter} = 2d + 2b = 4h + 2b = 64 \text{ cm}$$

$$\Rightarrow \quad b = \frac{64 - 4h}{2}$$

$$\therefore \quad \text{Area} = b \times h = \frac{64h - 4h^2}{2} = f(A)$$

$$\therefore f'(A) = \frac{1}{2}(64 - 8h) \text{ (Refer the differentiation)}$$

For the maximum area $= f'(A) = 0$

$$\therefore \quad \frac{1}{2}(64 - 8h) = 0$$

$$\Rightarrow \quad h = 8 \text{ cm} \quad \text{and} \quad d = 16 \text{ cm}$$

$$\therefore \quad b = 16 \text{ cm}$$

2. Volume of water displaced = volume of sphere

$$\pi \times (40)^2 \times h = \frac{4}{3}\pi \times (30)^3$$

$$\Rightarrow \quad h = \frac{90}{4} = 22.5 \text{ cm}$$

Thus, the level of water rises by 22.5 cm.

NOTE The volume of water will be calculated by considering it in the cylindrical shape since the water takes the shape of vessel in which it is filled.

3. O is the starting point and L is the end point.



$$(OL)^2 = (24)^2 + (10)^2$$

$$OL^2 = 676$$

$$\Rightarrow \quad OL = 26 \text{ m}$$

4.



$$a^2 + b^2 = 13^2 = 169$$

and $$\frac{a \times b}{2} = 30$$

Now $$(a + b)^2 = a^2 + b^2 + 2ab$$

$$(a + b)^2 = 169 + 120$$

$$\Rightarrow \quad a + b = 17 \quad \ldots(i)$$

Again $$(a - b)^2 = (a + b)^2 - 4ab$$

$$(a - b)^2 = 289 - 240$$

$$\Rightarrow \quad (a - b) = 7 \quad \ldots(ii)$$

$\therefore$ From Eq. (i) and (ii), we get

$$a = 12 \text{ cm} \quad \text{and} \quad b = 5 \text{ cm}$$

Now, $$\text{inradius} = \frac{(\text{Altitude} + \text{Base} - \text{Hypotenuse})}{2}$$

$$= \frac{(12 + 5 - 13)}{2} = 2 \text{ cm}$$

Alternatively: $$\text{Inradius } (r) = \frac{\text{Area}}{\text{Semiperimeter}}$$

$$= \frac{30}{15} = 2 \text{ cm}$$

$$\left(\text{Semiperimeter} = \frac{(12 + 5 + 13)}{2} = 15\right)$$

NOTE If you are well aware with Pythagorian triplets then it is very easy to find the sides (*i.e.*, altitude and base) of the right angle triangle.

5. General phenomenon: A convex polygon in which there is maximum number of sides, it has the greatest enclosed area when the perimeter of the polygon is constant. Remember that in a circle there are infinite sides of minimum possible length. So, the area of circle will be maximum.
Alternatively: Perimeters of hexagon and circumference of circle are same *i. e.*,

$$6a = 2\pi r \quad \Rightarrow \quad 21a = 22r$$

where a is the side of hexagon and r is the radius of circle.

then $$\text{Area of circle} = \pi r^2$$

and $$\text{Area of hexagon} = 6 \times \frac{\sqrt{3}}{4} \times a^2$$

$$= \frac{3\sqrt{3}}{4} \times \left(\frac{22r}{21}\right)^2$$

$$= \frac{3\sqrt{3}}{4} \times \frac{22}{7 \times 3} \times \frac{22}{7 \times 3} \times r^2$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{\sqrt{3}}{4} \times \frac{22}{21} \pi r^2 = 0.45\pi r^2$$

Therefore, area of circle πr^2 is greater than area of hexagon.
Similarly you can compare other figures.

Alternatively: Consider some suitable values. Let us assume perimeter of square and hexagon is 24 cm, then each side of square = 6 cm.

and Area = 36 cm^2

Similarly, each side of hexagon = 4 cm

and area of hexagon $= \frac{3\sqrt{3}}{2} \times (4)^2 = 24\sqrt{3}$ cm^2

Thus, we can say that for a particular (or constant) value of perimeter, area of hexagon is greater than that of square.

Similarly each side of octagon = 3 cm $\left(= \frac{24}{8}\right)$

$\therefore$ Area of octagon $= 2a^2(1 + \sqrt{2})$

$= 2 \times 9 (1 + \sqrt{2})$

≈ 43.5 cm^2

Thus, the area of octagon is greater then the area of hexagon.

Similarly, $2\pi r = 24 \Rightarrow r = \frac{12}{\pi}$ cm

$\therefore$ Area of circle $= \pi \times r^2$

$= \pi \times \frac{12}{\pi} \times \frac{12}{\pi} = 45.81$ cm^2

Thus, we can say that ultimately the area of the circle is greatest.

6.



Since sum of all the angles of a quadrilateral is 360°.

Therefore, $\angle A + \angle B + \angle C + \angle D = 360°$

$\Rightarrow \angle C + \angle D = 180°$

$\Rightarrow \angle D = 180° - \angle C$

7. $\angle ABC = 60°$

$\therefore \angle GBC = 90° - 60° = 30°$

Again $\angle BGC + \angle BCG = 180° - 30°$

$= 150°$

Now, since $\angle BGC = \angle BCG$

$\therefore \angle BGC = 75°$



NOTE In a triangle when two sides are equal, then the two angles opposite to these sides are also equal.

8. $\frac{r}{R} = \frac{3x}{4x}$

$\because 4x - 3x = 2$

$\Rightarrow x = 2$

$\therefore$ Outer radius = 8 cm

$\therefore$ Area of outer circle $= \pi \times (8)^2 = 64\pi$ cm^2



9. $\frac{h}{a} = \sin 60°$

$\frac{h}{a} = \frac{\sqrt{3}}{2}$

$\Rightarrow h = \frac{a\sqrt{3}}{2}$



$\therefore$ Area of rhombus $= a \times h = \frac{a \times \sqrt{3}a}{2}$

and Area of square $= a^2$

$\therefore$ Required ratio $= \frac{a^2}{\sqrt{3}a^2} \times 2 = \frac{2}{\sqrt{3}} \times \left(\frac{\sqrt{3}}{\sqrt{3}}\right) = \frac{2\sqrt{3}}{3}$

10.



$ABCD$ is a square,

$AB = BC = CD = AD = 20$ cm

and P, Q, R and S are the mid-points.

$\therefore PS = SR = RQ = PQ = 10\sqrt{2}$ cm ($\because AP = BP$ etc $= 10$ cm)

$\therefore$ Area of square $PQRS = (10\sqrt{2})^2 = 200$ cm^2

Alternatively: We can see that there are total 8 equal parts (or triangles) out of 8 we have taken only 4 parts *i.e.*, 50% area has been cut out.
So, the remaining area = 50% of 400 = 200 cm^2.



11. Area of right angle triangle

$= \frac{(x + 2) \times (2x + 3)}{2} = 60$

$\Rightarrow 2x^2 + 7x + 6 = 120$

$\Rightarrow 2x^2 + 7x - 114 = 0$

Solving the above quadratic equation, we get



$x = 6$

$\therefore x + 2 = 8$ cm

and $2x + 3 = 15$ cm

$\therefore$ Hypotenuse $AB = \sqrt{(8)^2 + (15)^2} = 17$ cm

(Using Pythagorus theorem)

12. Let us assume $PQRSTUVW$ is a regular octagon with each side a unit. Again, if we produce all the sides of octagon in both sides we get a square. Since each of the side of octagon is 'a' then

$UV = WP = QR = ST = a$



Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore \quad DU = DV \text{ (etc.)} = \frac{a}{\sqrt{2}}$

$\therefore \quad DU + UT + TC = \frac{a}{\sqrt{2}} + a + \frac{a}{\sqrt{2}}$

$= a(1 + \sqrt{2})$

$\therefore \quad$ Area of square $= a^2 (1 + \sqrt{2})^2$

$= a^2 (3 + 2\sqrt{2})$ sq unit

Again, area of each shaded portion (*i.e.*, an isosceles right angle triangle)

$= \frac{1}{2} \times \frac{a}{\sqrt{2}} \times \frac{a}{\sqrt{2}} = \frac{a^2}{4}$

$\therefore$ Total area of all the shaded region $= 4 \times \frac{a^2}{4} = a^2$

$\therefore$ Area of octagon = Area of square $ABCD$ – Area of total shaded region

$= a^2 (3 + 2\sqrt{2}) - a^2$

$= 2a^2 (1 + \sqrt{2})$ sq. unit

13. Let the each side of the square be 2 cm, then

area of square = 4 cm^2 and

area of 4 quadrants of the four circles (*i.e.*, unshaded part inside the square)



$= 4 \times \frac{1}{4} \pi \times (1)^2 = \pi$ cm^2

$\therefore \quad$ Area of shaded region $= (4 - \pi)$ cm^2

Therefore, the required ratio $= \frac{4 - \pi}{\pi} = \frac{6/7}{22/7} = \frac{3}{11}$

14. From the concept of mid point theorem, it is the average of the length of the parallel sides.

15. From the concept of similarity of triangles

$\frac{OP}{OQ} = \frac{1}{5} = \frac{PC}{BQ}$



Since, the ratio in radii of the two cones is 1 : 5. Therefore, the radius of smaller cone ODC is $\frac{21}{5} = 4.2$ cm.

Alternatively: Solve it in the proper way, which is actually a very tedious process. Still you have to apply the concept of similarity of triangles, which you will study in Geometry.

16. $l \times b = 2(l + b)$

$\Rightarrow \quad l = \frac{2b}{(b-2)} = \frac{2(b-2)+4}{b-2} = 2 + \frac{4}{(b-2)}$

Since, l is an integer, so 4 must be divisible by $(b - 2)$. Thus b can be 4 or 6 or 3.

Therefore, if $b = 4$, $l = 4$, it will be a square. If $b = 6$, $l = 3$ and if $b = 3$, $l = 6$.

Hence, $l = 6$ and $b = 3$

$\therefore \quad l - b = 3$

17. Area of $\Delta ABC = \frac{\sqrt{3}}{4} \times (14)^2$

$= 49\sqrt{3}$ cm^2



Area of sector $ABC = \pi \times (14)^2 \times \frac{60}{360}$

$= 102\frac{2}{3}$ cm^2

$\therefore$ Area of the shaded region $= \left(102\frac{2}{3} - 49\sqrt{3}\right)$ cm^2

18. $l_1 \times b_1 = l_2 \times b_2$

New area of first rectangle $= \frac{5}{4} l_1 \times \frac{3}{4} b_1 = \frac{15}{16} l_1 b_1$

New area of the second rectangle $= \frac{3}{4} l_2 \times \frac{5}{4} b_2 = \frac{15}{16} l_2 b_2$

Hence, areas of both the new rectangles are same.

19. $\frac{DM}{AD} = \sin 60°$



$\frac{6\sqrt{3}}{AD} = \frac{\sqrt{3}}{2}$

$\Rightarrow \quad AD = 12$ cm

20. $\frac{4}{3} \pi r^3 = \frac{1}{3} \pi r^2 h$

(Since radii of sphere and cone are same)

$\Rightarrow \quad 4r = h$

$\therefore \quad \frac{h}{r} = \frac{4}{1} \Rightarrow h : r = 4 : 1$

21. Area of the shaded region $= \left[\frac{1}{2} \pi (22)^2 - 2\left(\frac{1}{2} \pi \times (11)^2\right)\right]$

$= \frac{1}{2} \pi \times (11)^2 [4 - 2] = 121\pi$ cm^2

22. Area of path $= (l + b - w) w$

$= (60 + 40 - 5) 5 = 475$ m^2

Cost = Area × rate

$= 475 \times 0.8 =$ Rs. 380

23. Go through options. Let the length and breadth of the second rectangle is l and b respectively, then the area of second field $= l \times b$.

Now consider option (d) *i.e.*, $x = 80$, then

area of first field $= \frac{1}{5} l \times 5b = lb$

Hence, area of first field is same as that of second field, hence the presumed option is correct.

24. Area of quadrant $= \frac{1}{4} \pi a^2$

Area of triangle $ACB = \frac{a^2}{2}$

Scanned by CamScanner

yoursmahboob.wordpress.com



$\therefore$ Area of segment $= \frac{\pi a^2}{4} - \frac{a^2}{2} = \frac{a^2}{4}[\pi - 2]$

Area of semi-circle $= \frac{1}{2}\pi\left(\frac{a\sqrt{2}}{2}\right)^2 = \frac{\pi a^2}{4}$

$\therefore$ Area of required region $= \frac{\pi a^2}{4} - \frac{a^2}{4}[\pi - 2]$

$= \frac{a^2}{2}$ sq. unit

25. Wrongly calculated area $= 1.05 \times 0.92 = 0.966 = 96.6\%$

$\therefore$ % error $= 100 - 96.6 = 3.4\%$

Alternatively: Actual area $= l \times b$

Wrongly calculated area $= 1.05l \times 0.92b = 0.966lb$

Deficit in area $= lb - 0.966lb = 0.034lb$

% error in area $= \frac{0.034lb}{lb} \times 100 = 3.4\%$

26. Volume of water = Area of cross-section × Length of pool

$= \frac{(10+6)}{2} \times 6 \times 120 = 5760 \text{ m}^3$

27. Area of path $= \frac{22176}{1} = 22176 \text{ m}^2$



$\pi(R^2 - r^2) = 22176$

$(R^2 - r^2) = \frac{22176}{22} \times 7$

$R^2 - (112)^2 = 7056$

$\Rightarrow \quad R^2 = 19600 \Rightarrow R = 140$ m

$\therefore$ Width of the path $= 140 - 112 = 28$ m

28. From the figure itself it is clear that there are total 9 equilateral (congruent) triangles. Out of 9 triangles, 3 triangles are cut out.



Fig. (i)



Fig. (ii)

It means $\frac{1}{3}$ (i.e., 33.33%) area has been removed.

29. $\frac{SP}{AS} = \sin 60° = \frac{\sqrt{3}}{2}$

$\Rightarrow \quad SP = \frac{\sqrt{3}}{2} AS$



Also, $SP = SR = CS = CR$

(since, $SR \parallel AB \therefore \angle CSR = \angle SRC = \angle RCS = 60°$)

$\therefore \quad CS = \frac{\sqrt{3}}{2} AS$

$\therefore \quad \frac{CS}{AS} = \frac{\sqrt{3}}{2} = \frac{CR}{RB}$

30. Let the each side of a square be a then its area will be a^2. Therefore, area of circle will also be a^2.

Again since the perimeter of square and equilateral triangle is same then, the each side of equilateral triangle is $\frac{4a}{3}$

$\therefore$ Area of equilateral triangle $= \frac{\sqrt{3}}{4}\left(\frac{4a}{3}\right)^2$

$= \frac{4\sqrt{3}}{9} a^2$

Required ratio of area $= \frac{a^2 \times 9}{4\sqrt{3} \times a^2} = 9 : 4\sqrt{3}$

31. $ABCD$ is a square O is the point of intersection of diagonals. P, Q, R and S are the mid-points on the sides AB, BC, CD, DA respectively.



Fig. (i)



Fig. (ii)

In the above figure you can see that there are total 16 congruent isosceles right angled triangles.

In figure (iii) you can see that $OMPN$ is a square of maximum possible area which is made up of 2 isosceles right angled triangles OMP and ONP. Thus, there are 4 smaller squares around O and thus the total area of these 4 squares is half of the larger square. Hence, the required area $= 800 \text{ cm}^2$.



Fig. (iii)

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively: $ABCD$ is a square

$AB = 40$ cm

$OA = OB = 20\sqrt{2}$ cm

and $OP = 20$ cm



Square $OMPN$ has maximum area inside the triangle and OP is the diagonal of square $OMPN$.

$$\therefore \quad \text{Area of } OMPN = \frac{(20)^2}{2} = 200 \text{ cm}^2$$

Since, there are total 4 similar squares in each of the 4 triangles AOB, BOC, COD, DOA inside the larger square. So, the total required area of 4 smaller squares

$$= 4 \times 200 = 800 \text{ cm}^2$$

32. Let the each side of equilateral triangle be 'a' then circumradius of the circle $= \frac{a}{\sqrt{3}}$



$\therefore$ Area of circum circle

$$= \pi r^2 = \pi \times \left(\frac{a}{\sqrt{3}}\right)^2 = \frac{\pi}{3}a^2$$

Area of square whose side is equal to that of equilateral triangle $= a^2$.

$$\therefore \quad \text{Required ratio} = \frac{\frac{\pi}{3}a^2}{a^2} = \frac{\pi}{3}$$

NOTE A circumcircle always passes through the vertices of the inscribed figure (say triangle).

33. Best way is to go through option. Given that height of room $= 10$ m.

Volume of room $= 25 \times 400 = 10000 \text{ m}^3$

and Surface area of walls $= 2h(l + b) = 1300 \text{ m}^2$

Now, consider option (c) and verify it.

where $l = 40$ and $b = 25$

34. Let the each side of equilateral triangle be a then its perimeter $= 3a$



Again, $2(l + b) = 3a$

$$\Rightarrow \quad l + b = \frac{3}{2}a$$

$$\Rightarrow \quad a + b = \frac{3a}{2}$$

$AB = l = a$ (for the rectangle)

$$\Rightarrow \quad b = \frac{a}{2}$$

$$\therefore \quad \text{Area of rectangle} = a \times \frac{a}{2} = \frac{a^2}{2}$$

and $$\text{Area of triangle} = \frac{\sqrt{3}}{4} \times a^2$$

$$\therefore \quad \text{Required ratio} = \frac{a^2/2}{\sqrt{3}a^2/4} = \frac{2}{\sqrt{3}}$$

35. Since, b, l and $2(l + b)$ are in GP, therefore

$$\frac{l}{b} = \frac{2(l + b)}{l}$$

Suppose $\frac{l}{b} = x$,

then $$x = 2\left(1 + \frac{1}{x}\right) \Rightarrow x^2 - 2x - 2 = 0$$

$$\Rightarrow \quad x = \sqrt{3} + 1 = \frac{l}{b}$$

36. Non-polished area $= 4\pi(r)^2$

Polished area $= 4 \times \left(2 \times \frac{\pi r^2}{2}\right)$

$= 4\pi r^2$



In the adjoining one of the four parts of the sphere is shown (To understand it properly, take an apple and cut it in the four parts one across horizontal and another cut make vertical to it then you will notice that in a piece there are 2 semicircles.) Therefore, required ratio $= 1 : 1$.

37. Number of cubes $= \frac{85 \times 17 \times 5.1}{1.7 \times 1.7 \times 1.7}$

$= 1500$ (1.7 is the HCF of 85, 17 and 5.1)

Area of each cube $= 6 \times (1.7)^2$

$\therefore$ Area of all the 1500 cubes $= 1500 \times 6 \times (1.7)^2$

$= 26010 \text{ cm}^2$

38. Area of large cube $= 6 \times (5)^2 = 150 \text{ (unit)}^2$

Area of cuboid $= 2(1 \times 1 + 1 \times 125 + 125 \times 1)$

$= 502 \text{ (unit)}^2$

Therefore, increase in surface area $= \frac{(502 - 150)}{150} \times 100$

$= 234\frac{2}{3}\%$

39. $AO = BO = 13$ cm

$\Rightarrow$ $AC = BD = 26$ cm ($\because O$ is the point of bisector)

Now, since the diagonals are equal, it means the given figure is actually a rectangle.



$\therefore$ $BC^2 = AC^2 - AB^2$

$BC^2 = (26)^2 - (24)^2$

$BC^2 = 100$

$\Rightarrow$ $BC = 10$ cm

40. $AB = 16$ cm

$AQ = 10$ cm

and $AO = \frac{AB}{2} = 8$ cm

$\therefore$ $OQ = AQ - AO$

$= 10 - 8 = 2$ cm



Scanned by CamScanner

yoursmahboob.wordpress.com

OQ $(=OP)$ is the radius of smaller enclosed circle between two arcs.

$\therefore$ Area of circle with centre O is $\pi \times (2)^2 = 4\pi$ cm^2.

41. Area of the shaded region



= (Area of square $PQRS$ − 4 × area of each quadrant of circles)

$$= \left[(2)^2 - 4 \times \frac{1}{4}\pi \times (1)^2\right]$$

$$= (4 - \pi) \text{ cm}^2$$

42. Let each side of the square be a, then



$$AE = AB - BE = (a - 17)$$

$\therefore$ Area of triangle $= \frac{1}{2} \times AD \times AE$

$$= \frac{1}{2} a \times (a - 17) = 84$$

$\Rightarrow$ $a^2 - 17a - 168 = 0$

$\Rightarrow$ $a = 24$ cm

$\therefore$ Area of square $= (24)^2 = 576$ cm^2

43. The solid with the least number of sides will have maximum surface area. So, tetrahedron will have maximum surface area. Notice that in a sphere there are infinite number of sides with least possible length. So, the surface area of sphere will be least.

44. $$\frac{l}{b} = \frac{(l + b)}{l}$$

$\Rightarrow$ $l^2 = b(l + b) = lb + b^2$

$\Rightarrow$ $l^2 - b^2 = lb$ ...(A)

$\Rightarrow$ $(l + b)(l - b) = lb$ ...(B)

and $\frac{(l + b)}{l} = \frac{b}{(l - b)}$ ...(C)

Therefore, statements (ii) and (iii) are true from equation (A)

$$\frac{l^2}{b^2} = \frac{bl + b^2}{b^2}$$

$\Rightarrow$ $\frac{l^2}{b^2} = 1 + \frac{l}{b}$

$\Rightarrow$ $\frac{l}{b} = \frac{l^2}{b^2} - 1$

Hence, statement (i) is wrong.

45. Area of triangle $= \frac{\sqrt{3}}{4} \times (2)^2 = \sqrt{3}$ cm^2



Area of 3 circles enclosed by the triangle

$$= 3 \times \pi \times (1)^2 \times \frac{60}{360} = \frac{\pi}{2} \text{ cm}^2$$

$\therefore$ Area of shaded region

$$= \sqrt{3} - \frac{\pi}{2} = \frac{(2\sqrt{3} - \pi)}{2} \text{ cm}^2$$

46. Diameter of cube = 3 cm

$\therefore$ Number of cubes $= \frac{9 \times 9 \times 9}{3 \times 3 \times 3} = 27$ cubes

47.



$l \times b = 20000$

$\Rightarrow$ $\frac{l}{2} \times b = 10000$, Area of Kaurav's land

For the given area, a square gives the minimum perimeter.

$\therefore$ $\frac{l}{2} = b$

$\Rightarrow$ $b \times b = 10000$

$\Rightarrow$ $b = 100$ m

$\therefore$ Perimeter of Kaurav's land $= 4 \times 100 = 400$ m

$\therefore$ Expenses $= 2 \times 400 =$ Rs. 800

48. Ratio of height

$$\frac{h_1}{h_2} = \frac{9}{12} = \frac{3}{4}$$



$\therefore$ Ratio of volumes $= \frac{(3)^3}{(4)^3} = \frac{27}{64}$

Hence, the volume of smaller cone

$= 27x$

and the volume of larger (actual) cone $= 64x$

$\therefore$ the volume of frustum $= 64x - 27x = 37x$

$\therefore$ Required ratio $= \frac{64x}{37x} = 64 : 37$

49. $AB = 45$ km, $AC = 53$ km

(Since distance = speed × time)



$\therefore$ $BC = \sqrt{AC^2 - AB^2}$

$BC = \sqrt{(53)^3 - (45)^2}$

or $BC = 28$ km

$\therefore$ Area of field $= AB \times BC$

$= 45 \times 28 = 1260$ km^2

Scanned by CamScanner

yoursmahboob.wordpress.com

50.



Fig. (I)



Fig. (II)

$\angle AOB = 60°$

$AB = 8\sqrt{3}$ cm

$OC = 30$ cm

$\frac{OM}{MB} = \tan 60° = \sqrt{3}$

$OM = \sqrt{3}MB$

$OM = 12$ cm



Now, $\frac{OM}{MB} = \frac{OC}{CD}$

(Triangles OMB and OCD are similar)

$\therefore$ $CD = 10\sqrt{3}$ cm (which is the radius of cone)

$\therefore$ Volume of cone $= \frac{1}{3}\pi r^2 h$

$= \frac{1}{3}\pi \times (10\sqrt{3})^2 \times 30$

$= 3000\pi$ cm^3

51. Surface area of one cube $= 6a^2$

when 6 cubes are fixed on the 6 faces of a cube then only 5 faces of a cube are visible of each cube. Since, the central cube is completely covered. So, the only 6 cubes are visible each with 5 faces. Hence, the total surface area of this solid $= 5a^2 \times 6$.

$\therefore$ Required ratio $= \frac{5a^2 \times 6}{6a^2} = \frac{5}{1} \Rightarrow 5:1$

52. Ratio of areas = (Ratio of diagonals)^2

$= \left(\frac{3}{2}\right)^2 = \frac{9}{4}$

53. You should know that



$\frac{\text{Area of } \Delta BDF}{\text{Area of hexagon}} = \frac{1}{2}$

Accually there is a perfect symmetricity.

$\therefore$ Area of hexagon $= \frac{3\sqrt{3}}{2} \times (6)^2 = 54\sqrt{3}$ cm^2

$\therefore$ Area of $\Delta BDF = 27\sqrt{3}$ cm^2

Alternatively: Subtract the areas of three triangles DEF, BAF, BCD from the area of hexagon.

Area of $\Delta DEF = \frac{1}{2} \times 6 \times 6 \sin 120° = 9\sqrt{3}$ cm^2

$\therefore$ Area of all the three triangles $= 27\sqrt{3}$ cm

Therefore, required area of $\Delta BDF = 54\sqrt{3} - 27\sqrt{3}$

$= 27\sqrt{3}$ cm^2

Solutions for question number 54 and 55:



Total length of plot $= 17x$

and total breadth of the plot $= 4x$

$\therefore$ *Area of plot* $= 17x \times 4x = 9792$

$\Rightarrow$ $x = 12$

$\therefore$ $l = 17 \times 12 = 204\ m$

and $b = 4 \times 12 = 48\ m$

54. $\frac{4x \times 4x}{x \times x} = \frac{16}{1} \Rightarrow 16:1$

55. $l = 204$ m and $b = 48$ m

LEVEL 2

1.



Also, slant height $(l) = a$ $\therefore$ $r = \frac{a}{2\pi}$

2. $\because$ $l^2 = h^2 + r^2$

$\Rightarrow$ $h^2 = l^2 - r^2 = a^2 - \left(\frac{a}{2\pi}\right)^2$

$h^2 = a^2\left[\frac{4\pi^2 - 1}{4\pi^2}\right]$

$\therefore$ $h = \frac{a}{2\pi}\sqrt{4\pi^2 - 1}$

$\therefore$ Volume $= \frac{1}{3}\pi r^2 h = \frac{1}{3}\pi \times \frac{a^2}{4\pi^2} \times \frac{a}{2\pi}\sqrt{4\pi^2 - 1}$

$= \frac{a^3}{24\pi^2}\sqrt{4\pi^2 - 1}$

3. It will be in the form of a right angled triangle.



Scanned by CamScanner

yoursmahboob.wordpress.com

4. $2\pi r(r+h) = 1540 \text{ cm}^2$

and $(r+h) = 35 \text{ cm}$

$\therefore \quad 2\pi r = \dfrac{1540}{35} = 44 \text{ cm}$

5. Total volume $= \pi r^2 h_1 + \dfrac{1}{3}\pi r^2 h_2$

$= \pi r^2 \left[h_1 + \dfrac{h_2}{3}\right]$

$= \dfrac{22}{7} \times (21)^2 \left[80 + \dfrac{16}{3}\right]$

$= \dfrac{22}{7} \times 441 \times \dfrac{256}{3}$



$\text{Weight} = \dfrac{22}{7} \times 441 \times \dfrac{256}{3} \times \dfrac{8.45}{1000} = 999.39 \text{ kg}$

6. $ABCD$ is a square, each side of square is 'a'.



Fig. (i)

In figure (ii),

$\angle DOC = 120°$

and $\angle ODC = \angle OCD = 30°$



Fig. (ii)



Fig. (iii)

In figure (iii),

$\dfrac{PC}{OC} = \sin 60°$

$\dfrac{a/2}{OC} = \dfrac{\sqrt{3}}{2}$

$\Rightarrow \quad OC = \dfrac{a}{\sqrt{3}} \Rightarrow$ radius of the arc 'CD'.

$\therefore$ Area of triangle $OCD = \dfrac{1}{2} \times CD \times OP$

$= \dfrac{1}{2} \times a \times \dfrac{a}{2\sqrt{3}} = \dfrac{a^2}{4\sqrt{3}}$

$\left(\because \dfrac{OP}{PC} = \tan 30° \text{ and } \tan 30° = \dfrac{1}{\sqrt{3}}\right)$

and area of sector COD (figure ii)

$= \pi r^2 \dfrac{120}{360}$

$= \pi \times \left(\dfrac{a}{\sqrt{3}}\right)^2 \times \dfrac{1}{3} = \dfrac{\pi a^2}{9}$

$\therefore$ Area of segment = (Area of sector – Area of triangle)

$= \dfrac{\pi a^2}{9} - \dfrac{a^2}{4\sqrt{3}}$

Total area of all the four segments $= 4\left(\dfrac{\pi a^2}{9} - \dfrac{a^2}{4\sqrt{3}}\right)$

and the total area of whole figure $= a^2 + 4\left(\dfrac{\pi a^2}{9} - \dfrac{a^2}{4\sqrt{3}}\right)$

7. $2(l+b) = 26 \Rightarrow l + b = 13$

$12 + 1 = 13$

$11 + 2 = 13$

$10 + 3 = 13$

$9 + 4 = 13$

$8 + 5 = 13$

$7 + 6 = 13$

Since, $l > b$, therefore, there are only 6 integral values of the length *viz.*, 7, 8, 9, 10, 11 and 12.

8. Total surface area $= 2\pi R^2 + 2\pi r^2 + (\pi R^2 - \pi r^2)$

$= 3\pi R^2 + \pi r^2$

$= \pi(3R^2 + r^2)$



$\Rightarrow \quad 1436\dfrac{2}{7} = \pi[3 \times (12)^2 + r^2]$

$\Rightarrow \quad \dfrac{10054}{7} \times \dfrac{1}{\pi} = 432 + r^2$

$\Rightarrow \quad r = 5 \text{ cm}$

$\therefore$ Internal volume of hemisphere $= \dfrac{2}{3}\pi(R^3 - r^3)$

$= \dfrac{2}{3}\pi[(12)^3 - (5)^3]$

$= 3358\dfrac{2}{3} \text{ cm}^3$

9. Since, there are 3 faces which are visible in a corner cube. When the cube of a corner is removed then the 3 faces of other cubes will be visible from outside. So, there will not be any change in the surface area of this solid figure.





10. Number of spheres $= \dfrac{\frac{4}{3}\pi\left(\frac{15}{2}\right)^3}{\frac{4}{3}\pi\left(\frac{3}{2}\right)^2} = 125 \text{ spheres}$

Surface area of a large sphere $= 4\pi \times \left(\dfrac{15}{2}\right)^2$

and surface area of a small sphere $= 4\pi\left(\dfrac{3}{2}\right)^2$

Scanned by CamScanner

yoursmahboob.wordpress.com

and total surface area of all the smaller spheres

$$= 125 \times 4\pi \left(\frac{3}{2}\right)^2$$

$$\% \text{ change in area} = \left[\frac{500\pi\left(\frac{3}{2}\right)^2 - 4\pi\left(\frac{15}{2}\right)^2}{4\pi\left(\frac{15}{2}\right)^2} \times 100\right] = 400\%$$

Alternatively: Surface area of larger sphere $= 25x$

Surface area of smaller sphere $= x$

$\because$ the ratio of radii is 5 : 1.

Therefore, ratio in surface areas = 25 : 1

Now, since there are 125 smaller spheres

$\therefore$ Total surface area of smaller spheres $= 125x$

$\therefore$ % change in area $= \frac{125x - 25x}{25x} \times 100 = 400\%$

11. Let the radius of cone be R and radius of sector $= r$,



$\Rightarrow l = r$

then the slant height of cone $(l) = r$

and $2\pi R = 2\pi r \times \frac{60}{360}$

$\Rightarrow R = \frac{r}{6} = \frac{14}{6} = \frac{7}{3}$ cm

$\therefore$ Total surface area $= \pi r (l + r)$

$$= \frac{22}{7} \times \frac{7}{3}\left(14 + \frac{7}{3}\right)$$

$$= 119.78 \text{ cm}^2$$

12. Between 26 poles, total length is $(26 - 1) \times 4 = 100$ m

It means the length of each side of a square field is 100 m.

$\therefore$ Area of field $= (100)^2 = 10{,}000 \text{ m}^2 = 1$ hectare

13. It is clear that length of the lawn is 2 m more than the breadth of lawn.

To solve this problem quickly, go through options. Let us take option (c).

$$l = 10 \text{ m} \Rightarrow b = 8 \text{ m}$$

Area of path $= (l + b + 2w)\, 2w$

$$= (10 + 8 + 4)\, 4 = 88 \text{ m}^2$$

and area of lawn $= 10 \times 8 = 80 \text{ m}^2$

Reduced area of lawn $= 8 \times 8 = 64 \text{ m}^2$

$\therefore$ New area of path $= 88 + (80 - 64) = 104 \text{ m}^2$

$\therefore$ Ratio of areas of path $= \frac{104}{88} = \frac{13}{11}$

Hence, option (c) is correct.

Alternatively: Let the breadth of the lawn be 'b' then the length will be $(b + 2)$

$\therefore$ Area of path $= (l + 4)(b + 4) - lb$

$$= (b + 6)(b + 4) - (b + 2)b$$

$$= 8b + 24$$

and the new area of path $= (l + 4)(b + 4) - b \times b$

$$= (b + 6)(b + 4) - b^2$$

$$= 10b + 24$$

$\because$ $\frac{(10b + 24)}{(8b + 24)} = \frac{13}{11}$

$\Rightarrow$ $b = 8$ m $\therefore l = 10$ m

14. From the figure you can see that just half of the liquid has been flown off and half the liquid is remained in the cylindrical jar.



Thus it is clear that the capacity (or volume) of the cylinder

$$= 2 \times 2.1 = 4.2 \text{L}$$

15. When the height and base of the cone are same as that of cylinder, then the voume of cone is $\frac{1}{3}$ that of the cylinder.

Thus the capacity of cone $= \frac{1}{3} \times 4.2 = 1.4\, l$

Thus the remaining volume $= 2.1 - 1.4 = 0.7\, l$

$\therefore$ the required ratio $= \frac{0.7}{4.2} = \frac{1}{6}$

16. $AC = \sqrt{(30)^2 + (16)^2}$

$AC = 34$ m

but since elephant is itself 4 m long. So he has to travel only



$$(34 - 4) = 30 \text{ m}.$$

$\therefore$ the speed of elephant $= \frac{30}{15} = 2$ m/s

17. Arc of sector $= \frac{2\pi r\, 60}{360} = \frac{2\pi r}{6}$



This arc of sector will be equal to the perimeter of cone. Let the radius of cone be R,

then $2\pi R = \frac{2\pi r}{6} \Rightarrow R = \frac{r}{6}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Further the radius of sector will be equal to the slant height of cone

$\therefore \quad l = r$

Now since $l^2 = h^2 + R^2$

$\Rightarrow \quad h = \sqrt{l^2 - R^2}$

$$h = \sqrt{r^2 - \left(\frac{r}{6}\right)^2}$$

$$h = \frac{\sqrt{35}}{6} r$$

18. The diagonal of cube will be equal to the diameter of sphere.

$\therefore$ Volume of sphere $= \frac{4}{3}\pi\left(\frac{d}{2}\right)^3 = \frac{\pi d^3}{6}$

and each side of cube $= a = \frac{d}{\sqrt{3}}$

$\therefore$ Volume of cube $= a^3 = \frac{d^3}{3\sqrt{3}}$

$\therefore$ Remaining volume $= \frac{\pi d^3}{6} - \frac{d^3}{3\sqrt{3}} = \frac{d^3}{3}\left(\frac{\pi}{2} - \frac{1}{\sqrt{3}}\right)$

19. Let $AP = x$ then $AM = x$ and $MS = x$



$\therefore \quad AS = AM + MS$

$AS = 2x$

$\therefore \quad PS = \sqrt{AS^2 - AP^2}$

$PS = \sqrt{3}x$



$\therefore$ Area of square $PQRS = (\sqrt{3}x)^2 = 3x^2$

Area of circle $= \pi r^2 = \pi \times x^2 = \pi x^2$

Area of both the circles $= 2\pi x^2$

$\therefore$ Required ratio $= \frac{2\pi x^2}{3x^2} = \frac{2\pi}{3}$

20. Let the length of rectangle be 'l' and breadth be 'b', then

$2(l + b) = 12$

$\Rightarrow \quad l + b = 6$ cm



and area of larger equilateral triangle $= \frac{\sqrt{3}}{4} l^2$

Similarly area of smaller equilateral triangle $= \frac{\sqrt{3}}{4} b^2$

$\therefore$ Total area of all the 4 triangles $= 2 \times \frac{\sqrt{3}}{4}(l^2 + b^2) = 10\sqrt{3}$

$\Rightarrow \quad l^2 + b^2 = 20$

$\therefore \quad (l + b)^2 = l^2 + b^2 + 2lb$

$\Rightarrow \quad 36 = 20 + 2lb$

$\Rightarrow \quad lb = 8$

$\therefore \quad (l - b)^2 = l^2 + b^2 - 2lb = 20 - 16$

$(l - b)^2 = 4$

$\Rightarrow \quad l - b = 2$

$\because \quad l + b = 6$ and $l - b = 2$

$\therefore \quad l = 4$ and $b = 2$

$\therefore$ area of rectangle $= 4 \times 2 = 8$ cm^2

$\therefore$ Total area of the figure $= 8 + 10\sqrt{3}$

$= 2(4 + 5\sqrt{3})$ cm^2

21. Area of each square $= 16$ cm^2

Area of quadrant $ADMB = \frac{1}{4}\pi \times (4)^2 = 4\pi$

and radius of smaller quadrant

$CPMQ = CM = AC - MA$

$= 4\sqrt{2} - 4 = 4(\sqrt{2} - 1)$

$\therefore$ Area of smaller quadrant $= \frac{1}{4}\pi[4(\sqrt{2} - 1)]^2$

$= 4\pi(3 - 2\sqrt{2})$

Area of shaded region inside the square $ABCD$

$= 16 - [4\pi + 4\pi(3 - 2\sqrt{2})]$

$= 16 - [4\pi(1 + 3 - 2\sqrt{2})]$

$= 16 - [4\pi(4 - 2\sqrt{2})]$

$= 8[2 - 2\pi + \sqrt{2}\pi]$

Now, area of quadrants $= AEG + EFG = 2AEG$

$= 2 \times \frac{1}{4}\pi(4)^2 = 8\pi$

$\therefore$ Area of shaded region inside the square $EAGF$

$= 8\pi - 16 = 8(\pi - 2)$

$\therefore$ Required ratio $= \frac{8(2 - 2\pi + \sqrt{2}\pi)}{8(\pi - 2)}$

$= \frac{[2 + \pi(\sqrt{2} - 2)]}{(\pi - 2)}$

22. Given that $\frac{AB}{BC} = \frac{AD}{DF}$

Also $BE = BC$

Let $AD = 1$ and $AE = x$

$\therefore \quad \frac{AE}{EF} = \frac{AE}{AD} = \frac{AE}{BC} = x$

$\therefore \quad \frac{AE}{EF} = \frac{AD}{AB}$ $\left(\because \quad AD = BC = BE \text{ and } AB = AE - BE\right)$

$\frac{x}{1} = \frac{1}{x - 1}$

$\Rightarrow \quad x^2 - x - 1 = 0$

$\Rightarrow \quad x = \frac{(1 \pm \sqrt{5})}{2}$

$\therefore \quad x = \frac{(1 + \sqrt{5})}{2}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Since ratio of two sides can never be negative.

Alternatively: Since ratio of two side can never be negative therefore only option (c) is correct.

Solutions for question number 23 to 25:

$AB = 4$

$\therefore \quad AO = AC = \frac{4\sqrt{2}}{2} = 2\sqrt{2}$



$\therefore$ *Area of circle*

$ABCD = \pi \times (2 \times \sqrt{2})^2 = 8\pi$

Area of region 2 (only left part)

$$= \frac{\text{Area of circle} - \text{Area of square}}{4}$$

$$= \frac{8\pi - 16}{4} = (2\pi - 4)$$

Area of region 3 = Area of square

– 2 (Area of semicircle)

$$= 16 - 2\left(\frac{1}{2} \times \pi \times 4\right)$$

$= 16 - 4\pi = 4\,(4 - \pi)\ cm^2$



Area of region 1

= Area of semicircle AD

– Area of region 2

$= \frac{1}{2}\pi \times (2)^2 - (2\pi - 4) = 4\ cm^2$



23. Total area of region 1 = $2 \times 4 = 8\ cm^2$

24. Total area of region 2 = $2 \times (2\pi - 4) = 4\,(\pi - 2)\ cm^2$

25. Total area of region 3 = $4\,(4 - \pi)\ cm^2$

26. Total area of square = $64\ cm^2$

$\therefore \quad 4\,(x + y) = 64$

$\Rightarrow \quad x + y = 16 \quad \ldots(i)$



Again in a semicircle

$AOB = x + y + x = \frac{1}{2}\pi \times (4)^2$

$2x + y = 8\pi \quad \ldots(ii)$

From Eq. (i) and (ii), we get

$x = 8\pi - 16$

Total area of shaded region = $4\,(8\pi - 16)$

$= 32\,(\pi - 2)\ cm^2$

Alternatively: Area of square – 2 (Area of semicircles) = $2y$

$(64 - 16\pi) = 2y$

$\therefore \quad 4y = (128 - 32\pi)$

$\therefore$ Required area of shaded region $(4x)$ = (Area of square – $4y$)

$= 64 - (128 - 32\pi)$

$= 32\pi - 64$

$= 32\,(\pi - 2)\ cm^2$

27. You can see in the figure that the sides of one square is parallel to the diagonals of the other square.



Let $DP = a$, then

$DC = DP + PQ + QC$

$= a + a\sqrt{2} + a$

$DC = a\,(2 + \sqrt{2})$

$\therefore$ Area of $\Delta PGQ = \frac{1}{2} \times a \times a = \frac{a^2}{2}$

$\left.\begin{array}{l} \because \quad DP = QC \\ \text{and } DP = PG = GQ = QC \\ \angle G = 90^\circ \\ \therefore \quad PQ = \sqrt{2}a \end{array}\right\}$

$\therefore$ Area of all the triangles outside the square $ABCD$

$$= 4 \times \frac{a^2}{2} = 2a^2$$

But $\quad DC = a\,(2 + \sqrt{2}) = 4\ cm$

$\Rightarrow \quad a = \frac{4}{(2 + \sqrt{2})}$

$\therefore \quad 2\,(a)^2 = 2 \times \left(\frac{4}{2 + \sqrt{2}}\right)^2$

$$= \frac{16}{(3 + 2\sqrt{2})} \times \frac{(3 - 2\sqrt{2})}{(3 - 2\sqrt{2})}$$

$= 16\,(3 - 2\sqrt{2})$

and Area of square = $16\ cm$

$\therefore$ Total area of the figure = $16 + 16\,(3 - 2\sqrt{2})$

$= 16\,(4 - 2\sqrt{2})$

$= 32\,(2 - \sqrt{2})\ cm^2$

28. When $l = CD$, then the volume of cone will be maximum, where l is the slant height of the cone and the largest possible angle at the vertex of cone is 90°.





$$CD = \frac{12 \times 16}{20} = 9.6\ cm,$$

which is the radius of the sector.

Therefore, arc of the sector = $2\pi \times 9.6 \times \frac{90}{360} = 4.8\pi$

Let the radius of the cone be r, then

$2\pi r$ = arc of the sector

$2\pi r = 4.8\pi$

$r = 2.4$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore$ Height of the cone $(h) = \sqrt{l^2 - r^2}$

$= \sqrt{(9.6)^2 - (2.4)^2} = 2.4\sqrt{15}$ cm

$\therefore$ Volume of the cone $= \frac{1}{3}\pi r^2 h$

$= \frac{1}{3} \times \frac{22}{7} \times (2.4)^2 \times 2.4\sqrt{15}$

$= 56.1 \text{ cm}^3$

29. To increase the value (or price of diamond) they should cut (divide) the diamond in such a way that the surface area will be maximum.



Thus, when four parts are parallel to each other.

In this way total surface area

$= 6a^2 + 2a^2 + 2a^2 + 2a^2 = 12a^2$

Actual surface area of cubical diamond $= 6a^2$

Therefore, percentage increase in area

$= \frac{12a^2 - 6a^2}{6a^2} \times 100 = 100\%$

Remember that for the given volume, minimum surface area is possessed by a cube. So to maximize the area we have to increase the maximum possible difference between the edges of cuboid.

30. Side of square I $= a$

Side of square II $= \frac{a}{\sqrt{2}}$

Side of square III $= \frac{a}{2}$

Side of square IV $= \frac{a}{2\sqrt{2}}$

Side of square V $= \frac{a}{4}$

Therefore, sum of perimeters of all the squares

$= 4\left(a + \frac{a}{\sqrt{2}} + \frac{a}{2} + \frac{a}{2\sqrt{2}} + \frac{a}{4}\right)$

$= 4a\left(1 + \frac{1}{\sqrt{2}} + \frac{1}{2} + \frac{1}{2\sqrt{2}} + \frac{1}{4}\right)$

$= 4a\left(\frac{4 + 2\sqrt{2} + 2 + \sqrt{2} + 1}{4}\right)$

$= a(7 + 3\sqrt{2})$

31. Total area of the five squares

$= a^2 + \left(\frac{a}{\sqrt{2}}\right)^2 + \left(\frac{a}{2}\right)^2 + \left(\frac{a}{2\sqrt{2}}\right)^2 + \left(\frac{a}{4}\right)^2$

$= a^2\left[1 + \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \frac{1}{16}\right]$

$= a^2\left[\frac{16 + 8 + 4 + 2 + 1}{16}\right]$

$= a^2 \times \frac{31}{16} = \frac{31a^2}{16}$

32. $(n-2)^3$

33. $6(n-2)^2$

34. $12(n-2)$

35. These are the 8 cubes at the corners, which is always fix.

36. Volume of the whole body



$V_1 = \frac{1}{3}\pi r_1^2 h_1 + \pi r_1^2 h_2$

but $\frac{h_1}{h_2} = \frac{2}{3}$

$\therefore \quad V_1 = \pi r_1^2 \frac{11h_1}{6}$

and $h_3 = \frac{2}{3}(h_1 + h_2) = \frac{5h_1}{3}$

Hence, volume of the hole $(V_2) = \pi r_2^2 h_3$

$= \frac{5}{3}\pi r_2^2 h_1$

But it is given that $V_2 = \frac{V_1 - V_2}{3}$

$\therefore \quad V_1 = 4V_2$

$\Rightarrow \quad 4 \times \frac{5}{3}\pi r_2^2 h_1 = \pi r_1^2 \times \frac{11}{6} h_1$

$\Rightarrow \quad r_2 = \sqrt{\frac{55}{8}}$ cm

37. $19 \times 19 = 361$

Thus, we make equal 19 measurements each of 19°, then we get $(361 - 360) = 1°$ angle at the centre. Thus, moving continuously in the similar fashion, we can get all the 360° angle i. e., 360 equal sectors of 1°.

38. When we open the paper after cutting it, we will find it as shown in the following figure.



Radius of the larger circle = 5 cm

$\therefore$ Area of larger circle $= 25\pi$

and the radius of each smaller circle is 1 cm.

Therefore, total area of all the 9 circles $= 9 \times \pi \times (1)^2 = 9\pi$

$\therefore$ Remaining area $= (25 - 9)\pi = 16\pi$

Hence, the required ratio = 25 : 16

39. In the above layer we can see that total 13 cubes get a cut. So, in 7 layers total $13 \times 7 = 91$ cubes will get a cut and the remaining $(7^3 - 91) = 252$ cubes are without any cut.



Total number of pieces which are not a cube

$= 12 \times 2 \times 7 + 4 \times 7 = 196$

Scanned by CamScanner

yoursmahboob.wordpress.com

(Since 84 cubes are diagonally cut into two parts and 7 cubes which are in the centre are divided into 4 parts.)
Thus, total 196 children will get one-one piece and 252 adults get one-one piece.
Thus total 252 + 196 = 448 people can get a piece of cake.

NOTE It is clear that everyone get equal number of pieces but not according to the volume of pieces.

Solutions for questions number 40 to 42: Diameter (2R) of the outermost circle is equal to the diagonal of larger square.

Hence, the side of square $= \frac{2R}{\sqrt{2}} = \sqrt{2}R$

Again the side of larger square is equal to the diameter of middle most circle.

Hence, the radius of mid-circle is $\frac{R}{\sqrt{2}}$.

Once again the diameter of the mid-circle is equal to the diagonal of smaller square. Hence, side of the smaller square = R.
Similarly the diameter of innermost circle is equal to the side of the smaller square. Hence, radius of the innermost circle $= \frac{R}{2}$.

40. $\frac{R}{2}$

41. Area of larger square $= (\sqrt{2}R)^2 = 2R^2$
and area of smaller square $= R^2$
$\therefore$ Total area of both squares $= 3R^2$

42. Sum of all the circumferences $= 2\pi\left(R + \frac{R}{\sqrt{2}} + \frac{R}{2}\right)$

$= 2\pi R\left(\frac{2+\sqrt{2}+1}{2}\right)$

$= (3+\sqrt{2})\pi R$

Sum of perimeters of all the squares $= 4(\sqrt{2}R + R)$

$= 4R(\sqrt{2}+1)$

$\therefore$ Required ratio $= \frac{(3+\sqrt{2})\pi R}{(\sqrt{2}+1)4R} = \frac{(3+\sqrt{2})\pi}{(\sqrt{2}+1)4}$

Alternatively: Since circumference and perimeter both has R. So R will be cancelled in the ratio of circumference to the perimeter. Thus, neither of the choices *a*, *b* and *c* are admissible. Hence, the only correct choice is (d).

Solutions for questions number 43 and 44: Each side of outer (larger) hexagon is equal to the radius of circle which is R.



Now, OC = ON = OD
radii of the inner (smaller) circle

But $\frac{ON}{OA} = \sin 60° = \frac{\sqrt{3}}{2}$

$\Rightarrow$ $ON = \frac{\sqrt{3}}{2}OA = \frac{\sqrt{3}}{2}R$, *radius of the inner circle*

and this is also equal to the side of the inner hexagon.

43. Sum of perimeters of both the hexagons $= 6R + 6 \times \frac{\sqrt{3}}{2}R$

$= 6R\left(1 + \frac{\sqrt{3}}{2}\right) = 3(2+\sqrt{3})R$

44. $\frac{\text{Area of inner circle}}{\text{Area of outer circle}} = \frac{\pi}{\pi}\frac{\left[\left(\frac{\sqrt{3}}{2}\right)R\right]^2}{(R)^2} = \frac{3}{4}$

45. Radius of the first hexagon $= R$

Radius of the second hexagon $= \frac{\sqrt{3}}{2}R$

Radius of the third hexagon $= \frac{3}{4}R$

Radius of the fourth hexagon $= \frac{3\sqrt{3}}{8}R$

$\therefore$ Required ratio $= \frac{R}{\frac{3\sqrt{3}}{8}R} = \frac{8}{3\sqrt{3}}$

46. From the concept of similarity of triangles. All the five quadrilaterals *viz.*, *AOA'*, *BOB'*, *COC'*, *DOD'* and *EOE'* are similar.
From the figure (ii)



Fig. (i)

$\frac{r_2 - r_1}{r_2 + r_1} = \frac{r_3 - r_2}{r_3 + r_2}$

$= \frac{r_4 - r_3}{r_4 + r_3} = \frac{r_5 - r_4}{r_5 + r_4} = K$

$\Rightarrow$ $\frac{r_2}{r_1} = \frac{r_3}{r_2} = \frac{r_4}{r_3} = \frac{r_5}{r_4} = K$

(By componendo and dividendo)



Fig. (ii)

It means all the radii are in GP

Therefore, $\frac{r_5}{r_1} = (K)^4 = \frac{81}{16} = \left(\frac{3}{2}\right)^4$

$\Rightarrow$ $K = \frac{3}{2}$ $\therefore$ $r_3 = r_1(K)^2$

46. $r_3 = r_1 \times \frac{9}{4} = \frac{9r_1}{4} = \frac{9}{4} \times 16 = 36$ cm

47. $\because$ $r_1 = 16$, $r_2 = 24$, $r_3 = 36$, ... etc.
$\therefore$ $\frac{OP}{AP} = \frac{OQ}{BQ}$

$\frac{h + r_1}{r_1} = \frac{h + 2r_1 + r_2}{r_2}$

$\frac{h+16}{16} = \frac{h+56}{24}$ $\Rightarrow$ $h = 64$ cm

Scanned by CamScanner

yoursmahboob.wordpress.com

48.
$$60 = 1 \times 1 \times 60$$
$$= 1 \times 2 \times 30$$
$$= 1 \times 3 \times 20$$
$$= 1 \times 4 \times 15$$
$$= 1 \times 5 \times 12$$
$$= 1 \times 6 \times 10$$
$$= 2 \times 2 \times 15$$
$$= 2 \times 3 \times 10$$
$$\ldots \ldots \ldots$$
$$\ldots \ldots \ldots$$
$$= 3 \times 4 \times 5$$

Out of the given different combinations the first combination $(1 \times 1 \times 60)$ gives maximum length of diagonal of cuboid, but in this case two of the edges are same. So, the second combination gives the proper value *i.e.*, which gives the maximum length of diagonal whose all sides are different. Hence, the length of such a pencil is equal to the diagonal of cuboid

$$= \sqrt{1^2 + 2^2 + 30^2} = \sqrt{905}$$

49.



Fig. (i)



Fig. (ii)

In figure (ii)

$$OP = \frac{\sqrt{3}}{2} OA = 4\sqrt{3} \text{ cm}$$

Again
$$\frac{OP}{OQ} = \frac{OA}{OC}$$

$$\frac{4\sqrt{3}}{6\sqrt{3}} = \frac{8}{OC} \qquad (OQ = OP + PQ = 4\sqrt{3} + 2\sqrt{3})$$

$$\Rightarrow \quad OC = 12 \text{ cm}$$

$\therefore$ Each side of the outer hexagon is 12 cm.

$\therefore$ Required area = (Area of outer hexagon – Area of inner hexagon)

$$= \frac{3\sqrt{3}}{2}[12^2 - 8^2] = 120\sqrt{3} \text{ cm}^2$$

50. Area of region x = Area of square – Area of inscribed circle

$$= (4 - \pi)$$



Fig. (i)



Fig. (ii)



Fig. (iii)

Area of region y = Area of square – 4 (area of quadrant)

$$= 4 - 4\left(\frac{1}{4}\pi \times (1)^2\right) = (4 - \pi)$$

$\therefore$ Required area (of shaded region)

= Area of square – [Area of region x + Area of region y]

$$= 4 - [4 - \pi + 4 - \pi] = 2\pi - 4$$

51. Let the volume of solid block be V and radius of the spheres formed from the first block be r_1, then the volume of each sphere be V_1.

Similarly, let the radius of each sphere obtained from second block be r_2 $(= 2r_1)$, then the volume of each sphere be

$$V_2 = (8V_1)$$

$\therefore$ $V = kV_1 + 14$ ...(i)

and $V = lV_2 + 36$

or $V = 8lV_1 + 36$ ...(ii)

From equation (i) and (ii)

$$kV_1 + 14 = 8lV_1 + 36$$

$$\Rightarrow \quad V_1(k - 8l) = 22$$

The possible value of $V_1 = 22, 11, 2$ or 1

But V_1 can never be equal to or less than 14 (since remainder is always less than divisior) So, the only possible value of $V_1 = 22$

$\therefore$ $V_2 = 8 \times V_1 = 176 \text{ cm}^3$

52. The length of tether of the horse is 80 m.



Area grazed by horse

$$= \left[\pi \times (80)^2 \times \frac{270}{360} + \pi \times (30)^2 \times \frac{90}{360} + \pi \times (40)^2 \times \frac{90}{360}\right]$$

$$= \pi\left(6400 \times \frac{3}{4} + 900 \times \frac{1}{4} + 1600 \times \frac{1}{4}\right) = \pi\left[\frac{21700}{4}\right]$$

$$= 5425\pi \text{ m}^2$$

HINT When horse is tethered at B, then he can move freely 270° *i.e.*, from P to S with the full length of his tether as the radius of the arc PS. Again when horse reaches P and tries to move further in the right direction *i.e.*, towards D, his tether gets fixed at A and now only 30 m tether is free which works as a radius of the quadrant PAQ. Similarly when horse reaches S and tries to move left further in the direction of D, due to wall BC his tether gets fixed at C and now only 40 m tether is free to move further. At this moment point C behaves like a fixed point of tether (as centre of quadrant RSC).

Scanned by CamScanner

yoursmahboob.wordpress.com

NOTE You can tether horse at any of the four corners A, B, C and D area grazed by horse remains same.

53. Here each side is broken up into 6 parts *i. e.*, $n = 6$

Now, $N_0 = (n-2)^3 = (4)^3 = 64$

$N_1 = 6(n-2)^2 = 6 \times (4)^2 = 96$

$N_2 = 12(n-2) = 12(4) = 48$

$\therefore \quad N_0 : N_1 : N_2 = 64 : 96 : 98$

$= 4 : 6 : 3$

54. Let the radius of seed be r and radius of the whole fruit (pulp + seed) be R, then thickness of the pulp $= (R - r)$



Volume of mango fruit $= \frac{4}{3}\pi R^3$

and Volume of pulp $= \frac{4}{3}\pi (R^3 - r^3)$

but $= \frac{4}{3}\pi \left[R^3 - \left(\frac{2}{7}R\right)^3\right]$

$\left[\because \frac{r}{R-r} = \frac{2}{5} \Rightarrow r = \frac{2}{7}R\right]$

$\therefore$ Percentage of volume of pulp to the total volume of fruit

$$= \frac{\frac{4}{3}\pi R^3\left[1 - \frac{8}{343}\right]}{\frac{4}{3}\pi R^3}$$

$$= \frac{335}{343} \times 100 = 97.66\%$$

55. Let the radius of each smaller circle is r and radius of the larger circle is R, then



$\pi R^2 = 4\pi r^2 \Rightarrow R = 2r$

$OR = OP = R + r = 3r$

Also $PM = r$

(PM is the perpendicular on AB)

$\therefore \quad AP = \sqrt{2}r$

$\therefore \quad AO = AP + PO$

$= r\sqrt{2} + 3r = r(3 + \sqrt{2})$

$\therefore AC = 2AO = 2r(3 + \sqrt{2})$, which is the diagonal of square

$\therefore$ Required ratio $= \frac{2r(3+\sqrt{2})}{\sqrt{2}r} = (2 + 3\sqrt{2})$

56. Initial radius $= 14$ cm

Radius at a time when the balloon explodes $= 35$ cm

Change in volume $= \frac{4}{3}\pi[(35)^3 - (14)^3]$

$= \frac{4}{3}\pi(7)^3[125 - 8]$

$= \frac{4}{3}\pi \times 343 \times 117$

Required time to explode $= \frac{\frac{4}{3}\pi \times 343 \times 117}{156}$

$= 1078$ s

57. Let the each side of cube be a, then



$CD = \sqrt{2}a$

$\therefore \quad CQ = \frac{a}{\sqrt{2}}$

Let the radius of cone be r and height be h, then

$r = h\sqrt{2}$

$\therefore$ In ΔAPO and ΔCQO (Similar triangles)

$$\frac{AP}{PO} = \frac{CQ}{OQ} = \frac{r}{h} = \frac{\frac{a}{\sqrt{2}}}{(h-a)}$$

$\Rightarrow \quad \frac{\frac{a}{\sqrt{2}}}{(h-a)} = \sqrt{2}$

$\Rightarrow \quad a = 2(h - a)$

$\Rightarrow \quad h = \frac{3a}{2}$

$\therefore \quad r = \frac{3a}{2} \times \sqrt{2}$

and $h = \frac{3a}{2}$

$\therefore$ Volume of cone $= \frac{1}{3}\pi \times \left(\frac{3a\sqrt{2}}{2}\right)^2 \times \frac{3a}{2}$

$= \frac{9}{4}a^3\pi$

and Volume of cube $= a^3$

$\therefore$ Required ratio $= \frac{\frac{9}{4}\pi a^3}{a^3} = \frac{9}{4}\pi = 2.25\pi$

58. For the given volume, cube has minimum possible length of diagonal.

Therefore each side of cube $= 4$ cm

and its diagonal $= 4\sqrt{3}$ cm.

59. $l = 2\pi r \Rightarrow r = \frac{l}{2\pi}$



where r is the base radius of cylinder and l is the length of paper and $h = b$, where h is the height of cylinder and b is the breadth of the paper.

$\therefore$ Volume of cylinder $= \pi r^2 h = \pi \times \left(\frac{l}{2\pi}\right)^2 \times b$

$\Rightarrow \quad \frac{\pi \times l^2 b}{4\pi^2} = 48.125 = \frac{385}{8}$

$\Rightarrow \quad l^2 b = 11 \times 11 \times 5$

$\Rightarrow \quad l = 11$ and $b = 5$ $(\because l > b)$

Scanned by CamScanner

yoursmanboob.wordpress.com

$\therefore$ Volume of the box $= l \times b \times 4$

$= 10 \times 4 \times 0.5 = 20 \text{ cm}^3$



60. Vertical spacing between any two turns $= \dfrac{\text{Height of cone}}{\text{Number of turns}}$

$= \dfrac{h}{n}$

61. Number of turns $= \dfrac{h}{x}$

Length of string in each turn

$= 2\pi r = 2\pi \times \dfrac{4}{\pi} = 8 \text{ cm}$

$\therefore$ Total length of string in all the n turns

$= \dfrac{h}{x} \times 8 = \dfrac{8h}{x} \text{ cm}$



62. Total length of string $= 8n$ cm

Since, total length of string

= number of turns × perimeter of cylinder

$= 8 \times n = 8n$ cm



Length of string required for 1 turn (or round) $= \dfrac{8n}{4} = 2n$

but $2n = \sqrt{\left(\dfrac{a}{4}\right)^2 + (4a)^2}$



$\Rightarrow \quad a = \dfrac{8n}{\sqrt{257}}$

where a is the side of cube.

63. From the sheet of 10 ft long, maximum $\dfrac{10}{2} = 5$ circular discs can be cut along the length of the iron sheet.

$CM = \sqrt{AC^2 - AM^2} = \sqrt{4x^2 - x^2}$

$CM = x\sqrt{3} = \sqrt{3}$ ft (Since $x = 1$ ft)

$\therefore$ Width of the sheet $= AK + MC + CT$



Fig (i) Fig (ii)



Fig. (iii)



Fig. (iv)

$= 1 + \sqrt{3} + 1$

$= (2 + \sqrt{3})$ ft

64. Recall that for given perimeter the polygon of minimum number of sides has minimum area and the polygon of maximum number of sides has maximum area. So, the correct relation is $h > s > r$.

Thus, hexagon (6 sides) has maximum area.

Now, between square and rhombus, square has greater area than rhombus. For easier understanding consider some values.



Area $= 25 \text{ cm}^2$



Area = base × height

$= 5 \times 4 = 20 \text{ cm}^2$

Alternatively:



Square



Rhombus

In rhombus *ABCD*: Area of rhombus $= a \times h$

$= a \times a \sin\theta \qquad \left(\dfrac{h}{a} = \sin\theta\right)$

$= a^2 \sin\theta$

As you know the maximum value of $\sin\theta$ is 1 at $\theta = 90°$ but at $\theta = 90°$ rhombus will become a square. So except $\theta = 90°$ for all the rest values the area of rhombus will be less than the area of square.

65.



Fig. (i)



Fig. (ii)

Scanned by CamScanner

yoursmartbook.wordpress.com

PCQ is also an equilateral triangle

$\therefore \quad PC = PQ = PM = a$

$\therefore \quad \frac{a}{PA} = \frac{\sqrt{3}}{2}$

$\therefore \quad PA = \frac{2a}{\sqrt{3}}$

$\therefore \quad AC = AP + PC = \frac{2a}{\sqrt{3}} + a = 1 \text{ cm}$

$\Rightarrow \quad a = \frac{\sqrt{3}}{(2+\sqrt{3})} = \sqrt{3}(2-\sqrt{3})$

Now, in figure (iii)

$PM = MT = a$

Let the each side of square $RSYX$ be K, then $RT = K$ also (since RTS is an equilateral triangle)



Fig. (iii)

$\therefore \quad \frac{K}{RM} = \frac{\sqrt{3}}{2}$

$\therefore \quad RM = \frac{2K}{\sqrt{3}}$

$\therefore \quad MT = RT + RM = K + \frac{2K}{\sqrt{3}}$

$MT = \frac{(\sqrt{3}+2)}{\sqrt{3}} K$

but $MT = a$

$\therefore \quad a = \left(\frac{\sqrt{3}+2}{\sqrt{3}}\right) K$

$\therefore \quad K = \frac{\sqrt{3}a}{(\sqrt{3}+2)}$

But $a = \sqrt{3}(2-\sqrt{3})$

$\therefore \quad K = \frac{\sqrt{3}}{(\sqrt{3}+2)}[\sqrt{3}(2-\sqrt{3})]$

$K = \frac{3(2-\sqrt{3})}{(2+\sqrt{3})} \times \frac{(2-\sqrt{3})}{(2-\sqrt{3})}$

$\Rightarrow \quad K = \frac{3(2-\sqrt{3})^2}{1} = 3(7-4\sqrt{3})$

$\therefore$ Area of square $RSYX = K^2 = [3(7-4\sqrt{3})]^2$

$K^2 = 9(49 + 48 - 56\sqrt{3})$

$K^2 = (873 - 504\sqrt{3}) \text{ cm}^2$

66. For the minimum wastage of sheet he has to cut the sheet in the given manner.



Total area of sheet required

$(2\pi r + 4r) \times 2r = 4r^2(\pi + 2)$

Area of sheet utilised $= (2\pi r \times 2r) + 2(\pi r^2) = 6\pi r^2$

Area of wastage sheet $= 4r^2(\pi + 2) - 6\pi r^2$.

$= 8r^2 - 2\pi r^2$

$\therefore \quad$ Required ratio $= \frac{8r^2 - 2\pi r^2}{6\pi r^2}$

$= \frac{2r^2(4-\pi)}{6r^2\pi} = \frac{1}{11}$

67. Short cut: Very quickly check the options. If all the options have values.

Alternatively: The required capacity of box is 864 m^3. Let the length of the base be l and height of the box is 'h', then

$864 = l^2 h \Rightarrow h = \frac{864}{l^2}$

Now, surface area of the box $A = l^2 + 4lh$

$= l^2 + \frac{4l \times 864}{l^2}$

$= l^2 + \frac{3456}{l}$

Differentiating w.r. to l, we get

$\frac{dA}{dl} = 2l - \frac{3456}{l^2}$

For the minimum area $= \frac{dA}{dl} = 0$

$\therefore \quad 2l = \frac{3456}{l^2}$

$\Rightarrow \quad l^3 = 1728$

$\Rightarrow \quad l = 12$

$\therefore \quad$ Base area $= (12)^2 = 144$

and Height $= \frac{864}{l^2} = 6 \text{ m}$

68. Let the initial radius be r and volume be V, then

$V = \pi r^2 \times 4$

Ist case: $V_1 = \pi(r+12)^2 \times 4$

IInd case: $V_2 = \pi r^2 \times (4+12)$

But $V_1 = V + K$

and $V_2 = V + K$

$\therefore \quad V_1 = V_2$

$\Rightarrow \quad \pi(r+12)^2 \times 4 = \pi r^2 (16)$

$\Rightarrow \quad r = 12 \text{ ft}$

$\therefore$ Increased volume $= V_1 = V_2$

$= \pi \times (24)^2 \times 4$

$= 2304\pi \text{ cubic ft}$

Scanned by CamScanner

yoursmahboob.wordpress.com

11 TRIGONOMETRY

This chapter is basically written for those students who were either not so good in the secondary classes maths or who are not in touch with the following concepts from 4-5 years. Hardly a question is asked in CAT, directly from this chapter, but almost every year there are one or two questions in which we can find the application of the concepts of trigonometry *e.g.*, sometimes in geometry or in height and distance problems. So just refresh the concepts of trigonometry. Therefore CAT aspirants are not required to waste so much of precious time on this chapter. But this chapter is useful for IIFT, NIFT, FMS etc.

Angle : An angle is thought of as traced out by the rotation of a line (called the revolving line) from the initial position OX to a terminal position OP.



Then O is the vertex, OX is called the initial side and OP is called the terminal side of the angle.

Convention of Sign of Angles : It is customary to regard the angle traced out by a **counter-clockwise** rotation as positive and one traced out by a **clockwise** rotation as negative. The angle is indicated by using an arrow, starting from the initial line and ending at the terminal line.



(θ is positive)



(θ is negative)

Quadrants : Let XOX' and YOY' be two mutually perpendicular lines in any plane. These lines divide the plane into four regions called quadrants, numbered counter-clockwise. Thus the quadrants XOY, YOX', $X'OY'$ and $Y'OX$ are respectively called the first quadrant, the second quadrant, the third quadrant and the fourth quadrant.





NOTE θ will be more than 360°, if after making one complete revolution, the revolving line does not stop at the initial position OX but proceeds on further on.

Measures of Angles : There are three different systems of units for measurement in trigonometry, *viz.* (i) Sexagesimal system (ii) Centesimal system (iii) Circular system.

Sexagesimal System : In this system, 1 right angle is divided into 60 equal parts and each part (or division) is called a degree (*i.e.*, 1°, read as 1 degree).

$1° = 60'$ (60 sexagesimal minutes)

$1' = 60''$ (60 sexagesimal seconds)

This system is called the Common or the English system.

Centesimal System : In this system, 1 right angle is divided into 100 equal parts and each part (or division) is called a grade (or 1^g).

$90° = 100^g$

$1^g = 100'$ ($K' \to K$ centesimal minute)

$1' = 100''$ ($K'' \to K$ centesimal second)

Circular Measure : The unit of measurement of angles in this system is a radian (or 1^c)



A **radian** is defined as the angle subtended at the centre of a circle by an arc whose length is equal to the radius of the circle and it is denoted by 1^c.

In the figure $OA = OB = r$, (radius of the circle) and $\angle AOB = 1$ radian or 1^c.

Scanned by CamScanner

yoursmahboob.wordpress.com

IMPORTANT

1. In all circles, the ratio of the circumference to its diameter is constant.
   (Circumference = $\pi \times$ diameter)
   π is an incommensurable number, *i.e.*, it cannot be expressed exactly either by a whole number or by a fraction. Its approximate value is 22/7 or 3.1416, correct to four places of decimal only.
2. A radian is a constant angle.
   1 radian (1^c) = a constant angle
3. π radian = $180°$ (or $1° = \frac{\pi}{180}$ radian)
4. If an arc of length 's' subtends an angle θ radian at the centre of a circle of radius r, then $s = r\theta$. $\left(\theta = \frac{\text{arc}}{\text{radius}}\right)$
5. (i) Area of the sector $AOB = \frac{1}{2}r^2\theta$
   (ii) Area of the sector $AOB = \frac{1}{2}rs$
   ($s \to$ length of arc AB)

EXAMPLE 1 *Express the following angles in radian measure and centesimal measure :*
(i) 45° (ii) 20° 35′ (iii) 50° 38′ 40″

SOLUTION (i) $\because$ $180° = \pi$ rad

$\therefore$ $1° = \frac{\pi}{180}$ rad

$\therefore$ $45° = 45 \times \frac{\pi}{180} = \frac{\pi}{4}$ rad

Now, $90° = 100$ grade

$\Rightarrow$ $45° = 50$ grade

(ii) $20° 35′ = 20\frac{35}{60}$ degree $= \frac{247}{12}$ degree

Now, 180 degree = π rad

$\therefore$ $\frac{247}{12}$ degree $= \frac{247}{12} \times \frac{\pi}{180} = \frac{247}{2160}\pi$ rad

and $\because$ $90° = 100$ grade

$\therefore$ $\left(\frac{247}{12}\right)^\circ = \frac{247}{12} \times \frac{100}{90} = \frac{2470}{108}$ grade $= \frac{1235}{54}$ grade

(iii) $50° 38′ 40″ = 50° 38\frac{40}{60}$ min $= 50°\frac{116}{3}$ min

$= 50° \frac{116}{3 \times 60}$ degree

$= \frac{2279}{45}$ degree

Now $180° = \pi$ rad

$\because$ $\left(\frac{2279}{45}\right)^\circ = \frac{2279}{45} \times \frac{\pi}{180} = \frac{2279}{8100}\pi$ rad

and $90° = 100^g$

$\Rightarrow$ $\left(\frac{2279}{8100}\right)^\circ = \frac{2279}{8100} \times \frac{100}{90} = \frac{2279}{7290}$ grade.

EXAMPLE 2 *One angle of a triangle is 54° and another angle is $\frac{\pi}{4}$ radian. Find the third angle in centesimal unit.*

SOLUTION Let $\angle A = 54°$ and $\angle B = \frac{\pi}{4}$ rad

$\therefore$ $B = 45°$

Thus, $\angle A + \angle B = 99°$

$\therefore$ $\angle C = 180 - 99 = 81°$ ($\because \angle A + \angle B + \angle C = 180°$)



Now, since $90° = 100$ grade

$\Rightarrow$ $81° = 81 \times \frac{100}{90} = 90$ grade

EXAMPLE 3 *The difference between two acute angles of a right-angled triangle is $\frac{\pi}{6}$ radians. Find the angle in degrees.*

SOLUTION $\angle A + \angle B = 90°$

and $\angle A - \angle B = \frac{\pi}{6} = 30°$

$\therefore$ $\angle A = 60°$ and $\angle B = 30°$

Hence the two acute angles are 60° and 30°.



EXAMPLE 4 *In a circle of diameter 60 m, the length of a chord is 30 m. Find the length of the minor arc on one side of the chord. What is the length of the major arc?*

SOLUTION $2r = 60$ m $\Rightarrow$ $r = 30$ m

$\therefore$ $OA = OB = AB = 30$ m

$\therefore$ ΔOAB is an equilateral triangle.

Thus, $\angle AOB = 60° = \frac{\pi}{3}$ rad

Now, since $s = \theta$ $r = \frac{\pi}{3} \times 30$

$= 10 \times 3.142$

$= 31.42$ m (approx.)



Thus the length of minor arc $ACB = 31.42$ m and the length of major arc

$= (2\pi r -$ minor arc)

$= 2\pi \times 30 - 31.42 = 157.1$ m (approx.)

EXAMPLE 5 *An arc AB of a circle subtends an angle x radians at the centre O of the circle. Given that the area of the sector AOB is equal to the square of the length of the arc AB, find the value of x.*

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION Let arc $AB = s$

Given that area of the sector $AOB = (\text{arc } AB)^2$

$\therefore \frac{1}{2}r^2x = s^2$ and $s = rx$ $(\because \theta = x)$

$\therefore \frac{1}{2}r^2x = r^2x^2$ or $x = \frac{1}{2}$ radian



EXAMPLE 6 *Two arcs of two different circles are of equal lengths. If these arcs subtends angles of 45° and 60° at the centres of the circles. Find the ratio of the radii of the two circles.*

SOLUTION $45° = \frac{\pi}{4}$ rad and $60° = \frac{\pi}{3}$ rad

Let r_1 and r_2 be the radii of the two circles and s be the length of each arc.

$\therefore$ $s = r_1\frac{\pi}{4} = r_2\frac{\pi}{3}$ $(\because s = r\theta)$

$\Rightarrow$ $\frac{r_1}{r_2} = \frac{4}{3}$

Hence the required ratio of radii = 4 : 3

EXAMPLE 7 *The wheel of a railway carriage is 4 ft in diameter and makes 6 revolution per second, how fast is the train going ? ($\pi = 3.14$)*

SOLUTION Radius (r) of the wheel = 2 ft

$\therefore$ Circumference of wheel = $2 \times 3.14 \times 2 = 12.56$ ft

Since the wheel makes 6 revolutions per second,

$\therefore$ Distance traversed in 1 second = $6 \times 12.56 = 75.36$ ft.

Hence the velocity of the train = 75.36 ft/s

$= \frac{75.36 \times 60 \times 60}{3 \times 1760}$

$= 51.38$ mile/h

EXAMPLE 8 *A horse trots uniformly along a circular track of radius 27 m. The angle subtended at the centre of the track by the arc passed over by the horse in 3 seconds is 70°. What distance will the horse pass over in $\frac{1}{2}$ minute.*

SOLUTION $r = 27$ m

$\theta = 70° = \frac{7\pi}{18}$ radian

$\therefore$ $s = r\theta = 27 \times \frac{7\pi}{18} = 33$ m (approx.)

$\therefore$ Distance passed over by the horse in $\frac{1}{2}$ minute

$= \frac{33}{3} \times 30 = 330$ m (approx.)

INTRODUCTORY EXERCISE-11.1

1. The perimeter of a certain sector of a circle is equal to the length of the arc of the semicircle having the same radius. The angle of the sector (approx.) is :
   (a) 65° 27′ 16″ (b) 68° 18′ 19″
   (c) 56° 52′ 18″ (d) none of these
2. The length of a pendulum is 8 m while the pendulum swings through 1.5 rad, find the length of the arc through which the tip of the pendulum passes :
   (a) 8 m (b) 9 m
   (c) 12 m (c) none of these
3. The angles of a triangle are in AP and the greatest angle is 75°. Find all the three angles in degrees :
   (a) 55°, 55°, 70° (b) 45°, 60°, 75°
   (c) 40°, 65°, 75° (d) none of these
4. A circular wire of radius 2.5 cm is cut and bent so as to lie along the circumference of a hoop whose radius is 1.29 m. Find (in degrees) the angle which is subtended at the centre of the hoop :
   (a) 9.67° (b) 7.69°
   (c) 6.97° (d) none of these
5. A circle is drawn on AB as diameter. The centre of the circle is O and the length $AB = 13$ cm. P is a point on the circumference of the circle such that the chord $AP = 12$ cm. Calculate the value of the angles PAB and POB in radians :
   (a) 0.395, 0.789 (b) 0.786, 0.735
   (c) 0.398, 0.689 (d) 0.786, 0.753

TRIGONOMETRICAL RATIOS

$\sin\theta = \frac{P}{H}, \cos\theta = \frac{B}{H}, \tan\theta = \frac{P}{B}$

$\text{cosec}\,\theta = \frac{H}{P}, \sec\theta = \frac{H}{B}, \cot\theta = \frac{B}{P}$



Remember :

sin θ	cos θ	tan θ	
P	B	P	⇒ Pandit Badri Prasad
H	H	B	⇒ Hari Hari Bol
cosec θ	sec θ	cot θ	

$P \rightarrow$ Perpendicular (AC)
$B \rightarrow$ Base (BC)
$H \rightarrow$ Hypotenuse (AB)

Scanned by CamScanner

yoursmahboob.wordpress.com

Thus, $\sin\theta \operatorname{cosec}\theta = 1$, $\cos\theta \sec\theta = 1$, $\tan\theta \cot\theta = 1$ and $\tan\theta = \frac{\sin\theta}{\cos\theta}$, $\cot\theta = \frac{\cos\theta}{\sin\theta}$

NOTE $(\sin\theta)^{-1}$ is not written as $\sin^{-1}\theta$. Thus $\sin^{-1}\theta \neq (\sin\theta)^{-1}$ etc but $(\sin\theta)^2 = \sin^2\theta$ and $(\sin\theta)^3 = \sin^3\theta$

$\sin^2\theta + \cos^2\theta = 1$

$\sec^2\theta - \tan^2\theta = 1$

$\operatorname{cosec}^2\theta - \cot^2\theta = 1$

SIGN OF TRIGONOMETRICAL FUNCTIONS

sin and cosec +ve	All +ve
tan and cot +ve	cos and sec +ve

+ve → (Positive)



A → All

S → sin/cosec

T → tan/cot

C → cos/sec

Remember : "Add Sugar To Coffee"

Values of T-Ratios :

Angle	$\theta = 0°$	$\theta = 30°$	$\theta = 45°$	$\theta = 60°$	$\theta = 90°$	$\theta = 180°$
sin	0	1/2	$1/\sqrt{2}$	$\sqrt{3}/2$	1	0
cos	1	$\sqrt{3}/2$	$1/\sqrt{2}$	1/2	0	−1
tan	0	$1/\sqrt{3}$	1	$\sqrt{3}$	∞	0
cosec	∞	2	$\sqrt{2}$	$2/\sqrt{3}$	1	∞
sec	1	$2/\sqrt{3}$	$\sqrt{2}$	2	∞	−1
cot	∞	$\sqrt{3}$	1	$1/\sqrt{3}$	0	∞

Remember :

$\operatorname{cosec}\theta = \frac{1}{\sin\theta}$, $\sec\theta = \frac{1}{\cos\theta}$, $\cot\theta = \frac{1}{\tan\theta}$

and $\tan\theta = \frac{\sin\theta}{\cos\theta}$, $\cot\theta = \frac{\cos\theta}{\sin\theta}$

and $\tan\theta = \frac{1}{\cot\theta}$ or $\cot\theta = \frac{1}{\tan\theta}$

Range of Trigonometric Ratios :

(i) $-1 \le \sin\theta \le 1 \Rightarrow |\sin\theta| \le 1$

(ii) $-1 \le \cos\theta \le 1 \Rightarrow |\cos\theta| \le 1$

(iii) $\operatorname{cosec}\theta \le -1$ and $\operatorname{cosec}\theta \ge 1 \Rightarrow |\operatorname{cosec}\theta| \ge 1$

(iv) $\sec\theta \le -1$ and $\sec\theta \ge 1 \Rightarrow |\sec\theta| \ge 1$

(v) $-\infty < \tan\theta < \infty$ *i.e.*, $\tan\theta$ may assume any value.

INCREASING AND DECREASING FUNCTIONS OF T-RATIOS

	1st quadrant	2nd quadrant	3rd quadrant	4th quadrant
sin θ	increases from 0 to 1	decreases from 1 to 0	decreases from 0 to −1	increases from −1 to 0
cos θ	decreases from 1 to 0	decreases from 0 to −1	increases from −1 to 0	increases from 0 to 1
tan θ	increases from 0 to ∞	increases from −∞ to 0	increases from 0 to ∞	increases from −∞ to 0

INTRODUCTORY EXERCISE-11.2

Directions for question number 1 to 7: Find the values of the following expressions.

1. $\frac{\sec^2\theta - 1}{\tan^2\theta} = ?$

(a) 1 (b) 2
(c) 3 (d) 4

2. $\sin^4\theta + \sin^2\theta\cos^2\theta = ?$

(a) 0 (b) 1
(c) 2 (d) $\sin^2\theta$

3. $\frac{\sin\theta \operatorname{cosec}\theta \tan\theta \cot\theta}{\sin^2\theta + \cos^2\theta} = ?$

(a) 0 (b) 1
(c) −1 (d) 2

4. $\sin^2 A \cot^2 A + \cos^2 A \tan^2 A = ?$

(a) −1 (b) 0
(c) 3 (d) 1

5. $\tan\theta + \cot\theta$ is :

(a) 1 (b) $\tan\theta$
(c) $\operatorname{cosec}\theta\cot\theta$ (d) $\sec\theta\operatorname{cosec}\theta$

6. $\frac{3 - 4\sin^2\theta}{\cos^2\theta} + \tan^2\theta$ is :

(a) 1 (b) 2
(c) 3 (d) none of these

7. $\frac{\cot A + \tan B}{\cot B + \tan A}$ is :

(a) $\tan A \cot B$ (b) $\cot A \tan B$
(c) 1 (d) none of these

8. If $\sin\theta = \frac{21}{29}$, find the value of $\sec\theta + \tan\theta$, if θ lies between 0 and $\pi/2$:

(a) 1 (b) $\pi/2$
(c) 5/2 (d) none of these

9. If A is in the fourth quadrant and $\cos A = \frac{5}{13}$, find the value of $\frac{13\sin A + 5\sec A}{5\tan A + 6\operatorname{cosec} A}$:

(a) −2/37 (b) −3/27
(c) 2/37 (d) can't be determined

Scanned by CamScanner

yoursmahboob.wordpress.com

10. Find the value of,

$\frac{4}{3}\cot^2 30° + 3\sin^2 60° - 2\,\text{cosec}^2 60° - \frac{3}{4}\tan^2 30°$:

(a) 10 / 3 (b) 11 / 3
(c) 4 (d) none of these

11. Find the perimeter of a regular octagon inscribed in a circle of radius 100 cm :

(a) 532.87 cm (b) 612.32 cm
(c) 378.32 cm (d) 875 cm

12. Find the altitude and base of an isosceles triangle whose vertical angle is 65° and whose equal sides are 415 cm :

(a) 350 cm, 646 cm (b) 350 cm, 446 cm
(c) 630 cm, 445 cm (d) none of these

13. If $5\sin^2\theta + 3\cos^2\theta = 4$, find the value of $\sin\theta$ and $\cos\theta$:

(a) $\pm\frac{1}{\sqrt{2}}, \pm\frac{1}{\sqrt{2}}$ (b) $\pm\frac{\sqrt{3}}{2}, \pm\sqrt{2}$
(c) $\frac{\sqrt{3}}{2}, \frac{1}{\sqrt{2}}$ (d) none of these

14. Find the value of $\sqrt{\frac{1+\cos\theta}{1-\cos\theta}} + \sqrt{\frac{1-\cos\theta}{1+\cos\theta}}$:

(a) 2 sec θ (b) sec θ
(c) 2 cosec θ (d) none of these

15. If $\tan\theta = \frac{a}{b}$, find the value of $\frac{a\sin\theta - b\cos\theta}{a\sin\theta + b\cos\theta}$

(a) $\frac{a^2 - b^2}{a^2 + b^2}$ (b) $\frac{b^2 - a^2}{b^2 + a^2}$
(c) $\frac{a^2 + b^2}{a^2 - b^2}$ (d) none of these

Direction for question number 16-18 : For the every $0, 0 < \theta \le 90$, find the values of the following angles.

16. $\tan\theta + \cot\theta = 2$:

(a) 30° (b) 45°
(c) 60° (d) none of these

17. $2\sin^2\theta + 4\cos^2\theta = 3$:

(a) 30° (b) 60°
(c) 45° (d) none of these

18. $2\sin^2\theta - 3\sin\theta = -1$:

(a) 30° (b) 45°
(c) 90° (d) both (a) and (c)

TRIGONOMETRICAL RATIOS OF NEGATIVE AND ASSOCIATED ANGLES

Angle	$-\theta$	$(90-\theta)$	$(90+\theta)$	$(180-\theta)$	$(180+\theta)$	$(360-\theta)$	$(360+\theta)$
$\sin\theta$	$-\sin\theta$	$\cos\theta$	$\cos\theta$	$\sin\theta$	$-\sin\theta$	$-\sin\theta$	$\sin\theta$
$\cos\theta$	$\cos\theta$	$\sin\theta$	$-\sin\theta$	$-\cos\theta$	$-\cos\theta$	$\cos\theta$	$\cos\theta$
$\tan\theta$	$-\tan\theta$	$\cot\theta$	$-\cot\theta$	$-\tan\theta$	$\tan\theta$	$-\tan\theta$	$\tan\theta$

SUM, DIFFERENCE AND PRODUCT FORMULAE

1. $\sin(A+B) = \sin A\cos B + \cos A\sin B$
2. $\sin(A-B) = \sin A\cos B - \cos A\sin B$
3. $\cos(A+B) = \cos A\cos B - \sin A\sin B$
4. $\cos(A-B) = \cos A\cos B + \sin A\sin B$
5. $\tan(A+B) = \frac{\tan A + \tan B}{1 - \tan A\tan B}$
6. $\tan(A-B) = \frac{\tan A - \tan B}{1 + \tan A\tan B}$
7. $\sin(A+B)\sin(A-B) = \sin^2 A - \sin^2 B$
   $= \cos^2 B - \cos^2 A$
8. $\cos(A+B)\cos(A-B) = \cos^2 A - \sin^2 B$
   $= \cos^2 B - \sin^2 A$
9. $2\sin A\cos B = \sin(A+B) + \sin(A-B)$
10. $2\cos A\sin B = \sin(A+B) - \sin(A-B)$
11. $2\cos A\cos B = \cos(A+B) + \cos(A-B)$
12. $2\sin A\sin B = \cos(A-B) - \cos(A+B)$
13. $\cot(A+B) = \frac{\cot A\cot B - 1}{\cot A + \cot B}$
14. $\cot(A-B) = \frac{\cot A\cot B + 1}{\cot B - \cot A}$
15. $\sin C + \sin D = 2\sin\frac{C+D}{2}\cos\frac{C-D}{2}$
16. $\sin C - \sin D = 2\cos\frac{C+D}{2}\sin\frac{C-D}{2}$
17. $\cos C + \cos D = 2\cos\frac{C+D}{2}\cos\frac{C-D}{2}$
18. $\cos C - \cos D = 2\sin\frac{C+D}{2}\sin\frac{D-C}{2}$

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE-11.3

1. If $A + B = 45°$, find the value of $\tan A + \tan B + \tan A \tan B$:
   (a) -1 (b) $\frac{1}{2}$
   (c) $\sqrt{3}$ (d) 1

2. Find the value of $\tan 75°$:
   (a) $\frac{\sqrt{3}+1}{2\sqrt{2}}$ (b) $\frac{\sqrt{3}}{2+\sqrt{2}}$
   (c) $\frac{\sqrt{3}-1}{2\sqrt{2}}$ (d) $\frac{2+\sqrt{2}}{\sqrt{3}}$

3. Find the value of $\cos 28° \cdot \cos 32° - \sin 28° \cdot \sin 32°$:
   (a) 1 (b) 1/2
   (c) 1/3 (d) can't be determined

4. If $\cos A = \frac{3}{5}$ and $\sin B = \frac{5}{13}$, find the value of $\frac{\tan A + \tan B}{1 - \tan A \tan B}$:
   (a) $\frac{63}{16}$ (b) $\frac{36}{16}$
   (c) $\frac{61}{36}$ (d) none of these

5. Find the value of
   $\sin^2(120° - A) + \sin^2 A + \sin^2(120° + A)$:
   (a) $\frac{2}{3}$ (b) $\frac{3}{2}$
   (c) $\frac{5}{2}$ (d) $\frac{\sqrt{3}}{2}$

6. If $\cos(\alpha + \beta) = \frac{4}{5}$ and $\sin(\alpha - \beta) = \frac{5}{13}$ and α, β lie between 0° and 45°, find the value of $\tan 2\alpha$:
   (a) $\frac{56}{63}$ (b) $\frac{56}{33}$
   (c) $\frac{25}{33}$ (d) $\frac{65}{63}$

7. Find the maximum and minimum values of $7\cos\theta + 24\sin\theta$:
   (a) 25 and -25 (b) 16 and -9
   (c) 25 and 0 (d) 36 and 25

8. Find the value of $2\cos 45° \cdot \cos 15°$:
   (a) $\frac{(\sqrt{3}+1)}{2\sqrt{2}}$ (b) $\frac{(\sqrt{3}-1)}{2}$
   (c) $\frac{\sqrt{3}+1}{2}$ (d) none of these

9. Find the value of $\frac{\sin 75° + \sin 15°}{\cos 75° + \cos 15°}$:
   (a) 1 (b) 2
   (c) $\frac{\sqrt{3}}{2}$ (d) can't be determined

10. Find the value of $\cos 20° + \cos 100° + \cos 140°$:
    (a) -1 (b) 0
    (c) 1 (d) none of these

11. $\cos 20° \cdot \cos 40° \cdot \cos 60° \cdot \cos 80°$ is:
    (a) $\frac{1}{16}$ (b) $\frac{1}{50}$
    (c) $\frac{1}{24}$ (d) $\frac{1}{25}$

12. What is the value of;
    $\frac{\sin(90° - \theta)\sec(180° - \theta)\sin(-\theta)}{\sin(180° + \theta)\cot(360° - \theta)\operatorname{cosec}(90° + \theta)}$:
    (a) $\sin\theta$ (b) $\cos\theta$
    (c) 1 (d) $\frac{1}{\sqrt{2}}$

13. If $\sin(\alpha + \beta) = \frac{4}{5}$, $\sin(\alpha - \beta) = \frac{5}{13}$, find the value of $\tan 2\alpha$:
    (a) $\frac{16}{36}$ (b) $\frac{63}{16}$
    (c) $\frac{36}{16}$ (d) none of these

14. Find the value of $\frac{\cos 2B - \cos 2A}{\sin 2A + \sin 2B}$:
    (a) $\tan(A - B)$ (b) $\cos(A - B)$
    (c) $\cot(A - B)$ (d) $\tan(A + B)$

15. $\frac{\sin A + \sin 3A + \sin 5A + \sin 7A}{\cos A + \cos 3A + \cos 5A + \cos 7A}$ is:
    (a) $\tan 2A$ (b) $\tan 3A$
    (c) $\tan 4A$ (d) $\tan 8A$

TRIGONOMETRICAL RATIOS OF MULTIPLE AND SUB-MULTIPLE ANGLES

1. $\sin 2A = 2\sin A \cos A = \frac{2\tan A}{1 + \tan^2 A}$

2. $\cos 2A = \cos^2 A - \sin^2 A = 1 - 2\sin^2 A$
   $= 2\cos^2 A - 1 = \frac{1 - \tan^2 A}{1 + \tan^2 A}$

3. $\tan 2A = \frac{2\tan A}{1 - \tan^2 A}$

4. $\sin 3A = 3\sin A - 4\sin^3 A$

5. $\cos 3A = 4\cos^3 A - 3\cos A$

6. $\tan 3A = \frac{3\tan A - \tan^3 A}{1 - 3\tan^2 A}$

7. $\sin A = 2\sin\left(\frac{A}{2}\right)\cos\left(\frac{A}{2}\right) = \frac{2\tan(A/2)}{1 + \tan^2(A/2)}$

8. $\cos A = \cos^2\left(\frac{A}{2}\right) - \sin^2\left(\frac{A}{2}\right)$ etc.

9. $\tan A = \frac{2\tan(A/2)}{1 - \tan^2(A/2)}$

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE-11.4

1. If $\sin\theta = \frac{4}{5}$, find the value of $\sin 2\theta$:
   (a) 24/25 (b) 16/25
   (c) 9/20 (d) none of these

2. $\frac{\sin 2A}{1+\cos 2A}$ is :
   (a) $\tan 2A$ (b) $\cos 2A$
   (c) $\tan A$ (d) none of these

3. $\cos^4\theta - \sin^4\theta$ is :
   (a) $\cos 2\theta$ (b) $\sin 2\theta$
   (c) $\tan 2\theta$ (d) none of these

4. If $\cot x = \frac{a}{b}$, find the value of $a\cos 2x + b\sin 2x$
   (a) a (b) b
   (c) $\sin a$ (d) a/b

5. Find the value of $\cot 3\theta$:
   (a) $\frac{\cot^3\theta - 3\cot\theta}{3\cot^2\theta}$ (b) $\frac{\cot^3\theta - 3\cot\theta}{3\cot^2\theta - 1}$
   (c) $\frac{3\cot\theta - \cot^3\theta}{3\cot^2\theta - 1}$ (d) none of these

6. Find the value of $\sin\left(22\frac{1}{2}\right)^\circ$:
   (a) $\frac{\sqrt{(2-\sqrt{2})}}{2}$ (b) $\frac{\sqrt{(2-\sqrt{3})}}{3}$
   (c) $\frac{\sqrt{2-\sqrt{2}}}{4}$ (d) none of these

7. If $2\cos\theta = x + \frac{1}{x}$, find the value of $2\cos 3\theta$
   (a) $x^3 + \frac{1}{x^3}$ (b) $x^2 + \frac{1}{x^2}$
   (c) $x^3 - \frac{1}{x^3}$ (d) $\sqrt{x + \frac{1}{x}}$

8. Find the value of $\tan A + \tan B + \tan C$, if $A + B + C = \pi$:
   (a) $\tan A \tan B \tan C$ (b) 1
   (c) 0 (d) $\cot A \cot B \cot C$

PROPERTIES OF TRIANGLES

A triangle ABC has three angles and three sides. The three angles are denoted by A, B and C while the three sides are denoted by a, b and c respectively. The area of the triangle is denoted by Δ and its perimeter is denoted by $2s$, so that $a+b+c=2s$. Thus 's' is the semiperimeter of the triangle and $s=\frac{a+b+c}{2}$. Also we denote the circumradius by R and inradius by r.



1. **The law of sines :** In any triangle the sides are proportional to the sines of the opposite angles *i.e.*,

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C}$$

2. **The law of cosines :** The square on any side of a triangle is equal to the sum of the squares on the other two sides, minus twice the product of those two sides and the cosine of the included angle *i.e.*,

$$a^2 = b^2 + c^2 - 2bc\cos A$$
$$b^2 = c^2 + a^2 - 2ca\cos B$$
$$c^2 = a^2 + b^2 - 2ab\cos C$$

3. **Area of a triangle :**

(i) $\Delta = \frac{1}{2}bc\sin A = \frac{1}{2}ca\sin B = \frac{1}{2}ab\sin C$

(ii) $\Delta = \sqrt{s(s-a)(s-b)(s-c)}$ (Hero's formula)

4. **The area of a segment of a circle :**

Area of the segment APB
= Area of the sector AOB
− Area of ΔAOB

$$= \frac{1}{2}r^2\theta - \frac{1}{2}r^2\sin\theta$$
$$= \frac{1}{2}r^2(\theta - \sin\theta)$$



5. **Circumradius of a circle (R) :**

(i) $R = \frac{a}{2\sin A} = \frac{b}{2\sin B} = \frac{c}{2\sin C}$

(ii) $R = \frac{abc}{4\Delta}$

6. **Inradius of a circle (r)**

$$r = \frac{\Delta}{s} \qquad \left(s = \frac{a+b+c}{2}\right)$$

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE-11.5

1. If $\cos B = \frac{\sin A}{2\sin C}$, find the nature of triangle :
   (a) isosceles (b) scalene
   (c) can't be determined (d) none of these

2. If the angles of a triangle are in the ratio $1:2:3$ and its circumradius is 10 cm, find the sides of the triangle (in cm) :
   (a) 8, 16, 24 (b) 18, 12, 6
   (c) $10, 20, 20\sqrt{3}$ (d) $10, 20, 10\sqrt{3}$

3. If $a = 1$, $b = \sqrt{3}$ and $A = 30°$, find the value of the angle B:
   (a) 60° (b) 30°
   (c) 120° (d) either (a) or (c)

4. Find B and C of a triangle ABC, if $b = 2$ cm, $c = 1$ cm and $A = 60°$:
   (a) 90° and 45° (b) 90° and 30°
   (c) 60° and 30° (d) none of these

5. In a triangle ABC, $a = 1$ cm, $b = \sqrt{3}$ cm and $C = \frac{\pi}{6}$, find the third side of the triangle :
   (a) 1 cm (b) 1.5 cm
   (c) 2 cm (d) $3\sqrt{3}$ cm

6. If the angles of a triangle are in the ratio $1:2:3$, find the ratio between corresponding sides :
   (a) $3:2:1$ (b) $1:\sqrt{3}:2$
   (c) $6:3:2$ (d) $1:\sqrt{2}:\sqrt{3}$

7. If $a = 2b$ and $A = 3B$, find the angles A, B, C of ΔABC :
   (a) 90°, 30°, 60° (b) 30°, 60°, 90°
   (c) 45°, 45°, 90° (d) data insufficient

8. If in any triangle $a = 13$ cm, $b = 14$ cm and $c = 15$ cm, find the inradius of the circle :
   (a) 2 cm (b) 6.5 cm
   (c) 4 cm (d) 7 cm

9. In a right angled triangle $a^2 + b^2 + c^2$ is :
   (a) R^2 (b) $4R^2$
   (c) $8R^2$ (d) none of these

10. Abhinav and Brijesh started walking simultaneously @ 3 km/h and 4 km/h from the same point 'C' on two different paths which diverge from each other at an angle of 120°. They walked for 6 hours and they stopped at A and B respectively. What is the least possible distance between Abhinav and Brijesh when they are at A and B respectively.
    (a) $36\sqrt{37}$ (b) $6\sqrt{37}$ km
    (c) $12\sqrt{37}$ (d) none of these

HEIGHT AND DISTANCE

Angle of Elevation : $\angle OPM$ is called as the angle of elevation.

Suppose a person P is looking an object O which is at a higher level than P, then the angle θ ($\angle OPM$) is the angle of elevation for that person.



Fig. (i)

Angle of Depression : $\angle OPM$ in fig.(ii) is called as angle of depression.

Suppose a person P is looking downward an object O, which is at a lower level than P, then the angle θ ($\angle OPM$) is called as the angle of depression.



Fig. (ii)

NOTE It should be noted that the angle of elevation of one position as seen from the other is equal to the angle of depression of the latter as seen from the former.

EXAMPLE 1 *From the top of a tower 180 m high, it was observed that the angle of depression of the bottom of a cat sitting on the ground was 30°. Find the distance of the cat from the foot of the tower.*

SOLUTION Let PT be the tower and cat is sitting at C

then $\angle MTC = \angle TCP$

Now in ΔCPT, $\angle TCP = 30°$

$\therefore \quad \tan 30° = \frac{TP}{PC}$

$\frac{1}{\sqrt{3}} = \frac{180}{PC}$

$\Rightarrow \quad PC = 180\sqrt{3}$ m

$= 311.76$ m



Hence cat is 311.76 m away from the foot of the tower.

NOTE For a particular case, the angle of depression is equal to the angle of elevation.

EXAMPLE 2 *The angle of elevation of the top of a tower at a distance of 100 m from its foot on a horizontal plane is found to be 60°. Find the height of the tower.*

SOLUTION Let AB be the tower

then $\tan 60° = \frac{AB}{AC}$

$\sqrt{3} = \frac{AB}{100}$

$AB = 100\sqrt{3}$ m $= 173.2$ m



Thus the height of the tower is 173.2 m.

EXAMPLE 3 *A person standing on the bank of a river observes that the angle subtended by a tree on the opposite bank is 60°, when he retreats 40 m from the bank he finds the angle to be 30°. Find the height of the tree and the breadth of the river.*

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION Let height of the tree be AB and width of the river be AC.



In ΔABC, $\tan 60° = \frac{h}{x}$

$$\sqrt{3} = \frac{h}{x} \Rightarrow h = x\sqrt{3} \quad \ldots(1)$$

and in ΔABD, $\frac{AB}{AD} = \tan 30°$

$$\frac{h}{(x+40)} = \frac{1}{\sqrt{3}} \quad \ldots(2)$$

From equation (1) and (2), we get

$$\frac{x\sqrt{3}}{(x+40)} = \frac{1}{\sqrt{3}}$$

$$x = 20 \text{ m}$$

$\therefore$ $h = x\sqrt{3} = 20\sqrt{3} = 34.64$ m (approx.)

Thus the height of the tree is 34.46 m and breadth of the river is 20 m.

EXAMPLE 4 *Two towers of the same height stand on either side of a road 60 m wide. At a point on the road between the towers, the elevations of the towers are 60° and 30°. Find the height of the towers and the position of the point.*

SOLUTION In ΔAOB

$$\frac{AB}{AO} = \frac{h}{x} = \frac{1}{\sqrt{3}}$$



and in ΔCOD, $\frac{CD}{OC} = \frac{h}{(60-x)} = \sqrt{3}$ ...(1)

from equation (1) and (2)

$$\frac{x}{\sqrt{3}(60-x)} = \sqrt{3} \Rightarrow x = 45 \text{ m}$$

$\therefore$ $h = \frac{45}{\sqrt{3}} = 15\sqrt{3} = 15 \times 1.732 = 25.98$ m

Hence, the height of the towers is 25.98m and the distance of the point 'O' from A is 45 m and C is 15 m.

EXAMPLE 5 *From the top of a cliff, 200 m high, the angle of depression of the top and bottom of a tower are observed to be 30° and 60°, find the height of the tower.*

SOLUTION Let the height of the tower be h m, then



In ΔPBM, $\tan 60° = \frac{PM}{BM}$

$$\sqrt{3} = \frac{200}{BM}$$

$BM = \frac{200}{\sqrt{3}}$ m $= AL$ (also)

Now, in ΔALP,

$$\tan 30° = \frac{PL}{AL}$$

$$\frac{1}{\sqrt{3}} = \frac{PL}{(200/\sqrt{3})}$$

$\Rightarrow$ $PL = \frac{200}{3}$

$\therefore$ $LM = PM - PL = 200 - \left(\frac{200}{3}\right)$

$$LM = \frac{400}{3}$$

But $LM = AB = h$

$\therefore$ Height of the tower $(h) = \frac{400}{3}$ m

EXAMPLE 6 *A man on the top of a rock rising on a seashore observes a boat coming towards it. If it takes 10 minutes for the angle of depression to change form 30° to 60°, how soon the boat reach the shore ?*

SOLUTION Let AB be the rock of height 'h' metres.



Let C and D be the two positions of boat such that

$\angle ACB = \angle XBC = 30°$

and $\angle ADB = \angle XBD = 60°$

Let $CD = x$ m and $AD = y$ m

Now, in ΔABD, $\tan 60° = \frac{h}{y}$

$$\sqrt{3} = \frac{h}{y} \quad \ldots(1)$$

and in ΔABC, $\tan 30° = \frac{h}{x+y} = \frac{1}{\sqrt{3}}$ ...(2)

from equation (1) and (2), we get

$$\frac{\sqrt{3}y}{x+y} = \frac{1}{\sqrt{3}} \Rightarrow x = 2y \Rightarrow y = \frac{x}{2}$$

Since the boat takes 10 minutes to cover x m, hence it will take $\frac{10}{2} = 5$ minutes to cover $y = \frac{x}{2}$ metres. Thus the required time

$= 5$ minutes.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 7 *The angles of elevation of an aeroplane from two places 10 km apart are found to be 60° and 30° respectively. Find the height of the aeroplane.*

SOLUTION Let A and B be the two places such that $AB = 10$ kms and let C be the position of the aeroplane at a height of h metres above AB. Let CD be perpendicular to AB.

In Ist case :



In ΔBCD, $\quad \frac{h}{x} = \frac{1}{\sqrt{3}}$ ...(1)

and $\quad \frac{h}{10-x} = \sqrt{3}$ ...(2)

from equation (1) and (2)

$$\frac{x}{\sqrt{3}(10-x)} = \sqrt{3} \Rightarrow x = 7.5 \text{ km}$$

$$\therefore \quad h = \frac{7.5}{\sqrt{3}} = \frac{7.5}{3} \times \sqrt{3} = 2.5 \times \sqrt{3}$$

$$= 4.33 \text{ km (approx.)}$$

In IInd case :



In ΔACD, $\quad \frac{h}{x} = \sqrt{3}$ ...(1)

In ΔBCD, $\quad \frac{h}{10+x} = \frac{1}{\sqrt{3}}$ ...(2)

Therefore from equation (1) and (2)

$$h = 5\sqrt{3} \text{ km} \Rightarrow h = 8.66 \text{ km}$$

INTRODUCTORY EXERCISE-11.6

1. Two towers of the same height stand on opposite sides of a road 100 m wide. At a point on the road between the towers, the elevations of the towers are 30° and 45°. Find the height of the towers and the position of the point from the nearest tower :
   (a) 36.6 m and 63.4 m (b) 63.3 m and 63.4 m
   (c) 66.3 m and 63.4 m (d) 36.6 m and 86.4 m
2. The elevation of a tower at a station A due north of it is 45° and at a station B due west of A is 30°. If $AB = 40$ m, find the height of the tower :
   (a) 26.26 m (b) 28.28 m
   (c) 38.5 m (d) none of these
3. If the shadow of a tower is 30 m when the sun's altitude is 30° what is the length of the shadow when the sun's altitude is 60° ?
   (a) $10\sqrt{3}$ m (b) 20 m
   (c) 10 m (d) 12 m
4. A helicopter is in a stationary position at a certain height over the lake. At a point 200 m above the surface of the lake, the angle of elevation of the helicopter is 45°. At the same time, the angle of depression of its reflection in the lake is 75°. Calculate the height of the helicopter from the surface of the lake :
   (a) $\frac{200}{\sqrt{3}}$ m (b) $200\sqrt{3}$ m
   (c) 200 m (d) 150 m
5. A vertical tower stands on a horizontal plane and surmounted by a flagstaff of height 'h'. At a point on the plane, the angle of elevation of bottom of the flagstaff is α and that of the top of the flagstaff is β. Find the height of the tower :
   (a) $h \tan \alpha$ (b) $\frac{h \tan \alpha}{\tan \alpha - \tan \beta}$
   (c) $\frac{h \tan \alpha}{\tan \beta - \tan \alpha}$ (d) $\frac{\tan \alpha + \tan \beta}{h \tan \alpha}$
6. A round balloon of radius 'r' subtends an angle α at the eye of the observer, while the angle of elevation of its centre is β. Find the height of the centre of balloon.
   (a) $r \operatorname{cosec}\left(\frac{\alpha}{2}\right) \sin \beta$ (b) $r \sin \alpha \operatorname{cosec} \beta$
   (c) $\frac{r}{2} \sin \beta$ (d) $r \sec\left(\frac{\alpha}{2}\right)$
7. At the foot of a mountain the elevation of its summit is 45°, after ascending 1000 m towards the mountain up a stop of 30° inclination, the elevation is found to be 60°. Find the height of the mountain :
   (a) 1.3 km (b) 1.366 km
   (c) 2.72 km (d) none of these
8. An aeroplane when 3000 m high passes vertically above another aeroplane at an instant when their angles of elevation at the same observing point are 60° and 45° respectively. How many metres higher is the one than the other?
   (a) 1248 m (b) 1188 m
   (c) 1752 m (d) 1268 m
9. The angle of elevation of a cloud from a height h above the level of water in a lake is α and the angle of depression of its image in the lake is β. Find the height of the cloud above the surface of the lake :
   (a) $\frac{h \sin(\beta - \alpha)}{\sin(\alpha + \beta)}$ (b) $h \sin \alpha$
   (c) $\frac{h \sin(\alpha + \beta)}{\sin(\beta - \alpha)}$ (d) none of these
10. A palm tree 90 ft high, is broken by the wind and its upper part meet the ground at an angle of 30°. Find the distance of the point where the top of the tree meets the ground, from its root :
    (a) 43.69 ft (b) 51.96 ft
    (c) 60 ft (d) 30 ft

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. If $0 < \theta < 90°$, then $(\sin\theta + \cos\theta)$ is :
   (a) less than 1 (b) equal to 1
   (c) greater than 1 (d) greater than 2

2. The value of x satisfying the equation $\sin x + \frac{1}{\sin x} = \frac{7}{2\sqrt{3}}$ is :
   (a) 10° (b) 30°
   (c) 45° (d) 60°

3. If $\sin\theta - \cos\theta = 0$ and $0 < \theta \leq \pi/2$, then θ is equal to :
   (a) $\frac{\pi}{2}$ (b) $\frac{\pi}{4}$
   (c) $\frac{\pi}{6}$ (d) 0

4. Given that θ is acute and then $\sin\theta = \frac{3}{5}$. Let x, y be positive real numbers such that $3(x - y) = 1$, then one set of solutions for x and y expressed in terms of θ is given by :
   (a) $x = \sec\theta, y = \text{cosec}\,\theta$ (b) $x = \cot\theta, y = \tan\theta$
   (c) $x = \text{csoec}\,\theta, y = \cot\theta$ (d) $x = \sec\theta, y = \tan\theta$

5. Which one of the following pairs is correctly matched ?

If	then
(a) $x = \frac{1 + \sin 60° - \cos 60°}{1 + \sin 60° + \cos 60°}$	$x = \tan 60°$
(b) $x = \frac{1 + \sin 90° - \cos 90°}{1 + \sin 90° - \cos 90°}$	$x = \tan 30°$
(c) $x = \frac{2\tan 30°}{1 - \tan^2 30°}$	$x = \tan 60°$
(d) $x = \frac{1 - \tan^2 30°}{1 + \tan^2 30°}$	$x = \cos 60°$

6. If $x \tan 45° \cdot \cos 60° = \sin 60° \cot 60°$, then x is equal to
   (a) 1 (b) 1/2
   (c) $\sqrt{3}$ (d) $1/\sqrt{2}$

7. If θ lies in the second quadrant, then $\sqrt{\frac{1 - \sin\theta}{1 + \sin\theta}} + \sqrt{\frac{1 + \sin\theta}{1 - \sin\theta}}$ is equal to :
   (a) $-2\sec\theta$ (b) $2\sec\theta$
   (c) $2\,\text{cosec}\,\theta$ (d) $2\tan\theta$

8. $\sin^6 A + \cos^6 A$ is equal to :
   (a) $1 - 3\sin^2 A\cos^2 A$ (b) $1 - 3\sin A\cos A$
   (c) $1 + 3\sin^2 A\cos^2 A$ (d) 1

9. If $\sec x = P$, $\text{cosec}\,x = Q$, then :
   (a) $P^2 + Q^2 = PQ$ (b) $P^2 + Q^2 = P^2Q^2$
   (c) $P^2 - Q^2 = P^2Q^2$ (d) $P^2 + Q^2 = -P^2Q^2$

10. $\sin^2 A\cos^2 B - \cos^2 A\sin^2 B$ simplifies to :
    (a) $\sin^2 A + \sin^2 B$ (b) $\cos^2 A + \cos^2 B$
    (c) $\sin^2 A - \sin^2 B$ (d) $\sin^2 A - \cos^2 B$

11. If $\sin 2x = n\sin 2y$, then the value of $\frac{\tan(x+y)}{\tan(x-y)}$ is :
    (a) $\frac{n+1}{n-1}$ (b) $\frac{n-1}{n+1}$
    (c) $\frac{1-n}{n+1}$ (d) $\frac{1+n}{1-n}$

12. The least value of $2\sin^2\theta + 3\cos^2\theta$ is :
    (a) 1 (b) 2
    (c) 3 (d) 5

13. The value of $\tan(180 + \theta)\cdot\tan(90 - \theta)$ is :
    (a) 1 (b) −1
    (c) 0 (d) none of these

14. $\log\tan 1° + \log\tan 2° + \ldots + \log\tan 89°$ is :
    (a) 1 (b) $1/\sqrt{2}$
    (c) 0 (d) −1

15. If we convert $\sin(-566°)$ to same trigonometrical ratio of a positive angle lying between 0° and 45°, then we get :
    (a) $\cos 26°$ (b) $-\cos 26°$
    (c) $\sin 26°$ (d) $-\sin 26°$

16. From the mast head of ship, the angle of depression of a boat is 60°. If the mast head is 150 m, then the distance of the boat from the ship is :
    (a) 86.6 m (b) 68.6 m
    (c) 66.8 m (d) none of these

17. A portion of a 30 m long tree is broken by tornado and the top struck up the ground making an angle 30° with ground level. The height of the point where the tree is broken is equal to :
    (a) $30/\sqrt{3}$ m (b) 10 m
    (c) $30\sqrt{3}$ m (d) 60 m

18. Two posts are 25 m and 15 m high and the line joining their tips makes an angle of 45° with horizontal. The distance between these posts is :
    (a) 5 m (b) $10/\sqrt{2}$ m
    (c) 10 m (d) $10\sqrt{2}$ m

19. The angle of elevation of the top of a tower at a point G on the ground is 30°. On walking 20 m towards the tower the angle of elevation becomes 60°. The height of the tower is equal to :
    (a) $10/\sqrt{3}$ m (b) $20\sqrt{3}$ m
    (c) $20/\sqrt{3}$ m (d) $10\sqrt{3}$ m

Scanned by CamScanner

yoursmahboob.wordpress.com

20. If $x = \sec\theta + \tan\theta$, $y = \sec\theta - \tan\theta$, then the relation between x and y is :
(a) $x^2 + y^2 = 0$ (b) $x^2 = y^2$
(c) $x^2 = y$ (d) $xy = 1$

21. The value of θ for which $\sqrt{3}\cos\theta + \sin\theta = 1$ is :
(a) 0 (b) $\pi/3$
(c) $\pi/6$ (d) $\pi/2$

22. If $\tan\theta = \frac{4}{3}$, then the value of $\sqrt{\frac{1+\cos\theta}{1-\cos\theta}}$ is :
(a) 1 (b) 2
(c) 3 (d) 4

23. If the arcs of the same length in two circles subtend angles of 60° and 90° at the centre, then the ratio of their radii is :
(a) $\frac{1}{3}$ (b) $\frac{1}{2}$
(c) $\frac{3}{2}$ (d) 2

24. In the third quadrant, the values of $\sin\theta$ and $\cos\theta$ are :
(a) positive and negative respectively
(b) negative and positive respectively
(c) both positive
(d) both negative

25. The value of $\frac{\cot 40^\circ}{\tan 50^\circ} - \frac{1}{2}\frac{\cos 35^\circ}{\sin 55^\circ}$ is :
(a) 1 (b) -1
(c) $\frac{1}{2}$ (d) $-\frac{1}{2}$

26. The value of $\theta (0 \le \theta \le \pi/2)$ satisfying the equation $\sin^2\theta - 2\cos\theta + \frac{1}{4} = 0$ is :
(a) $\frac{\pi}{2}$ (b) $\frac{\pi}{3}$
(c) $\frac{\pi}{4}$ (d) $\frac{\pi}{6}$

27. If $\cos\theta = \frac{4}{5}$ and $0 < \theta < 90^\circ$, then the value of $\frac{3\cos\theta + 2\,\text{cosec}\,\theta}{4\sin\theta - \cot\theta}$ is :
(a) $-\frac{43}{2}$ (b) $-\frac{41}{2}$
(c) $\frac{43}{8}$ (d) $-\frac{43}{6}$

28. Maximum value of $(\cos\theta - \sin\theta)$ is :
(a) $\sqrt{2}$ (b) 1
(c) $\frac{1}{2}$ (d) $\frac{1}{\sqrt{2}}$

29. The value of $\sin 105^\circ$ is :
(a) $\frac{\sqrt{3}-1}{2\sqrt{2}}$ (b) $\frac{\sqrt{3}-1}{\sqrt{2}}$
(c) $\frac{\sqrt{3}+1}{2\sqrt{2}}$ (d) $\frac{\sqrt{3}+1}{\sqrt{2}}$

30. If $\tan\theta = t$, then $\sin 2\theta$ is equal to :
(a) $\frac{1}{1+t^2}$ (b) $\frac{2t}{1+t^2}$
(c) $\frac{t^2}{1+t}$ (d) $\frac{1+t^2}{1+t}$

31. If $\tan\theta = \sqrt{2}$, then the value of θ is :
(a) less than $\frac{\pi}{4}$ (b) equal to $\frac{\pi}{4}$
(c) between $\frac{\pi}{4}$ and $\frac{\pi}{3}$ (d) greater than $\frac{\pi}{3}$

32. If $\tan\theta = 2 - \sqrt{3}$, then $\tan(90 - \theta)$ is equal to :
(a) $2 + \sqrt{3}$ (b) $2 - \sqrt{3}$
(c) $3 + \sqrt{2}$ (d) $3 - \sqrt{2}$

33. If from point 100 m above the ground the angles of depression of two objects due south on the ground are 60° and 45°, then the distance between the objects is :
(a) $\frac{50(3-\sqrt{3})}{3}$ m (b) $\frac{50(3+\sqrt{3})}{3}$ m
(c) $\frac{100(3+\sqrt{3})}{3}$ m (d) $\frac{100(3-\sqrt{3})}{3}$ m

34. If the length of shadow of a vertical pole on the horizontal ground is $\sqrt{3}$ times of its height, then the angle of elevation of sun is :
(a) 15° (b) 30°
(c) 45° (d) 60°

35. A kite is flown with a thread of 250 m length. If the thread is assumed to be stretched and makes an angle of 60° with the horizontal, then the height of the kite above the ground is (approx.) :
(a) 216.25 m (b) 215. 25 m
(c) 212.25 m (d) 210.25 m

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE- 11.1

1 (a)	2. (c)	3. (b)	4. (c)	5. (a)					

INTRODUCTORY EXERCISE- 11.2

1 (a)	2. (d)	3. (b)	4. (d)	5. (d)	6. (c)	7. (b)	8. (c)	9. (a)	10. (a)
11. (b)	12. (b)	13. (a)	14. (c)	15. (a)	16. (b)	17. (c)	18. (d)		

INTRODUCTORY EXERCISE- 11.3

1 (d)	2. (a)	3. (b)	4. (a)	5. (b)	6. (b)	7. (a)	8. (c)	9. (a)	10. (b)
11. (a)	12. (a)	13. (b)	14. (a)	15. (c)					

INTRODUCTORY EXERCISE- 11.4

1 (a)	2. (c)	3. (a)	4. (a)	5. (b)	6. (a)	7. (a)	8. (a)		

INTRODUCTORY EXERCISE- 11.5

1 (a)	2. (d)	3. (d)	4. (b)	5. (a)	6. (b)	7. (a)	8. (c)	9. (c)	10. (b)

INTRODUCTORY EXERCISE- 11.6

1 (a)	2. (b)	3. (c)	4. (b)	5. (c)	6. (a)	7. (b)	8. (d)	9. (c)	10. (b)

LEVEL-1

1 (c)	2. (d)	3. (b)	4. (c)	5. (c)	6. (a)	7. (b)	8. (a)	9. (b)	10. (c)
11. (a)	12. (b)	13. (b)	14. (c)	15. (c)	16. (a)	17. (b)	18. (c)	19. (d)	20. (d)
21. (d)	22. (b)	23. (c)	24. (d)	25. (c)	26. (b)	27. (c)	28. (b)	29. (c)	30. (b)
31. (c)	32. (a)	33. (d)	34. (b)	35. (a)					

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1. Let $z = \sin\theta + \cos\theta$

$\Rightarrow z^2 = 1 + \sin 2\theta$

$\because 0 < \theta < 90°$ so $\sin 2\theta < 1$, so that $z^2 < 2$,

Thus $z < \sqrt{2}$ i.e., z is greater than 1.

2. Go through option.

3. $\sin\theta - \cos\theta = 0$

$\Rightarrow \sin\theta = \cos\theta$

$\Rightarrow \tan\theta = 1 \Rightarrow \theta = \frac{\pi}{4}$

4. Go through option.

HINT $\sin\theta = \frac{3}{5}$ and $\operatorname{cosec}\theta = \frac{5}{3}$

7. $\sqrt{\frac{1-\sin\theta}{1+\sin\theta}} + \sqrt{\frac{1+\sin\theta}{1-\sin\theta}} = \frac{(1-\sin\theta)+(1+\sin\theta)}{\cos\theta}$

$= 2\sec\theta$

8. $a^3 + b^3 = (a+b)^3 - 3ab(a+b)$

Let $a = \sin^2\theta$, $b = \cos^2\theta$, so that

$a + b = \sin^2\theta + \cos^2\theta = 1$

$\Rightarrow \sin^6\theta + \cos^6\theta = 1 - 3\sin^2\theta\cos^2\theta$

9. $\cos x = \frac{1}{P}$ and $\sin x = \frac{1}{Q}$

$1 = \cos^2 x + \sin^2 x = \frac{1}{P^2} + \frac{1}{Q^2}$

$\Rightarrow P^2 + Q^2 = P^2Q^2$

10. $\sin^2 A(1-\sin^2 B) - (1-\sin^2 A)\sin^2 B = \sin^2 A - \sin^2 B$

11. $\frac{n}{1} = \frac{\sin 2x}{\sin 2y}$

$\Rightarrow \frac{n+1}{n-1} = \frac{\sin 2x + \sin 2y}{\sin 2x - \sin 2y} = \frac{2\sin(x+y)\cos(x-y)}{2\cos(x+y)\sin(x-y)}$

$= \frac{\tan(x+y)}{\tan(x-y)}$

12. The value is least when $\theta = 90°$.

14. $\log\tan 1° + \log\tan 89° = \log\tan 1° + \log\tan(90-1)$

$= \log\tan 1° + \log\cot 1°$

$= \log\tan 1°.\cot 1° = \log 1 = 0$

Similarly, $\log\tan 2° + \log\tan 88° = 0$

Also, $\log\tan 45° = \log 1 = 0$

Thus, the value of the expression is 0.

15. $\sin(-566°) = -\sin(566°)$

$= -\sin(90\times 6 + 26) = \sin 26°$.

Scanned by CamScanner

yoursmahboob.wordpress.com

12 GEOMETRY

This chapter tests nothing but your imagination. I think it is the drawing of MATHS. You need not to be an artist or painter, but at least you must be capable to visualize the geometrical figures. So before going for the tedious and complex geometrical problems it is prerequisite to be familiar with the fundamentals of the geometry. Basically it consists of a very large proportion of problems in CAT. Sometimes 8-10 problems related to this chapter in addition with mensuration are asked in CAT. Therefore it is advised that you must learn this chapter religiously for the sake of your score in CAT. Apart from CAT other entrance tests for MBA ask a plethora of questions as well.

Remember if you don't take seriously any theorem, axiom or concept you cannot perform well since the complexity of ideas, figures and concepts makes it a daunting task for you.

For the sake of convenience this chapter is divided into 5 parts.

(i) Lines, angles and planes
(ii) Triangles
(iii) Quadrilaterals
(iv) Polygons
(v) Circles and Loci

"Well begun is half done"–Anonymous

(1) LINE AND ANGLES

Point : The figure of which length, breadth and height cannot be measured is called a point. It is infinitesimal.

Line : A line is made up of a infinite number of points and it has only length *i.e.*, it does not has any thickness (or width). A line is endless *i.e.*, it can be extended in both directions.

Line segment : A line segments has two end points, but generally speaking line segment is called a line.



(line segment $\overline{AB}$)

Ray : A ray extends indefinitely in one direction from any given point. This is exhibited by an arrow. The starting point is called as the initial point.



Plane : It is a flat surface, having length and breadth both, but no thickness. It is a two dimensional figure.



(Plane)

Type of Lines	Definition	Diagram
Parallel lines	Two lines, lying in a plane and having no common intersecting point are called parallel lines. The distance between two parallel lines is constant.	Symbol : $\parallel$
Perpendicular lines	Two lines, which lie in a single plane and intersect eachother at right angle, are called perpendicular lines.	Symbol : $\perp$
Concurrent lines	More than two straight lines intersecting at the same point.	

POINTS TO REMEMBER

1. A line contains infinitely many points.
2. The intersection of two different lines is a point.
3. Through a given point, there pass an infinite number of lines and these lines are called **concurrent lines.**
4. Only one line can pass through any two particular points.
5. When more than two points lie on a line, they are called as **collinear points** else they are called as **non-collinear** points.
6. Two lines can intersect maximum at one point. This point is called as **point of intersection** and these lines are called as **intersecting lines.**
7. There are an infinite number of planes which pass through a single (particular) point.
8. When more than three points lie in the same plane, they are called as **coplanar** else they are called as **non-coplanar.**
9. When more than one line lie in the same plane, then these lines are called as coplanar else they are called as non-coplanar.

Scanned by CamScanner

yoursmahboob.wordpress.com

10. When two plane intersect each other, they form a line *i.e.*, intersecting region is a line.
11. Two different lines which are perpendicular to the same (a third line) line, necessarily parallel to each other, lying on the same plane.
12. When two or more parallel lines are intercepted by some other intercepting lines, then the ratio of corresponding intercepts are equal. An intercepting line is generally called as a transversal.

$$i.e., \quad \frac{AB}{BC} = \frac{DE}{EF}$$

Angles : The amount of rotation about O, the vertex of the angle AOA', is called the magnitude of the angle.

$m\angle AOA'$ denotes the measure of $\angle AOA'$. Angles are said to be congruent when their measure is same. (symbol : $\cong$)



Types of Angles	Property	Diagram
Acute	$0° < \theta < 90°$ ($\angle AOB$ is an acute angle)	
Right	$\theta = 90°$ ($\angle AOB$ is a right angle)	
Obtuse	$90° < \theta < 180°$ ($\angle AOB$ is an obtuse angle)	
Straight	$\theta = 180°$ ($\angle AOB$ is a straight angle)	
Reflex	$180° < \theta < 360°$ ($\angle AOB$ is a reflex angle)	
Complementary	$\theta_1 + \theta_2 = 90°$ Two angles whose sum is 90°, are complementary to each other	
Supplementary	$\theta_1 + \theta_2 = 180°$ Two angles whose sum is 180°, are supplementary to each other.	

Scanned by CamScanner

yoursmahboob.wordpress.com

Types of Angles	Property	Diagram
Vertically opposite	$\angle DOA = \angle BOC$ and $\angle DOB = \angle AOC$	
Adjacent angles	$\angle AOB$ and $\angle BOC$ are adjacent angles Adjacent angles must have a common side. (*e.g.*, OB)	
Linear pair	$\angle AOB$ and $\angle BOC$ are linear pair angles. One side must be common (*e.g.*, OB) and these two angles must be supplementary.	
Angles on the one side of a line	$\theta_1 + \theta_2 + \theta_3 = 180°$	
Angles round the point	$\theta_1 + \theta_2 + \theta_3 + \theta_4 = 360°$	
Angle bisector	OC is the angle bisector of $\angle AOB$. *i.e.*, $\angle AOC = \angle BOC = \frac{1}{2}(\angle AOB)$ When a line segment divides an angle equally into two parts, then it is said to be the angle bisector (OC)	 (Angle bisector is equidistant from the two sides of the angle) *i.e.*,  $AC = BC$
Corresponding angles	When two lines are intersected by a transversal, then they form four pairs of corresponding angles (a) $\angle AGE, \angle CHG \Rightarrow (\angle 2, \angle 6)$ (b) $\angle AGH, \angle CHF \Rightarrow (\angle 3, \angle 7)$ (c) $\angle EGB, \angle GHD \Rightarrow (\angle 1, \angle 5)$ (d) $\angle BGH, \angle DHF \Rightarrow (\angle 4, \angle 8)$	
Exterior angles	These are following four angles (i) $\angle AGE \Rightarrow \angle 2$ (ii) $\angle CHF \Rightarrow \angle 7$ (iii) $\angle EGB \Rightarrow \angle 1$ (iv) $\angle DHF \Rightarrow \angle 8$	

Scanned by CamScanner

yoursmahboob.wordpress.com

Types of Angles	Property	Diagram
Interior angles	These are following four angles (i) $\angle AGH \Rightarrow \angle 3$ (ii) $\angle GHC \Rightarrow \angle 6$ (iii) $\angle BGH \Rightarrow \angle 4$ (iv) $\angle DHG \Rightarrow \angle 5$	
Alternate angles	These are two pairs of angles as following : (i) $\angle AGH, \angle GHD$ $(\angle 3, \angle 5)$ (ii) $\angle GHC, \angle BGH$ $(\angle 6, \angle 4)$	

When two parallel lines are intersected by a transversal then



1. The pairs of corresponding angles so formed are congruent.

i.e., $\angle 2 = \angle 6$

$\angle 3 = \angle 7$

$\angle 1 = \angle 5$

$\angle 4 = \angle 8$

NOTE If one pair of corresponding angles is congruent, then the rest pairs of corresponding angles are also congruent.

2. The pairs of alternate angles so formed are congruent

i.e., $\angle 3 = \angle 5$ and $\angle 4 = \angle 6$

3. The pair of interior angles (*i.e.,* the interior angles on the same side of a transversal) are supplementary.

NOTE The converse of all the 3 rules is also true *i.e.,* if the pair of corresponding angles, or alternate angles or interior angles is equal (*i.e.,* congruent) then the two line are parallel which are intersected by a transversal.

INTRODUCTORY EXERCISE-12.1

1. What is the value of x in the adjoining figure?



(a) 80
(b) 40
(c) 20
(d) 25

2. What is the value of x in the adjoining figure ?



(a) 18°
(b) 20°
(c) 21°
(d) 24°

3. In the following figure AB is a straight line. Find $(x + y)$:



(a) 55°
(b) 65°
(c) 75°
(d) 80°

4. In the following figure $\angle BOP = 2x°$, $\angle AOP = 2y°$, OC and OD are angle bisectors of $\angle BOP$ and $\angle AOP$ respectively. Find the value of $\angle COD$:



(a) 75°
(b) 90°
(c) 100°
(d) 120°

5. In the following figure find the value of $\angle BOC$:



(a) 101°
(b) 149°
(c) 71°
(d) 140°

6. Find y, if $x° = 36°$, as per the given diagram :



(a) 36°
(b) 16°
(c) 12°
(d) 42°

7. If $(2x + 17)°$, $(x + 4)°$ are complementary, find x:
(a) 63°
(b) 53°
(c) 35°
(d) 23°

8. If $(5y + 62)°$, $(22° \div y)$ are supplementary, find y:
(a) 16°
(b) 32°
(c) 8°
(d) 1°

Scanned by CamScanner

yoursmahboob.wordpress.com

9. If two supplementary angles are in the ratio 13 : 5 find the greater angle :
(a) 130° (b) 65°
(c) 230° (d) 28°

10. An angle is 30° more than one half of its complement, Find the angle in degrees :
(a) 60° (b) 50°
(c) 45° (d) 80°

11. In the given diagram $AB \parallel GH \parallel DE$ and $GF \parallel BD \parallel HI$, $\angle FGC = 80°$. Find the value of $\angle CHI$:
(a) 80°
(b) 120°
(c) 100°
(d) 160°



12. In the given figure $AB \parallel CD \parallel EF \parallel GH$ and $BH = 100$ cm. Find the value of DF :



(a) 26 cm (b) 40 cm
(c) 25 cm (d) 24 cm

13. The complement of 65°50′ is :
(a) 24° 50′ (b) 24°10′
(c) 14° 50′ (d) 34° 10′

14. The supplement of 123° 45′ is :
(a) 56° 55′ (b) 56° 15′
(c) 55° 56′ (d) none of these

15. If two angles are complementary of each other, then each angle is :
(a) a right angle
(b) a supplementary angle
(c) an obtuse angle
(d) an acute angle

16. How many degrees are there in an angle which equals one-fifth of its supplement?
(a) 15° (b) 30°
(c) 75° (d) 150°

17. In the given figure, $\angle a$ is greater than one sixth of right angle, then :
(a) $b > 165°$
(b) $b < 165°$
(c) $b \leq 165°$
(d) $b \geq 165°$



18. Let D be the mid-point of a straight line AB and let C be a point different from D such that $AC = BC$, then :
(a) $AC \perp AB$ (b) $\angle BDC = 90°$
(c) $\angle BDC$ is acute (d) $\angle BDC > 90°$

19. Answer on the basis of the following statements :
When two straight lines intersect, then :
1. adjacent angles are complementary
2. adjacent angles are supplementary
3. opposite angles are equal
4. opposite angles are supplementary
(a) 2 and 3 are correct (b) 1 and 4 are correct
(c) 1 and 3 are correct (d) 2 and 4 are correct

20. AB is a straight line and O is a point on AB, if a line OC is drawn not coinciding with OA or OB, then $\angle AOC$ and $\angle BOC$ are :
(a) equal (b) complementary
(c) supplementary (d) together equal to 100

21. In the adjoining figure $AE \parallel CD$ and $BC \parallel ED$, then find Y :
(a) 60°
(b) 80°
(c) 90°
(d) 75°



22. In the adjoining figure $\angle APO = 42°$ and $\angle CQO = 38°$. Find the value of $\angle POQ$:
(a) 68°
(b) 72°
(c) 80°
(d) 126°



23. In a ΔABC, a line XY parallel to BC intersects AB at X and AC at Y :
If BY bisects $\angle XYC$, then $m\angle CBY : m\angle CYB$ is :
(a) 5 : 4
(b) 4 : 5
(c) 1 : 1
(d) 6 : 5



24. In the adjoining figure $AB \parallel CD$ and PQ, QR intersects AB and CD both at E, F and G, H respectively. Given that $m\angle PEB = 80°$, $m\angle QHD = 120°$ and $m\angle PQR = x°$, find the value of x :
(a) 40° (b) 20°
(c) 100° (d) 30°



25. In the following figure, find the value of y :
(a) 70°
(b) 60°
(c) 50°
(d) 80°



26. In the adjoining figure $AB \parallel DE$, $\angle ABC = 67°$ and $\angle EDC = 23°$. Find $\angle BCD$:
(a) 90°
(b) 44°
(c) 46°
(d) none of the above



Scanned by CamScanner

yourshanboob.wordpress.com

27. In the given figure $AB \parallel DE$. Find $a° + b° - c°$:



(a) 160°
(b) 120°
(c) 180°
(d) 210°

28. In the given figure $AB \parallel CE$ and $BC \parallel FG$. Find the value of $x°$:



(a) 52°
(b) 32°
(c) 42°
(d) 36°

29. $AB \parallel CD$, shown in the figure. Find the value of x :



(a) 100°
(b) 90°
(c) 110°
(d) 140°

30. In the figure $PQ \parallel LM \parallel RS$. Find the value of $\angle LRS$:



(a) 30°
(b) 25°
(c) 35°
(d) 40°

31. In the figure $AB \parallel DC$ and $DE \parallel BF$. Find the value of x :



(a) 140°
(b) 155°
(c) 105°
(d) 115°

32. In the figure $AB \parallel CD$, $\angle ABE = 100$. Find $m\angle CDE$:



(a) 125°
(b) 55°
(c) 65°
(d) 75°

33. In the figure $AB \parallel CD$, find $x°$ (*i.e.*, $\angle CDF$) :



(a) 50°
(b) 90°
(c) 30°
(d) 70°

34. In the given figure $XY \parallel PQ$, find the value of x :



(a) 70°
(b) 40°
(c) 75°
(d) 15°

35. In the given figure $AB \parallel CD$ and $EF \parallel DQ$. Find the value of $\angle DEF$:



(a) 68°
(b) 78°
(c) 34°
(d) 39°

36. In the given figure $AB \parallel CD \parallel EF$ and $GH \parallel KL$. Find $m\angle HKL$:



(a) 85°
(b) 145°
(c) 120°
(d) 95°

37. Which one of the following statements is false?
(a) Two straight lines can intersect at only one point.
(b) Through a given point, only one straight line can be drawn.
(c) A line segment can be produced to any desired length.
(d) Through two given points, it is possible to draw one and only one straight line.

38. $AB \parallel CD$. $\angle ABO = 118°$, $\angle BOD = 152°$, find $\angle ODC$:



(a) 70°
(b) 80°
(c) 90°
(d) 34°

39. Two parallel lines AB and CD are intersected by a transversal EF at M and N respectively. The lines MP and NP are the bisectors of interior angles $\angle BMN$ and $\angle DNM$ on the same side of the transversal. Then $\angle MPN$ is equal to :
(a) 60°
(b) 90°
(c) 45°
(d) 120°

40. If the arms of one angle are respectively parallel to the arms of another angle, then the two angles are :
(a) either equal or supplementary
(b) neither equal not supplementary
(c) equal but not supplementary
(d) not equal but supplementary

Scanned by CamScanner

yoursmahboob.wordpress.com

41. AB and CD are two parallel lines. PQ cuts AB and CD at E and F respectively. EL is the bisector of $\angle BEF$. If $\angle LEB = 35°$ then $\angle CFQ$ will be :
(a) 70° (b) 55°
(c) 110° (d) 125°

42. A plane figure is bounded by straight lines only. If n is the number of these lines, then the least value of n is :
(a) 1 (b) 2
(c) 3 (d) 4

43. How many planes can pass through any three arbitrary points?
(a) 1 (b) 2
(c) 3 (d) 0

44. Out of the four arbitrary non-collinear points three points are taken at a time, then the number of planes that can be drawn through the three points is :
(a) 3 (b) 4
(c) 6 (d) 12

45. Maximum number of points of intersection of four lines on a plane is :
(a) 4 (b) 6
(c) 8 (d) 5

(2) TRIANGLES

Triangle : A three sided closed plane figure, which is formed by joining the three non-collinear points, is called as a triangle. It is denoted by the symbol Δ.



In the above Δ (triangle) ABC, A, B and C are three vertices, line segments AB, BC and AC are the three sides of the triangle. $\angle A$, $\angle B$ and $\angle C$ are the three **interior angles** of a triangle ABC.

In the adjoining figure $\angle FCB$, $\angle CBE$, $\angle ABD$, $\angle IAB$, $\angle HAC$, $\angle GCA$ are the **exterior angles** of the ΔABC.



- Sum of the three interior angles of a triangle is always 180°.
- Exterior angle = Sum of two interior opposite angles
  e.g., $\angle CBE = \angle CAB + \angle BCA$

Perimeter of triangle is equal to sum of all the three sides
i.e., $a + b + c$

Semiperimeter of a triangle is half of the perimeter
i.e., $s = \frac{a+b+c}{2}$, a, b, c are the length of three sides of a triangle.

Types of Triangles

(A) According to interior angles

Types of Triangles	Property/Definition	Diagram
Acute angle triangle	Each of the angle of a triangle is less than 90° *i.e.,* $a < 90°$, $b < 90°$, $c < 90°$	 $\{\angle a, \angle b, \angle c\} < 90°$
Right angled triangle	One of the angle is equal to 90°, then it is called as right angled triangle. Rest two angles are complementary to each other.	 $\angle C = 90°$
Obtuse angle triangle	One of the angle is obtuse (*i.e.,* greater than 90°), then it is called as obtuse angle triangle.	 $\angle C > 90°$

Scanned by CamScanner

yoursmahboob.wordpress.com

(B) According to the length of sides.

Types of triangles	Property/Definition	Diagram
Scalene triangle	A triangle in which none of the three sides is equal is called a scalene triangle (all the three angles are also different).	 $a \neq b \neq c$
Isosceles triangle	A triangles in which at least two sides are equal is called as isosceles triangle. In this triangle, the angles opposite to the congruent sides are also equal.	 $AB = AC$ $\angle B = \angle C$
Equilateral triangle	A triangle in which all the three sides are equal is called as, an equilateral triangle. In this triangle each angle is congruent and equal to 60°.	 $AB = BC = AC$ $\angle A = \angle B = \angle C = 60°$

FUNDAMENTAL PROPERTIES OF TRIANGLES

1. Sum of any two sides is always greater than the third side.
2. The difference of any two sides is always less than the third side.
3. Greater angle has a greater side opposite to it and smaller angle has a smaller side opposite to it *i.e.*, if two sides of a triangle are not congruent then the angle opposite to the greater side is greater.
4. Let a, b and c be the three sides of a ΔABC and c is the largest side. Then



(i) if $c^2 < a^2 + b^2$, the triangle is **acute angle triangle**

(ii) if $c^2 = a^2 + b^2$, the triangle is **right angled triangle**

(iii) if $c^2 > a^2 + b^2$, the triangle is **obtuse angle triangle**

5. **Sine rule :** In a ΔABC, if a, b, c be the three sides opposite to the angles A, B, C respectively, then

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C}$$



6. **Cosine rule :** In a ΔABC, if a, b, c be the sides opposite to angle A, B and C respectively, then

$$\cos A = \frac{b^2 + c^2 - a^2}{2bc},$$

$$\cos B = \frac{c^2 + a^2 - b^2}{2ca}$$

$$\cos C = \frac{a^2 + b^2 - c^2}{2ab}.$$

(These rules have been discussed already in trigonometry.)

7. The sum of all the three interior angles is always 180°

i.e., $\angle CAB + \angle ABC + \angle BCA = 180°$



Scanned by CamScanner

yoursmahboob.wordpress.com

8. The sum of three (ordered) exterior angles of a triangle is 360°



Fig. (i) Fig. (ii)

In fig. (i) : $(\angle FAC + \angle ECB + \angle DBA) = 360°$
In fig. (ii) : $(\angle FAB + \angle DBC + \angle ECA) = 360°$

9. The sum of an interior angle and its adjacent exterior angle is 180°.
10. A triangle must has at least two acute angles.
11. In a triangle, the measure of an exterior angle equals the sum of the measures of the interior opposite angles.
12. The measure of an exterior angle of a triangle is greater than the measure of each of the opposite interior angles.

Some Important Definitions

Nomenclature	Property/Definition	Diagram
Altitude (or height)	The perpendicular drawn from the opposite vertex of a side in a triangle is called an altitude of the triangle. ➢ There are three altitudes in a triangle.	 AE, CD and BF are the altitudes
Median	The line segment joining the mid-point of a side to the vertex opposite to the side is called a median. ➢ There are three medians in a triangle. ➢ A median bisects the area of the triangle *i.e.*, $A(ABE) = A(AEC) = \frac{1}{2} A(\Delta ABC)$ etc.	 AE, CD and BF are the medians $(BE = CE, AD = BD, AF = CF)$
Angle bisector	A line segment which originates from a vertex and bisects the same angle is called an angle bisector. $\left(\angle BAE = \angle CAE = \frac{1}{2} \angle BAC\right)$ etc.	 AE, CD and BF are the angle bisectors.
Perpendicular bisector	A line segment which bisects a side perpendicularly (i.e, at right angle) is called a perpendicular bisector of a side of triangle. ➢ All points on the perpendicular bisector of a line are equidistant from the ends of the line.	 DO, EO and FO are the perpendicular bisectors.
Orthocentre	The point of intersection of the three altitudes of the triangle is called as the orthocentre. $\angle BOC = 180 - \angle A$ $\angle COA = 180 - \angle B$ $\angle AOB = 180 - \angle C$	 'O' is the orthocentre

Scanned by CamScanner

yoursmahboob.wordpress.com

Types of Triangles	Property/Definition	Diagram
Centroid	The point of intersection of the three medians of a triangle is called the centroid. A centroid divides each median in the ratio 2 : 1 (vertex : base) $\frac{AO}{OE}=\frac{CO}{OD}=\frac{BO}{OF}=\frac{2}{1}$	 'O' is the centroid.
Incentre	The point of intersection of the angle bisectors of a triangle is called the incentre. Incentre O is the always equidistant from all three sides *i.e.*, the perpendicular distance between the sides and incentre is always same for all the three sides.	 'O' is the incentre.
Circumcentre	The point of intersection of the perpendicular bisectors of the sides of a triangle is called the circumcentre. $OA = OB = OC$ = (circum radius) Circumcentre O is always equidistant from all the three vertices A, B and C.	 'O' is the circumcentre.

Important Theorems on Triangles

Theorem	Statement/Explanation	Diagram
Pythagoras theorem	The square of the hypotenuse of a right angled triangle is equal to the sum of the squares of the other two sides. *i.e.*, $(AC)^2 = (AB)^2 + (BC)^2$ ➢ The converse of this theorem is also true. ➢ The numbers which satisfy this relation, are called Pythagorean triplets. *e.g.*, (3, 4, 5), (5, 12, 13), (7, 24, 25), (8, 15, 17), (9, 40, 41), (11, 60, 61), (12, 35, 37), (16, 63, 65), (20, 21, 29), (28, 45, 53), (33, 56, 65) **Note :** All the multiples (or submultiples) of Pythagorean triplets also satisfy the relation. *e.g.*, (6, 8,10), (15,36, 39), (1.5, 2, 2.5) etc	 $\angle B = 90°$ $\overline{AC}$ → Hypotenuse $AD = CD = BD$ (D is the mid-point of AC)
$45° - 45° - 90°$ triangle theorem	If the angles of a triangle are 45°, 45° and 90°, then the hypotenuse (*i.e.*, longest side) is $\sqrt{2}$ times of any smaller side. ➢ Excluding hypotenuse rest two sides are equal. *i.e.*, $AB = BC$ and $AC = \sqrt{2}AB = \sqrt{2}BC$	 $\angle A = 45°$ $\angle B = 90°$ $\angle C = 45°$

Scanned by CamScanner

yoursmahboob.wordpress.com

Theorem	Statement/Explanation	Diagram
$30°-60°-90°$ triangle theorem	If the angles of a triangle are 30°, 60° and 90°, then the sides opposite to 30° angle is half of the hypotenuse and the side opposite to 60° is $\frac{\sqrt{3}}{2}$ times the hypotenuse. *e.g.*, $AB = \frac{AC}{2}$ and $BC = \frac{\sqrt{3}}{2}AC$ $\therefore AB : BC : AC = 1 : \sqrt{3} : 2$	
Basic proportionality theorem (BPT) or Thales theorem	Any line parallel to one side of a triangle divides the other two sides proportionally. So if DE is drawn parallel to BC, it would divide sides AB and AC proportionally *i.e.*, $\frac{AD}{DB} = \frac{AE}{EC}$ or $\frac{AD}{AB} = \frac{AE}{AC}$ $\frac{AD}{DE} = \frac{AB}{BC} = \frac{AE}{DE} = \frac{AC}{BC}$	
Mid-point theorem	If the mid-points of two adjacent sides of a triangle are joined by a line segment, then this segment is parallel to the third side. *i.e.*, if $AD = BD$ and $AE = CE$ then $DE \parallel BC$	
Apollonius theorem	In a triangle, the sum of the squares of any two sides of a triangle is equal to twice the sum of the square of the median to the third side and square of half the third side. *i.e.*, $AB^2 + AC^2 = 2(AD^2 + BD^2)$	
Interior angle bisector theorem	In a triangle the angle bisector of an angle divides the opposite side to the angle in the ratio of the remaining two sides. *i.e.*, $\frac{BD}{CD} = \frac{AB}{AC}$ and $BD \times AC - CD \times AB = AD^2$	
Exterior angle bisector theorem	In a triangle the angle bisector of any exterior angle of a triangle divides the side opposite to the external angle in the ratio of the remaining two sides *i.e.*, $\frac{BE}{AE} = \frac{BC}{AC}$	

Scanned by CamScanner

yoursmahboob.wordpress.com

SOME USEFUL RESULTS

1. In a ΔABC, if the bisectors of $\angle B$ and $\angle C$ meet at O then
$\angle BOC = 90° + \frac{1}{2}\angle A$



2. In a ΔABC, if sides AB and AC are produced to D and E respectively and the bisectors of $\angle DBC$ and $\angle ECB$ interseect at O, then



$\angle BOC = 90° - \frac{1}{2}\angle A$

3. In a ΔABC, if AD is the angle bisector of $\angle BAC$ and $AE \perp BC$, then $\angle DAE = \frac{1}{2}(\angle ABC - \angle ACB)$



4. In a ΔABC, if BC is produced to D and AE is the angle bisector of $\angle A$, then



$\angle ABC + \angle ACD = 2\angle AEC.$

5. In a ΔABC, if side BC is produced to D and bisectors



of $\angle ABC$ and $\angle ACD$ meet at E, then

$$\angle BEC = \frac{1}{2}\angle BAC$$

6. In an acute angle ΔABC, AD is a perpendicular dropped on the opposite side of $\angle A$, then



$AC^2 = AB^2 + BC^2 - 2BD \cdot BC \quad (\angle B < 90°)$

7. In an obtuse angle ΔABC, AD is perpendicular dropped on BC. BC is produced to D to meet AD, then



$AC^2 = AB^2 + BC^2 + 2BD \cdot BC \quad (\angle B > 90°)$

8. In a right angle ΔABC, $\angle B = 90°$ and AC is hypotenuse. The perpendicular BD is dropped on hypotenuse AC from right angle vertex B, then



(i) $BD = \frac{AB \times BC}{AC}$ (ii) $AD = \frac{AB^2}{AC}$

(iii) $CD = \frac{BC^2}{AC}$ (iv) $\frac{1}{BD^2} = \frac{1}{AB^2} + \frac{1}{BC^2}$

- In a right angled triangle, the median to the hypotenuse $= \frac{1}{2} \times$ hypotenuse

i.e., $BN = \frac{AC}{2}$ (as per the fig.)



9. **Area of a triangle (General formula)**



$A(\Delta) = \frac{1}{2} \times$ base $\times$ height

$A(\Delta) = \frac{1}{2} \times BC \times AD$ (as per the figure.)

10. **Area of scalene triangle** $= \sqrt{s(s-a)(s-b)(s-c)}$



Scanned by CamScanner

yoursmahboob.wordpress.com

Also, $A(\Delta) = r \times s = \frac{abc}{4R}$

where a, b and c are the sides of the triangle.

$s \rightarrow$ semiperimeter $= \frac{a+b+c}{2}$

$r \rightarrow$ inradius

$R \rightarrow$ circumradius

11. Area of right angled triangle

$= \frac{1}{2} \times$ base $\times$ height

$= \frac{1}{2} \times BC \times AB$

(as per the figure)



12. Area of an isosceles triangle

$= \frac{b}{4}\sqrt{4a^2 - b^2}$

$AB = AC$

and $\angle B = \angle C$

$\Delta ABD \cong \Delta ACD$

($AD \rightarrow$ Angle bisector, median, altitude and perpendicular bisector)



13. Area of an equilateral triangle

$= \frac{\sqrt{3}}{4} a^2$

$\left[A(\Delta) = \frac{1}{2} BC \times AD \right.$

$\left. = \frac{1}{2} \times a \times \frac{\sqrt{3}}{2} a = \frac{\sqrt{3}}{4} a^2 \right]$



($a \rightarrow$ each side of the triangle)

$AD \rightarrow$ Altitude, median, angle bisector and perpendicular bisector also.

Inradius : $\frac{1}{3} \times$ height $= \frac{\text{side}}{2\sqrt{3}}$, $OD \rightarrow$ Inradius





Circumradius $= \frac{2}{3} \times$ height $= \frac{\text{side}}{\sqrt{3}}$

$OA \rightarrow$ Circumradius

NOTE In equilateral triangle orthocentre centroid, incentre and circumcentre coincide at the same point.

- Circumradius $= 2 \times$ inradius
- For the given perimeter of a triangle, the area of equilateral triangle is maximum.
- For the given area of a triangle, the perimeter of equilateral triangle is minimum.

14. In a right angled triangle

(i) Inradius $(r) = \frac{AB + BC - AC}{2}$

(ii) Inradius $(r) = \frac{\text{Area}}{\text{Semiperimeter}}$



$DO = EO = FO\ (r)$

(iii) Circumradius $(R) = \frac{AC}{2} = \left(\frac{\text{hypotenuse}}{2}\right)$



$AO = CO = BO = (R)$

AC is the diameter.

15. The ratio of areas of two triangles of equal heights is equal to the ratio of their corresponding bases. *i.e.,*



$$\frac{A(\Delta ABC)}{A(\Delta PQR)} = \frac{AC}{PR}$$

16. The ratio of areas of triangles of equal bases is equal to the ratio of their heights.



i.e., $\frac{A(\Delta ABC)}{A(\Delta PQR)} = \frac{BD}{RS}$

17. The ratio of the areas of two triangles is equal to the



Scanned by CamScanner

yoursmahboob.wordpress.com

ratio of the products of base and its corresponding height *i.e.*,

$$\frac{A(\Delta ABC)}{A(\Delta PQR)} = \frac{AC \times BD}{PR \times QS}$$

18. If the two triangles have the same base and lie between the same parallel lines (as shown in figure), then the area of two triangles will be equal.



i.e., $A(\Delta ABC) = A(\Delta ADB)$

19. In a triangle AE, CD and BF are the medians then



$$3(AB^2 + BC^2 + AC^2) = 4(CD^2 + BF^2 + AE^2)$$

Congruency of triangles : Two triangles are said to be congruent if they are equal in all respects. *i.e.*,

1. Each of the three sides of one triangle must be equal to the three respective sides of the other.
2. Each of the three angles of the one triangle must be equal to the three respective angles of the other.



i.e., $\left.\begin{matrix} AB = PQ \\ AC = PR \\ BC = QR \end{matrix}\right\}$ and $\left.\begin{matrix} \angle A = \angle P \\ \angle B = \angle Q \\ \angle C = \angle R \end{matrix}\right\}$

Tests of congruency : With the help of the following given tests, we can deduce without having detailed information about triangles that whether the given two triangles are congruent or not.

Test	Property	Diagram
$S-S-S$	(Side–Side–Side) If the three sides of one triangle are equal to the corresponding three sides of the other triangle, then the two triangles are congruent. $AB \cong PQ,\ AC \cong PR,\ BC \cong QR$ $\therefore\ \Delta ABC \cong \Delta PQR$	
$S-A-S$	(Side–Angle–Side) If two sides and the angle included between them are congruent to the corresponding sides and the angle included between them, of the other triangle then the two triangles are congruent. $AB \cong PQ,\ \angle ABC \cong \angle PQR,\ BC \cong QR$ $\therefore\ \Delta ABC \cong \Delta PQR$	
$A-S-A$	(Angle–Side–Angle) If two angles and the included side of a triangle are congruent to the corresponding angles and the included side of the other triangle, then the two triangles are congruent. $\angle ABC \cong \angle PQR,\ BC \cong QR,\ \angle ACB \cong \angle PRQ$ $\therefore\ \Delta ABC \cong \Delta PQR$	
$A-A-S$	(Angle–Angle–Side) If two angles and a side other than the included side of a one triangle are congruent to the corresponding angles and a corresponding side other than the included side of the other triangle, then the two triangles are congruent. $\angle ABC \cong \angle PQR,\ \angle ACB \cong \angle PRQ$ and $AC \cong PR$ (or $AB \cong PQ$)	

Scanned by CamScanner

yoursmahboob.wordpress.com

Test	Property	Diagram
R—H—S	(Right angle–Hypotenuse–Side) If the hypotenuse and one side of the right angled triangle are congruent to the hypotenuse and a corresponding side of the other right angled triangle, then the two given triangles are congruent. $AC \cong PR$, $\angle B = \angle Q$ and $BC \cong QR$ $\therefore \Delta ABC \cong \Delta PQR$	

Similarity of triangles : Two triangles are said to be similar if the corresponding **angles** are **congruent** and their corresponding **sides** are in **proportion**. The symbol for similarity is '~'.



If $\Delta ABC \sim \Delta PQR$ then

$\angle ABC \cong \angle PQR$, $\angle BCA \cong \angle QRP$, $\angle BAC \cong \angle QPR$

Tests for Similarity : Through the tests for similarity we can deduce the similarity of triangles with minimum required information.

Test	Property/Definition	Diagram
A – A	Angle-Angle If the two angles of one triangle are congruent to the corresponding two angles of the other triangle, then the two triangles are said to be similar $\angle ABC \cong \angle PQR$ $\angle ACB \cong \angle PRQ$ $\therefore \quad \Delta ABC \sim \Delta PQR$	
S-A-S	Side-Angle-Side If the two sides of one triangle are proportional to the corresponding two sides of the other triangle and the angle included by them are congruent, then the two triangles are similar. *i.e.,* $\frac{AB}{PQ} = \frac{BC}{QR}$ and $\angle ABC = \angle PQR$ $\therefore \quad \Delta ABC \sim \Delta PQR.$	 $\frac{AB}{PQ} = \frac{BC}{QR} = K$ (K is any constant)
S-S-S	Side-Side-Side If the three sides of one triangle are proportional to the corresponding three sides of the other triangle, then the two triangles are similar. *i.e.,* $\frac{AB}{PQ} = \frac{BC}{QR} = \frac{AC}{PR}$ $\therefore \quad \Delta ABC \sim \Delta PQR$	 $\frac{AB}{PQ} = \frac{BC}{QR} = \frac{AC}{PR} = K$

NOTE When the corresponding sides are in proportion , then the corresponding angles are in proportion.

PROPERTIES OF SIMILAR TRIANGLES

If the two triangles are similar, then for the proportional/corresponding sides we have the following results.



1. Ratio of sides = Ratio of heights (altitudes)
   = Ratio of medians
   = Ratio of angle bisectors
   = Ratio of inradii
   = Ratio of circumradii
2. Ratio of areas = Ratio of squares of corresponding sides.

i.e., if $\Delta ABC \sim \Delta PQR$, then

$$\frac{A(\Delta ABC)}{A(\Delta PQR)} = \frac{(AB)^2}{(PQ)^2} = \frac{(BC)^2}{(QR)^2} = \frac{(AC)^2}{(PR)^2}$$

NOTE Rule 1 can also apply with rule 2.

Scanned by CamScanner

yoursmahboob.wordpress.com

3. In a right angled triangle, the triangles on each side of the altitude drawn from the vertex of the right angle to the hypotenuse are similar to the original triangle and to each other too.

i.e., $\Delta BCA \sim \Delta BDC \sim \Delta CDA$.



INTRODUCTORY EXERCISE-12.2

1. In a triangle ABC, if AB, BC and AC are the three sides of the triangle, then which of the statements is necessarily true?
   (a) $AB + BC < AC$ (b) $AB + BC > AC$
   (c) $AB + BC = AC$ (d) $AB^2 + BC^2 = AC^2$

2. The sides of a triangle are 12 cm, 8 cm and 6 cm respectively, the triangle is :
   (a) acute (b) obtuse
   (c) right (d) can't be determined

3. If the sides of a triangle are produced then the sum of the exterior angles *i.e.*, $\angle DAB + \angle EBC + \angle FCA$ is equal to :
   (a) 180°
   (b) 270°
   (c) 360°
   (d) 240°



4. In the given figure BC is produced to D and $\angle BAC = 40°$ and $\angle ABC = 70°$. Find the value of $\angle ACD$:
   (a) 30°
   (b) 40°
   (c) 70°
   (d) 110°



5. In a ΔABC, $\angle BAC > 90°$, then $\angle ABC$ and $\angle ACB$ must be :
   (a) acute
   (b) obtuse
   (c) one acute and one obtuse
   (d) can't be determined



6. If the angles of a triangle are in the ratio 1 : 4 : 7, then the value of the largest angle is :
   (a) 135° (b) 84°
   (c) 105° (d) none of these

7. In the adjoining figure $\angle B = 70°$ and $\angle C = 30°$. BO and CO are the angle bisectors of $\angle ABC$ and $\angle ACB$. Find the value of $\angle BOC$:
   (a) 30° (b) 40°
   (c) 120° (d) 130°



8. In the given diagram of ΔABC, $\angle B = 80°$, $\angle C = 30°$. BF and CF are the angle bisectors of $\angle CBD$ and $\angle BCE$ respectively. Find the value of $\angle BFC$:
   (a) 110° (b) 50°
   (c) 125° (d) 55°



9. In an equilateral triangle, the incentre, circumcentre, orthocentre and centroid are :
   (a) concylic (b) coincident
   (c) collinear (d) none of these

10. In the adjoining figure D is the midpoint of BC of a ΔABC. DM and DN are the perpendiculars on AB and AC respectively and $DM = DN$, then the ΔABC is :
    (a) right angled (b) isosceles
    (c) equilateral (d) scalene



11. In the adjoining figure of ΔABC, AD is the perpendicular bisector of side BC. The triangle ABC is :
    (a) right angled
    (b) isosceles
    (c) scalene
    (d) equilateral



12. Triangle ABC is such that $AB = 9$ cm, $BC = 6$ cm, $AC = 7.5$ cm. Triangle DEF is similar to ΔABC. If $EF = 12$ cm then DE is :
    (a) 6 cm (b) 16 cm
    (c) 18 cm (d) 15 cm

13. In ΔABC, $AB = 5$ cm, $AC = 7$ cm. If AD is the angle bisector of $\angle A$. Then $BD : CD$ is :
    (a) 25 : 49 (b) 49 : 25
    (c) 6 : 1 (d) 5 : 7

14. In a ΔABC, D is the mid-point of BC and E is mid-point of AD, BF passes through E. What is the ratio of $AF : FC$?
    (a) 1 : 1
    (b) 1 : 2
    (c) 1 : 3
    (d) 2 : 3



15. In a ΔABC, $AB = AC$ and $AD \perp BC$, then :
    (a) $AB < AD$ (b) $AB > AD$
    (c) $AB = AD$ (d) $AB \leq AD$

16. The difference between altitude and base of a right angled triangle is 17 cm and its hypotenuse is 25 cm. What is the sum of the base and altitude of the triangle is :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 24 cm (b) 31 cm
(c) 34 cm (d) can't be determined

17. If AB, BC and AC be the three sides of a triangle ABC, then which one of the following is true?
(a) $AB - BC = AC$ (b) $(AB - BC) > AC$
(c) $(AB - BA) < AC$ (d) $AB^2 - BC^2 = AC^2$

18. In the triangle ABC, side BC is produced to D. $\angle ACD = 100°$ if $BC = AC$, then $\angle ABC$ is :


(a) 40°
(b) 50°
(c) 80°
(d) can't be determined

19. In the adjoining figure D, E and F are the mid-points of the sides BC, AC and AB respectively. ΔDEF is congruent to triangle :


(a) ABC
(b) AEF
(c) CDE, BFD
(d) AFE, BFD and CDE

20. In the adjoining figure $\angle BAC = 60°$ and $BC = a$, $AC = b$ and $AB = c$, then :


(a) $a^2 = b^2 + c^2$
(b) $a^2 = b^2 + c^2 - bc$
(c) $a^2 = b^2 + c^2 + bc$
(d) $a^2 = b^2 + 2bc$

21. In the adjoining figure of ΔABC, $\angle BCA = 120°$ and $AB = c$, $BC = a$, $AC = b$ then:


(a) $c^2 = a^2 + b^2 + ba$
(b) $c^2 = a^2 + b^2 - ba$
(c) $c^2 = a^2 + b^2 - 2ba$
(d) $c^2 = a^2 + b^2 + 2ab$

22. In a right angled ΔABC, $\angle C = 90°$ and CD is the perpendicular on the hypotenuse AB, $AB = c$, $BC = a$, $AC = b$ and $CD = p$, then :


(a) $\frac{p}{a} = \frac{p}{b}$
(b) $\frac{1}{p^2} + \frac{1}{b^2} = \frac{1}{a^2}$
(c) $p^2 = b^2 + c^2$
(d) $\frac{1}{p^2} = \frac{1}{a^2} + \frac{1}{b^2}$

23. If the medians of a triangle are equal, then the triangle is :
(a) right angled (b) isosceles
(c) equilateral (d) scalene

24. The incentre of a triangle is determined by the :
(a) medians
(b) angle bisector
(c) perpendicular bisectors
(d) altitudes

25. The circumcentre of a triangle is determined by the :
(a) altitudes
(b) median
(c) perpendicular bisector
(d) angle bisectors

26. The point of intersection of the angle bisectors of a triangle is :
(a) orthocentre (b) centroid
(c) incentre (d) circumcentre

27. A triangle PQR is formed by joining the mid-points of the sides of a triangle ABC. 'O' is the circumcentre of ΔABC, then for ΔPQR, the point 'O' is :
(a) incentre (b) circumcentre
(c) orthocentre (d) centroid

28. If in a ΔABC, 'S' is the circumcentre then :
(a) S is equidistant from all the vertices of a triangle
(b) S is equidistant from all the sides of a triangle
(c) AS, BS and CS are the angular bisectors
(d) AS, BS and CS produced are the altitudes on the opposite sides.

29. If AD, BE, CF are the altitudes of ΔABC whose orthocentre is H, then C is the orthocentre of :
(a) ΔABH (b) ΔBDH
(c) ΔABD (d) ΔBEA

30. In a right angled ΔABC, $\angle C = 90°$ and CD is the perpendicular on hypotenuse AB if $BC = 15$ cm and $AC = 20$ cm then CD is equal to :


(a) 18 cm (b) 12 cm
(c) 17.5 cm (d) can't be determined

31. In an equilateral ΔABC, if a, b and c denote the lengths of perpendiculars from A, B and C respectively on the opposite sides, then :
(a) $a > b > c$ (b) $a > b < c$
(c) $a = b = c$ (d) $a = c \neq b$

32. What is the ratio of side and height of an equilateral triangle?
(a) 2 : 1 (b) 1 : 1
(c) $2 : \sqrt{3}$ (d) $\sqrt{3} : 2$

33. The triangle is formed by joining the mid-points of the sides AB, BC and CA of ΔABC and the area of ΔPQR is 6 cm^2, then the area of ΔABC is :
(a) 36 cm^2 (b) 12 cm^2
(c) 18 cm^2 (d) 24 cm^2

34. One side other than the hypotenuse of right angle isosceles triangle is 6 cm. The length of the perpendicular on the hypotenuse from the opposite vertex is :
(a) 6 cm (b) $6\sqrt{2}$ cm
(c) 4 cm (d) $3\sqrt{2}$ cm

35. Any two of the four triangles formed by joining the mid-points of the sides of a given triangle are :
(a) congruent

Scanned by CamScanner

yoursmahboob.wordpress.com

(b) equal in area but not congruent
(c) unequal in area and not congruent
(d) none of the above

36. The internal bisectors of $\angle B$ and $\angle C$ of ΔABC meet at O. If $\angle A = 80°$ then $\angle BOC$ is :
(a) 50° (b) 160°
(c) 100° (d) 130°

37. The point in the plane of a triangle which is at equal perpendicular distance from the sides of the triangle is :
(a) centroid (b) incentre
(c) circumcenre (d) orthocentre

38. Incentre of a triangle lies in the interior of :
(a) an isosceles triangle only
(b) a right angled triangle only
(c) any equilateral triangle only
(d) any triangle

39. In a triangle PQR, $PQ = 20$ cm and $PR = 6$ cm, the side QR is :
(a) equal to 14 cm (b) less than 14 cm
(c) greater than 14 cm (d) none of these

40. The four triangles formed by joining the pairs of mid-points of the sides of a given triangle are congruent if the given triangle is :
(a) an isosceles triangle
(b) an equilateral triangle
(c) a right angled triangle
(d) of any shape

41. O is orthocentre of a triangle PQR, which is formed by joining the mid-points of the sides of a ΔABC, O is :
(a) orthocentre (b) incentre
(c) circumcentre (d) centroid

42. In a ΔABC, a line PQ parallel to BC cuts AB at P and AC at Q. If BQ bisects $\angle PQC$, then which one of the following relation is always true :
(a) $BC = CQ$ (b) $BC = BQ$
(c) $BC \neq CQ$ (d) $BC \neq BQ$

43. Which of the following is true, in the given figure, where AD is the altitude to the hypotenuse of a right angled ΔABC?
(i) ΔCAD and ΔABD are similar
(ii) ΔCDA and ΔADB are congruent
(iii) ΔADB and ΔCAB are similar
Select the correct answer using the codes given below :
(a) 1 and 2 (b) 2 and 3
(c) 1 and 3 (d) 1, 2 and 3

44. If D is such a point on the side, BC of ΔABC that $\frac{AB}{AC} = \frac{BD}{CD}$, then AD must be a/an :
(a) altitude of ΔABC
(b) median of ΔABC
(c) angle bisector of ΔABC
(d) perpendicular bisector of ΔABC

45. In right angled ΔABC, $\angle B = 90°$, if P and Q are points on the sides AB and BC respectively, then :
(a) $AQ^2 + CP^2 = 2(AC^2 + PQ^2)$
(b) $AQ^2 + CP^2 = AC^2 + PQ^2$
(c) $(AQ^2 + CP^2) = \frac{1}{2}(AC^2 + PQ^2)$
(d) $(AQ + CP) = \frac{1}{2}(AC + PQ)$



46. If ABC is a right angled triangle at B and M, N are the mid-points of AB and BC, then $4(AN^2 + CM^2)$ is equal to:
(a) $4AC^2$ (b) $6AC^2$
(c) $5AC^2$ (d) $\frac{5}{4}AC^2$

47. If ΔABC and ΔDEF are so related that $\frac{AB}{FD} = \frac{BC}{DE} = \frac{CA}{EF}$, then which of the following is true ?
(a) $\angle A = \angle F$ and $\angle B = \angle D$
(b) $\angle C = \angle F$ and $\angle A = \angle D$
(c) $\angle B = \angle F$ and $\angle C = \angle D$
(d) $\angle A = \angle E$ and $\angle B = \angle D$

48. ABC is a right angle triangle at A and AD is perpendicular to the hypotenuse. Then $\frac{BD}{CD}$ is equal to :
(a) $\left(\frac{AB}{AC}\right)^2$ (b) $\left(\frac{AB}{AD}\right)^2$
(c) $\frac{AB}{AC}$ (d) $\frac{AB}{AD}$

49. Let ABC be an equilateral triangle. Let $BE \perp CA$ meeting CA at E, then $(AB^2 + BC^2 + CA^2)$ is equal to :
(a) $2BE^2$ (b) $3BE^2$
(c) $4BE^2$ (d) $6BE^2$

50. If D, E and F are respectively the mid-points of sides BC, CA and AB of a ΔABC. If $EF = 3$ cm, $FD = 4$ cm and $AB = 10$ cm, then DE, BC and CA respectively will be equal to :
(a) 6, 8 and 20 cm (b) 4, 6 and 8 cm
(c) 5, 6 and 8 cm (d) $\frac{10}{3}$, 9 and 12 cm

51. In the right angle triangle $\angle C = 90°$. AE and BD are two medians of a triangle ABC meeting at F. The ratio of the area of ΔABF and the quadrilateral $FDCE$ is :
(a) 1 : 1 (b) 1 : 2
(c) 2 : 1 (d) 2 : 3

52. ABC is a triangle and DE is drawn parallel to BC cutting the other sides at D and E. If $AB = 3.6$ cm, $AC = 2.4$ cm and $AD = 2.1$ cm, then AE is equal to :
(a) 1.4 cm (b) 1.8 cm
(c) 1.2 cm (d) 1.05 m

53. Consider the following statements :
(1) If three sides of a triangle are equal to three sides of another triangle, then the triangles are congruent.
(2) If three angles of a triangle are equal to three angles of another triangle respectively, then the two triangles are congruent. Of these statements :
(a) 1 is correct and 2 is false
(b) both 1 and 2 are false
(c) both 1 and 2 are correct
(d) 1 is false and 2 is correct

Scanned by CamScanner

yoursmahboob.wordpress.com

54. In the figure ΔABE is an equilateral triangle in a square $ABCD$. Find the value of angle x in degrees :



(a) 60°
(b) 45°
(c) 75°
(d) 90°

55. In the given diagram $MN \parallel PR$ and $m\angle LBN = 70°$, $AB = BC$. Find $m\angle ABC$:



(a) 40°
(b) 30°
(c) 35°
(d) 55°

56. In the given diagram, equilateral triangle EDC surmounts square $ABCD$. Find the $m\angle BED$ represented by x. Where $m\angle EBC = \alpha°$:



(a) 45°
(b) 60°
(c) 30°
(d) none of the above

57. In the given diagram $XY \parallel PQ$. Find $m\angle x°$ and $m\angle y°$:



(a) 75° and 40°
(b) 45°, 60°
(c) 75°, 45°
(d) 60° and 45°

58. In the adjoining figure $m\angle CAB = 62°$, $m\angle CBA = 76°$ $m\angle ADE = 58°$ and $\angle DFG = 66°$,



Find $m\angle FGE$:
(a) 44°
(b) 34°
(c) 36°
(d) none of these

59. In the given figure $CE \perp AB$, $m\angle ACE = 20°$ and $m\angle ABD = 50°$. Find $m\angle BDA$:



(a) 50°
(b) 60°
(c) 70°
(d) 80°

60. In the ΔABC, BD bisects $\angle B$, and is perpendicular to AC. If the lengths of the sides of the triangle are expressed in terms of x and y as shown, find the value of x and y :



(a) 6, 12
(b) 10, 12
(c) 16, 8
(d) 8, 15

61. In the following figure $ADBC$. $BD = CD = AC$, $m\angle ABC = 27°$, $m\angle ACD = y$. Find the value of y :



(a) 27°
(b) 54°
(c) 72°
(d) 58°

62. ABC is an isosceles triangle with $AB = AC$. Side BA is produced to D such that $AB = AD$. Find $m\angle BCD$:
(a) 60°
(b) 90°
(c) 120°
(d) can't be determined

63. In ΔABC, $AC = 5$ cm. Calculate the length of AE where $DE \parallel BC$. Given that $AD = 3$ cm and $BD = 7$ cm :



(a) 2 cm
(b) 1 cm
(c) 1.5 cm
(d) 2.5 cm

64. In ΔPQR, $AP = 2\sqrt{2}$ cm, $AQ = 3\sqrt{2}$ cm and $PR = 10$ cm, $AB \parallel QR$. Find the length of BR :



(a) $6\sqrt{2}$ cm
(b) 6 cm
(c) $5\sqrt{2}$ cm
(d) none of these

65. In the adjoining figure (not drawn to scale) AB, EF and CD are parallel lines. Given that $EG = 5$ cm, $GC = 10$ cm and $DC = 18$ cm. Calculate AC, if $AB = 15$ cm :



(a) 21 cm
(b) 25 cm
(c) 18 cm
(d) 28 cm

Scanned by CamScanner

yoursmahboob.wordpress.com

66. In the adjoining figure PA, QB and RC are each perpendicular to AC. Which one of the following is true :



(a) $x + y = z$ (b) $xy = 2z$

(c) $\frac{1}{x} + \frac{1}{y} = \frac{1}{z}$ (d) $\frac{1}{x} + \frac{1}{y} + \frac{1}{z} = 0$

67. In the adjoining figure the angle BAC and $\angle ADB$ are right angles.
$BA = 5$ cm, $AD = 3$ cm and $BD = 4$ cm, what is the length of DC ?



(a) 2.5
(b) 3
(c) 2.25
(d) 2

68. The areas of the similar triangles are in the ratio of 25 : 36. What is the ratio of their respective heights?

(a) 5 : 6 (b) 6 : 5

(c) 1 : 11 (d) 2 : 3

69. In the given diagram $AB \parallel CD$, then which one of the following is true ?



(a) $\frac{AB}{CD} = \frac{AO}{OC}$ (b) $\frac{AB}{CD} = \frac{BO}{OD}$

(c) $\Delta AOB \sim \Delta COD$ (d) all of these

70. The bisector of the exterior $\angle A$ of ΔABC intersects the side BC produced to D. Here CF is parallel to AD.



(a) $\frac{AB}{AC} = \frac{BD}{CD}$ (b) $\frac{AB}{AC} = \frac{CD}{BD}$

(c) $\frac{AB}{AC} = \frac{BC}{CD}$ (d) none of these

71. The diagonal BD of a quadrilateral $ABCD$ bisects $\angle B$ and $\angle D$, then :



(a) $\frac{AB}{CD} = \frac{AD}{BC}$ (b) $\frac{AB}{BC} = \frac{AD}{CD}$

(c) $AB = AD \times BC$ (d) none of these

72. Two right triangles ABC and DBC are drawn on the same hypotenuse BC on the same side of BC. If AC and DB intersects at P, then :



(a) $\frac{AP}{PC} = \frac{BP}{DP}$ (b) $AP \times DP = PC \times BP$

(c) $AP \times PC = BP \times DP$ (d) $AP \times BP = PC \times PD$

73. A man goes 150 m due east and then 200 m due north. How far is he from the starting point?

(a) 200 m (b) 350 m

(c) 250 m (d) 175 m

74. From a point O in the interior of a ΔABC perpendiculars OD, OE and OF are drawn to the sides BC, CA and AB respectively, then which one of the following is true ?

(a) $AF^2 + BD^2 + CE^2 = AE^2 + CD^2 + BF^2$

(b) $AB^2 + BC^2 = AC^2$

(c) $AF^2 + BD^2 + CE^2 = OA^2 + OB^2 + OC^2$

(d) $AF^2 + BD^2 + CE^2 = OD^2 + OE^2 + OF^2$

75. In an equilateral triangle ABC, the side BC is trisected at D. Find the value of AD^2 :



(a) $\frac{9}{7} AB^2$

(b) $\frac{7}{9} AB^2$

(c) $\frac{3}{4} AB^2$

(d) $\frac{4}{5} AB^2$

76. ABC is a triangle in which $\angle A = 90°$. $AN \perp BC$, $AC = 12$ cm and $AB = 5$ cm. Find the ratio of the areas of ΔANC and ΔANB :

(a) 125 : 44 (b) 25 : 144

(c) 144 : 25 (d) 12 : 5

77. A vertical stick 15 cm long casts it shadow 10 cm long on the ground. At the same time a flag pole casts a shadow 60 cm long. Find the height of the flag pole :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 40 cm (b) 45 cm
(c) 90 cm (d) none of these

78. Vertical angles of two isoceles triangles are equal. Then corresponding altitudes are in the ratio 4 : 9. Find the ratio of their areas :
(a) 16 : 49 (b) 16 : 81
(c) 16 : 65 (d) none of these

79. In the figure $\Delta ACB \sim \Delta APQ$. If $BC = 8$ cm, $PQ = 4$ cm, $AP = 2.8$ cm, find CA:
(a) 8 cm
(b) 6.5 cm
(c) 5.6 cm
(d) none of these



80. In the figure $BC \| AD$. Find the value of x :



(a) 9, 10 (b) 7, 8
(c) 10, 12 (d) 8, 9

81. In an equilateral triangle of side $2a$, calculate the length of its altitude :
(a) $2a\sqrt{3}$ (b) $a\sqrt{3}$
(c) $a\frac{\sqrt{3}}{2}$ (d) none of these

82. In figure AD is the bisector of $\angle BAC$. If $BD = 2$ cm, $CD = 3$ cm and $AB = 5$ cm. Find AC :
(a) 6 cm
(b) 7.5 cm
(c) 10 cm
(d) 15 cm



83. In the figure $AB \| QR$. Find the length of PB :



(a) 2 cm (b) 3 cm
(c) 2.5 cm (d) 4 cm

84. In the figure QA and PB are perpendicular to AB. If $AO = 10$ cm, $BO = 6$ cm and $PB = 9$ cm. Find AQ :
(a) 8 cm
(b) 9 cm
(c) 15 cm
(d) 12 cm



85. In the given figure $AB = 12$ cm, $AC = 15$ cm and $AD = 6$ cm. $BC \| DE$, find the length of AE :
(a) 6 cm
(b) 7.5 cm
(c) 9 cm
(d) 10 cm



86. In the figure, ABC is a triangle in which $AB = AC$. A circle through B touches AC at D and intersects AB at P. If D is the mid-point of AC, Find the value of AB :
(a) $2AP$
(b) $3AP$
(c) $4AP$
(d) none of the above



87. In figure, ABC is a right triangle, right angled at B. AD and CE are the two medians drawn from A and C respectively. If $AC = 5$ cm and $AD = \frac{3\sqrt{5}}{2}$ cm, find the length of CE :
(a) $2\sqrt{5}$ cm
(b) 2.5 cm
(c) 5 cm
(d) $4\sqrt{2}$ cm



88. In a ΔABC, $AB = 10$ cm, $BC = 12$ cm and $AC = 14$ cm. Find the length of median AD. If G is the centroid , find length of GA :
(a) $\frac{5}{3}\sqrt{7}, \frac{5}{9}\sqrt{7}$ (b) $5\sqrt{7}, 4\sqrt{7}$
(c) $\frac{10}{\sqrt{3}}, \frac{8}{3}\sqrt{7}$ (d) $4\sqrt{7}, \frac{8}{3}\sqrt{7}$

89. ΔABC is a right angled at A and AD is the altitude to BC. If $AB = 7$ cm and $AC = 24$ cm. Find the ratio of AD is to AM if M is the mid-point of BC :
(a) 25 : 41 (b) 32 : 41
(c) $\frac{336}{625}$ (d) $\frac{625}{336}$

90. Area of $\Delta ABC = 30$ cm^2. D and E are the mid-points of BC and AB respectively. Find $A(\Delta BDE)$:
(a) 10 cm (b) 7.5 cm
(c) 15 cm (d) none of these

91. The three sides of a triangles are given which one of the following is not a right angle :
(a) 20, 21, 29 (b) 16, 63, 65
(c) 56, 90, 106 (d) 36, 35, 74

92. In the figure AD is the external bisector of $\angle EAC$, intersects BC produced to D. If $AB = 12$ cm, $AC = 8$ cm and $BC = 4$ cm, find CD :
(a) 10 cm
(b) 6 cm
(c) 8 cm
(d) 9 cm



Scanned by CamScanner

yoursmahboob.wordpress.com

93. In ΔABC, $AB^2 + AC^2 = 2500$ cm^2 and median $AD = 25$ cm. Find BC:
(a) 25 cm (b) 40 cm
(c) 50 cm (d) 48 cm

94. In the given figure, $AB = BC$ and $\angle BAC = 15°$, $AB = 10$ cm. Find the area of ΔABC:



(a) 50 cm^2 (b) 40 cm^2
(c) 25 cm^2 (d) 32 cm^2

95. In ABC, G is the centroid, $AB = 15$ cm, $BC = 18$ cm and $AC = 25$ cm. Find GD, where D is the mid-point of BC:
(a) $\frac{1}{3}\sqrt{86}$ cm (b) $\frac{2}{3}\sqrt{86}$ cm
(c) $\frac{8}{3}\sqrt{15}$ cm (d) none of these

96. In the given figure, if $\frac{DE}{BC} = \frac{2}{3}$ and if $AE = 10$ cm. Find AB:
(a) 16 cm
(b) 12 cm
(c) 15 cm
(d) 18 cm



97. Find the maximum area that can be enclosed in a triangle of perimeter 24 cm:
(a) 32 cm^2 (b) $16\sqrt{3}$ cm^2
(c) $16\sqrt{2}$ cm^2 (d) 27 cm^2

98. In the figure $AD = 12$ cm, $AB = 20$ cm and $AE = 10$ cm. Find EC:
(a) 14 cm
(b) 10 cm
(c) 8 cm
(d) 15 cm



99. In the given figure, $BC = AC = AD$, $\angle EAD = 81°$. Find the value of x:



(a) 45° (b) 54°
(c) 63° (d) 36°

100. What is the ratio of inradius to the circumradius of a right angled triangle?
(a) 1 : 2 (b) 1 : $\sqrt{2}$
(c) 2 : 5 (d) can't be determined

(3) QUADRILATERALS

A four sided closed figure is called a quadrilateral. It is denoted by symbol '▭'.

Properties

1. Sum of four interior angles is 360°.
2. The figure formed by joining the mid-points of a quadrilateral is a parallelogram.



3. The sum of opposite sides of a quadrilateral circumscribed about a circle, is always equal.
4. Area of quadrilateral $= \frac{1}{2} \times$ one of the diagonals $\times$ sum of the perpendiculars drawn to the diagonals from the opposite vertices.

i.e., $A(\square ABCD) = \frac{1}{2} \times AC \times (DE + BF)$

DIFFERENT TYPES OF QUADRILATERALS ARE GIVEN BELOW

Parallelogram : A quadrilateral whose opposite sides are parallel.

Properties

1. The opposite sides are parallel and equal.



2. Opposite angles are equal.
3. Sum of any two adjacent angles is 180°.
4. Diagonals bisect each other.



Scanned by CamScanner

yoursmahboob.wordpress.com

5. Diagonals need not be equal in length.
6. Diagonals need not bisect at right angle.
7. Diagonals need not bisect angles at the vertices.
8. Each diagonal divides a parallelogram into two congruent triangles.
9. Lines joining the mid-points of the adjacent sides of a **quadrilateral** form a **parallelogram.**
10. Lines joining the mid-points of of the adjacent sides of a **parallelogram** is a **parallelogram.**
11. The parallelogram that is inscribed in a circle is a rectangle.
12. The parallelogram that is circumscribed about a circle is a rhombus.
13. (a) Area of a parallelogram = base × height
    (b) Area of parallelogram
    = product of any two adjacent sides × sine of the included angles.
    $= AB \times AD \times \sin\theta$
14. Perimeter of a parallelogram = 2 (sum of any two adjacent sides)
15. $(AC)^2 + (BD)^2 = (AB)^2 + (BC)^2 + (CD)^2 + (AD)^2$
    $= 2(AB^2 + BC^2)$
16. Parallelogram that lie on the same base and between the same parallel lines are equal in area.
17. Area of a triangle is half of the area of a parallelogram which lie on the same base and between the same parallel lines.
18. A parallelogram is a rectangle if its diagonals are equal.

Rectangle : A parallelogram in which all the four angles at vertices are right (*i.e.*, 90°), is called a rectangle.

Properties

1. Opposite sides are parallel and equal.
2. Opposite angles are equal and of 90°.



3. Diagonals are equal and bisect each other, but not necessarily at right angles.
4. When a rectangle is inscribed in a circle, the diameter of the circle is equal to the diagonal of the rectangle.
5. For the given perimeter of rectangles, a square has maximum area.
6. The figure formed by joining the mid-points of the adjacent sides of a rectangle is a rhombus.
7. The quadrilateral formed by joining the mid-points of intersection of the angle bisectors of a parallelogram is a rectangle.
8. Every rectangle is a parallelogram.
9. Area of a rectangle = length × breadth $(= l \times b)$



10. Diagonals of a rectangle $= \sqrt{l^2 + b^2}$
11. Perimeter of a rectangle $= 2(l + b)$
    $l \rightarrow$ length and $b \rightarrow$ breadth

Rhombus : A parallelogram in which all sides are equal, is called a rhombus.

Properties

1. Opposite sides are parallel and equal.
2. Opposite angles are equal.
3. Diagonals bisect each other at right angle, but they are not necessarily equal.



4. Diagonals bisect the vertex angles.
5. Sum of any two adjacent angles is 180°.



6. Figure formed by joining the mid-points of the adjacent sides of a rhombus is a rectangle.
7. A parallelogram is a rhombus if its diagonals are perpendicular to each other.
8. (a) Area of a rhombus $= \frac{1}{2} \times$ product of diagonals
   $= \frac{1}{2} \times d_1 \times d_2$
   (b) Area of a rhombus = Product of adjacent sides × sine of the included angle.

Square : A rectangle whose all sides are equal or a rhombus whose all angles are equal is called a square. Thus each rhombus is a parallelogram, a rectangle and a rhombus.

Properties

1. All side are equal and parallel.
2. All angles are right angles.
3. Diagonals are equal and bisect each other at right angle.

Scanned by CamScanner

yoursmahboob.wordpress.com



4. Diagonal of an inscribed square is equal to diameter of the inscribing circle.
5. Side of a circumscribed square is equal to the diameter of the inscribed circle.





6. The figure formed by joining the mid-points of the adjacent sides of a square is a square.
7. Area = $(\text{side})^2$

$$= a^2 = \frac{(\text{diagonal})^2}{2} = \frac{d^2}{2}$$



8. Diagonal = side $\sqrt{2} = a\sqrt{2}$
9. Perimeter = 4 × side = $4a$

Trapezium : A quadrilateral whose only one pair of sides is parallel and other two sides are not parallel.

Properties

1. The line joining the mid-points of the oblique (non-parallel) sides is half the sum of the parallel sides and is called the median.



(*i.e.*, Median $= \frac{1}{2} \times$ sum of parallel sides

$$= \frac{1}{2} \times (AB + DC) = EF)$$

2. If the non-parallel sides are equal then the diagonals will also be equal to each other.
3. Diagonals intersect each other proportionally in the ratio of lengths of parallel sides.
4. By joining the mid-points of adjacent sides of a trapezium four similar triangles are obtained.
5. If a trapezium is inscribed in a circle, then it is an isosceles trapezium with equal oblique sides.
6. Area of trapezium $= \frac{1}{2} \times$ (sum of parallel sides × height)

$$= \frac{1}{2} \times (AB + CD) \times h$$

7. $AC^2 + BD^2 = BC^2 + AD^2 + 2AB \cdot CD$



Kite : In a kite two pairs of adjacent sides are equal.



Properties

1. $AB = BC$ and $AD = CD$
2. Diagonals intersect at right angles.
3. Shorter diagonal is bisected by the longer diagonal.
4. Area $= \frac{1}{2} \times$ product of diagonals

S. No.	Property	Parallelogram	Rectangle	Rhombus	Square
1.	Opposite sides are equal	✔	✔	✔	✔
2.	All sides are equal	✗	✗	✔	✔
3.	Opposite sides are parallel	✔	✔	✔	✔
4.	Opposite angles are equal	✔	✔	✔	✔
5.	All angles are equal and right angle	✗	✔	✗	✔
6.	Diagonals bisect each other	✔	✔	✔	✔
7.	Diagonals bisect each other at right angles	✗	✗	✔	✔
8.	Diagonals bisect vertex angles	✗	✗	✔	✔
9.	Diagonals are equal	✗	✔	✗	✔
10.	Diagonals form four triangles of equal area	✔	✔	✔	✔
11.	Diagonals form four congruent triangles	✗	✗	✔	✔

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE-12.3

1. The measures of the angles of a quadrilateral taken in order are proportional to 1 : 2 : 3 : 4, then the quadrilateral is :
(a) parallelogram (b) trapezium
(c) rectangle (d) rhombus

2. Find the measure of largest angle of a quadrilateral if the measures of its interior angles are in the ratio of 3 : 4 : 5 : 6 :
(a) 60° (b) 120°
(c) 90° (d) can't be determined

3. $ABCD$ is a parallelogram, P and Q are the points on the diagonal AC such that $AP = QC$, then quadrilateral $BPDQ$ is a :
(a) trapezium (b) parallelogram
(c) square (d) none of these

4. In a parallelogram $ABCD$, bisectors of consecutive angles A and B intersect at P. Find the measure of $\angle APB$:
(a) 90° (b) 60°
(c) 120° (d) data insufficient

5. AB and CD are two parallel lines and a transversal PQ intersects AB and CD at M and N respectively. The bisector of the interior angles form a quadrilateral :



(a) rectangle (b) square
(c) parallelogram (d) none of these

6. In the given figure $AE = BC$ and $AE \parallel BC$ and the three sides AB, CD and ED are equal in length. If $m\angle A = 102°$, find measures of $\angle BCD$:



(a) 138° (b) 162°
(c) 88° (d) none of these

7. $ABCD$ is a square, A is joined to a point P on BC and D is joined to a point Q on AB. If $AP = DQ$ and AP intersects DQ at R then $\angle DRP$ is :
(a) 60° (b) 120°
(c) 90° (d) can't be determined

8. A point X inside a rectangle $PQRS$ is joined to the vertices then, which of the following is true :
(a) $A(\Delta PSX) = A(\Delta RXQ)$
(b) $A(\Delta PSX) + A(\Delta PXQ) = A(\Delta RSX) + A(\Delta RQX)$
(c) $A(\Delta PXS) + A(\Delta RXQ) = A(\Delta SRX) + A(\Delta PXQ)$
(d) none of the above

9. $\square ABCD$ is a parallelogram, m $\angle DAB = 30°$, $BC = 20$ cm and $AB = 20$ cm. Find the area of parallelogram :
(a) 150 cm^2 (b) 200 cm^2
(c) 400 cm^2 (d) 260 cm^2

10. The length of a side of a rhombus is 10 m and one of its diagonal is 12 m. The length of the other diagonal is :
(a) 15 m (b) 18 m
(c) 16 m (d) can't be determined

11. $ABCD$ is a parallelogram and BD is a diagonal. $\angle BAD = 65°$ and $\angle DBC = 45°$, then $m\angle BDC$ is :
(a) 65° (b) 70°
(c) 20° (d) none of these

12. If $ABCD$ is a parallelogram in which P and Q are the centroids of ΔABD and ΔBCD, then, PQ equals :
(a) AQ (b) AP
(c) BP (d) DQ

13. Two parallelograms stand on equal bases and between the same parallels. The ratio of their areas is :
(a) 1 : 1 (b) $\sqrt{2}$: 1
(c) 1 : 3 (d) 1 : 2

14. If a rectangle and a parallelogram are equal in area and have the same base and are situated on the same side, then the ratio of perimeter of rectangle and that of parallelogram is k, then k is :
(a) $k > 1$ (b) $k < 1$
(c) $k = 1$ (d) can't be determined

15. If area of a parallelogram with sides l and b is A and that of a rectangle with sides l and b is B, then :
(a) $A < B$ (b) $A = B$
(c) $A > B$ (d) none of these

16. $ABCD$ is a parallelogram and M is the mid-point of BC. AB and DM are produced to meet at N, then :
(a) $AN = \sqrt{3}AB$ (b) $AN = 2AB$
(c) $AN^2 = \frac{3}{2}AB^2$ (d) $AN^2 = 2AB^2$

17. In a rectangle $ABCD$, P, Q are the mid-points of BC and AD respectively and R is any point on PQ, then ΔARB equals :
(a) $\frac{1}{2}(\square ABCD)$ (b) $\frac{1}{3}(\square ABCD)$
(c) $\frac{1}{4}(\square ABCD)$ (d) none of these

18. Diagonals of a parallelogram are 8 m and 6 m respectively. If one of side is 5m, then the area of parallelogram is :
(a) 18 m^2 (b) 30 m^2
(c) 24 m^2 (d) 48 m^2

19. In the given figure $AD = 15$ cm, $AB = 20$ cm and $BC = CD = 25$ cm. Find the area of $\square ABCD$:

Scanned by CamScanner

yoursmahboob.wordpress.com



(a) $\frac{25}{4}(24+25\sqrt{3})\,cm^2$ (b) $24(25+24\sqrt{3})\,cm^2$

(c) $\frac{25}{2}(24+25\sqrt{3})\,cm^2$ (d) none of these

20. In the trapezium $ABCD$, $\angle BAE = 30°$, $\angle CDF = 45°$. $BC = 6$ cm and $AB = 12$ cm. Find the area of trapezium :



(a) $18(3+\sqrt{3})\,cm^2$ (b) $36\sqrt{3}\,cm^2$

(c) $12(3+2\sqrt{3})\,cm^2$ (d) none of these

21. Area of quadrilateral $ACDE$ is 36 cm^2, B is the mid-point of AC. Find the area of ΔABE if $AC \parallel DE$ and $BE \parallel DC$:



(a) 10 cm^2

(b) 9 cm^2

(c) 12 cm^2

(d) can't be determined

22. A square and a rhombus have the same base and the rhombus is inclined at 30°. What is the ratio of area of the square to the area of the rhombus :

(a) $\sqrt{2}:1$ (b) $2:1$

(c) $1:1$ (d) $2:\sqrt{3}$

23. Find the area of a quadrilateral with sides 17, 25, 30 and 28 cm and one of its diagonal is 26 cm :

(a) 450 cm^2 (b) 360 cm^2

(c) 540 cm^2 (d) 720 cm^2

24. $PQRS$ is a parallelogram in which $\angle P = 70°$, $\angle Q = 90°$ and $\angle R = 100°$. How many points in the plane of the quadrilateral are there such that a point is equidistant from its vertices ?

(a) 0 (b) 1

(c) 2 (d) 3

25. $ABCD$ is a parallelogram. The diagonals AC and BD intersect at a point O. If E, F, G and H are the mid-points of AO, DO, CO and BO respectively, then the ratio of $(EF + FG + GH + HE)$ to $(AD + DC + CB + BA)$ is :

(a) 1 : 1 (b) 1 : 2

(c) 1 : 3 (d) 1 : 4

26. If $ABCD$ is a rhombus, then :

(a) $AC^2 + BD^2 = 4AB^2$ (b) $AC^2 + BD^2 = AB^2$

(c) $AC^2 + BD^2 = 2AB^2$ (d) $2(AC^2 + BD^2) = 3AB^2$

27. If P is a point within a rectangle $ABCD$, then :

(a) $AP^2 + PC^2 = BP^2 + PD^2$

(b) $AP^2 + BP^2 = PC^2 + PD^2$

(c) $AP + PC = BP + PD$

(d) $AP \times PC = BP \times PD$

28. $\square ABCD$ is a parallelogram, $AB = 14$ cm, $BC = 18$ cm and $AC = 16$ cm. Find the length of the other diagonal :

(a) 24 cm (b) 28 cm

(c) 36 cm (d) 32 cm

(4) POLYGONS

Polygon : It is a closed plane figure bounded by three or more than three straight lines.

e.g., triangle, quadrilateral, pentagon, hexagon, heptagon, octagon, nonagon and decagon.

Convex Polygon: A polygon in which none of its interior angle is more than 180°, is known as a convex polygon.



(a) (b) (c)

Convex Polygons

Concave Polygon: A polygon in which atleast one interior angle is more than 180°, then it is said to be concave.



(a) (b) (c)

Concave Polygons

Regular Polygon : A polygon in which all the sides are equal and also all the interior angles are equal, is called a regular polygon.

Formulae : For regular polygons

1. Sum of all interior angles $= (n-2)\times 180$
$= (2n-4)\times 90°$

2. Each interior angle $= 180 -$ exterior angle

3. Each exterior angle $= \left(\frac{360}{\text{Number of sides}}\right)$ (in degrees)

Scanned by CamScanner

yoursmahboob.wordpress.com

4. Sum of all exterior angle $= 360°$ (always constant)

5. Number of sides in a polygon $= \dfrac{360}{\text{Exterior angle}}$

$= 2(x+1)$ $\left(x = \dfrac{\text{Interior angle}}{\text{Exterior angle}}\right)$

6. Number of diagonals $= {}^{n}C_2 - n = \dfrac{n(n-1)}{2} - n$

$= \dfrac{n^2-3n}{2} = \dfrac{n(n-3)}{2}$

where $n \rightarrow$ number of sides of a polygon.

7. Star : Sum of angles of a n point star $= (n-4)\pi$

8. Area of a polygon $= \dfrac{na^2}{4} \times \cot\left(\dfrac{180}{n}\right)$;

where $n \rightarrow$ number of sides
$a \rightarrow$ length of sides

No. of sides	Polygon	Sum of all the angles	Each interior angle	Each exterior angle	No. of diagonals
3	Triangle	180°	60°	120°	0
4	Quadrilateral	360°	90°	90°	2
5	Pentagon	540°	108°	72°	5
6	Hexagon	720°	120°	60°	9
7	Heptagon	900°	$\left(128\frac{4}{7}\right)°$	$\left(51\frac{3}{7}\right)°$	14
8	Octagon	1080°	135°	45°	20
9	Nonagon	1260°	140°	40°	27
10	Decagon	1440°	144°	36°	35

INTRODUCTORY EXERCISE-12.4

1. Each interior angle of a regular polygon is 140°. The number of sides is :
   (a) 10 (b) 8
   (c) 6 (d) 9
2. Each angle of a regular hexagon is :
   (a) 60° (b) 120°
   (c) 90° (d) none of these
3. If one of the interior angles of a regular polygon is equal to 5/6 times of one of the interior angles of a regular pentagon, then the number of sides of the polygon is :
   (a) 3 (b) 4
   (c) 6 (d) 8
4. The sum of the interior angles of a polygon is 1260°. The number of sides of the polygon is :
   (a) 6 (b) 7
   (c) 8 (d) 9
5. If each interior angle of a regular polygon is 3 times its exterior angle, the number of sides of the polygon is :
   (a) 4 (b) 5
   (c) 6 (d) 8
6. Difference between the interior and exterior angles of regular polygon is 60°. The number of sides in the polygon is :
   (a) 5 (b) 6
   (c) 8 (d) 9
7. A polygon has 54 diagonals. The number of sides in the polygon is :
   (a) 7 (b) 9
   (c) 12 (d) none of these
8. The ratio between the number of sides of two regular polygon 1 : 2 and the ratio between their interior angle is 3 : 4. The number of sides of these polygons are respectively :
   (a) 3, 6 (b) 4, 8
   (c) 6, 9 (d) 5, 10
9. The sum of all the interior angles of a regular polygon is four times the sum of its exterior angles. The polygon is :
   (a) hexagon (b) triangle
   (c) decagon (d) nonagon
10. The ratio of the measure of an angle of a regular nonagon to the measure of its exterior angle is :
    (a) 3 : 5 (b) 5 : 2
    (c) 7 : 2 (d) 4 : 5

Scanned by CamScanner

yoursmahboob.wordpress.com

(5) CIRCLE

Circle : A circle is a set of points on a plane which lie at a fixed distance from a fixed point.

Nomenclature	Definition	Diagram
Centre	The fixed point is called the centre. In the given diagram 'O' is the centre of the circle.	
Radius	The fixed distance is called a radius. In the given diagram OP is the radius of the circle. (Point P lies on the circumference)	
Circumference	The circumference of a circle is the distance around a circle, which is equal to $2\pi r$. ($r \rightarrow$ radius of the circle)	
Secant	A line segment which intersects the circle in two distinct points, is called as secant. In the given diagram secant PQ intersects circle at two points at A and B.	
Tangent	A line segment which has one common point with the circumference of a circle *i.e.*, it touches only at only one point is called as tangent of circle. The common point is called as point of contact. In the given diagram PQ is a tangent which touches the circle at a point R.	 (R is the point of contact) **Note:** Radius is always perpendicular to tangent.
Chord	A line segment whose end points lie on the circle. In the given diagram AB is a chord.	
Diameter	A chord which passes through the centre of the circle is called the diameter of the circle. The length of the diameter is twice the length of the radius. In the given diagram PQ is the diameter of the circle. ($O \rightarrow$ is the centre of the circle)	
Arc	Any two points on the circle divides the circle into two parts the smaller part is called as minor arc and the larger part is called as major arc. It is denoted as '$\frown$'. In the given diagram $\overset{\frown}{PQ}$ is arc.	 $PQ \rightarrow$ minor arc $PQ \rightarrow$ major arc
Semicircle	A diameter of the circle divides the circle into two equal parts. Each part is called as semicircle.	

Scanned by CamScanner

yoursmabhoob.wordpress.com

Nomenclature	Definition	Diagram
Central angle	An angle formed at the centre of the circle, is called the central angle. In the given diagram $\angle AOB$ is the central angle.	
Inscribed angle	When two chords have one common end point, then the angle included between these two chords at the common point is called the inscribed angle. $\angle ABC$ is the inscribed angle by the arc $\overset{\frown}{ADC}$.	
Measure of an arc	Basically it is the central angle formed by an arc, *e.g.*, (a) measure of a circle = 360° (b) measure of a semicircle = 180° (c) measure of a minor arc = $\angle POQ$ (d) measure of a major arc = 360 – $\angle POQ$	 
Intercepted arc	In the given diagram $\overset{\frown}{AB}$ and $\overset{\frown}{CD}$ are the two intercepted arcs, intercepted by $\angle CPD$. The end points of the arc must touch the arms of $\angle CPD$ *i.e.*, CP and DP.	
Concentric circles	Circles having the same centre at a plane are called the concentric circles. In the given diagram there are two circles with radii r_1 and r_2 having the common (or same) centre. These are called as concentric circles.	
Congruent circles	Circles with equal radii are called as congruent circles.	
Segment of a circle	A chord divides a circle into two regions. These two regions are called the segments of a circle. (a) major segment (b) minor segment	

Scanned by CamScanner

yoursmahboob.wordpress.com

Nomenclature	Definition	Diagram
Cyclic quadrilateral	A quadrilateral whose all the four vertices lie on the circle.	
Circum-circle	A circle which passes through all the three vertices of a triangle. Thus the circumcentre is always equidistant from the vertices of the triangle. $OA = OB = OC$ (circumradius)	
Incircle	A circle which touches all the three sides of a triangle *i.e.*, all the three sides of a triangle are tangents to the circle is called an incircle. Incircle is always equidistant from the sides of a triangle. $OP = OQ = OR$ (inradius of the circle)	

- Two arcs of a circle (or of congruent circles) are congruent if their degree measures are equal.
- There is one and only one circle passes through three non-collinear points.

S. No.	Theorem	Diagram
1.	In a circle (or in congruent circles) equal chords are made by equal arcs. $\{OP = OQ\} = \{O'R = O'S\}$ and $\overset{\frown}{PQ} = \overset{\frown}{RS}$ $\therefore$ $PQ = RS$	
2.	Equal arcs (or chords) subtend equal angles at the centre $\overset{\frown}{PQ} = \overset{\frown}{AB}$ (or $PQ = AB$) $\therefore$ $\angle POQ = \angle AOB$	
3.	The perpendicular from the centre of a circle to a chord bisects the chord *i.e.*, if $OD \perp AB$ $\therefore$ $AB = 2AD = 2BD$	
4.	The line joining the centre of a circle to the mid-point of a chord is perpendicular to the chord. $\because$ $AD = DB$ $\therefore$ $OD \perp AB$	
5.	Perpendicular bisector of a chord passes through the centre. *i.e.*, if $OD \perp AB$ and $AD = DB$ $\therefore$ O is the centre of the circle.	

Scanned by CamScanner

yoursmahboob.wordpress.com

S. No.	Theorem	Diagram
6.	Equal chords of a circle (or of congruent circles) are equidistant from the centre. $\because$ $AB = PQ$ $\therefore$ $OD = OR$	
7.	Chords which are equidistant from the centre in a circle (or in congruent, circles) are equal. $\because$ $OD = OR$ $\therefore$ $AB = PQ$	
8.	The angle subtended by an arc (the degree measure of the arc) at the centre of a circle is twice the angle subtended by the arc at any point on the remaining part of the circle. $m\angle AOB = 2m\angle ACB$.	
9.	Angle in a semicircle is a right angle.	
10.	Angles in the same segment of a circle are equal *i.e.*, $\angle ACB = \angle ADB$	
11.	If a line segment joining two points subtends equal angle at two other points lying on the same side of the line containing the segment, then the four points lie on the same circle. $\angle ACB = \angle ADB$ $\therefore$ Points A, C, D, B are concyclic *i.e.*, lie on the circle.	
12.	The sum of pair of opposite angles of a cyclic quadrilateral is 180°. $\angle DAB + \angle BCD = 180°$ and $\angle ABC + \angle CDA = 180°$ (Inverse of this theorem is also true)	
13	Equal chords (or equal arcs) of a circle (or congruent circles) subtended equal angles at the centre. $AB = CD$ (or $\overset{\frown}{AB} = \overset{\frown}{CD}$) $\therefore$ $\angle AOB = \angle COD$ (Inverse of this theorem is also true)	

Scanned by CamScanner

yoursmahboob.wordpress.com

S. No.	Theorem	Diagram
14.	If a side of a cyclic quadrilateral is produced, then the exterior angle is equal to the interior opposite angle. $m\angle CDE = m\angle ABC$	
15.	A tangent at any point of a circle is perpendicular to the radius through the point of contact. (Inverse of this theorem is also true)	
16.	The lengths of two tangents drawn from an external point to a circle are equal. *i.e.*, $AP = BP$	
17.	If two chords AB and CD of a circle, intersect inside a circle (outside the circle when produced at a point E), then $AE \times BE = CE \times DE$	 
18.	If PB be a secant which intersects the circle at A and B and PT be a tangent at T then $PA \cdot PB = (PT)^2$	
19.	From an external point from which the tangents are drawn to the circle with centre O, then (a) they subtend equal angles at the centre. (b) they are equally inclined to the line segment joining the centre of that point. $\angle AOP = \angle BOP$ and $\angle APO = \angle BPO$	
20.	If P is an external point from which the tangents to the circle with centre O touch it at A and B then OP is the perpendicular bisector of AB. $OP \perp AB$ and $AC = BC$	
21.	**Alternate segment theorem :** If from the point of contact of a tangent, a chord is drawn then the angles which the chord makes with the tangent line are equal respectively to the angles formed in the corresponding alternate segments. In the adjoining diagram. $\angle BAT = \angle BCA$ and $\angle BAP = \angle BDA$	

Scanned by CamScanner

yoursmahboob.wordpress.com

S. No.	Theorem	Diagram
22.	The point of contact of two tangents lies on the straight line joining the two centres. (a) When two circles touch externally then the distance between their centres is equal to sum of their radii, *i.e.*, $AB = AC + BC$ (b) When two circles touch internally the distance between their centres is equal to the difference between their radii *i.e.*, $AB = AC - BC$	
23.	For the two circles with centre X and Y and radii r_1 and r_2. AB and CD are two Direct Common Tangents (DCT), then the length of DCT $= \sqrt{(\text{distance between centres})^2 - (r_1 - r_2)^2}$	
24.	For the two circles with centre X and Y and radii r_1 and r_2. PQ and RS are two transverse common tangent, then length of TCT $= \sqrt{(\text{distance between centres})^2 - (r_1 + r_2)^2}$	

INTRODUCTORY EXERCISE-12.5

1. In the given figure, O is the centre of the circle. Radius of the circle is 17 cm. If $OC = 8$ cm, then the length of the chord AB is :


(a) 35 cm
(b) 30 cm
(c) 15 cm
(d) 18 cm

2. In the given figure $OM \perp AB$, radius of the circle is 5 cm and length of the chord $AB = 8$ cm. Find the measure of OM :


(a) 3 cm
(b) 2.5 cm
(c) 2 cm
(d) 6 cm

3. In the given figure, two circles with their respective centres intersect each other at A and B and AB intersects OO' at M, then $m\angle OMA$ is :


(a) 60°
(b) 80°
(c) 90°
(d) can't be determined

4. In the above question (no. 3) what is the ratio of $AM : BM$?
(a) 5 : 6 (b) 3 : 2
(c) 1 ; 1 (d) can't be determined

5. In the given figure the two chords AC and BC are equal. The radius OC intersect AB at M, then $AM : BM$ is :


(a) 1 : 1
(b) $\sqrt{2} : 3$
(c) $3 : \sqrt{2}$
(d) none of the above

6. In the adjoining figure, O is the centre of circle and diameter $AC = 26$ cm. If chord $AB = 10$ cm, then the distance between chord AB and centre O of the circle is :


(a) 24 cm
(b) 16 cm
(c) 12 cm
(d) none of the above

7. In the adjoining circle $C(0, r)$ the degree measure of minor arc $AB = 130°$. Find the degree measure of major arc :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 230°
(b) 260°
(c) 310°
(d) none of the above



8. If the diagonals of a cyclic quadrilateral are equal, then the quadrilateral is :
(a) rhombus (b) square
(c) rectangle (d) none of these

9. In the given figure, AB is diameter of the circle. C and D lie on the semicircle. $\angle ABC = 65°$ and $\angle CAD = 45°$. Find $m\angle DCA$:



(a) 45° (b) 25°
(c) 20° (d) none of these

10. In the given figure, chords AB and CD are equal. If $\angle OBA = 55°$, then $m\angle COD$ is :
(a) 65°
(b) 55°
(c) 70°
(d) 50°



11. The quadrilateral formed by angle bisectors of a cyclic quadrilateral is a :
(a) rectangle (b) square
(c) parallelogram (d) cyclic quadrilateral

12. ΔABC and ΔDBC have a common base and drawn towards one sides. $\angle BAC = \angle BDC = 90°$. If AC and DB intersect at P, then :



(a) $AP \times PC = BP \times PD$ (b) $AP \times BP = PC \times PD$
(c) $AP \times PD = PC \times BP$ (d) none of these

13. In the given figure, $\angle BAC$ and $\angle BDC$ are the angles of same segments. $\angle DBC = 30°$ and $\angle BCD = 110°$. Find $m\angle BAC$ is :
(a) 35°
(b) 40°
(c) 55°
(d) 60°



14. In the given figure, O is the centre of the circle. $\angle ABO = 60°$. Find the value of $\angle ACB$:
(a) 40°
(b) 60°
(c) 50°
(d) 30°



15. In the given figure, $\angle AOC = 120°$. Find $m\angle CBE$, where O is the centre :



(a) 60° (b) 100°
(c) 120° (d) 150°

16. In the adjoining figure, O is the centre of the circle and $\angle OBD = 50°$. Find the $m\angle BAD$:
(a) 60°
(b) 40°
(c) 80°
(d) 45°



17. In the given figure, ΔABC is an equilateral triangle. Find $m\angle BEC$:
(a) 120°
(b) 60°
(c) 80°
(d) none of the above



18. In the given figure, AB is the diameter of the circle. Find the value of $\angle ACD$:
(a) 30°
(b) 60°
(c) 45°
(d) 25°



19. In the given figure, $ABCD$ is a cyclic quadrilateral and diagonals bisect each other at P. If $\angle DBC = 60°$ and $\angle BAC = 30°$, then $\angle BCD$ is :
(a) 90°
(b) 60°
(c) 80°
(d) none of the above



20. In the given figure, $ABCD$ is a cyclic quadrilateral and AB is the diameter. $\angle ADC = 140°$, then find $m\angle BAC$:
(a) 45°
(b) 40°
(c) 50°
(d) none of the above



21. In the given figure, $\angle COB = 40°$, AB is the diameter of the circle. Find $m\angle CAB$:
(a) 40°
(b) 20°
(c) 30°
(d) none of the above



Scanned by CamScanner

yoursmahboob.wordpress.com

22. In the given figure, O is the centre of circle. $\angle AOB = 80°$ and $\angle AOC = 120°$. Find $m\ \angle BAC$:



(a) 120°
(b) 80°
(c) 100°
(d) none of the above

23. In the given figure, O is the centre of the circle and $\angle AOC = 100°$. Find the ratio of $m\ \angle ADC : m\ \angle ABC$:



(a) 5 : 6
(b) 1 : 2
(c) 5 : 13
(d) none of the above

24. In the given figure, O is the centre of circle, $\angle AOB = 100°$. Find $m\ \angle BCD$:



(a) 80°
(b) 60°
(c) 50°
(d) 40°

25. In the given figure, AB is the diameter of the circle. $\angle ADC = 120°$. Find $m\ \angle CAB$:



(a) 20°
(b) 30°
(c) 40°
(d) can't be determined

26. In the given figure, O is the centre of the circle. $\angle AOB = 70°$, find $m\ \angle OCD$:



(a) 70°
(b) 55°
(c) 65°
(d) 110°

27. In the given figure, $\angle CAB = 40°$ and $\angle AKB = 105°$. Find $\angle KCD$:



(a) 65°
(b) 35°
(c) 40°
(d) 72°

28. In the given figure, ABC is an isosceles triangle in which $AB = AC$ and $m\ \angle ABC = 50°$, $m\ \angle BDC$:



(a) 80°
(b) 60°
(c) 65°
(d) 100°

29. In the given figure, AB is the diameter. $m\ \angle BAD = 70°$ and $m\ \angle DBC = 30°$. Find $m\ \angle BDC$:



(a) 25°
(b) 30°
(c) 40°
(d) 60°

30. Find the value of $\angle DCE$:



(a) 100°
(b) 80°
(c) 90°
(d) 75°

31. 'O' is the centre of the circle, line segment BOD is the angle bisector of $\angle AOC$, $m\ \angle COD = 50°$. Find $m\ \angle ABC$:



(a) 25°
(b) 50°
(c) 100°
(d) 120°

32. In the given figure, O is the centre of the circle and $\angle ACB = 25°$. Find $\angle AOB$:



(a) 25°
(b) 50°
(c) 75°
(d) 60°

33. In the given figure, O is the centre of the circle. $\angle AOB = 90°$. Find $m\ \angle APB$:



(a) 130°
(b) 150°
(c) 135°
(d) can't be determined

34. In the given figure, O is the centre of the circle. AB is tangent. $AB = 12$ cm and $OB = 13$ cm. Find OA:



(a) 6.5 cm
(b) 6 cm
(c) 5 cm
(d) none of these

35. In the given figure, PQ is the tangent of the circle. Line segment PR intersects the circle at N and R. $PQ = 15$ cm, $PR = 25$ cm, find PN:



(a) 15 cm
(b) 10 cm
(c) 9 cm
(d) 6 cm

36. In the given figure, there are two circles with the centres O and O' touching each other internally at P. Tangents TQ and TP are drawn to the larger circle and tangents TP and TR are drawn to the smaller circle. Find $TQ : TR$:



Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 8 : 7 (b) 7 : 8
(c) 5 : 4 (d) 1 : 1

37. In the given figure, PAQ is the tangent. BC is the diameter of the circle. $m\angle BAQ = 60°$, find $m\angle ABC$:



(a) 25°
(b) 30°
(c) 45°
(d) 60°

38. $ABCD$ is a cyclic quadrilateral PQ is a tangent at B. If $\angle DBQ = 65°$, then $\angle BCD$ is :



(a) 35°
(b) 85°
(c) 115°
(d) 90°

39. In the given figure, $AP = 2$ cm, $BP = 6$ cm and $CP = 3$ cm. Find DP :



(a) 6 cm
(b) 4 cm
(c) 2 cm
(d) 3 cm

40. In the given figure, $AP = 3$ cm, $BA = 5$ cm and $CP = 2$ cm. Find CD :



(a) 12 cm
(b) 10 cm
(c) 9 cm
(d) 6 cm

41. In the given figure, tangent $PT = 5$ cm, $PA = 4$ cm, find AB:



(a) $\frac{7}{4}$ cm
(b) $\frac{11}{4}$ cm
(c) $\frac{9}{4}$ cm
(d) can't be determined

42. Two circles of radii 13 cm and 5 cm touch internally each other. Find the distance between their centres :
(a) 18 cm (b) 12 cm
(c) 9 cm (d) 8 cm

43. Three circles touch each other externally. The distance between their centre is 5 cm, 6 cm and 7 cm. Find the radii of the circles :
(a) 2 cm, 3 cm, 4 cm (b) 3 cm, 4 cm, 1 cm
(c) 1cm, 2.5 cm, 3.5 cm (d) 1 cm, 2 cm, 4 cm

44. A circle touches a quadrilateral $ABCD$. Find the true statement :



(a) $AB + BC = CD + AD$
(b) $AB + CD = BC + AD$
(c) $BD = AC$
(d) none of the above

45. O and O' are the centres of two circles which touch each other externally at P. AB is a common tangent. Find $\angle APO$:
(a) 90° (b) 120°
(c) 60° (d) data insufficient

46. If AB is a chord of a circle, P and Q are two points on the circle different from A and B, then :
(a) the angle subtended by AB at P and Q are either equal or supplementary.
(b) the sum of the angles subtended by AB at P and Q always equal two right angles.
(c) the angles subtended at P and Q by AB are always equal.
(d) the sum of the angles subtended at P and Q is equal to four right angles.

47. In the given figure, AB and CD are two common tangents to the two touching circle. If $CD = 6$ cm, then AB is equal to :



(a) 9 cm
(b) 15 cm
(c) 12 cm
(d) none of the above

48. In the given figure, CD is a direct common tangent to two circles intersecting each other at A and B, then :

$\angle CAD + \angle CBD = ?$



(a) 120° (b) 90°
(c) 360° (d) 180°

49. O and O' are the centres of circle of radii 20 cm and 5 cm. $AB = 24$ cm. What is the distance OO' ?



(a) 51 cm (b) 45 cm
(c) 35 cm (d) 48 cm

50. In a circle of radius 5 cm, AB and AC are the two chords such that $AB = AC = 6$ cm. Find the length of the chord BC
(a) 4.8 cm (b) 10.8 cm
(c) 9.6 cm (d) none of these

51. In a circle of radius 17 cm, two parallel chords are drawn on opposite sides of a diameter. The distance between the chords is 23 cm. If the length of one chord is 16 cm then the length of the other is :
(a) 23 cm (b) 30 cm
(c) 15 cm (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

52. If two circles are such that the centre of one lies on the circumference of the other, then the ratio of the common chord of two circles to the radius of any of the circles is :
(a) $\sqrt{3}:2$ (b) $\sqrt{3}:1$
(c) $\sqrt{5}:1$ (d) none of these

53. Two circles touch each other internally. Their radii are 2 cm and 3 cm. The biggest chord of the other circle which is outside the inner circle, is of length :
(a) $2\sqrt{2}$ cm (b) $3\sqrt{2}$ cm
(c) $2\sqrt{3}$ cm (d) $4\sqrt{2}$ cm

54. Through any given set of four points P, Q, R, S it is possible to draw :
(a) atmost one circle
(b) exactly one circle
(c) exactly two circles
(d) exactly three circles

55. The distance between the centres of equal circles each of radius 3 cm is 10 cm. The length of a transverse tangent is :
(a) 4 cm (b) 6 cm
(c) 8 cm (d) 10 cm

56. The number of common tangents that can be drawn to two given circles is at the most :
(a) 1 (b) 2
(c) 3 (d) 4

57. ABC is a right angled triangle $AB = 3$ cm, $BC = 5$ cm and $AC = 4$ cm, then the inradius of the circle is :



(a) 1 cm (b) 1.25 cm
(c) 1.5 cm (d) none of these

58. A circle has two parallel chords of lengths 6 cm and 8 cm. If the chords are 1 cm apart and the centre is on the same side of the chords, then a diameter of the circle is of length :
(a) 5 cm (b) 6 cm
(c) 8 cm (d) 10 cm

59. Three equal circles of unit radius touch each other. Then, the area of the circle circumscribing the three circles is :
(a) $6\pi(2+\sqrt{3})^2$ (b) $\frac{\pi}{6}(2+\sqrt{3})^2$
(c) $\frac{\pi}{3}(2+\sqrt{3})^2$ (d) $3\pi(2+\sqrt{3})^2$

60. The radius of a circle is 20 cm. The radii (in cm) of three concentric circles drawn in such a manner that the whole area is divided into four equal parts, are :
(a) $20\sqrt{2}, 20\sqrt{3}, 20$ (b) $\frac{10\sqrt{3}}{3}, \frac{10\sqrt{2}}{3}, \frac{10}{3}$
(c) $10\sqrt{3}, 10\sqrt{2}, 10$ (d) 17, 14, 9

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. In the adjoining figure AB is a diameter of the circle and $\angle BCD = 130°$. What is the value of $\angle ABD$?



(a) 30°
(b) 50°
(c) 40°
(d) none of the above

2. In the given figure O is the centre of the circle and $\angle BAC = 25°$, then the value of $\angle ADB$ is :



(a) 40°
(b) 55°
(c) 50°
(d) 65°

3. In the given figure O is the centre of the circle and $\angle OCD = 26°$, find $\angle AOD$:



(a) 52°
(b) 154°
(c) 128°
(d) data insufficient

4. Three sides of a triangle ABC are a, b, c. $a = 4700$ cm, $b = 4935$ cm and $c = 6815$ cm. The internal bisector of $\angle A$ meets BC at P, and the bisector passes through incentre 'O'. What is ratio of $PO : OA$?

(a) 3 : 2
(b) 2 : 3
(c) 2 : 5
(d) can't be determined

5. In the given circle O is the centre of the circle and AD, AE are the two tangents. BC is also a tangent, then :



(a) $AC + AB = BC$
(b) $3AE = AB + BC + AC$
(c) $AB + BC + AC = 4AE$
(d) $2AE = AB + BC + AC$

6. What is the inradius of the incircle shown in the figure?



(a) 9 cm
(b) 4 cm
(c) can't be determined
(d) none of the above

7. One of the diagonal of a parallelogram is 18 cm, whose adjacent sides are 16 cm and 20 cm respectively. What is the length of other diagonal?

(a) $2\sqrt{247}$ cm
(b) 13 cm
(c) 15.2 cm
(d) 28.5 cm

8. In the adjoining figure CD is perpendicular on AB. CN is the angle bisector of $\angle ACB$. $\angle ACN = 50°$, then the angle NCD is :



(a) $\frac{1}{3}\angle ACB$
(b) $\angle CAB - \angle CBA$
(c) $\frac{1}{2}(\angle CBA - \angle BAC)$
(d) can't be determined

9. In a ΔPQR, points M and N are on the sides PQ and PR respectively such that $PM = 0.6.PQ$ and and $NR = 0.4PR$. What percentage of the area of the triangle PQR does that of triangle PMN form?

(a) 60%
(b) 50%
(c) 36%
(d) 55%

10. In a trapezium $ABCD$, the diagonals AC and BD intersect each other at O such that $OB : OD = 3 : 1$ then the ratio of areas of $\Delta AOB : \Delta COD$ is :

(a) 3 : 1
(b) 1 : 4
(c) 9 : 1
(d) can't be determined

11. Three cities Fatehpur, Barabanki and Lucknow are very famous. Fatehpur is 42 km, away from Barakanki and the distance between Fatehpur and Lucknow is 66 km. Which of the following cannot be the distance between Barabanki and Lucknow?

(a) 28 km
(b) 98 km
(c) 32 km
(d) 23 km

12. In the adjoining figure 'O' is the the centre of circle AC and BD are the two chords of circle which meets at T outside the circle. OT bisects CD, $OA = OB = 8$ cm and $OT = 17$ cm. What is the ratio of distance of AC and BD from the centre of the circle?



(a) 15 : 17
(b) 8 : 15
(c) 8 : 9
(d) none of the above

13. In the adjoining figure $ABCD$ is a rectangle and $DF = CF$ also $AE = 3BE$. what is the value of $\angle EOF$, if $\angle DFO = 28°$ and $\angle AEO = 42°$?



(a) 14°
(b) 42°
(c) 70°
(d) 90°

Scanned by CamScanner

yoursmahboob.wordpress.com

14. $ABCD$ is a square and AOB is an equilateral triangle. What is the value of $\angle DOC$?



(a) 120°
(b) 150°
(c) 125°
(d) can't be determined

15. In the triangle ABC, $BC = CD$ and $(\angle ABC - \angle BAC) = 30°$. The measure of $\angle ABD$ is :



(a) 30°
(b) 45°
(c) 15°
(d) can't be determined

16. In a trapezium $ABCD$, AB is a parallel to CD. BD is perpendicular to AD. AC is perpendicular to BC. If $AD = BC = 15$ cm and $AB = 25$ cm , then the area of the trapezium is :

(a) 192 cm^2 (b) 232 cm^2
(c) 172 cm^2 (d) none of these

17. In the adjoining figure O is the centre of the circle. The radius OP bisects a rectangle $ABCD$, at right angle. $DM = NC = 2$ cm and $AR = SB = 1$ cm and $KS = 4$ cm and $OP = 5$ cm. What is the area of the rectangle?



(a) 8 cm^2 (b) 10 cm^2
(c) 12 cm^2 (d) None of these

18. In the given figure of circle AB is the diameter with length 20 cm and BC is 16 cm, then find the length of CO when CO is perpendicular on AB :



(a) 9.6 cm
(b) 8.4 cm
(c) 10 cm
(d) data insufficient

19. In the adjoining figure BD is the diameter of the circle and $\angle BCA = 41°$. Find $\angle ABD$:



(a) 41°
(b) 49°
(c) 22.5°
(d) 20.5°

20. Each interior angle of a regular polygon exceeds its exterior angle by 132°. How many sides does the polygon have ?

(a) 9 (b) 15
(c) 12 (d) none of these

21. In a circle O is the centre and $\angle COD$ is right angle. $AC = BD$ and CD is the tangent at P. What is the value of $AC + CP$, if the radius of the circle is 1 metre?

(a) 105 cm
(b) 141.4 cm
(c) 138.6 cm
(d) can't be determined



22. In the given triangle ABC, CD, BF and AE are the altitudes. If the ratio of $CD : AE : BF = 2 : 3 : 4$, then the ratio of $AB : BC : CA$ is :



(a) 4 : 3 : 2
(b) 2 : 3 : 4
(c) 4 : 9 : 16
(d) 6 : 4 : 3

23. In the adjoining figure $AB \| CD$ and $PQ = SR$, then :



(a) $PQ = PS$
(b) $SR = RP$
(c) $PS = QR$
(d) $AP = RD$

24. In the given figure AB, CD and EF are three towers. The angle of elevation of the top of the tower CD from the top of the tower AB is 60° and that from EF is 30°. $BD = 2\sqrt{3}$ m, $CD : EF = 5 : 4$ and $DF = 4$ m. What is the height of the tower AB ?



(a) 6 m
(b) 12 m
(c) 7 m
(d) none of the above

25. In the equilateral triangle ABC, $AD = DE = BE$, D and E lies on the AB. If each side of the triangle (*i.e.*, AB, BC and AC) be 6 cm, then the area of the shaded region is :



(a) 9 cm^2
(b) $6\sqrt{3}$ cm^2
(c) $5\sqrt{3}$ cm^2
(d) none of the above

26. In the above question (number 25) what is the perimeter of triangle CDE ?

(a) $(3 + 2\sqrt{5})$ cm (b) $2(1 + 2\sqrt{7})$ cm
(c) $2(1 + 3\sqrt{7})$ cm (d) none of these

27. In a triangle ABC, O is the centre of incircle PQR, $\angle BAC = 65°$, $\angle BCA = 75°$, find $\angle ROQ$:



(a) 80°
(b) 120°
(c) 140°
(d) can't be determined

Scanned by CamScanner

yoursmehboob.wordpress.com

28. In the given figure, PT is a tangent at P and $ABCP$ is a quadrilateral. $\angle BAP$ is 60°, then the value of $\angle PCB$ is :



(a) 60°
(b) 90°
(c) 120°
(d) data insufficient

29. In the above question (number 28), what is the value of $\angle TPC$?

(a) 30° (b) 60°
(c) 90° (d) can't be determined

30. In the adjoining figure AT and BT are the to two tangents at A and B respectively CD is also a tangent at P.
There are some more circles touching each other and the tangents AT and BT also. Which one of the following is true?



(a) $PC + CT = PD + DT$ (b) $RG + GT = RH + HT$
(c) $PC + QE = CE$ (d) all of these

31. In the adjoining figure O is the centre of the circle. $\angle AOD = 120°$. If the radius of the circle be 'r', then find the sum of the areas of quadrilaterals $AODP$ and $OBQC$:



(a) $\frac{\sqrt{3}}{2}r^2$ (b) $3\sqrt{3}r^2$
(c) $\sqrt{3}r^2$ (d) none of these

32. In a right angled triangle ABC, CD is the perpendicular on the hypotenuse AB. Which of the following is correct?



(a) $CD = \frac{AC \times BC}{AB}$
(b) $AD = \frac{AC \times AC}{AB}$
(c) $BD = \frac{BC \times BC}{AB}$
(d) All of the the above

33. In the triangle ABC, MN is parallel to AB. Area of trapezium $ABNM$ is twice the area of triangle CMN. What is ratio of $CM : AM$?



(a) $\frac{1}{\sqrt{3}+1}$ (b) $\frac{\sqrt{3}-1}{2}$
(c) $\frac{\sqrt{3}+1}{2}$ (d) none of these

34. In the given figure $AD = AE$, $\angle BDE = 100°$, then what is the value of $\angle DBC + \angle BCE$?



(a) 200°
(b) 160°
(c) 80°
(d) can't be determined

35. In the given quadrilateral $ABCD$, $AB = 15$ cm, $BC = 20$ cm and $AD = 7$ cm, $\angle ABC = \angle ADC = 90°$. Find the length of side CD :



(a) 12 cm
(b) 18 cm
(c) 24 cm
(c) none of the above

36. There are two circles each with radius 5 cm. Tangent AB is 26 cm. The length of tangent CD is :



(a) 15 cm (b) 21 cm
(c) 24 cm (d) can't be determined

37. One of diagonal of a parallelogram is 10 cm and an angle of the parallelogram is $\pi/4$. If its height be 8 cm then find the area of the parallelogram :

(a) 112 cm^2 (b) 88 cm^2
(c) 92 cm^2 (d) 104 cm^2

38. ABC is a triangle in which $\angle CAB = 80°$ and $\angle ABC = 50°$, AE, BF and CD are the altitudes and O is the orthocentre. What is the value of $\angle AOB$?



(a) 65°
(b) 70°
(c) 50°
(d) 130°

39. ABC is a triangle in which 35 times the smallest angle is equal to the 26 times largest angle. What is the measure of the second largest angle?

(a) 63° (b) 58°
(c) 70° (d) 42°

40. In the adjoining figure O is the centre of the circle and AB is the diameter. Tangent PQ touches the circle at D. $\angle BDQ = 48°$. Find the ratio of $\angle DBA : \angle DCB$:



(a) $\frac{22}{7}$
(b) $\frac{7}{22}$
(c) $\frac{7}{12}$
(d) can't be determined

41. In the given diagram O is the centre of the circle and CD is a tangent. $\angle CAB$ and $\angle ACD$ are supplementary to each other $\angle OAC = 30°$. Find the value of $\angle OCB$:



(a) 30°
(b) 20°
(c) 60°
(d) none of the above

Scanned by CamScanner

yoursmahboob.wordpress.com

42. In the given diagram an incircle DEF is circumscribed by the right angled triangle in which $AF = 6$ cm and $EC = 15$ cm. Find the difference between CD and BD :



(a) 1 cm
(b) 3 cm
(c) 4 cm
(d) can't be determined

43. In the adjoining figure, a star is shown. What is the sum of the angles A, B, C, D and E?



(a) 120°
(b) 180°
(c) 240°
(d) can't be determined

44. $ABCD$ is a rectangle of dimensions 6 cm × 8 cm. DE and BF are the perpendiculars drawn on the diagonal of the rectangle. What is the ratio of the shaded to that of unshaded region?



(a) 7 : 3
(b) 16 : 9
(c) $4 : 3\sqrt{2}$
(d) data insufficient

45. In the adjoining figure 'O' is the centre of circle. $\angle CAO = 25°$ and $\angle CBO = 35°$. What is the value of $\angle AOB$?



(a) 55°
(b) 110°
(c) 120°
(d) data insufficient

46. In the given diagram $ABCD$ is a cyclic quadrilateral $\angle OCB = 50°$ and $\angle BOC = 110°$. Find the value of $\angle DAO$:



(a) 20°
(b) 30°
(c) 50°
(d) can't be determined

47. ABC and CDE are right angled triangle. $\angle ABC = \angle CDE = 90°$, D lies on AC and E lies on BC. $AB = 24$ cm, $BC = 60$ cm. If $DE = 10$ cm, then CD is :



(a) 28 cm
(b) 35 cm
(c) 25 cm
(d) can't be determined

48. In the above question (number 48) what is the ratio of $CE : BE$?

(a) $\sqrt{29} : (12 - \sqrt{29})$
(b) $12 : \sqrt{29}$
(c) $7 : \sqrt{21}$
(d) none of these

49. In the given diagram ΔABC is an isosceles right angled triangle, in which a rectangle is inscribed in such a way that the length of the rectangle in twice of breadth. Q and R lie on the hypotenuse and P, S lie on the two different smaller sides of the triangle. What is the ratio of the areas of the rectangle and that of triangle :



(a) $\sqrt{2} : 1$
(b) $1 : \sqrt{2}$
(c) 1 : 2
(d) $\sqrt{3} : 2$

50. An n sided polygon has 'n' diagonals, then the value of n is :

(a) 4
(b) 6
(c) 7
(d) 5

51. How many distinct equilateral triangles can be formed in a regular nonagon having at two of their vertices as the vertices of nonagon?

(a) 72
(b) 36
(c) 66
(d) none of these

52. ABC is a triangle in which D, E and F are the mid-points of the sides AC, BC and AB respectively. What is the ratio of the area of the shaded to the unshaded region in the triangle?



(a) 1 : 1
(b) 3 : 4
(c) 4 : 5
(d) none of the above

53. Three circles each of units radius intersects each other at P, Q and R. P, Q and R are the centres of the three circles. What is the sum of length of the arcs PQ, QR and PR ?

(a) $\sqrt{3}\pi$
(b) $2\sqrt{2}\pi$
(c) π
(d) none of these

54. ABC is an isosceles triangle in which $AB = AC$ and $(\angle A) = 2(\angle B)$. $AB = 4$ cm. What is the ratio of inradius to the circumradius?



(a) 1 : 2
(b) $(\sqrt{2} - 1) : 1$
(b) $1 : (2\sqrt{2} - 1)$
(c) none of the above

Scanned by CamScanner

yourshahbaab.wordpress.com

LEVEL (2)

1. The semiperimeter of a right angled triangle is 126 cm and the shortest median is 53 cm. What is the area of a triangle which has the largest median as its longest side?
(a) 1560 cm^2 (b) 1260 cm^2
(c) 1060 cm^2 (d) none of these

2. In an isosceles right angled triangle ABC, $\angle B$ is right angle. Angle bisector of $\angle BAC$ is AN cut at M to the median BO. Point 'O' lies on the hypotenuse. OM is 20 cm, then the value of AB is :
(a) 38.96 cm (b) 24.18 cm
(c) 34.134 cm (d) none of these

3. In a right angled triangle $\angle B$ and $\angle A$ are acute angles. If $\angle A - \angle B = k$, where A and B are integers, then how many integer values can 'k' take?
(a) 80 (b) 88
(c) 45 (d) 89

4. In the given figure 'O' is the centre of the circle SP and TP are the two tangents at S and T respectively. $\angle SPT$ is 50°, the value of $\angle SQT$ is :
(a) 125°
(b) 65°
(c) 115°
(d) none of the above



5. A ladder 6.5 m long is standing against a wall and the difference between the base of the ladder and wall is 5.2 m. If the top of the ladder now slips by 1.4 m, then by how much will the foot of the ladder slip?
(a) 1.2 m (b) 0.8 m
(c) 0.75 (d) can't be determined

6. In a triangle all the three angles A, B, C are in integers, then the number of values that A, B and C can take :
(a) 89 (b) 90
(c) 178 (d) 180

7. In the given figure of circle, 'O' is the centre of the circle $\angle AOB = 130°$. What is the value of $\angle DMC$?
(a) 65°
(b) 125°
(c) 85°
(d) can't be determined



8. In a right angled triangle ABC, $\angle B$ is right angle, side AB is half of the hypotenuse. AE is parallel to median BD and CE is parallel to BA. What is the ratio of length of BC to that of EC?
(a) $\sqrt{2} : 1$ (b) $\sqrt{3} : 2$
(c) $\sqrt{5} : \sqrt{3}$ (d) can't be determined

9. In an equilateral triangle ABC, AO, BO and CO are the angle bisectors meet at the incentre 'O'. D, E and F are the mid-points of AO, BO and CO respectively. A circle with centre 'O' passes through D, E and F. Area of the circle is 3π cm^2. What is the perimeter of triangles (Δ) ABC?
(a) $12\sqrt{3}$ cm (b) 18 cm
(c) $6\sqrt{3}$ cm (d) none of these

10. Two trains Punjab mail and Lucknow mail start simultaneously from Patiyala and Lakhimpur respectively towards each other with the speed of 40 km/h and 60 km/h respectively on the same track Lakhimpur is 500 km due east of Patiyala. A plane starts flying at 200 km/h at the same time from Patiyala to Jalandhar. Jalandhar is 100 km due north of Patiyala. After travelling sometime two trains Punjab mail and Lucknow mail collides with each other. The plane moves continuously to and fro between Patiyala to Jalandhar till the collision of the trains. How far would the plane have travelled?
(a) 100 km (b) 1000 km
(c) 2000 km (d) can't be determined

11. In the above question (number 10) what is the distance between the place of accident and the plane at the moment of accident of two trains?
(a) 200 km (b) 250 km
(c) 400 km (d) data insufficient

12. In the given figure $\angle B$ is right angle. $AD : BD = 3 : 2$ and $CE : BE = 5 : 2$ and $AF : FC = 1 : 1$.
What is the area of ΔABC, if the area of ΔBDE is 20 cm^2?
(a) 40 cm^2
(b) 35 cm^2
(c) 52.5 cm^2
(d) none of the above



13. In a triangle ABC with side $AB = AC$ and $\angle BAC = 20°$, D is a point on side AC and $BC = AD$. Find $\angle DBC$:
(a) 50° (b) 45°
(c) 65° (d) 70°

14. In the adjoining figure $ABCD$, $PQRS$ and $WXYZ$ are three squares. Find number of triangles and quadrilaterals in the figure :
(a) 24 and 16
(b) 28 and 15
(c) 27 and 16
(d) none of the above



15. In the given figure ABC is a triangle in which $CDEFG$ is a pentagon. Triangles ADE and BFG are equilateral triangles each with side 2 cm and $EF = 2$ cm. Find the area of the pentagon :
(a) $8\sqrt{3}$ cm
(b) $7\sqrt{3}$ cm^2
(c) $15\sqrt{3}$ cm^2
(d) 11.28 cm^2



16. $PQRS$ is a quadrilateral which is formed by joining the mid-points of a quadrilateral $ABCD$, such that $\angle A = 75°$, $\angle B = 95°$, $\angle C = 110°$.

Scanned by CamScanner

yoursmahboob.wordpress.com

If $\angle PQR = 90°$, what is the value of $\angle PSR$?
(a) 90° (b) 110°
(c) 60° (d) 75°

17. $ABCD$ is a quadrilateral in which $\frac{z}{y} = \frac{y}{x} = \frac{x}{w} = k$ and k is an integer. Also $\{w, x\} < 90$ and $\{y, z\} > 90$, then the difference between the greatest angle and smallest angle (*i.e.*, $z - w$) is :



(a) 168° (b) 172°
(c) 128° (d) 212°

18. In the adjoining figure 'O' is the centre of the circle and PQ, PR and ST are the three tangents. $\angle QPR = 50°$, then the value of $\angle SOT$ is :



(a) 30° (b) 75°
(c) 65° (d) can't be determined

19. The number of points of intersection of the diagonals of a regular hexagon is :
(a) 10 (b) 15
(c) 18 (d) 19

20. In the adjoining figure $ABCD$, P and R are the mid-points of the sides AB and CD. $ABCD$ is a parallelogram. What is the ratio of the shaded to the unshaded region?



(a) 1/2 (b) 1/3
(c) 1/4 (d) none of these

21. In the adjoining figure $ABCD$ is a rectangle. Find the maximum number of rectangles including the largest possible rectangle :



(a) 16 (b) 7
(c) 18 (d) 24

22. ABC is an isosceles triangle and AC, BC are the tangents at M and N respectively. DE is the diameter of the circle. $\angle ADP = \angle BEQ = 100°$. What is value of $\angle PRD$?



(a) 60°
(b) 50°
(c) 20° (d) can't be determined

23. In the above question if OC is the half of the AB, then the value of $\angle ACB$ is :
(a) 60° (b) 90°
(c) 80° (d) can't be determined

24. In the adjoining figure O is the centre of the circle with radius 'r'. AB, CD and EF are the diameters of the circle. $\angle OAF = \angle OCB = 60°$. What is the area of the shaded region?



(a) $\frac{r^2}{2}\left(\pi - \frac{3\sqrt{3}}{2}\right)$
(b) $\frac{r^2}{2}\left(\pi - \frac{3\sqrt{3}}{4}\right)$
(c) $\frac{r^2}{3}\left(\pi - \frac{2\sqrt{3}}{3}\right)$
(d) data insufficient

25. $ABCD$ is a cyclic quadrilateral. The angle bisector of $\angle A$, $\angle B$, $\angle C$ and $\angle D$ intersect at P, Q, R and S as shown in the figure. These four points form a quadrilateral $PQRS$. Quadrilateral $PQRS$ is a :



(a) square
(b) rhombus
(c) rectangle
(d) cyclic quadrilateral

26. In the adjoining figure the diameter of the larger circle is 10 cm and the smaller circle touches internally the lager circle at P and passes through O, the centre of the larger circle. Chord SP cuts the smaller circle at R and OR is equal to 4 cm. What is the length of the chord SP ?



(a) 9 cm (b) 12 cm
(c) 6 cm (d) $8\sqrt{2}$ cm

27. In the given figure $ABCD$ is a cyclic quadrilateral $DO = 8$ cm and $CO = 4$ cm. AC is the angle bisector of $\angle BAD$. The length of AD is equal to the length of AB. DB intersects diagonal AC at O, then what is the length of the diagonal AC ?



(a) 20 cm (b) 24 cm
(c) 16 cm (d) none of these

28. In the given triangle ABC, the length of sides AB and AC is same (*i.e.*, $b = c$) and $60° < A < 90°$, then the possible length of BC is :



(a) $b < a < 2b$
(b) $\frac{c}{3} < a < 3a$
(c) $b < a < b\sqrt{3}$
(d) $c < a < c\sqrt{2}$

29. In the following figure there is semicircle with centre 'O' and diameter AB ($= 2r$). $PQRS$ is a square of maximum possible area. P and Q lie on the diameter AB and R, S lie on the arc of the semicircle, there are two more squares of maximum possible area $EFGP$ and $CDQH$. What is the sum of lengths of RC and FS?

Scanned by CamScanner

yourSmanboob.wordpress.com



(a) $\sqrt{\frac{2}{5}}(2r)$ (b) $\frac{2\sqrt{2}r}{5}$

(c) $\frac{\sqrt{2}}{5}r$ (d) none of these

30. In the adjoining figure $\angle BAD = a$, $\angle ABC = b$ and $\angle BCD = c$ and $\angle ADC = d$, find the value of $\angle ABC$ in terms of a, c and d :



(a) $c-(a+d)$
(b) $a-(c+d)$
(c) $b-(c+d)$
(d) none of the above

31. In the given diagram CT is tangent at C, making an angle of $\frac{\pi}{4}$ with CD. O is the centre of the circle. $CD = 10$ cm. What is the perimeter of the shaded region (ΔAOC) approximately?



(a) 27 cm (b) 30 cm
(c) 25 cm (d) 31 cm

32. In the given diagram, 'O' is the centre of the circle and AC is the diameter. $\angle ADB$ is 120°. Radius of the circle is 6 cm, what is the area of the triangle ABC?



(a) $18\sqrt{3}$ cm^2
(b) $24\sqrt{3}$ cm^2
(c) 27 cm^2
(d) data insufficient

33. In the given figure ABC is a triangle in which $3AD = CD$ and E lies on BD, $DE = 2BE$. What is the ratio of area of ΔABE and area of ΔABC ?



(a) 1/12 (b) 1/3
(c) 1/2 (d) none of these

34. In the adjoining figure ABC is a right angled triangle, $BDEF$ is a square, $AE = 7.5$ cm and $AC = 18$ cm. What is the area of triangle ABC ?



(a) 76.621 cm^2
(b) 70.054 cm^2
(c) 83.25 cm^2
(d) 90.90 cm^2

35. There are two congruent triangles each with area 198 cm^2. Triangle DEF is placed over triangle ABC in such a way that the centroid of both the triangles coincides with each other and $AB \parallel DE$, as shown in figure, thus forming a star . What is the area of the common region ($PQRSTU$)?



(a) 99 cm^2 (b) 132 cm^2
(c) 148 cm^2 (d) can't be determined

36. What is the sum of all the angles of a 9 pointed star (i.e., $\angle 1 + \angle 2 + \angle 3 + \ldots \angle 8 + \angle 9$) :

(a) 909° (b) 900°
(c) 720° (d) 540°

37. A circle is circumscribed by the rhombus which in turn is made up by joining the mid-points of a rectangle whose sides, 12 cm and16 cm respectively. What is the area of the circle?

(a) $\frac{625}{26}\pi$ (b) $\frac{676}{25}\pi$

(c) $\frac{576}{25}\pi$ (d) can't be determined

38. There are n rectangles each with area 200 cm^2. If the dimensions of each n rectangles are in integers then the value of n is :

(a) 4 (b) 6
(c) 12 (d) none of these

39. There are 8 points on a plane, out of which 4 points lies on the circumference of the same circle and rest 4 points do not lie on a single circumference of a circle and also they are non-collinear. Maximum how many circles can be drawn such that each contains at least three of the given points?

(a) 53 (b) 32
(c) 35 (d) 56

40. ABC is an isosceles triangle a circle is such that it passes through vertex C and AB acts as a tangent at D for the same circle. AC and BC intersects the circle at E and F respectively $AC = BC = 4$ cm and $AB = 6$ cm. Also D is the mid-point of AB. What is the ratio of $EC : (AE + AD)$?



(a) 1 : 2 (b) 1 : 3
(c) 2 : 5 (d) none of these

41. A smaller circle touches internally to a larger circle at A and passes through the centre of the larger circle. O is the centre of the larger circle and BA, OA are of the diameters of the larger and smaller circles respectively. Chord AC intersects the smaller circle at a point D. If $AC = 12$ cm, then AD is :



Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 4 cm (b) 6 cm
(c) 5.6 cm (d) data insufficient

42. In the given figure $ADEC$ is a cyclic quadrilateral, CE and AD are extended to meet at B. $\angle CAD = 60°$ and $\angle CBA = 30°$. $BD = 6$ cm and $CE = 5\sqrt{3}$ cm,
What is the ratio of $AC : AD$?



(a) $\frac{3}{4}$
(b) $\frac{4}{5}$
(c) $\frac{2\sqrt{3}}{5}$
(d) cant' be determined

Directions for the question number 43 and 44 : *In the following diagram A and B are the centres of the two different*



circles. PQR is a common tangent. Points A, B, and R lie on the straight line.
Distance between A and B is 25 cm and the distance between P and Q is 24 cm. Diameter of the larger circle is 24 cm.

43. What is the ratio of $AB : BR$?
(a) 7 : 5 (b) 7 : 6
(c) 7 : 10 (d) data insufficient

44. What is the ratio of area of ΔAPR and ΔBQR ?
(a) 169 : 36 (b) 144 : 25
(c) 625 : 144 (d) can't be determined

45. If $x^2 + y^2 + z^2 = xy + yz + zx$, then the triangle is :
(a) isosceles
(b) right angled
(c) equilateral
(d) scalene



46. In the adjoining figure $ABCD$ is a rectangle in which length is twice of breadth. H and G divide the line CD into three equal parts. Similarly points E and F trisect the line AB. A circle $PQRS$ is circumscribed by a square $PQRS$ which passes through the points E, F, G and H. What is the ratio of areas of circle to that of rectangle?



(a) $3\pi : 7$ (b) $3 : 4$
(c) $25\pi : 72$ (d) $32\pi : 115$

47. In the adjoining figure there are two congruent regular hexagons each with side 6 cm.





What is the ratio of area of ΔBDF and ΔPQR, if P, Q and R are the mid-points of side AF, BC and DE ?
(a) 6 : 5 (b) 7 : 6
(c) 4 : 3 (d) 1 : 1

48. $ABCD$ is a square, in which a circle is inscribed touching all the sides of square. In the four corners of square 4 smaller circles of equal radii are drawn, containing maximum possible area.
What is the ratio of the area of larger circle to that of sum of the areas of four smaller circles ?



(a) $1 : (68 - 48\sqrt{2})$ (b) $1 : 17\sqrt{2}$
(c) $3 : (34 - 12\sqrt{2})$ (d) none of these

49. In the adjoining figure $\angle ACE$ is a right angle there are three circles which just touch each other and AC and EC are the tangents to all the three circles. What is the ratio of radii of the largest circle to that of the smallest circle?



(a) $17 : 12\sqrt{2}$
(b) $1 : (17 - 12\sqrt{2})$
(c) $12 : 17\sqrt{2}$
(d) none of the above

50. In a right angle triangle ABC, $\angle A$ is right angle DE is parallel to the hypotenuse BC and the length of DE is 65% the length of BC, what is the area of ΔADE, if the area of ΔABC is 68 cm^2 ?



(a) 27.83 cm^2
(b) 41.6 cm^2
(c) 28.73 cm^2
(d) none of the above

51. In the adjoining figure three congruent circles are touching each other. Triangle ABC circumscribes all the three circles. Triangle PQR is formed by joining the centres of the circle. There is a third triangle DEF. Points A, D, P and B, E, Q and C, F, R lie in the same straight lines respectively.



Scanned by CamScanner

yoursmahboob.wordpress.com

What is the ratio of perimeters of $\Delta ABC : \Delta DEF$ ΔPQR

(a) $3\sqrt{2} : 2\sqrt{2} : 1$ (b) $2(4+\sqrt{3}) : (2+\sqrt{3}) : \sqrt{3}$

(c) $2(1+\sqrt{3}) : (2+\sqrt{3}) : 2$ (d) $2(1+\sqrt{3}) : 2\sqrt{3} : \sqrt{3}$

52. In the given figure, P and Q are the mid-points of AC and AB. Also, $PG = GR$ and $HQ = HR$.

What is the ratio of area of ΔPQR : area of ΔABC?



(a) $\frac{1}{2}$

(b) $\frac{2}{3}$

(c) $\frac{3}{5}$

(d) none of the above

53. A trapezium $PQRS$ inscribes a circle which touches the circle at M, A, N, B, Radius of circle is 10 cm. The length of each non-parallel side is 21 cm. What is the perimeter of trapezium?

(a) 82 cm (b) 84 cm

(c) 85.5 cm (d) can't be determined

54. In the given diagram, river PQ is just perpendicular to the national highway AB. At a point B highway just turns at right angle and reaches to C. $PA = 500$ m and $BQ = 700$ m and width of the uniformly wide river (*i.e.*, PQ) is 300m. Also $BC = 3600$ m. A bridge has to be constructed across the river



perpendicular to its stream in such a way that a person can reach from A to C via bridge covering least possible distance. PQ is the widthness of the river, then what is the minimum possible required distance from A to C including the length of bridge?

(a) 4100 m (b) 3900 m

(c) $3000\sqrt{2}$ m (d) none of these

55. In a triangle ABC, AD is the angle bisector of $\angle BAC$ and $\angle BAD = 60°$. What is the length of AD ?



(a) $\frac{b+c}{bc}$

(b) $\frac{bc}{b+c}$

(c) $\sqrt{b^2+c^2}$

(d) $\frac{(b+c)^2}{bc}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-12.1

1. (c)	2. (c)	3. (b)	4. (b)	5. (b)	6. (a)	7. (d)	8. (a)	9. (a)	10. (b)
11. (a)	12. (c)	13. (b)	14. (b)	15. (d)	16. (b)	17. (b)	18. (b)	19. (a)	20. (c)
21. (b)	22. (c)	23. (c)	24. (b)	25. (c)	26. (a)	27. (c)	28. (c)	29. (a)	30. (b)
31. (c)	32. (a)	33. (a)	34. (c)	35. (a)	36. (b)	37. (b)	38. (c)	39. (b)	40. (a)
41. (c)	42. (c)	43. (a)	44. (b)	45. (b)					

INTRODUCTORY EXERCISE-12.2

1. (b)	2. (b)	3. (c)	4. (d)	5. (a)	6. (c)	7. (d)	8. (d)	9. (b)	10. (b)
11. (b)	12. (c)	13. (d)	14. (b)	15. (b)	16. (b)	17. (c)	18. (b)	19. (d)	20. (b)
21. (a)	22. (d)	23. (c)	24. (b)	25. (c)	26. (c)	27. (c)	28. (a)	29. (a)	30. (b)
31. (c)	32. (c)	33. (d)	34. (d)	35. (a)	36. (d)	37. (b)	38. (d)	39. (c)	40. (d)
41. (c)	42. (a)	43. (c)	44. (c)	45. (b)	46. (c)	47. (a)	48. (a)	49. (c)	50. (c)
51. (a)	52. (a)	53. (a)	54. (c)	55. (a)	56. (a)	57. (a)	58. (b)	59. (b)	60. (c)
61. (c)	62. (b)	63. (c)	64. (b)	65. (b)	66. (c)	67. (c)	68. (a)	69. (d)	70. (a)
71. (b)	72. (c)	73. (c)	74. (a)	75. (b)	76. (c)	77. (c)	78. (b)	79. (c)	80. (d)
81. (b)	82. (b)	83. (a)	84. (c)	85. (b)	86. (c)	87. (a)	88. (d)	89. (c)	90. (b)
91. (d)	92. (c)	93. (c)	94. (c)	95. (b)	96. (c)	97. (b)	98. (a)	99. (b)	100. (d)

INTRODUCTORY EXERCISE-12.3

1. (b)	2. (b)	3. (b)	4. (a)	5. (a)	6. (b)	7. (c)	8. (c)	9. (b)	10. (c)
11. (b)	12. (b)	13. (a)	14. (b)	15. (a)	16. (b)	17. (c)	18. (c)	19. (a)	20. (a)
21. (c)	22. (b)	23. (c)	24. (a)	25. (b)	26. (a)	27. (a)	28. (b)		

INTRODUCTORY EXERCISE-12.4

1. (d)	2. (b)	3. (b)	4. (d)	5. (d)	6. (b)	7. (c)	8. (d)	9. (c)	10. (c)

INTRODUCTORY EXERCISE-12.5

1. (b)	2. (a)	3. (c)	4. (c)	5. (a)	6. (c)	7. (a)	8. (c)	9. (c)	10. (c)
11. (d)	12. (a)	13. (b)	14. (d)	15. (c)	16. (b)	17. (a)	18. (c)	19. (a)	20. (c)
21. (b)	22. (b)	23. (c)	24. (c)	25. (b)	26. (b)	27. (b)	28. (a)	29. (c)	30. (b)
31. (b)	32. (b)	33. (c)	34. (c)	35. (c)	36. (d)	37. (b)	38. (c)	39. (b)	40. (b)
41. (c)	42. (d)	43. (a)	44. (b)	45. (a)	46. (a)	47. (c)	48. (d)	49. (a)	50. (c)
51. (b)	52. (b)	53. (d)	54. (a)	55. (c)	56. (b)	57. (a)	58. (d)	59. (c)	60. (c)

LEVEL-1

1. (c)	2. (d)	3. (a)	4. (c)	5. (d)	6. (b)	7. (a)	8. (c)	9. (c)	10. (c)
11. (d)	12. (d)	13. (c)	14. (b)	15. (c)	16. (a)	17. (b)	18. (a)	19. (b)	20. (b)
21. (b)	22. (d)	23. (c)	24. (c)	25. (b)	26. (b)	27. (c)	28. (c)	29. (d)	30. (d)
31. (c)	32. (d)	33. (c)	34. (b)	35. (c)	36. (c)	37. (a)	38. (d)	39. (b)	40. (b)
41. (a)	42. (a)	43. (b)	44. (b)	45. (c)	46. (a)	47. (c)	48. (a)	49. (c)	50. (d)
51. (c)	52. (a)	53. (c)	54. (b)						

LEVEL-2

1. (b)	2. (d)	3. (d)	4. (c)	5. (b)	6. (c)	7. (d)	8. (b)	9. (b)	10. (b)
11. (a)	12. (d)	13. (d)	14. (b)	15. (b)	16. (a)	17. (a)	18. (c)	19. (d)	20. (b)
21. (c)	22. (c)	23. (b)	24. (a)	25. (d)	26. (c)	27. (a)	28. (d)	29. (a)	30. (a)
31. (a)	32. (a)	33. (a)	34. (a)	35. (b)	36. (b)	37. (c)	38. (b)	39. (a)	40. (b)
41. (b)	42. (a)	43. (a)	44. (b)	45. (c)	46. (c)	47. (c)	48. (a)	49. (b)	50. (c)
51. (c)	52. (a)	53. (b)	54. (a)	55. (b)					

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 12.1

1. $4x + 5x = 180° \Rightarrow x = 20$
($4x$ and $5x$ are linear pair angles)

2. $(5x + 12) + 3x = 180° \Rightarrow x = 21°$

3. $105 + 3x = 180 \Rightarrow x = 25$
and $y + 90 + 2x = 180°$
$\Rightarrow y = 40°$
$\therefore x + y = 65°$

4. $2x + 2y = 180$
$\Rightarrow x + y = 90°$
$\therefore \angle COD = 90°$

5. $\angle DOE = 180 - (40 + 31) = 109°$
and $\angle BOF = 40°$ ($\because \angle AOE = \angle BOF$)
$\therefore \angle BOC = \angle BOF + \angle FOC$
$= 40 + 109$ ($\because \angle FOC = \angle DOE$)
$= 149°$

6. $2y + 3x = 180 \Rightarrow y = 36°$ ($\because x = 36°$)
or $x + 4y = 180° \Rightarrow y = 36°$ ($\because x = 36°$)

7. $(2x + 17) + (x + 4) = 90°$
$\Rightarrow 3x + 21 = 90°$
$\Rightarrow x = 23°$

8. $(5y + 62)° + (22° + y) = 180$
$\Rightarrow 6y + 84 = 180$
$\Rightarrow y = 16°$

9. $13x + 5x = 180° \Rightarrow x = 10°$
$\therefore 13x = 130°$

10. Let the angle be x, then its complementary angle be $(90 - x)$
$\therefore x - \frac{(90 - x)}{2} = 30 \Rightarrow x = 50$

Alternatively: The best way is to solve through options.

11.



(Pair of alternate angles)

12. $\frac{AG}{BH} = \frac{CE}{DF}$

$\frac{120}{100} = \frac{30}{DF} \Rightarrow DF = 25\,\text{cm}$

13. $65°50' + x = 90° = 89°\,60'$ ($1° = 60'$)
$\Rightarrow x = 89°60' - 65°50' = 24°\,10'$

14. $123°45' + x = 180° = 179°60'$ ($1° = 60'$)
$\Rightarrow x = 179°\,60' - 123°\,45'$
$\Rightarrow x = 56°\,15'$

15. $x + y = 90° \Rightarrow x < 90°$
If $y \neq 0$ *i.e.*, $y > 0$
and $y < 90°$ if $x \neq 0$ *i.e.*, $x > 0$

16. Let he angle be x, then is supplement be $(180° - x)$
$\therefore x = \frac{1}{5}(180° - x) \Rightarrow x = 30°$

Alternatively: Go through options.
$30 = \frac{1}{5}(180° - 30°)$

17. $a > \frac{90°}{6} \Rightarrow a > 15°$
$\because a + b = 180°$
$\therefore b < 165°$ ($\because a > 15°$)

18. $\because AC = BC$
and $AD = BD$
and CD is common
$\therefore \Delta CDA$ is similar to ΔCDB and
AB is a straight line
$\therefore \angle CDA = \angle CDB = 90°$



20.



21. $\angle ABP = \angle CDR = 100°$
$\therefore y = 80°$ ($\because \angle CDR + \angle CDS = 180°$)

22. $\angle APO = 42°$ and $\angle CQO = 38°$
$\angle POQ = \angle PON + \angle NOQ$
$= \angle APO + \angle OQC = 42° + 38° = 80°$

23. $\angle XYB = \angle YBC$ and $\angle XYB = \angle BYC$
$\Rightarrow \angle YBC = \angle BYC$

24. $\angle PGH = 80° \Rightarrow \angle QGH = 100°$
$\angle QHD = 120° \Rightarrow \angle CHQ = 60°$
$\therefore \angle x + 100 + 60 = 180°$
$\Rightarrow x = 20°$

25. $\angle z = 180° - 110 = 70°$ ($\because \angle QAC = \angle BCA$)
and $60° + y° + z° = 180°$
$\therefore y = 180° - (70° + 60°)$
$y = 50°$

26. $\angle BCD = \angle BCM + \angle DCM$
$= \angle ABC + \angle EDC$
$= 67° + 23° = 90°$



(Draw a line parallel to AB or DE through C.)

Scanned by CamScanner

yoursmahboob.wordpress.com

27. $a + x = 180°$

$c + x = b \Rightarrow x = b - c$



$\therefore \quad a + (b - c) = 180°$

$\Rightarrow \quad a + b - c = 180°$

28. $\angle x = \angle ABC = \angle CDG = 180° - 138° = 42°$

29. Use the same method as in question number 27.

i.e., $(a + b - c) = 180°$

$\Rightarrow \quad 100° + (x + 10°) - 30° = 180°$

$\Rightarrow \quad x = 100°$

Alternatively :



$\therefore \quad x + 10° = 80° + 30°$

$\Rightarrow \quad x = 100°$

30. $\angle PQR = \angle QRS$

$55° = \angle QRS$

$55° = \angle QRL + \angle LRS$

$55° = 30° + \angle LRS$

$\Rightarrow \quad \angle LRS = 25°$



31. $\angle ABC = 180° - (40° + 65°)$

$\angle ABC = 75°$

and $\angle DCF = \angle ABC = 75°$

$\therefore \quad \angle EDC = 180° - \angle DCF = 105°$

32. Extend CD to M, then

$\angle DME = \angle ABE = 100°$

$\angle MED = 25°$

$\therefore \angle MDE = 180° - (100° + 25°)$

$= 55°$

$\therefore \angle CDE = 180° - 55° = 125°$



33. $\angle CEF = \angle ABF = 70°$

$\therefore \quad \angle FED = 180° - 70° = 110°$

$\angle EDF + \angle DFE + \angle FED = 180°$

$\therefore \quad \angle FDE = 180° - (110° + 20°) = 50°$

34. $\angle BAO = 180° - (60° + 35°) = 85°$

$\angle AOB = 180° - (85° + 20°) = 75°$

35. $\angle AEP = \angle CDP = 34°$

$\angle AEP + \angle BEF + \angle DEF = 180°$

$34° + 78° + \angle DEF = 180°$

$\Rightarrow \quad \angle DEF = 68°$

36. $\angle AKH = \angle KHD = 25°$

$\angle EGH = \angle AKL = 180° - 60° = 120°$

$\therefore \quad \angle HKL = 120° + 25° = 145°$

38.



$\angle ABO = 118°$

$\therefore \quad MOB = 180° - 118° = 62°$

$\therefore \quad \angle MOD = 152° - 62° = 90°$

$\therefore \quad \angle ODC = 180° - 90° = 90°$

39. Let $\angle BMN = 2x$ and $\angle DNM = 2y$

$\therefore \quad 2x + 2y = 180°$



$\Rightarrow \quad x + y = 90°$

$\therefore \quad \angle MPN = 180° - 90° = 90°$

40.

Equal



$x \neq 90°$

Equal and Supplementary



$x = 90°$

41. $\angle BEF = 2\angle BEL = 70°$

$\therefore \quad \angle CFQ = \angle EFL = 180° - 70° = 110°$



44. ${}^4C_3 = \dfrac{4!}{3!1!} = \dfrac{4 \cdot 3 \cdot 2 \cdot 1}{3 \cdot 2 \cdot 1 \cdot 1} = 4$

45. ${}^4C_2 = \dfrac{4!}{2!2!}$

$= \dfrac{4 \cdot 3 \cdot 2 \cdot 1}{(2 \cdot 1) \cdot (2 \cdot 1)} = 6$



Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 12.2

1. The sum of the smaller sides cannot be equal to or less than the largest side.

2. $12^2 > 8^2 + 6^2 \Rightarrow$ obtuse triangle

3. Sum of exterior angles $= 360°$

4. $\angle ACD = \angle CBA + \angle BAC = 70° + 40° = 110°$

5. $\angle ABC + \angle ACB < 90°$

6. $x + 4x + 7x = 180°$

$\Rightarrow \quad x = 15°$

$\therefore \quad 7x = 105°$

7. $\angle OBC + \angle OCB = \frac{70}{2} + \frac{30}{2} = 50°$

$\therefore \quad \angle BOC = 180° - 50° = 130°$

8. $\angle BFC = 90° - \frac{1}{2}(\angle A)$

$= 90° - \frac{1}{2}[180° - (80° + 30°)] = 55°$

10. Prove with the help of similarity.

11. Prove with the help of the similarity.

12. $\Delta ABC \sim \Delta DEF$



$\therefore \quad \frac{AB}{BC} = \frac{DE}{EF}$

$\frac{9}{6} = \frac{DE}{12}$

$\Rightarrow \quad DE = 18$ cm

13. $\frac{AB}{AC} = \frac{BD}{CD} = \frac{5}{7}$

(By angle bisector theorem)



15. AB is hypotenuse and AD is perpendicular in ΔABD,

$\therefore \quad AB > AD$



16. $x^2 + (x - 17)^2 = 25^2$ (Using Pythagorus theorem)

$\therefore \quad x = 24$ cm

$\therefore$ Altitude + Base $= 24 + 7 = 31$ cm



17. Go back to the basics.

18. $\angle ACB = 180° - 100° = 80°$

and $\angle BAC + \angle ABC = 180° - 80° = 100°$

$\therefore \quad \angle ABC = 50°$ ($\because \angle BAC = \angle ABC$)

20. $\cos A = \frac{b^2 + c^2 - a^2}{2bc}$ (cosine rule)

$\frac{1}{2} = \frac{b^2 + c^2 - a^2}{2bc}$ ($\because \cos 60° = 1/2$)

$\therefore \quad a^2 = b^2 + c^2 - bc$

21. $\cos C = \frac{a^2 + b^2 - c^2}{2ab}$

$-\frac{1}{2} = \frac{a^2 + b^2 - c^2}{2ab}$

$\Rightarrow \quad c^2 = a^2 + b^2 + ab$

22. $\frac{1}{p^2} = \frac{1}{a^2} + \frac{1}{b^2}$ (Apply similarity of triangles)



27.



30. $CD = \frac{AC \times BC}{AB}$

or $\frac{1}{(CD)^2} = \frac{1}{(AC)^2} + \frac{1}{(BC)^2}$

32. $AB^2 = BD^2 + AD^2$ (Pythagorus theorem)

$a^2 = h^2 + \left(\frac{a}{2}\right)^2$

$\Rightarrow \quad h^2 = \frac{3}{4}a^2 \Rightarrow h = \frac{\sqrt{3}}{2}a$

$\Rightarrow \quad \frac{a}{h} = \frac{2}{\sqrt{3}}$



33. There are 4 congruent triangles.

Hence, $A(\Delta ABC) = 6 \times 4 = 24$ cm^2



34. $BD = \frac{AB \times BC}{AC}$

$= \frac{6 \times 6}{6\sqrt{2}} = 3\sqrt{2}$ cm



36. $\angle BOC = 90° + \frac{1}{2}\angle A$

$= 90° + 40° = 130°$

Scanned by CamScanner

yoursmahboob.wordpress.com

37.



42.



i.e.,



BQ is a transversal of PQ and BC.

45. Apply Pythagorus theorem.

46. Apply Pythagorus theorem.

47.



48. $\frac{BD}{CD} = \frac{(AB)^2}{(AC)^2}$



49. Apply Pythagorus theorem



50. $EF = 3$ cm $\quad \therefore BC = 6$ cm

$FD = 4$ cm $\quad \therefore AC = 8$ cm

$AB = 10$ cm $\quad \therefore DE = 5$ cm



51.



52. $\frac{AB}{AC} = \frac{AD}{AE}$

$\frac{3.6}{2.4} = \frac{2.1}{AE}$

$\Rightarrow \quad AE = 1.4$ cm



54. $\angle EAB = \angle OAB = 60°$

$\angle ABD = 45°$

$\therefore \quad \angle AOB = 180° - (60° + 45°) = 75°$

55. $\angle LBN = \angle BAC = \angle BCA = 70°$

$\therefore \quad \angle ABC = 180° - (70° + 70°) = 40°$

56. $\angle ECB = 60° + 90° = 150°$

$\therefore \quad \angle CEB + \angle EBC = 180° - 150° = 30°$

$\therefore \quad \angle BEC = 15°$ $\quad (\because \angle BEC = \angle EBC)$

$\therefore \quad \angle DEC = 60°$

$\therefore \quad \angle DEM = 60° - 15° = 45°$

58. $\angle ACB = 42° = \angle ECD$

$\therefore \quad \angle CED = 180° - (58° + 42°) = 80° = \angle FEG$

$\therefore \quad \angle FGE = 180° - (66° + 80°) = 34°$

59. $\angle BAD = 70°$

$\therefore \quad \angle BDA = 180° - (70° + 50°) = 60°$

60. $\frac{2x}{x} = \frac{3y + 8}{2y} \Rightarrow y = 8$

$\therefore \quad x = 2y = 16$

61. $\angle BCD = 27°$

$\angle BDC = 180° - (27° + 27°) = 126°$

$\therefore \quad \angle ADC = 54° = \angle DAC$

$\therefore \quad \angle ACD = 180° - (54° + 54°) = 72°$

62.



63. By mid-point theorem

64. $\frac{PB}{BR} = \frac{AP}{AQ}$

$\frac{PB}{BR} = \frac{2\sqrt{2}}{3\sqrt{2}} = \frac{2}{3}$

$\because \quad \frac{PB}{BR} = \frac{2x}{3x}$

$\therefore \quad BR = 6$ cm

66. Apply similarity of triangles

67. Apply similarity of triangles

$\Delta ADB \sim \Delta CDA$

71. $\Delta ABD \cong \Delta CBD$

73.





$AC = \sqrt{AB^2 + BC^2}$

74.



75. $BD = 2DF$

$AB^2 = BF^2 + AF^2$

and $\quad AD^2 = DF^2 + AF^2$



Scanned by CamScanner

yoursmanboob.wordpress.com

76. $\dfrac{A(\Delta ANC)}{A(\Delta ANB)} = \dfrac{\frac{AN \times NC}{2}}{\frac{AN \times BN}{2}}$

$= \dfrac{NC}{NB} = \dfrac{\frac{(12 \times 12)}{13}}{\frac{5 \times 5}{13}} = \dfrac{144}{25}$



77. $\dfrac{AB}{BC} = \dfrac{PQ}{QR}$

$\dfrac{15}{10} = \dfrac{PQ}{60}$



$\Rightarrow$ $PQ = 90$ cm

78. 16 : 81

79. $\dfrac{BC}{PQ} = \dfrac{AC}{AP} = \dfrac{AB}{AQ}$

80. $\dfrac{3}{x-3} = \dfrac{x-5}{3x-19}$

$\Rightarrow$ $x = 8$ or 9

81. $h = \dfrac{\sqrt{3}}{2}\text{ side} = \dfrac{\sqrt{3}}{2} \times 2a = a\sqrt{3}$

82. $\dfrac{AB}{AC} = \dfrac{BD}{CD}$

$\Rightarrow$ $\dfrac{5}{AC} = \dfrac{2}{3}$

$\Rightarrow$ $AC = 7.5$ cm

83. $\dfrac{AB}{QR} = \dfrac{PB}{PR}$

$\dfrac{3}{9} = \dfrac{PB}{6} \Rightarrow PB = 2$ cm

84. $\dfrac{AO}{BO} = \dfrac{AQ}{BP}$

$\dfrac{10}{6} = \dfrac{AQ}{9} \Rightarrow AQ = 15$ cm

85. $\dfrac{AB}{AC} = \dfrac{AD}{AE}$

$\dfrac{12}{15} = \dfrac{6}{AE}$

$\therefore$ $AE = 7.5$ cm

86. $AB = AC$ and $AD = CD$

$\therefore$ $AB = 2AD$

Now, since AD is a tangent

$\therefore$ $AD^2 = AP \times AB$

$\left(\dfrac{AB}{2}\right)^2 = AP \times AB$

$\Rightarrow$ $AB = 4AP$



87. $AC = 5$ cm

$AD = \dfrac{3\sqrt{5}}{2}$ cm



$AE = BE$ and $BD = CD$

$AB^2 = AC^2 - BC^2 = 25 - BC^2$

and $AB^2 = AD^2 - BD^2 = \left(\dfrac{3\sqrt{5}}{2}\right)^2 - BD^2$

$= \dfrac{45}{4} - \dfrac{BC^2}{4}$

From eq. (1) and (2)

$BC^2 = \dfrac{55}{3}$

Now, from eq. (1)

$AB^2 = 25 - \dfrac{55}{3} = \dfrac{20}{3}$

Also $CE^2 = BE^2 + BC^2$

$= \left(\dfrac{1}{2}AB\right)^2 + BC^2$

$= \dfrac{AB^2}{4} + BC^2 = CE^2$

$= \dfrac{5}{3} + \dfrac{55}{3} = \dfrac{60}{3} = 20$

$\therefore$ $CE = 2\sqrt{5}$ cm

88. By Apollonius theorem

$AB^2 + AC^2 = 2(AD^2 + BD^2)$

$100 + 196 = 2(AD^2 + 36)$

$\Rightarrow$ $AD^2 = 112$

$\therefore$ $AD = 4\sqrt{7}$

Now, since $\dfrac{AG}{GD} = \dfrac{2}{1}$

$\Rightarrow$ $AG = \dfrac{2}{3}AD$

$\therefore$ $AG = \dfrac{2}{3} \times 4\sqrt{7} = \dfrac{8}{3}\sqrt{7}$ cm



89. $\because$ AM is the median of a right angled triangle.

$\therefore$ $AM = \dfrac{BC}{2} = \dfrac{25}{2}$



Scanned by CamScanner

yoursmahboob.wordpress.com

and $AD = \frac{AB \times AC}{BC} = \frac{7 \times 24}{25}$

$\therefore \quad \frac{AD}{AM} = \frac{7 \times 24 \times 2}{25 \times 25} = \frac{336}{625}$

90. $\Delta BED \sim \Delta BAC$

$\therefore \quad \frac{BE}{BA} = \frac{ED}{AC} = \frac{BD}{BC} = \frac{1}{2}$

$\therefore \quad \frac{A(\Delta BED)}{A(\Delta BAC)} = \left(\frac{1}{2}\right)^2 = \frac{1}{4}$

$\therefore \quad A(\Delta BDE) = 7.5\,cm^2$



91. Apply Pythagorus theorem.

NOTE The sides given in option (d) cannot form any type of triangle.

92. $\frac{AB}{BD} = \frac{AC}{CD}$

$\frac{12}{BC + CD} = \frac{8}{CD}$

$\frac{12}{4 + CD} = \frac{8}{CD} \Rightarrow CD = 8\,cm$

93. $AB^2 + AC^2 = 2\left[AD^2 + \left(\frac{BC}{2}\right)^2\right]$

(Appollonius theorem)

$2500 = 2\left[625 + \left(\frac{BC}{2}\right)^2\right]$



$\Rightarrow \quad BC = 50\,cm$

94. $\angle BAC = 15°$

$\therefore \quad \angle BCA = 15° \quad (\because AB = BC)$

$\therefore \quad \angle ABC = 180° - (15° + 15°) = 150°$

$\therefore \quad \angle ABD = 30° \quad (180° - 150°)$

$\therefore \quad \sin 30° = \frac{AD}{AB}$

$\frac{1}{2} = \frac{AD}{AB} \Rightarrow AD = 5\,cm \quad (\because AB = 10\,cm)$

$\therefore \quad$ Area of $\Delta ABC = \frac{1}{2} \times BC \times AD$

$= \frac{1}{2} \times 10 \times 5 = 25\,cm^2$

95. $AB^2 + AC^2 = 2(AD^2 + BD^2)$



$\therefore \quad 225 + 625 = 2(AD^2 + 81)$

$\Rightarrow \quad AD^2 = 344$

$\Rightarrow \quad AD = 2\sqrt{86}$ and $GD = \frac{1}{3}AD$

$\therefore \quad GD = \frac{2}{3}\sqrt{86}\,cm$

96. $\angle BDE = 115°$

$\therefore \quad \angle ADE = 65°$

and $\angle AED = 75°$

$\therefore \quad \Delta AED \sim \Delta ABC$

$\therefore \quad \frac{DE}{BC} = \frac{AE}{AB} = \frac{AD}{AC}$

$\therefore \quad \frac{2}{3} = \frac{10}{AB}$

$\Rightarrow \quad AB = 15\,cm$

97. For the given perimeter of a triangle the maximum area is enclosed by an equilateral triangle.

$\therefore \quad 3a = 24\,cm$

$\Rightarrow \quad a = 8\,cm$

$\therefore \quad$ Area $= \frac{\sqrt{3}}{4}a^2$

$= \frac{\sqrt{3}}{4} \times (8)^2 = 16\sqrt{3}\,cm^2$



98. $\Delta ADE \sim \Delta ACB$ (A-A-A property)

$\therefore \quad \frac{AE}{AB} = \frac{AD}{AC}$

$\frac{10}{20} = \frac{12}{AC} \Rightarrow AC = 24\,cm$

$EC = AC - AE = 24 - 10 = 14\,cm$

99. $\angle ACD = \angle ADC = x$

$\therefore \quad \angle CAD = (180° - 2x)$

$\angle ABC = \angle BAC = \frac{x}{2}$

$(\because \angle ABC + \angle BAC = \angle ACD = x)$

$\therefore \quad \angle BAC + \angle CAD + 81° = 180°$

$\therefore \quad \frac{x}{2} + (180° - 2x) + 81° = 180°$

$\therefore \quad \frac{3}{2}x = 81° \Rightarrow x = 54°$

Alternatively: Applying the same process go through options.

100. It is value (side) dependent *i.e.*, it is different for different triangles unlike in equilateral triangle.

Scanned by CamScanner

yoursmanhoob.wordpress.com

INTRODUCTORY EXERCISE 12.3

1. $x + 2x + 3x + 4x = 360$

$\Rightarrow \quad x = 36$

$\therefore$ The angles of quadrilateral (in order) are

$36°, 72°, 108°, 144°$



Since opposite angles are supplementary, therefor $AB \| CD$. Hence it is a trapezium.

2. $3x + 4x + 5x + 6x = 360°$

$\Rightarrow \quad x = 20$

$\therefore \quad 6x = 120°$

Hence, the largest angle of a quadrilateral is 120°.

3.



4. $\angle DAB = 2x$

$\angle ABC = 2y$

$2x + 2y = 180$

$x + y = 90°$

i.e., $\angle PAB + \angle PBA = 90°$

$\therefore \quad \angle APB = 90°$



5. Prove that opposite sides are parallel, and diagonals are equal. Also all the interior angles are right angle.

6. $\angle BCE = 102°$ and $\angle ECD = 60°$

$\therefore \quad \angle BCD = 102° + 60° = 162°$

7. $90°$

$\because \quad \Delta ADQ \cong \Delta BAP$

$\angle DCR = 90°$

$\angle CDR$ and $\angle CRP$ are supplementary

$\therefore \quad \angle DCR + \angle DRP = 180°$

$\therefore \quad \angle DRP = 90°$



8. Area of $\Delta SXP = \dfrac{(SP) \times (AX)}{2}$

$A\,(\Delta RXQ) = \dfrac{(RQ) \times (BX)}{2}$

$A\,(\Delta SXR) = \dfrac{(SR) \times (DX)}{2}$

$A\,(\Delta PXQ) = \dfrac{(PQ) \times (CX)}{2}$



Area of $\Delta SXP + RXQ = \dfrac{SP \times AX}{2} + \dfrac{RQ \times BX}{2}$

$= \dfrac{1}{2}(l \times b)$ ...(1)

where $SP = RQ = b$ and $PQ = SR = l$

and $AX + BX = AB = PQ = SR = l$

and Area of $\Delta SXR + PXQ = \dfrac{(SR) \times (DX)}{2} + \dfrac{(PQ \times CX)}{2}$

$= \dfrac{(SR) \times (DX)}{2} + \dfrac{(SR) \times (CX)}{2}$

$= \dfrac{SR}{2}(DX + CX)$

$= \dfrac{l}{2} \times b = \dfrac{lb}{2}$

From eq. (1) and (2), we have option (c) is correct.

9. $AD = BC = 20$ cm

$AB = 20$



In ΔADM, $\dfrac{DM}{AD} = \sin 30° = \dfrac{1}{2}$

$\therefore \quad DM = \dfrac{1}{2} AD = 10$ cm

$\therefore$ Area of parallelogram = base × height

$= 20 \times 10 = 200$ cm^2

10. Let $DB = 12$ m

$\therefore \quad BM = 6$ m

$\therefore \quad AM = \sqrt{10^2 - 6^2}$

$AM = 8$ m



(**Remember:** Diagonals bisects each other at right angles)

(**Bisect:** Divide equally into two parts)

$\therefore \quad AC = 8 \times 2 = 16$ m

11. $\angle BCD = \angle DAB = 65°$

$\therefore \quad CDB = 180° - (65° + 45°) = 70°$



12. Let AC and BD bisects each other at R, then $AP = 2PR$ and $QC = 2RQ$



($\because AR$ and CR are the medians of ΔADB and ΔBDC)

and $AP = QC$ and $PR = RQ$ ($\because \Delta DAB \cong \Delta BCD$)

$\therefore \quad AP = PQ$

Scanned by CamScanner

yoursmahboob.wordpress.com

13. Since their base and perpendicular heights are same.

14. $ABCD$ is a parallelogram and $ABPQ$ is a rectangle having same base and equal perpendicular height. Therefore the area of both is same.



Now, since $AD > AQ$

and $BC > BP$

$\therefore \quad 2(AB + BC) > 2(AB + BP)$

$\therefore$ Perimeter of parallelogram > perimeter of rectangle

15. $AB = CD = PQ = l$

and $AQ = BP = AD = CB = b$

Bases of rectangle $ABPQ$ and parallelogram $ABCD$ is same, but perpendicular heights of parallelogram is less than that of rectangle. Therefore area of parallelogram is less than that of rectangle.



16. $AD = 2BM$ and $AD \parallel BM$



$\therefore$From mid-point theorem

$\therefore \quad \frac{NM}{ND} = \frac{NB}{NA} = \frac{BM}{AD} = \frac{1}{2}$

$\therefore \quad AN = 2AB$

17. $A(\square ABPQ) = \frac{1}{2} A(\square ABCD)$



and $A(\Delta ARB) = \frac{1}{2} A(\square ABPQ)$

$\therefore \quad A(\Delta ARB) = \frac{1}{4} A(\square ABCD) \quad \left[A(\Delta ARB) = \frac{1}{2} \times AB \times BP\right]$

18. Let $BD = 6$ cm and $AC = 8$ cm

$\therefore \quad AO = 4$ cm and $BO = 3$ cm



Let $AB = 5$ cm

$\therefore \quad \angle AOB = 90°$

$\Rightarrow \quad \angle BOC = \angle AOD = \angle DOC = 90°$

$\therefore BC$ is also 5 cm.

Hence, $ABCD$ is a rhombus

$\therefore \quad$ Area of rhombus $ABCD = \frac{AC \times BD}{2}$

$= \frac{6 \times 8}{2} = 24 \text{ cm}^2$

19. $BD = \sqrt{15^2 + 20^2} = 25$ cm (ΔABD is right angled triangle)

$\therefore \Delta BCD$ is equilateral triangle.

$\therefore$ Area of $\square ABCD$ = Area of ΔABD + Area of ΔBCD

$= \frac{1}{2} \times 15 \times 20 + \frac{\sqrt{3}}{4} \times (25)^2$

$= \frac{25}{4}(24 + 25\sqrt{3}) \text{ cm}^2$

20. $\frac{BE}{AB} = \sin 30° = \frac{1}{2}$

$\therefore \quad BE = \frac{1}{2} \times AB = 6 \text{ cm} = CF$

and $\frac{CF}{DF} = \tan 45° = 1$

$\therefore \quad DF = CF = 6$ cm

and $\frac{AE}{AB} = \cos 30° = \frac{\sqrt{3}}{2}$

$\therefore \quad AE = 6\sqrt{3}$ cm

$\therefore \quad AD = AE + EF + FD = 6\sqrt{3} + 6 + 6$

$= 6(2 + \sqrt{3}) \text{ cm}^2$

Area of trapezium $ADCB = \frac{1}{2} \times (AD + BC) \times BE$

$= \frac{1}{2} \times [6(2 + \sqrt{3}) + 6] \times 6$

$= \frac{6}{2}(2 + \sqrt{3} + 1) \times 6 = 18 \times (3 + \sqrt{3})$

$= 18(3 + \sqrt{3}) \text{ cm}^2$

21. $A(\Delta ABE) = A(\Delta BDE)$

$= A(\Delta BCE)$

$A(\Delta ABC) = \frac{1}{3} A(\square ACDE)$

$= \frac{1}{3} \times 36 = 12 \text{ cm}^2$



22. $ABCD$ is a square and $ABEF$ is a rhombus.

$\frac{FM}{AF} = \sin 30° = \frac{1}{2}$

$\therefore \quad FM = \frac{AF}{2}, \quad AF = AB$



Area of square $= a^2$ $\quad (AB = AD = a)$

Area of rhombus $= \frac{a \times a}{2}$ $\quad \left(FM = \frac{a}{2}\right)$

(Area of rhombus = base × height)

$\therefore \quad \frac{\text{Area of square}}{\text{Area of rhombus}} = \frac{2}{1}$

Scanned by CamScanner

yourmathbob.wordpress.com

23. Area of quadrilateral = Area of ΔABD + Area of ΔBCD

where $BD = 26$ cm



HINT Apply Hero's formula :

$$\text{Area of } \Delta = \sqrt{s(s-a)(s-b)(s-c)}$$

where $s = \dfrac{a+b+c}{2}$

24. It is not possible

$\because \angle P + \angle R = 170° \neq 180°$

$\therefore$ The given-quadrilateral is not cyclic so there is no any point in the given plane which is equidistant from its vertices.



25. By mid-point theorem,



$$\frac{EF}{AD} = \frac{FG}{DC} = \frac{GH}{BC} = \frac{EH}{AB} = \frac{1}{2}$$

26. Since diagonals bisect each other at right angles and all sides are equal.

Apply Pythagorus theorem or Apollonius theorem.

27. Use Pythagorus theorem



28. Apply Apollonius theorem.



$$AB^2 + BC^2 = 2(BO^2 + AO^2)$$

$$AB^2 + BC^2 = 2(BO^2 + 64)$$

$$196 + 324 = 2(BO^2 + 64)$$

$\therefore \quad BO^2 = 196$

$\therefore \quad BO = 14$ cm

$\therefore \quad BD = 2BO = 28$ cm

INTRODUCTORY EXERCISE 12.4

1. Each interior angle $= 140°$

$\therefore$ Exterior angle $= 180° - 140° = 40°$

$\therefore$ Number of sides $= \dfrac{360°}{\text{Exterior angle}} = \dfrac{360°}{40°} = 9$

Alternatively : It can be checked easily through options.

2. Exterior angle of a regular hexagon $= \dfrac{360°}{6} = 60°$

$\therefore$ Interior angle $= 180° - 60° = 120°$

3. $\therefore$ Interior angle of pentagon $= 180° - \dfrac{360°}{5} = 108°$

$\therefore$ Interior angle of required polygon $= \dfrac{5}{6} \times 108° = 90°$

$\therefore$ Each exterior angle of the requird polygon

$= 180° - 90° = 90°$

$\therefore$ Number of sides $= \dfrac{360°}{\text{Exterior angle}} = \dfrac{360°}{90°} = 4$

Alternatively : Best way is to go through options.

4. Sum of all the interior angles $= (n-2)\,180°$

$1260° = (n-2)\,180°$

$\Rightarrow \quad n = 9 \qquad (n \rightarrow$ number of sides)

5. Interior angle $= 3 \times$ exterior angle

$$180° - \frac{360°}{n} = 3 \times \left(\frac{360}{n}\right) \Rightarrow n = 8$$

Alternatively : Best way is to go through options.

6. Go through option

$$\text{Exterior angle} = \frac{360°}{6} = 60°$$

Interior angle $= 180° - 60° = 120°$

Difference between interior angle and exterior angle

$= 120° - 60° = 60°$

7. $\dfrac{n(n-3)}{2} = 54° \Rightarrow n^2 - 3n = 108° \Rightarrow n = 12$

Alternatively : Put the value of n from the choices given below.

8. Go through options. Let us consider the correct option (d)

Number of sides	5	:	10
Exterior angle =	72°		36°
Interior angle =	$180° - 72°$		$180° - 36°$
	$(= 108°)$		$(= 144°)$
	3	:	4

Hence, option (d) is correct.

9. Go through options

Alternatively : Sum of al exterior angles $= 360°$

$\therefore$ Sum of interior angles $= 4 \times 360° = 1440°$

$\therefore \quad 1440° = (n-2)\,180°$

$\Rightarrow \quad n = 10$ (no. of sides)

10. Exterior angle $= \dfrac{360°}{9} = 40°$

Interior angle $= 180° - 40° = 140°$

$\therefore$ Interior angle : exterior angle $= 140° : 40 = 7 : 2$

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 12.5

1. $AC = \sqrt{OA^2 - OC^2} = \sqrt{(17)^2 - (8^2)} = 15\text{ cm}$

$\therefore \quad AB = 2AC = 30\text{ cm} \quad (\because AC = BC)$

2. $AB = 8\text{ cm}$

$\therefore \quad AM = 4\text{ cm}$

and $\quad OA = 5\text{ cm}$

$\therefore \quad OM = \sqrt{(OA)^2 - (AM)^2}$

$= \sqrt{25 - 16} = 3\text{ cm}$

3. $\because AB$ is the perpendicular bisector of OO'

$\therefore \quad \angle OMA = 90°$

4. $AM : BM : 1 : 1$

5. $\angle AOC = \angle BOC \quad (\because AC = BC)$

$\therefore OC$ is the perpendicular bisector of AB.

$\therefore \quad AM = BM$

6. $OA = 13\text{ cm}$

$AM = 5\text{ cm}$

$\therefore \quad OM = \sqrt{(13)^2 - (5)^2} = 12\text{ cm}$

7. Degree measure of major arc $= 360° - 130° = 230°$

8. It is necessarily a rectangle.

9. $\angle ADC = 180° - 65° = 115°$

$\therefore \quad \angle DCA = 180° - (115° + 45°) = 20°$

($\square ADCB$ is a cyclic quadrilateral)

10. $\angle OBA = \angle OAB = 55°$

$\therefore \quad \angle AOB = 180° - (55° + 55°) = 70°$

and $\quad \angle AOB = \angle COD = 70°$

12. $\Delta BAP \sim \Delta CDP \quad (\because \angle A = \angle D \text{ and } \angle APB = \angle DPC)$

$\therefore \quad \frac{AB}{CD} = \frac{AP}{DP} = \frac{BP}{CP}$

$\therefore \quad AP \times PC = BP \times DP$

13. $\angle BDC = 180° - (110° + 30°) = 40°$

and $\quad \angle BAC = \angle BDC = 40°$ (angles of the same segment)

14. $\angle ABO = 60° = \angle BAO \ (\because AO = BO$, radii of the circle)

$\therefore \quad \angle AOB = 180° - (60° + 60°) = 60°$

$\therefore \quad \angle ACB = \frac{1}{2}\angle AOB = 30°$

15. $\angle CBA = \frac{1}{2}\angle COA = 60°$

$\therefore \quad \angle CBE = 180° - \angle CBA$

$180° - 60° = 120°$

16. $\angle BDA = 90°$

$\angle DBA = 50°$

$\therefore \quad \angle DAB = 180° - (90° + 50°) = 40°$

17. $\angle BAC = 60°$

$\therefore \quad \angle BEC = 180° - 60° = 120°$

18. $\angle ABD = 45°$

$\therefore \quad \angle ACD = 45°$

19. $\angle BDC = \angle BAC = 30°$

$\therefore \quad \angle BCD + \angle BDC + \angle DBC = 180°$

$\therefore \quad \angle BCD = 180° - (30° + 60°)$

$\angle BCD = 90°$

20. $\angle ADC = 140°$

$\therefore \quad \angle ABC = 40°$

$\angle ACB = 90°$

$\therefore \quad \angle BAC = 180° - (90° + 40°) = 50°$

21. $\angle CAB = \frac{1}{2}\angle BOC = \frac{1}{2} \times 40° = 20°$

22. $\angle OBA = \angle OAB = \left(\frac{180° - 80°}{2}\right) = 50°$

and $\quad \angle OCA = \angle OAC = \left(\frac{180° - 120°}{2}\right) = 30°$

$\therefore \quad \angle BAC = \angle BAO + \angle OAC = 50° + 30° = 80°$

23. $\angle ADC = \frac{100°}{2} = 50°$

$\therefore \quad \angle ABC = 180° - 50° = 130°$

$\therefore \quad \frac{m\angle ADC}{m\angle ABC} = \frac{50°}{130°} = \frac{5}{13}$

24. $\angle APB = 50° \quad \left(\because m\angle APB = \frac{1}{2} m\angle AOB\right)$

$\therefore \quad \angle ACB = 180° - 50° = 130°$

$\therefore \quad \angle BCD = 180° - 130° = 50°$

25. $\angle ABC = 180° - 120° = 60°$

$\angle ACB = 90°$

$\therefore \quad \angle CAB = 180° - (90° + 60°) = 30°$

26. $\angle COD = \angle AOB = 70°$

$\therefore \quad \angle OCD = \frac{180° - 70°}{2} = 55°$

27. $\angle ABK = 180° - (105° + 40°) = 35°$

$\therefore \quad \angle ACD = \angle ABD = 35°$

28. $\angle BAC = 80° \quad (\because \angle ABC = \angle ACB = 50°)$

$\therefore \quad \angle BDC = \angle BAC = 80°$

29. $\angle ADB = 90°$

$\therefore \quad \angle DBA = 20° \quad [180° - (90° + 70°)]$

$\therefore \quad \angle CBA = 30° + 20° = 50°$

$\therefore \quad \angle CDA = 180° - 50° = 130°$

$\therefore \quad \angle CDB = 130° - 90° = 40°$

30. $\angle BAD = 80°$

$\therefore \quad \angle DCE = 80°$

31. $\angle AOC = 2 \times 50 = 100°$

$\therefore \quad \angle ABC = \frac{100}{2} = 50°$

NOTE There are some more ways to solve it. Find them.

32. $\angle AOB = 2\angle ACB = 2 \times 25 = 50°$

33. $\angle APB = 180° - \frac{1}{2} \times 90° = 135°$

$\left[\because \angle ACB = 45° = \left(\frac{1}{2} \times 90°\right)\right.$

$\left.\text{and } \angle APB + \angle ACB = 180°\right]$



Scanned by CamScanner

yourSmahboob.wordpress.com

34. $OA = \sqrt{(OB)^2 - (AB)^2}$

$\therefore \quad OA = \sqrt{169 - 144} = 5$

35. $PN \times PR = PQ^2$

$PN \times 25 = (15)^2$

$\therefore \quad PN = 9 \text{ cm}$

36. $TQ = TP \quad \text{and} \quad TP = TR$

$\therefore \quad TQ = TP = TR$

37. $\angle BAC = 90°$

$\angle BCA = 60° \qquad (\because \angle BCA = BAQ)$

$\therefore \quad \angle ABC = 180° - (90° + 60°)$

$\angle ABC = 30°$

38. $\angle DBQ = 65°$

$\therefore \quad \angle DAB = 65°$

$\therefore \quad \angle DCB = 180° - 65° = 115°$

39. $AP \times BP = DP \times CP$

$2 \times 6 = DP \times 3$

$\Rightarrow \quad DP = 4 \text{ cm}$

40. $PA \times PB = PC \times PD$

$3 \times (3 + 5) = 2 \times PD$

$\therefore \quad PD = 12 \text{ cm}$

$\therefore \quad CD = PD - PC$

$= 12 - 2 = 10 \text{ cm}$

41. $PT^2 = PA \times PB$

$5 \times 5 = 4 \times (4 + x)$

$\Rightarrow \quad x = \frac{9}{4} \text{ cm}, \qquad$ where $AB = x$

42. Let they touch eachother at O and A, B be the centres of the two circles, then $OA = 13$ cm and $OB = 5$ cm

$\therefore \quad AB = OA - OB = 8 \text{ cm}$



43. $AB = 5 \text{ cm} = x + y$

$BC = 6 \text{ cm} = y + z$

$AC = 7 \text{ cm} = z + x$

$\therefore \quad 2(x + y + z) = 5 + 6 + 7 = 18 \text{ cm}$

$\therefore \quad x + y + z = 9 \text{ cm}$

$\therefore \quad x = (x + y + z) - (y + z) = 9 - 6 = 3 \text{ cm}$

$\therefore \quad x + y = 5 \text{ cm}$

$\therefore \quad y = 5 - x = 5 - 3 = 2 \text{ cm}$

$\therefore \quad z = 6 - y = 6 - 2 = 4 \text{ cm}$

$\therefore \quad x = 3 \text{ cm}$

$y = 2 \text{ cm} \quad \text{and} \quad z = 4 \text{ cm}$



44. Prove with the help of property of tangents : "Tangents drawn from the same point on a circle are always equal."

45. Tangent is always perpendicular to the radius.



46. $\angle APB = \angle AQB$

when $\angle APB = \angle AQB = 90°$

then they are supplementary. Also they are supplementary when they are in different segments.



$CD = 6 \text{ cm}$

47. $AC = 6 \text{ cm} \quad \text{and} \quad BC = 6 \text{ cm}$

$\therefore$ ($\because AC = CD$ and $BC = CD$. Two tangents from the same point are always equal.)

$AB = 12 \text{ cm}$

48. $\therefore \quad \angle CAB = \angle BCD$

$\angle DAB = \angle BDC$

and $\angle CAD = \angle CAB + \angle DAB = \angle BCD + \angle BDC$

$\therefore \quad \angle CAD = \angle BCD + \angle BDC$

$\Rightarrow \quad \angle CAD + \angle CBD = \angle BCD + \angle BDC + \angle CBD = 180°$

49. $AB = 24 \text{ cm}$

$\therefore \quad AC = BC = 12 \text{ cm}$

$OA = 20 \text{ cm}$

$\therefore \quad OC = \sqrt{(OA)^2 - (AC)^2}$

$= \sqrt{400 - 144} = 16 \text{ cm}$

and $O'A = 37 \text{ cm}$

$\therefore \quad O'C = \sqrt{(O'A)^2 - (AC)^2}$

$= \sqrt{(37)^2 - (12)^2} = 35 \text{ cm}$

$\therefore \quad OO' = OC + CO' = 16 + 35 = 51 \text{ cm}$

50. $AB = AC, OB = OC$

and BC is common and OA is common

also $\angle BOA = \angle COA$

$\therefore \quad \Delta BOA \cong \Delta COA$

$\therefore BC$ and OA are perpendicular bisector to each other

[Area of $\Delta = \sqrt{s(s-a)(s-b)(s-c)}$]

$s = \frac{a+b+c}{2} = \frac{5+5+6}{2} = 8 \text{ cm}$

Area of $\Delta BOA = \sqrt{8 \times 3 \times 3 \times 2} = 12 \text{ cm}^2$

Again area of $\Delta BOA = \frac{1}{2} OA \times BP = \frac{1}{2} \times 5 \times BP$

$12 = \frac{1}{2} \times 5 \times BP$

$\Rightarrow \quad BP = 4.8 \text{ cm}$

$\therefore \quad BC = 2BP = 2 \times 4.8 = 9.6 \text{ cm}$



51. $OA = OC = 17 \text{ cm}$

$AP = \frac{1}{2} AB = \frac{1}{2} \times 16 = 8 \text{ cm}$

$\therefore \quad OP = \sqrt{OA^2 - AP^2} = 15 \text{ cm}$

Now, $PQ = OP + OQ = 23 \text{ cm}$

$\therefore \quad 15 + OQ = 23 \text{ cm}$

$\therefore \quad OQ = 8 \text{ cm}$

Again, $CQ = \sqrt{(OC)^2 - (OQ)^2}$

$CQ = \sqrt{(17)^2 - (8)^2}$

$\therefore \quad CQ = 15 \text{ cm}$

$\therefore \quad CD = 2CQ = 30 \text{ cm}$



Scanned by CamScanner

yoursmahboob.wordpress.com

52. $AB = r$ (say)

then $AC = BC = r$, also

$\therefore$ $OA = OB = \frac{r}{2}$ (CD is a common chord)



$$\therefore OC = \sqrt{(AC)^2 - (OA)^2} = \sqrt{r^2 - \left(\frac{r}{2}\right)^2} = \sqrt{\frac{3r^2}{4}} = \frac{\sqrt{3}}{2}r$$

$$\therefore \quad CD = 2CO = 2 \times \frac{\sqrt{3}}{2}r = \sqrt{3}r$$

$$\therefore \quad \frac{l(CD)}{l(AC)} = \frac{\sqrt{3}r}{r} = \frac{\sqrt{3}}{1}$$

53. Let A be the centre of larger circle and B be the centre of the smaller circle.



$OA = 3$ cm and $BO = 2$ cm

and $AB = (OA - OB) = 1$ cm

also $BP = 2$ cm

$\therefore$ $AP = 1$ cm

P is the point of contact of tangent MN

$\therefore$ $MP = \sqrt{AM^2 - AP^2} = \sqrt{3^2 - 1^2} = 2\sqrt{2}$ cm

$\therefore$ $MN = 2MP = 4\sqrt{2}$ cm

55. $PQ = AS$ (PQ is a transverse common tangent)



and $BS = BQ + SQ = BQ + AP$

$BS = 2BQ$ ($BQ = AP$ = radius)

$BS = 6$ cm

$\therefore$ $AS = \sqrt{(AB)^2 - (BS)^2} = \sqrt{(10)^2 - (6)^2} = 8$ cm

$\therefore$ $AS = 8$ cm

$\therefore$ $PQ = 8$ cm

Alternatively : The length of transverse common tangent

$$= \sqrt{(\text{distance beween the centres})^2 - (r_1 + r_2)^2}$$

$$= \sqrt{(10)^2 - (3+3)^2} = 8 \text{ cm}$$

57. Inradius of an incircle of right angled triangle

$$= \frac{\text{Base} + \text{Altitude} - \text{Hypotenuse}}{2}$$

$$= \frac{4+3-5}{2} = 1 \text{ cm}$$

Alternatively : Inradius $= \dfrac{\text{Area of triangle}}{\text{Simiperimeter of triangle}}$

$$= \frac{(3 \times 4)/2}{(3+4+5)/2} = \frac{6}{6} = 1 \text{ cm}$$

58. Let AB and CD be the two chords, then $AB = 8$ cm and $CD = 6$ cm.



$\therefore$ $AP = 4$ cm and $CQ = 3$ cm

and $PQ = 1$ cm (given)

Let $OP = x$

$\therefore$ $AO^2 = AP^2 + OP^2$

$\therefore$ $AO^2 = 4^2 + x^2 = 16 + x^2$ ...(1)

and $OC^2 = CQ^2 + OQ^2$

$= CQ^2 + (OP + PQ)^2$

$= (3)^2 + (x+1)^2$

$OC^2 = 9 + x^2 + 1 + 2x$ ...(2)

But $OA = OC$, are the radii of the same circle.

$\therefore$ $16 + x^2 = 9 + x^2 + 1 + 2x$

$\Rightarrow$ $x = 3$ cm

$\therefore$ $OA^2 = 16 + x^2 = 16 + 9 = 25$

$\therefore$ $OA = 5$ cm

$\therefore$ Diameter of the circle $= 2(OA) = 10$ cm

59. $AB = BC = AC = 2$ cm

($\because$ radius of each circle = 1 cm)



$\therefore$ $AP = \frac{\sqrt{3}}{2} \times 2$

$AP = \sqrt{3}$ cm

Let O be the centroid, then

$$OA = \frac{2}{3} \times \sqrt{3} = \frac{2}{\sqrt{3}} \text{ cm}$$

and $AM = 1$ cm

$\therefore$ $OM = \frac{2}{\sqrt{3}} + 1 = \frac{2+\sqrt{3}}{\sqrt{3}}$ cm

OM is the radius of the larger circle.

$\therefore$ Area of the circumscribing circle $= \pi R^2$

$$= \pi \times \left(\frac{2+\sqrt{3}}{\sqrt{3}}\right)^2$$

$$= \frac{\pi}{3}(2+\sqrt{3})^2$$

60. OA is the radius of the largest circle and O is the centroid of the all concentric circles.



Let r_1, r_2, r_3 and r_4 be the radii of the concentric circles in increasing order then

Total area of given circle

$= \pi \times (20)^2 = 400\pi$

Area of each region $= \frac{1}{4} \times 400\,\pi = 100\pi$

$\therefore$ Area of central region $= 100\pi = \pi r_1^2$

$\Rightarrow$ $r_1 = 10$ cm

Similarly, area of second region $= 100\pi = \pi (r_2^2 - r_1^2)$

$100\pi = \pi (r_2^2 - 100)$

$\Rightarrow$ $r_2 = 10\sqrt{2}$ cm

Again, area of third region $= 100\pi = \pi (r_3^2 - r_2^2)$

$100\pi = \pi (r_3^2 - 200)$

$\Rightarrow$ $r_3^2 = 10\sqrt{3}$ cm

$\therefore$ The required radii are 10, $10\sqrt{2}$ and $10\sqrt{3}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL 1

1. $\angle BAD = 180° - 130° = 50°$ ($\because$ □ $ABCD$ is cyclic)

and $\angle ADB = 90°$ (angle of semicircle)

$\therefore$ $\angle ABD = 180 - (90 + 50) = 40°$

2. $\angle ACB = 180 - (90 + 25) = 65°$ ($\because \angle ABC = 90°$)

But since $\angle ADB = \angle ACB$

$\therefore$ $\angle ADB = 65°$

3. $\angle AOD = \angle ODC + \angle OCD$ ($\because \angle AOD$ is an external angle)

$= 52°$ ($\angle ODC = \angle OCD = 26°$)

($\because OD = OC$)

4. Note that $4700 : 4935 : 6815 = 20 : 21 : 29$



$\therefore$ ΔACB is right angled triangle and $\angle ACB$ is a right angle.

$\therefore$ The inradius of the right angled triangle

$$= \frac{20 + 21 - 29}{2} = 6 \text{ cm}$$



$\therefore$ $MO = MC = 6$ cm

$\therefore$ $AM = 21 - 6 = 15$ cm

$\therefore$ $\frac{AM}{MC} = \frac{AO}{OP} = \frac{15}{6} = \frac{5}{2}$

$\Rightarrow$ $\frac{PO}{AO} = \frac{2}{5}$

5. $CD = CP$ and $BE = BP$, since tangent from the same point are always same.

$\therefore$ $AE = AD$

Now, $AD = AC + CD = AC + CP$

and $AE = AB + BE = AB + BP$

$\therefore$ $AE + AD = AC + CP + AB + BP$

$2AE = AC + AB + (CP + BP)$

$2AE = AB + AC + BC$, Hence (d)

6. Inradius of a right angled triangle $= \frac{AC + BC - AB}{2}$

$$= \frac{9 + 40 - 41}{2} = 4 \text{ cm}$$

7. Let $AD = 16$ cm



then $AB = 20$ cm and $BD = 18$ cm

$\therefore$ $DO = BO = 9$ cm

NOTE In a parallelogram the two diagonal bisect each other, therefore by Appollonious theorem

$\therefore$ $16^2 + 20^2 = 2(9^2 + AO^2)$

$\Rightarrow$ $AO = \sqrt{247}$

$\therefore$ $AC = 2\sqrt{247}$ cm

8. Go back to the basics

9. It is clear that

$$\frac{PM}{MQ} = \frac{PN}{NR} = \frac{6}{4} = \frac{3}{2}$$



Therefore ΔPMN and ΔPQR are similar

Now Ratio of areas of $\Delta PMN : \Delta PQR$

$= 3 \times 3 : 5 \times 5 = 9 : 25$

$\therefore$ Percentage of area of ΔPMN over

$$\Delta PQR = \frac{9}{25} \times 100 = 36\%$$



10. Since, ΔAOB is similar to ΔCOD.

$\therefore$ Ratio of areas of $\frac{\Delta AOB}{\Delta COD} = \left(\frac{3}{1}\right)^2 = \frac{9}{1}$

11. The maximum possible distance between Barabanki and Lucknow is 108 km and minimum possible distance between Barabanki and Lucknow is 24 km. Hence (d)



Scanned by CamScanner

yoursmahboob.wordpress.com

12. Since $CS = SD$

$\therefore$ The two chords must be equidistant from the centre 'O'.

Thus, the required ratio is 1 : 1

13. $\angle DFO = \angle FOM$

and $\angle AEO = \angle EOM$ (since $CD \parallel AB$)



$\therefore$ $\angle FOE = (28° + 42°) = 70°$

14. $\angle AOB = 60°$

and $\angle AOD = \angle ADO = \dfrac{(180° - 30°)}{2} = 75°$

Also $\angle BOC = 75°$

$\therefore$ $\angle COD = 360° - (75° + 60° + 75°) = 150°$

15. $\angle ABD = \angle ABC - \angle DBC$

$= \angle ABC - \angle BDC$

$= \angle ABC - (\angle ABD + \angle BAD)$

$\therefore$ $2(\angle ABD) = \angle ABC - \angle BAD = 30°$

$\therefore$ $\angle ABD = 15°$ ($\because \angle BAD = \angle BAC$)

16. $BD = AC = 20$ cm (by Pythagorus theorem)



$\therefore$ $DM = \dfrac{AD \times BD}{AB}$

$\therefore$ $DM = \dfrac{15 \times 20}{25} = 12$ cm, also $CN = DM$

$\therefore$ $AM = \dfrac{AD^2}{AB}$

$\therefore$ $AM = \dfrac{15 \times 15}{25} = 9$ cm, also $AM = BN$

$\therefore$ $MN = AB - (AM + BN)$

$= 25 - (18) = 7$ cm

but $MN = CD = 7$ cm

$\therefore$ Area of trapezium $= \dfrac{1}{2} \times (CD + AB) \times DM$

$= \dfrac{1}{2} \times 32 \times 12 = 192\ \text{cm}^2$

17. $(OS)^2 = (OK)^2 + (KS)^2$

$25 = OK^2 + 16 \Rightarrow OK = 3$

and $(OS)^2 = (OL)^2 + (LN)^2$

$25 = (OL)^2 + 9$

$\Rightarrow$ $OL = 4$ cm

$\therefore$ $KL = OL - OK = 1$ cm

$\therefore$ Area of rectangle $= 1 \times 10 = 10\ \text{cm}^2$

18. $\angle ACB = 90°$

$\therefore$ $AC = 12$ cm

Now, since CO is perpendicular on AB

$\therefore$ $CO = \dfrac{AC \times BC}{AB} = \dfrac{16 \times 12}{20} = 9.6$ cm

19. $\angle ADB = \angle ACB = 41°$

(angles of the same segment)

$\therefore$ $\angle ABD = 180 - (\angle ADB + 90) = 49°$ ($\angle DAB = 90°$)

20. Go through options for quicker answer

Exterior angle $= \dfrac{360}{15} = 24°$ (for $n = 15$)

$\therefore$ Interior angle $= 180 - 24° = 156°$

$\therefore$ Interior – Exterior $= 156 - 24 = 132°$

Hence, option (b) is correct.

21. $OC = OD$ and $OA = OP = OB$

$OP = 1$ m

$\therefore$ $PC = 1$ m

$OC = \sqrt{2}$ m

$\therefore$ $AC = OC - OA$

$= (\sqrt{2} - 1)$ m

and $AC + CP = (\sqrt{2} - 1) + 1$

$= \sqrt{2}$ m

$= 1.414$ m

$= 141.4$ cm



22. $AB : BC : CA = \dfrac{1}{CD} : \dfrac{1}{AE} : \dfrac{1}{BF} = \dfrac{1}{2} : \dfrac{1}{3} : \dfrac{1}{4} = 6 : 4 : 3$

23. ΔPOQ and ΔROS are similar

$\therefore$ $PS = QR$

Option *a*, *b* and *d* are irrelevent.

24. $\dfrac{DQ}{BD} = \sin 60° \Rightarrow DQ = BD \times \dfrac{\sqrt{3}}{2} = 3$ m

and $\dfrac{DP}{DF} = \sin 30° = \dfrac{1}{2}$

$\therefore$ $DP = 2$ m ($\because DF = 4$ m)

$\therefore$ $PQ = 3 - 2 = 1$ m

Let $AB = CQ = x$ m

$\therefore$ $\dfrac{CD}{EF} = \dfrac{5}{4}$

$\dfrac{x + 3}{x + 1} = \dfrac{5}{4} \Rightarrow x = 7$ m.

25. Area of equilateral triangle

$ABC = \dfrac{\sqrt{3}}{4} \times (6)^2 = 9\sqrt{3}\ \text{cm}^2$

Area of $\Delta ADE = \dfrac{1}{2} \times DE \times CP$

$= \dfrac{1}{2} \times 2 \times \dfrac{\sqrt{3}}{2} \times 6$

$= 3\sqrt{3}\ \text{cm}^2$



$\therefore$ Area of shaded region $= 9\sqrt{3} - 3\sqrt{3} = 6\sqrt{3}\ \text{cm}^2$

26. $CD = CP^2 + DP^2 = (3\sqrt{3})^2 + (1)^2 = 2\sqrt{7}$ cm

and $CE = CD = 2\sqrt{7}$ and $DE = 2$ cm

Scanned by CamScanner

yoursmanboob.wordpress.com

$\therefore$ Perimeter of $\Delta CDE = 2(2\sqrt{7}) + 2$

$= 2(2\sqrt{7} + 1)$ cm

27. $\angle ABC = 180 - (65 + 75) = 40°$

$\angle ORB = \angle OQB = 90°$

$\therefore \quad \angle ROQ = 360 - (90 + 90 - 40)$

$\therefore \quad \angle ROQ = 140°$

28. $\angle BAP + \angle BCP = 180°$

($\square ABCP$ is a cyclic quadrilateral)

$\therefore \quad \angle BCP = 180 - 60° = 120°$

29. Since, we don't have requisite information.

30. $\because \quad AT = BT,$

($\because$ Tangents on the same circle from a fixed point is equal)

$AC = PC \quad$ and $\quad BD = PD$

$\therefore \quad AT = BT$

$\Rightarrow \quad AC + CT = BD + DT$

$PC + CT = PD + DT$

Similarly, all the relations can be verified.

31. $OQ = OB = OC = r$ (say)

$\angle AOD = \angle BOC = 120°$

$\therefore \quad \angle BOQ = \angle COQ = 60°$

$\therefore \quad \frac{SB}{OB} = \sin 60° = \frac{\sqrt{3}}{2}$

$\Rightarrow \quad SB = \frac{r\sqrt{3}}{2}$

$\therefore \quad BC = 2SB = r\sqrt{3}$

$\therefore$ Area of quadrilateral $BQCO$

$= \frac{1}{2} \times BC \times OQ$

$= \frac{1}{2} \times r\sqrt{3} \times r = \frac{r^2\sqrt{3}}{2}$ cm^2

$\therefore$ Area of both the quadrilateral $= 2\left(\frac{r^2\sqrt{3}}{2}\right) = r^2\sqrt{3}$ cm^2

32. Go back to the basics.

33. $\frac{(A)\,\Delta CMN}{(A)\,\square ABNM} = \frac{1}{2}$

$\therefore \quad \frac{(A)\,\Delta CMN}{(A)\,\Delta CAB} = \frac{1}{3}$

$\Rightarrow \quad \frac{MN}{AB} = \frac{CM}{CA} = \frac{1}{\sqrt{3}}$

$\Rightarrow \quad \frac{CM}{MA} = \frac{1}{\sqrt{3}-1} = \frac{\sqrt{3}+1}{2} \qquad MA = (CA - CM)$

34. $\angle ADE = \angle AED = 80°$

$\therefore \quad \angle BDE = \angle CED = 100°$

$\therefore \quad \angle DBC + \angle BCE = 360° - (100° + 100°) = 160°$

35. $AC = \sqrt{(15)^2 + (20)^2} = 25$ cm

$CD = \sqrt{(25)^2 - (7)^2} = 24$ cm

36.



$AB = PQ = 26$ cm

and $\quad PO = OQ = 13$ cm

$CO = \sqrt{(PO)^2 - (PC)^2}$

$CO = \sqrt{(13)^2 - (5)^2}$

$CO = 12$ cm

$\therefore \quad CD = 2CO = 24$ cm

Alternatively: Solve by using the formula of tangent

37. $\angle DAM = 45°$

$DM = 8$ cm

and

and $\quad BD = 10$ cm



$\therefore \quad BM = 6$ cm $\qquad (BM = \sqrt{BD^2 - BC^2})$

and $\quad \frac{AM}{DM} = \tan 45° = 1$

$\therefore \quad AM = 8$ cm

and $\quad AB = AM + MB = 8 + 6 = 14$ cm

$\therefore$ Area of parallelogram $ABCD = AB \times MD$

$= 14 \times 8 = 112$ cm^2

38. $\angle ACB = 50° \qquad (\because \angle A + \angle B + \angle C = 180°)$

$\angle CFO = \angle CEO = 90°$

$\therefore \quad \angle FOE = 360° - (90° + 90° + 50°) = 130°$

but $\quad \angle AOB = \angle FOE = 130°$

39. $35x = 26y \quad \Rightarrow \quad \frac{x}{y} = \frac{26k}{35k}$



$\therefore \quad x + y = 61k$

if $x = 1$, then $z = 119°$

But $\quad x < z < y$

again consider $k = 2$, then

$x = 52° \quad$ and $\quad y = 70°$

$\therefore \quad z = 180° - (70° + 52°) = 58°$

40. $\angle DAB = \angle BDQ = 48°$

$\therefore \quad \angle DBA = 180° - (90° + 48°) = 42° \quad (\because \angle ADB = 90°)$

$\angle DCB = 180° - \angle DAB = 132°$

$\therefore \quad \frac{\angle DBA}{\angle DCB} = \frac{42}{132} = \frac{7}{22}$

41. $\angle OCD = 90°$

$\angle OAC = \angle OCA = 30°$

$\angle ACD = \angle ACO + \angle OCD = 30° + 90° = 120°$

$\therefore \quad \angle BAC = 180° - 120° = 60°$

$\Rightarrow \quad \angle BCD = 60° \qquad (\angle BCD = \angle BAC)$

$\Rightarrow \quad \angle OCB = \angle OCD - \angle BCD$

$= 90° - 60° = 30°$

Scanned by CamScanner

yoursmahboob.wordpress.com

42. $OE = OF$ (inradius)

$BF = BD$



and $EC = DC = 15$ cm

Let $BF = x$ cm

then $AB = (6 + x)$ cm

and $AC = 6 + 15 = 21$ cm

$\therefore \quad (BC)^2 = (AB)^2 + (BC)^2$

$(x + 15)^2 = (6 + x)^2 + (21)^2 \quad (\because BC = BD + CD)$

$\Rightarrow \quad x = 14$ cm

$\Rightarrow \quad BD = 14$ cm

$\therefore \quad CD - BD = 15 - 14 = 1$ cm

43. $(\angle BPQ + \angle BQP) + (\angle EQR + \angle ERQ)$

$+ (\angle CRS + \angle CSR) + (\angle TSA + \angle ATS)$

$+ (\angle DTP + \angle DPT) = 2 \times 360$

$\angle A + \angle D + \angle B + \angle E + \angle C = 5 \times 180° - 2 \times 360° = 180°$

44. $\dfrac{\text{Area of } \Delta DAE}{\text{Area of } \Delta DEC} = \dfrac{\frac{1}{2} \times DE \times AE}{\frac{1}{2} \times DE \times CE}$

$= \dfrac{AE}{CE} = \dfrac{(AD)^2}{(DC)^2} = \left(\dfrac{6}{8}\right)^2 = \dfrac{9}{16}$

Similarly, in ΔABC,

$\dfrac{\text{Area of } \Delta BCF}{\text{Area of } \Delta BFA} = \dfrac{9}{16}$

$\therefore$ The area of shaded to unshaded region $= \dfrac{16}{9}$

45. $\angle OCA = \angle OAC = 25°$

and $\angle OCB = \angle OBC = 35°$

$\therefore \quad \angle ACB = \angle ACO + \angle BCO$

$= 25° + 35° = 60°$

$\therefore \quad \angle AOB = 2\angle ACB = 120°$



46. $\angle DOA = 110°$

and $\angle ADB = 50°$

$\therefore \quad \angle DAO = 180 - (110° + 50°) = 20°$

47. ΔABC is similar to ΔEDC

$\therefore \quad \dfrac{AB}{ED} = \dfrac{BC}{DC} = \dfrac{AC}{EC}$

$\therefore \quad \dfrac{AB}{DE} = \dfrac{BC}{DC} \Rightarrow \dfrac{24}{10} = \dfrac{60}{DC}$

$\Rightarrow \quad DC = 25$ cm

48. $AC = \sqrt{(24)^2 + (60)^2} \quad (\because AC^2 = AB^2 + BC^2)$

$AC = 12\sqrt{29}$

$\therefore \quad \dfrac{BC}{DC} = \dfrac{AC}{EC}$

$\Rightarrow \quad \dfrac{60}{25} = \dfrac{12\sqrt{29}}{EC}$

$\Rightarrow \quad EC = 5\sqrt{29}$

$\therefore \quad BE = BC - EC = 60 - 5\sqrt{29}$

$\Rightarrow \quad BE = 5(12 - \sqrt{29})$

$\therefore \quad \dfrac{CE}{BE} = \dfrac{5\sqrt{29}}{5(12 - \sqrt{29})} = \dfrac{\sqrt{29}}{(12 - \sqrt{29})}$

49. $PTUS$ is a square inscribed by a square $ABCD$.

Let each side of the square $ABCD$ be 'a', then

Area of square $ABCD = a^2$

also $PU = ST = a$

$\therefore$ Area of square $PTUS = \dfrac{a^2}{2}$



$\therefore \quad \dfrac{\text{Area of } PTUS}{\text{Area of } ABCD} = \dfrac{a^2/2}{a^2} = \dfrac{1}{2}$

$\therefore \quad \dfrac{\text{Area of } \square PQRS}{\text{Area of } \Delta ABC} = \dfrac{1}{2}$

50. Go through options. It is pentagon

Alternatively : ${}^nC_2 - n = n$

$\Rightarrow \quad {}^nC_2 = 2n$

$\Rightarrow \quad \dfrac{n(n-1)}{2} = 2n$

$\Rightarrow \quad n = 5$

51. Let $P_1, P_2, P_3, P_4, \ldots, P_9$ be the vertices of the regular nonagon then, we can select two vertices out of 9 vertices in ${}^9C_2$ ways and ${}^9C_2 = 36$ ways and number of equilateral triangles formed $= 36 \times 2 = 72$

But the three triangles $\{P_1, P_4, P_7\}$, $\{P_2, P_5, P_8\}$ and $\{P_3, P_6, P_9\}$ are each counted 3 times *i.e.*, counted as 9 triangles instead by 3 triangles.

So, net number of equilateral triangles $= 72 - 6 = 66$.

52. There are 4 triangles (smaller) are congruent.



So, out of these 4 triangles 2 triangles are taken thus the ratio of the shaded to the unshaded region is 1 : 1 (since two triangles are shaded and 2 are unshaded).

53. ΔPQR is an equilateral triangle *i.e.*, all the three angles are 60° each.

$\therefore \quad PQ = QR = PR$

Scanned by CamScanner

yoursmahboob.wordpress.com



Now, $\text{arc } PQ = 2\pi \times (1) \times \frac{60}{360} = \frac{\pi}{3}$

$\therefore$ Sum of all three arcs $= 3 \times \frac{\pi}{3} = \pi$

54. $\angle A = 90°$ and $\angle B = \angle C = 45°$



Inradius $\frac{(a+a)-a\sqrt{2}}{2} = \frac{a(2-\sqrt{2})}{2}$

and Circumradius $= \frac{a\sqrt{2}}{2}$

$\therefore \frac{\text{Inradius}}{\text{Circumradius}} = \frac{a(2-\sqrt{2})/2}{(a\sqrt{2})/2}$

$= \frac{2-\sqrt{2}}{\sqrt{2}} = \frac{\sqrt{2}(\sqrt{2}-1)}{\sqrt{2}}$

$= \frac{(\sqrt{2}-1)}{1}$

LEVEL 2

1. $BD = 53$ cm

$\therefore AD = CD = BD = 53$ cm

$\therefore AC = 2 \times 53 = 106$ cm

$AB + BC + AC = 2 \times 126$ cm

$= 252$ cm

$\therefore AB + BC = 146$ cm

Let $AB = x$ cm

$\therefore BC = (146 - x)$ cm

$\therefore AB^2 + BC^2 = AC^2$

$x^2 + (146 - x)^2 = (106)^2$ ...(1)



Solving the equation (1), we get $x = 56$ and $x = 90$



Consider $AB = 56$ cm

then $BC = 90$ cm

Longest median will fall on the shortest side.

Now, the area of $\Delta BCD = \frac{1}{2} \times BD \times BC$

$= \frac{1}{2} \times 28 \times 90 = 1260 \text{ cm}^2$

2. Let $AB = BC = a$

then $AC = \sqrt{2}a$

$\therefore AO = OC = BO = \frac{\sqrt{2}a}{2} = \frac{a}{\sqrt{2}}$



Now, by angle bisector theorem

$\frac{AB}{AO} = \frac{BM}{MO} \Rightarrow \frac{BM}{MO} = \frac{a}{a/\sqrt{2}} = \frac{\sqrt{2}}{1}$

$MO = 20$ cm

$\therefore BM = 20\sqrt{2}$ cm

$\therefore BO = 20 + 20\sqrt{2} = 20(1 + \sqrt{2})$ cm

Now, since $BO = \frac{a}{\sqrt{2}} = \frac{AB}{\sqrt{2}}$

$\therefore AB = \sqrt{2}(BO) = 1.414\ [20(1 + 1.414)]$

$= 68.2679 = 68.27$ cm

3. $\angle A + \angle B = 90°$

$\angle A - \angle B$

$89 - 1 = 88$

$88 - 2 = 86$

$87 - 3 = 84$

... ...

$45 - 45 = 0$

$44 - 46 = -2$

... ...

$1 - 89 = -88$



Thus k can assume total $44 + 1 + 44 = 89$ values

4. $\angle SPT$ and $\angle SOT$ are supplementary, then

$\angle SOT = 180° - 50° = 130°$

$\therefore \angle SRT = \frac{1}{2}(\angle SOT) = 65°$

$\therefore \angle SQT = 180 - 65° = 115°$



5. Let BC be the ladder, then



Scanned by CamScanner

yoursmahboob.wordpress.com

$BC = 6.5\text{ m}$ and $AB = 5.2\text{ m}$

$AC = \sqrt{(BC)^2 - (AB)^2}$

$\therefore \quad AC = 3.9\text{ m}$

$PQ^2 = PA^2 + AQ^2$

Now, $(6.5)^2 = (2.5)^2 + AQ^2$

$AQ = 6\text{ m}$

$\Rightarrow \quad BQ = AQ - AB = 6 - 5.2 = 0.8\text{ m}$

$\therefore$ The foot of the ladder will slip by 0.8 m

6. $\angle A + \angle B + \angle C = 180$

Any one of angle can posses the values from 1 to 178.



7. Cannot be determined.

8. ΔABC is a right angled



and $\angle ABC = 90°$

Let $AB = x$

then $AB = AD = CD = BD = x$

$\therefore \Delta ABD$ is equilateral triangle

$\therefore \quad \angle CAE = 60°$

$\therefore \quad \angle BCA = 30°$

$\Rightarrow \quad \angle ACE = 60°$

$\therefore \quad \angle CEA = 60°$, also

Hence, ΔACE is an equilateral triangle

Thus, $AC = AE = CE = 2x$

and $\dfrac{BC}{AB} = \tan 60° = \sqrt{3}$

$\Rightarrow \quad BC = AB\sqrt{3} = x\sqrt{3}$

$\therefore \quad \dfrac{BC}{AE} = \dfrac{x\sqrt{3}}{2x} = \dfrac{\sqrt{3}}{2}$

9. $\pi r^2 = 3\pi \Rightarrow r = \sqrt{3}$

$\therefore \quad DE = 2r^2 - 2r^2\cos 120°$

$DE = r^2 \qquad (\because \sqrt{3} = r)$

But $AB = 2DE$

(By similarly of triangles)

$\therefore \quad AB = 2r^2 = 2 \times (\sqrt{3})^2 = 6$

($\because D$ and E are the mid-points of OA and OB)

$\therefore$ Perimeter of triangle

$ABC = 3 \times 6 = 18$ unit



10. Time taken in the collision the two trains

$= \dfrac{500}{(40 + 60)} = 5\text{ h}$



In 5 hours, plane will cover $5 \times 200 = 1000$ km distance

11. Two trains meet with accident at a place $200 (= 40 \times 5)$ km away from Patiyala.

$\therefore$ The required distance = 200 km

12. Area of $\Delta BDE = \dfrac{1}{2} \times \dfrac{2}{5} AB \times \dfrac{2}{7} BC$

$= \dfrac{4}{35} \times \dfrac{1}{2}(AB \times BC)$

$= \dfrac{4}{35}$ area of ΔABC

$\therefore \quad$ Area of $\Delta ABC = \dfrac{35}{4} \times 20 = 175\text{ cm}^2$

13. Let E be on BC and $BE = EC$

Let F be on AE so that triangle FBC is equilateral.

$\angle DAB = \angle ABF = 20°$

and $DA = BF$

$\therefore$ Trapezoid $ADFB$ is isosceles.

$\angle FAD = \angle DBF = 10°$

$\therefore \quad \angle DBC = 10 + 60 = 70°$



14. Calculate them physically (or manually)

15. $AB = 6$ cm, $\angle C = 60°$

and $\angle A = \angle B = 60°$

$\therefore \Delta ABC$ is an equilateral triangle

$\therefore \quad$ Area of $\Delta ABC = \dfrac{\sqrt{3}}{4} \times (6)^2 = 9\sqrt{3}$

Area of $(\Delta ADE + \Delta BFG) = 2 \times \dfrac{\sqrt{3}}{4} \times (2)^2 = 2\sqrt{3}$

$\therefore \quad$ Area of pentagon $= 9\sqrt{3} - 2\sqrt{3} = 7\sqrt{3}\text{ cm}^2$

16. Since, $PQRS$ is a parallelogram



$\therefore \quad \angle PSR = 90° \qquad (\angle PSR + \angle PQR = 180°)$

Scanned by CamScanner

yoursmahboob.wordpress.com

17. Best way in to go through option

$r > 1$ and $r \in I$

Let us assume $r = 2$ $(r \to k)$

$w = a$

$x = ar$

$y = ar^2$

and $z = ar^3$

$\therefore \quad ar^3 - a = a(r^3 - 1) = 168$

$\Rightarrow \quad a(2^3 - 1) = 168$

$\Rightarrow \quad a = 24$

Note only option (a) gives a value (168) which is divisible by 7. Now,

$a = 24, \quad ar = 48, \quad ar^2 = 96$ and $ar^3 = 192$

This value satisfies all the required conditions hence it is correct.

NOTE For other values of r and other options are not being matched.

18. $\angle ROQ = 180 - 50 = 130°$

$(\because \angle OQP + \angle ORP + \angle QOR + \angle QPR = 360°$ and $\angle OQP = \angle ORP = 90°)$

Now, since $RT = TM$ and $QS = SM$

$\therefore$ also $OR = OM = OQ$

$\therefore \quad \angle ROT = \angle TOM$ and $\angle MOS = \angle SOQ$

$\therefore \quad \angle SOT = \frac{1}{2}\angle ROQ$

$\therefore \quad \angle SOT = \frac{130}{2} = 65°$

19. $12 + 6 + 1 = 19$



20. There are total 16 similar triangles each with equal area.



Here, 4 out of 16 triangles are taken. So the number of shaded triangles = 4 and number of unshaded triangles = 12

$\therefore \quad$ Required ratio $= \frac{1}{3}$

21. Number of total rectangles $= {}^4C_2 \times {}^3C_2 = 6 \times 3 = 18$

22. $\angle PDB = \angle QEA = 80°$

$\therefore \quad \angle PED = \angle QDE = 10°$ $(\because \angle DPE = \angle DQE = 90°)$

$\therefore \quad \angle DRE = 180 - (10 + 10) = 160°$

$\therefore \quad \angle PRD = 180 - \angle DRE = 20°.$

23. $OC = \frac{AB}{2}$

$AO = OC = OB$

$\angle OAC = \angle OCA$

$\therefore \quad = \angle BCO = \angle OBC = 45°$

$\angle ACB = 90°$

$\therefore$ Notice that all the given triangles are equilateral

24. Area of shaded region $= 3\left[\pi r^2 \frac{60}{360} - \frac{\sqrt{3}}{4} \times r^2\right]$

$= \frac{r^2}{2}\left[\pi - \frac{3\sqrt{3}}{2}\right]$

26. Notice $\angle ORP = 90°$ ($\because$ OP is a diameter of smaller circle)

$OS = 5$ cm and $OR = 4$ cm

$\therefore \quad SR = \sqrt{(5)^2 - (4)^2} = 3$ cm

$\therefore \quad SP = 2(SR) = 6$ cm

(Since, OR passes through centre O and perpendicular to SP therefore OR bisects SP.)

27. $\frac{AD}{AB} = \frac{DO}{BO} = 1$

$\Rightarrow \quad OB = OD = 8$ cm

$\because$ $ABCD$ is a cyclic quadrilateral

$\therefore \quad DO \times BO = CO \times AO$

$8 \times 8 = 4 \times AO$

$\Rightarrow \quad AO = 16$ cm

$\therefore \quad AC = 16 + 4 = 20$ cm

28. At $\angle A = 60°$, $BC = b = c$

and at $\angle A = 90°$, $BC = \sqrt{2}\, b = \sqrt{2}c$

$\therefore \quad 60° < A < 90°, \quad BC = c < a < c\sqrt{2}$

29. $OR^2 = (OQ)^2 + (RQ)^2$ $RQ = 2(OQ)$

$OR^2 = 5OQ^2$

$\Rightarrow \quad$ radius $(r) = OQ\sqrt{5}$

$\therefore \quad OQ = \frac{r}{\sqrt{5}}$

Again, $OC^2 = OH^2 + HC^2$

$r^2 = (OQ + QH)^2 + (QH)^2$ $(\because HQ = HC)$

$r^2 = \left(\frac{r}{\sqrt{5}} + QH\right)^2 + (QH)^2$

$\Rightarrow \quad QH = \frac{r}{\sqrt{5}}$

$\therefore \quad HC = \frac{r}{\sqrt{5}} = \frac{RQ}{2}$

$RC = \sqrt{(RD)^2 + (DC)^2}$

$= \sqrt{\left(\frac{r}{\sqrt{5}}\right)^2 + \left(\frac{r}{\sqrt{5}}\right)^2} = r\sqrt{\frac{2}{5}}$

$\therefore \quad RC + FS = 2r\sqrt{\frac{2}{5}}$

30. Best way is to consider some values and verify the results.

31. $\angle OCT = 90°, \quad \angle DCT = 45°$

$\therefore \quad \angle OCB = 45°$

$\therefore \quad \angle COB = 45°$ (ΔBOC is a right angled triangle)

$\therefore \quad \angle AOC = 180° - 45° = 135°$

Now, $\because \quad CD = 10 \Rightarrow BC = 5$ cm $= OB$

Scanned by CamScanner

yoursmahboob.wordpress.com

$OC = 5\sqrt{2}$ cm $= OA$

$\Rightarrow$ Again, $AC^2 = OA^2 + OC^2 - 2OA \cdot OC \cos 135°$

$= 2(OA)^2 - 2(OA)^2 . \cos 135°$

$= 2(5\sqrt{2})^2 - 2(5\sqrt{2})^2 \times \left(-\frac{1}{\sqrt{2}}\right)$

$= 100 + \frac{100}{\sqrt{2}}$

$AC^2 \approx 170.70$

$AC \approx 13$ cm

$\Rightarrow$ $\therefore$ Perimeter of $\Delta OAC = OA + OC + AC$

$= 5\sqrt{2} + 5\sqrt{2} + 13 = 27$ cm

32. $\angle ACB = 60°$ $(\because \angle ACB + \angle ADB = 180°)$

and $\angle CAB = 30°$ $(\because \angle ACB + \angle CAB = 90°)$

$AC = 2 \times 6 = 12\,\text{cm}^2$

$\frac{BC}{AC} = \sin 30° = \frac{1}{2}$

$\Rightarrow$ $BC = 6$ cm

and $\frac{BC}{AB} = \tan 30° = \frac{1}{\sqrt{3}}$

$\Rightarrow$ $AB = 6\sqrt{3}$ cm

$\therefore$ Area of $\Delta ABC = \frac{1}{2} \times 6 \times 6\sqrt{3} = 18\sqrt{3}$ cm

33. Area of $\Delta BAE = \frac{1}{4} AC \times \frac{1}{3} BD$

$= \frac{1}{12}$ Area of ΔABC



34. $\frac{AE}{EC} = \frac{AB}{BC} = \frac{7.5}{10.5} = \frac{5}{7}$

Now, $AB^2 + BC^2 = AC^2$

$(5k)^2 + (7k)^2 = (18)^2$

$74k^2 = 324 \Rightarrow k^2 = \frac{324}{74}$

Area of $\Delta ABC = \frac{1}{2} \times AB \times BC = \frac{1}{2} \times 5k \times 7k$

$= \frac{35}{2} k^2 = \frac{35}{2} \times \frac{324}{74}$

$= 76.621$ cm

35. There are total 12 similar triangles each with equal area. But a larger triangle ABC (or DEF) has only 9 smaller triangles. Out of 9 triangles only 6 triangles are common.

$\therefore$ Area of common region

$= \frac{6}{9} \times 198 = 132\,\text{cm}^2$



36. $9 \times 180 - 2 \times 360$

$= 180 \times 5 = 900°$

$\because \begin{Bmatrix} n \times 180 - 2 \times 360 \\ = 180\,(n-4) \end{Bmatrix}$

37. $DS = \frac{AD}{2} = 6$ cm

and $DR = \frac{DC}{2} = 8$ cm $= OS$



$\therefore SR = 10$ cm and $OR = 6$ cm

$\therefore$ Area of $\Delta ORS = \frac{OS \times OR}{2} = \frac{SR \times OT}{2}$

$\frac{8 \times 6}{2} = \frac{10 \times OT}{2}$

$\Rightarrow$ $OT = \frac{48}{10}$ cm

$\therefore$ Area of circle $= \pi r^2 = \pi \times \left(\frac{48}{10}\right)^2 = \frac{576}{25}\pi$

38. $200 = 2^3 \times 5^2$

Number of total factors $= (3+1) \times (2+1) = 12$

$\therefore$ Total number of required rectangles $= \frac{12}{2} = 6$

$\text{Area} = b \times l$

$200 = 1 \times 200 = 2 \times 100$

$= 4 \times 50 = 5 \times 40$

$= 8 \times 25 = 10 \times 20$

39. Maximum probable number of circles $= {}^8C_3$

(Since, a circle can pass through any three non-collinear points)

But since 4 points are lie on the same circle so which reduces the formation of some circles.

$\therefore$ Actual number of circles $= {}^8C_3 - {}^4C_3 + 1$

$= 56 - 4 + 1 = 53$

NOTE Since when we subtract ${}^4C_3$, then actually we reduce one actually possible circle, so we have to add up 1.

40. Here, AC and BC are the secants of the circle and AB is tangent at D

$\therefore$ $AE \times AC = AD^2$

$AE \times 4 = (3)^2 \Rightarrow AE = \frac{9}{4}$

$\therefore$ $CE = 4 - \frac{9}{4} = \frac{7}{4}$

$\therefore$ $CE : (AE + AD) = \frac{7}{4} : \left(\frac{9}{4} + 3\right) = \frac{7}{4} : \frac{21}{4} = 1 : 3$

41. $\angle ADO$ is a right angle (angle of semicircle)

Again when OD is perpendicular on the chord AC and OD passes through the centre of circle ABC, then it must bisect the chord AC at D.

$\therefore$ $AD = CD = 6$ cm



Scanned by CamScanner

yoursmahboob.wordpress.com

42. $\angle CED = 120^\circ$ ($\square ACED$ is cyclic)

$\therefore \quad \angle BED = 60^\circ$

$\therefore \quad \angle EDB = 90^\circ$

$\therefore \quad \dfrac{BD}{BE} = \cos 30^\circ$

$\dfrac{6}{BE} = \dfrac{\sqrt{3}}{2}$

$\Rightarrow \quad BE = 4\sqrt{3}$ cm

$\therefore \quad BC = BE + CE$

$= 4\sqrt{3} + 5\sqrt{3} = 9\sqrt{3}$ cm

Now, since AB and CB are the secants of the circle.

$\therefore \quad BD \times BA = BE \times BC$

$6 \times BA = 4\sqrt{3} \times 9\sqrt{3}$

$\Rightarrow \quad BA = 18$ cm

Again, ΔACB is a right angled triangle ($\because \angle C = 90^\circ$)

$\therefore \quad AC = AB \sin 30^\circ$ ($\sin 30^\circ = 1/2$)

$AC = 9$ cm (Alternatively apply Pythagorus theorem).

and $AD = AB - BD = 12$ cm

$\therefore \quad \dfrac{AC}{AD} = \dfrac{9}{12} = \dfrac{3}{4}$

43. $AB = SQ = 25$ cm

$PQ = 24$ cm

$\therefore \quad SP = 7$ cm



$AP = 12$ cm and $SP = 7$ cm

(ΔPSQ, ΔQBR and ΔPAR are similar)

$\therefore \quad AS\ (= BQ) = 12 - 7 = 5$ cm

$\therefore \quad \dfrac{PS}{SQ} = \dfrac{PA}{AR}$

$\dfrac{7}{25} = \dfrac{12}{AR} \Rightarrow AR = \dfrac{300}{7}$

$\therefore \quad BR = AR - AB = \dfrac{300}{7} - 25$

$BR = \dfrac{125}{7}$

$\therefore \quad \dfrac{AB}{BR} = \dfrac{25 \times 7}{125} = \dfrac{7}{5}$

44. $\dfrac{SP}{PQ} = \dfrac{BQ}{QR}$

$\dfrac{7}{24} = \dfrac{5}{QR} \Rightarrow QR = \dfrac{120}{7}$

$\therefore \quad \dfrac{\text{Area of } \Delta APR}{\text{Area of } \Delta BQR} = \dfrac{\frac{1}{2} \times AP \times PR}{\frac{1}{2} \times BQ \times QR} = \dfrac{12 \times \frac{288}{7}}{5 \times \frac{120}{7}} = \dfrac{144}{25}$

($PR = PQ + QR$)

Alternatively:

$\dfrac{\text{Area of } \Delta APR}{\text{Area of } \Delta BQR} = \left(\dfrac{AP}{BQ}\right)^2 = \left(\dfrac{12}{5}\right)^2 = \dfrac{144}{25}$

45. $x^2 + y^2 + z^2 = xy + yz + zx$

$\Rightarrow \quad x^2 + y^2 + z^2 - xy - yz - zx = 0$

$\Rightarrow \quad 2(x^2 + y^2 + z^2 - xy - yz - zx) = 0$

$\Rightarrow \quad (x^2 + y^2) + (y^2 + z^2) + (z^2 + x^2) - 2xy - 2yz - 2zx = 0$

$\Rightarrow \quad (x - y)^2 + (y - z)^2 + (z - x)^2 = 0$

$\Rightarrow \quad x = y = z$

$\therefore$ The given triangle is an equilateral triangle.

46. Let $AD = 3a$ and $DC = 6a$

$\therefore \quad DH = HG = GC = \dfrac{6a}{3} = 2a$

$HM = MG = \dfrac{2a}{2} = a = SM$

(also)

$\therefore \quad NQ = a$

$\therefore \quad SQ = SM + MN + NQ$

$= a + 3a + a = 5a$



Since diagonal of square $SQ = 5a$

But, diameter of circle SQ = diagonal of square SQ

$\therefore \quad$ Radius of the circle $= \dfrac{5a}{2}$

$\Rightarrow \quad$ Area of the circle $= \pi \times \left(\dfrac{5a}{2}\right)^2$

Here $\dfrac{\text{Area of circle}}{\text{Area of rectangle}} = \dfrac{\frac{25}{4}(a^2\pi)}{3a \times 6a} = \dfrac{25\pi}{72}$

47. Area of hexagon $ABCDEF = 6 \times \dfrac{\sqrt{3}}{4} \times (6)^2$

$= 54\sqrt{3}$ cm^2

$\therefore \quad$ Area of $BDF = \dfrac{1}{2}$(Area of hexagon)

$= 27\sqrt{3}$ cm^2

48. $OA = AB = BC = OC = OP$

Let $OA = R$ (radius of the larger circle) then $OB = R\sqrt{2}$

Similarly $PQ = MQ = QR = r$ (radius of the smaller circle)

then $BQ = r\sqrt{2}$

$\therefore \quad BP = r + r\sqrt{2}$

and $BP = OB - OP = R\sqrt{2} - R$



$R\sqrt{2} - R = r + r\sqrt{2}$

$R(\sqrt{2} - 1) = r(\sqrt{2} + 1)$

$\Rightarrow \quad r = R(\sqrt{2} - 1)^2$

$r = R(3 - 2\sqrt{2})$

$\therefore \quad \dfrac{\text{Area of larger circle}}{\text{Area of smaller circle}} = \dfrac{\pi R^2}{4\pi r^2}$

$= \dfrac{R^2}{4(3 - 2\sqrt{2})^2 R^2} = \dfrac{1}{4(17 - 12\sqrt{2})}$

Scanned by CamScanner

yoursmahboob.wordpress.com

49. Apply the same logic as in the previous problem.

50. $\frac{\text{Area of } \Delta ABC}{\text{Area of } \Delta AED} = \left(\frac{BC}{0.65\,BC}\right)^2 = \frac{1}{0.4225}$

$\therefore$ Area of $\Delta AED = 0.4225 \times 68 = 28.73 \text{cm}^2$

51. Let the radius of each circle be r unit then

$PQ = QR = PR = 2r$

$\angle PDM = \angle QEN = 30°$



$\therefore \quad \frac{DM}{DP} = \cos 30°$

$DM = DP \times \frac{\sqrt{3}}{2} \qquad [DP = QE = (r)]$

$DM = \frac{r\sqrt{3}}{2}$

$\therefore \quad DE = DM + MN + NE$

$= \frac{r\sqrt{3}}{2} + 2r + \frac{r\sqrt{3}}{2} = (2+\sqrt{3})r$

$\therefore \quad DE = DF = EF = (2+\sqrt{3})r$

Again, $\angle PAM = \angle QBN = 30°$

$\therefore \quad \frac{PM}{AM} = \tan 30° = \frac{1}{\sqrt{3}}$



$\frac{r}{AM} = \frac{1}{\sqrt{3}}$

$\Rightarrow \quad AM = r\sqrt{3} = BN$

$\therefore \quad AB = AM + MN + NB$

$= r\sqrt{3} + 2r + r\sqrt{3} = 2r(1+\sqrt{3})$

$\therefore \quad AB = BC = AC = 2r(1+\sqrt{3})$

Ratio of perimeter of equilateral triangle = ratio of their sides

$\therefore$ Ratio of perimeter of $\Delta ABC : \Delta DEF : \Delta PQR$

$= 2(1+\sqrt{3}) : (2+\sqrt{3}) : 2$

52. $\Delta APQ \sim \Delta ACB, \quad BC = 2PQ$

and $\quad BC \parallel PQ$

$\Rightarrow \quad AE = 2AF$

$\Rightarrow \quad AE = EF$

Again $\Delta RGH \sim \Delta RPQ$

and $\quad PQ = 2GH$

(By mid-point theorem)



$\Rightarrow \quad RJ = 2RK$

$\Rightarrow \quad RK = JK$

But since $\quad EF = JK$

$\therefore \quad AE = EF = JK = RK$

$\therefore \quad RJ = RK + JK \quad$ and $\quad AF = AE + EF$

and $\quad RJ = AF = h$ (say),

then $\quad \frac{\text{Area of } \Delta PQR}{\text{Area of } \Delta ABC} = \frac{\frac{1}{2} \times PQ \times h}{\frac{1}{2} \times BC \times h} = \frac{PQ}{BC} = \frac{1}{2}$

53. It can be solved using the property of tangents.

(Tangents on the circle drawn from the same points are same in length)

Points M, A, N and B are the points of tangent.



$\therefore \quad PS + QR = PQ + SR = 2(21) = 42 \text{ cm}$

$\therefore \quad$ Perimeter of trapezium $= 2(42) = 84 \text{ cm}$

54. Let MN be the bridge.

$\Delta APM \sim \Delta ABC$

$\therefore \quad \frac{AP}{PM} = \frac{AB}{BC}$

$\frac{500}{PM} = \frac{1500}{3600} \Rightarrow PM = 1200 = QN = BR$



$\therefore \quad RC = BC - BR = 2400 \text{ m}$

and $\quad NR = BQ = 700 \text{ m}$

$\therefore \quad NC = \sqrt{NR^2 + RC^2}$

$NC = 2500 \text{ m}$

Also $\quad AM = \sqrt{AP^2 + PM^2}$

$AM = 1300 \text{ m}$

$\therefore$ Total distance to be travelled $= AM + MN + NC$

$= 1300 + 300 + 2500$

$= 4100 \text{ m}$

55. Let $AD = h$ (say)

then Area of ΔABC

$= \frac{1}{2} bc \sin 120° = \frac{\sqrt{3}}{4} bc$

Area of ΔBAD

$= \frac{1}{2} ch \sin 60°$

$= \frac{\sqrt{3}}{4} ch$



and area of $\Delta CAD = \frac{1}{2} bh \sin 60° = \frac{\sqrt{3}}{4} bh$

Now, $\quad A(\Delta ABC) = A(\Delta BAD) + A(\Delta CAD)$

$\frac{\sqrt{3}}{4} bc = \frac{\sqrt{3}}{4} ch + \frac{\sqrt{3}}{4} bh$

$\Rightarrow \quad bc = h(b + c)$

$\Rightarrow \quad h = \frac{bc}{b+c}$

Scanned by CamScanner

yoursmahboob.wordpress.com

13 ELEMENTS OF ALGEBRA

Algebra plays a very crucial role in CAT since on an average 35–40% problems of 'quantitative aptitude' section are related to algebra and the question asked from this section are not very calculative and can be solved quickly through options. According to the past years question papers, the questions of this section are very logical even being algebraic. Their level can be of High School Standard or IIT-JEE level. But you need not to go for an IIT coaching or for higher studies in maths. For this, first you get the command over the fundamentals, then solve the plenty of problems so that you must be aware with variety and diversity of problems. This section is written in this book as per the needs of those students who are really very poor in algebra and for the same, I have started from the zero level and created the standard of problems higher than CAT level. So in this journey of learning of algebra you have to learn maximum from the problems given in the chapter, because theory is always not sufficient in itself.

FUNDAMENTAL CONCEPT OF ALGEBRA

1. Literal Numbers (or literals) : Algebra is a branch of mathematics in which all the arithmetical operations are performed by using letters (like, $a, b, c, ..., p, q, r, ... x, y, z$) alongwith numerals. The letters used in algebra represent generalised numbers (or unknown) numbers. They are called literals.

2. Operations on Literals : Since literals represent numbers, so they obey all the rules of operations of addition, subtraction, multiplication and division of numbers.

Addition of Literals and Numbers

(i) $x + y = y + x$

(ii) $x + 3 = 3 + x$

(iii) $(x + y) + z = x + (y + z)$

(iv) $(x + 0) = x = (0 + x)$

(v) $x + (-x) = 0 = (-x) + x$

Subtraction of Literals and Numbers

(i) $4 - x$

(ii) $x - 4$

(iii) $x - y = -(y - x)$

(iv) $y - x = -(x - y)$

(v) $x - 0 = x$

Multiplication of Literals and Numbers

(i) $x \times y = xy$ $\quad (xy = x + x + x + ... \ y \text{ times})$

(Ii) $4 \times x = 4x$ (not as $x4$) $\quad (4x = x + x + x + x)$

(iii) $1 \times x = x$ (not as $1x$)

(iv) $xy = yx$

(v) $(xy)z = x(yz)$

(vi) $1 \cdot x = x = x \cdot 1$

(vii) $x(y + z) = xy + xz$

(viii) $0 \cdot x = 0 = x \cdot 0$

Division of Literals and Numbers

(i) $4 \div x = \frac{4}{x}$ $\quad$ (ii) $x \div 4 = \frac{x}{4}$

(iii) $x \div y = \frac{x}{y}$ $\quad$ (iv) $0 \div x = 0$

NOTE $x \neq 0$, *i.e.*, $\frac{x}{0}$ is not defined.

Powers of a Literal

(i) $x \times x = x^2$ or $x \times x \times x = x^3$ etc.

i.e., $x \times x \times x \times ... \ n \text{ times} = x^n$

(ii) $x^1 = x$

(iii) $x^0 = 1$

NOTE x^n is read as x raised to the power n or x to the power n or x power n.

$x \rightarrow$ base

$n \rightarrow$ exponent or index

$x^n \rightarrow$ exponential expression

Scanned by CamScanner

yoursmahboob.wordpress.com

LANGUAGE OF ALGEBRA

Statement	Meaning
$a=b$	a is equal to b
$a\neq b$	a is not equal to b
$a<b$	a is less than b
$a>b$	a is greater than b
$a\leq b$	a is less than or equal to b
$a\geq b$	a is greater than or equal to b
$a\nless b$	a is not less than b
$a\ngtr b$	a is not greater than b.

CONSTANTS AND VARIABLES

Constants : A symbol which has a fixed value is called a constant.

e.g., $4, 5, 0, -3, \frac{2}{5}, 3\frac{2}{7}$, etc.

Variable : A symbol which can assume various numerical values is called a variable.

e.g., Area of rectangle = length $(l)\times$ breadth $(b)=l\times b$

here length (l) and breadth (b) can assume any possible numerical values.

Perimeter of a square $= 4a$ ($a \rightarrow$ side of a square)

here a can assume any possible numerical value.

Price of 10 balls $=10x=10\times 2=20$ or $10\times 5=50$, etc.

here x can assume any possible numerical value.

NOTE In $5x$, 5 is constant and x is variable but together $5x$ is variable.

Similarly, $5+x, x-5, 5-x, \frac{x}{5}$ and $\frac{5}{x}$ are variables.

Hence a combination of a constant and a variable is a variable.

ALGEBRAIC EXPRESSION

A collection of constants and literals connected by one or more of the operations of addition, subtraction, multiplication and division is called an **"algebraic expression".**

The various parts of an algebraic expression separated by + or − sign are called **"terms"** of the algebraic expression.,

e.g.,

	Algebraic expression	Number of terms	Terms
(i)	$4x$	1	$4x$
(ii)	$8x+3y$	2	$8x, 3y$
(iii)	$7+3x-2y^2$	3	$7, 3x, -2y^2$
(iv)	$\frac{7}{8}x^3+3x^2+4x-9$	4	$\frac{7}{8}x^3, 3x^2, 4x, -9$

NOTE Multiplication and division do not separate the terms of an algebraic expression, *e.g.*, $7x$ is a single term, similarly $\frac{x}{7}$ is also a single term.

TYPES OF ALGEBRAIC EXPRESSIONS

1. Monomial : An algebraic expression having only one term is called a monomial.

e.g., $3x, -5y, 12xy^2, \frac{3x}{y}, \frac{7x^2}{3y}$, etc.

2. Binomial : An algebraic expression having two terms is called a binomial, *e.g.*, $3x+4y, 7x^2+2x, 9yz^2-4x^2, 3x-\frac{2}{3}y$, etc.

NOTE A trinomial has three terms.

3. Polynomial (or multinomial) : An algebraic expression having two or more than two terms is called a multinomial or polynomial, *e.g.*,

(i) $7x^2-3y$ is a polynomial having 2 terms

(ii) $7x^4-3x^2+5x$ is a polynomial having 3 terms

(iii) $3x^4-7x^3+3xy+8$ is a polynomial having 4 terms, etc.

NOTE

Mono → single or one
Bi → two
Tri → three
Poly/Multi → many
and nomial → terms

Product : When two or more constants or literals (or both) are multiplied, then the result so obtained is called the **'product'**, *e.g.*, $7xy$ is the product of 7, x and y.

Factors : Each of the quantity (constant or literal) multiplied together to form a product is called a **'factor'** of the product.

A constant factor is called a **numerical factor** and any factor containing only literals is called a **literal factor.** *e.g.*,

(i) In $7xy$, the numerical factor is 7 and literal factors are x, y and xy.

(ii) In $-7x^2y$, the numerical factor is -7 and the literal factors are, x^2, y, x, xy and x^2y.

Constant term : The term of an algebraic expression having no literal factors is called its **constant term.** *e.g.*

In the algebraic expression $3x^2+7x+8$, the constant term is 8. (Since 8 is not associated with any literals)

Coefficients : In an algebraic expression any factor of a term is called the **coefficient** of the remaining factor of the term, *e.g.*,

$$4xy+5x^2y-17$$

In the first term $4xy$,

(i) numerical coefficient $=4$

(ii) literal coefficient $=xy$

(iii) coefficient of $4=xy$

(iv) coefficient of $x=4y$

(v) coefficient of $y=4x$

(vi) coefficient of $4x=y$

(vii) coefficient of $4y=x$

Similarly we can find the coefficient of the other two terms

Like and unlike terms : The terms having same literal coefficients are called **like terms** else the terms are called **unlike terms,**

Scanned by CamScanner

yoursmahboob.wordpress.com

e.g.,

(i) $7xy, 4xy, 9xy, -\frac{3}{2}xy$ are like terms

(ii) $3x^2y, 5x^2y, 8x^2y, \ldots -7x^2y$ are like terms

(iii) $3x, 5x^2y, 9xy^2z$ are unlike terms, etc.

Polynomials in one variable : An algebraic expression of the form $a+bx+cx^2+dx^3+\ldots$ where $a, b, c, d, \ldots$ are constants and x is a variable, is called a polynomial in the variable x.

The greatest power of x present in the polynomial is called the **degree of the polynomial.**

NOTE No term in a polynomial can be of the form $\frac{1}{x}, \frac{1}{x^2}$, etc.

e.g.,

(i) $7+3x$ is a polynomial in x of degree 1.

(ii) $7y^2+3y-10$ is a polynomial in y of degree 2.

(iii) $8k^3+3k^2-15$ is a polynomial in k of degree 3.

(iv) $7x^5+3x^2+8$ is a polynomial in x of degree 5.

(v) $3x^4+5x^3+7x-\frac{8}{x}$ is not a polynomial.

(vi) 8 can be written as $8x^0$, so it is a polynomial in x of degree 0, *i.e.*, in general a single constant term is always of degree 0 (zero).

Polynomials in two or more variables : Any algebraic expression in two or more variables is called a polynomial if every variable present in it has only non-negative integral powers.

In case of a polynomial in two or more variables, the sum of the powers of the variables in each term is taken and the greatest sum is the **degree of the polynomial.**

NOTE No term in a polynomial can be of the form $\frac{1}{x}, \frac{1}{x^2}, \frac{x}{y}$, etc.

Examples :

(i) $8x^2-5xy+3x-7y+2$ is a polynomial in two variables x and y.
The degree of its terms are 2, (1+1), 1, 1, 0, so the degree of the polynomial is 2.

(ii) $8a^3+9b^2a^3+12b^3-\frac{5}{7}a+15$ is a polynomial in two variables a and b.
The degree of its terms are 3, (2+3), 3, 1, 0, so the degree of the polynomial is 5.

NOTE The degree of a polynomial is equal to the maximum value of the sum of the powers of the variables in any term.
Degree is always a whole number. It is not defined for polynomials having fractional and negative exponent.

Substitution : The process of finding the value of an algebraic expression by replacing the variables (literals) by their particular values is called substitution.

EXAMPLE 1 *If $x=3$ and $y=4$, find the value of*
(i) $3x+2y$ (ii) $4x-3y$ (iii) $18xy$ (iv) $\frac{15x}{12y}$

SOLUTION (i) $3x+2y=3\times3+2\times4$ (Substituting $x=3$ and $y=4$)
$=9+8=17$

(ii) $4x-3y=4\times3-3\times4$ (Substituting $x=3$ and $y=4$)
$=12-12=0$

(iii) $18xy=18\times3\times4$ (Substituting $x=3$ and $y=4$)
$=216$

(iv) $\frac{15x}{12y}=\frac{15\times3}{12\times4}=\frac{15}{16}$

EXAMPLE 2 *If $x=-3$, find the value of $4x^2-5x+3$*

SOLUTION $4x^2-5x+3=4\times(-3)^2-5\times(-3)+3$
$=36+15+3=54$

EXAMPLE 3 *If $a=4$, $b=-3$, $c=2$, find the value of $4a^2+5b-12c$.*

SOLUTION $4a^2+5b-12c=4\times(4)^2+5(-3)-12(2)$
$=64-15-24=25$

OPERATIONS ON ALGEBRAIC EXPRESSION

Addition of like terms : In any algebraic expression only like terms can be added or subtracted.

Thus, the sum of two or more like terms is a like term whose numerical coefficient is the sum of coefficients of given like terms. *e.g.*,

$2x=x+x$, $3x=x+x+x$, $4x=x+x+x+x$.

$\therefore 2x+3x+4x=(x+x)+(x+x+x)+(x+x+x+x)$
$=9x$

Similarly, $2x^2+3x^2=(2+3)x^2=5x^2$

and $5xy+(-3xy)=[5+(-3)]xy=2xy$

Thus, we cannot further simplify $7x+5x^2$ into single term since both are unlike terms.

ADDITION OF ALGEBRAIC EXPRESSIONS

EXAMPLE 1 *Solve the following expression*
$(4a+2b-3c)+(3a-2b+4c)$

SOLUTION $(4a+2b-3c)+(3a-2b+4c)$
$=(4a+3a)+(2b-2b)+(-3c+4c)$
$=(4+3)a+(2-2)b+(-3+4)c$
$=7a+c$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 2 *Add* $2x^2 + 5xy - 2y^2$, $3x^2 - 2xy + 5y^2$ *and* $-2x^2 + 8xy + 3y^2$.

SOLUTION $(2x^2 + 5xy - 2y^2) + (3x^2 - 2xy + 5y^2) + (-2x^2 + 8xy + 3y^2)$

$= (2x^2 + 3x^2 - 2x^2) + (5xy - 2xy + 8xy) + (-2y^2 + 5y^2 + 3y^2)$

$= 3x^2 + 11xy + 6y^2$

SUBTRACTION OF ALGEBRAIC EXPRESSIONS

EXAMPLE 1 *Subtract* $3x + 2y - z$ *from* $4x - 5y + 3z$

SOLUTION $(4x - 5y + 3z) - (3x + 2y - z)$

$= (4x - 3x) + (-5y - 2y) + [3z - (-z)]$

$= x - 7y + 4z$

EXAMPLE 2 *Subtract* $7x^3 - 3x^2 + 8x + 16$ *from* $9x^3 + 6x^2 - 6x + 20$

SOLUTION $(9x^3 + 6x^2 - 6x + 20) - (7x^3 - 3x^2 + 8x + 16)$

$= (9x^3 - 7x^3) + [6x^2 - (-3x^2)] + [(-6x) - (8x)] + (20 - 16)$

$= 2x^3 + 9x^2 - 14x + 4$

MULTIPLICATION OF ALGEBRAIC EXPRESSIONS

It follows the distributive property. In this operation all the numerals are multiplied with each other individually and all the literals (or variables) multiplied with each other as per the rule.

EXAMPLE 1 *Find the product of* $6xy$ *and* $7x^2$.

SOLUTION $6xy \times 7x^2 = (6 \times 7) \times (xy \times x^2)$

$= (6 \times 7) \times (x \times y \times x \times x) = 42 \times x^3y$

EXAMPLE 2 *Find the product of* $3ab^2$ *and* $(4ab + 3b^2)$

SOLUTION $3ab^2 \times (4ab + 3b^2)$

$= 3ab^2 \times 4ab + 3ab^2 \times 3b^2$

$= 3 \times a \times b \times b \times 4 \times a \times b + 3 \times a \times b \times b \times 3 \times b \times b$

$= 12a^2b^3 + 9ab^4 = 3ab^3(4a + 3b)$

EXAMPLE 3 *Multiply* $(a + b)$ *by* $(c + d)$

SOLUTION $(a + b)(c + d) = a(c + d) + b(c + d)$

$= ac + ad + bc + bd$

EXAMPLE 4 *Multiply* $(5x - 4)$ *by* $(3x + 5)$

SOLUTION $(5x - 4) \times (3x + 5) = 5x \times (3x + 5) - 4(3x + 5)$

$= 15x^2 + 25x - 12x - 20$

$= 15x^2 + 13x - 20$

DIVISION OF ALGEBRAIC EXPRESSIONS

EXAMPLE 1 *Solve* $x^6 \div x^4$

SOLUTION $\frac{x^6}{x^4} = \frac{x \times x \times x \times x \times x \times x}{x \times x \times x \times x}$

$= x \times x = x^2$

EXAMPLE 2 *Solve* $35x^3y^2 \div 7x^2y^2$

SOLUTION $\frac{35x^3y^2}{7x^2y^2} = \frac{7 \times 5 \times x \times x \times x \times y \times y}{7 \times x \times x \times y \times y}$

$= 5x$

Thus, we can say $7x^2y^2$ and $5x$ are the two factors of $35x^3y^2$.

EXAMPLE 3 *Divide* $14x^3y^2 + 8x^2y^3 - 32x^2y^5$ *by* $-2xy^2$.

SOLUTION $\frac{14x^3y^2 + 8x^2y^3 - 32x^2y^5}{-2xy^2}$

$= \frac{(14x^3y^2)}{(-2xy^2)} + \frac{(8x^2y^3)}{(-2xy^2)} + \frac{(-32x^2y^5)}{(-2xy^2)}$

$= -7x^2 - 4xy + 16xy^3$

EXAMPLE 4 *Divide* $(4x^2 + 3x + 2)$ *by* $(x + 2)$

SOLUTION

$$\begin{array}{r|l} x+2 \;\overline{)\; 4x^2 + 3x + 2} & 4x - 5 \\ \cline{2-2} \quad 4x^2 + 8x & \\ \cline{1-1} \quad -5x + 2 & \\ \quad -5x - 10 & \\ \cline{1-1} \quad 12 & \end{array}$$

Here $(x + 2)$ is divisor
and $(4x - 5)$ is quotient
and 12 is remainder
and $(4x^2 + 3x + 2)$ is the dividend.

NOTE (i) If there is a '+' sign before a bracket, then the signs of the terms inside the bracket do not change.
(ii) If there is a '−' sign before a bracket, then the signs of all the terms inside the bracket change.

GENERAL FORM OF A POLYNOMIAL

The expression of the form $a_0x^n + a_1x^{n-1} + a_2x^{n-2} + \ldots a_n$ in which $a_0, a_1, a_2, \ldots a_n$ are constants ($a_0 \neq 0$) and n is a positive integer is called a polynomial (or rational integral function) in x of degree n. We may denote it by $f(x)$, *i.e.*,

$$f(x) = a_0x^n + a_1x^{n-1} + a_2x^{n-2} + \ldots a_n.$$

Algebraic Expression as a Function : A function is an operation which forms a relation between two variables. *e.g.*, $y = x^2$, $y = 3x$, $y = x^2 + 3$, etc.

This operation is represented by $f(x)$, *i.e.*,

$y = f(x) \Rightarrow f(x) = x^2$ (f is called operand)

$f(x) = 3x \Rightarrow f(x) = x^2 + 3$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 1 *If $f(x) = x^3 + 2x$, then find the value of $f(3)$.*

SOLUTION $\because \quad f(x) = x^3 + 2x$

$\therefore \quad f(3) = (3)^3 + 2(3) = 27 + 6 = 33.$

EXAMPLE 2 *If $f(x) = 2x^3 + 3x^2 + 5$, then find the value of $f(2)$.*

SOLUTION $\because \quad f(x) = 2x^3 + 3x^2 + 5$

$\therefore \quad f(2) = 2(2)^3 + 3(2)^2 + 5$

$= 16 + 12 + 5 = 33$

GRAPHICAL REPRESENTATION OF ALGEBRAIC EXPRESSION

All the polynomial expressions that can be written as $y = f(x)$ can be represented in two dimensional co-ordinate system.

EXAMPLE 1 $y = f(x) = 2x + 1$

SOLUTION

x	−3	−2	−1	0	1	2	3
y	−5	−3	−1	1	3	5	7

HINT Find the corresponding values of y for each value of x. Generally we consider some +ve and some −ve values of x.

Now we plot the graph as per the values obtained in the table.



The points are represented as (x, y) and the values of (x, y) represent the points on the plane.

NOTE $y = 2x + 1$ is a linear equation, therefore the graph of the given equation shows a straight line.

EXAMPLE 2 $f(x) = x^2 + 2x - 3$

SOLUTION $y = f(x) = x^2 + 2x - 3$



x	−4	−3	−2	−1	0	1	2	3
y	5	0	−3	−4	−3	0	5	12

Since $y = x^2 + 2x - 3$ is a quadratic equation, therefore the graph is a parabola.

Remainder theorem : If a polynomial (*i.e.*, a rational integral function) $f(x)$ is divided by $(x - a)$, then the remainder is obtained by substituting a for x in $f(x)$, *i.e.*, the remainder is $f(a)$.

EXAMPLE 1 *Find the remainder when $x^2 - 6x + 5$ is divided by $(x + 2)$.*

SOLUTION Let $f(x) = x^2 - 6x + 5$. Thus by remainder theorem, the remainder when $f(x)$ is divided by $(x + 2)$, *i.e.*, $[x - (-2)]$ is $f(-2)$

$\therefore \quad f(-2) = (-2)^2 - 6(-2) + 5$

$= 4 + 12 + 5 = 21.$

$\therefore$ Thus the remainder is 21.

NOTE
1. If a polynomial $f(x)$ is divided by $(x + a)$, then remainder is $f(-a)$
2. If a polynomial $f(x)$ is divided by $(x - a)$, then remainder is $f(a)$
3. If a polynomial $f(x)$ is divided by $(ax + b)$, then the remainder is $f(-b/a)$

HINT To get the value of remainder first of all write the divisor equal to zero, *i.e.*, if divisor is $(x + a)$, then write $x + a = 0$
Then find the value of x, *i.e.*, $x + a = 0 \Rightarrow x = -a$
Then put the obtained value of x in the polynomial, *i.e.*, $f(x) = 3x^2 + 4x - 5 \Rightarrow f(-a) = 3(-a)^2 + 4(-a) - 5$ then solve the function (or expression) and get the simplified value of remainder.

EXAMPLE 2 *If $2x^3 + 3x^2 + 7x + 6$ be divided by $2x + 1$, find the remainder.*

SOLUTION Let $f(x) = 2x^3 + 3x^2 + 7x + 6$.

Then the remainder when $f(x)$ is divided by $(2x + 1)$

$\therefore \quad 2x + 1 = 0$

$\Rightarrow \quad x = -\frac{1}{2}$

$$\therefore \quad f\left(-\frac{1}{2}\right) = 2\left(-\frac{1}{2}\right)^3 + 3\left(-\frac{1}{2}\right)^2 + 7\left(-\frac{1}{2}\right) + 6$$

$$= -\frac{1}{4} + \frac{3}{4} - \frac{7}{2} + 6$$

$$= \frac{-1 + 3 - 14 + 24}{4} = \frac{12}{4} = 3$$

EXAMPLE 3 *Find the remainder when the expression $3x^3 + 8x^2 - 6x + 1$ is divided by $(x + 3)$.*

SOLUTION Let $f(x) = 3x^3 + 8x^2 - 6x + 1$

$\because \quad x + 3 = 0 \Rightarrow x = -3$

Scanned by CamScanner

yoursmahboob.wordpress.com

$f(-3) = 2(-3)^3 + 3(-3)^2 - 6(-3) + 1$

$\therefore \quad = -81 + 72 + 18 + 1 = 10$

Hence the remainder is 10.

EXAMPLE 4 *When $x^3 + 3x^2 - kx + 4$ is divided by $x - 2$, the remainder is k. Find the value of the constant k.*

SOLUTION Let $f(x) = x^3 + 3x^2 - kx + 4$

Now, since $x - 2 = 0 \Rightarrow x = 2$

$\therefore \quad f(2) = (2)^3 + 3(2)^2 - k(2) + 4 = 24 - 2k$

$\therefore \quad$ Remainder $= 24 - 2k = k \Rightarrow k = 8$

(∵ the given remainder is k)

Factor Theorem : *If $f(x)$ be a polynomial (i.e. rational integral function) in x and $f(a) = 0$, then $(x - a)$ is a factor of $f(x)$.*

By remainder theorem if $f(x)$ be divided by $(x - a)$, the remainder is $f(a)$. But $f(a) = 0$, i.e., there is no remainder.

$\therefore$ $f(x)$ is exactly divisible by $(x - a)$

Hence $(x - a)$ is a factor of $f(x)$

NOTE 1. *If $f(x)$ be a polynomial and $f(-a) = 0$, then $(x + a)$ is a factor of $f(x)$.*

2. *If $f(x)$ be a polynomial and $f(-b/a) = 0$, then $(ax + b)$ is a factor of $f(x)$.*

EXAMPLE 1 *Show that $(x - 2)$ is a factor of the polynomial $2x^2 - 5x + 2$*

SOLUTION Let $f(x) = 2x^2 - 5x + 2$

$\because \quad (x - 2) = 0 \Rightarrow x = 2$

$\therefore \quad f(2) = 2(2)^2 - 5(2) + 2$

$f(2) = 0$

$\therefore$ By factor theorem $(x - 2)$ is a factor of $2x^2 - 5x + 2$

EXAMPLE 2 *Prove that $(2x + 5)$ is a factor of the polynomial $2x^2 + 11x + 15$.*

SOLUTION Let $f(x) = 2x^2 + 11x + 15$

$\because \quad 2x + 5 = 0 \Rightarrow x = -5/2$

$\therefore \quad f(-5/2) = 2(-5/2)^2 + 11(-5/2) + 15$

$= \frac{25}{2} - \frac{55}{2} + 15$

$f(-5/2) = 0$

Hence, $(2x - 5)$ is a factor of $f(x) = 2x^2 - 11x - 15$

EXAMPLE 3 *Prove that $(a - b)$ is a factor of $(a^5 - b^5)$*

SOLUTION Let $f(a) = a^5 - b^5$

$\because \quad (a - b) = 0 \Rightarrow a = b$

$\therefore \quad f(b) = (b)^5 - b^5$

$f(b) = 0$

$\therefore \quad f(a) = 0$

Hence $(a - b)$ is a factor of $a^5 - b^5$.

EXAMPLE 4 *If $(x - 3)$ and $(x - 4)$ are both the only factors of $f(x)$, then find $f(x)$.*

SOLUTION Since there are only two factors of $f(x)$, therefore the product of $(x - 3)$ and $(x - 4)$ is equal to $f(x)$

$\therefore \quad f(x) = (x - 3)(x - 4)$

$f(x) = x^2 - x - 12$

H.C.F. AND L.C.M. OF POLYNOMIALS

1. A polynomial $D(x)$ is a divisor of the polynomial $P(x)$ if it is a factor of $P(x)$. Where $Q(x)$ is another polynomial such that $P(x) = D(x) \cdot Q(x)$
2. **HCF/GCD (Greatest Common Divisor) :** A polynomial $h(x)$ is called the HCF or GCD of two or more given polynomials, if $h(x)$ is a polynomial of highest degree dividing each one of the given polynomials.

NOTE The coefficient of highest degree term is always taken as positive.

3. **L.C.M. (Least Common Multiple) :** A polynomial $P(x)$ is called the LCM of two or more given polynomials, if it is a polynomial of smallest degree which is divided by each one of the given polynomials. For any two polynomials $P(x)$ and $Q(x)$. We have :

$P(x) \times Q(x) =$ [HCF of $P(x)$ and $Q(x)$]

$\times$ [LCM of $P(x)$ and $Q(x)$]

EXAMPLE 1 *Find the HCF and LCM of the following polynomials $(x + 2)^2(x - 3)^2(x + 1)^2, (x + 1)^3(x + 2)^3(x - 3)$*

SOLUTION Let $P(x) = (x + 2)^2(x - 3)^2(x + 1)^2$

and $Q(x) = (x + 1)^3(x + 2)^3(x - 3)$

HCF $= (x + 1)^2(x + 2)^2(x - 3)$

(For the HCF we take the highest power of factors common to both $P(x)$ and $Q(x)$)

and LCM $= (x + 1)^3(x + 2)^3(x - 3)^2$

[For LCM we take the highest powers of the factors either of $P(x)$ or $Q(x)$]

EXAMPLE 2 *Find the HCF and LCM of the following polynomials $22x(x + 1)^2$, $36x^2(2x^2 + 3x + 1)$*

SOLUTION Let $P(x) = 22x(x + 1)^2$

and $Q(x) = 36x^2(2x^2 + 3x + 1)$

$P(x) = 2 \times 11 \times x \times (x + 1)^2$

and $Q(x) = 2 \times 18 \times x^2 \times (x + 1)(2x + 1)$

$\therefore \quad$ HCF $= 2 \times x \times (x + 1) = 2x(x + 1)$

and LCM $= 2x(x + 1) \times 11 \times 18 \times x \times (x + 1)(2x + 1)$

$= 396x^2(x + 1)^2(2x + 1)$

(To find the LCM, first take the HCF and then take all the rest factors).

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *Find the HCF and LCM of* $(3+13x-30x^2)$ *and* $(25x^2-30x+9)$

SOLUTION Let $P(x)=(3+13x-30x^2)$

and $Q(x)=(25x^2-30x+9)$

or $P(x)=3+13x-30x^2$

$=3+18x-5x-30x^2$

$=-(6x+1)(5x-3)$

$Q(x)=25x^2-30x+9=(5x-3)^2$

$\therefore$ HCF of $P(x)$ and $Q(x)=(5x-3)$

and LCM of $P(x)$ and $Q(x)=-(5x-3)^2(6x+1)$.

EXAMPLE 4 *The HCF of two polynomials is* $(x-2)(x+3)$ *and their LCM is* $(x-2)^2(x+3)(x+1)$. *If one of the polynomial is* x^2-x-2, *find the other.*

SOLUTION HCF $=(x-2)(x+3)$

LCM $=(x-2)^2(x+3)(x+1)$

and HCF $\times$ LCM $=(x-2)^3(x+3)^2(x+1)$

$\therefore$ $P(x)=x^2-x-2$

Let $=x^2-2x+x-2$

$=(x-2)(x+1)$

$\therefore$ $P(x)\cdot Q\cdot(x)=\text{HCF}\times\text{LCM}$

$\therefore$ $Q(x)=\dfrac{\text{HCF}\times\text{LCM}}{P(x)}$

$=\dfrac{(x-2)^3(x+3)^2(x+1)}{(x-2)(x+1)}$

$=(x-2)^2(x+3)^2$

$\therefore$ The other polynomial [say $Q(x)$] is $(x-2)^2(x+3)^2$.

Rational Expressions : If $P(x)$ and $Q(x)$ are two polynomials such that $Q(x)\neq 0$, then the quotient $\dfrac{P(x)}{Q(x)}$ is called a rational expression.

- Every polynomial is a rational expression but a rational expression need not be a polynomial.
- The rational expression $\dfrac{P(x)}{Q(x)}$ is said to be in its simplest form (or in lowest terms) if the G.C.D. of $P(x)$ and $Q(x)$ is 1.
- To express a rational expression in its simplest form, express the polynomials in the numerator and in the denominators as product of simplest factors (*i.e.*, no further factorization is possible), and then cancel the common factors.

EXAMPLE 1 *Which of the following algebraic expressions are polynomials?*

(a) $x^2-\sqrt{3}x+4$ (b) $x^3-3x^2+4\sqrt{x}$

(c) $\sqrt{2}x^2-\sqrt{3}x+\sqrt{5}$ (d) x^3-2x+x^{-2}

SOLUTION (a) $x^2-\sqrt{3}x+4$ is a polynomial.

and (c) $\sqrt{2}x^2-\sqrt{3}x+\sqrt{5}$ is also a polynomial

(b) $x^3-3x^2+4\sqrt{x}$ is not polynomial since $4\sqrt{x}=4x^{1/2}$, *i.e.*, power of x is $\dfrac{1}{2}$ (*i.e.*, fractional)

(d) x^3-2x+x^{-2} is not a polynomial since x^{-2} has negative power of x.

EXAMPLE 2 *Express the following in the lowest terms.*

$\dfrac{x^2+6x+9}{x^2-9}$

SOLUTION $\dfrac{x^2+6x+9}{x^2-9}=\dfrac{(x+3)(x+3)}{(x+3)(x-3)}=\dfrac{x+3}{x-3}$

IMPORTANT FORMULAE

1. $(a+b)^2=a^2+b^2+2ab$
2. $(a-b)^2=a^2+b^2-2ab$
3. $(a+b)^2=(a-b)^2+4ab$
4. $(a-b)^2=(a+b)^2-4ab$

} By taking the difference of formula 1 and 2.

5. $(a^2+b^2)=\dfrac{1}{2}[(a+b)^2+(a-b)^2]$
6. $a^2-b^2=(a+b)(a-b)$
7. $(a+b)^3=a^3+b^3+3ab(a+b)$
8. $(a-b)^3=a^3-b^3-3ab(a-b)$
9. $a^3+b^3=(a+b)(a^2+b^2-ab)$
10. $a^3-b^3=(a-b)(a^2+b^2+ab)$
11. $(a+b+c)^2=(a^2+b^2+c^2)+2(ab+bc+ac)$
12. $a^3+b^3+c^3-3abc$
$=(a+b+c)(a^2+b^2+c^2-ab-bc-ac)$

if $a+b+c=0$, then $a^3+b^3+c^3=3abc$

13. $a^4+b^4+a^2b^2=(a^2+b^2+ab)(a^2+b^2-ab)$
14. $a^4-b^4=(a-b)(a+b)(a^2+b^2)$
15. $a^8-b^8=(a-b)(a+b)(a^2+b^2)(a^4+b^4)$

BASIC FACTS TO REMEMBER

1. To factorize the cyclic expressions :

(a) Arrange the terms in decreasing or increasing powers of one of the letters (or literals)

(b) Make one factor common by taking two or three terms together.

(c) Rewrite the terms of the other factor in decreasing or increasing power of the next letter.

(d) Repeat the process till all the factors are found out.

Scanned by CamScanner

yoursmahboob.wordpress.com

2. Sigma (Σ) notation :

$\Sigma x = x + y + z$, for letters x, y, z

$\Sigma xy = xy + yz + zx$

$\Sigma x^2(y - z) = x^2(y - z) + y^2(z - x) + z^2(x - y)$

3. Some important results :

(a) $\Sigma(x - y) = 0$

(b) $\Sigma(x^2 - y^2) = 0$

(c) $\Sigma(x^3 - y^3) = 0$

(d) $\Sigma x(y - z) = 0$

(e) $\Sigma x^2(y^2 - z^2) = 0$

(f) $\Sigma x^2(y - z) = -(x - y)(y - z)(z - x)$

(g) $\Sigma x(y^2 - z^2) = (x - y)(y - z)(z - x)$

(h) $\Sigma(x - y)^3 = 3(x - y)(y - z)(z - x)$

EXAMPLE 1 *Factorize* $x(y^2 + z^2) + y(z^2 + x^2) + z(x^2 + y^2) + 2xyz$

SOLUTION $x(y^2 + z^2) + y(z^2 + x^2) + z(x^2 + y^2) + 2xyz$

$= xy^2 + xz^2 + yz^2 + x^2y + x^2z + y^2z + 2xyz$

Arranging in decreasing powers of x

$= x^2y + x^2z + xy^2 + xz^2 + 2xyz + y^2z + yz^2$

$= x^2(y + z) + x(y^2 + z^2 + 2yz) + yz(y + z)$

$= x^2(y + z) + x(y + z)^2 + yz(y + z)$

$= (y + z)[x^2 + x(y + z) + yz]$

$= (y + z)(x^2 + xy + xz + yz)$

$= (y + z)[x(x + y) + z(x + y)]$

$= (y + z)(x + y)(x + z)$

$= (x + y)(y + z)(z + x)$

EXAMPLE 2 *Factorize* $\Sigma xy(x + y) + 2xyz$

SOLUTION $\Sigma xy(x + y) + 2xyz$

$= xy(x + y) + yz(y + z) + zx(z + x) + 2xyz$

$= x^2y + x^2z + y^2z + y^2x + z^2x + z^2y + 2xyz$

$= x^2(y + z) + x(y^2 + z^2 + 2yz) + yz(y + z)$

$= x^2(y + z) + x(y + z)^2 + yz(y + z)$

$= (y + z)[x^2 + x(y + z) + (yz)]$

$= (y + z)[x(x + y) + z(x + y)]$

$= (y + z)(x + y)(y + z)$

INTRODUCTORY EXERCISE-13.1

1. Sunny Gupta scored x marks in Maths, y marks in *DI/DS* and 40 marks in English. What is his total score in these three subjects?
   (a) $100 - (x + y)$ (b) $100 - (x + y + 40)$
   (c) $x + y - 40$ (d) $x + y + 40$

2. Quotient of z by 4 is multiplied by thrice the number y.
   (a) $\frac{3y}{4z}$ (b) $\frac{3z}{4y}$
   (c) $\frac{3yz}{4}$ (d) $\frac{3}{4yz}$

3. Express $6 \times p \times q \times r \times p \times p \times p$ in the exponential form :
   (a) $6(p^4 + q + r)$ (b) $6 \times 4p \times q \times r$
   (c) $6p^4qr$ (d) none of these

4. Find the number of terms in $2x^2 - \frac{3}{x} + \frac{5}{x^2} + 9$.
   (a) 1 (b) 2
   (c) 3 (d) 4

5. Find the number of terms in
   $4xyz - \frac{3}{x^2} + 6xy^2 - 5z^3 + 6x$:
   (a) 3 (b) 4
   (c) 5 (d) 6

6. Find the number of terms in $7 \times a + b + 3 - c + b$.
   (a) 3 (b) 5
   (c) 4 (d) 6

7. Find the coefficient of z^3 in $-7xy^2z^3$.
   (a) xy^2 (b) -7
   (c) $7xy^2$ (d) $-7xy^2$

8. In the following, which pair contains like terms?
   (a) $2x^2y, 2xy^2$ (b) $2xy, -3yx$
   (c) $6, 6x$ (d) $2xy, 3xyz$

9. Find the degree of the polynomial $4x^3 - 2x^2y^3 + 6$.
   (a) 3 (b) 4
   (c) 5 (d) 6

10. Simplify the following :
    $2x^2 + 3y^2 - 5xy + 5x^2 - y^2 + 6xy - 3x^2$
    (a) $7x^2 + 4y^2 - 11xy$ (b) $7x^2 + 2y^2 - 30xy$
    (c) $4x^2 + 2y^2 - 11xy$ (d) $4x^2 + xy + 2y^2$

11. If sum of two polynomials is $5x^2 + 3x - 1$. If one of them is $3x^3 - 2x + 7$. Find the other.
    (a) $3x^3 + 5x^2 + 5x - 8$ (b) $-3x^3 + 5x^2 + 5x - 8$
    (c) $2x^2 + x + 6$ (d) none of these

12. Multiply $\frac{1}{2}a^2b - \frac{2}{3}ab^2 + 5$ by $6abc$:
    (a) $3a^3b^2c - 4a^2b^3c + 30abc$
    (b) $3a^3b^3c - 4a^3b^2c + 6abc$
    (c) $6a^3b^2 + 18ab^2c + 30abc$
    (d) none of the above

13. Find the product of $\left(\frac{1}{2}x^2 - \frac{1}{3}y^2\right)$ and $\left(\frac{1}{2}x^2 + \frac{1}{3}y^2\right)$.
    (a) $\frac{1}{9}y^4 - \frac{1}{4}x^4$ (b) $\frac{1}{4}x^4 - \frac{1}{9}y^4$
    (c) $4x^2 - 9y^4$ (d) $\frac{1}{4}x^4 - \frac{1}{9}y^9$

Scanned by CamScanner

yourmathbook.wordpress.com

14. Divide $36x^2y^5 + 42xy^3 - 24x^3y^2 - 12y^5$ by $-6y^2$.
(a) $6x^2y^3 - 7xy + 4x^3 + 2y^3$
(b) $-6x^2y^3 - 7xy^2 + 4x^2 + 2y^3$
(c) $-6x^2y^3 - 7xy + 4x^3 + 2y^3$
(d) none of the above

15. Find the remainder when the expression $3x^2 + 8x^2 - 6x + 1$ is divided by $x + 3$.
(a) 1 (b) 10
(c) 6 (d) 0

16. Find the value of a if the division of $ax^3 + 9x^2 + 4x - 10$ by $(x + 3)$ leaves a remainder 5.
(a) 1 (b) 2
(c) 3 (d) 4

17. If $(x + 1)$ and $(x - 2)$ are factors of $x^3 + ax^2 - bx - 6$, then find the values of a and b respectively.
(a) 2, 3 (b) 3, 5
(c) 5, 3 (d) 2, 5

18. If $(5x^2 + 14x + 2)^2 - (4x^2 - 5x + 7)^2$ is divided by $(x^2 + x + 1)$ then, quotient 'q' and remainder 'r' are given by :
(a) $q = (x^2 + 19x - 5), r = 0$ (b) $q = 9(x^2 + 19x - 5), r = 0$
(c) $q = (x^2 + 19x - 5), r = 1$ (d) $q = 9(x^2 + 19x - 5), r = 1$

19. On dividing $(x^3 - 6x + 7)$ by $(x + 1)$, then the remainder is :
(a) 2 (b) 0
(c) 12 (d) 6

20. When $(x^4 - 3x^3 + 2x^2 - 5x + 7)$ is divided by $(x - 2)$, then the remainder is :
(a) 0 (b) –3
(c) 2 (d) 3

21. If $x^3 + 5x^2 + 10k$ leaves remainder $-2x$ when divided by $x^2 + 2$, then the value of k is :
(a) –2 (b) –1
(c) 1 (d) 2

22. If $(x^{11} + 1)$ is divided by $(x + 1)$, then the remainder is :
(a) 0 (b) 2
(c) 1 (d) 10

23. If $5x^3 + 5x^2 - 6x + 9$ is divided by $(x + 3)$, then the remainder is :
(a) 0 (b) –32
(c) 23 (d) –63

24. If $f(x)$ is divided by $(2x + 3)$, then the remainder is :
(a) $f(2/3)$ (b) $f(-2/3)$
(c) $f(3/2)$ (d) $f(-3/2)$

25. When $(x^3 - 2x^2 + px - q)$ is divided by $(x^2 - 2x - 3)$, the remainder is $(x - 6)$. The values of p and q are :
(a) $p = -2, q = -6$ (b) $p = 2, q = -6$
(c) $p = -2, q = 6$ (d) $p = 2, q = 6$

26. If $(x - 2)$ is a factor of $(x^2 + 3qx - 2q)$, then the value of q is :
(a) –2 (b) –1
(c) 1 (d) 2

27. Find the value of k, if $(x + 2)$ exactly divides $x^3 + 6x^2 + 4x + k$.
(a) 4 (b) 6
(c) –8 (d) –10

28. Which one of the following is a factor of $x^4 - 5x^3 + 5x^2 - 10x + 24$?
(a) $(x + 2)$ (b) $(x + 4)$
(c) $(x - 2)$ (d) none of these

29. If $(x + k)$ is a common factor of $(x^2 + px + q)$ and $(x^2 + lx + m)$, then the value of k is :
(a) $l + p$ (b) $m - q$
(c) $\frac{l - p}{m - q}$ (d) $\frac{m - q}{l - p}$

30. If $(x - a)$ is a factor of $(x^3 - 3x^2a + 2a^2x + b)$, then the value of b is :
(a) 0 (b) 1
(c) 2 (d) 3

31. $(x^{29} - x^{25} + x^{13} - 1)$ is divisible by :
(a) $(x + 1)$ but not by $(x - 1)$
(b) $(x - 1)$ but not by $(x + 1)$
(b) both $(x + 1)$ and $(x - 1)$
(d) neither $(x - 1)$ nor $(x + 1)$

32. One of the factors of $3x^3 + x^2 - 12x - 4$ is :
(a) $3x - 2$ (b) $3x - 1$
(c) $3x + 1$ (d) $3x + 2$

33. $x^{100} + 2x^{99} + k$ is divisible by $(x + 1)$, then the value of k is :
(a) –3 (b) –2
(c) 1 (d) 2

34. If $(x - 1)$ is a factor of $(x^3 - m)$, then the value of m is :
(a) –6 (b) –5
(c) 1 (d) 3

35. If the polynomial $f(x)$ is such that $f(-3) = 0$, then a factor of $f(x)$ is :
(a) –3 (b) 3
(c) $\frac{1}{3}$ (d) $x + 3$

36. If $\left(x + \frac{1}{x}\right) = 2$, then $\left(x^2 + \frac{1}{x^2}\right)$ is equal, to :
(a) 2 (b) 4
(c) 5 (d) 6

37. If $\left(x - \frac{1}{x}\right) = 4$, then the value of $\left(x^2 + \frac{1}{x^2}\right)$ is :
(a) 16 (b) 18
(c) 14 (d) none of these

38. If $\left(x + \frac{1}{x}\right) = 2\sqrt{3}$, then the value of $\left(x^3 + \frac{1}{x^3}\right)$ is :
(a) $12\sqrt{3}$ (b) 18
(c) $18\sqrt{3}$ (d) none of these

39. If $\left(x + \frac{1}{x}\right) = 3$, then the value of $\left(x^3 + \frac{1}{x^3}\right)$ is equal to :
(a) $18\sqrt{3}$ (b) 18
(c) $9\sqrt{3}$ (d) 12

40. If $\left(x + \frac{1}{x}\right) = 2$, then the value of $\left(x^6 + \frac{1}{x^6}\right)$ is :
(a) 2 (b) 4
(c) 8 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

41. If $\left(x^2+\frac{1}{x^2}\right)=6$, then the value of $\left(x-\frac{1}{x}\right)$ is :
(a) 2 (b) 3
(c) −2 (d) both (a) and (c)

42. If $\left(x^3-\frac{1}{x^3}\right)=36$, then the value of $\left(x-\frac{1}{x}\right)$ is :
(a) 1 (b) 2
(c) 3 (d) 6

43. If $\left(x^3+\frac{1}{x^3}\right)=2$, then the value of $\left(x+\frac{1}{x}\right)$ is :
(a) 1 (b) 2
(c) 3 (d) 4

44. If $\left(x^4+\frac{1}{x^4}\right)=34$, then the value of $\left(x-\frac{1}{x}\right)$ is :
(a) 1 (b) 2
(c) 3 (d) 4

45. If $\left(x^4+\frac{1}{x^4}\right)=119$, then the value of $\left(x^3-\frac{1}{x^3}\right)$ is :
(a) 49 (b) 27
(c) 36 (d) 63

46. If $\left(3x-\frac{2}{x}\right)=5$, then the value of $\left(9x^2-\frac{4}{x^2}\right)$ is :
(a) 25 (b) 35
(c) 30 (d) none of these

47. If $m^2-4m+1=0$, then the value of $\left(m^3+\frac{1}{m^3}\right)$ is :
(a) 48 (b) 52
(c) 64 (d) none of these

48. If $x+y=13$ and $xy=40$, then the value of (x^2+y^2) is :
(a) 69 (b) 80
(c) 89 (d) none of these

49. If $(x+y)=13$ and $xy=36$, then the value of (x^3+y^3) is :
(a) 369 (b) 936
(c) 693 (d) none of these

50. If $(x+y)=8$ and $xy=15$, then the value of (x^3-y^3) is :
(a) 120 (b) 60
(c) 98 (d) 82

51. If $(x+y+z)=6$ and $(xy+yz+zx)=11$, then the value of $(x^3+y^3+z^3-3xyz)$ is :
(a) 81 (b) 54
(c) 18 (d) none of these

52. If $(x+y+z)=0$, then the value of $(x^3+y^3+z^3)$ is :
(a) $3x^3y^3z^3$ (b) $3xyz$
(c) xyz (d) $3(x+y+z)$

53. If $a^{1/3}+b^{1/3}+c^{1/3}=0$, then :
(a) $a+b+c=0$ (b) $a+b+c=3abc$
(c) $a^3+b^3+c^3=0$ (d) $(a+b+c)^3=27abc$

54. If $2^x-2^{x-1}=8$, then the value of x^3 is :
(a) 46 (b) 27
(c) 64 (d) 8

55. If $3^x+3^{x+1}=36$, then the value of x^x is :
(a) 64 (b) 3125
(c) 81 (d) 4

56. If a and b are non zero rational unequal numbers, then $\frac{(a+b)^2-(a-b)^2}{a^2b-ab^2}$ is equal to :
(a) $\frac{1}{a-b}$ (b) $\frac{2}{a-b}$
(c) $\frac{4}{a-b}$ (d) $\frac{1}{ab}$

57. If $\frac{x}{(b-c)(b+c-2a)}=\frac{y}{(c-a)(c+a-2b)}=\frac{z}{(a-b)(a+b-2c)}$, then the value of $(x+y+z)$ is :
(a) $a+b+c$ (b) 0
(c) $a^2+b^2+c^2$ (d) can't be determined

58. $(a^4+5a^3+6a^2)$ is equal to :
(a) $a(a^2+3)(a+2)$ (b) $a(a+3)(a^2+2)$
(c) $a^2(a+3)(a+2)$ (d) $a^2(a-2)(a-3)$

59. The factors of (x^4+16) are :
(a) $(x^2+4)(x^2-4)$ (b) $(x^2+4)(x^2+4)$
(c) $x(x^2+2)(x^4+4)$ (d) do not exist

60. If $(a^{3/2}-ab^{1/2}+a^{1/2}b-b^{3/2})$ is divided by $(a^{1/2}-b^{1/2})$, then the quotient is :
(a) $a+b$ (b) $a-b$
(c) $a^{1/2}+b^{1/2}$ (d) a^2-b^2

61. The factors of $x(y^2-z^2)+y(z^2-x^2)+z(x^2-y^2)$ are :
(a) $(x-y)(y-z)(z-x)$ (b) $(x+y)(y+z)(z+x)$
(c) $(y-x)(z-y)(x-z)$ (d) $(x+y)(z-y)(x-z)$

62. $(a+b)^3-(a-b)^3$ can be factorized as :
(a) $2a(a^2+3b^2)$ (b) $2a(3a^2+b^2)$
(c) $2b(3a^2+b^2)$ (d) $2a(a^2+3b^2)$

63. The factors of (x^4+4) are :
(a) $(x^2+2)^2$ (b) $(x^2+2x+2)(x^2-2x+2)$
(c) $(x^2+2)(x^2-2)$ (d) none of these

64. The factors of x^3-7x+6 are :
(a) $(x-1)(x+3)(x-2)$ (b) $(x+1)(x+2)(x-3)$
(c) $x(x-6)(x-1)$ (d) $(x^2-6)(x-1)$

65. The factors of $(64x^3-216y^3)$ are :
(a) $(4x-6y)(16x^2-36y^2)$
(b) $(4x-6y)[16x^2+36y^2+24xy]$
(c) $(4x+6y)(4x-6y)$
(d) none of the above

66. The factors of $(a^2+4b^2+4b-4ab-2a-8)$ are :
(a) $(a-2b-4)(a-2b+2)$
(b) $(a-b+2)(a-4b-4)$
(c) $(a+2b-4)(a+2b+2)$
(d) none of the above

67. The factors of $(a-b)^3+(b-c)^3+(c-a)^3$ are :
(a) $(a+b+c)(a^2+b^2+c^2+ab+bc+ac)$
(b) $(a+b+c)(a^2+b^2+c^2-ab-bc-ac)$
(c) $3(a-b)(b-c)(c-a)$
(d) $(a-b)(b-c)(c-a)$

68. If $a+b+c=0$, then $a^2+b^2+c^2$ is :
(a) 0 (b) $2(a^2-bc)$
(c) $-4(ab+bc+ca)$ (d) $-2(ab+bc+ca)$

Scanned by CamScanner

yoursmahboob.wordpress.com

69. Which of the following statements are true ?
1. LCM of $10a^2bc, 15abc, 20ab^2c^2$ is $120a^2b^2c^2$
2. HCF of $(x^2 - 6x + 9)$ and $(x^3 - 27)$ is $(x - 3)$
3. HCF of $(6x^2 - 7x - 3)$ and $(2x^2 + 11x - 21)$ is $2x - 3$.

(a) 1, 2, 3 (b) 1, 2
(c) 1, 3 (d) 2, 3

70. The LCM of $(2x^2 - 3x - 2)$ and $(x^3 - 4x^2 + 4x)$ is :
(a) $x(2x^2 + 1)(x^2 + 2)$ (b) $x(2x + 1)(x - 2)^2$
(c) $x(2x^2 + 1)(x - 1)^2$ (d) $x(2x + 1)(x^2 - 1)$

71. The G.C.D. of $2(x^2 - y^2)$ and $5(x^3 - y^3)$ is :
(a) $2(x^2 - y^2)$ (b) $x + y$
(c) $x - y$ (d) $10(x^2 - y^2)(x^2 + y^2 + xy)$

72. The GCD of $(x^4 - 4x^2 + 3)$ and $(x^4 - x^2 - 6)$ is :
(a) $(x - 1)$ (b) $(x + 1)$
(c) $(x^2 - 1)$ (d) $(x^2 - 3)$

73. The HCF of $(x^2 - 4)$, $(x^2 - 5x - 6)$ and $(x^2 + x - 6)$ is :
(a) 1 (b) $x + 2$
(c) $x - 2$ (d) $(x^2 + x - 6)$

74. The GCD of $[x^2 - ax - (a + 1)]$ and $[ax^2 - x - (a + 1)]$ is :
(a) $(x - 1)$ (b) $(x + 1)$
(c) $(x + a + 1)$ (d) $(x - a - 1)$

75. LCM of the polynomials P and Q, where
$P = (x - 2)(x + 1)^2(x + 3)^2$
$Q = (x + 1)^2(x + 3)(x + 4)$ is given by :
(a) $(x - 2)(x + 1)(x + 3)^2(x + 4)$
(b) $(x - 2)(x + 4)(x + 3)^2(x + 1)^2$
(c) $(x - 2)(x + 1)^2(x + 3)(x + 4)$
(d) $(x + 1)(x - 2)(x + 3)(x + 4)$

76. The LCM of $(a^3 + b^3)$ and $(a^4 - b^4)$ is :
(a) $(a^3 + b^3)(a^2 + b^2)(a - b)$
(b) $(a^3 + b^3)(a^2 + b^2)(a + b)$
(c) $(a^3 + b^3)(a^2 + b^2 + ab)(a + b)$
(d) $(a^3 + b^3)(a^2 - b^2)(a - b)$

77. The HCF of $(x^4 - 1)$ and $(x^3 + x^2 + x + 1)$ is :
(a) $(x^2 - 1)(x^2 + 1)$ (b) $(x^2 + 1)(x + 1)$
(c) $(x + 1)(x^2 - 1)$ (d) $(x + 1)(x^2 + 1)(x^3 + 1)$

78. The GCD of $(2x^2 - 4x)$, $(3x^4 - 12x^2)$ and $(2x^5 - 2x^4 - 4x^3)$ is :
(a) $x(x - 2)$ (b) $2x(x - 2)$
(c) $2x(2 - x)$ (d) $2x(2 + x)$

79. The HCF of two expressions P and Q is 1. Their LCM is :
(a) $(P + Q)$ (b) $(P - Q)$
(c) PQ (d) $(P)^Q$

80. The LCM of $(x + 2)^2(x - 2)$ and $(x^2 - 4x - 12)$ is :
(a) $(x + 2)(x - 2)^2$ (b) $(x - 2)(x + 2)(x - 6)$
(c) $(x - 2)(x + 2)$ (d) $(x - 2)(x - 6)(x + 2)^2$

81. The HCF of $a^2 - ab - 2b^2$ and $2a^2 - ab - b^2$ is :
(a) $(a + b)$ (b) $(a - b)$
(c) $(2a - 3b)$ (d) none of these

82. HCF and LCM of $a^2b^3c^4$ and $a^5b^4c^3$ are :
(a) $a^2b^3c^4$, $a^5b^4c^3$ (b) $a^2b^3c^3$, $a^2b^3c^4$
(c) $a^2b^3c^3$, $a^5b^4c^4$ (d) $a^5b^3c^3$, $a^5b^4c^3$

Directions for question number 83–86 : *Express each of the following as a rational expressions.*

83. $\frac{(x + 3)}{(x - 2)} - \frac{(x + 1)}{(x - 3)}$:
(a) $\frac{x - 7}{(x^2 + 5x - 6)}$ (b) $\frac{7 - x}{(x^2 - 5x + 6)}$
(c) $\frac{x - 7}{2x^2 - 5x + 6}$ (d) $\frac{x - 7}{x^2 - 5x + 6}$

84. $\frac{x + 1}{x - 1} + \frac{x - 1}{x + 1}$:
(a) $\frac{1}{2}\frac{(x^2 + 1)}{(x^2 - 1)}$ (b) $\frac{(x^2 + 1)}{(x^2 - 1)}$
(c) $\frac{2(x^2 + 1)}{(x^2 - 1)}$ (d) $\frac{x^2 - 1}{x^2 + 1}$

85. $\frac{x^2 - 5x + 6}{x^2 - 9x + 20} \div \frac{x^2 - 3x + 2}{x^2 - 5x + 4}$:
(a) $\frac{(x - 4)}{(x - 3)}$ (b) $\frac{(x - 3)}{(x - 5)}$
(c) $\frac{(x - 2)}{(x - 5)}$ (d) $\frac{(x - 5)}{(x - 3)}$

86. Sum of $\frac{2x^2 + 3}{x - 3}$ and its reciprocal is :
(a) $\frac{4x^4 + 13x^2 - 6x + 18}{2x^3 - 6x^2 + 3x - 9}$ (b) $\frac{4x^4 - 13x^2 + 6x - 18}{3x^2 - 6x^3 + 3x + 9}$
(c) $\frac{4x^4 - 13x^2 - 6x + 18}{4x^3 - 6x^2 + 3x - 9}$ (d) none of these

Directions for question number 87-89 : *Express the following in the lowest terms.*

87. $\frac{(x - 3)(x^2 - 5x + 4)}{(x - 4)(x^2 - 2x - 3)}$:
(a) $\frac{x - 1}{x + 1}$ (b) $\frac{x + 1}{x - 1}$
(c) $\frac{x - 1}{x - 2}$ (d) $\frac{x + 1}{x + 3}$

88. $\left(\frac{2x^2 + 1}{x - 1} + \frac{x - 1}{x + 1}\right) \times \left(\frac{x^2 - 1}{2x}\right)$:
(a) $\frac{2x^2 + 3x}{2}$ (b) $\frac{2x^3 + 3x^2 - x + 2}{2x}$
(c) $\frac{2x^3 - 3x^2 + x - 2}{2x}$ (d) none of these

89. $\sqrt{\frac{(x^2 + 3x + 2)(x^2 + 5x + 6)}{x^2(x^2 + 4x + 3)}}$:
(a) $\frac{x + 2}{2}$ (b) $\frac{x + 2}{x}$
(c) $\frac{x - 2}{x}$ (d) $\frac{x + 4}{x + 3}$

90. Simplify $\frac{1}{(a - b)(a - c)} + \frac{1}{(b - c)(b - a)} + \frac{1}{(c - a)(c - b)}$:
(a) 0 (b) 1
(c) 3 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

91. Express $\frac{1}{(1-x)}+\frac{1}{(1+x)}+\frac{2}{(1+x^2)}+\frac{4}{(1+x^4)}$ as a rational expression :

(a) 1 (b) $\frac{1-x^4}{1+x^4}$

(c) $\frac{8}{1-x^8}$ (d) none of these

LINEAR EQUATIONS

Equation : A statement of equality which involves literal number(s) is called an equation.

e.g., $4x=12$, $4+x=10$, $7-2x=5$ etc.

NOTE The literal numbers involved in each equation are called its variables (unknowns). Usually the variables are denoted by letters towards the end of English alphabet, *e.g.*, *x, y, z, u, v, w,* etc.

Linear Equation : An equation in which the highest power of the variables involved is one, is called a linear equation. *e.g.*, $x+y=10$, $7x=21$, $\frac{x}{3}=8$.

Linear Equation in one Variable : An equation containing only one variable (literal) with highest power 1 is called a linear equation in one variable. *e.g.*, $17x=51$, $23+x=30$, $5y=30$, etc.

Linear Equation in two Variables : An equation of the form $ax+by=c$, where a, b, c are real numbers is called a linear equation in two variables x and y.

The graph of a linear equation $ax+by=c$ is a straight line.

$3x+2y=18$, is an example of a linear equation in two variables.

- The value of the variables that satisfy the equation is called the solution (or solution set) of the equation.

An equation can be solved by using the following rules :

(i) The same number may be added to both sides of the equation.

(ii) The same number may be subtracted from both sides of the equation.

(iii) Both sides of the equation may be multiplied by same non zero number.

(iv) Both sides of the equation may be divided by same non-zero number.

(v) A term may be transposed from one side of the equation to the other side, but its sign will change. This is called rule of transposition.

Important points about linear equation in two variables:

(i) The graph of an equation of the type $x=k$ (where k is a constant) is a straight line parallel to the y-axis at a distance of k units from the y-axis.

(ii) The graph of an equation of the type $y=k$ (where k is a constant) is a straight line parallel to the x-axis at a distance of k units from the x-axis.

(iii) The point of intersection of the two lines gives the solution of the two equations.

(iv) A single linear equation in two variables has infinite no. of solutions.

Simultaneous Linear Equations : Two or more linear equations in two variables form a system of linear simultaneous equations. *e.g.*, $a_1x+b_1y=c_1$ and $a_2x+b_2y=c_2$

Consistent System : A system consisting of two simultaneous linear equations is said to be consistent, if it has at least one solution.

Inconsistent System : A system consisting of two simultaneous linear equations is said to be inconsistent, if it has no solution.

If there are two simultaneous equations :

$a_1x+b_1y=c_1$ and $a_2x+b_2y=c_2$ then

Unique solution	Infinite solution	No solution
$\frac{a_1}{a_2}\neq\frac{b_1}{b_2}$	$\frac{a_1}{a_2}=\frac{b_1}{b_2}=\frac{c_1}{c_2}$	$\frac{a_1}{a_2}=\frac{b_1}{b_2}\neq\frac{c_1}{c_2}$
(Independent equation)	(Dependent equation)	(Inconsistent equation)

- The homogeneous system has a non-zero solution only when $\frac{a_1}{a_2}=\frac{b_1}{b_2}$ and in this case, the system has an infinite number of solution.
- A system of equations has unique solution, when only one variable satisfies the equation.
- For a system of equations a unique solution is possible only when the number of variables is equal to or less than number of independent and consistent equations.

e.g., $2x+3y=5$ and $7x+5y=20$

and $2x+3y=5$, $7x+5y=12$, $5x+8y=13$

- The equation of the type $ax+by=c$ and $kax+kby=kc$ are known as dependent equations.

e.g., $2x+y=11$ ...(i)

$6x+3y=33$ ...(ii)

Here eq. (ii) is the multiple of eq. (i). Thus, there are basically both the equations same, *i.e.*, eq. (ii) is dependent on eq. (i). In this case there are infinite number of solutions.

- The equation of the type $ax+by=c$ and $kax+kby=lc$ are known as inconsistent equations.

e.g., $3x+2y=8$ ...(i)

and $6x+4y=6$ ...(ii)

Properties of graphs of $a_1x+b_1y=c_1$ and $a_2x+b_2y=c_2$

(i) intersecting if the system has a unique solution.

(ii) coincident if the system has infinite number of solution

Scanned by CamScanner

yoursmahboob.wordpress.com

(iii) parallel if the system has no solution.

Graphical representation of simultaneous equations :

(i) intersecting lines (unique solution)

e.g., $x + y = 4$ ...(i)

and $3x + 2y = 11$ ...(ii)

$\therefore \quad 3(x + y) = 3 \times 4 \Rightarrow 3x + 3y = 12$

$\therefore \quad 3x + 3y = 12$

$3x + 2y = 11$

$y = 1$

$\therefore \quad x + y = 4 \Rightarrow x + 1 = 4 \Rightarrow x = 3$

$\therefore \quad x = 3$ and $y = 1$

Thus two given lines instersect at $x = 3$, $y = 1$.



(ii) Coincident lines (infinite number of solutions)

e.g., $x + y = 4$ ...(i)

$2x + 2y = 8$ ...(ii)

The two equations are dependent, therefore the graph of two lines will coincide.



(iii) Parallel lines (no solution)

e.g., $x + y = 4$ ...(i)

$2x + 2y = 12$ ...(ii)

Since the system of equations is inconsistent therefore there is no any solution and in this case we obtain two different parallel lines.



Algebraic Methods of Solving Simultaneous Equations in Two Variables.

- Elimination method
  - Substitution method
  - Comparison method
  - Elimination method or Addition or Subtraction of Equations
- Cross multiplication method (Cramer's rule)

EXAMPLE 1 *Solve the following equations* $3x + 5y = 9$ *and* $2x + 3y = 4$

(a) by substitution method

(b) by elimination method

(c) by comparison method

SOLUTION (a) $3x + 5y = 9$ ...(i)

$2x + 3y = 4$ ...(ii)

Express y in terms of x from Eq. (i)

$$y = \frac{9 - 3x}{5} \quad \text{...(iii)}$$

Substitute this value of y in Eq. (ii)

$$2x + 3\left(\frac{9 - 3x}{5}\right) = 4$$

$\Rightarrow \quad 10x + 27 - 9x = 20 \Rightarrow x = -7$

Substitute $x = -7$ in Eq. (iii)

$\therefore \quad x = -7, \quad y = 6.$

NOTE We can express x in terms of y for one equation and substitute this value in other.

(b) $3x + 5y = 9$ ...(i)

$2x + 3y = 4$ ...(ii)

Multiply Eq. (i) by 3 and (2) by 5.

$9x + 15y = 27$ ...(iii)

$10x + 15y = 20$ ...(iv)

$-x + 0 = 7$

$\Rightarrow \quad x = -7$

Substitute $x = -7$ in Eq. (i)

$3(-7) + 5y = 9$

$\Rightarrow \quad -21 + 5y = 9$

$\Rightarrow \quad y = 6$

$\therefore \quad x = -7$ and $y = 6$

NOTE We can eliminate x by multiplying (i) by 2 and (ii) by 3 and then subtract the resulting equations.

(c) $3x + 5y = 9$ ...(i)

$2x + 3y = 4$ ...(ii)

From Eq. (i) $x = \frac{9 - 5y}{3}$ ...(iii)

and from Eq. (ii) $x = \frac{4 - 3y}{2}$ ...(iv)

Comparing Eq. (iii) and (iv)

$$\frac{9 - 5y}{3} = \frac{4 - 3y}{2}$$

$\Rightarrow \quad 2(9 - 5y) = 3(4 - 3y)$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$18 - 10y = 12 - 9y$$

$$\Rightarrow \quad y = 6 \qquad \ldots(v)$$

$\Rightarrow$ Substitute the value of y in Eq. (iii)

$$x = \frac{9 - 5(6)}{3} = \frac{-21}{3} = -7$$

$\therefore \quad x = -7$ and $y = 6$

NOTE We can compare the value of y in terms of x.

EXAMPLE 2 *Solve the equations* $3x + 5y = 9$ *and* $2x + 3y = 4$ *by cross multiplication method.*

SOLUTION If there are two simultaneous equations

$a_1x + b_1y = c_1$ and $a_2x + b_2y = c_2$, where $c_2 \neq 0$

then, $$\frac{x}{b_1c_2 - b_2c_1} = \frac{y}{c_1a_2 - c_2a_1} = \frac{-1}{a_1b_2 - a_2b_1}$$

$$\left[\frac{x}{b_1 \quad c_1} = \frac{y}{c_1 \quad a_1} = \frac{-1}{a_1 \quad b_1}\right]$$
$$\quad b_2 \quad c_2 \quad\; c_2 \quad a_2 \quad\; a_2 \quad b_2$$

Here $a_1 = 3 \quad b_1 = 5 \quad c_1 = 9$

$a_2 = 2 \quad b_2 = 3 \quad c_2 = 4$

$$\therefore \quad \frac{x}{(20 - 27)} = \frac{y}{(18 - 12)} = \frac{-1}{(9 - 10)}$$

$$\Rightarrow \quad \frac{x}{-7} = \frac{y}{6} = 1$$

$$\Rightarrow \quad x = -7 \quad \text{and} \quad y = 6.$$

EXAMPLE 3 *Find the correct choice.*

(A) $5x + 2y = 16$, $7x - 4y = 2$ — (P) *no solution*

(B) $5x + 2y = 16$, $3x + \frac{6}{5}y = 2$ — (Q) *unique solution*

(C) $5x + 2y = 16$, $\frac{15}{2}x + 3y = 24$ — (R) *infinite number of solution*

(a) $A - P, B - Q, C - R$ (b) $A - R, B - P, C - Q$

(c) $A - Q, B - P, C - R$ (d) $A - Q, B - R, C - P$

SOLUTION (A) $\frac{5}{7} \neq \frac{2}{-4}$.

$\therefore$ The system of equations has unique solution.

(B) $$\frac{5}{3} = \frac{2}{6/5} \neq \frac{16}{2}.$$

$$\Rightarrow \quad \frac{5}{3} = \frac{5}{3} \neq \frac{8}{1}$$

$\therefore$ The system of equations has no solution.

(C) $$\frac{5}{15/2} = \frac{2}{3} = \frac{16}{24}$$

$$\Rightarrow \quad \frac{2}{3} = \frac{2}{3} = \frac{2}{3}$$

$\therefore$ The system of equations has infinite number of solution.

EXAMPLE 4 *Solve for x and y*

$$4(x - 3) = 3(y + 3)$$
$$17 - 2x = 8 - (2y + 1)$$

SOLUTION $4(x - 3) = 3(y + 3)$

$$\Rightarrow \quad 4x - 3y = 21 \qquad \ldots(1)$$

and $17 - 2x = 8 - (2y + 1)$

$$\Rightarrow \quad x - y = 5 \qquad \ldots(2)$$

Multiply Eq. (2) by 3 and subtract from (1)

$$4x - 3y = 21$$
$$3x - 3y = 15$$
$$- \quad + \quad -$$
$$x = 6$$

Substitute $x = 6$ in Eq. (2), we get $y = 1$

$\therefore \quad x = 6$ and $y = 1$.

EXAMPLE 5 *Solve for x and y*

$$0.04x + 0.02y = 5$$
$$0.5(x - 2) - 0.4y = 29$$

SOLUTION $0.04x + 0.02y = 5$

$\Rightarrow \quad 4x + 2y = 500$ (multiply both sides by 100)

$$\Rightarrow \quad 2x + y = 250 \qquad \ldots(1)$$

and $0.5(x - 2) - 0.4y = 29$

$\Rightarrow \quad 5(x - 2) - 4y = 290$ (multiply both sides by 10)

$$\Rightarrow \quad 5x - 4y = 300 \qquad \ldots(2)$$

Multiply Eq. (1) by 4 and add to Eq. (2)

$$8x + 4y = 1000$$
$$5x - 4y = 300$$
$$13x = 1300$$

$$\Rightarrow \quad x = 100$$

Substitute $x = 100$, in Eq. (1), we get

$$y = 50$$

$\therefore \quad x = 100$ and $y = 50$.

EXAMPLE 6 *Solve for x and y*

$$\frac{3x - y}{5} = 2y - 1, \quad \frac{3x}{8} - \frac{y}{4} = \frac{1}{2}$$

SOLUTION $3x - y = 5(2y - 1)$

$$\Rightarrow \quad 3x - 11y = -5 \qquad \ldots(1)$$

and $$\frac{3x}{8} - \frac{y}{4} = \frac{1}{2}$$

$$\Rightarrow \quad 3x - 2y = 4 \qquad \ldots(2)$$

Subtract Eq. (2) from (1)

$$3x - 11y = -5$$
$$3x - 2y = 4$$
$$- \quad + \quad -$$
$$-9y = -9 \Rightarrow y = 1$$

Substitute $y = 1$ in Eq. (2), we get

$$x = 2$$

$\therefore \quad x = 2$ and $y = 1$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 7 *Solve for x and y*

$$\frac{2}{x}+\frac{3}{y}=2,\ \frac{8}{x}-\frac{6}{y}=2$$

SOLUTION

$$\frac{2}{x}+\frac{3}{y}=2 \quad ...(1)$$

$$\frac{8}{x}-\frac{6}{y}=2 \quad ...(2)$$

Let $\frac{1}{x}=A$ and $\frac{1}{y}=B$

$\therefore$ $2A+3B=2$ ...(3)

and $8A-6B=2$ ...(4)

Multiply Eq. (3) by 2

$$4A+6B=4$$
$$8A-6B=2$$
$$12A=6 \Rightarrow A=1/2$$

Substitute $A=\frac{1}{2}$ in Eq. (1), we get

$$B=\frac{1}{3}$$

$\therefore$ $x=2$ and $y=3$.

EXAMPLE 8 *Solve for x and y*

$$\frac{2}{3x+2y}+\frac{3}{3x-2y}=\frac{17}{5}$$

$$\frac{5}{3x+2y}+\frac{1}{3x-2y}=2$$

SOLUTION Let $\frac{1}{3x+2y}=A$ and $\frac{1}{3x-2y}=B$

$\therefore$ $2A+3B=\frac{17}{5} \Rightarrow 10A+15B=17$ ...(1)

and $5A+B=2$ ...(2)

Multiply Eq. (2) by 2 and subtract from (1)

$$10A+15B=17$$
$$10A+2B=4$$
$$13B=13 \Rightarrow B=1$$

Substitute $B=1$ in Eq. (2), we get $A=\frac{1}{5}$

Now, $A=\frac{1}{3x+2y}=\frac{1}{5} \Rightarrow 3x+2y=5$ ...(3)

and $B=\frac{1}{3x-2y}=1 \Rightarrow 3x-2y=1$ ...(4)

$\therefore$ Add Eq. (3) to Eq. (4)

$$3x+2y=5$$
$$3x-2y=1$$
$$6x=6 \Rightarrow x=1$$

Substitute $x=1$ in Eq. (3), we get $y=1$

$\therefore$ $x=1$ and $y=1$.

INTRODUCTORY EXERCISE-13.2

Directions for question number 1–4 : Solve the following system of equations :

1. $x-y=0.9, \frac{11}{2(x+y)}=1$:
   (a) 3.2, 3.5 (b) 3.2, 2.3
   (c) 2.3, 2.5 (d) 4, 3.1

2. $\frac{x+y}{xy}=2, \frac{x-y}{xy}=6$:
   (a) $-\frac{1}{2}, \frac{1}{4}$ (b) $\frac{1}{2}, -\frac{1}{4}$
   (c) $\frac{1}{2}, -\frac{3}{2}$ (d) $-\frac{1}{4}, -\frac{3}{4}$

3. $\frac{1}{2x}-\frac{1}{y}=-1, \frac{1}{x}+\frac{1}{2y}=8$:
   (a) $\frac{2}{3}, \frac{2}{5}$ (b) $\frac{1}{4}, \frac{1}{5}$
   (c) $\frac{1}{6}, \frac{1}{4}$ (d) $-\frac{1}{6}, -\frac{1}{4}$

4. $\frac{2x}{a}+\frac{y}{b}=2, \frac{x}{a}-\frac{y}{b}=4$:
   (a) $\frac{2}{a}, \frac{2}{b}$ (b) $2a, -2b$
   (c) $-2a, 2b$ (d) $\frac{a}{2}, -\frac{b}{2}$

5. For what value of k, the following equations have no solutions?
   $$9x+4y=9$$
   $$7x+ky=5$$
   (a) 3 (b) 4.7
   (c) 28/9 (d) 9/28

6. For what value of k, the system of equations $kx+2y=2$ and $3x+y=1$ will be coincident?
   (a) 2 (b) 3
   (c) 5 (d) 6

7. For what value of k, will the equations $2x+3y-5=0$, $6x+ky-15=0$ have an infinite number of solutions?
   (a) 0 (b) 9
   (c) 2 (d) 3

8. The total cost of 8 buckets and 5 mugs is Rs. 92 and the total cost of 5 buckets and 8 mugs is Rs. 77. Find the cost of 2 mugs and 3 buckets.
   (a) Rs. 35 (b) Rs. 70
   (c) Rs. 30 (d) Rs. 38

9. The sum of two numbers is 8. If their sum is four times their difference, find the numbers.
   (a) 6, 2 (b) 7, 1
   (c) 5, 3 (d) 6, 3

Scanned by CamScanner

yoursmahboob.wordpress.com

10. The numerator of a fraction is 4 less than its denominator. If the numerator is decreased by 2 and the denominator is increased by 1, then the denominator is eight times the numerator. Find the fraction.
(a) 3/7 (b) 4/8
(c) 2/7 (d) 3/8

11. Points A and B are 90 km apart from each other on a highway. A car starts from A and another from B at the same time. If they go in the same direction, they meet in 9 hours and if they go in opposite directions, they meet in 9/7 hours. Find their speed (in km/h).
(a) 25, 45 (b) 20, 50
(c) 30, 40 (d) 35, 65

12. Priyanka has only 25 paise coins and 50 paise coins in her purse. If in all she has 40 coins totalling Rs. 12.75, how many coins of 25 paise does she have?
(a) 30 (b) 29
(c) 32 (d) 26

13. Astha has pens and pencils which together are 40 in number. If she has 5 more pencils and 5 less pens, the number of pencils would have become 4 times the number of pens. Find the original number of pens with Astha.
(a) 11 (b) 12
(c) 13 (d) 14

14. A father is three times as old as his son. After twelve years, his age will be twice as that of the age of his son then, find their present ages.
(a) 10 y, 30 y (b) 12 y, 36 y
(c) 6 y, 36 y (d) 124 y, 24 y

15. Five years ago, A was three times as old as B and ten years later, A shell be twice as old as B. What are the present ages of A and B (in years)?
(a) 45, 15 (b) 30, 40
(c) 50, 30 (d) 50, 20

16. Astha and Saumya each have certain number of oranges. Astha says to Saumya, "If you give me 10 of your oranges, I will have twice the number of oranges left with you. "Saumya replies, "If you give me 10 of your oranges, I will have the same number of oranges as left with you." Find the number of oranges with Astha and Saumya respectively.
(a) 60, 40 (b) 70, 50
(c) 60, 80 (d) 70, 90

17. Shubham travels 760 km to his home partly by train and partly by car. He takes 8 hours if he travels 160 km by train and the rest by car. He takes 12 minutes more if he travels 240 km by train and the rest by car. Find the speed of the train and the car respectively (in km/hr.).
(a) 40, 80 (b) 60, 120
(c) 80, 100 (d) 100, 120

18. A person invested some amount at the rate of 12% simple interest and some other amount at the rate of 10% simple interest. He received yearly interest of Rs. 130. But if he had interchanged the amounts invested he would have received Rs. 4 more as interest. How much amount did he invest at 10% simple interest?
(a) Rs. 700 (b) Rs. 500
(c) Rs. 800 (d) Rs. 400

19. The solution of the equations
$\frac{3x-y+1}{3} = \frac{2x+y+2}{5} = \frac{3x+2y+1}{6}$ given by :
(a) $x = 2, y = 1$ (b) $x = 1, y = 1$
(c) $x = -1, y = -1$ (d) $x = 1, y = 2$

20. The course of an enemy submarine as plotted on a set of rectangular axes gives the equation $2x + 3y = 5$. On the same axes, the course of destroyer is indicated by $x - y = 10$. The point (x, y) at which the submarine can be destroyed is :
(a) (–3, 7) (b) (7, – 3)
(c) (–7, 3) (d) (3, – 7)

21. Let a, b, c be the positive numbers. The following system of equations in x, y and z.
$$\frac{x^2}{a^2} + \frac{y^2}{b^2} - \frac{z^2}{c^2} = 1$$
$$\frac{x^2}{a^2} - \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1$$
$$-\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1, \text{ has}$$
(a) no solution
(b) unique solution
(c) infinitely many solutions
(d) finitely many solutions

22. If the system of equations, $x - ky - z = 0, kx - y - z = 0$, $x + y + z = 0$, has a non zero solution, then the possible values of k are :
(a) –1, 2 (b) 1, 2
(c) 0, 1 (d) –1, 1

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. If $a+b+c=13$, what is the maximum value of $(a-3)(b-2)(c+1)$?
(a) 26 (b) 27
(c) 30 (d) 19

2. If $abcd = 81$, what is the minimum value of $a+b+c+d$?
(a) 18 (b) 9
(c) 12 (d) 36

3. Which one of the following is correct?
(a) $x+\frac{1}{x} \le -2$ (b) $x+\frac{1}{x}=0$
(c) $x+\frac{1}{x} \ge 2$ (d) both (a) and (c)

4. If a, b, c are all distinct positive numbers, then $(a+b)(b+c)(c+a)$:
(a) less than 4 (b) less than $4abc$
(c) greater than $8abc$ (d) greater than $(abc)^3$

5. If a, b, c are the distinct positive numbers then $(a+b+c)(ab+bc+ac)$ is :
(a) greater than $9abc$ (b) less than $8abc$
(c) equal to $10abc$ (d) greater than $25abc$

6. If $x+y=25$ and $x^2y^3+y^2x^3=25$, what is the value of xy?
(a) 0 (b) ± 1
(c) 5 (d) 4

7. If x and y are both positive, then the minimum value of $(x+y)\left(\frac{1}{x}+\frac{1}{y}\right)$ is :
(a) 0 (b) 1
(c) 2 (d) 4

8. If a, b, c and d are four positive numbers such that $a+b+c+d=4$, then what is the maximum value of $(a+1)(b+1)(c+1)(d+1)$?
(a) 32 (b) 8
(c) 16 (d) 81

9. If x, y, z are three distinct positive real numbers such that $x+y+z=1$, then the value of $\left(\frac{1}{x}-1\right)\left(\frac{1}{y}-1\right)\left(\frac{1}{z}-1\right)$ is :
(a) 16 (b) 8
(c) 4 (d) 1

10. If x, y, z are real numbers such that $x+y+z=4$ and $x^2+y^2+z^2=6$, then x, y, z lie in :
(a) $\left[\frac{3}{2}, 2\right]$ (b) $\left[\frac{2}{3}, 2\right]$
(c) $\left[0, \frac{2}{3}\right]$ (d) none of these

11. If $x=7+4\sqrt{3}$ and $xy=1$, then the value of $\left(\frac{1}{x^2}+\frac{1}{y^2}\right)$ is :
(a) 194 (b) 57
(c) $85\sqrt{3}$ (d) $\frac{7+4\sqrt{3}}{7-4\sqrt{3}}$

12. If a, b, c are positive real numbers, the least value of $(a+b+c)\left(\frac{1}{a}+\frac{1}{b}+\frac{1}{c}\right)$ is :
(a) 1 (b) 9
(c) 12 (d) none of these

13. If $a>0$, $b>0$ and $ab=1$, then the least value of the expression $(1+a)(1+b)$ is :
(a) 2 (b) 4
(c) 1 (d) 1/4

14. If a, b, c are all positive and not equal, then the value of $\frac{(a+b+c)(ab+bc+ca)}{abc}$ is :
(a) less than 9 (b) greater than 9
(c) less than or equal to 9 (d) can't be determined

15. If a, b, c are all positive, then the minimum value of the expression $\frac{(a^2+a+1)(b^2+b+1)(c^2+c+1)}{abc}$ is :
(a) 3 (b) 9
(c) 27 (d) 1

16. If $1 \le x \le 3$ and $2 \le y \le 4$, what is the maximum value of $\left(\frac{x}{y}\right)$?
(a) $\frac{2}{3}$ (b) 4
(c) $\frac{3}{2}$ (d) 2

17. If $a+b+c=3$, $a^2+b^2+c^2=6$ and $\frac{1}{a}+\frac{1}{b}+\frac{1}{c}=1$ where a, b, c are all non-zero, then abc is :
(a) $\frac{1}{3}$ (b) $\frac{2}{3}$
(c) $\frac{3}{2}$ (d) 1

18. $2^x=4^y=8^z$ and $xyz=288$, then value of $\frac{1}{2x}+\frac{1}{4y}+\frac{1}{8z}$ is :
(a) $\frac{11}{12}$ (b) $\frac{11}{96}$
(c) $\frac{29}{96}$ (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

19. If $a^x = b, b^y = c, c^z = a$, then the value of xyz is :
(a) 3 (b) 0
(c) 1 (d) can't be determined

20. Let $x, y \in N$ and $7x + 12y = 220$. The number of solutions is :
(a) 1 (b) 2
(c) 3 (d) infinitely many

21. If $a^x = (x + y + z)^y$, $a^y = (x + y + z)^z$, $a^z = (x + y + z)^x$, then :
(a) $3(x + y + z) = a$ (b) $2a = x + y + z$
(c) $x + y + z = 0$ (d) $x = y = z = \frac{a}{3}$

22. If $\frac{x}{a} = \frac{y}{b} = \frac{z}{c}$, then $xy + yz + zx$ is equal to :
(a) $\frac{(a+b+c)^2}{x^2+y^2+z^2}$
(b) $\frac{x^2(a+b+c)^2 - a^2(x^2+y^2+z^2)}{2a^2}$
(c) $\frac{ax+by+cz}{(a+b+c)^2}$
(d) none of the above

23. In the farm-house of Bhuwan Kisan, there were total 14 deer and ducks. One day a thief entered secretely in the farm-house and after killing all the deer and ducks he took away all the stuff except their legs. When Bhuwan noticed it he has found there 38 legs of deer and ducks. The number of deer in the farm house was :
(a) 5 (b) 8
(c) 9 (d) 10

24. In an autofair at Pragati Maidan, New Delhi, there are 600 vehicles consisting of only two wheelers and four wheelers. A world renowned tyre agency visits the fair to survey the trye market which finds that there are total 2000 tyres are fixed in all the 600 vehicles, but without any stepney (or spare tyre). The number of two wheelers in the autofair is :
(a) 300 (b) 400
(c) 180 (d) 200

25. In the battle of Mahabharat Veer Arjun destroyed all the 125 raths (horse-carts). Out of which few were driven by 3 horses each and rest were driven by 5 horses each. Thus, he captured 125 damaged raths along with 575 horses. The raths which were driven by 5 horses belonged to the Kaurav and the raths which were driven by 3 horses belonged to the allied army of Kaurav. It is known that no any horse was injured in the battle. The number of raths originally belonged to the Kaurav (not to their allied army) is :
(a) 60 (b) 25
(c) 75 (d) 100

26. In an electric appliances shop there were some fans and coolers containing 3 blades and 4 blades each respectively along with a motor each. The cost of a fan is Rs. 1200 and that of cooler is Rs. 3000. One day due to short circuit the shop caught the fire. After extinguishing the fire, shopkeeper has estimated that 90 sets of motor bodies and 320 blades were burned and then nothing was left useful in his shop. What is the loss incurred from the coolers alone?
(a) Rs. 1,50,000 (b) Rs. 12,000
(c) Rs. 4800 (d) can't be determined

27. In the air talent show in the eve of independence day 90 aircraft (only Sukhoi and Mig-21) participated. It is known that for every one hour flight a Sukhoi and a Mig-21 consume 2 litres and 3 litres of fuel respectively. The price of fuel for Sukhoi is $ 10 per litre and price for the fuel of Mig-21 is $ 15 per litre. Thus all the aircrafts accounted $ 3050 for the fuel in one hour show. The number of Sukhoi planes is :
(a) 20 (b) 30
(c) 40 (d) 50

Directions for question number 28 to 30: *In the fruit market adjacent to IIM Lucknow, a fruit vendor has total 20 kg of fruits containing only mangoes and apples. The vendor told to Ritika, an IIM student, that one kg apple contains only 7 apples while 1 kg of mangoes contains 10 mangoes and it is known that all the mangoes and apples are uniform in size individually. The vendor has initially 176 pieces of apples and mangoes, in all. Ritika purchased 55 fruits to distribute equally among the group of 11 students, irrespective of the kind of fruit i.e., mango or apple, and then the vendor is left with only 13 kg of fruits.*

28. The number of apples remaining with the vendor when Ritika has purchased 7 kg of fruits, is :
(a) 21 (b) 35
(c) 80 (d) none of these

29. If the selling price of mangoes and apples be Rs. 35 per kg and Rs. 40 per kg respectively, then how many rupees Ritika has spent for the 7 kg of fruits?
(a) Rs. 262.5 (b) Rs. 255
(c) Rs. 270 (d) Rs. 155

30. If the vendor has received 16.66% profit in selling of mangoes and 33.33% profit in the selling of apples to Ritika, but for the rest of the selling he exchanges the profit per cent between mangoes and apples. What is his overall profit per cent for the rest of the fruits? (Data can be used from the previous question if necessary)
(a) 29.48% (b) 5.92%
(c) no any profit (d) can't be determined

31. One day my assistant Rajesh went to a stationary shop to purchase marker pens. He purchased the pens for Rs. 52 and he gave a Rs. 100 note to the shopkeeper. The shopkeeper offered Rajesh to take back Rs. 48 in the denominations of only Re. 1, Rs. 2 and Rs. 5.
So, Rajesh received total 26 coins from the shopkeeper. Minimum number of Re. 1 coins which Rajesh has with him if he has at least one coin of each denomination offered by the shopkeeper :
(a) 4 (b) 5
(c) 7 (d) 10

32. What is the solutions of the following simultaneous equations?
$x + y + z = 6, \quad x + 2y + 3z = 14, \quad x + 3y + z = 10$
(a) $x = 1, y = 2, z = 4$ (b) $x = 1, y = 2, z = 3$
(c) $x = 2, y = 1, z = 3$ (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-13.1

1. (d)	2. (c)	3. (c)	4. (d)	5. (c)	6. (c)	7. (d)	8. (b)	9. (c)	10. (d)
11. (b)	12. (a)	13. (b)	14. (c)	15. (b)	16. (b)	17. (d)	18. (b)	19. (c)	20. (b)
21. (c)	22. (a)	23. (d)	24. (d)	25. (c)	26. (b)	27. (c)	28. (c)	29. (d)	30. (a)
31. (b)	32. (c)	33. (c)	34. (c)	35. (d)	36. (a)	37. (b)	38. (c)	39. (b)	40. (a)
41. (d)	42. (c)	43. (b)	44. (b)	45. (c)	46. (b)	47. (b)	48. (c)	49. (c)	50. (c)
51. (c)	52. (b)	53. (d)	54. (c)	55. (d)	56. (c)	57. (b)	58. (c)	59. (d)	60. (a)
61. (a)	62. (c)	63. (b)	64. (a)	65. (b)	66. (a)	67. (c)	68. (d)	69. (d)	70. (b)
71. (c)	72. (d)	73. (a)	74. (b)	75. (b)	76. (a)	77. (b)	78. (a)	79. (c)	80. (d)
81. (d)	82. (c)	83. (d)	84. (c)	85. (b)	86. (a)	87. (a)	88. (b)	89. (b)	90. (a)
91. (c)									

INTRODUCTORY EXERCISE-13.2

1. (b)	2. (a)	3. (c)	4. (b)	5. (c)	6. (d)	7. (b)	8. (a)	9. (c)	10. (a)
11. (c)	12. (b)	13. (c)	14. (b)	15. (d)	16. (b)	17. (c)	18. (a)	19. (b)	20. (b)
21. (d)	22. (d)								

LEVEL-1

1. (b)	2. (c)	3. (d)	4. (c)	5. (a)	6. (b)	7. (d)	8. (c)	9. (b)	10. (b)
11. (a)	12. (b)	13. (b)	14. (b)	15. (c)	16. (c)	17. (c)	18. (b)	19. (c)	20. (c)
21. (d)	22. (b)	23. (a)	24. (d)	25. (d)	26. (a)	27. (c)	28. (a)	29. (c)	30. (a)
31. (c)	32. (b)								

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 13.1

1. Total score $= x + y + 40$

2. Quotient $= \frac{z}{4}$

$\therefore \quad 3y \times \frac{z}{4} = \frac{3yz}{4}$

3. $6 \times p \times q \times r \times p \times p \times p = 6 \times p \times p \times p \times p \times q \times r$

$= 6 \times p^4 \times q \times r = 6p^4qr$

4. (i) $2x^2$ (ii) $-\frac{3}{x}$ (iii) $\frac{5}{x^2}$ (iv) 9

5. (i) $4xyz$ (ii) $-\frac{3}{x^2}$ (iii) $6xy^2$ (iv) $-5z^3$ (v) $6x$

6. $7 \times a + b \div 3 - c + b = 7a + \frac{b}{3} - c + b$

$\therefore$ (i) $7a$ (ii) $\frac{b}{3}$ (iii) $-c$ (iv) b

7. $\frac{-7xy^2z^3}{z^3} = -7xy^2$

9. $4x^3 \rightarrow$ degree 3

$2x^2y^3 \rightarrow$ degree $(2 + 3) = 5$

$6x^0y^0 \rightarrow$ degree 0

$\therefore$ the degree of whole expression is 5

10. $2x^2 + 3y^2 - 5xy + 5x^2 - y^2 + 6xy - 3x^2$

$= 2x^2 - 3x^2 + 5x^2 + 3y^2 - y^2 - 5xy + 6xy$

$= 4x^2 + 2y^2 + xy$

11. $(5x^2 + 3x - 1) - (3x^3 - 2x + 7)$

or

$$\begin{array}{r} 5x^2 + 3x - 1 \\ 3x^3 - 2x + 7 \\ - \quad + \quad - \\ \hline -3x^3 + 5x^2 + 5x - 8 \end{array}$$

(In subtraction we change the sign)

12. $\left(\frac{1}{2}a^2b - \frac{2}{3}ab^2 + 5\right) \times (6abc)$

$= \frac{1}{2}a^2b \times 6abc - \frac{2}{3}ab^2 \times 6abc + 5 \times 6abc$

$= 3a^3b^2c - 4a^2b^3c + 30abc$

13. $\left(\frac{1}{2}x^2 - \frac{1}{3}y^2\right) \times \left(\frac{1}{2}x^2 + \frac{1}{3}y^2\right)$

$= \frac{1}{2}x^2\left(\frac{1}{2}x^2 + \frac{1}{3}y^2\right) - \frac{1}{3}y^2\left(\frac{1}{2}x^2 + \frac{1}{3}y^2\right)$

$= \left(\frac{1}{2}x^2 \times \frac{1}{2}x^2 + \frac{1}{2}x^2 \times \frac{1}{3}y^2\right) - \frac{1}{3}y^2 \times \frac{1}{2}x^2 - \frac{1}{3}y^2 \times \frac{1}{3}y^2$

$= \frac{1}{4}x^4 + \frac{1}{6}x^2y^2 - \frac{1}{6}x^2y^2 - \frac{1}{9}y^4$

$= \frac{1}{4}x^4 - \frac{1}{9}y^4$

14. $\frac{36x^2y^5 + 42xy^3 - 24x^3y^2 - 12y^5}{-6y^2}$

$= \frac{36x^2y^5}{-6y^2} + \frac{42xy^3}{-6y^2} - \frac{24x^3y^2}{-6y^2} - \frac{12y^5}{-6y^2}$

$= -6x^2y^3 - 7xy + 4x^3 + 2y^3$

15. Since divisor is $x + 3$

$\therefore \quad x + 3 = 0 \rightarrow x = -3$

$\therefore$ put $x = -3$ in the expression

$3x^3 + 8x^2 - 6x + 1 = 3(-3)^3 + 8(-3)^2 - 6(-3) + 1$

$= -81 + 72 + 18 + 1 = 10$

16. Put $x = -3$ in the given expression

$ax^3 + 9x^2 + 4x - 10$

$\because \quad a(-3)^3 + 9(-3)^2 + 4(-3) - 10 = 5$

$\therefore \quad -27a + 81 - 12 - 10 = 5$

$\Rightarrow \quad -27a = -54 \Rightarrow a = 2$

17. Put $x = -1$, then

$(-1)^3 + a(-1)^2 - b(-1) - 6 = 0$

or $-1 + a + b - 6 = 0$

or $a + b - 7 = 0 \quad \ldots(1)$

and put $x = 2$, then

$(2)^3 + a(2)^2 - b(2) - 6 = 0$

$\Rightarrow \quad 8 + 4a - 2b - 6 = 0$

$\Rightarrow \quad 4a - 2b + 2 = 0 \quad \ldots(2)$

By solving Eq. (1) and (2)

$a + b - 7 = 0 \Rightarrow a + b = 7$

and $4a - 2b + 2 = 0 \Rightarrow 2a - b = -1$

$\therefore \quad 3a = 6 \Rightarrow a = 2$

Substituting $a = 2$ in Eq. (1) we get $b = 5$.

$\therefore \quad a = 2$ and $b = 5$

18. $\because A^2 - B^2 = (A + B) \cdot (A - B)$

$\therefore (5x^2 + 14x + 2)^2 - (4x^2 - 5x + 7)^2$

$= (5x^2 + 14x + 2 + 4x^2 - 5x + 7)$

$\times (5x^2 + 14x + 2 - 4x^2 + 5x - 7)$

$= 9(x^2 + 19x - 5)(x^2 + x + 1)$

$\therefore \frac{(5x^2 + 14x + 2)^2 - (4x^2 - 5x + 7)^2}{(x^2 + x + 1)} = 9(x^2 + 19x - 5)$

$\therefore \quad q = 9(x^2 + 19x - 5)$ and $r = 0$.

19. Putting $x = -1$ in the given polynomial, we get

$(-1)^3 - 6(-1) + 7 = -1 + 6 + 7 = 12 \quad (\because x + 1 = 0)$

20. Putting $x = 2$, we get $(\because x - 2 = 0)$

$(2)^4 - 3(2)^3 + 2(2)^2 - 5(2) + 7$

$= 16 - 24 + 8 - 10 + 7 = -3$

Scanned by CamScanner

yourchanbook.wordpress.com

21. Since divisor is $x^2 + 2$

$\therefore$ Substitute $x^2 = -2$, in the given expression

$x^3 + 5x^2 + 10k$ gives the remainder $-2x$

$$(-2)x + 5(-2) + 10k = -2x$$

$$\Rightarrow \quad k = 1$$

22. Putting $x = -1$, we get

$$(-1)^{11} + 1 = -1 + 1 = 0$$

23. Putting $x = -3$, we get

$$5(-3)^3 + 5(-3)^2 - 6(-3) + 9 = -135 + 45 + 18 + 9 = -63$$

25. Best way is that to consider some appropriate value of x (say $x = 1$), then check through options :

Let $x = 1$, then

$x^3 - 2x^2 + px - q = 1 - 2 + p - q \rightarrow$ dividend

and $\quad x - 6 = 1 - 6 = -5 \rightarrow$ remainder

and $\quad x^2 - 2x - 3 = 1 - 2 - 3 = -4 \rightarrow$ divisor

$\therefore$ now assume choice (c) as $p = -2$ and $q = 6$ then

$$\frac{-1 + p - q}{-4} = \frac{-1 + (-2) - 6}{-4} = \frac{-9}{-4} \rightarrow \text{Remainder} - 5$$

NOTE To avoid negative remainder you can assume $x = 7, 8, \ldots$, etc.)

Alternatively : Divide the given expression as conventionally and then compare the actual remainder with obtained remainder.

$$x^2 - 2x - 3 \overline{)x^3 - 2x^2 + px - q} \ (\times\times\times\times$$
$$\underline{\times \quad \times \quad \times \quad \times}$$

$$\text{Remainder} = (p + 3)x - q$$

$$\therefore \quad (p + 3)x - q = x - 6$$

$$\therefore \quad p + 3 = 1 \quad \text{and} \quad q = 6$$

$$\Rightarrow \quad p = -2 \quad \text{and} \quad q = 6$$

26. Put $x = 2$ in the given expression as :

$$x^2 + 3qx - 2q = 0$$

$$(2)^2 + 3q(2) - 2q = 0$$

$$\Rightarrow \quad 4 + 6q - 2q = 0 \quad \Rightarrow \quad 4 + 4q = 0$$

$$\Rightarrow \quad q = -1$$

27. Put $x = -2$ in the given polynomial.

$$(-2)^3 + 6(-2)^2 + 4(-2) + k = 0$$

$$\Rightarrow \quad k = -8$$

28. The best way is check by options. Let us consider choice (c). $(x - 2)$ is a factor of the given expression then at $x = 2$ the given expression must be zero.

$$\therefore \quad (2)^4 - 5(2)^3 + 5(2)^2 - 10(2) + 24 = 0$$

Hence, $(x - 2)$ is the factor of $x^4 - 5x^3 + 5x^2 - 10x + 24$.

29. Since $(x + k)$ is a factor of each one of the given expression, $x = -k$ will make each zero.

$$\therefore \quad k^2 - pk + q = k^2 - lk + m = 0$$

$$\Rightarrow \quad k = \frac{m - q}{l - p}$$

30. Substitute $x = a$ in the given expression since $(x - a)$ is a factor, which will make it equal to zero.

$$\therefore \quad (a)^3 - 3a^3 + 2a^3 + b = 0 \quad \Rightarrow \quad b = 0$$

31. Go through options

32. Go through options

33. Put $x = -1$ in the given expression

34. Put $x = 1$ in the given expression

36.
$$\left(x + \frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} + 2x \cdot \frac{1}{x}$$

$$(2)^2 = x^2 + \frac{1}{x^2} + 2 \quad \left(\text{Putting } x + \frac{1}{x} = 2\right)$$

$$\Rightarrow \quad x^2 + \frac{1}{x^2} = 2$$

37.
$$\left(x - \frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} - 2x \cdot \frac{1}{x}$$

$$(4)^2 = x^2 + \frac{1}{x^2} - 2$$

$$\Rightarrow \quad x^2 + \frac{1}{x^2} = 18$$

38.
$$\left(x + \frac{1}{x}\right)^3 = x^3 + \frac{1}{x^3} + 3x \cdot \frac{1}{x}\left(x + \frac{1}{x}\right)$$

$$\left(x + \frac{1}{x}\right)^3 = x^3 + \frac{1}{x^3} + 3\left(x + \frac{1}{x}\right)$$

$$\Rightarrow \quad (2\sqrt{3})^3 = x^3 + \frac{1}{x^3} + 3(2\sqrt{3})$$

$$\Rightarrow \quad x^3 + \frac{1}{x^3} = 18\sqrt{3}$$

39.
$$\left(x + \frac{1}{x}\right)^3 = x^3 + \frac{1}{x^3} + 3x \cdot \frac{1}{x}\left(x + \frac{1}{x}\right)$$

$$(3)^3 = x^3 + \frac{1}{x^3} + 3(3)$$

$$\Rightarrow \quad x^3 + \frac{1}{x^3} = 18$$

40.
$$\left(x + \frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} + 2 \cdot x \cdot \frac{1}{x}$$

$$(2)^2 = x^2 + \frac{1}{x^2} + 2$$

$$x^2 + \frac{1}{x^2} = 2$$

$$\text{Again} \left(x^2 + \frac{1}{x^2}\right)^3 = x^6 + \frac{1}{x^6} + 3x^2 \cdot \frac{1}{x^2}\left(x^2 + \frac{1}{x^2}\right)$$

$$(2)^3 = x^6 + \frac{1}{x^6} + 3(2)$$

$$\Rightarrow \quad x^6 + \frac{1}{x^6} = 2$$

41.
$$\left(x - \frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} - 2x \cdot \frac{1}{x}$$

$$\left(x - \frac{1}{x}\right)^2 = 6 - 2$$

$$\left(x - \frac{1}{x}\right)^2 = 4$$

$$\Rightarrow \quad \left(x - \frac{1}{x}\right) = \pm 2$$

Scanned by CamScanner

yoursmahboob.wordpress.com

43. $\left(x-\frac{1}{x}\right)^3 = x^3 - \frac{1}{x^3} - 3x\cdot\frac{1}{x}\left(x-\frac{1}{x}\right)$

$\left(x-\frac{1}{x}\right)^3 = 36 - 3\left(x-\frac{1}{x}\right)$

Let $\left(x-\frac{1}{x}\right) = P$

then $P^3 = 36 - 3P$

or $P^3 + 3P = 36 \Rightarrow P^3 + 3P - 36 = 0$

Clearly $P = 3$ satisfies the equation.

$\therefore$ $x - \frac{1}{x} = 3$

Alternatively: Go through options

43. $\left(x+\frac{1}{x}\right)^3 = x^3 + \frac{1}{x^3} + 3x\cdot\frac{1}{x}\left(x+\frac{1}{x}\right)$

$\Rightarrow \left(x+\frac{1}{x}\right)^3 = x^3 + \frac{1}{x^3} + 3\left(x+\frac{1}{x}\right)$

Now go through the given choices.

44. $x^4 + \frac{1}{x^4} = \left(x^2+\frac{1}{x^2}\right)^2 - 2$

$\therefore$ $34 = \left(x^2+\frac{1}{x^2}\right)^2 - 2$

$\Rightarrow \left(x^2+\frac{1}{x^2}\right)^2 = 36 \Rightarrow x^2 + \frac{1}{x^2} = 6$

Again $\left(x-\frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} - 2$

$\Rightarrow \left(x-\frac{1}{x}\right)^2 = 6 - 2 = 4$

$\Rightarrow x - \frac{1}{x} = 2$

Alternatively : Go through options.

45. $\left(x^2+\frac{1}{x^2}\right)^2 = x^4 + \frac{1}{x^4} + 2$

$\Rightarrow \left(x^2+\frac{1}{x^2}\right)^2 = 121$

$\Rightarrow x^2 + \frac{1}{x^2} = 11$

Again $\left(x-\frac{1}{x}\right)^2 = x^2 + \frac{1}{x^2} - 2$

$\therefore$ $\left(x-\frac{1}{x}\right)^2 = 9 \Rightarrow x - \frac{1}{x} = 3$

$\therefore$ $\left(x-\frac{1}{x}\right)^3 = x^3 - \frac{1}{x^3} - 3x\cdot\frac{1}{x}\left(x-\frac{1}{x}\right)$

$(3)^3 = x^3 - \frac{1}{x^3} - 3(3)$

$\Rightarrow x^3 - \frac{1}{x^3} = 36$

46. $\left(3x-\frac{2}{x}\right)^2 = 25$

$9x^2 + \frac{4}{x^2} - 12 = 25 \Rightarrow 9x^2 + \frac{4}{x^2} = 37$

Again $9x^2 + \frac{4}{x^2} + 12 = 37 + 12 = 49$

$\Rightarrow \left(3x+\frac{2}{x}\right)^2 = (7)^2 \Rightarrow 3x + \frac{2}{x} = 7$

$\therefore$ $\left(9x^2 - \frac{4}{x^2}\right) = \left(3x-\frac{2}{x}\right)\left(3x+\frac{2}{x}\right) = 5\times 7 = 35$

47. $m^2 - 4m + 1 = 0 \Rightarrow m^2 + 1 = 4m \Rightarrow \frac{m^2+1}{m} = 4$

$\Rightarrow m + \frac{1}{m} = 4$

$\therefore$ $\left(m+\frac{1}{m}\right)^3 = m^3 + \frac{1}{m^3} + 3\left(m+\frac{1}{m}\right) = 64$

$\Rightarrow m^3 + \frac{1}{m^3} = 52$

48. $(x+y)^2 = x^2 + y^2 + 2xy$

$169 = x^2 + y^2 + 2\times 40$

$\Rightarrow x^2 + y^2 = 89$

49. $(x+y)^3 = x^3 + y^3 + 3xy(x+y)$

$2097 = x^3 + \frac{1}{x^3} + 3\times 36(13)$

$\Rightarrow x^3 + \frac{1}{x^3} = 2097 - 1404$

$x^3 + \frac{1}{x^3} = 693$

50. $(x-y)^2 = (x+y)^2 - 4xy = 64 - 60 = 4$

$\Rightarrow (x-y) = 2$

$\therefore$ $x^3 - y^3 = (x-y)^3 + 3xy(x-y)$

$= 8 + 45(2)$

$x^3 - y^3 = 98$

51. $(x^3 + y^3 + z^3 - 3xyz)$

$= (x+y+z)(x^2 + y^2 + z^2 - xy - yz - zx)$

$= (x+y+z)[(x+y+z)^2 - 3(xy+yz+zx)]$

$= 6\times[36 - 3\times 11] = 6\times 3 = 18$

52. $x + y + z = 0 \Rightarrow x^3 + y^3 + z^3 = 3xyz.$

53. $\because x + y + z = 0 \Rightarrow x^3 + y^3 + z^3 = 3xyz$

$\therefore$ $a^{1/3} + b^{1/3} + c^{1/3} = 0$

$\Rightarrow a + b + c = 3a^{1/3}b^{1/3}c^{1/3}$

$\therefore$ $(a+b+c)^3 = 27abc$

54. $2^x - \frac{2^x}{2} = 8 \Rightarrow k - \frac{k}{2} = 8 \Rightarrow k = 16$

$\therefore$ $2^x = 16 \Rightarrow$ (say $2^x = k$)

$\Rightarrow 2^x = 2^4 \Rightarrow x = 4.$

$\therefore$ $x^3 = (4)^3 = 64$

Scanned by CamScanner

yoursmahboob.wordpress.com

55. $3^x + 3^{x+1} = 36 \Rightarrow 3^x + 3.3^x = 36$

Let $3^x = k$

$\therefore \quad k + 3k = 36 \Rightarrow k = 9$

$\therefore \quad 3^x = 9 \Rightarrow x = 2$

$\therefore \quad x^x = 2^2 = 4.$

56. $\dfrac{(a+b)-(a-b)^2}{a^2b-ab^2} = \dfrac{(a^2+b^2+2ab)-(a^2+b^2-2ab)}{ab(a-b)}$

$= \dfrac{4ab}{ab(a-b)} = \dfrac{4}{(a-b)}$

57. Let $\dfrac{x}{(b-c)(b+c-2a)} = \dfrac{y}{(c-a)(c+a-2b)}$

$= \dfrac{z}{(a-b)(a+b-2c)} = k$, then

$x = k(b-c)(b+c-2a), \; y = k(c-a)(c+a-2b),$

$z = k(a-b)(a+b-2c)$

$\therefore \quad (x+y+z) = k[(b^2-c^2+c^2-a^2+a^2-b^2)$

$-2\{a(b-c)+b(c-a)+c(a-b)\}]$

$= 0$

58. $a^4 + 5a^3 + 6a^2 = a^2(a^2+5a+6) = a^2(a+3)(a+2)$

60. $a^{3/2} - ab^{1/2} + a^{1/2}b - b^{3/2}$

$= a(a^{1/2} - b^{1/2}) + b(a^{1/2} - b^{1/2})$

$= (a+b)(a^{1/2} - b^{1/2})$

$\therefore \quad \dfrac{(a+b)(a^{1/2}-b^{1/2})}{(a^{1/2}-b^{1/2})} = (a+b)$

61. $x(y^2-z^2) + y(z^2-x^2) + z(x^2-y^2)$

$= x^2(z-y) - x(z^2-y^2) + yz(z-y)$

(Writing in descending power of x)

$= (z-y)[x^2 - x(z+y) + yz]$

$= (z-y)(x-z)(x-y)$

Alternatively: Consider $x = 1$, $y = 2$ and $z = 3$ and then verify the correct option.

62. Since $x^3 - y^3 = (x-y)(x^2+y^2+xy)$

$\therefore (a+b)^3 - (a-b)^3$

$= [(a+b)-(a-b)][(a+b)^2 + (a-b)^2 + (a+b)(a-b)]$

$= 2b[2(a^2+b^2) + (a^2-b^2)] = 2b(3a^2+b^2)$

63. $(x^2+4) = (x^2+2^2) = (x)^2 + (2)^2 + 4x^2 - 4x^2$

$= (x^2+2)^2 - (2x)^2$

$= (x^2+2+2x)(x^2+2-2x)$

64. Best way is to go through options.

$(x-1)(x+3)(x-2) = (x^2+2x-3)(x-2)$

$= x^3 + 2x^2 - 3x - 2x^2 - 4x + 6$

$= x^3 - 7x + 6$

Hence option (a) is correct.

65. $(64x^3 - 216y^3) = (4x)^3 - (6y)^3$

$= (4x-6y)[(4x)^2 + (6y)^2 + 24xy]$

66. $a^2 + 4b^2 + 4b - 4ab - 2a - 8$

$= a^2 + 4b^2 - 4ab + 4b - 2a - 8$

$= (a-2b)^2 - 2(a-2b) - 8$

$= k^2 - 2k - 8,$ where $k = a - 2b$

$= k^2 - 4k + 2k - 8$

$= k(k-4) + 2(k-4)$

$= (k-4)(k+2)$

$= (a-2b-4)(a-2b+2)$

67. Let $(a-b) = x$, $(b-c) = y$ and $(c-a) = z$

Then $x + y + z = 0$

$\therefore \quad x^3 + y^3 + z^3 = 3xyz$

Hence $(a-b)^3 + (b-c)^3 + (c-a)^3 = 3(a-b)(b-c)(c-a)$

68. $(a+b+c)^2 = a^2 + b^2 + c^2 + 2(ab+bc+ac)$

$0 = a^2 + b^2 + c^2 + 2(ab+bc+ac)$

$\therefore \quad a^2 + b^2 + c^2 = -2(ab+bc+ac)$

69. First of all factorize the expression then find the HCF or LCM as per the requirement.

(1) LCM of $10a^2b^2$, $15abc$, $20ab^2c^2$ is $3 \times 2^2 \times 5a^2b^2c^2 = 60a^2b^2c^2$, Hence (a) is wrong.

(2) $(x^2 - 6x + 9) = (x-3)^2$

and $(x^3 - 27) = (x-3)(x^2+3x+9)$

$\therefore \quad$ HCF $= (x-3)$

(3) $6x^2 - 7x - 3 = (2x-3)(3x+1)$

$(2x^2 + 11x - 21) = (x+7)(2x-3)$

$\therefore \quad$ HCF $= (2x-3)$.

Hence 2 and 3 are correct.

70. $2x^2 - 3x - 2 = 2x^2 - 4x + x - 2$

$= (x-2)(2x+1)$

and $(x^3 - 4x^2 + 4x) = x(x^2 - 4x + 4) = x(x-2)^2$

$\therefore \quad$ LCM $= x(x-2)^2(2x+1)$

71. $2(x^2 - y^2) = 2(x-y)(x+y)$

and $5(x^3 - y^3) = 5(x-y)(x^2+y^2+xy)$

$\therefore \quad$ HCF $= (x-y)$

72. $(x^4 - 4x^2 + 3) = x^4 - 3x^2 - x^2 + 3$

$= x^2(x^2-3) - 1(x^2-3)$

$= (x^2-3)(x^2-1)$

$= (x^2-3)(x-1)(x+1)$

and $x^4 - x^2 - 6 = x^4 - 3x^2 + 2x^2 - 6$

$= x^2(x^2-3) + 2(x^2-3)$

$= (x^2-3)(x^2+2)$

$\therefore \quad$ HCF $= (x^2-3)$

73. $x^2 - 4 = (x+2)(x-2)$

$(x^2 - 5x - 6) = (x+1)(x-6)$

$(x^2 + x - 6) = (x-2)(x+3)$

Since there is no any common factor. So HCF is 1.

74. $x^2 - ax - (a+1) = x^2 - (a+1)x + x - (a+1)$

$= (x+1)(x-a+1)$

and $ax^2 - x - (a+1) = ax^2 - a - x - 1$

$= a(x^2-1) - 1(x+1)$

$= (x+1)(ax-a-1)$

$\therefore \quad$ HCF $= (x+1)$

Scanned by CamScanner

yoursmahboob.wordpress.com

75. $P = (x-2)(x+1)^2(x+3)^2$

and $Q = (x+1)^2(x+3)(x+4)$

$\therefore$ LCM of P and $Q = (x-2)(x+1)^2(x+3)^2(x+4)$

76. $a^3+b^3 = (a+b)(a^2+b^2-ab)$

$(a^4-b^4) = (a-b)(a+b)(a^2+b^2)$

LCM $= (a-b)(a+b)(a^2+b^2)(a^2+b^2-ab)$

$\therefore$ $= (a-b)(a^2+b^2)(a+b)(a^2+b^2-ab)$

$= (a-b)(a^2+b^2)(a^3+b^3)$

77. $(x^4-1) = (x-1)(x+1)(x^2+1)$

$(x^3+x^2+x+1) = x^2(x+1)+1(x+1) = (x^2+1)(x+1)$

HCF $= (x+1)(x^2+1)$

$\therefore$

78. $2x^2-4x = 2x(x-2)$

$3x^4-12x^2 = 3x^2(x^2-4)$

$= 3x^2(x+2)(x-2)$

$2x^5-2x^4-4x^3 = 2x^3(x^2-x-2)$

$= 2x^3(x-2)(x+1)$

HCF $= x(x-2)$

$\therefore$

79. Since all the factors are distinct

80. $(x+2)^2(x-2)$ and $x^2-4x-12 = (x-6)(x+2)$

$\therefore$ LCM $= (x-6)(x+2)^2(x-2)$

81. $a^2-ab-2b^2 = (a^2-b^2)-(ab+b^2)$

$= (a+b)(a-b-b) = (a+b)(a-2b)$

and $2a^2-ab-b^2 = (a^2-ab)+(a^2-b^2)$

$= (a-b)a+(a^2-b^2) = (a-b)(2a+b)$

Since there is no common factor, hence HCF = 1.

82. HCF $= a^2b^3c^3$

LCM $= a^5b^4c^4$

83. $\dfrac{(x+3)}{(x-2)}-\dfrac{(x+1)}{(x-3)} = \dfrac{(x+3)(x-3)-(x-2)(x+1)}{(x-2)(x-3)}$

$= \dfrac{(x^2-9)-(x^2-x-2)}{(x^2-5x+6)} = \dfrac{x-7}{(x^2-5x+6)}$

84. $\dfrac{x+1}{x-1}+\dfrac{x-1}{x+1} = \dfrac{(x+1)^2+(x-1)^2}{(x-1)(x+1)} = \dfrac{2(x^2+1)}{(x^2-1)}$

85. $\dfrac{x^2-5x+6}{x^2-9x+20} \div \dfrac{x^2-3x+2}{x^2-5x+4}$

$= \dfrac{x^2-5x+6}{x^2-9x+20} \times \dfrac{x^2-5x+4}{x^2-3x+2}$

$= \dfrac{(x-2)(x-3)}{(x-4)(x-5)} \times \dfrac{(x-1)(x-4)}{(x-1)(x-2)}$

$= \left(\dfrac{x-3}{x-5}\right)$

86. $\dfrac{2x^2+3}{x-3}+\dfrac{x-3}{2x^2+3}$

$= \dfrac{(2x^2+3)^2+(x-3)^2}{(x-3)(2x^2+3)} = \dfrac{4x^4+9+12x^2+x^2+9-6x}{2x^3-6x^2+3x-9}$

$= \dfrac{4x^4+13x^2-6x+18}{2x^3-6x^2+3x-9}$

87. $\dfrac{(x-3)(x^2-5x+4)}{(x-4)(x^2-2x-3)} = \dfrac{(x-3)(x-1)(x-4)}{(x-4)(x-3)(x+1)} = \dfrac{(x-1)}{(x+1)}$

88. $\dfrac{(2x^2+1)(x+1)+(x-1)^2}{(x^2-1)} \times \dfrac{(x^2-1)}{2x}$

$= \dfrac{2x^3+2x^2+x+1+(x-1)^2}{(2x)}$

$= \dfrac{2x^3+3x^2-x+2}{2x}$

89. $\sqrt{\dfrac{(x^2+3x+2)(x^2+5x+6)}{x^2(x^2+4x+3)}}$

$= \sqrt{\dfrac{(x+1)(x+2)(x+2)(x+3)}{x^2(x+1)(x+3)}} = \sqrt{\dfrac{(x+2)^2}{x^2}} = \dfrac{x+2}{x}$

90. $\dfrac{1}{(a-b)(a-c)}+\dfrac{1}{(b-c)(b-a)}+\dfrac{1}{(c-a)(c-b)}$

$(b-c)(b-a)(c-a)(c-b)+(a-b)(a-c)(c-a)(c-b)$

$+(a-b)(a-c)(b-c)(b-a)$

$\dfrac{}{(a-b)(a-c)(b-c)(b-a)(c-a)(c-b)} = 0$

91. $\dfrac{1}{(1-x)}+\dfrac{1}{(1+x)}+\dfrac{2}{(1+x^2)}+\dfrac{4}{(1+x^4)}$

$= \dfrac{(1+x)+(1-x)}{(1-x^2)}+\dfrac{2}{(1+x^2)}+\dfrac{4}{(1+x^4)}$

$= \dfrac{2}{(1-x^2)}+\dfrac{2}{(1+x^2)}+\dfrac{4}{(1+x^4)}$

$= \dfrac{4}{(1-x^4)}+\dfrac{4}{(1+x^4)} = \dfrac{8}{1-x^8}$

INTRODUCTORY EXERCISE 13.2

1. $x-y = \dfrac{9}{10}$ and $(x+y) = \dfrac{11}{2}$

$\Rightarrow$ $x-y = \dfrac{9}{10}$

and $x+y = \dfrac{11}{2}$

By addition

$2x = \dfrac{64}{10}$

$\Rightarrow$ $x = \dfrac{32}{10} = 3.2$

$\Rightarrow \therefore$ $y = \dfrac{23}{10} = 2.3$

2. $\dfrac{x+y}{xy} = 2 \Rightarrow \dfrac{1}{x}+\dfrac{1}{y} = 2$ ...(1)

and $\dfrac{x-y}{xy} = 6 \Rightarrow \dfrac{1}{y}-\dfrac{1}{x} = 6$ ...(2)

By adding Eq. (1) and (2), we get

$\dfrac{2}{y} = 8 \Rightarrow y = \dfrac{1}{4}$

$\therefore$ $x = -\dfrac{1}{2}$

$\therefore$ $x = -\dfrac{1}{2}$ and $y = \dfrac{1}{4}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively:

$$x + y = 2xy \quad \text{and} \quad x - y = 6xy \qquad \ldots(1)$$

$$\Rightarrow \quad 3(x + y) = 6xy \quad \text{and} \quad x - y = 6xy$$

$$\Rightarrow \quad 3x + 3y = x - y$$

$$\Rightarrow \quad 2x = -4y$$

$$\Rightarrow \quad x = -2y$$

Substituting $x = -2y$ in the Eq. (1), we get

$$-3y = 6xy \quad \Rightarrow \quad x = -\frac{1}{2}$$

and $\therefore \quad y = \frac{1}{4}$

3. $\frac{1}{2x} - \frac{1}{y} = -1$ and $\frac{1}{x} + \frac{1}{2y} = 8$

$$\Rightarrow \quad \frac{1}{2x} - \frac{1}{y} = -1 \quad \text{and} \quad \frac{2}{x} + \frac{1}{y} = 16$$

By adding these two equations, we get

$$\frac{5}{2x} = 15 \quad \Rightarrow \quad x = \frac{1}{6}$$

$$\therefore \quad y = \frac{1}{4}$$

4. $$\frac{2x}{a} + \frac{y}{b} = 2 \qquad \ldots(i)$$

$$\frac{x}{a} - \frac{y}{b} = 4 \qquad \ldots(ii)$$

Adding Eq. (i) and (ii), we get

$$\frac{3x}{a} = 6 \quad \Rightarrow \quad \frac{x}{a} = 2 \quad \Rightarrow \quad x = 2a$$

Now put $x = 2a$ in Eq. (ii)

$$\frac{y}{b} = -2$$

$$\therefore \quad x = 2a \quad \text{and} \quad y = -2b.$$

5. For no solution

$$\frac{9}{7} = \frac{4}{k} \neq \frac{9}{5} \quad \Rightarrow \quad k = \frac{28}{9}$$

6. Two linear equations will coincide if there are infinite number of solutions,

i.e., $$\frac{a_1}{a_2} = \frac{b_1}{b_2} = \frac{c_1}{c_2}$$

for $$a_1x + b_1y = c_1$$

and $$a_2x + b_2y = c_2$$

$$\therefore \quad \frac{k}{3} = \frac{2}{1} = \frac{2}{1} \quad \Rightarrow \quad k = 6$$

7. For an infinite number of solutions

$$\frac{2}{6} = \frac{3}{k} = \frac{-5}{-15} \quad \Rightarrow \quad k = 9$$

8. $$8B + 5M = 92 \qquad \ldots(1)$$

$$5B + 8M = 77 \qquad \ldots(2)$$

Multiply Eq. (1) by 8 Eq. (2) by 5, we get

$$\left.\begin{aligned} 64B + 40M &= 736 \\ 25B + 40M &= 385 \end{aligned}\right\} \quad \text{[Subtracting]}$$

$$39B = 351$$

$$B = 9$$

$$M = 4$$

$$\therefore \quad 2M + 3B = 35$$

$\therefore$ The required cost of 2 mugs and 3 buckets is Rs. 35.

(Here $M \rightarrow$ Price of a mug and $B \rightarrow$ Price of a bucket)

9. Let the two numbers be x and y.

$$x + y = 8$$

then $$(x + y) = 4(x - y)$$

and $$x - y = 2$$

$$\Rightarrow \quad x + y = 8 \quad \text{and} \quad x - y = 2$$

$$\therefore \quad 2x = 10 \quad \Rightarrow \quad x = 5$$

$$y = 3$$

$\therefore$

10. Let numerator be x and denominator be y.

$$x = y - 4 \qquad \ldots(1)$$

then $$8(x - 2) = (y + 1) \qquad \ldots(2)$$

The above equations can be written as

$$\left.\begin{aligned} y - x &= 4 \\ y - 8x &= -17 \end{aligned}\right\} \qquad \ldots(3)$$

and

$$\begin{array}{ccc} - & + & + \\ \hline & 7x = 21 & \end{array}$$

$$x = 3 \quad \therefore \quad y = 7$$

$$\Rightarrow$$

$\therefore$ the required fraction $= \frac{x}{y} = \frac{3}{7}$

11. Distance = 90 km

Let the speeds of car be x km/h and y km/h

$\therefore$ Distance = Speed × Time

$$\therefore \quad 90 = (x + y) \times \frac{9}{7} \quad \Rightarrow \quad x + y = 70$$

and $$90 = (x - y) \times 9 \quad \Rightarrow \quad x - y = 10$$

$$\therefore \quad x = 40 \quad \text{and} \quad y = 30$$

$\therefore$ the required speeds of cars = 40 km/h and 30 km/h

12. Let there be x coins of 25 paise denomination and y coins of 50 paise denomination, then

$$x + y = 40 \quad \Rightarrow \quad 25x + 25y = 1000 \qquad \ldots(1)$$

and $$25x + 50y = 1275 \qquad \ldots(2)$$

$\therefore$ Subtracting Eq. (1) from (2) we get

$$25y = 275 \quad \Rightarrow \quad y = 11$$

$$\therefore \quad x = 29.$$

13. Let there be x pencils and y pens, then

$$\therefore \quad x + y = 40 \quad \Rightarrow \quad 4x + 4y = 160$$

$$(x + 5) = 4(y - 5)$$

$$\Rightarrow \quad x - 4y = -25$$

$$\therefore \quad 4x + 4y = 160$$

$$x - 4y = -25$$

$$5x = 135$$

$$\Rightarrow \quad x = 27 \quad \therefore \quad y = 13$$

14. Let the present age of the son be 'x' years and the present age of his father be 'y' years.

then $$y = 3x \qquad \ldots(1)$$

Again $$(y + 12) = 2(x + 12) \qquad \ldots(2)$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Substituting $y = 3x$ in Eq. (2), we get

$$x = 12$$

$$y = 36$$

$\therefore$

15. Let the present age of A is x and the present age of B is y (in years).

then, $(x-5) = 3(y-5) \Rightarrow x - 3y = -10$ ...(1)

$(x+10) = 2(y+10) \Rightarrow x - 2y = 10$ ...(2)

Subtracting Eq. (2) from Eq. (1), we get

$$-y = -20 \Rightarrow y = 20$$

$$x = 50$$

$\therefore$

16. Let Astha will have x number of oranges and Saumya will have y number of oranges. Then,

$(x+10) = 2(y-10) \Rightarrow x - 2y = -30$ ...(1)

and $(x-10) = (y+10) \Rightarrow x - y = 20$ ...(2)

Subtracting Eq. (2) from Eq. (1), we get

$$-y = -50 \Rightarrow y = 50$$

$$x = 70$$

$\therefore$

17. Total distance = 760 km.

Let the speed of car be x km/h and the speed of train be y km/h

$\therefore$ Distance = Speed × Time

$\Rightarrow$ $T = \frac{D}{S}$

$\therefore$ $\frac{600}{x} + \frac{160}{y} = 8$ ...(1)

and $\frac{520}{x} + \frac{240}{y} = 8\frac{1}{5}$ ...(2)

$\therefore$ Eq. (1) can be written as

$$600A + 160B = 8$$ ...(3)

and Eq. (2) can be written as

$$520A + 240B = \frac{41}{5}$$ ...(4)

where, $\frac{1}{x} = A$ and $\frac{1}{y} = B$

$\therefore$ Solving Eq. (3) and (4) we get

$$1800A + 480B = 24$$

$$1040A + 480B = \frac{82}{5}$$

$$760A = \frac{38}{5}$$

$\Rightarrow$ $A = \frac{1}{100} \Rightarrow x = 100$ km/h

$\therefore$ $B = \frac{1}{80} \Rightarrow y = 80$ km/h

18. Let he has invested Rs. x at 12% S.I. and Rs. y at 10% SI

$\therefore$ $\left(\because SI = \frac{P \times r \times t}{100}\right)$

$$\frac{x \times 12 \times 1}{100} + \frac{y \times 10 \times 1}{100} = 130$$

$\Rightarrow$ $12x + 10y = 13000$ ...(1)

$\Rightarrow$ $10x + 12y = 134000$ ...(2)

$\therefore$ $x = 500$ and $y = 700$

19. $\frac{3x - y + 1}{3} = \frac{2x + y + 2}{5}$

$\Leftrightarrow$ $5(3x - y + 1) = 3(2x + y + 2)$

$\Leftrightarrow$ $9x - 8y = 1$ ...(1)

$\Leftrightarrow$ $\frac{2x + y + 2}{5} = \frac{3x + 2y + 1}{6}$

$\Leftrightarrow$ $6(2x + y + 2) = 5(3x + 2y + 1)$

$\Leftrightarrow$ $3x + 4y = 7$ ...(2)

Multiplying (2) by 2 and adding to (1), we get

$$15x = 15 \text{ or } x = 1$$

Putting $x = 1$ in (1), we get

$$9 \times 1 - 8y = 1 \Rightarrow y = 1.$$

20. Submarino can be destroyed when it meets the destroyer. Thus

$$2x + 3y = 5$$ ...(1)

$$x - y = 10$$ ...(2)

$\therefore$ $x = 7$ and $y = -3$

So the required point is $(7, -3)$

21. $\frac{x^2}{a^2} + \frac{y^2}{b^2} - \frac{z^2}{c^2} = 1$ ...(1)

$\frac{x^2}{a^2} - \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1$ ...(2)

$-\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1$ ...(3)

Adding Eq. (1), (2) and (3), we have

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 3$$ ...(4)

$\therefore$ $\frac{x^2}{a^2} = 1 \Rightarrow x = \pm a$

$\frac{y^2}{b^2} = 1 \Rightarrow y = \pm b$

$\frac{z^2}{c^2} = 1 \Rightarrow z = \pm c$

Hence (d) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL 1

1. If $x + y + z$ is constant, the product xyz takes maximum value when each of x, y, z takes equal value.

$\because \quad a + b + c = 13$

$\therefore \quad (a-3) + (b-2) + (c+1) = 13 - 3 - 2 + 1 = 9$

For the maximum value of $(a-3)(b-2)(c+1)$

$$= (a-3) = (b-2) = (c+1) = \frac{9}{3} = 3$$

So, $\quad (a-3)(b-2)(c+1) = 3 \times 3 \times 3 = 27$

2. If xyz is constant, then the sum of x, y, z (*i.e.*, $x + y + z$) takes minimum value when each of x, y, z takes equal value.

$\therefore$ Minimum value of $a + b + c + d$ for given constant product $abcd$ will be when $a = b = c = d$

$\therefore \quad a = b = c = d = 3$

$\therefore$ Minimum value of $a + b + c + d = 3 + 3 + 3 + 3 = 12$

3. For $x \geq 0$, $\quad x + \frac{1}{x} \geq 2$

and for $x \leq 0$, $\quad x + \frac{1}{x} \leq 2$



Graph of $\left(x + \frac{1}{x}\right)$

4. This is the standard inequality formula.

5. This is the standard inequality formula.

NOTE The result can be proved by considering suitable values.

6. $\quad x^2y^3 + y^2x^3 = 25$

$\Rightarrow \quad x^2y^2(x + y) = 25$

$\Rightarrow \quad (xy)^2(x + y) = 25$

$\Rightarrow \quad (xy)^2 = 1 \qquad (\because x + y = 25)$

$\Rightarrow \quad xy = \pm 1$

7. $x > 0$ and $y > 0$

$\therefore \quad (x + y)\left(\frac{1}{x} + \frac{1}{y}\right) = 2 + \frac{x}{y} + \frac{y}{x}$

$$= 2 + \left(k + \frac{1}{k}\right), \quad \text{where } k = \frac{x}{y}$$

Since the minimum value of the expression $\left(k + \frac{1}{k}\right)$ is 2.

$\therefore$ Minimum value of the given expression is 4.

8. If $a + b + c + d$ is constant, then the product $abcd$ is maximum when $a = b = c = d$.

$\therefore \quad (a+1) = (b+1) = (c+1) = (d+1)$

Given that $(a+1) + (b+1) + (c+1) + (d+1) = 8$

$\therefore \quad 4(a+1) = 8$

$\Rightarrow \quad (a+1) = 2$

$\therefore \quad$ Maximum value $= 2 \times 2 \times 2 \times 2 = 16$

9. As $\quad x + y + z = 1$

$$\left(\frac{1}{x} - 1\right)\left(\frac{1}{y} - 1\right)\left(\frac{1}{z} - 1\right) = \frac{y+z}{x} \cdot \frac{z+x}{y} \cdot \frac{x+y}{z}$$

But $\quad \frac{y+z}{2} \geq yz$ etc.

Hence, $\quad \text{LHS} \geq \frac{8xyz}{xyz} = 8$

10. $x + y + z = 4$ and $x^2 + y^2 + z^2 = 6$

$\therefore \quad y + z = 4 - x$

and $\quad y^2 + z^2 = 6 - x^2$

$$yz = \frac{1}{2}\{(y+z)^2 - (y^2 + z^2)\}$$

$$= \frac{1}{2}\{(4-x)^2 - (6 - x^2)\}$$

$\Rightarrow \quad yz = x^2 - 4x + 5$

Hence, y and z are the roots of

$$t^2 - (4-x)t + (x^2 - 4x + 5) = 0$$

Since the roots y and z are real

$$(4-x)^2 - 4(x^2 - 4x + 5) \geq 0$$

$\Rightarrow \quad 3x^2 - 8x + 4 \leq 0$

$\Rightarrow \quad (3x - 2)(x - 2) \leq 0$

$\Rightarrow \quad x \in \left[\frac{2}{3}, 2\right]$

By symmetry y, z also $\in \left[\frac{2}{3}, 2\right]$.

11. $\frac{1}{x^2} + \frac{1}{y^2} = \frac{x^2 + y^2}{(xy)^2}$

$$= \frac{(7 + 4\sqrt{3})^2 + (7 - 4\sqrt{3})^2}{[(7 + 4\sqrt{3})(7 - 4\sqrt{3})]^2} = \frac{2(49 + 48)}{(1)^2} = 194$$

12. $\text{AM} \geq \text{GM} \Rightarrow \frac{a+b+c}{3} \geq (abc)^{1/3}$

(AM → Arithmetic mean, GM → Geometric mean)

and $\quad \frac{1}{3}\left(\frac{1}{a} + \frac{1}{b} + \frac{1}{c}\right) \geq \left(\frac{1}{abc}\right)^{1/3}$

$$\Rightarrow \frac{1}{3}(a+b+c)\frac{1}{3}\left(\frac{1}{a} + \frac{1}{b} + \frac{1}{c}\right) \geq (abc)^{1/3}\left(\frac{1}{abc}\right)^{1/3} = 1$$

$\Rightarrow \quad (a+b+c)\left(\frac{1}{a} + \frac{1}{b} + \frac{1}{c}\right) \geq 9$

Putting $a = b = c = 1$, expression takes the value 9, which is therefore, its least value.

Scanned by CamScanner

yoursmahboob.wordpress.com

13. If ab is constant, then $(a+b)$ takes minimum value when $a = b$

$\therefore a = b = 1$

$\therefore (1+a)(1+b) = (1+1)(1+1) = 4$

14. $\dfrac{(a+b+c)(ab+bc+ac)}{abc} = (a+b+c)\left(\dfrac{ab}{abc}+\dfrac{bc}{abc}+\dfrac{ac}{abc}\right)$

$= (a+b+c)\left(\dfrac{1}{c}+\dfrac{1}{a}+\dfrac{1}{b}\right)$

$= (a+b+c)\left(\dfrac{1}{a}+\dfrac{1}{b}+\dfrac{1}{c}\right) > 9$

(See the problem number 12 in this exercise.)

15. The expression will have minimum value of the expression when $a = b = c$.

Therefore, the required minimum value

$= \dfrac{(1+1+1)}{1} \times \dfrac{(1+1+1)}{1} \times \dfrac{(1+1+1)}{1} = 27$

16. $\text{Max}\left(\dfrac{x}{y}\right) = \dfrac{\text{Max}\,(x)}{\text{Min}\,(y)} = \dfrac{3}{2}$

17. $\dfrac{1}{a}+\dfrac{1}{b}+\dfrac{1}{c} = 1$

$\Rightarrow \dfrac{bc+ac+ab}{abc} = 1$

$\Rightarrow bc+ac+ab = abc$ ...(1)

Again, $(a+b+c)^2 = a^2+b^2+c^2+2(ab+bc+ac)$

$(a+b+c)^2 = a^2+b^2+c^2+2abc$

$(3)^2 = 6 + 2abc \Rightarrow abc = \dfrac{3}{2}$

18. $2^x = 4^y = 8^z \Rightarrow 2^x = 2^{2y} = 2^{3z}$

$\Rightarrow x = 2y = 3z = k$ (say)

Then $xyz = \dfrac{k^3}{6} = 288 \Rightarrow k = 12$

$\therefore x = 12, \quad y = 6, \quad z = 4$

$\Rightarrow \dfrac{1}{2x}+\dfrac{1}{4y}+\dfrac{1}{8z} = \dfrac{11}{96}$

19. $a = c^z$

$\Rightarrow a = (b^y)^z$ $(\because c = b^y)$

$\Rightarrow a = b^{yz}$

$\Rightarrow a = (a^x)^{yz}$ $(\because b = a^x)$

$\Rightarrow a = a^{xyz}$

$\Rightarrow a^1 = a^{xyz}$

$\Rightarrow xyz = 1$

20. $7x + 12y = 220$

$\Rightarrow 7x = 220 - 12y$

$x = \dfrac{220-12y}{7} = \dfrac{4(55-3y)}{7}$

It means $55 - 3y$ must be divisible by 7. Since 4 is not divisible by 7.

$\therefore$ at $y = 2, 9, 16$

we get $x = 28, 16, 4$

Thus we have 3 solutions of x, y

$(x, y) = (28, 2), (16, 9)$ and $(4, 16)$

21. $a^x \cdot a^y \cdot a^z = (x+y+z)^{x+y+z}$

$\Rightarrow a^{x+y+z} = (x+y+z)^{(x+y+z)}$

$\Rightarrow a = x+y+z$ ...(1)

$\therefore (x+y+z)^y = a^x = (x+y+z)^x$

$\Rightarrow x = y$

Similarly $y = z$ and $z = x$

$\therefore x = y = z = \dfrac{a}{3}$ [using (1)]

22. Let $\dfrac{x}{a} = \dfrac{y}{b} = \dfrac{z}{c} = k$

$\therefore x = ak, \quad y = bk, \quad z = ck$

$\therefore (x+y+z) = k(a+b+c)$

$\therefore (x+y+z)^2 = k^2(a+b+c)^2$

$\therefore x^2+y^2+z^2+2(xy+yz+zx) = k^2(a+b+c)^2$

$\therefore 2(xy+yz+zx) = k^2(a+b+c)^2 - (x^2+y^2+z^2)$

$\therefore xy+yz+zx = \dfrac{k^2}{2}(a+b+c)^2 - \dfrac{1}{2}(x^2+y^2+z^2)$

$= \dfrac{x^2(a+b+c)^2 - a^2(x^2+y^2+z^2)}{2a^2}$ $\left(\because k = \dfrac{x}{a}\right)$

23. Let x and y be the number of deer and ducks respectively.

$\therefore x + y = 14$ ...(1)

and $4x + 2y = 38$ ...(2)

($\because$ A deer has 4 legs and a duck has 2 legs)

By solving the above two Eq. (1) and (2), we get

$x = 5$ and $y = 9$

Thus, the number of deer is 5.

Alternatively: Assume that there are only ducks (because a duck has less number of legs than that of deer). Hence, there must be $9 \times 2 = 2 = 18$ legs, but in this way there are 10 legs $(= 28 - 18)$ more.

So, there must be some deer which fulfill this gap. Now this difference of 10 legs is compensated by 5 deer because a deer has 2 extra legs (*i.e.*, 2 more legs than a duck has).

Hence, there are 5 deer and $14 - 5 = 9$ ducks.

In short: Step 1. $2 \times 14 = 28$

Step 2. $38 - 28 = 10$

Step 3. $10 \div 2 = 5$

Step 4. $14 - 5 = 9$

Hence, there were 5 deer and 9 ducks.

Alternatively: Going through options. First of all option (d) is ruled out. Now we have to check just 3 options. Again we can leave option (b) and (c) also.

So, we can check the option (a).

(14) heads $\quad [5 \times 4 = 20,\ 9 \times 2 = 18] \quad$ (38) legs

24. Going through options, we find that option (d) is correct *i.e.*,

(600) No. of vehicles $\quad [200 \times 2 = 400,\ 400 \times 4 = 1600] \quad$ (2000) No. of tyres

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively:

Step 1. $2 \times 600 = 1200$

($2 \rightarrow$ number of tyres in two wheelers)

Step 2. $2000 - 1200 = 800$

Step 3. $800 \div 2 = 400 \rightarrow$ number of 4 wheelers

Step 4. $600 - 400 = 200 \rightarrow$ number of 2 wheelers

25. Go through options. Let us consider option (d).

(125) $\begin{bmatrix} 100 \times 5 = 500 \\ 25 \times 3 = 75 \end{bmatrix}$ (575)

No. of raths — No. of horses

Alternatively:

Step 1. $3 \times 125 = 375$ → Number of horses in a rath carried by 3 horses

Step 2. $575 - 375 = 200$

Step 3. $200 \div 2 = 100$ → Number of extra horses in a rath carried by 5 horses.

Step 4. $125 - 100 = 25$

$\therefore$ Number of raths of Kaurav = 100

Number of raths of allied army of Kaurav = 25

26. Let us assume option (a) is correct

then the number of coolers $= \frac{150000}{3000} = 50$

$\therefore$ the number of coolers = 50

and the number of fans = 40 (= 90 − 50)

Now (90) $\begin{bmatrix} 50 \times 4 = 200 \\ 40 \times 3 = 120 \end{bmatrix}$ (320)

Thus, the assumed option (a) is correct.

Alternatively: Step 1. $3 \times 90 = 270$

Step 2. $320 - 270 = 50$

Step 3. $50 \div 1 = 50$

Step 4. $90 - 50 = 40$

Hence, number of fans = 40

and number of coolers = 50

$\therefore$ Cost of coolers = $50 \times 3000 = 150000$

27. Let us assume option (c), then

(90) $\begin{bmatrix} 40 \times 2 = 80 \rightarrow 80 \times 10 \\ 50 \times 3 = 150 \rightarrow 150 \times 15 \end{bmatrix}$ $\begin{matrix} 800 \\ 2250 \end{matrix}$ (3050)

Hence, assumed option (c) is correct.

Alternatively: Per hour expenditure in fuel for Sukhoi

$= 2 \times 10 = \$20$

and per hour expenditure in fuel for Mig-21 $= 3 \times 15 = \$45$

Now, Step 1. $90 \times 20 = 1800$

Step 2. $3050 - 1800 = 1250$

Step 3. $1250 \div 25 = 50$ $(25 = 45 - 20)$

Step 4. $90 - 50 = 40$

Hence, the number of Sukhoi is 40.

28. Step 1. $20 \times 7 = 140$

Step 2. $176 - 140 = 36$

Step 3. $36 \div 3 = 12 \rightarrow$ weight of mangoes, initially

Step 4. $20 - 12 = 8 \rightarrow$ weight of apples, initially

$\therefore$ Number of mangoes $= 12 \times 10 = 120$

and Number of apples $= 8 \times 7 = 56$

Again, since she is left with 13 kg of mangoes and apples containing 121 fruits $(176 - 55 = 121)$

$\therefore$ Step 1. $13 \times 7 = 91$

Step 2. $121 - 91 = 30$

Step 3. $30 \div 3 = 10 \rightarrow$ weight of mangoes

Step 4. $13 - 10 = 3 \rightarrow$ weight of apples

Thus, the number of apples left with vendor $= 3 \times 7 = 21$.

Alternatively: In the first instance option (c) is ruled out since, $176 - 55 = 121$ and $121 - 80 = 41$

$$\frac{80}{7} + \frac{41}{10} \neq 13$$

Again $\frac{35}{7} + \frac{86}{10} \neq 13$ kg, option (b) is wrong.

Once again $\frac{21}{7} + \frac{100}{10} = 13$ kg

Hence, option (a) is correct.

29. Since we know that Ritika has purchased 2 kg mangoes and 5 kg apples. Thus, she has spent $(2 \times 35 + 5 \times 40) =$ Rs. 270.

30.

	Mangoes	Apples
SP	35	40
CP	30	30
New SP	40	35

Therefore, $CP = 30 \times 10 + 30 \times 3 = 390$

and $\text{New SP} = 40 \times 10 + 35 \times 3 = 505$

$\therefore$ $\text{Profit} = 505 - 390 = 115$

and $\text{Profit percentage} = \frac{115}{390} \times 100 = 29.48\%$

31. Solving with the help of options: In this type of questions we start with least valued options and tend towards higher valued option.

Option (a): If we take 4 coins of Re 1, then

$(5 \times 1) + (2 \times 21) = 47 \neq 44$ $(48 - 4 = 44)$

$5 \times 2 + 2 \times 20 = 50 \neq 44$ and $(26 - 4 = 22)$

Thus, we need to move further since the value of money is exceeding.

Option (b): If we take 5 coins of Re 1, then

$5 \times 1 + 2 \times 20 = 45 \neq 43$ $(43 = 48 - 5)$

$5 \times 2 + 2 \times 19 = 48 \neq 43$ and $(21 = 26 - 5)$

Option (c): If we take 7 coins of Re 1, then

$5 \times 1 + 2 \times 18 = 41 = 41$ $\begin{cases} (48 - 7 = 41) \\ \text{and } (26 - 7 = 19) \end{cases}$

Thus, the option (c) is correct.

Alternatively:

$5a + 2b + c = 48$ — $a \rightarrow$ Rs. 5 coin

$a + b + c = 26$ — $b \rightarrow$ Rs. 2 coin

$4a + b = 22$ — $c \rightarrow$ Re. 1 coin

$(a, b) \rightarrow (c)$

$(1, 18) \rightarrow 7$

$(2, 14) \rightarrow 10$

$(3, 10) \rightarrow 13$

$(4, 6) \rightarrow 16$

$(5, 2) \rightarrow 19$

32. Go through options.

Scanned by CamScanner

yoursmahboob.wordpress.com

14 THEORY OF EQUATIONS

As per the past years CAT papers, on an average two-three questions are being asked. The problems of this chapter are not so much difficult to solve. Since this chapter is concerned with secondary level syllabus therefore it is important in JMET, XAT and SNAP etc.

In this chapter we study quadratic equation, inequation and higher degree polynomial expressions.

QUADRATIC EQUATIONS

Quadratic Equation : An equation of the form

$$ax^2 + bx + c = 0 \quad \ldots(i)$$

where $a, b, c \in C$ and $a \neq 0$ is called a quadratic equation.

The numbers a, b, c are called the coefficients of this equation.

A root of the quadratic Eq (i) is a complex number α such that $a\alpha^2 + b\alpha + c = 0$.

Discriminant $D = b^2 - 4ac$

The roots of Eq (i) are given by the formula

$$x = \frac{-b \pm \sqrt{D}}{2a}$$

or

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

Properties of Quadratic Equations

1. A quadratic equation has two and only two roots.
2. A quadratic equation cannot have more than two different roots.
3. If α be a root of the quadratic equation $ax^2 + bx + c = 0$, then $(x - \alpha)$ is a factor of $ax^2 + bx + c = 0$.

NOTE The possible values of x which satisfy the quadratic equation are called the roots of the quadratic equation.

Sum and Product of the roots of a Quadratic Equation

Let α, β be the roots of a quadratic equation $ax^2 + bx + c = 0; a \neq 0$, then

$$\alpha + \beta = \frac{-b}{a} = -\left(\frac{\text{coefficient of } x}{\text{coefficient of } x^2}\right)$$

and

$$\alpha \cdot \beta = \frac{c}{a} = \left(\frac{\text{constant term}}{\text{coefficient of } x^2}\right)$$

Therefore,

- If the two roots α and β be reciprocal to each other, then $a = c$.
- If the two roots α and β be equal in magnitude and opposite in sign, then $b = 0$.

Sign of the Roots

1. The roots α, β are both negative, if $(\alpha + \beta)$ and $\alpha\beta$ are both positive (*i.e.*, if $\frac{-b}{a}$ and $\frac{c}{a}$ are both positive).
2. The roots α, β are both positive, if $\alpha + \beta$ is negative and $\alpha\beta$ is positive (*i.e.*, if $\frac{b}{a}$ is negative and $\frac{c}{a}$ is positive).
3. The roots α, β are of opposite signs, if $\alpha\beta$ is negative (*i.e.*, $\frac{c}{a}$ is negative).

Sign of $(\alpha + \beta)$	Sign of $(\alpha\beta)$	Sign of the α, β
+ve	+ve	α and β are positive
−ve	+ve	α and β are negative
+ve	−ve	α is positive and β is negative if $\alpha > \beta$ (numerically)
−ve	−ve	α is negative and β is positive if $\alpha > \beta$ (numerically)

Scanned by CamScanner

yoursmahboob.wordpress.com

Nature of Roots

For a quadratic equation $ax^2 + bx + c = 0$ where $a, b, c \in R$ and $a \neq 0$ and $D = b^2 - 4ac$.

(i) If $D < 0$, roots are imaginary (ii) If $D \geq 0$ roots are real.

- $D < 0$ (roots are complex with non-zero imaginary part)
- $D = 0$ (roots are rational and equal)
- $D > 0$
  - D is a perfect square → roots are rational and unequal
  - D is not a perfect square → roots are irrational and conjugate pairs

- If $a, b, c \in R$ and $p + iq$ is one root of quadratic equation (where $q \neq 0$) then the other root must be conjugate $p - iq$ and vice-versa. ($p, q \in R$ and $i = \sqrt{-1}$)
- If $a, b, c \in Q$ and $p + \sqrt{q}$ is one root of the quadratic equation, then the other root must be the conjugate $p - \sqrt{q}$ and vice-versa (where p is a rational and $\sqrt{q}$ is a surd).
- If $a = 1$ and $b, c \in I$ and the roots of quadratic equation are rational numbers, then these roots must be integers.
- If the quadratic equation has more than 2 roots (complex numbers), then the equation becomes an identity *i.e.*, $a = b = c = 0$.

Condition for Common Roots

Consider two quadratic equations

$$ax^2 + bx + c = 0 \quad \ldots(i) \quad a \neq 0$$

and

$$a'x^2 + b'x + c' = 0 \quad \ldots(ii) \quad a' \neq 0$$

(A) If one root is common then,

$$(ab' - a'b)(bc' - b'c) = (ca' - c'a)^2$$

(B) If two roots are common then,

$$\frac{a}{a'} = \frac{b}{b'} = \frac{c}{c'}$$

Condition that $ax^2 + bx + c = 0$, is Factorizable into two Linear Factors

When $D \geq 0$, then the equation $ax^2 + bx + c = 0$ is factorizable into two linear factors.

i.e., $ax^2 + bx + c = 0 \Rightarrow (x - \alpha)(x - \beta) = 0$, where α and β are the roots of quadratic equation.

Formation of a Quadratic Equation : Let α, β be the two roots then we can form a quadratic equation as follows:

$x^2 - (\text{sum of roots})\,x + (\text{product of roots}) = 0$

i.e., $x^2 - (\alpha + \beta)x + (\alpha\beta) = 0$

or $(x - \alpha)(x - \beta) = 0$

Graph of a Quadratic Function $ax^2 + bx + c = 0, a \neq 0$

Characteristics of the Function	$b^2 - 4ac < 0$	$b^2 - 4ac = 0$	$b^2 - 4ac > 0$
When a is positive *i.e.*, $a > 0$			
When a is negative *i.e.*, $a < 0$			

- The graph of a quadratic function (expression) is called a parabola. The point at which its direction changes is called its turning point, commonly called the vertex of the parabola.
- The graph of the function is concave upwards when $a > 0$ and concave downwards when $a < 0$.
- If the graph has no points in common with the x-axis, the roots of the equation are imaginary and cannot be determined from the graph.
- If the graph is tangent to the x-axis, the roots are real and equal.

Scanned by CamScanner

yoursmahboob.wordpress.com

- If the graph cuts the x-axis, the roots of the equation will be real and unequal. Their values will be given by the abscissae of the points of intersection of the graph and the x-axis.

QUADRATIC INEQUATIONS

The following properties of inequations will be useful in solving the problems on inequations :

1. Square of any real quantity ≥ 0
2. If a, b, c are three real numbers such that $a \geq b$ then, $a \pm c \geq b \pm c$
3. (i) If a, b, c are three real numbers such that $a \geq b$ and $c > 0$, then $ac \geq bc$.
   (ii) If $a \leq b$ and $c > 0$, then $ac \leq bc$
4. (i) If a, b, c are three real numbers such that $a \geq b$ and $c < 0$, then $ac \leq bc$
   (ii) If $a \leq b$ and $c < 0$, then $ac \geq bc$
5. (i) If $ab > 0$, then a and b are either both positive or both negative.
   (ii) If $ab < 0$, then a and b are of opposite signs, *i.e.*, either $a > 0$ and $b < 0$ or $a < 0$ and $b > 0$.

Formation of a New Quadratic Equation by Changing the Roots of a given Quadratic Equation

Let α, β be the roots of a quadratic equation $ax^2 + bx + c = 0$; then we can form a new quadratic equation as per the following rules.

(a) A quadratic equation whose roots are p more than the roots of the equation $ax^2 + bx + c = 0$ (*i.e.*, the roots are $\alpha + p$ and $\beta + p$).
The required equation is
$$a(x - p)^2 + b(x - p) + c = 0$$

(b) A quadratic equation whose roots are less by p than the roots of the equation $ax^2 + bx + c = 0$, (*i.e.*, the roots are $\alpha - p$ and $\beta - p$)
The required equation is
$$a(x + p)^2 + b(x + p) + c = 0$$

(c) A quadratic equation whose roots are p times the roots of the equation $ax^2 + bx + c = 0$ (*i.e.*, the roots are $p\alpha$ and $p\beta$)
The required equation is $a\left(\frac{x}{p}\right)^2 + b\left(\frac{x}{p}\right) + c = 0$

(d) A quadratic equation whose roots are $1/p$ times the roots of the equation $ax^2 + bx + c = 0$ (*i.e.*, the roots are α / p and β / p)
The required equation is $a(px)^2 + b(px) + c = 0$

(e) A quadratic equation whose roots are the reciprocals of the roots of the equation $ax^2 + bx + c = 0$, (*i.e.*, the roots are $1/\alpha$ and $1/\beta$).
The required equation is $a\left(\frac{1}{x}\right)^2 + b\left(\frac{1}{x}\right) + c = 0$
$$\Rightarrow \quad cx^2 + bx + a = 0$$

(f) A quadratic equation whose roots are the negative of the roots of the equation $ax^2 + bx + c = 0$ (*i.e.*, the roots are $-\alpha$ and $-\beta$)
The required equation is $a(-x)^2 + b(-x) + c = 0$
$$\Rightarrow \quad ax^2 - bx + c = 0$$

(g) A quadratic equation whose roots are the squares of the roots of the equation $ax^2 + bx + c = 0$ (*i.e.*, the roots are α^2 and β^2)
The required equation is $a(\sqrt{x})^2 + b(\sqrt{x}) + c = 0$
$$\Rightarrow \quad ax + b\sqrt{x} + c = 0$$

(h) A quadratic equation whose roots are the cubes of the roots of the equation $ax^2 + bx + c = 0$ (*i.e.*, the roots are α^3 and β^3)
The required equation is $a(x^{1/3})^2 + b(x^{1/3}) + c = 0$
$$\Rightarrow \quad ax^{2/3} + bx^{1/3} + c = 0$$

Maximum or Minimum value of a Quadratic Equation

At $x = -b/2a$ we get the maximum or minimum value of the quadratic expression.

(i) When $a > 0$ (in the equation $ax^2 + bx + c$) the expression gives minimum value $y = \frac{4ac - b^2}{4a}$

(ii) When $a < 0$ (in the equation $ax^2 + bx + c$) the expression gives maximum value $y = \frac{4ac - b^2}{4a}$

QUADRATIC INEQUALITY

By a quadratic inequality we mean an inequality of the following kinds :

(a) $ax^2 + bx + c \geq 0$ (b) $ax^2 + bx + c < 0$

Quadratic inequations can be solved by the following methods

(i) Algebraic method (ii) Method of intervals

(i) Algebraic method : This will be explained by the application of examples.

(ii) Method of intervals :

Step 1. Express the quadratic inequation $ax^2 + bx + c$ whose roots are α and β in the form $(x - \alpha)(x - \beta)$, where $\alpha < \beta$ and $a > 0$.

Step 2. On the number line, the numbers α and β must be arranged in order of increasing magnitude then place the plus sign in the interval to the right of the largest number (*i.e.*, β). In the next interval (from right to left) place the minus sign, then in the next interval plus sign, etc.

The solution of the inequality, *i.e.*, $ax^2 + bx + c \geq 0$ will then consists of the intervals having the plus sign.

$(\alpha < \beta)$

Scanned by CamScanner

yoursmahboob.wordpress.com

The solution of the inequality, *i.e.*, $ax^2+bx+c<0$ will then consists of the intervals having the minus sign.

$(\alpha < \beta)$

Thus, if $(x-\alpha)(x-\beta)>0$, then x lies outside the interval $[\alpha, \beta]$, *i.e.*, $x \in (-\infty, \alpha) \cup (\beta, \infty)$



If $(x-\alpha)(x-\beta) \geq 0$, then x lies on and outside the interval $(-\infty, \alpha] \cup [\beta, \infty)$



If $(x-\alpha)(x-\beta)<0$, then x lies inside the interval (α, β), *i.e.*, $x \in (\alpha, \beta)$



If $(x-\alpha)(x-\beta) \leq 0$, then x lies in the interval $[\alpha, \beta]$, *i.e.*, $x \in [\alpha, \beta]$



Quadratic fraction (or Quadratic Rational Expression) :

An expression of the form $\frac{a_1x^2+b_1x+c}{a_2x^2+b_2x+c}$ is known as Quadratic fraction (or rational expression)

VALUES OF A RATIONAL EXPRESSION

Step 1. Equate the rational expression to y.

Step 2. Obtain a quadratic equation in x by simplifying the expression in step 1.

Step 3. Obtain the discriminant (D) of the quadratic equation in step 2.

Step 4. Put $D \geq 0$ and solve the inequation for y. The values of y so obtained determined the set of values attained by the given rational expression.

Solution of Rational Inequalities

Let $P(x)=a_1x^2+b_1x+c$ and $Q(x)=a_2x^2+b_2x+c$, then

$$\frac{P(x)}{Q(x)}>0, \quad \frac{P(x)}{Q(x)} \geq 0, \quad \frac{P(x)}{Q(x)}<0 \quad \text{and} \quad \frac{P(x)}{Q(x)} \leq 0$$

are known as rational algebraic inequations.

To obtain the range of values of solution set we apply the following algorithm.

Step 1. Factorize $P(x)$ and $Q(x)$ into linear factors, *i.e.*, in the form of $\frac{(x-\alpha_1)(x-\beta_1)}{(x-\alpha_2)(x-\beta_2)}$, where the coefficient of x must be positive in all factors.

Step 2. On the number line represent $\alpha_1, \beta_1, \alpha_2$ and β_2 in the increasing order which divide the number line into $(4+1)=5$ regions.

[If there are $\alpha_1, \alpha_2, ..., \alpha_m$, and $\beta_1, \beta_2, \beta_3, ..., \beta_n$ roots then the number line is being divided into $(m+n+1)$ regions]

Step 3. In the right region the expression $\frac{P(x)}{Q(x)}$ bears positive sign and in other regions the expression bears alternate positive and negative signs.

(Note the greatest value of root will be written in the rightmost)

Sign of Quadratic Expression ax^2+bx+c

As we know that if α, β are the roots of the corresponding quadratic equation, then for $x=\alpha$ and $x=\beta$, the value of the expression is equal to zero. *i.e.*, $f(x)=ax^2+bx+c=0$.

But for other real values of x (*i.e.*, except α and β) the expression is either less than zero or greater than zero, *i.e.*, $f(x)<0$ or $f(x)>0$.

Thus the sign of $ax^2+bx+c, x \in R$, is determined by the following rules :

1. If $D<0$ *i.e.*, α and β are imaginary, then
   $ax^2+bx+c>0$, if $a>0$
   and $ax^2+bx+c<0$, if $a<0$
2. If $D=0$ *i.e.*, α and β are real and equal, then
   $ax^2+bx+c \geq 0$, if $a>0$
   and $ax^2+bx+c \leq 0$, if $a<0$
3. If $D>0$ *i.e.*, α and β are real unequal $(\alpha<\beta)$, then the sign of the expression ax^2+bx+c, $x \in R$ is determined as follows :



POSITION OF ROOTS OF A QUADRATIC EQUATION WITH RESPECT TO ONE OR TWO REAL NUMBERS

Let $f(x)=ax^2+bx+c$, where $a, b, c \in R, a \neq 0$. Let α, β, $(\alpha<\beta)$ be the roots of the corresponding quadratic equation. Let $k, k_1, k_2 \in R$ and $k_1<k_2$.

1. **Position of roots with respect to one real number:**
   (a) If both the roots of $f(x)=0$ are greater than k, then
   (i) $D \geq 0$
   (ii) $af(k)>0$
   (iii) $k<-\frac{b}{2a}$



   (b) If both the roots of $f(x)=0$ are less than k, then
   (i) $D \geq 0$
   (ii) $af(k)>0$
   (iii) $k>-\frac{b}{2a}$



   (c) If one root is less than k and other is greater than k, then
   (i) $D>0$
   (ii) $af(k)<0$



2. **Position of roots with respect to two real numbers:**
   (a) If exactly one root of $f(x)=0$ lies in the interval (k_1, k_2), then
   (i) $D>0$
   (ii) $f(k_1) \cdot f(k_2)<0$



Scanned by CamScanner

yoursmahboob.wordpress.com

(b) If both roots of $f(x)=0$ lie between k_1 and k_2, then



(i) $D \geq 0$

(ii) $af(k_1)>0, af(k_2)>0$

(iii) $k_1 < -\frac{b}{2a} < k_2$

(c) If k_1 and k_2 lie between the roots of $f(x)=0$, then



(i) $D \geq 0$

(ii) $af(k_1)<0, af(k_2)<0$

POLYNOMIAL OF HIGHER DEGREE

Let $a_0, a_1, a_2, ..., a_n$ be real numbers and x is a real variable. Then $f(x)=a_0+a_1x+a_2x^2+...a_nx^n$ is called a real polynomial of degree n.

e.g., $ax^2+bx+c=0$ is a quadratic polynomial of degree 2.

and $ax^3+bx^2+cx+d=0$ is a cubic polynomial of degree 3.

and $ax^4+bx^3+cx^2+dx+e=0$ is a biquadratic polynomial of degree 4.

NOTE If $a_0, a_1, a_2, ..., a_n$ be complex numbers and x is a varying complex number, then $f(x)=a_0+a_1x+a_2x^2+...a_nx^n$ is called a complex polynomial.

Roots of a polynomial (expression) : The values of the variable satisfying the given equation are called its roots *i.e.*, $x=\alpha$ is a root of the equation $f(x)=0$

if $f(\alpha)=0$.

NOTE The real roots of an equation $f(x) = 0$ are the x-coordinates of the points through which the curve $y = f(x)$ passes the x-axis.

In the given graph α, β and γ are the roots of a particular cubic polynomial. Simply when $y=0$, then the corresponding values of x are called the roots (or zeros) of the polynomial expression.



- An equation of degree n has n roots (real or imaginary)
- An odd degree equation has at least one real root having sign opposite to that of its last term, provided that the coefficient of highest degree term is positive.
- An even degree equation whose constant term is negative and the coefficient of highest degree term is positive, has at least two real roots, one positive and one negative.
- Surd and imaginary roots always occur in conjugate pairs.

i.e., if $a+\sqrt{b}$ is a root of an equation, then $a-\sqrt{b}$ is also a root of the equation

Similarly if $a+ib$ is a root of an equation, then $a-ib$ is also a root of the given equation.

Sign Rules

1. The maximum number of positive real roots of a polynomial equation $f(x)=0$ is the number of changes of signs from positive to negative and negative to positive in $f(x)$. *e.g.*,

   Let an equation be

   $$ax^3+bx^2-cx+d=0$$

   $\therefore$ The signs of the various terms are

   $$+ \; + \; - \; +$$

   Clearly there are two changes of sign in the given expression. So, the given equation has at most two positive real roots.
2. The maximum number of negative real roots of the polynomial equation $f(x)=0$ is the number of changes from positive to negative and negative to positive in $f(-x)$.

e.g., Let $f(x)=ax^4-bx^3+cx^2+dx-e=0$

$\therefore \quad f(-x)=ax^4+bx^3+cx^2-dx-e=0$

The signs of various terms in $f(-x)$ are :

$$+ \; + \; + \; - \; -$$

Clearly there is only one change of sign. So, the given equation has at most one negative real solution (or root)

RELATION BETWEEN ROOTS AND COEFFICIENTS

If $f(x)=a_0x^n+a_1x^{n-1}+a_2x^{n-2}+...a_{n-1}x+a_n=0$ and $\alpha_1, \alpha_2, \alpha_3, ..., \alpha_n$ be the roots of the polynomial, then

$$S_1=\alpha_1+\alpha_2+\alpha_3+...\alpha_n=\Sigma\alpha_i=-\frac{a_1}{a_0}$$

$$S_2=\alpha_1\alpha_2+\alpha_1\alpha_3+...=\sum_{i\neq j}\alpha_i\alpha_j=(-1)^2\frac{a_2}{a_0}$$

$$S_3=\alpha_1\alpha_2\alpha_3+\alpha_2\alpha_3\alpha_4+...=\sum_{i\neq j\neq k}\alpha_i\alpha_j\alpha_k=(-1)^3\frac{a_3}{a_0}$$

$$\vdots \quad \vdots \quad \vdots \quad \vdots$$

Similarly

$$S_n=\alpha_1\alpha_2\alpha_3...\alpha_n=(-1)^n\frac{a_n}{a_0}=(-1)^n\frac{a_n}{a_0}$$

$a_n \rightarrow$ constant term

Hence for **quadratic equation** $ax^2+bx+c=0$, having the roots α and β, then

$$\alpha+\beta=\frac{-b}{a} \quad \text{and} \quad \alpha\beta=\frac{c}{a}$$

and for **cubic equation** $ax^3+bx^2+cx+d=0$, having roots α, β and γ, then

$$\alpha+\beta+\gamma=\frac{-b}{a},$$

Scanned by CamScanner

yousmahboob.wordpress.com

$$\alpha\beta+\beta\gamma+\gamma\alpha=(-1)^2\frac{c}{a}=\frac{c}{a}$$

and $$\alpha\beta\gamma=(-1)^3\frac{d}{a}=\frac{-d}{a}$$

Similarly for **biquadratic equation**

$$ax^4+bx^3+cx^2+dx+e=0$$

having roots $\alpha, \beta, \gamma, \delta$, then

$$S_1=\alpha+\beta+\gamma+\delta=\frac{-b}{a}$$

$$S_2=\alpha\beta+\beta\gamma+\gamma\delta+\alpha\gamma+\alpha\delta+\beta\delta$$
$$=(-1)^2\frac{c}{a}=\frac{c}{a}$$

or $$S_3=\alpha\beta\gamma+\beta\gamma\delta+\gamma\delta\alpha+\alpha\beta\delta=(-1)^3\frac{d}{a}=-\frac{d}{a}$$

and $$S_4=\alpha\beta\gamma\delta=(-1)^4\frac{e}{a}=\frac{e}{a}$$

Formation of a Polynomial Equation from given Roots

If $\alpha_1, \alpha_2, \ldots, \alpha_n$ are the roots of an nth degree equation, then the equation is

$$x^n-S_1x^{n-1}+S_2x^{n-2}-S_3x^{n-3}+\ldots+(-1)^nS_n=0$$

where S_k $(k=1,2,3,\ldots n)$ denotes the sum of the products of roots taken k at a time.

Formation of a Quadratic Equation

$$x^2-S_1x+S_2=0$$

$$\Rightarrow \quad x^2-(\alpha+\beta)x+(\alpha\beta)=0$$

Formation of a Cubic Equation

$$x^3-S_1x^2+S_2x-S_3=0$$

i.e., $$x^3-(\alpha+\beta+\gamma)x^2+(\alpha\beta+\beta\gamma+\gamma\alpha)x-\alpha\beta\gamma=0$$

Formation of a Biquadratic Equation

$$x^4-S_1x^3+S_2x^2-S_3x+S_4=0$$

i.e., $$x^4-(\alpha+\beta+\gamma+\delta)x^3+(\alpha\beta+\beta\gamma+\gamma\delta+\alpha\delta+\beta\delta+\alpha\gamma)x^2-(\alpha\beta\gamma+\alpha\beta\delta+\beta\gamma\delta+\gamma\delta\alpha)x+\alpha\beta\gamma\delta=0$$

METHODS OF SOLVING THE QUADRATIC EQUATIONS

(1) By factorization method
(2) By Sridharacharya's method

(1) By factorization method : If ax^2+bx+c can be factorized as $(x-\alpha)(x-\beta)$, then $ax^2+bx+c=0$ is equivalent to $(x-\alpha)(x-\beta)=0$

Thus, $$(x-\alpha)(x-\beta)=0$$

$\Rightarrow$ $$(x-\alpha)=0 \quad \text{or} \quad (x-\beta)=0$$

i.e., $$x=\alpha \quad \text{or} \quad x=\beta$$

Here α and β are called the roots of the equation $ax^2+bx+c=0$.

The following steps are required to solve the quadratic equation by factorization :

(1) Clear fractions and brackets, if necessary.
(2) Transfer all the terms to LHS and combine like terms.
(3) Write the equation in the standard form, *i.e.,* $ax^2+bx+c=0$
(4) Factorize the LHS.
(5) Put each factor equal to zero and solve.

(2) By Sridharacharya's method : Write the equation in the standard form $ax^2+bx+c=0$, then the roots are

$$\alpha=\frac{-b+\sqrt{b^2-4ac}}{2a}$$

and $$\beta=\frac{-b-\sqrt{b^2-4ac}}{2a}; \qquad b^2-4ac=D$$

EXAMPLE 1 *Which of the following are quadratic equations?*

(a) $3x^2-2=0$ *(b)* $3x^2-2x+4=\frac{1}{3}(9x^2-x+3)$

(c) $x^3-6x=x^2-3$ *(d)* $x+\frac{1}{x}=4$

SOLUTION (a) and (d) are only two quadratic equations. On simplifying (b) gives a linear equation and (c) is a cubic equation.

EXAMPLE 2 *Determine whether the given values are solutions (i.e., roots) of the equation or not.*

$$3x^2+5x+2=0, \quad x=3, x=-1$$

SOLUTION On substituting $x=3$, we get

$$3(3)^2+5(3)+2=44\neq 0$$

Therefore $x=3$ is not a solution of the given equation.

Again, substitute $x=-1$, we get

$$3(-1)^2+5(-1)+2=0$$

Therefore $x=-1$ is the solution (*i.e.,* root) of the given equation.

EXAMPLE 3 *Solve the following equation by factorization.*

$$6x^2-x-2=0$$

SOLUTION

$$6x^2-x-2=0$$

$\Rightarrow$ $$6x^2-4x+3x-2=0$$

$\Rightarrow$ $$2x(3x-2)+1(3x-2)=0$$

$\Rightarrow$ $$(3x-2)(2x+1)=0$$

Either $(2x+1)=0$ or $(3x-2)=0$

$\Rightarrow$ $$x=-\frac{1}{2} \quad \text{or} \quad x=\frac{2}{3}$$

$$x=-\frac{1}{2}, \frac{2}{3}$$

EXAMPLE 4 *Find the value of K for which $x=2$ is a root of the equation $3x^2-2Kx+5=0$.*

SOLUTION If $x=2$ is a root of the given equation, then $x=2$ must satisfy it.

$\therefore$ $$3(2)^2-2K(2)+5=0$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$12 - 4K + 5 = 0$$

$$\Rightarrow \quad -4K = -17 \Rightarrow K = \frac{17}{4}$$

$$\Rightarrow$$

EXAMPLE 5 *Solve the following equation by using the formula :*

$$8x - 2x^2 = 5$$

SOLUTION $8x - 2x^2 = 5 \Rightarrow 2x^2 - 8x + 5 = 0$

Here $a = 2, \quad b = -8 \quad \text{and} \quad c = 5$

Substituting the values of a, b and c in the formula

$$\alpha = \frac{-b + \sqrt{b^2 - 4ac}}{2a} \quad \text{and} \quad \beta = \frac{-b - \sqrt{b^2 - 4ac}}{2a}$$

$$\alpha = \frac{8 + \sqrt{64 - 40}}{4} \quad \text{and} \quad \beta = \frac{8 - \sqrt{64 - 40}}{4}$$

$$\alpha = \frac{8 + 2\sqrt{6}}{4} \quad \text{and} \quad \beta = \frac{8 - 2\sqrt{6}}{4}$$

$$\alpha = \frac{4 + \sqrt{6}}{2} \quad \text{and} \quad \beta = \frac{4 - \sqrt{6}}{2}$$

NOTE The values of α and β can be interchanged.

EXAMPLE 6 *Write the discriminant of the following quadratic equations and mention the nature of the root :*

(a) $9x^2 - 6x + 1 = 0$ *(b)* $x^2 + x - 12 = 0$

(c) $4\sqrt{3}x^2 + 5x + 2\sqrt{3} = 0$

SOLUTION (a) $D = b^2 - 4ac = (-6)^2 - 4(9)(1) = 0$

Since $D = 0$, therefore the roots are real and equal.

(b) $D = b^2 - 4ac = (1)^2 - 4 \times 1 \times (-12) = 49$

Since $D > 0$ and D is a perfect square, therefore the roots are real, unequal and rational.

(c) $D = b^2 - 4ac = (5)^2 - 4(4\sqrt{3}) \times (2\sqrt{3}) = -71$

Since $D < 0$, therefore the roots are complex (*i. e.*, no real roots).

SOLUTIONS OF EQUATIONS REDUCIBLE TO QUADRATIC FORM

Equation which are not quadratic at a glance but can be reduced to quadratic equations by suitable transformations. Some of the common types are :

Type 1. $ax^4 + bx^2 + c = 0.$

This can be reduced to a quadratic equation by substituting $x^2 = y$. *i.e.*, $ay^2 + by + c = 0$

Tpye 2. $px + \frac{q}{x} = r,$

$$p(x - a) + \frac{q}{(x - b)} = r$$

Multiply both sides by the LCD of LHS to get a quadratic equation :

$$px + \frac{q}{x} = r \quad \Rightarrow \quad px^2 - rx + q = 0$$

and $$p(x - a) + \frac{q}{(x - b)} = r$$

$$\Rightarrow \quad p(x - a)(x - b) - r(x - b) + q = 0$$

Type 3. $\sqrt{a - x^2} = bx + c$

Square both sides and simplify.

i.e., $a - x^2 = b^2x^2 + 2bcx + c^2$

$$\Rightarrow \quad (1 + b^2)x^2 + 2bcx + (c^2 - a) = 0$$

Type 4. $\sqrt{ax + b} + \sqrt{cx + d} = e$

Transform one of the radicals to RHS and square $\sqrt{ax + b} = e - \sqrt{cx + d}$, such equations may require squaring and your solution must satisfy $ax + b \geq 0$ and $cx + d \geq 0$

Type 5. $a\left(x^2 + \frac{1}{x^2}\right) + b\left(x + \frac{1}{x}\right) + c = 0$

For this type of equations we use the following identity

$$x^2 + \frac{1}{x^2} = \left(x + \frac{1}{x}\right)^2 - 2$$

Thus $a\left[\left(x + \frac{1}{x}\right)^2 - 2\right] + b\left(x + \frac{1}{x}\right) + c = 0$

Now put $x + \frac{1}{x} = y$ to get a quadratic equation *i.e.*, $ay^2 + by + (c - 2a) = 0$

Type 6. $a\left(x^2 + \frac{1}{x^2}\right) + b\left(x - \frac{1}{x}\right) + c = 0$

Use the following identity.

$$x^2 + \frac{1}{x^2} = \left(x - \frac{1}{x}\right)^2 + 2$$

Thus, $a\left[\left(x - \frac{1}{x}\right)^2 + 2\right] + b\left(x - \frac{1}{x}\right) + c = 0$, put $x - \frac{1}{x} = y$, to get a quadratic equation in y.

i.e., $ay^2 + by + (c - 2a) = 0$

Type 7. (i) $x^{2a} + x^a + b = 0$ (ii) $x^a + x^{-a} = b$

Put $x^a = y$ to get a quadratic equation in y,

i.e., (i) $y^2 + y + b = 0$ (ii) $y + \frac{1}{y} = b$

NOTE In all the equations involving radical signs, the answer must be checked by substituting in the original equation.

Type 8. $(x + a)(x + b)(x + c)(x + d) + k = 0.$

When sum of the quantities a, b, c, d is equal to the sum of the other two, can be solved as shown in example 16.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 7 *Solve for* y : $9y^4 - 29y^2 + 20 = 0$.

SOLUTION $9y^4 - 29y^2 + 20 = 0$

Put $y^2 = x$.

$$9x^2 - 29x + 20 = 0$$
$$\Rightarrow \quad 9x^2 - 20x - 9x + 20 = 0$$
$$\Rightarrow \quad (x-1)(9x-20) = 0$$
$$\Rightarrow \quad x = 1 \quad \text{or} \quad x = \frac{20}{9}$$
$$\Rightarrow \quad y^2 = 1 \quad \text{or} \quad y^2 = \frac{20}{9}$$
$$\Rightarrow \quad y = \pm 1 \quad \text{and} \quad y = \pm \frac{2\sqrt{5}}{3}$$

EXAMPLE 8 *Solve for* x : $x^6 - 26x^3 - 27 = 0$.

SOLUTION $x^6 - 26x^3 - 27 = 0$

Let $x^3 = y$

then, $y^2 - 26y - 27 = 0$

$\Rightarrow \quad y^2 - 27y + y - 27 = 0$

$\Rightarrow \quad (y+1)(y-27) = 0$

$\Rightarrow \quad y = -1 \quad \text{or} \quad y = 27$

$\Rightarrow \quad x^3 = -1 \quad \text{or} \quad x^3 = 27$

$\Rightarrow \quad x = -1 \quad \text{or} \quad x = 3$

EXAMPLE 9 *Solve* : $2x - \frac{3}{x} = 5$

SOLUTION $2x - \frac{3}{x} = 5$

$\Rightarrow \quad 2x^2 - 3 = 5x$

$\Rightarrow \quad (2x+1)(x-3) = 0$

$\Rightarrow \quad x = -\frac{1}{2} \quad \text{or} \quad x = 3$

EXAMPLE 10 *Solve* $\sqrt{2x+9} + x = 13$

SOLUTION $\sqrt{2x+9} + x = 13$

$\Rightarrow \quad \sqrt{2x+9} = 13 - x$

Squaring both sides

$$2x + 9 = (13-x)^2$$
$$\Rightarrow \quad x^2 - 28x + 160 = 0$$
$$\Rightarrow \quad (x-8)(x-20) = 0$$
$$\Rightarrow \quad x = 8, \quad x = 20$$

NOTE Here we must have $2x + 9 \geq 0$ Thus for $x = 8, \sqrt{2x+9} > 0$
Also for $x = 20, \sqrt{2x+9} > 0$.
$\therefore$ Both the values satisfy the condition.

EXAMPLE 11 *Solve* $\sqrt{2x+9} - \sqrt{x-4} = 3$

SOLUTION $\sqrt{2x+9} - \sqrt{x-4} = 3$

$\Rightarrow \quad \sqrt{2x+9} = 3 + \sqrt{x-4}$

Squaring both sides and simplifying, we get

$$x + 4 = 6\sqrt{x-4}$$

Again squaring both sides,

$$(x+4)^2 = 36(x-4)$$
$$\Rightarrow \quad x^2 - 28x + 160 = 0$$
$$\Rightarrow \quad (x-8)(x-20) = 0$$
$$\Rightarrow \quad x = 8, \quad x = 20$$

Verification: $2x + 9 \geq 0$ and $x - 4 \geq 0$

$$\Rightarrow \quad x \geq \frac{-9}{2} \quad \text{and} \quad x \geq 4$$

Since the values $x = 8$ and 20 satisfy both these conditions

$$\therefore \quad x = 8, \quad x = 20$$

EXAMPLE 12 *Solve for* x : $2\left(x^2 + \frac{1}{x^2}\right) - 9\left(x + \frac{1}{x}\right) + 14 = 0$

SOLUTION Put $x^2 + \frac{1}{x^2} = \left(x + \frac{1}{x}\right)^2 - 2$

$$\therefore \quad 2\left(x^2 + \frac{1}{x^2}\right) - 9\left(x + \frac{1}{x}\right) + 14 = 0$$
$$\Rightarrow \quad 2\left[\left(x + \frac{1}{x}\right)^2 - 2\right] - 9\left(x + \frac{1}{x}\right) + 14 = 0$$

Substitute $x + \frac{1}{x} = y$

$$\therefore \quad 2(y^2 - 2) - 9y + 14 = 0$$
$$\Rightarrow \quad 2y^2 - 4 - 9y + 14 = 0$$
$$\Rightarrow \quad (y-2)(2y-5) = 0$$
$$\Rightarrow \quad y = 2 \quad \text{or} \quad y = \frac{5}{2}$$

Since $x + \frac{1}{x} = 2 \Rightarrow x^2 - 2x + 1 = 0$

$$\Rightarrow \quad (x-1)^2 = 0 \Rightarrow x = 1$$

Also, $y = \frac{5}{2} \Rightarrow x + \frac{1}{x} = \frac{5}{2}$

$$\Rightarrow \quad 2x^2 - 5x + 2 = 0$$
$$\Rightarrow \quad x = 2 \quad \text{or} \quad x = \frac{1}{2}$$
$$\therefore \quad x = \frac{1}{2}, 1, 2$$

EXAMPLE 13 *Solve* $6\left(x^2 + \frac{1}{x^2}\right) - 25\left(x - \frac{1}{x}\right) + 12 = 0$

SOLUTION Put $x^2 + \frac{1}{x^2} = \left(x - \frac{1}{x}\right)^2 + 2$

$$\therefore \quad 6\left[\left(x - \frac{1}{x}\right)^2 + 2\right] - 25\left(x - \frac{1}{x}\right) + 12 = 0$$

Let $x - \frac{1}{x} = y$

$$\Rightarrow \quad 6(y^2 + 2) - 25y + 12 = 0$$
$$\Rightarrow \quad y = \frac{3}{2}, \quad y = \frac{8}{3}$$

Since $y = x - \frac{1}{x}$ and $x - \frac{1}{x} = \frac{8}{3}$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore \quad x - \frac{1}{x} = \frac{3}{2}$ and $x = -\frac{1}{3}, \quad x = 3$

$\Rightarrow \quad x = -\frac{1}{2}$ and $x = 2$

$\therefore \quad x = -\frac{1}{3}, -\frac{1}{2}, 2, 3$

EXAMPLE 14 *Solve for*

$x: \sqrt{x^2 + x - 6} - x + 2 = \sqrt{x^2 - 7x + 10}, \quad x \in R$

SOLUTION $\sqrt{x^2 + x - 6} - x + 2 = \sqrt{x^2 - 7x + 10}$

$\sqrt{(x+3)(x-2)} - (x-2) = \sqrt{(x-5)(x-2)}$

$\Rightarrow \sqrt{(x-2)}[\sqrt{(x+3)} - \sqrt{(x-2)} - \sqrt{(x-5)}] = 0$

Either $\sqrt{(x-2)} = 0 \Rightarrow x = 2$

or $\sqrt{(x+3)} - \sqrt{(x-2)} - \sqrt{(x-5)} = 0$

$\Rightarrow \sqrt{(x+3)} - \sqrt{(x-2)} = \sqrt{x-5}$

Squaring both sides

$x^2 + 12x + 36 = 4(x^2 + x - 6)$

$\Rightarrow \quad x = 6, \quad x = -\frac{10}{3}$

Since the equation involves radical therefore substituting $x = 2, 6$ and $-\frac{10}{3}$ in the original equation, we find that $x = -\frac{10}{3}$ does not satisfy the equation.

$\therefore \quad x = 2, 6$

EXAMPLE 15 *Solve for* $x: 3^{x+2} + 3^{-x} = 10$

SOLUTION $3^{x+2} + 3^{-x} - 10 = 0$

$\Rightarrow \quad 3^x \cdot 3^2 + \frac{1}{3^x} - 10 = 0$

Let $3^x = y \Rightarrow 9y + \frac{1}{y} - 10 = 0$

$\Rightarrow \quad 9y^2 - 10y + 1 = 0$

$\Rightarrow \quad (9y - 1)(y - 1) = 0 \Rightarrow y = \frac{1}{9}$ or $y = 1$

When $y = \frac{1}{9} \Rightarrow 3^x = \frac{1}{3^2}$

$\Rightarrow \quad x = -2$

when $y = 1 \Rightarrow 3^x = 1$

$\Rightarrow \quad x = 0$

$\therefore \quad x = -2, 0$

EXAMPLE 16 *Solve for* $x: (x+1)(x+2)(x+3)(x+4) = 24$

SOLUTION $(x+1)(x+2)(x+3)(x+4) = 24$

$\Rightarrow \quad [(x+1)(x+4)][(x+2)(x+3)] = 24$

$\Rightarrow \quad (x^2 + 5x + 4)(x^2 + 5x + 6) = 24$

Let $x^2 + 5x = y$

$\therefore \quad (y+4)(y+6) = 24$

$\Rightarrow \quad y^2 + 10y = 0$

$\Rightarrow \quad y = 0$ and $y = -10$

Now, $y = x^2 + 5x$

When $y = 0, x^2 + 5x = 0 \Rightarrow x = 0, x = -5$

Again when $y = -10, x^2 + 5x = -10$

$\Rightarrow \quad x^2 + 5x + 10 = 0$

Since LHS expression cannot be factorized, therefore we should use the formula for finding the value of x.

Here $D = b^2 - 4ac$

$= 25 - 4 \times 1 \times 10 = -15$

Since $D < 0$, the equation $x^2 + 5x + 10 = 0$ has no real solution

$\therefore \quad x = 0, -5$

EXAMPLE 17 *Find the sum and product of the roots of the quadratic equation :*

$3x^2 + 2x - 1 = 0$

SOLUTION Let α, β be the two roots of the equation then,

$\alpha + \beta = -\frac{b}{a} = -\frac{2}{3}$

and $\alpha\beta = \frac{c}{a} = -\frac{1}{3}$

EXAMPLE 18 *Find the quadratic equation whose roots are, –3, 5*

SOLUTION **Method (I):**

$\alpha + \beta = -3 + 5 = 2$

and $\alpha\beta = -3 \times 5 = -15$

$\therefore$ The required quadratic equation

$x^2 - (\alpha + \beta)x + (\alpha\beta) = 0$

$\Rightarrow \quad x^2 - (2)x + (-15) = 0$

$\Rightarrow \quad x^2 - 2x - 15 = 0$

Method (II): Let $\alpha = -3$ and $\beta = 5$, then the require equation

$(x - \alpha)(x - \beta) = 0$

$\Rightarrow \quad (x + 3)(x - 5) = 0$

$\Rightarrow \quad x^2 - 2x - 15 = 0$

EXAMPLE 19 *If* α *and* β *are the roots of the equation* $ax^2 + bx + c = 0$, *find the values of the following expressions in terms of a, b and c*

(a) $\alpha^2 + \beta^2$ *(b)* $\frac{1}{\alpha} + \frac{1}{\beta}$ *(c)* $\alpha^4 - \beta^4$

SOLUTION (a) Let $ax^2 + bx + c = 0$ and α, β be the roots of th equation, then

$\alpha + \beta = -\frac{b}{a}, \quad \alpha\beta = \frac{c}{a}$

$\therefore \quad \alpha^2 + \beta^2 = (\alpha + \beta)^2 - 2\alpha\beta$

$= \left(-\frac{b}{a}\right)^2 - \frac{2c}{a} = \frac{b^2}{a^2} - \frac{2c}{a}$

$= \frac{b^2 - 2ac}{a^2}$.

(b) $\frac{1}{\alpha} + \frac{1}{\beta} = \frac{\alpha + \beta}{\alpha\beta} = \frac{-b/a}{c/a} = -\frac{b}{c}$

(c) $\alpha^4 - \beta^4 = (\alpha^2 + \beta^2)(\alpha + \beta)(\alpha - \beta)$

$= [(\alpha + \beta)^2 - 2\alpha\beta](\alpha + \beta)\sqrt{(\alpha + \beta)^2 - 4\alpha\beta}$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \left(\frac{b^2 - 2ac}{a^2}\right)\left(-\frac{b}{a}\right)\sqrt{\frac{b^2}{a^2} - 4\frac{c}{a}}$$

$$= -\frac{b}{a^4}(b^2 - 2ac)\sqrt{b^2 - 4ac}$$

EXAMPLE 20 *If α, β are the roots of the equation $2x^2 - 3x + 2 = 0$, form the equation whose roots are α^2, β^2.*

SOLUTION $2x^2 - 3x + 2 = 0$, and α, β are the roots

$$\therefore \quad \alpha + \beta = \frac{3}{2}, \quad \alpha\beta = 1$$

For the new equation, roots are α^2 and β^2

∴ Sum of the roots

$$\alpha^2 + \beta^2 = (\alpha + \beta)^2 - 2\alpha\beta = \left(\frac{3}{2}\right)^2 - 2(1)$$

$$= \frac{9}{4} - 2 = \frac{1}{4}$$

and product of the roots $= \alpha^2\beta^2 = (\alpha\beta)^2 = (1)^2 = 1$

∴ the required equation is

$x^2 -$ (sum of roots) $x +$ product of roots $= 0$

$$\Rightarrow \quad x^2 - \frac{1}{4}x + 1 = 0$$

$$\Rightarrow \quad 4x^2 - x + 4 = 0$$

EXAMPLE 21 *Determine k for which the roots of the equation $9x^2 + 2kx + 4 = 0$ are equal.*

SOLUTION Let the roots be α and α.

$$\therefore \quad \text{Sum of roots} = \alpha + \alpha = 2\alpha = -\frac{2k}{9}$$

$$\Rightarrow \quad \alpha = -\frac{k}{9}$$

and product of the roots $= \alpha^2 = \frac{4}{9}$

$$\therefore \quad \left(-\frac{k}{9}\right)^2 = \frac{4}{9} \Rightarrow \frac{k^2}{81} = \frac{4}{9}$$

$$\Rightarrow \quad k^2 = 36 \Rightarrow k = \pm 6.$$

Alternatively: In order that roots of a quadratic equation are equal, its discriminant must be zero.

i.e., $b^2 - 4ac = 0$

$$\therefore \quad (2k)^2 - 4 \times 9 \times 4 = 0$$

$$\Rightarrow \quad k = \pm 6.$$

EXAMPLE 22 *Which of the following quadratic expression can be expressed as a product of real linear factors?*

(a) $x^2 - 2x + 3$ *(b)* $3x^2 - \sqrt{2}x - \sqrt{3}$

(c) $2x^2 + 3x - 4$ *(d)* $\sqrt{2}x^2 - \sqrt{5}x + 3$

SOLUTION (a) $D = b^2 - 4ac < 0$ cannot be expressed

(b) $D = b^2 - 4ac > 0$ can be expressed

(c) $D = b^2 - 4ac > 0$ can be expressed

(d) $D = b^2 - 4ac < 0$, can't be expressed.

NOTE If $D < 0$, then the quadratic equation cannot be expressed into two linear factors.

EXAMPLE 23 *Find the set of values of p for which the quadratic equation has real linear factors.*

$$9x^2 - px + 4$$

SOLUTION For any quadratic polynomial to have real linear factors, we must have $D \geq 0$

$$\therefore \quad b^2 - 4ac \geq 0$$

$$\therefore \quad p^2 - 4 \times 9 \times 4 \geq 0$$

$$p^2 - 144 \geq 0$$

$$\Rightarrow \quad p^2 \geq 144$$

$$\Rightarrow \quad p \geq \pm 12$$

$$\Rightarrow \quad \text{Either } p \leq -12 \text{ or } p \geq 12$$

EXAMPLE 24 *The length of a rectangle is 7 cm more than its width. The area is 60 cm^2. Find the dimensions of the rectangle.*

SOLUTION Let width of the rectangle $= x$

$$\therefore \quad \text{Length of rectangle} = (x + 7) \text{ cm.}$$

$$\therefore \quad \text{Area of rectangle} = (x + 7) \times x$$

$$(x + 7)(x) = 60$$

$$\Rightarrow \quad x^2 + 7x - 60 = 0$$

$$\Rightarrow \quad (x + 12)(x - 5) = 0$$

$$\Rightarrow \quad x = -12 \text{ and } x = 5$$

Since width can never be negative, therefore $x = 5$ cm and $x + 7 = 12$ cm are the required values.

i.e., Length $= 12$ cm and width $= 5$ cm

EXAMPLE 25 *A passenger train takes 2 hours less for a journey of 300 km if its speed is increased by 5 km/hr from its usual speed. Find the usual speed of the train.*

SOLUTION Let the usual speed of the train be x km/hr

$$\therefore \quad \text{Usual time} = \frac{\text{Distance}}{\text{speed}} = \frac{300}{x} \text{ hour}$$

If the speed is increased by 5 km/hr *i.e.,* $(x + 5)$ km/hr,

the time $= \frac{300}{x + 5}$ hour

$$\therefore \quad \frac{300}{x} - \frac{300}{x + 5} = 2$$

$$\Rightarrow \quad 2x(x + 5) = 1500$$

$$\Rightarrow \quad x^2 + 5x - 750 = 0$$

$$\Rightarrow \quad x = 25 \text{ or } x = -30$$

$$\therefore \quad \text{Speed} = 25 \text{ km/hr } (x = -30 \text{ is inadmissible})$$

EXAMPLE 26 *A two digit number is such that the product of its digits is 12. When 36 is added to the number, its digits are reversed. Find the number.*

SOLUTION Let the number be $10x + y$

$$\therefore \quad xy = 12 \Rightarrow y = \frac{12}{x}$$

∴ the number is $10x + \frac{12}{x}$

and the number with digits reversed is

$$10y + x = 10\left(\frac{12}{x}\right) + x = \frac{120}{x} + x$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$\left(10x + \frac{12}{x}\right) + 36 = \frac{120}{x} + x$$

$$\therefore \quad 10x - x + \frac{12}{x} - \frac{120}{x} + 36 = 0$$

$$\Rightarrow \quad 9x + \frac{1}{x}(12 - 120) + 36 = 0$$

$$\Rightarrow \quad 9x - \frac{108}{x} + 36 = 0$$

$$\Rightarrow \quad 9x^2 + 36x - 108 = 0$$

$$\Rightarrow \quad x = 2 \text{ or } x = -6$$

$$\therefore \quad y = \frac{12}{x} = \frac{12}{2} = 6 \quad (x = -6 \text{ is inadmissible})$$

$\therefore$ Hence, the number is $10x + y = 10 \times 2 + 6 = 20 + 6 = 26$.

EXAMPLE 27 *Two candidates attempt to solve a quadratic equation of the form $x^2 + px + q = 0$. One starts with a wrong value of p and finds the roots to be 2 and 6. The other starts with a wrong value of q and finds the roots to be 2 and –9. Find the correct roots and the equation.*

SOLUTION When p is wrong i.e., $\frac{-b}{a}(= \alpha + \beta)$ is wrong but $\frac{c}{a}(= \alpha \cdot \beta)$ is correct.

Hence $\alpha\beta = \frac{c}{a} = 2 \times 6 = 12$

Again when q is wrong *i.e.*, $\frac{c}{a} = (\alpha\beta)$ is wrong but $\frac{-b}{a} = \alpha + \beta$ is correct.

$$\therefore \quad \frac{-b}{a} = \alpha + \beta = 2 + (-9) = -7$$

$\therefore$ the required correct quadratic equation is

$$x^2 - (\alpha + \beta)x + \alpha\beta = 0$$

$$x^2 - (-7)x + 12 = 0$$

$$\Rightarrow \quad x^2 + 7x + 12 = 0$$

and the correct roots of this equation are $-3, -4$.

EXAMPLE 28 *For which value of k will the equations $x^2 - kx - 21 = 0$ and $x^2 - 3kx + 35 = 0$ have one common root.*

SOLUTION Let the common root be α, then,

$$\alpha^2 - k\alpha - 21 = 0 \quad \ldots(i)$$

$$\alpha^2 - 3k\alpha + 35 = 0 \quad \ldots(ii)$$

Solving by the rules of cross multiplication,

$$\frac{\alpha^2}{-35k - 63k} = \frac{\alpha}{-21 - 35} = \frac{1}{-3k + k}$$

$$\therefore \quad \alpha = \frac{-98k}{-56} = \frac{7k}{4}$$

and $\therefore \frac{7k}{4} = \frac{28}{k} \Rightarrow 7k^2 = 28 \times 4 \Rightarrow k = \pm 4$

EXAMPLE 29 *Find the sign of $6x^2 - 5x + 1$ for all real values of x.*

SOLUTION $\because \quad D = b^2 - 4ac$

$$D = 25 - 4 \times 6 \times 1 = 1$$

$\because$ The roots are real and different and the roots are $\frac{5 \pm \sqrt{25 - 24}}{12}$ *i.e.*, $\frac{1}{2}$ and $\frac{1}{3}$

$\therefore$ The given expression has the same sign as the coefficient of x^2, *i.e.*, positive for all real values of x except for those which lie between $\frac{1}{3}$ and $\frac{1}{2}$



EXAMPLE 30 *Find the ranges of the values of x for which $x^2 - 4x + 2$ lies between +1 and –1.*

SOLUTION $x^2 - 4x + 2 > -1$ or $x^2 - 4x + 3 > 0$

Since the coefficient of x^2 is positive and the roots of $x^2 - 4x + 3 = 0$ are 1 and 3, therefore

$$x^2 - 4x + 3 > 0 \text{ for } x < 1 \text{ and } x > 3 \quad \ldots(i)$$

Again, $x^2 - 4x + 2 < 1$ or $x^2 - 4x + 1 < 0$

Since the coefficient of x^2 is positive and the roots of $x^2 - 4x + 1 = 0$ are $2 - \sqrt{3}$ and $2 + \sqrt{3}$, therefore

$$x^2 - 4x + 1 < 0 \text{ for } 2 - \sqrt{3} < x < 2 + \sqrt{3} \quad \ldots(ii)$$

Combining (i) and (ii), we get $2 - \sqrt{3} < x < 1$ or $3 < x < 2 + \sqrt{3}$

Which are the required ranges of the values of x.

EXAMPLE 31 *If x be real, find the maximum value of $7 + 10x - 5x^2$.*

SOLUTION

NOTE When $a < 0$, we get maxima otherwise if $a > 0$ we get minima.

As we know, at $x = \frac{-b}{2a}$, we get the maxima,

$$\therefore \quad y = \frac{4ac - b^2}{4a} = \frac{4 \times (-5) \times 7 - (10)^2}{4 \times (-5)}$$

$$= \frac{-140 - 100}{-20} = \frac{-240}{-20} = 12$$

Thus the maximum value of the given quadratic equation is 12.

EXAMPLE 32 *If x is real, prove that the value of the expression $\frac{(x-1)(x+3)}{(x-2)(x+4)}$ cannot be between $\frac{4}{9}$ and 1.*

SOLUTION Let $\frac{(x-1)(x+3)}{(x-2)(x+4)} = y$, then

$$x^2 + 2x - 3 = y(x^2 + 2x - 8)$$

or $\quad x^2(1 - y) + 2x(1 - y) + (8y - 3) = 0$

For x to be real, its discriminant $D \geq 0$

or $\quad [2(1 - y)]^2 - 4(1 - y)(8y - 3) \geq 0$

Scanned by CamScanner

yoursmahboob.wordpress.com

or $(1-y)(4-9y) \geq 0$

or $(1-y)\left(\frac{4}{9}-y\right) \geq 0$

It shows that $(1-y)$ and $\left(\frac{4}{9}-y\right)$ should be of the same sign.

$\therefore$ we get $y = \frac{4}{9}, 1$

If $y < \frac{4}{9}$, $(1-y)\left(\frac{4}{9}-y\right) > 0$

If $\frac{4}{9} < y < 1$, $(1-y)\left(\frac{4}{9}-y\right) < 0$

If $y > 1$ $(1-y)\left(\frac{4}{9}-y\right) > 0$

Hence for x to be real, y, (i.e., the value of the given expression) cannot lie between $\frac{4}{9}$ and 1.

EXAMPLE 33 *If x be real, find the maximum value of* $\frac{(x+2)}{(2x^2+3x+6)}$.

SOLUTION Let $y = \frac{x+2}{2x^2+3x+6}$

then $2x^2y + (3y-1)x + 6y - 2 = 0$

For x to be real, $(3y-1)^2 - 8y(6y-2) \geq 0$

or $(1+13y)(1-3y) \geq 0$

or $(13y+1)(3y-1) \leq 0$

$\therefore$ Putting each factor equal to zero, we get

$$y = -\frac{1}{13}, \frac{1}{3}$$

If $y < -\frac{1}{13}$, $(1+13y)(1-3y) < 0$

If $-\frac{1}{13} < y < \frac{1}{3}$, $(1+13y)(1-3y) > 0$

If $y > \frac{1}{3}$, $(1+13y)(1-3y) < 0$

Thus, y will lie between $-\frac{1}{13}$ and $\frac{1}{3}$.

Hence the maximum value of y is $\frac{1}{3}$ and minimum value is $-\frac{1}{13}$.

EXAMPLE 34 *Solve $x^2 - 5x + 4 > 0$.*

SOLUTION $x^2 - 5x + 4 = (x-1)(x-4)$

Since $f(x) = x^2 - 5x + 4 > 0$

therefore the required range is $x < 1$ and $x > 4$.

EXAMPLE 35 *Solve $-x^2 + 6x - 8 > 0$*

SOLUTION $-x^2 + 6x - 8 > 0$

$\Rightarrow$ $x^2 - 6x + 8 < 0$

$\Rightarrow$ Now $x^2 - 6x + 8 = (x-2)(x-4)$

Since $f(x) = x^2 - 6x + 8 < 0$

therefore the required range is $2 < x < 4$.

EXAMPLE 36 *Solve the inequality* $\frac{x-2}{x+2} > \frac{2x-3}{4x+1}$.

SOLUTION The range of the variable x in this inequality consists of all values of x except $x = -2$ and $x = 1/4$. Hence we cannot cross multiply. So we adopted another method

$$\frac{x-2}{x+2} - \frac{2x-3}{4x-1} > 0 \quad \ldots(i)$$

or $$\frac{(x-2)(4x-1) - (x+2)(2x-3)}{(x+2)(4x-1)} > 0$$

or $$\frac{2(x^2-5x+4)}{(x+2)(4x-1)} > 0$$

or $$\frac{(x-1)(x-4)}{(x+2)(x-1/4)} > 0 \quad \ldots(ii)$$

Now multiply both sides of (ii) by the expression $(x+2)^2\left(x-\frac{1}{4}\right)^2$, which is positive for the x under consideration.

$\therefore$ $$\frac{(x-1)(x-4)(x+2)^2\left(x-\frac{1}{4}\right)^2}{(x+2)\left(x-\frac{1}{4}\right)} > 0$$

or $(x-1)(x-4)(x+2)(x-1/4) > 0$ ...(iii)



Thus, the range is $x < -2$ or $\frac{1}{4} < x < 1$ or $x > 4$

EXAMPLE 37 *Determine the range of values of x for which* $\frac{x^2-2x+5}{3x^2-2x-5} > \frac{1}{2}$.

SOLUTION $$\frac{x^2-2x+5}{3x^2-2x-5} > \frac{1}{2}$$

or $$\frac{x^2-2x+5}{3x^2-2x-5} - \frac{1}{2} > 0$$

or $$\frac{x^2+2x-15}{3x^2-2x-5} < 0$$

or $$\frac{(x+5)(x-3)}{(x+1)(3x-5)} < 0$$

or $$\frac{(x+5)(x-3)(x+1)^2(3x-5)^2}{(x+1)(3x-5)} < 0$$

or $(x+5)(x-3)(x+1)(3x-5) < 0$



$\therefore$ $-5 < x < -1$ or $\frac{5}{3} < x < 3$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 38 *Find the range of real values of x for which* $\frac{x-1}{(4x+5)} < \frac{x-3}{4x-3}$

SOLUTION $\frac{x-1}{4x+5} < \frac{x-3}{4x-3}$ or $\frac{x-1}{4x+5} - \frac{x-3}{4x-3} < 0$

or $\frac{(x-1)}{(4x+5)} \times \frac{(4x-3)}{(4x-3)} - \frac{(x-3)}{(4x-3)} \times \frac{(4x+5)}{(4x+5)} < 0$

or $\frac{4x^2-7x+3}{(4x+5)(4x-3)} - \frac{(4x^2-7x-15)}{(4x+5)(4x-3)} < 0$

or $\frac{18}{(4x+5)(4x-3)} < 0$

Since 18 is positive

$\therefore$ $(4x+5)(4x-3) < 0$

or $16\left(x+\frac{5}{4}\right)\left(x-\frac{3}{4}\right) < 0$



$\therefore$ $\frac{-5}{4} < x < \frac{3}{4}$

INTRODUCTORY EXERCISE-14.1

Directions for question number 1–12: Find the roots of the following equations.

1. $15x^2 - 7x - 36 = 0$:
(a) $\frac{5}{9}, -\frac{4}{3}$ (b) $\frac{9}{5}, -\frac{4}{3}$
(c) $\frac{9}{5}, -\frac{3}{4}$ (d) none of these

2. $\sqrt{7}y^2 - 6y - 13\sqrt{7} = 0$:
(a) $\sqrt{7}, 2\sqrt{7}$ (b) $3, \frac{2}{\sqrt{7}}$
(c) $\frac{13}{\sqrt{7}}, -\sqrt{7}$ (d) none of these

3. $6x^2 + 40 = 31x$:
(a) $\frac{3}{8}, \frac{2}{5}$ (b) $\frac{3}{8}, \frac{3}{2}$
(c) $0, \frac{8}{3}$ (d) $\frac{8}{3}, \frac{5}{2}$

4. $6\left(\frac{y-3}{2y+1}\right) + 1 = 5\sqrt{\frac{y-3}{2y+1}}, y \neq \frac{1}{2}$:
(a) $4, \frac{13}{2}$ (b) $4, \frac{11}{2}$
(c) $\frac{13}{2}, \frac{9}{2}$ (d) none of these

5. $(x+2)(x-5)(x-6)(x+1) = 144$:
(a) $-1, -2, -3$ (b) $7, -3, 2$
(c) $2, -3, 5$ (d) none of these

6. $\sqrt{x+5} + \sqrt{x+21} = \sqrt{6x+40}$:
(a) 1 (b) 2
(c) 4 (d) 6

7. $2\left(x^2 + \frac{1}{x^2}\right) - 3\left(x + \frac{1}{x}\right) - 1 = 0$:
(a) $2, \frac{1}{2}$ (b) $-2, 4$
(c) $2, \frac{3}{2}$ (d) none of these

8. $\sqrt{\frac{x}{1-x}} + \sqrt{\frac{1-x}{x}} = \frac{13}{6}$:
(a) $\frac{13}{4}, 5$ (b) $\frac{4}{13}, \frac{9}{13}$
(c) $\frac{4}{13}, 6$ (d) none of these

9. $\sqrt{2x^2 - 2x + 1} - 2x + 3 = 0$:
(a) 2 (b) 3
(c) 4 (d) 5

10. $\sqrt{x^2 - 9x + 20} - \sqrt{x^2 - 12x + 32} = \sqrt{2x^2 - 25x + 68}$:
(a) 4, 9 (b) 3, 9
(c) 2, 4 (d) 2, 6

11. $\left(x - \frac{1}{x}\right)^2 + 8\left(x + \frac{1}{x}\right) = 29, x \neq 0$:
(a) $-5, 4$ (b) 3, 2
(c) 1, 3 (d) $\frac{3+\sqrt{5}}{2}, \frac{-11 \pm 3\sqrt{13}}{2}$

12. $\left(\frac{1}{x+1} + \frac{1}{x+5}\right) = \left(\frac{1}{x+2} + \frac{1}{x+4}\right)$:
(a) 7 (b) -3
(c) -5 (d) 4

13. Determine k such that the quadratic equation $x^2 + 7(3+2k) - 2x(1+3k) = 0$ has equal roots :
(a) 2, 7 (b) 7, 5
(c) $2, \frac{-10}{9}$ (d) none of these

14. Discriminant of the equation $-3x^2 + 2x - 8 = 0$ is :
(a) -92 (b) -29
(c) 39 (d) 49

15. The nature of the roots of the equation $x^2 - 5x + 7 = 0$ is :
(a) no real roots (b) 1 real root
(c) can't be determined (d) none of these

16. The roots of $a^2x^2 + abx = b^2, a \neq 0$ are :
(a) equal (b) non-real
(c) unequal (d) none of these

17. The equation $x^2 - px + q = 0, p, q \in R$ has no real roots if:
(a) $p^2 > 4q$ (b) $p^2 < 4q$
(c) $p^2 = 4q$ (d) none of these

18. Determine the value of k for which the quadratic equation $4x^2 - 3kx + 1 = 0$ has equal roots :
(a) $\pm\left(\frac{2}{3}\right)$ (b) $\pm\left(\frac{4}{3}\right)$
(c) ± 4 (d) ± 6

Scanned by CamScanner

yoursmahboob.wordpress.com

19. Find the value of k such that the equation $x^2 - (k+6)x + 2(2k-1) = 0$ has sum of the roots equal to half of their product :
(a) 3 (b) 4
(c) 7 (d) 10

20. Find the value of k so that the sum of the roots of the quadratic equation is equal to the product of the roots :
$$(k+1)x^2 + 2kx + 4 = 0$$
(a) –2 (b) –4
(c) 6 (d) 8

21. If –4 is a root of the quadratic equation $x^2 - px - 4 = 0$ and the quadratic equation $x^2 - px + k = 0$ has equal roots, find the value of k :
(a) 9/4 (b) 1
(c) 2.5 (d) 3

22. Find the value of k such that the sum of the squares of the roots of the quadratic equation $x^2 - 8x + k = 0$ is 40 :
(a) 12 (b) 2
(c) 5 (d) 8

23. Find the value of p for which the quadratic equation $x^2 + p(4x + p - 1) + 2 = 0$ has equal roots :
(a) $-1, \frac{2}{3}$ (b) 3, 5
(c) $1, -\frac{4}{3}$ (d) $\frac{3}{4}, 2$

24. If α and β are the roots of the equation $3x^2 + 7x + 3 = 0$ Find the value of $\alpha\beta$:
(a) 1 (b) 0
(c) 2 (d) 3

25. If α and β are the roots of the equation $x^2 - 3x + 2 = 0$. Find the quadratic equation whose roots are $-\alpha$ and $-\beta$:
(a) $x^2 - 3x + 2 = 0$ (b) $x^2 + 3x + 2 = 0$
(c) $x^2 + 3x - 2 = 0$ (d) none of these

26. Find the quadratic equation whose roots are $\sqrt{3}$ and $2\sqrt{3}$:
(a) $x^2 + 3\sqrt{3}x - 6 = 0$ (b) $x^2 - 3\sqrt{3}x + 6 = 0$
(c) $x^2 + 3\sqrt{3}x + 5 = 0$ (d) none of these

27. If α and β are the roots of equation $6x^2 + x - 2 = 0$, find the value of $\frac{\alpha}{\beta} + \frac{\beta}{\alpha}$:
(a) $-\frac{25}{12}$ (b) $-\frac{12}{75}$
(c) $-\frac{4}{9}$ (d) none of these

28. If a and c are such that the quadratic equation $ax^2 - 5x + c = 0$ has 10 as the sum of the roots and also as the product of the roots, find a and c respectively :
(a) $\frac{1}{2}, 6$ (b) $\frac{1}{2}, 5$
(c) $\frac{1}{2}, 8$ (d) none of these

29. If α and β are the roots of the equation $x^2 - x - 4 = 0$, find the value of $\frac{1}{\alpha} + \frac{1}{\beta} - \alpha\beta$:
(a) $\frac{16}{7}$ (b) $\frac{8}{5}$
(c) $\frac{15}{4}$ (d) none of these

30. If α and β are the roots of the equation $x^2 - 2x - 1 = 0$, find the value of $\alpha^2\beta + \alpha\beta^2$:
(a) –8 (b) –5
(c) 6 (d) –2

31. If α and β are the roots of $x^2 - x - 2 = 0$, find the quadratic equation in x whose roots are $(2\alpha + 1)$ and $(2\beta + 1)$:
(a) $x^2 + 5x - 4 = 0$ (b) $x^2 - 4x - 5 = 0$
(c) $x^2 + 4x - 5 = 0$ (d) none of these

32. If α, β be the roots of the quadratic equation $3x^2 - 6x + 4 = 0$, find the value of
$$\left(\frac{\alpha}{\beta} + \frac{\beta}{\alpha}\right) + 2\left(\frac{1}{\alpha} + \frac{1}{\beta}\right) + 3\alpha\beta :$$
(a) 6 (b) 8
(c) 7 (d) 5

33. If α, β be the roots of the quadratic equation $x^2 - 5x + k = 0$, find the value of k such that $\alpha - \beta = 1$:
(a) 2 (b) 4
(c) 6 (d) 8

34. If one root of the quadratic equation $ax^2 + bx + c = 0$ is double the other then which one of the following is correct?
(a) $b^2 = 3ac$ (b) $2b^2 = 5ac$
(c) $2b^2 = 9ac$ (d) $2b^2 > 9ac$

35. The length of a hypotenuse of a right triangle exceeds the length of its base by 2 cm and exceeds twice the length of the altitude by 1 cm. Find the length of each side of the triangle (in cm) :
(a) 6, 8, 10 (b) 7, 24, 25
(c) 8, 15, 17 (d) 7, 40, 41

36. A two digit number is such that the product of its digits is 12. When 9 is addded to the number, the digits interchange their places, find the number :
(a) 62 (b) 34
(c) 26 (d) 43

37. A plane left 40 minutes late due to bad weather and in order to reach its destination, 1600 km away in time, it had to increase its speed by 400 km/h from its usual speed. Find the usual speed of the plane :
(a) 600 km/h (b) 750 km/h
(c) 800 km/h (d) none of these

38. The sum of the squares of two consecutive positive odd numbers is 290. Find the sum of the numbers :
(a) 14 (b) 24
(c) 28 (d) none of these

39. A shopkeeper buys a number of books for Rs. 80. If he had bought 4 more for the same amount, each book would have cost Re. 1 less. How many books did he buy?
(a) 8 (b) 16
(c) 24 (d) 28

40. Two square have sides x cm and $(x + 4)$ cm. The sum of their areas is 656 cm^2. Find the sides of the square :
(a) 8 cm, 12 cm (b) 12 cm, 15 cm
(c) 6 cm, 10 cm (d) 16 cm, 20 cm

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. If p and q ($\neq 0$) are the roots of the equation $x^2 + px + q = 0$, then the least value of $x^2 + px + q$ ($x \in R$) is :
(a) $-\frac{1}{4}$ (b) $\frac{1}{4}$
(c) $\frac{-9}{4}$ (d) $\frac{9}{4}$

2. The value of p for which the sum of the squares of the roots of the equation $x^2 - (p-2)x - p - 1 = 0$ assume the least value is :
(a) -1 (b) 1
(c) 0 (d) 2

3. If the equation $x^2 + 2(p+1)x + 9p - 5 = 0$ has only negative roots, then :
(a) $p \leq 0$ (b) $p \leq -6$
(c) $p \geq 6$ (d) $p \geq 36$

4. The ratio of the roots of the equation $ax^2 + bx + c = 0$ is same as the ratio of the roots of the equation $px^2 + qx + r = 0$. If D_1 and D_2 are the discriminants of $ax^2 + bx + c = 0$ and $px^2 + qx + r = 0$ respectively then $D_1 : D_2 =$
(a) $\frac{a^2}{q^2}$ (b) $\frac{a^2}{p^2}$
(c) $\frac{b^2}{q^2}$ (d) none of these

5. If every pair from among the equations $x^2 + px + qr = 0$ $x^2 + qx + rp = 0$ and $x^2 + rx + pq = 0$ has a common root, then the sum of the three common roots is :
(a) $2(p+q+r)$ (b) $p+q+r$
(c) $-(p+q+r)$ (d) pqr

6. If the roots of the equation, $ax^2 + bx + c = 0$, are of the form $\frac{\alpha}{\alpha - 1}$ and $\frac{\alpha + 1}{\alpha}$ then the value of $(a+b+c)^2$ is :
(a) $b^2 - 2ac$ (b) $b^2 - 4ac$
(c) $2b^2 - ac$ (d) $4b^2 - 2ac$

7. Equation $ax^2 + 2x + 1$ has one double root if :
(a) $a = 0$ (b) $a = -1$
(c) $a = 1$ (d) $a = 2$

8. The number of quadratic equations which remain unchanged by squaring their roots, is :
(a) 0 (b) 2
(c) 4 (d) infinitely many

9. The value of $\sqrt{6 + \sqrt{6 + \sqrt{6 + \sqrt{6 + \ldots \infty}}}}$ is :
(a) 2 (b) 3
(c) 4 (d) 5

10. If α, β, γ are the roots of the equation $x^3 + a_0x^2 + a_1x + a_2 = 0$, then $(1-\alpha^2)(1-\beta^2)(1-\gamma^2)$ is equal to :
(a) $(1-a_1)^2 + (a_0 - a_2)^2$ (b) $(1+a_1)^2 - (a_0 + a_2)^2$
(c) $(1+a_1)^2 + (a_0 + a_2)^2$ (d) none of these

11. If $x \in R$, and $K = \frac{(x^2 - x + 1)}{(x^2 + x + 1)}$, then :
(a) $x \leq 0$ (b) $\frac{1}{3} \leq k \leq 3$
(c) $k \geq 5$ (d) none of these

12. If $x = \sqrt{2 + \sqrt{2 + \sqrt{2 + \sqrt{2 + \ldots \infty}}}}$ then x is :
(a) 1 (b) 2
(c) 3 (d) none of these

13. If α, β, γ are the roots of the equation $x^3 - 3x + 11 = 0$ then the equation whose roots are $(\alpha + \beta)$, $(\beta - \gamma)$ and $(\gamma + \alpha)$ is :
(a) $x^3 + 3x + 11 + 0$ (b) $x^3 - 3x + 11 = 0$
(c) $x^3 + 3x - 11 = 0$ (d) $x^3 - 3x - 11 = 0$

14. If $x^2 - ax - 21 = 0$ and $x^2 - 3ax + 35 = 0$; $a > 0$ have a common root, then a is equal to :
(a) 1 (b) 2
(c) 4 (d) 5

15. If α, β, γ are such that $\alpha + \beta + \gamma = 2$, $\alpha^2 + \beta^2 + \gamma^2 = 6$, $\alpha^3 + \beta^3 + \gamma^3 = 8$, then $\alpha^4 + \beta^4 + \gamma^4$ is equal to :
(a) 10 (b) 12
(c) 18 (d) none of these

16. The real values of a for which the quadratic equation $2x^2 - (a^3 + 8a - 1)x + a^2 - 4a = 0$ possesses roots of opposite signs are given by :
(a) $a > 6$ (b) $a > 9$
(c) $0 < a < 4$ (d) $a < 0$

17. If α, β are the roots of $ax^2 + bx + c = 0$ and $\alpha + k, \beta + k$ are the roots of $px^2 + qx + r = 0$, then $k =$
(a) $-\frac{1}{2}\left(\frac{a}{b} - \frac{p}{q}\right)$ (b) $\left(\frac{a}{b} - \frac{p}{q}\right)$
(c) $\frac{1}{2}\left(\frac{b}{a} - \frac{q}{p}\right)$ (d) $(ab - pq)$

18. If $\alpha, \beta \in R$, are the roots of the equation $ax^2 + bx + c = 0$, $k \in R$ lies between α and β, if :
(a) $a^2k^2 + bk + c < 0$ (b) $a^2k^2 + abk + ac < 0$
(c) $ak^2 + abk + ac > 0$ (d) none of these

19. If the equation $(3x)^2 + (27 \times 3^{1/k} - 15)x + 4 = 0$ has equal roots, then $k =$

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) -2 (b) $-\frac{1}{2}$
(c) $\frac{1}{2}$ (d) 0

20. The least possible integral value of a for which the equation $x^2 - 2(a-1)x + (2a+1) = 0$ has both the roots positive, is :
(a) 1 (b) 3
(c) 4 (d) 6

21. The number of real solutions of the equation $2^{3x^2-7x+4} = 1$ is :
(a) 0 (b) 4
(c) 2 (d) infinitely many

22. The number of real solutions of the equation $2|x|^2 - 5|x| + 2 = 0$ is :
(a) 0 (b) 4
(c) 2 (d) none of these

23. The number of real roots of the equation $(x-1)^2 + (x-2)^2 + (x-3)^2 = 0$:
(a) 0 (b) 2
(c) 3 (d) 6

24. The equation $\sqrt{x+1} - \sqrt{x-1} = \sqrt{4x-1}$ has :
(a) no solution
(b) one solution
(c) two solutions
(d) more than two solutions

25. If α, β are the roots of the equation $8x^2 - 3x + 27 = 0$, then the value of $[(\alpha^2/\beta)^{1/3} + (\beta^2/\alpha)^{1/3}]$ is :
(a) 1/3 (b) 1/4
(c) 1/5 (d) 1/6

26. The quadratic equation $3x^2 + 2(a^2+1)x + a^2 - 3a + 2 = 0$ possesses roots of opposite sign then a lies in :
(a) $(-\infty, 0)$ (b) $(-\infty, 1)$
(c) (1, 2) (d) (4, 9)

27. The expression $\frac{(x-a)(x-b)}{(x-c)}$ will assume all real values for every $x \in R$, if :
(a) $a < b < c$ (b) $a > b > c$
(c) c lies between a and b (d) none of these

28. If α and β are the roots of the equation $ax^2 + bx + c$, where $(a, b, c) > 0$, then α and β are :
(a) rational numbers (b) real and negative
(c) negative real parts (d) none of these

29. The number of solutions of the equation $3^{x-1} + 5^{x-1} = 34$:
(a) 0 (b) 1
(c) 2 (d) none of these

30. If $(2+\sqrt{3})^{x^2-2x+1} + (2-\sqrt{3})^{x^2-2x-1} = \frac{2}{2-\sqrt{3}}$, then x is equal to :
(a) 0 (b) 1
(c) 2 (d) both (a) and (c)

31. The values of a for which the quadratic equations $(1-2a)x^2 - 6ax - 1 = 0$ and $ax^2 - x + 1 = 0$ have at least one root in common are :
(a) $\frac{1}{2}, \frac{2}{9}$ (b) $0, \frac{1}{2}$
(c) $\frac{2}{9}$ (d) $0, \frac{1}{2}, \frac{2}{9}$

32. The integer k for which the inequality $x^2 - 2(4k-1)x + 15k^2 - 2k - 7 > 0$ is valid for any x is :
(a) 2 (b) 3
(c) 4 (d) 6

33. The values of a for which $2x^2 - 2(2a+1)x + a(a+1) = 0$ may have one root less than a and other root greater than a are given by :
(a) $-1 < a < 0$ (b) $0 < a < 1$
(c) $a \geq 0$ (d) $a < -1$ or $a > 0$

34. The condition that $x^3 - ax^2 + bx - c = 0$ may have two of its roots equal to each other but of opposite signs is :
(a) $ab = c$ (b) $\frac{2}{3}a = bc$
(c) $a^2b = c$ (d) none of these

35. If the roots of $ax^2 + bx + c = 0$, $a > 0$, be each greater than unity, then :
(a) $a + b + c = 0$ (b) $a + b + c > 0$
(c) $a + b + c < 0$ (d) none of these

36. The number of real solutions of $x - \frac{1}{x^2-4} = 2 - \frac{1}{x^2-4}$ is :
(a) 0 (b) 1
(c) 2 (d) infinite

37. The number of real solutions of the equation $2^{x/2} + (\sqrt{2}+1)^x = (5+2\sqrt{2})^{x/2}$ is :
(a) one (b) four
(c) six (d) infinite

38. If $xy = 2(x+y)$, $x \leq y$ and $x, y \in N$, the number of solutions of the equation :
(a) 2 (b) 3
(c) 0 (d) infinitely many

39. If $a, b, c \in R$ and equality $ax^2 + bx + c = 0$ has complex roots which are reciprocal to each other, then one has :
(a) $a = c$ (b) $|b| \leq |c|$
(c) $|b| \leq |a|$ (d) all of these

40. The equation $|x+1||x-1| = a^2 - 2a - 3$ can have real solutions for x if a belongs to :
(a) $(-\infty, -1] \cup [3, \infty)$
(b) $[1-\sqrt{5}, 1+\sqrt{5}]$
(c) $[1-\sqrt{5}, -1] \cup [3, 1+\sqrt{5}]$
(d) none of the above

41. $p, q, r \in R$ and k is a prime number such that $p + qk^{1/3} + rk^{2/3} = 0$, then :
(a) $p = \frac{q}{r}$ (b) $p = q^{1/3} \neq r^{2/3}$
(c) $p = q = r = 0$ (d) none of these

42. The expression $x^4 + 2px^3 + x^2 + 2px + 1 = 0$ has at least two distinct negative roots if :
(a) $p < 1$ (b) $p = 0$
(c) $p > \frac{3}{4}$ (d) $p \in \left(-\frac{1}{2}, \frac{1}{2}\right)$

43. The roots of the expression $x^2 - 2a|x-a| - 3a^2 = 0; a < 0$:
(a) $(1+\sqrt{2})a, (-1-\sqrt{6})a$
(b) $(1-\sqrt{2})a, (\sqrt{6}-1)a$
(c) $(1 \pm \sqrt{2})a$
(d) none of the above

Scanned by CamScanner

yoursmahboob.wordpress.com

44. The possible values of x for the equation $2^{x+2} - |2^{x+1} - 1| - 2^{x+1} = 1$ is :
(a) $x = -3$ (b) $x \geq -1$
(c) $x = 0$ (d) $(x \geq -1) \cup (x = -3)$

45. The values of x which satisfy the expression :
$$(5 + 2\sqrt{6})^{x^2-3} + (5 - 2\sqrt{6})^{x^2-3} = 10$$
(a) $\pm 2, \pm\sqrt{3}$ (b) $\pm\sqrt{2}, \pm 4$
(c) $\pm 2, \pm\sqrt{2}$ (d) $2, \sqrt{2}, \sqrt{3}$

46. If $a, b \in \{1, 2, 3, 4\}$, then the number of quadratic equations of the form $ax^2 + bx + 1 = 0$, having real roots is :
(a) 6 (b) 7
(c) 8 (d) none of these

47. The minimum value of the expression $a + \frac{1}{a}; a > 0$ is :
(a) 0 (b) 1
(c) 2 (d) 4

48. If $a^2 + b^2 + c^2 = 1$, then $ab + bc + ac$ lies in the interval :
(a) $[1, 2/3]$ (b) $[-1/2, 1]$
(c) $[-1, 1/2]$ (d) $[2, -4]$

49. The integral values of x satisfying the equation $2^{|x+1|} - 2^x = |2^x - 1| + 1$ is :
(a) $(-\infty, 0)$ (b) $[1, \infty)$
(c) $[0, \infty)$ (d) $2n : n \in I$

50. Number of values of x satisfying the equation $(15 + 4\sqrt{14})^t + (15 - 4\sqrt{14})^t = 30$, where $t = x^2 - 2|x|$:
(a) 0 (b) 2
(c) 4 (d) 6

51. The inequality $|2x - 3| < 1$ is valid when x lies in the interval :
(a) $(-4, 3)$ (b) $(-1, 2)$
(c) $(1, 2)$ (d) $(3, 4)$

52. Let α and β be the roots of the equation $x^2 + x + 1 = 0$. The equation whose roots are α^{19}, β^7 is :
(a) $x^2 - x - 1 = 0$ (b) $x^2 - x + 1 = 0$
(c) $x^2 + x - 1 = 0$ (d) $x^2 + x + 1 = 0$

53. The value of p for which the difference between the roots of the equation $x^2 + px + 8 = 0$ is 2 are :
(a) ± 2 (b) ± 4
(c) ± 6 (d) ± 8

54. If $x > 0$, $xy = 1$, minimum value of $x + y$ is :
(a) 1 (b) 0
(c) 2 (d) $\sqrt{2}$

55. If $x = 7 + 4\sqrt{3}$ and $xy = 1$, then the value of $\frac{1}{x^2} + \frac{1}{y^2}$ is :
(a) 64 (b) 128
(c) 184 (d) 194

56. If $x \in R$, and $\alpha = \frac{x^2}{(1 + x^4)}$, then :
(a) $0 \leq \alpha \leq 2$ (b) $0 \leq \alpha \leq 1$
(c) $0 \leq \alpha \leq \frac{1}{4}$ (d) $0 \leq \alpha \leq \frac{1}{2}$

57. The set of values for which $x^3 + 1 \geq x^2 + x$ is :
(a) $x \geq 0$ (b) $x \leq 0$
(c) $x \geq -1$ (d) $-1 \leq x \leq 1$

LEVEL 2

1. The value of x satisfying the equation
$$|x - 1|^{\log_3 x^2 - 2\log_x 9} = (x - 1)^7 :$$
(a) $\sqrt{3}$ (b) 3^4
(c) 3 (d) $\log_4 3$

2. If the roots of $10x^3 - cx^2 - 54x - 27 = 0$ are in HP, then find the value of c :
(a) 2 (b) 6
(c) 9 (d) none of these

3. Find the number of pairs for (x, y) from the following equations :
$$\log_{100} |x + y| = \frac{1}{2}$$
$$\log_{10} y - \log_{10} |x| = \log_{100} 4$$
(a) 0 (b) 1
(c) 2 (d) none of these

4. The number of solutions for real x, which satisfy the equation $2\log_2 \log_2 x + \log_{1/2} \log_2 (2\sqrt{2}x) = 1$:
(a) 1 (b) 2
(c) 4 (d) none of these

5. The solution set for which the equation satisfies $|x^2 + 4x + 3| + 2x + 5 = 0$:
(a) $(-1 + \sqrt{3}, -1 - \sqrt{3})$ (b) $[-2, (-1 + \sqrt{3})]$
(c) $[-4, (-1 - \sqrt{3})]$ (d) none of these

6. The real numbers x_1, x_2, x_3 satisfying the equation $x^3 - x^2 + \beta x + \gamma = 0$ are in A.P. Find the intervals in which β and γ lie, respectively :
(a) $(-\infty, 1/3] [-1/27, \infty)$
(b) $(-\infty, 3)$
(c) $(-1/3, 1/3)(-1/27, 1/27)$
(d) none of these

7. For all $x \in (0, 1)$:
(a) $e^x < 1 + x$ (b) $\log_e (1 + x) < x$
(c) $\sin x > x$ (d) $\log_e x > x$

8. Let $p \geq 3$ be an integer and α, β be the roots of $x^2 - (p + 1)x + 1 = 0$, then the value of $\alpha^n + \beta^n$, where $n \in N$
(a) is divisible by 'p'
(b) is an integer
(c) is a rational number
(d) both (b) and (c)

9. Let a, b, c be real, if $ax^2 + bx + c = 0$ has two real roots α, β, where $\alpha < -1$ and $\beta > 1$, then the value of $1 + \frac{c}{a} + \left|\frac{b}{a}\right|$ is :
(a) less than zero (b) greater than zero
(c) equal to zero (d) equal to $b^2 - 4ac$

10. If p and q are the roots of $x^2 + px + q = 0$, then :
(a) $p = 1$ (b) $p = 1$ or 0
(c) $p = -2$ (d) $p = -2$ or 0

Scanned by CamScanner

yoursmahboob.wordpress.com

11. If p, q, r are positive and are in AP, the roots of quadratic equation $px^2 + qx + r = 0$ are real for :

(a) $\left|\frac{r}{p} - 7\right| \geq 4\sqrt{3}$ (b) $\left|\frac{p}{r} - 7\right| \geq 4\sqrt{3}$

(c) all p and r (d) no p and r

12. The sum of all the real roots of the equation $|x-2|^2 + |x-2| - 2 = 0$ is :

(a) 2 (b) 3

(c) 4 (d) none of these

13. Let p and q be the roots of the equation $x^2 - 2x + A = 0$ and let r and s be the roots of the equation $x^2 - 18x + B = 0$. If $p < q < r < s$ are in arithmetic progression, then A, B respectively equal to :

(a) 8, 17 (b) 3, 7

(c) –3, 11 (d) none of these

14. If the roots of the equation $x^2 - 2ax + a^2 + a - 3 = 0$ are real and less than 3, then :

(a) $a < 2$ (b) $2 \leq a \leq 3$

(c) $3 < a \leq 4$ (d) $a > 4$

15. If α and β $(\alpha < \beta)$, are the roots of the equation $x^2 + bx + c = 0$, where $c < 0 < b$, then :

(a) $0 < \alpha < \beta$

(b) $\alpha < 0 < \beta < |\alpha|$

(c) $\alpha < \beta < 0$

(d) $\alpha < 0 < |\alpha| < \beta$

16. If $b > a$, then the equation $(x-a)(x-b) - 1 = 0$ has :

(a) both roots in $[a, b]$

(b) both roots in $(-\infty, 0)$

(c) both roots in $(b, +\infty)$

(d) one root in $(-\infty, a)$ and other root in $(b, +\infty)$

17. Let α, β be the roots of $x^2 - x + p = 0$ and γ, δ be the roots of $x^2 - 4x + q = 0$. If $\alpha, \beta, \gamma, \delta$ are in GP, then the integral values of p and q respectively are :

(a) –2, –32 (b) –2, 3

(c) –6, 3 (d) –6, –32

18. If α, β are the roots of the equation $x^2 - px + q = 0$, then find the quadratic equation, the roots of which are $(\alpha^2 - \beta^2)(\alpha^3 - \beta^3)$ and $(\alpha^3\beta^2 + \alpha^2\beta^3)$:

(a) $px^2 - (5p + 7q)x - (p^6q^6 + 4p^2q^6) = 0$

(b) $x^2 - (p^5 - 5p^3q + 5pq^2)x + (p^6q^2 - 5p^4q^3 + 4p^2q^4) = 0$

(c) $x^2 - (p^3q - 5p^5 + p^4q) - (p^6q^2 - 5p^2q^6) = 0$

(d) all of the above

19. Given that α, γ are the roots of the equation $Ax^2 - 4x + 1 = 0$ and β, δ are the roots of the equation $Bx^2 - 6x + 1 = 0$, then the values of A and B respectively such that α, β, γ and δ are in HP :

(a) –5, 9 (b) 3/2, 5

(c) 3, 8 (d) none of these

20. Let α, β be the roots of the equation $(x-a)(x-b) = c, c \neq 0$, then the roots of the equation $(x-\alpha)(x-\beta) + c = 0$ are :

(a) a, c (b) b, c

(c) a, b (d) $a + c, b + c$

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-14.1

1 (b)	2. (c)	3. (d)	4. (a)	5. (b)	6. (c)	7. (a)	8. (b)	9. (c)	10. (a)
11. (d)	12. (b)	13. (c)	14. (a)	15. (a)	16. (c)	17. (b)	18. (b)	19. (c)	20. (a)
21. (a)	22. (a)	23. (a)	24. (a)	25. (b)	26. (b)	27. (a)	28. (b)	29. (c)	30. (d)
31. (b)	32. (b)	33. (c)	34. (c)	35. (c)	36. (b)	37. (c)	38. (b)	39. (b)	40. (d)

LEVEL-1

1 (c)	2. (b)	3. (c)	4. (c)	5. (b)	6. (b)	7. (c)	8. (c)	9. (b)	10. (b)
11. (b)	12. (b)	13. (d)	14. (c)	15. (c)	16. (c)	17. (c)	18. (b)	19. (b)	20. (c)
21. (c)	22. (b)	23. (a)	24. (a)	25. (b)	26. (c)	27. (c)	28. (c)	29. (b)	30. (d)
31. (c)	32. (b)	33. (d)	34. (a)	35. (b)	36. (a)	37. (a)	38. (a)	39. (d)	40. (a)
41. (c)	42. (c)	43. (b)	44. (d)	45. (c)	46. (b)	47. (c)	48. (b)	49. (d)	50. (c)
51. (c)	52. (d)	53. (c)	54. (c)	55. (d)	56. (d)	57. (c)			

LEVEL-2

1 (b)	2. (c)	3. (c)	4. (a)	5. (c)	6. (a)	7. (b)	8. (d)	9. (a)	10. (b)
11. (b)	12. (c)	13. (d)	14. (a)	15. (b)	16. (d)	17. (a)	18. (b)	19. (c)	20. (c)

Scanned by CamScanner

yourmathbook.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 14.1

1. $\because \quad x = \dfrac{-b \pm \sqrt{b^2 - 4ac}}{2a}$

$\therefore \quad x = \dfrac{7 \pm \sqrt{49 - 4 \times 15 \times (-36)}}{2 \times 15}$

$\Rightarrow \quad x = \dfrac{7 \pm 47}{30}$

$\therefore \quad x = \dfrac{54}{30}$ or $x = \dfrac{-40}{30}$

$x = \dfrac{9}{5}$ or $x = \dfrac{-4}{3}$

NOTE (i) The above problem can also be solved by factorization.
(ii) The same problem can also be solved through options.

2. $\because \quad x = \dfrac{-b \pm \sqrt{b^2 - 4ac}}{2a}$

$x = \dfrac{6 \pm \sqrt{36 - 4\sqrt{7} \times (-13\sqrt{7})}}{2 \times \sqrt{7}}$

$\Rightarrow \quad x = \dfrac{6 \pm \sqrt{36 + 364}}{2\sqrt{7}}$

$\Rightarrow \quad x = \dfrac{6 \pm 20}{2\sqrt{7}}$

$\therefore \quad x = \dfrac{13}{\sqrt{7}}$ or $x = \dfrac{-7}{\sqrt{7}}$

$\Rightarrow \quad x = \dfrac{13}{\sqrt{7}}$ or $x = -\sqrt{7}$

3. $6x^2 - 31x + 40 = 0$

$\Rightarrow \quad \left(x - \dfrac{8}{3}\right)\left(x - \dfrac{5}{2}\right) = 0$

$\Rightarrow \quad x = \dfrac{8}{3}, \dfrac{5}{2}$

4. Consider $\sqrt{\dfrac{y-3}{2y+1}} = t$

then, $6t^2 + 1 = 5t$

$\Rightarrow \quad 6t^2 - 5t + 1 = 0$ ...(i)

get the values of t by solving the eq. (i) and then substitute the value of t in the relation

$$t = \sqrt{\frac{y-3}{2y+1}} \quad \text{...(ii)}$$

Solve the eq. (i) and then get the values of t and subsequently y.

5. $(x+2)(x-5)(x-6)(x+1) = 144$

$\Rightarrow \quad [(x+2)(x-6)][(x-5)(x+1)] = 144$

$\Rightarrow \quad (x^2 - 4x - 12)(x^2 - 4x - 5) = 144$

$\Rightarrow \quad \{(x^2 - 4x - 5) - 7\}\{x^2 - 4x - 5\} = 144$

Let $t = x^2 - 4x - 5$ ...(i)

$\therefore \quad (t-7)(t) = 144$

$\Rightarrow \quad t^2 - 7t - 144 = 0$

$\Rightarrow \quad (t-16)(t+9) = 0$

$\Rightarrow \quad t = 16$ or $t = -9$

Substituting the values of t in eq. (i), we get

$$x = 7, -3, 2$$

6. Check through options
Alternatively, square both the sides twice.

7. $2\left(x^2 + \dfrac{1}{x^2}\right) - 3\left(x + \dfrac{1}{x}\right) - 1 = 0$

$\Rightarrow \quad 2\left[x^2 + \dfrac{1}{x^2} + 2 - 2\right] - 3\left(x + \dfrac{1}{x}\right) - 1 = 0$

$\Rightarrow \quad 2\left[\left(x + \dfrac{1}{x}\right)^2 - 2\right] - 3\left(x + \dfrac{1}{x}\right) - 1 = 0$

$\Rightarrow \quad 2\left(x + \dfrac{1}{x}\right)^2 - 3\left(x + \dfrac{1}{x}\right) - 5 = 0$

$\Rightarrow \quad 2t^2 - 3t - 5 = 0$ (Substituting $x + \dfrac{1}{x} = t$)

Now solve it and you will get

$$t = -1 \quad \text{and} \quad t = \frac{5}{2}$$

Now if $t = -1$, then $x + \dfrac{1}{x} = -1$.

$\Rightarrow \quad x^2 + 1 + x = 0$

$\Rightarrow \quad x^2 + x + 1 = 0$

$\therefore \quad x = \dfrac{-1 \pm \sqrt{1-4}}{2} = \dfrac{-1 \pm \sqrt{-3}}{2}$

and if $t = \dfrac{5}{2}$ then $x + \dfrac{1}{x} = \dfrac{5}{2}$

$\Rightarrow \quad 2x^2 - 5x + 2 = 0$

$\Rightarrow \quad x = \dfrac{1}{2}, 2$

8. Assume $\sqrt{\dfrac{x}{1-x}} = t$

$\therefore \quad \sqrt{\dfrac{1-x}{x}} = \dfrac{1}{t}$

$\therefore \quad t + \dfrac{1}{t} = \dfrac{13}{6}$

Now, solve it as in the previous problem.

9. $\sqrt{2x^2 - 2x + 1} = 2x - 3$

Square on both sides and simplify
(Hint: Type -3 problem)

Scanned by CamScanner

yoursmahboob.wordpress.com

10. **Hint:** Type-3 problem. It requires double squaring.
Alternatively : Go through options.

11. **Hint:** Type 6 problem.

12. $$\frac{1}{x+1}+\frac{1}{x+5}=\frac{1}{x+2}+\frac{1}{x+4}$$

$$\Rightarrow \left(\frac{1}{x+1}-\frac{1}{x+4}\right)+\left(\frac{1}{x+5}-\frac{1}{x+2}\right)=0$$

$$\Rightarrow \frac{3}{(x+1)(x+4)}-\frac{3}{(x+5)(x+2)}=0$$

$$\Rightarrow \frac{3[(x^2+7x+10)-(x^2+5x+4)]}{(x+1)(x+4)(x+5)(x+2)}=0$$

$$\Rightarrow (x^2+7x+10)-(x^2+5x+4)=0$$

$$\Rightarrow 2x+6=0 \Rightarrow x=-3$$

13. For equal roots $D=0$

i.e., $$b^2-4ac=0$$

$$\Rightarrow [-2(1+3k)]^2-4\times1\times7\times(3+2k)=0$$

Solve it and get the value of k.

14. $D=b^2-4ac$

$=4-4\times(-3)\times(-8)=-92$

15. $D=b^2-4ac=25-4\times1\times7=-3$

Since $D<0$, therefore roots are not real, *i.e.*, roots will be imaginary.

16. $$a^2x^2+abx-b^2=0$$

$$D=b^2-4ac=(ab)^2-4\times a^2\times(-b^2)$$

$$=(ab)^2+4a^2b^2$$

$$=(ab)^2[1+4]=(ab)^2(5)$$

$\therefore$ The roots are real and unequal

17. For non-real roots $D<0$

$$\therefore b^2-4ac<0$$

$$\therefore (-p)^2-4\times1\times q<0$$

$$\Rightarrow p^2-4q<0$$

$$\Rightarrow p^2<4q$$

18. $$4x^2-3kx+1=0$$

$$D=b^2-4ac=0$$

$$\therefore 9k^2-4\times1\times4=0$$

$$\Rightarrow k^2=\frac{16}{9} \Rightarrow k=\pm\frac{4}{3}$$

19. Let α, β be the roots of the equation, then

$$\alpha+\beta=\frac{1}{2}\alpha\beta$$

$$-\frac{b}{a}=\frac{1}{2}\cdot\frac{c}{a}$$

$$\Rightarrow -b=\frac{c}{2}$$

$$\Rightarrow (k+6)=\frac{2(2k-1)}{2}$$

$$\Rightarrow k=7$$

20. $$\alpha+\beta=\alpha\beta$$

$$\Rightarrow \frac{-b}{a}=\frac{c}{a} \Rightarrow -b=c$$

$$\therefore -2k=4$$

$$\Rightarrow k=-2$$

21. Since -4 is a root of $x^2-px-4=0$

$$\therefore (-4)^2-p(-4)-4=0$$

$$\Rightarrow p=-3$$

$\therefore$ The equation becomes $x^2+3x+k=0$

Since both the roots of this equation are equal.

$\therefore$ Sum of the roots $(\alpha+\alpha)=2\alpha=-3 \Rightarrow \alpha=-\frac{3}{2}$

$\therefore$ Product of the roots $(\alpha\cdot\alpha)=\alpha^2=(-3/2)^2=\frac{9}{4}=k$

$$\therefore k=\frac{9}{4}$$

22. $$\alpha^2+\beta^2=40$$

$$\Rightarrow (\alpha+\beta)^2-2\alpha\beta=40$$

$$\Rightarrow (8)^2-2k=40$$

$$\Rightarrow k=12$$

23. For equal roots, $D=0$

i.e., $$b^2-4ac=0$$

But now $$x^2+p(4x+p-1)+2=0$$

$$\Rightarrow x^2+4px+p^2-p+2=0$$

$$\Rightarrow x^2+4px+(p^2-p+2)=0$$

$$\therefore (4p)^2-4\times1\times(p^2-p+2)=0$$

$$\Rightarrow 16p^2-4p^2+4p-8=0$$

$$\Rightarrow 12p^2+4p-8=0$$

$$\Rightarrow 12p^2+12p-8p-8=0$$

$$\Rightarrow 12p(p+1)-8(p+1)=0$$

$$\Rightarrow (p+1)(12p-8)=0$$

$$\Rightarrow p=-1 \text{ or } p=\frac{8}{12}=\frac{2}{3}$$

24. $\alpha\beta=\frac{c}{a}=\frac{3}{3}=1$

25. $$x^2-3x+2=0$$

$$\Rightarrow x^2-x-2x+2=0$$

$$\Rightarrow (x-1)(x-2)=0$$

$$\Rightarrow \alpha=1 \text{ and } \beta=2$$

$$\therefore -\alpha=-1 \text{ and } -\beta=-2$$

$\therefore$ The required equation is

$$[x-(-\alpha)][x-(-\beta)]=0$$

$$\Rightarrow (x+1)(x+2)=0$$

$$\Rightarrow x^2+3x+2=0$$

26. **Method I.** If α and β be the roots of a quadratic equation, then the equation will be

$$(x-\alpha)(x-\beta)=0$$

$$\therefore (x-\sqrt{3})(x-2\sqrt{3})=0$$

$$\Rightarrow x^2-3\sqrt{3}x+6=0$$

Scanned by CamScanner

yourshahbaab.wordpress.com

Method II. The required equation

$$x^2 - (\alpha + \beta)x + (\alpha \cdot \beta) = 0$$

$$\Rightarrow \quad x^2 - (\sqrt{3} + 2\sqrt{3})x + (\sqrt{3} \cdot 2\sqrt{3}) = 0$$

$$\Rightarrow \quad x^2 - 3\sqrt{3}x + 6 = 0$$

27.

$$\alpha + \beta = \frac{-b}{a} = \frac{-1}{6}$$

$$\alpha\beta = \frac{c}{a} = -\frac{2}{6} = -\frac{1}{3}$$

$$\therefore \quad \frac{\alpha}{\beta} + \frac{\beta}{\alpha} = \frac{\alpha^2 + \beta^2}{\alpha\beta} = \frac{(\alpha + \beta)^2 - 2\alpha\beta}{\alpha\beta}$$

$$= \frac{(-1/6)^2 - 2(-1/3)}{-1/3}$$

$$= \frac{\frac{1}{36} + \frac{2}{3}}{-\frac{1}{3}} = \frac{\frac{25}{36}}{-\frac{1}{3}} = -\frac{25}{12}$$

Alternatively : $6x^2 + x - 2 = 0$

$$\Rightarrow \quad 6x^2 - 3x + 4x - 2 = 0$$

$$\Rightarrow \quad 3x(2x - 1) + 2(2x - 1) = 0$$

$$\Rightarrow \quad x = \frac{1}{2} \text{ or } x = -\frac{2}{3}$$

$$\therefore \quad \frac{\alpha}{\beta} + \frac{\beta}{\alpha} = \frac{1/2}{-2/3} + \frac{-2/3}{1/2}$$

$$= -\frac{3}{4} - \frac{4}{3} = -\frac{25}{12}$$

28. $\alpha + \beta = 10$ and $\alpha \cdot \beta = 10$

$$\Rightarrow \quad -\frac{b}{a} = 10 \text{ and } \frac{c}{a} = 10$$

$$\Rightarrow \quad \frac{5}{a} = 10$$

$$\Rightarrow \quad a = \frac{1}{2} \quad \therefore \frac{c}{1/2} = 10$$

$$\Rightarrow \quad c = 5$$

$$\therefore \quad a = \frac{1}{2} \text{ and } c = 5$$

29. $\alpha + \beta = -\frac{b}{a} = 1$ and $\alpha\beta = \frac{c}{a} = -4$

$$\therefore \quad \frac{1}{\alpha} + \frac{1}{\beta} - \alpha\beta = \frac{\alpha + \beta}{\alpha\beta} - \alpha\beta$$

$$= \frac{1}{-4} - (-4) = 4 - \frac{1}{4} = \frac{15}{4}$$

30. $\alpha + \beta = 2$ and $\alpha\beta = -1$

$$\therefore \quad \alpha^2\beta + \alpha\beta^2 = \alpha\beta(\alpha + \beta)$$

$$= 2(-1) = -2$$

31. Sum of roots $= (2\alpha + 1) + (2\beta + 1)$

$$= 2\alpha + 2\beta + 2$$

$$= 2(\alpha + \beta) + 2$$

and product of roots $= (2\alpha + 1)(2\beta + 1)$

$$= 4\alpha\beta + 2\alpha + 2\beta + 1$$

$$= 4\alpha\beta + 2(\alpha + \beta) + 1$$

Now since $\alpha + \beta = 1$

and $\alpha\beta = -2$

$\therefore$ Sum of roots $= 2(\alpha + \beta) + 2 = 2(1) + 2 = 4$

and product of roots $= 4\alpha\beta + 2(\alpha + \beta) + 1$

$$= 4 \times (-2) + 2(1) + 1$$

$$= -8 + 2 + 1 = -5$$

$\therefore$ Required equation is $x^2 - 4x - 5 = 0$.

32. $\alpha + \beta = \frac{6}{3} = 2$ and $\alpha\beta = \frac{4}{3}$

$$\therefore \quad \left(\frac{\alpha}{\beta} + \frac{\beta}{\alpha}\right) + 2\left(\frac{1}{\alpha} + \frac{1}{\beta}\right) + 3\alpha\beta$$

$$= \frac{\alpha^2 + \beta^2}{\alpha\beta} + 2\left(\frac{\alpha + \beta}{\alpha\beta}\right) + 3\alpha\beta$$

$$= \frac{(\alpha + \beta)^2 - 2\alpha\beta}{\alpha\beta} + 2\left(\frac{\alpha + \beta}{\alpha\beta}\right) + 3\alpha\beta$$

$$= \frac{4 - 8/3}{4/3} + 2\left(\frac{2}{4/3}\right) + 3 \times \frac{4}{3}$$

$$= \frac{4/3}{4/3} + 3 + 4 = 8$$

33.

$$\alpha + \beta = 5$$

$$\alpha - \beta = 1$$

$$\therefore \quad \alpha = 3 \text{ and } \beta = 2$$

$$\therefore \quad \alpha\beta = \frac{c}{a} = \frac{k}{1} = 3 \times 2 = 6$$

$$\Rightarrow \quad k = 6$$

34. Let the one root be α and other root be β, then $\beta = 2\alpha$.

$$\therefore \quad \alpha + \beta = 3\alpha = \frac{-b}{a} \quad \Rightarrow \quad \alpha = \frac{-b}{3a}$$

and $\alpha\beta = 2\alpha^2 = \frac{c}{a}$

$$\therefore \quad 2\alpha^2 = \frac{c}{a}$$

$$\Rightarrow \quad 2 \times \left(\frac{-b}{3a}\right)^2 = \frac{c}{a}$$

$$\Rightarrow \quad \frac{2b^2}{9a^2} = \frac{c}{a}$$

$$\Rightarrow \quad 2b^2 = 9ac$$

35. Let the base of the triangle be x cm, then $BC = x$ cm and hypotenuse $AC = (x + 2)$ cm and the perpendicular

$$AB = \frac{(x + 2) - 1}{2} = \frac{(x + 1)}{2}$$

[Let the length of AB be k, then $AC = 2k + 1 \Rightarrow k = \frac{AC - 1}{2}$]



$\therefore$ By Pythagorus theorem

$AB^2 + BC^2 = AC^2$

(see the figure)

$$\left(\frac{x + 1}{2}\right)^2 + x^2 = (x + 2)^2$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$\frac{x^2+1+2x}{4}+x^2=x^2+4+4x$$

$\Rightarrow$ $x^2+1+2x+4x^2=4x^2+16+16x$

$\Rightarrow$ $x^2-14x-15=0$

$\Rightarrow$ $(x-15)(x+1)=0$

$\Rightarrow$ $x=15$ cm ($\because x=-1$ cm is inadmissible)

$\Rightarrow$ base $=15$ cm

$\therefore$ perpendicular $=8$ cm

and hypotenuse $=17$ cm

and

36. Let the tens digit be x and unit digit be y. Then the two digit number $=10x+y$

but $x\times y=12 \Rightarrow y=\frac{12}{x}$

$\therefore$ the number is $\left(10x+\frac{12}{x}\right)$

Again $10x+\frac{12}{x}+9=10\times\left(\frac{12}{x}\right)+x$

$\Rightarrow$ $10x^2+12+9x=120+x^2$

$\Rightarrow$ $9x^2+9x-108=0$

$\Rightarrow$ $x^2+x-12=0$

$\Rightarrow$ $(x+4)(x-3)=0$

$\Rightarrow$ $x=-4, 3$

but x cannot be negative

$\therefore$ $x=3$ only.

$\therefore$ $y=\frac{12}{x}=\frac{12}{3}=4$

$\therefore$ the number $=10x+y=10\times3+4=34$

37. Let the usual speed of plane be x km/hr

$\therefore$ Usual time taken $=\frac{1600}{x}$ hr

New speed $=(x+400)$ km/hr

and the new time $=\frac{1600}{x}-\frac{40}{60}=\left(\frac{1600}{x}-\frac{2}{3}\right)$ hr

$\therefore$ Distance = speed $\times$ time

$$1600=(x+400)\left(\frac{1600}{x}-\frac{2}{3}\right)$$

$$1600=1600-\frac{2x}{3}+\frac{640000}{x}-\frac{800}{3}$$

$\Rightarrow$ $4800x=4800x-2x^2+1920000-800x$

$\Rightarrow$ $2x^2-1920000+800x=0$

$\Rightarrow$ $x^2-960000+400x=0$

$\Rightarrow$ $x^2+400x-960000=0$

$\Rightarrow$ $x^2+1200x-800x-960000=0$

$\Rightarrow$ $x(x+1200)-800(x+1200)=0$

$(x+1200)(x-800)=0$

$\Rightarrow$ $x=800$ km/hr ($\because x=-1200$ is inadmissible)

38. Let the two consecutive odd numbers be x and $x+2$

$\therefore$ $x^2+(x+2)^2=290$

$\Rightarrow$ $x^2+x^2+4+4x=290$

$\Rightarrow$ $2x^2+4x+4=290$

$\Rightarrow$ $x^2+2x+2=145$

$\Rightarrow$ $x^2+2x-143=0$

$\Rightarrow$ $(x+13)(x-11)=0$

$\Rightarrow$ $x=11$ or $x=-13$, but x is positive

$\therefore$ $x+2=13$

$\therefore$ Sum of the numbers $=11+13=24$

39. Let the shopkeeper buys x books

$\therefore$ Rate of the book $=\frac{80}{x}$

the new number of books $=(x+4)$

$\therefore$ the new price $=\frac{80}{(x+4)}$

$\therefore$ $\frac{80}{(x+4)}+1=\frac{80}{x}$

$\Rightarrow$ $\left(\frac{1}{x}-\frac{1}{(x+4)}\right)=\frac{1}{80}$

$\Rightarrow$ $\frac{4}{x^2+4x}=\frac{1}{80}$

$\Rightarrow$ $x^2+4x-320=0$

$\Rightarrow$ $(x+20)(x-16)=0$

$\Rightarrow$ $x=16$, ($x=-20$, is inadmissible)

$\therefore$ He bought 16 books.

40. $x^2+(x+4)^2=656$

$\Rightarrow$ $x^2+x^2+16+8x=656$

$\Rightarrow$ $x^2+4x-320=0$

$\Rightarrow$ $(x+20)(x-16)=0$

$\Rightarrow$ $x=16$, ($x=-20$ is inadmissible)

$\therefore$ Sides of the square are $x=16$ cm

and $(x+4)=20$ cm.

Scanned by CamScanner

yourshahbood.wordpress.com

LEVEL 1

1. $y_{min.} = \frac{-b^2 + 4ac}{4a}$ at $x = -\frac{b}{2a}$

$\therefore$ $y_{min.} = \frac{-p^2 + 4 \times 1 \times q}{4 \times 1} = \frac{4q - p^2}{4}$

Now, since p and q are the roots of the equation $x^2 + px + q = 0$.

$\therefore$ $p + q = -p \Rightarrow q = -2p$

and $pq = q \Rightarrow p = 1$ $(\because q \neq 0)$

$\therefore$ $q = -2$

$\therefore$ $y_{min} = \frac{4q - p^2}{4} = \frac{4 \times (-2) - (1)^2}{4} = -\frac{9}{4}$.

2. Let α, β be the roots of the given equation, then, $\alpha + \beta = p - 2$ and $\alpha\beta = -(p + 1)$.

Now, $\alpha^2 + \beta^2 = (\alpha + \beta)^2 - 2\alpha\beta = (p - 2)^2 + 2(p + 1)$

$= p^2 - 2p + 6 = (p - 1)^2 + 5$

Clearly $\alpha^2 + \beta^2 \geq 5$. So minimum value of $\alpha^2 + \beta^2$ is 5, which attains at $p = 1$.

3. Let $f(x) = x^2 + 2(p + 1)x + 9p - 5$. Let α, β be the roots of $f(x) = 0$. The equation $f(x) = 0$ will have both negative roots, if

(i) $D \geq 0$ (ii) $\alpha < 0, \beta < 0$, *i.e.*, $(\alpha + \beta) < 0$

(iii) $f(0) > 0$

Now, $D \geq 0 \Rightarrow 4(p + 1)^2 - 36p + 20 \geq 0$

$\Rightarrow p^2 - 7p + 6 \geq 0$

$\Rightarrow (p - 6)(p - 1) \geq 0$

$\Rightarrow p \leq 1$ or $p \geq 6$ ...(i)

$\alpha + \beta < 0 \Rightarrow -2(p + 1) < 0$

$\Rightarrow p + 1 > 0 \Rightarrow p > -1$ ...(ii)

and $f(0) > 0 \Rightarrow 9p - 5 > 0$

$\Rightarrow p > \frac{5}{9}$ ...(iii)

from (i), (ii) and (iii) we get $p \geq 6$.

4. Let α_1, β_1 be the roots of $ax^2 + bx + c = 0$ and α_2, β_2 be the roots of $px^2 + qx + r = 0$, then,

$\frac{\alpha_1}{\beta_1} = \frac{\alpha_2}{\beta_2} \Rightarrow \frac{\alpha_1 + \beta_1}{\alpha_1 - \beta_1} = \frac{\alpha_2 + \beta_2}{\alpha_2 - \beta_2}$

$\Rightarrow \frac{(\alpha_1 + \beta_1)^2}{(\alpha_1 - \beta_1)^2} = \frac{(\alpha_2 + \beta_2)^2}{(\alpha_2 - \beta_2)^2}$

$\Rightarrow \frac{(\alpha_1 + \beta_1)^2}{(\alpha_1 + \beta_1)^2 - 4\alpha_1\beta_1} = \frac{(\alpha_2 + \beta_2)^2}{(\alpha_2 + \beta_2)^2 - 4\alpha_2\beta_2} = \frac{b^2/a^2}{\frac{b^2 - 4ac}{a^2}}$

$= \frac{q^2/p^2}{\frac{q^2 - 4rp}{p^2}} = \frac{b^2}{D_1} = \frac{q^2}{D_2}$

$\Rightarrow \frac{D_1}{D_2} = \frac{b^2}{q^2}$

Alternatively : Let 2, 3 be the roots of the equation $ax^2 + bx + c = 0$

$\therefore$ the equation is $x^2 - 5x + 6 = 0$

$\therefore$ $a = 1, \quad b = -5$ and $c = 6$

$\therefore$ $D_1 = b^2 - 4ac = 25 - 4 \times 1 \times 6 = 1$

Again, if 4, 6 be the roots of the equation $px^2 + qx + r = 0$, then the equation will be $x^2 - 10x + 24 = 0$

$\Rightarrow$ $p = 1, \quad q = -10$ and $r = 24$

$\therefore$ $D_2 = q^2 - 4pr = 100 - 4 \times 1 \times 24 = 4$

$\therefore$ $\frac{D_1}{D} = \frac{1}{4}$.

Now, check through option, only option (c) is correct as

$\frac{b^2}{q^2} = \frac{(-5)^2}{(-10)^2} = \frac{1}{4} = \frac{D_1}{D_2}$.

Caution : $\frac{\alpha_1}{\beta_1} \neq \frac{\alpha_1}{\alpha_2}$, when solving through numerical values.

5. The given equations are :

$x^2 + px + qr = 0$ ...(i)

$x^2 + qx + rp = 0$ ...(ii)

and $x^2 + rx + pq = 0$ ...(iii)

Let α, β be the roots of (i), β, γ be roots of (ii) and γ, α be the roots of (iii). Since β is a common root of (i) and (ii)

$\therefore$ $\beta^2 + p\beta + qr = 0$

and $\beta^2 + q\beta + rp = 0$

$\Rightarrow$ $(p - q)\beta + r(q - p) = 0 \Rightarrow \beta = r$

Now, $\alpha\beta = qr \Rightarrow \alpha r = qr \Rightarrow \alpha = q$

Since β and γ are roots of (ii). Therefore

$\beta r = rp \Rightarrow \gamma r = rp \Rightarrow \gamma = p$

$\therefore$ $\alpha + \beta + \gamma = q + r + p = p + q + r$

NOTE $\alpha + \beta + \gamma$ can also be equal to 0 and $-\frac{1}{2}(p + q + r)$.

6. By hypothesis,

$\frac{\alpha}{\alpha - 1} + \frac{\alpha + 1}{\alpha} = -\frac{b}{a}$ and $\frac{\alpha}{\alpha - 1} \cdot \frac{\alpha + 1}{\alpha} = \frac{c}{a}$

$\Rightarrow \frac{2\alpha^2 - 1}{\alpha^2 - \alpha} = -\frac{b}{a}$ and $\alpha = \frac{c + a}{c - a}$

$\Rightarrow (c + a)^2 + 4ac = -2b(c + a)$

$\Rightarrow (c + a)^2 + 2b(a + c) + b^2 = b^2 - 4ac$

$\Rightarrow (a + b + c)^2 = b^2 - 4ac$

7. One double root means a single root appears two times *i.e.*, two roots are equal.

$\therefore$ $D = 0 \Rightarrow (2)^2 - 4a \cdot 1 = 0$

$\Rightarrow a = 1$.

8. Let α, β be the roots of a quadratic equation and α^2, β^2 be the roots of another quadratic, Since the quadratic remains the same, we have

$\alpha + \beta = \alpha^2 + \beta^2$ ...(i)

and $\alpha\beta = \alpha^2\beta^2$ ...(ii)

Now, $\alpha\beta = \alpha^2\beta^2 \Rightarrow \alpha\beta(\alpha\beta - 1) = 0$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\alpha = 0$ or $\beta = 0$ or $\alpha\beta = 1$.

$\Rightarrow$ If $\alpha = 0$, then $\beta = \beta^2$ [putting $\alpha = 0$ in (i)]

$\Rightarrow$ $\beta(1-\beta) = 0 \Rightarrow \beta = 0, \beta = 1$.

Thus, we get two sets of values of α and β viz. $\alpha = 0, \beta = 0$ and $\alpha = 0, \beta = 1$. Now, if $\alpha\beta = 1$,

then $\alpha + \frac{1}{\alpha} = \alpha^2 + \frac{1}{\alpha^2}$ [Putting $\beta = \frac{1}{\alpha}$ in (i)]

$\Rightarrow$ $\alpha + \frac{1}{\alpha} = \left(\alpha + \frac{1}{\alpha}\right)^2 - 2$

$\Rightarrow$ $\left(\alpha + \frac{1}{\alpha}\right)^2 - \left(\alpha + \frac{1}{\alpha}\right) - 2 = 0$

$\Rightarrow$ $\alpha + \frac{1}{\alpha} = 2$ or $\alpha + \frac{1}{\alpha} = -1$

$\Rightarrow$ $\alpha = 1$ or $\alpha = \omega, \omega^2$

Putting $\alpha = 1$, in $\alpha\beta = 1$, we get $\beta = 1$, and putting $\alpha = \omega$ in $\alpha\beta = 1$, we get $\beta = \omega^2$

Putting $\alpha = \omega^2$ in $\alpha\beta = 1$, we get $\beta = \omega$. Thus, we get four sets of values of α, β viz., $\alpha = 0, \beta = 0$, $\alpha = 0, \beta = 1$, $\alpha = \omega, \beta = \omega^2$, $\alpha = 1, \beta = 1$.

Thus, there are four quadratics which remain unchanged by squaring their roots.

9. Let $x = \sqrt{6 + \sqrt{6 + \ \ldots \infty}} \Rightarrow x^2 = x + 6 \Rightarrow x^2 - x - 6 = 0 \Rightarrow x = 3, -2$, but $x > 0$.

10. The best way is to consider some values of the roots α, β and γ.

Let $\alpha = 2$, $\beta = 3$ and $\gamma = 4$, then

$(x-\alpha)(x-\beta)(x-\gamma) = 0$

$\Rightarrow$ $(x-2)(x-3)(x-4) = 0$

$\Rightarrow$ $x^3 - 9x^2 + 26x - 24 = 0$

$\Rightarrow$ $a_0 = -9$

$a_1 = 26$

$a_2 = -24$

Now, $(1-\alpha^2)(1-\beta^2)(1-\gamma^2) = (1-4)(1-9)(1-16)$

$= -3 \times -8 \times -15 = -360$

Now, go through options and verify.

Consider option (b)

$(1 + a_1)^2 - (a_0 + a_2)^2 = (1 + 26)^2 - (-9 - 24)^2$

$= (27)^2 - (33)^2$

$= (27 + 33)(27 - 33)$

$= 60 \times (-6) = -360$

Hence option (b) is correct.

11. $k = \frac{x^2 - x + 1}{x^2 + x + 1}$

$\Rightarrow$ $kx^2 + kx + k = x^2 - x + 1$

$\Rightarrow$ $(k-1)x^2 + (k+1)x + k - 1 = 0$

Since x is real, the discriminant

$D = (k+1)^2 - 4(k-1)^2 \geq 0$

$\Rightarrow$ $(3k-1)(-k+3) \geq 0$

$\Rightarrow$ $\left(k - \frac{1}{3}\right)(k-3) \leq 0$

$\Rightarrow$ $\frac{1}{3} \leq k \leq 3$

12. Let $x = \sqrt{2 + \sqrt{2 + \sqrt{2 + \sqrt{2 + \ldots \infty}}}}$

$\therefore$ $x = \sqrt{2 + x}$

$\Rightarrow$ $x^2 = 2 + x$

$\Rightarrow$ $x^2 - x - 2 = 0$

$\Rightarrow$ $x = \frac{1 \pm \sqrt{9}}{2} = \frac{1 \pm 3}{2} = 2, -1$

$\because$ $x > 0$, $\therefore x = 2$

13. We have, $\alpha + \beta + \gamma = 0$

$\therefore$ $\beta + \gamma = -\alpha$, $\gamma + \alpha = -\beta$ and $\alpha + \beta = -\gamma$.

$\therefore$ The equation whose roots are $-\alpha, -\beta, -\gamma$ can be obtained by replacing x by $-x$ in the given equation.

Therefore the required equation is :

$(-x)^3 - 3(-x) + 11 = 0$

or $x^3 - 3x - 11 = 0$

14. Let α be a common root of the two given equations, then $\alpha^2 - 3a\alpha + 35 = 0$ and $\alpha^2 - a\alpha - 21 = 0$. On subtracting we get $-2a\alpha + 56 = 0$ or $\alpha = \frac{28}{a}$.

As α is a root of $x^2 - ax - 21 = 0$,

$\therefore$ $\left(\frac{28}{a}\right)^2 - a\left(\frac{28}{a}\right) - 21 = 0$

or $a^2 = 4^2$ or $a = \pm 4$

$\therefore a > 0$, we get $a = 4$

15. $(\alpha + \beta + \gamma)^2 = \alpha^2 + \beta^2 + \gamma^2 + 2(\alpha\beta + \beta\gamma + \gamma\alpha)$

$4 = 6 + 2(\alpha\beta + \beta\gamma + \gamma\alpha)$

$\Rightarrow$ $\alpha\beta + \beta\gamma + \gamma\alpha = -1$

Also, $\alpha^3 + \beta^3 + \gamma^3 - 3\alpha\beta\gamma$

$= (\alpha + \beta + \gamma)(\alpha^2 + \beta^2 + \gamma^2 - \alpha\beta - \beta\gamma - \gamma\alpha)$

$8 - (3\alpha\beta\gamma) = 2(6 + 1)$

$\Rightarrow$ $\alpha\beta\gamma = -2$

Now, $(\alpha^2 + \beta^2 + \gamma^2)^2 = \Sigma\alpha^4 + 2\Sigma\beta^2\gamma^2$

$= \Sigma\alpha^4 + 2[(\Sigma\beta\gamma)^2 - 2\alpha\beta\gamma(\Sigma\gamma)]$

$\Rightarrow$ $\Sigma\alpha^4 = 36 - 2[(-1)^2 - 2(-2)(2)] = 18$

16. The roots of the given equation will be of opposite signs if they are real and their product is negative, *i.e.*,

$D \geq 0$ and product of roots < 0

$\Rightarrow$ $(a^3 + 8a - 1)^2 - 8(a^2 - 4a) \geq 0$

and $\frac{a^2 - 4a}{2} < 0$

$\Rightarrow$ $a^2 - 4a < 0$

[$\because a^2 - 4a < 0 \Rightarrow (a^3 + 8a - 1)^2 - 8(a^2 - 4a) \geq 0$]

$\Rightarrow$ $0 < a < 4$.

17. We have $\alpha + \beta = -\frac{b}{a}$, $\alpha\beta = \frac{c}{a}$

and $\alpha + k + \beta + k = -\frac{q}{p}$

and $(\alpha + k)(\beta + k) = \frac{r}{p}$

Scanned by CamScanner

yourSmartboob.wordpress.com

$$\Rightarrow \quad \alpha+\beta+2k=-\frac{q}{p}$$

$$\Rightarrow \quad -\frac{b}{a}+2k=-\frac{q}{p} \qquad \left(\because\ \alpha+\beta=-\frac{b}{a}\right)$$

$$\therefore \quad k=\frac{1}{2}\left(\frac{b}{a}-\frac{q}{p}\right)$$

NOTE The problem can also be solved by assuming some appropriate values.

18. Let $f(x)=ax^2+bx+c$. It is given that α, β are real roots of $f(x)=0$. So, k lies between α and β, if

$$af(k)<0 \quad \Rightarrow \quad a(ak^2+bk+c)<0$$

$$\Rightarrow \quad a^2k^2+abk+ac<0$$

19. The given equation will have equal roots iff $D=0$.

$$\Rightarrow \quad (27\times 3^{1/k}-15)^2-144=0$$

$$\Rightarrow \quad 27\times 3^{1/k}-15=\pm 12$$

$$\Rightarrow \quad 27\times 3^{1/k}=27 \text{ or } 3$$

$$\Rightarrow \quad 3^{1/k}=1 \quad \text{or} \quad 3^{1/k}=\frac{1}{9}$$

$$\Rightarrow \quad \frac{1}{k}=0 \text{ or } -2$$

But $\frac{1}{k}$ cannot be zero. So $k=-\frac{1}{2}$.

20. Let $f(x)=x^2-2(a-1)x+(2a+1)=0$.
Then, $f(x)=0$ will have both roots positive, if
(i) $D>0$ (ii) Sum of the roots >0 and (iii) $f(0)>0$
Now, $D\geq 0 \Rightarrow 4(a-1)^2-4(2a+1)\geq 0$

$$\Rightarrow \quad a^2-4a\geq 0 \quad \Rightarrow \quad a\leq 0 \quad \text{or} \quad a\geq 4 \qquad \ldots(i)$$

Sum of the roots >0

$$\Rightarrow \quad 2(a-1)>0 \quad \Rightarrow \quad a>1 \qquad \ldots(ii)$$

and $f(0)>0$

$$\Rightarrow \quad (2a+1) \quad \Rightarrow \quad a>-\frac{1}{2} \qquad \ldots(iii)$$

From (i), (ii) and (iii) we get $a\geq 4$.
Hence, the least integral value of a is 4.

21.

$$2^{3x^2-7x+4}=1=2^0$$

$$\Rightarrow \quad 3x^2-7x+4=0$$

$$\Rightarrow \quad 3x^2-3x-4x+4=0$$

$$\Rightarrow \quad 3x(x-1)-4(x-1)=0$$

$$\Rightarrow \quad x=1 \quad \text{or} \quad x=\frac{4}{3}$$

$$\therefore \quad x=1, \frac{4}{3}$$

22.

$$2|x|^2-5|x|+2=0$$

$$\Rightarrow \quad (2|x|-1)(|x|-2)=0$$

$$\therefore \quad |x|=\frac{1}{2}, 2$$

$$\therefore \quad x=\pm\frac{1}{2}, \pm 2$$

23.

$$(x-1)^2+(x-2)^2+(x-3)^2=0 \qquad \ldots(i)$$

It is possible only when $x-1=0,\ x-2=0,\ x-3=0$

$$x=1, \quad x=2, \quad x=3$$

but $x=1, 2, 3$ do not satisfy eq. (i).

24.

$$\sqrt{x+1}-\sqrt{x-1}=\sqrt{4x-1}$$

$$\therefore \quad x+1\geq 0, \quad x-1\geq 0, \quad 4x-1\geq 0$$

All these inequalities are satisfied when $x\geq 1$. Squaring both the sides of the equation we get

$$(x+1)+(x-1)-2\sqrt{x^2-1}=4x-1$$

$$\Rightarrow \quad 2\sqrt{x^2-1}=1-2x$$

Squaring again, we get

$$4(x^2-1)=1-4x+4x^2$$

$$\Rightarrow \quad x=\frac{5}{4}$$

For $x=\frac{5}{4}$, $\quad \text{LHS}=\sqrt{\frac{5}{4}+1}-\sqrt{\frac{5}{4}-1}=1$

and $\quad \text{RHS}=\sqrt{4\left(\frac{5}{4}\right)-1}=\sqrt{4}=2$

but $\quad \text{LHS}\neq\text{RHS}$

$\therefore\ x=\frac{5}{4}$ is not a root of the equation.

25.

$$\alpha+\beta=\frac{3}{8}, \quad \alpha\beta=\frac{27}{8}$$

$$\therefore \quad \left(\frac{\alpha^2}{\beta}\right)^{1/3}+\left(\frac{\beta^2}{\alpha}\right)^{1/3}=\left(\frac{\alpha^3}{\alpha\beta}\right)^{1/3}+\left(\frac{\beta^3}{\alpha\beta}\right)^{1/3}$$

$$=\frac{\alpha+\beta}{(\alpha\beta)^{1/3}}=\frac{3/8}{(27/8)^{1/3}}$$

$$=\frac{3/8}{3/2}=\frac{1}{4}$$

26. The quadratic equation $3x^2+2(a^2+1)x+(a^2-3a+2)=0$ will have two roots of opposite sign if it has real roots and the product of the roots is negative, *i.e.*, if

$$D\geq 0 \quad \text{and} \quad \alpha\cdot\beta<0$$

$$\Rightarrow \quad 4(a^2+1)^2-12(a^2-3a+2)\geq 0$$

and $\quad \frac{a^2-3a+2}{3}<0$

$$\therefore \quad a^2-3a+2<0,$$

i.e., if $\quad (a-1)(a-2)<0 \quad \text{or} \quad 1<a<2$

27. Let $\quad y=\frac{(x-a)(x-b)}{(x-c)}$

$$\Rightarrow \quad x^2-(a+b+y)x+ab+cy=0$$

Since x is real, then $D\geq 0$

$$\Rightarrow \quad (a+b+y)^2-4(ab+cy)\geq 0$$

$$\Rightarrow \quad y^2+2(a+b-2c)y+(a+b)^2-4ab\geq 0$$

$$\Rightarrow \quad y^2+2(a+b-2c)y+(a-b)^2\geq 0 \qquad \ldots(i)$$

Since y takes all real values (i) is possible iff

$$4(a+b-2c)^2-4(a-b)^2<0$$

$$\Rightarrow \quad (a+b-2c+a-b)(a+b-2c-a+b)<0$$

$$\Rightarrow \quad 4(a-c)(b-c)<0$$

$$\Rightarrow \quad (a-c)(b-c)<0$$

This is possible if c lies between a and b, that is if $a<c<b$ or $a>c>b$.

Scanned by CamScanner

yoursmahboob.wordpress.com

$$D = b^2 - 4ac$$

28. ∵ and, if $D \geq 0$, then the roots of the equation are given by

$$x = \frac{-b \pm \sqrt{D}}{2a}$$

As $D = b^2 - 4ac < b^2$ (∵ $a > 0$ and $c > 0$)

It follows that the roots of the quadratic equation are negative.

In case $D < 0$, then the roots of the equation are given by

$$x = \frac{-b \pm i\sqrt{-D}}{2a}$$

which have negative real parts.

29. It is very obvious that at $x = 3$ the given expression satisfies. Now, $y = 3^{x-1}$ and $y = 5^{x-1}$ are both increasing function of x (exponential functions with base greater than 1). Therefore their sum $y = 3^{x-1} + 5^{x-1}$ is also an increasing function of x. It means for $x < 3$, $y = 3^{x-1} + 5^{x-1} < 34$ and for $x > 3$, $y = 3^{x-1} + 5^{x-1} > 34$.



Thus, the equation has no other solution.

30. ∵ $$2 - \sqrt{3} = \frac{1}{2 + \sqrt{3}}$$

∴ the given equation can be expressed as

$$(2+\sqrt{3})^{x^2-2x+1} + \frac{1}{(2+\sqrt{3})^{x^2-2x-1}} = 2(2+\sqrt{3}) \quad \ldots(i)$$

Let us put $y = (2+\sqrt{3})^{x^2-2x+1}$, then the eq. (i) can be expressed as

$$y + \frac{(2+\sqrt{3})^2}{y} = 2(2+\sqrt{3})$$

$$\Rightarrow \quad y^2 - 2(2+\sqrt{3})y + (2+\sqrt{3})^2 = 0$$

$$\Rightarrow \quad [y - (2+\sqrt{3})]^2 = 0 \Rightarrow y = 2+\sqrt{3}$$

$$\therefore \quad (2+\sqrt{3})^{x^2-2x+1} = (2+\sqrt{3})$$

$$\Rightarrow \quad x^2 - 2x + 1 = 1 \Rightarrow x(x-2) = 0$$

$$\Rightarrow \quad x = 0 \text{ or } 2.$$

31. For $a = 0$ or $a = \frac{1}{2}$ one of the quadratic equation becomes linear, So $a \neq 0$, $a \neq \frac{1}{2}$.

Hence the only answer is $a = \frac{2}{9}$

32. Let $f(x) = x^2 - 2(4k-1)x + 15k^2 - 2k - 7$. Then $f(x) > 0 \Rightarrow D < 0$ [∵ Coefficient of $x^2 > 0$]

$$\Rightarrow \quad 4(4k-1)^2 - 4(15k^2 - 2k - 7) < 0$$

$$\Rightarrow \quad k^2 - 6k + 8 < 0 \Rightarrow 2 < k < 4$$

33. According to the given condition a lies between the roots.

Let $f(x) = 2x^2 - 2(2a+1)x + a(a+1)$.

For a to lie between the roots, we must have $D \geq 0$ and $f(a) < 0$

Now, $D \geq 0 \Rightarrow 4(2a+1)^2 - 8a(a+1) \geq 0$

$$\Rightarrow \quad 8\left[a^2 + a + \frac{1}{2}\right] \geq 0, \quad \text{which is always true}$$

$$\therefore \quad f(a) < 0 \Rightarrow 2a^2 - 2a(2a+1) + a(a+1) < 0$$

$$\Rightarrow \quad -a^2 - a < 0 \Rightarrow a^2 + a > 0$$

$$\Rightarrow \quad a > 0 \text{ or } a < -1$$

34. Let α, β and γ be the roots of the given equation such that $\alpha = -\beta$. Then

$$\alpha + \beta + \gamma = a \Rightarrow \gamma = a$$

Since γ is a root of the given equation, so it satisfies the equation, *i.e.*,

$$\gamma^3 - a\gamma^2 + b\gamma - c = 0$$

$$\Rightarrow \quad a^3 - a^3 + ab - c = 0 \Rightarrow ab = c$$

35. Let $f(x) = ax^2 + bx + c$. Since 1 lies outside the roots of $f(x) = 0$. So,

$$af(1) > 0 \Rightarrow f(1) > 0 \quad (\because a > 0)$$

$$\Rightarrow \quad a + b + c > 0$$

36. $$x - \frac{1}{x^2-4} = 2 - \frac{1}{x^2-4}$$

Here $x^2 - 4 \neq 0$

$$\Rightarrow \quad x \neq \pm 2 \Rightarrow (x-2) = 0$$

$\Rightarrow x = 2$, which is inadmissible.

37. $$2^{x/2} \div (\sqrt{2}+1)^x = (5+2\sqrt{2})^{x/2}$$

$$\Rightarrow \quad \left(\frac{\sqrt{2}}{\sqrt{5+2\sqrt{2}}}\right)^x + \left(\frac{\sqrt{2}+1}{\sqrt{5+2\sqrt{2}}}\right)^x = 1$$

which is of the form

$$\cos^x \alpha + \sin^x \alpha = 1$$

$$\therefore \quad x = 2.$$

38. $$xy = 2(x+y) \Rightarrow y(x-2) = 2x$$

$\therefore y = \frac{2x}{x-2}$ but $x, y \in N$ by trial, we get $x = 3, 4, 6$

$$\therefore \quad y = 6, 4, 3 \qquad \text{but } x \leq y$$

$$\therefore \quad x = 3, 4 \text{ and } y = 6, 4$$

Thus two solutions are possible

39. Let the roots be α and $\frac{1}{\alpha}$

$$\therefore \quad \alpha \cdot \frac{1}{\alpha} = \frac{c}{a} \Rightarrow c = a$$

$$\because \quad (|a| - |b|)^2 \geq 0$$

$$\text{or} \quad |a| \geq |b|$$

$$\text{but} \quad c = a \quad \therefore |c| \geq |b|$$

40. $$|x+1||x-1| = a^2 - 2a - 3$$

$$\Rightarrow \quad |x^2 - 1| = a^2 - 2a - 3$$

$$\Rightarrow \quad x^2 - 1 = \pm (a^2 - 2a - 3)$$

$$\text{but} \quad a^2 - 2a - 3 \geq 0$$

$$\therefore \quad x^2 - 1 = a^2 - 2a - 3$$

Scanned by CamScanner

yousmahboob.wordpress.com

$\Rightarrow \quad x^2 = a^2 - 2a - 2, \quad -a^2 + 2a + 4 \geq 0$

for real solutions,

$a^2 - 2a - 2 \geq 0$ and $-a^2 + 2a + 4 \geq 0$,

Thus we have $a \in (-\infty, -1] \cup [3, \infty)$

41. Since k is a prime number

$\therefore \quad k \neq 0$

Again $p = 0$, $qk^{1/3} = 0$ and $rk^{2/3} = 0$

$\Rightarrow \quad p = 0$ and $q = 0$ and $r = 0$

$\therefore \quad p = q = r = 0$

42. The equation $x^4 + 2px^3 + x^2 + 2px + 1 = 0$ cannot have 0 as a root. Dividing by x^2, we can write as

$$x^2 + \frac{1}{x^2} + 2p\left(x + \frac{1}{x}\right) + 1 = 0$$

$$\Rightarrow \quad \left(x + \frac{1}{x}\right)^2 + 2p\left(x + \frac{1}{x}\right) - 1 = 0 \qquad \ldots(1)$$

Put $x + \frac{1}{x} = y$. Then we can write eq. (1) as

$$y^2 - 2py - 1 = 0 \qquad \ldots(2)$$

Since $D > 0$, *i.e.*, $4p^2 + 4 > 0$, hence eq. (2) has two distinct real roots. These roots are

$$y = \frac{-2p \pm \sqrt{4p^2 + 4}}{2} = -p \pm \sqrt{p^2 + 1}$$

Since $-p + \sqrt{p^2 + 1} > 0$, the equation

$$x + \frac{1}{x} = -p + \sqrt{p^2 + 1} \qquad \ldots(3)$$

has either positive roots or non-real complex roots.

Since $-p - \sqrt{p^2 + 1} < 0$, both the roots of the equation $x + \frac{1}{x} = -p - \sqrt{p^2 + 1}$ are negative.

We can write eq. (3) as

$$\left(\sqrt{-x} - \frac{1}{\sqrt{-x}}\right)^2 = p - 2 + \sqrt{p^2 + 1}$$

As $\left(\sqrt{-x} - \frac{1}{\sqrt{-x}}\right)^2 > 0$, we must have,

$p - 2 + \sqrt{p^2 + 1} > 0$, *i.e.*, $\sqrt{p^2 + 1} > |2 - p|$.

Since $p^2 + 1 = (p - 2)^2 + 4a - 3$,

$\sqrt{p^2 + 1} > |2 - p|$ iff $4p - 3 > 0$.

i.e., iff $p > \frac{3}{4}$.

43. **Case 1.** Suppose $x \geq a$. Thus the given equation becomes

$$x^2 - 2a(x - a) - 3a^2 = 0$$

$$\Rightarrow \quad x^2 - 2ax - a^2 = 0$$

$$\Rightarrow \quad x = \frac{2a \pm 2\sqrt{2}a}{2} = (1 \pm \sqrt{2})a$$

As $a < 0$ and $1 + \sqrt{2} > 1$, $(1 + \sqrt{2})a < a$.

Therefore, $x \neq 1(1 + \sqrt{2})a$.

Again as $1 - \sqrt{2} < 1$, $(1 - \sqrt{2})a > a$.

$\therefore \quad x = (1 - \sqrt{2})a$.

Case 2. Suppose $x < a$, then the given equation becomes

$$x^2 - 2a(a - x) - 3a^2 = 0$$

$$x^2 + 2ax - 5a^2 = 0$$

$$\Rightarrow \quad x = \frac{-2a \pm \sqrt{24}a}{2} = (-1 \pm \sqrt{6})a$$

As $a < 0$, $-1 - \sqrt{6} < 0 < 1$, so $(-1 - \sqrt{6})a > a$,

$\therefore \quad x \neq (-1 - \sqrt{6})a$ (∵ $x < a$)

Again, as $a < 0$, $-1 + \sqrt{6} > 1$ and $(-1 + \sqrt{6})a < a$

$\therefore \quad x = (-1 + \sqrt{6})a = (\sqrt{6} - 1)a$.

44. **Case 1.** Let $x + 2 \geq 0$.

$\therefore |x + 2| = x + 2$ and the equation becomes

$$2^{x+2} - 2^{x+1} - 1 - |2^{x+1} - 1| = 0$$

$$\Rightarrow \quad 2^{x+1}(2 - 1) - 1 - |2^{x+1} - 1| = 0$$

$$\Rightarrow \quad 2^{x+1} - 1 = |2^{x+1} - 1|$$

$$\Rightarrow \quad 2^{x+1} - 1 \geq 0 \text{ or } x + 1 \geq 0 \text{ or } x \geq -1$$

Case 2. Let $x + 2 < 0$.

$\therefore \quad |x + 2| = -(x + 2)$ and the equation becomes

$$2^{-(x+2)} - |2^{x+1} - 1| = 2^{x+1} + 1 \qquad \ldots(i)$$

Put $2^{x+1} = y$. Then eq. (i) becomes

$$\frac{1}{2y} - |y - 1| = y + 1$$

or $\quad 2y^2 + 2y + |y - 1|2y = 1 \qquad \ldots(ii)$

If $y \geq 1$, then LHS of eq. (ii) becomes

$$2y^2 + 2y - 2y(y - 1) - 1 = 0$$

$$\Rightarrow \quad 4y = 1 \text{ or } y = \frac{1}{4}$$

Also $\quad 2^{x+1} = 2^{-2}$ or $x = -3$

45. Let $y = 5 + 2\sqrt{6}$, then $\frac{1}{y} = 5 - 2\sqrt{6}$. Thus the given equation becomes

$$y^{x^2-3} + \left(\frac{1}{y}\right)^{x^2-3} = 10 \qquad \ldots(i)$$

Again let $y^{x^2-3} = t$. Then eq. (i) becomes

$$t + \frac{1}{t} = 10 \quad \Rightarrow \quad t^2 - 10t + 1 = 0$$

Thus, $\quad t = 5 \pm 2\sqrt{6}$

$\therefore \quad (5 + 2\sqrt{6})^{x^2-3} = 5 \pm 2\sqrt{6} = (5 + 2\sqrt{6})^{\pm 1}$

$\Rightarrow \quad x^2 - 3 = 1$ or $x^2 - 3 = -1$

$\Rightarrow \quad x^2 = 4$ or $x^2 = 2$

$\Rightarrow \quad x = \pm 2$ or $x = \pm\sqrt{2}$

46. For the real roots we must have $D \geq 0$. *i.e.*, $b^2 - 4ac \geq 0$

$b^2 \geq 4a$ (∵ $c = 1$)

b	b^2	a	$4a$	
1	1	×	×	
2	4	1	4	→ 1
3	9	1, 2	4, 8	→ 2 } 7
4	16	1, 2, 3, 4	4, 8, 12, 16	→ 4

Thus, there are 7 possible equations of the given form.

Scanned by CamScanner

yoursmahboob.wordpress.com

47. Let $y = a + \frac{1}{a}$ ...(i)

Differentiating above eq. (i), we get

$$\frac{dy}{da} = 1 - \frac{1}{a^2} \quad ...(ii)$$

Equating eq. (ii) with zero, we get

$$1 - \frac{1}{a^2} = 0 \Rightarrow a^2 = 1 \Rightarrow a = \pm 1$$

But since $a > 0$, hence only $a = 1$ is acceptable. Now substituting $a = 1$ in the original eq. (i) we get the required minimum value of the expression.

Hence, minimum of

$$y = 1 + \frac{1}{1} = 2$$

Alternatively: See the following graph of $y = x + \frac{1}{x}$.



Here, $x = a$

$$y = x + \frac{1}{x} = a + \frac{1}{a}$$

a	$\frac{1}{a}$	$a + \frac{1}{a}$
1	1	2
2	1/2	2.5
3	1/3	3.33
4	1/4	4.25
5	1/5	5.20
1/2	2	2.5
1/3	3	3.33
1/4	4	4.25

48. $(a+b+c)^2 \geq 0$

$\therefore (a+b+c)^2 = a^2 + b^2 + c^2 + 2(ab + bc + ca) \geq 0$ ...(i)

$\therefore 1 + 2(ab + bc + ca) \geq 0 \quad (a^2 + b^2 + c^2 = 1)$

$\Rightarrow (ab + bc + ca) \geq -\frac{1}{2}$ ...(ii)

Also, $a^2 + b^2 \geq 2ab$, $b^2 + c^2 \geq 2bc$, $c^2 + a^2 \geq 2ac$

$(a^2 + b^2 + b^2 + c^2 + c^2 + a^2) \geq 2ab + 2bc + 2ac$

$\Rightarrow a^2 + b^2 + c^2 \geq ab + bc + ac \quad (\because a^2 + b^2 + c^2 = 1)$

$\Rightarrow ab + bc + ac \leq 1$

$\therefore -\frac{1}{2} \leq ab + bc + ac \leq 1.$

49. Best way is to go through options. It satisfies for every even integer.

50. Let $(15 + 4\sqrt{14})^t = k$

$\therefore (15 - 4\sqrt{14}) = \frac{1}{k}$

$\therefore$ The given equation can be written as

$$k + \frac{1}{k} = 30$$

$\Rightarrow k^2 - 30k + 1 = 0$

$\Rightarrow k = 15 \pm 4\sqrt{14}$

Now, the equation will hold only at $t = \pm 1$.

$\therefore x^2 - 2|x| = \pm 1$

Again if $x^2 - 2|x| = 1$

$\Rightarrow x = \pm(1 + \sqrt{2})$

and if $x^2 - 2|x| = -1$

$\Rightarrow x = \pm 1$

Hence $x = \pm 1, \ \pm(1 + \sqrt{2})$

51. We have $|2x - 3| < 1 \Leftrightarrow -1 < 2x - 3 < 1$

$\Leftrightarrow 1 < x < 2 \Leftrightarrow x \in (1, 2)$

52. The roots of the equation are ω and ω^2.

Let $\alpha = \omega$ and $\beta = \omega^2$. Then

$$\alpha^{19} = \omega^{19} = \omega$$

and $\beta^7 = \omega^{14} = \omega^2$

Hence α^{19} and β^7 are roots of the same equation.

53. Let α, β be the roots of the equation $x^2 + px + 8 = 0$. Then $\alpha + \beta = -p$ and $\alpha\beta = 8$

But $\alpha - \beta = 2 \Rightarrow (\alpha + \beta)^2 - 4\alpha\beta = (2)^2$

$\Rightarrow p^2 - 32 = 4 \Rightarrow p = \pm 6.$

54. $(x + y)^2 = x^2 + y^2 + 2xy$

$(x + y)^2 = x^2 + y^2 + 2 \quad (\because xy = 1)$

For the minimum value of the expression

$x = y \ \therefore x = 1$ and $y = 1$

Hence, $(x + y)_{min} = \sqrt{x^2 + y^2 + 2} = \sqrt{4} = 2$

$(x + y)_m = 2$ (Since $x > 0$ and $xy > 0 \therefore y > 0$)

Alternatively :

xy	x	y	$\sqrt{x^2 + y^2 + 2} = (x + y)$
1	1/10	10	101/10
1	1/5	5	26/5
1	1/2	2	5/2
1	1	1	2
1	2	1/2	5/2
1	4	1/4	17/4
1	10	1/10	101/10

55. $x = 7 + 4\sqrt{3}$

$\therefore y = \frac{1}{7 + 4\sqrt{3}} = 7 - 4\sqrt{3}$

$\therefore \frac{1}{x^2} + \frac{1}{y^2} = \frac{x^2 + y^2}{(xy)^2}$

$$= \frac{(7 + 4\sqrt{3})^2 + (7 - 4\sqrt{3})^2}{[(7 + 4\sqrt{3})(7 - 4\sqrt{3})]^2}$$

$$= \frac{2(49 + 48)}{1} = 194$$

56. For real x, we have $x^2/(1 + x^4) \geq 0$ Also

$$1 + x^4 - 2x^2 = (1 - x^2)^2 \geq 0$$

$\Rightarrow 1 + x^4 \geq 2x^2$

$\therefore \left(\frac{x^2}{1 + x^4}\right) \leq \frac{1}{2}$

So $0 \leq \frac{x^2}{1 + x^4} \leq \frac{1}{2}$

57. $x^3 + 1 \geq x^2 + x \Rightarrow x^3 - x^2 - x + 1 \geq 0$

$\Rightarrow (x - 1)^2(x + 1) \geq 0 \Rightarrow x \geq -1$

Scanned by CamScanner

yoursmartboob.wordpress.com

LEVEL (2)

1. Best way is to go through options.

Consider option (b)

$$|3^4-1|^{\log_3(3^4)^2-2\log_{81}9}=(3^4-1)^7$$

$$|80|^{\log_3 3^8-\log_{81}81}=(80)^7$$

$\Rightarrow \quad \log_3 3^8-\log_{81}81=7$

$\Rightarrow \quad 8-1=7$

$7=7$

Hence option (b) is correct.

2. Putting $x=\frac{1}{y}$, we get

$$27y^3+54y^2+cy-10=0 \qquad ...(i)$$

This above eq. (i) must be in AP.

Let the roots of equation in y be

$$\alpha-\beta,\quad \alpha,\quad \alpha+\beta \qquad (\because \text{roots are in AP})$$

$\therefore \quad \Sigma\alpha=\alpha-\beta+\alpha+\alpha+\beta=3\alpha$

$\Rightarrow \quad 3\alpha=\frac{-54}{27} \Rightarrow \alpha=\frac{-2}{3}$

Now $\alpha=\frac{-2}{3}$ will satisfy the eq. (i) we get

$$27\times\frac{-8}{27}+54\times\frac{4}{9}-\frac{2c}{3}-10=0$$

$\Rightarrow \quad c=9$

3. $\log_{100}|x+y|=\frac{1}{2} \Rightarrow (100)^{1/2}=|x+y|$

$\Rightarrow \quad |x+y|=10 \qquad ...(1)$

Again, $\log_{10}y-\log_{10}|x|=\log_{100}4$

$\log_{10}y-\log_{10}|x|=\log_{10}2$

$\Rightarrow \quad \log_{10}\frac{y}{|x|}=\log_{10}2$

$\Rightarrow \quad y=2|x| \qquad ...(2)$

From eq. (2) we can conclude that y is always positive.

Now, when $x>0$ and $y>0$ (always)

$$|x+y|=10 \Rightarrow |x+2|x||=10$$

$\Rightarrow \quad x+2|x|=10 \qquad (\because x>0)$

$\Rightarrow \quad x+2x=10$

$\Rightarrow \quad x=\frac{10}{3}$

$\therefore \quad y=\frac{20}{3}$

Again, $x<0$ and $y>0$ (always positive)

$$|-x+2|-x||=10$$

$\Rightarrow \quad |-x+2x|=10$

$\Rightarrow \quad |x|=10$

$\Rightarrow \quad x=-10 \qquad (\because x<0)$

$\therefore \quad y=20$

Hence, $x=-10$, $y=20$ and $x=\frac{10}{3}$ and $y=\frac{20}{3}$.

4. $2\log_2\log_2 x+\log_{1/2}\log_2(2\sqrt{2}x)=1$

$\Rightarrow \quad 2\log_2\log_2 x-\log_2\log_2(2\sqrt{2}x)=\log_2 2$

$\Rightarrow \quad \log_2(\log_2 x)^2-\log_2[\log_2 2\sqrt{2}x]=\log_2 2$

$\Rightarrow \quad \log_2\frac{(\log_2 x)^2}{[\log_2 2\sqrt{2}x]}=\log_2 2$

$\Rightarrow \quad \frac{(\log_2 x)^2}{\log_2(2\sqrt{2}x)}=2$

$\Rightarrow \quad (\log_2 x)^2=2\log_2(2\sqrt{2}x)=2\log_2(2^{3/2}x)$

$\Rightarrow \quad (\log_2 x)^2=2[3/2\log_2 x+\log_2 x]=3+2\log_2 x$

$\Rightarrow \quad (\log_2 x)^2-2\log_2 x-3=0$

$\log_2 x=-1 \quad \text{or} \quad \log_2 x=3$

$\Rightarrow \quad x=\frac{1}{2} \quad \text{or} \quad x=8$

But for $x=\frac{1}{2}$, $\log_2\log_2(1/2)$ is undefined

$\therefore$ Only possible value of $x=8$.

5. Consider $x^2+4x+3\geq 0$ ...(i)

then $(x^2+4x+3)+2x+5=0$

$\Rightarrow \quad x=-2 \quad \text{and} \quad x=-4$

but $x=-2$ does not satisfy eq (i)

Now, if $x^2+4x+3<0$ ...(ii)

then $-(x^2+4x+3)+2x+5=0$

$\Rightarrow \quad x=-1-\sqrt{3} \quad \text{or} \quad x=-1+\sqrt{3}$

but only $x=-1-\sqrt{3}$ satisfies the eq. (ii).

Hence the solution set of x is $(-4,-1-\sqrt{3})$.

Alternatively, check the options by substituting the value from the options given in the question.

6. $\because x_1, x_2, x_3$ are in AP.

$\Rightarrow \quad x_1=a-d,\quad x_2=a,\quad x_3=a+d$

where d is the common difference

Now, since x_1, x_2, x_3 are the roots of the given equation

$$x^3-x^2+\beta x+\gamma=c$$

So, $\Sigma\alpha=x_1+x_2+x_3=1$

$\Rightarrow \quad (a-d)+(a)+(a+d)=1$ ...(i)

$\Sigma\alpha\beta=x_1x_2+x_2x_3+x_1x_3$

$\Rightarrow \quad \beta=(a-d)a+a(a+d)+(a-d)(a+d)$ ...(ii)

and $\Sigma=\alpha\beta\gamma=x_1x_2x_3=-\gamma=(a-d)(a)(a+d)$ ...(iii)

hence from (i) we get $a=\frac{1}{3}$

and from eq. (ii) we get

$$\beta=3a^2-d^2$$

$\Rightarrow \quad \beta=\frac{1}{3}-d^2 \qquad \left(\because a=\frac{1}{3}\right)$

Thus $\beta=\frac{1}{3}-d^2\leq\frac{1}{3} \qquad [\because d^2\geq 0]$

$\Rightarrow \quad \beta\leq\frac{1}{3}$

$\therefore \quad \beta\in\left(-\infty,\frac{1}{3}\right]$

Scanned by CamScanner

your shahbooks.wordpress.com

Again from eq. (iii)

$$a(a^2 - d^2) = -\gamma$$

$$\Rightarrow \quad \left(\frac{1}{27}\right) + \left(-\frac{d^2}{3}\right) = -\gamma$$

$$\Rightarrow \quad \gamma = \frac{d^3}{3} - \frac{1}{27}$$

$$\Rightarrow \quad \gamma \geq \frac{-1}{27} \qquad (\because\ d^2 \geq 0)$$

Hence option (a) is correct.

7. (a) $\rightarrow e^x < 1 + x$

(b) $\rightarrow e^x > (1 + x) \Leftrightarrow \log_e (1 + x) < x$

(c) $\rightarrow \sin x > x$

(d) $\rightarrow e^x < x \Leftrightarrow \log_e x > x$

NOTE $e \approx 2.714$ and $e^2 \approx 7.366$



from the graph it is clear that when $0 < x < 1, e^x > (1 + x)$

Option (c) is clearly wrong.

8. Let us consider some value of $p = 3$ (say), then

$$x^2 - 4x + 1$$

and $\quad (\alpha, \beta) = 2 \pm \sqrt{3}$ $\quad$ (α, β are the roots)

Now, $\quad \alpha^n + \beta^n = (2 + \sqrt{3})^n + (2 - \sqrt{3})^n \quad \ldots(i)\ (n \in N)$

then $\alpha^n + \beta^n$ will always be an integer, for the validity of statement you can put $n = 1, 2, 3, \ldots$ etc. in Eq. (i).

Similarly for $p = 4, 5, 6, \ldots$ etc. we can conclude the same results.

NOTE In this question, the discriminant D is always positive, *i.e.*, $b^2 - 4ac > 0$. So the roots will always be real, unequal and irrational.

But the fact is that $\alpha^n + \beta^n$, for $n \in N$, always yields integral value. This can be easily proved by mathematical induction method. So if the answer is an integer, then it must be a rational number, hence (d) is correct.

9. Just assume some values of α, β conforming the basic constraints of the problem.

e.g., $\alpha = -2, \beta = 8$, then the equation becomes $x^2 - 6x - 16$

$$\Rightarrow \quad b = -6 \quad \text{and} \quad c = -16$$

$$\therefore \quad 1 + \frac{c}{a} + \left|\frac{b}{a}\right| = 1 - 16 + 6 = -9$$

$\therefore$ The value of the expression is negative, hence choice (a) is correct.

NOTE Since $\quad \alpha < 1$ and $\beta > 1$

$$\therefore \quad \alpha\beta < 1 \Rightarrow \frac{c}{a} < 1$$

Further the product of any two numbers ($n_1, n_2 \neq 0$) is less than the sum of the number if any one of them is negative.

So, $\quad \alpha\beta < \alpha + \beta$ $\quad$ ($\because$ Here $\alpha\beta$ is negative)

$$\therefore \quad \frac{c}{a} < \left|\frac{b}{a}\right|;$$

but $\frac{c}{a}$ is numerically greater than $\left|\frac{b}{a}\right|$.

$$\Rightarrow \quad 1 + \frac{c}{a} + \left|\frac{b}{a}\right| < 0.$$

10. Since p and q are the roots of given equation $x^2 + px + q = 0$

then $p + q = -p \Rightarrow q = -2p$

and $\quad pq = q \quad \Rightarrow \quad p = 1$

So, when $p = 1$, then $q = -2$

Again, when $q = 0$, then $p = 0$ hence,

$$p = 1, 0 \quad \text{and} \quad q = -2, 0$$

Thus, option (b) is most appropriate.

11. $\because p, q, r$ are in AP.

$$\therefore \quad q = \frac{p + r}{2} \qquad [\because\ p + r = 2q]$$

For the real roots $\quad q^2 - 4pr \geq 0$

$$\Rightarrow \quad \left(\frac{p + r}{2}\right)^2 - 4pr \geq 0$$

$$\Rightarrow \quad p^2 + r^2 - 14pr \geq 0$$

$$\Rightarrow \quad \left(\frac{p}{r}\right)^2 - 14\left(\frac{p}{r}\right) + 1 \geq 0$$

$$\Rightarrow \quad \left(\frac{p}{r} - 7\right)^2 \geq 48$$

$$\Rightarrow \quad \left|\frac{p}{r} - 7\right| \geq 4\sqrt{3}$$

12. The given equation is $|x - 2|^2 + |x - 2| - 2 = 0$.

Let us assume $|x - 2| = m$

then $\quad m^2 + m - 2 = 0$

$$(m - 1)(m + 2) = 0$$

Only admissible value is

$$m = 1 \qquad (\because\ m \neq -2 \text{ as } m \geq 0]$$

$$\therefore \quad |x - 2| = 1$$

$$\Rightarrow \quad x - 2 = 1 \quad \Rightarrow \quad x = 3$$

or $\quad -(x - 2) = 1 \quad \Rightarrow \quad x = 1$

Hence $\quad x = 1, 3$

$\therefore$ Sum of the roots of equation $= 1 + 3 = 4$.

13. Just consider an option, and then substitute the values of A and B from assumed option, if the roots p, q, r, s are in A.P., then the presumed option is correct, else not.

thus we get options a, b and c are incorrect, hence (d) is the right choice.

Alternatively : Let us consider $p = a - 3d$, $q = a - d$, $r = a + d$, and $s = a + 3d$

$$\therefore \quad 2a - 4d = 2 \qquad \ldots(i)$$

and $\quad 2a + 4d = 18 \qquad \ldots(ii)$

Scanned by CamScanner

yoursmathbook.wordpress.com

Solving equations (i) and (ii), we get

$$a = 5, d = 2$$

$\therefore$ $p = -1, \quad q = 3, \quad r = 7, \quad s = 11$

Hence $A = pq = -3$

and $B = rs = 77$

Thus (d) is the right choice

14. Let $f(x) = x^2 - 2ax + a^2 + a - 3$

Since $f(x)$ has real roots both less than 3.

Therefore, $D > 0$ and $f(3) > 0$

$\Rightarrow$ $a^2 - (a^2 + a - 3) > 0$

and $a^2 - 5a + 6 > 0$

$\Rightarrow$ $a < 3$ and $(a - 2)(a - 3) > 0$

$\Rightarrow$ $a < 3$ and $a < 2$ or $a > 3$

$\Rightarrow$ $a < 2$

15. Considering the given constraints in the problem.

Let us consider $\alpha, \beta = (-3, 2)$

then the given equation becomes

$$x^2 + x - 6 = 0$$

$\Rightarrow$ $b = 1$ and $c = -6$

Now, we check for the given choices, which satisfy the aforesaid conditions

(a) It is clearly wrong

(b) It is correct

(c) It is also wrong

(d) It is also wrong

Hence option (b) is appropriate.

NOTE Students don't be worried about this technique. It must be clear to them that while assuming the values of α, β, they have to strictly follow the basic given constraints, *i.e.*, α must be less than β and after forming the similar equation they should have $c < 0 < b$. So I think it is even very intelligent method to solve the problems rather than conventional methods.

16. Let us assume $a = 3$, $b = 4$, given that $a < b$ then the given equation becomes

$$(x - 3)(x - 4) - 1 = 0$$

$$x^2 - 7x + 11 = 0$$

$\therefore$ $x = \dfrac{7 \pm \sqrt{49 - 44}}{2} \Rightarrow x = \dfrac{7 \pm \sqrt{5}}{2}$

$\Rightarrow$ $x = \dfrac{7 + \sqrt{5}}{2} > 4$ and $\dfrac{7 - \sqrt{5}}{3} < 3$

Hence only option (d) is satisfied, hence correct.

Alternatively: Since $f(x) = (x - a)(x - b) - 1 = 0$

$\Rightarrow$ $(x - a)(x - b) = 1$



$\alpha < a$ and $\beta > b$

It means x-axis is shifted to -1 unit below the original position. So it is clear from the graph that $\alpha < a$ and $\beta > b$

$\alpha\beta = p$ and $\gamma\delta = q$

17. Now since, $\alpha, \beta, \gamma, \delta$ are in GP and integral values. So the options (b) and (c) are ruled out as they have no required proper integral factors. Now let us look for option (a). We see that

$$\alpha\beta = -2 = -1 \times 2$$

$$\gamma\delta = -32 = -4 \times 8$$

So, $-1, 2, -4, 8$ are in GP satisfying the above conditions. Again in option (d) the two values don't have the factors with common ratio, hence its wrong. Finally option (a) is correct.

Alternatively : The sum of roots and product of roots is as follows :

$$\alpha + \beta = 1, \qquad \alpha\beta = p$$

$$\gamma + \delta = 4, \qquad \gamma\delta = q$$

Let r be the common ratio of the GP $\alpha, \beta, \gamma, \delta$.

Then, $\alpha + \beta = 1$ and $\gamma + \delta = 4$

$\alpha + \alpha r = 1$ and $\alpha r^2 + \alpha r^3 = 4$

$\Rightarrow$ $\alpha(1 + r) = 1$ and $\alpha r^2(1 + r) = 4$

So $1 + r = \dfrac{1}{2}$ and $\alpha r^2 \left(\dfrac{1}{\alpha}\right) = 4$

$\Rightarrow$ $r = \pm 2$

When $r = 2$, then $\alpha = \dfrac{1}{3}$ which is inadmissible.

Hence, $r = -2$ is to be considered, then $\alpha = -1$

Thus $\alpha\beta = p = -2$

and $r\delta = q = -32$

18. When this problem will be solved by algebraic methods, it will take too much time to solve beyond the normal required time. So, the best way to get the correct and quick answer is to assume some simple roots (*i.e.*, α and β) then go through options.

Let us take two arbitrary values $\alpha = -1$, $\beta = 2$, then the equation will be $x^2 - x - 2 = 0$

Comparing with the equation $x^2 - px + q = 0$

$\Rightarrow$ $p = 1, \quad q = -2$

Now, the sum of the roots of the required equation

$$= [(\alpha^2 - \beta^2)(\alpha^3 - \beta^3)] + [\alpha^3\beta^2 + \alpha^2\beta^3]$$

$$= 27 + 4 = 31$$

and product of roots $[(\alpha^2 - \beta^2)(\alpha^3 - \beta^3)[\alpha^3\beta^2 + \alpha^2\beta^3]$

$= 27 \times 4 = 108$

Hence equation is $x^2 - 31x + 108 = 0$

Now putting the values of p and q in the equation options a, b and c we get option (b) is correct. as :

$x^2 - [1 - \{5 \times 1 (-2)\} + 5 \times 1 \times 4] + [1 \times 4 - \{5 \times 1 \times (-8)\}$

$+ 4 \times 1 \times 16] = 0$

$$= x^2 - 31x + 108 = 0$$

19. Let us consider choice (a). When we put the values of A and B respectively, we get the values of α, β, γ and δ as -1, $1/3$, $1/5$, $1/3$, which are not in HP. So this option is not correct.

Now for our convenience we consider choice (c), then by substituting the values of A and B, we get the values of α, β, γ and δ as 1, 1/2, 1/3 and 1/4 which are in HP. Hence this could be the correct choice.

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively :

$$Ax^2 - 4x + 1 = 0 \quad \ldots(i)$$

$$\alpha + \gamma = \frac{4}{A} \quad \ldots(1)$$

$$\alpha\gamma = \frac{1}{A} \quad \ldots(2)$$

and

$$Bx^2 - 6x + 1 = 0 \quad \ldots(ii)$$

$$\beta + \delta = \frac{6}{B} \quad \ldots(3)$$

$$\beta\delta = \frac{1}{B} \quad \ldots(4)$$

Since it is given that $\alpha, \beta, \gamma, \delta$ are in HP.

$$\therefore \quad \beta = \frac{2\alpha\gamma}{\alpha + \gamma} = \frac{1}{2}$$

and

$$\gamma = \frac{2\beta\delta}{\beta + \delta} = \frac{1}{3}$$

Again since β and γ are the roots of the given equation hence they must satisfy the equation. So

$$B\beta^2 - 6\beta + 1 = 0$$

and

$$A\gamma^2 - 4\gamma + 1 = 0$$

$$\Rightarrow \quad B = 8 \quad \text{and} \quad A = 3$$

Hence option (c) is correct.

20. Assume some convenient and appropriate values of a, b, c as

$$a = 3, \quad b = 4, \quad c = 6.$$

then $(x-3)(x-4) - 6 = 0 \quad [\because (x-a)(x-b) = c, c \neq 0]$

$$\Rightarrow \quad x^2 - 7x + 6 = 0$$

$$\Rightarrow \quad \alpha = 6, \quad \beta = 1$$

Again $(x-6)(x-1) + 6 \; (\because (x-\alpha)(x-\beta) + c = 0)$

$$x^2 - 7x + 6 + 6 = 0$$

$$x^2 - 7x + 12 = 0$$

$\therefore$ the roots $k_1 = 3$ and $k_2 = 4$

which are same as a and b

Hence, option (c) is correct.

Alternatively : $x^2 - (a+b)x + (ab - c) = 0$

$$\therefore \quad \alpha + \beta = a + b$$

and

$$\alpha\beta = ab - c$$

Again if k_1 and k_2 be the roots of the other equation, then

$$(x-\alpha)(x-\beta) + c = 0$$

i.e., $x^2 - (\alpha + \beta)x + (\alpha\beta + c) = 0$

$$\therefore \quad k_1 + k_2 = \alpha + \beta = a + b \quad \ldots(i)$$

and $k_1 \cdot k_2 = \alpha\beta + c = (ab - c) + c = ab \quad \ldots(ii)$

Thus, from eq. (i) and (ii) it is clear that the roots are a and b.

Hence correct choice is c.

Scanned by CamScanner

yoursmanboob.wordpress.com

15 SET THEORY

It is one of the easiest and most interesting chapter. Almost every year 2-3 questions appear in CAT from this chapter, either in QA or in DI/DS section. The important feature of this chapter is Venn diagrams which play a vital role in the logical reasoning. That's why this chapter is interesting logical and important in CAT, XLRI, FMS, CET etc. Since we have to solve most of the problems through Venn diagrams, therefore the whole emphasis is given on the theory and concepts of Venn diagrams. Formulae and algebraic theory is not important particularly in CAT, still we have to know some fundamentals of sets and their applications.

SET

A well defined collection of objects is called a set.

The objects in a set are called its members or elements.

If a is an element of a set A, then we write $a \in A$ (and say a belongs to A) *i.e.*, 'a' is a member of 'A'.

If a does not belong to A, then we write $a \notin A$

By convention the sets are denoted by capital alphabets *e.g.*, $A, B, C, \ldots X, Y, Z$ etc and elements of a set are denoted by $a, b, c, \ldots, x, y, z$ etc.

Some Important Notations of Standard Sets

N	:	the set of natural numbers
Z	:	the set of integers
Z^+	:	the set of positive integers
Q	:	the set of all rational numbers
Q^+	:	the set of all positive rational numbers
R	:	the set of real numbers
R^+	:	the set of all positive real numbers
C	:	the set of all complex numbers.

METHODS OF REPRESENTATION OF SETS

1. Roster Method : In this method a set is described by listing all the elements, separated by commas, within braces { }, *e.g.*,

(1) The set of perfect squares upto 100 may be described as {0, 1, 4, 9, 16, 25, 36, 49, 64, 81, 100}

(2) The set of all the days of a week may be described as {Sunday, Monday, Tuesday, Wednesday, Thursday, Friday, Saturday}.

NOTE The order of elements (*i.e.*, position of elements) is not important. Hence any element can be written anywhere within braces { }.

2. Set Builder Method : In this method, a set is described by listing its property in the given manner.

The set $P(x)$ is described as

$$P = \{x : P(x) \text{ holds}\} \quad \text{or} \quad \{x \mid P(x) \text{ holds}\}$$

or $P = \{x : x$ has the property $abc \ldots\}$

which is read as 'the set of all x such that $P(x)$ holds'. The symbol '|' or ':' is read as 'such that', *e.g.*,

1. The set of perfect squares upto 100 can be written as

$$P = \{x : x \text{ is a perfect square and } 0 \le x \le 100, x \in N\}$$

or $P = \{x : x \in N,\ x = n^2,\ 0 \le x < 100, n \in Z\}$

or $P = \{x^2 : x \in Z\}$

2. The set of all the odd natural numbers can be expressed as

$$A = \{x : x \in N,\ x = 2n - 1,\ n \in N\}$$

TYPES OF SETS

Singleton Set : A set consisting of a single element is called a singleton set.

e.g., 1. {cat}, {7} etc.

2. $\{x : x + 5 = 7\} = \{2\}$

3. {0} is a singleton set.

Empty Set : A set containing no element at all is called an empty set or a null set or a void set and is denoted by ϕ.

In set builder form it is expressed as $\phi = \{\}$

e.g., 1. $\{x : x \in N,\ 9 < x < 10\} = \phi$

2. $\{x : x \in R,\ x^2 = -8\} = \phi$

NOTE A set containing atleast one element is called a non-empty or non-void set.

Finite Set : If a set has finite number of elements that can be counted or listed *i.e.*, the counting of elements surely comes to an end, is called a finite set, *e.g.*,

Scanned by CamScanner

yoursmahboob.wordpress.com

1. Set of all the management institutes in the world.
2. Set of all the recognised countries in the world.

Cardinal Number : The number of distinct elements in a finite set is called the 'cardinal number' of the set *e.g.*, $n(A) \to n$ is the number of distinct elements in the set A.

Infinite Set : If the number of elements of a set is infinite *i.e.*, which cann't be counted by natural numbers, is called infinite set in other words if a set is not finite then it must be an infinite set. *e.g.*

1. Set of all points on the arc of a circle
2. Set of all concentric circles with a given centre
3. Number of all lines in a particular plane.
4. $\{x : x \in R,\ 1 < x < 2\}$ and $\{x : x \in I,\ x < 10\}$

Equivalent Sets : Two finite sets A and B are equivalent if their cardinal numbers are same

i.e., $n(A) = n(B)$

e.g., $A = \{a, e, i, o, u\}$ and $B = \{1, 3, 5, 7, 9\}$

$\Rightarrow$ $n(A) = n(B)$

Equal Sets : Two sets A and B are said to be equal, if every element of A is in B and every element of B is in A and it is denoted as $A = B$

When the elements of A and B are distinct, then $A \neq B$ *i.e.*, A and B are not equal *e.g.*,

1. $A = \{a, e, i, o, u\}$ and $B = \{e, o, i, a, u\}$

$\Rightarrow$ $A = B$

2. $A = \{p, q, r\}$, $B = \{q, p, r\}$ and $C = \{r, q, p\}$

$\Rightarrow$ $A = B = C$

3. $A = \{C, A, T\}$
   $B = \{C, A, T, A\}$
   $C = \{A, C, A, A, T\}$

$\Rightarrow$ $A = B = C$

Remark

1. Order of elements in the list of elements is not important *i.e.*, meaningless.
2. The repetition of elements in a set is meaningless.
3. $\phi \neq \{0\} \neq 0$, since ϕ is a set containing no element at all, $\{0\}$ is a singleton set and 0 is not a set.
   Remember that equivalent sets are not always equal but equal sets are always equivalent.
   Thus $\{1, 2, 3, 4\}$ and $\{W, X, Y, Z\}$ are equivalent but not equal.

Subsets : Let A and B be two sets such that every element of A is the element of B (*i.e.*, every element of A is in B), then A is called a subset of B and is denoted as-$A \subseteq B$ (Read it as-A is a subset of B)

Superset : If $A \subseteq B$, we say that B is a superset of A and we write $B \supseteq A$.

Read it as-B is the superset of A.

e.g., $B = \{2, 4, 6, 8, 10\}$, $A = \{4, 8\} \Rightarrow B \supseteq A$

Proper Subset : If $A \subseteq B$ and $A \neq B$, then A is called a proper subset of B and denoted as $A \subset B$ *e.g.*,

1. $\{5, 15, 25\} \subset \{5, 10, 15, 20, 25\}$
2. $N \subset W \subset I \subset Q \subset R$

Comparable Sets : Two sets A and B are said to be comparable if either $A \subseteq B$ or $B \subseteq A$.

Results on Subsets

1. The empty set ϕ is a subset of every set.
2. Every set is a subset of itself.
3. The number of all possible subsets of a set containing n elements is 2^n.
4. The number of all proper subsets of a set containing n elements is $(2^n - 1)$.
5. The set of all subsets of a given set A is called the power set of A, denoted by $P(A)$. Thus, if A has n elements $P(A)$ has 2^n elements.

Universal Set : A set that contains all sets in a given context is called the universal set *e.g.*,

1. In a two dimensional coordinate geometry, the set of all points in x-y plane is the universal set.
2. Sets containing natural numbers have a universal set N
3. If $A = \{1, 2, 4\}$, $B = \{2, 2, 4, 6\}$, $C = \{1, 2, 5, 6, 7\}$, then $U = \{1, 2, 3, 4, 5, 6, 7\}$



Power Set : The collection or family of all the subsets of a set A is called the power set of A and is denoted by $P(A)$.

NOTE The power set is always non-empty, because the empty set and the given set itself are the members or elements of the power set.
$A = \{1, 2, 3\}$, then the number of subsets of the $P(A)$ will be $2^3 = 8$
$P(A) = \{\}, \{1\}, \{2\}, \{3\}, \{1, 2\}, \{2, 3\}, \{1, 3\}, \{1, 2, 3\}$

VENN DIAGRAMS

First of all Swiss mathematician Euler elucidated the idea of representing the sets by points in a closed curve. Later on British mathematician Venn brought this into practice. That's why this whole concept is known as Euler-Venn diagram or simply Venn diagrams.

In Venn diagrams the universal set U is represented by points within a rectangle and its subsets are represented by points in closed curves (usually circles) within a rectangle.

OPERATIONS ON SETS

1. Union of Sets : If A and B be two sets, then the union of A and B is the set of the all those elements which belong either to A or to B or to both A and B. It is denoted as $A \cup B$ (read as 'A union B') *e.g.*,



[The shaded region is representing the union of sets]

Scanned by CamScanner

yoursmahboob.wordpress.com

$A = \{2, 3, 5\}$, $B = \{1, 2, 4, 5\}$

$A \cup B = \{1, 2, 3, 4, 5\}$

2. Intersection of Sets : If A and B be two sets then the intersection of A and B is the set of all those elements that belong to both A and B. It is denoted by $A \cap B$ (read as "A intersection B").



[The shaded region is representing the intersection of sets]

e.g., $A = \{3, 6, 9, 12, 15, 18\}$,

$B = \{4, 6, 8, 10, 12, 14, 16, 18\}$

$\therefore \quad A \cap B = \{6, 12, 18\}$

Disjoint Sets : Two sets A and B are said to be disjoint if $A \cap B = \phi$. If $A \cap B \neq \phi$ then A and B are said to be intersecting or overlapping sets.

e.g., $A = \{1, 3, 5, 7, 9\}$ $B = \{2, 4, 6, 8, 10\}$,

$C = \{4, 8, 12\}$

Here $A \cap B = \phi$ $\therefore A$ and B are disjoint sets

and $B \cap C \neq \phi$ $\therefore B$ and C are intersecting sets.



Sets A and B have no elements common.

Difference of Sets : The difference of set A and set B (written as $A - B$) is the set of all those elements of A which do not belong to B.

Thus, $A - B = \{x : x \in A \text{ and } x \notin B\}$

or $A - B = \{x \in A : x \notin B\}$

Clearly $x \in A - B \Leftrightarrow x \in A$ and $x \notin B$

e.g., If $A = \{1, 2, 3, 4, 5, 6\}$, $B = \{2, 4, 6, 8, 10\}$

$A - B = \{1, 3, 5\}$

and $B - A = \{8, 10\}$



$(A - B)$ is represented by the shaded region



$(B - A)$ is represented by the shaded region

Symmetric difference of two Sets : The symmetric difference of sets A and B is the set $(A - B) \cup (B - A)$ and is denoted by $A \Delta B$



Thus

$A \Delta B = (A - B) \cup (B - A)$

$= \{x : x \notin A \cap B\}$

Complement of a Set : If U be the universal set and a set A is such that $A \subset U$ then, the complement of A with respect to U is denoted by A' or A^c or $U - A$ and is defined by the set of all those elements of U which are not in A.

Thus $A' = \{x \in U : x \notin A\}$

Clearly $x \in A' \Leftrightarrow x \notin A$



A' is shown by the shaded region

e.g., $U = \{2, 3, 5, 7, 11, 13 \ldots\}$

$A = \{2\}$

$A' = U - A = \{3, 5, 7, 11, 13, \ldots\}$

ALGEBRAIC LAWS OF SETS

1. **Idempotent Laws :** For any set A, we have
   (i) $A \cup A = A$ (ii) $A \cap A = A$
2. **Identity Laws :** For any set A, we have
   (i) $A \cup \phi = A$ (ii) $A \cap U = A$
3. **Commutative Laws :** For any two sets A and B, we have
   (i) $A \cup B = B \cup A$ (ii) $A \cap B = B \cap A$
4. **Associative Laws :** If A, B and C are any three sets, then
   (i) $(A \cup B) \cup C = A \cup (B \cup C)$
   (ii) $A \cap (B \cap C) = (A \cap B) \cap C$
5. **Distributive Laws :** If A, B and C are any three sets, then
   (i) $A \cup (B \cap C) = (A \cup B) \cap (A \cup C)$
   (ii) $A \cap (B \cup C) = (A \cap B) \cup (A \cap C)$
6. **De-Morgan's Laws :** If A and B are any two sets, then
   (i) $(A \cup B)' = A' \cap B'$ (ii) $(A \cap B)' = A' \cup B'$

SOME IMPORTANT RESULTS ON OPERATIONS ON NUMBERS

1. $A - B = A \cap B'$
2. $B - A = B \cap A'$
3. $A - B = A \Leftrightarrow A \cap B = \phi$
4. $(A - B) \cup B = A \cup B$
5. $(A - B) \cap B = \phi$
6. $A \subseteq B \Leftrightarrow B' \subseteq A'$
7. $(A - B) \cup (B - A) = (A \cup B) - (A \cap B)$

SOME IMPORTANT RESULTS ON NUMBERS OF ELEMENTS IN SETS

If A, B and C are finite sets, and U be the finite universal set then

(i) $n(A \cup B) = n(A) + n(B) - n(A \cap B)$

(ii) $n(A \cup B) = n(A) + n(B) \Leftrightarrow A, B$ are disjoint non-void sets.

(iii) $n(A - B) = n(A) - n(A \cap B)$ *i.e.*,

$n(A - B) + n(A \cap B) = n(A)$

Scanned by CamScanner

yoursmahboob.wordpress.com

(iv) $n(A \Delta B)$ = Number of elements which belong to exactly one of A or B.

$$= n(A) + n(B) - 2n(A \cap B)$$

(v) $n(A \cup B \cup C) = n(A) + n(B) + n(C) - n(A \cap B) - n(B \cap C) - n(A \cap C) + n(A \cap B \cap C)$

(vi) number of elements in exactly two of the sets A, B, C

$$= n(A \cap B) + n(B \cap C) + n(C \cap A) - 3n(A \cap B \cap C)$$

(vii) number of elements in exactly one of the sets A, B, C

$$= n(A) + n(B) + n(C) - 2n(A \cap B) - 2n(B \cap C) - 2n(A \cap C) + 3n(A \cap B \cap C)$$

(viii) $n(A' \cup B') = n[(A \cap B)'] = n(U) - n(A \cap B)$

(ix) $n(A' \cap B') = n[(A \cup B)'] = n(U) - n(A \cup B)$

INTRODUCTORY EXERCISE-15.1

1. If $A = \{S\}$, which of the following is a correct statement ?
   (a) $S \in A$ (b) $S \subset A$
   (c) $\{S\} \in A$ (d) $A = S$

2. Consider the following statements :
   1. Any set A is comparable with itself
   2. $\{0\}$ is a singleton set
   3. $\{\phi\}$ is an empty set.
   Of these statements, the correct ones are :
   (a) 1 and 2 (b) 2 and 3
   (c) 1 and 3 (d) 1, 2 and 3

3. The total number of elements in the power set of a set A containing n elements is :
   (a) n^2 (b) 2^n
   (c) $2^n - 1$ (d) none of these

4. Let $A = \{3, \pi, \sqrt{2}, -5, 3 + \sqrt{7}, 2/7\}$. The subset of A containing all the elements from it which are irrational numbers is :
   (a) $\{\pi, \sqrt{2}, 3 + \sqrt{7}\}$
   (b) $\{3, \pi, 2/7, -5, 3 + \sqrt{7}\}$
   (c) $\{3, 2/7, -5\}$
   (d) $\{3, -5\}$

5. The set $\{x : (x - 3)(x - 5) > 0\}$ is equal to :
   (a) $\{x : 3 < x < 5\}$ (b) $\{x : x < 3\} \cup \{x : x < 5\}$
   (c) $\{x : x < 3\} \cup (x : x > 5)$ (d) none of these

6. If A is the set of all integral multiples of 3 and B is the set of all integral multiples of 5, then $A \cap B$ is the set of all integral multiples of :
   (a) 3 + 5 (b) 5 - 3
   (c) GCD (3, 5) (d) LCM (3, 5)

7. If $X = \{4^n - 3n - 1 : n \in N\}$ and $Y = \{9(n - 1) : n \in N$, then precisely :
   (a) $X \subset Y$ (b) $X \subseteq Y$
   (c) $X = Y$ (d) $X \supseteq Y$

8. The number of elements of the set $\{x : x \in N, x^2 = 1\}$, where N is the set of all natural numbers is :
   (a) 2 (b) 1
   (c) 0 (d) 3

9. If $A = \{1, 2, 3, 4\}$ and $B = \{5, 6, 7\}$, then $A \cap B$ is :
   (a) $\{1, 2, 3\}$ (b) $\{5, 6, 7\}$
   (c) $\{4\}$ (d) ϕ

10. If $A = \{1, 2, 3, \ldots 9\}$, $B = \{2, 4, 6, 7, 8\}$ and $C = \{3, 4, 5, 8, 9, 10\}$, then $(A - B) \cup C$ is :
    (a) $\{1, 3, 4, 5, 8, 9, 10\}$ (b) $\{1, 2, 3, 4, 5, 6, 7, 8, 9\}$
    (c) $\{2, 4, 6, 7, 8\}$ (d) $\{1, 3, 4, 5, 8, 9\}$

11. $A \cup B = A$, then :
    (a) $A \subset B$ (b) $B \subset A$
    (c) $A \not\subset B$ and $B \not\subset A$ (d) none of these

12. If A has 3 elements and B has 6 elements, then the minimum number of elements in $A \cup B$ is :
    (a) 3 (b) 6
    (c) 9 (d) 18

13. Let $X = \{1, 2, 3, 4, 5, 6, 7, 8, 9, 10\}$ be the universal set and $A = \{2, 4, 6\}$, $B = \{1, 3, 7\}$, then $A^c \cap B^c$ is equal to :
    (a) $\{2, 4, 5, 6, 8, 9, 10\}$ (b) $\{1, 3, 5, 7, 8, 9, 10\}$
    (c) X (d) $\{5, 8, 9, 10\}$

14. If A, B, C are any three sets, then :
    (a) $A - (B \cup C) = (A - B) \cup (A - C)$
    (b) $A - (B \cup C) = (A - B) \cap (A - C)$
    (c) $A - (B \cap C) = (A - B) \cup (A - C)$
    (d) $A - (B \cup C) = (A \cup B) - (A \cup C)$

15. Consider the following statements :
    For any two sets A and B
    (1) $(A - B) \cup B = A$ (2) $(A - B) \cup A = A$
    (3) $(A - B) \cap B = \phi$ (4) $A \subseteq B \Rightarrow A \cup B = B$
    Of these statements :
    (a) 1, 2, 3 are correct (b) 2, 3, 4 are correct
    (c) 1, 3, 4 are correct (d) 1, 2, 4 are correct

16. If X and Y are two sets and X' denotes the complement of X, then $X \cap (X \cup Y)'$ equals :
    (a) X (b) Y
    (c) ϕ (d) none of these

17. If $B \subseteq A$, which of the following statements is correct?
    (a) $A \cup B = B \Rightarrow A = B$ (b) $A \cap B = B \Rightarrow A \supseteq B$
    (c) $A - B = A \Rightarrow A = B$ (d) $B - A = B \Rightarrow A = B$

18. If A, B and C be any three sets, then $A \cup (B \cap C)$ is the same as :
    (a) $(A \cap C) \cup (B \cap C)$ (b) $(A \cup B) \cap (A \cup C)$
    (c) $(A \cup B) \cap (B \cup C)$ (d) $(A \cup C) \cap (B \cup C)$

19. $A - (B \cup C)$ equals :
    (a) $(A - B) \cup (A - C)$ (b) $(A - B) \cap (A \cap C)$
    (c) $(A - B) \cup C$ (d) $(A - C) \cup B$

Scanned by CamScanner

yourshahbood.wordpress.com

PROBLEMS BASED ON VENN DIAGRAMS

EXAMPLE 1 *In a group of 1000 people 700 can speak English and 500 can speak Hindi. If all the people speak atleast one of the two languages, find :*

(a) how many can speak both the languages?

(b) how many can speak exactly one language?

SOLUTION (a) $n(E \cup H) = n(E) + n(H) - n(E \cap H)$

$1000 = 700 + 500 - n(E \cap H)$



$\{E \to$ English, $H \to$ Hindi$\}$

$\Rightarrow \quad n(E \cap H) = 200$

(b) People speaking exactly one language

$n(E \cup H) - n(E \cap H) = 1000 - 200 = 800$

Alternatively: People speaking exactly one language

$= 500 + 300 = 800$

EXAMPLE 2 *In an exam 60% of the candidates passed in Maths and 70% candidates passed in English and 10% candidates failed in both the subjects. If 300 candidates passed in both the subjects. The total number of candidates appeared in the exam, if they took test in only two subjects viz-Maths and English.*

SOLUTION



Fail in both subjects = 10%



Failed number of candidates

$\therefore$ Total number of candidates failed in atleast one subject

$= 30 + 10 + 20 = 60\%$

$\therefore$ Total number of candidates passed in both the subjects

$= 100 - 60 = 40\%$

Let total number of candidates appeared in exam $= x$

$\therefore \quad \frac{40x}{100} = 300 \Rightarrow x = 750$

Hence total 750 candidates appeared in exam.

EXAMPLE 3 *A class took two tests, one in Physics and other in Maths. $\left(\frac{1}{3}\right)^{rd}$ class failed in Maths and $\frac{1}{2}$ class failed in Physics. 60% of those passed in Physics also passed in Maths. If 300 students took both the tests then how many students failed in both?*

SOLUTION





Total number of students passed in atleast one subject

$= 110 + 90 + 60 = 260$

Therefore number of students failed in both the subjects

$= 300 - 260 = 40$

EXAMPLE 4 *In an exam 49% candidates failed in English and 36% failed in Hindi and 15% failed in both subjects. If the total number of candidates who passed in English alone is 630. What is the total number of candidates appeared in exam?*

SOLUTION



Number of candidates failed in atleast one subject

$= 34 + 15 + 21 = 70\%$



$\therefore$ Number of candidates passed in both the subjects

$= 100 - 70 = 30\%$

Number of candidates passed in English only $= 51 - 30 = 21\%$

Let the total number of candidates be x, then

$\frac{21x}{100} = 630 \Rightarrow x = 3000$

Alternatively: Since 21% candidates failed in Hindi only it means they are pass in only English.

Hence number of candidates who are passed only in English $= 21\%$

EXAMPLE 5 *In a survey it was found that 69% of Indians like romantic movies and 61% like action movies. What percentage of Indians like both type of movies?*

SOLUTION $n(R \cap A) = (69 + 61) - 100$



NOTE In general we cannot determine the solution but this can be done if we assume that all the Indians like atleast one of these two types of movies.

EXAMPLE 6 *In a certain city only two cellular (mobile) phone services are available. One is Radiance and other is DSML. It is known that 25% of the city population uses the services of Radiance and 20% uses the services of DSML, while 8% uses both Radiance and DSML. It is also known that 30% of those who uses Radiance services but not services of DSML have prepaid cards and 40% of those who uses DSML but not Radiance have prepaid cards while 50% of those who uses the services of both Radiance and DSML have prepaid cards. What percentage of the population have prepaid cards?*

(a) 12·5% (b) 10% (c) 13·9% (d) 20%

Scanned by CamScanner

yoursmahboob.wordpress.com

SOLUTION



∴ Percentage of people have prepaid cards
= (30 % of 17) + (40% of 12) + (50% of 8)
= 13.9%

VENN DIAGRAMS CONTAINING THREE CIRCLES

Explanation of the concept using an example



Let P, Q, R be three books, then
$a \rightarrow$ number of people reading only P
$b \rightarrow$ number of people reading only Q
$c \rightarrow$ number of people reading only R
$x \rightarrow$ number of people reading P and Q both but not R
$y \rightarrow$ number of people reading Q and R both but not P
$z \rightarrow$ number of people reading P and R both but not Q
$k \rightarrow$ number of people reading all the three books
$x + k \rightarrow$ number of people reading P and Q both
$y + k \rightarrow$ number of people reading Q and R both
$z + k \rightarrow$ number of people reading P and R both
$a + x + k + z \rightarrow$ number of people reading P
$b + x + k + y \rightarrow$ number of people reading Q
$c + y + k + z \rightarrow$ number of people reading R
$a + x + b \rightarrow$ number of people reading P or Q but not R
$b + y + c \rightarrow$ number of people reading Q or R but not P
$c + z + a \rightarrow$ number of people reading P or R but not Q.
$a + b + c \rightarrow$ number of people reading only one book
$x + y + z \rightarrow$ number of people reading only two books
$k \rightarrow$ number of people reading all of three books
$(a + b + c) + (x + y + z) + (k) \rightarrow$ number of people reading atleast one book
$(x + y + z) + (k) \rightarrow$ number of people reading atleast two books
$(a + b + c) + (x + y + z) + (k) \rightarrow$ total number of readers.

FINDING THE VALUES OF COMPONENTS

$$P + Q + R = (a + x + k + z) + (b + x + k + y) + (c + y + k + z)$$
$$P + Q + R = (a + b + c) + 2(x + y + z) + 3k$$
$$P + Q + R = \alpha + 2\beta + 3\gamma$$
where $\alpha = a + b + c, \quad \beta = x + y + z, \quad \gamma = k$
Again $(x + k) + (y + k) + (z + k) = (x + y + z) + 3k$
$= \beta + 3\gamma$
$\therefore \quad (\alpha + 2\beta + 3\gamma) - (\beta + 3\gamma) = \alpha + \beta$
and $\quad (\alpha + \beta + \gamma) - (\alpha + \beta) = \gamma$

NOTE 'And' means intersection, 'or' means union

EXAMPLE 1 *In a group of 100 children, 32% play hockey, 64% play football and 40% play cricket. 14% play hockey and football, 15% play football and cricket, 13% play hockey and cricket. Only 6% play all the three games.*

(a) How many children play only one game?
(b) How many children play atleast two game?
(c) How many children play hockey or football but not cricket?

SOLUTION (a) $11 + 41 + 18 = 70$
(b) $(8 + 7 + 9) + 6 = 30$
(c) $(11 + 41) + 8 = 60$



EXAMPLE 2 *In a hostel of 100 students capacity, 42 are science graduate, 34 are law graduate and 58 are commerce graduate. 8 students are science and law graduate, 13 students are law and commerce graduate, 18 students are commerce and science graduate. How many students are only science graduate?*

SOLUTION $\alpha + \beta + \gamma = 100$
$\alpha + 2\beta + 3\gamma = 42 + 34 + 58$
$= 134$
$\beta + 3\gamma = 8 + 13 + 18 = 39$
$\alpha + \beta = (\alpha + 2\beta + 3\gamma) - (\beta + 3\gamma)$
$= 134 - 39 = 95$
$\therefore \quad \gamma = (\alpha + \beta + \gamma) - (\alpha + \beta)$
$\Rightarrow \quad \gamma = 100 - 95 = 5$



∴ Number of students who are only science graduate
$= 42 - [(18 + 8) - 5]$
$= 42 - (13 + 3 + 5) = 21$

EXAMPLE 3 *In a premier B-school having 100 students in the MBA final year, 15 students specializes in Marketing and HR. 17 students specializes in HR and Systems, 16 students specializes in Marketing and Systems. The number of students specializes in only one field is equal and is 22 in each field of specialization. How many students specializes in all three fields viz- Marketing, HR and Systems?*

SOLUTION $\alpha = a + b + c = 22 + 22 + 22 = 66$
$\therefore \quad \beta + \gamma = 100 - \alpha = 100 - 66 = 34$

Scanned by CamScanner

yoursmahboob.wordpress.com

Again $\beta + 3\gamma = x + y + z + 3k$

$= 15 + 16 + 17 = 48$

$\therefore \quad (\beta + 3\gamma) - (\beta + \gamma) = 2\gamma$

$= 48 - 34 = 14$

$\Rightarrow \quad \gamma = 7$

Hence, 7 students specializes in all the three fields.



EXAMPLE 4 *In a music school 28 students learn trumpet, 30 students learn violin and 32 students learn guitar. 6 students learn trumpet and violin, 8 students learn violin and guitar, 10 students learn guitar and trumpet. The number of students who learn only one instrument is 54. Also 20 students learn only violin. Every student learn atleast one instrument out of the three instruments.*

(a) Find the number of students in the music school.

(b) Find the number of students who learn trumpet and guitar but not violin?

SOLUTION



$x + b + k + y = 30$

$b = 20$

$\Rightarrow \quad x + k + y = 10$

But, $\quad (x + k) + (y + k) = 14$

$\Rightarrow \quad (x + y + k) + k = 14$

$\Rightarrow \quad 10 + k = 14$

$\Rightarrow \quad k = 4$



(a) Number of students in music school

$= (16 + 20 + 18) + (2 + 4 + 6) + 4$

$= 70$

(b) Number of students who learn trumpet and guitar but not violin = 6



EXAMPLE 5 *Out of 180 students in a class 7 students failed in all the three subjects viz., Physics, Chemistry, Maths. Only 144 students pass in only one subject and 21 students pass in only two subjects.*

(a) How many students passed in all the three subjects?

(b) How many students passed in atleast two subjects?

(c) How many students passed in at most two subjects but atleast in one subject?

SOLUTION $\alpha = a + b + c = 144$

$\beta = x + y + z = 21$

$\alpha + \beta + \gamma = 180 - 7 = 173$

$\therefore \quad \gamma = (\alpha + \beta + \gamma) - (\alpha + \beta)$

$\Rightarrow \quad \gamma = (173) - (144 + 21)$

$\Rightarrow \quad \gamma = 8 \qquad (\gamma = k)$

(a) 8

(b) Atleast two subjects

$= \beta + \gamma = 21 + 8 = 29$

(c) Atleast one subject but atmost two subjects

$= \alpha + \beta = 144 + 21 = 165.$



EXAMPLE 6 *In a marriage party total 278 guests were present. 20 guests took Pepsi and Dew, 23 guests took Dew and Sprite and 21 guests took Pepsi and Sprite and 9 guests took all the three cold drinks viz. Pepsi, Sprite and Dew. It is also known that there were equal number of bottles of each of three kinds viz. Pepsi, Dew and Sprite*

(a) How many guests took only one bottle colddrink?

(b) How many guests enjoyed Dew or Sprite but not Pepsi?

(c) How many guests enjoyed Pepsi and Dew but not Sprite.

SOLUTION Number of guests

$= (a + b + c) + (11 + 12 + 14) + (9)$

$= 278$

Number of bottles

$= (a + b + c) + 2(11 + 12 + 14) + 3(9)$

$= [(a + b + c) + (11 + 12 + 14) + (9)] + (11 + 12 + 14) + 2(9)$

$= 278 + 55 = 333$

$\therefore \quad$ Each kind of bottles $= \dfrac{333}{3} = 111$



$\because \quad a = 111 - (11 + 9 + 12) = 79$

$b = 111 - (11 + 9 + 14) = 77$

$c = 111 - (12 + 9 + 14) = 76$

(a) Number of guests who took only one bottle $= a + b + c$

$= (79 + 77 + 76) = 232$

(b) Dew or Sprite but not Pepsi $= b + 14 + c$

$= 77 + 14 + 76 = 167$

(c) Dew and Pepsi but not Sprite $= 20 - 9 = 11$

EXAMPLE 7 *250 students appeared in MOCK CAT consisting of three sections viz. Maths, Data Interpretation (DI) and English. 20 students did not qualify any of the three sections and 66 students qualified all the three sections, 24 students did not qualify DI only. 12 did not qualify DI and Maths only. Those who qualified Maths only exceeded those who did not qualify any of the section by 16. Those who did not qualify Maths only exceeded those who did not qualify only DI and Maths by 8. Those who did not qualify English only were twice the number of students who did not qualify Maths only. Find the number of students who has qualified atleast two sections.*

SOLUTION Total students = 250

Number of students who did not qualify any of the three sections = 20

$\therefore$ Number of students who qualified atleast one section

$= 250 - 20 = 230$

Scanned by CamScanner

yoursmahboob.wordpress.com



Ans $y = 24$ (It means 24 students must have qualified English and Maths)

$b = 12$ (It means they have qualified neither DI nor Maths but English only)

$c = 36 = (20 + 16)$

$x = 20 = (12 + 8)$

$z = 40 = (20 \times 2)$

$\therefore \quad (a + b + c) + (x + y + z) + 66 = 230$

$(a + 12 + 36) + (20 + 24 + 40) + 66 = 230$

$\Rightarrow \quad a = 32$

but the required answer $= (x + y + z) + 66$

$= 84 + 66 = 150$

CONCEPT OF MAXIMUM OR MINIMUM

Type 1. In a Business School there are 3 electives and atleast one elective is compulsory to opt. 75% students opted for Marketing, 62% students opted for Finance and 88% students opted for HR. A student can have dual or triple specialization.

(a) What is the minimum number of students that are specialize in all three streams?

(b) What is the maximum number of students that can specialize in all three streams?

SOLUTION (a) 75% students opted for Marketing, it means atleast 25% students opted for HR or Finance or HR and Finance both.



Similarly atleast 12% students opted for Marketing or Finance or Marketing and Finance both.

Again atleast 38% students opted for Marketing or HR or Marketing and HR both.

$\therefore \quad 25 + 12 + 38 = 75\%$

It means that if there is no intersection in these three courses, 75% would be maximum number of students in M, H, F alone or $(M \cap H)$, $(M \cap F)$, $(H \cap F)$.

Thus it gives atleast $25\% = (100 - 75)$ students in all 3 departments.

(b) $(75 - x) + (88 - x) + (62 - x) + x = 100 \Rightarrow x = 62.5\%$



Type 2. In a Business school there are 3 electives offered to the students, where students have a choice of not choosing any electives.

70% students opted for Marketing, 60% students opted for HR and 50% students opted for Finance. 30% students opted for Marketing and HR both, 40% opted for HR and Finance both, 20% opted for Marketing and Finance both.

(a) What is the minimum number of students opted for all 3 electives?

(b) What is the maximum number of students opted for all 3 electives?

SOLUTION Total number of students

$= 70 + (x - 10) + (40 - x) + (x - 10)$

$= 90 + x$



(a) The minimum value of x so that none of the categories becomes negative $= 10$

(b) The maximum value of x so that none of the categories becomes negative $= 20$

Type 3. In a hostel there are 250 students. 120 watch news channels, 80 watch sports channels and 90 watch music channels. Each channel telecasts the content as per their nature 50 students watch both news and sports channel 60 students watch both sports and music channel and 65 students watch both news and music channels.

(a) What is the minimum number of students who watch atleast one of the given channel?

(b) What is the maximum number of students who watch atleast one of the given channels?

(c) What is the minimum number of students who watch all the three types of channels?

(d) What is the maximum number of students who watch all the three types of channels?

SOLUTION Since the number of students cannot be negative

$\therefore \quad \left.\begin{matrix} x - 30 \geq 0 \\ x - 35 \geq 0 \end{matrix}\right\}$

Also $\left.\begin{matrix} 50 - x \geq 0 \\ 60 - x \geq 0 \\ 65 - x \geq 0 \end{matrix}\right\}$



Total number of students playing atleast one game

$= 120 + (x - 30) + (60 - x) + (x - 35) = 115 + x$

(a) Minimum number of students watching atleast one channel $= 115 + 35 = 150$

(b) Maximum number of students watching atleast one channel $= 115 + 50 = 165$

(c) Minimum number of students watching all the 3 channels $= 35$

(d) Maximum number of students watching all the 3 channels $= 50$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. In a city 45% of the people read English and Hindi newspapers. 15% read only Urdu newspaper and 75% read Hindi newspaper. If nobody reads all the three newspapers and everybody read atleast one newspaper out of English, Hindi and Urdu newspapers, how many read Urdu newspaper?
(a) Max 45% (b) Max. 55%
(c) Min 25% (d) Min 30%

Directions for question number 2-5 : In our coaching institute there are total 170 students and they use different vehicles for transportation viz. bike, car and taxi.
The ratio of students using all 3 vehicles to students using atleast 2 vehicles is 2 : 9. The ratio of students using only one vehicle to students using atleast 2 vehicles is 8 : 9.
Number of students using car only exceeds number of students using bike only by 14.
Number of students using taxi only exceeds number of students using bike only by 12. Number of students using taxi, bike, car is 90, 93, 97 respectively.

2. Number of students using all three vehicles is :
(a) 18 (b) 12
(c) 20 (d) none of these

3. Number of students using no more than one vehicles is :
(a) 76 (b) 80
(c) 60 (d) can't be determined

4. Number of students using exactly two vehicles is :
(a) 38 (b) 55
(c) 70 (d) none of these

5. The number of students who are using both bike and car but not taxi is :
(a) 23 (b) 40
(c) 36 (d) data insufficient

6. In a survey among *B*-school students, 68% of those surveyed were in favour of atleast one of the three magazines- *A*, *B* and *C*. 38% of those surveyed favoured magazine *A*, 26% favoured magazine *B* and 36% favoured magazine *C*. If 11% of those surveyed favoured all three magazines. What per cent of those surveyed favoured more than one of the three magazines?
(a) 25% (b) 33%
(c) 21% (d) 26%

Directions of question number 7 and 8: In a class of 80 students 25 passed in QA and DI, 25 passed in DI and English, 20 passed in QA and English. 10 student passed in all the three subjects.

7. How many students passed only in Q.A.?
(a) 20 (b) 15
(c) 12 (d) can't be determined

8. If no student failed in all three subjects, what is the total number of students who passed in QA only, DI only and English only?
(a) 50 (b) 30
(c) 25 (d) can't be determined

Directions for question number 9 and 10: A survey shows that 41%, 35% and 60% of the people watch "Maine Pyaar Kiya" "Maine Pyaar Kyun Kiya" and "Pyaar to Hona Hi Tha" respectively. 27% people watch exactly two of the three movies and 3% watch none.

9. What percentage of people watch all the three movies ?
(a) 40% (b) 6%
(c) 9% (d) 12%

10. If another survey indicates that 16% of the people watch Maine Pyaar Kiya and Pyaar to Hona Hi Tha, and 14% watch Maine Pyaar Kyun Kiya and Pyaar to Hona Hi Tha, then what percentage of the people watch only Maine Pyaar Kyun Kiya? (Use the data from the previous question, if necessary)
(a) 10% (b) 8%
(c) 12% (d) 15%

11. Find the number of positive integers up to 100 which are not divisible by any 2, 3 and 5 ?
(a) 24 (b) 25
(c) 26 (d) 27

12. A survey was conducted at a coaching institution and it was found that there were 34 students who appeared in MAT. There were 37 students who appeared in CAT of which 17 students appeared in MAT. 30 students appeared in XAT of which 13 students appeared in MAT. Of the XAT applicants (*i.e.*, appeared students) 14 appeared in CAT and these 6 appeared in MAT. How many students appeared in CAT but not in MAT or XAT ?
(a) 9 (b) 10
(c) 12 (d) none of these

13. A survey among 151 persons is conduced regarding their favourite channel of radio - Radio city, Radio mirchi and Radio life. It was found that every listener of Radio mirchi also listen either Radio city or Radio life. The number of persons listening all the radio channels is the same as the number of persons who listen none of the channels. 55 persons listen exactly two channels and 70 persons listen only

Scanned by CamScanner

yoursmahboob.wordpress.com

one channel. The number of people who listen all the three channels ?

(a) 16 (b) 13

(c) 9 (d) data insufficient

14. In a group of 132 people 50, 60, 70 people like three different sweets-Barfi, Jalebi, Rasgulla, respectively. The number of people who like all the three sweets is half the number of people who like exactly two sweets. The number of people who like exactly any two out of the three sweets is the same as those who like exactly any other two of the three sweets. The number of people who like the three sweets :

(a) 12 (b) 6

(c) 8 (d) none of these

15. In the previous question (number 14) find the number of people who like Rasgulla or Jalebi but not Barfi.

(a) 82 (b) 42

(c) 48 (d) 38

16. In a group of 80 employees, the number of employees who are engineers is twice that of the employees who are MBAs. The number of employees who are not engineers is 32 and that of those who are not MBAs is 56. The number of employees who are both engineers and MBAs is twice that of the employees who are only MBAs. How many employees are neither engineer (B. Tech) nor MBAs ?

(a) 24 (b) 38

(c) 36 (d) can't be determined

Direction for question number 17-19: *There are 60 workers who work for M/s. Nottan Dibbawala Pvt. Ltd. Mumbai, out of which 25 are women. Also :*

(i) 28 workers are married

(ii) 26 workers are graduate

(iii) 20 married workers are graduate of which 9 are men

(iv) 15 men are graduate

(v) 15 men are married.

17. How many unmarried women are graduate ?

(a) 20 (b) 8

(c) 0 (d) can't be determined

18. How many unmarried women work in the company ?

(a) 11 (b) 12

(c) 9 (d) none of these

19. How many graduate men are married ?

(a) 9 (b) 15

(c) 13 (d) none of these

Directions for question number20-23: *In the year 222 B.C. 100 CAT aspirants appeared in CAT- (Common Admission Test for MBA in some prestigious institutions). They had to show their competency in all the following four areas viz- Maths, Data Interretation (DI), Logical Reasoning (LR) and English.*

Number of aspirants who had qualified Maths is 55.

Number of aspirants who had qualified LR is 38

Number of aspirants who had qualified Maths and English is 30.

Number of aspirants who had qualified LR and English is 15.

Number of aspirants who had qualified Maths and LR is 20.

Number of aspirants who had qualified Maths, LR and English is 5.

Number of aspirants who had qualified DI is 22.

Number of aspirants who had qualified DI and LR is 5.

Number of aspirants who had qualified DI and Maths is 5.

Number of aspirants who had qualified DI, Maths and LR is 5.

Number of aspirants who had qualified English is 50.

Number of aspirants who had qualified English could not qualify DI section.

20. Number of aspirants who had qualified only in DI section :

(a) 17 (b) 22

(c) 27 (d) none of these

21. Number of aspirants who had qualified in only Maths and LR sections :

(a) 20 (b) 10

(c) 28 (d) 38

22. Find the number of aspirants who had qualified in atleast two sections out of 4 sections.

(a) 45 (b) 35

(c) 55 (d) can't be determined

23. Find the number of aspirants who had qualified none of the sections.

(a) 12 (b) 18

(c) 7 (d) 0

24. In a survey among 80 people, 50 people like arrange marriage and 70 people like love marriage. What is the minimum and maximum number of people like both the marriages respectively?

(a) 40, 45 (b) 40,50

(c) 30, 40 (d) can't be determined

25. In a car agency one day 120 cars were decorated with three different accessories *viz.*, power window, AC and music system. 80 cars were decorated with power windows, 65 cars were decorated with AC and 80 cars were decorated with music systems. What is the minimum and maximum number of cars which were decorated with all of three accessories ?

(a) 10 ,61 (b) 10, 45

(c) 25, 35 (d) none of these

26. In our coaching there were 200 students enrolled for DI, 150 for English and 150 for Maths. Of these 80 students enrolled for both DI and English. 60 students enrolled for Maths and English, while 70 students enrolled for DI and Maths. Some of these students enrolled for all the three subjects. Diwakar teaches those students who are enrolled for DI classes only. Priyanka teaches those students who are enrolled for English only and Varun teaches those students who are enrolled for Maths only. Sarvesh is a senior most faculty therefore, he can teach all the three subjects. Students always prefer a specialist for their respective subjects. If Diwakar teaches 80 students then the other three faculty can be arranged in terms of the number of students taught as :

(a) Sarvesh > Varun > Priyanka

(b) Sarvesh > Priyanka > Varun

(c) Varun > Sarvesh > Priyanka

(d) none of the above

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions : ***Answer the question no. 27 to 29 on the basis of the information given below :***

Sanskaram Karoti (SK) is a spiritual organisation involved in performing spiritual rites. Currently it has 37 volunteers. They are involved in three jobs : Body Massage (BM), Yoga and Pooja. Each volunteer working with Sanskaram Karoti (SK) has to be involved in atleast one of the three jobs mentioned above.

- *A maximum number of volunteers are involved in Yoga. Among them, the number of volunteers involved in Yoga alone is equal to the volunteers having additional involvement in the Pooja.*
- *The number of volunteers involved in Pooja alone is double the number of volunteers involved in all the three jobs.*
- *17 volunteers are involved in Body Massage (BM).*
- *The number of volunteers involved in Body Massage alone is one less than the number of volunteers involved in Pooja alone.*
- *Ten volunteers involved in the Body Massage are also involved in atleast one more job.*

27. Based on the information given above, the minimum number of volunteers involved in both Yoga and Body Massage, but not in the Pooja is :

(a) 1 (b) 3
(c) 4 (d) 5

28. Which of the following additional information would enable to find the exact number of volunteers involved in various jobs?

(a) Twenty volunteers are involved in Yoga
(b) Four volunteers are involved in all the three jobs
(c) Twenty three volunteers are involved in exactly one task
(d) No need for any additional information

29. After some time, the volunteers who were involved in all the three tasks were asked to withdraw from one task. As a result, one of the volunteers opted out of the Body Massage and one opted out of the Pooja, while the remaining ones involved in all the three tasks opted out of the Yoga. Which of the following statements, then, necessarily follows?

(a) The least number of volunteers is now performing Body Massage
(b) More volunteers are now associated with Yoga as compared to Pooja
(c) More volunteers are now performing Body Massage as compared to Pooja
(d) None of the above

Answers

INTRODUCTORY EXERCISE-15.1

1. (a)	2. (a)	3. (b)	4. (a)	5. (c)	6. (d)	7. (a)	8. (b)	9. (d)	10. (a)
11. (b)	12. (b)	13. (d)	14. (b)	15. (b)	16. (c)	17. (b)	18. (b)	19. (b)	

LEVEL-1

1. (b)	2. (c)	3. (b)	4. (c)	5. (a)	6. (c)	7. (d)	8. (b)	9. (b)	10. (c)
11. (c)	12. (c)	13. (b)	14. (a)	15. (a)	16. (a)	17. (c)	18. (b)	19. (a)	20. (a)
21. (b)	22. (c)	23. (d)	24. (b)	25. (d)	26. (a)	27. (c)	28. (a)	29. (b)	

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

LEVEL 1

1. It is clear that 45% people cannot read another third (*i.e.*, Urdu) newspaper. Besides them all of the rest people can read Urdu newspaper.
Hence maximum 55% (100 – 45) people can read Urdu newspaper.



Solution for question number 2-5:



$a+b+c=\alpha,\quad x+y+z=\beta\quad k=\gamma$

$\alpha+\beta+\gamma=170$

$\alpha+2\beta+3\gamma=90+93+97=280$

$\gamma:(\beta+\gamma)=2:9$

$\Rightarrow\quad \gamma:\beta=2:7$

and $\quad \alpha:(\beta+\gamma)=8:9$

$\Rightarrow\quad \alpha:\beta:\gamma=8:7:2$

$\therefore\quad \alpha=80,\beta=70$ and $\gamma=20$

$\Rightarrow\quad a+b+c=80,\quad x+y+z=70$ ...(1)

and $\quad k=20$

Again $\quad c-b=14$ and $a-b=12$ ...(2)

On solving eq. (1) and (2) we get $a=30,\ b=18,\ c=32$

Again $(a+x+k+z)-(a+k)=(x+z)$

$=90-(30+20)=40$

and $\quad (x+y+z)-(x+z)=y=70-40=30$

similarly $\quad x=25$ and $z=15$

2. 20

3. 80

4. 70

5. 14

6.

$\alpha+\beta+\gamma=68$

$\alpha+2\beta+3\gamma=(38+26+36)=100$

and $\quad \gamma=11$

$\therefore(\alpha+2\beta+3\gamma)-[(\alpha+\beta+\gamma)+\gamma)]=\beta+\gamma$

$=100-[68+11]$

$=21$

Hence 21% favoured more than one magazine.



($\alpha\rightarrow$ favoured only one magazine, $\beta\rightarrow$ favoured only two magazines, $\gamma\rightarrow$ favoured all three magazines)

Solution for question number 7-8 :

7. Since we don't know how many students failed in all the three subjects, the questions cannot be answered. Hence (d).



8. $(a+b+c)=80-[(15+15+10)+(10)]=30$

9. $\alpha+\beta+\gamma=97\%$



$\alpha+2\beta+3\gamma=41+35+60=136\%$

But $\quad \beta=(x+y+z)=27\%$

$\therefore\quad (\alpha+2\beta+3\gamma)-(\alpha+\beta+\gamma)=\beta+2\gamma=39\%$

$\therefore\quad (\beta+2\gamma)-\beta=2\gamma=39-27=12\%$

$\therefore\quad \gamma=6\%=(k)$

$\therefore$ 6% people watch all the three movies

10. $z+k=16\ \Rightarrow\ z=10\quad\{\because \gamma=k=6\}$

$y+k=14\ \Rightarrow\ y=8$

$\therefore\quad x=9\quad(\because x+y+z=27)$

$\therefore\quad b=35-(x+k+y)=35-(9+6+8)=12\%$

11. Total numbers divisible by 2 upto 100 = 50
Total numbers divisible by 3 upto 100 = 33
Total numbers divisible by 5 upto 100 = 20
Total numbers divisible by 2 and 3 *i.e.*, 6 upto 100 = 16

Scanned by CamScanner

yoursmahboob.wordpress.com



Total numbers divisible by 3 and 5 i.e., 15 upto 100 = 6

Total numbers divisible by 2 and 5 i.e., 10 upto 100 = 10

Total numbers divisible by 2, 3 and 5 i.e., 30 upto 100 = 3

∴Total number of numbers upto 100 which are divisible by at least one of 2, 3 and 5 = 74

∴Total number of numbers upto 100 which are not divisible by any 2, 3 or 5 = 100 − 74 = 26

12.



Hence there are 12 students who appeared in CAT but not in MAT or XAT

13. $\beta = (x + y + z) = 55$

$\alpha = (a + b + c) = 70$

$\gamma = k$

Let m people listen none of the three channels, then $m = \gamma = k$

$$(\alpha + \beta + \gamma) + m = 151$$

$$\Rightarrow \quad \alpha + \beta + \gamma + \gamma = 151$$

$$\Rightarrow \quad (55 + 70) + 2\gamma = 151$$

$$\Rightarrow \quad \gamma = 13$$



Hence, there are 13 people listen all three channels.

14. $\alpha = a + b + c$

$\beta = x + y + z$

$\gamma = k$

Here $\gamma = \frac{1}{2}\beta \Rightarrow 2\gamma = \beta$

Again $x = y = z = p$

$\therefore \quad \beta = 3p$

$\Rightarrow \quad \gamma = \frac{3}{2}p$



Now, $\alpha + 2\beta + 3\gamma = 50 + 60 + 70 = 180$

$\Rightarrow \quad \alpha + 4\gamma + 3\gamma = 180$

$\Rightarrow \quad \alpha + 7\gamma = 180 \quad ...(1)$

Again $\alpha + \beta + \gamma = 132$

$\alpha + 2\gamma + \gamma = 132$

$\Rightarrow \quad \alpha + 3\gamma = 132 \quad ...(2)$

From eq. (1) and (2), we get

$\gamma = 12$

Hence 12 people like all 3 sweets.

15. $\gamma = \frac{3}{2}p \Rightarrow 12 = \frac{3}{2}p$

$\Rightarrow \quad p = 8$

Hence the number of persons who like Rasgulla or Jalebi but not Barfi

$= 32 + 8 + 42 = 82$



16. Let a be the number of engineers only

c be the number of MBAs only

b be the number of employees who are both engineers and MBAs and

d be the number of employees who are neither engineer nor MBA



$\therefore \quad a + b + c + d = 80 \quad ...(1)$

$(a + b) = 2(b + c) \Rightarrow (a - b) = 2c \quad ...(2)$

and $c + d = 32 \quad ...(3)$

and $a + d = 56 \quad ...(4)$

and $b = 2c \quad ...(5)$

From eq. (2) and (5), we get

$a = 2b \quad ...(6)$

From eq. (1) and (3), we get

$a + b = 48$

From eq. (6), we get

$b = 16$

$\therefore \quad a = 32$ (from eq. 6)

and $c = 8$ (from eq. 5)

and $d = 24$

Hence 24 employees are neither engineer nor MBAs.

Solutions for question number 17-19:

Total number of employees $= 60$

Women $= 25$

Men $= 35$

Married workers $= 28$

Graduate workers $= 26$

$a \rightarrow$ *unmarried men who are not graduate*

$b \rightarrow$ *married women who are not graduate*



$c \rightarrow$ *unmarried women who are graduate*

$x \rightarrow$ *married men who are not graduate*

$y \rightarrow$ *married women who are graduate*

$z \rightarrow$ *unmarried men who are graduate*

$k \rightarrow$ *married men who are graduate*

$p \rightarrow$ *unmarried women who are not graduate*

According to the given information the Venn diagram can be completed as given below.

17. No one unmarried woman is graduate. Hence (c)



Scanned by CamScanner

yoursmahboob.wordpress.com

18. Number of unmarried women
$= 60 - [14 + 2 + 6 + 6 + 11 + 9] = 12$

19. There are 9 graduate men who are married

Solutions of question number 20-23:



20. 17
21. 10
22. 55
23. 0

24. For the minium value of x people who like only arrange marriage and only love marriage must be greater



$\therefore \quad x = (70 + 50) - 80 = 40$

For the maximum value of x: $(50 - x)$ and $(70 - x)$ must not be negative, therefore max. possible value of x is 50.

25. 80 cars were decorated with power windows it means at least 40 cars were decorated with AC or music system or both.
84 cars were decorated with ACs, it means atleast 36 cars were decorated with power windows or music systems.
80 cars were decorated with music system means at least 40 cars were decorated with power windows or ACs.
It means if there is no intersection in these three, then at most 40 + 36 + 40 = 116 cars had been decorated with one or two accessories.
Hence at least 4 cars would have been decorated with all three accessories.

For maximum value of x :



Total number of cars $= (80 - x) + (84 - x) + (80 - x) + x$

$120 = 244 - 2x$

$\Rightarrow \quad 2x = 124 \Rightarrow x = 62$

minimum → 4 cars and maximum → 62 cars

26. $a + x + k + z = 200$ ...(i)
$b + x + k + y = 150$ ...(ii)
$c + y + k + z = 150$ ...(iii)
But since Diwakar teaches only 80 students of DI.
Therefore, $a = 80$
Hence, $x + k + z = 120$
but $(x + k) + (k + z) = 150$
$\therefore \quad k = 30$
Hence, $x = 50, \; z = 40, \; y = 30, \; b = 40$





$\therefore$ No. of students taught by Diwakar $= a = 80$
No. of students taught by Priyanka $= b = 40$
No. of students taught by Varun $= c = 50$
No. of students taught by Sarvesh $= x + y + z + k = 150$
Hence choice (a) is correct.

Solutions for question no. 27-29 :



Remember : *Maximum number of volunteers are involved in Yoga.*

Now,
$b = k + y$ ...(1)
$c = 2k$ ...(2)
$a + x + k + z = 17$ ...(3)
$a = c - 1$ ...(4)
$x + k + z = 10$ ...(5)

From eq. (3) *and* (5), *we obtain*
$a = 7$ ...(6)

and from eq. (4) *and* (6), *we obtain*
$c = 8 \Rightarrow k = 4$
$\therefore \quad (z + x) = 6 \Rightarrow x = (6 - z)$
$\therefore \quad b = (y + 4)$ *from eq.* (1).



Again $7 + (6 - z) + 4 + z + (y + 4) + y + 8 = 37$
$\Rightarrow \quad 29 + 2y = 37 \Rightarrow y = 4$

Scanned by CamScanner

yoursmahboob.wordpress.com

27. Since no. of volunteers involved in Yoga are maximum so we can compare it from the no. of volunteers involved in Pooja and that of Body Massage.



Since

$6 - z > z \forall\ z \in (0, 1, 2, 3, \ldots)$

$\therefore \quad z = 0, 1, 2 \Rightarrow (6 - z) = 4, 5, 6$

Hence the minimum possible value of $(6 - z) = 4$.

28. See the venn diagram shown in solution no. 27,then you will notice that you are required to know the value of y.

Thus from the data provided by choice (a) enable us to calculate all the required details.

$\because \quad \{(6 - z) + 4 + 4 + 8\}_{\text{Yoga}} = 20$

$\Rightarrow \quad z = 4$

Hence, we can find the exact number of volunteers involved in various projects.

NOTE Coincidentally we obtain $z = 4$ in both the questions 27 and 28 but actually these two answers have no any relation between them.

29. Initially



After the withdraw of volunteers :



The volunteer who is opted out of the BM will be involved in the Yoga and Pooja.

Similarly the volunteer who is opted out of Pooja will be involved in the BM and Yoga.

and the remaining two volunteers who are opted out of Yoga will be involved in BM and Pooja.

NOTE Since initially 4 volunteers are involved in all the three jobs, but when a volunteer leave one job, he or she still continue to perform other two jobs.

Total no. of volunteers in BM $= 7 + (x + 1) + 0 + (z + 2)$

$= 16 \qquad (\because\ x + z = 6)$

Since we know that $x = 4, 5, 6$

Therefore corresponding values of $z = 2, 1, 0 \quad (\because\ x + z = 6)$

$\therefore$ No. of volunteers involved in Yoga = 18, 19 or 20

and No.of volunteers involved in Pooja = 17, 16 or 15

Hence it is clear that choice (b) is correct.

❑❑❑

Scanned by CamScanner

yoursmahboob.wordpress.com

16 LOGARITHM

Atleast one question from this chapter is necessarily being asked in CAT. Whenever a question appears related with logarithm, it is of applied nature and the logic behind the question is the application of logarithm.

One more thing I would like to mention that many a student are scared of this chapter. But In my opinion they should not bother about the word 'logarithm' instead they should look the problems of logarithm as problems of exponents and most of the problems can be easily solved by plotting the graph. Notice that this chapter is important for SNAP, MAT, IIFT, JMET and XAT etc.

EXPONENTIAL FUNCTION

For every $x \in R$, $e^x = 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!} + \ldots \frac{x^n}{n!} + \ldots$

or $$e^x = \sum_{n=0}^{\infty} \frac{x^n}{n!}$$

Here e^x is called as exponential function and it is a finite number for every $x \in R$.

Properties : For every $x \in R$, e^x is defined, then

(i) $e^x > 0$ for all $x \in R$ and $e^0 = 1$

(ii) $e^a > e^b$ if $a > b$ and $a, b \in R$

(iii) $e^a \times e^b = e^{(a+b)}$ for all $a, b \in R$

(iv) $e^a \div e^b = e^{(a-b)}$ for all $a, b \in R$

(v) $(e^a)^b = e^{ab}$ for all $a, b \in R$

(vi) For each positive real number x there exists one and only one real number y such that $e^y = x$

(vii) e^x is one-one function

(viii) $e \approx 2.714$



Graph of $y = e^x$

Logarithm : Let a, b be positive real numbers then $a^x = b$ can be written as

$$\log_a b = x; \quad a \neq 1, a > 0, b > 0$$

e.g., $2^5 = 32 \Leftrightarrow \log_2 32 = 5$

$10^3 = 1000 \Leftrightarrow \log_{10} 1000 = 3$

$3^{-4} = \frac{1}{81} \Leftrightarrow \log_3\left(\frac{1}{81}\right) = -4$ etc.

(i) Natural Logarithm : $\log_e N$ is called Natural logarithm or Naperian Logarithm, denoted by $\ln N$ *i.e.,* when the base is 'e' then it is called as Natural logarithm.

e.g., $\log_e 5, \log_e\left(\frac{1}{81}\right), \log_e 72 \ldots$ etc.

(ii) Common Logarithm : $\log_{10} N$ is called common logarithm or Brigg's Logarithm *i.e.,* when base of log is 10, then it is called as common logarithm

e.g., $\log_{10}(100), \log_{10} 25, \log_{10} 248$ etc.

PROPERTIES OF LOGARITHM

1. $\log_a 1 = 0, \quad a > 0, a \neq 1$
2. $\log_a a = 1, \quad a > 0, a \neq 1$
3. $\log_a a^x = x \; \forall \; x \in R, x > 0$
4. $a^{\log_a x} = x \; \forall \; x \in R, x > 0$

NOTE $\log_a a^x$ is the inverse function of a^x.

5. $\log_a (m.n) = \log_a m + \log_a n \; \forall \; m, n > 0, a > 0, a \neq 1$
6. $\log_a (m/n) = \log_a m - \log_a n \; \forall \; m, n > 0, a > 0, a \neq 1$
7. $\log_a (m^n) = n \log_a m \; \forall \; m > 0, a > 0, a \neq 1$
8. $\log_a\left(\frac{1}{m}\right) = -\log_a m \; \forall \; m > 0, a > 0, a \neq 1$
9. $\log_a b = \frac{1}{\log_b a} = \frac{\log_c b}{\log_c a}$

   $\forall \; a, b, c > 0$ and $a \neq 1, b \neq 1, c \neq 1$
10. If $\log_a b = x \; \forall \; a > 0, a \neq 1, b > 0$ and $x \in R$

    (i) $\log_{(1/a)} b = -x$

Scanned by CamScanner

yoursmahboob.wordpress.com

(ii) $\log_a\left(\frac{1}{b}\right) = -x$

(iii) $\log_{1/a}\left(\frac{1}{b}\right) = x$

11. $\log_{a^m}(b) = \frac{1}{m}\log_a b$

12. $\log_a x$ is a decreasing function, if $0 < a < 1$

13. $\log_a x$ is an increasing function, if $a > 1$

NOTE The base of logarithm can never be equal to 1.
i.e., $\log_1 x$ is undefined $\forall x$

14. On the real number line the base of logarithm can assume any positive real value except 1 (*i.e.*, unity)
Hence at $a = 1$, $\log_a x$ is not defined; $x > 0$



Thus at $a > 0$ except $a = 1$, $\log_a x$ is defined; $x > 0$

15. On the real number line x can assume any positive real value (number) for $\log_a x$; $a > 0, a \neq 1$



Thus the logarithm of only positive values is defined
i.e., $\log_a x$ is defined for every $x > 0, a > 0, a \neq 1$
Hence for $f(x) = \log_a x$
Domain $\to R^+$ and Range $\to R$

16.



at $a = 1$, $\log_a x$ is not defined.

17.



For $0 < a < 1$

$\log_a x > 1$ if $x < a$ $\forall x > 0$

$\log_a x = 1$ if $x = a$ $\forall x > 0$

$\log_a x < 1$ if $x > a$ $\forall x = 0$

18.



For $a > 1$

$\log_a x < 1$ if $x < a$ $\forall x > 0$

$\log_a x = 1$ if $x = a$ $\forall x > 0$

$\log_a x > 1$ if $x > a$ $\forall x > 0$

19.	$0 < a < 1$	$a > 1$
	$\log_a x$ is a decreasing function	$\log_a x$ is an increasing function
	$\log_a x > \log_a y$ $(x < y)$ *i.e.*, inequality gets reversed	$\log_a x < \log_a y$ $(x < y)$ *i.e.*, the inequality remains unchanged
		
	Sign of $\log_a x$	Sign of $\log_a x$
		
20.	$0 < a < 1$	$a > 1$
	 Domain $\to R$ Range $\to R^+$	 Domain $\to R$ Range $\to R^+$
	Decreasing function	Increasing function

21. For $|x| < 1$

(i) $\log(1+x) = \left(x - \frac{x^2}{2} + \frac{x^3}{3} - \frac{x^4}{4} + \ldots\right)$

(ii) $\log(1-x) = -\left(x + \frac{x^2}{2} + \frac{x^3}{3} + \frac{x^4}{4} + \ldots\right)$

(iii) $\log\left(\frac{1+x}{1-x}\right) = 2\left[x + \frac{x^3}{3} + \frac{x^5}{5} + \ldots\right]$

(iv) $\log 2 = \left(1 - \frac{1}{2} + \frac{1}{3} - \ldots\right)$

Scanned by CamScanner

yoursmahboob.wordpress.com

(v) $\log_{10} 2 = 0.3010$

(vi) $\log_{10} 3 = 0.4771$

22. Logarithmic Inequalities

$0 < a < 1$	$a > 1$
$\log_a b \geq \log_a c \Leftrightarrow b \leq c$	$\log_a b \geq \log_a c \Leftrightarrow b \geq c > 0$
$\log_a b \geq c \Leftrightarrow b \leq a^c$	$\log_a b \geq c \Leftrightarrow b \geq a^c$

CHARACTERISTICS AND MANTISSA

Characteristic : The integral part of logarithm is known as characteristic.

Mantissa : The decimal part is known as mantissa and is always positive.

e.g., In $\log_a x$, the integral part of x is called the characteristic and the decimal part of x is called the mantissa.

For example : In $\log 3274 = 3.5150$, the integral part is 3 *i.e.*, characteristic is 3 and the decimal part is .5150 *i.e.*, mantissa is .5150.

To find the characteristic of common logarithm $\log_{10} x$:

(a) When the number is greater than 1 *i.e.*, $x > 1$
In this case , the characteristic is one less than the number of digits in the left of the decimal point in the given number.

(b) When the number is less than 1 *i.e.*, $0 < x < 1$
In this case the characteristic is one more than the number of zeros between the decimal point and the first significant digit of the number and is negative.

NOTE The characteristic may be positive or negative. If the characteristic is negative, it is always represented by putting a bar on the number *i.e.*,

$-1 \to \bar{1}$
$-2 \to \bar{2}$
$-3 \to \bar{3}$

EXAMPLE

Number	Characteristic	Number	Characteristic
8.3145	0	0.457	$\bar{1}$
74.8120	1	0.0546	$\bar{2}$
568.31	2	0.001324	$\bar{3}$

Remark : (1) Students must note that $\bar{2}.784$ is not the same as -2.784

i.e., $\bar{2}.784 = (-2) + (.784)$

$-2.784 = (-2) - (.784)$

(2) If the logarithm of a number is negative, then we have to make the **mantissa** positive.
For this we subtract 1 from the integral part and add up 1 to the decimal part.

e.g., $-2.5436 = (-2) + (-.5436)$ Step 1.

$\Rightarrow \quad = (-2-1) + (-.5436+1)$ Step 2.

$\Rightarrow \quad = (-3) + (.4564)$ Step 3.

$\Rightarrow \quad = \bar{3}.4564$ Step 4.

POINTS TO REMEMBER ABOUT CHARACTERISTICS

1. The characteristic of common logarithm of positive number less than unity (*i.e.*, 1) is negative.
2. The characteristic of common logarithm of a positive number greater than 1 is positive.
3. If the logarithm to any base a gives the characteristic 'n', then the number of possible integral values is given by $a^{n+1} - a^n$.
   For example $\log_{10} x = n.abcd$, then the number of integral values that x can have given by $10^{n+1} - 10^n$
   e.g., $\log_{10} x = 2.abcd$ gives $10^{2+1} - 10^2 = 900$ integral values for x *i.e.*, $x = 100, 101, 102, 103, \ldots 998, 999$. For all these 900 integral numbers (100 – 999) all the characteristic is 2.
   Similarly $\log_{10} x = 3.abcd$ give $10^{3+1} - 10^3 = 9000$ integral values for x *i.e.*, $x = 1000, 1001, 1002, \ldots, 9999$. For all these 9000 integral numbers (1000 – 9999) the characteristic is 3.
4. If the characteristic of $\log_{10} x$ is negative (*i.e.*, $-n$), then the number of zeros between the decimal and the first significant number after the decimal is $(n-1)$
   e.g., $\log_{10} x = -3.abcd$ has $a = 0$ and $b = 0$.
   i.e., first two places after the decimal point are filled with zeros since characteristic is -3.

Hence $\log_{10} x = -3.abcd = -3.00cd$

IMPORTANT CONVERSIONS

(i) For $a > 1, a \neq 1, c > 0$

$$a^b > c \Leftrightarrow \log_a c < b$$

(ii) For $0 < a < 1, a \neq 1, c > 0$

$$a^b > c \Leftrightarrow \log_a c > b$$

EXAMPLE 1 *The value of log 6 is equal to :*

(a) $\log 1 + \log 2 + \log 3$ (b) $\log (1 + 2 + 3)$
(c) $\log (1 \times 2 \times 3)$ (d) *all of the above*

SOLUTION $\log 6 = \log (1 \times 2 \times 3) = \log 1 + \log 2 + \log 3$

Also $\log 6 = \log (1 + 2 + 3)$, Hence (d)

EXAMPLE 2 *Find the value of* $\log_8 128$.

SOLUTION Let $\log_8 128 = x$

$\Rightarrow \quad 8^x = 128$

$\Rightarrow \quad 2^{3x} = 2^7$

$\Rightarrow \quad 3x = 7$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow \quad x = \frac{7}{3}$

$\therefore \quad \log_8 128 = \frac{7}{3}$

EXAMPLE 3 *Find the value of* $\log_{5\sqrt{5}}(125)$.

SOLUTION Let $\log_{5\sqrt{5}}(125) = x$

$\Rightarrow \quad (5\sqrt{5})^x = 125$

$\Rightarrow \quad 5^{(3/2)x} = 5^3$

$\Rightarrow \quad \frac{3}{2}x = 3 \Rightarrow x = 2$

$\therefore \quad \log_{5\sqrt{5}}(125) = 2$

EXAMPLE 4 *Find the value of* $\log_5 \log_5(3125)$.

SOLUTION $\log_5 \log_5(3125) = \log_5 \log_5 5^5 = \log_5 5 \log_5 5$

$= \log_5 5.1 \qquad (\because \log_5 5 = 1)$

$= \log_5 5 = 1$

$\therefore \quad \log_5 \log_5(3125) = 1$

EXAMPLE 5 *If* $\log_{10} x - \log_{10} \sqrt{x} = \frac{2}{\log_{10} x}$, *find the value of* x.

SOLUTION $\log_{10} x - \log_{10} \sqrt{x} = \frac{2}{\log_{10} x}$

$\Rightarrow \quad \log_{10}\left(\frac{x}{\sqrt{x}}\right) = \frac{2}{\log_{10} x}$

$\Rightarrow \quad \log_{10}(x)^{1/2} = \frac{2}{\log_{10} x}$

$\Rightarrow \quad \frac{1}{2}\log_{10} x = \frac{2}{\log_{10} x}$

$\Rightarrow \quad \frac{1}{2}(\log_{10} x)^2 = 2$

$\Rightarrow \quad (\log_{10} x)^2 = 4$

$\Rightarrow \quad \log_{10} x = \pm 2$

If $\log_{10} x = 2 \Rightarrow x = 10^2 \Rightarrow x = 100$

If $\log_{10} x = -2 \Rightarrow x = 10^{-2} \Rightarrow x = \frac{1}{100}$

$\therefore \quad x = 100, \frac{1}{100}$

EXAMPLE 6 *Find the value of* $\log_y x \times \log_z y \times \log_x z$.

(a) 0 (b) 1 (c) $\log x$ (d) xyz

SOLUTION $\log_y x \times \log_z y \times \log_x z$

$= \frac{\log_a x}{\log_a y} \times \frac{\log_a y}{\log_a z} \times \frac{\log_a z}{\log_a x} = 1$

EXAMPLE 7 *If* $\frac{\log a}{b-c} = \frac{\log b}{c-a} = \frac{\log c}{a-b}$, *then find the value of* $a^a \cdot b^b \cdot c^c$.

SOLUTION We have,

$\frac{\log a}{b-c} = \frac{\log b}{c-a} = \frac{\log c}{a-b} = k$ (say)

Then, $\log a = k(b-c)$

$\log b = k(c-a)$

$\log c = k(a-b)$

Let $A = a^a \cdot b^b \cdot c^c$

Then $\log A = a \log a + b \log b + c \log c$

$= ak(b-c) + bk(c-a) + ck(a-b)$

$= abk - ack + bck - abk + cak - bck = 0$

Thus $\log A = 0 = \log 1$

$\therefore \quad A = 1$

i.e., $a^a \cdot b^b \cdot c^c = 1$

EXAMPLE 8 *Find the value of* $\log_8 25$, *given that* $\log_{10} 2 = 0.3010$.

SOLUTION $\log_8 25 = \frac{\log_{10} 25}{\log_{10} 8} = \frac{2}{3}\frac{\log 5}{\log 2} = \frac{2\log_{10}(10/2)}{3\log_{10} 2}$

$= \frac{2(\log_{10} 10 - \log_{10} 2)}{3 \times 0.3010}$

$= \frac{2(1 - 0.3010)}{0.9030} = 1.5482$

EXAMPLE 9 *Find the value of* $\frac{\log\sqrt{27} + \log 8 + \log\sqrt{1000}}{\log 120}$.

SOLUTION $\frac{\log(27)^{1/2} + \log 2^3 + \log(10^3)^{1/2}}{\log(3 \times 2^2 \times 10)}$

$= \frac{\frac{1}{2}\log 3^3 + 3\log 2 + \frac{1}{2}\log(10)^3}{\log 3 + \log 2^2 + \log 10}$

$= \frac{\frac{3}{2}\log 3 + \frac{3}{2} \cdot 2\log 2 + \frac{3}{2}\log 10}{\log 3 + 2\log 2 + \log 10}$

$= \frac{\frac{3}{2}(\log 3 + 2\log 2 + \log 10)}{\log 3 + 2\log 2 + \log 10} = \frac{3}{2}$

EXAMPLE 10 *Solve for* x, *if* $\log_x(8x-3) - \log_x 4 = 2$

SOLUTION $\log_x(8x-3) - \log_x 4 = 2$

$\Rightarrow \quad \log_x\left(\frac{8x-3}{4}\right) = 2$

$\Rightarrow \quad x^2 = \frac{8x-3}{4}$

$\Rightarrow \quad 4x^2 - 8x + 3 = 0$

$\Rightarrow \quad x = \frac{3}{2}$ or $\frac{1}{2}$

EXAMPLE 11 *Find the value of*

$x^{\log y - \log z} \times y^{\log z - \log x} \times z^{\log x - \log y}$

SOLUTION Let $P = x^{\log y - \log z} \times y^{\log z - \log x} \times z^{\log x - \log y}$

Then $\log P = \log x^{\log y - \log z} + \log y^{\log z - \log x} + \log z^{\log x - \log y}$

$= (\log y - \log z)\log x + (\log z - \log x)\log y$

$+ (\log x - \log y)\log z$

$= \log x \log y - \log z \log x + \log y \log z - \log x \log y$

$+ \log z \log x - \log y \log z = 0$

Scanned by CamScanner

yoursmahboob.wordpress.com

Logarithm

i.e., $\log P = 0 = \log 1$

$\therefore \quad P = 1$

EXAMPLE 12 *If* $\dfrac{xy\log(xy)}{x+y} = \dfrac{yz\log(yz)}{y+z} = \dfrac{zx\log(zx)}{z+x}$, *then show that* $x^x = y^y = z^z$.

SOLUTION $\dfrac{xy\log(xy)}{x+y} = \dfrac{yz\log(yz)}{y+z} = \dfrac{zx\log(zx)}{z+x} = k$ (say)

Then $xy\log xy = k(x+y)$

or $\log xy = k\left(\dfrac{1}{x}+\dfrac{1}{y}\right)$

or $\log x + \log y = k\left(\dfrac{1}{x}+\dfrac{1}{y}\right)$ ...(1)

Similarly, $\log y + \log z = k\left(\dfrac{1}{y}+\dfrac{1}{z}\right)$ ...(2)

and $\log z + \log x = k\left(\dfrac{1}{z}+\dfrac{1}{x}\right)$ ...(3)

Adding (1), (2) and (3), we get

$$2(\log x + \log y + \log z) = 2k\left(\frac{1}{x}+\frac{1}{y}+\frac{1}{z}\right)$$

or $\log x + \log y + \log z = k\left(\dfrac{1}{x}+\dfrac{1}{y}+\dfrac{1}{z}\right)$ ...(4)

Subtracting (1), (2) and (3) successively from (4), we get

$$\log z = k\cdot\frac{1}{z}, \quad \log x = k\cdot\frac{1}{x}, \quad \log y = \frac{k}{y}$$

or $z\log z = k, \quad x\log x = k$ and $y\log y = k$

or $x\log x = y\log y = z\log z$

or $\log(x^x) = \log(y^y) = \log(z^z)$

Hence $x^x = y^y = z^z$

EXAMPLE 13 *If* $\log_a bc = x$, $\log_b ca = y$, $\log_c ab = z$, *prove that*

$$\frac{1}{x+1}+\frac{1}{y+1}+\frac{1}{z+1} = 1$$

SOLUTION $\dfrac{1}{x+1}+\dfrac{1}{y+1}+\dfrac{1}{z+1}$

$$= \frac{1}{(\log_a bc)+1}+\frac{1}{(\log_b ca)+1}+\frac{1}{(\log_c ab)+1}$$

$$= \frac{1}{\log_a bc + \log_a a}+\frac{1}{\log_b ca + \log_b b}+\frac{1}{\log_c ab + \log_c c}$$

$$= \frac{1}{\log_a abc}+\frac{1}{\log_b abc}+\frac{1}{\log_c abc}$$

$$= \log_{abc} a + \log_{abc} b + \log_{abc} c \qquad \left(\because \log_a b = \frac{1}{\log_b a}\right)$$

$$= \log_{abc}(abc) = 1$$

EXAMPLE 14 *Given* $\log 2 = 0.3010$ *and* $\log 3 = 0.4771$, *find the value of* $\log 45$.

SOLUTION $\log 45 = \log 3^2 \cdot 5 = \log 3^2 + \log 5 = 2\log 3 + \log 5$

$$= 2\times 0.4771 + \log\frac{10}{2}$$

$$= 0.9542 + \log 10 - \log 2$$

$$= 0.9542 + 1 - 0.3010$$

$$= 1.6532$$

EXAMPLE 15 *Given* $\log 2 = 0.3010$ *and* $\log 3 = 0.4771$. *Find the value of* $\log 0.0075$.

SOLUTION $\log 0.0075 = \log\dfrac{75}{10000} = \log 75 - \log 10000$

$$= \log 3\times 5^2 - \log 10^4$$

$$= \log 3 + 2\log 5 - 4\log 10$$

$$= \log 3 + 2[\log 10 - \log 2] - 4\log 10$$

$$= 0.4771 + 2[1 - 0.3010] - 4$$

$$= -2.1249$$

EXAMPLE 16 *What is the number of digits in* 3^{3^3}? *Given that* $\log 3 = 0.47712$?

SOLUTION Let $x = 3^{3^3} = (3)^{3^3}$

Then $\log x = 3^3 \log 3$

$$= 27\times 0.47712 = 12.88224$$

Since the characteristic in the resultant value of $\log x$ is 12

$\therefore$ The number of digits in x is $(12+1) = 13$

Hence the required number of digits in 3^{3^3} is 13.

EXAMPLE 17 *If* $\log 3 = 0.4771$, *find the number of digits in* 3^{43}.

SOLUTION Let $x = 3^{43}$

$\therefore \quad \log x = \log 3^{43} = 43\log 3 = 43\times 0.4771$

$$= 20.5153$$

Since the characteristic of $\log 3^{43}$ is 20, then number of digits in 3^{43} is $(20+1) = 21$.

EXAMPLE 18 *How many zeros are there between the decimal point and the first significant figure in* $(0.5)^{100}$? *Given that* $\log\dfrac{1}{2} = \bar{1}.6990$

SOLUTION Let $x = (0.5)^{100}$

$\therefore \quad \log x = 100\log(0.5) = 100\times\bar{1}.6990$

$$= 100(-1 + 0.6990)$$

$$= -100 + 69.90$$

$$= -31 + 0.90 = \bar{31}.90$$

Since the characteristics of $\log(0.5)^{100}$ is $\bar{31}$, the number of zeros between the decimal point and the first significant figure is $31 - 1 = 30$.

EXAMPLE 19 *If* $\dfrac{x(y+z-x)}{\log x} = \dfrac{y(z+x-y)}{\log y} = \dfrac{z(x+y-z)}{\log z}$, *then :*

(a) $xy = yz = zx$ (b) $x^y y^x = z^y y^z = x^z z^x$

(c) $xyz = 1$ (d) *none of these*

Scanned by CamScanner

yourshahbob.wordpress.com

SOLUTION Let $\frac{x(y+z-x)}{\log x} = \frac{y(z+x-y)}{\log y}$

$$= \frac{x(x+y-z)}{\log z} = \frac{1}{k} \quad \text{(say)}$$

$\Rightarrow$ $\log x = kx(y+z-x)$

$\log y = ky(z+x-y)$

$\log z = kz(x+y-z)$

Hence $y \log x + x \log y = 2kxyz$

$y \log z + z \log y = 2kxyz$

$z \log x + x \log z = 2kxyz$

Thus $y \log x + x \log y = y \log z + z \log y$

$= z \log x + x \log z$

$\Rightarrow$ $\log(x^y y^x) = \log(z^y y^z) = \log(x^z z^x)$

$\Rightarrow$ $x^y y^x = z^y y^z = x^z z^x$

INTRODUCTORY EXERCISE-16.1

1. If $x^y = k$, then :
(a) $\log_y k = x$ (b) $\log_x y = k$
(c) $\log_k x = y$ (d) $\log_x k = y$

2. If $\log_m n = p$, then :
(a) $m^n = p$ (b) $p^n = m$
(c) $m^p = n$ (d) $n^p = m$

3. $\log_a(mn)$ is equal to :
(a) $n \log_a(m)$ (b) $\log_a m \times \log_a n$
(c) $\log_a m + \log_a n$ (d) $\log_a m - \log_a n$

4. $\log_a\left(\frac{m}{n}\right)$ is equal to :
(a) $\log_a(m-n)$ (b) $\log_a m - \log_a n$
(c) $\frac{(\log_a m)}{n}$ (d) $\log_a m \div \log_a n$

5. The value of $\log_{81} 27$ is :
(a) 3^7 (b) $\frac{4}{3}$
(c) $\frac{3}{4}$ (d) $\frac{1}{3}$

6. The value of $\log_{36} \frac{1}{216}$ is :
(a) $\frac{2}{3}$ (b) $-\frac{3}{2}$
(c) $\frac{1}{6}$ (d) none of these

7. The value of $\log_{\sqrt{6}} 216$ is :
(a) $\frac{1}{6}$ (b) $\sqrt{6}$
(c) 3 (d) 6

8. The value of $\log_{3\sqrt{2}} 5832$ is :
(a) 12 (b) 9
(c) 6 (d) none of these

9. The value of $\log_{(-1/5)} 625$ is :
(a) $\frac{1}{4}$ (b) -5
(c) -4 (d) -3

10. The value of $\log_{10}(0.0001)$ is :
(a) $\frac{1}{1000}$ (b) -3
(c) -4 (d) none of these

11. The value of $\log_{(0.01)}(10000)$ is :
(a) 1/2 (b) -2
(c) 1/4 (d) -4

12. The value of $(\log_4 32 + \log_9 243)$:
(a) 5 (b) 4
(c) 3 (d) none of these

13. The value of $(\log_2 8 + \log_3 9 + \log_5 25)$ is :
(a) 5 (b) 6
(c) 7 (d) none of these

14. The value of $\log_2(\log_3 81)$ is :
(a) 0 (b) 1
(c) 2 (d) 6

15. The value of $\log_2 \log_2 \log_3 \log_5(125)^3$ is :
(a) 0 (b) 1
(c) 2 (d) 3

16. The value of $\log_2 \log_2 \log_2 \log_2(65536)$ is :
(a) 4 (b) 2
(c) 1 (d) 0

17. The value of
$\log_{10} 1 + \log_{10} 10 + \log_{10} 100 + \ldots \log_{10} 10000000000$
(a) 10 (b) 11
(c) 11111111111 (d) 55

18. The value of $\log_5 5 + \log_5 5^2 + \log_5 5^3 + \ldots + \log_5 5^n$:
(a) $n!$ (b) $n^2 - 1$
(c) $\frac{(n+1)n}{2}$ (d) none of these

19. The value of $27^{\log_3 81}$ is :
(a) 27381 (b) 531441
(c) 65631 (d) none of these

20. The value of ${}_{216}\log_6 49$ is :
(a) 117694 (b) 117649
(c) 216649 (d) none of these

21. The value of $25^{(-1/4\log_5 25)}$ is :
(a) $\frac{1}{5}$ (b) $-\frac{1}{25}$
(c) -25 (d) none of these

22. $(\log_{10} 500000 - \log_{10} 5)$ is equal to :
(a) 5 (b) 50
(c) 49995 (d) 100000

23. If $\log_5[\log_3(\log_2 x)] = 1$, then x is :
(a) 2^{234} (b) 243
(c) 2^{243} (d) none of these

24. If $\log_2 \log_{10} 4x = 1$, then the value of x is :
(a) 1/25 (b) 25
(c) 5 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

25. If $\log_{27} x = \frac{4}{3}$, then the value of x is :
(a) 9 (b) 27
(c) 81 (d) none of these

26. If $\log_x\left(\frac{4}{9}\right) = -\frac{1}{2}$, then the value of x is :
(a) $\frac{16}{81}$ (b) $-\frac{2}{3}$
(c) $\frac{81}{16}$ (d) none of these

27. If $\log_{100} x = -4$, then the value of x is :
(a) $\frac{1}{(10)^{-4}}$ (b) $(10)^{-4}$
(c) $\frac{1}{(10)^8}$ (d) none of these

28. If $\log_{100} x = -\frac{1}{2}$, then the value of x is :
(a) 0.001 (b) $\frac{1}{10}$
(c) 0.00001 (d) 10^{-2}

29. If $\log_x(0.2) = -\frac{1}{4}$, then the value of x is :
(a) 4^{-5} (b) 0.016
(c) 5^4 (d) none of these

30. The value of x satisfying $\log_{243} x = 0.8$ is :
(a) 81 (b) 1.8
(c) 2.43 (d) none of these

31. If $\log_e(x-1) + \log_e x + \log_e(x+1) = 0$, then
(a) $x^2 + e^{-1}$ (b) $x^3 - x - 1 = 0$
(c) $x^2 + e - 1 = 0$ (d) $x^3 - x - e = 0$

32. The value of $\log_3 5 \times \log_{25} 9$ is :
(a) 0 (b) 1
(c) 2 (d) 4

33. The value of $\left(\log\frac{14}{3} + \log\frac{11}{5} - \log\frac{22}{15}\right)$ is :
(a) log 77 (b) log 11
(c) log 7 (d) none of these

34. The value of $\left[3\log\left(\frac{81}{80}\right) + 5\log\left(\frac{25}{24}\right) + 7\log\left(\frac{16}{15}\right)\right]$ is :
(a) log 3 (b) log 5
(c) log 7 (d) log 2

35. $\left(\log\frac{a^3}{bc} + \log\frac{b^3}{ac} + \log\frac{c^3}{ab}\right)$ is equal to :
(a) 1 (b) log abc
(c) abc (d) none of these

36. $\frac{1}{(\log_a bc)+1} + \frac{1}{(\log_b ac)+1} + \frac{1}{(\log_c ab)+1}$ is equal to :
(a) 1 (b) 2
(c) 0 (d) abc

37. $\frac{1}{\log_{ab} abc} + \frac{1}{\log_{bc} abc} + \frac{1}{\log_{ca} abc}$ is equal to :
(a) 0 (b) 1
(c) 2 (d) 3

38. The value of $\left(\frac{1}{\log_5 210} + \frac{1}{\log_6 210} + \frac{1}{\log_7 210}\right)$ is :
(a) 0 (b) 1
(c) 18 (d) 21

39. The value of $\left[\frac{1}{\log_{a/b} x} + \frac{1}{\log_{b/c} x} + \frac{1}{\log_{c/a} x}\right]$ is :
(a) 0 (b) 1
(c) abc (d) x^3

40. If $\log_{10} 2 = 0.3010$, then $\log_2 10$ is :
(a) 3.010 (b) 1.5050
(c) 3.3222 (d) none of these

41. If $2^x \cdot 3^{2x} = 100$, then the value of x is (log 2 = 0.3010, log 3 = 0.4771)
(a) 2.3 (b) 1.59
(c) 1.8 (d) 1.41

42. If $\log_{10} 2 = 0.3010$ and $5^x = 400$, then the value of x is :
(a) 3.72 (b) 2.52
(c) 0 (d) none of these

43. If log 2 = 0.3010, the number of digits in 5^{20} is :
(a) 16 (b) 14
(c) 8 (d) none of these

44. If $\log(m+n) = \log m + \log n$, then :
(a) $mn = 1$ (b) $m = -n$
(c) $\frac{m}{(m-1)} = n$ (d) none of these

45. If $\log_{10} a + \log_{10} b = c$, then the value of a is :
(a) bc (b) $\frac{c}{b}$
(c) $\frac{(10)^c}{b}$ (d) $\frac{10b}{c}$

46. The mantissa of log 3274 is 0.5150. The value of log (0.3274) is :
(a) $\bar{1}.5150$ (b) 1.5150
(c) $\bar{2}.5150$ (d) none of these

47. If $\log_{10} x = 1.9675$, then the value of $\log_{10}(100x)$ is :
(a) 196.75 (b) 3.9675
(c) 2.9675 (d) none of these

48. If $5^x = (0.5)^y = 1000$, then the value of $\left(\frac{1}{x} - \frac{1}{y}\right)$ is :
(a) $\frac{1}{4}$ (b) $\frac{1}{3}$
(c) $\frac{1}{2}$ (d) 1

49. If $\frac{1}{2}\log x + \frac{1}{2}\log y + \log 2 = \log(x+y)$, then :
(a) $x + y = 0$ (b) $x = y$
(c) $x = 2, y = 0$ (d) $x = \log y$

50. If $p = \log_3 5$ and $q = \log_{17} 25$, which one of the following is correct ?
(a) $p < q$ (b) $p = q$
(c) $p > q$ (d) can't say

Scanned by CamScanner

yoursmahboob.wordpress.com

51. If $x^2 + 4y^2 = 12xy$, then $\log(x + 2y)$ is equal to :
(a) $\frac{1}{2}(\log x + \log y + 2\log 2)$
(b) $\frac{1}{2}(\log x + \log y + 4\log 2)$
(c) $\frac{1}{2}(\log x + \log y - \log 2)$
(d) none of the above

52. The value of $(2^{\log_3 7} - 7^{\log_3 2})$ is :
(a) 0 (b) 1
(c) $\log_7 5$ (d) $\log_7 6$

53. $\frac{1}{\log_2 a} + \frac{1}{\log_4 a} + \frac{1}{\log_8 a} + \ldots$ to n terms $= \frac{n(n+1)}{k}$, then k is equal to :
(a) $\log_2 a^2$ (b) $\log_2\left(\frac{a}{2}\right)$
(c) $\log_a 2$ (d) none of these

54. The value of $(\log \tan 1° + \log \tan 2° + \ldots + \log \tan 89°)$ is :
(a) -1 (b) 0
(c) $\frac{1}{\sqrt{2}}$ (d) 1

55. The value of x for which $\log_9 x - \log_9\left(\frac{x}{10} + \frac{1}{9}\right) = 1$ is :
(a) 2 (b) 4
(c) 9 (d) 10

56. If $(x^4 - 2x^2y^2 + y^4)^{a-1} = (x - y)^{2a}(x + y)^{-2}$, then the value of a is :
(a) $(x^2 - y^2)$ (b) $\frac{x - y}{x + y}$
(c) $\frac{\log(x + y)}{\log(x - y)}$ (d) $\frac{\log(x - y)}{\log(x + y)}$

57. $\log_2 7$ is :
(a) an integer
(b) a prime number
(c) a rational number
(d) an irrational number

58. $\log_y x = ?$
(a) $x \log_e y$ (b) $\frac{x}{\log_e y}$
(c) $\frac{\log_e x}{\log_e y}$ (d) $\frac{\log_e y}{\log_e x}$

59. The value of
$\log_{10} 2 + 16\log_{10}\left(\frac{16}{15}\right) + 12\log_{10}\left(\frac{25}{24}\right) + 7\log_{10}\left(\frac{81}{80}\right)$ is :
(a) 0 (b) 1
(c) 2 (d) 3

60. If $\log_{10} x = a$, $\log_{10} y = b$ and $\log_{10} z = c$, then antilog $(pa + qb - rc) = ?$
(a) $\frac{pxqy}{rz}$ (b) $px + qy - rz$
(c) $\frac{x^p y^q}{z^r}$ (d) $x^p y^q z^r$

61. $\log_{10} a^p \cdot b^q \cdot c^r = ?$
(a) $pqr(\log_{10} abc)$
(b) $p\log_{10} a + q\log_{10} b + r\log_{10} c$
(c) $pqr(\log_{10} a + \log_{10} b + \log_{10} c)$
(d) $(\log_{10} a)^p + (\log_{10} b)^q + (\log_{10} c)^r$

62. If a, b, c are in GP then $\log_{10} a, \log_{10} b, \log_{10} c$ are in :
(a) GP (b) HP
(c) AP (d) none of these

63. If $\log_{10} x, \log_{10} y, \log_{10} z$ are in AP then x, y, z are in :
(a) AP (b) GP
(c) HP (d) none of these

64. If a, b, c are in GP then $\frac{1}{\log_a x}, \frac{1}{\log_b x}, \frac{1}{\log_c x}$ are in :
(a) AP (b) GP
(c) HP (d) none of these

65. If $\log(x - 1) + \log(x + 1) = 3\log 2$, then x is equal to :
(a) ± 1 (b) 4
(c) ± 3 (d) none of these

66. If a, b, c are three consecutive integers, then $\log(ac + 1)$ has the value :
(a) $\log b$ (b) $(\log b)^2$
(c) $2\log b$ (d) $\log 2b$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. Find the value of $\log_{10} \sqrt[7]{13}$ if $\log_{10} 13 = 1.1139$:
(a) 0.15913 (b) 0.5119
(c) 1.15913 (d) none of these

2. Find the logarithm of 144 to the base $2\sqrt{3}$:
(a) 8 (b) 4
(c) $2\sqrt{3}$ (d) none of these

3. If $\log_a N = (\log_b N) \times P$, then find P in terms of a and b :
(a) b^a (b) a^b
(c) $\log_a b$ (d) none of these

4. The value of $\log (ab)^2 - \log (ac) + \log (bc^4) - 3 \log (bc)$ is :
(a) 0 (b) $\log b$
(c) $\log c$ (d) $\log a$

5. If $\log_2 x + \log_4 x + \log_{64} x = 5$, find x :
(a) 8 (b) 16
(c) 7 (d) 2

6. If $\log_q (xy) = 3$ and $\log_q (x^2 y^3) = 4$, find the value of $\log_q x$:
(a) 4 (b) 5
(c) 3 (d) 2

7. If $\frac{\log x}{l+m-2n} = \frac{\log y}{m+n-2l} = \frac{\log z}{n+l-2m}$, then xyz is equal to :
(a) 0 (b) 1
(c) lmn (d) 2

8. If a, b, c be the p^{th}, q^{th}, r^{th} terms of a GP then the value of $(q-r) \log a + (r-p) \log b + (p-q) \log c$ is :
(a) 0 (b) 1
(c) -1 (d) pqr

9. If $a^{3-x} b^{5x} = a^{x+5} b^{3x}$, then the value of $x \log \left(\frac{b}{a}\right)$ is :
(a) $\log a$ (b) $\log b$
(c) $\log x$ (d) 1

10. If $u = v^2 = w^3 = z^4$, then $\log_u (uvwz)$ is equal to :
(a) $1 + \frac{1}{2} - \frac{1}{3} - \frac{1}{4}$ (b) 24
(c) $1 + \frac{1}{2} + \frac{1}{3} + \frac{1}{4}$ (d) $\frac{1}{24}$

11. Find the value of $\frac{\log \sqrt{27} + \log \sqrt{8} - \log \sqrt{125}}{\log 6 - \log 5}$:
(a) $\frac{2}{3}$ (b) $\frac{1}{3}$
(c) $\frac{3}{2}$ (d) none of these

12. The first term and the last term of a GP are a and k respectively. If the number of terms be n, then n is equal to ($r \rightarrow$ common ratio) :
(a) $1 - \frac{\log k - \log a}{\log r}$ (b) $1 + \frac{\log a + \log k}{\log r}$
(c) $1 + \frac{\log k - \log a}{\log r}$ (d) $\log r = \log k - \log a$

13. If a, b, c are in GP, then $\log_a d$, $\log_b d$, $\log_c d$ are in :
(a) AP (b) HP
(c) GP (d) none of these

14. Find the value of x for $\log_x 2 \cdot \log_{x/16} 2 = \log_{x/64} 2$:
(a) 4 (b) 4, 16
(c) 4, 8 (d) 4, 8, 32

15. Find the value of x and y respectively for
$\log_{10} (x^2 y^3) = 7$ and $\log_{10} (x/y) = 1$:
(a) $x = 10, y = 100$ (b) $x = 100, y = 10$
(c) $x = 10, y = 20$ (d) none of these

16. If $y = a^{\left(\frac{1}{1-\log_a x}\right)}$ and $z = a^{\left(\frac{1}{1-\log_a y}\right)}$, then x is equal to :
(a) $1 + \log yz$ (b) $\frac{1}{1-\log_a z}$
(c) $a^{\left(\frac{1}{1-\log_a z}\right)}$ (d) $\frac{y}{z}$

17. If $x = \log_c b + \log_b c$, $y = \log_a c + \log_c a$ and $z = \log_b a + \log_a b$, then $x^2 + y^2 + z^2$ is equal to :
(a) 1 (b) 2
(c) xyz (d) $xyz + 4$

18. Find the value of $\frac{1}{\log_3 e} + \frac{1}{\log_3 e^2} + \frac{1}{\log_3 e^4} + \ldots$ is :
(a) $\log_e 9$ (b) 0
(c) 1 (d) $\log_e 270$

19. If $\log_{10} x^2 - \log_{10} \sqrt{y} = 1$, find the value of y, when $x = 2$
(a) 2/9 (b) 4/25
(c) 25/4 (d) 4/9

20. Find the value of $(b^2)^{5 \log_b x}$:
(a) 10^x (b) x^4
(c) $10x$ (d) x^{10}

21. Find the value of $(7^3)^{-2 \log_7 8}$:
(a) 8^{-7} (b) 6^{-8}
(c) 8^{-6} (d) none of these

22. log 12900 is equal to :
(a) 2 log 129 (b) log 129 + log 2
(c) 4 + log 1.29 (d) none of these

23. log 0.786 is equal to :
(a) log 786 – log 3 (b) log 78.6 – log 100
(c) log 786 – 3 (d) both (b) and (c)

Scanned by CamScanner

yoursmahboob.wordpress.com

24. If $\log_5 x = y$, then 5^{5y} is equal to :
(a) $\frac{x}{5}$ (b) $5x$
(c) $\log_x 5$ (d) x^5

25. If $A = \log_{13} 189$ and $B = \log_{23} 521$, then which one of the following is correct?
(a) $A < B$ (b) $A = B$
(c) $A > B$ (d) none of these

26. If $A = \frac{(\log_3 2187)}{5}$ and $B = \log_{243} 2187$, then which one of the following is correct?
(a) $A < B$ (b) $A = B$
(c) $A > B$ (d) can't be determined

27. If $(150)^x = 7$, then x is equal to :
(a) $\frac{\log 7}{(\log 3) + (\log 5) + 1}$ (b) $\frac{\log 7}{(\log 3) + (\log 6)}$
(c) $\frac{\log 7}{(\log 3) + (\log 5) + 10}$ (d) none of these

28. The value of x satisfying the following relation
$$\log_{1/2} x = \log_2 (3x - 2)$$
(a) $\frac{1}{3}$ (b) $-\frac{1}{3}$
(c) 3 (d) none of these

29. If $\log_2 (x + y) = 3$ and $\log_2 x + \log_2 y = 2 + \log_2 3$ then the values of x and y are
(a) $x = 1, y = 8$ (b) $x = 4, y = 4$
(c) $x = 4, y = 8$ (d) $x = 2, y = 6$

30. The set of all the solutions of the equation
$\log_5 x \log_6 x \log_7 x = \log_5 x \cdot \log_6 x + \log_6 x \cdot \log_7 x - \log_7 x \cdot \log_5 x$ is :
(a) $\{0, 1\}$ (b) $\{1, 210\}$
(c) $\{1, 5, 6, 7, 210\}$ (d) none of these

31. The value of $\frac{\log_3 54}{\log_{486} 3} - \frac{\log_3 1458}{\log_{18} 3}$ is :
(a) 0 (b) 1
(c) 2 (d) 3

32. The number of solutions of $\log_9 (2x - 5) = \log_3 (x - 4)$ is :
(a) 0 (b) 1
(c) 2 (d) 3

33. If $\log_3 2$, $\log_3 (2^x - 5)$ and $\log_3 (2^x - 7/2)$ are in AP then x is equal to :
(a) 2 (b) 3
(c) 4 (d) 5

34. If $1, \log_y x, \log_z y, -15 \log_x z$ are in AP, then
(a) $z^3 = x$ (b) $x = y^{-1}$
(c) $z^{-3} = y$ (d) $x = y^{-1} = z^3$

35. If $\log_x a$, $a^{x/2}$ and $\log_b x$ are in GP, then x is equal to :
(a) $\log_a (\log_b a)$ (b) $\log_a (\log_e a) - \log_a (\log_e b)$
(c) $-\log_a (\log_a b)$ (d) both (a) and (b)

36. If $1, \log_9 (3^{1-x} + 2)$ and $\log_3 (4 \cdot 3^x - 1)$ are in AP, then x is equal to :
(a) $\log_4 3$ (b) $\log_3 4$
(c) $1 + \log_3 4$ (d) $\log_3 (3/4)$

37. The value of $\frac{1}{\log_{100} n} + \frac{1}{\log_{99} n} + \frac{1}{\log_{98} n} + \ldots + \frac{1}{\log_2 n}$ is :
(a) 1 (b) $\frac{1}{\log_{100!} n}$
(c) $\frac{1}{\log_n 99!}$ (d) $\frac{1}{\log_n 100!}$

38. If $\log_2 (1 + 3^{x-1}) + 2 = \log_2 (3^{2x-2} + 7)$, then x is :
(a) 0 (b) 1
(c) 2 (d) both (b) and (c)

39. $x^{\log_5 x} > 5$ implies :
(a) $x \in (0, \infty)$ (b) $x \in (1, \infty)$
(c) $x \in (1, 2)$ (d) $x \in (0, 1/5) \cup (5, \infty)$

40. Find x, if $\log x^3 - \log 3x = 2 \log 2 + \log 3$:
(a) 3 (b) 6
(c) 9 (d) none of these

41. If x satisfies $\log_5 (2x + 3) < \log_5 7$, then x lies in :
(a) $\left(-\frac{3}{2}, 2\right)$ (b) $\left(\frac{3}{2}, 2\right)$
(c) $(0, \infty)$ (d) $(0, 2)$

42. Find x, if $\log_{2x} \sqrt{x} + \log_{2\sqrt{x}} x = 0$:
(a) $1, 2^{-5/6}$ (b) $1, 2^{-6/5}$
(c) $4, -2$ (d) none of these

43. For a positive real x $(x > 1)$, which one of the following is correct ?
(a) $\frac{x}{1+x} < x < \log (x + 1)$ (b) $x < \frac{x}{1+x} < \log (x + 1)$
(c) $\log (x + 1) < \frac{x}{1+x} < x$ (d) $\frac{x}{1+x} < \log (x + 1) < x$

44. For $x \in N$, $x > 1$, if $P = \log_x (x + 1)$ and $Q = \log_{(x+1)} (x + 2)$, then which one of the following is correct ?
(a) $P < Q$ (b) $P = Q$
(c) $P > Q$ (d) can't be determined

45. If $a = 1 + \log_x yz$, $b = 1 + \log_y zx$ and $c = 1 + \log_z xy$, then $ab + bc + ca$ is :
(a) 1 (b) 0
(c) abc (d) none of these

46. Find the values of x and y for the given equation
$xy^2 = 4$ and $\log_3 (\log_2 x) + \log_{1/3} (\log_{1/2} y) = 1$:
(a) $x = \frac{1}{8}, y = 64$ (b) $x = \frac{1}{4}, y = 48$
(c) $x = 64, y = \frac{1}{4}$ (d) none of these

47. Find x if $\log_{1/\sqrt{2}} (1/\sqrt{8}) = \log_2 (4^x + 1) \cdot \log_2 (4^{x+1} + 4)$:
(a) 0 (b) 1
(c) 2 (d) none of these

48. The value of x satisfying
$$\log_3 4 - 2 \log_3 \sqrt{3x + 1} = 1 - \log_3 (5x - 2)$$
(a) 1 (b) 2
(c) 3 (d) none of these

49. The solution set of $|3 - 4x| > 2$ is :
(a) $\left(\frac{7}{4}, \infty\right)$ (b) $\left(-\frac{1}{4}, \frac{7}{4}\right)$
(c) $\left(-\infty, -\frac{1}{4}\right) \cup \left(\frac{7}{4}, \infty\right)$ (d) $\left(-\infty, \frac{1}{4}\right) \cup \left(\frac{5}{4}, \infty\right)$

50. Solve the following equations for x and y
$$\log_{100} |x + y| = \frac{1}{2}, \log_{10} y - \log_{10} |x| = \log_{100} 4 :$$
(a) $\left(\frac{8}{3}, \frac{16}{3}\right), (-8, -16)$ (b) $\left(\frac{10}{3}, \frac{20}{3}\right), (-10, 20)$
(c) $\left(-\frac{10}{3}, -\frac{20}{3}\right), (70, 20)$ (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

1. In the adjoining diagram there are two curvature graphs of $\log_a x$ and $\log_b x$ shown for $x > 0$. If $(a, b) > 0$ and $a \neq b \neq 1$, then :



(a) $a < b$
(b) $a > b$
(c) can't be determined
(d) none of the above

2. In the adjoining diagram graphs of $\log_a x$ and $\log_b x$ are shown for $x > 0$ and $0 < a < 1$, then :



(a) $a < b$
(b) $a > b$
(c) can't be determined
(d) none of these

3. Find the sum of 'n' terms of the series.

$$\log_2\left(\frac{x}{y}\right) + \log_4\left(\frac{x}{y}\right)^2 + \log_8\left(\frac{x}{y}\right)^3 + \log_{16}\left(\frac{x}{y}\right)^4 + \ldots :$$

(a) $\log_2\left(\frac{x}{y}\right)^{4n}$
(b) $n\left(\log_2 \frac{x}{y}\right)$
(c) $\log_2\left(\frac{x^{n-1}}{y^{n-1}}\right)$
(d) $\frac{1}{2}\log_2\left(\frac{x}{y}\right)^{n(n+1)}$

4. Find the value of $\log m + \log m^2 + \log m^3 + \ldots + \log m^n$:

(a) $\frac{n(n+1)}{2}$
(b) $\frac{mn}{2}$
(c) $\frac{n(n+1)}{2}\log m$
(d) $n(n+1)\log m^2$

5. The greatest possible value of n could be if $9^n < 10^6$, given that $\log 3 = 0.4771$ and $n \in N$:

(a) 7 (b) 8 (c) 9 (d) 10

6. The set of solutions for all x satisfying the equation

$$x^{\log_3 x^2 + (\log_3 x)^2 - 10} = \frac{1}{x^2} \text{ is :}$$

(a) $\{1, 9\}$
(b) $\{1, 4, 16\}$
(c) $\{1, 9, 81\}$
(d) $\left\{9, \frac{1}{81}, 1\right\}$

7. The set of all the solutions of the inequality $\log_{(2-x)}(x-3) \geq 1$ is :

(a) $x < 2$
(b) $x > 3$
(c) $(x < 2) \cup (x > 3)$
(d) none of these

8. If $\log_3 30 = \frac{1}{a}$ and $\log_5 30 = \frac{1}{b}$ then the value of $3\log_{30} 2$ is :

(a) $3(1 + a + b)$
(b) $2(1 - a - b)$
(c) $3(1 - a - b)$
(d) $3(1 + a - b)$

9. The set of all values of x satisfying $x^{\log_x |3-x|^2} = 4$:

(a) $(\sqrt{3}, 2)$ (b) $(1, 5)$ (c) $[1, \infty)$ (d) $\{1, 5\}$

10. The number of solutions of the expression satisfying $4^{x^2+2} - 9 \cdot 2^{x^2+2} + 8 = 0$ is :

(a) 0
(b) 1
(c) 2
(d) none of these

11. The number of solutions satisfying, for $x \in R$

$$x^{\left[(\log_3 x)^2 - \frac{9}{2}\log_3 x + 5\right]} = 3\sqrt{3}$$

(a) 0 (b) 1 (c) 2 (d) 3

12. Find the values of x satisfying

$$\log_{x^2+6x+8} \log_{2x^2-2x+3} (x^2 - 2x) = 0 \text{ is :}$$

(a) 0 (b) -1 (c) 2 (d) -3

13. For every p being real number the solution set of the inequality

$$\log_{10} p + (\log_{10} 10p)^2 + (\log_{10^{100p}})^2 \leq \log_{10}(10)^9$$

(a) $p \geq 10^{-4}$
(b) $p > 10^{1/2}$
(c) $10^{-4} \leq p \leq 10^{1/2}$
(d) none of these

14. The number of real solutions of the equation

$$2\log_2 \log_2 x + \log_{1/2} \log_2(2\sqrt{2}x) = 1 \text{ is :}$$

(a) 1
(b) 2
(c) 3
(d) more than 3

15. The number of solutions of the equation $\log_{x/2} x^2 + 40 \log_{4x} \sqrt{x} - 14 \log_{16x} x^3 = 0$ is :

(a) 0 (b) 1 (c) 2 (d) 3

16. Find the solution set of x, for the given inequality $\log_m n > 1$, where $m = \frac{(5)^2 - (x)^2}{(4)^2}$ and $n = \frac{2(12-x) - x^2}{14}$:

(a) $(-5, 4)$
(b) $\{-3, 3\}$
(c) $(-3, 1) \cup (3, 4)$
(d) none of these

17. Find the values of x satisfying the following system of inequalities

$$\frac{\sqrt{(2-x)(x-8)}}{\log_{3/10}\frac{10}{7}\left[\log_2\left(\frac{5}{2}\right)\right]} \geq 0 \quad \text{and} \quad \frac{2^x}{8} - (2^5 - 1) > 0$$

(a) 6 (b) 8 (c) 4 (d) (2, 8)

18. The least value of expression $2\log_{10} x - \log_x(1/100)$ for $x > 1$ is :

(a) 2 (b) 3 (c) 4 (d) 5

19. The equation $x^{[(3/4)(\log_2 x)^2 + \log_2 x - (5/4)]} = \sqrt{2}$ has :

(a) at least one real solution
(b) exactly three real solutions
(c) exactly one irrational solution
(d) all of these

20. The values of x for which the given equation satisfy $\log_{(2x+3)}(6x^2 + 23x + 21) = 4 - \log_{(3x+7)}(4x^2 + 12x + 9)$ are :

(a) $(-8, 5)$ (b) $-\frac{1}{4}$ only (c) $-4, -\frac{1}{4}$ (d) $-\frac{1}{4}, -2$

21. Find all real values of x satisfying equation

$$|x-1|^{\log x^2 - 2\log_x 9} = (x-1)^7$$

(a) (2, 9)
(b) (9, 81)
(c) (2, 81)
(d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-16.1

1. (d)	2. (c)	3. (c)	4. (b)	5. (c)	6. (b)	7. (d)	8. (c)	9. (c)	10. (c)
11. (b)	12. (a)	13. (c)	14. (c)	15. (a)	16. (c)	17. (d)	18. (c)	19. (b)	20. (b)
21. (a)	22. (a)	23. (c)	24. (b)	25. (c)	26. (c)	27. (c)	28. (b)	29. (c)	30. (a)
31. (b)	32. (b)	33. (c)	34. (d)	35. (b)	36. (a)	37. (c)	38. (b)	39. (a)	40. (c)
41. (b)	42. (a)	43. (b)	44. (c)	45. (c)	46. (a)	47. (b)	48. (b)	49. (b)	50. (c)
51. (b)	52. (a)	53. (a)	54. (b)	55. (d)	56. (d)	57. (d)	58. (c)	59. (b)	60. (c)
61. (b)	62. (c)	63. (b)	64. (a)	65. (d)	66. (c)				

LEVEL-1

1. (a)	2. (b)	3. (c)	4. (d)	5. (a)	6. (b)	7. (c)	8. (a)	9. (a)	10. (c)
11. (c)	12. (c)	13. (b)	14. (c)	15. (b)	16. (c)	17. (d)	18. (a)	19. (b)	20. (d)
21. (c)	22. (c)	23. (d)	24. (d)	25. (c)	26. (b)	27. (a)	28. (d)	29. (d)	30. (b)
31. (d)	32. (b)	33. (b)	34. (d)	35. (d)	36. (d)	37. (b)	38. (d)	39. (d)	40. (b)
41. (a)	42. (b)	43. (d)	44. (c)	45. (c)	46. (c)	47. (a)	48. (a)	49. (d)	50. (b)

LEVEL-2

1. (a)	2. (a)	3. (b)	4. (c)	5. (b)	6. (d)	7. (d)	8. (c)	9. (d)	10. (c)
11. (d)	12. (b)	13. (c)	14. (a)	15. (d)	16. (b)	17. (c)	18. (c)	19. (d)	20. (b)
21. (c)									

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 16.1

1. $x^y = k \Rightarrow \log_x k = y$
2. $\log_m n = p \Rightarrow m^p = n$
3. $\log_a(mn) = \log_a m + \log_a n$
4. $\log_a\left(\frac{m}{n}\right) = \log_a m - \log_a n$
5. $\log_{27} 27 = \frac{\log_3 27}{\log_3 81} = \frac{\log_3 3^3}{\log_3 3^4} = \frac{3\log_3 3}{4\log_3 3} = \frac{3}{4}$
6. $\log_{36}\left(\frac{1}{216}\right) = \log_{36} 6^{-3} = \frac{\log 6^{-3}}{\log 36}$
$= \frac{-3\log 6}{2\log 6} = -\frac{3}{2}$
7. $\log_{\sqrt{6}} 216 = \frac{\log 216}{\log \sqrt{6}} = \frac{\log(\sqrt{6})^6}{\log \sqrt{6}} = \frac{6\log\sqrt{6}}{\log\sqrt{6}} = 6$
8. $\log_{2\sqrt{2}} 5832 = \log_{2\sqrt{2}}(18)^3 = \log_{2\sqrt{2}}[(3\sqrt{2})^2]^3$
$= \log_{2\sqrt{2}}(3\sqrt{2})^6 = 6 \qquad (\because \log_a a^m = m)$
9. Let $\log_{(-1/5)} 625 = x$
$\therefore \left(-\frac{1}{5}\right)^x = 625$
$\Rightarrow \left(-\frac{1}{5}\right)^x = (5)^6$
$\Rightarrow (-5)^{-x} = (5)^6 = (-5)^6$
$\Rightarrow x = -4$
10. Let $\log_{10}(0.0001) = x$
$\therefore 10^x = 0.0001 = 10^{-4}$
$\Rightarrow x = -4$
11. Let $\log_{0.01}(10000) = x$
$\therefore (0.01)^x = 10000$
$\Rightarrow (10^{-2})^x = 10000$
$\Rightarrow 10^{-2x} = 10^4$
$\Rightarrow x = -2$
12. $\log_4 32 + \log_9 243 = \frac{\log 32}{\log 4} + \frac{\log 243}{\log 9}$
$= \frac{5\log_2 2}{2\log_2 2} + \frac{5\log_3 3}{2\log_3 3}$
$= \frac{5}{2} + \frac{5}{2} = 5$
13. $\log_2 2^3 + \log_3 3^2 + \log_5 5^2 = 3 + 2 + 2 = 7$
14. $\log_2(\log_3 81) = \log_2(\log_3 3^4) = \log_2(4\log_3 3)$
$= \log_2 4 = \log_2 2^2 = 2$
15. $\log_2 \log_2 \log_3 \log_5(125)^3 = \log_2 \log_2 \log_3 \log_5 5^9$
$= \log_2 \log_2 \log_3 9$
$= \log_2 \log_2(2) = \log_2 1 = 0$
16. $\log_2 \log_2 \log_2 \log_2(65536) = \log_2 \log_2 \log_2 \log_2(2^{16})$
$= \log_2 \log_2 \log_2 16 = \log_2 \log_2 4$
$= \log_2 2 = 1$
17. $\log_{10} 1 + \log_{10} 10 + \log_{10} 100 + \ldots + \log_{10} 10000000000$
$= \log_{10}(1 \times 10 \times 100 \times \ldots \times 10000000000)$
$= \log_{10} 10^{(0+1+2+3+\ldots+10)}$
$= \log_{10} 10^{55} = 55$

Alternatively :

$\log_{10} 1 + \log_{10} 10 + \log_{10} 10^2 + \ldots + \log_{10} 10^{10}$
$= 0 + 1 + 2 + 3 + 4 + \ldots + 10 = 55$

18. $\log_5 5 + \log_5 5^2 + \log_5 5^3 + \ldots + \log_5 5^n = 1 + 2 + 3 + \ldots + n$
$= \frac{n(n+1)}{2}$
19. $27^{\log_3 81} = 3^{3\log_3 81}$
$= 3^{\log_3(81)^3} = (81)^3 = 531441 \qquad (\because a^{\log_a m} = m)$
20. $216^{\log_6 49} = 6^{3\log_6 49}$
$= 6^{\log_6(49)^3} = (49)^3 = 117649$
21. $25^{[(-1/4)\log_5 25]} = 5^{[2(-1/4)\log_5 25]}$
$= 5^{(-1/2)\log_5 25} = 5^{\log_5(25)^{-1/2}}$
$= 25^{-1/2} = \frac{1}{5}$
22. $\log_{10} 500000 - \log_{10} 5 = \log_{10}\left(\frac{500000}{5}\right) = \log_{10} 100000$
$= \log_{10} 10^5 = 5$
23. $\log_5[\log_3(\log_2 x)] = 1 = \log_5 5$
$\Rightarrow \log_3(\log_2 x) = 5 = \log_3 3^5$
$\Rightarrow \log_2 x = 3^5 = 243$
$\Rightarrow 2^{243} = x$
24. $\log_2 \log_{10} 4x = 1 = \log_2 2$
$\Rightarrow \log_{10} 4x = 2 = \log_{10} 10^2 = \log_{10} 100$
$\Rightarrow 4x = 100 \Rightarrow x = 25$
25. If $\log_{27} x = \frac{4}{3}$
$\Rightarrow (27)^{4/3} = x$
$\Rightarrow (3^3)^{4/3} = x$
$\Rightarrow 3^4 = x$
$\Rightarrow x = 81$
26. $\log_x\left(\frac{4}{9}\right) = -\frac{1}{2}$
$\Rightarrow x^{-1/2} = \frac{4}{9}$
$\Rightarrow \frac{1}{x^{1/2}} = \frac{4}{9}$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow \left(\frac{1}{x}\right)^{1/2} = \frac{4}{9}$

$\Rightarrow \frac{1}{x} = \left(\frac{4}{9}\right)^2 \Rightarrow x = \frac{81}{16}$

27. $\log_{100} x = -4$

$\Rightarrow (100)^{-4} = x$

$\Rightarrow x = (10^2)^{-4} = 10^{-8}$

$\Rightarrow x = \frac{1}{10^8}$

28. $\log_{100} x = -\frac{1}{2} \Rightarrow (100)^{-1/2} = x$

$\Rightarrow (10^2)^{-1/2} = x$

$\Rightarrow 10^{-1} = x$

$\Rightarrow x = \frac{1}{10}$

29. $\log_x 0.2 = -\frac{1}{4}$

$\Rightarrow x^{-1/4} = 0.2 = \frac{2}{10}$

$\Rightarrow x^{-1} = \left(\frac{2}{10}\right)^4$

$\Rightarrow x = \left(\frac{10}{2}\right)^4 \Rightarrow x = 5^4$

30. $\log_{243} x = 0.8$

$\Rightarrow 243^{0.8} = x$

$\Rightarrow (3^5)^{4/5} = x$

$\Rightarrow 3^4 = x \Rightarrow x = 81$

31. $\log_e(x-1) + \log_e x + \log_e(x+1) = 0$

$\Rightarrow \log_e(x-1) \times x \times (x+1) = \log_e 1$

$\Rightarrow \log_e(x^2-1)x = \log_e 1$

$\Rightarrow (x^2-1)x = 1$

$\Rightarrow x^3 - x - 1 = 0$

32. $\log_3 5 \times \log_{25} 9 = \frac{\log 5}{\log 3} \times \frac{\log 3^2}{\log 5^2}$

$= \frac{\log 5}{\log 3} \times \frac{2\log 3}{2\log 5} = 1$

33. $\log \frac{14}{3} + \log \frac{11}{5} - \log \frac{22}{15}$

$= \log\left(\frac{14}{3} \times \frac{11}{5} \times \frac{15}{22}\right) = \log 7$

34. $3\log \frac{81}{80} + 5\log \frac{25}{24} + 7\log \frac{16}{15}$

$= \log\left[\left(\frac{81}{80}\right)^3 \times \left(\frac{25}{24}\right)^5 \times \left(\frac{16}{15}\right)^7\right]$

$= \log\left(\frac{3^{12} \times 5^{10} \times 2^{28}}{2^{12} \times 5^3 \times 2^{15} \times 3^5 \times 3^7 \times 5^7}\right)$

$= \log 2$

35. $\log \frac{a^3}{bc} + \log \frac{b^3}{ac} + \log \frac{c^3}{ab} = \log\left(\frac{a^3b^3c^3}{ab \cdot bc \cdot ac}\right)$

$= \log abc$

36. $\frac{1}{(\log_a bc)+1} + \frac{1}{(\log_b ac)+1} + \frac{1}{(\log_c ab)+1}$

$= \frac{1}{\log_a bc + \log_a a} + \frac{1}{\log_b ac + \log_b b} + \frac{1}{\log_c ab + \log_c c}$

$= \frac{1}{\log_a abc} + \frac{1}{\log_b abc} + \frac{1}{\log_c abc}$

$= \log_{abc} a + \log_{abc} b + \log_{abc} c$

$= \log_{abc} abc = 1$

37. $\frac{1}{\log_{ab} abc} + \frac{1}{\log_{bc} abc} + \frac{1}{\log_{ca} abc}$

$= \log_{abc}(ab) + \log_{abc}(bc) + \log_{abc}(ca)$

$= \log_{abc}(abc)^2 = 2$

38. $\frac{1}{\log_5 210} + \frac{1}{\log_6 210} + \frac{1}{\log_7 210}$

$= \log_{210} 5 + \log_{210} 6 + \log_{210} 7$

$= \log_{210}(5 \times 6 \times 7) = \log_{210} 210 = 1$

39. $\frac{1}{\log_{a/b} x} + \frac{1}{\log_{b/c} x} + \frac{1}{\log_{c/a} x}$

$= \log_x \frac{a}{b} + \log_x \frac{b}{c} + \log_x \frac{c}{a}$

$= \log_x\left(\frac{a}{b} \times \frac{b}{c} \times \frac{c}{a}\right) = \log_x 1 = 0$

40. $\log_2 10 = \frac{1}{\log_{10} 2} = \frac{1}{0.3010} = 3.3222$

41. $2^x \cdot 3^{2x} = 100$

$\Rightarrow x\log 2 + 2x\log 3 = \log 100$

$\Rightarrow x(0.3010 + 2 \times 0.4771) = 2$

$\Rightarrow x = \frac{1}{1.2552} = 1.59$

42. $\log_{10} 2 = 0.3010$ and $5^x = 400$

$\therefore 5^x = 400$

$\Rightarrow x\log 5 = \log 4 + \log 100$

$\Rightarrow x(\log 10 - \log 2) = 2\log 2 + 2$

$\Rightarrow x(1 - 0.3010) = 2(0.3010 + 1)$

$\Rightarrow x = 3.72$

43. $5^{20} = 20\log 5$

$= 20\log\left(\frac{10}{2}\right) = 20(\log 10 - \log 2)$

$= 20 \times [1 - 0.3010]$

$= 20 \times 0.6990 = 13.98$

Characteristic = 13

$\therefore$ Number of digits = $(13+1) = 14$

44. $\log(m+n) = \log m + \log n$

$\Rightarrow \log(m+n) = \log(mn)$

$\Rightarrow m + n = mn$

$m = n(m-1)$

$\Rightarrow n = \frac{m}{(m-1)}$

45. $\log_{10} a + \log_{10} b = c$

$\Rightarrow \log_{10}(ab) = c$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$10^c = ab$$

$$\Rightarrow \quad a = \frac{(10)^c}{b}$$

46. Since 0.3274 gives characteristic $\bar{1}$. Therefore value of $\log(0.3274) = \bar{1}.5150$

47. $\log_{10}(100x) = \log_{10} 100 + \log_{10} x$

$= 2 + 1.9675 = 3.9675$

48. $(5)^x = 1000$

$$\Rightarrow \quad 5 = 10^{3/x} \qquad \ldots(1)$$

And $(0.5)^y = 1000$

$$\Rightarrow \quad \left(\frac{5}{10}\right)^y = 10^3$$

$$\Rightarrow \quad 5^y = 10^3 \times 10^y$$

$$\Rightarrow \quad 5 = 10^{\frac{(3+y)}{y}} \qquad \ldots(2)$$

From eq. (1) and (2)

$$5 = 10^{3/x} = 10^{\frac{(3+y)}{y}}$$

$$\Rightarrow \quad \frac{3}{x} = \frac{3+y}{y}$$

$$\Rightarrow \quad \frac{1}{x} - \frac{1}{y} = \frac{1}{3}$$

49. $\frac{1}{2}\log x + \frac{1}{2}\log y + \log 2 = \log(x+y)$

$$\Rightarrow \quad \log(x^{1/2} y^{1/2} \times 2) = \log(x+y)$$

$$\Rightarrow \quad 2\sqrt{xy} = (x+y)$$

$$\Rightarrow \quad 4xy = (x+y)^2$$

$$\Rightarrow \quad (x+y)^2 - 4xy = 0$$

$$\Rightarrow \quad (x-y)^2 = 0$$

$$\Rightarrow \quad x - y = 0 \quad \Rightarrow \quad x = y$$

50. $q = \log_{17}(5)^2 = 2\log_{17} 5$

$$\Rightarrow \quad \frac{1}{q} = \frac{1}{2}\log_5 17$$

And $\frac{1}{p} = \log_5 3 = \frac{1}{2} \times (2\log_5 3)$

$$= \frac{1}{2}(\log_5 9)$$

$$\therefore \quad \frac{1}{p} < \frac{1}{q} \quad \Rightarrow \quad p > q$$

51. $x^2 + 4y^2 = 12xy$

$$\Rightarrow \quad x^2 + (2y)^2 + 4xy = 12xy + 4xy$$

$$\Rightarrow \quad (x+2y)^2 = 16xy$$

$$\Rightarrow \quad (x+2y)^2 = (2^4)\,xy$$

$$\Rightarrow \quad 2\log(x+2y) = 4\log 2 + \log x + \log y$$

$$\Rightarrow \quad \log(x+2y) = \frac{1}{2}(\log x + \log y + 4\log 2)$$

52. $\log_3 7 = \frac{\log_2 7}{\log_2 3} = (\log_2 7)(\log_3 2)$

$\log_3 7 = (\log_3 2)(\log_2 7) = \log_2 7^{\log_3 2}$

$$\therefore \quad 2^{\log_3 7} = 2^{\log_2 7 \log_3 2}$$

$$\Rightarrow \quad 2^{\log_3 7} = 7^{\log_3 2}$$

$$\Rightarrow \quad 2^{\log_3 7} - 7^{\log_3 2} = 0$$

53. $\frac{1}{\log_2 a} + \frac{1}{\log_4 a} + \frac{1}{\log_8 a} + \ldots + \frac{1}{\log_{2^n} a} = \frac{n(n+1)}{k}$

$= \log_a 2 + \log_a 2^2 + \log_a 2^3 + \ldots + \log_a 2^n = \frac{n(n+1)}{k}$

$$\Rightarrow \quad (\log_a 2)(1 + 2 + 3 + \ldots + n) = \frac{n(n+1)}{k}$$

$$\Rightarrow \quad (\log_a 2)\left[\frac{n(n+1)}{2}\right] = \frac{n(n+1)}{k}$$

$$\Rightarrow \quad \frac{1}{2}\log_a 2 = \frac{1}{k}$$

$$\Rightarrow \quad \log_a 2 = \frac{2}{k}$$

$$\Rightarrow \quad \log_2 a = \frac{k}{2}$$

$$\Rightarrow \quad 2\log_2 a = k$$

$$\Rightarrow \quad \log_2 a^2 = k$$

54. $\log\tan 1° + \log\tan 2° + \ldots + \log\tan 89°$

$= (\log\tan 1° + \log\tan 89°) + (\log\tan 2° + \log\tan 88°) + \ldots + \log\tan 45°$

$= \log(\tan 1° \cdot \tan 89°) + \log(\tan 2° \cdot \tan 88°) + \ldots \log 1$

$= \log(\tan 1° \cdot \cot 1°) + \log(\tan 2° \cdot \cot 2°) + \ldots \log 1$

$= \log 1 + \log 1 + \ldots + \log 1$

$(\because \tan(90 - \theta) = \cot\theta$ and $\tan 45° = 1)$

$= 0$

55. $\log_9 x - \log_9\left(\frac{x}{10} + \frac{1}{9}\right) = 1 = \log_9 9$

$$\Rightarrow \quad \log_9 \frac{x}{\left(\frac{x}{10} + \frac{1}{9}\right)} = \log_9 9$$

$$\Rightarrow \quad \frac{x}{\left(\frac{x}{10} + \frac{1}{9}\right)} = 9$$

$$\Rightarrow \quad \frac{x \times 90}{9x + 10} = 9$$

$$\Rightarrow \quad 10x = 9x + 10$$

$$\Rightarrow \quad x = 10$$

Alternatively : Go through options.

56. $[(x^2 - y^2)^2]^{a-1} = (x-y)^{2a}(x+y)^{-2}$

$$\Rightarrow \quad (x^2 - y^2)^{2(a-1)} = (x-y)^{2a}(x+y)^{-2}$$

$$\Rightarrow (x-y)^{2(a-1)}(x+y)^{2(a-1)} = (x-y)^{2a}(x+y)^{-2}$$

$$\Rightarrow \quad \frac{(x-y)^{2a-2}}{(x-y)^{2a}} \frac{(x+y)^{2a-2}}{(x+y)^{-2}} = 1$$

$$\Rightarrow \quad (x-y)^{-2}(x+y)^{2a} = 1$$

$$\Rightarrow \quad -2\log(x-y) + 2a\log(x+y) = \log 1$$

$$\Rightarrow \quad 2a\log(x+y) = 2\log(x-y)$$

$$a = \frac{\log(x-y)}{\log(x+y)}$$

Scanned by CamScanner

yourshabbooh.wordpress.com

57. Let $\log_2 7$ be a rational

$$\log_2 7 = \left(\frac{p}{q}\right) \qquad q \neq 0$$

$\Rightarrow \quad 2^{(p/q)} = 7 \quad \Rightarrow \quad 2^p = 7^q$

Here p and q being the integers cannot satisfy the above relation.

Hence $\log_2 7$ is an irrational number.

(Clearly (a) and (b) are wrong)

58. $\log \dfrac{x}{y} = \dfrac{\log_e x}{\log_e y}$ (see the theory)

59. $\log_{10} 2 + \log_{10}\left(\dfrac{16}{15}\right)^{16} + \log_{10}\left(\dfrac{25}{24}\right)^{12} + \log_{10}\left(\dfrac{81}{80}\right)^{7}$

$= \log_{10} 2 + \log_{10}\left(\dfrac{2^{64}}{3^{16} \times 5^{16}}\right) + \log\left(\dfrac{5^{24}}{2^{36} \times 3^{12}}\right)$

$+ \log\left(\dfrac{3^{28}}{2^{28} \times 5^{7}}\right)$

$= \log_{10} \dfrac{2^{65} \times 3^{28} \times 5^{24}}{2^{64} \times 3^{28} \times 5^{23}}$

$= \log_{10}(2 \times 5) = \log_{10} 10 = 1$

60. $(pa + qb - rc) = p \log_{10} x + q \log_{10} y - r \log_{10} z$

$= \log_{10}(x^p) + \log_{10}(y^q) - \log_{10}(z^r)$

$= \log_{10}\left(\dfrac{x^p y^q}{z^r}\right)$

$\Rightarrow$ antilog $(pa + qb - rc) = \dfrac{x^p y^q}{z^r}$.

61. $\log_{10} a^p . b^q . c^r = \log_{10} a^p + \log_{10} b^q + \log_{10} c^r$

$= p \log_{10} a + q \log_{10} b + r \log_{10} c$

62. $\because$ a, b, c are in GP

$\Rightarrow \quad b^2 = ac$

$\Rightarrow \quad 2 \log b = \log a + \log c$

$\Rightarrow$ $\log_x a, \log_x b, \log_x c$ are in AP

$\Rightarrow$ $\log_{10} a, \log_{10} b, \log_{10} c$ are in AP

63. $\log_{10} x, \log_{10} y, \log_{10} z$ are in AP

$\therefore \quad 2 \log_{10} y = \log_{10} x + \log_{10} z$

$\Rightarrow \quad \log_{10} y^2 = \log_{10}(xz)$

$\Rightarrow \quad y^2 = xz$

$\Rightarrow$

$\Rightarrow$ x, y, z are in GP

64. $\because$ a, b, c, are in GP

$\therefore$ $\log_x a, \log_x b, \log_x c$ are in AP

$\Rightarrow \dfrac{1}{\log_a x}, \dfrac{1}{\log_b x}, \dfrac{1}{\log_c x}$ are in AP

65. $\log(x-1) + \log(x+1) = 3 \log 2 = \log 2^3$

$\Rightarrow \quad \log[(x-1)(x+1)] = \log 8$

$\Rightarrow \quad \log(x^2 - 1) = \log 8$

$\Rightarrow \quad x^2 - 1 = 8 \quad \Rightarrow \quad x^2 = 9 \quad \Rightarrow \quad x = \pm 3$

But at $x = -3$ logarithm equation is not defined.

Hence $x = 3$

66. a, b, c are consecutive integers

$\therefore \quad b = a + 1$ and $c = a + 2$

$\therefore \log(ac + 1) = \log[a(a+2) + 1]$

$= \log[(b-1)(b-1+2) + 1]$ $(\because a = b-1)$

$= \log b^2 = 2 \log b$

LEVEL 1

1. $\log_{10} \sqrt[7]{13} \quad \Rightarrow \quad \log_{10}(13)^{1/7}$

$\Rightarrow \quad \dfrac{1}{7} \log_{10} 13 = \dfrac{1}{7} \times 1.1139 = 0.15913$

2. $\log_{2\sqrt{3}} 144 = \log_{2\sqrt{3}} (2\sqrt{3})^4 = 4$

3. $\log_a N = \log_b N \times P$

$\Rightarrow \quad \dfrac{\log_a N}{\log_b N} = P$

$\Rightarrow \quad \dfrac{\frac{1}{\log_N a}}{\frac{1}{\log_N b}} = P$

$\Rightarrow \quad \dfrac{\log_N b}{\log_N a} = P \quad \Rightarrow \quad \log_a b = P$

4. $\log(ab)^2 - \log(ac) + \log(bc^4) - 3\log(bc)$

$= \log \dfrac{(ab)^2}{ac} + \log \dfrac{(bc^4)}{(bc)^3}$

$= \log\left[\dfrac{(ab)^2}{ac} \times \dfrac{(bc^4)}{(bc)^3}\right] = \log a$

5. $\log_2 x + \log_4 x + \log_{64} x = 5$

$\Rightarrow \quad \dfrac{1}{\log_x(2)} + \dfrac{1}{2\log_x(2)} + \dfrac{1}{6\log_x(2)} = 5$

$\Rightarrow \quad \dfrac{10}{6\log_x(2)} = 5$

$\Rightarrow \quad \log_x(2) = \dfrac{1}{3}$

$\Rightarrow \quad \log_2 x = 3$

$\Rightarrow \quad 2^3 = x \quad \therefore \quad x = 8$

Alternatively: Go through options.

6. $\log_q(xy) = 3$ and $\log_q(x^2y^3) = 4$

$\therefore \quad \log_q(x^2y^3) = 4 \quad \Rightarrow \quad \log_q[(xy)^2 \cdot y]$

$\Rightarrow \quad \log_q(xy)^2 + \log_q y = 4$

$\Rightarrow \quad 2\log_q(xy) + \log_q y = 4$

$\Rightarrow \quad 2 \times 3 + \log_q y = 4$

$\Rightarrow \quad \log_q y = -2$

Again $\log_q(xy) = \log_q x + \log_q y = 3$

$\Rightarrow \quad \log_q x + (-2) = 3$

$\Rightarrow \quad \log_q x = 5$

7. $\dfrac{\log x}{l + m - 2n} = \dfrac{\log y}{m + n - 2l} = \dfrac{\log z}{n + l - 2m} = k$ (say)

$\Rightarrow \quad \log x = k(l + m - 2n) \quad ...(1)$

$\log y = k(m + n - 2l) \quad ...(2)$

$\log z = k(n + l - 2m) \quad ...(3)$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore \log x + \log y + \log z$
$= k(l + m - 2n) + k(m + n - 2l) + k(n + l - 2m)$
$\log(xyz) = 0$
$\log xyz = \log 1$
$\Rightarrow \quad xyz = 1$
$\Rightarrow$

8. Let m be the first term and k be the common ratio of GP, then
$a = mk^{p-1}$
$b = mk^{q-1}$
$c = mk^{r-1}$

$\therefore (q-r)\log a + (r-p)\log b + (p-q)\log c$
$= \log[mk^{(p-1)}]^{q-r} + \log b[mk^{(q-1)}]^{r-p}$
$+ \log[mk^{(r-1)}]^{p-q}$
$= \log(m^{q-r+r-p+p-q})(k^{p-1})^{q-r}(k^{q-1})^{r-p}(k^{r-1})^{p-q}$
$= \log m^0 k^0 = \log 1 = 0$

9. $a^{3-x} \cdot b^{5x} = a^{x+5} \cdot b^{3x}$
$\Rightarrow \quad \frac{a^{3-x}}{a^{x+5}} = \frac{b^{3x}}{b^{5x}}$
$\Rightarrow \quad a^{-2(x+1)} = b^{-2x}$
$\Rightarrow \quad a^{-2x} \cdot a^{-2} = b^{-2x}$
$\Rightarrow \quad \left(\frac{b}{a}\right)^{-2x} = a^{-2}$
$\Rightarrow \quad \left(\frac{b}{a}\right)^{x} = a$
$\Rightarrow \quad \log\left(\frac{b}{a}\right)^{x} = \log a$
$\Rightarrow \quad x\log\left(\frac{b}{a}\right) = \log a$

10. $v = u^{1/2}, \quad w = u^{1/3}, \quad z = u^{1/4}$
$\therefore \quad uvwz = u^{\left(1+\frac{1}{2}+\frac{1}{3}+\frac{1}{4}\right)}$
$\therefore \quad \log_u uvwz = \log_u u^{\left(1+\frac{1}{2}+\frac{1}{3}+\frac{1}{4}\right)}$
$= \left(1+\frac{1}{2}+\frac{1}{3}+\frac{1}{4}\right)\log_u u = \left(1+\frac{1}{2}+\frac{1}{3}+\frac{1}{4}\right)$

11. $\frac{\log\sqrt{27} + \log\sqrt{8} - \log\sqrt{125}}{\log 6 - \log 5} = \frac{\log(3^{3/2} \times 2^{3/2}) - \log(5)^{3/2}}{\log 6 - \log 5}$
$= \frac{\log 6^{3/2} - \log 5^{3/2}}{\log 6 - \log 5}$
$= \frac{\frac{3}{2}\log\left(\frac{6}{5}\right)}{\log\left(\frac{6}{5}\right)} = \frac{3}{2}$

12. Last term $k = a \cdot r^{n-1}$, $r \rightarrow$ common ratio
$\therefore \quad \log k = \log(a \cdot r^{n-1})$
$\Rightarrow \quad \log k = \log a + (n-1)\log r$
$\Rightarrow \quad \frac{\log k - \log a}{\log r} = n - 1$
$\Rightarrow \quad n = 1 + \left(\frac{\log k - \log a}{\log r}\right)$

13. $\because a, b, c$ are in GP
$\therefore \quad b^2 = ac$
$\Rightarrow \quad 2\log b = \log a + \log c$
$\therefore \log a, \log b, \log c$ are in AP
i. e., $\log_d a, \log_d b, \log_d c$ are in AP
$\therefore \log_a d, \log_b d, \log_c d$ are in HP

14. Best way is to go through options

15. Best way is to go through options
Alternatively: $\log_{10} x^2y^3 = 7$
$\Rightarrow \quad x^2y^3 = 10^7 \quad \ldots(1)$
and $\log_{10}\left(\frac{x}{y}\right) = 1$
$\Rightarrow \quad \frac{x}{y} = 10 \quad \ldots(2)$
$\therefore \quad \frac{x^2y^3}{(x/y)^2} = \frac{10^7}{(10)^2} \Rightarrow y^5 = 10^5$
$\Rightarrow \quad y = 10 \quad \therefore x = 100$

16. $y = a^{\left(\frac{1}{1-\log_a x}\right)}$
$\Rightarrow \quad \log_a y = \frac{1}{1-\log_a x}$ (taking log of both sides)
$\Rightarrow \quad \log_a x = 1 - \frac{1}{\log_a y} \quad \ldots(1)$
Again $z = a^{\left(\frac{1}{1-\log_a y}\right)}$
$\Rightarrow \quad \log_a z = \frac{1}{1-\log_a y}$
$\Rightarrow \quad \log_a y = 1 - \frac{1}{\log_a z} \quad \ldots(2)$
$\therefore$From eq. (1) and (2), we get
$\log_a x = 1 - \frac{1}{\left(1 - \frac{1}{\log_a z}\right)}$
$\Rightarrow \quad \log_a x = \frac{1}{(1-\log_a z)}$
$\Rightarrow \quad x = a^{\frac{1}{1-\log_a z}}$

Alternatively: Consider some numerical values suppose $a = 10$ and $x = \sqrt{10}$
$\therefore \quad y = a^{\left(\frac{1}{1-\log_a x}\right)}$
$y = 10^{\left(\frac{1}{1-\log_{10}\sqrt{10}}\right)}$
$\Rightarrow \quad y = 100$
and $z = a^{\left(\frac{1}{1-\log_a y}\right)}$
$\therefore \quad z = 10^{\left(\frac{1}{1-\log_{10}100}\right)}$
$\Rightarrow \quad z = \frac{1}{10}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Now, go through options. Consider option (c)

$$x = a^{\frac{1}{1-\log_a x}} = 10^{\left(\frac{1}{1-\log_{10}(1/10)}\right)}$$

$$x = 10^{1/2} = \sqrt{10}$$

Hence option (c) is correct.

NOTE You can check other options but they do not satisfy.

17. Let $a = 10$, $b = 100$ and $c = 1000$, then

$$x = \log_{1000}(100) + \log_{100}(1000) = \frac{13}{6}$$

$$y = \log_{10} 1000 + \log_{1000} 10 = \frac{10}{3}$$

$$z = \log_{100} 10 + \log_{10} 100 = \frac{5}{2}$$

$$\therefore \quad x^2 + y^2 + z^2 = \left(\frac{13}{6}\right)^2 + \left(\frac{10}{3}\right)^2 + \left(\frac{5}{2}\right)^2 = \frac{794}{36}$$

and $$xyz = \frac{13}{6} \times \frac{10}{3} \times \frac{5}{2} = \frac{650}{36}$$

$$\therefore \quad xyz + 4 = \left(\frac{650}{36}\right) + 4 = \frac{794}{36}$$

Hence choice (d) is correct.

18. $$\frac{1}{\log_3 e} + \frac{1}{\log_3 e^2} + \frac{1}{\log_3 e^4} + \ldots$$

$$= \frac{1}{\log_3 e} + \frac{1}{2\log_3 e} + \frac{1}{4\log_3 e} + \ldots$$

$$= \frac{1}{\log_3 e}\left(1 + \frac{1}{2} + \frac{1}{4} + \ldots\right)$$

$$= \log_e 3\left(\frac{1}{1-1/2}\right)$$

(Using sum of infinite GP) $\left(s_\infty = \frac{a}{1-r}; |r| < 1\right)$

$$= 2\log_e 3 = \log_e 3^2 = \log_e 9$$

19. $$\log_{10} x^2 - \log_{10}\sqrt{y} = 1$$

$$\Rightarrow \quad \log_{10}\left(\frac{x^2}{\sqrt{y}}\right) = \log_{10} 10$$

$$\Rightarrow \quad \frac{x^2}{\sqrt{y}} = 10 \quad \Rightarrow \quad \frac{4}{\sqrt{y}} = 10$$

$$\Rightarrow \quad \sqrt{y} = \frac{4}{10} = \frac{2}{5}$$

$$\Rightarrow \quad y = \frac{4}{25}$$

20. $(b^2)^{5\log_b x} = b^{10\log_b x} = b^{\log_b (x)^{10}} = x^{10}$

21. $(7^3)^{-2\log_7 8} = 7^{-6\log_7 8} = 7^{(\log_7 8^{-6})}$

$$= 8^{-6} = \frac{1}{8^6}$$

22. $\log 12900 = \log(1.29 \times 10000)$

$$= \log 1.29 + \log 10000$$

$$= \log 1.29 + 4$$

23. $\log 0.786 = \log\left(\frac{786}{1000}\right) = \log 786 - \log 1000$

$$= \log 786 - 3$$

Also $$\log 0.786 = \log\frac{78.6}{100} = \log 78.6 - \log 100$$

24. $$\log_5 x = y \quad \Rightarrow \quad 5^y = x$$

$$(5^y)^5 = x^5 \quad \Rightarrow \quad 5^{5y} = x^5$$

$\therefore$

25. $$A = \log_{13} 189 = \log_{13}(13^2 + 20)$$

and $$B = \log_{23} 521 = \log_{23}(23^2 - 8)$$

$\therefore$ $A > B$ ($\because A > 2$ and $B < 2$)

26. $$A = \frac{\log_3 2187}{5} = \frac{1}{5}\log_3 2187$$

$$= \frac{1}{5}\log_3(3^7) = \frac{7}{5}\log_3 3 = \frac{7}{5}$$

and $$B = \log_{243} 2187 = \frac{\log_3 2187}{\log_3 243} = \frac{\log_3 3^7}{\log_3 3^5} = \frac{7}{5}$$

$\therefore$ $A = B$

27. $$(150)^x = 7$$

$$\Rightarrow \quad \log_{150} 7 = x$$

$$\Rightarrow \quad \frac{\log 7}{\log 150} = x$$

$$\Rightarrow \quad x = \frac{\log 7}{\log(3 \times 5 \times 10)} = \frac{\log 7}{\log 3 + \log 5 + \log 10}$$

$$= \frac{\log 7}{\log 3 + \log 5 + 1}$$

28. $$\log_{1/2} x = \log_2(3x - 2)$$

$$\Rightarrow \quad -\log_2 x = \log_2(3x - 2)$$

$$\Rightarrow \quad \log_2(x^{-1}) = \log_2(3x - 2)$$

$$\Rightarrow \quad x^{-1} = (3x - 2)$$

$$\Rightarrow \quad 3x^2 - 2x - 1 = 0$$

$$\Rightarrow \quad 3x^2 - 3x + x - 1 = 0$$

$$\Rightarrow \quad 3x(x-1) + 1(x-1) = 0$$

$$\Rightarrow \quad x = 1, -1/3$$

but at $x = -1/3$, $\log x$ is not defined

The only admissible value of x is 1.

Alternatively : Go through options.

29. $$\log_2(x + y) = 3$$

and $$\log_2 x + \log_2 y = 2 + \log_2 3$$

$\because$ $$\log_2(x + y) = 3 = \log_2 2^3 = \log_2 8$$

$\Rightarrow$ $$x + y = 8,$$

Hence option (c) is wrong.

Again, $$\log_2 x + \log_2 y = 2 + \log_2 3 = \log_2 4 + \log_2 3$$

$\Rightarrow$ $$\log_2(xy) = \log_2 12$$

$\Rightarrow$ $$xy = 12$$

Hence option (d) is correct.

30. Go through option.

at $x = 0$, $\log x$ is not defined.

at $x = 1$, both sides are equal.

Again at $x \neq 1$

$$\log_5 x \log_6 x \log_7 x = \log_5 x \log_6 x + \log_6 x \cdot \log_7 x + \log_7 x \cdot \log_5 x$$

$$\Rightarrow \quad 1 = \frac{1}{\log_7 x} + \frac{1}{\log_5 x} + \frac{1}{\log_6 x}$$

(By dividing both sides by $\log_5 x \log_6 x \log_7 x$)

$\therefore$ $$1 = \log_x 7 + \log_x 5 + \log_x 6$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$1 = \log_x(7 \cdot 5 \cdot 6) = \log_x 210$$
$$\log_x 210 = 1$$
$$\Rightarrow \quad x = 210$$
$$\Rightarrow \quad x = \{1, 210\}$$

Hence

31. Let $\log_3 18 = a$

$$\therefore \frac{\log_3 54}{\log_{486} 3} - \frac{\log_3 1458}{\log_{18} 3}$$
$$= \log_3(18 \times 3)\log_3(18 \times 27) - \log_3(18 \times 81)\log_3 18$$
$$= (\log_3 18 + \log_3 3)(\log_3 18 + 3\log_3 3) - (\log_3 18 + 4\log_3 3)\log_3 18$$
$$= (a+1)(a+3) - (a+4)a$$
$$= a^2 + 3 + 4a - a^2 - 4a = 3$$

32.
$$\log_9(2x-5) = \log_3(x-4)$$
$$\Rightarrow \quad \frac{1}{2}\log_3(2x-5) = \log_3(x-4)$$
$$\Rightarrow \quad \log_3(2x-5) = \log_3(x-4)^2$$
$$\Rightarrow \quad (2x-5) = (x-4)^2$$
$$\Rightarrow \quad (2x-5) = x^2 + 16 - 8x$$
$$\Rightarrow \quad x^2 - 10x + 21 = 0$$
$$\Rightarrow \quad (x-3)(x-7) = 0$$
$$\Rightarrow \quad x = 3 \quad \text{or} \quad x = 7$$

but at $x = 3$, $\log_3(x-4)$ is not defined since $(x-4)$ becomes negative

Hence $x = 7$ is the only possible solution.

33. Since we know that when a, b, c are in GP, then $\log a$, $\log b$ and $\log c$ are in AP.

Therefore 2, $(2^x - 5)$ and $(2^x - 7/2)$ must be in GP

Now, going through options, we get

at $x = 3$ the three terms 2, $(2^x - 5)$and $(2^x - 7/2)$ are in GP

Hence $\log 2$, $\log(2^x - 5)$ and $\log(2^x - 7/2)$ are in AP.

Alternatively :

We have $2\log_3(2^x - 5) = \log_3 2 + \log_3(2^x - 7/2)$

$$\Rightarrow \quad \log_3(2^x - 5)^2 = \log_3 2(2^x - 7/2)$$
$$\Rightarrow \quad (2^x - 5)^2 = 2(2^x - 7/2)$$
$$\Rightarrow \quad (2^x)^2 - 10 \cdot 2^x + 25 = 2 \cdot 2^x - 7$$

$[10 \cdot 2^x + 2 \cdot 2^x = 12\ 2^x]$ $\quad [\because (a-b)^2 = a^2 - 2ab + b^2]$

$$\Rightarrow \quad (2^x)^2 - 12 \cdot 2^x + 32 = 0$$
$$\Rightarrow \quad (2^x - 8)(2^x - 4) = 0$$
$$\Rightarrow \quad x = 3, \quad x = 2$$

but at $x = 2$, $\log(2^x - 5)$ is undefined

Hence $x = 3$

34. Go through options.

35. As $\log_x a$, $a^{x/2}$, $\log_b x$ are in GP.

$$\therefore \quad (a^{x/2})^2 = \log_x a \cdot \log_b x$$
$$\Rightarrow \quad a^x = \frac{\log a}{\log x} \cdot \frac{\log x}{\log b} = \frac{\log a}{\log b} = \log_b a$$
$$\Rightarrow \quad a^x = \log_b a$$
$$\Rightarrow \quad x = \log_a(\log_b a)$$
$$= \log_a\left(\frac{\log_e a}{\log_e b}\right)$$
$$= \log_a(\log_e a) - \log_a(\log_e b)$$

36. $1, \log_3(3^{1-x} + 2), \log_3(4 \cdot 3^x - 1)$ are in AP

$1, \log_3(3^{1-x} + 2)^{1/2}, \log_3(4 \cdot 3^x - 1)$ are in AP

$\therefore \log_3 3, \log_3(3^{1-x} + 2)^{1/2}, \log_3(4 \cdot 3^x - 1)$ are in AP

$\therefore 3, (3^{1-x} + 2)^{1/2}, (4 \cdot 3^x - 1)$ are in GP

$$\therefore \quad [(3^{1-x} + 2)^{1/2}]^2 = 3 \cdot (4 \cdot 3^x - 1)$$
$$\Rightarrow \quad 3^{1-x} + 2 = 4 \cdot 3^{x+1} - 3$$
$$\Rightarrow \quad 4 \cdot 3^{x+1} - 3^{1-x} = 5$$

Solving we get $\quad x = \log_3\left(\frac{3}{4}\right)$

Alternatively: Go through options. Consider option (d)

$$x = \log_3 \frac{3}{4} \Rightarrow 3^x = \frac{3}{4}$$
$$\Rightarrow 1, \log_9\left(\frac{3}{3^x} + 2\right), \log_3\left(4 \cdot \frac{3}{4} - 1\right)$$
$$\Rightarrow 1, \log_9 6, \log_3 2$$
$$\Rightarrow \log_9 9, \log_9 6, \log_9 4 \text{ are in AP}$$

Since 9, 6, 4 are in GP

37. $\frac{1}{\log_{100} n} + \frac{1}{\log_{99} n} + \ldots + \frac{1}{\log_2 n}$

$$= \log_n 100 - \log_n 99 + \ldots - \log_n 2$$
$$= \log_n(100 \times 99 \times 98 \times \ldots \times 2)$$
$$= \log_n 100! = \frac{1}{\log_{100!} n}$$

38. Best way is to go through options.

At $x = 1$,

$$\log_2(1 + 3^0) + 2 = \log_2(3^0 + 7)$$
$$\Rightarrow \quad \log_2 2 + 2 = \log_2 8 \qquad (\because x^0 = 1)$$
$$\Rightarrow \quad 1 + 2 = \log_2 2^3$$
$$\Rightarrow \quad 3 = 3$$

Similarly, at $\quad x = 2$

$$\log_2(1 + 3) + 2 = \log_2(9 + 7)$$
$$\Rightarrow \quad (\log_2 4) + 2 = \log_2(16)$$
$$\Rightarrow \quad 4 = 4$$

Hence (d) is the correct answer

39. $x^{\log_5 x} > 5$

Taking logarithm with base 5 we have

$$(\log_5 x)(\log_5 x) > 1$$
$$\Rightarrow \quad (\log_5 x)^2 > 1$$
$$\Rightarrow \quad (\log_5 x)^2 - 1 > 0$$
$$\Rightarrow \quad (\log_5 x - 1)(\log_5 x + 1) > 0$$
$$\Rightarrow \quad \log_5 x > 1 \quad \text{Or} \quad \log_5 x < -1$$
$$\Rightarrow \quad x > 5 \quad \text{or} \quad x < \frac{1}{5}$$

Also, x must be greater than zero

$$\therefore \quad x \in (0, 1/5) \cup (5, \infty)$$

Alternatively: Go through options

Let us assume $x = 25$

then $\quad 25^{\log_5 25} = 625 > 5,$ which is true

Hence option (d) is correct.

Again consider $x = 5$, then

$5^{\log_5 5} = 5$, which is not greater than 5.

Hence choices (a) and (b) are wrong.

Thus option (d) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

40. $\log x^3 - \log 3x = 2\log 2 + \log 3$

$$\log \frac{x^2}{3} = \log 12$$

$$\Rightarrow \quad \frac{x^2}{3} = 12 \Rightarrow x = \pm 6$$

But at $x = -6$, $\log 3x$ and $\log x^3$ are not defined.

Hence $x = 6$ is the only correct answer.

41. $\log_5(2x+3) < \log_5 7$

$$\Rightarrow \quad (2x+3) < 7$$

$$\Rightarrow \quad 2x < 4$$

$$\Rightarrow \quad x < 2$$

But $(2x+3) > 0 \Rightarrow x > -\frac{3}{2}$

$$\therefore \quad x \in \left(-\frac{3}{2}, 2\right)$$

42. Best way is to go through options.

Alternatively: Suppose $\log_2 x = t$, then

$$\log_{2\sqrt{x}} x = \frac{\log_2 x}{\log_2 2\sqrt{x}} = \frac{t}{1+\frac{t}{2}}$$

and $$\log_{2x}\sqrt{x} = \frac{\log_2 \sqrt{x}}{\log_2 2x} = \frac{\frac{1}{2}\log_2 x}{1+\log_2 x} = \frac{t/2}{1+t}$$

$$\log_{2\sqrt{x}} x + \log_{2x}\sqrt{x} = \frac{2t}{2+t} + \frac{t}{2+2t} = 0$$

$$2t(2+2t) + t(2+t) = 0$$

$$\Rightarrow \quad 4t + 4t^2 + 2t + t^2 = 0$$

$$\Rightarrow \quad 5t^2 + 6t = 0$$

$$\Rightarrow \quad t(5t+6) = 0$$

$$\Rightarrow \quad t = 0 \text{ or } t = -\frac{6}{5}$$

$$\Rightarrow \quad \log_2 x = 0 \Rightarrow x = 2^0 = 1$$

and $$\log_2 x = -\frac{6}{5} \Rightarrow x = 2^{-6/5}$$

$$\therefore \quad x = 1 \text{ and } x = 2^{-6/5}$$

43. Clearly option (b) is wrong

$$\therefore \quad \frac{x}{1+x} < x \qquad \text{for every } x > 1$$

Again $$\frac{x}{1+x} < \log(x+1);\ x > 1$$

Hence option (c) is also wrong

and $$\log(x+1) < x$$

$\therefore$ Option (d) is correct.

44. $$\frac{k}{l} > \frac{k+1}{l+1} \quad \text{for } (k, l) > 0 \text{ and } k > l$$

Let $k = x+1$ and $l = x$

$$\therefore \quad \frac{x+1}{x} > \frac{(x+1)+1}{(x)+1}$$

$\because$ $(x+1) > x$

$$\therefore \quad \frac{\log(x+1)}{\log x} > \frac{\log(x+2)}{\log(x+1)}$$

$$\Rightarrow \quad \log_x(x+1) > \log_{x+1}(x+2)$$

45. $a = 1 + \log_x yz = \log_x x + \log_x yz = \log_x xyz$

Similarly $b = \log_y xyz$

and $c = \log_z xyz$

Now, $ab + bc + ca = abc\left[\frac{1}{c} + \frac{1}{a} + \frac{1}{b}\right]$

$$= abc\left[\frac{1}{\log_x xyz} + \frac{1}{\log_y xyz} + \frac{1}{\log_z xyz}\right]$$

$$= abc[\log_{xyz} x + \log_{xyz} y + \log_{xyz} z]$$

$$= abc[\log_{xyz} xyz] = abc$$

46. $\log_3(\log_2 x) + \log_{1/3}(\log_{1/2} y) = 1$

$$\Rightarrow \quad \log_3(\log_2 x) - \log_3(\log_{1/2} y) = 1$$

$$\Rightarrow \quad \log_3\left(\frac{\log_2 x}{\log_{1/2} y}\right) = 1 = \log_3 3$$

$$\Rightarrow \quad \frac{\log_2 x}{\log_{1/2} y} = 3$$

$$\Rightarrow \quad \log_2 x = 3\log_{1/2} y = -3\log_2 y$$

$$\Rightarrow \quad x = y^{-3}$$

$$\Rightarrow \quad xy^3 = 1 \qquad \text{...(1)}$$

Again dividing eq. (1) by $xy^2 = 4$, we get $y = \frac{1}{4}$

$$\therefore \quad x = 64, \qquad \text{[From eq. (1)]}$$

Alternatively : Go through options.

47. Best way is to check the options.

Alternatively :

$$\log_{(1/\sqrt{2})}(1/\sqrt{8}) = \log_2(4^x + 1) \cdot \log_2(4^{x-1} + 4)$$

$$\Rightarrow \quad \frac{\log_2(1/\sqrt{8})}{\log_2(1/\sqrt{2})} = \log_2(4^x + 1) \cdot \log_2(4^{x-1} + 4)$$

$$\Rightarrow \quad 3 = [\log_2 4 + \log_2(4^x + 1)][\log_2(4^x + 1)]$$

$$\Rightarrow \quad (2+t)t = 3, \qquad \text{where } t = \log_2(4^x + 1)$$

$$\Rightarrow \quad t = -3, 1$$

If $\log_2(4^x + 1) = -3$, then $4^x = -7/8$ which is not possible

If $\log_2(4^x + 1) = 1$, then $4^x + 1 \Rightarrow 2 \Rightarrow 4^x = 1$

$$\Rightarrow \quad x = 0$$

48. $\log_3 4 - \log_3(3x+1) = \log_3 \frac{3}{(5x-2)}$

$$\log_3 \frac{4}{3x+1} = \log_3 \frac{3}{(5x-2)}$$

$$\Rightarrow \quad \frac{4}{(3x+1)} = \frac{3}{(5x-2)}$$

$$\Rightarrow \quad 20x - 8 = 9x + 3$$

$$\Rightarrow \quad 11x = 11$$

$$\Rightarrow \quad x = 1$$

Alternatively : Go through options.

49. $|3 - 4x| > 2$

$$\Rightarrow \quad (3-4x) > 2 \text{ or } -(3-4x) > 2$$

$$\Rightarrow \quad x < \frac{1}{4} \text{ or } x > \frac{5}{4}$$

$$\therefore \quad x \in \left(-\infty, \frac{1}{4}\right) \cup \left(\frac{5}{4}, \infty\right)$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$\log_{100} |x+y| = \frac{1}{2}$$

$$\Rightarrow \quad |x+y| = 10 \qquad (-10 \text{ is inadmissible})$$

and $$\log_{10} y - \log_{10} |x| = \log_{100} 4$$

$$\Rightarrow \quad \log_{10}\left(\frac{y}{|x|}\right) = \log_{10} 2$$

$$\Rightarrow \quad \frac{y}{|x|} = 2 \Rightarrow y = 2|x|$$

Hence we have $|x+2|\,|x|| = 10$

Now, if $x > 0$, then we have

$$3x = 10 \Rightarrow x = \frac{10}{3}$$

and if $x < 0$, then

$$|-x| = 10$$

$$\Rightarrow \quad x = -10$$

Thus, $$x = \frac{10}{3}, \quad y = \frac{20}{3}$$

and $$x = -10, \quad y = 20$$

LEVEL 2

1. See the theory of this chapter

3. $$\log_2\left(\frac{x}{y}\right) + \log_4\left(\frac{x}{y}\right)^2 + \log_8\left(\frac{x}{y}\right)^3 + \ldots$$

$$= \log_2\left(\frac{x}{y}\right) + \log_2\left(\frac{x}{y}\right) + \log_2\left(\frac{x}{y}\right) + \ldots$$

$$= \log_2\left(\frac{x}{y} \times \frac{x}{y} \times \frac{x}{y} \times \ldots n \text{ times}\right)$$

$$= \log_2\left(\frac{x}{y}\right)^n = n \log_2\left(\frac{x}{y}\right)$$

4. $$\log m + \log m^2 + \log m^3 + \ldots + \log m^n$$

$$= \log (m \cdot m^2 \cdot m^3 \ldots m^n)$$

$$= \log m^{(1+2+3+\ldots n)}$$

$$= \log (m)^{\frac{n(n+1)}{2}}$$

$$= \frac{n(n+1)}{2} \log m$$

5. Given that $9^n < 10^8$

Taking log to both sides

$$\log 9^n < \log 10^8$$

$$\Rightarrow \quad 2n \log 3 < 8 \log 10$$

$$\Rightarrow \quad 2n \times 0.4771 < 8$$

$$\Rightarrow \quad n \times 0.9542 < 8$$

$$\Rightarrow \quad n < \frac{8}{0.9542}$$

$$n < 8.3839$$

$$\therefore \quad n = 8 \qquad (\because n \in N)$$

6. Taking log of both sides with base 3 we have,

$$[\log_3 x^2 + (\log_3 x)^2 - 10] \log_3 x = -2 \log_3 x$$

$$\Rightarrow \quad \log_3 x = 0$$

or $$(\log_3 x)^2 + 2 \log_3 x - 8 = 0$$

$\Rightarrow x = 1,$ $(\log_3 x + 4)(\log_3 x - 2) = 0$

$\Rightarrow x = 1,$ $\log_3 x = -4$ and $\log_3 x = 2$

$\Rightarrow x = 1,$ $x = \frac{1}{81}$ and $x = 9$

$$\therefore \quad x = \left\{1, \frac{1}{81}, 9\right\}$$

7. $$(x-3) > 0 \Rightarrow x > 3$$

and $$(2-x) > 0 \text{ and } 2 - x \neq 1$$

$$\therefore \quad x < 2 \text{ and } x \neq 1$$

Clearly there is no single value for which these inequalities are satisfied. Thus the set of its solutions is empty.

8. $\log_3 30 = \frac{1}{a} \Rightarrow a = \log_{30} 3$ and $\log_5 30 = \frac{1}{b}$

$$\Rightarrow \quad b = \log_{30} 5$$

$$3 \log_{30} 2 = 3[\log_{30}(30/15)]$$

$$= 3[\log_{30} 30 - \log_{30} 15]$$

$$= 3[\log_{30} 30 - (\log_{30} 3 + \log_{30} 5)]$$

$$= 3[1 - a - b]$$

9. $$x^{\log_x |3-x|^2} = 4$$

$$\Rightarrow \quad |3-x|^2 = 4$$

$$\Rightarrow \quad |3-x| = 2 \qquad (-2 \text{ is inadmissible})$$

$$\Rightarrow \quad (3-x) = 2 \text{ or } -(3-x) = 2$$

$$\Rightarrow \quad x = 1 \text{ or } x = 5$$

10. Let $2^{x^2+2} = t$, then

$$4^{x^2+2} - 9 \cdot 2^{x^2+2} + 8 = 0 \text{ becomes}$$

$$t^2 - 9t + 8 = 0$$

$$\Rightarrow \quad t = 1, 8$$

$$\Rightarrow \quad 2^{x^2+2} = 1$$

$$\Rightarrow \quad x^2 + 2 = 0 \quad \text{but this has no solution}$$

If $$2^{x^2+2} = 8 \Rightarrow x^2 + 2 = 3$$

$$\Rightarrow \quad x^2 = 1 \Rightarrow x = \pm 1$$

11. Taking log of both sides, we get

$$\left[(\log_3 x)^2 - \frac{9}{2} \log_3 x + 5\right] \log_3 x = \frac{3}{2}$$

$$\Rightarrow \quad 2(\log_3 x)^3 - 9(\log_3 x)^2 + 10(\log_3 x) - 3 = 0$$

$$\Rightarrow \quad (\log_3 x - 1)(\log_3 x - 3)(2 \log_3 x - 1) = 0$$

$$\Rightarrow \quad \log_3 x = 1, \log_3 x = 3, 2 \log_3 x = 1$$

$$\Rightarrow \quad x = 3, x = 27, x = \sqrt{3}$$

i.e., $$x = (\sqrt{3}, 3, 27)$$

12. $$x^2 + 6x + 8 > 0 \text{ and } 2x^2 + 2x + 3 > 0$$

$$\Rightarrow \quad (x+4)(x+2) > 0 \text{ and } \left(x + \frac{1}{2}\right)^2 + \frac{5}{4} > 0$$

$$\Rightarrow \quad x \in (-\infty, -4) \cup (-2, \infty) \qquad \ldots(1)$$

The given equation can be written as

$$\log_{(2x^2+2x+3)}(x^2 - 2x) = 1$$

$$\Rightarrow \quad x^2 - 2x = 2x^2 + 2x + 3$$

$$\Rightarrow \quad x^2 + 4x + 3 = 0$$

$$\Rightarrow \quad x = -1, -3$$

but at $x = -3$, $\log_{(x^2+6x+8)}$ is not defined

Hence, $$x = -1$$

Scanned by CamScanner

yoursmahboob.wordpress.com

13. Let $u = \log_{10} p$, then the given inequality reduces to

$$(2+u)^2 + (1+u)^2 + u \le 9$$
$$2u^2 + 7u + 5 \le 9$$
$$2u^2 + 7u - 4 \le 0$$
$$\Rightarrow \quad 2u^2 + 8u - u - 4 \le 0$$
$$\Rightarrow \quad 2u(u+4) - 1(u+4) \le 0$$
$$\Rightarrow \quad (u+4)(2u-1) \le 0$$
$$\Rightarrow \quad -4 \le u \le \frac{1}{2}$$
$$\Rightarrow \quad -4 \le \log_{10} p \le \frac{1}{2}$$
$$\Rightarrow \quad 10^{-4} \le p \le 10^{1/2}$$

14. Let $u = \log_2 x$, then

$$2\log_2 \log_2 x + \log_{1/2} \log_2 (2\sqrt{2}x) = 1$$
$$\Rightarrow \quad 2\log_2 u + \log_{1/2}(\log_2 2^{3/2} + u) = 1$$
$$\Rightarrow \quad \log_2 u^2 - \log_2 (3/2 + u) = 1$$
$$\Rightarrow \quad \log_2 \left(\frac{u^2}{3/2+u}\right) = 1$$
$$\Rightarrow \quad u^2 = 2\left(\frac{3}{2} + u\right)$$
$$\Rightarrow \quad u^2 - 2u - 3 = 0$$
$$\Rightarrow \quad u = -1, 3$$
$$\Rightarrow \quad x = \frac{1}{2}, 8$$

but at $x = \frac{1}{2}$, $2\log_2 \log_2 x$ is undefined

Hence, $x = 8$

15. By changing the base to 2 the given equation becomes

$$\frac{\log_2 x^2}{\log_2 x/2} + \frac{40\log_2 \sqrt{x}}{\log_2 4x} - 14\frac{\log_2 x^3}{\log_2 16x} = 0$$
$$\Rightarrow \quad \frac{2\log_2 x}{\log_2 x - 1} + 20\frac{\log_2 x}{2 + \log_2 x} - 42\frac{\log_2 x}{4 + \log_2 x} = 0$$

Let $t = \log_2 x$, then we have

$$2t(4+t)(2+t) - 42t(t-1)(t+2) + 20t(t-1)(t+4) = 0$$
$$\Rightarrow \quad 2t[t^2 + 6t + 8 - 21t^2 - 21t + 42 + 10t^2 + 30t - 40] = 0$$
$$\Rightarrow \quad t[2t^2 - 3t - 2] = 0$$
$$\Rightarrow \quad t = 0, \quad t = 2, \quad t = -\frac{1}{2}$$
$$\Rightarrow \quad x = 1, \quad x = 4, \quad x = \frac{1}{\sqrt{2}}$$

16. $m > 0$ and $n > 0$ and $m \ne 1$

i.e., $25 - x^2 > 0$ and $x \ne \pm 3$

and $24 - 2x - x^2 > 0$

$\Rightarrow \quad -5 < x < 5, \; x \ne \pm 3$

and $x^2 + 2x - 24 < 0$

$-5 < x < 5, \quad x \ne \pm 3$

and $-6 < x < 4$

$x \in (-5, 4) - \{-3, 3\}$ ...(1)

Case 1. $0 < m < 1 \Rightarrow 9 < x^2 < 25$

$\Rightarrow \quad x \in (-5, -3) \cup (3, 5)$ ...(2)

$\therefore$ The given inequality can be written as

$$\frac{24 - 2x - x^2}{14} < \frac{25 - x^2}{16}$$
$$\Rightarrow \quad x^2 + 16x - 17 > 0$$
$$\Rightarrow \quad (x+17)(x-1) > 0$$
$$\Rightarrow \quad x < -17 \quad \text{or} \quad x > 1$$

From (1) and (2), we have

$$x \in (3, 4)$$

Case 2. If $m > 1$, *i.e.*, $\frac{25 - x^2}{16} > 1$

$$\Rightarrow \quad x \in (-3, 3)$$ ...(3)

The given inequality reduces to

$$\frac{24 - 2x - x^2}{14} > \frac{25 - x^2}{16}$$
$$\Rightarrow \quad x^2 + 16x - 17 < 0$$
$$\Rightarrow \quad -17 < x < 1$$

Thus combining with (3), we get

$$x \in (-3, 1)$$

but $x \in (-5, 4) - \{-3, 3\}$ by (1)

thus $x \in (-3, 1)$

Hence the required value of x should lie in $(-3, 1) \cup (3, 4)$

17. $$\log_2 \left(\frac{5}{2}\right) = (\log_2 5) - 1$$

but $\because \quad (\log_2 5) - 1 > (\log_2 4) - 1$

$$\therefore \quad \log_{3/10}\left[\frac{10}{7}(\log_2 5 - 1)\right] < \log_{3/10}\frac{10}{7} < \log_{3/10} 1 \; (= 0)$$

($\because \log_a x < \log_a y$ if $x > y$ for $0 < a < 1$)

Since $\log_{3/10}\frac{10}{7}(\log_2 5 - 1) < 0$

Hence, the first inequality is true only if

$$\sqrt{(x-8)(2-x)} = 0$$
$$\Rightarrow \quad x = 8 \quad \text{or} \quad x = 2$$

If $x = 8$, then $\frac{2^x}{8} - (2^5 - 1) = 1 > 0$

If $x = 2$ then $\frac{2^x}{8} - (2^5 - 1) = \frac{1}{2} - (2^5 - 1) < 0$

Hence $x = 8$ is the required value.

18. $$2\log_{10} x - \log_x \frac{1}{100} = 2\log_{10} x - \frac{\log_{10} 10^{-2}}{\log_{10} x}$$
$$= 2\log_{10} x + \frac{2}{\log_{10} x}$$
$$= 2\left(\log_{10} x + \frac{1}{\log_{10} x}\right)$$

Since $x > 1 \Rightarrow \log_{10} x > 0$

But since AM $\ge$ GM

$$\therefore \quad \frac{\left(\log_{10} x + \frac{1}{\log_{10} x}\right)}{2} \ge \sqrt{\log_{10} x \times \frac{1}{\log_{10} x}}$$
$$\Rightarrow \quad \log_{10} x + \frac{1}{\log_{10} x} \ge 2$$
$$\Rightarrow \quad 2\left(\log_{10} x + \frac{1}{\log_{10} x}\right) \ge 4$$

Scanned by CamScanner

yoursmahboob.wordpress.com

For $x = 10$, $\quad 2\left(\log_{10} x + \dfrac{1}{\log_{10} x}\right) \geq 4$

Hence the least value of $\left(\log_{10} x - \log_x \dfrac{1}{100}\right)$ is 4.

19. We have, $x^{[(3/4)(\log_2 x)^2 + \log_2 x - (5/4)]} = \sqrt{2}$

$$\Rightarrow \quad \log_x \sqrt{2} = \frac{3}{4}(\log_2 x)^2 + \log_2 x - \left(\frac{5}{4}\right)$$

$$\Rightarrow \quad \frac{\log \sqrt{2}}{\log x} = \frac{3}{4}(\log_2 x)^2 + \log_2 x - \left(\frac{5}{4}\right)$$

$$\Rightarrow \quad \log \sqrt{2} = \log x \left[\frac{3}{4}(\log_2 x)^2 + \log_2 x - \left(\frac{5}{4}\right)\right]$$

$$\Rightarrow \quad \log_2 \sqrt{2} = \log_2 x \left[\frac{3}{4}(\log_2 x)^2 + \log_2 x - \left(\frac{5}{4}\right)\right]$$

$$\Rightarrow \quad \frac{1}{2} = \alpha\left[\frac{3}{4}\alpha^2 + \alpha - \frac{5}{4}\right] \qquad (\text{say } \alpha = \log_2 x)$$

$$\Rightarrow \quad 2 = 3\alpha^3 + 4\alpha^2 - 5\alpha$$

$$\Rightarrow \quad 3\alpha^3 + 4\alpha^2 - 5\alpha - 2 = 0$$

$$\Rightarrow \quad (\alpha - 1)(3\alpha^2 + 7\alpha + 2) = 0$$

$$\Rightarrow \quad \alpha = 1 \Rightarrow \log_2 x = 1 \Rightarrow x = 2$$

Again $\quad 3\alpha^2 + 7\alpha + 2 = 0$

$$\Rightarrow \quad \alpha = -2, -\frac{1}{3}$$

$$\Rightarrow \quad \log_2 x = -2 \quad \text{and} \quad \log_2 x = \frac{-1}{3}$$

$$\Rightarrow \quad x = \frac{1}{4} \Rightarrow x = 2^{-1/3}$$

Hence $\quad x = 2, \dfrac{1}{4}, 2^{-1/3}$

Thus option (d) is most appropriate.

20. $\quad 2x + 3 > 0 \quad \text{and} \quad 2x + 3 \neq 1$

$$\Rightarrow \quad x > -\frac{3}{2} \quad \text{and} \quad x \neq -1$$

And $\quad 3x + 7 > 0 \quad \text{and} \quad 3x + 7 \neq 1$

$$\Rightarrow \quad x > \frac{-7}{3} \Rightarrow x \neq -2$$

Now, $\log_{(2x+3)}(6x^2 + 23x + 21)$

$$= 4 - \log_{(3x+7)}(4x^2 + 12x + 9)$$

$$\Rightarrow \log_{(2x+3)}(2x + 3)(3x + 7) = 4 - \log_{(3x+7)}(2x + 3)^2$$

$$\Rightarrow \log_{(2x+3)}(2x + 3) + \log_{(2x+3)}(3x + 7) = 4 - 2\log_{(3x+7)}(2x + 3)$$

$$\Rightarrow 1 + \log_{(2x+3)}(3x + 7) + 2\log_{(3x+7)}(2x + 3) - 4 = 0$$

$$\Rightarrow \quad \frac{2\log(2x + 3)}{\log(3x + 7)} + \frac{\log(3x + 7)}{\log(2x + 3)} - 3 = 0 \qquad \ldots(1)$$

Putting $\dfrac{\log(2x + 3)}{\log(3x + 7)} = y$ in eq. (1), we get

$$2y + \frac{1}{y} - 3 = 0 \quad \Rightarrow \quad 2y^2 - 3y + 1 = 0$$

$$(2y - 1)(y - 1) = 0$$

$$\Rightarrow \quad y = \frac{1}{2} \quad \text{and} \quad y = 1$$

Now, when $y = \dfrac{1}{2}$

$$\therefore \quad \frac{\log(2x + 3)}{\log(3x + 7)} = \frac{1}{2}$$

$$\Rightarrow \quad (2x + 3)^2 = (3x + 7)$$

$$4x^2 + 9x + 2 = 0$$

$$(4x + 1)(x + 2) = 0$$

$$x = -\frac{1}{4}, -2$$

Again if $y = 1$, then

$$\frac{\log(2x + 3)}{\log(3x + 1)} = 1$$

$$\Rightarrow \quad 2x + 3 = 3x + 7$$

$$x = -4$$

Since we know that $x > -\dfrac{3}{2}$ and $x > -\dfrac{7}{3}$

therefore $x = -2$ and $x = -4$ are not admissible values

Again since $x \neq -1$ and $x \neq -2$

Hence $x = -2$ is also inadmissible value

Thus, $x = -\dfrac{1}{4}$ is only possible value.

$\therefore$ Option (b) is correct.

Alternatively: Go through options

21. $x > 0, x \neq 1$

Since exponential function assumes positive value, so we must have $(x - 1)^{\bar{y}} > 0$ *i.e.*, $x > 1$.

Taking logarithm on both sides, we get

$$(\log_3 x^2 - 2\log_x 9)\log(x - 1) = 7\log(x - 1)$$

Either $\log(x - 1) = 0$ *i.e.*, $x = 2$

or $\quad \log_3 x^2 - 2\log_x 9 = 7$

$$\Rightarrow \quad 2(\log_3 x) - 4\log_x 3 = 7$$

$$\Rightarrow \quad 2t - \frac{4}{t} = 7, \qquad (\because t = \log_3 x)$$

$$\Rightarrow \quad 2t^2 - 7t - 4 = 0$$

$$\Rightarrow \quad t = 4, -\frac{1}{2}$$

$$\log_3 x = 4 \quad \Rightarrow \quad x = 81$$

If $\log_3 x = -\dfrac{1}{2}$, then $x = 3^{-1/2} < 1$, which is not the case

Hence, $\quad x = 2, 81$

❑❑❑

Scanned by CamScanner

yoursmahboob.wordpress.com

17 FUNCTIONS AND GRAPH

In the introduction of this chapter, I would like to mention that in the recent past this chapter contributed 3-12 questions in some years. Basically on an average 4-5 questions are being asked from this chapter. Besides most of the questions are based on the user defined (or self defined) functions which are rather easier in comparison to the problems based on the algebraic functions of pure mathematics. Still you are required to know some basic characteristic and applications of standard algebraic functions since they are not uncommon in CAT. Remember that a little bit of practice on this chapter will give you an edge over your competitor since the problems related to this chapter are very easy provided that these problems are being solved patiently. Moreover, you need not to remember any formula at all.

The structure of the chapter is as follows :

1. Function (An introduction)
2. Domain, range and graphs of different types of functions and operations on real valued functions.
3. Transformation of graphs.
4. Composite functions
5. Even and odd functions
6. Surjective and injective functions
7. Inverse functions
8. Binary operations
9. User defined (or self defined) operations (Also important for XAT)
10. Maxima and minima.

FUNCTIONS

Suppose we have to produce some required products from the raw materials, then the raw material is known as input and the desired products are known as output. For this we have to look into two points.

1. Every input must give some output (to avoid wastage of inputs)
2. No input should give more than one output. (To avoid ambiguity or variation from the desired output)

Thus, if the above conditions are satisfied by any input output relation, then this relation is called function, *e.g.*,



Here you can see that each input gives an output necessarily and no input give more than one output.

The collection of raw materials (*i.e.*, input) is called the "Domain" and the collection of products (or output) is called the "Range".

Definitions

1. **Domain :** Set of inputs (also called pre-images) is called domain.
2. **Codomain :** Set of possible outputs is called codomain.
3. **Range :** Set of actual outputs (also called images) is known as range.

Here, Range $\subseteq$ Codomain.

Mathematical Definition of Function

Let A and B be two non-empty sets, then a function from 'A' to 'B' is a rule that assigns to each element in a set A, one and only one element of a set B.

In general, the sets A and B need not be sets of real numbers. However, we consider only those functions for which A and B are both subsets of the real numbers.

If the number of elements in A be n and the number of elements in B be m, then the total number of functions that can be defined from A to B is n^m.

$$A \xrightarrow{f} B \quad \text{or} \quad f : A \longrightarrow B$$

If a pre-image is denoted by x and an image is denoted by y then we can write.

$$y = f(x)$$

Here, $f(x)$ is called the value of the function f at the point x.

Remember : A function cannot be multiple-valued. For example, the expression $\pm\sqrt{x}$ does not define a function of x, since it assigns two values to each positive x.

i.e., $y = f(x)$

or $y = \pm\sqrt{x}$ is not a function since y assumes two values *i.e.*, $y = +\sqrt{x}$ and $y = -\sqrt{x}$, which is impossible.

Scanned by CamScanner

yoursmahboob.wordpress.com

Methods of Representation of a Function

1. Verbal description : For example, if f is a function which assigns to each state in the country its capital city.



2. Arrow diagram :



Domain = {1, 2, 3, 4, 5}

Codomain = {1, 2, 4, 9,16, 25}

Range = {1, 4, 9, 16, 25}

3. Tabular form :

e.g.,

x	-1	-2	-3	0	1	2
y	-1	-8	-27	0	1	8

$D = \{-1, -2, -3, 0, 1, 2\}$

$R = \{-1, -8, -27, 0, 1, 8\}$

$f(2) = 8, \quad f(-2) = -8$ etc.

4. Graph :



$D = [1, 4]$

$R = [1, 3] \cup (4, 5)$

5. Equation (or formula) :

$f : R \to R \quad f(x) = x^2 \ \forall \ x \in R$



$D = R$ (all real numbers),

Codomain = R (All real numbers)

(Range) $R = R^+ \cup \{0\}$

($R^+ \to$ set of positive real numbers)

DOMAIN & GRAPHS OF DIFFERENT TYPES OF FUNCTIONS

A function $f : A \to B$ is called a real valued if the image of every element of A, under f is a real number *i.e.*, if $f(x) \in R \ \forall \ x \in A$

$$y = f(x)$$

$x \to$ independent variable

$y \to$ dependent variable

Domain : The values of x must be such that for every x, y must be real is called the domain.

In other words the value of x for which the values of $f(x)$ is not a real number cannot be included in the domain of the function $y = f(x)$. There are five different common situations where the domain of $f(x)$ for some particular value(s) is not defined.

(a) When base of $(1/2n)^{th}$ power is negative for any $n \in I$:

If $x^{1/2} = k \Rightarrow x = k^2$ since k^2 is always positive even when x is negative, therefore this equality is not satisfied.

Hence the domain of definition of $y = \sqrt{x}$ is defined for only $x \geq 0$ *i.e.*, not defined for $x < 0$

EXAMPLES

Function	Domain defined for	Domain not defined for
$(x-3)^{1/2}$	$(x-3) \geq 0 \Rightarrow x \geq 3$	$(x-3) < 0 \Rightarrow x < 3$
$(x+4)^{1/6}$	$(x+4) \geq 0 \Rightarrow x \geq -4$	$(x+4) < 0 \Rightarrow x < -4$
$(\lvert x \rvert - 3)^{1/10}$	$\lvert x \rvert - 3 \geq 0 \Rightarrow \lvert x \rvert \geq 3$ $\Rightarrow x \leq -3$ and $x \geq 3$	$\lvert x \rvert - 3 < 0 \Rightarrow \lvert x \rvert < 3$ $\Rightarrow -3 < x < 3$

(b) When denominator of a function is zero : If $\frac{x^2+1}{2x}$ is such that $x = 0$, then $\frac{x^2+1}{2x}$ is not defined *i.e.*, the function $y = \frac{1}{x}$ is defined only for $x \neq 0$ (*i.e.*, non zero real numbers) therefore the domain of function $f(x) = \frac{1}{x}$ is $(-\infty, 0) \cup (0, \infty)$ or $(-\infty, \infty) - \{0\}$ or $-\infty < x < 0 \cup 0 < x < \infty$.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLES

Function	Domain defined for	Domain not defined for
$\frac{1}{(x-3)}$	$x \in (-\infty, \infty) - \{3\}$	$x = 3$
$\frac{19}{(x^2-16)}$	$x \in (-\infty, \infty) - \{\pm 4\}$	$x = \pm 4$
$\frac{(x^2+4)}{\lvert x\rvert - 5}$	$x \in (-\infty, \infty) - \{\pm 5\}$	$x = \pm 5$
$\frac{1}{(\log_e x) - 1}$	$x \in (0, \infty) - \{e\}$	$x = e$

(c) **When function becomes 0° :**
Example $y = (\lvert x\rvert - 3)^{(x-3)}$ is undefined for $x = 3$

(d) **When the value of x in $\log_a x$ becomes non-positive** (*i.e*, negative or zero)
$\therefore \log_{10}(-3)$ is not defined.

(e) **When the value of a in $\log_a x$ becomes 1 or 0 or negative.**
$\therefore \log_1 5$ is not defined.
Similarly, $\log_{(-3)} 10$ is not defined.

EXAMPLES

Function	Domain defined for	Domain not defined for
$\log_{10}(x-5)$	$(x-5) > 0 \Rightarrow x > 5$	$x - 5 \le 0 \Rightarrow x \le 5$
$\log_{15}(7-x)$	$(7-x) > 0 \Rightarrow x < 7$	$(7-x) \le 0 \Rightarrow x \ge 7$
$\log_{(x^2-4)} 12$	$(x^2-4) > 0$ and $x^2 - 4 \ne 1$ $\Rightarrow x < -2$ and $x^2 \ne 5$ and $x > 2$ and $x \ne \pm\sqrt{5}$ $\therefore x \in (-\infty, -2) \cup (2, \infty)$ excluding $\pm\sqrt{5}$	$x^2 - 4 \le 0$ and $x^2 - 4 = 1$ $\Rightarrow -2 \le x \le 2$ and $x^2 = 5$ and $x = \pm\sqrt{5}$ $\therefore x \in [-2, 2] \cup \{\pm\sqrt{5}\}$

Range : The set of all images of all the elements of domain. It can be obtained by one of the following ways.

(i) Obtaining x in terms of y and then finding the values of y for which we get real x.

e.g., $$f(x) = \frac{x+2}{x+3} = y$$

$$\Rightarrow \quad yx + 3y = x + 2$$
$$\Rightarrow \quad x(y-1) = (2-3y)$$
$$\Rightarrow \quad x = \frac{2-3y}{y-1}$$

for $y = 1$, there is no real value of x for the above equation is satisfied hence.

Range $= R - \{1\}$ $\quad R \to$ Set of real numbers

(ii) If the given function is continuous, then Range $= [l, m]$ where l is the least value of the function in its domain and m is the maximum value in its domain.

(iii) By sketching the graphs of the function.

Equal Function : Two functions f and g are said to be equal iff (*i.e.*, if and only if)

(i) the domain of f = domain of g
(ii) the co-domain of f = co-domain of g, and
(iii) $f(x) = g(x)$ for every x belong to their common domain.

If two functions f and g are equal then we write $f = g$, e.g.,

1. Let $A = \{1, 2\}$, $B = \{3, 6\}$ and $f : A \to B$ given by $f(x) = x^2 + 2$ and $g : A \to B$ given by $g(x) = 3x$. Then we observe that f and g have the same domain and co-domain also.

$$f(1) = 3 = g(1)$$
$$f(2) = 6 = g(2)$$

Hence $f = g$

2. Let $f(x) = \sqrt{\frac{x-3}{x-5}}$ and $g(x) = \frac{\sqrt{x-3}}{\sqrt{x-5}}$

$f(x)$ is defined when $x - 3$ and $x - 5$ both are negative since $\left(\frac{x-3}{x-5}\right) > 0$

But when $x - 3$ and $x - 5$ are negative then both $\sqrt{x-3}$ and $\sqrt{x-5}$ are undefined. Hence $g(x)$ is undefined

$\therefore$ Domain of $f \ne$ Domain of g

Hence $f(x)$ and $g(x)$ are different.



ALGEBRAIC FUNCTIONS

A function which contains finite number of terms having different powers of independent variable (x) and the operations $+, -, \times, \div$ is called algebraic function *e.g.*,

$$4x^2 - 3x^{1/2} + 7, \quad 5x^2 + 13x + 8, \quad \frac{x^2+1}{x^2-2} \text{ etc.}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

(A–1) Polynomial Functions : A function $f(x)$ of the following form is known as polynomial function.

$$f(x) = a_0 + a_1x + a_2x^2 + \ldots + a_nx^n$$

where $n \in N$ and $a_1, a_2, a_3 \ldots a_n \in R$

Domain : It is the set of real numbers

Range : It is the set of real numbers

(A–1.1) Constant function : $f(x) = c$, $c \in R$, c is constant.



Domain : It is the set of real numbers

Range : It is a particular real number $\{c\}$

(A–1.2) Identity function

$y = x$ *i.e.*, $f(x) = x$



(*i.e*, input equals to output or pre image equals to image)

Domain → It is the set of real numbers.

Range → It is also the set of real numbers.

(A–1.3) Linear function

$y = mx + c$ $(m, c \in R, m$ is positive)



Domain → It is the set of real numbers.

Range → It is also the set of real numbers.

(A–1.4.) Quadratic function

$y = f(x) = x^2$



$\because \quad f(x) = f(-x)$

$\therefore$ Graph of $f(x)$ is symmetric about y-axis.

Domain → It is the set of real values.

Range → $R^+ \cup \{0\}$ *i.e.*, non-negative real numbers

(A–1.5) Cubic equation



$$y = f(x) = x^3$$

$\because \quad f(-x) = -f(x)$

$\therefore$ Graph of $f(x)$ is symmetric about origin

Domain → R (set of real numbers)

Range → R (set of real numbers)

(A–1.6) Biquadratic function

$$y = f(x) = x^4$$

$\because \quad f(x) = f(-x)$

$\therefore$ Graph of $f(x)$ is symmetric about y-axis.

Domain → R (set of real numbers)

Range → $R^+ \cup \{0\}$ *i.e.*, set of non-negative real numbers.



NOTE Graph of $f(x) = x^n$ is symmetric about
(a) y-axis if n is even
(b) origin if n is odd

Relation between the values of $x, x^2, x^3 \ldots$etc.

For	Order of the values	
$x \in (0, 1)$	$x > x^2 > x^3 > x^4 \ldots$	
$x \in (1, \infty)$	$x < x^2 < x^3 < x^4 \ldots$	
$x \in (-1, 0)$	$x < x^3 < x^5 \ldots$	(–ve values)
	$x^2 > x^4 > x^6 \ldots$	(+ve values)
$x \in (-\infty, -1)$	$x > x^3 > x^5 \ldots$	(–ve values)
	$x^2 < x^4 < x^6 \ldots$	(+ve values)

(A–2) Rational Function

$$f : A \to R; \quad f(x) = \frac{P(x)}{Q(x)}$$

Here $P(x)$ and $Q(x)$ are polynomial functions and $A = \{x : x \in R$ such that $Q(x) \neq 0\}$

EXAMPLES

	Function	Domain
1.	$\dfrac{a_0 + a_1x + a_2x^2 + \ldots + a_nx^n}{P_0 + P_1x + P_2x^2 + \ldots + P_nx^n}$	Set of all the real numbers except the real roots of the equation $P_0 + P_1x + P_2x^2 + \ldots + P_nx^n$
2.	$\dfrac{x^2 + 5x + 8}{x^2 - 5x + 6}$	$R - \{2, 3\}$
3.	$\dfrac{1}{x^n}; n \in N$	$R - \{0\}$

Scanned by CamScanner

yoursmahboob.wordpress.com

Graphs of some Rational Functions

1. $y = f(x) = \frac{1}{x}$

$\Rightarrow \quad f(x) = -f(-x)$

Domain $\rightarrow R - \{0\}$; set of non-zero rational numbers

Range $\rightarrow R - \{0\}$; set of non-zero rational numbers



2. $y = f(x) = \frac{1}{x^2}$

$\Rightarrow \quad f(x) = f(-x)$



Domain $\rightarrow R - \{0\}$ *i.e.*, set of non-zero rational numbers

Range $\rightarrow R^+$ *i.e.*, set of positive rational numbers

3. $y = f(x) = \frac{1}{x^3}$

$f(-x) = -f(x)$

Domain $\rightarrow R - \{0\}$ *i.e.*, set of non-zero rational numbers

Range $\rightarrow R - \{0\}$ *i.e.*, set of non-zero rational numbers.



NOTE Graph of $f(x) = \frac{1}{x^n} (n \in N)$ is symmetric about

(a) y axis if n is even (b) origin if n is odd.

Relation between the values of $\frac{1}{x}, \frac{1}{x^2}, \frac{1}{x^3}, \frac{1}{x^4} \ldots$

For	The order of the values
$x \in (1, \infty)$	$\frac{1}{x} > \frac{1}{x^2} > \frac{1}{x^3} > \frac{1}{x^4} \ldots$
$x \in (0, 1)$	$\frac{1}{x} < \frac{1}{x^2} < \frac{1}{x^3} < \frac{1}{x^4} \ldots$
$x \in (-1, 0)$	$\frac{1}{x^2} < \frac{1}{x^4} < \frac{1}{x^6} \ldots$ (positive values) $\frac{1}{x} > \frac{1}{x^3} > \frac{1}{x^5} \ldots$ (negative values)
$x \in (-\infty, -1)$	$\frac{1}{x^2} > \frac{1}{x^4} > \frac{1}{x^6} \ldots$ (positive values) $\frac{1}{x} < \frac{1}{x^3} < \frac{1}{x^5} \ldots$ (negative values)

(A–3) Irrational Functions : The algebraic functions containing one or more terms having non-integral rational powers of x are called irrational functions. *e.g.*,

$y = 4x^2 + \sqrt{2x}$ then y is undefined if $x < 0$

$y = \sqrt{x}$ then y is undefined if $x < 0$

$y = \frac{5x^3 + 7x^2 + 3\sqrt{x}}{\sqrt{x+4}}$ then y is undefined if $x < 0$ and $\sqrt{x+4} \le 0$

These functions are not defined for $f(x) < 0$. They are also not-defined if the denominator is zero.

Graphs of some Simple Irrational Functions

1. $y = f(x) = x^{1/2}$ (*i.e.*, $\sqrt{x}$)

Domain $\rightarrow R^+ \cup \{0\}$ *i.e.*, set of non-negative real numbers.

Range $\rightarrow R^+ \cup \{0\}$ *i.e.*, set of non-negative real numbers



2. $y = f(x) = x^{1/3}$



Domain $\rightarrow$ (*i.e.*, set of real numbers)

Range $\rightarrow R$ (*i.e.*, set of real numbers)

3. $y = f(x) = x^{1/4}$



Domain $\rightarrow R^+ \cup \{0\}$ *i.e.*, set of non-negative real numbers

Range $\rightarrow R^+ \cup \{0\}$ *i.e.*, set of non-negative real numbers

Relation between the values of $x^{1/2}, x^{1/3}, x^{1/4} \ldots$

For	Order of the values
$x \in (1, \infty)$	$x^{1/2} > x^{1/3} > x^{1/4} > x^{1/5} > \ldots$
$x \in (0, 1)$	$x^{1/2} < x^{1/3} < x^{1/4} < x^{1/5} < \ldots$
$x \in (-1, 0)$	$x^{1/3} > x^{1/5} > x^{1/7} \ldots$
$x \in (-\infty, -1)$	$x^{1/3} < x^{1/5} < x^{1/7} \ldots$

(A–4) Piecewise Defined Functions

(A–4.1) Modulus function (or absolute-value function)

$$y = f(x) = |x| = \begin{cases} x \text{ if } x \ge 0 \\ -x \text{ if } x < 0 \end{cases}$$

$\because \quad f(-x) = f(x)$

Scanned by CamScanner

yoursmahboob.wordpress.com



$\therefore f(x)$ is symmetric about y-axis.
Domain $\to R$ (*i.e.*, set of real numbers)
Range $\to R \cup \{0\}$ (*i.e.*, set of non-negative real numbers)

(A–4.2) Signum function [Sgn (x)]

$$y = f(x) = \text{Sgn}(x) = \begin{cases} 1 \text{ if } x > 0 \\ 0 \text{ if } x = 0 \\ -1 \text{ if } x < 0 \end{cases}$$



Domain $\to R$
Range $\to \{-1, 0, 1\}$
o indicates that the points (0, 1) and (0, – 1) are not included in the graphs.
• indicates that the point (0, 0) is included in the graphs

(a) $\text{Sgn}(x) = \begin{cases} \dfrac{x}{|x|} \text{ if } x \neq 0 \\ 0 \text{ if } x = 0 \end{cases}$ (b) $\text{Sgn}(x) = \begin{cases} \dfrac{|x|}{x} \text{ if } x \neq 0 \\ 0 \text{ if } x = 0 \end{cases}$

(A–4.3) Greatest integer function

$y = [x]$ denotes the greatest integer less than or equal to x.

e.g.,
$$[2.3] = 2$$
$$[4.7] = 4$$
$$[5.2] = 5$$
$$[-8.3] = -9$$
$$[-13.2] = -14$$

i.e., $[n] = n$, if n is an integer
and $[x] = n$, if $n \leq x < n+1$
Any real number x can be expressed as
Integral part + Fractional part
i.e., $I + f$ where $0 \leq f < 1$
then $[x]$ gives the integral part of x.



Domain $\to R$ (Set of real numbers)
Range $\to I$ (Integral values) $\{\ldots -3, -2, -1, 0, 1, 2, 3, \ldots \text{etc.}\}$
(It is also called the step functions)

(A–4.4) Smallest (or least) integer function

The function whose value at any number x is the smallest integer greater than or equal to x is called the least integer function *e.g.*, if $y = f(x) = \{x\}$ = Smallest integer, greater than or equal to x.

then,
$$\{2.8\} = 3$$
$$\{7.5\} = 8$$
$$\{-3.6\} = -3$$
$$\{-7.4\} = -7$$

i..e, $\{n\} = n$, if n is an integer
and $\{x\} = n$, if $n < x \leq n+1$



Domain $\to R$ (Set of real numbers)
Range $\to I$ (Integral values) e.g., $\{-3, -2, -1, 0, 1, 2, 3$ etc.$\}$

TRANSCENDENTAL FUNCTION

A function which is not an algebraic function is called a transcendental function.

e.g., trigonometry, logarithmic and exponential function.

(T–1) Trigonometric Function :

(T–1.1) $y = f(x) = \sin x$



It is a periodic function with period 2π
Domain $\to R$ (Set of real numbers)
Range $\to [-1, 1]$ *i.e.*, $\{x \in R : -1 \leq x \leq 1\}$

(T–1.2) $y = f(x) = \cos x$



Period $= 2\pi$
Domain $\to R$ Range $\to [-1, 1]$

(T–1.3)



Scanned by CamScanner

yoursmahboob.wordpress.com

Period $= \pi$

Domain $\rightarrow R - \left\{(2n+1)\frac{\pi}{2},\ n \in I\right\}$

Range $\rightarrow R$ (Set of real numbers)

(T–1.4) $y = f(x) = \text{cosec } x$



Period $= 2\pi$

Domain $\rightarrow R - \{n\pi : n \in I\}$

Range $(-\infty, -1] \cup [1, \infty)$

(T–1.5) $y = f(x) = \sec x$



Period $= 2\pi$

Domain $\rightarrow R - \left\{(2n+1)\frac{\pi}{2} : n \in I\right\}$

Range $\rightarrow (-\infty, -1] \cup [1, \infty)$

(T–1.6) $y = f(x) = \cot x$



Period $= \pi$

Domain $\rightarrow \{n\pi : n \in I\}$

Range $\rightarrow R$ (set of real numbers)

(T–2.1) $y = \sin^{-1} x \Rightarrow x = \sin y \in [-1, 1]$

$\therefore$ Domain $= [-1, 1]$

(T–2.2) $y = \cos^{-1} x \Rightarrow x = \cos y \in [-1, 1]$

$\therefore$ Domain $= [-1, 1]$

(T–2.3) $y = \tan^{-1} x \Rightarrow x = \tan y \in R$

$\therefore$ Domain $= R$

(T–2.4) $y = \cot^{-1} x \Rightarrow x = \cot y \in R$

$\therefore$ Domain $= R$

(T–2.5) $y = \sec^{-1} x \Rightarrow x = \sec y \in (-\infty, -1] \cup [1, \infty)$

$\therefore$ Domain $= (-\infty, -1] \cup [1, \infty)$

(T–2.6) $y = \text{cosec}^{-1} x \Rightarrow x = \text{cosec } y \in (-\infty, -1] \cup [1, \infty)$

$\therefore$ Domain $= (-\infty, -1] \cup [1, \infty)$

(T–3) Exponential Function

$y = a^x$

(i) $y = a^x; a > 1$

Domain $\rightarrow R$

Range $\rightarrow R^+$



(ii) $y = a^x; 0 < a < 1$

Domain $\rightarrow R$

Range $\rightarrow R^+$



NOTE		
$0 < a < 1$	function is decreasing	i.e., $a^x > a^y$ if $x < y$
$a > 1$	function is increasing	i.e., $a^x < a^y$ if $x < y$

(iii) (a) $y = e^x$ and (b) $y = e^{|x|}$



Fig. (a) Fig. (b)

(a) Domain $\rightarrow R$ (b) Domain $\rightarrow R$

Range $\rightarrow R^+$ Range $\rightarrow R^+$

(T–4) Logarithmic Function







Scanned by CamScanner

yoursmahboob.wordpress.com

ALGEBRAIC OPERATIONS ON REAL VALUED FUNCTIONS

Addition : If f and g are two functions, then the sum of the functions $(f+g)(x) = f(x) + g(x)$ is defined only for those values of x for which both f and g are defined *i.e.*,

$x \in \text{Dom } f \cap \text{Dom } g$

$\therefore$ $\text{Dom } (f+g) = \text{Dom } f \cap \text{Dom } g$

Subtraction : If f and g are two functions, then the difference of the functions $(f-g)x = f(x) - g(x)$

Where $x \in \text{Dom } f \cap \text{Dom } g$

$\therefore$ $\text{Dom of } (f-g) = \text{Dom } f \cap \text{Dom } g$

Multiplication : If k is any real number and f is a function, then kf is defined for all $x \in \text{Dom } f$ by

$$(kf)\,x = k\,f(x)$$

Hence,

if f and g are two functions, then the pointwise product fg is defined for all $x \in \text{Dom } f \cap \text{Dom } g$ by $(fg)\,x = f(x)\,g(x)$

$\therefore$ $\text{Dom of } (fg)\,x = \text{Dom } f \cap \text{Dom } g$

Division : If f and g are two functions, then f/g is defined for all $x \in \text{Dom } f \cap \text{Dom } g \cap \{x : g(x) \neq 0\}$ by

$$(f/g)\,x = \frac{f(x)}{g(x)}$$

$\therefore \text{Dom } (f/g)\,x = \text{Dom } f \cap \text{Dom } g - \{x : x \in \text{Dom } g \text{ and } g(x) = 0\}$

Composition : Let $f : A \to B$ and $g : B \to C$ be functions,

then $gof : A \to C$ defined by

$$(gof)\,x = g\,(f(x))$$

Alternatively : $(gof(x)) = g\,f(x)$

i.e., gof is defined when

(a) input of f (*i.e.*, x) $\in$ Domain of f and

(b) input of g (i.e., $f(x) \in$ Domain of g

Note that gof is defined, then fog may not be defined

INTRODUCTORY EXERCISE-17.1

1. The domain of the function $f(x) = x$ is :
   (a) R (b) R^+
   (c) $R - \{0\}$ (d) $R^+ \cup \{0\}$
2. The domain of the function $f(x) = \sqrt{x}$ is :
   (a) R (b) R^+
   (c) $R^+ \cup \{0\}$ (d) $R - \{0\}$
3. The domain of the function $f(x) = \frac{1}{x}$ is :
   (a) R (b) R^+
   (c) $R - \{0\}$ (d) $R^+ \cup \{0\}$
4. The domain of the function $f(x) = |x|$ is :
   (a) R (b) R^+
   (c) $R - \{0\}$ (d) $R^+ \cup \{0\}$
5. The domain of the function $f(x) = \sqrt{|x|}$ is :
   (a) $x \in (-\infty, \infty)$ (b) $x \in (0, \infty)$
   (c) $x \in (-\infty, 0) \cup (0, \infty)$ (d) $x \in [0, \infty)$
6. The domain of the function $f(x) = |\sqrt{x}|$ is :
   (a) $x \in (-\infty, +\infty)$ (b) $x \in (0, \infty)$
   (c) $x \in (9, 16)$ (d) $x \in [0, \infty)$
7. The domain of the function $f(x) = \frac{1}{\sqrt{x}}$ is :
   (a) $-\infty < x < \infty$ (b) $0 < x < \infty$
   (c) $R - \{0\}$ (d) $0 \le x < \infty$
8. The domain of the function $f(x) = \sqrt{x^2}$ is :
   (a) $-\infty < x < \infty$ (b) $0 < x < \infty$
   (c) $R - \{0\}$ (d) $R^+ \cup \{0\}$
9. The domain of the function $f(x) = (\sqrt{x})^2$ is :
   (a) $-\infty < x < \infty$ (b) $0 < x < \infty$
   (c) $0 \le x < \infty$ (d) none of these
10. The domain of the function $f(x) = \log_{10} x$ is :
    (a) $-\infty < x < \infty$ (b) $0 < x < \infty$
    (c) $0 \le x < \infty$ (d) none of these
11. The domain of the function $f(x) = \log x^2$ is :
    (a) R (b) R^+
    (c) $R - \{0\}$ (d) $R^+ \cup \{0\}$
12. The domain of the function $f(x) = \frac{1}{\log_{10} x}$ is :
    (a) R (b) $R^+ - \{1\}$
    (c) $R^* \cup \{0\}$ (d) $R - \{0\}$
13. The domain of the function $f(x) = \frac{1}{\sqrt{\log_{10} x}}$ is
    (a) R (b) $R^+ - (0, 1]$
    (c) $R - \{0\}$ (d) none of these
14. The domain of the function $f(x) = \sqrt{3x-4}$ is :
    (a) $[0, \infty)$ (b) $\left[\frac{3}{4}, \infty\right)$
    (c) $\left[\frac{4}{3}, \infty\right)$ (d) $(4, \infty)$
15. The domain of the function $f(x) = \sqrt{4x-3} + \sqrt{2x-6}$ is :
    (a) $[0, \infty)$ (b) $\left[\frac{3}{4}, \infty\right)$
    (c) $\left[\frac{4}{3}, \infty\right)$ (d) $[3, \infty)$
16. The domain of $y = \frac{1}{\sqrt{|x| - x}}$ is :
    (a) $[0, \infty)$ (b) $(0, \infty)$
    (c) $(-\infty, 0)$ (d) $(-\infty, 0]$
17. The domain of $y = \frac{x}{\sqrt{x^2 - 3x + 2}}$
    (a) $(-\infty, \infty)$ (b) $[0, \infty)$
    (c) $(-\infty, 1] \cup [2, \infty)$ (d) none of these
18. The domain of $y = \log_{10}(\sqrt{6-x} + \sqrt{x-4})$ is :
    (a) R (b) $R - \{0\}$
    (c) $[6, \infty)$ (d) $(4, 6)$

Scanned by CamScanner

yourshahbaab.wordpress.com

19. The domain of definition of the function $y = \frac{1}{\log_{10}(1-x)} + \sqrt{x+2}$ is :

(a) $[-2, 1)$ (b) $[-2, 0)$
(c) $[-2, 0) \cup (0, 1)$ (d) $(-2, 1]$

20. The domain of definition of $f(x) = \frac{\log_2(x+3)}{x^2+3x+2}$ is :

(a) $(-3, -2)$ (b) $(-2, -1]$
(c) $(-3, \infty) \sim \{-1, -2\}$ (d) $[0, \infty)$

21. The domain of $f(x) = 2\sin x + 3\cos x + 4$ is :

(a) R (b) R^+
(c) $R - \{0\}$ (d) $R - \{n\pi : n \in I^+\}$

22. The domain of the function $y = \sqrt{\log \frac{1}{|\sin x|}}$ is :

(a) R (b) $R \sim \left(\frac{n}{2}\pi; n \in I\right)$
(c) $[0, \infty)$ (d) $R \sim \{n\pi, n \in I\}$

23. The domain of $f(x) = (x^2 + x + 1)^{-3/2}$ is :

(a) $(-\infty, \infty)$ (b) $(0, \infty)$
(c) $\left(\frac{3}{2}, \infty\right)$ (d) none of these

24. The domain of $f(x) = \log(5x - 6 - x^2)$ is :

(a) $(5, 6)$ (b) $(2, 3)$
(c) $[2, \infty)$ (d) none of these

25. The domain of $y = \log_x 5$ is :

(a) $x > 5$ (b) $(0, \infty)$
(c) $(0, \infty) \sim \{1\}$ (d) $[5, \infty)$

26. The domain of $y = 9 - \sqrt{9 - x^2}$ is :

(a) $x < -3$ (b) $-3 < x < 3$
(c) $x \in [-3, 3]$ (d) none of these

27. The domain of $y = \frac{x}{\sqrt{x^2 - 5x + 6}}$ is :

(a) $R \sim \{2, 3\}$ (b) $R \sim (2, 3)$
(c) $R - [2, 3]$ (d) none of these

28. The range of the function $y = \frac{x^2}{1+x^4}$ is :

(a) $[0, \infty)$ (b) $[0, 2]$
(c) $\left(0, \frac{1}{2}\right)$ (d) $\left[0, \frac{1}{2}\right]$

29. Find the range of $f(x) = \frac{x^2 - 2}{x^2 - 3}$:

(a) $(1, \infty)$ (b) $(-\infty, 2/3]$
(c) $(-\infty, 2/3)$ (d) $(-\infty, 2/3] \cup (1, \infty)$

30. If $f(x) = \frac{x^2 + 2x + 3}{x}$, then the range of the function is :

(a) $[2\sqrt{3}, 3\sqrt{2}]$ (b) $R - (2 - 2\sqrt{3}, 2 + 2\sqrt{3})$
(c) $R - (2, 2\sqrt{3})$ (d) none of these

31. Which of the following pairs are identical :

(a) $f(x) = \sqrt{x^2}$, $g(x) = (\sqrt{x})^2$

(b) $f(x) = \frac{1}{\sqrt{x^2}}$, $g(x) = \frac{x}{x^2}$

(c) $f(x) = \log(x-1) + \log(x-2)$, $g(x) = \log(x-1)(x-2)$

(d) none of the above

32. If $f(x) = \frac{1}{\sqrt{|x| - x}}$ and $g(x) = \frac{1}{\sqrt{x - |x|}}$, then :

(a) dom $f \neq \phi$ and dom $g = \phi$
(b) dom $f = \phi$ and dom $g \neq \phi$
(c) dom $f = \phi$ and dom $g = \phi$
(d) f and g have the same domain

33. If $f(x) = x$, $g(x) = \sqrt{x^2}$ and $h(x) = \frac{x^2}{x}$, then the set of values for which the given functions $f(x)$, $g(x)$ and $h(x)$ are identical is :

(a) $R - \{0\}$ (b) R
(c) R^+ (d) $R^+ \cup \{0\}$

34. If $f(x) = \log x^4$ and $g(x) = 4\log x$ then the domain for which $f(x)$ and $g(x)$ are identical ?

(a) $(-\infty, \infty)$ (b) $[0, \infty)$
(c) $(0, \infty)$ (d) none of these

35. If $f(x) = \text{Sgn } x$ and $g(x) = 1 + x - [x]$. Then for all x, $f(g(x))$ is equal to :

(a) 0 (b) 1
(c) x (d) $f(x)$

36. If $f(x) = 64x^3 + \frac{1}{x^3}$ and α, β are the roots of $4x + \frac{1}{x} = 2$ then :

(a) $f(\alpha) = -24$ (b) $f(\alpha) = -16$
(c) $f(\beta) = -16$ (d) both (b) and (c)

37. If $f(x) = \frac{x}{\sqrt{1+x^2}}$, then $f(f(f(x)))$ is :

(a) $\frac{3x}{\sqrt{1+x^2}}$ (b) $\frac{x}{\sqrt{1+3x^2}}$
(c) $\frac{x^3}{\sqrt{1+x^2}}$ (d) $\frac{x}{\sqrt{3+3x^2}}$

38. If $f(x) = \frac{4^x}{4^x + 2}$, then the value of $f(x) + f(1-x)$ is :

(a) 0 (b) -1
(c) 1 (d) can't be determined

39. If $f(x) = 1 - f(1-x)$, then the value of $f\left(\frac{1}{999}\right) + f\left(\frac{2}{999}\right) + \ldots + f\left(\frac{998}{999}\right)$ is :

(a) 998 (b) 1
(c) 499 (d) none of these

40. Let $f(x) = x^2$ and $g(x) = \sqrt{x}$, then :

(a) gof (3) = 9 (b) gof $(-3) = 9$
(c) gof (3) = 3 (d) gof $(-9) = 3$

41. If $g(x) = x^2 - x + 7$ and $\left(\frac{1}{9}\right)$ $gof(x) = x^2 + x + 1$ then $f(x)$ is :

(a) $2x - 3$ (b) $3x + 2$
(c) $3x - 2$ (d) none of these

42. Let $f(x) = \frac{x}{x+3}$, then $f(x+1) = ?$

(a) $\frac{3x+2}{x+2}$ (b) $\frac{x+1}{x+4}$
(c) $\frac{x+1}{x+3}$ (d) $\frac{2x+3}{x+3}$

Scanned by CamScanner

yoursmanboob.wordpress.com

43. Let $f(x)=\frac{x}{x+3}$, then $\frac{1}{f(x+1)}-f\left(\frac{1}{x+1}\right)=?$

(a) $\frac{3x^2+7x+4}{3(x^2+5x+5)}$ (b) $\frac{3(x^2+5x+5)}{3x^2+7x+4}$

(c) $\frac{-x(2x+3)}{(x+3)^2}$ (d) $\frac{-(x+3)^2}{x(2x+3)}$

44. If $f(x)=\frac{x+1}{x-1}, x\neq 1$, find $f(f(f(f(f(2)))))$

(a) 2 (b) 3

(c) 4 (d) 6

TRANSFORMATION OF GRAPHS

Here we study some techniques for the following transformation.

1. $f(x)\to f(x)+k$ 2. $f(x)\to f(x)-k$

3. $f(x)\to k\,f(x)$ 4. $f(x)\to\frac{1}{k}f(x)$

5. $f(x)\to -f(x)$ 6. $f(x)\to|f(x)|$

7. $f(x)\to f(x+k)$ 8. $f(x)\to f(x-k)$

9. $f(x)\to f(kx)$ 10. $f(x)\to f\left(\frac{x}{k}\right)$

11. $f(x)\to f(-x)$ 12. $f(x)\to f|x|$

1. $f(x)\to f(x)+k$, k is a positive constant.

Shift the graph of $f(x)$ upwards by 'k'.



$f(x)=|x|$



$f(x)=|x|+2$

2. $f(x)\to f(x)-k$; k is a positive constant



$f(x)=|x|$



$f(x)=|x|-2$

3. $f(x)\to kf(x)$; $(k>1)$

stretch the graph of $f(x)$, 'k' times along y-axis.





4. $f(x)\to\frac{1}{k}f(x)$; $(k>1)$

shrink the graph of $f(x)$ 'k' times along y-axis.



Scanned by CamScanner

yourshabbooh.wordpress.com



5. $f(x) \to -f(x)$

Turn the graph of $f(x)$ by 180° about x-axis.

or Take the mirror image of $f(x)$ in x-axis.





6. $f(x) = |f(x)|$,

where $|f(x)| = \begin{cases} f(x) \text{ if } f(x) \geq 0 \\ -f(x) \text{ if } f(x) < 0 \end{cases}$



Turn the portion of the graph of $f(x)$ lying below x-axis by 180° about x-axis.

or, Take the mirror image (in x-axis) of the portion of the graph of $f(x)$ which lies below x-axis.



7. $f(x) \to f(x+k)$

Shift the graph of $f(x)$ towards left by 'k'.





8. $f(x) \to f(x-k)$

Shift the graph of $f(x)$ towards right by 'k'



Scanned by CamScanner

yoursmahboob.wordpress.com



$f(x) = |x-2|$

9. $f(x) \to f(kx)\,;(k>1)$

Shrink the graph of $f(x)$ 'k' times along x-axis.



$f(x) = \sin x$



$f(x) = \sin 2x$

10. $f(x) \to f\left(\dfrac{x}{k}\right)$

Stretch the graph of $f(x)$ 'k' times along x-axis.



$f(x) = \sin x$



11. $f(x) \to f(-x)$

Turn the graph of $f(x)$ by 180° about y-axis.

or Take the mirror image of the graph of $f(x)$ in y-axis.



$f(x) = \sin(x)$



$f(x) = \sin(-x)$

12. $f(x) \to f|x|$

$\because \quad f|x| = \begin{cases} f(x) \text{ if } x \geq 0 \\ f(-x) \text{ if } x < 0 \end{cases}$

$\therefore$ On the right of y-axis, plot the graph of $f(x)$ as such and on the left of y-axis, plot the mirror image of the graph of $f(x)$ of the portion lying on the right of y-axis.



$f(x) = \sin|x|$



$f(x) = \sin|x|$

COMPOSITE FUNCTIONS



When the output of the first operation is the input for the second operation, then there is a composition of functions (operations).

If $f : A \to B$ and $g : B \to C$, then

$(gof) : A \to C$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow \quad (gof)(a) = g\{f(a)\}$

Example 1.



$(gof)(a) = g\{f(a)\} = g(q) = x$

$(gof)(b) = g\{f(b)\} = g(p) = y$

$(gof)(c) = g\{f(c)\} = g(p) = y$

Properties

1. **Associative :** If $f_1 : A \to B, f_2 : B \to C, f_3 : C \to D$ then $f_1 o(f_2 o f_3) = (f_1 o f_2) o f_3$
2. **Not commutative :** Let $f(x) = \cos x$ and $g(x) = x^3$ then, $gof(x) = g(f(x)) = g(\cos x) = \cos^3 x$ and $fog(x) = f(x^3) = \cos x^3$ Hence $gof \neq fog$
3. Range of (gof) may not be the same as the range of g

$(gof)(a) = x$

$(gof)(b) = y$

$(gof)(c) = y$

$\therefore$ Range of $(gof) = \{x, y\}$

and Range of $g = \{x, y, z\}$

EVEN AND ODD FUNCTIONS

1. **Even function :** A function $y = f(x)$ is said to be an even function if $f(-x) = f(x) \; \forall \, x \in \text{Dom}(f)$

   e.g., $y = \cos x, \; y = x^{2n} \; \forall \, n \in N, \; y = |x|$







NOTE Graph of an even function is symmetric about y-axis.

2. **Odd function :** A function $y = f(x)$ is said to be an odd function if $f(-x) = -f(x), \quad \forall \, x \in \text{Dom}(f)$

   e.g., $y = \sin x, \quad y = x^{2n-1} \; \forall \, n \in N$







NOTE Graph of an odd function is symmetric about origin.

Scanned by CamScanner

yoursmahboob.wordpress.com

Properties of even and odd functions

1. Sum : Even + Even = Even
Odd + Odd = Odd
Even + Odd = (neither even nor odd)
Odd + Even = (neither even nor odd)

2. Difference : Even − Even = Even
Odd − Odd = Odd
Even − Odd = (neither even nor odd)
Odd − Even = (neither even nor odd)

Remember : Any function $y = f(x)$ can be expressed uniquely as the sum of an even and an odd function as follows :

$$f(x) = \frac{1}{2}[f(x) + f(-x)] + \frac{1}{2}[f(x) - f(-x)]$$

3. Product: Even × Even = Even
Odd × Odd = Even
Even × Odd = Odd
Odd × Even = Odd

NOTE If the number of odd functions in the product is odd → odd function.
If the number of odd functions in the product is even → even function

4. Division : Even ÷ Even = Even
Odd ÷ Odd = Even
Even ÷ Odd = Odd
Odd ÷ Even = Odd

5. Composition : Even (Even) = Even
Even (Odd) = Even
Odd (Even) = Even
Odd (Odd) = Odd

NOTE If all the functions in the composition are odd → Odd function
If at least one of the functions in the composition is even → even function.

INTRODUCTORY EXERCISE-1.2

1. Which one of the following is correct for the following graph?



(a) $f(x) = \{x\}$ (b) $f(x) = [x]$
(c) $f(x) = |[x]|$ (d) none of these

2. Which one of the following is correct for the following graph?



(a) $f(x) = \left|\left|\frac{1}{x}\right| - 2\right|$ (b) $f(x) = \left(\frac{1}{x}\right)^2$
(c) $f(x) = \left|\frac{1}{x^3}\right|$ (d) $f(x) = \log|x|$

3. Which one of the following is correct for the following graph?



(a) $f(x) = e^x$ (b) $f(x) = \log|x|$
(c) $f(x) = 2^{|x|}$ (d) $f(x) = x^2$

4. Which one of the following is correct for the given graph?



(a) $f(x) = |x^3 - 2|$ (b) $f(x) = x^2 - 2$
(c) $f(x) = \left|\frac{x^3}{4}\right| - 2$ (d) $f(x) = \log|x - 1|$

Scanned by CamScanner

yourshahbood.wordpress.com

5. The equation $\frac{x^2}{1-|x-2|}=1$ has n real solutions, then :

(a) $n=0$ (b) $n=1$
(c) $n=2$ (d) $n=3$

6. The number of real solutions of the equation $\log_{0.5}|x|=2|x|$ is :

(a) 0 (b) 1
(c) 2 (d) none of these

7. The graph of the function $f: R \to R$ defined by $f(x)=\frac{|x|^3+|x|}{1+x^2}$ may lie in :

(a) Ist and IInd quadrant
(b) IInd and IIIrd quadrant
(c) IIIrd and IVrd quadrant
(d) none of these

8. The two roots of the equation $f(x)=f\left(\frac{x+8}{x-1}\right)$ are :

(a) $2,-2$ (b) $4,-2$
(c) $-4,-2$ (d) $2,4$

9. If the functions f, g, h are defined from 'R' to 'R' by $f(x)=x^2-1$, $g(x)=\sqrt{x^2+1}$, $h(x)=\begin{cases}0, & \text{if } x\le 0\\ x, & \text{if } x\ge 0\end{cases}$ then $hofog$ is equal to :

(a) x^2 (b) $\sqrt{x^4-1}$
(c) 0 (d) none of these

10. If $f(x)=(a-x^n)^{1/n}$, where $a>0$, then $f(f(x))$ is :

(a) x^n (b) x^2
(c) $2x$ (d) none of these

11. If $f(x)=\left(\frac{x-1}{x+1}\right)$, then $f(f(ax))$ in terms of $f(x)$ is equal to :

(a) $\frac{f(x)+1}{a(f(x)+1)}$ (b) $\frac{f(x)+1}{a(f(x)-1)}$
(c) $\frac{f(x)-1}{a(f(x)+1)}$ (d) $\frac{f(x)+1}{a(f(x)-1)}$

12. If $f(x)=\frac{x}{\sqrt{1+x^2}}$, then $fofof(x)$ is equal to :

(a) $\frac{x}{\sqrt{(1+3x^2)}}$ (b) $\frac{3x}{\sqrt{(1-x^2)}}$
(c) $\frac{3x}{\sqrt{(1+x^2)}}$ (d) none of these

13. If $f(x)=\begin{cases}1+|x|; & x<-1\\ [x]; & x\ge -1\end{cases}$ Also, [.] is greatest integer function then $f(f(-2.4))$ is equal to :

(a) -3 (b) 2
(c) 3 (d) 4

14. If $f(x)=x^n$, $n\in N$ and $(gof)(x)=ng(x)$, then $g(x)$ can be :

(a) $n|x|$ (b) $\sqrt[3]{x}$
(c) e^x (d) $\log x$

15. Let $f: N \to R$; $f(x)=2x-1$
$g: z \to R$; $g(x)=\frac{x^2}{2}$, then $(gof)(0)$ is :

(a) $-\frac{1}{2}$ (b) $\frac{1}{2}$
(c) 1 (d) none of these

16. Let $f\left(x+\frac{1}{x}\right)=x^2+\frac{1}{x^2}$; $(x\neq 0)$, then $f(x)$ is equal to :

(a) x^2-1 (b) x^2-2
(c) x^2 (d) none of these

17. Let $f(x)=\sqrt{x^5}$, then $f(5x)$ is equal to :

(a) $5x\sqrt{5x}$ (b) $25x^2\sqrt{5x}$
(c) $5x$ (d) $\sqrt{5x^5}$

18. If $f(x)=4x-5$, $g(x)=x^2$ and $h(x)=\frac{1}{x}$, then $f(g(h(x)))$ is :

(a) $\frac{4}{(x-5)}$ (b) $\frac{1}{(4x-5)^2}$
(c) $\left(\frac{x}{4}-5\right)$ (d) $\left(\frac{4}{x^2}-5\right)$

19. If $[x]$ is greatest integer function (GIF) and $\{x\}$ is smallest integer function (SIF), and $x\in R-I$, then $[x]-\{x\}$ is equal to :

(a) -1 (b) 0
(c) 1 (d) 2

20. If the graph of the function $f(x)=\frac{a^x-1}{x^n(a^x+1)}$ is symmetric about y-axis, then n is equal to :

(a) $-\frac{1}{3}$ (b) $\frac{1}{4}$
(c) 2/3 (d) 2

21. $f(x)=\ln(x+\sqrt{x^2+1})$ is :

(a) an even function (b) an odd function
(c) neither even nor odd (d) none of these

22. If a function f satisfies the condition $f(x+y)=f(x)+f(y)\forall x, y\in R$, then f is :

(a) an even function (b) an odd function
(c) neither even nor odd (d) none of these

23. Which of the following function is an even function?

(a) $f(x)=\frac{a^x+1}{a^x-1}$ (b) $f(x)=\frac{a^x-a^{-x}}{a^x+a^{-x}}$
(c) $f(x)=x\frac{a^x+1}{a^x-1}$ (d) $f(x)=\sin x$

24. Which of the following function is odd ?

(a) $\ln\left(\frac{1+x^3}{1-x^3}\right)$ (b) $x\cdot\frac{e^{ax}-1}{e^{ax}+1}$
(c) $\frac{(1+2^x)^2}{2^x}$ (d) none of these

25. Which of the following function is even function ?

(a) $f(x)=\log\frac{1-x}{1+x}$
(b) $f(x)=x\cdot\frac{a^x+1}{a^x-1}$
(c) $f(x)=\log\left[x+\sqrt{(1+x^2)}\right]$
(d) $f(x)=\sqrt{(1+x+x^2)}-\sqrt{(1-x+x^2)}$

Scanned by CamScanner

yoursmartbook.wordpress.com

26. If $f(x) = \sqrt[3]{(1-x^2)} + \sqrt[3]{(1+x^2)}$, then $f(x)$ is:
(a) an even function
(b) an odd function
(c) constant function
(d) none of these

27. Which of the following function is an odd function ?
(a) $f(x) = 2^{-x^2}$ (b) $f(x) = 2^{x-x^4}$
(c) $f(x) = \cos x$ (d) none of these

28. The function $f(x) = \frac{x}{e^x - 1} + \frac{x}{2} + 1$ is :
(a) even (b) odd
(c) constant (d) neither even nor odd

29. The graph of the function $y = f(x)$ is symmetrical about the line $x = 2$, then :
(a) $f(x+2) = f(x-2)$ (b) $f(2+x) = f(2-x)$
(c) $f(x) = f(-x)$ (d) none of these

30. Given $f(x) = \frac{1}{(1-x)}$, $g(x) = f(f(x))$ and $h(x) = f(f(f(x)))$, then the value of $f(x) \cdot g(x) \cdot h(x)$ is :
(a) 0 (b) -1
(c) 1 (d) 2

SURJECTIVE AND INJECTIVE FUNCTIONS



One to One (or Injective) Function

A function f is said to be one-to-one if it does not take the same values at two distinct points in its domain. For example, $f(x) = x^3$ is one to one whereas $f(x) = x^2$ is not, as $f(1) = 1$ and $f(-1) = 1$

In order to show that a function $f : A \to B$ is one-one we may take any $x, y \to A$ such that $f(x) = f(y)$ and try to show that $x = y$.

Graphically, if every horizontal line intersects the graph of a given function at not more than one point, *i.e.*, the function is strictly increasing (or decreasing) then the function is one-one.

NOTE 1. Functions which are not one to one are called many-one function.
2. One many function does not exist.

Onto (or Surjective Function)

If a function $f : A \to B$ is such that each element in B is the f-image of at least one element in A, then we say that f is function of A 'onto' B. Equivalently a function f is an onto function if codomain of f = Range of f.

In order to show that a function $f : A \to B$ is onto we start with any $y \in B$ and try to find $x \in A$ such that $f(x) = y$.

NOTE If there exists at least one element in B which is not the f-image of any element of A, then f is called an into function.

Bijective Function : If a function f is both one-to-one and onto then f is said to be a bijective function *e.g.*, an identity function is a bijective function.

INVERSE FUNCTION

Inverse of a function : If $f : A \to B$ is a bijection, we can define a new function from B to A which associates each element $y \in B$ to its pre-image $f^{-1}(y) \in A$. Such a function is known as the inverse of function f and is denoted by f^{-1}.

- Inverse of a function is defined iff the function is one-to-one and onto.
- In the inverse function inputs and outpts interchange their roles.
- Inverse of a function is not defined if the given function is a many-one function or into function or both.
- If the graph of a function $f(x)$ is symmetric about the line $y = x$, then $f(x)$ and $f^{-1}(x)$ are identical function.
- The graph of $f(x)$ and $f^{-1}(x)$ is symmetric about $y = x$.

BINARY OPERATIONS

Binary Operation : Let S be a non-emply set. A function f from $S \times S$ to S is called a binary operation on S *i.e.*, $f : S \times S \to S$ is a binary operation on S.

Generally binary operations are represented by the symbols $*$, $\oplus$ etc. instead of letters f, g etc.

Types of Binary Operation :

1. **Commutative binary operation :** A binary operation $*$ on a set S is said to be commutative if $a * b = b * a$ for all $a, b, \in S$.
2. **Associative binary operation :** A binary operation $*$ on a set S is said to be associative if
$(a * b) * c = a * (b * c)$ for all $a, b, c \in S$.
3. **Distributive binary operation :** Let $*$ and $\oplus$ be two binary operations on a set S. Then $*$ is said to be :

Scanned by CamScanner

yoursmahboob.wordpress.com

(i) Left distributive over $\oplus$ if
$a * (b \oplus c) = (a * b) \oplus (a * c)$ for all $a, b, c \in S$,

(ii) Right distributive over $\oplus$ if
$(b \oplus c) * a = (b * a) \oplus (c * a)$ for all $a, b, c \in S$.

If $*$ is both left and right distributive over $\oplus$, then $*$ is said to be distributive over $\oplus$.

Composition table : Le $S = \{a_1, a_2, a_3, \ldots a_n\}$ be finite set and $*$ be a binary operation on S. Then the composition table is constructed in the manner given below:

$*$	a_1	a_2	...	a_i	...	a_j	...	a_n
a_1	$a_1 * a_1$	$a_1 * a_2$	...	$a_1 * a_i$	...	$a_1 * a_j$	...	$a_1 * a_n$
a_2	$a_2 * a_1$	$a_2 * a_2$	...	$a_2 * a_i$	...	$a_2 * a_j$	...	$a_2 * a_n$
...								
a_i	$a_i * a_1$	$a_i * a_2$	...	$a_i * a_i$	...	$a_i * a_j$	...	$a_i * a_n$
...			...					
a_j	$a_j * a_1$	$a_j * a_2$	...	$a_j * a_i$	...	$a_j * a_j$	...	$a_j * a_n$
a_n	$a_n * a_1$	$a_n * a_2$	...	$a_n * a_i$	...	$a_n * a_j$	...	$a_n * a_n$

Example : Consider the set $S = \{1, 2, 3, 4\}$. Define a binary operation $*$ on S as follows :

For any $a, b \in S$ define $a * b = r$, where 'r' is the least non-negative remainder when ab is divided by 5.

Solution We have

$1*1=1, 1*2=2, 1*3=3, 1*4=4$

$2*1=2, 2*2=4, 2*3=1, 2*4=3$

$3*1=3, 3*2=1, 3*3=4, 3*4=2$

$4*1=4, 4*2=3, 4*3=2, 4*4=1$

Thus the following is the composition table for the binary operation $*$ on S.

$*$	1	2	3	4
1	1	2	3	4
2	2	4	1	3
3	3	1	4	2
4	4	3	2	1

USER DEFINED FUNCTIONS

These functions are defined as per the requirement of user. Basically these functions are not standard function. There are some examples illustrated below :

EXAMPLE 1 *If* $f(A, B) = A \# B = A^4 - B^3 + A^2 - B + AB$, *then find the value of* $f(3, 4)$

SOLUTION $f(3, 4) = 3 \# 4 = 3^4 - 4^3 + 3^2 - 4 + (3 \times 4)$
$= 81 - 64 + 9 - 4 + 12 = 34$

EXAMPLE 2 *If* $A \# B = A + B + AB$. *If for any* A *there is a number* C *such that* $A \# C = A$, *then* $C = ?$

SOLUTION $A \# C = A$, we get

$A + C + AC = A$

$\Rightarrow \quad C(1 + A) = 0$

$\Rightarrow \quad C = 0 \quad \text{or} \quad A = -1$

EXAMPLE 3 *If*

$$f(a, b) = \frac{a+b}{2}$$

$g(a, b) = a^2 + b^2$

$h(a, b) = \max(a, b)$

Find the value of $f(g(3, 9), h(-1, 1))$.

SOLUTION $f(g(3, 9), h(-1, 1)) = f((3^2 + 9^2), 1) = f(90, 1) = 45.5$

EXAMPLE 4

$$f_n = \begin{cases} f_{n-1} \text{ if } n \text{ is even} \\ 2f_{n-1} \text{ if } n \text{ is odd} \end{cases}$$

and $f_0 = 1$, *find the value of* $f_4 + f_5$

SOLUTION $f_4 + f_5 = f_3 + 2f_4 = 2f_2 + 2f_3$
$= 2(f_2 + f_3)$
$= 2(f_1 + 2f_2)$
$= 2(2f_0 + 2f_1)$
$= 4(f_0 + f_1)$
$= 4(1 + 2f_0)$
$= 4(1 + 2) = 12$

EXAMPLE 5

$$f_n = \begin{cases} f_{n-1} \text{ if } n \text{ is even} \\ 2f_{n-1} \text{ if } n \text{ is odd} \end{cases}$$

and $f_0 = 1$, *find the value of* f_{16}.

SOLUTION $f_{16} = f_{15} = 2f_{14} = 2f_{13} = 2^2 f_{12}$
$= 2^2 f_{11} = 2^3 f_{10} = \ldots\ldots$
$f_{16} = 2^8 f_0 = 2^8 = 256$

EXAMPLE 6 *If* $f(n)$ *defines the number of pages read by a person in* n*th hour, where* $f(n) = \{\sqrt{n}\}$; $\{x\} \to$ *least integer greater than or equal to* x *and* n *is the* n^{th} *hour. If a person reads the book for 10 hours, then find the total number of pages read by him.*

SOLUTION Total number of pages read by him
$= f_1 + f_2 + f_3 + \ldots + f_{10}$
$f_1 = \{\sqrt{1}\} = \{1\} = 1$

Scanned by CamScanner

yoursmahboob.wordpress.com

$f_2 = \{\sqrt{2}\} = \{1.414\} = 2$
$f_3 = \{\sqrt{3}\} = \{1.732\} = 2$
$f_4 = \{\sqrt{4}\} = 2$
$f_5 = \{\sqrt{5}\} = 3$
$f_6 = \{\sqrt{6}\} = 3$
$f_7 = \{\sqrt{7}\} = 3$
$f_8 = \{\sqrt{8}\} = 3$
$f_9 = \{\sqrt{9}\} = 3$
$f_{10} = \{\sqrt{10}\} = 4$

$\therefore$ Total number of pages read by a person
$= 1 + 2 + 2 + 2 + 3 + 3 + 3 + 3 + 3 + 4$
$= 26$ pages

MAXIMA AND MINIMA

In this topic we study the maximum and minimum value of various functions. In advance mathematics, we find the maxima and minima through differentiation of the function (As in calculus). But for those students who are not well-versed with calculus, they can solve these problems with some unconventional methods.

Recall that we have been already studied the maxima and minima in the chapter "Theory of Equations."

EXAMPLE 1 *What is the minimum value of the expression* $x^2 + 8x + 10$ *?*

SOLUTION **Method 1.** $x^2 + 8x + 10 = x^2 + 8x + 16 - 6$

$\Rightarrow \quad = (x + 4)^2 - 6$

Now the smallest possible value of the above expression can be -6

Since $(x + 4)^2$ can be minimum 0, when $x = -4$

Method 2. Compare the given expression with the standard quadratic equation $ax^2 + bx + c = 0$

$\therefore \quad a = 1, b = 8, c = 10$

Now, $\text{minima} = \dfrac{-(b^2 - 4ac)}{4a}$ $\qquad (D = b^2 - 4ac$

$D \rightarrow$ Discriminant)

$= \dfrac{-(64 - 40)}{4} = -6$

Method 3. By differentiating the given expression twice w.r. to the given variable, we get minima or maxima.

Let $\quad y = x^2 + 8x + 10$

$\therefore \quad \dfrac{dy}{dx} = y' = 2x + 8$

Again $\quad \dfrac{d^2y}{dx^2} = y'' = 2$

Since $\dfrac{d^2y}{dx^2} = 2$ (+ve value), hence the given expression gives minima.

Now since $\quad y' = 2x + 8$

Let $\quad y' = 0$

$\Rightarrow \quad 2x + 8 = 0 \Rightarrow x = -4$

$\therefore \quad y = x^2 + 8x + 10 = (-4)^2 + 8(-4) + 10 = -6$

NOTE If $\dfrac{d^2y}{dx^2}$ is a –ve value then we get maxima.

Hence the minimum value of the expression is -6.

EXAMPLE 2 *What is the maximum value of the expression* $5 - 6x - x^2$

SOLUTION **Method 1.** $5 - 6x - x^2 = 14 - (3 + x)^2$

Thus the expression can have maximum value 14, when $x = -3$

Since the minimum value of $(3 + x)^2$ is zero.

Method 2. $\quad -x^2 - 6x + 5 = 0 \qquad \ldots(1)$

Comparing the above expression with standard quadratic equation $ax^2 + bx + c = 0$, we get

$a = -1, \quad b = -6, \quad c = 5$

Since a is negative, therefore the expression gives maxima.

Now, $\quad \text{Maxima} = \dfrac{-D}{4a} = \dfrac{-(b^2 - 4ac)}{4a}$

$= \dfrac{-(36 + 20)}{-4} = 14$

Method 3. Let $y = -x^2 - 6x + 5 \qquad \ldots(1)$

$\therefore \quad \dfrac{dy}{dx} = -2x - 6$

$\therefore \quad \dfrac{d^2y}{dx^2} = -2$

Since $\dfrac{d^2y}{dx^2} = -2$ (– ve value), therefore we get maxima

Now, let $\quad \dfrac{dy}{dx} = 0$

$\Rightarrow \quad -2x - 6 = 0$

$\Rightarrow \quad x = -3$

Substituting $x = -3$ in equation (1), we get the

$\text{maxima} = -(-3)^2 - 6(-3) + 5$

$= -9 + 18 + 5 = 14$

EXAMPLE 3 *What is the maximum value of the function*

$$y = \frac{2x^2 + 3x + 4}{x^2 + x + 3}$$

SOLUTION $\quad y = \dfrac{2x^2 + 3x + 4}{x^2 + x + 3}$

$\Rightarrow \quad (y - 2)x^2 + (y - 3)x + (3y - 4) = 0$

$\therefore \quad (y - 3)^2 - 4(y - 2)(3y - 4) \geq 0 \quad \{\because \quad x \in R\}$

$\Rightarrow \quad 11y^2 - 34y + 23 \leq 0 \quad \{\because b^2 - 4ac \geq 0\}$

$\therefore \quad 1 \leq y \leq \dfrac{23}{11}$

$\therefore$ The maximum value of the expression is $\dfrac{23}{11}$

(and minimum value is 1)

Scanned by CamScanner

yoursmahboob.wordpress.com

Points to remember :

(i) When $a_1 + a_2 + a_3 + \ldots a_n = k$, then the maximum value of $a_1 \cdot a_2 \cdot a_3 \ldots a_n$ is obtained when $a_1 = a_2 = a_3 = \ldots = a_n$.

(ii) When $a_1 \cdot a_2 \cdot a_3 \ldots a_n = k$, then the minimum value of $a_1 + a_2 + a_3 + \ldots a_n$ is obtained when $a_1 = a_2 = a_3 = \ldots a_n$.

EXAMPLE 4 *If $a + b = 20$, then the maximum value of ab is :*
(a) 19 (b) 75 (c) 100 (d) 120

SOLUTION Maximum of $(ab) = 10 \times 10$ $(\because a + b = 20)$
$= 100$ $(a = b = 10)$

EXAMPLE 5 *If $a + b + c = 24$, then the maximum value of abc is :*
(a) 215 (b) 512 (c) 125 (d) 576

SOLUTION abc can be maximum only when $a = b = c$ for a given sum $a + b + c = 24$

$\therefore$ $(abc)_{max} = (8 \times 8 \times 8)$ $(\because a = b = c)$
$= 512$

EXAMPLE 6 *If $ab = 25$, then the minimum value of $a + b$ is :*
(a) 10 (b) 8 (c) 24 (d) 16

SOLUTION Minimum value of $(a + b)$ can be obtained when $a = b$
then $a + b = 5 + 5$ $(\because ab = 25$ and $a = b)$
$= 10$

EXAMPLE 7 *If $f(x) = \min(4x + 3, x + 4)$ for $x \in [0, 2]$, what is the maximum value of $f(x)$?*

SOLUTION $f(x) = \min(4x + 3, x + 4)$ is an increasing function for every $x \in [0, 2]$
It means the value of $f(x)$ increases as x increases.
$\therefore$ at $x = 2$, $f(x)$ will be maximum
$f(x)_{max} = \min(11, 6)$ at $x = 2$
$f(x)_{max} = 6$
Hence the maximum value of the function is 6.

EXAMPLE 8 *If $f(x) = \max(4x + 3, 3x + 6)$ for $x \in [-6, 10]$, Find the maximum value of $f(x)$.*

SOLUTION Since the function $f(x) = \max(4x + 3, 3x + 6)$ is an increasing function. Therefore at $x = 10$ we get the maximum value
$f(x)_{max} = \max(43, 36)$
$f(x)_{max} = 43$

EXAMPLE 9 *What is the maximum value $f(x) = \min(4 - 5x, x - 3)$ for every $x \in (0, 4)$?*

SOLUTION At $x = 0$ $f(x) = \min(4, -3) = -3$
$x = 1$, $f(x) = \min(-1, -2) = -2$
$x = 2$, $f(x) = \min(-6, -1) = -6$
$x = 3$, $f(x) = \min(-11, 0) = -11$
$x = 4$, $f(x) = \min(-16, 1) = -16$ etc.



It is clear from the graph that $f(x)_{max}$ will lie between $x = 1$ and $x = 2$ i.e., when $x \in (1, 2)$ and the $f(x)_{max}$ will be obtained when
$4 - 5x = x - 3$
$\Rightarrow$ $6x = 7$
$\Rightarrow$ $x = \frac{7}{6}$
$\therefore$ $f(x)_{max} = \min(4 - 5x, x - 3)$
$= \min\left(-\frac{11}{6}, -\frac{11}{6}\right) = -\frac{11}{6}$

NOTE In case of $f(x)_{max} = \min(x, y)$
$f(x)_{max}$ will be obtained when $x = y$
Similarly in case of $f(x)_{min} = \max(x, y)$
$f(x)_{min}$ will be obtained when $x = y$

INTRODUCTORY EXERCISE-17.3

Directions for question number 1-4 :
Mark (a) if function is one-one and into
Mark (b) if function is one-one and onto
Mark (c) if function is many one and into
Mark (d) if function is many one and onto

1. $f(x) = x^2$
$f : R \to R$



2. $f(x) = x^2$
$f : R \to R^+ \cup \{0\}$



3. $f(x) = x^2$
$f : R^+ \to R$

Scanned by CamScanner

yoursmahboob.wordpress.com

4. $f(x) = x^2$
$f : R^+ \to R^+$



5. Let $f : R \to R$ be a function defined by $f(x) = \frac{e^{|x|} - e^{-x}}{e^x + e^{-x}}$, then :
(a) f is both one–one and onto
(b) f is one–one but not onto
(c) f is onto but not one–one
(d) f is neither one–one nor onto

6. Let $n(A) = 3$ and $n(B) = 5$, then the number of one–one functions from A to B is :
(a) 15 (b) 60
(c) 125 (d) 10

7. Let $A = R - \{3\}$, $B = R - \{1\}$. Let $f : A \to B$ be defined by $f(x) = \left(\frac{x-2}{x-3}\right)$, then
(a) f is bijective
(b) f is one–one only
(c) f is onto only
(d) f is one–one but not onto

8. The function $f : N \to N$ (N is the set of natural numbers defined by $f(n) = 2n + 3$ is :
(a) surjective (b) injective
(c) bijective (d) none of these

9. The function $f : R \to R$ defined by $f(x) = (x-1)(x-2)(x-3)$ is :
(a) one–one but not onto
(b) onto but not one–one
(c) both one–one and onto
(d) neither one-one nor onto

10. If the function $f : R \to R$ be such that $f(x) = x - [x]$, where $[k]$ denotes the greatest integer less than or equal to k, then $f^{-1}(x)$ is :
(a) $[x] - x$ (b) $\frac{1}{x - [x]}$
(c) not defined (d) none of these

11. If $f(x) = x^2 + 2$ then $f^{-1}(x)$ is :
(a) $\sqrt{x-2}$ (b) $\sqrt{x+2}$
(c) $\sqrt{x} + 2$ (d) $x + 4$

12. If $f(x) = 5^x$, then $f^{-1}(x)$ is :
(a) x^5 (b) 5^{-x}
(c) $\log_5 x$ (d) none of these

13. If $f(x) = \frac{x}{x+1}$, then $f^{-1}(x)$ is :
(a) $\frac{x+1}{x}$ (b) $\frac{x}{1-x}$
(c) $\frac{x-1}{x}$ (d) none of these

14. If $f(x) = \frac{x-1}{x+1}$, then $f^{-1}(x)$ is :
(a) $\frac{1+x}{1-x}$ (b) $\frac{x+1}{x-1}$
(c) $\frac{1}{x+1}$ (d) none of these

15. Let $f : (-\infty, 1] \to (-\infty, 1]$ such that $f(x) = x(2-x)$, then $f^{-1}(x)$ is :
(a) $1 + \sqrt{1-x}$ (b) $1 - \sqrt{1-x}$
(c) $\sqrt{1-x}$ (d) none of these

16. If $f(x)$ is a one to one function, where $f(x) = x^2 - x + 1$, then find the inverse of the $f(x)$:
(a) $\left(x - \frac{1}{2}\right)$ (b) $\sqrt{x - \frac{3}{4}} + \frac{1}{2}$
(c) $\sqrt{x - \frac{3}{4}} - \frac{1}{2}$ (d) none of these

17. In the above question find the value of $f\left(\frac{3}{4}\right) + f^{-1}\left(\frac{3}{4}\right)$
(a) $\frac{21}{16}$ (b) $\frac{4}{5}$
(c) $\frac{16}{5}$ (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

Directions for questions number 1 and 2 :
$P(A, B) = A \times B$, $S(A, B) = A - B$, $D(A, B) = A + B$

1. $D(P(3, 5), S(5, 3))$ is equal to :
(a) 15 (b) 17
(c) 0 (d) 30

2. $P(S(D(7, 3), P(2, 3)), P(6, 5))$ is equal to :
(a) 120 (b) 60
(c) 30 (d) none of these

Directions for question number 3-5 : *For every $a, b \in N$*
$a @ b = a^2$ *when* $(a + b)$ *is even*
$= a^2 - b^2$ *when* $(a + b)$ *is odd*
$a \# b = b^2$ *when* $a \times b$ *is odd*
$= a^2 - b^2$ *when* $a \times b$ *is even*

3. Find the value of $20 \# (21 @ 22)$:
(a) 0 (b) 2249
(c) -1849 (d) can't be determined

4. What is the value of $(a \# a) @ (a @ a)$?
(a) 0 (b) a^4
(c) either (a) or (b) (d) neither (a) nor (b)

5. Find the value of $(p \# q) - (q @ p)$; p is even and q is odd :
(a) 0 (b) $2(p^2 + q^2)$
(c) $2(p^2 - q^2)$ (d) none of these

6. If $M(a, b) = a^2 + b^2 + ab$; $N(a, b) = a^2 + b^2 - ab$. Find the value of $M(7, N(9, 4))$.
(a) 5197 (b) 3197
(c) 4197 (d) none of these

7. If $f(x) = x^3 - x^2$, then $f(x + 1)$ is :
(a) $x^3 - x^2 + 1$ (b) $x(x + 1)^2$
(c) $x^2(x - 1)$ (d) none of these

Directions for question number 8-10 :

$$a \cup b = \begin{cases} a + b, \text{ if } a < b \\ a \vee b, \text{otherwise} \end{cases}$$

$$a \cup\cup b = \begin{cases} a \times b, \text{ if } a < b \\ a \vee\vee b, \text{otherwise} \end{cases}$$

$$a \cup\cup\cup b = \begin{cases} a^b, \text{ if } a < b \\ a \vee\vee\vee b, \text{otherwise} \end{cases}$$

$$a \vee b = \begin{cases} a - b, \text{ if } a \geq b \\ a \cup b, \text{otherwise} \end{cases}$$

$$a \vee\vee b = \begin{cases} \frac{a}{b}, \text{ if } a \geq b \\ a \cup\cup b, \text{otherwise} \end{cases}$$

$$a \vee\vee\vee b = \begin{cases} \frac{1}{a^b}, \text{ if } a \geq b \\ a \cup\cup\cup b, \text{otherwise} \end{cases}$$

8. Find the value of $[(5 \cup 4) \vee\vee (2 \cup\cup\cup 3)] \cup (8 \vee 3)$:
(a) 1 (b) 2
(c) 3 (d) 4

9. Which of the following is true?
(a) $2 \cup\cup 8 = 2 \cup\cup\cup 4$ (b) $8 \cup\cup 2 = 4 \cup\cup\cup 2$
(c) $8 \cup\cup\cup 2 = 2 \vee\vee\vee 5$ (d) none of these

10. Which one of the following is/are true?
(a) $a \cup b = a \vee b$ for all real values of a and b
(b) $a \vee\vee b = a \cup\cup b$ is true for integer values of a and b
(c) $a \vee\vee\vee b = a \cup\cup\cup b$ is true only for natural numbers
(d) none of the above

Directions for question number 11-14 :
$x @ y = (x + y)^2$
$x \# y = (x - y)^2$

11. Find the value of $(20 @ 4) \# 35$:
(a) 280081 (b) 292681
(c) 262781 (d) 301756

12. Find the value of $12 \# (14 @ (12 \# 13))$:
(a) 4539 (b) 42336
(c) 45369 (d) 89719

13. Find the value of $(9 \# 7) @ (21 \# 5)$:
(a) 67600 (b) 62500
(c) 57600 (d) none of these

14. $(2 @ 2) + (3 \# 3) - (4 @ 4) + (5 \# 5)$ is equal to :
(a) 64 (b) -48
(c) 28 (d) none of these

Directions for question number 15 and 16 :

$$CAT(a, b) = \begin{cases} a^b, \text{ if } a > 0 \text{ and } b \in I \\ 0, \text{otherwise} \end{cases}$$

$$MAT(a, b) = \begin{cases} b - a - 1, \text{ if } b > 0 \\ 1, \text{otherwise} \end{cases}$$

$$XAT(a, b) = \begin{cases} \text{remainder } (b / a), \text{ if } a > 0 \\ 2, \text{otherwise} \end{cases}$$

15. $\dfrac{XAT[MAT\{2, CAT(3, XAT[3, 2])\}, 5]}{CAT[4, XAT\{MAT(2, -5), 4\}]}$:
(a) 0 (b) 2
(c) 5 (d) none of these

16. $\dfrac{XAT(r, s)}{MAT(r, s)} = 2$:
(i) $r = 3, s = 5$ (ii) $r = -3, s = -5$
(a) (i) is true (b) (ii) is true
(c) both are true (d) none is true

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions for question number 17-19 : a and b are any numbers and x and y are any non negative integers.
$l(a)$ = the greatest integer less than or equal to a
$g(a)$ = the smallest integer greater than or equal to a
$r(x, y)$ = the remainder when x is divided by y.

17. $r(16, 7) - 2$ is equal to :
(a) 0 (b) 1
(c) 2 (d) 3

18. $g(4.7) - l(2)$ is equal to :
(a) 1 (b) 2
(c) 3 (d) 4

19. $r(x, y)$ with both x and y not equal to zero is equal to :
(a) $l\left(\frac{x}{y}\right)$ (b) $x - \left[y l\left(\frac{x}{y}\right)\right]$
(c) $y - \left[x l\left(\frac{x}{y}\right)\right]$ (d) $\left[l\left(\frac{x}{y}\right) - y\right]$

Directions for question number 20-22 :

$$x \# y = \begin{cases} x + 2y; \text{ if } |x + y| \text{ is even} \\ 2x @ 2y; \text{ if } |x + y| \text{ is odd} \end{cases}$$

$$x @ y = \begin{cases} 3x - y; \text{ if } |x + y| \text{ is even} \\ 2x \# 2y; \text{ if } |x + y| \text{ is odd} \end{cases}$$

20. Find the value of $2 \# ((7 @ (4 \# 5)) @ 3)$:
(a) 204 (b) 306
(c) 408 (d) 102

21. Which of the following is true?
(i) If $q = 2p$ and $p + q$ is even, then $p \# q = q \# p$
(ii) If $q = 3p$, $p @ q$ will always be zero
(iii) If $q = 2p$ and p is odd, then $p @ q$ will be even
(a) (ii) only (b) (iii) only
(c) (i) and (iii) only (d) (ii) and (iii) only

22. Which of the following is true?
(i) $6 @ 2 = 12 \# 2$
(ii) $6 \# 3 = (14 @ 12) + (2 @ 6)$
(iii) $(6 @ 2) + (6 \# 3) = (12 \# 2) + (14 @ 12) - (2 @ 6)$
(a) (i) and (ii) only (b) (i) and (iii) only
(c) (ii) and (iii) only (d) (i), (ii) and (iii)

Directions for question number 23-25 :

$$a \# b = a^2 + b - 1$$
$$a \$ b = a^2 + b^2 + 1$$
$$\text{Max}(a, b) = |a + b|$$
$$\text{Min}(a, b) = |a - b|$$

23. Max [(2 #3) $ (3 #4), (3 #4) $ (4 $ 4)] is equal to :
(a) 1234 (b) 1236
(c) 1335 (d) none of these

24. Max[Min ((1 $ 2), (2 $ 3)), Max ((3 # 4), (4 # 5))] is equal to :
(a) 24 (b) 40
(c) 42 (d) none of these

25. Find the value of
Min [(1 # 2) $ 3, 4#(5 $ 6)] $ Max (6 # 7), (7 # 8)] :
(a) 13574 (b) 14573
(c) 13575 (d) 14674

26. If $a \Delta b = a^b + ab + \frac{a}{b}$, then $(9 \Delta 3)$ is equal to :
(a) 729 (b) 927
(c) 759 (d) none of these

27. $a * b \# c = (ab)^c$:
$a \# b * c = a^b$, c, then find the value of $3 \# 4 * 5 + 3 * 4 \# 5$
(a) 35287 (b) 249237
(c) 12345 (d) none of these

Directions for question number 28 and 29 :

$$a \# b = (-1)^{ab}(a^b + b^a)$$
$$f(x) = x^2 - 2x \text{ if } x \geq 0$$
$$= 0 \text{ if } x < 0$$
$$g(x) = 2x \text{ ; if } x \geq 0$$
$$= 1 \text{ ; if } x < 0$$

28. Find the value of $f(2 \# 3) \# g(3 \# 4)$:
(a) 2045 (b) $(17)^{18}$
(c) $(180)^{81}$ (d) none of these

29. Find the value of $f(g(2 \# 3)) + g(f(1 \# 2))$:
(a) 9401 (b) 1049
(c) 1094 (d) none of these

Directions for question number 30, 31 :

$$a \oplus b = (a + b)^2 - ab$$
$$a * b = (ab)^2 - ab$$
$$a @ b = (a - b)^2 - ab$$

30. Find the value of $(5 \oplus 6) - (6 @ 3) + (2 * 4)$
(a) 156 (b) 256
(c) 1056 (d) none of these

31. Find the vlaue of $(((1 \oplus 2) * 3) @ 20)$:
(a) 151600 (b) 141500
(c) 161500 (d) none of these

Directions for question number 32 and 33 :
If $m < n$ then $m\,Dn = m\,Cn$ else $mDn = nCm$
If $m = n$ then $mEn = mn$ else $mEn = mCn$ where $mCn = \frac{m}{n}$

32. Find the value of (3 D 4) D (12 D 5) :
(a) $\frac{9}{5}$ (b) $\frac{5}{9}$
(c) $\frac{2}{3}$ (d) $\frac{5}{3}$

33. Find the value of (12 D 60) E (2 C 10) :
(a) 1 (b) $\frac{1}{5}$
(c) 1/25 (d) 0

Directions for question number 34-38 : The operands in the Devic Mathematics are as follows :
+ → multiplication
− → division
× → addition
/ → subtraction
^ → power (or index) for exponential expression.
But Devic Mathematics must follow the same conventional BODMAS rule of mathematics. Solve the following questions in Devic Mathematics.

34. $30 + 20 - 4 \times 6$ is equal to :
(a) 156 (b) 276
(c) 330 (d) none of these

35. $50 / 40 - 5 + 4 \times 54$ is equal to :
(a) 720 (b) 72
(c) 144 (d) none of these

36. $(5 \wedge 5) \times (4 \wedge 4) / (3 \wedge 3) \times (2 \wedge 2) / (1 \wedge 1)$ is equal to :
(a) 2987 (b) 4013
(c) 3357 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

37. The value of the following expression in Devic mathematics is : $[(x^2 \times y^2) - (x + y)^2] + \left[(x + y)^3 - \left\{\left(\frac{x}{y}\right)^2 \times 2 + x + y\right\}\right]$

(a) $\frac{x}{y}$ (b) $x + y$

(c) $x \times y$ (d) $x \wedge y$

38. The value of the following expression in Devic mathematics is $a + a + a - a + a + a / a + a - a$:

(a) 1 (b) 0

(c) $1 - a$ (d) $\frac{1}{a}$

✍ ***Directions for question number 39 and 40 :***

$P\Delta Q = P + Q$, if $PQ < 0$

$P\Delta Q = P - Q$, if $PQ > 0$

39. $[(2\Delta 3) \Delta (-2\Delta 3)]$ is equal to :

(a) 0 (b) 1

(c) 2 (d) 3

40. If $(a\Delta b) \Delta (a\Delta - b) = 0$ and $a > 0$ then which of the following is true?

(a) $a < b$ and $b > 0$ (b) $|a| > |b|$ and $b < 0$

(c) $a > b$ and $b > 0$ (d) all of these

41. If $f(x) = x^3 + 3x^2 + 3x$, then $f(x + 1)$ is equal to

(a) $x^3 + 6x^2 + 12x + 7$ (b) $x^3 + 4x^2 + 5$

(c) $3x^3 + 12x^2 + 4x + 1$ (d) $2x^3 + 6x^2 + 3$

42. $x @ y = xy - 1$, if $x > y$

$= 0$; otherwise

and $x \# y = \frac{x + y}{x - y}$ if $x \geq 0, y \geq 0$

$= 1$; otherwise.

The value of $\frac{(4 \# 2) @ (9 \# (-1))}{(2 @ 3) \# (5 @ 2)}$:

(a) 1 (b) -2

(c) 0 (d) none of these

✍ ***Directions for question number 43 and 44 :*** *The following functions are defined for any two distinct, non zero integers a and b*

$$f_1(a, b) = |a| \times b^2$$
$$f_2(a, b) = a^2 \times |b|$$
$$f_3(a, b) = \frac{(a^2 + b^2)}{2}$$
$$f_4(a, b) = \left(\frac{a}{2} + \frac{b}{2}\right)$$

43. Which of the following is equal to $(a + b)^2$?

(a) $f_3(a, b) \div f_4(a, b)$ (b) $2 \times f_3(a, b) \times f_4(a \times b)$

(c) $4 \times f_3(a, b) \times f_4(a, b)$ (d) none of these

44. Which one of the following is necessarily greater than zero?

(a) $f_1(a, b) \times f_2(a, b) \times f_3(a, b)$

(b) $f_1(a, b) \times f_2(a, b) \times f_4(a, b)$

(c) $f_1(a, b) \times f_3(a, b) \times f_4(a, b)$

(d) $f_2(a, b) \times f_3(a, b) \times f_4(a, b)$

✍ ***Directions for question number 45-47 :***

lt (p) → the least possible integer greater than or equal to p.

gt (p) → the greatest possible integer less than or equal to p.

$\Delta(p, q) = \text{Min}\ (\text{lt}\ (p), \text{gt}\ (q))$

45. What is the value of lt (8.3) − gt (5.3) + lt (6.8) + gt (9.4)

(a) 15 (b) 20

(c) 19 (d) none of these

46. Find the value of

$\Delta(3, 2) - \Delta(2, 3) + \text{gt}\ (4.8) - \text{lt}\ (2.7) + \Delta(4, 5)$

(a) 4 (b) 5

(c) 6 (d) none of these

47. Which of the following statements is always true about $(a - b)$ where $a = \frac{p + q}{2}$ and $b = \frac{\text{lt}(p) + \text{gt}(q)}{2}$

(a) $-\frac{1}{4} \leq (a - b) \leq \frac{1}{4}$, always

(b) $-\frac{1}{2} \leq (a - b) \leq \frac{1}{2}$

(c) $-1 \leq (a - b) \leq 1$

(d) $-1 \leq (a - b) \leq 1$, except zero

✍ ***Directions for question number 48-49 :***

$$a @ b = \frac{a}{a + b}$$

and $$b \# a = \frac{a + b}{b}$$

48. Which of the following is true ?

(a) $\frac{a @ b}{b \# a} = \frac{a}{b}$ (b) $(a @ b)(b \# a) = a^2 b^2$

(c) $(a @ b)(b \# a) = \frac{a}{b}$ (d) $\frac{a @ b}{b \# a} = \frac{a + b}{b + a}$

49. Which of the following is true?

(a) $a @ b + b \# a = \frac{a^2 + b^2 + 3ab}{a(b + a)}$

(b) $a @ b - b \# a = \frac{a^2 + b^2 + ab}{b(b + a)}$

(c) $b \# a - a @ b = \frac{a^2 + b^2 + ab}{b(a + b)}$

(d) $a @ b + b \# a = 1$

✍ ***Directions for question number 50 and 51 :*** *The following operations are defined for any two real number a and b.*

$mn\ (p, q) = \min\ (p, q)$

$mx\ (p, q) = \max\ (p, q)$

$md\ (p) = |p|$

50. Find the value of $mn\ (md\ (p), mx\ (q, mn\ (p, md(q))))$ if $p = -2, q = 5$:

(a) -2 (b) 2

(c) 3 (d) -7

51. Find the value of $md\ (mn\ (P, mx\ (md\ (q), mn\ (P, r))))$ if $p = -2, q = 5, r = 7$.

(a) -1 (b) 0

(c) 2 (d) none of these

✍ ***Directions for question number 52 and 53 :***

$a @ b = (a + b)(ab + b)$

$a \# b = (a - b)(ab - b)$

$a\Delta b = (a @ b) - (a \# b)$

52. Find the value of $((1 @ (2\Delta 3)) \# 4)$:

(a) 35500 (b) 482420

(c) 123400 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

53. Find the value of $(1 @ 1) \Delta (2 \# 2)$
(a) 5 (b) 22
(c) 17 (d) none of these

Directions for question number 54 and 55 :

$$a @ b = |a - b|$$
$$a * b = ab$$
$$a \# b = |a^2 - b^2|$$
$$a \Delta b = a^2 + b^2$$

where $a, b \in R$ and $a \neq b$ and the real algebraic operations are unchanged.

54. Find the value of $(a \Delta b) + (a \# b)$:
(a) $2a^2$ (b) $2b^2$
(c) $2(a^2 + b^2)$ (d) can't be determined

55. The value of the expression $[(a \# b) \div (a @ b)]^2 - 2(a * b)$:
(a) $a \# b$ (b) $a \Delta b$
(c) $(a \# b)(a @ b)$ (d) can't be determined

Directions for question number 56-58 : *A function $f(x) = \log(g(x))$, where $g(x)$ is any function of x.*

56. For what value of $g(x)$, $g(x) = g(f(x))$?
(a) e (b) e^x
(c) $\log x$ (d) none of these

57. For what value of $g(x)$ is the function of $f(x) = g(x)$?
(a) $g(x) = e$ (b) $g(x) = e^x$
(c) $g(x) = \log x$ (d) none of these

58. If $g(x) = e^x$, then $f(f(x))$ is equal to :
(a) e (b) e^x
(c) $\log x$ (d) none of these

59. If $f(x) = 2x + 3$ and $g(x) = 9x + 6$, then find $g[f(x)] - f[g(x)]$
(a) 18 (b) 22
(c) 20 (d) none of these

60. If $f(x) = x^2 + 2x + 2;\ x \geq -1$
$= -x^3 + 3x + 1;\ x < -1$
then find the value of $f(f(-2))$:
(a) 15 (b) 17
(c) 22 (d) none of these

Directions for question number 61-63 :
$[m]$ is defined as the greatest integer less than m
$\{m\}$ is defined as the least integer greater than m

$$f(x, y) = \{x\} + [y]$$
$$g(x, y) = [x] - \{y\}$$
$$F(f(x, y)) = \{f(x, y)\} - [g(x, y)]$$
$$G(g(x, y)) = [f(x, y)] - \{g(x, y)\}$$

61. Given that $x^2 = 4$ and $y^2 = 9$ and $|F(f(x, y))| = |G(g(x, y))|$ then find the vlaue of $x + y$:
(a) -1 (b) 0
(c) 1 (d) 5

62. If x and y are consecutive integers, then find $g(x, y)$
(a) -1 (b) -3
(c) -1 or -3 (d) none of these

63. Which of the following is false?
(a) $f(x, y) + g(x, y) = F(f(x, y)) + G(g(x, y))$
(b) $F(f(x, y)) - G(g(x, y)) = -2[g(x, y)]$
(c) $F(f(x, y) + G(g(x, y)) = 2\{f(x, y)\} + 2$
(d) none of the above

Directions for question number 64-66 : *A decimal number 'm' (say) can be expressed as*
$m = I + D$
where $I \rightarrow$ integral part
and $D \rightarrow$ decimal part, $0 \leq D < 1$
and $[m]$ = greatest integer less than or equal to m if $0 < D < 0.5$
also $\{m\}$ = least integer greater than or equal to m if $0.5 \leq D < 1$

Hence, $f(x, y) = \begin{cases} [x + y] \text{ if } 0 < D < 0.5 \\ \{x + y\} \text{ if } 0.5 \leq D < 1 \\ (x + y) \text{ otherwise} \end{cases}$

Also, $F(f(x, y)) = -f(x, y)$
and $G(f(x, y)) = -F(f(x, y))$

64. What is the value of the following
$f(G(f(1.2, 1.3))),\ f(F(f(0,1))),\ G(f(0.8, 0.4)))$?
(a) 1 (b) 2
(c) 3 (d) 4

65. Which of the following statements is true if x and y are positive ?
(a) $F(f(x, y)) . G(f(x, y)) = -F(f(x, y)) . G(f(x, y))$
(b) $F(f(x, y)) . G(f(x, y)) > -F(f(x, y)) . G(f(x, y))$
(c) $F(f(x, y)) . G(f(x, y)) \neq G(f(x, y)) . F(f(x, y))$
(d) $F(f(x, y)) + G(f(x, y)) + F(x, y)) = F(x, y)$

66. Which of the following expressions will yield a number which has a positive integral square root if x, y are positive
(a) $G(f(1.2, 1.3)) \times f(F(f(2, 1), G(f(4, 1))$
(b) $F(f(2, 2)) + G(f(2, 2))$
(c) $f(1.1, 1.2) \times G(f(1.1, 1.2))$
(d) $G(f(0, 1)) \times G(f(0, 1))$

67. $f(x) = \frac{1}{x}; g(x) = \left(x + \frac{1}{x}\right)$, then which of the following is true?
(a) $f(g(x)) . g(f(x)) = 1$ (b) $\frac{f(g(x))}{g(f(x))} = 1$
(c) $f(g(x)) + g(f(x)) = 1$ (d) none of these

68. If $f(x) = 2x^2 + 7x - 9$ and $g(x) = 2x + 3$, then find the value of $g(f(x))$ at $x = 2$
(a) 92 (b) 39
(c) 29 (d) none of these

69. Find $f(f(f(f(f(2)))))$ if $f(x) = \frac{x + 1}{x - 1};\ x \neq 1$
(a) 1 (b) 2
(c) 3 (d) 5

Directions for question number 70 and 71 :
$f(x) = 1 - h(x),\ g(x) = 1 - k(x),\ h(x) = f(x) + 1$
$j(x) = g(x) + 1,\ k(x) = j(x) + 1$

70. Find the value of $\frac{j(f(x)) + k(h(x))}{h(k(x)) + f(j(x))}$:
(a) 0 (b) 1
(c) 2 (d) none of these

71. $\frac{h(f(k(x))) + j(g(h(x))) + k(j(f(x)))}{[f(x) + j(x) + k(x)][f(x) . j(x) k(x)]}$ is equal to :
(a) 0 (b) 3
(c) 3/2 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

72. If $f(x)$ and $g(x)$ are odd functions of x, then which of the following is true?
(a) $f+g$ is odd, fg is odd
(b) $f+g$ is odd, fg is even
(c) $f+g$ is even, fg is odd
(d) $f+g$ is even, fg is even

73. If $f(x)$ is an even function of x and $g(x)$ is an odd function then which of the following is true?
(a) $f[g(x)]$ is odd , $g[f(x)]$ is even
(b) $f[g(x)]$ is odd, $g[f(x)]$ is odd
(c) $f[g(x)]$ is even, $g[f(x)]$ is even
(d) $f[g(x)]$ is even, $g[f(x)]$ is odd

74. If $y = \min(x^2+2, 6-3x)$, then the greatest value of y for $x>0$
(a) 1 (b) 2
(c) 3 (d) none of these

75. If $p^2+q^2+r^2=1$, then the maximum value of pqr is :
(a) 1 (b) $\frac{1}{3\sqrt{3}}$
(c) 3 (d) none of these

Directions for question number 76-78 : Following functions are defined for three distinct positive numbers, such that $x<y<z$.

$f(x,y,z) = \min(\max(x+y, y+z), \max(z+x, x+y))$
$g(x,y,z) = \max(\min(x+y, y+z), \min(z+x, x+y))$
$h(x,y,z) = \max(\max(x+y, y+z), \max(z+x, x+y))$
$j(x,y,z) = \min(\min(x+y, y+z), \min(z+x, x+y))$
$k(x,y,z) = \text{int.}((x+y+z)/3)$
such that $k(x,y,z) \le (x+y+z)/3$
$l(x,y,z) = \min(x,y,z)$
$m(x,y,z) = \max(x,y,z)$

76. Which of the following expression is necessarily equal to 1?
(a) $\frac{(f(x,y,z)-m(x,y,z))}{(m(x,y,z)-l(x,y,z))}$
(b) $\frac{g(x,y,z)}{j(x,y,z)}$
(c) $\frac{(m(x,y,z)-f(x,y,z))}{k(x,y,z)+j(x,y,z)}$
(d) $\frac{(h(x,y,z)-f(x,y,z))}{f(x,y,z)}$

77. Which of the following expression gives negative value?
(a) $\frac{(m(x,y,z)-f(x,y,z))}{h(x,y,z)\times k(x,y,z)\times l(x,y,z)}$
(b) $\frac{(m(x,y,z)-l(x,y,z)+j(x,y,z))}{k(x,y,z)}$
(c) $\frac{l(x,y,z)-m(x,y,z)}{g(x,y,z)-j(x,y,z)}$
(d) $\frac{h(x,y,z)-g(x,y,z)}{k(x,y,z)}$

78. Which of the following expressions is necessarily greater than 1 ?
(a) $\frac{[h(x,y,z)-j(x,y,z)]}{k(x,y,z)}$
(b) $[g(x,y,z)-j(x,y,z)]\times m(x,y,z)$
(c) $\frac{g(x,y,z)}{j(x,y,z)}$
(d) $\frac{f(x,y,z)+h(x,y,z)-g(x,y,z)}{j(x,y,z)}$

Directions for question number 79-83 :

$A(x,y,z) = \min(x+y, y+z, z+x)$
$B(x,y,z) = \max(x-y, y-z, z-x)$
$C(x,y,z) = \max(A(x,y,z), B(x,y,z))$
$D(x,y,z) = \min.(A(x,y,z), B(x,y,z))$

79. The value of $C(1,2,3)$ is :
(a) 1 (b) 2
(c) 3 (d) 4

80. The value of $D(0,1,2)$ is :
(a) -1 (b) 1
(c) 0 (d) none of these

81. What is the value of $A(2,3,4)+B(2,3,4)$?
(a) 13 (b) 4
(c) 7 (d) none of these

82. What is the value of $C(0,1,D(1,2,3))$?
(a) 1 (b) 2
(c) -2 (d) none of these

83. What is the value of $D(1,2,C(0,1,2))$?
(a) 1 (b) 2
(c) 3 (d) 4

84. What is the maximum possible value of xy, where $|x+5|=1$ and $y = 9-|x-4|$
(a) 401 (b) 124
(c) 104 (d) none of these

LEVEL 2

1. Let a function is defined as $f(x)=\frac{a^x+a^{-x}}{2}$; $a>0$, what is the value of $f(x+y)+f(x-y)$?
(a) $f(x)+f(y)$ (b) $f(x)f(y)$
(c) $2f(x)f(y)$ (d) $4f(x)f(y)$

2. If $\left|\frac{30-x}{5}\right|<4$, then find x :
(a) $-6<x<6$ (b) $10<x<50$
(c) $x>10$ (d) none of these

3. Let $f(x,y)=|x+y|$ and $g(x,y)=|x-y|$, then how many ordered pairs of the form (x,y) would satisfy $f(x,y)=g(x,y)$
(a) 1 (b) 2
(c) 4 (d) infinitely many

4. What is the value of x if $|x-1|+|x|=2$:
(a) $-\frac{1}{2}$ (b) $\frac{3}{2}$
(c) both (a) and (b) (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

5. Which of the following graph represents e^{-x} ?



(a)

(b)



(c)

(d)

6. Which of the following represents the graph of e^{-x^2} :



(a)

(b)



(c)

(d)

7. A function is defined as $f(x) = a^x \; \forall \; x \in R$ and $0 < a < 1$, then which of the following is true?
(i) It is an increasing function
(ii) It is a decreasing function
(iii) All such functions must meet at (0, 1)
(a) only (i) is true (b) only (ii) is true
(c) (i) and (iii) are true (d) (ii) and (iii) are true

Directions for question number 8-13 : *The following figure represents various functions. Match the figure with the appropriate function.*



(A)



(B)



(C)



(D)



(E)



(F)

8. $f(x) = -x$:
(a) B (b) C
(c) E (d) D

9. $f(x) = |x|$:
(a) A (b) B
(c) C (d) D

10. $f(x) = -|x|$:
(a) E (b) B
(c) A (d) F

11. $f(x) = x$:
(a) E (b) F
(c) A (d) B

12. $f(x) = |x| - x$:
(a) A (b) C
(c) B (d) none of these

13. $f(x) = ||x| - x|$:
(a) B (b) D
(c) A (d) none of these

14. If $x = 10^y$ then the graph of inverse of this function is :



(A)



(B)



(C)



(D)

(a) A (b) B
(c) C (d) D

15. If $f(x) = \begin{cases} 1-x, & 0 \le x \le 2 \\ x-1, & 2 \le x \le 4 \\ 1, & 4 \le x \le 6 \end{cases}$

then find, $f(0) + f\left(\frac{1}{2}\right) + f(1) + f\left(\frac{45}{18}\right)$:
(a) 1 (b) 2
(c) 3 (d) none of these

16. Which one of the following is true about the given graph ?
(a) $x = \frac{|y|}{y}, y \neq 0$

Scanned by CamScanner

yoursmahboob.wordpress.com

(b) $y = \frac{|x|}{x}, x \neq 0$

(c) $x = -\frac{|y|}{y}, y \neq 0$

(d) $y = \frac{-|x|}{x}, x \neq 0$



✍ ***Directions for question number 17 and 18 :*** *In each question there are two graphs $f(x)$ and $g(x)$ for the real values of x.*
Mark (a) if $g(x) = f(-x)$
Mark (b) if $g(x) = -f(x)$
Mark (c) if $g(x) = |f(x)|$
Mark (d) if none of the above is true.

17.





18.





✍ ***Directions for question number19-22:*** *In the following questions a function is represented by the graph.*
Mark (a) if $f(x) = f(-x)$
Mark (b) if $f(x) = -f(-x)$
Mark (c) if $f(x)$ does not exist
Mark (d) if none of the above is true.

19.



20.



21.



22.



23. In the following graph for $x \in [-1, 1]$, $f(x)$ is defined by:



(a) $|x| + 1$ (b) $-|x| + 1$
(c) $-|x + 1|$ (d) $-|x| - 1$

24. How many times does the graph of $y = x^3 - 3x^2 - x + 3$ intersects the x-axis :
(a) 1 (b) 2
(c) 3 (d) none of these

25. Which one of the following is true for $x \in R$:
(a) $f(x) = \log|x|$ (b) $f(x) = \frac{|x|}{\log|x|}$
(c) $f(x) = \log(x^2 + 2)$ (d) $f(x) = \log_x 100$

26. Which one of the following is correct about the given graph of $f(x)$:
(a) $|xy| = 1$
(b) $|x|y = 1$
(c) $x|y| = 1$
(d) $|x||y| = 1$



27. A function is defined as $f(x) = \frac{25}{(x+5)^2}$, then the value of $f(x)$:
(a) decreases as the value of x increases, only if x is negative
(b) increases as the value of x increases, only if x is negative
(c) decreases as the value of x increases, only if x is positive
(d) both (a) and (c) are true

✍ ***Directions for question number 28 and 29 :*** *The following functions are defined for the set of variables $x_1, x_2, x_3, \ldots, x_n$*

$$f(x_i, x_j) = \begin{cases} x_{i+j} \text{ if } i + j \leq n^2 \\ x_{i+j-n} \text{ if } i + j > n^2 \end{cases}$$

$$g(x_i, x_j) = x_m,$$

where m is the remainder when $i \times j$ is divided by n.

28. Find the value of $f(f(x_2, x_3), f(x_5, x_6))$ if $n = 3$
(a) x_5 (b) x_{10}
(c) x_{13} (d) none of these

29. Find the value of $g(g(x_2, x_3), g(x_7, x_8))$ if $n = 5$
(a) x_1 (b) x_2
(c) x_5 (d) none of these

✍ ***Directions for question number 30-34 :*** *In each of the following questions a graph of a function is being shown. Select the correct equation of the function of the graph.*

Scanned by CamScanner

yoursmahboob.wordpress.com

30.



(a) $y = |x-1|$ (b) $x = |y|+1$
(c) $y = |x|-1$ (d) $y = |x|-2$

31.



(a) $x = |y|+y$ (b) $y = |x|+x$
(c) $y = |x|$ (d) $x = |y|$

32.



(a) $x = y+1$ (b) $y = x-1$
(c) $x = y-1$ (d) $y = 1-x$

33.



(a) $y = |x-1||x-2|$ (b) $y = |||x|-1|-2|-1$
(c) $y = |||x|-2|-1|$ (d) none of these

34.



(a) $y = |x-1||x-2|$ (b) $y = -(|x|-1)(|x|-2)$
(c) $y = |||x|-1|-2|$ (d) $y = (|x|-1)(|x|-2)$

✍ ***Directions for question number 35-37 :*** *In each of the following questions a pair of graphs $f(x)$ and $g(x)$ is given, defined for every $x \in (-1, 1)$ Choose the correct answer as*

(a) if $f(x) = -g(x)$ for every x
(b) if $f(x) = g(x)$ for $x < 0$ and $f(x) = -g(x)\ x > 0$
(c) if $f(x) = -g(x)$ for $x < 0$ and $f(x) = g(x), x > 0$
(d) none of the above

35.



36.



37.



38. In the adjacent diagram two graphs of equal magnitude are being shown. Their maxima and minima are also same, then the correct choice for the two equation of functions is :



(a) $y = ax^2 + b$ and $y = ax^2 - b$
(b) $f(x) = ax^2$ and $f(x) = bx^2; a \neq b$
(c) $f(x) = ax^2 + bx$ and $f(x) = -ax^2 + bx$
(d) $y + ax^2 + c = 0$ and $y - ax^2 - c = 0$

39. If $f(x) = \frac{1}{x}; x \neq 0$ and $f^{n+1}(x) = f^n(f(x))$, find the product of $f^{11}(1).f^{33}(1).f^{55}(1)\ f^{77}(1).f^{99}(1)$:
(a) 110 (b) 88
(c) 275 (d) 1

40. If $f(x) = \frac{1}{x}$, $x \neq 0$ $f^n(x) = f(f^{n-1}(x))$ and $f^{12} = 11$, what is the value of $f(x) = ?$
(a) 1 (b) 2
(c) 1/11 (d) none of these

✍ ***Directions for question number 41-43 :*** *A program module is given below with various steps involved, which starts with the values of a, b, c as 1, 2, 3 respectively. These values remain unchanged till step 1.*
The program is executed with the help of following operators.

Milan $2(P) = P \times 2$
Milaap $2(P) = P + 2$

and $b = a$ means the value of a is assigned to b.
START
Step 1. *Read (a, b, c)*

Scanned by CamScanner

yourshahboob.wordpress.com

Step 2. *Milan* $2(a)$
Step 3. *Milaap* $2(b)$
Step 4. $c = a + b$
Step 5. *If,* $c > 111$, *then go to step 6 else go to step 2.*
Step 6. *STOP*

41. How many times in the above program does c take a perfect square value ?
(a) 1 (b) 2
(c) 0 (d) none of these

42. In a particular cycle a, b and c get the values such that $9a = 8c$, then the value of b is :
(a) 6 (b) 8
(c) 16 (d) none of these

43. How many times is the program module repeated?
(a) 6 (b) 7
(c) 5 (d) none of these

Directions for question number 44-46 : *In the following algorithm x, y and z are variables which change their values in each step such that the value of the expression on the right hand side is assigned to the variable on the left hand side of the equation. Each cycle consists of 5 steps. $S_1, S_2, S_3 \ldots$ are the sum of each corresponding cycle 1, 2, 3....*

START
Step 0. $x = 1, y = -2, z = 3$
Step 1. $x = y - z$
Step 2. $y = z - x$
Step 3. $z = x - y$
Step 4. $S = x + y + z$
Step 5. *Go to step 1.*

44. Which one of the following is correct for each cycle?
(a) $S = 2x$ (b) $S = 3x$
(c) S is an odd number (d) none of these

45. What is the value of S_4 ?
(a) 987 (b) 754
(c) -178 (d) none of these

46. Which of the following is correct?
(a) S_{11} is an odd number
(b) S_{13} is a negative number
(c) S_{15} is an even number
(d) both (b) and (c)

Directions for question number 47–48 : *There are three bottles of water K, L, M whose capacities are 9 litres, 5 litres and 4 litres respectively. For transferring water from one bottle to another and to drainout the bottles, there exists a piping system. The flow through these pipes is computer controlled. The computer that controls the flow through these pipes can be fed with three types of instructions, as explained below. Initially K is completely filled up with water and L, M are empty.*

Instruction type	*Explanation of the instruction*
Fill (X, Y)	*Fill bottle labelled X from the water in bottle labelled Y, where the remaining capacity of X is less than or equal to the amount of water in Y.*
Empty (X, Y)	*Empty out the water in bottle labelled X into bottle labelled Y, where the amount of water in X is less than or equal to remaining capacity of Y.*
Drain (X)	*Drain out all the water contained in bottle X.*

47. How much water would be there in bottle labelled L after the execution of the sequence of the following four instructions:
First instruction : Fill (L, K)
Second instruction : Fill (M, L)
Third instruction : Empty (L, K)
Fourth instruction : Empty (M, L)
(a) 0 litre (b) 4 litres
(c) 5 litres (d) none of these

48. After executing a sequence of 6 instructions, bottle K has half of the water that the bottles L and M together have and the bottle L has half of the water that the bottle M has. Find the fourth instruction if the rest instructions are given below.
Instruction 1. Fill (L, K)
Instruction 2. Fill (M, L)
Instruction 3. Empty (M, K)
Instruction 5. Fill (L, K)
Instruction 6. Fill (M, L)
(a) Fill (L, M) (b) Empty (L, M)
(c) Fill (M, K) (d) Empty (M, L)

Final Round

(The questions in this exercise given are very similar to the questions which are asked in XAT for XLRI, XIM etc.

Directions for question number 1-10 : *Solve the following questions on the basis of following functions*
(a) $P_{(n+1)} = P_{(n)} - P_{(n-1)}$, *$P$ is the term of the sequence and* $P_{(0)} = 0, P_{(1)} = 1$
(b) $Q_{(n+1)} = Q_{(n)} + Q_{(n+1)}$; *Q is the term of the sequence and* $Q_{(0)} = 0, Q_{(1)} = 1$

1. What is the 10^{th} term of series $Q_{(n+1)}$ starting from $n = 0$?
(a) 34 (b) 89
(c) -1 (d) 55

2. What is the 12^{th} term of the series $P_{(n+1)}$ starting from $n = 0$?
(a) -1 (b) 0
(c) 1 (d) none of these

3. The value of Q cannot be :
(a) 144 (b) 55
(c) 98 (d) 34

4. The value of P cannot be :
(a) -1 (b) 0
(c) 1 (d) 4

5. Which of the following can be a positive value of $Q_n + P_{(n+1)}$?
(a) 55 (b) 234
(c) 146 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

6. The value of $Q_n + P_n$ cannot be :
(a) 2 (b) 22
(c) 55 (d) 88

7. The value of $Q_{[Q(n+1)]}$ can be :
(a) 55 (b) 13
(c) 21 (d) 89

8. The value of $Q_n \times P_n$ can be :
(a) -34 (b) 89
(c) -233 (d) 377

9. The value of $[Q_{(n)}]^{P_n}$ can be :
(a) -1 (b) 0.2
(c) -13 (d) 5.5

10. The value of $Q_{(n-1)} + Q_{(n+1)} + L_{(n-1)} + L_{(n+1)}$ cannot be :
(a) 30 (b) 75
(c) 18 (d) 122

Directions for question number 11-14 : Let S be a sequence of the form $[K(1), K(2), \ldots K(m)]$. Each term can be defined by the following four functions :

$$P[K(x)] = 3Q[K(x)] - 4$$
$$Q[K(x)] = 2R[K(x)] + R[K(2x)]$$
$$R[K(x)] = S[K(2x)] - S[K(x)]$$
$$S[K(x)] = \begin{cases} 0 \text{ if } x < 0 \\ 3x + 4 \text{ if } 0 \le x \le 6 \\ 4x + 3 \text{ if } x > 6 \end{cases}$$

Also if $Q[K(x)] = y$ then $PQ[K(x)] = P[K(y)]$

11. What is the value of $P[K(3)]$?
(a) 3 (b) 5
(c) 32 (d) 137

12. What is the value of $QRS[K(1)]$:
(a) 112 (b) 224
(c) 448 (d) none of these

13. What is the value of $R[K(5)] - S[K(10)]$:
(a) 43 (b) -19
(c) 14 (d) none of these

14. What is the value of $\sum_{x=-\infty}^{+\infty} R[K(x)]$ if

$$\sum_{x=1}^{4} R[K(x)] = R[K(1)] \times R[K(2)] \times R[(K(3)] \times R[K(4)]?$$

(a) -1 (b) 0
(c) 1 (d) none of these

Directions for question number 15-20 : These questions are based on the given data.
A polynomial can be represented in an equivalent sequence form.
The polynomial $P_1x^{k_1} + P_2x^{k_2} + P_3x^{k_3} + \ldots P_nx^{k_n}$ where $k_1 > k_2 > k_3 \ldots > k_n$ and $a_i \neq 0$ for $1 \le i \le n$ will be represented as the sequence $(P_1, k_1, P_2, k_2, P_3, k_3 \ldots P_n, k_n)$
Also, we add, subtract, multiply as we do for corresponding polynomials. The resulting polynomial is again represented as a sequence.

15. $(3, 4, 2, 2, 5, 1) + (2, 4, 3, 3, 7, 2)$ equals :
(a) (5, 4, 3, 4, 9, 3, 5, 1) (b) (5, 4, 5, 5,12, 3)
(c) (5, 4, 3, 3, 9, 2,5,1) (d) none of these

16. $(6, 5, 7, 4, 8,3) - (3, 5, 5,3, 7, 1)$ equals
(a) (3, 5, 2, 2, 1, 2) (b) (3, 5, 7, 4, 3, 3, -7, 1)
(c) (3, 5, 7, 3, 8, 2) (d) none of these

17. $(1, 1, 2, 0) \times (1, 1, 2, 0) \times (1, 1, 2, 0)$ equals :
(a) (1, 3, 6, 2, 12,1, 8, 0) (b) (1, 3, 2, 2, 3, 1, 4, 0)
(c) (1, 8, 2,4, 3, 2) (d) none of these

18. The expression $\frac{3, 3, -10, 2, 7, 1}{3, 2, -7, 1}$ equals :
(a) (1, 1, -1, 1) (b) (1, 1, -1, 0)
(c) (2, 2, -2, 0) (d) none of these

19. Which of the following is incorrect?
(a) $(1, 1, 1, 0) \times (1, 2, -1, 1, 1, 0) = (1, 3, 1, 0)$
(b) $(2, 2, 1, 1) \times (4, 4, 4, 4) = (16, 6, 10, 5)$
(c) $\frac{(1, 2, 4, 1, 4, 0)}{(1, 1, 2, 0)} = (1, 1, 2, 0)$
(d) none of the above

20. $(4, 4, 3,3) \times (2, 2, 1, 1) + (2, 2, 1, 1) - (3, 5, 2, 4)$ equals :
(a) (8, 6, 5, 5, 7, 4, 2, 3, 2, 1)
(b) (8, 6, 7, 5, 1, 4,2, 2, 1, 1)
(c) (8,6,7,5,2, 4, 3,2, 1,1)
(d) none of the above

Directions for question number 21-25 :
If p, q, r, s be the distinct integers such that :
$f(p, q, r, s)$ = maximum of (p, q, r, s)
$g(p, q, r, s)$ = minimum of (p, q, r, s)
$h(p, q, r, s)$ = remainder when $p \times q$ is divided by $r \times s$ if $p \times q > r \times s$.
= remainder when $r \times s$ is divided by $p \times q$ if $r \times s > p \times q$
Also, the same operations are valid with two variable functions of the form $f(p, q)$
Also a function $fgh(p, q, r, s)$
$= f(p, q, r, s) \times g(p, q, r, s) \times h(p, q, r, s)$

21. What is the value of $h(3, 2, 8, 7) \div g(4, 7, 10, 8)$?
(a) 1 (b) 1/2
(c) 24 (d) none of these

22. What is the value of $h(fg(2, 5, 7, 3), 9)$?
(a) 2 (b) 3
(c) 5 (d) none of these

23. What is the value of $h(h(7, 13, 5, 9), h(4, 6, 12, 14)$?
(a) 1 (b) 1/7
(c) 7 (d) not defined

24. If $A = h(3, 7, 6, 5)$, $B = h(16, 11, 13, 3)$ $C = h(9, 4, 8, 7)$, $D = h(19, 14, 18, 7)$, then which of the following is true?
(i) $A > B > C > D$ (ii) $D > A > C$
(iii) $A < D < B$ (iv) $B = C < D$
(a) only (i) is true (b) only (iii) is true
(c) (ii) and (iii) are true (d) (iii) and (iv) are true.

25. If $a_k \times b_k$ is an integral multiple of $c_k \times d_k$ or $c_k \times d_k$ is an integral multiple of $a_k \times b_k$, which of the following is indeterminable ?
(a) $f(g(a_1, b_1, c_1, d_1), h(a_2, b_2, c_2, d_2))$
(b) $h(h(a_1, b_1, c_1, d_1), h(a_2, b_2, c_2, d_2))$
(c) $h(hh(a_1, b_1, c_1, d_1), g(a_2, b_2, c_2, d_2))$
(d) none of the above

Scanned by CamScanner

yousmahboob.wordpress.com

✍ ***Directions for question number 26-32 :*** *Following questions are based on the given information for the following functions* $f(x)$

$f(x) = 2bx + f(-x)$; if $x < 0$

$f(x) = a$ if $x = 0$

$f(x) = b + c - 2cx + f(x-1)$; if $x > 0$

26. $f(8)$ equals :
(a) $a + 8b - 32c$ (b) $a + 8(b - 8c)$
(c) $8(a + b - c)$ (d) none of these

27. $f(-19)$ equals :
(a) $a - 19b + 361c$ (b) $a + 19(b - 19c)$
(c) $a - 19(b + 19c)$ (d) none of these

28. If $a = 15$, $b = 11$, $c = -3$, then $f(7)$ equals :
(a) 239 (b) 115
(c) -147 (d) none of these

29. If $a = 10$, $b = -7$, $c = 6$, then $f(-10)$ equals :
(a) -660 (b) -520
(c) -250 (d) none of these

30. If $a = 4$, $b = -17$ and $c = -18$, then for what value of x, $f(x) = 0$?
(a) 4 or 9 (b) $\frac{1}{2}$ or $\frac{4}{9}$
(c) -1 or 18 (d) none of these

31. If $a = 12$, $b = 10$ and $c = 8$, then for what value of x, $f(x) < 0$?
(a) $\frac{3}{4}$ (b) 1
(c) -2 (d) none of these

32. If $b = -a$, $c = a$, $f(f(1))$ equals :
(a) $a + a^2 + a^3$ (b) $a + a^2 - a^3$
(c) $a - a^2 + a^3$ (d) none of these

✍ ***Directions for question number 33-37 :***

A function $f(z_1, z_2, z_3, \ldots z_n) = f(z_1, z_n) + f(z_2, z_3, \ldots z_{n-1}) + (z_1 + z_2 + \ldots z_n)$; for $n > 0$

$f(y, z) = f(z, 0) + f(0, y)$

$f(y, 0) = y + f(y - 1, 0)$

$f(0, y) = y - f(0, y - 1)$

$f(0, 0) = 1$

33. Find the value of $f(1, 2, 3, 4, \ldots n)$, where n is a perfect cube less than 50 and n is greater than 25 :
(a) 1665 (b) 1089
(c) 729 (d) not defined

34. Find the value of $f(0, 1, 0, 1)$:
(a) 2 (b) 4
(c) 8 (d) none of these

35. Find the value of $f(8, 8, 8, 2, 2, 2)$:
(a) 22 (b) 88
(c) 77 (d) 66

36. Find the value of $f(1, 1, 3, 1, 1, 3)$:
(a) 17 (b) 28
(c) 21 (d) none of these

37. $f(9, 2, k, 0, 9, 4) = 124$, then the value of k is :
(a) 0 (b) 5
(c) 9 (d) none of these

✍ ***Directions for question number 38–40 :*** *A function is defined as follows :*

$f(a_1, a_2, a_3 \ldots a_n) = a_1 2^{n-1} + a_2 2^{n-2} + a_3 2^{n-3} + \ldots a_n 2^0$

The above function is repeated until the value of function reduces to a single digit number.

38. $f(128)$ equals :
(a) 1 (b) 2
(c) 4 (d) 8

39. What is the value of $f[f(888222) + f(113113)]$:
(a) 6 (b) 7
(c) 8 (d) 9

40. $f(9235) + f(9450)$ equals :
(a) 5 (b) 3
(c) 2 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-17.1

1 (a)	2. (c)	3. (c)	4. (a)	5. (a)	6. (d)	7. (b)	8. (a)	9. (c)	10. (b)
11. (c)	12. (b)	13. (b)	14. (c)	15. (d)	16. (c)	17. (d)	18. (d)	19. (c)	20. (c)
21. (a)	22. (d)	23. (a)	24. (b)	25. (c)	26. (c)	27. (c)	28. (d)	29. (d)	30. (b)
31. (d)	32. (a)	33. (c)	34. (c)	35. (b)	36. (d)	37. (b)	38. (c)	39. (c)	40. (c)
41. (b)	42. (b)	43. (b)	44. (b)						

INTRODUCTORY EXERCISE-17.2

1 (c)	2. (a)	3. (c)	4. (c)	5. (a)	6. (c)	7. (a)	8. (b)	9. (a)	10. (d)
11. (c)	12. (a)	13. (c)	14. (d)	15. (d)	16. (b)	17. (b)	18. (d)	19. (a)	20. (a)
21. (b)	22. (b)	23. (c)	24. (a)	25. (b)	26. (a)	27. (d)	28. (a)	29. (b)	30. (b)

INTRODUCTORY EXERCISE-17.3

1 (c)	2. (d)	3. (a)	4. (b)	5. (d)	6. (b)	7. (a)	8. (b)	9. (b)	10. (c)
11. (a)	12. (c)	13. (b)	14. (a)	15. (b)	16. (b)	17. (a)			

LEVEL-1

1 (b)	2. (a)	3. (d)	4. (c)	5. (c)	6. (c)	7. (b)	8. (c)	9. (a)	10. (a)
11. (b)	12. (c)	13. (a)	14. (b)	15. (c)	16. (c)	17. (a)	18. (c)	19. (b)	20. (b)
21. (d)	22. (d)	23. (d)	24. (b)	25. (a)	26. (c)	27. (b)	28. (d)	29. (c)	30. (a)
31. (a)	32. (b)	33. (c)	34. (a)	35. (b)	36. (c)	37. (b)	38. (d)	39. (a)	40. (d)
41. (a)	42. (b)	43. (d)	44. (a)	45. (b)	46. (b)	47. (b)	48. (c)	49. (d)	50. (b)
51. (c)	52. (d)	53. (d)	54. (d)	55. (b)	56. (b)	57. (d)	58. (d)	59. (a)	60. (b)
61. (a)	62. (c)	63. (a)	64. (c)	65. (d)	66. (c)	67. (a)	68. (c)	69. (c)	70. (c)
71. (d)	72. (b)	73. (c)	74. (c)	75. (b)	76. (b)	77. (a)	78. (d)	79. (c)	80. (b)
81. (c)	82. (b)	83. (a)	84. (c)						

LEVEL-2

1 (c)	2. (b)	3. (d)	4. (c)	5. (b)	6. (d)	7. (d)	8. (c)	9. (a)	10. (b)
11. (b)	12. (d)	13. (d)	14. (b)	15. (c)	16. (a)	17. (b)	18. (a)	19. (a)	20. (c)
21. (a)	22. (b)	23. (b)	24. (c)	25. (c)	26. (c)	27. (c)	28. (b)	29. (a)	30. (c)
31. (b)	32. (c)	33. (b)	34. (b)	35. (a)	36. (c)	37. (b)	38. (d)	39. (d)	40. (c)
41. (d)	42. (c)	43. (a)	44. (a)	45. (b)	46. (d)	47. (b)	48. (b)		

FINAL ROUND

1 (d)	2. (b)	3. (c)	4. (d)	5. (b)	6. (a)	7. (c)	8. (d)	9. (b)	10. (b)
11. (d)	12. (c)	13. (b)	14. (b)	15. (c)	16. (b)	17. (a)	18. (b)	19. (b)	20. (b)
21. (b)	22. (c)	23. (d)	24. (b)	25. (b)	26. (b)	27. (c)	28. (a)	29. (b)	30. (b)
31. (c)	32. (b)	33. (d)	34. (b)	35. (c)	36. (b)	37. (b)	38. (d)	39. (b)	40. (a)

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

Introductory Exercise 17.1

1. x is defined for all real numbers (R)
$\therefore$ Domain of x is R

2. $\because \sqrt{x}$ is not defined for negative values of x
hence $x \geq 0$
$\therefore \quad x \in R^+ \cup \{0\}$

3. Since a rational number is not defined if denominator is zero.
Hence $\frac{1}{x}$ is defined for only non zero numbers.
Thus $x < 0$ and $x > 0$
$\Rightarrow (-\infty < x < 0) \cup (0 < x < \infty)$
$\Rightarrow x \in (-\infty, 0) \cup (0, \infty)$
$\Rightarrow x \in R - \{0\}$

4. $\because x$ is defined for all real values
$\therefore |x|$ is also defined for all real values
Hence $|x| \in R$

5. $\because \quad |x| \geq 0 \ \forall \ x \in R$
$\therefore \sqrt{|x|}$ is defined for all real values of x.
Hence, domain of $\sqrt{|x|}$ is R.

6. Since domain of $\sqrt{x}$ is $[0, \infty)$
therefore domain of $|\sqrt{x}|$ is also $[0, \infty)$

7. $\sqrt{x}$ is defined only when $x \geq 0$
but $\frac{1}{\sqrt{x}}$ is defined only when $x > 0$
Since rational expressions are not defined for zero denominator so, $\sqrt{x} \neq 0$
$\therefore$ Domain of $\frac{1}{\sqrt{x}}$ is $(0, \infty)$ *i.e.*, R^+

8. Since x^2 is positive for all values of x
i.e., $x^2 \geq 0 \ \forall \ x \in R$
$\therefore \sqrt{x^2}$ is defined for all values of R
Hence domain of $\sqrt{x^2}$ is R.

9. Since $\sqrt{x}$ is defined for only non-negative real numbers.
Hence domain of $(\sqrt{x})^2$ is $[0, \infty)$

10. $\log_a x$ is defined only for $x > 0$
Hence the domain of $\log_{10} x$ is $(0, \infty)$

11. x^2 is positive for all values of x except at $x = 0$
Since $\log_a b$ is defined only if $b > 0$
$\therefore$ Domain of $\log_{10} x^2$ is $R - \{0\}$

12. $\log_{10} x$ is defined for only $x > 0$
also denominator must be non-zero
$\therefore$ Domain of $f(x) = \frac{1}{\log_{10} x}$ is $R^+ - \{1\}$

13. $\log x$ is defined for only $x > 0$
Also denominator be non-zero real number
Again square root of negative numbers is not defined.
Hence domain of $f(x) = \frac{1}{\sqrt{\log_{10} x}}$ is $1 < x < \infty$ *i.e.*, $R^+ - [0,$

14. $f(x) = \sqrt{3x - 4}$ ($\because \sqrt{k}$ is not defined for $k <$
$\Rightarrow \quad 3x - 4 \geq 0$
$\Rightarrow \quad 3x \geq 4 \Rightarrow x \geq \frac{4}{3}$
$\therefore \quad \frac{4}{3} \leq x < \infty$
$\Rightarrow \quad x \in \left[\frac{4}{3}, \infty\right)$

15. $f(x) = \sqrt{4x - 3} + \sqrt{2x - 6}$
$\therefore \quad 4x - 3 \geq 0$ and $2x - 6 \geq 0$
$\Rightarrow \quad 4x \geq 3$ and $2x \geq 6$
$\Rightarrow \quad x \geq \frac{3}{4}$ and $x \geq 3$
$\therefore \quad x \in [3, \infty)$
(since if $x < 3$, $\sqrt{2x - 6}$ is not defined)
Therefore we consider only common values of domain.



Domain of $\sqrt{4x - 3} = \left[\frac{3}{4}, \infty\right)$



Domain of $\sqrt{2x - 6} = [3, \infty)$

16. $|x| - x > 0 \quad (\because |x| - x \neq 0)$
$\Rightarrow |x| > x$ also $|x| - x > 0$ for the condition of square roo
Since $|x|$ is positive value and $|x|$, x are numerically equ
Therefore $x < 0$
Hence, the domain of $f(x) = \frac{1}{\sqrt{|x| - x}}$ is $(-\infty, 0)$

17. $x \in R$
but $x^2 - 3x + 2 > 0$
$\Rightarrow (x - 1)(x - 2) > 0 \quad (\because x^2 - 3x + 2 \neq 0$
$\Rightarrow x < 1$ and $x > 2$

$\therefore$ Domain of $f(x) = \frac{x}{\sqrt{x^2 - 3x + 2}}$ is $(-\infty, 1) \cup (2, \infty)$

18. $(\sqrt{6 - x} + \sqrt{x - 4}) > 0$
Also $(6 - x) > 0$ and $(x - 4) > 0$
$\Rightarrow \quad 6 > x$ and $x > 4$
$\therefore \quad 4 < x < 6$
$\therefore$ domain of given function is $(4, 6)$.

Scanned by CamScanner

yoursmahboob.wordpress.com

19. $(1-x)>0 \Rightarrow 1>x$

$\Rightarrow x<1$ ...(1)

Also $\log_{10}(1-x) \neq 0$

$\Rightarrow 10^{\circ} \neq (1-x)$

$\Rightarrow 1 \neq 1-x$

$\Rightarrow 0 \neq -x$

$\Rightarrow x \neq 0$ ...(2)

Again $(x+2) \geq 0$

$\Rightarrow x \geq -2$ ...(3)

$\therefore x \in [-2, 0) \cup (0, 1)$

or $x \in [-2, 1) - \{0\}$

or $-2 \leq x < 1$, excluding zero.

20. $f(x) = \dfrac{\log_2(x+3)}{x^2+3x+2}$

$(x+3)>0 \Rightarrow x>-3$ ...(1)

Also $x^2+3x+2 \neq 0$

$\Rightarrow (x+1)(x+2) \neq 0$

$\Rightarrow x \neq -1$ or $x \neq -2$ ...(2)

$\therefore$ Domain of $f(x) = (-3, \infty) - \{-1, -2\}$

or $(-3, -2) \cup (-2, -1) \cup (-1, \infty)$



NOTE 'o' indicates absence of domain
'#' indicates presence of domain on the real number line.

21. Domain of $\sin x$ is R
and Domain of $\cos x$ is also R
$\therefore$ Domain of given function is R

22. $\log_{10} \dfrac{1}{|\sin x|} \geq 0$

$\Rightarrow 10^0 \leq \dfrac{1}{|\sin x|} \Rightarrow 1 \leq \dfrac{1}{|\sin x|}$

$\Rightarrow |\sin x| \leq 1$

$\Rightarrow -1 \leq \sin x \leq 1$

$\Rightarrow x \in R$

but $\dfrac{1}{|\sin x|} > 0$

$\Rightarrow |\sin x| > 0$

$\Rightarrow x \in R$ ($\because |k|$ is always positive)

Again $|\sin x| \neq 0$

$\Rightarrow x \neq n\pi, \quad n \in I$

$\therefore$ Domain of $f(x)$ is $R \sim \{n\pi, n \in I\}$

23. $f(x) = (x^2+x+1)^{-3/2}$

Now $x^2+x+1 \neq 0$

$\Rightarrow \left(x+\dfrac{1}{2}\right)^2 + \dfrac{3}{4} \neq 0$

$\left(x+\dfrac{1}{2}\right)^2$ is always positive for all the values of real numbers and the whole expression is never zero and never negative for any value of R.

Hence domain of $f(x) = (x^2+x+1)^{-3/2}$ is R.

24. $5x-6-x^2>0$

$\Rightarrow x^2-5x+6<0$

$\Rightarrow (x-2)(x-3)<0$

$\Rightarrow 2<x<3$

$\Rightarrow x \in (2, 3)$

25. $y = \log_x 5 = \dfrac{\log 5}{\log x}$

$\log x \neq 0 \Rightarrow x \neq 1$

and $x>0$

$\therefore x \in (0, \infty) \sim \{1\}$

or $x \in (0, 1) \cup (1, \infty)$

26. $f(x) = 9 - \sqrt{9-x^2}$

$\therefore 9-x^2 \geq 0$

$\Rightarrow x^2-9 \leq 0$

$\Rightarrow (x-3)(x+3) \leq 0$

$\Rightarrow -3 \leq x \leq 3$

$\Rightarrow x \in [-3, 3]$

27. $x^2-5x+6 \geq 0$

but $x^2-5x+6 \neq 0$

$\therefore x^2-5x+6>0$

$\Rightarrow (x-2)(x-3)>0$

$\Rightarrow x<2$ or $x>3$

$\Rightarrow x \in (-\infty, 2) \cup (3, \infty)$

or $x \in (-\infty, \infty) - [2, 3]$

28. Clearly $\dfrac{x^2}{1+x^4} \geq 0$ for any $x \in R$

Again $(x^2-1)^2 \geq 0$

$\Rightarrow x^4+1-2x^2 \geq 0$

$\Rightarrow x^4+1 \geq 2x^2$

$\therefore \dfrac{x^2}{1+x^4} \leq \dfrac{x^2}{2x^2}$

$\Rightarrow \dfrac{x^2}{1+x^4} \leq \dfrac{1}{2}$

Hence, the range of f is $\left[0, \dfrac{1}{2}\right]$.

29. Let $y = \dfrac{x^2-2}{x^2-3}$

$\Rightarrow yx^2-3y = x^2-2$

$\Rightarrow x^2(y-1) = 3y-2$

$\Rightarrow x^2 = \dfrac{3y-2}{y-1}$

$\therefore \dfrac{3y-2}{y-1} \geq 0$

$\therefore y \in \left(-\infty, \dfrac{2}{3}\right] \cup (1, \infty)$

30. Let $y = \dfrac{x^2+2x+3}{x}$

$\Rightarrow x^2+(2-y)x+3=0$

$\because x \in R$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore \quad (2-y)^2 - 4\times 1\times 3 \geq 0$

$\Rightarrow \quad y^2 - 4y + 4 - 12 \geq 0$

or $\quad y^2 - 4y - 8 \geq 0$

or $\quad [y-(2-2\sqrt{3})][y-(2+2\sqrt{3})] \geq 0$

$\Rightarrow \quad y \in (-\infty, 2-2\sqrt{3}] \cup [2+2\sqrt{3}, \infty)$

i.e., $\quad y \in R - (2-2\sqrt{3}, 2+2\sqrt{3})$

31. Domain of $f(x) = \sqrt{x^2}$ is R *i.e.*, $x \in (-\infty, \infty)$

Domain of $g(x) = (\sqrt{x})^2$ is $R^+ \cup \{0\}$ *i.e.*, $x \in [0, \infty)$

$\therefore \quad \sqrt{x^2} \neq (\sqrt{x})^2$

Again co-domain of $f(x) = \dfrac{1}{\sqrt{x^2}}$ is $R^+ \sim \{0\}$

and co-domain of $g(x) = \dfrac{x}{x^2}$ is R^+ *i.e.*, $g(x) \in (0, \infty)$

i.e, $\quad g(x) \in (-\infty, 0) \cup (0, \infty)$

$\therefore \quad \dfrac{1}{\sqrt{x^2}} \neq \dfrac{x}{x^2}$

Again, Domain of $f(x) = \log(x-1) + \log(x-2)$ is $(2, \infty)$

and Domain of $g(x) = \log(x-1)(x-2)$ is $(-\infty, 1) \cup (2, \infty)$

$\therefore \quad \log(x-1) + \log(x-2) \neq \log(x-1)(x-2)$

Since in each point domain of definition of $f(x)$ is unequal, therefore the given pairs of functions are not identical.

HINT See the concept of "Equal functions".

32. Domain of $f(x) = \dfrac{1}{\sqrt{|x| - x}}$ is $(-\infty, 0)$

and domain of $g(x) = \dfrac{1}{\sqrt{x - |x|}}$ is ϕ

$\therefore \quad$ dom $f \neq \phi$ and dom $g = \phi$

HINT $\phi \rightarrow$ There is no any single value of x, which satisfy the given function.

33. Dom. of $f(x) = x$ is $(-\infty, \infty)$

Dom. of $g(x) = \sqrt{x^2}$ is $(-\infty, \infty)$, but Range $\equiv [0, \infty)$

Dom. of $h(x) = \dfrac{x^2}{x}$ is $(-\infty, \infty) \sim \{0\}$

$\therefore$ the common domain is $[-0, \infty) \sim \{0\} = R^+$

(Since for every $f(x)$, $g(x)$, $h(x) \in R^+$ the range of each $f(x)$, $g(x)$ and $h(x)$ is same)

34. Dom. $f(x)$ is $R - \{0\}$ *i.e.*, $(-\infty, 0) \cup (0, \infty)$

and Dom. $g(x)$ is R^+ *i.e.*, $(0, \infty)$

$\therefore$ Common domain of $f(x)$ and $g(x)$ is $(0, \infty)$

Hence if $x \in (0, \infty)$, then $f(x) = g(x)$

35. Since $\quad [x] \leq x$ or $x \geq [x]$

$\Rightarrow \quad x - [x] \geq 0$

$\therefore \quad 1 + x - [x] > 0$

$\therefore \quad f(g(x)) = f(1 + x - [x]) = 1$

HINT See the definition of Signum function.

36. $f(x) = 64x^3 + \dfrac{1}{x^3} = \left(4x + \dfrac{1}{x}\right)^3 - 3\cdot 4\left(4x + \dfrac{1}{x}\right)$

So $\quad f(\alpha) = 2^3 - 3\cdot 4\cdot 2 = -16$

Also $\quad f(\beta) = 2^3 - 3\cdot 4\cdot 2 = -16$

Hence (d).

37. Let $\quad y = \dfrac{x}{\sqrt{1+x^2}}$

$\therefore \quad f(f(x)) = f(y) = \dfrac{y}{\sqrt{1+y^2}} = \dfrac{x/\sqrt{1+x^2}}{\sqrt{1+\left(\dfrac{x}{\sqrt{1+x^2}}\right)^2}}$

$= \dfrac{x}{\sqrt{1+2x^2}} = z$ (say)

$\therefore \quad f(f(f(x))) = f(z) = \dfrac{z}{\sqrt{1+z^2}} = \dfrac{x/\sqrt{1+2x^2}}{\sqrt{1+\left(\dfrac{x}{\sqrt{1+2x^2}}\right)^2}}$

$= \dfrac{x}{\sqrt{1+3x^2}}$

38. $f(x) = \dfrac{4^x}{4^x + 2}$

$\therefore \quad f(1-x) = \dfrac{4^{1-x}}{4^{1-x}+2} = \dfrac{2}{2+4^x}$

$\therefore \quad f(x) + f(1-x) = \dfrac{4^x}{4^x+2} + \dfrac{2}{4^x+2} = 1$

Hence (c) is correct

39. $f(x) = 1 - f(1-x)$

$\Rightarrow \quad f(x) + f(1-x) = 1$

Now, $f\left(\dfrac{1}{999}\right) + f\left(\dfrac{2}{999}\right) + \ldots f\left(\dfrac{997}{999}\right) + f\left(\dfrac{998}{999}\right)$

$= \left[f\left(\dfrac{1}{999}\right) + f\left(\dfrac{998}{999}\right)\right] + \left[f\left(\dfrac{2}{999}\right) + f\left(\dfrac{997}{999}\right)\right] + \ldots$

$= \left[f\left(\dfrac{1}{999}\right) + f\left(1 - \dfrac{1}{999}\right)\right] + \left[f\left(\dfrac{2}{999}\right) + f\left(1 - \dfrac{2}{999}\right)\right] + \ldots$

$= 1 + 1 + 1 + \ldots 499$ times $= 499$

40. $f(3) = 9$

$\therefore \quad g(f(3)) = g(9) = 3$

Alternatively: $gof = g(f(x)) = g(x^2) = \sqrt{x^2} = x$

41. Solve through options

Let us consider $f(x) = 3x + 2$

$\therefore \quad g(f(x)) = (3x+2)^2 - (3x+2) + 7$

$\Rightarrow \quad gof(x) = 9(x^2 + x + 1)$

$\Rightarrow \quad \left(\dfrac{1}{9}\right) gof(x) = x^2 + x + 1$

Hence choice (b) is correct.

42. $f(x+1) = \dfrac{(x+1)}{(x+1)+3} = \dfrac{x+1}{x+4}$

43. $\dfrac{1}{f(x+1)} - f\left(\dfrac{1}{x+1}\right) = \dfrac{x+4}{x+1} - \dfrac{1/(x+1)}{1/(x+1)+3}$

$= \dfrac{x+4}{x+1} - \dfrac{1/(x+1)}{(3x+4)/(x+1)}$

$= \dfrac{x+4}{x+1} - \dfrac{1}{(3x+4)} = \dfrac{3(x^2+5x+5)}{3x^2+7x+4}$

Scanned by CamScanner

yoursmahboob.wordpress.com

14. $f(2) = \dfrac{2+1}{2-1} = 3$

$f(f(2)) = f(3) = \dfrac{3+1}{3-1} = 2$

$f(f(f(2))) = f(f(3)) = f(2) = \dfrac{2+1}{2-1} = 3$

$f(f(f(f(2)))) = f(3) = \dfrac{3+1}{3-1} = 2$

$f(f(f(f(f(2))))) = f(2) = \dfrac{2+1}{2-1} = 3$

INTRODUCTORY EXERCISE 17.2

1. Choice (a) is ruled out since the given graph is the graph of GIF (greatest integer function)
Again the graph of $[x]$ is parallel to the graph of $y = x$. But since in the left part (*i.e.*, left of y-axis) all the values of y are positive which are transformed by the modulus.
Alternatively: Go through options and put the values (*e.g.*, $-3, -2, -1, 0, 1, 2, 3$, etc) and then verify the correct option.

2. Best way is to check the option by substituting the values of x *eg.*, $x = -3, -2, -1, 0, 1, 2, 3, \ldots$.

choice (b) is wrong since at $x = 2$, $f(x) = \dfrac{1}{4}$

choice (d) is wrong since at $x = 1$, $f(x) = 0$

choice (c) is wrong since at $x = 2$, $f(x) = \dfrac{1}{8}$

$\therefore$ choice (a) is correct, since at $x = 1$, $f(x) = 1$

at $x = 2$, $f(x) = \dfrac{3}{2}$

at $x = \dfrac{1}{2}$, $f(x) = 0$, etc.

3. Choice (a) is wrong, since graph is even
also at $x = 1$, $e^x = f(x) = 2.714$
choice (d) is wrong since at $x = 0$, $f(x) = 0$
choice (b) is wrong since at $x = 1$, $f(x) = 0$
also at $x = 0$, $f(x)$ is not defined
choice (c) is correct, since at $x = 0$, $f(x) = 1$
at $x = 1$, $f(x) = 2$
at $x = 2$, $f(x) = 4$
at $x = -1$, $f(x) = 2$
at $x = -2$, $f(x) = 4$

4. Choice (a) is wrong since at $x = 1$, $f(x) = 1$
at $x = 2$, $f(x) = 6$
choice (b) is wrong since at $x = 2$, $f(x) = 2$
choice (d) is wrong since at $x = 0$ $f(x) = 0$
choice (c) is correct since at $x = 0$, $f(x) = -2$
at $x = 2$, $f(x) = 0$
at $x = 3$, $f(x) = 4.25$
at $x = -2$, $f(x) = 0$
at $x = -3$, $f(x) = 4.25$

5. **Algebraic solution**
x^2 is always positive $\forall\ x \in R$
$1 - |x-2|$ is positive, if $1 < x < 3 (x - 2 \neq 1)$
but when $1 < x < 3$, $x^2 \in (1, 9)$
and $(1 - |x-2|) \in (0, 1)$
therefore there is no real solution of the given expression.

Graphical solution :

$$\frac{x^2}{1-|x-2|} = 1 \Rightarrow x^2 = 1 - |x-2|$$



Hence it is clear from the graph that there is no real solution, since the two graphs do not cut each other at any point.

6. **Algebraic solution :**

$$\log_{0.5}|x| = 2|x|$$

$$\Rightarrow (0.5)^{2|x|} = |x|$$

$$\Rightarrow \left(\frac{1}{2}\right)^{2|x|} = |x|$$

$$\Rightarrow \left(\frac{1}{2}\right)^{|x|} = |x|^{1/2}$$

$$\Rightarrow x = -\frac{1}{2}, \frac{1}{2}$$

Graphical Solution :



Clearly at $x = -\dfrac{1}{2}$ and $x = \dfrac{1}{2}$ the graphs of $\log_{(0.5)}|x|$ and $2|x|$ intersect each other.
Thus there are two solutions.

Scanned by CamScanner

yoursmahbub.wordpress.com

7.



$$f(x)=\frac{|x|^3+|x|}{1+x^2}$$

8. $$f(x)=f\left(\frac{x+8}{x-1}\right)$$

$$\Rightarrow \quad x=\frac{x+8}{x-1}$$

$$\Rightarrow \quad x^2-2x-8=0$$

$$\Rightarrow \quad x=4,-2$$

Alternatively : Go through options

9. $$g(x)=\sqrt{x^2+1}$$

$$f(g(x))=(\sqrt{x^2+1})^2-1$$

$$\Rightarrow \quad f(g(x))=x^2$$

$$\therefore \quad h(f(g(x)))=h(x^2)=x^2 \qquad (\because h(x)=x,\ x\geq 0)$$

10. $$f(x)=(a-x^n)^{1/n}$$

$$\therefore \quad f(f(x))=(a-(f(x))^n)^{1/n}$$

$$=(a-((a-x^n)^{1/n})^n)^{1/n}$$

$$=(a-(a-x^n))^{1/n}=(x^n)^{1/n}=x$$

11. At $$y=f(x)=\frac{x-1}{x+1}$$

$$\Rightarrow \quad y(x+1)=x-1$$

$$\Rightarrow \quad x=\frac{y+1}{1-y} \qquad ...(1)$$

Now, $$f(f(x))=f\left(\frac{x-1}{x+1}\right)=\frac{\frac{x-1}{x+1}-1}{\frac{x-1}{x+1}+1}=-\frac{1}{x}$$

$$\therefore \quad f(f(ax))=-\frac{1}{ax}=-\frac{1}{a\left(\frac{y+1}{1-y}\right)}$$

$$=\frac{y-1}{a(y+1)}=\frac{f(x)-1}{a(f(x)+1)}$$

12. $$f(x)=\frac{x}{\sqrt{1+x^2}}$$

$$\therefore \quad f(f(x))=\frac{\frac{x}{\sqrt{1+x^2}}}{\sqrt{1+\left(\frac{x}{\sqrt{1+x^2}}\right)^2}}=\frac{x}{\sqrt{1+2x^2}}$$

$$\therefore \quad f(f(f(x)))=\frac{\frac{x}{\sqrt{1+2x^2}}}{\sqrt{1+\left(\frac{x}{\sqrt{1+2x^2}}\right)^2}}=\frac{x}{\sqrt{1+3x^2}}$$

Alternatively : Consider some value for x, then mark the correct option

$$f(2)=\frac{2}{\sqrt{1+4}}=\frac{2}{\sqrt{5}}$$

$$\therefore \quad f(f(2))=f\left(\frac{2}{\sqrt{5}}\right)=\frac{\frac{2}{\sqrt{5}}}{\sqrt{1+\left(\frac{2}{\sqrt{5}}\right)^2}}=\frac{2}{3}$$

$$\therefore \quad f(f(f(2)))=f\left(\frac{2}{3}\right)=\frac{\frac{2}{3}}{\sqrt{1+\left(\frac{2}{3}\right)^2}}=\frac{2}{\sqrt{13}}$$

Now, verify the options.

Consider option (a)

$$f(f(f(2)))=\frac{2}{\sqrt{1+3(2)^2}}=\frac{2}{\sqrt{13}}$$

Hence option (a) is correct.

13. $f(-2.4)=1+|-2.4|$ $(\because -2.4<-1)$

$$f(-2.4)=3.4$$

$$\therefore \quad f(f(-2.4)=f(3.4)=[3.4] \qquad (\because 3.4>-1)$$

$$=3$$

14. Go through options

Let us consider $g(x)=\log x$,

$$\therefore \quad f(x)=x^n$$

and $$g(f(x))=g(x^n)=\log x^n$$

$$=n\log x=ng(x)$$

Hence, choice (d) is correct.

15. Since $f:N\to R$

but $0\notin N$

$\therefore f(0)$ is not defined

Hence (d)

16. Go through options.

Let us consider $f(x)=x^2-2$

$$\therefore \quad f\left(x+\frac{1}{x}\right)=\left(x+\frac{1}{x}\right)^2-2$$

$$=x^2+\frac{1}{x^2}+2-2=x^2+\frac{1}{x^2}$$

Hence choice (b) is correct.

17. $$f(x)=\sqrt{x^5}$$

$$\therefore \quad f(5x)=\sqrt{(5x)^5}=25x^2\sqrt{5x}$$

18. $$h(x)=\frac{1}{x}$$

$$g(h(x))=g\left(\frac{1}{x}\right)=\left(\frac{1}{x}\right)^2$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$f(g(h(x))) = f\left(\left(\frac{1}{x}\right)^2\right) = \left(4\cdot\frac{1}{x^2}\right) - 5$$

$$= \frac{4}{x^2} - 5$$

19. Let $x = 2.6$, then $[x] - \{x\} = 2 - 3 = -1$
and $x = 3.8$, then $[x] - \{x\} = 3 - 4 = -1$
and $x = -3.6$, then $[x] - \{x\} = (-4) - (-3) = -1$
and $x = -7.3$, then $[x] - \{x\} = (-8) - (-7) = -1$
Hence (a) is the correct choice

20. $f(x) = \dfrac{a^x - 1}{x^n(a^x + 1)} = \underbrace{\dfrac{1}{x^n}}_{g(x)} \cdot \underbrace{\dfrac{a^x - 1}{a^x + 1}}_{h(x)}$ (By breaking the function)

$f(x)$ is even since graph of $f(x)$ is symmetric about y-axis.

Now, $h(-x) = \dfrac{a^{-x} - 1}{a^{-x} + 1} = \dfrac{1 - a^x}{1 + a^x} = -h(x)$

i.e., $h(x)$ is an odd function.
Hence, $g(x) \times$ odd function = even function
$\therefore g(x)$ is an odd function
($\because$ odd $\times$ odd = Even but even $\times$ odd = odd)
$\therefore g(x) = \dfrac{1}{x^n}$ is an odd function, which is positive only when

$n = -\dfrac{1}{3}$

21. $f(x) = \ln(x + \sqrt{x^2 + 1})$

$\therefore \quad f(-x) = \ln(-x + \sqrt{(-x)^2 + 1})$

$= \ln(-x + \sqrt{x^2 + 1})$

Here it is not obvious whether f is an odd or even function.
So in such case we check for

$f(x) + f(-x) = 0 \Rightarrow f$ is an odd function

$f(x) - f(-x) = 0 \Rightarrow f$ is an even function

Now, $f(x) + f(-x) = \ln(x + \sqrt{x^2 + 1}) + \ln(-x + \sqrt{x^2 + 1})$

$= \ln((\sqrt{x^2 + 1} + x)(\sqrt{x^2 + 1} - x))$

$= \ln(x^2 + 1 - x^2)$

($\because \ln x + \ln y = \ln x \cdot y$)

$= \ln 1 = 0$ ($\because \ln 1 = 0$)

Hence, f is an odd function.

23. $f(x) = \dfrac{a^x + 1}{a^x - 1}$

$\therefore \quad f(-x) = \dfrac{a^{-x} + 1}{a^{-x} - 1} = \dfrac{1 + a^x}{1 - a^x}$

$\Rightarrow f(x) \neq f(-x)$, hence $f(x)$ is not an even function

Again $f(x) = \dfrac{a^x - a^{-x}}{a^x + a^{-x}}$

$\therefore \quad f(-x) = \dfrac{a^{-x} - a^x}{a^{-x} + a^x}$

$\therefore f(x) \neq f(-x)$, hence $f(x)$ is not an even function

Again $f(x) = x \cdot \dfrac{a^x + 1}{a^x - 1}$

$\therefore \quad f(-x) = (-x)\dfrac{a^{-x} + 1}{a^{-x} - 1} = (-x)\dfrac{\frac{(1 + a^x)}{a^x}}{\frac{1 - a^x}{a^x}}$

$= (-x)\dfrac{1 + a^x}{1 - a^x} = (-x)\dfrac{1 + a^x}{-(a^x - 1)}$

$= x\dfrac{1 + a^x}{a^x - 1} = x \cdot \dfrac{a^x + 1}{a^x - 1}$

$\therefore \quad f(x) = f(-x)$

Hence, $f(x)$ is an even function.

24. $f(x) = \ln\left(\dfrac{1 + x^3}{1 - x^3}\right)$ (ln → natural logarithm)

$\therefore \quad f(-x) = \ln\left(\dfrac{1 + (-x)^3}{1 - (-x)^3}\right) = \ln\left(\dfrac{1 - x^3}{1 + x^3}\right)$

$\therefore \quad -f(-x) = -\ln\left(\dfrac{1 - x^3}{1 + x^3}\right)$

$= \ln\left(\dfrac{1 - x^3}{1 + x^3}\right)^{-1} = \ln\left(\dfrac{1 + x^3}{1 - x^3}\right)$

$\Rightarrow \quad f(x) = -f(-x)$

Hence $f(x) = \ln\left(\dfrac{1 + x^3}{1 - x^3}\right)$ is an odd function.

25. $f(x) = \log\dfrac{(1 - x)}{(1 + x)}$ is an odd function.

$f(x) = x \cdot \dfrac{a^x + 1}{a^x - 1}$ is an even function.

$f(x) = \log[x + \sqrt{(1 + x^2)}]$ is an odd function.

$f(x) = \sqrt{(1 + x + x^2)} - \sqrt{(1 - x + x^2)}$ is an odd function

26. $f(x) = \sqrt[3]{(1 - x^2)} + \sqrt[3]{(1 + x^2)}$

$\therefore \quad f(-x) = \sqrt[3]{(1 - (-x)^2)} + \sqrt[3]{1 + (-x)^2}$

or $\quad f(-x) = \sqrt[3]{1 - x^2} + \sqrt[3]{1 + x^2}$

$\Rightarrow \quad f(x) = f(-x)$

Hence $f(x)$ is even function

27. $f(x) = 2^{-x^2}$

$\therefore \quad f(-x) = 2^{-(-x)^2} = 2^{-x^2}$

$\because f(x) = f(-x)$, hence $f(x)$ is an even function

Again $\quad f(x) = 2^{x - x^4} = \dfrac{2^x}{2^{x^4}}$

$\therefore \quad f(-x) = 2^{-x-(-x)^4} = 2^{-x-x^4} = \dfrac{1}{2^{x + x^4}}$

$\because f(x) = -f(-x)$, Hence $f(x)$ is not an odd function.

Again $f(x) = \cos x$ is an even function
Hence (d).

28. $f(x) = \dfrac{x}{e^x - 1} + \dfrac{x}{2} + 1$

$\therefore \quad f(-x) = \dfrac{-x}{e^{-x} - 1} + \dfrac{(-x)}{2} + 1$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{-xe^x}{1-e^x} - \frac{x}{2} + 1$$

$$= \frac{xe^x}{e^x - 1} - \frac{x}{2} + 1$$

If $f(x) - f(-x) = 0$, then $f(x)$ is an even function.

$$\therefore \quad f(x) - f(-x) = \left(\frac{x}{e^x - 1} + \frac{x}{2} + 1\right) - \left(\frac{xe^x}{e^x - 1} - \frac{x}{2} + 1\right)$$

$$= \frac{x(1 - e^x)}{(e^x - 1)} + \left(\frac{x}{2} + \frac{x}{2}\right) + (1 - 1)$$

$$= \frac{-x(e^x - 1)}{(e^x - 1)} + x + 0$$

$$= -x + x$$

$f(x) - f(-x) = 0$, hence the given function is an even function.

30. $f(x) = \frac{1}{1-x}$

$$\therefore \quad g(x) = f(f(x)) = f\left(\frac{1}{1-x}\right)$$

$$\Rightarrow \quad g(x) = \frac{1}{1 - \left(\frac{1}{1-x}\right)} = \frac{1-x}{-x} = \frac{x-1}{x}$$

$$\therefore \quad h(x) = f(f(f(x))) = f(g(x)) = f\left(\frac{x-1}{x}\right)$$

$$\Rightarrow \quad h(x) = \frac{1}{1 - \left(\frac{x-1}{x}\right)}$$

$$h(x) = x$$

$$\therefore \quad f(x) \cdot g(x) \cdot h(x) = \frac{1}{1-x} \times \frac{(1-x)}{-x} \times x = -1$$

INTRODUCTORY EXERCISE 17.3

1. $f(x) = x^2$

$f(1) = 1$

and $f(-1) = 1$

$\Rightarrow f(x)$ is many-one

$\because \quad f : R \to R$

$(x) \quad (y)$

but the negative values of y are not the actual output (or images) of any element of x. Hence function is into.

2. $f : R \to R^+ \cup \{0\}$

$f(x) = x^2$

$f(1) = 1$

and $f(-1) = 1$

Hence $f(x)$ is many-one

again $f : \underset{(x)}{R} \to \underset{(y)}{R^+ \cup \{0\}}$

Since each element of y is the actual output of some element of x therefore function is onto.

3. $f : R^+ \to R$

$f(x) = x^2 \Rightarrow f(0) = 0, f(1) = 1, f(2) = 4$ etc.

Since non-positive values of x (*i.e.*, input) are not in the domain therefore no two inputs produce same output hence function is one-one.

Also function is into since non-positive values of y are not the images (output) of any value of x (*i.e.*, input)

4. $f : R^+ \to R^+$

$f(x) = x^2$

$f(1) = 1$

$f(2) = 4$

$f(3) = 9$ etc.

Since there are no two inputs which produce same output hence the function is one-one.

Again the function is onto since every element of y is an actual output/image of some element of x.

5. f is not one-one as $f(0) = 0$ and $f(-1) = 0$

f is not onto as for $y = 1$, there is no $x \in R$ such that $f(x) = 1$

If there is such a $x \in R$ then $e^{|x|} - e^{-x} = e^x + e^{-x}$ clearly $x \neq 0$ ($\because$ at $x = 0$, $f(x) \neq 1$)

Again for $x > 0$, this equation gives $-e^{-x} = e^{-x}$ which is not possible

Again for $x < 0$, the above equation gives $-e^{-x} = e^x$, which is also not possible.

6. If $n(A) = m$ and $n(B) = n \geq m$, then the number of one-one functions from A to B is ${}^nP_m : n > m$

$${}^nP_m = \frac{n!}{(n-m)!}$$

Hence $n = 5$ and $m = 3$

$\therefore$ Number of one-one function from A to B

$$= {}^5P_3 = \frac{5!}{2!} = \frac{5 \cdot 4 \cdot 3 \cdot 2 \cdot 1}{2} = 60$$

7. Let $x, y \in A$ be such that $f(x) = f(y)$

$$\Rightarrow \quad \frac{x-2}{x-3} = \frac{y-2}{y-3}$$

$$\Rightarrow \quad xy - 3x - 2y + 6 = xy - 3y - 2x + 6$$

$$\Rightarrow \quad -2y + 3y = 3x - 2x$$

$$\Rightarrow \quad x = y$$

Hence f is one-one.

Let $y \in B$, we want to got $x \in A$ such that $f(x) = y$,

i.e., $\frac{x-2}{x-3} = y$

$\Rightarrow x = \frac{3y-2}{y-1} \in A$, Hence f is onto

Thus f is bijective.

8. For any $x, y \in N$, we have

$f(x) = f(y) \Rightarrow 2x + 3 = 2y + 3 \Rightarrow x = y$

Scanned by CamScanner

yoursmahboob.wordpress.com

Also, f is not surjective

$\because 1 \in N$ does not have its pre image.

9. We have, $f(x) = (x-1)(x-2)(x-3)$

$\Rightarrow f(1) = f(2) = f(3) = 0$

$\Rightarrow f(x)$ is not one-one

For every $y \in R$, there exists $x \in R$ such that $f(x) = y$. Therefore f is onto.

Hence $f : R \to R$ is onto but not one-one.

10. Since $x - [x] = 0$ for all integral values of x.

Therefore, the function is many-one and therefore inverse function is not defined.

11. $y = x^2 + 2 \Rightarrow x^2 = y - 2$

$\Rightarrow x = \sqrt{y-2}$

$\Rightarrow f^{-1}(x) = \sqrt{x-2}$

12. $y = 5^x \Rightarrow \log_5 y = x$

$\Rightarrow x = \log_5 y$

$\Rightarrow f^{-1}(x) = \log_5 x$

13. $y = \dfrac{x}{x+1} \Rightarrow yx + y - x = 0$

$\Rightarrow x(y-1) = -y$

$\Rightarrow x = -\dfrac{y}{y-1} = \dfrac{y}{1-y}$

$\Rightarrow f^{-1}(x) = \dfrac{x}{1-x}$

14. $y = \dfrac{x-1}{x+1} \Rightarrow yx + y = x - 1$

$\Rightarrow yx - x = -(y+1)$

$\Rightarrow x(y-1) = -(y+1)$

$\Rightarrow x = \dfrac{-(y+1)}{(y-1)} = \dfrac{y+1}{1-y} = \dfrac{1+y}{1-y}$

$\Rightarrow f^{-1}(x) = \dfrac{1+x}{1-x}$

15. Let $f(x) = y = x(2-x)$

$\Rightarrow x^2 - 2x - y = 0$

$\Rightarrow x = \dfrac{2 \pm 2\sqrt{1-y}}{2} = 1 \pm \sqrt{1-y}$

But $x < 1$

So $x = 1 - \sqrt{1-y}$

$\therefore f^{-1}(x) = 1 - \sqrt{1-x}$

16. $y = x^2 - x + 1$

$\Rightarrow y = x^2 - x + \dfrac{1}{4} + \dfrac{3}{4}$

$\Rightarrow y = \left(x - \dfrac{1}{2}\right)^2 + \dfrac{3}{4}$

$\Rightarrow y - \dfrac{3}{4} = \left(x - \dfrac{1}{2}\right)^2$

$\Rightarrow \left(x - \dfrac{1}{2}\right) = \sqrt{y - \dfrac{3}{4}}$

$\Rightarrow x = \sqrt{y - \dfrac{3}{4}} + \dfrac{1}{2}$

$\Rightarrow y = \sqrt{x - \dfrac{3}{4}} + \dfrac{1}{2}$

17. $f(x) + f^{-1}(x) = (x^2 - x + 1) + \sqrt{x - \dfrac{3}{4}} + \dfrac{1}{2}$

$= \left(\dfrac{3}{4}\right)^2 - \dfrac{3}{4} + 1 + \sqrt{\dfrac{3}{4} - \dfrac{3}{4}} + \dfrac{1}{2}$

$= \dfrac{9}{16} + \dfrac{1}{4} + \dfrac{1}{2}$

$= \dfrac{9 + 4 + 8}{16} = \dfrac{21}{16}$

LEVEL 1

1. $P(3, 5) = 3 \times 5 = 15$

$S(5, 3) = 5 - 3 = 2$

$D(P(3, 5)), S(5, 3) = D(15, 2) = 15 + 2 = 17$

2. $P(S(10, 6), 30)) = P(4, 30) = 120$

3. $20 \# (-43)$ ($\because 21 @ 22 = -43$)

We cannot determine further the value of $20 \# (-43)$ since we don't know $a \# b$ takes what value in case of negative product as a, b is defined only for natural numbers. Hence (d)

4. $(a \# a) @ (a @ a)$

Since, it is given that a and b are natural numbers. Two cases arise.

Case I. a is even

$a \# a = a^2 - a^2 = 0$

$a @ a = a^2$

$\therefore 0 @ a^2 = 0$ ($\because 0 + a^2$ is even)

Case II. a is odd

$a \# a = a^2$, which is odd

$a @ a = a^2$

$\therefore a^2 @ a^2 = a^4$ ($\because a^2 + a^2$ will be even)

Hence (c) is correct.

5. $(p \# q) - (q @ p)$

Since p is even and q is odd

$p \# q = p^2 - q^2$

$q @ p = q^2 - p^2$

$\therefore p^2 - q^2 - (q^2 - p^2)$

$= 2p^2 - 2q^2 = 2(p^2 - q^2)$

6. $M(7, N(9, 4)) = M(7, (9^2 + 4^2 - 9.4))$

$= M(7, 61) = 7^2 + 61^2 + 7 \cdot 61 = 4197$

7. $f(x) = x^3 - x^2$

$\therefore f(x+1) = (x+1)^3 - (x+1)^2$

$= (x+1)^2 (x + 1 - 1) = (x+1)^2 (x)$

8. $[(5 \cup 4) \vee\vee (2 \cup\cup\cup 3)] \cup (8 \vee 3) = [1 \vee\vee 8] \cup (5) = 8 \cup 5 = 3$

9. $2 \cup\cup 8 = 2 \times 8 = 16$

and $2 \cup\cup\cup 4 = 2^4 = 16$

Hence (a) is true.

Scanned by CamScanner

yoursmahboob.wordpress.com

10. $a \cup b = a \vee b$ if $a \geq b$

$a \vee b = a \cup b$ if $a < b$

$\therefore\ a \cup b = a \vee b$ for all real values.

11. $(20 @ 4) \# 35 = 576 \# 35$

$= (541)^2 = 292681$

12. $12 \# (14 @ (12 \# 13)) = 12 \# (14 @ 1)$

$= 12 \# 225 = (-213)^2 = 45369$

13. $(9 \# 7) @ (21 \# 5) = 4 @ 256$

$= (260)^2 = 67600$

14. $(2 @ 2) + (3 \# 3) - (4 @ 4) + (5 \# 5)$

$= 16 + 0 - 64 + 0 = -48$

15. $$\frac{XAT\,[MAT\,\{2,\ CAT\,(3,\ XAT\,[3,\ 2])\},\ 5]}{CAT\,[4,\ XAT\,\{MAT\,(2,\ -5),\ 4\}]}$$

$$= \frac{XAT\,[MAT\,\{2,\ CAT\,(3,\ 2)\},\ 5]}{CAT\,[4,\ XAT\,\{1, 4\}]}$$

$$= \frac{XAT\,[MAT\,\{2,\ 9\},\ 5]}{CAT\,[4,\ 0]}$$

$$= \frac{XAT\,[6,\ 5]}{1} = 5$$

16. $$\frac{XAT\,(3, 5)}{MAT\,(3, 5)} = \frac{2}{1} = 2,\ \text{hence true}$$

and $$\frac{XAT\,(-3, -5)}{MAT\,(-3, -5)} = \frac{2}{1} = 2,\ \text{hence true}$$

Thus, (c) is correct.

17. $r\,(16, 7) - 2 = 2 - 2 = 0$

18. $g(4.7) - l(2) = 5 - 2 = 3$

19. $\because$ Dividend = Divisor × Quotient + Remainder

$\therefore\quad x = y \times k + r$ (k is a quotient and $k \in I$)

But $$k = I\left(\frac{x}{y}\right)$$

$\therefore\quad r = x - yk$

$\Rightarrow\quad r = x - \left[y \cdot I\left(\frac{x}{y}\right)\right]$

20. $2 \# ((7 @ (4 \# 5)) @ 3) = 2 \# ((7 @ 14) @ 3)$

$= 2 \# (70 @ 3)$

$= 2 \# 152 = 306$

21. (i) $\begin{cases} p \# q = p \# 2p = 5p \\ q \# p = 2p \# p = 4p \end{cases}$ ($\because p + q$ is even)

(ii) $p @ q = p @ 3p = 0$ ($\because p + 3p = 4p$ is even)

(iii) $p @ q = p @ 2p$ ($p + 2p$ is odd)

$= 2p \# 4p$ ($2p + 4p = 6p$ is even)

$= 2p + 8p$

$= 10p$, which is even

Hence (ii) and (iii) are true

Thus (d) is correct.

22. $6 @ 2 = 18 - 2 = 16$

$12 \# 2 = 12 + 4 = 16$

Hence (i) is true

Again $6 \# 3 = 12 @ 6 = 36 - 6 = 30$

$(14 @ 12) + (2 @ 6) = 30 + 0 = 30$

Hence (ii) is true

Again $(6 @ 2) + (6 \# 3) = 16 + 30 = 46$

$(12 \# 2) + (14 @ 12) - (2 @ 6) = 16 + 30 - 0 = 46$

Hence (iii) is also true

Thus (d) is correct option.

23. $\text{Max}\,[(2 \# 3)\ \$\ (3 \# 4),\ (3 \# 4)\ \$\ (4\ \$\ 4)]$

$= \text{Max}\,[(6\ \$\ 12),\ (12\ \$\ 33)]$

$= \text{Max}\,[181, 1234]$

$= |181 + 1234| = 1415$

24. $\text{Max}\,[\text{Min}\,((1\ \$\ 2),\ (2\ \$\ 3)),\ \text{Max}\,((3 \# 4),\ (4 \# 5))]$

$= \text{Max}\,[\text{Min}\,(6,\ 14),\ \text{Max}\,(12,\ 20)]$

$= \text{Max}\,[8, 32] = 40$

25. $\text{Min}\,[(1 \# 2)\ \$\ 3,\ 4 \# (5\ \$\ 6)]\ \$\ \text{Max}\,[(6 \# 7),\ (7 \# 8)]$

$= \text{Min}\,[(2\ \$\ 3),\ (4 \# 62)]\ \$\ \text{Max}\,[42, 56]$

$= \text{Min}\,[14, 77]\ \$\ [98]$

$= 63\ \$\ 98 = 13574$

26. $9 \Delta 3 = 9^3 + 9 \times 3 + \frac{9}{3}$

$= 729 + 27 + 3 = 759$

27. $3 \# 4 * 5 + 3 * 4 \# 5$

$= 3^4 \times 5 + (3 \times 4)^5$

$= 81 \times 5 + (12)^5$

$= 405 + 248832 = 249237$

28. $f(2 \# 3) \# g(3 \# 4) = f(17) \# g(145)$

$= 255 \# 290$

$= 255^{290} + 290^{255}$

29. $f(g(2 \# 3)) + g(f(1 \# 2)) = f(g(17)) + g(f(3))$

$= f(34) + g(3)$

$= 1088 + 6 = 1094$

30. $(5 \oplus 6) - (6 @ 3) + (2 * 4) = 91 - (-9) + 56$

$= 91 + 9 + 56 = 156$

31. $(((1 \oplus 2) * 3) @ 20) = ((7 * 3) @ 20)$

$= (420 @ 20)$

$= 160000 - 8400$

$= 151600$

32. $(3\,D\,4)\,D\,(12\,D\,5) = \left(\frac{3}{4}\right) D \left(\frac{5}{12}\right) = \frac{\frac{5}{12}}{\frac{3}{4}} = \frac{5}{9}$

33. $(12\,D\,60)\,E\,(2C\,10) = \left(\frac{1}{5}\right) E \left(\frac{1}{5}\right) = \frac{1}{25}$

34. $30 + 20 - 4 \times 6 = 30 \times 20 \div 4 + 6$

$= 30 \times 5 + 6 = 156$

35. $50/40 - 5 + 4 \times 54$

$= 50 - 40 \div 5 \times 4 + 54 = 50 - 8 \times 4 + 54$

$= 50 - 32 + 54 = 72$

36. $(5 \wedge 5) \times (4 \wedge 4) / (3 \wedge 3) \times (2 \wedge 2) / (1 \wedge 1)$

$= (5^5) + (4^4) - (3^3) + (2^2) - (1^1)$

$= 3125 + 256 - 27 + 4 - 1 = 3357$

Scanned by CamScanner

yoursmahboob.wordpress.com

37. $[(x^2 \times y^2) - (x+y)^2 + [(x+y)^3 - \{(x/y)^2 \times 2 + x + y\}]$
$= [(x^2+y^2) \div (xy)^2] \times [(xy)^3 \div \{(x-y)^2 + 2xy\}]$
$= \left[\frac{x^2+y^2}{(xy)^2}\right] \times \left[\frac{(xy)^3}{(x-y)^2+2xy}\right]$
$= \left[\frac{(x^2+y^2)}{(xy)^2} \times \frac{(xy)^3}{(x^2+y^2)}\right] = xy$
$= x + y$ (In Devic Mathematics)

38. $a + a + a - a + a + a / a + a - a$
$= a \times a \times a \div a \times a \times a - a \times a \div a$
$= a^3 \div a^3 - a^2 \div a = 1 - a$
$= \frac{1}{a}$ (In Devic maths)

39. $[(2 \Delta 3) \Delta (-2 \Delta 3)] = [(2-3) \Delta (-2+3)]$
$[(-1) \Delta (1)] = -1 + 1 = 0$

40. $\because \quad a \Delta a = 0 \; \forall \; a \in R$
Given $a > 0$
$b > 0$
If $(a \Delta b) \Delta (a \Delta (-b)) = (a-b) \Delta (a-b) \quad (\because a \times -b < 0)$
$= 0$

Again if $b < 0$, then
$(a \Delta b) \Delta (a \Delta (-b))$ ($\because b$ is negative, $\therefore -b$ is positive)
$= (a+b) \Delta (a+b) = 0$

Hence, (d).

41. $f(x) = x^3 + 3x^2 + 3x$
$\therefore f(x+1) = (x+1)^3 + 3(x+1)^2 + 3(x+1)$
$= x^3 + 1 + 3x(x+1) + 3(x^2 + 1 + 2x) + 3x + 3$
$= x^3 + 1 + 3x^2 + 3x + 3x^2 + 3 + 6x + 3x + 3$
$= x^3 + 6x^2 + 12x + 7$

42. $\frac{(4 \# 2) @ (9 \# (-1))}{(2 @ 3) \# (5 @ 2)} = \frac{3 @ 1}{0 \# 9} = \frac{2}{-1} = -2$

43. Solve the options as per the directions.

44. Since, f_4 can assume negative values also, but f_1, f_2 and f_3 always give positive values only.
Hence choice (b), (c) and (d) are not possible.

45. $lt\,(8.3) - gt\,(5.3) + lt\,(6.8) + gt\,(9.4)$
$= 9 - 5 + 7 + 9 = 20$

46. $\Delta(3, 2) - \Delta(2, 3) + gt\,(4.8) - lt\,(2.7) + \Delta(4, 5)$
$= 2 - 2 + 4 - 3 + 4 = 5$

47. $a = \frac{p+q}{2}$, $b = \frac{lt\,(p) + qt\,(q)}{2}$

Now, $lt\ p = p + k; \quad 0 \le k \le 1$
$gt\ q = q - m; \quad 0 \le m \le 1$ where $p, q \in I$

Also $k + m = 1$ (Actually it is just less than 1)

$\therefore \quad (a-b) = \frac{p+q}{2} - \frac{(p+k)+(q-m)}{2}$

$\Rightarrow \quad (a-b) = \frac{p+q}{2} - \frac{p+q+k-m}{2}$

$\Rightarrow \quad (a-b) = \frac{k-m}{2}$

Now, $(a-b) = \frac{k-(1-k)}{2} \quad (\because k+m=1)$
$= k - \frac{1}{2}$

and $(a-b) = \frac{(1-m)-m}{2} \quad (\because k+m=1)$
$= \frac{1}{2} - m$
$(a-b) = k - \frac{1}{2}$

$\Rightarrow \quad \frac{1}{2} \le (a-b) \le \frac{1}{2} \quad (\because 0 \le k \le 1)$

(Similarly $-\frac{1}{2} \le (a-b) \le \frac{1}{2}$, since $0 \le m \le 1$)

NOTE The correct result (In practical) is $-\frac{1}{2} < (a-b) < \frac{1}{2}$ since $0 \le k < 1$ and $0 \le m < 1$.

48. $(a @ b)(b \# a) = \frac{a}{a+b} \times \frac{a+b}{b} = \frac{a}{b}$

Hence (c) is correct.

49. $b \# a - a @ b = \frac{(a+b)}{b} - \frac{a}{(a+b)} = \frac{(a+b)^2 - ab}{b(a+b)}$
$= \frac{a^2 + b^2 + 2ab - ab}{b(a+b)}$
$= \frac{a^2 + b^2 + ab}{b(a+b)}$

50. $mn\,(md\,(-2), mx\,(5, mn\,(-2, md\,(5))))$
$= mn\,(2, mx(5, mn\,(-2, 5)))$
$= mn\,(2, mx\,(5, -2)) = mn\,(2, 5) = 2$

51. $md\,(mn\,(-2, mx\,(md(5), mn\,(-2, -7))))$
$= md(mn\,(-2, mx\,(5, -7)))$
$= md\,(mn\,(-2, 5)) = md\,(-2) = 2$

52. $((1 @ (2 \Delta 3)) \# 4) = ((1 @ ((2 @ 3) - (2 \# 3)) \# 4))$
$= ((1 @ (45 - (-3)) \# 4$
$= ((1 @ 48) \# 4)$
$= (4704 \# 4) = 88416400$

53. $(1 @ 1) \Delta (2 \# 2) = 4 \Delta 0$
$= (4 @ 0) - (4 \# 0) = 0 - 0 = 0$

54. $(a \Delta b) + (a \# b) = (a^2 + b^2) + (|a^2 - b^2|)$

Case I. When $(a^2 - b^2)$ is positive
$(a^2 + b^2) + (a^2 - b^2) = 2a^2$

Case II. When $(a^2 - b^2)$ is negative
$(a^2 + b^2) - (a^2 - b^2) = 2b^2$

Hence we cannot determine the required value.

HINT $|k| \Rightarrow \pm k$

55. $[(a \# b) \div (a @ b)]^2 - 2(a * b)$
$= [|a^2 - b^2| \div |a - b|]^2 - 2ab \quad (\because |k| \ge$
$= (|a+b|)^2 - 2ab$
$= a^2 + b^2 = a \Delta b$

Scanned by CamScanner

yoursmahboob.wordpress.com

56. Consider $g(x) = e^x$ (from the given options)

$\therefore \quad e^x = g(f(x))$

$\Rightarrow \quad e^x = g \log (g(x))$

$\Rightarrow \quad e^x = g \log (e^x)$

$\Rightarrow \quad e^x = g(x)$

$\Rightarrow \quad e^x = e^x$

Hence, choice (b) is correct.

57. Going through options, we find that none of the choices (a), (b) and (c) satisfy the relation, hence (d)

58. None of the options (a), (b) and (c) satisfy the given conditions.

59. $g[f(x) - f[g(x)] = g(2x + 3) - f(9x + 6)$

$= [9(2x + 3) + 6] - [2(9x + 6) + 3]$

$= [18x + 27 + 6] - [(18x + 12) + 3] = 18$

60. $f(f(-2)) = f(8 - 6 + 1) \quad (\because -2 < -1)$

$= f(3)$

$= (9 + 6 + 2) \quad (\because 3 > -1)$

$= 17$

61.

$x^2 = 4 \Rightarrow x = \pm 2$

$y^2 = 9 \Rightarrow y = \pm 3$

	(2, 3)	(−2, 3)	(−2, −3)	(2, −3)
$f(x, y)$ =	5	1	−5	−1
$g(x, y)$ =	−3	−7	−1	3
$F(f(x, y))$ =	10	10	−2	−2
$G(g(x, y))$ =	2	−6	−6	2

Also, $|F(f(x, y))| = |G(g(x, y))|$, which is true for $x = 2$ and $y = -3$

$\therefore \quad x + y = -1$

62. Let $x = 8, \quad y = 9$

$\therefore \quad [x] = 7$ and $\{y\} = 10$

$\therefore \quad g(x, y) = -3$

Again if $x = 9$ and $y = 8$, then

$[x] = 8$ and $\{y\} = 9 \quad \therefore g(x, y) = -1$

Hence (c) is correct choice.

HINT There are two cases (i) when $x < y$ (ii) when $x > y$

Alternatively : Let $x = n \therefore y = n + 1$

$\therefore \quad g(x, y) = (n - 1) - (n + 1 + 1) = -3$

Also, if $x = n, \quad y = n - 1$

$g(x, y) = (n - 1) - (n - 1 + 1) = -1$

Hence (c).

63. $f(x, y) = x + 1 + y - 1 = x + y$

$g(x, y) = x - 1 - y - 1 = x - y - 2$

$F(f(x, y)) = x + y + 1 - x + y + 2 + 1 = 2y + 4$

$G(g(x, y)) = x + y - 1 + x - y - 2 + 1 = 2x - 2$

Hence, only (a) is false.

64. $F(f(x, y)) = -f(x, y)$

$G(f(x, y)) = -F(f(x, y)) = f(x, y)$

$\therefore f(G(f(1.2, 1.3)), f(F(f(0, 1)), G(f(0.8, 0.4))))$

$= f(f(1.2, 1.3)), f(-f(0, 1)), f(0.8, 0.4)))$

$= f(\{2.5\}), f(-(1)), [1.2]))$

$= f(3, f(-1, 1)) = f(3, 0)$

$= 3$, hence (c) is correct.

65. $F(f(x, y)) + G(f(x, y)) = 0$

Hence (d) is correct.

66. $f(1.1, 1.2) \times G(f(1.1, 1.2)) = f(1.1, 1.2) \times f(1.1, 1.2)$

$= [2.3] \times [2.3] = 2 \times 2 = 4$

67. $f(g(x)) = f\left(x + \frac{1}{x}\right) = \frac{1}{x + \frac{1}{x}} = \frac{x}{x^2 + 1}$

$g(f(x)) = g\left(\frac{1}{x}\right) = \frac{1}{x} + x = \frac{x^2 + 1}{x}$

$\therefore \quad f(g(x)) \cdot g(f(x)) = \frac{x}{x^2 + 1} \times \frac{x^2 + 1}{x} = 1$

68. $g(f(x)) = g(f(2)) = g(13) = 29$

$\because \quad f(2) = 2 \cdot (2)^2 + 7(2) - 9 = 13$

and $\quad g(13) = 2 \times 13 + 3 = 29$

69. $f(f(f(f(f(2))))) = f(f(f(f(3)))) \quad \left(\because f(2) = \frac{2+1}{2-1} = 3\right)$

$= f(f(f(2))) \quad \left(\because f(3) = \frac{3+1}{3-1} = 2\right)$

$= f(f(3)) = f(2) = 3$

✍ ***Solutions for question number 70 and 71 :***

$f(x) = 1 - h(x) \quad ...(1)$

$g(x) = 1 - k(x) \quad ...(2)$

$h(x) = f(x) + 1 \quad ...(3)$

$j(x) = g(x) + 1 \quad ...(4)$

$k(x) = j(x) + 1 \quad ...(5)$

From (1) and (3)

$f(x) + h(x) = 1 - h(x) + f(x) + 1$

$\Rightarrow \quad h(x) = 1 \quad ...(6)$

$\Rightarrow \quad f(x) = 0 \quad ...(7)$

From (2) and (4)

$g(x) = 1 - k(x) = 1 - (j(x) + 1)$

$g(x) = -j(x) \quad ...(8)$

From (4) and (8)

$j(x) - g(x) = 1$

and $\quad g(x) = -j(x)$

$\Rightarrow \quad j(x) = \frac{1}{2} \quad ...(9)$

$\therefore \quad g(x) = -\frac{1}{2} \quad ...(10)$

$\therefore \quad k(x) = j(x) + 1 = \frac{3}{2} \quad ...(11)$

Hence $\quad f(x) = 0$

$g(x) = -\frac{1}{2}$

$h(x) = 1$

$j(x) = \frac{1}{2}$

$k(x) = \frac{3}{2}$

Thus all the functions are constant.

Scanned by CamScanner

yoursmahboob.wordpress.com

70. $\dfrac{f(j(x))+k(h(x))}{h(k(x))+f(j(x))}=\dfrac{\frac{1}{2}+\frac{3}{2}}{1+0}=\dfrac{2}{1}=2$

71. $\dfrac{1+\frac{1}{2}+\frac{3}{2}}{\left(0+\frac{1}{2}+\frac{3}{2}\right)\left(0\cdot\frac{1}{2}\cdot\frac{3}{2}\right)}=\dfrac{3}{0}=\infty$

i.e., not defined

72. Since, odd function + odd function = odd function
and (odd function) (odd function) = even function.

73. Even (Odd) = Even
and Odd (Even) = Even

74. y is maximum when $x^2+2=6-3x$
i.e., $x^2+3x-4=0$
$\Rightarrow \quad x^2+4x-x-4=0$
$\Rightarrow \quad x(x+4)-1(x+4)=0$
$\Rightarrow \quad x=1 \quad \text{or} \quad x=-4$
$\therefore$ at $x=1$, $y=3 (\because x>0)$

75. $p^2\times q^2\times r^2$ is maximum when $p^2=q^2=r^2=\dfrac{1}{3}$

$\therefore \quad (pqr)^2_{\max}=\dfrac{1}{27}$

$\Rightarrow \quad (pqr)_{\max}=\dfrac{1}{3\sqrt{3}}$

76. $\dfrac{g(x,y,z)}{j(x,y,z)}=\dfrac{3}{3}=1$

77. $\dfrac{(m(x,y,z)-f(x,y,z))}{h(x,y,z)\times k(x,y,z)\times l(x,y,z)}=\dfrac{3-4}{5\times 2\times 1}=\dfrac{-1}{10}$

78. $\dfrac{f(x,y,z)+h(x,y,z)-g(x,y,z)}{j(x,y,z)}=\dfrac{4+5-3}{3}=2>1$

79. $C(1,2,3)=\max(A(1,2,3), B(1,2,3))$
$=\max(3,2)=3$

80. $D(0,1,2)=\min(A(0,1,2), B(0,1,2))$
$=\min(1,2)=1$

81. $A(2,3,4)+B(2,3,4)=5+2=7$

82. $C(0,1,D(1,2,3))=C(0,1,\min(A(1,2,3), B(1,2,3)))$
$=C(0,1,\min(3,2))=C(0,1,2)$
$=\max(A(0,1,2), B(0,1,2))$
$=\max(1,2)=2$

83. $D(1,2,C(0,1,2))=D(1,2,2) \qquad (\because C(0,1,2)=2)$
$=\min(A(1,2,2), B(1,2,2))$
$=\min(3,1)=1$

84. $|x+5|=8$
$\Rightarrow \quad x=3 \quad \text{and} \quad x=-13$
and $9-|x-4|=y=f(x)$
for $x=3, \quad y=f(x)=8$
and for $x=-13, y=f(x)=-8$
Max. $(x\cdot y)=(-13)\times(-8)=104$

LEVEL (2)

1. $f(x)=\dfrac{a^x+a^{-x}}{2}, \quad f(y)=\dfrac{a^y+a^{-y}}{2}$

$\therefore \quad f(x+y)=\dfrac{a^{x+y}+a^{-(x+y)}}{2} \qquad \ldots(1)$

and $\quad f(x-y)=\dfrac{a^{x-y}+a^{-(x-y)}}{2} \qquad \ldots(2)$

adding (1) and (2), we get

$$f(x+y)+f(x-y)=\frac{a^{x+y}+a^{-x-y}}{2}+\frac{a^{x-y}+a^{-x+y}}{2}$$
$$=\frac{1}{2}[a^x(a^y+a^{-y})+a^{-x}(a^y+a^{-y})]$$
$$=\frac{1}{2}(a^x+a^{-x})(a^y+a^{-y})$$
$$=2f(x)f(y)$$

2. $\left|\dfrac{30-x}{5}\right|<4$
$\Rightarrow \quad |30-x|<20$
$\Rightarrow \quad -20<(30-x)<20$
$\Rightarrow \quad -20<30-x<20$
$\Rightarrow \quad -50<-x<-10$
$\Rightarrow \quad 50>x>10$
or $\quad 10<x<50$

3. $|x+y|=|x-y| \Rightarrow (x+y)^2=(x-y)^2 \quad \Rightarrow \quad 4xy=0$
$\Rightarrow \quad$ either $x=0 \quad$ or $\quad y=0$
If $x=0$ and y is any real number, we have infinite possible values of y as

$|0+y|=|0-y| \quad \Rightarrow \quad |y|=|-y|$
Similarly $(x, 0)$ where x can be any real number also satisfies $|x+0|=|x-0|$
So there are infinite number of solutions.

6. $e^{-x^2}=\dfrac{1}{e^{x^2}}$

Since x^2 is an even function therefore e^{-x^2} is also an even function, hence it is symmetric about y-axis.
Also it is always positive.
and at $x=0, \quad e^{-x^2}=1$
Hence (b) is not true. Thus only choice (d) is correct.

7. $y=a^x \Rightarrow$ at $x=0, y=1$
Hence (iii) statement is true.



at $\quad a=\dfrac{1}{2}, f(x)=\left(\dfrac{1}{2}\right)^x$

e.g., $a=\dfrac{1}{2}$, then $f(x)=a^x=\left(\dfrac{1}{2}\right)^x$

Hence the function is decreasing.

14. Inverse of an exponential function is a logarithmic function.
$\therefore \quad x=10^y \quad \Rightarrow \quad \log_{10} x=y$
graph (A) is an exponential function
graph (B) is a logarithmic function
graph (C) is also an exponential function
graph (D) represents inverse function like $\left|\dfrac{1}{x}\right|$.

Scanned by CamScanner

yourmahboob.wordpress.com

Logarithmic function is defined only for positive values hence choice (a), (c) and (d) are wrong.
Also the inverse function (*i.e.*, $f^{-1}(x)$ of a function $f(x)$) is symmetric about $x = y$

15. $f(0) = 1 - 0 = 1, f\left(\frac{1}{2}\right) = 1 - \frac{1}{2} = \frac{1}{2} = 0.5$

$f(1) = 1 - 1 = 0, f\left(\frac{45}{18}\right) = 2.5 - 1 = 1.5$

$\therefore f(0) + f\left(\frac{1}{2}\right) + f(1) + f\left(\frac{45}{18}\right) = 1 + 0.5 + 0 + 1.5 = 3$

16. $x = \frac{|y|}{y}, y \neq 0$

if $y > 0, x = \frac{y}{y} = 1$

$\therefore$ for all values of $y > 0$, $x = 1$

and for all values of $y < 0$, $x = -1$

17. Since the reflection of $g(x)$ is about x-axis therefore $g(x) = -f(x)$

18. Since the reflection of $g(x)$ is about y-axis

$\therefore \quad g(x) = f(-x)$

19. $f(x)$ is an even function

20. Since for each x there are more than 1 value of $f(x)$

21. $f(x)$ is an even function

22. $f(x)$ is an odd function

23. $f(x) = |x|$



$f(x) = -|x|$



$f(x) = -|x| + 1$



24. $f(x) = x^3 - 3x^2 - x + 3$

$f(x) = (x - 1)(x + 1)(x - 3)$



$\Rightarrow \quad x = -1, 1, 3$

Thus the graph of $f(x)$ intersects the x-axis three times *viz.*, at $x = -1, 1, 3$

25. Choice (a) $\rightarrow$ at $x = 0$ $f(x)$ is not defined
Choice (b) $\rightarrow$ at $x = 0$ and $x = 1$, $f(x)$ is not defined
Choice (d) $\rightarrow$ x is defined for only positive real numbers except 1.
Hence choice (c) is correct as x^2 is always positive as $x^2 + 2 \neq 0$

26. Since x is always positive and y can assume both positive and negative values therefore (c) is the correct choice.

$x|y| = 1 \Rightarrow x = \frac{1}{|y|}$ for $x > 0$

27.



28. $f(x_2, x_3) = x_{2+3} = x_5$ ($\because 2 + 3 < 3^2$)

$f(x_5, x_6) = x_{5+6-3} = x_8$ ($\because 5 + 6 > 3^2$)

$\therefore \quad f(f(x_2, x_3), f(x_5, x_6)) = f(x_5, x_8) = x_{5+8-3} = x_{10}$ ($\because 5 + 8 > 3^2$)

29. $g(x_2, x_3) = x_1$ $\left[\because \frac{2 \times 3}{5} \rightarrow m = 1\right]$

$g(x_7, x_8) = x_1$ $\left[\because \frac{7 \times 8}{5} \rightarrow m = 1\right]$

$\therefore \quad g(g(x_2, x_3), g(x_7, x_8))$

$= g(x_1, x_1) = x_1$ $\left[\because \frac{1 \times 1}{5} \rightarrow m = 1\right]$

30. $\because$ at $x = 1 \quad y = 0$
$x = -1 \quad y = 0$
$x = 0 \quad y = -1$
$x = 2 \quad y = 1$
$x = -2 \quad y = 1$

31. $y = |x| + x$

at		
	$x = 0$	$y = 0$
	$x = 1$	$y = 2$
	$x = 2$	$y = 4$
	$x = -1,$	$y = 0$
	$x = -2,$	$y = 0$

Scanned by CamScanner

yoursmahboob.wordpress.com

33. $x = y - 1$
$y = x + 1$
$\Rightarrow$ $x = 0, \quad y = 1$
at $x = -1, \quad y = 0$
$x = 1, \quad y = 2$
$x = -2, \quad y = 1$

34. Option (a) is wrong since at $x = 1, 2, \ y = 0$
Option (c) is wrong since at $x = 0, y = 1$
Option (b) is correct since at $x = -2, 2, y = 0$
also $x = 0, y = 0$ etc.
Also the graph is symmetric about y-axis hence $|x|$ is must to be appeared.

35. The graph intersects x axis at four different points therefore choice (c) is wrong. Since graph is symmetric about y-axis therefore choice (a) is wrong since at $x = 1, y = 0$
but at $x = -1, y = 6$
choice (d) is wrong since at $x = 0, y = +2$
Hence choice (b) is correct.

36. $f(x) = \begin{cases} -x & x < 0 \\ x & x > 0 \end{cases}$

$g(x) = \begin{cases} x & x < 0 \\ -x & x > 0 \end{cases}$

$\therefore \quad f(x) = -g(x)$

37. $f(x) = \begin{cases} x \ \forall \ x < 0 \\ x \ \forall \ x > 0 \end{cases}$

$g(x) = \begin{cases} -x & x < 0 \\ x & x > 0 \end{cases}$

$\therefore \quad f(x) = -g(x)$ for $x < 0$
and $f(x) = g(x)$ for $x > 0$

38. $f(x) = \begin{cases} -x & x < 0 \\ -x & x > 0 \end{cases} \Rightarrow g(x) = \begin{cases} -x & x < 0 \\ x & x > 0 \end{cases}$

$\therefore f(x) = g(x)$ for $x < 0$ and $f(x) = -g(x)$ for $x > 0$

39. Choice (b) is wrong since at $x = 0$, $f(x) = 0$. Choices (a) and (c) are also wrong.
Now, choice (d) is correct, since
$y = -(ax^2 + c)$ and $y = (ax^2 + c)$
These two equations give equal but opposite values.

40. $f(1) = 1$
$f^2(1) = f(f(1)) = 1$
$f^3(1) = f^2(f(1)) = f^2(1) = 1$
$f^4(1) = f^3(f(1)) = f^3(1) = 1$
therefore $f^{11}(1) f^{33}(1) . f^{55}(1) f^{77}(1) f^{99}(1)$
$= 1 \times 1 \times 1 \times 1 \times 1 = 1$

41. $f^2(x) = f(f(x)) = f\left(\frac{1}{x}\right) = x$

$f^3(x) = f(f^2(x)) = f(x) = \frac{1}{x}$

$\therefore \quad f^2(x) = f^4(x) = f^6(x) = f^8(x) \ldots = x$
and $f(x) = f^3(x) = f^5(x) = f^7(x) \ldots = \frac{1}{x}$

$\therefore \quad f^{12}(x) = f^2(x) = 11$

$\therefore \quad f(f(x)) = 11$

$\Rightarrow \quad f\left(\frac{1}{x}\right) = 11 \Rightarrow f(x) = \frac{1}{11}$

✍ ***Solutions for question number 41-43 :***

Cycle	Values of		
	a	b	c
Start	1	2	3
1	2	4	6
2	4	6	10
3	8	8	16
4	16	10	26
5	32	12	44
6	64	14	78
7	128	16	144

41. 16 and 144

42. $b = 16$

43. Basically the module takes 7 cycles to reach step 6 (*i.e.*, to stop), Hence the number of repetitions $= 7 - 1 = 6$

✍ ***Solutions for question number 44-47 :***

Cycle	x	y	z	Sum
C_0	1	-2	3	$2 = S_0$
C_1	-5	8	-13	$-10 = S_1$
C_2	21	-34	55	$42 = S_2$
C_3	-89	144	-233	$-178 = S_3$
C_4	377	-610	987	$754 = S_4$

44. We can see from the above table that sum of each cycle is twice the each corresponding value of x in the same cycle.

45. $S_4 = 754$

46. $S_1, S_3, S_5, S_7 \ldots$ etc are negative integers
Hence S_{13} is negative
and each sum $S_1, S_2, S_3, S_4, S_5, S_6 \ldots$ is an even number
Hence (d)

47.

	K	L	M
initially	9	0	0
Fill (L, K)	4	5	0
Fill (M, L)	4	1	4
Empty (L, K)	5	0	4
Empty (M, L)	5	4	0

$\therefore L$ has 4 litres of water.

48. Note that we can feed the instruction of Empty (L, M) since the amount of water in L is less than the remaining capacity of M.

Scanned by CamScanner

yoursmahboob.wordpress.com

Final Round

Solutions for question number 1 to 10 :

P_0	P_1	P_2	P_3	P_4	P_5	P_6	P_7	P_8	P_9	P_{10}	P_{11}	P_{12}
0	1	1	0	−1	−1	0	1	1	0	−1	−1	0
Q_0	Q_1	Q_2	Q_3	Q_4	Q_5	Q_6	Q_7	Q_8	Q_9	Q_{10}	Q_{11}	Q_{12}
0	1	1	2	3	5	8	13	21	34	55	89	144

5. $Q_{13} = 233, \quad P_{14} = 1$

$\therefore \quad Q_{13} + P_{14} = 234$

6. $Q_{10} + P_{10} = 55 + (-1) = 54$

7. $Q_6 = 8 \ \therefore Q_8 = 21$

i.e. $Q_{[Q_6]} = Q_{[8]} = 21$

8. $\because$ (a), (b) and (c) are wrong

9. $(Q_5)^{P_5} = (5)^{-1} = \frac{1}{5} = 0.2$

Solutions for question number 11-14 :

11. $P[k(3)] = 3Q\,[k(3)] - 4$

$= 3\,(2R\,[k(3)] + R\,[k(6)]) - 4$

$= 3\,(2(S\,[k(6)]) - S\,[k(3)] + (S\,[k(12)] - S\,[k\,(6)])) - 4$

$= 3\,(2\,(22 - 13) + (51 - 22)) - 4$

$= 3(18 + 29) - 4 = 141 - 4 = 137$

12. $S\,[k(1)] = 7$

$R\,[k(7)] = S\,[k(14)] - S[k(7)]$

$= 59 - 31 = 28$

$Q\,[k(28)] = 2R\,[k(28)] + R\,[k(56)]$

$= 2(S\,[k(56)] - S\,[k\,(28)] + S[k(112) - S\,(k(56))]$

$= 2(227 - 115) + (451 - 227)$

$= 2(112) + (224) = 448$

$\therefore \quad QRS\,[k(1)] = QR\,[k(7)] = Q\,[k(28)] = 448$

13. $R\,[k(5)] = S\,[k(10)] - S\,[k(5)]$

$= 43 - 19 = 24$

and $S\,[k(10)] = 43$

$\therefore \quad R[k(5)] - S[k(10)] = 24 - 43 = -19$

14. $\forall\ x < 0$, $R\,[k(x)]$ and $S\,[k(x)]$ are equal to zero. Therefore the whole product will be zero.

Solutions for question number 15-20 :

15. $(3x^4 + 2x^2 + 5x) + (2x^4 + 3x^3 + 7x^2)$

$= 5x^4 + 3x^3 + 9x^2 + 5x$

$= (5, 4, 3, 3, 9, 2, 5, 1)$

16. $(6, 5, 7, 4, 8, 3) - (3, 5, 5, 3, 7, 1)$

$= (6x^5 + 7x^4 + 8x^3) - (3x^5 + 5x^3 + 7x)$

$= (3x^5 + 7x^4 + 3x^3 - 7x)$

$= (3, 5, 7, 4, 3, 3, -7, 1)$

17. $(1, 1, 2, 0) \rightarrow (x + 2)$

$\therefore \quad (x + 2)^3 = x^3 + 6x^2 + 12x + 8$

$= (1, 3, 6, 2, 12, 1, 8, 0)$

18. $(3, 3, -10, 2, 7, 1) \div (3, 2, -7, 1)$

$= (3x^3 - 10x^2 + 7x) \div (3x^2 - 7x)$

$= x\,(3x^2 - 10x + 7) \div x\,(3x - 7)$

$= x\,(x - 1)\,(3x - 7) \div x\,(3x - 7)$

$= (x - 1)$

$= (1, 1, -1, 0)$

20. $(4x^4 + 3x^3) \times (2x^2 + x) + (2x^2 + x) - (3x^5 + 2x^4)$

$= (8x^6 + 10x^5 + 3x^4) + (2x^2 + x - 3x^5 - 2x^4)$

$= (8x^6 + 7x^5 + x^4 + 2x^2 + x)$

$= (8, 6, 7, 5, 1, 4, 2, 2, 1, 1)$

Solutions for question number 21-25 :

21. $h(3, 2, 8, 7) \div g(4, 7, 10, 8) = 2 \div 4 = \frac{1}{2}$

22. $h(fg(2, 5, 7, 3), 9) = h(f(2, 5, 7, 3) \times g(2, 5, 7, 3), 9)$

$= h((7 \times 2), 9) = h(14, 9) = 5$

23. $h(h(7, 13, 5, 9), h(4, 6, 12, 14)) = h(1, 0)$

$= \frac{1}{0}$, which is not defined

24. $A = 9, B = 20, C = 20, D = 14$

$\therefore \quad B = C > D > A$

Hence (b) is the appropriate answer

25. $h(h(a_1, b_1, c_1, d_1), h(a_2, b_2, c_2, d_2)) = h(0, 0)$

$= \frac{0}{0}$ is not defined, while $0 \times 0 = 0$ is defined

Solutions for question number 26-32 : *In case of $x > 0$, we get the following pattern.*

$f(1) = b + c - 2c + a = a + b - c$

$f(2) = b + c - 4c + a + b - c = a + 2b - 4c$

$f(3) = b + c - 6c + a + 2b - 4c = a + 3b - 9c$

$f(4) = b + c - 8c + a + 3b - 9c = a + 4b - 16c$

(i.e., $f(x) = a + bx - cx^2$)

26. Hence $f(8) = a + 8b - 64c = a + 8\,(b - 8c)$

Hence (b) is correct.

27. $f(-19) = 2b \times (-19) + f(-(-19))$

$= -38b + f(19)$

$= -38b + a + 19b - 361c$

$= a - 19b - 361c = a - 19\,(b + 19c)$

HINT For $x < 0$ i.e., $f(-x) = a + b(-x) - c(-x)^2$

28. $f(7) = a + 7b - 49c$

$\therefore$ when $a = 15, \quad b = 11$ and $c = -3$

$f\,(7) = 15 + 7 \times 11 - 49\,(-3)$

$= 15 + 77 + 147 = 239$

29. $f(-10) = a - 10b - 100c$

$\therefore$ at $a = 10$, $b = -7$ and $c = 6$

$f(-10) = 10 - 10(-7) - 100 \times 6$

$= 10 + 70 - 600 = -520$

Scanned by CamScanner

yoursmahboob.wordpress.com

30. $f(x) = a + b(x) - c(x)^2$ for every x

$\therefore$ $0 = 4 - 17x + 18x^2$

Now, for convenience go through options.

31. $f(x) < 0$

$\Rightarrow$ $a + b(x) - c(x)^2 < 0$

$\Rightarrow$ $12 + 10(x) - 8(x)^2 < 0$ ...(1)

Now, for convenience go through options.

Alternatively : Solve the quadratic inequality (1) and then get the required set of values.

32. $f(1) = a + b - c = -a$ $(\because b = -a, c = a)$

$\therefore$ $f(f(1)) = f(-a)$

$= a + b(-a) - c(-a)^2$

$= a - ab - ca^2$

$= a + a^2 - a^3$

Solutions for question number 33-37 :

$f(y, 0) = y + f(y - 1, 0)$

$= y + (y - 1) + f(y - 2, 0)$

$= y - (y - 1) + (y - 2) + ... + 1 + f(0, 0)$

$= \frac{y(y+1)}{2} + 1$

and $f(0, y) = y - f(0, y - 1)$

$= y - [(y - 1) - f(0, y - 2)]$

$= y - (y - 1) + f(0, y - 2)$

$= 1 + (y - 2) - f(0, y - 3)$

$= 1 + (y - 2) - (y - 3) + f(0, y - 4)$

$= 2 + f(0, y - 4)$

Thus, $f(0, y) = \begin{cases} \frac{y-1}{2}, & \text{if } y \text{ is odd} \\ \frac{y+2}{2}; & \text{if } y \text{ is even} \end{cases}$

33. $f(y_1, y_2, y_3, \ldots y_n)$ is not defined for every odd n.

Here $n = 27$

34. $f(0, 1, 0, 1) = f(0, 1) + f(1, 0) + (0 + 1 + 0 + 1)$

$= 0 + 2 + 2 = 4$

35. $f(8, 8, 8, 2, 2, 2) = f(8, 2) + f(8, 8, 2, 2) + (8 + 8 + 8 + 2 + 2 + 2)$

$= f(2, 0) + f(0, 8) + [f(8, 2) + f(8, 2) + (8 + 8 + 2 + 2)] + 30$

$= 4 + 5 + [2 f(8, 2) + 20] + 30$

$= 9 + [2(9) + 20] + 30$

$= 9 + [38] + 30 = 77$

36. $f(1, 1, 3, 1, 1, 3)$

$= f(1, 3) + f(1, 3, 1, 1) + (1 + 1 + 3 + 1 + 1 + 3)$

$= f(3, 0) + f(0, 1) + [f(1, 1) + f(3, 1) + (1 + 3 + 1 + 1)] + 10$

$= 7 + 0 + [f(1, 0) + f(0, 1) + f(1, 0) + f(0, 3) + 6] + 10$

$= 17 + [2 + 0 + 2 + 1 + 6]$

$= 17 + 11 = 28$

37. $f(9, 2, k, 0, 9, 4)$

$= f(9, 4) + f(2, k, 0, 9) + (9 + 2 + k + 0 + 9 + 4)$

$= f(4, 0) + f(0, 9) + [f(2, 9) + f(k, 0) + (2 + k + 0 + 9)] + 24 + k$

$= 11 + 4 + [\{f(9, 0) + f(0, 2)\} + f(k, 0) + (11 + k)] + 24 + k$

$= 15 + [48 + f(k, 0) + (11 + k)] + 24 + k$

$= 98 + 2k + f(k, 0)$

$= 98 + 2k + \left[\frac{k(k+1)}{2} + 1\right] = 124$

$\Rightarrow$ $k^2 + 5k - 50 = 0$

$\Rightarrow$ $k = -10$ or $k = 5$

Since k is a positive integer, hence $k = 5$

38. $f(128) = 1 \cdot 2^2 + 2 \cdot 2^1 + 8 \cdot 2^0$

$= 4 + 4 + 8 = 16$

$\therefore$ $f(16) = 1 \cdot 2^1 + 6 \cdot 2^0$

$= 2 + 6 = 8$

39. $f(888222) = 8 \cdot 2^5 + 8 \cdot 2^4 + 8 \cdot 2^3 + 2 \cdot 2^2 + 2 \cdot 2^1 + 2 \cdot 2^0$

$= 2^8 + 2^7 + 2^6 + 2^3 + 2^2 + 2^1$

$= 2^6(7) + 14$

$= 448 + 14 = 462$

$f(462) = 4 \cdot 2^2 + 6 \cdot 2^1 + 2 \cdot 2^0 = 30$

$f(30) = 3 \cdot 2^1 + 0 \cdot 2^0 = 6$

Again $f(113113) = 1 \cdot 2^5 + 1 \cdot 2^4 + 3 \cdot 2^3 + 1 \cdot 2^2 + 1 \cdot 2^1 + 3 \cdot 2^0$

$= 32 + 16 + 24 + 4 + 2 + 3 = 81$

$f(81) = 8 \cdot 2^1 + 1 \cdot 2^0$

$= 16 + 1 = 17$

$f(17) = 1 \cdot 2^1 + 7 \cdot 2^0$

$= 2 + 7 = 9$

$\therefore$ $f[f(888222) + f(113113)] = f(6 + 9]$

$= f(15) = 1 \cdot 2^1 + 5 \cdot 2^0$

$= 2 + 5 = 7$

40. $f(9235) = 9 \cdot 2^3 + 2 \cdot 2^2 + 3 \cdot 2^1 + 5 \cdot 2^0$

$= 72 + 8 + 6 + 5 = 91$

$f(91) = 9 \cdot 2^1 + 1 \cdot 2^0 = 19$

$f(19) = 1 \cdot 2^1 + 9 \cdot 2^0 = 11$

$f(11) = 1 \cdot 2^1 + 1 \cdot 2^0 = 3$

$f(9450) = 9 \cdot 2^3 + 4 \cdot 2^2 + 5 \cdot 2^1 + 0 \cdot 2^0$

$= 72 + 16 + 10 = 98$

$f(98) = 9 \cdot 2^1 + 8 \cdot 2^0 = 26$

$f(26) = 2 \cdot 2^1 + 6 \cdot 2^0 = 10$

$f(10) = 1 \cdot 2^1 + 0 \cdot 2^0 = 2$

$\therefore$ $f(9235) + f(9450) = 3 + 2 = 5$

❑❑❑

Scanned by CamScanner

yoursmahboob.wordpress.com

18 SEQUENCE, SERIES & PROGRESSIONS

This is one of the chapters which contributes really very logical problems which can be solved easily by some innovative methods rather than conventional methods (like applying formulae etc.) Basically CAT is an exam where logic prevails over pure mathematics. Therefore the students who use their ingenuity to solve these problems score better than those who rely on the formula based approach. In the starting of the chapter I have given the proper mathematical methods, then later on I have gradually moved towards novel techniques for faster and smarter calculation. Remember that almost 1–2 questions are necessarily asked in CAT and this chapter is also important for rest of the entrance tests eg. XAT, FMS, IIFT, CET, MAT etc.

Once again I would like to advise you that maximum problems must be attempted with the help of given choices. Besides most of the problems can be solved by substituting the values of variables *e.g.*, n, x, etc. for nth term or sum of the series/progression. The above method is so smart that it reduces the time of problem solving upto 80% for some complex and typical problems.

Sequence : A set of numbers occuring in a definite order or by a rule is called a sequence. Thus any set of numbers $a_1, a_2, a_3, \ldots a_n$ such that to each positive integer n, there corresponds a number a_n, is sequence. The numbers $a_1, a_2, a_3, \ldots, a_n \ldots$ are called elements (or members) of the sequence.

e.g., $1, \frac{1}{2}, \frac{1}{3}, \frac{1}{4}, \frac{1}{5}, \ldots, \frac{1}{n} \ldots$ is a sequence, since the number occur in a definite order. A sequence can be finite or infinite according to the number of elements in it. If there are finite number of elements, then it is a finite sequence and if there are infinite number of elements in it, then it is an infinite sequence and is denoted by $\{a_n\}$.

Series : Let $u_1, u_2, u_3, \ldots, u_n$ be a given sequence of n numbers, where n is a specified positive integer. Then their sum *i.e.* $u_1 + u_2 + u_3 + \ldots + u_n$ is called a finite series and the numbers $u_1, u_2, u_3 \ldots u_n$ are called terms of the series.

If $S_n = u_1 + u_2 + u_3 + \ldots + u_n$, then S_n is called the sum to n terms (or the sum of the first n terms) of the series and is denoted by

$$\sum_{r=1}^{n} u_r \text{ or } \Sigma u_r$$

e.g., $2+4+6+\ldots+30$ is a finite series and can be denoted as $\sum_{n=1}^{15} (2n)$ ($\Sigma \rightarrow$ Sigma, summation notation)

Progressions : Sequences of special types are called progressions. The sequences $a_1, a_2, \ldots, a_n \ldots$ or $\{a_n\}$ is known when its nth term a_n is given.

For example :

(i) If $a_n = 2n$, then the sequence is 2, 4, 6, 8, ...

(ii) If $a_n = 2n - 1$, then the sequence is 1, 3, 5, 7, ...

But to define a sequence we may not always have a formula for the nth term. For example, the sequence of the prime numbers is 2, 3, 5, 7, 11, 13, ... for which a formula for the nth term may not be given.

In this chapter we study basically Arithmetic Progression (A.P.) and Geometric Progression (G.P.) and get a overview of Harmonic Progressions (H.P.) also.

ARITHMETIC PROGRESSION (A.P.)

A sequence $a_1, a_2, a_3, \ldots, a_n$ is said to be in arithmetic progression, when $a_2 - a_1 = a_3 - a_2 = \ldots$ *i.e.*, when the quantities increase or decrease continuously by a common quantity and this constant (or common) quantity is called the common difference of the A.P. *e.g.*,

Progressions	Common Difference
1, 3, 5, 7, 9, ...	$\rightarrow 2$
12, 9, 6, 3, 0, –3, – 6, ...	$\rightarrow -3$
7, 12, 17, 22, ...	$\rightarrow 5$
– 6, – 4, – 2, 0, 2, 4, 6, ...	$\rightarrow 2$

GENERAL TERM (OR n^{th} TERM) OF AN A.P.

Let us look at the following :

1, 4, 7, 10, 13, ...

Each next term in the above sequence is being increased by 3 (which is the common difference). So you can see that from the second term onwards 3 is being added to every next term *i.e.*,

Scanned by CamScanner

yoursmahboob.wordpress.com

$1 = 1$

$4 = 1 + 3$

$7 = 1 + 3 + 3$

$10 = 1 + 3 + 3 + 3$

$13 = 1 + 3 + 3 + 3 + 3$ etc.

Let if a be the first term of the progression and d be the common difference, then the

First term $\longrightarrow a$

Second term $\longrightarrow a + d$

Third term $\longrightarrow a + 2d$

Fourth term $\longrightarrow a + 3d$

Fifth term $\longrightarrow a + 4d$

And nth term $\longrightarrow a + (n-1)d$

The general term or nth term is denoted by T_n.

Hence $T_n = a + (n-1)d$

also $l = a + (n-1)d$

l is the last term of A.P.

EXAMPLE 1 *Find the 11th term of* $-7, -2, 3, 8, 13, \ldots$

SOLUTION $T_{11} = -7 + (11-1)5 = 43$

$(\because\ a = -7,\ d = 5$ and $n = 11)$

Sum of First n terms of an A.P.

Let us look at the following :

$1, 4, 7, 10, 13, \ldots$

Let the sum of 'n' terms is denoted by S_n, then

$S_1 = 1$

$S_2 = 1 + 4 = 5$

$S_3 = 1 + 4 + 7 = 12$

$S_4 = 1 + 4 + 7 + 10 = 22$

$S_5 = 1 + 4 + 7 + 10 + 13 = 35$

$\therefore\ S_n = T_1 + T_2 + T_3 + \ldots + T_n$

$= (a) + (a + d) + (a + 2d) + \ldots + (a + (n-1)d)$

$= na + \dfrac{n(n-1)d}{2}$

$S_n = \dfrac{n}{2}[2a + (n-1)d]$

Alternatively :

$S_n = \left(\dfrac{a+l}{2}\right)n$, ($l \rightarrow$ last term of the progression)

NOTE In my own experience the alternative formula of S_n is better for problem solving since in this formula we have to just take the product of average of first and last term with number of terms. Also for our convenience to use this formula we can consider any term as last term.

EXAMPLE 2 *Find the sum of 11 terms of* $-7, -2, 3, 8, \ldots$

SOLUTION $a = -7$

$l = -7 + (10)\cdot 5 = 43$

$\therefore\ S_{11} = \dfrac{-7 + 43}{2} \times 11$

$S_{11} = 198$

NOTE Personally I hardly use the formula $S_n = \dfrac{n}{2}[2a + (n-1)d]$

Since I prefer $S_n = \left(\dfrac{a+l}{2}\right)n$.

ARITHMETIC MEAN (A.M.)

When three quantities are in A.P., the middle one is called arithmetic mean (A.M.) of the other two.

Let a, m, b are in A.P., then A.M. of a and b

i.e., $m = \dfrac{a+b}{2}$

$\therefore\ \text{A.M.} = \dfrac{a+b}{2}$

In general, if $a, m_1, m_2, m_3, \ldots, m_n, b$ are in A.P. then the intermediate numbers $m_1, m_2, m_3, \ldots, m_n$ are called the n arithmetic means between a and b

also the A.M. of $a_1, a_2, a_3, \ldots, a_n$, which are in A.P. is

$$\text{A.M.} = \frac{(a_1 + a_2 + a_3 + \ldots + a_n)}{n}$$

To Insert n Arithmetic Means Between a and b.

If a and b are the first and last term respectively between which we have to insert n arithmetic means $m_1, m_2, m_3, \ldots, m_n$, then common difference $d = \dfrac{b-a}{n+1}$

Thus $m_1 = a + \left(\dfrac{b-a}{n+1}\right)$

$m_2 = a + 2\left(\dfrac{b-a}{n+1}\right)$

$m_3 = a + 3\left(\dfrac{b-a}{n+1}\right)$

... ...

... ...

$m_n = a + n\left(\dfrac{b-a}{n+1}\right)$

EXAMPLE 3 *Insert 3 arithmetic means between 5 and 21.*

SOLUTION $d = \dfrac{21-5}{3+1} = 4$

$\therefore$ First A.M. $= a + d = 5 + 4 = 9$

Second A.M. $= a + 2d = 5 + 2(4) = 13$

Third A.M. $= a + 3d = 5 + 3(4) = 17$

Hence the new sequence is 5, 9, 13, 17, 21, where all the terms are in A.P.

Scanned by CamScanner

yoursmahboob.wordpress.com

PROPERTIES OF ARITHMETIC PROGRESSIONS

1. If a certain number is added or subtracted to each term of a given A.P., then the resulting sequence is also an A.P. and it has the same common difference as that of the given A.P.

   e.g., 1, 4, 7, 10, 13, 16, ... then
   3, 6, 9, 12, 15, 18, ... is also an A.P.
   and 2, 5, 8, 11, 14, 17, ... is also an A.P.
   In the second sequence each term is increased by 2 than that of the first sequence and each term of the third sequence is decreased by 1 than that of second sequence.

2. If each term of an A.P. is multiplied by a fixed constant (or divided by a non-zero fixed constant), then the resulting sequence is also an A.P.

   e.g., 6, 12, 18, 24, 30, 36, ..., then
   9, 18, 27, 36, 45, 54, ... is also an A.P.
   and 3, 6, 9, 12, 15, 18, ... is also an A.P.

   In the second sequence each term is $\frac{3}{2}$ times that of the first sequence and in the third sequence each term is half of the each term of the first sequence.

3. If $m_1, m_2, m_3, \ldots, m_k$ and $n_1, n_2, n_3, \ldots, n_k$ are in A.P., then $(m_1 + n_1), (m_2 + n_2), (m_3 + n_3), \ldots, (m_k + n_k)$ are also in A.P.

   e.g., $S_1 = 3, 7, 11, 15, 19, \ldots$
   and $S_2 = 5, 11, 17, 23, 29, \ldots$
   then $S_1 + S_2 = (3+5), (7+11), (11+17), (15+23), (19+29) \ldots$

   $\Rightarrow S_1 + S_2 = 8, 18, 28, 38, 48, \ldots$ is also an A.P.

4. If $m_1, m_2, m_3, \ldots, m_k$ and $n_1, n_2, n_3, \ldots, n_k$ are in A.P., then $(m_1 - n_1), (m_2 - n_2), (m_3 - n_3), \ldots, (m_k - n_k)$ are also in A.P.

   e.g., $S_1 = 7, 12, 17, 22, 27, \ldots$
   $S_2 = 4, 13, 22, 31, 40, \ldots$
   then $S_1 - S_2 = (7-4), (12-13), (17-22), (22-31), (27-40) \ldots$

   $\Rightarrow S_1 - S_2 = 3, -1, -5, -9, -13, \ldots$ is also an A.P.

5. If there are odd number of terms in an A.P. as $a_1, a_2, a_3, \ldots, a_n$ then the middle most term is the A.M. of the given sequence.

   e.g., 4, 10, 16, 22, 28

   then, $\frac{4+10+16+22+28}{5} = 16$

   Also $\frac{4+28}{2} = \frac{10+22}{2} = 16$ (A.M.)

   (It is the most important point for logical problems.)

6. If there are even number of terms in an A.P. as $a_1, a_2, a_3, \ldots, a_n$ then
   $a_1 + a_n = a_2 + a_{n-1} = a_3 + a_{n-2} = a_4 + a_{n-3}$ etc.

   e.g., 4, 10, 16, 22, 28, 34, 40, 46

   then, $4 + 46 = 10 + 40 = 16 + 34 = 22 + 28$

   also $\frac{4+46}{2} = \frac{10+40}{2} = \frac{16+34}{2} = \frac{22+28}{2} = 25$ (A.M.)

7. The sum of an A.P. with n terms is given by
   $S_n = n$ (A.M.)

   e.g. (1) 3, 7, 11, 15, 19, then
   $S_5 = 5 \times 11 = 55$

   (2) 5, 8, 11, 14, 17, 20
   $\therefore \quad S_6 = 6 \times \frac{25}{2} = 75$

8. If we have to take three terms in A.P. it is convenient to take them as $(m-k), m, (m+k)$ where $(m-k), m$ and $(m+k)$ are consecutive terms of an A.P. and k is the common difference.
   Similarly we can take five terms in A.P. as $(m-2k), (m-k), m, (m+k), (m+2k)$.

EXAMPLE 4 *If the sum of five terms of an A.P. is 75, then find the third term of the A.P.*

SOLUTION $(m-2k) + (m-k) + m + (m+k) + (m+2k) = 75$
$\Rightarrow \quad 5m = 75 \Rightarrow m = 15$
Hence the third term (*i.e.* middle most term) is 15.

NOTE In general to take odd number of terms, we assume m as the middlemost term and take other terms with common difference k, as per their position.

9. If we have to take 4 terms in A.P., it is convenient to take them as $(m-3k), (m-k), (m+k), (m+3k)$ where $(m-3k), (m-k), (m+k), (m+3k)$ are consecutive terms of an A.P. and '$2k$' is the common difference.
   Similarly we can take six terms in A.P. as $(m-5k), (m-3k), (m-k), (m+k), (m+3k), (m+5k)$.

EXAMPLE 5 *If the sum of 4 terms of an A.P. is 36, then find the A.M. of the A.P.*

SOLUTION $(m-3k) + (m-k) + (m+k) + (m+3k) = 36$
$\Rightarrow \quad 4m = 36$
$\therefore \quad S_4 = 4m = 36$
$\therefore \quad \text{A.M.} = \frac{S_4}{4} = \frac{4m}{4} = \frac{36}{4} = 9$

10. The sum of first n natural numbers
    $$\Sigma n = 1 + 2 + 3 + \ldots + n = \frac{n(n+1)}{2}$$

EXAMPLE 6 *Find the sum of first 10 natural numbers.*

SOLUTION $\Sigma 10 = 1 + 2 + 3 + \ldots + 10$
$= \frac{10 \times 11}{2} = 55$

Scanned by CamScanner

yourshahbook.wordpress.com

11. The sum of squares of first 'n' natural numbers

$$\Sigma n^2 = 1^2 + 2^2 + 3^2 + \ldots + n^2$$
$$= \frac{n(n+1)(2n+1)}{6}$$

EXAMPLE 7 *Find the sum of squares of first 11 natural numbers.*

SOLUTION $\Sigma n^2 = 1^2 + 2^2 + 3^2 + \ldots + 11^2$

$$= \frac{11 \times 12 \times 23}{6} = 506$$

12. The sum of cubes of first 'n' natural numbers

$$\Sigma n^3 = 1^3 + 2^3 + 3^3 + \ldots + n^3$$
$$= \left[\frac{n(n+1)}{2}\right]^2 = [\Sigma n]^2$$

EXAMPLE 8 *Find the sum of cubes of first 10 natural numbers.*

SOLUTION $\Sigma(10)^3 = 1^3 + 2^3 + 3^3 + \ldots + 10^3$

$$= \left(\frac{10 \times 11}{2}\right)^2 = 3025$$

13. The sum of first 'n' odd numbers

i.e., $1 + 3 + 5 + 7 + \ldots (2n-1) = n^2$

EXAMPLE 9 *Find the sum of* $1 + 3 + 5 + 7 + \ldots 11$

SOLUTION $1 + 3 + 5 + 7 + \ldots 11 = (11)^2 = 121$

14. The sum of first n even numbers

i.e., $2 + 4 + 6 + \ldots 2n = n(n+1)$

EXAMPLE 10 *Find the sum of first 10 even numbers.*

SOLUTION $2 + 4 + 6 + 8 \ldots 20 = 10 \times 11 = 110$

INTRODUCTORY EXERCISE-18.1

1. Find the 41st term of the progression 3, 8, 13, 18, ... :
(a) 102 (b) 203
(c) 304 (d) none of these

2. Find the 25th term of the A.P. 10, 6, 2, −2, −6, −10, ... :
(a) −86 (b) 106
(c) 96 (d) none of these

3. What term of the A.P. 2, 5, 8, ... is 56 ?
(a) 20 (b) 21
(c) 19 (d) 15

4. What is the 10th term of the sequence 2, 4, ... ?
(a) 18 (b) 20
(c) 1024 (d) can't be determined

5. If the 3rd and 7th terms of an A.P. are 17 and 27 respectively. Find the first term of the A.P. :
(a) 9 (b) 12
(c) 14 (d) none of these

6. Find the nth term of an A.P. whose 6th and 8th terms are 12 and 22 respectively :
(a) $7n - 30$ (b) $n^2 - 24$
(c) $5n - 18$ (d) none of these

7. If 7 times the seventh term of an A.P. is equal to 11 times its eleventh term, the value of eighteenth term of the A.P. is :
(a) 0 (b) −8
(c) 18 (d) 77

8. If the pth, qth and rth terms of an A.P. are a, b, c respectively, then the value of
$a(q-r) + b(r-p) + c(p-q)$ is :
(a) 0 (b) 1
(c) abc (d) pqr

9. If the pth term of an A.P. is q and its qth term is p then its mth term is :
(a) $\frac{pq}{m}$ (b) $pq - m$
(c) $p + q - m$ (d) pqm

10. Find the sum of the A.P. 11, 13, 15, ..., 99 :
(a) 2475 (b) 2500
(c) 1122 (d) 1580

11. Find the number of terms in the A.P. 22, 28, 34, ..., 616 :
(a) 80 (b) 78
(c) 99 (d) 100

12. Find the sum of 222, 224, 226, ..., 888 :
(a) 185370 (b) 195300
(c) 183000 (d) 899000

13. If the second and seventh terms of an A.P. are 2 and 22 respectively. Find the sum of first 35 terms :
(a) 2310 (b) 3210
(c) 2130 (d) none of these

14. The 12th term of an A.P. is −13 and the sum of the first four terms of it is 24. Find the sum of its first ten terms :
(a) −48 (b) −26
(c) 0 (d) 52

15. The third term of an A.P. is $\frac{1}{5}$ and the 5th term is $\frac{1}{3}$. Find the sum to 15 terms of the A.P. :
(a) 1/15 (b) 3/5
(c) 8 (d) 15

16. How many terms of the A.P. 1, 4, 7, ... are needed to give the sum 925 ?
(a) 20 (b) 22
(c) 24 (d) 25

17. How many terms of the series $20 + 16 + 12$ amounts to 48 ?
(a) 3 (b) 5
(c) 8 (d) both a and c

18. p, q, r, s, t are first five terms of an A.P. such that $p + r + t = -12$ and $p \cdot q \cdot r = 8$. Find the first term of the above A.P. :
(a) 3 (b) 2
(c) 4 (d) −4

19. The sum of all the terms of the A.P. 7, 10, 13, ... l is 1242, where l is the last term of the A.P. Find the value of l.
(a) 67 (b) 79
(c) 85 (d) 102

Scanned by CamScanner

yoursmahboob.wordpress.com

20. Find the sum of all the integers between 55 and 5555 which are divisible by 7 :
(a) 678 (b) 786
(c) 876 (d) none of these

21. How many terms are there in A.P. whose first and fifth terms are – 14 and 2 respectively and the sum is 40 :
(a) 12 (b) 10
(c) 16 (d) 8

22. The first and last terms of an A.P. are – 7 and 233 and the sum of the A.P. is 9153. Find the number of terms in the A.P. :
(a) 83 (b) 81
(c) 49 (d) 99

23. The sum of three numbers in A.P. is 12 and sum of their cubes is 408. Find the product of the numbers :
(a) 17 (b) 35
(c) 28 (d) 36

24. The series of natural numbers is written as follows :

1
2 3 4
5 6 7 8 9
... ...
... ...

Find the sum of the numbers in the nth row :
(a) $n^3 + 1$ (b) $(2n)^2 - 1$
(c) $n^3 + (n-1)^3$ (d) none of these

25. If you save Re. 1 today, Rs. 2 the next day, Rs. 3 the succeeding day and so on, what will be your total savings in 365 days ?
(a) 66579 (b) 66795
(c) 56795 (d) none of these

26. The ratio of the 7th to the 3rd terms of an A.P. is 12 : 5, find the ratio of the 13th to 4th term :
(a) 13 : 7 (b) 4 : 3
(c) 10 : 3 (d) none of these

27. Find the sum of the first hundred even natural numbers divisible by 5 :
(a) 50500 (b) 55000
(c) 50050 (d) 50005

28. If m times the mth term of an A.P. is equal to n times its nth term, find $(m + n)$ th term of the A.P. :
(a) – 1 (b) 0
(c) mn (d) 4

29. The sum of the first fifteen terms of an A.P. is 105 and the sum of the next fifteen terms is 780. Find the common difference of A.P. :
(a) 4 (b) 3
(c) 6 (d) 5

30. If the first term of an A.P. is 2 and the sum of the first five terms is equal to one-fourth of the sum of the next five terms, then find the 20th term ?
(a) – 114 (b) – 82
(c) – 112 (d) none of these

31. The sum of the first six terms of an A.P. is 42. The ratio of the 10th term to the 30th term of A.P. is $\frac{1}{3}$. Find the 40th term of the A.P. :
(a) – 60 (b) 20
(c) 39 (d) 80

32. The sums of n terms of two arithmetic series are in the ratio of $\frac{7n+1}{4n+27}$. Find the ratio of their 11th terms :
(a) 4 : 3 (b) 5 : 4
(c) 7 : 4 (d) none of a, b, c

33. The sum of three numbes in A.P. is 15 and sum of their squares is 93. Find the greatest number :
(a) 6 (b) 10
(c) 8 (d) 7

34. If the nth term of an A.P. is $4n - 1$, find the 30th term and the sum of first 30 terms.
(a) 119 and 1830 (b) 69 and 1665
(c) 119 and 1380 (d) none of these

35. The sum of n terms of a series is $3n^2 + 5n$. Find the value of n if nth term is 152 :
(a) 15 (b) 18
(c) 20 (d) 25

36. Find the number of terms of the A.P. 98, 91, 84, ... must be taken to give a sum of zero :
(a) 14 (b) 15
(c) 31 (d) 29

37. What is the greatest possible sum of the A.P. 17, 14, 11, ... :
(a) 51 (b) 73
(c) 57 (d) 75

38. What is the least possible sum of the A.P. – 23, – 19, – 15, ... :
(a) – 3 (b) – 78
(c) – 87 (d) none of these

39. Find the sum of all odd numbers of four digits which are divisible by 9 :
(a) 2784491 (b) 2478429
(c) 2754000 (d) 2448729

40. If a, b, c be the pth, qth and rth terms of an A.P., then $p(b-c) + q(c-a) + r(a-b)$ equals to :
(a) 0 (b) 1
(c) 3 (d) $\frac{abc}{pqr}$

41. If a, b, c be respectively the sum of first p, q, r terms of an A.P. then $\frac{a}{p}(q-r) + \frac{b}{q}(r-p) + \frac{c}{r}(p-q)$ equals :
(a) pqr (b) $ap + bq + cr$
(c) 0 (d) $p + q + r$

42. Divide 20 into four parts which are in A.P. and such that the product of the first and fourth is to the product of the second and third in the ratio 2 : 3. Find the product of the first and fourth term of the A.P. :
(a) 12 (b) 16
(c) 20 (d) 25

43. The sum of the first p terms of an A.P. is q and the sum of the first q terms is p. Find the sum of the first $(p+q)$ terms :
(a) pq (b) $p - q$
(c) $-(p+q)$ (d) 0

Scanned by CamScanner

yoursmahboob.wordpress.com

GEOMETRIC PROGRESSION (G.P.)

Geometric Progression : A sequence $a_1, a_2, a_3, \ldots, a_n$ is said to be in Geometric Progression when

$$\frac{a_2}{a_1} = \frac{a_3}{a_2} = \frac{a_4}{a_3} = \ldots r \text{ (say)}$$

and $a_1, a_2, a_3, \ldots, a_n$ are all non-zero numbers and r is said to be the common ratio of the G.P.

e.g., (i) $2, 4, 8, 16, \ldots \to r = 2$

(ii) $1, 3, 9, 27, 81 \ldots \to r = 3$

(iii) $-3, 6, -12, 24, -48, 96 \ldots \to r = -2$

(iv) $\frac{1}{2}, \frac{3}{2}, \frac{9}{2}, \frac{27}{2} \ldots \to = r = 3$

(v) $k, kr, kr^2, kr^3, kr^4, \ldots \to r = r$

(vi) $64, 16, 4, 1, \frac{1}{4}, \frac{1}{16}, \ldots \to r = \frac{1}{4}$

GENERAL TERM (Or nth TERM) OF a G.P.

Let us look at the following :

$$1, 3, 9, 27, 81, 243, 729, 2187, \ldots$$

Each next term in the above sequence is becoming th (*i.e.* 3 times) which is called as common ratio.

$1 = 1$

$3 = 1 \times 3$

$9 = 1 \times 3 \times 3$

$27 = 1 \times 3 \times 3 \times 3$

$81 = 1 \times 3 \times 3 \times 3 \times 3$

$243 = 1 \times 3 \times 3 \times 3 \times 3 \times 3$

$729 = 1 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3$

and nth term $= a \times r \times r \times r \times \ldots \times (n-1)$ times

$$T_n = a \cdot r^{(n-1)}$$

∴The general term or nth term is represented by T_n

Hence $T_n = a \cdot r^{(n-1)}$

also $l = a \cdot r^{(n-1)}$

where l is the last term of the G.P.

EXAMPLE 1 *Find the 7th term of the sequence 2, 10, 50, 250, ...*

SOLUTION The given sequence is a G.P. with common ratio = 5

$$\left(\because \frac{10}{2} = \frac{50}{10} = 5\right)$$

and first term $(a) = 2$

$\therefore$ $T_7 = 2 \cdot (5)^6$ $\quad (\because T_n = a \cdot r^{n-1})$

$T_7 = 31250$

Sum of First n terms of a G.P.

Let us look at the following :

$$3, 6, 12, 24, 48, 96, \ldots$$

Let the sum of n terms is denoted by S_n, then

$S_1 = 3$

$S_2 = 3 + 6 = 9$

$S_3 = 3 + 6 + 12 = 21$

$S_4 = 3 + 6 + 12 + 24 = 45$

$S_5 = 3 + 6 + 12 + 24 + 48 = 93$

$\therefore$ $S_n = T_1 + T_2 + T_3 + \ldots, T_n$

$\therefore$ $S_n = \frac{a \cdot (r^n - 1)}{(r-1)}$ if $r > 1$

and $S_n = \frac{a \cdot (1 - r^n)}{(1-r)}$ if $r < 1$

also, $S_n = \frac{lr - a}{r - 1}$

NOTE The above formulae for S_n fails when $r = 1$, as the form $\frac{0}{0}$ is undefined. However,

$S_n = a + a + a + \ldots$ to n terms $= n \cdot a$

EXAMPLE 2 *Find the sum of the first 6 terms of the G.P.*

$$3, \frac{9}{2}, \frac{27}{4}, \frac{81}{8}, \ldots$$

SOLUTION Here $a = 3$, $r = \frac{3}{2}$ and $n = 6$, then

$$S_6 = \frac{3 \cdot \left[\left(\frac{3}{2}\right)^6 - 1\right]}{\left(\frac{3}{2} - 1\right)}$$

$$= \frac{3 \cdot \left(\frac{729}{64} - 1\right)}{\frac{1}{2}} = \frac{3 \cdot \left(\frac{665}{64}\right)}{\frac{1}{2}}$$

$$= \frac{3 \times 665 \times 2}{64 \times 1} = 62.34375$$

EXAMPLE 3 *Find the sum of first five terms of the G.P. 1, 2, 4, ...*

SOLUTION $S_5 = \frac{1 \cdot (2^5 - 1)}{(2-1)} = 31$

GEOMETRIC MEAN (G.M.)

If three quantities are in G.P., the middle one is called the geometric mean (G.M.) of the other two quantities.

If a, m, b are in G.P. then m is the G.M. of a and b

and since $\frac{m}{a} = \frac{b}{m}$

$\therefore$ $m^2 = ab$

$\Rightarrow$ $m = \pm\sqrt{ab} = \pm (ab)^{1/2}$

In general, if $a_1, a_2, a_3, \ldots, a_n$ are in G.P. then

$$\text{G.M.} = (a_1 \cdot a_2 \cdot a_3 \ldots . a_n)^{1/n}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 4 *Find the G.M. of 4, 12, 36, which are in G.P.*

SOLUTION G.M. of 4, 12, 36 $= (4 \times 12 \times 36)^{1/3}$

$= (1728)^{1/3} = (12^3)^{1/3} = 12$

EXAMPLE 5 *Find the G.M. of 3, 6, 12, 24, 48.*

SOLUTION G.M. $= (3 \times 6 \times 12 \times 24 \times 48)^{1/5}$

$= (12^5)^{1/5} = 12$

To Insert n Geometric Means between a and b

If a and b are the first and last term respectively between which we have to insert n geometric means $m_1, m_2, m_3, \ldots, m_n$ then

Common ratio, $r = \left(\frac{b}{a}\right)^{\frac{1}{n+1}}$

Thus, $m_1 = a \cdot \left(\frac{b}{a}\right)^{\frac{1}{n+1}}$

$m_2 = a \cdot \left(\frac{b}{a}\right)^{\frac{2}{n+1}}$

$m_3 = a \cdot \left(\frac{b}{a}\right)^{\frac{3}{n+1}}$

$\ldots\ldots\ldots$

$\ldots\ldots\ldots$

$m_n = a \cdot \left(\frac{b}{a}\right)^{\frac{n}{n+1}}$

EXAMPLE 6 *Insert 3 geometric means between 3 and 48.*

SOLUTION $r = \left(\frac{48}{3}\right)^{\frac{1}{3+1}} = (2^4)^{\frac{1}{4}} = 2$

$\therefore$ $m_1 = 3 \cdot 2 = 6$

$m_2 = 3 \cdot (2)^2 = 12$

$m_3 = 3 \cdot (2)^3 = 24$

Hence the new sequence is 3, 6, 12, 24, 48 where all the terms are in G.P.

PROPERTIES OF GEOMETRIC PROGRESSION

1. If each term of a G.P. is multiplied or divided by a certain non-zero constant, then the resulting sequence is also a G.P.
   e.g., 3, 6, 12, 24, 48, 96,... then 9, 18, 36, 72, 144, 288, ... is also a G.P. and $\frac{9}{2}$, 9, 18, 36, 72, 144, ... is also a G.P.
   In the second sequence each term is multiplied by 3 and each term of the third sequence is divided by 2 (compare with the second sequence)
2. If $a_1, a_2, a_3, \ldots$ and $b_1, b_2, b_3, \ldots$ are two geometric progressions, then the sequence $a_1b_1, a_2b_2, a_3b_3, \ldots$ is also a G.P.
   e.g., 2, 6, 18, 54, 162, ... and 1, 2, 4, 8, 16, ... then $(2 \times 1), (6 \times 2), (18 \times 4), (54 \times 8), (162 \times 16)$ ...
   i.e. 2, 12, 72, 432, 2592 is also a G.P.
   (Similarly $\frac{2}{1}, \frac{6}{2}, \frac{18}{4}, \frac{54}{8}, \frac{162}{16}, \ldots$
   i.e., $2, 3, \frac{9}{2}, \frac{27}{4}, \frac{81}{8}, \ldots$ is also a G.P.)
3. If there are odd number of terms in a G.P. as $a_1, a_2, a_3, \ldots, a_n$ then the middle most term is the G.M. of the given sequence.
   e.g., 2, 4, 8, 16, 32
   then $(2 \times 4 \times 8 \times 16 \times 32)^{1/5} = (2^{15})^{1/5} = 2^3 = 8$
   Also $(2 \times 32)^{1/2} = (4 \times 16)^{1/2} = 8$

NOTE In this case without knowing all the terms we can find the G.M. of the G.P.

4. If there are even number of terms in a G.P. as $a_1, a_2, a_3, \ldots, a_n$, then

$\sqrt{a_1 \cdot a_n} = \sqrt{a_2 \cdot a_{n-2}} = \sqrt{a_3 \cdot a_{n-3}} = \ldots$ G.M.

5. If we have to take three terms in G.P., it is convenient to take them as

   $\frac{m}{k}, m, mk$

   where $\frac{m}{k}$, m and mk are consecutive terms of G.P. and k is the common ratio.
   Similarly we can take five terms of G.P. as $\frac{m}{k^2}, \frac{m}{k}, m, mk, mk^2$.

EXAMPLE 7 *If the product of five consecutive terms of G.P. is 1024, then find the third term of this set.*

SOLUTION $\frac{m}{k^2} \times \frac{m}{k} \times m \times mk \times mk^2 = 1024$

$\Rightarrow$ $m^5 = 1024 = 2^{10} = 4^5$

$\Rightarrow$ $m = 4$

Hence the third term (*i. e.* middle most term) is 4.

In general to take odd number of terms, we assume m as the middle most term and take other terms with common ratio k, as per their position.

6. If we have to take 4 terms in G.P. it is convenient to take them as $\frac{m}{k^3}, \frac{m}{k}, mk, mk^3$ where $\frac{m}{k^3}, \frac{m}{k}, mk$ and mk^3 are four consecutive terms of a G.P. and k^2 is the common ratio.
   Similarly we can take six terms in G.P. as

   $\frac{m}{k^5}, \frac{m}{k^3}, \frac{m}{k}, mk, mk^3, mk^5$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 8 *If the product of 4 terms of a G.P. is 729, then find the G.M. of the G.P.*

SOLUTION

$$\frac{m}{k^3} \times \frac{m}{k} \times mk \times mk^3 = 729$$

$$m^4 = 729 = 3^6$$

$$\Rightarrow \quad m = 3^{6/4} = 3^{3/2}$$

$$\Rightarrow \quad m = \sqrt{27}$$

$$\Rightarrow$$

7. If $a_1, a_2, a_3, \ldots, a_n$ are in G.P. then $a_1^m, a_2^m, a_3^m, \ldots, a_n^m$ are also in G.P.

   e.g. 1, 2, 4, 8, 16, ... then 1, 4, 16, 64, 256, ... are also in G.P.

8. If $a_1, a_2, a_3, \ldots, a_n$ are in G.P. (for every $a_i > 0$; $i \in I^+$ then $\log a_1, \log a_2, \log a_3, \ldots$ are in A.P.

   (The converse of the above is also true)

Sum of an Infinite G.P.

$$S_\infty = \frac{a}{1-r}; \qquad |r| < 1$$

where a is the first term and r is the common ratio of the G.P. of infinite terms.

EXAMPLE 9 *Find the sum of an infinite G.P. whose first term is 28 and the second term is 4.*

SOLUTION $a = 28, \qquad T_2 = ar = 4$

$$\Rightarrow \quad r = \frac{1}{7}$$

$$\therefore \quad S_\infty = \frac{a}{1-r} = \frac{28}{1-\frac{1}{7}} = \frac{28}{6} \times 7 = \frac{98}{3}$$

INTRODUCTORY EXERCISE-18.2

1. Find the 22nd term of the G.P. $-2, 2, -2, \ldots$:
   (a) -22 (b) -2
   (c) 2 (d) none of these

2. Find the 7th term of the series $-\frac{1}{8} + \frac{1}{4} - \frac{1}{2} + 1 \ldots$:
   (a) 8 (b) -16
   (c) -8 (d) none of these

3. The 5th, 8th and 11th terms of a G.P. are a, b, c respectively, then which one of the following is true ?
   (a) $2b = ac$ (b) $b^2 = ac$
   (c) $a + b + c = 0$ (d) none of these

4. The 5th and 12th terms of a G.P. are 32 and 4096 respectively. Find the nth term of the G.P. :
   (a) 2^n (b) n^2
   (c) $2n^2$ (d) none of these

5. What is the least number of terms of the G.P. $5 + 10 + 20 + \ldots$ whose sum would surely exceed 10^6?
   (a) 17 (b) 18
   (c) 19 (d) 21

6. The A.M. of two positive numbers is 15 and their G.M. is 12. What is the smaller number ?
   (a) 8 (b) 12
   (c) 6 (d) 24

7. The sum of 3 numbers in G.P. is 38 and their product is 1728. Find the greatest number :
   (a) 24 (b) 18
   (c) 16 (d) 8

8. The sum of first three terms of a G.P. is to the sum of the first six terms is 125 : 152. Find the common ratio of the G.P. :
   (a) 3/5 (b) 3
   (c) 2/5 (d) 5/8

9. The sum of three numbers in G.P. is 14. If the first two terms are each increased by 1 and the third term is decreased by 1, the resulting numbers are in A.P. Find the product of these three numbers :
   (a) 125 (b) 64
   (c) 216 (d) 124

10. The third term of a G.P. is 4. The product of first five terms is :
    (a) 4^3 (b) 4^4
    (c) 4^5 (d) none of these

11. The sum of first three terms of a G.P. is 21 and sum of their squares is 189. Find the common ratio :
    (a) $\frac{1}{2}$ or 2 (b) 3 or $\frac{1}{3}$
    (c) 4 or $\frac{1}{4}$ (d) none of these

12. The sum of the first and the third term of a G.P. is 15 and that of the 5th and the 7th terms is 240. Find the 9th term :
    (a) 678 (b) 786
    (c) 867 (d) 768

13. Sum of three consecutive terms in a G.P. is 42 and their product is 512. Find the largest of these numbers :
    (a) 28 (b) 16
    (c) 32 (d) none of these

14. The sum of three numbers in G.P. is 70, if the two extremes be multiplied each by 4 and the mean by 5, the new numbers so formed are in A.P. Find the product of original numbers :
    (a) 8000 (b) 6000
    (c) 7000 (d) none of these

15. The sum of four terms in G.P. is 312. The sum of first and fourth term is 252. Find the product of second and third term :
    (a) 500 (b) 150
    (c) 60 (d) none of these

16. A bouncing tennis ball rebounds each time to a height equal to one half the height of the previous bounce. If it is dropped from a height of 16 m, find the total distance it has travelled when it hits the ground for the 10th time :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $47\frac{15}{16}$ (b) $37\frac{5}{16}$

(c) $67\frac{11}{16}$ (d) none of these

17. Find the sum to n terms of the series

$$7 + 77 + 777 + 7777 + \ldots$$

(a) $\frac{7}{9}\{10(10^n - 1) - n\}$ (b) $\frac{7}{9}\left\{\frac{10}{9}(10^n - 1) - n\right\}$

(c) $7\left\{\frac{10}{9}(10^n - 1) - n\right\}$ (d) none of these

18. Find the sum to n terms of $0.8 + 0.88 + 0.888 + \ldots$

(a) $\frac{8}{9}\left[\frac{1}{9}\{1 - (0.1)^n\}\right]$ (b) $\frac{8}{9}\left[\frac{1}{10}\{1 - (0.1)^n\}\right]$

(c) $\frac{8}{9}\left[n - \frac{1}{9}\{1 - (0.1)^n\}\right]$ (d) none of these

19. If the pth, qth and rth terms of a G.P. be respectively a, b, and c then the value of $a^{q-r} \cdot b^{r-p} \cdot c^{p-q}$ is :

(a) 0 (b) 1

(c) 3 (d) $\frac{abc}{pqr}$

20. If a, b, c are respectively the xth, yth and zth terms of a G.P. then the value of

$(y - z)\log a + (z - x)\log b + (x - y)\log c$:

(a) 0 (b) 1

(c) 3 (d) none of these

21. There are four numbers such that the first three of them form an Arithmetic Progression and the last three form a Geometric Progression. The sum of the first and the third is 2 and that of second and fourth is 26. What is the sum of first and fourth number?

(a) $85\frac{13}{25}$ (b) $25\frac{73}{85}$

(c) 83 (d) none of these

22. Find the sum to n terms of the series $1 + 3 + 7 + 15 + \ldots$

(a) $[(2^n - 1) - n]$ (b) $[(2^n - 1) + n]$

(c) $[2(2^n - 1) - n]$ (d) none of these

23. Find the sum of $\frac{1}{2} + \frac{3}{2^2} + \frac{5}{2^3} + \ldots + \frac{2n-1}{2^n}$:

(a) $\left(\frac{2n-3}{2^n}\right)$ (b) $\left(3 - \frac{2n+3}{2^n}\right)$

(c) $\left(\frac{2n+3}{2^n}\right)$ (d) none of these

24. Find the sum to n terms of the series

$$11 + 102 + 1003 + 10004 + \ldots :$$

(a) $(10^n - 1) + \frac{n(n+1)}{2}$ (b) $\frac{10}{9}(10^n - 1) + \frac{n(n+1)}{2}$

(c) $10^n + n^2 - 1$ (d) none of these

25. Find the sum to first n groups of

$(1) + (1 + 3) + (1 + 3 + 9) + (1 + 3 + 9 + 27) + \ldots$

(a) $\frac{1}{2}(3^n - 1)$ (b) $\frac{3}{4}(3^n - 1) - \frac{n}{2}$

(c) $n^2 + 1$ (d) none of these

26. Find the sum to n terms of the following series :

$$2 + 5 + 14 + 41 + \ldots$$

(a) $\frac{3}{4}(3^{n-1}) + \frac{n}{2}$ (b) $\frac{3}{4}(3^n - 1) + \frac{n}{2}$

(c) $(3n + 1)$ (d) none of these

27. Find the sum to n terms :

$$1 + 2x + 3x^2 + 4x^3 + \ldots ; x \neq 1 :$$

(a) $1 + nx^n$ (b) $\frac{x(x+1)}{2} + x^n$

(c) $\frac{1 - x^n}{(1-x)^2}$ (d) $\left\{\frac{1 - x^n}{(1-x)^2} - \frac{nx^n}{(1-x)}\right\}$

28. Find the sum to n terms of $1 + 3x + 5x^2 + 7x^3 + \ldots$

(a) $2(1 - x^{n-1})$

(b) $\frac{2x(1 - x^{n-1})}{(1-x^2)}$

(c) $\frac{2x(1 - x^{n-1})}{(1-x)^2} + \frac{1 - (2n-1)x^n}{(1-x)}$

(d) none of these

29. Find the sum to first n terms :

$$1 + \frac{2}{3} + \frac{3}{3^2} + \frac{4}{3^3} + \ldots$$

(a) $\frac{3}{4} - \frac{3 + 2n}{4(3^{n-1})}$ (b) $\frac{9}{4} - \frac{3}{4}\left[\frac{3 + 2n}{3^n}\right]$

(c) $2n - \left(\frac{1}{n}\right)^2$ (d) none of these

30. Find the sum to n terms of

$$3 \cdot 2 + 5 \cdot 2^2 + 7 \cdot 2^3 + \ldots$$

(a) $2^{n+2} - 2^{n+1} - 2$ (b) $n \cdot 2^{n+2} - 2^{n+1} + 2$

(c) $n \cdot 2^{n+2} + 2^{n-2}$ (d) none of these

31. Find the sum of the series :

$$1 + \frac{4}{5} + \frac{7}{5^2} + \frac{10}{5^3} + \ldots \text{ to } n \text{ terms :}$$

(a) $\frac{35}{16} + \frac{7n}{5}$ (b) $\frac{12n - 7}{16(5^{n-1})}$

(c) $\frac{35}{16} - \left[\frac{12n + 7}{16(5^{n-1})}\right]$ (d) none of these

32. Find the sum of the series

$$1 \cdot 3^2 + 2 \cdot 5^2 + 3 \cdot 7^2 + \ldots \text{ to 20 terms :}$$

(a) 12896 (b) 187898

(c) 98970 (d) 188090

33. Find the sum of the series

$$\frac{1^3}{1} + \frac{1^3 + 2^3}{1 + 3} + \frac{1^3 + 2^3 + 3^3}{1 + 3 + 5} + \ldots \text{ to 16 terms :}$$

(a) 224 (b) 446

(c) 2356 (d) none of these

34. In a set of four numbers, the first three are in G.P. and the last three are in A.P. with common difference 6. If the first number is the same as the fourth, find the first number :

(a) -8 (b) 4

(c) 2 (d) can't be determined

35. The sum of an infinite G.P. is 16 and the sum of the squares of its terms is $153\frac{3}{5}$. Find the fourth term of the progression :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $\frac{7}{16}$ (b) $\frac{5}{32}$

(c) $\frac{3}{16}$ (d) none of these

36. If $x = 1 + a + a^2 + \ldots$ to ∞ and $y = 1 + b + b^2 + \ldots$ to ∞, and $|a| < 1, |b| < 1$, then the value of :

$1 + ab + a^2b^2 + \ldots$ to ∞ is :

(a) $\frac{xy}{x+y}$ (b) $\frac{x+y+1}{xy}$

(c) $\frac{xy}{x-y}$ (d) $\frac{xy}{x+y-1}$

37. A person is entitled to receive an annual payment which for each year is less by one tenth of what it was for the year before. If the first payment is 100, then find the maximum possible payment which he can receive, however long he may live :

(a) 900 (b) 9999

(c) 1000 (d) none of these

38. Find the sum of the series $\frac{1}{4} - \frac{3}{16} + \frac{9}{64} - \frac{27}{256} + \ldots$

(a) $\frac{1}{3}$ (b) $\frac{1}{4}$

(c) $\frac{1}{7}$ (d) none of these

39. The sum of first two terms of a G.P. is $\frac{5}{3}$ and the sum to infinity of the series is 3. Find the first term :

(a) 1 (b) $\frac{2}{3}$

(c) 5 (d) both (a) and (c)

40. A ball is dropped from a height of 96 feet and it rebounds $\frac{2}{3}$ of the height it falls. If it continues to fall and rebound, find the total distance that the ball can travel before coming to rest.

(a) 240 ft (b) 360 ft

(c) 480 ft (d) none of these

HARMONIC PROGRESSION

Harmonic Progression (H.P.) : A series of quantities $a_1, a_2, a_3, a_4 \ldots, a_n$ is said to be in H.P. when their reciprocals $\frac{1}{a_1}, \frac{1}{a_2}, \frac{1}{a_3}, \ldots, \frac{1}{a_n}$ are in A.P.

NOTE The converse is also true.

$\therefore$ If a, b, c are in H.P., then $\frac{1}{a}, \frac{1}{b}, \frac{1}{c}$ are in A.P.

Simply there is no general formula for the sum of any number of quantities in H.P. All questions in H.P. are generally solved by inverting the terms and making use of the properties of the corresponding A.P.

Harmonic Mean (H.M.) : When three quantities are in H.P., the middle one is called the Harmonic Mean (H.M.) between the other two.

If a, H, b are in H.P., then H is the H.M. of a and b and $\frac{1}{a}, \frac{1}{H}, \frac{1}{b}$ are in A.P.

$\therefore \quad \frac{1}{H} - \frac{1}{a} = \frac{1}{b} - \frac{1}{H}$

or $\quad \frac{2}{H} = \frac{1}{a} + \frac{1}{b} = \frac{a+b}{ab}$

$\therefore \quad H = \frac{2ab}{a+b}$

EXAMPLE 1 *Find the 10th term of the H.P.* $1, \frac{1}{3}, \frac{1}{5}, \frac{1}{7}, \frac{1}{9}, \frac{1}{11}, \ldots$

SOLUTION Since $\frac{1}{1}, \frac{1}{3}, \frac{1}{5}, \frac{1}{7}, \ldots$ are in H.P.

$\therefore$ 1, 3, 5, 7, ... are in A.P.

$\therefore \quad T_{10} = 1 + 9 \times 2$

$T_{10} = 19$

Since 10th term of the A.P. is 19

therefore 10th term of the H.P. is $\frac{1}{19}$.

EXAMPLE 2 *If the 4th and the 7th terms of an H.P. are* $\frac{1}{2}$ *and* $\frac{2}{7}$ *respectively. Find the first term.*

SOLUTION 4th term in H.P. $= \frac{1}{2}$

$\therefore$ 4th term in A.P. $= 2$

7th term in H.P. $= \frac{2}{7}$

$\therefore$ 7th term in A.P. $= \frac{7}{2}$

$\therefore \quad T_4 = a + 3d = 2$

and $\quad T_7 = a + 6d = \frac{7}{2}$

$\Rightarrow \quad d = \frac{1}{2}$

$\therefore \quad a = \frac{1}{2}$ (which is the first term of the A.P.)

$\therefore$ the first term of H.P. $= 2$

Scanned by CamScanner

yourshahbook.wordpress.com

ARITHMETICO-GEOMETRIC SEQUENCE

If $a_1, a_2, a_3, \ldots, a_n$ are in A.P. and $b_1, b_2, b_3 \ldots, b_n$ are in G.P., then the sequence $a_1b_1, a_2b_2, a_3b_3, \ldots, a_nb_n$ is said to be in arithmetico- geometric sequence.

An Arithmetico-Geometric sequence is of the form $ab, (a+d)br, (a+2d)\,br^2, (a+3d)br^3, \ldots$

$$\therefore \quad S_n = \frac{ab}{1-r} + \frac{dbr(1-r^{n-1})}{(1-r)^2} - \frac{[a+(n-1)d]br^n}{1-r}$$

and $$S_\infty = \frac{ab}{1-r} + \frac{dbr}{(1-r)^2}$$

EXAMPLE 3 *Find the sum to n terms of the series*

$$1 + \frac{4}{5} + \frac{7}{5^2} + \frac{10}{5^3} + \ldots$$

SOLUTION This is an A.G. series

$$\therefore \quad S_n = 1 + \frac{4}{5} + \frac{7}{5^2} + \frac{10}{5^3} + \ldots + \frac{3n-2}{5^{n-1}}$$

$$\therefore \quad \frac{S_n}{5} = \frac{1}{5} + \frac{4}{5^2} + \frac{7}{5^3} + \ldots + \frac{3n-5}{5^{n-1}} + \frac{3n-2}{5^n}$$

subtracting we get

$$\frac{4}{5}S_n = 1 + \frac{3}{5} + \frac{3}{5^2} + \frac{3}{5^3} + \ldots + \frac{3}{5^{n-1}} - \frac{3n-2}{5^n}$$

or $$\frac{4}{5}S_n = 1 + \frac{\frac{3}{5}\left(1 - \frac{1}{5^{n-1}}\right)}{1 - \frac{1}{5}} - \frac{3n-2}{5^n}$$

$$= \frac{35}{16} - \frac{12n+7}{16(5^{n-1})}$$

EXAMPLE 4 *In the above example find the sum to infinite number of terms.*

SOLUTION

$$S_\infty = \frac{ab}{1-r} + \frac{dbr}{(1-r)^2}$$

$$= \frac{1 \times 1}{1 - \frac{1}{5}} + \frac{3 \times 1 \times \frac{1}{5}}{\left(1 - \frac{1}{5}\right)^2}$$

$$= \frac{1}{\frac{4}{5}} + \frac{\frac{3}{5}}{\frac{16}{25}} = \frac{5}{4} + \frac{15}{16} = \frac{35}{16}$$

INTRODUCTORY EXERCISE-18.3

1. Which one of the following is true about A.M., G.M. and H.M. :
   (a) H.M. ≥ G.M. ≥ A.M. (b) A.M. ≥ H.M. ≥ G.M.
   (c) A.M. ≥ G.M. ≥ H.M. (d) G.M. ≥ H.M. ≥ A.M.
2. If a, b, c are in A.P. b, c, d are in G.P. and c, d, e are in H.P., then which one of the following is true :
   (a) $2c = a + e$ (b) $ae = c^2$
   (c) $c = \frac{2ae}{a+e}$ (d) $ab = de$
3. If A.M. and G.M. of two numbers is 10 and 8 respectively then find their H.M. :
   (a) 9 (b) 12
   (c) 6 (d) 6.4

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL (1)

1. Find the number of terms in the G.P. whose first term is 3, sum is $\frac{4095}{1024}$ and the common ratio is $\frac{1}{4}$:
(a) 4 (b) 5
(c) 6 (d) none of these

2. Find the common ratio of the G.P. whose first and last terms are 5 and $\frac{32}{625}$ respectively and the sum of the G.P. is $\frac{5187}{625}$:
(a) $\frac{1}{5}$ (b) $\frac{2}{5}$
(c) $\frac{5}{3}$ (d) $\frac{4}{5}$

3. Find the sum of the series $2\sqrt{3}, 2\sqrt{2}, \frac{4}{\sqrt{3}}, \ldots$
(a) $6(\sqrt{3}+\sqrt{2})$ (b) $6(\sqrt{3}-\sqrt{2})$
(c) $\frac{6}{(\sqrt{3}+\sqrt{2})}$ (d) none of these

4. The number of terms in an A.P. is even, the sum of odd terms is 63 and that of even terms is 72 and the last term exceeds the first term by 16.5. Find the number of terms :
(a) 8 (b) 12
(c) 9 (d) 10

5. There are two pockets, each containing 3 coins of different denominations, which are in A.P. and the total value of coins in each pocket is Rs. 21. The common difference of the first set of coins is greater than that of the second set by 1, and the product of the first set is the product of the second set as 8 to 9. Find the value of the coin of largest denomination, among the six coins :
(a) 9 (b) 8
(c) 11 (d) 10

6. Find the sum of the three numbers in G.P. whose product is 216 and the sum of the products of them taken in pairs is 126 :
(a) 28 (b) 21
(c) 35/4 (d) none of these

7. The sum of four consecutive terms in A.P. is 36 and the ratio of product of the first and fourth is to the product of the second and third is 9 : 10. Find the largest of the numbers :
(a) 9 (b) 10
(c) 8 (d) 12

8. The sum of four integers in A.P. is 24 and their product is 945. Find the product of the smallest and greatest integers :
(a) 30 (b) 27
(c) 35 (d) 39

9. In an A.P. consisting of 23 terms, the sum of the three terms in the middle is 114 and that of the last three is 204. Find the sum of first three terms :
(a) 14 (b) 42
(c) 24 (d) 69

10. The sum of an infinite G.P. is 4 and the sum of their cubes is 192. Find the first term :
(a) 4 (b) 8
(c) 6 (d) 2

11. Vibhor joined as an area manager in Quick Corporation in the pay scale of Rs. 12,000 – 500 – 18,500. Minimum how many years he has to work in the corporation to avail the salary of Rs. 18,500 per month :
(a) 12 years (b) 10 years
(c) 13 years (d) 11 years

12. How many terms are common in two arithmetic progression 1, 4, 7, 10. ... upto 63 terms and 3, 7, 11, 15, ... upto 47 terms :
(a) 12 (b) 16
(c) 15 (d) none of these

13. The value of $3^{1/3} \cdot 9^{1/18} \cdot 27^{1/81} \ldots$:
(a) 3 (b) 9
(c) 27 (d) none of these

14. The sum to n terms of the series $1 + (1 + 3) + (1 + 3 + 5) + \ldots$ is :
(a) $\left[\frac{n(n+1)}{2}\right]^2$ (b) n^2
(c) $\frac{n(n+1)(2n+1)}{6}$ (d) none of these

15. The sum to n terms of the series
$1^2 + (1^2 + 3^2) + (1^2 + 3^2 + 5^2) + \ldots$ is :
(a) $\frac{1}{3}(n^4 + 2n^2)$ (b) $\frac{1}{3}(n^3 + 3n^2 - n)$
(c) $\frac{1}{6}n(n+1)(2n^2+2n-1)$ (d) none of these

16. If x, y, z are in G.P. and $a^x = b^y = c^z$, then :
(a) $\log_b a = \log_c b$ (b) $\log_b a = \log_a c$
(c) $\log_c b = \log_a c$ (d) none of these

17. The sum of integers from 113 to 113113 which are divisible by 7 is :
(a) 92358576 (b) 913952088
(c) 94501895 (d) 912952066

18. The sum of n terms of a progression is $3n^2 + 5$. The number of terms which equals 123 is :
(a) 12 (b) 18
(c) 21 (d) 23

19. If a, b, c are in A.P., $b - a, c - b$ and a are in G.P. then $a : b : c$ is :
(a) 4 : 3 : 2 (b) 2 : 3 : 4
(c) 1 : 2 : 3 (d) 3 : 4 : 5

Scanned by CamScanner

yoursmathbook.wordpress.com

20. The sum of first n terms of the series $\frac{1}{2}+\frac{3}{4}+\frac{7}{8}+\frac{15}{16}+\ldots$

(a) 2^n-1 (b) $1-2^{-n}$
(c) 2^n-n+1 (d) $n+2^{-n}-1$

21. The sum of all 4 digit numbers which when divided by 4 leave the remainder 1 :

(a) 12372750 (b) 12327027
(c) 12370705 (d) 109980

22. If n arithmetic means are inserted between two quantities a and b, then their sum is equal to :

(a) $n(a+b)$ (b) $\frac{n}{2}(a+b)$
(c) $2n(a+b)$ (d) $\frac{n}{2}(a-b)$

23. The product of n geometric means between two given numbers a and b is :

(a) $(ab)^n$ (b) $(ab)^{2n}$
(c) $(ab)^{n/2}$ (d) none of these

24. If $a_1, a_2, a_3, \ldots$ is an A.P. such that

$$a_1+a_5+a_{10}+a_{15}+a_{20}+a_{24}=225$$

then $a_1+a_2+a_3+\ldots+a_{23}+a_{24}$ is equal to :

(a) 999 (b) 900
(c) 1225 (d) none of these

25. The sum to n terms of the series, where n is an even number :

$$1^2-2^2+3^2-4^2+5^2-6^2+\ldots:$$

(a) $n(n+1)$ (b) $\frac{n(n+1)}{2}$
(c) $-\frac{n(n+1)}{2}$ (d) none of these

26. $\underbrace{(666\ldots6)}_{n\text{-digits}}+\underbrace{(888\ldots8)}_{n\text{-digits}}$ is equal to :

(a) $14(n^2-1)$ (b) $\frac{48}{9}(10^{2n}-1)$
(c) $\frac{14}{9}(10^n-1)$ (d) none of these

27. The cubes of the natural numbers are grouped as $1^3, (2^3, 3^3), (4^3, 5^3, 6^3), \ldots$ then the sum of the numbers in the nth group is :

(a) $\frac{n^3}{12}(n^2+2)(n^2+4)$ (b) $\frac{1}{8}n^3(n^2+1)(n^2+3)$
(c) $\frac{n^3}{6}(n^2+1)(n^2+2)$ (d) none of these

28. Three non-zero real numbers form an A.P. and the squares of these numbers taken in the same order form a G.P. Then the number of all possible common ratio of the G.P. is :

(a) 1 (b) 2
(c) 3 (d) none of these

29. If three positive real numbers a, b, c are in A.P. such that $a\cdot b\cdot c=4$, then the minimum value of b is :

(a) $2^{1/2}$ (b) $2^{1/3}$
(c) $2^{2/3}$ (d) $2^{3/2}$

30. Three numbers form an increasing G.P. If the middle number is doubled, then the new numbers are in A.P. The common ratio of the G.P. is :

(a) $2-\sqrt{3}$ (b) $2+\sqrt{3}$
(c) $\sqrt{3}-2$ (d) $3+\sqrt{2}$

31. If a, b, c $(a>0)$ are three successive terms of a G.P. with common ratio r, the value of r for which $c>4b-3a$ holds given by :

(a) $1<r<3$ (b) $-3<r<-1$
(c) $r<1$ and $r>3$ (d) none of these

32. Let a_n be the nth term of an A.P and $a_7=22$, then the value of the common difference (d) that would make $a_3\cdot a_7\cdot a_8$ greatest is :

(a) 4 (b) 2
(c) 0 (d) 7

33. If the A.M of two positive numbers a and b, $(a>b)$, is twice their G.M., then $a:b$ is :

(a) $2:\sqrt{3}$ (b) $2:7+4\sqrt{3}$
(c) $2+\sqrt{3}:2-\sqrt{3}$ (d) $7+4\sqrt{3}:7-4\sqrt{3}$

34. The number of common terms to the two sequences 17, 21, 25, ..., 417 and 16, 21, 26, ..., 466 is :

(a) 19 (b) 20
(c) 21 (d) 84

35. The sum to n terms of the series

$$\frac{1}{\sqrt{1}+\sqrt{3}}+\frac{1}{\sqrt{3}+\sqrt{5}}+\frac{1}{\sqrt{5}+\sqrt{7}}+\ldots \text{ is :}$$

(a) $\sqrt{2n+1}$ (b) $\frac{1}{2}\sqrt{2n+1}$
(c) $\sqrt{2n-1}$ (d) $\frac{1}{2}\{\sqrt{2n+1}-1\}$

36. Let T_r be the rth term of an A.P. for $r=1, 2, 3, \ldots$ If for some positive integers m, n we have $T_m=\frac{1}{n}$ and $T_n=\frac{1}{m}$ then T_{mn} equals :

(a) $\frac{1}{mn}$ (b) $\frac{1}{m}+\frac{1}{n}$
(c) 1 (d) 0

37. Find the sum to n terms of the series $3+6+10+16+\ldots$:

(a) $\frac{n(n-1)}{2}-1$ (b) $n(n+1)+2^n-1$
(c) $n(n+2)+1$ (d) $3(2n+1)-2^n$

38. In a certain colony of cancerous cells, each cell divides into two every minute. How many cells will be produced from a single cell if the rate of division continues for 12 minutes :

(a) 9180 (b) 8190
(c) 8910 (d) none of these

39. Divakar and Subhank set out to meet each other from Delhi and Saharanpur, 330 km apart. Divakar travels 30 km on the first day 28 km on the second day, 26 km on the third day and so on. Subhank travels 20 km on the first day, 24 km on the second day, 28 km on the third day and so on. In how many days they meet, if they started moving towards each other at the same time ?

(a) 4 (b) 5
(c) 6 (d) none of these

40. Find the sum to n terms of the series

$$1+(1+2)+(1+2+3)+(1+2+3+4)+\ldots:$$

(a) $\frac{n(n+1)(2n+1)}{6}$ (b) $\frac{n(n+1)(n+2)}{6}$
(c) $\frac{n(n+1)(n+2)}{12}$ (d) $\frac{n(n+1)}{2}$

41. If a, b, c are in H.P. then the value of $\left(\frac{1}{b}+\frac{1}{c}-\frac{1}{a}\right)\left(\frac{1}{c}+\frac{1}{a}-\frac{1}{b}\right)$ is :

(a) $\frac{3}{b^2}-\frac{2}{ab}$ (b) $a^2+b^2+c^2$
(c) $\frac{2}{bc}-\frac{1}{b^2}$ (d) both (a) and (c)

Scanned by CamScanner

yoursmahboob.wordpress.com

42. Find the sum to n terms of the series
$1\cdot3\cdot5+3\cdot5\cdot7+5\cdot7\cdot9+\ldots$ is :
(a) $n(8n^3+11n^2-n+3)$ (b) $n(2n^3+8n^2+7n-2)$
(c) $8n^3+12n^2-2n-3$ (d) none of these

43. What is the sum of 100 terms of the series
$1-2+3-4+5-6+\ldots$?
(a) 100 (b) 50
(c) 550 (d) none of these

LEVEL 2

1. An A.P. whose first term is unity and in which the sum of the first half of any even number of terms to that of the second half of the same number of terms is in constant ratio, the common difference 'd' is given by :
(a) 1 (b) 2
(c) 3 (d) 4

2. The number of divisors of 187, 637 and 1001 are in :
(a) A.P. (b) G.P.
(c) H.P. (d) none of these

3. The sum to n terms of the series
$1^2+(1^2+3^2)+(1^2+3^2+5^2)+\ldots$ is :
(a) $\frac{1}{3}(n^3+n^2+1)$ (b) $\frac{1}{6}n(n+1)(2n^2+2n-1)$
(c) $\frac{1}{3}(2n^2+2n-1)$ (d) none of these

4. If $|a|<1$ and $|b|<1$, then the sum of the series
$a(a+b)+a^2(a^2+b^2)+a^3(a^3+b^3)+\ldots$ upto ∞ is :
(a) $\frac{a^2}{b}+1$ (b) $\frac{a^2}{1-ab}$
(c) $\frac{a^2}{1-a^2}+\frac{ab}{1-ab}$ (d) $\frac{a^2}{b^2}+\frac{1}{ab}$

5. The sum to n terms of the series
$\frac{3}{1^2\cdot2^2}+\frac{5}{2^2\cdot3^2}+\frac{7}{3^2\cdot4^2}+\ldots$ is :
(a) $\frac{n^2-2n}{(n-1)^2}$ (b) $\frac{n^2+2n}{(n+1)^2}$
(c) $\frac{2n^2+1}{n}$ (d) none of these

6. The natural numbers are written as follows :
1
2 3
4 5 6
7 8 9 10
... ...
... ...
The sum of numbers in the nth row is :
(a) $\frac{n(n+1)}{2}$ (b) $\frac{n^2+1}{2}$
(c) $\frac{n(n^2+1)}{2}$ (d) none of these

7. The number $\underbrace{1\,1\,1\,1\ldots1}_{119\text{ times}}$ is a :
(a) prime number (b) composite number
(c) multiple of 3 (d) none of these

8. The interior angles of a polygon are in A.P. If the smallest angle is 120° and the common difference is 5°, then the number of sides in the polygon is :
(a) 8 (b) 12
(c) 9 (d) 6

9. If $n\in N$ and n is an odd number, then
$10^0+10^4+10^8+10^{12}+\ldots+10^{4n}$ is a :
(a) prime number (b) composite number
(c) a multiple of 10 (d) none of these

10. The value of $0.1\overline{23}$ is :
(a) $\frac{61}{495}$ (b) $\frac{71}{485}$
(c) $\frac{62}{719}$ (d) $\frac{123}{999}$

11. If n is a positive integer, then $\underbrace{1\,1\,1\ldots1}_{2n\text{ times}}-\underbrace{2\,2\,2\ldots2}_{n\text{ times}}$ is :
(a) a perfect square (b) a perfect cube
(c) prime number (d) none of these

12. One side of an equilateral triangle is 24 cm. The mid-points of its sides are joined to form another triangle whose mid points are in turn joined to form still another triangle. This process continues indefinitely. Find the sum of the perimeters of all the triangles :
(a) 144 cm (b) 72 cm
(c) 536 cm (d) 676 cm

13. The odd positive integers are arranged in a triangle as follows :
1
3 5
7 9 11
13 15 17 19
21 23 25 27 29
... ...
... ...
Find the sum of the numbers in the nth row of this arrangement :
(a) n^2+n (b) $2n^2-2+n$
(c) n^3 (d) none of these

14. Find the sum to n terms of the series
$\log a+\log\frac{a^3}{b}+\log\frac{a^5}{b^2}+\log\frac{a^7}{b^3}+\ldots$
(a) $\log\left(\frac{a^{2n}}{b^{n-1}}\right)^{n/2}$ (b) $\log\frac{a^{2n-1}}{b^{n-1}}$
(c) $\log\frac{a^{2n}}{b^n}$ (d) none of these

15. The value of $(0.2)^{\log_{\sqrt{5}}\left(\frac{1}{4}+\frac{1}{8}+\frac{1}{16}+\ldots\right)}$:
(a) 2 (b) $\frac{1}{2}$
(c) 4 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

16. If a, b, c are in H.P., then $\frac{b+a}{b-a}+\frac{b+c}{b-c}$ equals:
(a) 1 (b) 2
(c) $\frac{b-c}{a-b}$ (d) $\frac{ab}{c}$

17. Let a, b, c are in G.P. with common ratio r $(0<r<1)$. Then $a, 2b, 3c$ are in A.P., if r equals :
(a) $\frac{1}{2}$ (b) $\frac{1}{\sqrt{2}}$
(c) $\frac{1}{3}$ (d) none of these

18. The sum of the series
$\frac{5}{13}+\frac{55}{(13)^2}+\frac{555}{(13)^3}+\frac{5555}{(13)^4}+\ldots\infty$:
(a) $\frac{55}{39}$ (b) $\frac{65}{39}$
(c) $\frac{110}{169}$ (d) $\frac{65}{36}$

19. The sum of the infinite series
$\frac{1}{1\cdot4}+\frac{1}{4\cdot7}+\frac{1}{7\cdot10}+\ldots\infty$ is equal to :
(a) $\frac{1}{3}$ (b) $\frac{1}{4}$
(c) $\frac{38}{27}$ (d) none of these

20. A sequence $a_1, a_2, a_3, \ldots, a_n$ of real numbers is such that $a_1=0, |a_2|=|a_1+1|, |a_3|=|a_2+1|, \ldots, |a_n|=|a_{n-1}+1|$. then the A.M. $\left(i.e.\ \frac{a_1+a_2+a_3+\ldots+a_n}{n}\right)$ can not be less than :
(a) $\frac{1}{2}$ (b) $-\frac{1}{2}$
(c) 1 (d) can't be determind

21. Find the A.M. of second and third term of a G.P. of real numbers such that the sum of its first four terms is equal to 30 and the sum of the squares of the first four terms is 340.
(a) 5 (b) 6
(c) 8 (d) 10

22. A square is drawn by joining the mid points of the sides of a given square. A third square is drawn inside the second square in the same way and this process continues indefinitely. If a side of the first square is 4 cm, determine the sum of the areas of all the squares :
(a) 32 cm^2 (b) 16 cm^2
(c) 20 (d) none of these

23. An A.P. and a G.P. with positive terms have the same number of terms and their first terms as well as last terms are equal. Then what can be said about the sum of the A.P. and G.P. if A_s and G_s denote the sum of the A.P. and G. P. respectively :
(a) $A_S \geq G_S$
(b) $A_S \leq G_S$
(c) $A_S = G_S$
(d) can not be determined

24. An A.P. and a G.P. have all the terms positive. Also the first and second terms of the progressions are equal, If a_i and g_i denote the terms of A.P. and G.P. respectively for every $i \in N$ and $i > 2$, then which one of the following is true ?
(a) $a_i \geq g_i$ (b) $a_i \leq g_i$
(c) $a_i = g_i$ (d) none of these

25. $1^k + 2^k + 3^k + \ldots + n^k$ is divisible by $1+2+3+\ldots n$ for every $n \in N$, then k is :
(a) even (b) odd
(c) only prime (d) none of these

26. If pth, qth, rth and sth terms of an A.P. are in G.P. then $p-q, q-r, r-s$ are in :
(a) A.P. (b) G.P.
(c) H.P. (d) none of these

27. In our country 'Dreamland' the currency consists of a set of notes of different denominations. If the sum of all the denominations is 63 units of currency then what is the minimum number of denominations that can be there so that all the transactions can be made (in integers).
(a) 3 (b) 5
(c) 6 (d) 9

28. A retailer has n stones by which he can measure (or weigh) all the quantities from 1 kg to 121 kg (in integers only, e.g., 1 kg, 2 kg, 3 kg, etc) keeping these stones on either side of the balance. What is the minimum value of n?
(a) 3 (b) 4
(c) 5 (d) 11

29. What will be the 33rd term of the sequence 1, 7, 25, 79, ...?
(a) $33^3 - 1$ (b) $3^{33} - 2$
(c) $3(33^3 - 2)$ (d) none of these

30. All the four angles of a quadrilateral are in G.P. with common ratio r $(r \in N)$. Any two angles are acute and other two angles are obtuse, then the measure of the smallest angle of the quadrilateral is :
(a) 18° (b) 32°
(c) 24° (d) 36°

Directions for question number 31, 32 : In the kingdom of YAMRAJ, there are certain number of souls in a particular day. Where a single soul can merge with another soul in every second and thus two souls reduced to a single soul and if any soul can not merge with anyother soul in a particular second then it has to become a ghost and suffer in the hell. Thus every soul tries to avoid to become a ghost, but after a certain time it has to go to hell after maximum possible survival.

31. In a particular day there were $(2^{43200}-1)$ souls after how many seconds will all the souls become ghost :
(a) 43200 (b) 43199
(c) 43201 (d) 21600

32. If after n seconds there are k souls left, then what is the maximum number of souls there can be initially in a particular day ?
(a) $2^{k \cdot n}$ (b) $2^{kn} + 2k$
(c) $2^n k + 2^n - 1$ (d) $2^k n + 2^n + 1$

33. The income of HBI on the nth day is Rs. (n^2+2) and the expenditure of HBI on the nth day is Rs. $(2n+1)$.
Also income = expenditure + savings
In how many days his total saving will be Rs. 1240. :
(a) 10 (b) 12
(c) 15 (d) 16

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions for question numbers 34 and 35: In the zoological park Lucknow there are four kinds of animals viz. Elephant, monkey, lion and tiger which are in increasing G.P. and in the local zoo in Kanpur there are the same kinds of animals but in A.P. The number of elephants is least and equal in each of the places. Also the number of monkeys in each of the places is same but just greater than that of elephants. Total number of animals in zoological park is 50% more than that of local zoo. Also the common ratio of the G.P. is same as the common difference of the A.P. Number of tigers in both the places is maximum.

34. What is the number of elephants in each of the places ?
(a) 1 (b) 2
(c) 3 (d) 4

35. What is the number of lions in zoological park Lucknow :
(a) 5 (b) 6
(c) 8 (d) can not be determine

36. What is the sum of n terms of the series $-1+1^2-2+2^2-3+3^2\ldots$?
(a) $\frac{n(n^2+1)}{3}$ (b) n^2+n
(c) $\frac{n(n^2-1)}{3}$ (d) none of these

37. Find the sum of $1+\frac{2}{3}+\frac{4}{9}+\frac{6}{27}+\frac{8}{81}+\frac{10}{243}+\ldots\infty$:
(a) $\frac{2}{3}$ (b) $\frac{5}{2}$
(c) $\frac{19}{45}$ (d) $\frac{81}{17}$

38. Sum of n terms of the series
$$\log a+\log\left(\frac{a^2}{b}\right)+\log\left(\frac{a^3}{b^2}\right)+\log\left(\frac{a^4}{b^3}\right)+\ldots \text{ is :}$$
(a) $\log\left\{\frac{a^n}{b^{n-1}}\right\}^{n/2}$ (b) $\log\left\{\frac{a^{n+1}}{b^{n-1}}\right\}^{n/2}$
(c) $\log\left\{\frac{a^n}{b^n}\right\}^{n/2}$ (d) $\log\left\{\frac{a^{n+1}}{b^n}\right\}^{n/2}$

39. If $a_1, a_2, a_3, \ldots, a_n$ are in A.P. where $a_i > 0$ for all i, then the value of
$$\frac{1}{\sqrt{a_1}+\sqrt{a_2}}+\frac{1}{\sqrt{a_2}+\sqrt{a_3}}+\ldots+\frac{1}{\sqrt{a_{n-1}}+\sqrt{a_n}}:$$
(a) $\frac{n-1}{\sqrt{a_1}+\sqrt{a_2}}$ (b) $\frac{n+1}{\sqrt{a_1}+\sqrt{a_2}}$
(c) $\frac{n}{\sqrt{a_1}-\sqrt{a_2}}$ (d) none of these

40. If $\log_5 2, \log_5(2^x-3)$ and $\log_5\left(\frac{17}{2}+2^{x-1}\right)$ are in A.P. then the value of x is :
(a) 2 (b) 3
(c) $\log_2 3$ (d) $\log_2 5$

41. If $1, \log_y x, \log_z y, -15\log_x z$ are in A.P., then which is correct ?
(a) $x=z^3$ (b) $x=\frac{1}{y}$
(c) $y=\frac{1}{z^3}$ (d) all of these

42. If x, y, z are in G.P. and $a^x=b^y=c^z$, then $\log_b a\cdot\log_b c$ is equal to :
(a) 0 (b) 1
(c) ac (d) none of these

43. If $\log_2(5\cdot 2^x+1), \log_4(2^{1-x}+1)$ and 1 are in A.P. then x equals :
(a) $\log_2 5$ (b) $1-\log_5 2$
(c) $\log_5 2$ (d) none of these

44. If $1, \log_9(3^{1-x}+2)$ and $\log(4\cdot 3^x-1)$ are in A.P. then x is equal to :
(a) $\log_4 3$ (b) $\log_3 4$
(c) $1-\log_3 4$ (d) $\log_3\left(\frac{1}{4}\right)$

45. If $x>1, y>1, z>1$ are in G.P., then $\frac{1}{1+\ln x}, \frac{1}{1+\ln y}, \frac{1}{1+\ln z}$ are in :
(a) A.P. (b) H.P.
(c) G.P. (d) none of these

46. Let $a_1, a_2, \ldots, a_{10}$ be in A.P. and $h_1, h_2, \ldots, h_{10}$ be in H.P. If $a_1=h_1=2$ and $a_{10}=h_{10}=3$, then a_4h_7 is:
(a) 2 (b) 3
(c) 5 (d) 6

47. Let $S_1, S_2, \ldots$ be squares such that for each $n\geq 1$, the length of a side of S_n equals the length of a diagonal of S_{n+1}. If the length of a side of S_1 is 10 cm, then for which of the following values of n is the area of S_n less than 1 square cm ?
(a) 7 (b) 8
(c) 6 (d) 4

Final Round

1. A bacteria gives birth to two new bacterias in each second and the life span of each bacteria is 5 seconds. The process of the reproduction is continuous untill the death of the bacteria. Initially there is one newly born bacteria at time $t=0$, then find the total number of live bacterias just after 10 seconds :
(a) $\frac{3^{10}}{2}$ (b) $3^5(3^5-1)$
(c) $3^{10}-2^{10}$ (d) $3^{10}-2^5$

2. If S_n be defined as the sum of n terms of the series S. Such that $S=2^{66}-2^{65}-2^{64}\ldots$ Find S_{20}:
(a) 400 (b) 2^{47}
(c) 2^{20} (d) none of these

3. If U_m be defined as the sum of m terms of the series V, where $V=S_m+S_{m+1}+S_{m+2}+\ldots$ Find U_{34} :
(a) $2^{33}-1$ (b) $2^{33}+1$
(c) $2^{34}-1$ (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

4. Let $a_1, a_2, a_3, \ldots, a_n$ be an A.P. and S_1, S_2 and S_3 be the sum of first n, $2n$ and $3n$ terms respectively then $S_3 - S_2 - S_1$ is equal to, if a is first term and d is common difference :

(a) $3a - 2n - d$ (b) $a(n + 2d)$
(c) $3a + 2nd$ (d) $2n^2d$

5. Consider the sets

$$T_n = \{n, n + 3, n + 5, n + 7, n + 9\}$$

where $n = 1, 2, 3, \ldots, 99$. How many of these sets contain 5 or any integral multiple thereof (*i. e.* any one of the numbers 5, 10, 15, 20, 25, ...) ?

(a) 81 (b) 79
(c) 80 (d) none of these

6. If $\{x\}$ is the least integer greater than or equal to x, then find the value of the following series :

$$\{\sqrt{1}\} + \{\sqrt{2}\} + \{\sqrt{3}\} + \{\sqrt{4}\} + \ldots + \{\sqrt{99}\} + \{\sqrt{100}\}$$

(a) 715 (b) 55
(c) 157 (d) 835

7. If $[x]$ is the greatest integer less than or equal to x, then find the value of the following series

$$[\sqrt{1}] + [\sqrt{2}] + [\sqrt{3}] + [\sqrt{4}] + \ldots + [\sqrt{323}]$$

(a) 3237 (b) 2373
(c) 3723 (d) none of these

Directions for question number 8–14 : *King Dashratha of Ayodhya on his birthday decided to offer 100 coins of gold among his 4 sons and 3 wives. The denomination of each coin is Re. 1. He put all the 100 coins in 7 bags in such a way that by taking a proper combination of various bags any integral sum (i.e. Rs. 1, 2, 3, 4, ..., 100) can be obtained and it is known that the only whole sum of any bag can be taken.*

8. What is the maximum amount received by any one of the recipient ?

(a) Rs. 79 (b) Rs. 96
(c) Rs. 37 (d) none of these

9. If all the coins, of these who have odd number of coins, are combined then minimum how many people are required to combine their coins to make the same amount having even number of coins :

(a) 2 (b) 3
(c) 4 (d) can't be determined

10. If the two least amounts are combined with highest one then minimum how many persons combined their coins to get the same amount :

(a) 2 (b) 3
(c) 4 (d) 5

11. If the king wanted to distribute the amount equally among them, then how many people would have received more amount (number of coins) than that of previously retaining two coins with himself :

(a) 6 (b) 3
(c) 4 (d) none of these

12. If the king also included Hanuman another 8th candidate, in this occassion and distributed 200 coins in similar fashion such that the combination of two or more person's coin could yield any integral sum from 1 to 200, then what was the maximum amount (in Rs.) that anybody had received ?

(a) 128 (b) 73
(c) 37 (d) 64

13. In the previous problem (number 12), if the people who had obtained the coins equal to odd powers of 2 (*i. e.* $2^1, 2^3, 2^5, \ldots$ etc.) can not combine their money with any other. Then maximum how many different sums can be made ?

(a) 51 (b) 28
(c) 31 (d) 158

14. In the problem number 12 if we assume Hanuman as a special guest who received the maximum amount but he distributed his sum in the same proportion as others had received previously leaving the person who had received initally the second highest amount. The number of coins that Hanuman was left with :

(a) 10 (b) 13
(c) 11 (d) 9

15. The sum of an infinite geometric progression (G.P.) is 2 and the sum of the G.P. made from the cubes of the terms of this infinite series is 24. The values a and r respectively (where a is the first term and r denotes common ratio of the series) :

(a) $-2, 3$ (b) $3, -\frac{1}{2}$
(c) $0, \frac{1}{2}$ (d) can't be determined

16. The sum of first ten terms of an A.P. is 155 and the sum of first two terms of a G.P. is 9. The first term of the A.P. is equal to the common ratio of the G.P. and the first term of the G.P. is equal to the common difference of the A.P. which can be the A.P. as per the given conditions ?

(a) 2, 4, 6, 8, 10,... (b) $\frac{25}{2}, \frac{79}{6}, \frac{83}{6}, \ldots$
(c) 2, 5, 8, 11,... (d) both (b) and (c)

17. The sum of an infinite geometric series is 162 and the sum of its first n terms is 160. The inverse of its common ratio is an integer, then how many values of the common ratio (r) are possible ?

(a) 1 (b) 2
(c) 4 (d) 5

18. In the previous question how many values of n are possible?

(a) 1 (b) 2
(c) 3 (d) 4

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-18.1

1 (b)	2. (a)	3. (c)	4. (d)	5. (b)	6. (c)	7. (a)	8. (a)	9. (c)	10. (a)
11. (d)	12. (a)	13. (a)	14. (c)	15. (c)	16. (d)	17. (d)	18. (b)	19 (c)	20. (d)
21. (b)	22. (b)	23. (c)	24. (c)	25. (b)	26. (c)	27. (a)	28. (b)	29. (b)	30. (c)
31. (d)	32. (a)	33. (c)	34. (a)	35. (d)	36. (d)	37. (c)	38. (b)	39. (c)	40. (a)
41. (c)	42. (b)	43. (c)							

INTRODUCTORY EXERCISE-18.2

1 (c)	2. (c)	3. (b)	4. (a)	5. (b)	6. (c)	7. (b)	8. (a)	9. (b)	10. (c)
11. (a)	12. (d)	13. (c)	14. (a)	15. (a)	16. (a)	17. (b)	18. (c)	19 (b)	20. (a)
21. (d)	22. (c)	23. (b)	24. (b)	25. (b)	26. (b)	27. (d)	28. (c)	29. (b)	30. (b)
31. (c)	32. (d)	33. (b)	34. (c)	35. (c)	36. (d)	37. (c)	38. (c)	39. (d)	40. (c)

INTRODUCTORY EXERCISE-18.3

1 (c)	2. (b)	3. (d)							

LEVEL-1

1 (c)	2. (b)	3. (a)	4. (b)	5. (d)	6. (b)	7. (d)	8. (b)	9. (c)	10. (c)
11. (c)	12. (b)	13. (d)	14. (c)	15. (c)	16. (a)	17. (b)	18. (c)	19. (c)	20. (d)
21. (a)	22. (b)	23. (c)	24. (b)	25. (c)	26. (c)	27. (b)	28. (c)	29. (c)	30. (b)
31. (c)	32. (c)	33. (c)	34. (b)	35. (d)	36. (c)	37. (b)	38. (b)	39. (c)	40. (b)
41. (d)	42. (b)	43. (d)							

LEVEL-2

1 (b)	2. (a)	3. (b)	4. (c)	5. (b)	6. (c)	7. (b)	8. (c)	9. (b)	10. (a)
11. (a)	12. (a)	13. (c)	14. (a)	15. (c)	16. (b)	17. (c)	18. (d)	19. (a)	20. (b)
21. (b)	22. (a)	23. (a)	24. (b)	25. (b)	26. (b)	27. (c)	28. (c)	29. (b)	30. (c)
31. (a)	32. (c)	33. (d)	34. (b)	35. (c)	36. (d)	37. (b)	38. (b)	39. (a)	40. (b)
41. (d)	42. (b)	43. (b)	44. (c)	45. (b)	46. (d)	47. (b)			

FINAL ROUND

1 (b)	2. (b)	3. (a)	4. (d)	5. (b)	6. (a)	7. (c)	8. (c)	9. (b)	10. (a)
11. (c)	12. (b)	13. (c)	14. (c)	15. (b)	16. (d)	17. (d)	18. (c)		

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 18.1

1. $T_{41} = 3 + 40 \times 5 = 203$ $(\because T_n = a + (n-1)d$

2. $T_{25} = 10 + 24(-4) = -86$ $(a = 10, d = -4)$

3. $T_n = l = a + (n-1)d$

$= 2 + (n-1)3 = 56$

$\Rightarrow \quad 3(n-1) = 56 - 2$

$\Rightarrow \quad n = 19$

4. Since there are only two consecutive terms so we can not find the pattern of the sequence that whether it is a non-progression sequence or A.P. or G.P. or H.P. etc. Hence (d).

5. $T_3 = a + 2d = 17$ ...(1)

$T_7 = a + 6d = 27$ ...(2)

$\therefore$ subtracting equation (1) from equation (2), we get

$4d = 10 \Rightarrow d = 2.5$

$\therefore \quad a + 2 \times 2.5 = 17$

$\Rightarrow \quad a = 12$

6. $T_6 = a + 5d = 12$ ...(1)

$T_8 = a + 7d = 22$

$\Rightarrow \quad 2d = 10$ or $d = 5$

$\therefore \quad a + 25 = 12$ [from eq. (1)]

$\Rightarrow \quad a = -13$

$\therefore \quad T_n = -13 + (n-1)5$

$\Rightarrow \quad T_n = 5n - 18$

Alternatively : Check the options.

$5n - 18 \Rightarrow 5 \times 6 - 18 = 12$

and $5 \times 8 - 18 = 22$

Hence option (c) is correct.

7. $T_7 = a + 6d$

$T_{11} = a + 10d$

$\because \quad 7 \cdot T_7 = 11 \cdot T_{11}$

$\Rightarrow \quad 7(a + 6d) = 11(a + 10d)$

$\Rightarrow \quad 4a = -68d$

$\Rightarrow \quad a = -17d$

Now $T_{18} = a + 17d$

$\Rightarrow \quad T_{18} = -17d + 17d$

$\Rightarrow \quad T_{18} = 0$

8. $T_p = a_1 + (p-1)d$

$T_q = a_1 + (q-1)d$

$T_r = a_1 + (r-1)d$

$\therefore$ L.H.S. $= a(q-r) + b(r-p) + c(p-q)$

$= \{a_1 + (p-1)d\}(q-r) + \{a_1 + (q-1)d\}(r-p)$

$+ \{a_1 + (r-1)d\}(p-q)$

$= a_1 \cdot (q - r + r - p + p - q) + d[(p-1)(q-r)$

$+ (q-1)(r-p) + (r-1)(p-q)]$

$= 0$

Alternatively : Let us assume an A.P.

2, 5, 8, 11, 14, 17, 20, ...

Again assume $p = 2, q = 4, r = 5$

$\therefore \quad T_p = T_2 = 5 = a$

$T_q = T_4 = 11 = b$

$T_r = T_5 = 14 = c$

and $a(q-r) + b(r-p) + c(p-q) = 5(-1) + 11(3) + 14(-2)$

$= -5 + 33 - 28 = 0$

Hence (a) is the correct choice.

9. $T_p = a + (p-1)d = q$ ...(1)

and $T_q = a + (q-1)d = p$ ...(2)

and $T_m = a + (m-1)d$ ...(3)

From (1) and (2)

$a = q - (p-1)d$ and $a = p - (q-1)d$

$\Rightarrow \quad q - (p-1)d = p - (q-1)d$

$\Rightarrow \quad (q-p) = -d[(q-1) - (p-1)]$

$\Rightarrow \quad d = -1$

Again, $a + (p-1)d = q$

$\Rightarrow \quad a + (p-1) \times -1 = q$

$\Rightarrow \quad a = p + q - 1$

$\therefore \quad T_m = (p + q - 1) + (m-1) \times -1$

$\Rightarrow \quad T_m = p + q - m$

10. $11 + 13 + 15 + \ldots + 99$

Here number of terms $= 50 - 5 = 45$

or Number of terms $= \left(\frac{99 - 11}{2}\right) + 1 = 45$

NOTE When both the extremes of a sequence are counted then,

number of terms $= \left(\frac{l - a}{d}\right) + 1$

Now the sum of the progression $= \left(\frac{a + l}{2}\right)n$

$= \left(\frac{11 + 99}{2}\right) \times 45 = 2475$

Alternatively : $11 + 13 + \ldots + 99$

$= (1 + 3 + 5 + \ldots + 99) - (1 + 3 + \ldots + 9)$

$= (50)^2 - (5)^2 = 2475$

11. Number of terms $= \left(\frac{616 - 22}{6}\right) + 1$

$= \frac{594}{6} + 1 = 100$

Alternatively :

22, 28, 34, ..., 616 = (4, 10, 16, 22, 28, ..., 616) − (4, 10, 16)

$\Rightarrow$ (6, 12, 18, 24, 30, ..., 618) − (6, 12, 18)

$\Rightarrow$ (1, 2, 3, 4, 5, ..., 103) − (1, 2, 3)

$\Rightarrow$ 103 − 3 = 100

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively : 22, 28, 34, ..., 616
$\Rightarrow$ 24, 30, 36, ..., 618
$\Rightarrow$ 4, 5, 6, ..., 103
$\Rightarrow$ 103 – 3 = 100

12. Number of terms $= \left(\frac{888-222}{2}\right)+1 = 334$

$\therefore \quad S_{334} = \left(\frac{222+888}{2}\right)\times 334$

$= 555 \times 334 = 185370$

Alternatively : $222 + 224 + \ldots + 888$
$= (2+4+6+\ldots+888) - (2+4+6+\ldots+220)$
$= (444 \times 445) - (110 \times 111)$
$= 111(4 \times 445 - 110) = 111(1780 - 110)$
$= 111 \times 1670 = 185370$

13. $T_2 = a + d = 2 \quad \ldots(1)$

$T_7 = a + 6d = 22 \quad \ldots(2)$

$\Rightarrow 5d = 20$ (subtracting (1) from (2))

$\Rightarrow \quad d = 4$

$\therefore a = -2$ (substituting 'd' in equation (1))

$\therefore \quad l = T_{35} = -2 + 34 \times 4 = 134$

$\therefore \quad S_{35} = \left(\frac{-2+134}{2}\right)\times 35 = 2310$

14. $T_{12} = a + 11d = -13 \quad \ldots(1)$

$S_4 = 24 = \left(\frac{a+T_4}{2}\right)\times 4 \quad \left\{\because S_n = \left(\frac{a+l}{2}\right)n\right\}$

$\Rightarrow \quad a + T_4 = 12$

$\Rightarrow \quad a + a + 3d = 12$

$\Rightarrow \quad 2a + 3d = 12 \quad \ldots(2)$

from equations (1) and (2)

$$\begin{array}{r} 2a + 22d = -26 \\ 2a + 3d = 12 \\ - \quad - \quad - \\ \hline 19d = -38 \end{array}$$

$\Rightarrow \quad d = -2$

$\therefore \quad a = 9$

Hence $S_{10} = \left(\frac{a+T_{10}}{2}\right)10$

$= \left[\frac{9+(-9)}{2}\right]\times 10 = 0 \quad \{\because T_{10} = -9\}$

15. $T_3 = a + 2d = \frac{1}{5} \quad \ldots(1)$

$T_5 = a + 4d = \frac{1}{3} \quad \ldots(2)$

$\Rightarrow \quad 2d = \frac{1}{3} - \frac{1}{5} = \frac{2}{15}$

$\Rightarrow \quad d = \frac{1}{15} \quad \therefore \quad a = \frac{1}{15}$

$\therefore \quad S_{15} = \left(\frac{a+T_{15}}{2}\right)15$

$= \left(\frac{1/15+1}{2}\right)\times 15 \quad (\because T_{15} = 1)$

$= \frac{\left(\frac{16}{15}\right)}{2}\times 15 = 8$

16. Let $n = 24$, then

$T_{24} = 1 + 23 \times 3 = 70$

$\therefore \quad S_{24} = \left(\frac{1+70}{2}\right)\times 24 = 71 \times 12 = 852$

$\therefore \quad S_{24} = 852 < 925$, hence wrong

Thus it is obvious that n must be greater than 24, which gives us $n = 25$, as per the choices given.

$\therefore \quad S_{25} = \left(\frac{a+T_{25}}{2}\right)25 \quad (\because T_{25} = T_{24} + d = 73)$

$= \left(\frac{1+73}{2}\right)\times 25 = 925$

Hence (d) is correct.

Alternatively : $S_n = 925 = \frac{n}{2}[2\times 1 + (n-1)3]$

$\Rightarrow \quad 1850 = 2n + 3n^2 - 3n$

$\Rightarrow \quad 3n^2 - n - 1850 = 0$

$\Rightarrow \quad 3n^2 - 75n + 74n - 1850 = 0$

$\Rightarrow \quad 3n(n-25) + 74(n-25) = 0$

$\Rightarrow \quad n = 25 \quad \text{or} \quad n = -\frac{74}{3}$

The only admissible value of $n = 25$
Since number of terms cannot be negative and as a fraction too.
Hence (d).

17. Best way is to go through options

$20 + 16 + 12 = 48,$

hence number of terms = 3

Again $20 + 16 + 12 + 8 + 4 + 0 + (-4) + (-8) = 48$

hence number of terms = 8

Thus choice (d) is most appropriate answer.

Alternatively :

$S_n = 48 = \frac{n}{2}[2\times 20 + (n-1)(-4)]$

$\Rightarrow \quad 96 = 40n - 4n^2 + 4n$

$\Rightarrow \quad n^2 - 11n + 24 = 0$

$\Rightarrow \quad (n-8)(n-3) = 0$

$\Rightarrow \quad n = 8 \quad \text{or} \quad n = 3$

Hence (d) is the correct answer.

18. $p = (r-2d), \quad q = (r-d), \quad r = r$

$s = (r+d), t = (r+2d)$

$\therefore \quad p + r + t = 3r = -12$

$\Rightarrow \quad r = -4$

Again $p \cdot q \cdot r = 8$

$\Rightarrow \quad p \cdot q = -2 \quad (\because r = -4)$

$\Rightarrow \quad (r-2d)(r-d) = -2$

$\Rightarrow \quad (-4-2d)(-4-d) = -2$

$\Rightarrow \quad (2+d)(4+d) = -1$

$\Rightarrow \quad d^2 + 6d + 9 = 0$

$\Rightarrow \quad (d+3)^2 = 0$

$\Rightarrow \quad d = -3$

$\therefore \quad p = (r-2d) = -4 - 2\times(-3) = 2$

Alternatively : Go through options.

Scanned by CamScanner

yourSmanboob.wordpress.com

Let us consider choice (a)

If $p + r + t = -12$

$\Rightarrow$ $r = -4$ ($\because$ r is the A.M. of p, r, t)

Now if $p = 3$, then

p	q	r	s	t
3	$-\frac{1}{2}$	-4	$-\frac{15}{2}$	-11

$\therefore$ $p \cdot q \cdot r = 3 \times \left(-\frac{1}{2}\right) \times (-4) = 6$, which is wrong.

Again consider choice (b)

p	q	r	s	t
2	-1	-4	-7	-10

$\therefore$ $p \cdot q \cdot r = 2 \times (-1) \times (-4) = 8$, which is correct.

Hence (b) is the right choice.

19. $l = a + (n-1)d$

$l = 7 + (n-1)3$

$\Rightarrow$ $l = 3n + 4$

Let us assume option (d), then

$102 = 3n + 4$

$\Rightarrow n = \frac{98}{3}$, which is inadmissible

Since number of terms can never be a fraction.

Now, assume option (b)

$79 = 3n + 4$

$\Rightarrow$ $n = 25$

$\therefore$ $S_{25} = \left(\frac{7 + 79}{2}\right) \times 25 = 1075$

but since $S_{25} = 1075 < 1242$

Hence l must be greater than 79, therefore choice (c) is possible.

Let us consider choice (c).

$l = 85 = 3n + 4$

$\Rightarrow$ $n = 27$

$\therefore$ $S_{27} = \left(\frac{7 + 85}{2}\right) \times 27 = 1242$

Hence (c) is correct.

Alternatively : $S_n = \frac{n}{2}[2a + (n-1)d]$

$1242 = \frac{n}{2}[14 + (n-1)3]$

$\Rightarrow$ $n(3n + 11) = 2484$

$\Rightarrow$ $3n^2 + 11n - 2484 = 0$

$\Rightarrow$ $3n^2 - 81n + 92n - 2484 = 0$

$\Rightarrow$ $3n(n - 27) + 92(n - 27)$

$\Rightarrow$ $n = 27$ or $n = -\frac{92}{3}$

Hence $n = 27$ is the only admissible value.

$\therefore$ $l = a + (n-1)d = 7 + 26 \times 3 = 85$

20. The required numbers are 56, 63, 70, ..., 5551

number of terms = 786

$\therefore$ $S_{786} = 56 + 63 + \ldots + 5551$

$= \left(\frac{56 + 5551}{2}\right) \times 786 = 2203551$

21. $T_1 = a = -14$

$T_5 = a + 4d = 2$

$d = 4$

$\Rightarrow$

Now, $S_n = \frac{n}{2}[2a + (n-1)d]$

$40 = \frac{n}{2}[-28 + (n-1)4]$

$\Rightarrow$ $n^2 - 8n - 20 = 0$

$\Rightarrow$ $n = 10$ or $n = -2$

Since number of terms can not be negative, hence $n = 10$

Alternatively : Since S_n is very small, therefore we can solve it physically within seconds.

$T_1 = -14, T_5 = 2$

T_1	T_2	T_3	T_4	T_5	T_6	T_7	T_8	T_9	T_{10}
-14	-10	-6	-2	2	6	10	14	18	22
				0					40

$\Rightarrow$ $T_1 + T_2 + \ldots + T_{10} = 0 + 40 = 40$

22. $S_n = \left(\frac{a + l}{2}\right)n$

$9153 = \left(\frac{-7 + 233}{2}\right)n$

$\Rightarrow$ $9153 = 113 \times n$

$\Rightarrow$ $n = 81$

23. Let the three consecutive numbers in A.P. be p, q, r such that

$p = (q - d)$ and $r = (q + d)$

$\therefore$ $p + q + r = 12$

$\Rightarrow$ $q = 4$

and $p^3 + q^3 + r^3 = 408$

$\Rightarrow$ $p^3 + r^3 = 344$ ($\because$ $q = 4$)

and $p + q + r = 12$

$\Rightarrow$ $p + r = 8$

Now, let us assume $p = 1$, then $r = 7$

$\therefore$ $p^3 + r^3 = 344$, which is true

Hence $p = 1$, $q = 4$ and $r = 7$

$\therefore$ $p \cdot q \cdot r = 1 \times 4 \times 7 = 28$

NOTE Another possible value of $p = 7$ and $r = 1$.

Alternatively : $p + q + r = 12$

$\Rightarrow$ $q = 4$ ($\because$ q is A.M. of p, q, r)

$\Rightarrow$ $p + r = 8$

and $p^3 + q^3 + r^3 = 408$

$\Rightarrow$ $p^3 + r^3 = 344$ ($\because$ $q^3 = 64$)

Now, $(p + r)^3 = p^3 + r^3 + 3pr(p + r)$

$(8)^3 = 344 + 3pr(8)$

$\Rightarrow$ $pr = 7$

$\therefore$ $pqr = q \cdot pr = 4 \times 7 = 28$

Alternatively : $p = (q - d)$

$q = q$

Scanned by CamScanner

yoursmahboob.wordpress.com

$r = (q + d)$

$(q - d) + q + (q + d) = 12$

$\therefore \quad q = 4$

$\Rightarrow \quad (q - d)^3 + q^3 + (q + d)^3 = 408$

and $\quad q^3 + 2qd^2 = 136$

$\Rightarrow \quad 8d^2 = 72 \qquad (\because\ q = 4)$

$\Rightarrow \quad d = \pm 3$

$\Rightarrow \quad p = 1 \text{ and } r = 7 \qquad \text{when } d = +3$

$\therefore \quad p = 7 \text{ and } r = 1 \qquad \text{when } d = -3$

and $\quad p \cdot q \cdot r = 1 \times 4 \times 7 = 7 \times 4 \times 1 = 28$

$\therefore$

24. Go through options.

Let us consider choice (c)

for $n = 1 \quad S_1 = (1)^3 + (1-1)^3 = 1$

for $n = 2 \quad S_2 = (2)^3 + (2-1)^3 = 9$

for $n = 3 \quad S_3 = (3)^3 + (3-1)^3 = 35$

Hence choice (c) is correct.

25. $S_{365} = \dfrac{365 \times 366}{2} \qquad \left(S_n = \dfrac{n(n+1)}{2}\right)$

or $\quad S_{365} = 66795$

26. $\dfrac{T_7}{T_3} = \dfrac{a + 6d}{a + 2d} = \dfrac{12}{5}$

$\Rightarrow \quad 5(a + 6d) = 12(a + 2d)$

$\Rightarrow \quad \dfrac{a}{d} = \dfrac{6}{7}$

Now, $\quad \dfrac{T_{13}}{T_4} = \dfrac{a + 12d}{a + 3d}$

$= \dfrac{\frac{a}{d} + 12}{\frac{a}{d} + 3} = \dfrac{\frac{6}{7} + 12}{\frac{6}{7} + 3} = \dfrac{10}{3}$

27. The numbers which are even and divisible by 5 also are 10, 20, 30 ... 1000.

$\therefore \quad S_{100} = 10 + 20 + 30 + \ldots + 1000$

$= 10(1 + 2 + 3 + \ldots + 100)$

$= 10 \times \dfrac{100 \times 101}{2} = 50500$

28. $m \cdot T_m = n \cdot T_n$

$m[a + (m-1)d] = n[a + (n-1)d]$

$\Rightarrow \quad m[a + md - d] = n[a + nd - d]$

$\Rightarrow \quad ma + m^2d - md = na + n^2d - nd$

$\Rightarrow \quad (m - n)a = (n^2 - m^2)d + (m - n)d$

$\Rightarrow \quad (m - n)a = -(m + n)(m - n)d + (m - n)d$

$\Rightarrow \quad (m - n)a = (m - n)d[1 - (m + n)]$

$\Rightarrow \quad a = [1 - (m + n)]d$

Now $\quad T_{(m+n)} = a + [(m + n) - 1]d$

$= [1 - (m + n)]d + [(m + n) - 1]d = 0$

29. $S_{15} = \dfrac{15}{2}[2a + 14d] = 105$

$\Rightarrow \quad 2a + 14d = 14 \qquad \ldots(1)$

and $\quad S_{30} = \dfrac{30}{2}[2a + 29d] = 105 + 780 = 885$

$\Rightarrow \quad 2a + 29d = 59 \qquad \ldots(2)$

$\therefore$ from equation (1) and (2)

$15d = 45 \quad \Rightarrow \quad d = 3$

30. $a \to 2$

and $\quad S_5 = \dfrac{1}{4}(S_{10} - S_5)$

$\Rightarrow \quad 5(S_5) = S_{10}$

$\Rightarrow \quad 5\left[\dfrac{5}{2}(4 + 4d)\right] = \dfrac{10}{2}[4 + 9d]$

$\Rightarrow \quad d = -6$

$\therefore \quad T_{20} = a + 19d$

$= 2 + 19 \times (-6) = -112$

31. $S_6 = 42$

$\Rightarrow \quad \dfrac{6}{2}[2a + 5d] = 42$

$\Rightarrow \quad 2a + 5d = 14 \qquad \ldots(1)$

Now, $\quad \dfrac{T_{10}}{T_{30}} = \dfrac{a + 9d}{a + 29d} = \dfrac{1}{3}$

$\Rightarrow \quad a = d$

$\therefore$ from equation (1)

$a = d = 2$

$\therefore \quad T_{40} = 2 + 39 \times 2 = 80$

32. $\dfrac{S_n}{S'_n} = \dfrac{7n + 1}{4n + 27}$

$\Rightarrow \quad \dfrac{\frac{n}{2}[2a + (n-1)d]}{\frac{n}{2}[2a' + (n-1)d']} = \dfrac{7n + 1}{4n + 27}$

$\Rightarrow \quad \dfrac{2a + (n-1)d}{2a' + (n-1)d'} = \dfrac{7n + 1}{4n + 27} \qquad \ldots(1)$

Now, $\quad \dfrac{T_{11}}{T'_{11}} = \dfrac{a + 10d}{a' + 10d'}$

Substituting $n = 21$ in equation (1), we get

$\dfrac{2a + 20d}{2a' + 20d'} = \dfrac{148}{111}$

$\Rightarrow \quad \dfrac{a + 10d}{a' + 10d'} = \dfrac{148}{111} = \dfrac{4}{3}$

33. $a + b + c = 15$

or $\quad (b - d) + b + (b + d) = 15$

$d \to$ common difference

$\Rightarrow \quad b = 5$

Again $\quad a^2 + b^2 + c^2 = 93$

$\Rightarrow \quad (b - d)^2 + b^2 + (b + d)^2 = 93$

$\Rightarrow \quad (b - d)^2 + (b + d)^2 = 68$

$\Rightarrow \quad (5 - d)^2 + (5 + d)^2 = 68$

$\Rightarrow \quad 2(5^2 + d^2) = 68$

$\Rightarrow \quad 25 + d^2 = 34$

$\Rightarrow \quad d = \pm 3$

$\therefore$ if $d = 3$, then $a = 2$ and $c = 8$

if $d = -3$, then $a = 8$ and $c = 2$

Therefore the greatest value is 8.

Scanned by CamScanner

yoursmathbook.wordpress.com

Alternatively : Go through option.
Since middle term $b = 5$
and let $c = 10$, then $a = 0$
$\therefore \quad a^2 + b^2 + c^2 = 125 \neq 93$, hence wrong
Again let $c = 8$, then $a = 2$
$\therefore \quad a^2 + b^2 + c^2 = 4 + 25 + 64 = 93$ hence correct.

34. $T_n = 4n - 1$
$\therefore \quad T_{30} = 119$
$\therefore \quad T_1 = 3, \quad T_2 = 7, \quad T_3 = 11, \ldots, 8, \quad T_{30} = 119$
$\therefore \quad S_{30} = \left(\frac{T_1 + T_{30}}{2}\right) \times 30 = \left(\frac{3 + 119}{2}\right) \times 30$
or $\quad S_{30} = 1830$

35. $S_n = 3n^2 + 5n$
$T_n = S_n - S_{(n-1)}$
$152 = [3n^2 + 5n] - [3(n-1)^2 + 5(n-1)]$
$152 = 6n + 2$
$\Rightarrow \quad n = 25$

Alternatively : Go through options.
$[3 \times (25)^2 + 5 \times 25] - [3 \times (24)^2 + 5 \times 24]$
$= (2000) - (1848) = 152$
Hence (d) is correct.

36. $S_n = \frac{n}{2}[2a + (n-1)d]$
$0 = \frac{n}{2}[196 + (n-1) \times (-7)]$
$\Rightarrow \quad 0 = n(203 - 7n)$
$\Rightarrow \quad 7n = 203 \quad \text{or} \quad n = 0$
$\Rightarrow \quad n = 29$
Since $n = 0$ is not acceptable.
The A.P. is 98, 91, 84, ... 0, ..., – 91, –98
(Try to understand it as it is a problem of common sense, there is no need to calculate with the help of formula.)

37. It is possible only when all the terms of A.P. are non-negative.
∴ Let T_n be the least possible non-negative term of the A.P. then
$T_n \geq 0$
$\therefore \quad a + (n-1)d \geq 0$
$17 + (n-1) \times (-3) \geq 0$
$\Rightarrow \quad 20 - 3n \geq 0$
$\Rightarrow \quad n \leq \frac{20}{3}$
$\Rightarrow \quad n \leq 6$ (only integral part is considerable)
$\therefore \quad n = 6$
$\therefore \quad T_6 = 17 + 0.5 \times (-3)$
$T_6 = 2$
$\therefore \quad S_6 = \left(\frac{17 + 2}{2}\right) \times 6 = 57$

(The required A.P. is 17, 14, 11, 8, 5, 2).

38. The least possible sum can be obtained only when all the terms of A.P. be non-positive.
Let the last term be T_n which must be non-positive.
$T_n \leq 0$
$\therefore \quad a + (n-1)d \leq 0$
$-23 + (n-1)4 \leq 0$
$4n \leq 27$
$n \leq 6$
$n = 6$
$\therefore \quad T_n = T_6 = -23 + 5 \times 4 = -3$
$\therefore \quad S_6 = \left[\frac{(-23) + (-3)}{2}\right] \times 6 = -78$

(The required A.P. is – 23, – 19, – 15, – 11, – 7, – 3).

39. The required numbers are 1017, 1035, 1053, ..., 9999
Total number of terms = 500 $\left[\because \ n = \left(\frac{9999 - 1017}{18}\right) + 1\right]$
∴ Sum of all the numbers $= \left(\frac{1017 + 9999}{2}\right) \times 500$
$= 2754000$

40. Let an A.P. be 3, 7, 11, 15, 19, 23, 27, ...
and Let $p = 2, \quad q = 3, \quad r = 7$
then $T_p = a = 7$
$T_q = b = 11$
$T_r = c = 27$
$\therefore \quad p(b-c) + q(c-a) + r(a-b)$
$= 2(11 - 27) + 3(27 - 7) + 7(7 - 11)$
$= -32 + 60 - 28 = 0$
Hence (a) is true.

41. Let an A.P. be 2, 5, 8, 11, 14, 17, 20, 23, ...
and let $p = 3, q = 5, r = 6$
then $S_p = a = (2 + 5 + 8) = 15$
and $S_q = b = (2 + 5 + 8 + 11 + 14) = 40$
and $S_r = c = (2 + 5 + \ldots + 14 + 17) = 57$
$\therefore \frac{a}{p}(q-r) + \frac{b}{q}(r-p) + \frac{c}{r}(p-q)$
$= \frac{15}{3}(5-6) + \frac{40}{5}(6-3) + \frac{57}{6}(3-5)$
$= -5 + 24 - 19 = 0$
Hence (c) is correct.

42. Let p, q, r, s be the four consecutive terms in A.P. then
$p = (m - 3d)$
$q = (m - d)$
$r = (m + d)$
$s = (m + 3d)$
$\therefore \ p + q + r + s = (m - 3d) + (m - d) + (m + d) + (m + 3d) = 20$
$\Rightarrow \quad 4m = 20$
$\Rightarrow \quad m = 5 \quad \ldots(1)$
Again $(m - 3d)(m + 3d) : (m - d)(m + d) = 2 : 3$
$\Rightarrow \quad \frac{m^2 - 9d^2}{m^2 - d^2} = \frac{2}{3}$
$\Rightarrow \quad m = 5d$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore \quad d = 1$ (from equation 1)

Hence $(m - 3d)(m + 3d) = (5 - 3)(5 + 3) = 16$

Alternatively : Since p, q, r and s are in A.P.

$p + q + r + s = 20$

and $p + s = 10$ and $q + r = 10$

$\Rightarrow$

Let $p = 1$, then $s = 9$

$\therefore \quad q = 1 + \frac{8}{3} = \frac{11}{3} \qquad \left(\because\ d = \frac{8}{3}\right)$

and $r = \frac{11}{3} + \frac{8}{3} = \frac{19}{3}$

$\therefore \quad \frac{p \cdot s}{q \cdot r} = \frac{1 \times 9}{\frac{11}{3} \times \frac{19}{3}} = \frac{9 \times 9}{11 \times 19} = \frac{81}{209} \neq \frac{2}{3}$

Hence the values of p, q, r and s are wrong.

Again if $p = 2$, then $s = 8$

$\therefore \quad q = 2 + 2 = 4 \qquad (\because\ d = 2)$

and $r = 4 + 2 = 6$

$\therefore \quad \frac{p \cdot s}{q \cdot r} = \frac{2 \times 8}{4 \times 6} = \frac{2}{3}$, hence true.

Thus the values of p, q, r and s are correct.

Hence $p \cdot s = 2 \times 8 = 16$

43. $S_p = \frac{p}{2}[2a + (p-1)d] = q \qquad \ldots(1)$

and $S_q = \frac{q}{2}[2a + (q-1)d] = p \qquad \ldots(2)$

from (1) $2a + (p-1)d = \frac{2q}{p} \qquad \ldots(3)$

and from (2) $2a + (q-1)d = \frac{2p}{q} \qquad \ldots(4)$

subtracting equation (4) from equation (3), we get

$(p - q)d = \frac{-2(p+q)(p-q)}{pq}$

$\Rightarrow \quad d = \frac{-2(p+q)}{pq}$

Now, from equation (3)

$2a + (p-1)\left(\frac{-2(p+q)}{pq}\right) = \frac{2p}{q}$

$\Rightarrow \quad a = \frac{p^2 + q^2 + pq - (p+q)}{pq}$

$\therefore \quad S_{p+q} = \frac{(p+q)}{2}[2a + (p+q-1)d]$

$= \frac{(p+q)}{2}\left[\frac{2(p^2 + q^2 + pq - (p+q))}{pq} - \frac{2(p+q-1)(p+q)}{pq}\right]$

$= \frac{(p+q)}{2}\left[\frac{2}{pq}(p^2 + q^2 + pq - p - q - p^2 - q^2 - pq + p + q - pq)\right]$

$= \frac{(p+q)}{pq}(-pq)$

$S_{(p+q)} = -(p+q)$

INTRODUCTORY EXERCISE 18.2

1. Every even term is equal to 2

common ratio of the G.P. is -1

2. $r = -2 \qquad \left(\because\ r = \frac{\frac{1}{4}}{-\frac{1}{8}} = \frac{\frac{-1}{2}}{\frac{1}{4}} = -2\right)$

$\therefore \quad T_7 = \frac{-1}{8} \cdot (-2)^6$

$= -\frac{1}{8} \times 64 = -8$

3. $T_5 = a_1 \cdot r^4 = a$

$T_8 = a_1 \cdot r^7 = b$

$T_{11} = a_1 \cdot r^{10} = c$

$\therefore$ Let $b^2 = ac$

then $(a_1 r^7)^2 = a_1 r^4 \cdot a_1 r^{10}$

$\Rightarrow \quad a_1^2 r^{14} = a_1^2 r^{14}$

Hence (b) is correct.

4. $T_5 = ar^4 = 32$

$T_{12} = ar^{11} = 4096$

$\therefore \quad r^7 = \frac{4096}{32} = 2^7$

$\Rightarrow \quad r = 2$

$\therefore \quad a = 2 \qquad (\because\ ar^4 = 32)$

$\therefore \quad T_n = ar^{n-1} = 2 \cdot 2^{n-1} = 2^{1+n-1} = 2^n$

5. $S_n > 10^6$, for least possible $n \in I^+$

then, $\frac{5(2^n - 1)}{(2-1)} > 10^6$

$\Rightarrow \quad 2^n - 1 > 2 \times 10^5$

$\Rightarrow \quad 2^n > 200001$

at $n = 17$, $2^n = 2^{17} = 131072$

and at $n = 18$, $2^n = 2^{18} = 262144$

Hence the least possible value of $n = 18$

6. Let a, b be the two numbers then

$\text{A.M.} = \frac{a+b}{2} = 15$

$\Rightarrow \quad a + b = 30$

and $\text{G.M.} = \sqrt{ab} = 12$

$\Rightarrow \quad ab = 144$

Now go through options

let $a = 6$, then $b = 24$

$\therefore \quad a \cdot b = 6 \times 24$

Hence choice (c) is correct.

Alternatively : $(a - b)^2 = (a + b)^2 - 4ab$

$= (30)^2 - 4 \times 144$

$= 900 - 576 = 324$

$\Rightarrow \quad a - b = \pm 18$

$\therefore \quad (a, b) = (6, 24)$ or $(24, 6)$

Scanned by CamScanner

yoursmahboob.wordpress.com

7. Let a, b, c be the three numbers in G.P. then

$$a + b + c = 38$$

and $$abc = 1728$$

$\Rightarrow$ $$b = (abc)^{1/3} = (1728)^{1/3} = 12$$

$\therefore$ $$a \times c = 144$$

and $$a + c = 26$$

Now, go through options

Let $c = 18$, then $a = 8$

$\therefore$ $$a \cdot c = 8 \times 18 = 144$$

Hence choice (b) is correct

Alternatively : Let the three numbers in G.P. be

$$\frac{a}{r}, a, ar$$

$\therefore$ $$\frac{a}{r} + a + ar = 38 \quad \ldots(1)$$

and $$\frac{a}{r} \cdot a \cdot ar = 1728 \quad \ldots(2)$$

$\Rightarrow$ $$a = 12$$

$\therefore$ $$\frac{12}{r} + 12 + 12r = 38$$

or $$\frac{6}{r} + 6 + 6r = 19$$

$\Rightarrow$ $$6r^2 - 13r + 6 = 0$$

$\Rightarrow$ $$6r^2 - 9r - 4r + 6 = 0$$

$\Rightarrow$ $$(2r - 3)(3r - 2) = 0$$

$\Rightarrow$ $$r = \frac{3}{2} \text{ or } r = \frac{2}{3}$$

$\therefore$ Three number in G.P. are 8, 12, 18 or 18, 12, 8.
Hence (b) is correct.

8.
$$\frac{S_3}{S_6} = \frac{125}{152} = \frac{\frac{a(r^3 - 1)}{(r - 1)}}{\frac{a(r^6 - 1)}{(r - 1)}} = \frac{r^3 - 1}{r^6 - 1}$$

$\Rightarrow$ $$\frac{r^3 - 1}{(r^3)^2 - 1} = \frac{125}{152}$$

$\Rightarrow$ $$\frac{(r^3 - 1)}{(r^3 + 1)(r^3 - 1)} = \frac{125}{152}$$

$\Rightarrow$ $$\frac{1}{r^3 + 1} = \frac{125}{152}$$

$\Rightarrow$ $$r^3 + 1 = \frac{152}{125}$$

$\Rightarrow$ $$r^3 = \frac{27}{125}$$

$\Rightarrow$ $$r = \frac{3}{5}$$

Alternatively : Go through options.

9. $$a + b + c = 14$$

Let $$abc = 125$$

$\Rightarrow$ $$b = 5$$

let $a = 1$, then $c = 25$

$\therefore$ $a + b + c = 31$, which is wrong.

Again let $$a \cdot b \cdot c = 64$$

$$b = 4$$

$\Rightarrow$

Let $a = 1$ then $c = 16$

$\Rightarrow$ $a + b + c = 21$, which is wrong

again if $a = 2$ then $c = 8$

$\therefore$ $$a + b + c = 2 + 4 + 8 = 14$$

Hence choice (b) may be correct

$$a = 2, \quad b = 4, \quad c = 8$$

$$a' = 3, \quad b' = 5, \quad c' = 7$$

$\because$ a', b' and c' are in A.P.

Hence choice (b) is correct.

Alternatively : $a + b + c = 14$

since $(a + 1), (b + 1)$ and $(c - 1)$ are in A.P.

$\therefore$ $$(b + 1) - (a + 1) = (c - 1) - (b + 1)$$

$\Rightarrow$ $$2b + 2 = a + c$$

Now, from equation (1)

$$3b + 2 = 14$$

$\Rightarrow$ $$b = 4$$

Again $$a = \frac{b}{r} \text{ and } c = br$$

$\therefore$ $$a + b + c = 14$$

$\Rightarrow$ $$\frac{b}{r} + b + br = 14$$

$\Rightarrow$ $$\frac{4}{r} + 4 + 4r = 14$$

$\Rightarrow$ $$2r^2 - 5r + 2 = 0$$

$\Rightarrow$ $$r = 2 \text{ or } r = \frac{1}{2}$$

$\therefore$ $$a \cdot b \cdot c = 2 \times 4 \times 8 = 8 \times 4 \times 2 = 64$$

Shortcut : Since $b = 4$

$\therefore$ $abc = b^3$ ($\because$ a, b, c are in G.P.)

$\therefore$ $abc = 64$

10. Let a, b, c, d, e be five consecutive terms in G.P. then

$$a = \frac{c}{r^2}, \quad b = \frac{c}{r}, \quad d = cr, \quad e = cr^2$$

$\therefore$ $$a \cdot b \cdot c \cdot d \cdot e = \frac{c}{r^2} \cdot \frac{c}{r} \cdot c \cdot cr \cdot cr^2 = c^5$$

$\therefore$ $a \cdot b \cdot c \cdot d \cdot e = 4^5$ ($\because$ $c = 4$)

11. Let a, b, c be in G.P., then

$$a + b + c = 21 = 3(7) = 3(1 + 2 + 4)$$

and $a^2 + b^2 + c^2 = 189 = 9(21) = 9(1 + 4 + 16)$

Hence common ratio = 2

Alternatively : $a + ar + ar^2 = 21$

$\Rightarrow$ $$a(1 + r + r^2) = 21$$

and $$a^2 + (ar)^2 + (ar^2)^2 = 189$$

$\therefore$ $$a^2(1 + r^2 + r^4) = 189$$

$\Rightarrow$ $$a^2[(1 + r^2)^2 - r^2] = 189$$

$\Rightarrow$ $$a^2[(1 + r^2 + r)(1 + r^2 - r)] = 189$$

Dividing equation (2) by equation (1), we get

$$a(1 - r + r^2) = 9$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Dividing equation (1) by equation (3), we get

$$\frac{1+r^2+r}{1+r^2-r}=\frac{21}{9}=\frac{7}{3}$$

$$\Rightarrow \quad \frac{(1+r^2)+r}{(1+r^2)-r}=\frac{7}{3}$$

$$\Rightarrow \quad \frac{1+r^2}{r}=\frac{5}{2}$$

(By componendo and dividendo)

$$\Rightarrow \quad 2r^2-5r+2=0$$

$$\Rightarrow \quad r=2 \text{ or } r=\frac{1}{2}$$

12. $T_1+T_3=a+ar^2=15$ ...(1)

and $T_5+T_7=ar^4+ar^6=240$ ...(2)

From equation (1) $a(1+r^2)=15$

and equation (2) becomes $ar^4(1+r^2)=240$

$$\therefore \quad r^4=16$$

$$\Rightarrow \quad r=\pm 2$$

$\therefore a=3$ (from equation (1))

$$\therefore \quad T_9=a\cdot r^8=3\cdot(2)^8=768$$

13. $a+b+c=42$

$abc=512$

$$\Rightarrow \quad b=8 \qquad (\because (abc)^{1/3}=b=8)$$

$$\therefore \quad ac=64$$

and $a+c=34$

Now, go through options (or by hit and trial)

$\therefore$ either $a=2$, then $c=32$

or $a=32$ then $c=2$

Hence, (c) is correct.

14. $a+b+c=70$

and $4a, 5b, 4c$ are in A.P.

$$\therefore \quad 10b=4(a+c)$$

$$\Rightarrow \quad a+c=\frac{5b}{2}$$

$$\therefore \quad a+b+c=\frac{7b}{2}=70$$

$$\Rightarrow \quad b=20$$

$$\therefore \quad a+c=50$$

By hit and trial $a=10$ and $c=40$

Now $4a=40$, $5b=100$ and $4c=160$

Hence, $a\times b\times c=10\times 20\times 40=8000$

Alternatively : $\frac{b}{r}+b+br=70$

$$\Rightarrow \quad \frac{20}{r}+20+20r=70$$

$$\Rightarrow \quad \frac{2}{r}+2+2r=7$$

$$\Rightarrow \quad 2r^2-5r+2=0$$

$$\Rightarrow \quad r=2 \text{ or } r=\frac{1}{2}$$

$\therefore a, b, c = 10, 20, 40$ or $40, 20, 10$

$$\therefore \quad abc=8000$$

15. $a+b+c+d=312$

$a+ar+ar^2+ar^3=312$

and $a+d=252$

and $b+c=312-252=60$

$$\Rightarrow \quad a+ar^3=252$$

and $ar+ar^2=60$

$$\Rightarrow \quad a(1+r^3)=252$$

and $a(r+r^2)=60$

$$\therefore \quad \frac{a(1+r^3)}{a(r+r^2)}=\frac{252}{60}=\frac{21}{5}$$

$$\Rightarrow \quad \frac{1+r^3}{r+r^2}=\frac{21}{5}$$

$$\Rightarrow \quad \frac{(1+r)(1+r^2-r)}{r(1+r)}=\frac{21}{5}$$

$$(\because \ a^3+b^3=(a+b)(a^2+b^2-ab))$$

$$\Rightarrow \quad \frac{1+r^2-r}{r}=\frac{21}{5}$$

$$\Rightarrow \quad 5r^2-26r+5=0$$

$$\Rightarrow \quad r=5 \text{ or } r=\frac{1}{5}$$

$$\therefore \quad a=2 \text{ and } ar\times ar^2=500 \qquad (\text{when } r=5)$$

and $a=250$ and $ar\times ar^2=500$ (when $r=\frac{1}{5}$)

Alternatively : Go through options.

16. Distance travelled before the first hit = 16 m

Distance travelled before the second hit $=16+\frac{1}{2}\times 16\times 2$

$=(16+16)$ m

Distance travelled before the third hit

$=16+16+\frac{1}{2}\times 8\times 2$

$=(16+16+8)$ m

Distance travelled before the fourth hit

$=16+16+8+\frac{1}{2}\times 4\times 2$

$=(16+16+8+4)$ m

and so on.

Hence the required distance

$$=16+16+8+4+2+1+\frac{1}{2}+\frac{1}{4}+\frac{1}{8}+\frac{1}{16}$$

$$=16+\left(16+8+4+\ldots+\frac{1}{16}\right)$$

$$=16+\frac{16\left(1-\left(\frac{1}{2}\right)^9\right)}{1-\frac{1}{2}}=16+16\times\left(\frac{511}{512}\right)\times\frac{2}{1}$$

$$=16+\frac{511}{16}=47\frac{15}{16}$$

17. $S_n=7+77+777+\ldots$ to n terms

$=7(1+11+111+\ldots$ to n terms$)$

$=\frac{7}{9}(9+99+999+\ldots$ to n terms$)$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{7}{9}\{(10-1)+(100-1)+(1000-1)+\ldots \text{to } n \text{ terms}\}$$

$$= \frac{7}{9}\{(10+100+1000+\ldots \text{ to } n \text{ terms}) - (1+1+1+\ldots \text{to } n \text{ terms})\}$$

$$= \frac{7}{9}\left\{\frac{10\cdot(10^n-1)}{10-1} - n\right\}$$

$$= \frac{7}{9}\left\{\frac{10}{9}(10^n-1) - n\right\}$$

Alternatively : Best way is to go through options.

Consider $n = 2$, then $S_2 = 7 + 77 = 84$

Now, put $n = 2$ in choice (b).

NOTE This type of questions necessarily be solved by options and must take at least two values for $n = 2, 3$ etc. as a measure of safety.

18. It is very similar to the previous question.

19. Let a G.P. be 1, 3, 9, 27, 81, 243, 729, ...

Consider $p = 2, \quad q = 5, \quad r = 6$

$\therefore \quad T_p = 3 = a$

$T_q = 81 = b$

$T_r = 243 = c$

$\therefore \quad a^{q-r}\cdot b^{r-p}\cdot c^{p-q} = 3^{(5-6)}\cdot 81^{(6-2)}\cdot 243^{(2-5)}$

$= 3^{-1}\cdot 81^4\cdot 243^{-3}$

$= 3^{-1}\cdot 3^{16}\cdot 3^{-15}$

$= 3^{-16}\cdot 3^{16} = 3^0 = 1$

20. Let the G.P. be 1, 2, 4, 8, 16, 32, 64, ...

Let $x = 3, \quad y = 5$ and $z = 6$

$\therefore \quad T_x = 4 = a$

$T_y = 16 = b$

$T_z = 32 = c$

$\therefore (y-z)\log a + (z-x)\log b + (x-y)\log c$

$= -1\cdot\log 4 + 3\log 16 + (-2)\log 32$

$= \log 2^{-2} + \log 2^{12} + \log 2^{-10}$

$= \log 2^0 = \log 1 = 0$

21. Let a, b, c, d be four numbers such that a, b, c are in A.P. and b, c, d are in G.P.

$\therefore \quad a + c = 2b \quad \ldots(1)$

and $\quad bd = c^2 \quad \ldots(2)$

Also $\quad a + c = 2 \quad \ldots(3)$

and $\quad b + d = 26 \quad \ldots(4)$

$\Rightarrow \quad b = 1$

from (4), $d = 25$

$\therefore$ from (2) $c = \pm 5$

when $c = 5$, then $a = -3$

when $c = -5$, then $a = 7$

Hence the four numbers are $-3, 1, 5, 25$ or $7, 1, -5, 25$

22. $S_n = 1 + 3 + 7 + 15 + \ldots + t_n \quad \ldots(1)$

and $S_n = 1 + 3 + 7 + \ldots + t_{n-1} + t_n \quad \ldots(2)$

subtracting, we get

$0 = (1 + 2 + 4 + 8 + \ldots + \text{to } n \text{ terms}) - t_n$

$\Rightarrow \quad t_n = 1 + 2 + 4 + 8 + \ldots \text{to } n \text{ terms}$

$\Rightarrow \quad t_n = \frac{1\cdot(2^n-1)}{(2-1)} = 2^n - 1$

again $S_n = t_1 + t_2 + t_3 + \ldots + t_n$

$= (2-1) + (2^2-1) + (2^3-1) + \ldots + (2^n-1)$

$= (2 + 2^2 + 2^3 + \ldots 2^n) - (n)$

$= \frac{2(2^n-1)}{(2-1)} - n$

$= 2(2^n-1) - n$

Alternatively : Go through options.

23. $S = \frac{1}{2} + \frac{3}{2^2} + \frac{5}{2^3} + \frac{7}{2^4} + \ldots + \frac{2n-3}{2^{n-1}} + \frac{2n-1}{2^n}$

and $\frac{1}{2}S = \frac{1}{2^2} + \frac{3}{2^3} + \frac{5}{2^4} + \ldots + \frac{2n-3}{2^n} + \frac{2n-1}{2^{n+1}}$

subtracting we get,

$$\frac{1}{2}S = \frac{1}{2} + \frac{2}{2^2} + \frac{2}{2^3} + \ldots + \frac{2}{2^n} - \frac{2n-1}{2^{n+1}}$$

$$= \frac{1}{2} + 2\left(\frac{1}{2^2} + \frac{1}{2^3} + \frac{1}{2^4} + \ldots + \frac{1}{2^n}\right) - \frac{2n-1}{2^{n+1}}$$

$$= \frac{1}{2} + \frac{2\cdot\frac{1}{2^2}\left\{1 - \left(\frac{1}{2}\right)^{n-1}\right\}}{1-\frac{1}{2}} - \frac{2n-1}{2^{n+1}}$$

$\therefore \quad S = 3 - \frac{2n+3}{2^n}$

24. Go through options.

Alternatively : $11 + 102 + 1003 + \ldots$

$= (10+1) + (100+2) + (1000+3)$

$= (10 + 100 + 1000 + \ldots) + (1 + 2 + 3 + \ldots)$

25. Go through options.

Alternatively : $T_n = 1 + 3 + 9 + \ldots$

or $\quad T_n = \frac{1}{2}(3^n - 1)$

$\therefore \quad S_n = t_1 + t_2 + t_3 + \ldots + t_n$

$S_n = \frac{1}{2}[(3^1 + 3^2 + 3^3 + \ldots + 3^n) - n]$

$= \frac{1}{2}\left[\frac{3(3^n-1)}{2} - n\right]$

$= \frac{1}{4}[3(3^n-1) - 2n]$

$= \frac{3}{4}(3^n-1) - \frac{n}{2}$

26. $S_n = 2 + 5 + 14 + 41 + \ldots \text{to } n \text{ terms} \quad \ldots(i)$

and $S_n = 2 + 5 + 14 + 41 + \ldots \text{to } n \text{ terms} \quad \ldots(ii)$

subtracting we get,

$0 = 2 + 3 + 9 + 27 + \ldots - t_n$

$\Rightarrow \quad t_n = 2 + 3 + 9 + 27 + \ldots$

$\Rightarrow \quad t_n = 2 + \{3 + 9 + 27 + \ldots \text{to } (n-1) \text{ terms}\}$

$\Rightarrow \quad t_n = 2 + \frac{3(3^{n-1}-1)}{2}$

$\therefore \quad S_n = t_1 + t_2 + t_3 + \ldots + t_n$

$S_n = \Sigma t_n = t_1 + t_2 + t_3 + \ldots + t_n$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \Sigma\left\{2 + \frac{3(3^{n-1} - 1)}{2}\right\}$$

$$= \Sigma\left\{2 + \frac{3^n}{2} - \frac{3}{2}\right\}$$

$$= \Sigma\left\{\frac{1}{2} + \frac{3^n}{2}\right\}$$

$$= \left\{\frac{n}{2} + \frac{1}{2}(3 + 3^2 + 3^3 + \ldots + 3^n)\right\}$$

$$= \left\{\frac{n}{2} + \frac{1}{2}\left(\frac{3\cdot(3^n - 1)}{2}\right)\right\}$$

$$= \left\{\frac{n}{2} + \frac{1}{4}3\cdot(3^n - 1)\right\}$$

$$= \frac{3}{4}(3^n - 1) + \frac{n}{2}$$

Alternatively : You should go through options.
Consider $n = 1$, 2 or 3 and verify the correct option.

As, when you put $n = 1$, in the correct formula you will get $S_1 = 2$

and at $n = 2$, $S_2 = 7$ $(2 + 5)$

and at $n = 3$, $S_3 = 21$ $(2 + 5 + 14)$

27. $S_n = 1 + 2x + 3x^2 + 4x^3 + \ldots$

$x\cdot S_n = x + 2x^2 + 3x^3 + 4x^4 + \ldots$

subtracting we get

$$(1 - x)S_n = (1 + x + x^2 + x^3 + \ldots + x^{n-1}) - nx^n$$

$$(1 - x)S_n = \frac{1 - x^n}{(1 - x)} - nx^n$$

$$\Rightarrow \quad S_n = \frac{1 - x^n}{(1 - x)^2} - \frac{nx^n}{(1 - x)}$$

Alternatively : Go through options.

28. Solve through options.

NOTE This is very similar to the previous problem.

29. Let $S_n = 1 + \frac{2}{3} + \frac{3}{3^2} + \frac{4}{3^3} + \ldots + \frac{n}{3^{n-1}}$

$$\therefore \quad \frac{1}{3}S_n = \frac{1}{3} + \frac{2}{3^2} + \frac{3}{3^3} + \frac{4}{3^4} + \ldots + \frac{n-1}{3^{n-1}} + \frac{n}{3^n}$$

subtracting we get,

$$\frac{2}{3}S_n = \left(1 + \frac{1}{3} + \frac{1}{3^2} + \frac{1}{3^3} + \frac{1}{3^4} + \ldots\right) - \frac{n}{3^n}$$

$$\Rightarrow \quad \frac{2}{3}S_n = \left[\frac{1\left\{1 - \left(\frac{1}{3}\right)^n\right\}}{1 - \frac{1}{3}}\right] - \frac{n}{3^n}$$

$$\Rightarrow \quad \frac{2}{3}S_n = \frac{3}{2}\left\{1 - \left(\frac{1}{3}\right)^n\right\} - \frac{n}{3^n}$$

$$\Rightarrow \quad S_n = \frac{9}{4} - \frac{3}{4}\left(\frac{3 + 2n}{3^n}\right)$$

30. Let $S_n = 3\cdot 2 + 5\cdot 2^2 + 7\cdot 2^3 + \ldots + (2n - 1)\cdot 2^n$

$\therefore 2S_n = 3\cdot 2^2 + 5\cdot 2^3 + \ldots + (2n - 1)\cdot 2^n + (2n + 1)\cdot 2^{n+1}$

subtracting, we get

$-S_n = 3\cdot 2 + 2\cdot 2^2 + 2\cdot 2^3 + \ldots + 2\cdot 2^n - (2n + 1)\cdot 2^{n+1}$

$= 3\cdot 2 + 2(2^2 + 2^3 + \ldots + 2^n) - (2n + 1)\cdot 2^{n+1} = \text{etc}$

Now, simplify by yourself.

31. Go through options.

32. $t_n = n(2n + 1)^2$

$= 4n^3 + 4n^2 + n$

$\therefore \quad S_n = \Sigma t_n = 4\Sigma n^3 + 4\Sigma n^2 + \Sigma n$

then put $n = 20$

33. $$t_n = \frac{n^2(n + 1)^2}{4n^2} = \frac{1}{4}(n^2 + 2n + 1)$$

$$\therefore \quad S_n = \Sigma t_n = \frac{1}{4}[\Sigma n^2 + 2\Sigma n + n]$$

then put $n = 16$.

34. Let a, b, c and d be the required numbers, then a, b, c are in G.P. and b, c, d are in A.P.

a	b	c	d	
↓	↓	↓	↓	
a	b	$b + 6$	$b + 12$	(common difference = 6)
↓	↓	↓	↓	
$b + 12$	b	$b + 6$	$b + 12$	$(\because\ a = d)$

Now, since a, b, c are in G.P.

$$\therefore \quad \frac{c}{b} = \frac{b}{a}$$

$$\Rightarrow \quad \frac{b + 6}{b} = \frac{b}{b + 12}$$

$$\Rightarrow \quad (b + 6)(b + 12) = b^2$$

$$\Rightarrow \quad b = -4$$

$$\therefore \quad c = b + 6 = -4 + 6 = 2$$

Alternatively : Go through options.

35. Let a be the first term and r be the common ratio of the G.P. then

$$S_\infty = a + ar + ar^2 + \ldots = 16 = \frac{a}{1 - r}, |r| < 1$$

$$\therefore \quad \frac{a}{1 - r} = 16 \qquad \ldots(1)$$

and $\quad a^2 + (ar)^2 + (ar^2)^2 + \ldots = 153\frac{3}{5}$

$$\Rightarrow \quad a^2 + a^2r^2 + a^2r^4 + \ldots = \frac{768}{5}$$

$$\Rightarrow \quad \frac{a^2}{1 - r^2} = \frac{768}{5} \qquad \ldots(2)$$

dividing equation (2) by equation (1), we get

$$\frac{\frac{a^2}{(1 - r^2)}}{\frac{a}{(1 - r)}} = \frac{\frac{768}{5}}{16}$$

$$\Rightarrow \quad \frac{a}{1 + r} = \frac{48}{5} \qquad \ldots(3)$$

dividing equation (1) by equation (3)

Scanned by CamScanner

yourmanboob.wordpress.com

$$\frac{\frac{a}{(1-r)}}{\frac{a}{(1+r)}} = \frac{16}{\frac{48}{5}}$$

$$\Rightarrow \quad \frac{1+r}{1-r} = \frac{5}{3}$$

$$\Rightarrow \quad \frac{1}{r} = 4 \quad \text{(By componendo-dividendo)}$$

$$\Rightarrow \quad r = \frac{1}{4}$$

$$\therefore \quad a = 16 \times \left(1 - \frac{1}{4}\right) \text{ from equation (1)}$$

$$a = 12$$

$$\therefore \quad T_4 = ar^3 = 12 \times \left(\frac{1}{4}\right)^3 = \frac{3}{16}$$

36. $x = 1 + a + a^2 + a^3 + \ldots \infty$

$$\therefore \quad x = \frac{1}{1-a} \quad \because |a| < 1$$

Similarly, $y = \frac{1}{1-b}$

Let $S = 1 + ab + a^2b^2 + \ldots \infty$

$= 1 + ab + (ab)^2 + \ldots \infty$

$= \frac{1}{1-ab}$ $(\because |ab| < 1)$ ...(1)

Now, go through option

$$\frac{xy}{x+y-1} = \frac{\frac{1}{1-a} \times \frac{1}{1-b}}{\frac{1}{1-a} + \frac{1}{1-b} - 1} = \frac{1}{1-ab}$$

Hence, $S = 1 + ab + a^2b^2$

$= \frac{1}{1-ab} = \frac{xy}{x+y-1}$

37. His first payment = Rs. 100

His second payment = Rs. $90 = \left(100 \times \frac{9}{10}\right)$

His third payment = Rs. 81 etc. $= \left(90 \times \frac{9}{10}\right)$

∴ The annual payments are 100, 90, 81, ... which are in G.P. with common ratio $\frac{9}{10}$ (< 1)

Therefore the sum to infinity of this G.P.

$= 100 + 90 + 81 + \ldots \infty$

$$= \frac{100}{1 - \frac{9}{10}} = \frac{100}{\frac{1}{10}} = 1000$$

Hence the person can receive maximum amount of Rs. 1000.

38. $S_\infty = \frac{1}{4} - \frac{3}{16} + \frac{9}{64} - \frac{27}{256} + \ldots$

$$S_\infty = \frac{\frac{1}{4}}{1 - \left(-\frac{3}{4}\right)} = \frac{\frac{1}{4}}{\frac{7}{4}}$$

$$S_\infty = \frac{1}{7}$$

39. $a + ar = \frac{5}{3} \Rightarrow a(1+r) = \frac{5}{3}$ ...(1)

and $\frac{a}{1-r} = 3$ ...(2)

Dividing equation (1) by equation (2), we get

$$(1+r)(1-r) = \frac{5}{9}$$

$$\Rightarrow \quad 1 - r^2 = \frac{5}{9}$$

$$\Rightarrow \quad r^2 = \frac{4}{9} \Rightarrow r = \pm\frac{2}{3}$$

If $r = \frac{2}{3}$, then $a = 1$ and if $r = -\frac{2}{3}$, then $a = 5$

40. Distance covered by ball just before it hits the ground for the first time = 96 feet.

In the first round (*i.e.* going up and returning to the earth) ball covers the distance $= \left(96 \times \frac{2}{3}\right) \times 2$

In the third round distance covered by ball $= 96 \times \left(\frac{2}{3}\right)^2 \times 2$

In the fourth round distance covered by ball

$= 96 \times \left(\frac{2}{3}\right)^3 \times 2$ etc.

NOTE In each round ball covers equal distance while going up and coming down to the earth).

Hence the required distance

$$= 96 + 2\left[96 \times \frac{2}{3} + 96 \times \frac{4}{9} + 96 \times \frac{8}{27} + \ldots\right]$$

$$= 96 + 96 \times 2\left[\frac{2}{3} + \frac{4}{9} + \frac{8}{27} + \ldots\right]$$

$$= 96 + 192\left(\frac{\frac{2}{3}}{1 - \frac{2}{3}}\right)$$

$$= 96 + 192\left(\frac{\frac{2}{3}}{\frac{1}{3}}\right)$$

$= 96 + 192 \times 2 = 480$ ft.

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 18.3

1. Let A, G, H be the Arithmetic mean, Geometric mean and Harmonic mean of a and b respectively.

Then, we have

$$A = \frac{a+b}{2}, \quad G = \sqrt{ab}, \quad H = \frac{2ab}{a+b}$$

$$\text{A.H.} = \frac{a+b}{2} \times \frac{2ab}{a+b} = ab = G^2$$

$\therefore$

$$\text{Again } A - G = \frac{a+b}{2} - \sqrt{ab}$$

$$= \frac{a+b-2\sqrt{ab}}{2}$$

$$= (\sqrt{a})^2 + (\sqrt{b})^2 - 2\sqrt{ab}$$

$$= \frac{(\sqrt{a}-\sqrt{b})^2}{2} \geq 0$$

$$A \geq G$$

$\therefore$ Again since $\text{A.H.} = G^2 = G \times G$

$$H \leq G \qquad (\because A \geq G)$$

$\therefore$ i.e.

$$G \geq H$$

$\therefore$

$$A \geq G \geq H$$

Alternatively : Let $a = 6$ and $b = 24$

$$\therefore \quad \text{A.M.} = \frac{6+24}{2} = 15$$

and

$$\text{G.M.} = \sqrt{6 \times 24} = 12$$

and

$$\text{H.M.} = \frac{2 \times 6 \times 24}{6+24} = 9.6$$

$\therefore$

$$\text{A.M.} > \text{G.M.} > \text{H.M.}$$

Hence (c) is the correct option

NOTE The equality depends upon values as

$$a = 2 \text{ and } b = 2$$

then A.M. = 2 and G.M. = 2 and H.M. = 2

then A.M. = G.M. = H.M.

2. Let a, b, c, d, e are taken such that a, b, c are in A.P. and b, c, d are in G.P. and c, d, e are in H.P. then

$$a, b, c, d, e$$

$$2, 4, 6, 9, 18$$

$\therefore$

$$a \cdot e = c^2$$

Hence choice (b) is correct

3.

$$\frac{a+b}{2} = 10 \Rightarrow a + b = 20$$

$$\sqrt{a \cdot b} = 8 \Rightarrow ab = 64$$

$\therefore$

$$a, b = 16, 4 \text{ or } 4, 16$$

$\therefore$

$$\text{H.M.} = \frac{2 \times 4 \times 16}{(4+16)} = 6.4$$

NOTE $\text{G.M.} = \sqrt{\text{A.M.} \times \text{H.M.}}$

HINT Choices (a) and (b) are clearly wrong since H.M. ≤ G.M. ≤ A.M. Now you are left with choices (c) and (d) only.

LEVEL 1

1.

$$S_n = \frac{a(1-r^n)}{1-r}; \qquad r < 1$$

$$S_n = \frac{4095}{1024} = \frac{3(1-r^n)}{1-\frac{1}{4}}$$

$$\Rightarrow \quad \frac{4095}{1024} = 4(1-r^n)$$

$$\Rightarrow \quad \frac{4095}{4096} = 1 - r^n$$

$$\Rightarrow \quad r^n = \frac{1}{4096}$$

$$\Rightarrow \quad r^n = \left(\frac{1}{4}\right)^6$$

$$\Rightarrow \quad \left(\frac{1}{4}\right)^n = \left(\frac{1}{4}\right)^6 \qquad \left(\because r = \frac{1}{4}\right)$$

$$\Rightarrow \quad n = 6$$

2. Since $a > l$, therefore $r < 1$

Now, since $S_n = \frac{a-lr}{1-r}$ if $r < 1$

$\therefore$

$$\frac{5187}{625} = \frac{5 - \frac{32}{625}r}{1-r}$$

$$(1-r)\frac{5187}{625} = 5 - \frac{32r}{625} \Rightarrow r = \frac{2}{5}$$

3.

$$r = \frac{2\sqrt{2}}{2\sqrt{3}} = \frac{\frac{4}{\sqrt{3}}}{2\sqrt{2}} = \frac{\sqrt{2}}{\sqrt{3}} = \sqrt{\frac{2}{3}}$$

$\therefore$

$$S_\infty = \frac{a}{1-r}; \quad |r| < 1$$

$$= \frac{2\sqrt{3}}{1-\sqrt{\frac{2}{3}}} = \frac{2\sqrt{3} \times \sqrt{3}}{\sqrt{3}-\sqrt{2}}$$

$$= \frac{6}{\sqrt{3}-\sqrt{2}}$$

$$= 6(\sqrt{3}+\sqrt{2})$$

4. (Sum of odd terms − sum of even terms) = 72 − 63

$$\Rightarrow \frac{\text{number of terms}}{2} \times \text{common difference} = 9$$

$$\Rightarrow \quad nd = 18 \qquad \ldots(1)$$

($n \to$ number of terms, $d \to$ common difference)

Again

$$l - a = 16.5$$

$$\Rightarrow \quad (n-1)d = 16.5 \qquad \ldots(2)$$

$\therefore$ from (1) and (2), we get

$$d = 1.5$$

$\therefore$

$$n = 12$$

5. Go through option

{First Pocket: 4, 7, 10} {Second Pocket: 5, 7, 9}

Scanned by CamScanner

yourshahbood.wordpress.com

6. $a \cdot b \cdot c = a \cdot ar \cdot ar^2 = 216$

$\Rightarrow \quad b = ar = 6 \quad \ldots(1)$

and $ab + bc + ac = a \cdot ar + ar \cdot ar^2 + a \cdot ar^2 = 126$,

$\Rightarrow \quad a^2r + a^2r^3 + a^2r^2 = 126$

$\Rightarrow \quad a^2r + a^2r^3 = 90 \quad (\because ar = 6)$

$\Rightarrow \quad 6a + 36r = 90$

$\therefore \quad a + 6r = 15 \quad \ldots(2)$

from equation (1) and (2), we get

$$\frac{6}{r} + 6r = 15$$

$\Rightarrow \quad 6r^2 - 15r + 6 = 0$

$\Rightarrow \quad r = 2 \quad \text{or} \quad \frac{1}{2}$

$\therefore$ $a, ar, ar^2 = 3, 6, 12$ or $12, 6, 3$

$\therefore \quad a + b + c = 21$

Alternatively: Go through options

7. Let a, b, c, d be in A.P. then

$$\frac{ad}{bc} = \frac{9}{10}$$

Also $\quad a + b + c + d = 36$

$\Rightarrow \quad (a + d) = (b + c) = 18$

Now, go through options.

8. Let a, b, c, d be four integers in A.P.

then $\quad a + d = b + c = 12$

Since $a \cdot b \cdot c \cdot d = 945$, it means one of the a, b, c and d has its unit digit 5.

$\therefore$ Therefore the obvious possibility is $b = 5$

So, if $b = 5$, then $c = 7$

$\therefore \quad a = 3 \quad$ and $\quad d = 9$

$\therefore \quad a \cdot b \cdot c \cdot d = 3 \times 5 \times 7 \times 9 = 945$

Hence the values of a, b, c and d are correct.

Therefore $\quad a \times d = 3 \times 9 = 27$

Alternatively : Option a is not suitable as

$30 = 1 \times 30 \quad \times$

$30 = 2 \times 15 \quad \times$

$30 = 3 \times 10 \quad \times$

$30 = 5 \times 6 \quad \times$

Since difference between a and d must be divisible by 3.

Option (c) is not suitable as

$35 = 1 \times 35 \quad \times$

$35 = 5 \times 7 \quad \times$

Since the difference between a and d is not divisible by 3.

Option (d) is also wrong as

$39 = 1 \times 39 \quad \times$

$= 3 \times 13 \quad \times$

Since the difference between a and d is not divisible by 3.

Choice (b) is correct as

$27 = 1 \times 27 \quad \times$

$27 = 3 \times 9 \quad \checkmark$

If $\quad a = 3 \quad$ and $\quad d = 9$

then $\quad b = 5 \quad$ and $\quad c = 7$

$\therefore \quad a \cdot b \cdot c \cdot d = 945$

NOTE Choices (a) and (d) are wrong since 30 and 39 are not the factors of 945.

Alternatively: Find the factors of 945 and then find the required values of b and c under the condition $a + b + c + d = 24$.

9. $T_{11} + T_{12} + T_{13} = 114$

$\Rightarrow \quad T_{12} = \frac{114}{3} = 38$

$\Rightarrow \quad a + 11d = 38 \quad \ldots(1)$

and $\quad T_{21} + T_{22} + T_{23} = 204$

$\Rightarrow \quad T_{22} = 68$

$\Rightarrow \quad a + 21d = 68 \quad \ldots(2)$

from equations (1) and (2)

$10d = 30 \Rightarrow d = 3$

$a = 5$

$\therefore$

$\therefore \quad T_1 + T_2 + T_3 = 5 + 8 + 11 = 24$

Alternatively: $(T_1 + T_2 + T_3) + (T_{21} + T_{22} + T_{23})$

$= 2T_{11} + T_{12} + T_{13})$

$\Rightarrow \quad (T_1 + T_2 + T_3) + 204 = 2 \times 114$

$\Rightarrow \quad T_1 + T_2 + T_3 = 24$

10. $a + ar + ar^2 + ar^3 + \ldots \infty = 4$

$\Rightarrow \quad \frac{a}{1 - r} = 4$

or $\quad \frac{a^3}{(1 - r)^3} = 64 \quad \ldots(1)$

and $\quad a^3 + (ar)^3 + (ar^2)^3 + (ar^3)^3 + \ldots \infty = 192$

$= \frac{a^3}{1 - r^3} = 192 \quad \ldots(2)$

from equation (1) and (2)

$64(1 - r)^3 = (1 - r^3)192$

$\Rightarrow \quad 2r^3 + 3r^2 - 3r - 2 = 0$

$r = -\frac{1}{2}, 1, -2$

But $\quad |r| < 1$

$\therefore r = -\frac{1}{2}$ is the only admissible value

$\therefore \quad \frac{a}{1 - r} = 4$

$\Rightarrow \quad \frac{a}{1 - \left(-\frac{1}{2}\right)} = 4 \Rightarrow \quad a = 6$

11. $\frac{18500 - 12000}{500} = 13$ years

He has to work minimim 13 years to reach the highest scale of 18500.

12. 1, 4, 7, 10, 13, 16, 19, 22, 25, 28, 31, 34, 37, ..., 187

3, 7, 11, 15, 19, 23, 27, 31, 35, 39, ..., 187

The Common terms are 7, 19, 31, 43, ... 187

Therefore number of such terms $= \left(\frac{187 - 7}{12}\right) + 1 = 16$

13. $3^{1/3} \cdot 9^{1/18} \cdot 27^{1/81} \ldots = 3^{1/3} \cdot 3^{1/9} \cdot 3^{1/27} \ldots$

$= 3^{1/3 + 1/9 + 1/27 + \ldots}$

$= 3^{\left(\frac{1/3}{1 - 1/3}\right)} = 3^{1/2} = \sqrt{3}$

Scanned by CamScanner

yoursmahboob.wordpress.com

14. $1+4+9+16+\ldots+n^2$
$=1^2+2^2+3^2+4^2+\ldots+n^2=\dfrac{n(n+1)(2n+1)}{6}$

15. Put $n=2$ and 3 and then check for the correct choice
Sum of 2 terms = 11
Sum of 3 terms = 46
and
at $n=2$, $\dfrac{1}{6}\times 2(3)(11)=11$
and at $n=3$, $\dfrac{1}{6}\times 3\times 4\times 23=46$
Hence choice (c) is correct.

16. Let x, y, z be 1, 2, 4 respectively
$$a^1=b^2=c^4$$
$$\therefore \quad 16^1=4^2=2^4$$
$$\Rightarrow \quad a=16,\quad b=4 \quad \text{and} \quad c=2$$
$$\Rightarrow \quad \log_4 16=\log_2 4$$
$$\therefore \quad 2=2$$
$$\Rightarrow$$
Hence choice (a) is correct.

17. Since 913952088 is divisible by 7
Alternatively : $a=119$
$a+d=119+7=126$
$a+2d=119+14=133$
∴ The numbers which are divisible by 7 are
119, 126, 133, ..., 113113 ...
∴ Number of terms $=\left(\dfrac{113113-119}{7}\right)+1=16143$
$$\therefore \quad S_{16143}=\left(\frac{119+113113}{2}\right)\times 16143$$
$$=913952088$$

HINT The unit digit will be 8 as $\left(\dfrac{9+3}{2}\right)\times 3$
$$\Rightarrow \quad 6\times 3\Rightarrow 8$$
Hence only choice (b) is appropriate.

18. Going through options
$$S_{21}-S_{20}=T_{21}$$
$$\Rightarrow \quad [3(21)^2+5]-[3(20)^2+5]=3\times 441-3\times 400$$
$$=3(41)=123$$
Thus choice (c) is correct.

19. Let us consider choice (a)
then
$$b-a=3-4=-1$$
$$c-b=2-3=-1$$
$$a=4$$
Which are not in G.P., hence wrong.
Now, let us consider choice (c)
$$b-a=1$$
$$c-b=1$$
$$a=1$$
Since $b-a, c-b, a$ (*i.e.* 1, 1, 1) are in G.P. hence correct

20. $n=1$, $S_n=\dfrac{1}{2}$
$n=2$, $S_n=\dfrac{5}{4}=\left(\dfrac{1}{2}+\dfrac{3}{4}\right)$
$n=3$, $S_n=\dfrac{17}{8}=\left(\dfrac{1}{2}+\dfrac{3}{4}+\dfrac{7}{8}\right)$
Choice (a) is wrong
Since at $n=2$, $S_2=3\neq\dfrac{5}{4}$
Choice (b) is also wrong
Since at $n=2$, $S_2=\dfrac{3}{4}\neq\dfrac{5}{4}$
Choice (c) is also wrong
Since at $n=2$, $S_2=3\neq\dfrac{5}{4}$
Choice (d) is correct
Since at $n=1$, $S_1=\dfrac{1}{2}$
at $n=2$, $S_2=\dfrac{5}{4}$
at $n=3$, $S_3=\dfrac{17}{18}$

21. The required numbers are 1001, 1005, 1009, ..., 9997 and total number of terms in the above A.P. is 2250.
$$\therefore \quad S_{2250}=\frac{(1001+9997)}{2}\times 2250$$
$$=\frac{10998}{2}\times 2250$$
$$=5499\times 2250=12372750$$

HINT Choice (a) is the only suitable option since last two digits in the resultant value must be 50.

22. Let 3, 5, 7, 9, 11, 13, ... are in A.P.
where 5, 7, 9 and 11 are 4 arithmetic means berween 3 and 13
Hence choice (b) is correct
Since $\dfrac{4}{2}(3+13)=5+7+9+11$
$$32=32$$

23. Let 1, 2, 4, 8, 16 are in G.P.
then 2, 4, 8 are 3 geometric means between 1 and 16
Hence choice (c) is correct
Since $(1\times 16)^{3/2}=2\times 4\times 8$
$$64=64$$

24. $a_1+a_5+a_{10}+a_{15}+a_{20}+a_{24}=225$
$\Rightarrow a_1+(a_1+4d)+(a_1+9d)+(a_1+14d)$
$+(a_1+19d)+(a_1+23d)=225$
$$\Rightarrow \quad 6a_1+69d=225 \qquad \ldots(1)$$
Now, $a_1+a_2+a_3+a_4+\ldots+a_{23}+a_{24}=24a_1+276d$
$=4(6a_1+69d)$
$=4\times 225=900$

25. $1^2-2^2+3^2-4^2+5^2-6^2+7^2-8^2+\ldots$
$=(1-2)(1+2)+(3-4)(3+4)+(5-6)(5+6)$
$+(7+8)(7-8)+\ldots$
$=-(1+2)-(3+4)-(5+6)\ldots$
$=-[(1+2)+(3+4)+(5+6)+\ldots]$
$=-[1+2+3+4+5+6+\ldots]=-\left[\dfrac{n(n+1)}{2}\right]$

Alternatively : Go through options.

Scanned by CamScanner

yoursmahboob.wordpress.com

26. If $n = 1$, then $6 + 8 = 14$
If $n = 2$, then $66 + 88 = 154$
If $n = 3$, then $666 + 888 = 1554$
Now, go through options.
If you put $n = 1, 2, 3$ etc. in choice (c) you will find satisfactory results.

27. If $n = 1$, then sum of 1st group = 1
If $n = 2$, then sum of 2nd group = 35
If $n = 3$, then sum of 3rd group = 405
Now, going through options, we get choice (b) is correct
since at $n = 1$, $Sg_1 = 1$
at $n = 2$, $Sg_2 = 35$
at $n = 3$, $Sg_3 = 405$

28. Let the numbers be $a - d$, a, $a + d$
then $(a - d)^2$, a^2, $(a + d)^2$ are in G.P.
$$\therefore \quad a^4 = (a - d)^2(a + d)^2$$
$$\Rightarrow \quad d^4 - 2a^2d^2 = 0$$
$$\Rightarrow \quad d = 0, \pm\sqrt{2}a$$
Hence d has three values.

29. Since we know that when $a \cdot b \cdot c = k$ (any constant value) then the minimum value of $a + b + c$ is obtained
when $a = b = c$
$$\therefore \quad b^3 = 4 = 2^2$$
$$\Rightarrow \quad b = 2^{2/3}$$
Alternatively : Since a, b, c are in A.P.
Therefore $a = b - d$ and $c = b + d$
where d is the common difference.
Now, $abc = 4 \Rightarrow (b - d) \cdot b \cdot (b + d) = 4$
$$\Rightarrow \quad b(b^2 - d^2) = 4$$
But $b \cdot (b^2 - d^2) < b \cdot b^2 \quad (\because\ b^2 - d^2 < b^2)$
$$\therefore \quad b(b^2 - d^2) < b^3$$
$$4 < b^3$$
$$\Rightarrow \quad 2^2 < b^3$$
$$\Rightarrow \quad 2^{2/3} < b$$
Hence the minimum value of b is $2^{2/3}$.

30. Let the three numbers be $\frac{a}{r}$, a, ar. As the numbers form an increasing G.P.
Therefore $r > 1$
Also $\frac{a}{r}$, $2a$, ar are in A.P.
$$\therefore \quad 2(2a) = \frac{a}{r} + ar$$
$$\Rightarrow \quad r^2 - 4r + 1 = 0$$
$$\Rightarrow \quad r = 2 \pm \sqrt{3}$$
$$\Rightarrow \quad r = 2 + \sqrt{3} \qquad (\because\ 2 - \sqrt{3} < 1)$$

HINT If you go through options then options (a) and (d) are inadmissible.
Since $2 - \sqrt{3} < 1$
and $\sqrt{3} - 2 < 1$
Now you have only two probable choices consider three terms in G.P. with $r = 2 + \sqrt{3}$ or $r = 3 + \sqrt{2}$ and then satisfy the condition.

31. Best approach is to go through options. Choice (c) is correct.
Let $r = 4$, then a, b, c can be 1, 4, 16
$$\therefore \quad 16 > 4 \times 4 - 3 \times 1$$
$$\Rightarrow \quad 16 > 13$$
Let $r = -5$ then a, b, c can be 1, -5, 25
$$\therefore \quad 25 > -5 \times 4 - 1 \times 3$$
$$\Rightarrow \quad 25 > -23$$
Let $r = 2$ then a, b, c can be 1, 2, 4
$$\therefore \quad 4 > 4 \times 2 - 3 \times 1$$
$$\Rightarrow \quad 4 > 5, \qquad \text{which is wrong.}$$
Hence choice (a) is wrong and choice (c) is correct also the range of choice (b) is the subsect of the range of choice (c).
Alternatively : Let a, b, c be the first three consecutive terms of G.P. with common ratio r, then
$$b = ar \quad \text{and} \quad c = ar^2$$
Now, $c > 4b - 3a$
$$\Rightarrow \quad ar^2 > 4ar - 3a$$
$$\Rightarrow \quad r^2 > 4r - 3$$
$$\Rightarrow \quad r^2 - 4r + 3 > 0$$
$$\Rightarrow \quad (r - 1)(r - 3) > 0$$
$$\Rightarrow \quad r < 1 \quad \text{or} \quad r > 3$$

32. Let d be the common difference of the A.P.
Then $a_3 \cdot a_7 \cdot a_{11} = (22 - 4d) \cdot 22 \cdot (22 + 4d)$
$$= 88(121 - 4d^2)$$
Obviously, R.H.S. is greatest for $d = 0$

33. Given that A.M. = 2 G.M.
$$\Rightarrow \quad \frac{a + b}{2} = 2\sqrt{ab}$$
$$\Rightarrow \quad a + b = 4\sqrt{ab}$$
Now, let us consider choice (c)
$$\therefore \quad (2 + \sqrt{3}) + (2 - \sqrt{3}) = 4\sqrt{(2 + \sqrt{3})(2 - \sqrt{3})}$$
$$4 = 4 \cdot 1$$
$$4 = 4$$
Hence choice (c) is correct
Alternatively : $a + b = 4\sqrt{ab}$
$$\Rightarrow \quad (a + b)^2 = 16ab$$
$$\Rightarrow \quad a^2 + b^2 + 2ab = 16ab$$
$$\Rightarrow \quad a^2 + b^2 = 14ab$$
$$\Rightarrow \quad \frac{a}{b} + \frac{b}{a} = 14$$
$$\Rightarrow \quad x + \frac{1}{x} = 14 \qquad \left(\because \frac{a}{b} = x\right)$$
$$\Rightarrow \quad x^2 - 14x + 1 = 0$$
$$\Rightarrow \quad x = \frac{14 \pm \sqrt{192}}{2}$$
$$\Rightarrow \quad x = 7 \pm 4\sqrt{3}$$
$$\Rightarrow \quad \frac{a}{b} = 7 + 4\sqrt{3} = (2)^2 + (\sqrt{3})^2 + 4\sqrt{3}$$
$$\frac{a}{b} = (2 + \sqrt{3})^2 = \frac{2 + \sqrt{3}}{2 - \sqrt{3}}$$
Now $x = 7 - 4\sqrt{3}$
$\Rightarrow x = \frac{2 - \sqrt{3}}{2 + \sqrt{3}} \neq \frac{a}{b}$, since a should be greater than b.
Hence, $x \neq 7 - 4\sqrt{3}$

Scanned by CamScanner

yoursmahboob.wordpress.com

34. The two sequences are

17, 21, 25, 29, 33, 37, 41, ..., 417

16, 21, 26, 31, 36, 41, ..., 466

The common terms are

21, 41, 61, 81, ... 381, 401

$\therefore$ number of terms (which are common) = 20

35. $S_n = \frac{1}{\sqrt{1}+\sqrt{3}} + \frac{1}{\sqrt{3}+\sqrt{5}} + \ldots \frac{1}{\sqrt{2n-1}+\sqrt{2n+1}}$

$= \frac{1}{2}[(\sqrt{3}-\sqrt{1}) + (\sqrt{5}-\sqrt{3}) + (\sqrt{7}-\sqrt{5}) + \ldots$

$+ \ldots (\sqrt{2n+1}-\sqrt{2n-1})]$

$= \frac{1}{2}(\sqrt{2n+1}-1)$

Alternatively : Substitute $n = 1, 2, 3$ etc. and check the correct answer.

36. Let a be the first term and d be the common difference of the given A.P. then

$$T_m = \frac{1}{n} \Rightarrow a + (m-1)d = \frac{1}{n} \quad \ldots(1)$$

$$T_n = \frac{1}{m} \Rightarrow a + (n-1)d = \frac{1}{m} \quad \ldots(2)$$

Solving (1) and (2), we get

$$d = \frac{1}{mn} \quad \text{and} \quad a = \frac{1}{mn}$$

$\therefore$ $T_{mn} = a + (mn-1)d$

$= \frac{1}{mn} + (mn-1)\frac{1}{mn} = 1$

Alternatively : Let $m = 2$ and $n = 4$, then

$$T_2 = \frac{1}{4} \quad \text{and} \quad T_4 = \frac{1}{2}$$

$\therefore$ $a + d = \frac{1}{4}$ ...(1)

and $a + 3d = \frac{1}{2}$ ...(2)

$\Rightarrow$ $2d = \frac{1}{4} \Rightarrow d = \frac{1}{8}$

$\therefore$ $a = \frac{1}{4} - \frac{1}{8} = \frac{1}{8}$ [from (1)]

$\therefore$ $T_{mn} = T_8 = a + 7d$

$= \frac{1}{8} + 7 \times \frac{1}{8} = 1$

Hence (c) is the correct choice.

37. Go through options

Let $n = 2$, then $S_n = 3 + 6 = 9$

$\therefore$ $S_n = 2(3) + 2^2 - 1 = 9$

at $n = 3$, $S_n = 19$

$\therefore$ $S_n = 3 \times 4 + 2^3 - 1 = 19$

Hence choice (b) is correct.

Alternatively : $3 + 6 + 10 + 16 + \ldots$

$= (2 + 4 + 6 + 8 + \ldots) + (1 + 2 + 4 + 8 + \ldots)$

$= n(n+1) + (2^n - 1)$

38. Total number of cells $= 2 + (2^2 + 2^3 + 2^4 + \ldots + 2^{12})$

$= 2^1 + 2^2 + 2^3 + \ldots + 2^{12}$

$= \frac{2(2^{12}-1)}{2-1} = 8190$

39.



Div. + Su. → Total

Ist day 30 + 20 → 50

2nd day 28 + 24 → 52

3rd day 26 + 28 → 54 and so on.

$\therefore$ $50 + 52 + 54 + 56 + 58 + 60 = 330$

Hence required number of days = 6

40. Best way is to go through options

Let $n = 2$, then $S_n = S_2 = 1 + (1 + 2) = 4$

from choice (b)

$$S_2 = \frac{2 \times 3 \times 4}{6} = 4$$

and for $n = 3$

$S_n = S_3 = 1 + (1 + 2) + (1 + 2 + 3) = 10$

$\therefore$ from choice (b)

$$S_3 = \frac{3 \times 4 \times 5}{6} = 10$$

Hence choice (b) is correct

Alternatively : $T_n = \frac{n(n+1)}{2}$

$\therefore$ $S_n = \Sigma\left[\frac{n(n+1)}{2}\right] = \Sigma\left[\frac{n^2+n}{2}\right]$

$= \frac{1}{2}[\Sigma n^2 + \Sigma n]$

$= \frac{1}{2}\left[\frac{n(n+1)(2n+1)}{6} + \frac{n(n+1)}{2}\right]$

$= \frac{n(n+1)}{4}\left[\frac{2n+1}{3} + 1\right]$

$= \frac{n(n+1)}{4}\left[\frac{2n+4}{3}\right] = \frac{n(n+1)(n+2)}{6}$

41. $a = 2$ (since 3, 2, 1 are in A. P.)

$b = 3$ ($\therefore$ 2, 3, 6 are in H. P.)

and $c = 6$

$\therefore$ $\left(\frac{1}{b}+\frac{1}{c}-\frac{1}{a}\right)\left(\frac{1}{c}+\frac{1}{a}-\frac{1}{b}\right) = \left(\frac{1}{3}+\frac{1}{6}-\frac{1}{2}\right)\left(\frac{1}{6}+\frac{1}{2}-\frac{1}{3}\right) = 0$

Check the option (a)

$\frac{3}{3^2} - \frac{2}{6} = 0$, which is satisfied

again check the option (c)

$\frac{2}{bc} - \frac{1}{b^2} = \frac{2}{18} - \frac{1}{9} = 0$, which is also true.

Hence (d) is the most appropriate answer.

42. Go through options

$S_1 = 1 \cdot 3 \cdot 5 = 15$

and $S_2 = 1 \cdot 3 \cdot 5 + 3 \cdot 5 \cdot 7 = 120$ etc.

Now, put $n = 1$ in choice (b)

$1(2 + 8 + 7 - 2) = 15$

again put $n = 2$ in choice (b)

$2(16 + 32 + 14 - 2) = 120$

Hence choice (b) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

NOTE For the certainty of the result you can check for $n = 3$ also.

Alternatively : $T_n = (2n-1)(2n+1)(2n+3)$

$= 8n^3 + 12n^2 - 2n - 3$

$\therefore \quad S_n = 8\Sigma n^3 + 12\Sigma n^2 - 2\Sigma n - 3n$

$= 8\left[\frac{n(n+1)}{2}\right]^2 + \frac{12(n)(n+1)(2n+1)}{6} - \frac{2(n)(n+1)}{2} - 3n$

$= n(2n^3 + 8n^2 + 7n - 2)$

43. $(1-2) + (3-4) + (5-6) + (7-8) + \ldots + (99-100)$

$= (-1) + (-1) + (-1) + (-1) + \ldots 50 \text{ times} = -50$

LEVEL (2)

1. Let us consider $d = 1$, then the A.P. is

$1, 2, 3, 4, 5, 6, 7, 8$

$\therefore \quad 1 + 2 + 3 + 4 = 10$

and $\quad 5 + 6 + 7 + 8 = 26$

Again $1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12$

$\therefore \quad 1 + 2 + 3 + 4 + 5 + 6 = 21$

and $\quad 7 + 8 + 9 + 10 + 11 + 12 = 57$

$\because \quad \frac{10}{26} \neq \frac{21}{57}$

hence $\quad d \neq 1$

Now, consider $d = 2$, then the A.P. is

$1, 3, 5, 7, 9, 11, 13, 15$

$\therefore \quad 1 + 3 + 5 + 7 = 16$

and $\quad 9 + 11 + 13 + 15 = 48$

Again $1, 3, 5, 7, 9, 11, 13, 15, 17, 19, 21, 23$

$\therefore \quad 1 + 3 + 5 + 7 + 9 + 11 = 36$

and $\quad 13 + 15 + 17 + 19 + 21 + 23 = 108$

$\because \quad \frac{16}{48} = \frac{36}{108} \Rightarrow \frac{1}{3} = \frac{1}{3}$

hence $d = 2$ is the correct answer.

Alternatively : Let S_n denote the sum to n terms of the A.P. then,

$\frac{S_n}{S_{2n} - S_n} = k$ for every $n \geq 1$

$\Rightarrow \quad \frac{S_1}{S_2 - S_1} = \frac{S_2}{S_4 - S_2}$

$\Rightarrow \quad S_1 S_4 = S_2^2$

$\Rightarrow \quad a \cdot [2(2a + 3d)] = (2a + d)^2$

$\Rightarrow \quad 2ad = d^2$

$\Rightarrow \quad d = 2 \quad (\because a = 1)$

2. Number of divisors of $187 = 4$

Number of divisors of $637 = 6$

Number of divisors of $1001 = 8$

Hence they are in A.P.

HINT To know more about how to find the number of divisors refer to chapter 1 "Fundamentals".

3. $S_1 = 1^2 = 1$

$S_2 = 1^2 + (1^2 + 3^2) = 11$

$S_3 = 1^2 + (1^2 + 3^2) + (1^2 + 3^2 + 5^2) = 46$

Now Put $n = 1, 2, 3$ in choice (b) you will get

$S_1 = \frac{1}{6} \times 1 \times 2 \times 3 = 1$

$S_2 = \frac{1}{6} \times 2(3)(11) = 11$

$S_3 = \frac{1}{6} \times 3(4)23 = 46$

Hence choice (b) is correct.

Alternatively : $t_r = 1^2 + 3^2 + 5^2 + \ldots + (2r-1)^2$

$\therefore \quad = \sum_{k=1}^{r} (2k-1)^2 = \sum_{k=1}^{r} (4k^2 - 4k + 1)$

$= 4\left\{\frac{1}{6} r(r+1)(2r+1)\right\} - \frac{4}{2} r(r+1) + r$

$= \frac{1}{3}(4r^3 - r)$

$\therefore \quad S_n = \frac{4}{3} \sum_{r=1}^{n} r^3 - \frac{1}{3} \sum_{r=1}^{n} r$

$= \frac{4}{3} \cdot \frac{1}{4} n^2 (n+1)^2 - \frac{1}{3} \cdot \frac{1}{2} n(n+1)$

$= \frac{1}{6} n(n+1)(2n^2 + 2n - 1)$

4. Since $|a| <$ and $|b| <$, therefore $|ab| = |a||b| < 1$

Also, $a(a+b) + a^2(a^2 + b^2) + a^3(a^3 + b^3) + \ldots$

$= (a^2 + a^4 + a^6 + \ldots \infty) + (ab + a^2b^2 + a^3b^3 + \ldots \infty)$

$= \frac{a^2}{1 - a^2} + \frac{ab}{1 - ab}$

5. Best way is to go through options by substituting the values of $n = 1, 2, 3, \ldots$

Alternatively : $\frac{3}{1^2 \cdot 2^2} + \frac{5}{2^2 \cdot 3^2} + \frac{7}{3^2 \cdot 4^2} + \ldots$

$= \left(1 - \frac{1}{2^2}\right) + \left(\frac{1}{2^2} - \frac{1}{3^2}\right) + \ldots + \left(\frac{1}{n^2} - \frac{1}{(n+1)^2}\right)$

$= 1 - \frac{1}{(n+1)^2} = \frac{n^2 + 2n}{(n+1)^2}$

6. Best way is to go through options by substituting the values.

Sum of the terms of first row $= 1$

Sum of the terms of second row $= 2 + 3 = 5$

Sum of the terms of third row $= 4 + 5 + 6 = 15$ etc.

7. We have

$\underbrace{1\,1\,1 \ldots 1}_{119 \text{ times}} = 10^{118} + 10^{117} + \ldots + 10^2 + 10^1 + 1$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{(10^{119}-1)}{10-1} = \left(\frac{10^{119}-1}{10^7-1}\right)\left(\frac{10^7-1}{10-1}\right)$$

$$= (10^{112} + 10^{105} + 10^{98} + \ldots 1)(10^6 + 10^5 + \ldots 10 + 1)$$

Thus $\underbrace{1\,1\,1\ldots1}_{119 \text{ terms}}$ is not a prime number.

8. Since we know that the sum of the interior angles of a polygon of n sides is $(n-2)\pi$

$$\therefore \quad \frac{n}{2}[2(120) + (n-1)5] = (n-2)180$$

$$\Rightarrow \quad n = 9, 16$$

But if $n = 16$, then the greatest angle will be 195° and other interior angles are 190°, 185°, 180°. But no interior angle of a polygon can be equal to 180°.
Hence $n = 9$.

9. If $n = 1$, then

$$1 + 10^4 = 10001 = 73 \times 137$$

$\therefore 10^4 + 1$ is a composite number.

10. $0.1\overline{23} = \frac{1}{10} + \frac{23}{10^3} + \frac{23}{10^5} + \frac{23}{10^7} + \ldots$

$$= \frac{1}{10} + \frac{\frac{23}{10^3}}{1 - \left(\frac{1}{10^2}\right)}$$

$$= \frac{1}{10} + \frac{23}{1000 - 10} = \frac{122}{990} = \frac{61}{495}$$

11. $11 - 2 = 9 = 3^2$

$1111 - 22 = 1089 = 33^2$

$111111 - 222 = 110889 = 333^2$

$11111111 - 2222 = 11108889 = 3333^2$ etc.

12. Perimeter of the outer most triangle is 72 cm and perimeter of the second outer most triangle is 36 cm.
Similarly perimeter of the third outermost triangle is 18 cm.
∴ Sum of perimeters of all such triangles



$$= 72 + 36 + 18 + 9 + 4.5 + \ldots \infty \qquad \left(\because S_\infty = \frac{a}{1-r}\right)$$

$$= \frac{72}{1 - \frac{1}{2}} = \frac{72}{\frac{1}{2}} = 144 \text{ cm}$$

13. Go through options.

14. $\log a + \log \frac{a^3}{b} + \log \frac{a^5}{b^2} + \log \frac{a^7}{b^3} + \ldots + \log \frac{a^{2n-1}}{b^{n-1}}$

$$= \log a \times \frac{a^3}{b} \times \frac{a^5}{b^2} \times \frac{a^7}{b^3} \times \ldots \times \frac{a^{2n-1}}{b^{n-1}}$$

$$= \log \frac{a^{(1+3+5+7+\ldots+2n-1)}}{b^{(1+2+3+4+\ldots+n-1)}}$$

$$= \log \frac{a^{n^2}}{b^{(n-1)n/2}}$$

$$= \log \left(\frac{a^{2n}}{b^{n-1}}\right)^{n/2}$$

15. $_{(0.2)}\log_{\sqrt{5}}\left(\frac{1}{4} + \frac{1}{8} + \frac{1}{16} + \ldots\right) = {}_{(0.2)}\log_{\sqrt{5}}\left(\frac{1}{2}\right)$

$$= {}_{(5^{-1})}\log_{\sqrt{5}}\left(\frac{1}{2}\right)$$

$$= {}_5\log_{\sqrt{5}} 2 \qquad (\because m \log n = \log (n)^m)$$

$$= {}_{(\sqrt{5})^2}\log_{\sqrt{5}}(2)$$

$$= {}_{(\sqrt{5})}\log_{\sqrt{5}}(4) \qquad (\because {}_a\log_a b = b)$$

$$= 4$$

16. Since a, b, c are in H.P.
Therefore we can assume $a = 2, b = 3, c = 6$

$$\therefore \quad \frac{b+a}{b-a} + \frac{b+c}{b-c} = \frac{5}{1} + \frac{9}{-3} = 2$$

17. Let $r = \frac{1}{2}$, then $(a, b, c) = (4, 2, 1)$

$\therefore$ $(a, 2b, 3c) = (4, 4, 3)$ which are not in A.P.

Again if $r = \frac{1}{3}$ then

$$(a, b, c) = (9, 3, 1)$$

$\therefore$ $(a, 2b, 3c) = (9, 6, 3)$ which are in A.P.
Hence choice (c) is correct.

18. Let $S = \frac{5}{13} + \frac{55}{(13)^2} + \frac{555}{(13)^3} + \frac{5555}{(13)^4} + \ldots \infty$

$$\therefore \quad \frac{S}{13} = \frac{5}{(13)^2} + \frac{55}{(13)^3} + \frac{555}{(13)^4} + \frac{5555}{(13)^5} + \ldots \infty$$

$$\therefore \quad \left(S - \frac{S}{13}\right) = \frac{5}{13} + \frac{50}{(13)^2} + \frac{500}{(13)^3} + \frac{5000}{(13)^4} + \ldots \infty$$

$$S\left(1 - \frac{1}{13}\right) = \frac{5}{13} + \frac{5}{13}\left(\frac{10}{13}\right) + \frac{5}{13}\left(\frac{10}{13}\right)^2 + \frac{5}{13}\left(\frac{10}{13}\right)^3 + \ldots \infty$$

$$\frac{12}{13}S = \frac{5/13}{3/13} \qquad \left(\because S_\infty = \frac{a}{1-r}\right)$$

$$\frac{12}{13}S = \frac{5}{3} \Rightarrow S = \frac{65}{36}$$

19. Let $S = \frac{1}{1\cdot4} + \frac{1}{4\cdot7} + \frac{1}{7\cdot10} + \ldots \infty$

$$\Rightarrow \quad S = \frac{1}{3}\left[\frac{3}{1\cdot4} + \frac{3}{4\cdot7} + \frac{3}{7\cdot10} + \ldots \infty\right]$$

$$\Rightarrow \quad S = \frac{1}{3}\left[\left(\frac{1}{1} - \frac{1}{4}\right) + \left(\frac{1}{4} - \frac{1}{7}\right) + \left(\frac{1}{7} - \frac{1}{10}\right) + \ldots \infty\right]$$

$$\Rightarrow \quad S = \frac{1}{3}[1] \quad \therefore \quad S = \frac{1}{3}$$

20. Let us add up one more number a_{n+1} to the given sequence such that $|a_{n+1}| = |a_n + 1|$.
Now, squaring all the numbers, we get

$$a_1^2 = 0$$
$$a_2^2 = a_1^2 + 2a_1 + 1$$
$$a_3^2 = a_2^2 + 2a_2 + 1$$
$$a_4^2 = a_3^2 + 2a_3 + 1$$
$$\ldots \ldots \ldots$$
$$\ldots \ldots \ldots$$
$$a_n^2 = a_{n-1}^2 + 2a_{n-1} + 1$$
$$a_{n+1}^2 = a_n^2 + 2a_n + 1$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore \quad a_1^2 + a_2^2 + a_3^2 + \ldots + a_{n+1}^2 = a_1^2 + a_2^2 + \ldots + a_n^2 + 2(a_1 + a_2 + \ldots + a_n) + n$

$\Rightarrow \quad 2(a_1 + a_2 + \ldots + a_n) = -n + a_{n+1}^2 \geq -n$

$\Rightarrow \quad \frac{a_1 + a_2 + \ldots + a_n}{n} \geq -\frac{1}{2}$

21. Let a, b, c, d are the first consecutive terms in G.P.

Let us consider choice (a)

$\therefore \quad \frac{b+c}{2} = 5 \Rightarrow b + c = 10$

Now if $(b, c) = (1, 9)$, then a and d can not be found so that $a + b + c + d = 30$.

Similarly $(b, c) = (2, 8), (3, 7), (4, 6), (5, 5)$ are also not suitable.

Again consider choice (b)

$\therefore \quad \frac{b+c}{2} = 6 \Rightarrow b + c = 12$

Now if $(b, c) = 4, 8$, then $a = 2$ and $d = 16$

$\therefore \quad a + b + c + d = 30$

Hence this can be the correct answer.

Further $a^2 + b^2 + c^2 + d^2 = 4 + 16 + 64 + 256 = 340$

Hence choice (b) is correct.

Alternatively : Let a, ar, ar^2, ar^3 be the 4 consecutive terms of G.P. then

$\therefore \quad a + ar + ar^2 + ar^3 = 30 \quad \ldots(1)$

and $\quad a^2 + a^2r^2 + a^2r^4 + a^2r^6 = 340 \quad \ldots(2)$

clearly $r \neq 1$

$[\because (a + ar + ar^2 + ar^3)^2 \neq 4(a^2 + a^2r^2 + a^2r^4 + a^2r^6)]$

$\therefore \quad \frac{(1 + r + r^2 + r^3)^2}{(1 + r^2 + r^4 + r^6)} = \frac{(30)^2}{340} = \frac{45}{17}$

$\Rightarrow \quad \frac{\left[\frac{(r^4 - 1)}{(r - 1)}\right]^2}{\left(\frac{r^8 - 1}{r^2 - 1}\right)} = \frac{45}{17} \quad (\because r \neq 1)$

$\Rightarrow \quad \frac{(r^4 - 1)^2}{(r - 1)^2} \cdot \frac{(r^2 - 1)}{(r^8 - 1)} = \frac{45}{17}$

$\Rightarrow \quad \frac{(r^4 - 1)(r^4 - 1)(r - 1)(r + 1)}{(r - 1)(r - 1)(r^4 - 1)(r^4 + 1)} = \frac{45}{17}$

$\Rightarrow \quad \frac{(r^4 - 1)}{(r - 1)} \cdot \frac{(r + 1)}{(r^4 + 1)} = \frac{45}{17}$

$\Rightarrow \quad (r^3 + r^2 + r - 1) \cdot \frac{(r + 1)}{(r^4 + 1)} = \frac{45}{17}$

$\Rightarrow \quad 17r^4 + 34r^3 + 34r^2 + 34r + 17 = 45r^4 + 45$

$\Rightarrow \quad 14r^4 - 17r^3 - 17r^2 - 17r + 14 = 0$

Dividing by r^2, we get

$14\left(r^2 + \frac{1}{r^2}\right) - 17\left(r + \frac{1}{r}\right) - (17) = 0$

$\Rightarrow \quad 14\left[\left(r + \frac{1}{r}\right)^2 - 2\right] - 17\left(r + \frac{1}{r}\right) - 17 = 0$

$\Rightarrow \quad 14y^2 - 17y - 45 = 0$

$\Rightarrow \quad y = \frac{17 \pm \sqrt{17^2 + 4 \times 14 \times 45}}{28}$

$\Rightarrow \quad y = \frac{17 \pm \sqrt{2809}}{28} = \frac{17 \pm 53}{28} = \frac{5}{2}, -\frac{9}{7}$

$\therefore \quad \left(r + \frac{1}{r}\right) = \frac{5}{2} \Rightarrow r = 2, \frac{1}{2}$

and $\left(r + \frac{1}{r}\right) = -\frac{9}{7}$ has no real roots.

$\therefore$ when $r = 2$, $a = 2$

and when $r = \frac{1}{2}$, $a = 16$

Thus the required progression is $2, 4, 8, 16, 32, 64, \ldots$ or $16, 8, 4, 2, 1, \frac{1}{2}, \ldots$

22. Side of the first square is 4 cm

Side of the second square is $2\sqrt{2}$ cm

and side of the third square is 2 cm

and so on.

i.e., each side of first, second, third square ...

$= 4, 2\sqrt{2}, 2, \sqrt{2}, 1, \frac{1}{\sqrt{2}}, \ldots$

$\therefore$ Area of each of first, second, third square ...

$= 16, 8, 4, 2, 1, \frac{1}{2}, \ldots$

$\therefore$ Sum of the area of first, second, third square ...

$= 16 + 8 + 4 + 2 + \ldots = \frac{16}{1 - \left(\frac{1}{2}\right)} = 32 \text{ cm}^2$

23. Best way consider some suitable values to check it physically.

Let A.P. be 2, 9.5, 17, 24.5, 32

and G.P. be 2, 4, 8, 16, 32

$\therefore \quad A_s = 2 + 9.5 + 17 + 24.5 + 32 = 85$

and $\quad G_s = 2 + 4 + 8 + 16 + 32 = 62$

Since $\quad A_s > G_s$

Hence (a) is the correct option.

NOTE For the fool proof testing you can consider some more values (*i.e.*, Progressions)

24. Consider any A.P. and G.P. as per the given conditions ., then

A.P. 2, 4, 6, 8, 10, 12, 14, ...

G.P. 2, 4, 8, 16, 32, 64, ...

Hence $a_i < g_i$ for $i > 2$ and $i \in N$

NOTE You can consider some more examples and then you will find that only choice (b) is correct

25. $\frac{1^1 + 2^1 + 3^1 + 4^1}{1 + 2 + 3 + 4} = 1$

$\frac{1^3 + 2^3 + 3^3 + 4^3}{1 + 2 + 3 + 4} = \frac{100}{10} = 10$ and so on.

26. Let the A.P. be 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, ...

where $\quad p = 1, \quad q = 2, \quad r = 4, \quad s = 8$

$\therefore \quad p - q = -1$ and $q - r = -2$ and $r - s = -4$

hence $(p - q), (q - r)$ and $(r - s)$ are in G.P. with common ratio 2 and first term -1.

27. $2^0 + 2^1 + 2^2 + 2^3 + 2^4 + 2^5 = 1 + 2 + 4 + 8 + 16 + 32 = 63$

Scanned by CamScanner

yoursmahboob.wordpress.com

28. $n = 5$
The weight of each stone (in kg) is
1, 3, 9, 27, 81
1 kg = 1 kg
2 kg = 3 – 1 = 2 kg
3 kg = 3 kg
4 kg = (3 + 1) = 4 kg
5 kg = 9 – (3 + 1) = 5 kg
6 kg = (9 – 3) = 6 kg
7 kg = (9 + 1) – 3 = 7 kg
8 kg = (9 – 1) = 8 kg
9 kg = 9 kg
10 kg = (9 + 1) = 10 kg and so on.

Remember he is allowed to put the stones on either side of the balance.

29. $T_1 = 3^1 - 2$
$T_2 = 3^2 - 2$
$T_3 = 3^3 - 2$
$T_4 = 3^4 - 2$

30. Try with the options.

31. $2^1 - 1$ souls become ghost in 1 second
$2^2 - 1$ souls become ghost in 2 second
$2^3 - 1$ souls become ghost in 3 second
$2^4 - 1$ souls become ghost in 4 second
$\therefore (2^{43200} - 1)$ souls become ghost in 43200 seconds

32. Assume some values of n and k and then verify the correct answer.
Alternatively : At a particular moment there are x souls left
Just 1 second before there are
$$2^1 x + 1 = 2^1 x + 2^1 - 1 \text{ souls}$$
Just 2 seconds before there are
$$2^2 x + 2 + 1 = 2^2 x + 2^2 - 1 \text{ souls}$$
Just 3 seconds before there are
$$2^3 x + 2^2 + 2 + 1 = 2^3 x + 2^3 - 1 \text{ souls}$$
Hence n seconds before there are
$$2^n x + 2^n - 1 \text{ souls left.}$$

33. Savings = Income – Expenditure
Savings on Ist day = 3 – 3 = 0
Savings on 2nd day = 6 – 5 = 1
Savings on 3rd day = 11 – 7 = 4
Savings on 4th day = 18 – 9 = 9
$\therefore$ Total savings = 1240 = 0 + 1 + 4 + 9 + 16 + 25 + ... + 225
This will take 16 days.

34. Check through options.
Let us consider choice (a)

	E	M	L	T	
Lucknow (G.P.)	1	1	1	1	} 4
Kanpur (A.P.)	1	2	3	4	} 10

It is wrong since $M = E$

Again	E	M	L	T	
Lucknow (G.P.)	1	2	4	8	} 15
Kanpur (A.P.)	1	3	5	7	} 16

It is wrong since $15 \neq \frac{3}{2} \times 16$, also $2 \neq 3$

Again	E	M	L	T	
Lucknow (G.P.)	1	3	9	27	} 40
Kanpur (A.P.)	1	4	7	10	} 22

It is also wrong since $40 \neq \frac{3}{2} \times 22$, also $3 \neq 4$

Again	E	M	L	T	
Lucknow (G.P.)	2	4	8	16	} 30
Kanpur (A.P.)	2	4	6	8	} 20

It is correct since number of monkeys and number of elephants in both the places are equal respectively. Also total number of animals in zoological park is 50% more than that of Local zoo in Kanpur.

36. Go through options
Let $n = 4$, then
$$S_n = -1 + 1^2 - 2 + 2^2 = 2$$
form option (a) $\frac{4 \times 17}{3} = \frac{68}{3} \neq 2$
from option (b) $16 + 4 = 20 \neq 2$
from option (c) $\frac{4 \times 15}{3} = 20 \neq 2$
Hence choice (d) is correct.

37. Let $S = 1 + \frac{2}{3} + \frac{4}{9} + \frac{6}{27} + \frac{8}{81} + \frac{10}{243} + \ldots \infty$

$\therefore \quad 3(S) = 3 + 2 + \frac{4}{3} + \frac{6}{9} + \frac{8}{27} + \frac{10}{81} + \ldots \infty$

$\therefore \quad 2(S) = 4 + \frac{2}{3} + \frac{2}{9} + \frac{2}{27} + \frac{2}{81} + \ldots \infty$

$\therefore \quad 2(S) = 4 + 2\left(\frac{1}{3} + \frac{1}{9} + \frac{1}{27} + \frac{1}{81} + \ldots \infty\right)$

$\Rightarrow \quad 2(S) = 4 + 2\left[\frac{\frac{1}{3}}{1 - \left(\frac{1}{3}\right)}\right]$

$\Rightarrow \quad 2(S) = 4 + 1$

$\Rightarrow \quad 2(S) = 5$

$\therefore \quad S = \frac{5}{2}$

38. $\log a + \log \frac{a^2}{b} + \log \frac{a^3}{b^2} + \log \frac{a^4}{b^3} + \ldots + \log \frac{a^n}{b^{n-1}}$

$$= \log\left(a \cdot \frac{a^2}{b} \cdot \frac{a^3}{b^2} \cdot \frac{a^4}{b^3} \cdots \frac{a^n}{b^{n-1}}\right)$$

$$= \log\left[\frac{a^{(1+2+3+4+\ldots+n)}}{b^{(1+2+3+4+\ldots+(n-1))}}\right]$$

$$= \log\left[\frac{a^{\frac{n(n+1)}{2}}}{b^{\frac{(n+1)n}{2}}}\right] = \log\left[\frac{a^{(n+1)}}{b^{(n-1)}}\right]^{n/2}$$

39. Go through options
Let 1, 2, 3, 4, 5, ... be an A.P. then
$$\frac{1}{\sqrt{a_1} + \sqrt{a_2}} + \frac{1}{\sqrt{a_2} + \sqrt{a_3}} + \frac{1}{\sqrt{a_3} + \sqrt{a_4}} + \frac{1}{\sqrt{a_4} + \sqrt{a_5}}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{1}{\sqrt{1}+\sqrt{2}} + \frac{1}{\sqrt{2}+\sqrt{3}} + \frac{1}{\sqrt{3}+\sqrt{4}} + \frac{1}{\sqrt{4}+\sqrt{5}}$$
$$= -(\sqrt{1}-\sqrt{2}) - (\sqrt{2}-\sqrt{3}) - (\sqrt{3}-\sqrt{4}) - (\sqrt{4}-\sqrt{5})$$
$$= \sqrt{5}-\sqrt{1}$$
$$= \sqrt{5}-\sqrt{1} \times \frac{\sqrt{5}+\sqrt{1}}{\sqrt{5}+\sqrt{1}} = \frac{5-1}{\sqrt{5}+\sqrt{1}}$$
$$= \frac{4}{\sqrt{1}+\sqrt{5}} = \frac{n-1}{\sqrt{a_1}+\sqrt{a_n}}$$

Alternatively : $\frac{1}{\sqrt{a_1}+\sqrt{a_2}} + \frac{1}{\sqrt{a_2}+\sqrt{a_3}} + \frac{1}{\sqrt{a_3}+\sqrt{a_4}} + \ldots + \frac{1}{\sqrt{a_{n-1}}+\sqrt{a_n}}$

$$= \frac{\sqrt{a_2}-\sqrt{a_1}}{(\sqrt{a_2}+\sqrt{a_1})(\sqrt{a_2}-\sqrt{a_1})} + \frac{\sqrt{a_3}-\sqrt{a_2}}{(\sqrt{a_3}+\sqrt{a_2})(\sqrt{a_3}-\sqrt{a_2})} + \ldots + \frac{\sqrt{a_n}-\sqrt{a_{n-1}}}{(\sqrt{a_n}+\sqrt{a_{n-1}})(\sqrt{a_n}-\sqrt{a_{n-1}})}$$
$$= \frac{\sqrt{a_2}-\sqrt{a_1}}{a_2-a_1} + \frac{\sqrt{a_3}-\sqrt{a_2}}{a_3-a_2} + \ldots + \frac{\sqrt{a_n}-\sqrt{a_{n-1}}}{a_n-a_{n-1}}$$
$$= \frac{\sqrt{a_2}-\sqrt{a_1}}{d} + \frac{\sqrt{a_3}-\sqrt{a_2}}{d} + \ldots + \frac{\sqrt{a_n}-\sqrt{a_{n-1}}}{d}$$
$$= \frac{1}{d}[(\sqrt{a_2}-\sqrt{a_1}) + (\sqrt{a_3}-\sqrt{a_2}) + \ldots + (\sqrt{a_n}-\sqrt{a_{n-1}})]$$
$$= \frac{1}{d}[\sqrt{a_n}-\sqrt{a_1}] = \frac{a_n-a_1}{d(\sqrt{a_n}+\sqrt{a_1})}$$
$$= \frac{n-1}{\sqrt{a_n}+\sqrt{a_1}} = \frac{n-1}{\sqrt{a_1}+\sqrt{a_n}}$$

40. Go through options.
Remember If $\log a$, $\log b$, $\log c$ are in A.P., then a, b, c are in G.P.

$\therefore$ $2, (2^x - 3)$ and $\left(\frac{17}{2} + 2^{x-1}\right)$ must be in G.P.

Let $x = 3$, then the value of $2^x - 3 = 5$

and $\frac{17}{2} + 2^{x-1} = \frac{25}{2}$

Since $2, 5, \frac{25}{2}$ are in G.P.

Hence, the given terms of the sequence are in A.P.

41. Combining all of the three relations we get

$$x = y^{-1} = z^3$$

$\therefore 1, \log_y x, \log_z y, -15 \log_x z$

$\Rightarrow 1, -1, -3, -5$, which are in A.P.

Hence, choice (d) is most appropriate.

42. Let $x = 1, y = 2, z = 4$

$\therefore$ $a = 16, \quad b = 4, \quad c = 2 \qquad (\because a^x = b^y = c^z)$

$\therefore$ $\log_b a \cdot \log_b c = \log_4 16 \cdot \log_4 2$

$$= (2\log_4 4) \cdot \left(\frac{\log 2}{2\log 2}\right)$$
$$= (2 \cdot 1)\left(\frac{1}{2}\right) = 1$$

43. Go through options.
Let us consider choice (b)

$$x = 1 - \log_2 5 = \log_2 2 - \log_2 5 = \log_2\left(\frac{2}{5}\right)$$

$\therefore \log_2(5 \cdot 2^x + 1), \log_4(2^{1-x} + 1), 1$

$$= \log_2(5 \cdot 2^{\log_2 2/5} + 1), \log_4(2^{1-\log_2 2/5} + 1), 1$$
$$= \log_2\left(5 \times \frac{2}{5} + 1\right), \log_4\left(\frac{2}{2^{\log_2 2/5}} + 1\right), 1$$
$$= \log_2 3, \log_4\left(\frac{2}{2/5} + 1\right), 1$$
$$= \log_2 3, \log_4 6, 1 = \log_4 9, \log_4 6, \log_4 4$$

$\because 9, 6, 4$ are in G.P.

Hence the assumed choice (b) is correct.

HINT If a, b, c are in G.P. then $\log a$, $\log b$, $\log c$ are in A.P.

44. Very similar to the previous problem.

45. Let $x = e$, $y = e^2$ and $z = e^3$, then

$$\frac{1}{1+\ln e}, \frac{1}{1+\ln e^2} + \frac{1}{1+\ln e^3} = \frac{1}{1+1}, \frac{1}{1+2}, \frac{1}{1+3}$$
$$= \frac{1}{2}, \frac{1}{3}, \frac{1}{4}$$ which are in H.P.

46. Let d be the common difference of the A.P.

then $a_{10} = 3 \Rightarrow a_1 + 9d = 3$

$\Rightarrow$ $2 + 9d = 3 \Rightarrow d = \frac{1}{9}$

$\therefore$ $a_4 = a_1 + 3d = 2 + \frac{1}{3} = \frac{7}{3}$

Let D be the common difference of $\frac{1}{h_1}, \frac{1}{h_2}, \ldots, \frac{1}{h_{10}}$

Then, $h_{10} = 3 \Rightarrow \frac{1}{h_{10}} = \frac{1}{3}$

$\Rightarrow$ $\frac{1}{h_1} + 9D = \frac{1}{3} \Rightarrow \frac{1}{2} + 9D = \frac{1}{3}$

$\Rightarrow$ $D = -\frac{1}{54}$

$\therefore$ $\frac{1}{h_7} = \frac{1}{h_1} + 6D = \frac{1}{2} - \frac{1}{9} = \frac{7}{18}$

$\Rightarrow$ $h_7 = \frac{18}{7}$

$\therefore$ $a_4 h_7 = \frac{7}{3} \times \frac{18}{7} = 6$

47. $S_4 < 1 \text{ cm}^2$

Therefore the side of square also be less than 1 cm.

$\therefore$ $l_1 = 10, \quad l_2 = \frac{10}{\sqrt{2}},$

$l_3 = \frac{10}{2}, \quad l_4 = \frac{10}{2\sqrt{2}}$

$l_5 = \frac{10}{4}, \quad l_6 = \frac{10}{4\sqrt{2}},$

$l_7 = \frac{10}{8}, \quad l_8 = \frac{10}{8\sqrt{2}}$



Hence $l_8 = \frac{10}{8\sqrt{2}} < 1 \text{ cm}$

$\therefore$ area of $S_8 < 1 \text{ cm}^2$

where $l_1, l_2, \ldots, l_{10}$ are the lengths of sides of different squares, from outwards to inwards.

Scanned by CamScanner

yoursmahboob.wordpress.com

Final Round

1. Total number of bacterias after 10 seconds
$= 3^{10} - 3^5 = 3^5(3^5 - 1)$

since just after 10 seconds all the bacterias (*i.e.* 3^5) are dead after living for 5-5 seconds.

2. $S_{20} = 2^{66} - 2^{65} - 2^{64} - 2^{63} - 2^{62} - \ldots - 2^{47}$
$= 2^{65}(2-1) - 2^{64} - 2^{63} - \ldots - 2^{47}$
$= 2^{65} - 2^{64} - 2^{63} - \ldots - 2^{47}$
$= 2^{64}(2-1) - 2^{63} - \ldots - 2^{47}$
$= 2^{64} - 2^{63} - 2^{62} - \ldots - 2^{47}$
$= 2^{63}(2-1) - 2^{62} - \ldots - 2^{47}$
$= 2^{63} - 2^{62} - 2^{61} - \ldots - 2^{47}$
... ...
... ...
$= 2^{47}$

3. Since $S_{67} = 2^0$ $(\because S_n = 2^{67-n})$
$S_{66} = 2^1$
$S_{65} = 2^2$
$S_{64} = 2^3$
$S_{63} = 2^4$
... ...
... ...
$S_{34} = 2^{33}$ etc.

Now, $U_m = S_m + S_{m+1} + S_{m+2} + \ldots + S_{m+(m-1)}$
$\therefore \quad U_{34} = S_{34} + S_{35} + S_{36} + \ldots + S_{67}$
$\Rightarrow \quad U_{34} = 2^{33} + 2^{32} + 2^{31} + \ldots + 2^0$
$\Rightarrow \quad U_{34} = 1 + 2^1 + 2^2 + 2^3 + \ldots + 2^{32} + 2^{33}$
$\Rightarrow \quad U_{34} = (2^{33} - 1)$

4. Consider an A. P, then go through options
Let 1, 2, 3, 4, 5, 6 be an A.P. with 6 terms
i.e. $3n = 6, \quad 2n = 4 \quad \text{and} \quad n = 2$
$\therefore \quad S_3 - S_2 - S_1$
$= (1 + 2 + \ldots 6) - (1 + 2 + 3 + 4) - (1 + 2)$
$= 21 - 10 - 3 = 8$

Choice (a) gives
$S_3 - S_2 - S_1 = 3a - 2n - d = 3 - 4 - 1$
$= -2$, hence wrong

Check the choice (d)
$S_3 - S_2 - S_1 = 2n^2 d = 8$
Hence it is correct.

Alternatively : Since $S_3 - S_2 - S_1$ is independent of a (i.e., first term).
Hence only choice (d) is correct.

5.

$T_n = n$	$n+3$	$n+5$	$n+7$	$n+9$
$T_1 = 1$	4	6	8	10
$T_2 = 2$	5	7	9	11
$T_3 = 3$	6	8	10	12
$T_4 = 4$	7	9	11	13
$T_5 = 5$	8	10	12	14
$T_6 = 6$	9	11	13	15
$T_7 = 7$	10	12	14	16
$T_8 = 8$	11	13	15	17
$T_n = 9$	12	14	16	18

In general when $n = 4, 9, 13, 17, \ldots, 99$ does not contain 5 or its multiple.
i.e. $n = 5k - 1$ where $k = 1, 2, 3, \ldots, 20$
Hence out of 99 sets 20 sets does not contain the 5 or its multiples.
Thus the required number of sets $= 99 - 20 = 79$

6. Let $S = \{\sqrt{1}\} + \{\sqrt{2}\} + \{\sqrt{3}\} + \{\sqrt{4}\} + \ldots + \{\sqrt{99}\} + \{\sqrt{100}\}$
$\Rightarrow \quad S = 1 + 2 + 2 + 2 + 3 + 3 + 3 + 3 + 3 + \ldots + 10$
$\Rightarrow \quad S = 1 + 3(2) + 5(3) + 7(4) + 9(5) + \ldots + 19(10)$
Since $T_n = (2n-1)n = 2n^2 - n$
$\therefore \quad S_n = \Sigma(2n^2 - n) = 2\Sigma n^2 - \Sigma n$
$= \frac{2n(n+1)(2n+1)}{6} - \frac{n(n+1)}{2}$
$= \frac{n(n+1)}{2}\left[\frac{2}{3}(2n+1) - 1\right]$
$= \frac{n(n+1)}{2}\left[\frac{4n+2-3}{3}\right]$
$= \frac{n(n+1)(4n-1)}{6}$
$\therefore \quad S_{10} = \frac{10 \times 11 \times 39}{6} = 715$

7. Let $S = [\sqrt{1}] + [\sqrt{2}] + [\sqrt{3}] + \ldots + [\sqrt{323}]$
$\Rightarrow \quad S = 1 + 1 + 1 + 2 + 2 + 2 + 2 + 2 + \ldots + 17 + 17$
$\Rightarrow \quad S = 1(3) + 2(5) + 3(7) + 4(9) + \ldots + 17(35)$
$\because \quad T_n = n(2n+1)$
$\therefore \quad S_n = \Sigma n(2n+1) = 2\Sigma n^2 + \Sigma n$
$= \frac{2 \cdot n(n+1)(2n+1)}{6} + \frac{n(n+1)}{2}$
$= \frac{n(n+1)}{2}\left[\frac{2}{3}(2n+1) + 1\right]$
$= \frac{n(n+1)}{2}\left[\frac{4n+5}{3}\right]$
$= \frac{n(n+1)(4n+5)}{6}$
$\therefore \quad S = \frac{17 \times 18 \times 73}{6} = 3723$

8. This can be done only by giving the number of coins as $2^0, 2^1, 2^2, 2^3, 2^4, \ldots$ etc.
So, the amounts are 1, 2, 4, 8, 16, 32, 37.
Hence (c) is the correct answer.

9. $(1 + 37) = (32 + 4 + 2)$
Hence, 3 people are required.

10. $(1 + 2 + 37) = (32 + 8)$
Hence 2 people are required.

12. 1, 2, 4, 8, 16, 32, 64, 73

Scanned by CamScanner

yoursmahboob.wordpress.com

13. Since there are only 5 people left with their amount viz. 1, 4, 16, 64, 73, (excluding 2, 8, 32).
So total number of combinations are $2^5 - 1 = 31$
Hence option (c) is correct.

14.
$$1 + 2 + 4 + 8 + 16 + 32 = 63$$
$$3(1 + 2 + 4 + 8 + 16 + 32) = 189$$
$$200 - 189 = 11$$

15. First of all choice (c) is ruled out since 'd' can not be zero.
Again choice (a) is ruled out because $|r| \neq 1$
Now let us check the option (b)

$$S_\infty = 3 + \left(-\frac{3}{2}\right) + \frac{9}{4} + \left(-\frac{27}{8}\right) + \ldots \infty$$

$$\therefore \quad S_\infty = \frac{3}{1-\left(-\frac{1}{2}\right)} = \frac{3}{\frac{3}{2}} = 2$$

Again, $\quad 27 - \frac{27}{8} + \frac{729}{64} - \ldots \infty$

$$S_\infty = \frac{27}{1-\left(-\frac{1}{8}\right)} = \frac{27}{\frac{9}{8}} = 24$$

Hence choice (b) is the appropriate choice.

Alternatively : $S_1 = \frac{a}{1-r} = 2$

$$S_2 = \frac{a^3}{1-r^3} = 24$$

By solving these two equations, we get

$$a = 3, \quad r = -\frac{1}{2}$$

16. When you check option (a) it will be proved wrong. Again for convenience consider option (c)

$$2, 5, 8, 11, \ldots$$

then first term of that G.P. = 3
and the common ratio of G.P. = 2
Hence G.P. = 3, 6, 12, 24, ...
So $a_1 + a_2 = 9$, which is correct
and S_n of A.P. $= \frac{10}{2}[2 \times 2 + 9 \times 3] = 155$

which is also correct. Hence choice (c) is correct.

Similarly choice (b) is also correct.
Hence choice (d) is most appropriate.

Alternatively : $a, a + d, a + 2d, \ldots$ be an A.P.
and $A, Ar, Ar^2, Ar^3 \ldots$ be a G.P.

then, $\quad \frac{n}{2}[2a + (n-1)d] = 155$

$$5[2a + 9d] = 155$$
$$2a + 9d = 31$$

Again
$$A + Ar = 9 \quad \ldots(1)$$
$$d + ad = 9 \quad \ldots(2)$$

Solving equations (1) and (2) by substitution method,

$$a = 2\frac{25}{2} \quad \text{and} \quad d = 3\frac{2}{3}$$

Thus A.P. → 2, 5, 8, 11, ...
G.P. → 3, 6, 12, 24, ...
or A.P. → $\frac{25}{2}, \frac{79}{6}, \frac{83}{6}, \ldots$
G.P. → $\frac{2}{3}, \frac{25}{3}, \frac{625}{6}, \ldots$

Thus choice (d) is correct.

17.
$$\frac{a}{1-r} = 162, \quad \frac{a(1-r^n)}{1-r} = 160$$

$$\therefore \quad 1 - r^n = \frac{80}{81} \Rightarrow r^n = \frac{1}{81}$$

Now, $\quad$ since $\frac{1}{r} \in Z$

$$\therefore \quad \frac{1}{r^n} = 81 \Rightarrow \frac{1}{r} = 3^{4/n}$$

$$\Rightarrow \therefore \quad n = 1, 2, 4$$

Here 1, 2, 4 are the factors of 4.

Hence

n	r	a
1	$\frac{1}{81}$	160
2	$\frac{1}{9}, -\frac{1}{9}$	144 and 180
4	$\frac{1}{3}, -\frac{1}{3}$	108 and 216

Hence choice (d) is correct.

Scanned by CamScanner

yoursmahboob.wordpress.com

19 PERMUTATIONS & COMBINATIONS

In this chapter we study the selection and arrangement of things, persons, groups etc. which is the most logical phenomenon of mathematics. Since this chapter is logic based, that's why in CAT and XAT it is very important. Every year CAT asks 2-3 questions while XAT asks almost 5-10 questions from this chapter only.

I would like to advise those students who are not familiar with this topic or who are afraid of it, they blend their common sense while solving the problem by formula and beginners should look at the problem through various angles so that they become aware of all the cases inherent in the problem.

One thing is clear about the problems of this chapter is that they do not involve any algebraic equations/expressions. They just require the ability to interpret the situations with open mind and quick multiplication is must.

FUNDAMENTAL PRINCIPLE OF COUNTING

(i) **Multiplication :** If one operation can be performed in 'm' ways and corresponding to each way of performing the first operation a second operation can be performed in n ways, then the two operations together can be performed in $m \times n$ ways.

If after two operations are performed in any one of the $m \times n$ ways a third operation can be performed in p ways, then the three operations together can be performed in $m \times n \times p$ ways and so on.

In general if there are n jobs (works/operations) $j_1, j_2, j_3, ..., j_n$ such that job j_i can be performed independently in m_i ways. $(i = 1, 2, 3, ..., n)$. Then the total number of ways in which all the jobs can be performed is $m_1 \times m_2 \times m_3 \times ... \times m_n$.

Here the different jobs/operations are mutually inclusive. It implies that all the jobs are being done in succession. In this case we use the word **'and'** to complete the all stages of operation and the meaning of **'and'** is multiplication.

e.g., A student has to select a letter from vowels and another letter from consonants, then in how many ways can he make this selection?

SOLUTION Out of 5 vowels he can select one vowel (letter) in 5 ways and out of 21 consonants he can select one consonant (letter) in 21 ways. Thus a letter from the vowels and a letter from the consonants can be selected together in $5 \times 21 = 105$ ways.

(ii) **Addition :** If there are two jobs such that they can be performed independently in m and n ways respectively, then either of the two jobs can be performed in $(m + n)$ ways.

In general if there are various jobs which are mutually exclusive, then they can be performed in $m_1 + m_2 + m_3 + ... + m_n$ ways.

In this case we use the word **'or'** between various jobs and the meaning of **'or'** is addition.

e.g. A student has to select a letter either from vowels 'or' from consonants, then in how many ways can he make this selection?

SOLUTION Out of 5 vowels he can select one letter in 5 ways.

Similarly he can select one letter from 26 consonants in 21 ways.

Thus he can select one letter in $5 + 21 = 26$ ways.

EXAMPLE 1 *If a die is cast and then a coin is tossed, find the number of all possible outcomes.*

SOLUTION A die can fall in 6 different ways showing six different points 1,2 , 3, 4, 5, 6, ... and a coin can fall in 2 different ways showing head (H) or tail (T).

$\therefore$ The number of all possible outcomes from a die and a coin $= 6 \times 2 = 12$

HINT (1, H), (1, T), (2, H), (2, T), (3, H), (3, T), (4, H), (4, T), (5, H), (5, T), (6, H), (6, T) *i.e.*, the total number of all possible outcomes is 12. *i.e.*, the total number of all possible outcomes is 12.

EXAMPLE 2 *There are 6 trains running between Indore and Bhopal. In how many ways can a man go from Indore to Bhopal and return by a different train?*

SOLUTION A man can go from Indore to Bhopal in 6 ways by any one of the 6 trains available. Then he can return from Bhopal to Indore in 5 ways by the remaining 5 trains, since he cannot return by the same train by which he goes to Bhopal from Indore.

Thus the required number of ways $= 6 \times 5 = 30$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 3 *In the previous question, if the person can return by any one of the 6 trains, then find the number of ways in which he can go from Indore to Bhopal and return from Bhopal to Indore.*

SOLUTION He can go from Indore to Bhopal in 6 ways and he can return from Bhopal to Indore in 6 ways also.

Hence the number of ways in which he can go from Indore to Bhopal and return from Bhopal to Indore = $6 \times 6 = 36$ ways.

EXAMPLE 4 *Four persons entered the lift cabin on the ground floor of a six floor office. Suppose each of them can leave the cabin independently at any floor beginning with the first. Find the total number of ways in which each of the four persons can leave the cabin at different floors.*

SOLUTION Suppose M_1, M_2, M_3 and M_4 are four persons. M_1 can leave at any of the 5 floors. So M_1 can leave the cabin in 5 ways. Now, M_2 can leave the cabin at any of remaining 4 floors. So M_2 can leave the cabin in 4 ways. Similarly M_3 and M_4 can leave the cabin in 3 ways and 2 ways respectively. Thus, the total number of ways in which each of the 4 persons can leave the cabin at different floors is $5 \times 4 \times 3 \times 2 = 120$.

EXAMPLE 5 *In the above question if the 4 persons can leave the cabin at any one of the 5 floors, then find the number of ways in which this can be done.*

SOLUTION Since each of the four person can leave the cabin at any one of the 5 floors. Hence each one of M_1, M_2, $M_3$and M_4 can leave the cabin in 5 ways.

Hence total number of ways in which each of the four persons can leave the cabin at any of the 5 floors is $5 \times 5 \times 5 \times 5 = 625$

EXAMPLE 6 *In a MOCK CAT there are 3 sections viz, QA, English and D I containing 4, 6 and 11 questions respectively. In how many ways can a candidate select one question from each of the three sections?*

SOLUTION The candidate can select one question from Q A in 4 ways, one question from English in 6 ways and one question from D I in 11 ways. Hence he can select one question from each of three sections in $4 \times 6 \times 11 = 264$ ways.

EXAMPLE 7 *A tricolour flag is to be formed having three adjacent strips of three different colours choosen from six different colours. How many different coloured flags can be formed with different design in which all the three strips are always in horizontal position ?*

SOLUTION First strip can be coloured in 6 ways and second strip can be coloured in 5 ways and third strip can be coloured in 4 ways.

Hence all the three strips can be coloured in $6 \times 5 \times 4 = 120$ ways.

Hence there can be 120 differently coloured flags.

EXAMPLE 8 *In how many ways can a chairman and vice-chairman be elected from a committee of 8 members who are equally eligible for the post?*

SOLUTION The chairman can be elected in 8 ways, and the vice chairman can be elected in 7 ways from the remaining 7 members.

Hence the required number of ways = $8 \times 7 = 56$ ways.

EXAMPLE 9 *In how many ways can 5 prizes be given away to 7 boys when each boy is eligible for all the prizes?*

SOLUTION First prize can be given away to any one of 7 boys in 7 ways. Again second prize can be given away to any one of the 7 boys since each boy is eligible for all the prizes. Similarly third, fourth and fifth prize can also be given away in 7 ways.

Hence the required number of ways = $7 \times 7 \times 7 \times 7 \times 7 = 7^5$

EXAMPLE 10 *A test paper consists of 10 questions and each question has 4 choices. If each question is necessarily attempted, then find the number of ways of answering the test paper.*

SOLUTION Since each question can be answered in 4 ways. So, the total number of ways of answering 10 questions

$= 4 \times 4 \times 4 \times 4 \times 4 \ldots 10$ times $= 4^{10}$.

EXAMPLE 11 *A set of 6 questions contains true/false type questions. Maximum how many students can take the test if all the students answer differently from others and must attempt all the questions?*

SOLUTION A question can be answered in two ways i.e. either true or false. Hence all the 6 questions can be answered in $2 \times 2 \times 2 \times 2 \times 2 \times 2 = 2^6 = 64$ ways.

Thus there can be maximum 64 students.

EXAMPLE 12 *In a test paper first section contains 5 question each with 4 choices and second section contains 4 questions each with 3 choices. In how many different ways can the paper be answered if all the questions are attempted?*

SOLUTION First section can be answered in $4 \times 4 \times 4 \times 4 \times 4 = 4^5$ ways

Second section can be answered in $3 \times 3 \times 3 \times 3 = 3^4$ ways.

Hence the whole test paper can be answered in $4^5 \times 3^4$ ways.

EXAMPLE 13 *How many three letter words can be formed using only consonants but each only once?*

SOLUTION There are only 21 consonants in English alphabet. So, there are 21 ways of filling up the first place. Now, there are only 20 ways of filling up the second place and the third place can be filled up in 19 ways.

Hence, the required number of words = $21 \times 20 \times 19 = 7980$

EXAMPLE 14 *How many four digit numbers can be formed with the digits 3, 5, 7 and 9 only?*

4	4	4	4
Th	*H*	*T*	*U*

A four digit number has 4 places *viz*, thousands, hundreds, tens and unit place. All the four places can be filled up in $4 \times 4 \times 4 \times 4 = 256$ ways since repetition of digits is not restricted.

EXAMPLE 15 *How many 3 digit number can be formed whose unit digit is always zero and repetition of digits is not allowed?*

SOLUTION

9	8	1

$\Rightarrow \quad 9 \times 8 \times 1 = 72$

Since zero is fixed for the unit digit place. So only 9 digits are available for the hundreds place. Now only 8 digits are available for

Scanned by CamScanner

yoursmahboob.wordpress.com

the tens place since out of 10 digits (i.e., 0, 1, 2, 3, ..., 9) two digits at two places have been used. Therefore required possible numbers $= 9 \times 8 \times 1 = 72$

EXAMPLE 16 *How many numbers can be formed with digits 2, 4, 6, 8 without repetition?*

SOLUTION **Case 1.** There are 4 numbers of 1 digit.

Case 2. | 4 | 3 | $\Rightarrow 4 \times 3 = 12$

There are 12 numbers of 2 digits.

Case 3. | 4 | 3 | 2 | $\Rightarrow 4 \times 3 \times 2 = 24$

There are 24 numbers of 3 digits.

Case 4. | 4 | 3 | 2 | 1 | $\Rightarrow 4 \times 3 \times 2 \times 1 = 24$

There are 24 numbers of 4 digits.

Hence total required numbers $= 4 + 12 + 24 + 24 = 64$

NOTE No any number of 5, 6, 7, ... digits can be formed since we have only four digits and repetition of digits is not allowed.

EXAMPLE 17 *How many four digit numbers can be formed using 5 only once but 5 must be used in all such numbers?*

SOLUTION **Case 1.** | 8 | 9 | 9 | 1 | $\Rightarrow 8 \times 9 \times 9 \times 1 = 648$

When 5 is fixed at unit place, then there are only 8 digits available for thousands place (*i.e.*, except to 0 and 5).

Again hundreds and tens places can be filled by any one of digits from 0 to 9 except 5.

Case 2. | 8 | 9 | 1 | 9 | $\Rightarrow 8 \times 9 \times 1 \times 9 = 648$

When 5 is fixed at tens, place then there are only 8 digits available for thousands place and 9 digits are available for each of the hundreds and unit places.

Case 3. | 8 | 1 | 9 | 9 | $\Rightarrow 8 \times 1 \times 9 \times 9 = 648$

Here 5 is fixed at hundreds place.

Case 4. | 1 | 9 | 9 | 9 | $\Rightarrow 9 \times 9 \times 9 = 729$

Here 5 is fixed at thousands place and each of the hundreds, tens and unit place can be filled up in 9 ways each.

Therefore, the total required numbers of ways

$= 648 + 648 + 648 + 729 = 2673$

EXAMPLE 18 *How many four digit numbers can be formed with the digits 0, 2, 3, 5, 8, 9 if*

(i) repetition of digits is allowed?

(ii) repetition of digits is not allowed?

SOLUTION (i) | 5 | 6 | 6 | 6 | $\Rightarrow 5 \times 6 \times 6 \times 6 = 1080$

Since at thousands place zero can not be placed.

(ii) | 5 | 5 | 4 | 3 | $\Rightarrow 5 \times 5 \times 4 \times 3 = 300$

Since at thousands place zero cannot be placed so only 5 digits are available and there are only 5 remaining digits available for hundreds place and 4 digits for tens place and 3 digits for unit place.

PERMUTATIONS

Each of the different "arrangements" that can be made out of a given number of things by taking some or all of them at a time is called "permutation".

Thus the permutations of three letters (say) a, b, c taken two at a time are

ab, ba, bc, cb, ac, ca

Therefore the number of permutations of three different things taken two at-a time is ${}^3P_2 = 6$

EXAMPLE 1 *Write down all the permutations of the set of four letters E, O, N, T, taken two at a time.*

SOLUTION *EO, OE, EN, NE, ET, TE, ON, NO, OT, TO, NT, TN*

Thus there are total 12 permutations

i.e., ${}^4P_2 = 12$

Notations : The numbers of permutations of 'n' different things taken r at a time is denoted by the symbol $P(n, r)$ or ${}^nP_r$, for every $1 \le r \le n$

Thus ${}^nP_r$ = Total number of permutations of n distinct things taken r at a time.

$$ {}^nP_r = \frac{n!}{(n-r)!} $$

and $n! = 1.2.3.4...(n-1).n$

and $(n-r)! = 1.2.3.4.....(n-r-1).(n-r)$

NOTE $0! = 1 = 1!$

- PERMUTATIONS of n different things taken r at a time $= {}^nP_r = \frac{n!}{(n-r)!}$
- PERMUTATIONS of n different things taken all at a time $= {}^nP_n = n!$
- PERMUTATIONS of n different things taken r at a time, when a particular things always occurs $= r \cdot {}^{(n-1)}P_{(r-1)}$
- PERMUTATIONS of n different things taken r at a time when a particular thing never occurs $= {}^{(n-1)}P_r$.

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE-19.1

1. Find the value of ${}^9P_3$.
(a) 504 (b) 309
(c) 405 (d) 600

2. Find the value of n, if ${}^nP_5 = 20\ {}^nP_3$.
(a) 5 (b) 8
(c) 6 (d) 4

3. If ${}^{56}P_{r-6} : {}^{54}P_{r+3} = 30800 : 1$, find r.
(a) 14 (b) 20
(c) 41 (d) 21

4. How many different numbers of 3 digits can be formed with the digits 1, 2, 4, 5, 7, 8 ; none of the digits being repeated in any of the numbers so formed?
(a) 120 (b) 1200
(c) 180 (d) 270

5. How many even numbers less than 10,000 can be formed with the digits 3, 5, 7,8, 9 without any repetition?
(a) 32 (b) 16
(c) 44 (d) 41

6. How many numbers with different digits each greater than 4000 can be formed from the digits 0, 2, 5, 7, 8?
(a) 160 (b) 168
(c) 320 (d) 270

7. How many numbers greater than 5000 can be formed with the digits, 3, 5, 7, 8, 9 no digit being repeated?
(a) 216 (b) 126
(c) 512 (d) 252

8. How many 6 digit telephone numbers can be constructed with the digits 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 if each number starts with 35 and no digit appears more than once?
(a) 1600 (b) 1680
(c) 900000 (d) 9000

9. How many 6 digit numbers can be formed from the digits 1, 2, 4, 5, 6, 7 (no digit being repeated) which are divisible by 5?
(a) 555 (b) 156
(c) 120 (d) none of these

10. Find the sum of all the four digit numbers which are formed by the digits 1, 2, 5, 6.
(a) 933510 (b) 93324
(c) 65120 (d) 8400

11. How many even numbers greater than 300 can be formed with the digits 1, 2, 3, 4, 5 no digit being repeated?
(a) 111 (b) 600
(c) 900 (d) none of these

12. How many numbers each lying between 100 and 1000 can be formed with the digits 0, 2, 3, 4, 5 (no digit being repeated)?
(a) 24 (b) 48
(c) 72 (d) 96

13. In how many ways the letters of the word RAINBOW be arranged?
(a) 5040 (b) 4050
(c) 3040 (d) 8040

14. In the above question how many words begin with R?
(a) 720 (b) 360
(c) 1440 (d) none of these

15. In the question number 13 how many words begin with R and ends with W?
(a) 120 (b) 240
(c) 180 (d) 360

16. In the question number 13 how many words are there in which R and W are at the end positions ?
(a) 120 (b) 180
(c) 210 (d) 240

17. In the question number 13 how many words are there in which N and B are together ?
(a) 720 (b) 360
(c) 540 (d) 1440

18. In the question number 13 how many words are there in which I and O are never together?
(a) 1440 (b) 720
(c) 3600 (d) none of these

19. In the question number 13 how many words are there in which vowels are never together?
(a) 720 (b) 1440
(c) 360 (d) 3600

20. In the question number 13 how many words are there in which A is always before I and I is always before O?
(a) 840 (b) 420
(c) 720 (d) none of these

21. In the question number 13 how many words are there in which vowels are always before the consonants?
(a) 72 (b) 144
(c) 96 (d) none of these

22. In the question number 13 how many words are there in which first and last letters are vowels?
(a) 360 (b) 720
(c) 1440 (d) 2880

23. If all the words formed by the letters of the word RAINBOW are arranged in a dictionary form, then what is the position of the word RAINBOW in that dictionary?
(a) 3136 (b) 3631
(c) 3361 (d) 1363

24. If no two consonants are together then in how many ways can the word RAINBOW be arranged?
(a) 441 (b) 420
(c) 360 (d) 144

25. How many words can be formed of the letters in the word RAINBOW, so that the vowels may occupy only even positions?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 567 (b) 144
(c) 576 (d) 625

26. How many different words can be formed with the letters of the word RAINBOW so that the vowels occupy odd places?
(a) 676 (b) 625
(c) 343 (d) 576

27. In how many ways can the letters of the word MOBILE be arranged so that the consonants always occupy the odd places?
(a) 18 (b) 36
(c) 54 (d) 72

28. In how many ways can the letters of the word RAINBOW be arranged so that only two vowels always remain together?
(a) 2880 (b) 1440
(c) 3200 (d) none of these

29. In how many ways can the letters of the word MOBILE be arranged so that at least two consonants remain together?
(a) 2880 (b) 3200
(c) 576 (d) 1600

30. In how many ways can the letters of the word STRANGE be arranged so that the vowels may appear in the odd places?
(a) 720 (b) 1092
(c) 1440 (d) none of these

31. Four men and three women are to be seated for a dinner such that no two women sit together and no two men sit together. Find the number of ways in which this can be arranged.
(a) 144 (b) 72
(c) 36 (d) none of these

32. 5 men and 4 women are to be seated in a row so that the women occupy the even places. How many such arrangements are possible?
(a) 2880 (b) 1440
(c) 720 (d) 2020

33. In how many ways 6 students and 4 teachers be arranged in a row so that no two teachers are together?
(a) 604800 (b) 24680
(c) 25860 (d) none of these

34. In how many ways can 5 girls and 3 boys stand in a row so that no two boys are together?
(a) 14400 (b) 7200
(c) 3600 (d) 3200

35. In how many different ways can 8 examination papers be arranged in a row, so that the best and the worst papers may never come together?
(a) 30240 (b) 2340
(c) 12340 (d) none of these

36. There are 6 books on Physics, 3 on Chemistry and 4 on Biology. In how many ways can these be placed on a shelf if the books on the same subject are to be together?
(a) 622080 (b) 888000
(c) 222000 (d) 413080

37. In how many ways three different rings can be worn in four fingers with at most one in each finger?
(a) 24 (b) 12
(c) 36 (d) 120

38. How many different signals can be given using any number of flags from 6 flags of different colours?
(a) 1240 (b) 1956
(c) 3976 (d) 1976

39. A person has 3 shirts 4 coats and 6 ties. In how many ways can he wear them?
(a) 27 (b) 36
(c) 72 (d) 130

40. Four friends have 7 shirts, 6 paints and 8 ties. In how many ways can they wear them?
(a) 336000 (b) 33600
(c) 12480 (d) 508032000

41. In how many ways can 7 soldiers stand in a queue?
(a) 5040 (b) 2880
(c) 280 (d) none of these

42. In how many ways can 10 soldiers stand in two rows having 5 soldiers in each row?
(a) 7257600 (b) 235600
(c) 923500 (d) 35400

43. How many different signals can be made by taking 3 different coloured flags at a time from 5 different coloured flags?
(a) 120 (b) 60
(c) 15 (d) 125

44. 10 students took a test and each one got different score. In how many ways can three different prizes be given?
(a) 270 (b) 360
(c) 720 (d) none of these

45. There are 10 stations on a certain railway line. How many different kinds of tickets of class IInd must be printed in order that a passenger may go from one station to any other by purchasing ticket?
(a) 90 (b) 45
(c) 135 (d) 100

46. Find the number of ways in which 12 different books can be arranged on a shelf so that two particular books shall not be together.
(a) 12! (b) $1320 \times 9!$
(c) 387892 (d) 399168000

47. Find the number of ways in which 12 different books can be arranged on a shelf so that three particular books shall not be together.
(a) $126 \times 10!$ (b) 125000
(c) 357500 (d) 123040

Scanned by CamScanner

yoursmahboob.wordpress.com

PERMUTATIONS OF n THINGS NOT ALL DIFFERENT

- Number of permutations of n things, taken all at a time, of which p are alike of one kind, q are alike of second kind, r are alike of third kind and rest are different

$$= \frac{n!}{p!\,q!\,r!}$$

- Number of permutations of n things, of which P_1 are alike of one kind, P_2 are alike of second kind, P_3 are alike of third kind, ... P_r are alike of r^{th} kind such that $P_1 + P_2 + P_3 + ... + P_r = n$ is $\frac{n!}{P_1!\,P_2!\,P_3!\,...\,P_r!}$

INTRODUCTORY EXERCISE-19.2

1. In how many ways can the letters of the word REPEAT be arranged ?
   (a) 2240 (b) 232230
   (c) 360 (d) 235760
2. In how many ways can the letters of the word TAMANNA be arranged?
   (a) 120 (b) 420
   (c) 840 (d) none of these
3. In how many ways can the letters of the word RECUPERATE be arranged?
   (a) 234000 (b) 123000
   (c) 232300 (d) 302400
4. In how many ways can the letters of the word ASSASSINATION be arranged?
   (a) 181800 (b) 818100
   (c) 108108 (d) 10810800
5. In the above question (number 4) find the number of arrangements of four different letters of the word in a row?
   (a) 360 (b) 180
   (c) 540 (d) none of these
6. How many arrangements can be made out of the letters of the word COMMITTEE, taken all at a time, such that the four vowels do not come together?
   (a) 216 (b) 45360
   (c) 1260 (d) 43200
7. In how many ways can the letters of the word DUMDUMDIGADIGA be arranged?
   (a) 180 (b) 90
   (c) 270 (d) none of these
8. How many different words can be formed with the letters of the word NAINITAL such that each of the word begin with L and end with T?
   (a) 90 (b) 80
   (c) 88 (d) 82
9. How many words can be made from the word MATHEMATICS in which vowels are together?
   (a) 12960 (b) 120960
   (c) 15400 (d) none of (a), (b), (c)
10. How many words can be made from the word IMPORTANT in which both T do not come together?
    (a) 141120 (b) 112244
    (c) 113113 (d) 888222
11. How many words can be made from the word TING TING TRING in which vowels occupy even positions?
    (a) 336000 (b) 85360
    (c) 113600 (d) none of these
12. If the different permutations of the word PRODIGIOUS are listed as in a dictionary, then what is the rank of the word PRODIGIOUS?
    (a) 200966 (b) 609902
    (c) 12500 (d) 24800
13. If all the letters of the word SEQUESTERED be arranged as in a dictionary, what is 50^{th} word?
    (a) DEEEEQURSTS (b) RUQDESTESEE
    (c) ESSTREEUQDE (d) DQUESTREEES
14. How many 7 digit numbers can be formed using the digits 1, 2, 0, 2, 4, 2, 4?
    (a) 120 (b) 360
    (c) 240 (d) 424
15. How many 6 digit numbers can be formed out of the digits of the number 113113?
    (a) 15 (b) 180
    (c) 888 (d) 222
16. How many 6 digit numbers can be formed out of the number 567724, which are even?
    (a) 360 (b) 480
    (c) 180 (d) 220
17. How many numbers greater than a million can be formed with the digits 5, 5, 2, 2, 1, 7, 0?
    (a) 980 (b) 1080
    (c) 920 (d) 1200
18. How many different words can be formed with the letters of the word REGURGITATE so that the two T's are always together?
    (a) 453600 (b) 543600
    (c) 183600 (d) 5040
19. The number of ways in which the letters of the word SUMPTUOS can be arranged so that the two U's do not come together is :
    (a) 5040 (b) 7560
    (c) 38920 (d) none of (a), (b), (c)
20. In how many ways the letters of the word AFLATOON be arranged if the consonants and vowels must occupy alternate places?
    (a) 144 (b) 143
    (c) 288 (d) 248
21. In how many ways can the letters of the word SOOTHSAYER be arranged so that the two S's and two O's come together?
    (a) 23400 (b) 302050
    (c) 12340 (d) 40320
22. There are three copies of each of 4 different books. In how many ways can they be arranged on a shelf?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 369600 (b) 366900
(c) 396600 (d) 306609

23. There are 3 red, 4 green and 5 pink marbles in a bag. They are drawn one by one and arranged in a row. Assuming that all the 12 marbles are drawn, determine the number of different arrangements.
(a) 22770 (b) 27720
(c) 22077 (d) 27270

PERMUTATIONS WHERE REPETITIONS ARE ALLOWED

- The number of permutations of n different things taken r at a time, when each may be repeated any number of times in each arrangement is 'n^r'.

INTRODUCTORY EXERCISE-19.3

1. How many numbers of 5 digits can be formed with the digits 0, 2, 3, 4 and 5 if the digits may repeat?
(a) 2500 (b) 250
(c) 120 (d) 2400
2. How many numbers each lying between 9 and 1000 can be formed with the digits 0, 1, 2, 3, 7, 8 (numbers can be repeated) ?
(a) 30 (b) 120
(c) 210 (d) 90
3. How many five-figures numbers can be formed with the digits 1, 2, 3, 4, 5 given that an even digit may not occupy an even place if the digits may be repeated?
(a) 1125 (b) 5210
(c) 1152 (d) 2120
4. How many of the numbers from 1000 to 9999 (both inclusive) do not have four different digits?
(a) 4446 (b) 4664
(c) 4464 (d) 6444
5. Find the number of three digit numbers (repetitions allowed) such that atleast one of the digits is 9.
(a) 252 (b) 648
(c) 468 (d) 864
6. How many natural numbers not exceeding 4321 can be formed with the digits 1, 2, 3, 4 if repetition is allowed?
(a) 123 (b) 113
(c) 222 (d) 313
7. In how many ways 4 rings of different types can be worn in 3 fingers?
(a) 49 (b) 12
(c) 24 (d) 81
8. In how many ways can 5 prizes be given away to 4 boys, when each boy is eligible for all the prizes?
(a) 1024 (b) 20
(c) 625 (d) 540
9. In how many ways can n balls be randomly distributed in n cells?
(a) $n!$ (b) n^n
(c) $n(n-1)$ (d) 2^n
10. In the above question, what will be the number of ways if it is specified that each cell is to be occupied?
(a) $n!$ (b) n^n
(c) n^3 (d) 2^n
11. In how many ways can 5 letters be posted in 4 letter boxes?
(a) 512 (b) 1024
(c) 625 (d) 20

CIRCULAR PERMUTATIONS

In the previous articles we have learned linear permutations. Now we have to know about circular permutations. In circular permutation things are to be arranged in the form of a ring or a circle, *e.g.*, arrangements of persons around circular dinning table, conferencing table, garland etc.

Since in the circular permutation there is no any end point *i.e.*, we can not say which one is the beginning article or ending article in the possible arrangements.

Hence the number of circular permutations of n objects $= \frac{n!}{n} = (n-1)!$

Thus in a circular permutation one thing is kept fixed and the remaining $(n-1)$ things are arranged in $(n-1)!$ ways.

- If the clockwise and counter clockwise orders are not distinguishable, then the number of ways $= \frac{1}{2}\{(n-1)!\}$

INTRODUCTORY EXERCISE-19.4

1. In how many ways can 6 boys form a ring?
(a) 120 (b) 720
(c) 119 (d) none of (a), (b), (c)
2. In how many ways can 6 boys be arranged at a round table so that 2 particular boys may be together?
(a) 24 (b) 48
(c) 360 (d) 60
3. In how many ways can 6 beads be strung into a necklace?
(a) 60 (b) 360
(c) 720 (d) 120
4. In how many ways can 5 men and 2 ladies be arranged at a round table if two ladies are never together?
(a) 5040 (b) 480
(c) 240 (d) 720

Scanned by CamScanner

yoursmahboob.wordpress.com

5. 9 persons were invited for a business meeting by Ambani, where the host be seated at a circular table. How many different arrangements are possible if two invitees *viz.*, Sahara and Mahindra be seated on either side of the host Ambani?
(a) 10080 (b) 10800
(c) 9200 (d) 4600

6. In a G-20 meeting there were total 20 people representing their own country. All the representative sat around a circular table. Find the number of ways in which we can arrange them around a circular table so that there is exactly one person between two representatives namely Manmohan and Musharraf.
(a) $2 \times (17!)$ (b) $2 \times (18!)$
(c) $(3!) \times (18!)$ (d) $(17!)$

7. 6 men and 6 women are to be seated at a circular table such that no two women are adjacent, then the number of arrangements is :
(a) 86400 (b) 46800
(c) 12! (d) $\frac{1}{2}(12!)$

8. There are 3 boys and 4 girls, seated around a circular table so that no two boys are together. Find the number of ways in which this can be done :
(a) 36 (b) 120
(c) 144 (d) 132

9. 7 sisters dine at a round table. They dine together till each of them dine with different neighbours *i.e.*, they do not like to dine with same neighbours in any two arrangements. In a year how many days they dine together?
(a) 180 (b) 504
(c) 720 (d) 360

10. Find the number of ways in which 10 different flowers can be strung to form a garland so that 3 particular flowers are always together.
(a) 30240 (b) 30420
(c) 23400 (d) none of (a), (b), (c)

11. 3 Male and 3 female singers sat around a circular table. Alka is a female singer did not sat adjacent to a male singer and Sonu is a male singer did not sat adjacent to a female singer. In how many ways this could be done?
(a) 4 (b) 6
(c) 9 (d) 10

COMBINATIONS

Let *A, B, C* be three letters, then we can combine any two of them in the following ways :

AB, BC, AC

Similarly if *A, B, C, D* are four letters, then we can combine any two of them in the following manner :

AB, AC, AD, BC, BD, CD

Similarly we can combine any 3 of *A, B, C, D* as :

ABC, ABD, ACD, BCD

NOTE In the combinations order of the letters (or things) is not considered.
Here *AB, BA* are same and *BC, CB* are also same and so on.
Hence *ABC, ACB, BAC, BCA, CAB* and *CBA* are same and counted as a single combination of *A, B, C*.

NOTE The word combination is generally used for selection of things and the word permutation is used for arrangements of things.

Combinations of 'n' different things taken 'r' at a time

The number of all combinations of n distinct things taken r at a time $(r \le n)$ is

$${}^nC_r = \frac{n!}{(n-r)!\,r!}, \quad C \text{ denotes combination.}$$

PROPERTIES/FACTS ABOUT COMBINATIONS

1. ${}^nC_r = ({}^nP_r)/(r!)$
2. ${}^nC_0 = {}^nC_n = 1$
3. ${}^nC_r = {}^nC_{n-r}\ (0 \le r \le n)$
4. ${}^nC_x = {}^nC_y$ if $x + y = n$ or $x = y\ (x, y \in W)$
5. ${}^nC_{r-1} + {}^nC_r = {}^{n+1}C_r$
6. If n is even, the greatest value of ${}^nC_r = {}^nC_m$ where, $m = \frac{n}{2}$.
7. If n is odd, the greatest value of ${}^nC_r = {}^nC_m$ where, $m = \frac{(n-1)}{2}$ or $m = \frac{(n+1)}{2}$
8. ${}^rC_r + {}^{r+1}C_r + {}^{r+2}C_r + \ldots + {}^nC_r = {}^{n+1}C_{r+1};\ r \le n$
9. ${}^nC_0 + {}^nC_1 + {}^nC_2 + {}^nC_3 + \ldots + {}^nC_n = 2^n$
10. ${}^nC_1 + {}^nC_2 + {}^nC_3 + \ldots + {}^nC_n = 2^n - 1$
11. ${}^nC_0 + {}^nC_2 + {}^nC_4 + \ldots = 2^{2n}$

INTRODUCTORY EXERCISE-19.5

1. Find the vlaue of ${}^8C_3$.
(a) 56 (b) 8!
(c) 65 (d) 3^8

2. Find the value of ${}^{10}C_5$.
(a) 525 (b) 126
(c) 252 (d) 50

3. If ${}^{13}C_x = {}^{13}C_y$ and $x \ne y$, what is the value of $x + y$?
(a) 6 (b) 7
(c) 13 (d) 26

4. ${}^{17}C_r = {}^{17}C_{r+3}$. Find the value of r.
(a) 17 (b) 6
(c) 7 (d) 13

5. ${}^7P_3 = n.{}^7C_3$, find the value of n.
(a) 4 (b) 8
(c) 6 (d) 9

6. If $C(2n, 3) : C(n, 2) = 12 : 1$, find n.
(a) 3 (b) 5
(c) 6 (d) 4

Scanned by CamScanner

yoursmahboob.wordpress.com

7. What is the least possible value of n if : ${}^{n-1}C_3 + {}^{n-1}C_4 > {}^{n}C_3$
(a) 6 (b) 8
(c) 7 (d) 12

8. If ${}^{n}C_x = 56$ and ${}^{n}P_x = 336$, find n and x.
(a) 7, 3 (b) 8, 4
(c) 8, 3 (d) 9, 6

9. What is the value of x when ${}^{11}C_x$ is maximum ?
(a) 7 (b) 6
(c) 5 (d) both (b) and (c)

10. What is the maximum value of ${}^{12}C_x$ for any natural number x ?
(a) 6 (b) 7
(c) 8 (d) 4

11. For what value of x, ${}^{14}C_x$ is maximum?
(a) 5 (b) 6
(c) 7 (d) 8

12. How many different committees of 5 members may be formed from 6 gentlemen and 4 ladies?
(a) 181 (b) 357
(c) 603 (d) 252

13. In a test paper there are total 10 questions. In how many different ways can you choose 6 questions to answer?
(a) 210 (b) 540
(c) 336 (d) none of these

14. In the above question (no. 13) if the question number 1 is compulsory in how many ways can you choose to answer 6 questions in all?
(a) 53 (b) 63
(c) 126 (d) 210

15. Droupdi has 5 friends. In how many ways can she invite one or more of them to a dinner?
(a) 31 (b) 5^5
(c) 13 (d) 2^5

16. In how many ways can a committee of 6 members be formed from 7 men and 6 ladies consisting of 4 men and 2 ladies?
(a) 252 (b) 525
(c) 625 (d) 256

17. A committee of 5 persons is to be formed from a group of 6 gentlemen and 4 ladies. In how many ways can this be done if the committee is to be included atleast one lady?
(a) 123 (b) 113
(c) 246 (d) 945

18. A committee of 7 persons is to be chosen from 13 persons of whom 6 are Americans and 7 are Indians. In how many ways can the selection be made so as to retain a majority of Indians?
(a) 945 (b) 1057
(c) 923 (d) 1056

19. In how many ways can a committee of 4 men and 3 women be appointed from 6 men and 8 women?
(a) 480 (b) 408
(c) 420 (d) 840

20. In the previous question (no. 19) what will be the number of committees in which Miss A refuses to serve if Mr. B is a member?
(a) 210 (b) 420
(c) 630 (d) none of these

21. In how many ways 7 members forming a committee out of 11 be selected so that 3 particular members must be included?
(a) 60 (b) 130
(c) 80 (d) 70

22. In the previous question (no. 21) how many committees can be formed if 3 particular members must not be included?
(a) 6 (b) 8
(c) 10 (d) 61

23. A committee of 3 experts is to be selected out of a panel of 7 persons, three of them are engineers, three of them are managers and one is both engineer and manager. In how many ways can the committee be selected if it must have at least an engineer and a manager?
(a) 33 (b) 22
(c) 11 (d) 66

24. A committee of 5 persons is to be formed out of 6 gents and 4 ladies. In how many ways this can be done, when at most two ladies are included?
(a) 186 (b) 168
(c) 136 (d) 169

25. In an election, a voter may vote for any number of candidates not greater than the number to be chosen. There are 7 candidates and 4 members are to be chosen. In how many ways can a person vote?
(a) 89 (b) 98
(c) 79 (d) 101

26. At an election there are 5 candidates and 3 members are to be elected and a voter is entitled to vote for any number to be elected. In how many ways a voter can a vote?
(a) 25 (b) 5^3
(c) 3^5 (d) 15

27. A question has two parts, Part A and Part B, each containing 8 questions. If the students has to choose 6 from part A and 5 questions from part B, in how many ways can he choose the questions?
(a) 1268 (b) 1788
(c) 1024 (d) 1568

28. An examinee is required to answer six questions out of twelve questions which are divided into two groups each containing six questions and he is not permitted to answer more than four questions from any group. In how many ways can he answer six questions?
(a) 750 (b) 850
(c) 580 (d) 570

29. An examination paper consists of 12 questions divided into two parts, part A and part B. Part A contains 7 questions and part B contains 5 questions. A candidate is required to attempt 8 questions, selecting atleast 3 from each part. In how many ways can he select the questions?
(a) 240 (b) 60
(c) 420 (d) 480

30. In MOCK CAT Quantitative Aptitude Section was divided into 3 groups of 5, 5 and 4 questions respectively. A candidate is required to answer 6 questions taking at least two questions from each of the first two groups and atleast one question from the third group. In how many ways can he make up his choice?
(a) 1200 (b) 1400
(c) 1284 (d) 1560

Scanned by CamScanner

yoursmahboob.wordpress.com

31. Mr. Daruwala has 18 acquaintances of whom 13 are relatives. In how many ways he may invite 10 guests so that 8 of whom are relatives?
(a) 12870 (b) 22022
(c) 20222 (d) 12780

32. If there are 11 players in a cricket team, all of whom shake hands with each other, how many shake hands take place in the team?
(a) 36 (b) 55
(c) 66 (d) none of these

33. Amitabh has a list of 24 friends. He wishes to invite some of them in such a manner that he can enjoy maximum number of parties, but in each party the number of friends (*i.e.*, invitees) be same and each party must have different set of persons. Then how many parties can Amitabh enjoy?
(a) 2704156 (b) 357600
(c) 235763 (d) 270156

34. An ice-cream parlour offers only family packs of ice-creams with 11 different flavours. If each member of a family loves different flavours, then maximum how many such families can purchase the ice-cream if each family contains equal number of persons?
(a) 246 (b) 462
(c) 123 (d) $^{11}C_2$

35. In the previous question (no. 34) what is the maximum possible number of member in a family?
(a) 4 (b) 5
(c) 6 (d) 8

36. In a meeting everyone had shaken hands with everyone else, it was found that 66 handshakes were exchanged. How many members were present in the meeting?
(a) 10 (b) 14
(c) 12 (d) 8

37. In how many ways can a cricket team of eleven players be chosen out of a batch of 16 players if a particular player is always chosen?
(a) 2002 (b) 3003
(c) 1003 (d) 7603

38. In the previous question (no. 37) if a particular player is never chosen, then the number of ways in which a cricket team of eleven players can be chosen is :
(a) 2365 (b) 2359
(c) 1365 (d) 1056

39. A cricket team of 11 players is to be formed from 16 players including 4 bowlers and 2 wicket keepers. In how many different ways can a team be formed so that the team has atleast 3 bowlers and atleast one wicket keeper?
(a) 2472 (b) 2274
(c) 2427 (d) 1236

40. A cricket team of 11 players is to be formed from 20 players including 6 bowlers and 3 wicket keepers. In how many different ways can a team be formed so that the team contain exactly 2 wicket keepers and atleast 4 bowlers?
(a) 22725 (b) 27225
(c) 22275 (d) none of (a), (b), (c)

41. A team of 11 cricketers containing 1 wicket keeper, 2 bowlers, 3 all rounders and 5 batsmen, is to be formed from a group of 25 cricketers containing 2 wicket keepers, 8 bowlers, 5 all rounders and 10 batsmen?
(a) 141120 (b) 111240
(c) 101240 (d) none of (a), (b), (c)

42. Out of 3 books on Economics, 4 books on Corporate Strategy and 5 books on Philosophy, how many collection consists of exactly one book on each subject?
(a) 40 (b) 36
(c) 60 (d) 120

43. In the previous question (no. 42) what is the number of different collections of books if atleast one book on each subject is taken?
(a) 2365 (b) 3255
(c) 4224 (d) 1236

44. A box contains 7 red, 6 white and 4 blue balls. How many selection of three balls can be made so that all three are red balls?
(a) 35 (b) 70
(c) 42 (d) 17

45. In the previous question (no. 44) if the red coloured ball is not taken, then the number of selections is :
(a) 30 (b) 120
(c) 60 (d) none of (a), (b), (c)

46. In the question (no. 44), if there is one ball of each colour, then the number of selections is :
(a) 148 (b) 124
(c) 168 (d) 186

47. An urn contains 5 different red and 6 different green balls. In how many ways can 6 balls be selected so that there are atleast two balls of each colour?
(a) 425 (b) 245
(c) 125 (d) 625

48. Find the number of straight lines formed by joining 6 different points on a plane, no three of them being collinear.
(a) 21 (b) 15
(c) 16 (d) 24

49. How many different straight lines can be formed by joining 12 different points on a plane of which 4 are collinear and the rest are non-collinear?
(a) 16 (b) 32
(c) 61 (d) 64

50. Find the number of diagonals in a decagon.
(a) 25 (b) 35
(c) 45 (d) $^nC_2 - n$

51. Find the number of diagonals in an n-sided polygon.
(a) n^2 (b) $\frac{n(n-3)}{2}$
(c) $n!$ (d) 2^n

52. A polygon has 54 diagonals. Find the number of its sides.
(a) 6 (b) 12
(c) 27 (d) 18

Scanned by CamScanner

yoursmahboob.wordpress.com

53. Find the number of triangles that can be formed by joining the 6 non-collinear points on a plane.
(a) 18 (b) 20
(c) 24 (d) 36

54. Find the number of triangles formed by joining 12 different points on a plane, no three of them being collinear (with the exception of 4 points which are collinear).
(a) 126 (b) 216
(c) 220 (d) 222

55. Two parallel lines each have a number of distinct points marked on them. On one line there are 2 points P and Q. On the other line there are 8 points. Find the number of different triangles which could be formed having 3 of the 10 points as vertices.
(a) 216 (b) 126
(c) 64 (d) 32

56. In the above question (no. 55) how many of these triangles have P as a vertex?
(a) 63 (b) 64
(c) 36 (d) 31

57. If 20 straight lines be drawn in a plane, no two of them being parallel and no three of them concurrent, how many points of intersection will there be?
(a) 95 (b) 380
(c) 400 (d) 190

58. Find the number of different straight lines obtained by joining n points on a plane, no three of which are collinear.
(a) n^3 (b) $\frac{n(n-1)}{2}$
(c) $n!$ (d) 2^4

59. In the previous question (no. 58) what will be the number of straight lines if p points out of n points are in the same straight line?
(a) ${}^{m+n}C_2$ (b) ${}^{n-m}C_2$
(c) ${}^nC_2 - {}^pC_2 + 1$ (d) none of (a), (b), (c)

60. There are n points in a plane no three of which are in the same straight line with the exception of them m ($m < n$) points which are all in the same straight line. Find the number of triangles formed by joining them.
(a) ${}^{n-m}C_3$ (b) ${}^nC_3 - {}^mC_3$
(c) ${}^nC_m$ (d) none of (a), (b), (c)

61. If m parallel lines in plane are intersected by a family of n parallel lines. Find the number of parallelograms formed.
(a) m^n (b) $(m+1)(n+1)$
(c) $\frac{(m-n)}{n!}$ (d) $\frac{mn(m-1)(n-1)}{4}$

62. In a plane there are 37 straight lines, of which 13 pass through the point A and 11 pass through the point B. Besides, no three lines pass through one point, no line passes through both points A and B, and no two are parallel. Find the number of points of intersection of the straight lines.
(a) 535 (b) 525
(c) 235 (d) 355

63. Find the number of different words that can be formed from 15 consonants and 5 vowels by taking 2 consonants and 4 vowels in each word.
(a) 625 (b) 630
(c) 525 (d) 615

64. Find the number of ways of selecting 4 letters from the word EXAMINATION.
(a) 136 (b) 126
(c) 252 (d) 525

65. How many words can be formed by using 4 letters at a time out of the letters of the word MATHEMATICS?
(a) 2445 (b) 2454
(c) 1243 (d) 1454

66. In how many ways can 3 ladies and 3 gentlemen be seated at a round table, so that any two and only two of ladies sit together?
(a) 72 (b) 36
(c) 24 (d) 144

67. Eighteen guests have to be seated half on each side of a long table. Four particular guests desire to sit on one particular side and three others on other side. Determine the number of ways in which the sitting, arrangements can be made.
(a) 18! (b) $462 \times (9!)^2$
(c) $(9!)^2$ (d) $7! \times (9!)^2$

68. There are 4 different letters and 4 addressed envelopes. In how many ways can the letters be put in the envelopes so that atleast one letter goes to the correct address?
(a) 15 (b) 16
(c) 18 (d) 12

69. Find the number of ways in which none of the letters goes to the correct address? (as per the previous question)
(a) 6 (b) 9
(c) 10 (d) 11

SOME RESTRICTED COMBINATIONS

1. Number of combinations of n things taken 'r' at a time in which x **particular things always occur** is ${}^{n-x}C_{r-x}$.
2. Number of combinations of n things taken 'r' at a time in which x **particular things never occur** is ${}^{n-x}C_r$.
3. Number of ways of selections of **zero or more** things from a group of 'n' **distinct things** is 2^n.
i.e., ${}^nC_0 + {}^nC_1 + {}^nC_2 + {}^nC_3 + \ldots + {}^nC_n = 2^n$
4. Number of ways of selection of **one or more** things from a group of 'n' **distinct things** is $2^n - 1$.
i.e., ${}^nC_1 + {}^nC_2 + {}^nC_3 + \ldots + {}^nC_n = 2^n - 1$
$(\because {}^nC_0 = 1)$

Scanned by CamScanner

yoursmahboob.wordpress.com

5. Number of ways of selection of 'r' **things** out of 'n' **identical things** is 1. $(r \le n)$
6. Number of ways of selection of **zero or more** things from a group of 'n' **identical things** is $(n+1)$.
7. Number of ways of selection of **some or all things** *i.e.*, atleast 1 out of $(p+q+r+\ldots)$ things of which p are alike of one kind, q are alike of second kind r are alike of third kind and so on, is $\{(p+1)(q+1)(r+1)\ldots\}-1$.
8. Total number of ways of selecting one or more things from 'p' identical things of one kind, 'q' identical things of second kind, 'r' identical things of third kind and n different things is $\{(p+1)(q+1)(r+1)2^n\}-1$
9. Number of selections of k consecutive things out of n things in a row is $(n-k+1)$.
10. Number of selection of k consecutive things out of n things in a circle $= \begin{cases} n & \text{when } k<n \\ 1 & \text{when } k=n \end{cases}$

INTRODUCTORY EXERCISE-19.6

1. Given 3 different red dyes, 4 different blue dyes, and 5 different green dyes, how many combinations of dyes can be made taking atleast one green and one blue dye?
   (a) 2300 (b) 31
   (c) 3720 (d) 3560
2. In how many ways is it possible to make a selection by taking any number of 15 fruits, namely 3 oranges, 5 apples and 7 mangoes?
   (a) 131 (b) 191
   (c) 68 (d) 3720
3. In how many ways can a person choose one or more beverages out of Sodawater, Mirinda, Whisky and Coffee?
   (a) 16 (b) 4
   (c) 15 (d) 4!
4. A bag contains 4 mangoes and 5 oranges. In how many ways can I make a selection so as to take atleast one mango and one orange?
   (a) 465 (b) 365
   (c) 8 (d) 19
5. In now many ways is it possible to make a selection by taking any number of all 20 fruits, namely 9 mangoes, 7 oranges and 4 apples?
   (a) 199 (b) $^{20}C_3$
   (c) $^{20}P_3$ (d) 399
6. A student is allowed to select at most n books from a collection of $(2n+1)$ books. If the total number of ways in which he can select atleast one book is 63, find the value of n.
   (a) 5 (b) 6
   (c) 3 (d) 7

DIVISION INTO GROUPS

Division of Items into Groups of Unequal Size

1. The number of ways in which $(m+n)$ different things can be divided into two groups containing m and n things respectively is $\dfrac{(m+n)!}{m!n!}$.

   Since m things can be selected out of $(m+n)$ things in $^{m+n}C_m$ ways and each time when m things are taken, n things left out to form the other group of n things in ^nC_n ways *i.e.*, in 1 way only.

   Hence the required number of ways

   $$= {}^{m+n}C_n = \frac{(m+n)!}{m!\cdot n!}$$

2. The number of ways in which $(m+n+p)$ different things can be divided into three groups containing m, n and p things respectively is $\dfrac{(m+n+p)!}{m!\cdot n!\cdot p!}$.

NOTE If $(m+n)$ things are distributed among two persons in the groups of m, n things, then the number of ways $= \dfrac{(m+n)!}{m!\cdot n!} \times 2!$

Similarly : If $(m+n+p)$ things are distributed among three persons in the groups of m, n and p things then the number of ways

$$= \frac{(m+n+p)!}{m!\cdot n!\cdot p!} \times 3!$$

3. The number of ways in which 'n' distinct things can be distributed to r different persons $= r^n$.

Division of Items into Groups of Equal Size

The number of ways in which mn different things can be divided equally into m groups, each group containing n things

$$= \left(\frac{(mn)!}{(n!)^m}\right)\frac{1}{m!}$$

The number of ways in which mn different things can be distributed equally into m groups, each group containing n things $= \dfrac{(mn)!}{(n!)^m}$.

NOTE In the distribution order is important hence the divisible things can be arranged in $m!$ ways.
Since things are divided into m groups.

Scanned by CamScanner

yoursmahboob.wordpress.com

DIVISION OF IDENTICAL ITEMS INTO GROUPS

1. The number of ways of dividing n identical things among r persons (or groups), each of whom, can receive zero or more things is ${}^{n+r-1}C_{r-1}$ where $0 \le r \le n$.
2. The number of ways of dividing n identical things among r persons, each one of whom, receives atleast one item is ${}^{n-1}C_{r-1}$ where $1 \le r \le n$.
3. The number of ways in which 'n' identical things can be divided into r groups so that no group contains less than m items and more than k (where $m < k$) is coefficient of x^n in the expansion of $(x^m + x^{m+1} + \ldots + x^k)^r$.

INTRODUCTORY EXERCISE-19.7

1. Find the number of ways in which 12 students may be equally divided into three groups.
(a) 3355 (b) 5775
(c) 7755 (d) 8822

2. Find the number of ways in which 12 mangoes may be equally divided among 3 boys.
(a) 57750 (b) 34650
(c) 23450 (d) 12345

3. Five balls of different colours are to be placed in three boxes of different sizes. Each box can hold all the five balls. In how many ways can we place the balls so that no box remains empty?
(a) ${}^5C_3$ (b) 5!
(c) 150 (d) 5^3

4. In how many ways can a pack of 52 cards be divided equally among four players in order?
(a) $(52!)^4$ (b) $4 \times (13!)$
(c) $\dfrac{52!}{(13!)^4}$ (d) none of these

5. In how many ways can a pack of 52 cards be divided equally into four groups?
(a) $\dfrac{52!}{(13!)^4 \times 4!}$ (b) $4!\left[\dfrac{52!}{(13!)^4}\right]$
(c) $\dfrac{52!}{(13!)^4}$ (d) none of these

6. In how many ways can a pack of 52 cards be divided into 4 sets, three of them having 16 cards each and the fourth just 4 cards?
(a) $16! \times 52!$ (b) $\dfrac{(52!)}{(16!)^3}$
(c) $\dfrac{52!}{(3!)^{16}}$ (d) $\dfrac{52!}{(16!)^3 \times (3!)}$

7. In how many ways can $2n$ students be divided into n pairs?
(a) n^2 (b) $\dfrac{n!}{2}$
(c) $\dfrac{2n!}{(2!)^n \cdot (n!)}$ (d) none of these

8. Total number of ways in which 20 mangoes can be distributed among 4 persons is :
(a) ${}^{20}C_3$ (b) ${}^{23}C_3$
(c) ${}^{24}C_4$ (d) $\dfrac{20!}{4!}$

9. Find the number of ways of distributing 7 identical balls into three boxes so that no box is empty and each box being large enough to accomodate all balls.
(a) 15 (b) 7^3
(c) 3^7 (d) $\dfrac{7!}{3!}$

10. Find the number of non negative integral solutions of :
$x_1 + x_2 + x_3 + x_4 = 44$
(a) ${}^{44}C_4$ (b) ${}^{43}C_3$
(c) ${}^{47}C_3$ (d) none of these

11. How many integral solutions are there to $a + b + c = 18$ when $a \ge 1$, $b \ge 2$, $c \ge 3$?
(a) ${}^{19}C_3$ (b) ${}^{17}C_2$
(c) ${}^{15}C_3$ (d) ${}^{14}C_2$

12. Find the number of ways in which 21 balls can be distributed among 3 persons such that each person does not receive less than 5 balls.
(a) 28 (b) 14
(c) 21 (d) 7

SOME IMPORTANT RESULTS

1. Number of squares in a square of having 'n' columns and 'n' rows
$$= 1^2 + 2^2 + 3^2 + \ldots + n^2 = \Sigma n^2$$
$$= \frac{n(n+1)(2n+1)}{6}$$
2. Number of rectangles in a square having 'n' columns and 'n' rows
$$= 1^3 + 2^3 + 3^3 + \ldots + n^3 = \Sigma n^3 = \left[\frac{n(n+1)}{2}\right]^2$$
3. Number of squares in a rectangle having 'm' columns and 'n' rows
$= m \cdot n + (m-1)(n-1) + (m-2)(n-2) + \ldots 0.$
4. Number of rectangles in a rectangle having 'm' columns and 'n' rows
$= (1 + 2 + 3 + \ldots + m) \cdot (1 + 2 + 3 + \ldots + n).$
5. Number of quadrilaterals if m parallel lines intersect 'n' parallel lines $= {}^mC_2 \times {}^nC_2$.
6. Number of terms in $(a_1 + a_2 + \ldots + a_n)^m$ is ${}^{m+n-1}C_{n-1}$.
7. Number of terms in $(1 + x + x^2 + \ldots + x^n)^m$ is $m \cdot n + 1$.

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. A letter lock consists of 4 rings, each ring contains 9 non-zero digits. This lock can be opened by setting a 4 digit code with the proper combination of each of the 4 rings. Maximum how many codes can be formed to open the lock?
(a) 4^9 (b) ${}^9P_4$
(c) 9^4 (d) none of these

2. In the previous question, if the lock opens in only one arrangement of 4 digits, how many unsuccessful attempts are possible in which lock can not be opened?
(a) $4^9 - 1$ (b) $9^4 - 1$
(c) ${}^9C_4$ (d) none of these

3. A group consists of 4 couples in which each of the 4 persons have one wife each. In how many ways could they be arranged in a straight line such that the men and women occupy alternate positions?
(a) 1152 (b) 1278
(c) 1296 (d) none of these

4. In the previous question (no. 3) in how many ways can they be arranged in a straight line such that no two men were sitting together?
(a) 1242 (b) 1440
(c) 3880 (d) 2880

5. In question number 3, in how many ways can they be seated such that each husband sit with his own wife?
(a) 384 (b) 275
(c) 184 (d) none of these

6. In question no. 3, in how many ways can they be seated around a circular table such that the men and women occupy the alternate position?
(a) 288 (b) 144
(c) 72 (d) 720

7. In question (no. 3) in how many ways can they be seated on the single bench such that all the men sit together and all the women sit together?
(a) 1512 (b) 1296
(c) 1152 (d) none of these

8. How many different words can be made using the letters of the word 'HALLUCINATION' if all consonants are together?
(a) 129780 (b) 1587600
(c) 35600 (d) none of these

9. If all vowels occupy odd places, how many words can be formed from the letters of the word HALLUCINATION?
(a) 129650 (b) 1587600
(c) 78500 (d) none of these

10. In how many ways can the letters of the word SUCCESSFUL be arranged?
(a) 1215700 (b) 1251600
(c) 151200 (d) none of these

11. If all $S's$ come together, then in how many ways the letters of the word SUCCESSFUL be arranged?
(a) 10080 (b) 40080
(c) 2378 (d) none of these

12. If all $C's$ occur together and all $U's$ also occur together, then how many arrangements are possible of the word SUCCESSFUL?
(a) 5745 (b) 2760
(c) 6720 (d) 5432

13. What is the sum of all the 4 digit numbers which can be formed with the digits 1, 2, 3, 4 without repetition?
(a) 15560 (b) 87660
(c) 45600 (d) 66660

14. What is the sum of all 5 digit numbers which can be formed with the digits 0, 1, 2, 3, 4 without repetition?
(a) 2599980 (b) 235500
(c) 923580 (d) 765432

15. Which one of the following polygon has as many diagonals as the number of sides in it?
(a) 4 (b) 6
(c) 5 (d) 7

16. In how many ways can the letters of the word PROPORTION be arranged by taking 4 letters at a time?
(a) 123 (b) 758
(c) 658 (d) 578

17. In the previous question (no. 16) how many words can be formed without changing the relative positions of the vowels and consonants?
(a) 217 (b) 720
(c) 920 (d) 1040

18. There are 16 executives including two brothers, Lehman and Mckinsey. In how many ways can they be arranged around the circular table if the two brothers can not be seated together?
(a) $(14!)\cdot 13$ (b) ${}^{14}P_3$
(c) $\frac{14!}{3!}$ (d) none of these

19. In the previous question how many arrangements are possible if there is exactly one executive between these two brothers?
(a) $(14!)^2$ (b) $(14!)$
(c) $2\cdot(14!)$ (d) none of these

20. In how many different ways can 6 different balls be distributed to 4 different boxes, when each box can hold any number of ball?
(a) 2048 (b) 1296
(c) $(24)^2$ (d) 4096

Scanned by CamScanner

yoursmahboob.wordpress.com

21. In how many different ways can 6 identical balls be distributed to 4 different boxes, when each box can have any number of balls?
(a) 12 (b) 18
(c) 84 (d) 88

22. If $a+b+c=21$, what is the total number of non-negative integral solutions?
(a) 123 (b) 253
(c) 321 (d) 231

23. If $a+b+c=21$ what is the total number of positive integral solutions?
(a) 109 (b) 190
(c) 901 (d) 910

24. What is the total number of ways of selecting atleast one object from 2 sets of 12 different objects, each set contains 6 objects?
(a) 4096 (b) 4095
(c) 2048 (d) none of these

25. What is the total number of ways of selecting atleast one object from 2 different sets, each set containing 6 identical objects?
(a) 24 (b) 48
(c) 76 (d) 96

26. What is the total number of ways of selecting atleast one item from each of the two sets containing 6 different items each?
(a) 2856 (b) 3969
(c) 480 (d) none of these

27. What is the total number of ways of selecting atleast one item from each of the two sets containing 6 identical items each?
(a) 16 (b) 36
(c) 32 (d) 18

28. A girl has to climb 12 steps. She climbs in either a single step or 2 steps simultaneously. In how many ways can she do it?
(a) 233 (b) 223
(c) 322 (d) 232

29. In how many ways can 8 identical apples be divided among 3 sisters?
(a) 25 (b) 65
(c) 45 (d) 24

30. In how many ways can 100 soldiers be divided into 4 squads of 10, 20, 30, 40 respectively?
(a) 1700 (b) 18!
(c) 190 (d) none of these

31. What is the total number of 4 digit numbers that can be formed using the digits 0, 1, 2, 3, 4, 5 without repetition, such that the number is divisible by 9?
(a) 36 (b) 28
(c) 15 (d) 18

32. How many 5 digit numbers contain exactly two 7's in them?
(a) 4268 (b) 6804
(c) 2340 (d) 1269

33. In how many ways can 15 billiard balls be arranged in a row if 3 are red, 4 are white and 8 are black?
(a) 12 (b) 18
(c) 96 (d) none of these

34. Seven delegates are to address a meeting. If a particular speaker is to speak before another particular speaker, find the number of ways in which this can be arranged.
(a) 1220 (b) 2520
(c) 3250 (d) 7826

35. How many 7 digit telephone numbers can be formed from the digits 0, 1, 2, ..., 9, where each telephone number begins with digit 2?
(a) 10^6 (b) 6^{10}
(c) 10! (d) ${}^{10}P_6$

36. A man has 4 sons. There are 6 proposals of marriage for his sons. In how many ways can they select a proposal for their marriages, such that none of them marry with more than one girl?
(a) 180 (b) 270
(c) 360 (d) none of these

37. In how many ways can 4 books be selected out of 16 books on different subjects?
(a) 1208 (b) 1820
(c) 1296 (d) 1860

38. In how many ways can 4 books be arranged out of 16 books on different subjects?
(a) 34650 (b) 43680
(c) 43890 (d) none of these

39. In how many ways can 16 books on different subjects be divided equally into 4 groups?
(a) $\frac{16!}{(4!)}$ (b) $4!\times(16!)$
(c) $\frac{16!}{(4!)^5}$ (d) none of these

40. In a badminton tournament each player played one game with all the other players. How many players participated in the tournament if they played 105 games in all?
(a) 35 (b) 12
(c) 15 (d) none of these

41. There are 9 subjects in eighth standard but there are only 6 periods in a day. In how many ways can the time table be formed?
(a) 60480 (b) 23460
(c) 56780 (d) 61280

42. How many 6 digit numbers can be formed using the digit 2 two times and the digit 4 four times?
(a) 16 (b) 15
(c) 18 (d) 24

43. There are 4 different monitors and 6 different mother boards. How many different arrangements can be made to purchase a monitor and a motherboard?
(a) 12 (b) 24
(c) 18 (d) 6^4

44. The number of five digit numbers having atleast one of their digits repeated is :
(a) 900 (b) 1000
(c) 62784 (d) none of these

45. Four dice are rolled. The number of possible outcomes in which atleast one die shows 4 is :
(a) 671 (b) 168
(c) 176 (d) none of these

46. The number of signals that can be generated by using 5 differently coloured flags, when any number of them may be hoisted at a time is :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) 235 (b) 253
(c) 325 (d) none of these

47. If the letters of the word VERMA are arranged in all possible ways and these words are written out as in a dictionary, then the rank of the word VERMA is :
(a) 108 (b) 117
(c) 810 (d) 180

48. How many 5 digit numbers divisible by 3 can be formed using the digits 0, 1, 2, 3, 4 and 5, without repetition?
(a) 108 (b) 216
(c) 810 (d) 180

49. In how many ways can a mixed double game can be arranged from amongst 8 married couples if no husband and wife play in the same game?
(a) 840 (b) 240
(c) 480 (d) none of these

50. If n objects are arranged in a row, then the number of ways of selecting three of these objects so that no two of them are next to each other is :
(a) ${}^nC_3$ (b) ${}^{n-2}C_3$
(c) ${}^nC_2$ (d) none of these

51. The number of times the digit 8 will be written when listing the integers from 1 to 1000 is :
(a) 100 (b) 200
(c) 300 (d) 400

52. Five balls of different colours are to be placed in three boxes of different sizes. Each box can hold all five balls. The number of ways in which we can place the balls in the boxes so that no box remains empty is :
(a) 30 (b) 150
(c) 600 (d) 900

53. The number of squares on a chessboard is :
(a) 102 (b) 108
(c) 216 (d) 204

54. A train going from Lucknow to Mumbai stops at 7 intermediate stations. Five persons enter the train during the journey with five different tickets of the same class. How many different set of tickets they could have had ?
(a) 98280 (b) 2898
(c) 7325 (d) none of these

55. In how many ways can a committee of 4 women and 5 men be chosen from 9 women and 7 men, if Mr. A refuses to serve on the committee if Ms. B is a member?
(a) 1608 (b) 1860
(c) 1680 (d) 1806

Directions for question number 56-63 : There are 5 different caps c_1, c_2, c_3, c_4 and c_5 and 5 different boxes B_1, B_2, B_3, B_4 and B_5. The capacity of each box is sufficient to accomodate all the 5 caps.

56. If any box can have any number of caps, in how many ways can all the caps be distributed?
(a) 3125 (b) 1235
(c) 2358 (d) 1248

57. In how many arrangements does B_1 have cap C_1?
(a) 5! (b) 5^4
(c) ${}^5P_4$ (d) none of these

58. If all the caps are of different colours and each box can have only one cap, in how many ways can you arrange the caps among the 5 boxes?
(a) 120 (b) 180
(c) 360 (d) none of these

59. If atleast one cap has to be distributed and the caps have to be arranged such that any box can have a maximum of one cap only, in how many ways can you arrange the caps among 5 boxes?
(a) 1 (b) 16
(c) 1545 (d) none of these

60. If all the caps are identical, in how many ways can the caps be arranged in the different boxes such that no box is empty?
(a) 1 (b) 2
(c) 6 (d) 8

61. If C_1 and C_5 are similar in all aspects, in how many ways can you arrange the caps in such a way that all the boxes have one cap?
(a) 70 (b) 60
(c) 75 (d) 80

62. If B_3 can have only C_1 or C_5, in how many ways can you arrange the caps such that all boxes have one cap?
(a) 480 (b) 420
(c) 48 (d) 88

63. If B_1 and B_5 have the caps C_1 and C_5 among themselves, in how many ways can you arrange the caps among the 5 boxes ?
(a) 400 (b) 485
(c) 500 (d) 365

LEVEL 2

1. In how many ways can the following prizes be given away to a class of 30 students, first and second in Mathematics, first and second in Physics, first in Chemistry and first in English?
(a) $\frac{30!}{4!}$ (b) $(30)^4 \times (29)^2$
(c) $(30)^3 - 1$ (d) $(30)^4 \times (29)^4$

2. If P_r stands for ${}^rP_r$, then the value of
$1 + 1.P_1 + 2.P_2 + 3.P_3 + \ldots + n.P_n$ is :
(a) $\frac{(n-1)!}{2}$ (b) $\frac{(n+1)!}{2}$
(c) $2(n-1)!$ (d) $(n+1)!$

3. In an examination hall there are four rows of chairs. Each row has 6 chairs one behind the other. There are two classes sitting for the examination with 12 students in each class. It is desired that in each row, all students belong to the same class and that no two adjacent rows are alloted to the same class. In how many ways can these 24 students be seated?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $2(12!)^2$ (b) $3! \times (12!)^2$
(c) $(6!)^2$ (d) none of these

4. How many 3 digit even numbers are there such that if 3 is one of the digits then 9 is the next digit?
(a) 365 (b) 536
(c) 210 (d) 156

5. A number plate of a vehicle has always a fixed code UP–32 for Lucknow city followed by the number of particular vehicle which is in two parts. First part is occupied by 2 English alphabets and second part is occupied by 4 digit numbers (0001, 0002, ... 9999). If the latest registration number of vehicle is $\begin{Bmatrix} UP-32 \\ SK-0123 \end{Bmatrix}$, find the number of vehicles registered before this vehicle number in Lucknow.
(a) 2449744 (b) 4779644
(c) 4669235 (d) 9235888222

6. How many 4 digit numbers divisible by 4 can be formed without using the digits 0, 6, 7, 8, 9 if the repetition of digits is not allowed?
(a) 67 (b) 68
(c) 24 (d) 48

7. In how many ways three girls and nine boys can be seated in two vans, each having numbered seats, 3 in the front and 4 at the back?
(a) $^{14}C_{12}$ (b) 9^4
(c) $^{14}P_{12}$ (d) none of these

8. In the previous question, how many seating arrangements are possible if 3 girls sit together in a back row on adjacent seats?
(a) $(3!)^2$ (b) 6!
(c) 5! (d) none of these

9. In how many ways 5 plus (+) signs and 5 minus (–) signs be arranged in a row so that no two minus signs are together?
(a) 6 (b) 7
(c) 8 (d) 10

10. In how many ways can 11 identical books on English and 9 identical books on Maths be placed in a row on a shelf so that two books on Maths may not be together?
(a) 110 (b) 220
(c) 330 (d) 440

11. Find the total number of factors of 1680.
(a) 40 (b) 50
(c) 60 (d) 30

12. $\sum_{k=m}^{n} {}^kC_r$ equals :
(a) $^{n+1}C_{r-1}$ (b) $^{n+1}C_{r+1} - {}^mC_r$
(c) $^{n+1}C_{r+1} - {}^mC_{r+1}$ (d) $^{n+1}C_{r+1} + {}^mC_{r+1}$

13. In a certain test there are n questions. In this test 2^{n-k} students gave wrong answers to atleast k questions, where $k = 1, 2, 3, \ldots, n$. If the total number of wrong answers given is 2047, then n is equal to :
(a) 10 (b) 11
(c) 12 (d) 13

14. The number of triangles whose vertices are at the vertices of an octagon but none of the sides of such triangles are taken from the sides of the octagon.
(a) 8 (b) 15
(c) 16 (d) none of these

15. The number of ways in which we can select 5 numbers from the set of numbers {1, 2, 3, ..., 25} such that none of the selections includes four consecutive numbers is :
(a) 53109 (b) 13350
(c) 10035 (d) none of these

16. The number of integral solutions for the equation $a + b + c + d = 12$, where $(a, b, c, d) \geq -1$ is :
(a) $^{19}C_3$ (b) $^{18}C_4$
(c) $^{20}C_4$ (d) none of these

17. If $n = {}^kC_2$, the value of $^nC_2$ is :
(a) $2({}^{k+2}C_4)$ (b) $(n-2)!$
(c) $(k-2)!$ (d) $3({}^{k+3}C_4)$

18. The number of positive integral solutions of $abc = 42$ is :
(a) 17 (b) 27
(c) 21 (d) $3! \times 42$

19. There are three piles of identical red, green and blue balls and each pile contains atleast 10 balls. The number of ways of selecting 10 balls if twice as many red balls as green balls are to be selected is :
(a) 1 (b) 2
(c) 4 (d) 6

20. Between Shirdee and Khandala, there are 10 intermediate stations. The number of ways in which a train can be made to stop at 4 of these stations so that no two of these halting stations are consecutive is :
(a) 35 (b) 70
(c) 105 (d) 10

21. The number of ways in which an examiner can assign 30 marks to 8 questions, giving not less than 2 marks to any question is :
(a) 11 (b) $^{21}C_7$
(c) 18 (d) 235

22. The exponent of 3 in 33! is :
(a) 15 (b) 2
(c) 11 (d) none of these

23. The total number of natural numbers of 6 digits that can be formed with digits 1, 2, 3, 4, if all the digits are to appear in the same number atleast once, is :
(a) 740 (b) 1830
(c) 1560 (d) none of these

24. The total number of seven digit numbers, the sum of whose digits is even are :
(a) 2500000 (b) 4500000
(c) 35×10^5 (d) none of these

25. The number of ways in which 4 pictures can be hung from 6 picture nails on the wall is :
(a) 4^6 (b) $^6P_6$
(c) $^6P_4$ (d) 6^4

26. The total number of ways of selecting 6 coins out of 10 one rupee coins, 6 fifty paise coins and 8 twenty paise coins is :
(a) 28 (b) 14
(c) 13 (d) 19

Scanned by CamScanner

yoursmahboob.wordpress.com

27. Nargis has 8 children and she takes 3 at a time to children's park as often as she can without taking the same 3 children together more than once. The number of times she will go to the park is :
(a) 56 (b) 14
(c) 28 (d) 76

28. In the previous problem (no. 27), the number of times each child will go the park is :
(a) 14 (b) 8
(c) 21 (d) none of these

29. The sides AB, BC, CA of a triangle ABC have 3, 4 and 5 interior points respectively on them. The total number of triangles that can be constructed by using these points as vertices is :
(a) 105 (b) 307
(c) 420 (d) 205

30. The number of all the possible selections which a student can make for answering one or more questions out of 10 given questions in a paper, when each question has an alternative is :
(a) 1345 (b) 23560
(c) 541340 (d) 59048

31. The number of ways in which a team of eleven players can be selected from 22 players including 2 of them and excluding 4 of them is :
(a) ${}^{15}C_{10}$ (b) ${}^{16}C_{10}$
(c) ${}^{16}C_{9}$ (d) none of these

32. There are 10 lamps in a hall. Each one of them can be switched on independently. The number of ways in which the hall can be illuminated is :
(a) 1022 (b) 1023
(c) 1024 (d) none of these

33. How many 10 digits numbers can be formed by using the digits 2 and 3?
(a) 2^{10} (b) 10^2
(c) 10! (d) none of these

34. How many subsets containing at most n elements from the set of $(2n + 1)$ elements can be selected?
(a) 2^n (b) 2^{n-1}
(c) 2^{n+1} (d) 2^{2n}

35. The sum of the divisors of $2^3 \cdot 3^4 \cdot 5^2$ is :
(a) 15625 (b) 1234
(c) 56265 (d) 56789

36. The number of ways of selecting 10 balls out of an unlimited number of white, red, blue and green balls is :
(a) 268 (b) 286
(c) 246 (d) 468

37. If 10 objects are arranged in a row, then the number of ways of selecting three of these objects so that no two of them are next to each other is :
(a) 56 (b) 65
(c) 28 (d) 13

38. The number of non-negative integral solutions of $x_1 + x_2 + x_3 + x_4 \le n$ (where n is a positive integer) is :
(a) ${}^{n+3}C_3$ (b) ${}^{n+2}C_3$
(c) ${}^{n+4}C_4$ (d) ${}^{n+4}C_3$

39. The total number of permutations of $(n > 1)$ different things taken not more than r at a time, when each thing may be repeated any number of times is :
(a) $\dfrac{n^r - 1}{(n-1)}$ (b) $r^n - 1$
(c) $\dfrac{n(n^r - 1)}{(n-1)}$ (d) none of these

40. Number of rectangles on a chessboard is :
(a) 1008 (b) 1296
(c) 1124 (d) 1600

41. Ten persons, amongst whom A, B and C are to speak at a function. The number of ways in which it can be done if A wants to speak before B and B wants to speak before C is :
(a) $\dfrac{10!}{6}$ (b) $\dfrac{9!}{6}$
(c) ${}^{9}C_{6}$ (d) none of these

42. The number of natural numbers which are smaller than $2 \cdot 10^8$ and which can be written by means of the digits 1 and 2 is :
(a) 678 (b) 786
(c) 766 (d) 677

43. Tweleve persons are arranged in a row. The number of ways of selecting four persons so that no two persons sitting next to each other are selected is :
(a) 124 (b) 136
(c) 126 (d) none of these

44. The number of n-bit (digits 0 and 1) strings having exactly k zeros with no two zeros consecutive is, where $2k < n$.
(a) ${}^{n+1-k}C_k$ (b) ${}^{n+k}C_k$
(c) ${}^{n-k}C_k$ (d) ${}^{n-1}C_k$

45. A question paper has two parts–Part A and Part B. Part A contains 5 questions and part B has 4. Each question in part A has an alternative. A student has to attempt atleast one question from each part. Find the number of ways in which the student can attempt the question paper.
(a) 3360 (b) 1258
(c) 3850 (d) 3630

46. How many different vehicle licence plates can be made if the licences contain 2 letters of the English alphabet followed by a three digit number if repetitions are allowed?
(a) 54320 (b) 67534
(c) 23456 (d) 675324

47. In the previous question (no. 46), how many different plates can be formed if the repetitions are not allowed?
(a) 468000 (b) 13000
(c) 15680 (d) none of these

48. $2m$ people are arranged along two sides of a long table with m chairs each side. r men wish to sit on one particular side and s on the other. In how many ways can they be seated? $(r, s \le m)$
(a) ${}^{48}C_r$ (b) $68\ m$
(c) $\dfrac{(2m + r)!}{r!\,s!}$ (d) none of these

49. Management city has m parallel roads running East-West and n parallel roads running North-South. How many shortest possible routes are possible to go from one corner of the city to its diagonally opposite corner?

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) ${}^{m+n}C_{m-1}$ (b) ${}^{m+n}C_n$
(c) ${}^{(m+n-2)}C_{(m-1)}$ (d) none of these

50. Priyanka has 11 different toys and Supriya has 8 different toys. Find the number of ways in which they can exchange their toys so that each keeps her initial number of toys.
(a) ${}^{19}C_{11}$ (b) ${}^{18}C_{10}$
(c) ${}^{20}C_{11}$ (d) ${}^{19}C_{11} - 1$

51. The sum of the numbers of the n^{th} term of the series $(1) + (1 + 2) + (1 + 2 + 3) + (1 + 2 + 3 + 4) + \ldots$ $(1 + 2 + 3 + \ldots n)$:
(a) ${}^{n+1}C_3$ (b) ${}^{n+1}C_2$
(c) ${}^{n}C_2$ (d) ${}^{n+2}C_3$

52. Two packs of 52 playing cards are shuffled together. Find the number of ways in which a man can be dealt 26 cards so that he does not get two cards of the same suit and same denomination.
(a) ${}^{52}C_{26} \times 2^{26}$ (b) $\frac{52!}{(2!)^{26}}$
(c) 2^{26} (d) none of these

53. In how many ways we can select four cards of different suits and different values from a deck of 52 cards?
(a) 10! (b) $\frac{13!}{10!}$
(c) $\frac{13!}{9!}$ (d) none of these

54. How many 5 digit numbers can be formed having the digits 0 three times and 3 two times?
(a) 4 (b) 6
(c) 8 (d) 10

55. How many different four digit numbers can be formed with the digits 1, 2, 3, 4, 5, 6, 7, 8 and 9 such that the digit 5 appears exactly once?
(a) 1024 (b) 2048
(c) 4096 (d) none of these

56. How many different four digit numbers can be formed using digits 1, 2, 3, 4, 5, 6, 7, 8, 9 without repetition such that the digit 5 appears exactly once?
(a) 1243 (b) 1234
(c) 1344 (d) 1355

57. How many different eight digit numbers can be formed using only four digits 1, 2, 3, 4 such that the digit 2 occurs twice?
(a) 20412 (b) 12042
(c) 25065 (d) none of these

58. In how many ways can 8 distinct things be divided among three people such that any one can receive any number of things?
(a) 1556 (b) 6561
(c) ${}^{8}C_2$ (d) ${}^{7}C_2$

59. There are 6 numbered chairs placed around a circular table. 3 boys and 3 girls want to sit on them such that neither of two boys nor two girls sit adjacent to each other. How many such arrangements are possible?
(a) 36 (b) 58
(c) 72 (d) none of these

60. In how many ways one black and one white rook can be placed on a chessboard so that they are never in an attacking position?
(a) 1234 (b) 3136
(c) 9516 (d) 1024

61. There are 9 pairs of white shoes and 6 pairs of black shoes contained in a box. We are allowed to draw only one shoe at a time. Minimum how many shoes are required to be drawn out to get one pair of white shoes?
(a) 11 (b) 22
(c) 33 (d) 15

62. In the previous question, minimum how many shoes must be drawn out to get at least 1 pair of either black or white shoes?
(a) 15 (b) 18
(c) 16 (d) 22

63. There are four different coloured balls and 4 boxes of the same colours as that of the balls. Find the number of ways in which exactly one ball can be put in a different colour box that of the ball.
(a) 16 (b) 10
(c) ${}^{4}C_2$ (d) none of these

64. In the previous question (no. 63) find the number of ways in which only two balls can be put in the correct boxes *i.e.*, the colour of box and the colour of contained ball be same.
(a) 3 (b) 6
(c) 9 (d) none of these

65. Find the number of digits required to write down the number of pages in a 300 pages book.
(a) 792 (b) 279
(c) 729 (d) none of these

66. Find the number of numbers that can be formed using all the digits 1, 2, 3, 4, 3, 2, 1 only once so that the odd digits occupy odd places only.
(a) 9 (b) 16
(c) 18 (d) 27

Directions for question numbers 67–74 : There are 5 different boxes and 7 different balls. All the 7 balls are to be distributed in the 5 boxes placed in a row so that any box can receive any number of balls.

67. In how many ways can these balls be distributed into these boxes?
(a) 5^7 (b) 7^5
(c) ${}^{7}C_5$ (d) ${}^{7}P_5$

68. In how many ways can these balls be distributed so that no box is empty?
(a) 7! (b) 16800
(c) 1775 (d) none of these

69. Suppose all the balls are identical, then in how many ways can all these balls be distributed into these boxes?
(a) 110 (b) 220
(c) 330 (d) 440

70. Suppose all the balls and all the boxes are also identical. Then in how many ways can all these balls be distributed into these boxes?
(a) 12 (b) 13
(c) 16 (d) 255

Scanned by CamScanner

yoursmahboob.wordpress.com

71. In the previous question (no. 70) in how many ways can all these balls be distributed into these boxes so that no box remains empty and no two consecutive boxes have the same number of balls?
(a) 1 (b) 4
(c) 12 (d) none of these

72. In how many ways can these balls be distributed so that box 2 and box 4 contain only 1 and 2 balls respectively?
(a) 5522 (b) 8505
(c) 2305 (d) none of these

73. In how many ways can these balls be distributed into these boxes if ball 2 can be put into either box 2 or box 4?
(a) 12360 (b) 31250
(c) 13490 (d) 31526

74. In how many ways can these balls be distributed such that no box is empty and ball 2 and ball 4 cannot be put in the same box?
(a) 1200 (b) 15000
(c) 3800 (d) none of these

Directions for question numbers 75–82 : There are 3 pots and 4 coins. All these coins are to be distributed into these pots where any pot can contain any number of coins.

75. In how many ways these coins can be distributed if all the coins and all the pots are different?
(a) 3^4 (b) 4^3
(c) ${}^3P_4$ (d) ${}^4P_3$

76. In how many ways these coins can be distributed if all the coins and all the pots are identical?
(a) 4 (b) 6
(c) 8 (d) 1

77. In how many ways all these coins can be distributed if all coins are identical but all pots are different?
(a) 15 (b) 16
(c) 17 (d) 81

78. In how many ways all these coins can be distributed if all coins are different but all pots are identical?
(a) 14 (b) 21
(c) 27 (d) none of these

79. In how many ways all these coins can be distributed such that no pot is empty if all coins are different but all pots are identical?
(a) 16 (b) 6
(c) 42 (d) 21

80. In how many ways all these coins can be distributed such that no pot is empty if all coins are identical but all pots are different?
(a) 6 (b) 3
(c) 9 (d) 27

81. In how many ways all these coins can be distributed if all coins are identical and two pots are also identical?
(a) 1 (b) 10
(c) 9 (d) 11

82. In how many ways all these coins can be distributed if out of 4 coins 2 coins are identical and all pots are different?
(a) 45 (b) 27
(c) 54 (d) none of these

Final Round

1. Maximum number of points of intersection of 6 circles, is :
(a) 30 (b) 28
(c) 15 (d) none of these

2. Maximum number of points of intersection of 6 straight lines is :
(a) 30 (b) 15
(c) 28 (d) none of these

3. Maximum number of points into which 3 circles and 3 lines intersect is :
(a) 21 (b) 9
(c) 27 (d) 31

4. Eight identical coins are arranged in a row. The total number of ways in which the number of heads is equal to the number of tails, is :
(a) 35 (b) 15
(c) 140 (d) 70

5. Two straight lines intersect at a point O. Points $A_1, A_2, A_3, A_4, A_5, \ldots, A_m$ are taken on one line and points $B_1, B_2, B_3, \ldots, B_n$ on the other. If the point O is not included, the number of triangles that can be drawn using these points as vertices, is :
(a) ${}^nC_2 + {}^mC_2$ (b) ${}^{2n}C_2$
(c) ${}^{m+n}C_2$ (d) none of these

6. How many different nine digit numbers can be formed from the number 22 33 55 888 by rearranging its digits so that the odd digits occupy even positions?
(a) 60 (b) 75
(c) 88 (d) 77

7. The straight lines l_1, l_2, l_3 are parallel and lie in the same plane. A total number of m points on l_1, n points on l_2, k points on l_3 are used to produce the triangles, the maximum number of triangles formed with vertices at these points are :
(a) ${}^mC_3 \times {}^nC_3 \times {}^kC_3$
(b) ${}^{(m+n+k)}C_3 - ({}^mC_3 + {}^nC_3 + {}^kC_3)$
(c) ${}^{(m+n+k)}C_3$
(d) none of the above

8. Given that n is the odd, the number of ways in which three numbers in AP can be selected from 1, 2, 3, 4, ..., n is :
(a) $\frac{(n-1)^2}{4}$ (b) n^2
(c) n^3 (d) $(n-2)^2$

9. Eight straight lines are drawn in the plane such that no two lines are parallel and no three lines are concurrent. The number of parts into which these lines divide the plane, is :
(a) 73 (b) 37
(c) 17 (d) 72

10. Number of divisors of the form $4n + 2 (n \geq 0)$ of the integer 240 is :
(a) 6 (b) 4
(c) 3 (d) 12

Scanned by CamScanner

yoursmahboob.wordpress.com

11. The number of rectangles excluding squares from a rectangle of size of 12×8 is :
(a) 1234 (b) 625
(c) 2460 (d) 256

12. Two lines intersect at O. Points $A_1, A_2, \ldots, A_n$ are taken on one of them and $B_1, B_2, \ldots, B_n$ on the other the number of triangles that can be drawn with the help of these $(2n + 1)$ points is :
(a) n (b) n^2
(c) n^3 (d) n^4

13. The number of ways in which 9 identical balls can be placed in three identical boxes is :
(a) 12 (b) 6
(c) 9 (d) $\frac{9!}{3!}$

14. The number of ways in which 30 coins of one rupee each be given to six persons so that none of them receives less than 4 rupees is :
(a) 246 (b) 462
(c) $\frac{30!}{6!}$ (d) none of these

15. Find the number of circles that can be drawn out of 10 points, of which 7 points are collinear is :
(a) 35 (b) 85
(c) 70 (d) 124

16. The number of natural numbers of two or more than two digits in which digits from left to right are in increasing order is :
(a) 205 (b) 520
(c) 502 (d) none of these

17. In how many ways a cricketer can make a century with fours and sixes only?
(a) 6 (b) 9
(c) 8 (d) 10

18. The number of permutations of the letters of the word LUMINARY such that neither the pattern LURY nor MINA occurs is :
(a) 46800 (b) 24600
(c) 40086 (d) none of these

19. 10 students are to be seated in two rows equally for the MOCK CAT in a room. There are two sets of papers, code A and code B. Each of the two rows can have only one set of paper but different that from the other row. In how many ways these students can be arranged?
(a) 2775600 (b) 1200560
(c) 125600 (d) 7257600

20. Aman Verma and Mini Mathur jointly host a TV programme in which one day n guests attended the show. There each guest shakes hands with every other guest and each guest has to shake hand with each of the hosts. If there happens to be total 65 shake hands, find the number of guests attended the show.
(a) 13 (b) 14
(c) 10 (d) 9

21. The number of ways in which an examiner can assign 50 marks to 10 questions giving not less than 3 marks to any question is :
(a) $^{29}C_9$ (b) $^{47}C_3$
(c) $^{52}C_2$ (d) $^{40}C_{10}$

22. For $x \in R$, let $[x]$ denote the largest integer less than or equal to x, then the value of :
$$E = \left[\frac{1}{3}\right] + \left[\frac{1}{3} + \frac{1}{100}\right] + \left[\frac{1}{3} + \frac{2}{100}\right] + \ldots + \left[\frac{1}{3} + \frac{99}{100}\right] \text{ is :}$$
(a) 22 (b) 66
(c) 33 (d) none of these

23. The number of positive integers from 1 to 10^6 (both inclusive) which are neither perfect squares, nor cubes, nor perfect fourth powers is :
(a) 918990 (b) 998911
(c) 998910 (d) none of these

24. Kumar's family consists of a grandfather, 'm' sons and daughters and '$2n$' grand children. They are to be seated in a row for dinner. The grandchildren wish to occupy the n seats at each end and the grandfather refuses to have a grandchild on either side of him. In how many ways can the Kumar's family be made to sit?
(a) $(2n!)(m-1)!$ (b) $(2n!)(m!)(m-1)$
(c) $(2m!)(n!)$ (d) none of these

25. Six Ps have to be placed in the squares of the diagram given below such that each column contains at least one P. In how many ways this can be done?

(a) 26 (b) 13
(c) 8 (d) 24

26. A box contains two red, three green and four blue balls. In how many ways can three balls be drawn from the box if atleast one green ball is to be included in the draw?
(a) 23 (b) 64
(c) 46 (d) none of these

27. Ajay has 7 relatives, 3 men and 4 women. His wife Kajol also has 7 relatives, 3 women and 4 men. In how many ways can they invite 3 men and 3 women so that 3 of them are the Ajay's relatives and 3 his wife Kajol's?
(a) 485 (b) 458
(c) 365 (d) none of these

28. Serena and Venus were only two women participiting in a chess tournament. Every participant played two games with every other participant. The number of games that men played between themselves proved to exceed by 66, compared to the number of games the men played with women. How many participants were there?
(a) 156 (b) 610
(c) 13 (d) 108

29. In the previous questions (no. 28) how many games were played?
(a) 208 (b) 156
(c) 316 (d) none of these

30. Six Burfis and six rasgullas are to be distributed among ten girls so that each girl receives at least one piece of sweets out of burfis and rasgullas. Find the number of ways in which the sweets can be distributed.
(a) 26250 (b) 22560
(c) 22330 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

31. Mr. John has x children by his first wife and Ms. Bashu has $x+1$ children by her first husband. They marry and have children of their own. The whole family has 10 children. Assuming that two children of the same parents do not fight, find the maximum number of fights that can take place among children.
(a) 33 (b) 22
(c) 111 (d) none of these

32. Find the number of natural numbers which are smaller than $2 \cdot 10^8$ and are divisible by 3 which can be written by means of the digits 0, 1 and 2.
(a) 7272 (b) 4373
(c) 3437 (d) none of these

33. Find the number of whole numbers formed on the screen of a calculator which can be recognised as numbers with (unique) correct digits when they are read inverted. The greatest number that can be formed on the screen of the calculator is 999999.
(a) 98970 (b) 89912
(c) 110050 (d) 100843

34. Find the number of ways of putting five distinct rings on four fingers of the left hand. (Ignore the difference of size of rings and the fingers)
(a) 1250 (b) 6720
(c) 5260 (d) none of these

35. If n distinct things are arranged in a circle, find the number of ways of selecting three of these things so that no two of them are next to each other.
(a) $n(n-2)(n-3)$ (b) $\frac{1}{6}n(n-4)(n-5)$
(c) $\frac{1}{3}(n^2+3n-5)$ (d) none of these

36. The number of different selections of 5 letters from 1 A, 2 B's, 3 C's, 4 D's and 5 E's is :
(a) 71 (b) 41
(c) 117 (d) none of these

37. In the entrance test of Wharton Business School, the maximum marks for each of three papers is n and that for the fourth paper is $2n$. Find the number of ways in which a candidate can get $3n$ marks.
(a) $\frac{1}{6}(n+1)(n+2)$
(b) $\frac{1}{6}(n+1)(5n^2+10n+6)$
(c) $\frac{1}{2}(n^2+3n-6)$
(d) none of the above

38. An examination consists of 4 papers. Each paper has a maximum of 'n' marks. Find the number of ways in which a students can get $2n$ marks in the examination.
(a) $\frac{1}{3}(n^2-5n+4)$
(b) $\frac{1}{3}(n+1)(2n^2+4n+3)$
(c) $\frac{1}{6}(n+1)(n+4)$
(d) none of the above

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE-19.1

1 (a)	2. (b)	3. (c)	4. (a)	5. (d)	6. (b)	7. (a)	8. (b)	9. (c)	10. (b)
11. (a)	12. (b)	13. (a)	14. (a)	15. (a)	16. (d)	17. (d)	18. (c)	19. (b)	20. (a)
21. (b)	22. (b)	23. (b)	24. (d)	25. (b)	26. (d)	27. (b)	28. (a)	29. (c)	30. (c)
31. (a)	32. (a)	33. (a)	34. (a)	35. (a)	36. (a)	37. (a)	38. (b)	39. (c)	40. (d)
41. (a)	42. (a)	43. (b)	44. (c)	45. (a)	46. (d)	47. (a)			

INTRODUCTORY EXERCISE-19.2

1 (c)	2. (b)	3. (d)	4. (d)	5. (a)	6. (d)	7. (d)	8. (a)	9. (b)	10. (a)
11. (a)	12. (b)	13. (a)	14. (b)	15. (a)	16. (c)	17. (b)	18. (a)	19. (b)	20. (c)
21. (d)	22. (a)	23. (b)							

INTRODUCTORY EXERCISE-19.3

1 (a)	2. (c)	3. (a)	4. (c)	5. (a)	6. (d)	7. (d)	8. (a)	9. (b)	10. (a)
11. (b)									

INTRODUCTORY EXERCISE-19.4

1 (a)	2. (b)	3. (a)	4. (b)	5. (a)	6. (b)	7. (a)	8. (c)	9. (d)	10. (a)
11. (a)									

INTRODUCTORY EXERCISE-19.5

1 (a)	2. (c)	3. (c)	4. (c)	5. (c)	6. (b)	7. (b)	8. (c)	9. (d)	10. (a)
11. (c)	12. (d)	13. (a)	14. (c)	15. (a)	16. (b)	17. (c)	18. (b)	19. (d)	20. (c)
21. (d)	22. (b)	23. (a)	24. (a)	25. (b)	26. (a)	27. (d)	28. (b)	29. (c)	30. (b)
31. (a)	32. (b)	33. (a)	34. (b)	35. (c)	36. (c)	37. (b)	38. (c)	39. (a)	40. (b)
41. (a)	42. (c)	43. (b)	44. (a)	45. (b)	46. (c)	47. (a)	48. (b)	49. (c)	50. (b)
51. (b)	52. (b)	53. (b)	54. (b)	55. (c)	56. (c)	57. (d)	58. (b)	59. (c)	60. (b)
61. (d)	62. (a)	63. (c)	64. (a)	65. (b)	66. (a)	67. (b)	68. (a)	69. (b)	

INTRODUCTORY EXERCISE-19.6

1 (c)	2. (b)	3. (c)	4. (a)	5. (d)	6. (c)				

INTRODUCTORY EXERCISE-19.7

1 (b)	2. (b)	3. (c)	4. (c)	5. (a)	6. (d)	7. (c)	8. (b)	9. (a)	10. (c)
11. (d)	12. (a)								

LEVEL-1

1 (c)	2. (b)	3. (a)	4. (d)	5. (a)	6. (b)	7. (c)	8. (b)	9. (b)	10. (c)
11. (a)	12. (c)	13. (d)	14. (a)	15. (c)	16. (b)	17. (b)	18. (a)	19. (c)	20. (d)
21. (c)	22. (b)	23. (b)	24. (b)	25. (b)	26. (b)	27. (b)	28. (a)	29. (c)	30. (d)
31. (a)	32. (b)	33. (d)	34. (b)	35. (a)	36. (c)	37. (b)	38. (b)	39. (c)	40. (c)
41. (a)	42. (b)	43. (b)	44. (c)	45. (a)	46. (c)	47. (a)	48. (b)	49. (a)	50. (b)
51. (c)	52. (b)	53. (d)	54. (a)	55. (d)	56. (a)	57. (b)	58. (a)	59. (a)	60. (a)
61. (b)	62. (c)	63. (c)							

Scanned by CamScanner

yoursmahboob.wordpress.com

LEVEL-2

1. (b)	2. (d)	3. (a)	4. (a)	5. (b)	6. (c)	7. (c)	8. (d)	9. (a)	10. (b)
11. (a)	12. (c)	13. (b)	14. (c)	15. (a)	16. (a)	17. (d)	18. (b)	19. (c)	20. (a)
21. (b)	22. (a)	23. (c)	24. (b)	25. (c)	26. (a)	27. (a)	28. (c)	29. (d)	30. (d)
31. (c)	32. (b)	33. (a)	34. (d)	35. (c)	36. (b)	37. (a)	38. (c)	39. (c)	40. (b)
41. (a)	42. (c)	43. (c)	44. (a)	45. (d)	46. (d)	47. (a)	48. (d)	49. (c)	50. (d)
51. (b)	52. (a)	53. (c)	54. (a)	55. (b)	56. (c)	57. (a)	58. (b)	59. (c)	60. (b)
61. (b)	62. (c)	63. (d)	64. (b)	65. (a)	66. (c)	67. (a)	68. (b)	69. (c)	70. (b)
71. (a)	72. (b)	73. (b)	74. (b)	75. (a)	76. (a)	77. (a)	78. (a)	79. (b)	80. (b)
81. (c)	82. (c)								

FINAL ROUND

1. (a)	2. (b)	3. (c)	4. (d)	5. (d)	6. (a)	7. (b)	8. (a)	9. (b)	10. (b)
11. (c)	12. (c)	13. (a)	14. (b)	15. (b)	16. (c)	17. (b)	18. (c)	19. (d)	20. (c)
21. (a)	22. (c)	23. (c)	24. (b)	25. (a)	26. (b)	27. (a)	28. (c)	29. (b)	30. (a)
31. (a)	32. (b)	33. (d)	34. (b)	35. (b)	36. (a)	37. (b)	38. (b)		

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 19.1

1. ${}^9P_3 = \frac{9!}{6!}$ $\left(\because {}^nP_r = \frac{n!}{(n-r)!}\right)$

$= \frac{9 \times 8 \times 7 \times 6!}{6!}$

$= 9 \times 8 \times 7 = 504$

2. ${}^nP_5 = 20 \,.\, {}^nP_3$

$\Rightarrow \frac{n!}{(n-5)!} = 20 \,.\, \frac{n!}{(n-3)!}$

$\Rightarrow \frac{(n-3)!}{(n-5)!} = 20$

$\Rightarrow \frac{(n-3)(n-4)(n-5)!}{(n-5)!} = 20$

$\Rightarrow (n-3)(n-4) = 20$

$\Rightarrow n = 8$ ($n = -1$ is inadmissible)

Alternatively : Go through options.

3. $\frac{{}^{56}P_{r+6}}{{}^{54}P_{r+3}} = \frac{30800}{1}$

$\frac{\frac{56!}{(50-r)!}}{\frac{54!}{(51-r)!}} = \frac{30800}{1}$

$\Rightarrow \frac{56 \times 55 \times (51-r)!}{(50-r)!} = \frac{30800}{1}$

$\Rightarrow \frac{(51-r)!}{(50-r)!} = \frac{10}{1}$

$\Rightarrow \frac{(51-r) \times (50-r)!}{(50-r)!} = \frac{10}{1}$

$\Rightarrow 51 - r = 10$

$\Rightarrow r = 41$

Alternatively : Go through options

4. Since there are 6 digits available and out of 6 digits we have to take only 3 digits for the arrangement. Therefore, required number of 3 digits numbers $= {}^6P_3 = \frac{6!}{3!} = 120$

Alternatively : $\boxed{6}\boxed{5}\boxed{4} \Rightarrow 6 \times 5 \times 4 = 120$

We have 6 digits to fill up hundreds place and only 5 digits for tens place and only 4 digits for unit place since repetition is not allowed.

5. **Case 1.** There is only one even number of one digit.

Case 2. $\boxed{4}\boxed{1} = 4 \times 1 = 4$

There are only 4 even numbers of two digit
(Numbers are 38, 58, 78 and 98)

Case 3. $\boxed{4}\boxed{3}\boxed{1} \Rightarrow 4 \times 3 \times 1 = 12$

There are only 12 even numbers of 3 digit.

Case 4. $\boxed{4}\boxed{3}\boxed{2}\boxed{1} \Rightarrow 4 \times 3 \times 2 \times 1 = 24$

There are 24 even numbers of 4 digits
Thus there are total $1 + 4 + 12 + 24 = 41$ even numbers.

NOTE In each case 8 is fixed at unit place, since if the unit digit is an even digit then the whole number is an even number.

6. $\boxed{3}\boxed{4}\boxed{3}\boxed{2} \Rightarrow 3 \times 4 \times 3 \times 2 = 72$

Thousands place can assume only 3 values *viz.*, 5, 7, 8. Since required numbers are greater than 4000.

$\boxed{4}\boxed{4}\boxed{3}\boxed{2}\boxed{1} \Rightarrow 4 \times 4 \times 3 \times 2 \times 1 = 96$

Ten thousands place can assume all the remaining non-zero digits and thousands place can assume zero also except the digit which has been filled up at thousands place.
Therefore total required numbers
= number of 4 digit numbers + number of 5 digit numbers
$= 72 + 96 = 168$

7. $\boxed{4}\boxed{4}\boxed{3}\boxed{2} \Rightarrow 4 \times 4 \times 3 \times 2 = 96$

Thousands place can not assume 3 since required numbers are greater than 5000.

$\boxed{5}\boxed{4}\boxed{3}\boxed{2}\boxed{1} \Rightarrow 5 \times 4 \times 3 \times 2 \times 1 = 120$

Total required numbers $= 96 + 120 = 216$

8. $\boxed{8}\boxed{7}\boxed{6}\boxed{5} \Rightarrow 8 \times 7 \times 6 \times 5 = 1680$

3 and 5 have been already used, so we have 8 digits for thousands place, then 7 digits for hundreds place, 6 digits for tens digit and remaining 5 digits for unit place.

Alternatively : ${}^8P_4 = \frac{8!}{4!} = \frac{8 \times 7 \times 6 \times 5 \times 4!}{4!}$

$= 8 \times 7 \times 6 \times 5 = 1680$

9. A number is divisible by 5 only if its unit digit is either 5 or 0. So we fix 5 as unit digit and then we fill up the remaining places.

$\boxed{5}\boxed{4}\boxed{3}\boxed{2}\boxed{1} \Rightarrow 5 \times 4 \times 3 \times 2 \times 1 \times 1 = 120$

Hence required number = 120

10. $\boxed{4}\boxed{3}\boxed{2}\boxed{1} \Rightarrow 4 \times 3 \times 2 \times 1 = 24$

There are total 24 numbers of 4 digit.
Since we have only 4 digits it means we use each of the digit $6\left(=\frac{24}{4}\right)$ times in each of the unit, tens hundreds and thousands place.

Scanned by CamScanner

yoursmahboob.wordpress.com

Therefore the sum of the digits in the units place
$= 6(1 + 2 + 5 + 6) = 84$
Similarly, the sum of the digits in each of tens, hundreds, and thousands places = 84
Hence the required sum of all the numbers
$= 84 \times 1 + 84 \times 10 + 84 \times 100 + 84 \times 1000$
$= 84(1 + 10 + 100 + 1000)$
$= 84 \times 1111 = 93324$

11. **Case 1.** | 3 | 3 | 1 | $\Rightarrow 3 \times 3 \times 1 = 9$

When 2 is fixed at unit place we have 3, 4 and 5 *i.e.*, 3 digits for hundreds place and remaining 3 digits (out of 5) for the tens place.

| 2 | 3 | 1 | $\Rightarrow 2 \times 3 \times 1 = 6$

When 4 is fixed at unit place, we have 3 and 5 *i.e.*, only two digits for hundreds place and remaining 3 digits for tens place.

Case 2. | 4 | 3 | 2 | 2 | $= 48$

4 digit numbers = 48

Case 3. | 4 | 3 | 2 | 1 | 2 | $= 48$

5 digit numbers = 48
Thus there are total $15 + 48 + 48 = 111$ even numbers greater than 300.

12. | 4 | 4 | 3 | $= 48$

Hundred's place can not assume 0.

13. There are 7 letters in the word RAINBOW and each letter is used only once. So all the 7 letters can be arranged in 7 !ways.
$7! = 7 \times 6 \times 5 \times 4 \times 3 \times 2 \times 1 = 5040.$

14. If we fix *R* as the initial letter, then we have to arrange only 6 remaining letters.
Hence required number of permutations = 6!
$= 6 \times 5 \times 4 \times 3 \times 2 \times 1 = 720$

15. If we fix *R* and *W* as the first and last letters then we have to arrange only 5 remaining letters which can be arranged in $5! = 120$ ways.

16. When *R* and *W* are the first and last letters of all the words then we can arrange them in 5!ways. Similarly when *W* and *R* are the first and last letters of the words then the remaining letters can be arrange in 5!ways.
Thus the total number of permutations = $2 \times 5!$
$= 2 \times 120 = 240$

Alternatively : Except to *R* and *W* all the remaining 5 letters can be arranged in 5! ways and *R* and *W* can be arranged in 2! ways at the end positions.
Thus total number of permutations = $2! \times 5! = 2 \times 120 = 240$

17. Assume *N* and *B* as a single letter, then we have only 6 letters for the arrangement
i.e., *A, I, R, O, W, BN*
which can be arranged in 6! ways.
Now *B* and *N* can also be mutually arranged in 2! ways
Therefore total number of arrangements = $2! \times 6!$
$= 2 \times 720 = 1440$

18. Number of permutations when *I* and *O* are together
$= 2! \times 6! = 1440$
(Very similar to the previous question)
Total number of permutations = $7! = 5040$
∴Number of permutations when *I* and *O* are not together
$= 5040 - 1440 = 3600$

19. There are three vowels *viz.*,A, *I* and *O*
First of all arrange all the four consonants which can be done in 4! ways.
Now we have 5 places available for the three vowels to be filled up, which can be done in ${}^5P_3$ ways.
Thus the total number of arrangements = $4! \times {}^5P_3 = 24 \times \frac{5!}{2!}$
$= 24 \times 60 = 1440$

20. First of all we arrange all the 4 consonants in 4! ways.
Now we have 5 places for the 3 vowels as
1. C_1 2. C_2 3. C_3 4. C_4 5.
1. When all the three vowels *AIO* are together then 5 places can be filled in 5 ways.
2. When *A* and *I* are together and *O* is separated from "*AI*" then the 5 places can be filled up in 10 ways.
3. When *I* and *O* are together and *A* is separated from "IO" then the 5 places can be filled up in 10 ways.
4. When *A*, *I* and *O* are separated from each other then the 5 places can be filled up in 10 ways.

Thus there are total $5 + 10 + 10 + 10 = 35$ ways in which 5 places can be filled up such that *A* is before *I* and *I* is before O.
Hence total number of ways in which all the 7 letters of RAINBOW can be arranged in which *A* is before *I* and *I* is before $O = 4! \times 35 = 24 \times 35 = 840$.

Alternatively : All the 7 letters of the word RAINBOW can be arranged in 7! ways.
and 3 particular letters (A,I,O) can be arranged in 3! ways.
But the given condition is satisfied by only 1 out of 6 ways.
Hence required number of arrangements
$= \frac{7!}{3!} = 7 \times 6 \times 5 \times 4 = 840$

21. Let all the vowels be in a single packet and all the consonants be in the other packet.
Now all the vowels can be arranged in 3! ways and all the consonants can be arranged in 4! ways.
Hence total number of arrangements = $3! \times 4! = 6 \times 24 = 144$

22. The first and last letters can be arranged in ${}^3P_2$ ways and the remaining letters can be arranged in 5! ways.
Hence required number of permutations
$= {}^3P_2 \times 5! = 6 \times 120 = 720$

23. The correct order of the letters is as follows :
A, B, I, N, O, R, W
Number of words begin with *A* = 6!
Number of words begin with *B* = 6!
Number of words begin with *I* = 6!
Number of words begin with *N* = 6!
Number of words begin with *O* = 6!
Number of words begin with *RAB* = 4!
Number of words begin with *RAIB* = 3!

Scanned by CamScanner

yoursmanboob.wordpress.com

Now the next word is RAINBOW (it is the first word which begins with RAIN)
So the ranking of the word RAINBOW
$= 5 \times 6! + 4! + 3! + 1 = 3631$

24. First arrange the 3 vowels which can be done in 3! ways.
Now there are 4 places created by the 3 vowels which can be filled up by 4 consonants in ${}^4P_4$ ways.
Therefore total number of required permutations
$= 3! \times {}^4P_4 = 6 \times 24 = 144$

25. 1 2 3 4 5 6 7
In order that vowels may occupy even places arrange all the 3 vowels, then arrange all the four consonants in four places.
Thus the required number of arrangements $= 3! \times 4! = 144$

26. 1 2 3 4 5 6 7
First of all arrange any 3 consonants at even places in ${}^4P_3$ ways. Now the newly created four odd places can be filled by the remaining letters which includes 3 vowels and 1 consonants, which can be done in ${}^4P_4$ ways. Hence the required number of permutation
$= {}^4P_3 \times {}^4P_4 = 24 \times 24 = 576$

27. $\frac{}{1}\ \frac{2}{}\ \frac{}{3}\ \frac{4}{}\ \frac{}{5}\ \frac{6}{}$
First of all arrange 3 vowels at 3 even places, which can be done 3! ways. Again arrange the 3 consonants at 3 odd places which can be done in 3! ways.
Hence required number of permutations $= 3! \times 3! = 36$ ways

Alternatively :

3	3	2	2	1	1	= 36 ways

Assume vowels are even numbers say 2, 4, 6 and consonants are odd numbers say 1, 3, 5.
Now, if we have to form the numbers in which odd integers always occupy odd places then this can be done as above. (*O, E, O, E, O, E*)

28. First of all arrange all the four consonants *R, N, B, W* in 4! ways.
Then there are 5 places to be filled up by the vowels. But any two vowels are always together then we assume that there are only two vowels which can be filled in 5 places in ${}^5P_2$ ways. But we have to take any two vowels together out of 3 vowels then this can be done in ${}^3P_2$ ways.
Hence the total number of permutation $= {}^5P_2 \times {}^3P_2 \times 4!$
$= 20 \times 6 \times 24$
$= 2880$

Alternatively : Since there can be only 3 cases
(i) When *A, I* and *O* are separate from each other
(ii) When *A, I* and *O* can always together
(iii) When any two vowels out of three vowels *A, I* and *O* are together.
Now we need to calculate the value of Case (iii).
∴Required number of permutations
= Total number of permutations – [Case (i) + Case (ii)]
∴ $7! - (1440 + 720) = 5040 - (2160)$
$= 2880$

29. At least two consonants remain together means
(i) Any two consonants are together
(ii) All the three consonants are together
which implies that all of the consonants are not separated from each other.
Hence required number of permutations
= (Total number of permutations
– number of permutations when all of the vowels are separated from each other)
$= 6! - (3! \times {}^4P_3) = 720 - 144 = 576$

30. There are 5 consonants and 2 vowels in the word STRANGE out of 7 places for the 7 letters, 4 places are odd and 3 places are even.
2 vowels can be arranged in 4 odd places in ${}^4P_2$ ways and then 5 consonants can be arranged in the remaining 5 places in ${}^5P_5$ ways.
Hence, the required number of ways $= {}^4P_2 \times {}^5P_5 = 1440$

31. Since no two men or two women sit together it means they sit on the alternate positions.
Therefore first of all we arrange 3 women in 3! ways then we arrange 4 men in newly created 4 places in ${}^4P_4$ ways.
Thus the total number of arrangements $= 3! \times {}^4P_4$
$= 6 \times 24 = 144$

32. There are total 9 places out of which 4 are even and rest 5 places are odd.
4 women can be arranged at 4 even places in 4! ways.
and 5 men can be placed in remaining 5 places in ${}^5P_5$ ways.
Hence, the required number of permutations
$= 4! \times {}^5P_5 = 24 \times 120 = 2880$

33. First of all the 6 students can be arranged in 6! ways then 4 teachers can be arranged in 7 places in ${}^7P_4$ ways.
Hence, the required number of arrangements $= 6! \times {}^7P_4$
$= 720 \times 840 = 604800$

34. First of all we arrange 5 girls in 5! ways, then we arrange 3 boys in the remaining 6 places in ${}^6P_3$ ways.
Hence, the required number of permutations $= 5! \times {}^6P_3$
$= 120 \times 120 = 14400$

35. Total number of arrangements $= 8! = 40320$
Number of arrangements when best and worst papers are together $= 7! \times 2! = 10080$
∴ Number of arrangements in which best and worst papers are not together $= 40320 - 10080 = 30240$

36. All the 6 books on Physics can be mutually arranged in 6! ways.
Similarly 3 books on Chemistry and 4 books on Biology can be arranged in 3! and 4! ways respectively.
Besides it the three sets of Physics, Chemistry and Biology also can be arranged in 3! ways
∴ Required number of permutations $= 3! \times 6! \times 3! \times 4!$
$= 622080$

37. Since we can not wear more than one ring in any finger means repetition is not allowed.

Scanned by CamScanner

yoursmahboob.wordpress.com

Hence, the first ring can be worn in any of the available 4 fingers in 4 ways and second ring can be worn in any of the remaining 3 fingers in 3 ways and third ring can be worn in any of the remaining 2 fingers in 2 ways.
So the required number of ways in which all the 3 rings can be worn in 4 fingers = $4 \times 3 \times 2 = 24$.
Alternatively : We have 4 places to be filled up by 3 different things (i.e., rings), which can be done in ${}^4P_3$ ways.
${}^4P_3 = 24$

38. The signals can be made by using at a time one or two or three or four or five or six flags out of 6 different coloured flags.
∴ Required number of flags
$= {}^6P_1 + {}^6P_2 + {}^6P_3 + {}^6P_4 + {}^6P_5 + {}^6P_6$
$= 6 + 30 + 120 + 360 + 720 + 720 = 1956$

39. The required number of permutation $= 3 \times 4 \times 6 = 72$

40. Required number of permutations $= {}^7P_4 \times {}^6P_4 \times {}^8P_4$
$= 840 \times 360 \times 1680$
$= 508032000$

41. 7 soldiers can be stand in a queue in 7! ways
∴ $7! = 5040$

42. Any 5 soldiers can stand in one row and the remaining 5 soldiers can stand in other row.
∴ Required number of arrangements
$= {}^{10}P_5 \times {}^5P_5 \times 2! = 7257600$

43. Required number of signals $= {}^5P_3 = 60$

44. Required number of permutations $= {}^{10}P_3 = 720$
Alternatively : First prize can be given to any of the 10 students and second prize can be given to any one of the remaining 9 students and the third prize can be given to any one of the remaining 8 students.
Therefore it can be done in
${}^{10}P_1 \times {}^9P_1 \times {}^8P_1 = 10 \times 9 \times 8 = 720$ ways.

45. A passanger from any station may purchase ticket for anyone of the other 9 stations. Therefore, there must be 9 tickets in each station.
Therefore total number of different tickets $= 9 \times 10 = 90$

46. Required number of ways $= 12! - 11! \times 2!$
$= 11!(12 - 2)$
$= 10 \times 11!$
$= 399168000$

47. Total number of permutations $= 12!$
Number of permutations when three particulars books are together $= 10! \times 3!$
∴ Number of permutations when three particular books are not together $= 12! - 10! \times 3!$
$= 10!(12 \times 11 - 6)$
$= 10! \times 126 = 457228800$

INTRODUCTORY EXERCISE 9.2

1. In the given word there are 6 letters of which E occurs 2 times.
Hence the required number of ways $= \frac{6!}{2!}$
$= \frac{6 \times 5 \times 4 \times 3 \times 2 \times 1}{2} = 360$

2. There are total 7 letters of which A occurs 3 times and N occurs 2 times.
Hence, the required number of ways $= \frac{7!}{3!.\,2!} = 420$

3. There are total 10 letters of which R occurs 2 times, E occurs 3 times.
Hence the required number of ways $= \frac{10!}{2!.\,3!} = 302400$

4. Required number of permutations $= \frac{13!}{3!.\,4!.\,2!.\,2!}$
$= 10810800$

5. There are 6 different letters in the word which are A, S, I, N, T, O.
The number of arrangements of 6 different letters taken 4 at a time
$= {}^6P_4 = 360$

6. There are total 9 letters in the word COMMITTEE in which there are $2M$'s, $2T$'s, $2E$'s.
∴ The number of ways in which 9 letters can be arranged
$= \frac{9!}{2! \times 2! \times 2!} = 45360$
There are 4 vowels O, I, E, E in the given word. If the four vowels always come together, taking them as one letter we have to arrange $5 + 1 = 6$ letters which include 2Ms and 2Ts and this be done in $\frac{6!}{2! \times 2!} = 180$ ways.
In which of 180 ways, the 4 vowels O, I, E, E remaining together can be arranged in $\frac{4!}{2!} = 12$ ways.
∴ The number of ways in which the four vowels always come together $= 180 \times 12 = 2160$.
Hence, the required number of ways in which the four vowels do not come together $= 45360 - 2160 = 43200$

7. $\frac{14!}{4! \times 2! \times 2! \times 2! \times 2!} = 113513400$

8. When L and T are fixed as first and last letters of the word, then we have only 6 letters to be arranged.
Hence required number of permutations
$= \frac{6!}{2! \times 2! \times 2!} = 90$

9. $\underbrace{M, M, T, T, H, C, S}_{7}\ \underbrace{A, A, E, I}_{4}$
When all the vowels are together then $n = 7 + 1 = 8$
∴ Required number of permutations $= \frac{8! \times 4!}{2! \times 2! \times 2!} = 120960$

Scanned by CamScanner

yoursmahboob.wordpress.com

HINT (*M*, *T* and *A* occur 2 times and *A A E I* can be arranged mutually in $\frac{4!}{2!}$ ways)

10. *I,M,P,O,R,T,A,N,T*

Total number of permutations $= \frac{9!}{2!} = 181440$

Number of permutations when 2*T*'s are together

$$= \frac{8! \times 2!}{2!} = 8! = 40320$$

∴Number of permutations when 2*T*'s are not together

$$= 181440 - 40320 = 141120$$

11. *T,T,T, N,N,N, G,G,G, R, I,I,I*

There are total 13 leters of which 3 are *T*'s, 3 are *N*'s, 3 are *G*'s, 3 are *I*'s.

Also there are 6 even places and 7 odd places. 3*I*s (i.e., vowels) can be arranged in the 6 even places in $\frac{^6P_3}{3!} = 20$ ways.

Now, we are left with 10 places in which 10 letters can be filled up in $\frac{10!}{3! \times 3! \times 3!} = 16800$

∴The total number of permutations in which vowels occupy even places $= 20 \times 16800 = 336000$

12. Correct order of the letters in *D, G, I, I, O, O, P, R, S, U*

Word begin with	Number of words
D	$\frac{9!}{2!2!}$
G	$\frac{9!}{2!2!}$
I	$\frac{9!}{2!}$
O	$\frac{9!}{2!}$
PD	$\frac{8!}{2!2!}$
PG	$\frac{8!}{2!2!}$
PI	$\frac{8!}{2!}$
PO	$\frac{8!}{2!}$
PRD	$\frac{7!}{2!2!}$
PRG	$\frac{7!}{2!2!}$
PRI	$\frac{7!}{2!}$
PRODG	$\frac{5!}{2!}$

Now the next two words are

PRODIGIOSU and PRODIGIOUS

Hence the rank of the word PRODIGIOUS

$$= 2\left(\frac{9!}{2!2!}\right) + 2\left(\frac{9!}{2!}\right) + 2\left(\frac{8!}{2!2!}\right) + 2\left(\frac{8!}{2!}\right) + 2\left(\frac{7!}{2!2!}\right) + \frac{7!}{2!} + \frac{5!}{2!} + 2$$

$$= 3\left(\frac{9!}{2!}\right) + 3\left(\frac{8!}{2!}\right) + 7! + \frac{5!}{2!} + 2$$

$$= 544320 + 60480 + 5040 + 60 + 2$$

$$= 609902$$

13. The correct order of letters is D, E, E, E, E, Q, R, S, S, T, U.

Number of words begin with DEEEEQR $= \frac{4!}{2!} = 12$

Number of words begin with DEEEEQS $= 4! = 24$

Number of words begin with DEEEEQT $= \frac{4!}{2!} = 12$

Now, the next two words are

DEEEEQURSST and DEEEEQURSTS

Hence the 50th word is DEEEEQURSTS

14. There are 7 digits 1, 2, 0, 2, 4, 2, 4 in which 2 occurs 3 times, 4 occurs 2 times.

∴ Number of 7 digit numbers $= \frac{7!}{3! \times 2!} = 420$

But out of these 420 numbers there are some numbers which begin with '0' and they are not 7-digit numbers. The number of such numbers beginning with '0'.

$$= \frac{6!}{3! \times 2!} = 60$$

Hence the required number of 7 digits numbers

$$= 420 - 60 = 360$$

Alternatively :

6	6	5	4	3	2	1

$\Rightarrow 6.(6!)$

Since the left most place can assume only non-zero digit hence it can consider only 6 digits. Now the remaining 6 places can be filled up in normal ways.

But since 2 occurs 3 times, 4 occurs 2 times, therefore required number of 7 digit numbers $= \frac{6.(6!)}{3!.2!} = 360$

15. Required number of 6 digit numbers $= \frac{6!}{4!.2!} = 15$

16.

5	4	3	2	1	3

$\Rightarrow 3.(5!)$

Unit place can assume any of the three even digits *viz.*,2 ,4 ,6 and rest of the places can be filled up in 5! ways.

But since digit 7 occurs 2 times.

∴ Required number of numbers $= \frac{3.(5!)}{2!} = 180$

17.

6	6	5	4	3	2	1

Since left most place can assume only non-zero digit and rest can assume all the given digits.

Therefore the number of numbers $= 6.(6!)$

But since 5 occurs 2 times and 2 occurs 2 times

Hence the required number of numbers $= \frac{6(6!)}{2!.2!} = 1080$

18. *REGUITA*

REG T

There are total 11 letters, but since 2*T*'s are together.

Therefore number of numbers when 2*T*'s are together

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{10!}{2! \times 2! \times 2!} \times \frac{2!}{2!} = 453600$$

$\uparrow R \quad \uparrow E \quad \uparrow G \quad \uparrow T$

Here R is 2 times, E is 2 times, G is 2 times and T is 2 times.

19. $SUMPTO$

SU

Number of ways in which 2U's are always together is

$$\frac{7!}{2!} \times \frac{2!}{2!} = 2520$$

Total number of permutations $= \frac{8!}{2!.\,2!} = 10080$

$\therefore$ Number of ways in which 2U's are not together

$= 10080 - 2520 = 7560$

20. $AFLTON$

$A \quad O$

There are 4 consonants F, L, T and N and 4 vowels A, A, O, O

4 vowels can be arranged in $\frac{4!}{2!.\,2!} = 6$ ways.

Now the 4 consonants can be arranged in 4 places in 4! = 24 ways.

Therefore required number of permutations

$= (6 \times 24) \times 2! = 288$

HINT There are two cases :
(i) $OCOCOCOC$ (ii) $COCOCOCO$
where $O \rightarrow$ vowel, $C \rightarrow$ consonant)

21. $SOTHAYER$

SO

Since two S's and two O's together therefore we can consider there are only 8 letters, which can be permuted in $\frac{8! \times 2! \times 2!}{2! \times 2!} = 8! = 40320$ ways

22. Total number of books $= 3 \times 4 = 12$ in which each of 4 different books is repeated 3 times.

Hence the required number of permutations

$$= \frac{12!}{3! \times 3! \times 3! \times 3!} = \frac{12!}{(3!)^4} = 369600$$

23. There are total $3 + 4 + 5 = 12$ marbles of which 3 are red (alike), 4 are green (alike) and 3 are pink (alike).

$\therefore$ The required number of arrangements $= \frac{12!}{3! \times 4! \times 5!}$

$= 27720$

INTRODUCTORY EXERCISE 19.3

1. Ten thousands place can assume only non-zero digits hence ten thousands place can be filled up in 4 ways and thousands place can be filled up in 5 ways since repetition is allowed (and 0 can be filled up in this place). Similarly hundreds, tens and unit places can be filled up in 5 ways each.

$\therefore$ The required number of numbers $= 4 \times 5 \times 5 \times 5 \times 5 = 2500$

2. The numbers lying between 9 and 1000 consist of 2 or 3 digits in which repetitions are allowed.

Case 1. (For two digit numbers)

As the tens place can be filled by only non-zero digits and unit digit can be filled up in 6 ways.

$\therefore$ The number of 2 digit numbers $= 5 \times 6 = 30$

Case 2. (For three digit numbers)

Hundreds place can be filled up by only non-zero digits hence it can be done in 5 ways and the rest of the places *i.e.*, tens and unit places can be filled up in 6 ways each.

$\therefore$ The number of 3 digit numbers $= 5 \times 6 \times 6 = 180$

$\therefore$ Total number of numbers $= 30 + 180 = 210$

3. Since even digit may not occupy an even place therefore even places can be filled up in only 3 ways (with odd digits) and rest of the 3 odd places can be filled up in 5 ways with all the 5 digits.

Therefore the required number of numbers

$= \boxed{5}\boxed{3}\boxed{5}\boxed{3}\boxed{5}$

$= 5 \times 3 \times 5 \times 3 \times 5 = 1125$

4. Number of numbers of 4 digit in which repetition allowed $= 9 \times 10 \times 10 \times 10 = 9000$

Number of numbers of 4 digit in which repetitions is not allowed $= 9 \times 9 \times 8 \times 7 = 4536$

Hence the required number of numbers of 4 digit

$= 9000 - 4536 = 4464$

5. Total number of 3 digit numbers $= 9 \times 10 \times 10 = 900$

Number of 3 digit numbers in which none of the digits is 9

$= 8 \times 9 \times 9 = 648$

$\therefore$ Number of 3 digit numbers in which there is atleast one digit is $9 = 900 - 648 = 252$

6. Total one digit numbers = 4

Total 2 digit numbers $= 4 \times 4 = 16$

Total 3 digit numbers $= 4 \times 4 \times 4 = 64$

Number of 4 digit numbers beginning with $1 = 4 \times 4 \times 4 = 64$

Number of 4 digit numbers beginning with $2 = 4 \times 4 \times 4 = 64$

Number of 4 digit numbers beginning with $3 = 4 \times 4 \times 4 = 64$

Number of 4 digit numbers beginning with $41 = 4 \times 4 = 16$

Number of 4 digit numbers beginning with $42 = 4 \times 4 = 16$

Number of 4 digit numbers beginning with 431 = 4

Number of 4 digit numbers beginning with 432 = 1

Total number of 4 digit numbers

$= 64 + 64 + 64 + 16 + 16 + 4 + 1 = 229$

Hence the total number of natural numbers not exceeding 4321 is $4 + 16 + 64 + 229 = 313$

7. First ring can be worn in any of the 3 fingers similarly second, third and fourth ring can be worn in any of the three fingers.

$\therefore$ 4 rings can be worn in $3 \times 3 \times 3 \times 3 = 81$ ways,

8. First prize can be given away to 4 boys in 4 ways.

Similarly second, third, fourth and fifth prizes can also be given away to four boys in 4 ways.

Hence the required number of way in which all the 5 prizes can be given away to 4 boys

$= 4 \times 4 \times 4 \times 4 \times 4 = 1024$

Scanned by CamScanner

yoursmahboob.wordpress.com

9. The first ball can be placed in any one of the n cells in n ways.
The second ball can also be placed in any one of the n cells in n ways.
∴ The first and second balls can be placed in n cells in $n \times n$ i.e., n^2 ways.
Similarly each of the rest balls can be placed in n ways.
Hence the required number of ways $= n \times n \times \ldots \times n$ times
$= n^n$

10. Since each cell is to be occupied, 1 ball is to be placed in one cell. First ball can be placed in any one of the n cells in n ways, 2^{nd} ball can be placed in any one of the remaining $(n-1)$ cells in $(n-1)$ ways, similarly 3^{rd}, 4^{th}... ball can be arranged in $(n-2), (n-3)\ldots$ ways.
Hence the required number of ways
$= n(n-1)(n-2)\ldots 2.1 = n!$

11. First letter can be posted in 4 letter boxes in 4 ways.
Similarly second letter can be posted in 4 letter boxes in 4 ways and so on.
Hence all the 5 letters can be posted in
$= 4 \times 4 \times 4 \times 4 \times 4 = 1024$

INTRODUCTORY EXERCISE 19.4

1. Required number of permutations $= 5! = 120$

2. Assume there are only 5 boys since two boys always remain together and these two boys can be arranged mutually in 2 ways.
∴ Required number of permutations $= 4! \times 2 = 48$

3. Required number of permutations $= \frac{1}{2} \times 5! = 60$
(Since there is no difference in clockwise and anticlockwise arrangements)

4. Total number of arrangements $= 6! = 720$
Number of arrangements in which two ladies are together $= 2 \times 5! = 240$
∴ Number of arrangements in which two ladies are never together $= 720 - 240 = 480$
Alternatively : First of all place the five men in 4! ways, then place the two ladies in any 5 spaces in ${}^5P_2$ ways.
Hence, the required number of ways $= 4! \times {}^5P_2 = 480$

5. Assuming Sahara, Ambani and Mahindra as a single personality, then there are total $(10-3)+1 = 8$ person, which can be arranged in 7! ways.
Also Sahara and Mahindra can be mutually permuted in 2 ways.
Therefore required number of arrangements $= 2 \times 7!$
$= 10080$

6. A person can be chosen out of 18 people in 18 ways to be seated between Musharraf and Manmohan. Now consider Musharraf, Manmohan and the third person, sitting between them, as a single personality, we can arrange them in 17! ways but Musharraf and Manmohan can also be arranged in 2 ways.
∴ Required number of permutations $= 18 \times (17!) \times 2$
$= 2 \times 18!$

7. 6 Men can be arranged in 5! ways then 6 women can be arranged in 6 places in 6! ways.
Hence the required number of ways $= 5! \times 6!$
$= 120 \times 720 = 86400$

8. First of all 4 girls can be arranged in 3! ways then 3 boys can be seated in 4 places in ${}^4P_3$ ways.
∴ Required number of arrangements $= 3! \times {}^4P_3$
$= 6 \times 24 = 144$

9. Clearly 7 sisters can sit around a table in 6! ways. But in clockwise and anticlockwise arrangements each of the ladies have the same neighbours.
So, the required number of ways $= \frac{1}{2} \times (6!) = 360$
Hence they dine together only 360 days.

10. Since 3 particulars flowers are together
Hence there can be total $(10-3)+1 = 8$ flowers. These 8 flowers can be arranged 7! ways but the 3 flowers which are together can be arranged mutually in 3! ways.
Hence, the required number of ways $= 3! \times 7!$
$= 6 \times 5040$
$= 30240$

11. Sonu can have only male singer as his neighbours which can be mutually arranged in 2! ways.
Similarly Alka can have only female singers as her neighbours which can be arranged in 2! ways.
Hence the required number of arrangements $= 2! \times 2! = 4$

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 19.5

1. $^8C_3 = \frac{8!}{3!5!} = \frac{8\times7\times6}{6} = 56$

2. $^{10}C_5 = \frac{10\times9\times8\times7\times6\times5!}{5\times4\times3\times2\times1\times(5!)} = 252$

3. $\because {}^{13}C_x = {}^{13}C_y$

$\Rightarrow$ either $x = y$ or $x + y = 13$

But since $x \neq y$, therefore $x + y = 13$

4. Since $^{17}C_r = {}^{17}C_{r+3}$

$\Rightarrow$ either $r = r + 3$ or $r + r + 3 = 17$

But since $r \neq r + 3$

$\therefore$ $r + r + 3 = 17 \Rightarrow r = 7$

5. $^7P_3 = n\,{}^7C_3$

$\Rightarrow$ $5\times6\times7 = n\times5\times7$

$\Rightarrow$ $n = 6$

Alternatively : $^nP_r = r!\,(^nC_r)$

$\Rightarrow$ $r! = 3! = 6 = n$

6. $^{2n}C_3 : {}^nC_2 = 12:1$

$\Rightarrow$ $\frac{2n(2n-1)(2n-2)}{3\times2\times1} : \frac{n(n-1)}{2\times1} = 12:1$

$\Rightarrow$ $(2n-1) = 9 \Rightarrow n = 5$

Alternatively : Go through options.

7. Go through options : The least possible value of n is 8. To verify the result put the vlaue of n as given in the choices.

Let us consider choice (a) *i.e.*, $n = 6$, then

$$^5C_3 + {}^5C_4 > {}^6C_3$$

$10 + 5 > 20$, which is wrong.

Again consider choice (c) *i.e.*, $n = 7$, then

$$^6C_3 + {}^6C_4 > {}^7C_3$$

$20 + 15 > 35$, which is also wrong.

Now consider choice (b) *i.e.*, $n = 8$, then

$$^7C_3 + {}^7C_4 > {}^8C_3$$

$35 + 35 > 56$, which is correct.

Hence the least possible value of $n = 8$.

Now you need not to check the option (d).

8. $\frac{^nP_x}{^nC_x} = \frac{\frac{(n!)}{(n-x)!}}{\frac{(n!)}{(x!)(n-x)!}} = \frac{336}{56}$

$\Rightarrow$ $\frac{^nP_x}{^nC_x} = x! = 6$

$\Rightarrow$ $x! = 3! \Rightarrow x = 3$

Now since $^nP_3 = 336$

$\Rightarrow$ $n(n-1)(n-2) = 8\times7\times6$

$\Rightarrow$ $n = 8$

Alternatively : Go though options.

9. If n is odd, the greatest value of $^nC_r = {}^nC_m$

where $m = \frac{(n-1)}{2}$ or $m = \frac{(n+1)}{2}$

$\therefore$ $x = \frac{(11-1)}{2} = 5$ or $x = \frac{(11+1)}{2} = 6$

Hence (d) is the correct choice.

10. If n is even, the greatest value of $^nC_r = {}^nC_m$

where $m = \frac{n}{2}$

$x = \frac{12}{2} = 6$

11. $^{14}C_x$ is maximum when $x = \frac{14}{2} = 7$

Alternatively : Go through options.

12. Since there are total 10 persons and out of these 10 persons we have to select any 5 persons which can be done in $^{10}C_5$ ways.

$\therefore$ $^{10}C_5 = \frac{10!}{5!\times5!} = 252$

13. Out of 10 questions, 6 questions can be selected in $^{10}C_6$ ways

$\therefore$ $^{10}C_6 = 210$

14. Since question number 1 is compulsory so we have to choose only 5 questions from rest of the 9 questions, which can be done in $^9C_5$ ways

$\therefore$ $^9C_5 = 126$

15. She may invite one or more friends by selecting either 1 or 2 or 3 or 4 or 5 friends out of 5 friends.

$\therefore$ 1 friend can be selected out of 5 in $^5C_1$ ways

2 friends can be selected out of 5 in $^5C_2$ ways

3 friends can be selected out of 5 in $^5C_3$ ways

4 friends can be selected out of 5 in $^5C_4$ ways

5 friends can be selected out of 5 in $^5C_5$ ways

Hence the required number of ways

$= {}^5C_1 + {}^5C_2 + {}^5C_3 + {}^5C_4 + {}^5C_5$

$= 5 + 10 + 10 + 5 + 1 = 31$

Alternatively : $^5C_1 + {}^5C_2 + {}^5C_3 + {}^5C_4 + {}^5C_5 = 2^5 - 1 = 31$

Since, $^nC_1 + {}^nC_2 + {}^nC_3 + \ldots + {}^nC_n = 2^n - 1$

16. 4 men can be selected out of 7 men in $^7C_4$ ways and 2 ladies can be selected out of 6 ladies in $^6C_2$ ways

Hence, the required number of ways $= {}^7C_4 \times {}^6C_2$

$= 35\times15 = 525$

17. A committee of 5 persons is to be formed from 6 gentlemen and 4 ladies by taking.

(i) 1 lady out of 4 and 4 gentlemen out of 6.

(ii) 2 ladies out of 4 and 3 gentlemen out of 6.

(iii) 3 ladies out of 4 and 2 gentlemen out of 6.

(iv) 4 ladies out of 4 and 1 gentleman out of 6.

In case I the number of ways $= {}^4C_1 \times {}^6C_4 = 4\times15 = 60$

Scanned by CamScanner

yoursmahboob.wordpress.com

In case II the number of ways = ${}^4C_2 \times {}^6C_3 = 6 \times 20 = 120$

In case III the number of ways = ${}^4C_3 \times {}^6C_2 = 4 \times 15 = 60$

In case IV the number of ways = ${}^4C_4 \times {}^6C_1 = 1 \times 6 = 6$

Hence, the required number of ways

$= 60 + 120 + 60 + 6 = 246$

18. A committee of 7 persons retaining a majority of Indians can be made from 6 Americans and 7 Indians by taking

(i) 1 American out of 6 and 6 Indians out of 7.

(ii) 2 Americans out of 6 and 5 Indians out of 7.

(iii) 3 Americans out of 6 and 4 Indians out of 7.

In case I the number of ways = ${}^6C_1 \times {}^7C_6 = 6 \times 7 = 42$

In case II the number of ways = ${}^6C_2 \times {}^7C_5 = 15 \times 21 = 315$

In case III the number of ways = ${}^6C_3 \times {}^7C_4 = 20 \times 35 = 700$

Hence, the required number of ways

$= 700 + 315 + 42 = 1057$

19. Required number of ways = ${}^6C_4 \times {}^8C_3 = 15 \times 56 = 840$

20. The number of committees in which both Miss. *A* and Mr. *B* are always members. We can select rest 3 men from the remaining 5 in ${}^5C_3$ ways and rest 2 women from the remaining 7 in ${}^7C_2$ ways.

∴The required number of ways in which both Miss. *A* and Mr. *B* are always included

$= {}^5C_3 \times {}^7C_2 = 10 \times 21 = 210$

Hence the required number of ways in which Miss. *A* and Mr. *B* do not serve together = 840 – 210 = 630

21. Since 3 particular members are already selected, then we are required to select only 4 members out of the remaining 8 members.

It can be done in ${}^8C_4$ ways.

$\therefore \quad {}^8C_4 = 70$

22. Since 3 particular members are not included hence we have to select 7 members out of remaining 8 members. It can be done in ${}^8C_7$ ways

$\therefore \quad {}^8C_7 = 8$

23. 3 experts including atleast an engineer and a manager can be selected by taking.

(i) 2 managers out of 3 and 1 engineer out of 3.

(ii) 1 manager out of 3 and 2 engineer out of 3.

(iii) 2 persons out of 6 (3 managers and 3 engineers) and 1 person out of one who is both engineer and manager.

In case I, the number of ways = ${}^3C_2 \times {}^3C_1 = 9$

In case II, the number of ways = ${}^3C_1 \times {}^3C_2 = 9$

In case III, the number of ways = ${}^6C_2 \times {}^1C_1 = 15$

Hence, the required number of ways = 9 + 9 + 15 = 33.

24. A committee of 5 persons, consisting of at most two ladies, can be formed in the following ways.

(i) selecting 5 gents only out of 6.

(ii) selecting 4 gents only out of 6 and one lady out of 4.

(iii) selecting 3 gents only out of 6 and two ladies out of 4.

In case I, the number of ways = ${}^6C_5$

In case II, the number of ways = ${}^6C_4 \times {}^4C_1$

In case III, the number of ways = ${}^6C_3 \times {}^4C_2$

∴Required number of ways $= {}^6C_5 + {}^6C_4 \times {}^4C_1 + {}^6C_3 \times {}^4C_2$

$= 6 + 60 + 120 = 186$

25. A voter may cast vote for either 1 candidate or 2 candidates or 3 candidates or 4 candidates out of 7.

The voter may cast vote for 1 candidate in ${}^7C_1$ ways

The voter may cast vote for 2 candidates in ${}^7C_2$ ways

The voter may cast vote for 3 candidates in ${}^7C_3$ ways

The voter may cast vote for 4 candidate in ${}^7C_4$ ways

Hence, the required number of ways

$= {}^7C_1 + {}^7C_2 + {}^7C_3 + {}^7C_4$

$= 7 + 21 + 35 + 35 = 98$

26. Required number of ways $= {}^5C_1 + {}^5C_2 + {}^5C_3$

$= 5 + 10 + 10 = 25$

27. Required number of ways $= {}^8C_6 \times {}^8C_5$

$= 28 \times 56 = 1568$

28. Required number of ways

$= ({}^6C_4 \times {}^6C_2) + ({}^6C_3 \times {}^6C_3) + ({}^6C_2 \times {}^6C_4)$

$= (15 \times 15) + (20 \times 20) + (15 \times 15)$

$= 225 + 400 + 225 = 850$

29. Required number of ways

$= {}^7C_3 \times {}^5C_5 + {}^7C_4 \times {}^5C_4 + {}^7C_5 \times {}^5C_3$

$= 35 \times 1 + 35 \times 5 + 21 \times 10$

$= 35 + 175 + 210 = 420$

30. Required number of ways

$= ({}^5C_2 \times {}^5C_3 \times {}^4C_1) + ({}^5C_3 \times {}^5C_2 \times {}^4C_1) + ({}^5C_2 \times {}^5C_2 \times {}^4C_2)$

$= (10 \times 10 \times 4) + (10 \times 10 \times 4) + (10 \times 10 \times 6)$

$= 1400$

31. Required number of ways $= {}^{13}C_8 \times {}^5C_2$

$= 1287 \times 10 = 12870$

32. One hand shake requires two different persons.

∴ Number of hand shakes

= number of ways of selecting two persons out of 11 persons

$= {}^{11}C_2 = 55$

33. If n is even, ${}^nC_r$ is maximum when $r = \frac{n}{2}$

$\therefore \quad$ Number of invitees in a party $= \frac{24}{2} = 12$

and maximum possible number of parties $= {}^{24}C_{12}$

$= 2704156$

34. If n is odd, ${}^nC_r$ is maximum when

$$r = \frac{n-1}{2} \quad \text{or} \quad r = \frac{n+1}{2}$$

$$\therefore \quad r = \frac{11-1}{2} = 5 \quad \text{or} \quad r = \frac{11+1}{2} = 6$$

$$\therefore \quad {}^{11}C_5 = {}^{11}C_6 = 462$$

35. Possible number of members in a family is either 5 or 6.

So, the maximum possible number of family members = 6

36. Let there were n persons in the meeting, then number of handshakes = ${}^nC_2$

$\therefore \quad {}^nC_2 = 66$

Scanned by CamScanner

yoursmanboob.wordpress.com

$$\Rightarrow \quad \frac{n!}{2!(n-2)!} = 66$$

$$\Rightarrow \quad \frac{n(n-1)}{2} = 66$$

$$\Rightarrow \quad n(n-1) = 132$$

$$\Rightarrow \quad n = 12$$

Alternatively : Go through options.

37. Since a particular player is always chosen therefore we have to choose only 10 players out of remaining 15 players.

$\therefore$ Required number of ways $= {}^{15}C_{10} = 3003$

38. Since a player is never chosen,hence we have to choose 11 players out of remaining 15 players.

$\therefore$ Required number of ways $= {}^{15}C_{11} = 1365$

39. Total number of bowlers = 4
Total number of wicket keepers = 2
Rest (normal) players = 10
Possible Combinations :

Bowlers	Wicket keepers	Normal players
3	1	7
3	2	6
4	1	6
4	2	5

$\therefore$ Required number of ways

$= ({}^4C_3 \times {}^2C_1 \times {}^{10}C_7) + ({}^4C_3 \times {}^2C_2 \times {}^{10}C_6) + ({}^4C_4 \times {}^2C_1 \times {}^{10}C_6) + ({}^4C_4 \times {}^2C_2 \times {}^{10}C_5)$

$= (3 \times 1 \times 7) + (3 \times 2 \times 6) + (4 \times 1 \times 6) + (4 \times 2 \times 5)$

$= 960 + 840 + 420 + 252 = 2472$

40. Total number of bowles = 6
Total number of wicket keepers = 3
Total number of normal players = 11 [20 – (6 + 3)]
Possible combinations :

Bowlers	Wicket keepers	Normal players
4	2	5
5	2	4
6	2	3

$\therefore$ Required number of ways

$= ({}^6C_4 \times {}^3C_2 \times {}^{11}C_5) + ({}^6C_5 \times {}^3C_2 \times {}^{11}C_4) + ({}^6C_6 \times {}^3C_2 \times {}^{11}C_3)$

$= 20790 + 5940 + 495 = 27225$

41. Total number of wicket keepers = 2
Total number of bowlers = 8
Total number of batsman = 10
Total number of all rounders = 5
1 Wicket keeper can be selected out of 2 in ${}^2C_1$ ways
2 Bowlers can be selected out of 8 in ${}^8C_2$ ways
5 Batsmen can be selected out of 10 in ${}^{10}C_5$ ways
3 All rounders can be selected out of 5 in ${}^5C_3$ ways
$\therefore$ Required number of ways $= {}^2C_1 \times {}^8C_2 \times {}^{10}C_5 \times {}^5C_3$

$= 2 \times 28 \times 252 \times 10 = 141120$

42. 1 book on Economics can be collected out of 3 in ${}^3C_1$ ways
1 book on Corporate strategy can be collected out of 4 in ${}^4C_1$ ways 1 book on Philosophy can be collected out of 5 in ${}^5C_1$ ways
Hence the required number of collections each of which consists of exactly one book on each subject

$= {}^3C_1 \times {}^4C_1 \times {}^5C_1$

$= 3 \times 4 \times 5 = 60$

43. At least one book on Economics can be collected out of $3 = {}^3C_1 + {}^3C_2 + {}^3C_3 = 2^3 - 1 = 7$ ways.
Similarly one book on corporate strategy can be collected out of $4 = {}^4C_1 + {}^4C_2 + {}^4C_3 + {}^4C_4 = 2^4 - 1 = 15$ ways.
Similarly one book on Philosophy can be collected out of $5 = {}^5C_1 + {}^5C_2 + {}^5C_3 + {}^5C_4 + {}^5C_5 = 2^5 - 1 = 31$ ways.
Hence the required number of ways $= 7 \times 15 \times 31 = 3255$

44. Since all the three balls are red which can be selected from 7 red balls only.

$\therefore$ Required number of selections $= {}^7C_3 = 35$

45. Since red balls can not be taken thus we can select 3 balls out of 6 white and 4 blue balls.

$\therefore$ Required number of selections $= {}^{10}C_3 = 120$ ways

46. The required number of selections

$= {}^7C_1 \times {}^6C_1 \times {}^4C_1 = 168$

47. Total number of red balls = 5
Total number of green balls = 6
Possible combinations are :

Red	Green
2	4
3	3
4	2

$\therefore$ Required number of selections

$= ({}^5C_2 \times {}^6C_4) + ({}^5C_3 \times {}^6C_3) + ({}^5C_4 \times {}^6C_2) = 425$

48. A line requires 2 end points for its formation.
Hence required number of lines

= 2 points selected from 6 points

$= {}^6C_2 = 15$

Thus out of total 6 non-collinear points 15 lines can be drawn.

49. Total number of lines formed by 12 points $= {}^{12}C_2$
Number of lines formed by 4 points $= {}^4C_2$
$\therefore$ Required number of lines = Total lines formed by 12 points – number of lines formed by 4 collinear points + 1

$= {}^{12}C_2 - {}^4C_2 + 1 = 61$

Explanation : If no three points are collinear, a straight line can be formed by joining any two points out of given non-collinear points. But since if some points are collinear then some lines become overlapped.
Here 12 points can make ${}^{12}C_2$ lines, but since 4 points are collinear, we can find only one line by joining these 4 collinear points where as we have considered ${}^4C_2$ lines in ${}^{12}C_2$ lines.
Hence the required number of straight lines

$= {}^{12}C_2 - {}^4C_2 + 1 = 61$

Scanned by CamScanner

yoursmahboob.wordpress.com

50. A decagon has 10 vertices *i.e.*, 10 non-collinear points. Hence the total number of lines formed by 10 non-collinear points $= {}^{10}C_2 = 45$

But since out of 45 lines 10 lines are the sides of the decagon and the remaining 35 lines are diagonals of a decagon.

Alternatively : Number of diagonals $= {}^{n}C_2 - n$

51. Number of diagonals in an n-sided polygon

= Number of total lines − Number of sides

$= {}^{n}C_2 - n$

$= \frac{n(n-1)}{2} - n = \frac{n(n-3)}{2}$

52. Number of diagonals $= {}^{n}C_2 - n = 54$

$\Rightarrow \quad \frac{n(n-1)}{2} - n = 54$

$\Rightarrow \quad \frac{n(n-3)}{2} = 54$

$\Rightarrow \quad n = 12$

Alternatively : Go through options.

53. A triangle can be formed by joining 3 non-collinear points. Hence number of triangles is equal to the number of ways in which 3 points can be selected out of 6 non-collinear points.

$\therefore$ Number of triangles $= {}^{6}C_3 = 20$

54. Number of triangles that can be formed if no three points are collinear $= {}^{12}C_3 = 220$.

But since 4 points are collinear, we cannot form any triangle from these 4 points by joining any three of them where as we have taken ${}^{4}C_3$ triangles in the above result (*i.e.*, ${}^{12}C_3$).

Hence the required number of triangles $= {}^{12}C_3 - {}^{4}C_3$

$= 220 - 4 = 216$

55.



A triangle can be formed by selecting 1 point out of P and Q and selecting 2 points out of 8 points on the other parallel line.

or a triangle can be formed by selecting 2 points out of 2 points (P and Q) and selecting 1 point out of 8 points.

$\therefore$ Required number of triangles $= ({}^{2}C_1 \times {}^{8}C_2) + ({}^{2}C_2 \times {}^{8}C_1)$

$= (2 \times 28) + (1 \times 8) = 64$

56. Number of triangles whose vertex is P = total number of triangles − number of triangles which do not contain P as a vertex.

$\therefore$ Number of triangles which do not contain P as a vertex

$= {}^{1}C_1 \times {}^{8}C_2 = 28$

$\therefore$ Required number of triangles $= 64 - 28 = 36$

57. An intersection point is formed by the intersection of two lines. Hence number of intersection points is equal to the number of ways of selecting 2 lines out of the given 20 non-parallel and non-concurrent lines.

i.e., Required number of points $= {}^{20}C_2 = 190$.

58. Number of straight lines formed by 'n' non-collinear points

$= {}^{n}C_2 = \frac{n(n-1)}{2}$.

59. Since 'p' points are in a straight line therefore they will form only one line instead of ${}^{p}C_2$ lines.

$\therefore$ Required number of lines $= {}^{n}C_2 - {}^{p}C_2 + 1$.

60. Number of triangles formed by 'n' non-collinear points is ${}^{n}C_3$.

But since m points are in a straight line therefore from these m points ${}^{m}C_3$ triangles can not be formed. Hence required number of triangles $= {}^{n}C_3 - {}^{m}C_3$.

61. A parallelogram is formed by choosing two straight lines. From the set of m parallel lines and two straight lines from the set of n parallel lines.

Two straight lines from the set of m parallel lines can be chosen in ${}^{m}C_2$ ways and two straight lines from the set of n parallel lines can be chosen in ${}^{n}C_2$ ways. Hence the number of parallelograms formed

$= {}^{m}C_2 \times {}^{n}C_2 = \frac{m(m-1)}{2} \times \frac{n(n-1)}{2}$

$= \frac{mn(m-1)(n-1)}{4}$

62. The number of points of intersection of 37 lines is ${}^{37}C_2$. But 13 straight lines out of the given 37 straight lines pass through the same point A. Therefore instead of getting ${}^{13}C_2$ points, we get only one point A. Similarly 11 straight lines out of the given 37 straight lines intersect at point B. Therefore instead of getting ${}^{11}C_2$ points, we get only one point B.

Hence the number of intersection points of the lines is

${}^{37}C_2 - {}^{13}C_2 - {}^{11}C_2 + 2 = 535$

63. Required number of words $= {}^{15}C_2 \times {}^{5}C_4$

$= 105 \times 5 = 525$

64. There are 11 letters in the given word of which 2 are A's, 2 are I's, 2 are N's and the remaining 5 letters are different. Thus we have 11 letters of 8 different kinds *viz.*, (A, A), (I, I), (N, N), E, X, M, T, O.

A group of 4 letters can be classified as follows :

(i) Two alike of one kind and two alike of another kind.

(ii) Two alike and the other two different.

(iii) All four different.

In case I, the number of ways $= {}^{3}C_2 = 3$

In case II, the number of ways $= {}^{3}C_1 \times {}^{7}C_2 = 63$

In case III, the number of ways $= {}^{8}C_4 = 70$

Hence, the required number of ways $= 3 + 63 + 70 = 136$

65. There are 11 letters in the given word where M occurs 2 times, A occurs 2 times and T occurs 2 times and rest letters occur one times each.

i.e., M, A, T, H, E, I, C, S

M, A, T

A group of 4 letters can be selected in the following manner.

(i) Two alike of one kind and two alike of other kind.

(ii) Two alike and the other two different.

(iii) All four different.

Scanned by CamScanner

yoursmahboob.wordpress.com

Case I. ${}^3C_2 \times \frac{4!}{2!2!} = 18$

Case II. ${}^3C_1 \times {}^7C_2 \times \frac{4!}{2!} = 756$

Case III. ${}^8C_4 \times 4! = 1680$

$\therefore$ Total required words of 4 letters $= 18 + 756 + 1680$

$= 2454$

66. Let L_1, L_2, L_3 be 3 ladies and G_1, G_2, G_3 be 3 gents.
Any two of the ladies out of 3 can be selected in ${}^3C_2$ ways and can be arranged mutually in 2! ways.
Now we are left with 3 gents and 1 lady these 4 persons can be arranged at a round table in 3! ways.
Now we have only two places among 4 persons to place the two selected ladies which can be done in ${}^2P_1$ ways.
Hence the required number of arrangements

$= {}^3C_2 \times 2! \times 3! \times {}^2P_1$

$= 3 \times 2 \times 6 \times 2 = 72$

67. Since 4 guests desire to sit on one side and the other 3 guests desire to sit on the other side.



Hence we are left with 11 guests only out of which we choose 5 guests for the side A in ${}^{11}C_5$ ways and remaining 6 guests can be selected for the side B in ${}^6C_6$ ways.
Further in each side 9 guests can be arranged in 9! ways.
Hence the required number of arrangements

$= {}^{11}C_5 \times {}^6C_6 \times 9! \times 9! = 462 \times (9!)^2$

68. The number of ways in which none of the n letters goes to the correct place

$$= n!\left[1 - \frac{1}{1!} + \frac{1}{2!} - \frac{1}{3!} + \frac{1}{4!} - \frac{1}{5!} + \ldots + (-1)^n \frac{1}{n!}\right]$$

$\therefore$ Number of ways in which all the 4 letters go to the wrong place

$$= 4!\left[1 - \frac{1}{1!} + \frac{1}{2!} - \frac{1}{3!} + \frac{1}{4!}\right]$$

$$= 24\left[1 - \frac{1}{1} + \frac{1}{2} - \frac{1}{6} + \frac{1}{24}\right]$$

$$= 24\left[\frac{12 - 4 + 1}{24}\right] = 9$$

Now the number of ways in which all the possibilities can occur $= 4! = 24$.
$\therefore$ Number of ways in which atleast one letter goes to the correct place $= 24 - 9 = 15$.

69. Required number of ways = 9.

INTRODUCTORY EXERCISE 19.6

1. Atleast 1 green dye can be selected out of 5 green dyes in $(2^5 - 1)$ *i.e.*, 31 ways.
Similarly, atleast one blue dye can be selected out of 4 in $(2^4 - 1)$ *i.e.*, 15 ways,
and atleast 1 red or no red dye can be selected out od 3 red dyes in 2^3 *i.e.*, 8 ways.
Hence the required number of ways $= 31 \times 15 \times 8 = 3720$.

2. Out of 15 fruits, 7 are alike of one kind, 5 are alike of a second kind and 3 are alike of a third kind.
Hence, the required number of ways

$= [(7 + 1)(5 + 1)(3 + 1) - 1] = 191$

3. Out of 4 beverages he can select atleast one beverage in $2^4 - 1$ *i.e.*, 15 ways.

4. Atleast one mango can be selected in $2^4 - 1 = 15$ ways and atleast one orange can be selected in $2^5 - 1 = 31$ ways.
Hence the required number of ways $= 15 \times 31 = 465$

5. Required number of ways $= [(9 + 1)(7 + 1)(4 + 1)] - 1$

$= 399$

6. ${}^{(2n+1)}C_1 + {}^{(2n+1)}C_2 + {}^{(2n+1)}C_3 + \ldots + {}^{(2n+1)}C_n = 63$
Now going through options we get $n = 3$.
$\therefore \quad {}^7C_1 + {}^7C_2 + {}^7C_3 = 7 + 21 + 35 = 63$
Hence $n = 3$ is the correct answer.

INTRODUCTORY EXERCISE 19.7

1. The required number of ways in which 12 students may be equally divided into three groups.

$$= \frac{12!}{3! \times (4!)^3} = 5775$$

2. The required number of ways in which 12 mangoes may be equally divided among three boys

$$= \frac{12!}{(4!)^3} = 34650$$

3. Let three boxes of different sizes be denoted by B_1, B_2, B_3. 5 balls can be placed in the three boxes so that no box is empty as follows :

Case	I	II	III	IV	V	VI
B_1	1	1	1	2	2	3
B_2	1	2	3	1	2	1
B_3	3	2	1	2	1	1

Scanned by CamScanner

yoursmahboob.wordpress.com

In case I, the number of ways $= \frac{5!}{1!\times1!\times3!} = 20$

In case II, the number of ways $= \frac{5!}{1!\times2!\times2!} = 30$

In case III, the number of ways $= \frac{5!}{1!\times3!\times1!} = 20$

In case IV, the number of ways $= \frac{5!}{2!\times1!\times2!} = 30$

In case V, the number of ways $= \frac{5!}{2!\times2!\times1!} = 30$

In case VI, the number of ways $= \frac{5!}{1!\times1!\times3!} = 20$

Hence, the required number of ways

$= 20 + 30 + 20 + 30 + 30 + 20 = 150$

4. It mean each player can receive 13 cards.

∴First player can get 13 cards in ${}^{52}C_{13}$ ways.

Second player can get 13 cards in ${}^{39}C_{13}$ ways.

Third player can get 13 cards in ${}^{26}C_{13}$ ways

Fourth player can get 13 cards in ${}^{13}C_{13}$ ways.

Hence the total number of ways

$= {}^{52}C_{13} \times {}^{39}C_{13} \times {}^{26}C_{13} \times {}^{13}C_{13} = \frac{52!}{(13!)^4}$

Alternatively : 52 cards can be divided equally among 4 players in $\frac{52!}{(13!)^4 \times (4!)}$ ways.

But since order is important, hence the required number of ways

$= \frac{52!\times4!}{(13!)^4\times(4!)} = \frac{52!}{(13!)^4}$

5. Required number of ways $= \frac{52!}{(13!)^4\times(4!)}$.

6. First player can get 16 cards in ${}^{52}C_{16}$ ways.

Second player can get 16 cards in ${}^{36}C_{16}$ ways.

Third player can get 16 cards in ${}^{20}C_{16}$ ways.

and fourth player can get 4 cards in ${}^{4}C_{4}$ ways.

But since first three sets can be interchanged in 3! ways.

Hence, the required number of ways

$= {}^{52}C_{16} \times {}^{36}C_{16} \times {}^{20}C_{16} \times {}^{4}C_{4} \times \frac{1}{3!}$

$= \frac{52!}{(16!)^3\times(3!)}$

7. Since the order of the couples is not important.

So, the required number of ways $= \frac{2n!}{(2!)^n\cdot n!}$.

8. Number of ways in which 20 mangoes can be distributed among 4 persons is ${}^{20+4-1}C_{4-1} = {}^{23}C_3$.

9. Number of ways of distributing 7 identical balls among 3 boxes so that a box receives atleast one ball

$= {}^{7-1}C_{3-1} = {}^{6}C_2 = 15$

10. Total number of non-negative integral solutions of the given equations is same as the number of ways of distributing 44 items among 4 persons such that each person can receive any number of items.

Hence, total number of solutions $= {}^{44+4-1}C_{4-1} = {}^{47}C_3$.

11. Let $u \geq 0, v \geq 0, w \geq 0$, then

$a \geq u+1, \quad b \geq v+2, \quad c \geq w+3$

$\therefore \quad a+b+c = 18$

$\Rightarrow \quad u+1+v+2+w+3 = 18$

$\Rightarrow \quad u+v+w = 12$

∴Total number of solutions of this equations is

${}^{12+3-1}C_{3-1} = {}^{14}C_2$

12. Let x, y, z be the number of balls received by the three persons, then

$x \geq 5, y \geq 5, z \geq 5$ and $x+y+z = 21$

Let $u \geq 0, v \geq 0, w \geq 0$, then

$\therefore \quad x+y+z = 21$

$\Rightarrow \quad u+5+v+5+w+5 = 21$

$\Rightarrow \quad u+v+w = 6$

∴ Total number of solutions $= {}^{6+3-1}C_{3-1} = {}^{8}C_2 = 28$

LEVEL (1)

1. $9\times9\times9\times9 = 9^4$.

2. $9^4 - 1$ (It is considered that the lock opens in the last attempt.)

3. **Case I.** *MW MW MW MW*

Case II. *WM WM WM WM*

Let us arrange 4 men in 4! ways, then we arrange 4 women in ${}^4P_4$ ways at 4 places either left of the men or right of the men.

Hence required number of arrangements

$= 4! \times {}^4P_4 + 4! \times {}^4P_4 = 2\times576 = 1152$

4. First of all we arrange 4 women in 4! ways then we arrange 4 men in 5 places in ${}^5P_4$ ways.

Hence, the total number of arrangements $= 4! \times {}^5P_4 = 2880$

5. Let us arrange 4 persons in 4! ways then we place their respective wives adjacent to them in 2! ways i.e., either left or right sides of the husbands.

Hence, the required numbr of ways $= 4!\times2!\times2!\times2!\times2!$

6. Let us first of all we arrange 4 men in 3! ways then 4 women can be arranged in 4 places in ${}^4P_4$ ways.

Hence the required number of ways $= 3! \times {}^4P_4 = 144$.

7. All the 4 men can be arranged in 4! ways.

Similarly all the 4 women can be arranged in 4! ways but the two different groups of men and women can be mutually arranged in 2! ways.

Hence the required number of ways $= (4!)^2 \times 2! = 1152$

Scanned by CamScanner

yoursmahboob.wordpress.com

8. *H L C N T A U I O*
L N A I

There are total 13 letters out of which 7 are consonants and 6 are vowels. Also there are $2L's$, $2N's$, $2A's$, and $2I's$.

If all the consonants are together then the number of arrangements $= \frac{7!}{2!.2!}$.

but the 7 consonants can be arranged themselves in $\frac{7!}{2!.2!}$ ways.

Hence the required number of ways $= \frac{7!}{2!\times 2!} \times \frac{7!}{2!\times 2!}$

$= (1260)^2 = 1587600$

9. There are 7 odd places and 6 vowels of which 2 vowels occur two times.

Hence number of arrangements of vowels $= \frac{{}^7P_6}{2!\times 2!}$.

Now the remaining 7 consonants of which two consonants occur two times, can be arranged in 7 places in $\frac{7!}{2!\times 2!}$ ways.

Hence, the required number of ways $= \frac{{}^7P_6}{2!\times 2!} \times \frac{7!}{2!\times 2!}$

$= 1587600$

10. *S U C C E F L*
S U C
S

There are 10 letters in the word SUCCESSFUL and S occurs 3 times, U occurs 2 times and C occurs 2 times.

∴ The letters of the word SUCCESSFUL can be arranged in

$= \frac{10!}{3!\times 2!\times 2!}$ ways

$= 151200$ ways

11. Since all three $S's$ are together, hence there will be 8 letters of which C occurs 2 times and U occurs 2 times.

Thus the required number of arrangements $= \frac{8!}{2!\times 2!}$

$= 10080$

12. $(C, C), (U, U), S, S, S, E, F, L$

These 8 letters now can be arranged in $\frac{8!}{3!}$ ways.

13. Total number of 4 digit numbers without repetition of digits $= 4! = 24$.

Each of the digits in each of the 4 places (thousands, hundreds and tens and unit) place will be 3! times *i.e.*, 6 times.

Hence the sum of all the digits at each of the four places

$= 6(1 + 2 + 3 + 4) = 60$

Hence the sum of all the required 4 digit numbers

$= 60(1000 + 100 + 10 + 1)$

$= 60 \times 1111 = 66660$

14. Total number of 5 digit numbers (including which begins with zero) $= 5! = 120$.

Number of 5 digit numbers which begin with zero $= 4! = 24$.

Sum of all 5 digit numbers

$= (0 + 1 + 2 + 3 + 4) \times 4! \times (11111)$

$= 240 \times 11111 = 2666640$

Sum of all five digit numbers which begin with zero

$= (1 + 2 + 3 + 4) \times 3! \times (1111) = 66660$

Hence the sum of the required numbers

= sum of all 5 digit numbers including those numbers which begin with zero

− sum of all 5 digit numbers which begin with zero

$= 2666640 - 66660 = 2599980$

15. Number of polygons $= {}^nC_2$ − Number of sides (n)

$\therefore \quad {}^nC_2 - n = n$

$\Rightarrow \quad {}^nC_2 = 2n$

$\Rightarrow \quad \frac{n(n-1)}{2} = 2n$

$\Rightarrow \quad n = 5$

16. There are 10 letters in the given word PROPORTION and we have 10 letters of 6 different kinds *viz.*,
$(O, O, O), (P, P), (R, R), T, I, N$.
For a group of four letters, we have four cases :
(i) Three alike and one different.
(ii) Two alike and two other alike.
(iii) Two alike and other two different.
(iv) All four different.
In case I, the number of selections $= {}^1C_1 \times {}^5C_1 = 5$.
In case II, the number of selections $= {}^3C_2 = 3$.
[Since we can select two pairs out of 3 pairs $(O, O), (P, P), (R, R)$]
In case III, the number of selections $= {}^3C_1 \times {}^5C_2 = 30$.
(∵ We can select one of 3 pairs and then two from the remaining 5 letters say, P, R, T, I, N.)
In case IV, the number of selections $= {}^6C_4 = 15$.
(∵ We can select 4 different letters from 6 letters O, P, R, T, I, N.)

In case I, the number of arrangements $= 5 \times \frac{4!}{3!} = 20$.

In case II, the number of arrangements $= 3 \times \frac{4!}{2!\times 2!} = 18$.

In case III, the number of arrangements $= 30 \times \frac{4!}{2!} = 360$.

In case IV, the number of arrangements $= 15 \times 4! = 360$.

Hence the required number of arrangements

$= 20 + 18 + 360 + 360 = 758$

17. Vowels themselves can be permuted in $\frac{4!}{3!}$ ways

and consonants can be permuted in $\frac{6!}{2!\times 2!}$ ways

Therefore the required number of ways $= \frac{4!}{3!} \times \frac{6!}{2!\times 2!}$

$= 4 \times 180 = 720$

18. Total number of ways of arranging 16 people $= 15!$ ways
Number of ways in which two brothers are together $= 14! \times 2$
∴ Number of ways in which two brothers are never together

$= 15! - 14! \times 2$

$= 14!(15 - 2) = 14! \times 13$

Scanned by CamScanner

yoursmahboob.wordpress.com

19. A person out of remaining 14 persons can be selected in ${}^{14}C_1 = 14$ ways.
Now consider Lehman, Mckinsey and a third (selected person) as a single person, then we can arrange all of them in 13! ways.
But the two brothers mutually can be arranged in 2! ways.
Hence the required number of ways $= 14 \times 13! \times 2 = 14! \times 2$

20. Every ball can be distributed in 4 ways.
Hence the required number of ways $= 4 \times 4 \times 4 \times 4 \times 4 \times 4$
$= 4^6 = 4096$

21. Number of ways of distribution of 'n' identical things taken r at a time $= {}^{n+r-1}C_{r-1}$
$\therefore$ Required number of ways $= {}^{6+4-1}C_{4-1} = {}^9C_3 = 84$

22. Number of non-negative integral solutions $= {}^{n+r-1}C_{r-1}$
$= {}^{21+3-1}C_{3-1}$
$= {}^{23}C_2 = 253$

23. Number of positive integral solutions $= {}^{n-1}C_{r-1}$
$= {}^{21-1}C_{3-1} = {}^{20}C_2$
$= 190$

24. Number of ways of selecting items from 6 different items $= 2^6$.
Similarly from second set of 6 different objects we can select items in 2^6 ways.
Therefore, total number of selections $= 2^6 \times 2^6$
but we have to select at least one item therefore we subtract one case in which none of the items is selected $= 2^6 \times 2^6 - 1$
$= 2^{12} - 1 = 4095$

25. Number of ways of selecting the items from 6 identical items $= 6 + 1 = 7$
Similarly we can select from other set of 6 identical items $= 7$
$\therefore$ Total number of ways in which at least one item can be selected from the two sets $= (7 \times 7) - 1 = 48$

Note Since we can select either 0, 1, 2, 3, 4, 5, or 6 items which can be done in 7 ways.

26. We can select atleast one item from 6 different items $= (2^6 - 1)$
Similarly we can select atleast one item from other set of 6 different items in $(2^6 - 1)$ ways.
$\therefore$ Required number of ways $= (2^6 - 1)(2^6 - 1)$
$= (2^6 - 1)^2 = 3969$

27. We can select atleast one item from 6 identical items in 6 ways.
Similarly from other set also we can select atleast one item in 6 ways.
Hence, the required number of ways $= 6 \times 6 = 36$.

28.

Single step	Double step	Number of ways
12	0	$\frac{12!}{12!} = 1$
10	1	$\frac{11!}{10!} = 11$
8	2	$\frac{10!}{(8! \times 2!)} = 45$
6	3	$\frac{9!}{(6! \times 3!)} = 84$
4	4	$\frac{8!}{(4! \times 4!)} = 70$
2	5	$\frac{7!}{(2! \times 5!)} = 21$
0	6	$\frac{6!}{6!} = 1$

$\therefore$ Total number of ways $= 1 + 11 + 45 + 84 + 70 + 21 + 1$
$= 233$

29. Using ${}^{n+r-1}C_{r-1}$, we get ${}^{8+3-1}C_{3-1} = {}^{10}C_2 = 45$

30. ${}^{100}C_{10} \times {}^{90}C_{20} \times {}^{70}C_{30} \times {}^{40}C_{40} = \frac{100!}{10! \times 20! \times 30! \times 40!}$

31. There are two sets of numbers 0, 1, 3, 5 and 0, 2, 3, 4.
Therefore number of 4 digit numbers using digits 0, 1, 3, 5
$= 3 \times 3 \times 2 \times 1 = 18$
Similarly number of 4 digit numbers using digits 0, 2, 3, 4
$= 3 \times 3 \times 2 \times 1 = 18$
Hence the total required numbers $= 18 + 18 = 36$.

32.

When 7 is at ten thousands place →	1	1	9	9	9	$\to 9^3$
	1	9	1	9	9	$\to 9^3$
	1	9	9	1	9	$\to 9^3$
	1	9	9	9	1	$\to 9^3$
When 7 is not at the ten thousands place →	8	1	1	9	9	$\to 8 \times 9^2$
	8	1	9	1	9	$\to 8 \times 9^2$
	8	1	9	9	1	$\to 8 \times 9^2$
	8	9	1	1	9	$\to 8 \times 9^2$
	8	9	1	9	1	$\to 8 \times 9^2$
	8	9	9	1	1	$\to 8 \times 9^2$

Hence the required number of ways $= 4 \times 9^3 + 6 \times 8 \times 9^2$
$= 9^2 (36 + 48)$
$= 81 \times 84 = 6804$

33. Required number of ways $= \frac{15!}{3! \times 4! \times 8!}$.

34. Total number of ways $= 7!$
Let A has to speak before B.
Now since there are half of the total cases in which A speaks before B (Similarly in half of the total cases B speaks before A)
$\therefore$ Required number of ways $= \frac{1}{2} \times 7! = 2520$.

35.

1	10	10	10	10	10	10	$\Rightarrow 10^6$

Total number of 7 digit telephone numbers which begin with digit $2 = 10^6$.

36. ${}^6P_4 = 360$.
Alternatively : First son can accept any of the 6 proposals and second son can accept any of the 5 proposals and so on.
Hence required number of ways $= 6 \times 5 \times 4 \times 3 = 360$

37. ${}^{16}C_4 = 1820$

38. ${}^{16}P_4 = 43680$

Scanned by CamScanner

yoursmahboob.wordpress.com

39. ${}^{16}C_4 \times {}^{12}C_4 \times {}^{8}C_4 \times {}^{4}C_4 \times \frac{1}{4!} = \frac{16!}{(4!)^5}$.

40. ${}^{n}C_2 = 105$, where n is the number of players

$$\Rightarrow \quad \frac{n(n-1)}{2} = 105 \Rightarrow n = 15$$

41. ${}^{9}P_6 = 60480$

42. $\frac{6!}{2! \times 4!} = 15$

43. $4 \times 6 = 24$

44. Total number of 5 digit numbers $= 9 \times 10^4 = 90000$
Number of 5 digit numbers without any repetition
$= 9 \times 9 \times 8 \times 7 \times 6 = 27216$
∴Required number of 5 digit numbers in which atleast one of the digit repeats $= 90000 - 27216 = 62784$

45. Total number of possible outcomes $= 6^4$.
The number of possible outcomes in which 4 does not appear on any die is 5^4.
Therefore the number of possible outcomes in which atleast one die shows digit $4 = 6^4 - 5^4 = 671$

46. Required number of signals $= {}^{5}P_1 + {}^{5}P_2 + {}^{5}P_3 + {}^{5}P_4 + {}^{5}P_5$
$= 5 + 20 + 60 + 120 + 120 = 325$

47. The number of words begin with A is 4!.
The number of words begin with E is 4!.
The number of words begin with M is 4!.
The number of words begin with R is 4!.
Number of words begin with VA is 3!
Words begin with VE are $VEAMR$
$VEARM$
$VEMAR$
$VEMRA$
$VERAM$
$VERMA$
∴ The rank of the word $VERMA = 4 \times 4! + 3! + 6$
$= 96 + 6 + 6 = 108$

48. **Case I:** 0, 1, 2, 4, 5
Case II: 1, 2, 3, 4, 5
Since we know that a number is divisible by 3, if and only if the sum of its digits is divisible by 3.
Case I, number of 5 digit numbers $= 4 \times 4 \times 3 \times 2 = 96$
Case II, number of 5 digit numbers $= 5 \times 4 \times 3 \times 2 = 120$
∴ Total required numbers $= 216$

49. We can choose two men out of 8 in ${}^{8}C_2$ ways. Since no husband and wife are to play in the same game, two women out of the remaining 6 can be chosen in ${}^{6}C_2$ ways.
If M_1, M_2, W_1, W_2 are chosen, then a team may consist of M_1 and W_1 or M_1 and W_2. Thus the number of ways of arranging the game is
$= {}^{8}C_2 \times {}^{6}C_2 \times 2 = 840$

50. ${}^{n-2}C_3$.

51. Since 8 does not occur in 1000, we have to count the number of times 8 occurs when we list the integers from 1 to 999. Any number between 1 and 999 is of the form xyz, where $0 \le x, y, z \le 9$.
Let us first count the numbers in which 8 occurs exactly once.
Since 8 can occur at one place in ${}^{3}C_1$ ways. There are ${}^{3}C_1 (9 \times 9) = 3 \times 9^2$ such numbers.
Next, 8 can occur in exactly two places in ${}^{3}C_2 (9) = 3 \times 9$ such numbers. Lastly, 8 can occur in all three digits in one number only.
Hence, the number of times 8 occurs is
$1 \times (3 \times 9^2) + 2 \times (3 \times 9) + 3 \times 1 = 300$

52. **Case I** [2] [2] [1]
Number of possible arrangements $= {}^{5}C_2 \times {}^{3}C_2 \times {}^{1}C_1 \times 3 = 90$
Case II [1] [1] [3]
Number of possible arrangements $= {}^{5}C_1 \times {}^{4}C_1 \times {}^{3}C_3 \times 3 = 60$
Hence, the total number of ways is $90 + 60 = 150$.

53. In a chess board there are 8 columns and 8 rows.



Since number of columns = number of rows
Hence it is considered as a square.
∴Number of square in a square of
$n \times n = 1^2 + 2^2 + \ldots + n^2$
Hence required number of squares
$= 1^2 + 2^2 + 3^2 + \ldots + 8^2$
$= \frac{8 \times 9 \times 17}{6} = 204 \qquad \left[\because \Sigma n^2 = \frac{n(n+1)(2n+1)}{6}\right]$

54. $L \quad S_1 \quad S_2 \quad S_3 \quad S_4 \quad S_5 \quad S_6 \quad S_7 \quad M$
Since these five people enter the train during journey it means they must have enter the train after Lucknow. Hence if a person enters at S_1 he can have 7 different tickets for $S_2, S_3, \ldots S_7$ and Mumbai.
Similarly if a person enters at S_2 he can have 6 different tickets and if a person enters at S_3 he can have 5 different tickets and so on.
∴Total numer of possible tickets $= 7 + 6 + 5 + 4 + 3 + 2 + 1$
$= 28$
Now, the five different tickets must be out of these 28 tickets. Therefore, the required number of ways
$= {}^{28}C_5 = 98280$

55. The number of ways of choosing the committee when Ms. B is a member (when Mr. A refuses to serve)
$= {}^{8}C_3 \times {}^{6}C_5$
$= 56 \times 6 = 336$
The number of ways of choosing the committee when Ms. B is not a member (when Mr. A can serve)
$= {}^{8}C_4 \times {}^{7}C_5$
$= 70 \times 21 = 1470$

Scanned by CamScanner

yoursmahboob.wordpress.com

Thus the required number of ways = 336 + 1470 = 1806.

Alternatively : Total number of ways of selecting 4 women and 5 men = ${}^9C_4 \times {}^7C_5 = 2646$.

Number of ways of selecting 4 women and 5 men in which Ms. B and Mr. A are not present together

$= {}^6C_3 \times {}^6C_4 = 840$

Hence the number of ways in which Ms. B and Mr. A do not serve together = 2646 − 840 = 1806

56. Required number of ways = $5 \times 5 \times 5 \times 5 \times 5 = 3125$

57. Required number of arrangements = $5 \times 5 \times 5 \times 5 = 625$

Since we fix cap C_1 in box B_1 then we arrange the remaining 4 caps in any of the 5 boxes.

Alternatively : Total number of arrangements = 5^5

Number of arrangements in which B_1 have cap $C_1 = \frac{5^5}{5} = 5^4$

58. Required number of arrangements = ${}^5P_5$

$\therefore \quad {}^5P_5 = 5 \times 4 \times 3 \times 2 \times 1 = 120$

59. 1 cap can be selected in ${}^5C_1$ ways.

Now this selected cap can be arranged in 5 boxes in ${}^5P_1$ ways.

Again 2 caps can be selected in ${}^5C_2$ ways.

Now, these selected caps can be arranged in 5 boxes in ${}^5P_2$ ways and so on.

Hence the required number of ways

$= {}^5C_1 \times {}^5P_1 + {}^5C_2 \times {}^5P_2 + {}^5C_3 \times {}^5P_3 + {}^5C_4 \times {}^5P_4 + {}^5C_5 \times {}^5P_5$

$= 25 + 200 + 600 + 600 + 120 = 1545$

60. Since all the boxes are filled with exactly one cap and all the caps are identical. Hence the required number of ways = 1.

61. Required number of ways = $\frac{5!}{2!} = 60$

(Since 2 caps are identical)

62. B_3 can be filled in 2! ways and rest can be filled in 4! ways. Hence, required number of ways = $2 \times 4! = 48$.

63. B_1 and B_5 can be filled up in $2 \times 2 = 4$ ways and B_2, B_3, B_4 can be filled up in $= 5 \times 5 \times 5 = 125$ ways.

Hence the required number of ways = $4 \times 125 = 500$

LEVEL (2)

1. First and second prizes can be given in Mathematics in (30×29) ways.

First and second prizes can be given in Physics in (30×29) ways.

First prize can be given Chemistry in 30 ways.

First prize can be given in English in 30 ways.

Hence, the number of ways to give prizes in all the four subjects

$(30 \times 29) \times (30 \times 29) \times 30 \times 30 = (30)^4 \times (29)^2$

2. $1 + 1 \cdot P_1 + 2 \cdot P_2 + 3 \cdot P_3 + 4 \cdot P_4 + \ldots + n \cdot P_n$

$= 1 + 1 + 2 \cdot 2! + 3 \cdot 3! + 4 \cdot 4! + \ldots + n \cdot n!$

$= 1 + [(2! - 1!) + (3! - 2!) + (4! - 3!) + \ldots + ((n+1)! - n!)]$

$= 1 + [(n+1)! - 1!]$

$= (n+1)!$

Alternatively : Consider $n = 1, 2, 3, \ldots$ etc. and then verify the result.

3.

	Row-1	Row-2	Row-3	Row-4
Case 1.	Class 1	Class 2	Class 1	Class 2
Case 2.	Class 2	Class 1	Class 2	Class 1

Required seating arrangement can be done in two ways-case 1 and case 2.

Total numer of arrangements

= Number of arrangements in case 1 + Number of arrangements in case 2

Now, 12 students of class 1 can be seated in 12 chairs in ${}^{12}P_{12}$ ways and 12 students of class 2 can be seated in 12 chairs in ${}^{12}P_{12}$ ways.

Hence, the total number of arrangements

$= (12! \times 12!) + (12! \times 12!) \qquad (\because {}^{12}P_{12} = 12!)$

$= 2(12!)^2$

4. There are 5 even digits *viz.*, 0, 2, 4, 6 and 8. Digit 3 can not be at the tens place, since if 3 is at tens place, then 9 must be at unit place which is impossible. Hence 3 can be only at hundred's place. Now there are two cases :

(1) **When 3 is at hundred's place :** If 3 is at hundred's place, then 9 will be at ten's place. So unit place can be filled up in only 5 ways by using even digits.

So, the total number of even numbers = $1 \times 1 \times 5 = 5$.

(2) **When 3 is not at hundred's place :** In this case hundred's place can be filled up in 8 ways (0 and 3 can not be used). In tens place we can use any one of the 10 digits except 3. So tens place can be filled up in 9 ways and unit place can be filled up in 5 ways by using 0, 2, 4, 6 and 8.

So, the total number of even numbers = $8 \times 9 \times 5 = 360$

Hence the total number of required 3 digit even numbers

$= 5 + 360 = 365$

5. Number of vehicles registered upto RZ 9999

$= 18 \times 26 \times (9999)$

Number of vehicles registered between SA-0001 and SJ 9999 = $1 \times 10 \times 9999$

Therefore number of vehicles registered before SK-0123

$= 18 \times 26 \times 9999 + 1 \times 10 \times 9999 + 122$

$= 9999 \times 478 + 122 = 4779644$

6. Available digits are 1, 2, 3, 4 and 5. Now since we know that a number is divisible by 4 if and only if the number formed by last two digits is divisible by 4. So the following cases are possible.

Thousands	Hundreds	Tens	Unit
x	y	1	2
x	y	2	4
x	y	3	2
x	y	5	2

In each case thousands and hundreds places can be filled up in ${}^3P_2$ ways.

Hence the required number of ways = ${}^3P_2 \times 4 = 24$.

Scanned by CamScanner

yoursmahboob.wordpress.com

7. Total number of seats = $2(3+4) = 14$
Total number of persons = $3 + 9 = 12$
$\therefore$ Total number of required arrangements = ${}^{14}P_{12}$.

8. Three girls can be seated together in a back row on adjacent seats in the following ways :
1, 2, 3 or 2, 3, 4 of first van and 1, 2, 3 or 2, 3 4 of second van.
In each of the above four cases all the three girls can be inter change among themselved in 3! ways.
So the total number of ways = $4 \times 3!$
Now, 9 boys can be seated in remaining 11 seats, which can be done in ${}^{11}P_9$ ways.
Hence, the required number of ways = ${}^{11}P_9 \times 4 \times 3!$

9. 5 '+' (plus) signs can be arranged in 1 way, then we have 6 places to arrange 5 '–' (minus) signs in ${}^6C_5$ ways but since all the minus (–) signs are identical, therefore minus signs can be arranged in only 1 way in 5 chosen places out of 6.
Hence the required number of arrangements = $1 \times {}^6C_5 \times 1 = 6$

10. In order that no two books on Maths be together we first arrange 11 identical books on English which can be done in 1 way.
Now we can choose 9 places out of 12 (11 + 1) places for Maths books, which can be done in ${}^{12}C_9$ ways.
Again since all books on Maths are identical which can be mutually arranged in only 1 way.
Hence the required number of arrangements = $1 \times {}^{12}C_9 \times 1$
$= 220$

11. $1680 = 2^4 \times 3 \times 5 \times 7$
Since if $N = a^p \cdot b^q \cdot c^r \cdot \ldots$
we have number of factors of $N = (p+1)(q+1)(r+1)\ldots$
Hence the total number of factors of the given number
$= (4+1)(1+1)(1+1)(1+1) = 40$

12. $\sum_{k=m}^{n} {}^kC_r = {}^mC_r + {}^{m+1}C_r + {}^{m+2}C_r + \ldots + {}^{(n-1)}C_r + {}^nC_r$
Now assume some values of m and n, then verify the correct result from the choices given in the question.

13. The number of students answering exactly k $(1 \le k \le n-1)$ questions wrongly is $2^{n-k} - 2^{n-k-1}$.
The number of students answering all n questions wrongly is 2^0. Thus, the total number of wrong answers is :
$1(2^{n-1} - 2^{n-2}) + 2(2^{n-2} - 2^{n-3}) + \ldots$
$\ldots + (n-1)(2^1 - 2^0) + n(2^0)$
$= 2^{n-1} + 2^{n-2} + 2^{n-3} + \ldots + 2^0 = 2^n - 1$
$\Rightarrow \quad 2^n - 1 = 2047$
$\Rightarrow \quad 2^n = 2048$
$\Rightarrow \quad n = 11$

14. Required number of triangles = Total number of triangles
– Number of triangles having one side common with the octagon
– Number of triangles having two sides common with the octagon
$= {}^8C_3 - ({}^8C_1 \times {}^4C_1) - 8 = 16$

15. The number of ways of selecting any five numbers from the given set = ${}^{25}C_5$.
Now, the five consecutive numbers can be chosen in the following ways
(1, 2, 3, 4, 5); (2, 3, 4, 5, 6); (3, 4, 5, 6, 7);...(21, 22, 23, 24, 25)
Thus the required number of ways = ${}^{25}C_5 - 21 = 53109$

16. $\because a \ge -1, b \ge -1, c \ge -1, d \ge -1$.
Let $u \ge 0, \quad v \ge 0, \quad w \ge 0, \quad x \ge 0$.
$\therefore \quad a + b + c + d = 12$
$\Rightarrow \quad (u-1) + (v-1) + (w-1) + (x-1) = 12$
$\Rightarrow \quad u + v + w + x = 16$
$\therefore$ Required number of solutions = ${}^{16+4-1}C_{4-1} = {}^{19}C_3$

17. Assume some value of k then find 'n' and hence ${}^nC_2$.
Now, verify the correct option.

18. $42 = 2 \times 3 \times 7$
Here each of a, b and c can take 3 values.
Hence the required number of solutions = $3 \times 3 \times 3 = 27$.

19. Let (r, b, g) denotes the number of red, blue and green balls respectively.
Therefore the possibilities are (0, 10, 0), (2, 7, 1), (4, 4, 2) and (6, 1, 3).
Hence, the required number of ways = 4.

20. Let x_1 be the number of stations before the first halting station, x_2 between first and second, x_3 between second and third, x_4 between third and fourth and x_5 on the right of the fourth station, then
$x_1 \ge 0, \quad x_2, x_3, x_4 \ge 1 \quad$ and $\quad x_5 \ge 0$
such that $x_1 + x_2 + x_3 + x_4 + x_5 = 6$.
Now, the total number of ways is the number of solutions of the above equation.
Let $y_2 \ge 0, \quad y_3 \ge 0, \quad y_4 \ge 0$.
$\therefore \quad x_1 + x_2 + x_3 + x_4 + x_5 = 6$
$\Rightarrow \quad x_1 + (y_2 + 1) + (y_3 + 1) + (y_4 + 1) + x_5 = 6$
$\Rightarrow \quad x_1 + y_2 + y_3 + y_4 + x_5 = 3$
$\therefore$ The number of solutions = ${}^{3+5-1}C_{5-1} = {}^7C_4 = 35$

21. Let x_i denote the marks assigned to the i^{th} question. Then
$x_1 + x_2 + x_3 + \ldots + x_7 + x_8 = 30$
where $\quad i = 1, 2, 3, \ldots, 8 \quad$ and $\quad x_i \ge 2$
and $\quad y_1 + y_2 + \ldots + y_7 + y_8 = 14$
where $\quad y_i = x_i - 2, \quad i = 1, 2, 3, \ldots$
$\therefore$ The total number of solutions of this equation is
${}^{14+8-1}C_{8-1} = {}^{21}C_7$

22. $\therefore$ The exponent of 3 in 33! is 15.

3	33	
3	11	←
3	3	←
	1	←

15

HINT For more information about exponents refer the first chapter of the book.

Scanned by CamScanner

yoursmahboob.wordpress.com

23. There are two distinct possibilities
(i) When any of the four digits may repeat thrice.
(ii) When any two of the four digits may repeat twice.
(i) $\frac{6!}{3!} \times {}^4C_1 = 480$
(ii) $\frac{6!}{2!2!} \times {}^4C_2 = 1080$
Therefore the required number = 480 + 1080 = 1560.

24.

9	10	10	10	10	10	5

$= 4500000$
Since if we fix first digit then unit digit will determine the odd/even nature of the numbers so formed.
But unit place can assume half even and half odd. Hence unit place can assume just 5 digits which makes the sum of previous six digits even.

25. Required number of ways $= {}^6P_4$.

26. Suppose x one rupee coins, y fifty paise coins and z twenty paise coins are selected.
Then $x + y + z = 6$
∴Total number of ways
= Number of solutions of the above equation
$= {}^{6+3-1}C_{3-1} = {}^8C_2 = 28$

27. Required number of times
= Number of selections of 3 children taking at a time
$= {}^8C_3 = 56$

28. Each child will go as often as he or she can be accompanied by two others. Therefore the required number
$= {}^7C_2 = 21$

29. Total number of points = 12
Total number of triangles $= {}^{12}C_3$
But there are 3 cases which must be excluded for the required number of triangles.
Case 1. The number of triangles formed by 3 points on
$AB = {}^3C_3 = 1$
Case 2. The number of triangles formed by 4 points on
$BC = {}^4C_3 = 4$
Case 3. The number of triangles formed by 5 points on
$CA = {}^5C_3 = 10$
Hence, the required number of triangles = 220 − (10 + 4 + 1)
= 205

30. Each question can be attempted in 3 ways *i.e.*, either it can be omitted or one of the two parts can be attempted.
Hence required number of ways $= 3^{10} - 1 = 59048$.

31. Required number of ways $= {}^{16}C_9$.

32. Since each bulb has two choices, either switched on or off, therefore required number $= 2^{10} - 1 = 1023$.

33. Since each digit of a 10 digit number can be written as either 2 or 3, therefore required number of 10 digit number is 2^{10}.

34. Consider some value of n then verify the result.

35. Any divisor of $2^3 \cdot 3^4 \cdot 5^2$ is of the form $2^a \cdot 3^b \cdot 5^c$ where $0 \le a \le 3, 0 \le b \le 4$ and $0 \le c \le 2$ Thus, the sum of the divisors of $2^3 \cdot 3^4 \cdot 5^2$ is

$$(1 + 2 + \ldots + 2^3)(1 + 3 + \ldots + 3^4)(1 + 5 + 5^2)$$
$$= \frac{(2^4 - 1)(3^5 - 1)(5^3 - 1)}{(2-1)(3-1)(5-1)}$$
$$= \frac{15 \times 242 \times 124}{1 \times 2 \times 4} = 56265$$

36. Required number of ways $= {}^{10+4-1}C_{4-1} = {}^{13}C_3 = 286$

37. Since we know that out of n things arranged in a row then we can select r things out of n such that no two of them are adjacent to each other in ${}^{n+1-r}C_r$ ways.
Hence required number of ways $= {}^{10+1-3}C_3 = {}^8C_3 = 56$
Alternatively : To each selection of 3 objects we associated a binary sequence of the form 1001000100 where 1 at i^{th} place means the i^{th} object is selected and 0 at ith place means the i^{th} object is not selected.
There exists one to one correspondence between the set of selections of 3 objects and set of binary sequences containing 7 zeros and 3 ones.
Actually we are concerned with the binary sequences in which 2 ones are consecutive we first arrange 7 zeros.
This can be done in just one way. Now, 3 ones can be arranged at any of the 3 places marked with a cross in the following arrangement.
$$\times 0 \times 0 \times 0 \times 0 \times 0 \times 0 \times 0 \times$$
We can arrange 3 ones at 8 places in ${}^8C_3$ ways = 56

38. Let x_5 be such that $x_1 + x_2 + x_3 + x_4 + x_5 = n$
Now we require the non-negative integral solutions of
$$x_1 + x_2 + x_3 + x_4 + x_5 = n$$
The number of required solutions $= {}^{n+5-1}C_{5-1} = {}^{n+4}C_4$

39. When we arrange things one at a time, the number of possible permutations is n.
When we arrange them two at a time, the number of possible permutations is $n \times n = n^2$ and so on.
Hence, the total number of required permutations is
$$n + n^2 + n^3 + \ldots + n^r = \frac{n(n^r - 1)}{n - 1}$$

40. In a chess board there are 8 columns and 8 rows.
Hence the number of rectangles $= 1^3 + 2^3 + 3^3 + \ldots + 8^3$
$$= \left(\frac{8 \times 9}{2}\right)^2 = 1296$$
Alternatively : A chessboard is a network of 9 vertical and 9 horizontal lines.
Since we know that number of quadrilaterals formed by m vertical and n horizontal lines is ${}^mC_2 \times {}^nC_2$.
Hence the required numer of rectangles $= {}^9C_2 \times {}^9C_2 = 1296$

41. Order of speaking is equivalent to the order of placing the things.
Thus A, B and C can be placed in ${}^{10}C_3$ ways and the remaining 7 persons can be placed in 7! ways.
Hence, the number of ways in which they can speak is
$${}^{10}C_3 \times 7! = \frac{10!}{3!}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Alternatively : All the 10 persons can speak in 10! ways in which A, B and C can speak in 6 different ways.
But we are required to find a single case out of 6 cases in which A speaks before B and B speaks before C.

Hence the required number of ways $= \frac{10!}{3!} = \frac{10!}{6}$

42. Total one digit number = 2
Total two digit numbers = 2^2
Total three digit numbers = 2^3
Total four digit numbers = 2^4
... ...
Total eight digit numbers = 2^8
There are total 9 digit numbers = 2^9
but out of these 2^9 numbers half of the numbers begin with digit 1 and rest half numbers begin with digit 2.
The greatest possible number less than $2 \cdot 10^8$ is 122222222, which in turn is the greatest possible number of 9 digit begin with 1.
Thus the maximum possible number of 9 digit numbers

$$= \frac{2^9}{2} = 2^8$$

Hence, the required total numbers

$$= 2 + 2^2 + 2^3 + 2^4 + \ldots + 2^8 + 2^8$$

$$= \frac{2(2^8 - 1)}{2 - 1} + 2^8 = 2^9 - 2 + 2^8$$

$$= 2^8 (2 + 1) - 2 = 766$$

43. Required number of ways $= {}^{12+1-4}C_4 = {}^9C_4 = 126$.

44. Since $2k < n \Rightarrow k < \frac{n}{2}$

Hence, number of zeros is less than the number of ones.
Now, first of all we arrange $(n - k)$ ones as follows

$$\times 1 \times 1 \times 1 \times 1 \times 1 \times \ldots \times 1 \times$$

The above arrangement leaves $(n - k + 1)$ places marked with $\times$.
Now we can arrange k zeros in the $(n - k + 1)$ places in ${}^{n-k+1}C_k$ ways.

45. Part A can be attempted in 3 ways
(i) The student do not solve the question.
(ii) The student attempts the first part of the question.
(iii) The student attempts the second (*i.e.*, alternative) part of the question.

$\therefore$ Total number of choices in the first part $= 3^5$

Hence, the required number of ways in which a student must attempt at least one question $= 3^5 - 1 = 242$
Similarly we can show that there are $2^4 - 1$
i.e., 15 choices for part B.
Hence the required number of ways $= 242 \times 15 = 3630$.

46. Required number of number plates of licences $= (26)^2 \times (999)$
$= 675324$

47. Required number of plates $= {}^{26}P_2 \times {}^{10}P_3 = 468000$

48. We can arrange r persons on m chairs on a particular side in ${}^mP_r$ ways and s persons on m chairs on the other side in ${}^mP_s$ ways. Now, we can arrange $(2m - r - s)$ persons on the remaining $(2m - r - s)$ chairs in ${}^{(2m-r-s)}P_{(2m-r-s)}$ ways.
Thus, the required number of ways of arranging the persons

$$= ({}^mP_r)({}^mP_s)({}^{2m-r-s}P_{2m-r-s})$$

49. The diagram of roads can be as follows :



Suppose the distance between two successive parallel roads be one unit then a person can travel $(m - 1)$ steps in north-south direction and he can travel $(n - 1)$ steps in east-west direction.
Thus he has to travel $\{(m - 1) + (n - 1)\} = (m + n - 2)$ steps to reach from one corner to diagonally opposite corner.
Thus he can arrange his steps in

$${}^{(m+n-2)}C_{(m-1)} \times {}^{(n-1)}C_{(n-1)} \text{ ways}$$

i.e., ${}^{m+n-2}C_{m-1}$ ways.

50. The required number of ways is equal to the number of ways in which they can select the same number of toys from the collection of their combined number of toys – the number of ways in which each can select her original toys.
Hence, required number of ways $= ({}^{19}C_{11} \times {}^8C_8) - 1$
$= {}^{19}C_{11} - 1$

51. Go through options.

52. The number of ways of choosing 26 cards out of 52 cards is ${}^{52}C_{26}$. There are two ways in which each card can be dealt because a card can be either from a first pack or from the second pack.
Hence, the number of ways in which the card can be dealt is

$${}^{52}C_{26} \times 2^{26}$$

53. There are 4 suits and each suit contains 13 cards so we can select any one card from the first suit in 13 ways. Similarly we can select one card different from the first card out of second suit in 12 ways and so on.
Hence, the required number of ways $= 13 \times 12 \times 11 \times 10$

$$= \frac{13!}{9!}$$

54. First digit (*i.e.*, ten thousands place) can be filled up in 2! ways by the digit 3, but since 3 is being repeated twice, hence the actual number of ways $= \frac{2!}{2!} = 1$

Remaining 4 places can be filled up in 4! ways but since zero is being repeated thrice hence the actual number of ways

$$= \frac{4!}{3!} = 4$$

$\therefore$ The required number of ways $= 1 \times 4 = 4$.

55. Digit 5 can be placed in any one of the 4 places in 4 ways. Now the remaining 3 places can be filled up with remaining 8 digits in 8^3 ways.
Hence, the required number of ways $= 4 \times 8^3 = 2048$.

Scanned by CamScanner

yoursmahboob.wordpress.com

56. Required number of ways $= 4 \times 8 \times 7 \times 6 = 1344$

57. Digit 2 can be arranged in two places out of 8 places in $\frac{{}^8P_2}{2!}$ ways.
Now, the remaining 6 places can be filled by the rest 3 digits in 3^6 ways.
Hence, the required number of ways $= \frac{{}^8P_2}{2!} \times 3^6$
$= {}^8C_2 \times 3^6 = 20412$

58. Required number of ways $= 3^8 = 6561$.

59. Since chairs are numbered, hence these are distinguishable.
Therefore 3 boys can be arranged in 3! ways on alternate chairs and 3 girls can be arranged in remaining 3 chairs in 3! ways.
Also 3 girls can be arranged before the boys are arranged.
Hence the required number of ways $= 2 \times (3!)^2 = 72$

60. First rook can be selected in 64 ways $({}^{64}C_1)$.
Second rook can not be selected from the same row and same column from which the first rook has been selected hence there are only $64 - (8 + 7) = 49$ places for the second rook.
Hence, the second rook can be selected in ${}^{49}C_1$ ways.
$\therefore$ Required number of ways $= {}^{64}C_1 \times {}^{49}C_1 = 3136$.

61. Number of white shoes = 9 pairs
$\Rightarrow$ 9 left and 9 right shoes
Number of black shoes = 6 pairs
$\Rightarrow$ 6 left and 6 right
In such questions we always consider the worst situation.
Therefore we assume that initially we get $6 + 6 = 12$ black shoes and 9 white shoes either left or right.
Thus we have taken out $12 + 9 = 21$ shoes still we don't have required pair of white shoes.
Now we drawout just one white shoe which will fulfill our requirement of getting one pair of white shoes.
[One pair of white shoes means 1 left shoe and 1 right shoe.]
Thus we have to draw out $12 + 9 + 1 = 22$ shoes to get correct pair of white shoes.

62. The worst possible situations are :

White	Black
9 left	6 left
9 left	6 right
9 right	6 left
9 right	6 right

Thus before getting the required correct pair of shoes we have to draw out $9 + 6 = 15$ shoes.
Now when we will draw out one more shoe which will give the required combination of correct shoes either white or black.
Hence we have to draw out minimum $15 + 1 = 16$ shoes.

63. We can not put only one incorrect ball since if we make a wrong choice it will simultaneously make another choice wrong. For example if we put red colour ball in either of green, blue or black box then we have to fill the red colour box with different colour ball, hence one colour combination can never be wrong.
Since atleast two combinations will be different.

64. Select any two balls out of 4 then interchange the combination of colours.
Hence the required number of ways $= {}^4C_2 = 6$.
Alternatively :

$\begin{Bmatrix} R & B & G & W \\ B & R & G & W' \end{Bmatrix}$ $\begin{Bmatrix} R & B & G & W \\ G & B & R & W \end{Bmatrix}$
$\begin{Bmatrix} R & B & G & W \\ W & B & G & R' \end{Bmatrix}$ $\begin{Bmatrix} R & B & G & W \\ R & G & B & W \end{Bmatrix}$
$\begin{Bmatrix} R & B & G & W \\ R & W & G & B' \end{Bmatrix}$ $\begin{Bmatrix} R & B & G & W \\ R & B & W & G \end{Bmatrix}$

65. For one digit number 1 to $9 \rightarrow 1 \times 9 = 9$
For two digit numbers 10 to $99 \rightarrow 2 \times 90 = 180$
For threee digit numbers 100 to $300 \rightarrow 3 \times 201 = 603$
Hence, total number of required digits $= 9 + 180 + 603 = 792$

66. Four odd digits (1, 1, 3, 3) can be arranged in 4 odd places in $\frac{4!}{2!2!} = 6$ ways.
Now the remaining 3 even digits (2, 2, 4) can be arranged in 3 even place in $\frac{3!}{2!} = 3$ ways.
Hence the required number of ways $= 6 \times 3 = 18$.

67. Each of the 7 balls can be distributed into 5 ways.
Hence the required number of ways $= 5^7$.

68. There can be two cases
(1) 1, 1, 1, 1, 3
(2) 1, 1, 1, 2, 2
Case 1. A box (in which 3 balls can be put) is selected in ${}^5C_1$ ways.
Now, 3 balls can be selected in ${}^7C_3$ ways and remaining 4 balls can be arranged in 4! ways.
Hence, total number of ways $= {}^5C_1 \times {}^7C_3 \times 4!$
Case 2. 2 boxes (in which 2–2 balls can be put) are selected in ${}^5C_2$ ways.
Now, any two ball can be selected in ${}^7C_2$ ways and for the other selected box, 2 balls can be selected from the remaining 5 balls in ${}^5C_2$ ways and the remaining balls can be distributed in 3! ways.
Hence, the total number of ways $= {}^5C_2 \times ({}^7C_2 \times {}^5C_2) \times 3!$
$\therefore$ The required number of ways
$= ({}^5C_1 \times {}^7C_3 \times 4!) + ({}^5C_2 + {}^7C_2 \times {}^5C_2 \times 3!) = 16800$

69. Required number of ways $= {}^{7+5-1}C_{5-1}$ (using ${}^{n+r-1}C_{r-1}$)
$= {}^{11}C_4 = 330$

70. Possible ways of distribution are as follows :
(i) (7) (ii) (6 + 1)
(iii) (5 + 2) (iv) (4 + 3)
(v) (5 + 1 + 1) (vi) (4 + 2 + 1)
(vii) (3 + 2 + 2) (viii) (3 + 3 + 1)
(ix) (4 + 1 + 1 + 1) (x) (3 + 2 + 1 + 1)
(xi) (2 + 2 + 2 + 1) (xii) (3 + 1 + 1 + 1 + 1)
(xiii) (2 + 2 + 1 + 1 + 1)
Hence total number of ways of distribution = 13

71. There is only one way, which is as follows :
1, 2, 1, 2, 1.

Scanned by CamScanner

yoursmahboob.wordpress.com

72. One ball can be selected for the box 2 in ${}^7C_1$ ways and two balls can be selected out of remaining 6 balls for the box 4 in ${}^6C_2$ ways and the remaining 4 balls can be distributed in 3 boxes in 3^4 ways.
Hence, the required number of ways = ${}^7C_1 \times {}^6C_2 \times 3^4 = 8505$

73. Ball 2 can be distributed between 2 boxes (*viz.*, box 2 and box 4) in 2 ways.
Now, the remaining 6 balls can be distributed in any of the 5 boxes in 5^6 ways.
Hence, the required number of ways = 2×5^6 ways
= 31250 ways

74. Required number of distribution
= Total number of distribution
– Number of distribution in which ball 2 and ball 4 are together.
Here total number of distribution (as calculated in question number 68) = 16800.
Now, consider ball 2 and ball 4 are stuck together and this arrangement is assumed to be a single ball.
Thus we have 6 balls to be distributed into 5 boxes. Which can be done as 1, 1, 1, 1, 2 in ${}^5C_1 \times {}^6C_2 \times 4!$ ways = 1800.
${}^5C_1 \rightarrow$ Number of ways of selecting one box in which two balls are kept together.
${}^6C_2 \rightarrow$ Number of ways of selecting 2 balls out of 6 balls.
$4! \rightarrow$ Number of ways of distribution of remaining 4 balls in remaining 4 boxes.
Hence, the required number of ways = 16800 – 1800 = 15000

75. Required number of ways = 3^4.

76. Following 4 distributions are possible :
(4, 0, 0), (3, 1, 0), (2, 2, 0), (2, 1, 1)

77. Required number of ways = ${}^{4+3-1}C_{3-1}$ (using ${}^{n+r-1}C_{r-1}$)
= ${}^6C_2 = 15$

78. Since pots are identical then there will be 4 cases (4, 0, 0), (3, 1, 0), (2, 2, 0) and (2, 1, 1) but since all coins are different hence selection of coins matters.
Therefore for the first case number of selections = ${}^4C_4 = 1$
For the second case number of selections = ${}^4C_3 \times {}^1C_1 = 4$
For the third case number of selections = $\frac{{}^4C_2 \times {}^2C_2}{2!} = 3$
For the fourth case number of selections
$$= \frac{{}^4C_2 \times {}^2C_1 \times {}^1C_1}{2!} = 6$$
Hence the total number of distributions = 1 + 4 + 3 + 6 = 14.

79. Since no box is empty and all pots are identical so the possible case is (1, 1, 2).
But since all the coins are different, then the 2 balls can be selected in ${}^4C_2$ ways and rest can be put in $\frac{{}^2C_1 \times {}^1C_1}{2!}$ ways.
Hence, the required number of distribution
$$= \frac{{}^4C_2 \times {}^2C_1 \times {}^1C_1}{2!} = 6$$

80. Since no pot is empty and all coins are identical, the possible case is (1, 1, 2).
But since all three pots are different hence a pot (which contains 2 coins together) can be selected in ${}^3C_1$ ways.
Hence the required number of distribution = ${}^3C_1 \times 1 = 3$

81. The possible arrangements are as follows :
(4, 0, 0) → can be done in 2 ways
i.e., 4 balls can be put either one of the two identical pots or can be put in different pot.
(3, 1, 0) → can be done in 3 ways
either distinct pot can be filled up with 3 balls, or 1 ball or remained empty.
(2, 2, 0) → can be done in 2 ways
either distinct pot can be filled by 2 balls or remained empty.
(2, 1, 1) → can be done in 2 ways
either distinct pot can be filled up with 1 ball or 2 ball.
Hence, the required number of ways = 2 + 3 + 2 + 2 = 9.

82. The possible arrangements are as follows :
(4, 0, 0) → can be done in 3 ways
let the 4 coins be *A*, *A*, *B* and *C* then all these 4 coins as a single packet of coins can be arranged 3 different pots in 3 ways.
(3, 1, 0) → can be done in 18 ways
out of *A*, *A*, *B* and *C* we can select one coin in 3 ways *i.e.*, either *A* or *B* or *C*.
Now we can arrange this selected coin in any 3 pots in 3 ways and the remaining 3 coins as a single packet of coins can be arranged in remaining 2 pots in 2 ways.
Hence, the required number of ways = $3 \times 3 \times 2 = 18$.
(2, 2, 0) → can be done in 12 ways
There are two possible cases :
(i) (*A*, *A*), (*B*, *C*)
(ii) (*A*, *B*), (*A*, *C*)
In each of two cases we assume that there are two packets of coins which can be arranged in $3 \times 2 = 6$ ways.
Since there are two cases, hence the total number of required ways = $6 \times 2 = 12$.
(2, 1, 1) → can be done in 21 ways.
There are 4 possible cases :
(i) (*A*, *A*), (*B*), (*C*) (ii) (*A*, *B*), (*A*), (*C*)
(iii) (*A*, *C*), (*A*), (*B*) (iv) (*B*, *C*), (*A*), (*A*)
For the first 3 cases in each cases all the 3 packets of coins can be arranged in 3! ways.
Hence, the number of arrangements = $3 \times 3! = 18$.
Now in the fourth (iv) case two coins are identical so the third packet of coins can be arranged in 3 pots in 3 ways.
Hence, the total number of arrangements = 18 + 3 = 21.
Thus the required number of ways = 3 + 18 + 12 + 21 = 54 ways.

Scanned by CamScanner

yoursmahboob.wordpress.com

Final Round

1. ${}^6P_2 = 30$.
2. ${}^6C_2 = 15$
3. 3 lines intersect each other in ${}^3C_2 = 3$ points.
   3 circles intersect each other in ${}^3P_2 = 6$ points.
   Every line cuts 3 circles into 6 points. Therefore 3 lines cuts 3 circles into 18 points.
   Therefore, the maximum number of points = 3 + 6 + 18 = 27
4. $\frac{8!}{4!4!} = 70$
5. Required number of triangles $= {}^{m+n}C_3 - {}^mC_3 - {}^nC_3$.
6. Number of even places = 4
   Number of evendigits = 5 (2, 2, 8, 8, 8)
   Number of odd places = 5
   Number of odd digits = 4 (3, 3, 5, 5)
   Odd digits can be arranged in $\frac{4!}{2!\times 2!}$ ways = 6 ways.
   Even digits can be arranged in $\frac{5!}{2!\times 3!} = 10$ ways.
   Hence the required number of ways = $6 \times 10 = 60$ ways.
7. Required number of triangles $= {}^{m+n+k}C_3 - {}^mC_3 - {}^nC_3 - {}^kC_3$
8. Let $n = 2m + 1$, for the three numbers are in AP we have the following patterns :

Common differences	Numbers	Number of ways
1	(1, 2, 3)(2, 3, 4) ... $(n-2, n-1, n)$	$(n-2)$
2	(1, 3, 5), (2, 4, 6) ... $(n-4, n-2, n)$	$(n-4)$
3	(1, 4, 7), (2, 5, 8) ... $(n-6, n-3, n)$	$(n-6)$
—	... ...	—
—	... ...	—
m	$(1, m+1, 2m+1)$	1

   ∴ Favourable number of ways
   $= (n-2) + (n-4) + (n-6) + \ldots + 3 + 1$ (total m terms)
   $= \frac{m}{2}(n - 2 + 1)$
   $= \frac{(n-1)}{2} \cdot \frac{(n-1)}{2} = \frac{(n-1)^2}{4}$
   Alternatively : Consider some proper value of n and verify the result.
9. Required number of parts $= 1 + \sum_{r=1}^{8} r$
   $= 1 + \frac{8\times 9}{2} = 37$
10. $\frac{240}{4n+2} = k \in I$
    ∴ $k = \frac{120}{2n+1} = \frac{2^3 \times 3 \times 5}{2n+1}$
    Since probable divisors are 1, 3, 5, 7, 9, 11, 13, ..., $(2n + 1)$ but we have only 4 possible divisors 1, 3, 5, 15.
11. Total number of rectangles
    $= (1 + 2 + 3 + \ldots + 12) \times (1 + 2 + \ldots + 8)$
    $= \frac{12\times 13}{2} \times \frac{8\times 9}{2} = 2808$
    Total number of squares
    $= (12\times 8) + (11\times 7) + (10\times 6) + \ldots + (5\times 1) = 348$
    ∴ Required number of rectangles = 2808 − 348 = 2460

HINT Number of squares $= \sum_{r=1}^{8} (13 - r)(9 - r)$

12. Required number of triangles $= ({}^{2n}C_3 - {}^nC_3 - {}^nC_3) + (n \times n)$
    $= n^2 (n-1) + n^2 = n^3$
    Alternatively : Required number of triangles
    $= ({}^nC_2 \times {}^nC_1) + ({}^nC_1 \times {}^nC_2) + (n \times n) = n^3$
13. There are 12 ways as follows :
    (9, 0, 0), (8, 1, 0), (7, 2, 0), (6, 3, 0), (5, 4, 0), (7, 1, 1), (6, 2, 1), (5, 3, 1), (5, 2, 2), (4, 4, 1) (4, 3, 2), (3, 3, 3).
14. First of all we give 4 coins to each of the six persons so that each one must have at least 4 coins.
    Now we are left with = 30 − (6 × 4) = 6 coins.
    These remaining 6 coins can be distributed among 6 persons in such a way that any one can receive any number of coins which can be done in ${}^{6+6-1}C_{6-1} = {}^{11}C_5$ ways
    = 462 ways
15. Required number of circles = ${}^{10}C_3 - {}^7C_3 = 85$.
16. 0 can not be placed as the left most digit so we have only 9 digits to be placed.
    Also we will not consider 1 digit numbers.
    Now we can form a two digit number in ${}^9C_2$ ways.
    Now we can form a three digit number in ${}^9C_3$ ways.
    Now we can form a four digit number in ${}^9C_4$ ways.
    ... ...
    ... ...
    We can form 9 digit number in ${}^9C_9$ way.
    Hence the required numbers = ${}^9C_2 + {}^9C_3 + {}^9C_4 + \ldots + {}^9C_9$
    = 502
17. The possible ways are
    (25×4)
    $(22 \times 4 + 2 \times 6)$
    $(19 \times 4 + 4 \times 6)$
    $(16 \times 4 + 6 \times 6)$
    $(13 \times 4 + 8 \times 6)$
    $(10 \times 4 + 10 \times 6)$
    $(7 \times 4 + 12 \times 6)$
    $(4 \times 4 + 14 \times 6)$
    $(1 \times 4 + 16 \times 6)$
    Hence there are total 9 ways.
18. Total number of permutations = 8! = 40320
    Number of permutations when word LURY occurs
    = (8 − 4 + 1)! = 5! = 120

Scanned by CamScanner

yoursmahboob.wordpress.com

Number of permutations when word MINA occurs = 5! = 120
Number of permutation when words LURY and MINA both occurs = 3! = 6
Required number of permutations

$$= 40320 - (120 + 120) + 6 = 40086$$

19. 5 students can be selected out of 10 students in ${}^{10}C_5$ ways remaining 5 students can be selected in ${}^{5}C_5$ ways. These students (in each row) can be arranged mutually in $5! \times 5!$ ways.
Besides it the two set of papers can be arranged in 2! ways between two rows.
Hence, the required number of arrangements

$$= {}^{10}C_5 \times (5!)^2 \times 2 = 7257600$$

20. ${}^{n}C_2 + 2n = 65$
Now, for convenience go through options.

21. First of all deduce $3 \times 10 = 30$ marks to assign atleast 3 marks to each of the 10 students.
Now remaining 20 marks can be assigned to 10 students in ${}^{20+10-1}C_{10-1}$ ways $= {}^{29}C_9$ ways

22.

$$\left[\frac{1}{3}\right] = \left[\frac{1}{3} + \frac{1}{100}\right] = \left[\frac{1}{3} + \frac{2}{100}\right]$$

$$= \ldots \left[\frac{1}{3} + \frac{65}{100}\right] = \left[\frac{1}{3} + \frac{66}{100}\right] = 0$$

and $\left[\frac{1}{3} + \frac{67}{100}\right] = \left[\frac{1}{3} + \frac{68}{100}\right] = \left[\frac{1}{3} + \frac{69}{100}\right]$

$$= \ldots \left[\frac{1}{3} + \frac{98}{100}\right] = \left[\frac{1}{3} + \frac{99}{100}\right] = 1$$

Hence, $E = \left[\frac{1}{3}\right] + \left[\frac{1}{3} + \frac{1}{100}\right] + \ldots + \left[\frac{1}{3} + \frac{99}{100}\right]$

$$= 33 \times 1 = 33$$

23. Total numbers $= 10^6$ $(1, 2, 3, 4, \ldots, 10^6)$

$$n^2 \Rightarrow \begin{Bmatrix} 1, 4, 9, 16, 25, \ldots 10^6 \\ 1, 2, 3, 4, 5, \ldots (10^3) \end{Bmatrix} \rightarrow 10^3 = 1000$$

$$n^3 \Rightarrow \begin{Bmatrix} 1, 8, 27, 64, 125, \ldots, 10^6 \\ 1, 2, 3, 4, 5, \ldots, (10^2) \end{Bmatrix} \rightarrow 10^2 = 100$$

$$n^4 \Rightarrow \begin{Bmatrix} 1, 16, 81, 256, \ldots, 923521 \\ 1, 2, 3, 4, \ldots, 31 \end{Bmatrix} \rightarrow 31$$

HINT $\sqrt[4]{10^6} = 10^{6/4} = 10^{3/2} = \sqrt{1000} \Rightarrow 31$

$$n^2 \cap n^3 \Rightarrow n^6 \begin{Bmatrix} 1, 64, 729, 4096, \ldots, 10^6 \\ 1, 2, 3, 4, \ldots, 10 \end{Bmatrix} \rightarrow 10$$

$$n^3 \cap n^4 \Rightarrow n^{12} \begin{Bmatrix} 1^{12}, 2^{12}, 3^{12} \\ 1, 2, 3 \end{Bmatrix} \rightarrow 3$$

HINT $\sqrt[12]{10^6} = 10^{6/12} = 10^{1/2} = \sqrt{10} \Rightarrow 3$

$$n^2 \cap n^4 \Rightarrow n^4 \begin{Bmatrix} 1, 16, 81, 256, \ldots, (31)^4 \\ 1, 2, 3, 4, \ldots, 31 \end{Bmatrix} \rightarrow 31$$

$$n^2 \cap n^3 \cap n^4 \Rightarrow n^{12} \begin{Bmatrix} 1^{12}, 2^{12}, 3^{12} \\ 1, 2, 3 \end{Bmatrix} \rightarrow 3$$

Hence the number of numbers which are either perfect square or perfect cube or perfect fourth powers or all of these

$$= n^2 + n^3 + n^4 - (n^2 \cap n^3 + n^3 \cap n^4 + n^2 \cap n^4)$$

$$= 1131 - 44 + 3 = 1090$$

Hence, the required number of ways
= Total numbers − Numbers which are perfect squares or perfect cubes or perfect fourth powers

$$= 10^6 - 1090 = 998910$$

24. Total number of required seats $= 1 + m + 2n$
The Grandchildren can occupy the n seats on either side of the table in $({}^{2n}P_{2n})$ ways. Remaining seats are $(1 + m)$.
Since grandfather can not occupy adjacent seats of the grandchildren hence the grandfather can access only $m + 1 - 2 = m - 1$ seats. Hence he can occupy a seat in ${}^{(m-1)}P_1$ ways.
Now the remaining seats can be occupied in ${}^{m}P_m$ ways by the 'm' sons and daughters.
Hence the required number of ways $= {}^{2n}P_{2n} \times {}^{m}P_m \times {}^{m-1}P_1$

$$= (2n!)\,(m!)\,(m-1)$$

25. The 4 possible cases are as follows :

C_1	C_2	C_3
2	3	1
2	2	2
1	4	1
1	3	2

$C_1 \rightarrow$ First column
$C_2 \rightarrow$ Second column
$C_3 \rightarrow$ Third column

Hence, the required number of ways

$$= {}^{2}C_2 \times {}^{4}C_3 \times {}^{2}C_1 + {}^{2}C_2 \times {}^{4}C_2 \times {}^{2}C_2 + {}^{2}C_1 \times {}^{4}C_4 \times {}^{2}C_1 + {}^{2}C_1 \times {}^{4}C_3 \times {}^{2}C_2$$

$$= 1 \times 4 \times 2 + 1 \times 6 \times 1 + 2 \times 1 \times 2 + 2 \times 4 \times 1$$

$$= 8 + 6 + 4 + 8 = 26$$

26. The total number of balls in the box $= 2 + 3 + 4 = 9$.
Total number of selections of 3 balls out of 9 balls $= {}^{9}C_3$
Number of selections in which no any green ball is selected $= {}^{6}C_3$
Hence the required number of selections $= {}^{9}C_3 - {}^{6}C_3 = 64$.

27. There are 4 possible cases :

$H \rightarrow$ Husband's
Relatives
$W \rightarrow$ Wife's relatives

	H	W
M	0	3
F	3	0

H	W
1	2
2	1

H	W
2	1
1	2

H	W
3	0
0	3

$M \rightarrow$ Male
$F \rightarrow$ Female

Hence, the required number of ways

$$= ({}^{4}C_3 \times {}^{4}C_3) + ({}^{3}C_1 \times {}^{4}C_2)({}^{4}C_2 \times {}^{3}C_1) + ({}^{3}C_2 \times {}^{4}C_1)({}^{4}C_1 \times {}^{3}C_2) + ({}^{3}C_3 \times {}^{3}C_3)$$

$$= (4 \times 4) + (3 \times 6 \times 6 \times 3) + (3 \times 4 \times 4 \times 3) + (1 \times 1)$$

$$= 485$$

28. Let the number of men participating in the tournament be n.
Since every participant played two games with every other participant.
Therefore the total number of games played among men is $2 \times {}^{n}C_2 = n\,(n-1)$.
And the number of games played with each woman $= 2n$.
but since there are two women, hence the total number of games men played with 2 women $= 2 \times 2n = 4n$

$$\therefore \quad \{n\,(n-1)\} - 4n = 66$$

$$\Rightarrow \quad n^2 - 5n - 66 = 0$$

Scanned by CamScanner

yoursmahboob.wordpress.com

$n = 11$ ($\because n < 0$, is not possible)

$\Rightarrow$ $\therefore$ Number of participants = 11 men + 2 women = 13.

29. Number of games played by them is $2(^{13}C_2) = 156$.

30. There are two possible cases in which 12 sweets can be distributed among 10 girls.

(i) Any 9 girls get one sweets each and the remaining 1 girl gets 3 sweets.

(ii) Any 8 girls get one sweets each and the remaining 2 girls get 2 piece of sweets each.

Case 1. 3 pieces of sweets can be given to a girl in the following four way :

Burfi	3	2	1	0
Rasgulla	0	1	2	3

After giving 3 pieces of sweets to a single girl. We can distribute the remaining. 9 sweets to the 9 girls in the following ways :

$$^9C_3 \times {}^6C_6 + {}^9C_4 \times {}^5C_5 + {}^9C_5 + {}^4C_4 + {}^9C_6 \times {}^3C_3$$
$$= 2(^9C_3 + {}^9C_4)$$

One particular girl can be chosen in $^{10}C_1$ ways.

Therefore 3 sweets can be given to a single girl in

$$^{10}C_1 \times 2 \times (^9C_3 + {}^9C_4) = 4200 \text{ ways.}$$

Case II. We can give two sweets to two girls (say A and B) in the following ways :

A	Burfi	2	1	0	2	1	0	2	1	0
	Rasgulla	0	1	2	0	1	2	0	1	2
B	Burfi	2	2	2	1	1	1	0	0	0
	Rasgulla	0	0	0	1	1	1	2	2	2

Now, remaining 8 pieces of sweets can be distributed among eight girls in the following ways

$$(^8C_2 \times {}^6C_6) + (^8C_3 \times {}^5C_5) + (^8C_4 \times {}^4C_4) + (^8C_3 \times {}^5C_5)$$
$$+ (^8C_4 \times {}^4C_4) + (^8C_5 \times {}^3C_3)$$
$$+ (^8C_4 \times {}^4C_4) + (^8C_5 \times {}^5C_5) + (^8C_6 \times {}^2C_2)$$
$$= 2(^8C_2) + 4(^8C_3) + 3(^8C_4)$$

Further, two girls can be selected in $^{10}C_2$ ways.

Therefore two girls can get two sweets each in

$$(^{10}C_2)[2(^8C_2) + 4(^8C_3) + 3(^8C_4)] = 22050 \text{ way}$$

Hence, the required number of ways = 4200 + 22050

$$= 26250$$

31. Number of common children of Mr. John and Ms. Bashu

$$= 10 - (x + x + 1) = 9 - 2x$$

Let N = The number of fights between children of different parents

= (Total number of fights that can take place among all the children)

− (The number of fights among the children of the same parents)

$$= {}^{10}C_2 - [{}^xC_2 + {}^{x+1}C_2 + {}^{9-2x}C_2] \quad \ldots(i)$$

$$= 45 - \left[\frac{x(x-1)}{2} + \frac{(x+1)(x)}{2} + \frac{(9-2x)(8-2x)}{2}\right]$$

$$= 45 - \frac{1}{2}[x^2 - x + x^2 + x + 72 - 34x + 4x^2]$$

$$= \frac{397}{12} - 3\left(x - \frac{17}{6}\right)^2$$

For N to be maximum, x must be $\frac{17}{6}$. As x can not be in fraction, we take $x = 3\left(\approx \frac{17}{6}\right)$.

Thus, maximum value of $N = 33$ which is attained at $x = 3$.

Alternatively : After making the equation (i) go through options.

32. Let the form of the required numbers be $a_1, a_2 \ldots a_9$, where $0 \le a_1 \le 1$ and $0 \le a_i \le 2$ for $i = 2, 3, \ldots, 9$ and where all $a_1, a_2, \ldots, a_9$ can not be equal to zero.

Now, we can choose a_1 in two ways (0 or 1) and a_i for $i = 2, 3, \ldots 8$ in 3 ways (0, 1, 2).

After selecting $a_1, a_2, a_3 \ldots, a_8$ we find the sum $s = a_1 + a_2 + \ldots a_8$ which is of the form $3m - 2$, $3m - 1$ or $3m$.

Now we can select a_9 in just one way.

Actually a_9 can be selected out of 2, 1 or 0 depending on whether $s = 3m - 2$, $3m - 1$ or $3m$. Therefore, we can choose the numbers in $2 \times 3^7 \times 1 = 4374$ ways.

But this includes the case in which each of $a_i = 0$. Thus, the required number of numbers = 4374 − 1 = 4373

33. The digits which can be recognised as digits on the screen of a calculator when they are read inverted *i.e.*, upside down are 0, 1, 2, 5, 6, 8 and 9.

Since a number can not begin with zero hence left most digit and right most digit can never be 0 as when an 'n' digit number read upside down it will become a number of less than n digit.

Hence,

Number of digits	Total number of numbers
1	7
2	$6 \times 6 = 6^2$
3	$6 \times 7 \times 6 = 6^2 \times 7$
4	$6 \times 7 \times 7 \times 6 = 6^2 \times 7^2$
5	$6 \times 7 \times 7 \times 7 \times 6 = 6^2 \times 7^3$
6	$6 \times 7 \times 7 \times 7 \times 7 \times 6 = 6^2 \times 7^4$

Thus, the number of required numbers

$$= 7 + 6^2 + 6^2 \cdot 7 + \ldots + 6^2 \cdot 7^4$$

$$= 7 + 6^2 \frac{(7^5 - 1)}{(7 - 1)} = 7 + 6(7^5 - 1)$$

$$= 6 \cdot 7^5 + 1 = 100843$$

34. Since rings are distinct, hence they can be named as R_1, R_2, R_3, R_4 and R_5.

The ring R_1 can be placed on any of the four fingers in 4 ways.

The ring R_2 can be placed on any of the four fingers in 5 ways since the finger in which R_1 is placed now has 2 choices, one above the R_1 and one below the ring R_1.

Similarly R_3, R_4 and R_5 can be arrange in 6, 7 and 8 ways respectively.

Hence, the required number of ways

$$= 4 \times 5 \times 6 \times 7 \times 8 = 6720$$

Scanned by CamScanner

yoursmahboob.wordpress.com

35. We can select first object out of n objects in ${}^nC_1$ ways.

Now, number of ways of choosing two objects such that they are always together $(n-4)$ ways.

Since we assume two objects as a single object. Further we can select three objects *viz.*, the one object which has been already selected and two objects of one either side of the first object.

Therefore the number of ways of choosing two objects such that they are not together

$$= {}^{(n-3)}C_2 - (n-4) = \frac{1}{2}(n-4)(n-5)$$

Since these two objects can be arranged in 2! ways, the number of ways of choosing three objects (in order of the first, second and third) is

$$n \times \frac{1}{2}(n-4)(n-5) \times 2 = n(n-4)(n-5)$$

But, since the order in which the objects are taken is immaterial, the number of ways of choosing the objects is $\frac{1}{6}n(n-4)(n-5)$

36.

Number of similar letters	Number of different letters	Number of selections
5	0	${}^1C_1 = 1$
4	1	${}^4C_1 \times {}^2C_1 = 8$
3	2	${}^3C_1 \times {}^4C_2 = 18$
3 of one type and 2 of another type	0	${}^3C_1 \times {}^3C_1 = 9$
2 of one type and 2 of another type	1	${}^4C_2 \times {}^3C_1 = 18$
2	3	${}^4C_1 \times {}^4C_3 = 16$
0	5	${}^5C_5 = 1$

Hence, the total number of selections

$$= 1 + 8 + 18 + 9 + 18 + 16 + 1 = 71$$

37.

	1st paper	2nd paper	3rd paper	4th paper
Max. marks	n	n	n	$2n$

Let us consider $n = 1$, then a candidate required 3 marks out of 5 marks, which can be done in the following ways :

1st paper	2nd paper	3rd paper	4th paper	Total
0	0	1	2	3
0	1	0	2	3
1	0	0	2	3
1	1	1	0	3
1	1	0	1	3
1	0	1	1	3
0	1	1	1	3

Hence, there are total 7 ways.

Now, go through options.

Let us consider option (b).

Putting $n = 1$, we get

$$\frac{1}{6}(1+1)(5 \times 1^2 + 10 \times 1 + 6) = 7$$

Hence the choice (b) is correct.

38. Do this problem similarly as discussed in the previous problem.

NOTE The general solution of this type of problems involves higher mathematics. But we have given in question number 37 a very simple, lucid and a novel solution for the lay students.

Scanned by CamScanner

yoursmahboob.wordpress.com

20 PROBABILITY

Generally this chapter is considered as an extension of permutation and combination, since it is as logical in nature as permutation and combination. I hope that you must have been well-versed with the permutation and combination (previous chapter) which will enable you to solve the problems of this chapter quickly and easily. This chapter is important for XAT, SNAP and other MBA entrance tests. Over the past years CAT has shown no great interest in this chapter, still you should learn it heartly due to uncertain syllabus and irregular pattern of CAT. Remember that so far CAT has asked very simple and logical problems from this chapter which could be solved by applying just commonsense.

The literal meaning of probability is the chance of occurrence of an event. For example, if a person is standing at the crossing of two roads which direct towards North, South, East and West. Thus he has total four alternatives (*i.e.* four different directions) to proceed. Now if he wish to go towards a particular direction then the probability of completing his wish is $\frac{1}{4}$ since he can choose only one direction at a time out of four directions.

Consider another example, A person has two different cars *viz.*, Scorpio and Safari, which he uses randomly,then it can be said that the probability of using Scorpio is $\frac{1}{2}$ since out of two cars he can use any one car at a time. Similarly the probability of using Safari is also $\frac{1}{2}$. Thus we can say that the probability of using any one car at a time is $\frac{1}{2}$ *i.e.*, 50%. So there are chances that in 50% cases he can use Scorpio and in other 50% cases he can use Safari.

Hence from the above illustrations we can conclude that the probability of an event

$$= \frac{\text{(No. of ways in which favourable (or desired event occurs.)}}{\text{(Total number of possible outcomes)}}$$

IMPORTANT ARTICLES/DEFINITIONS

1. Experiment
2. Random Experiment
3. Sample Space
4. Events
5. Elementary Events
6. Compound Events
7. Occurrence of Events
8. Impossible Events
9. Sure Events
10. Equally Likely Events
11. Favourable Events
12. Complementary Events
13. Algebra of Events
14. Mutually Exclusive Events
15. Mutually Exclusive and Exhaustive Events
16. Addition Theorems on Probability
17. Conditional Probability
18. Multiplication Theorems on Probability
19. Independent Events
20. The Law of Total Probability
21. Baye's Rule

Experiment : An operation which can produce some well-defined outcomes, is known as an experiment.

The various experiments, when repeated under identical conditions, results. (*i.e.*, outcomes) in each case are same *e.g.*, standard scientific experiments.

But there are some other experiment, when repeated under identical conditions, results in each case are different *e.g.*, rolling of a fair die, tossing of a coin etc.

Random Experiment : If in each trial of an experiment conducted under identical conditions, the outcome is not unique, but may be any of the possible outcomes then such an experiment is known as a random experiment. *e.g.*, rolling of an unbiased die, tossing of a fair coin, drawing of a card from a well shuffled pack of cards.

Sample Space : The set of all possible outcomes in a random experiment is called a sample space and it is generally denoted by *S*.

Scanned by CamScanner

yoursmahboob.wordpress.com

If $E_1, E_2, E_3 \ldots E_n$ are the possible outcomes of a random experiment, then $S = \{E_1, E_2, \ldots E_n\}$. Also, each of the element of sample space 'S' is called a **sample point.**

EXAMPLE 1 In tossing of a fair coin, there are two possible outcomes, *viz.*, head (H) and tail (T). So, the sample space in this random experiment is $S = \{H, T\}$

EXAMPLE 2 When two fair coins are tossed together, the possible outcomes of the experiment are HH, HT, TH and TT. So the sample space is given by $S = \{HH, HT, TH, TT\}$

EXAMPLE 3 When unbiased die is thrown, it gives 6 possible outcomes *viz.*, 1, 2, 3, 4, 5 and 6. So, the sample space $S = \{1, 2, 3, 4, 5, 6\}$

NOTE
- A die is a cubical solid having 6 similar faces. In each of the six faces there are unique number of holes *viz.*, 1 hole, 2 holes, 3 holes, 4 holes, 5 holes and 6 holes.
- Remember that the sum of number of holes in any two opposite faces is always 7 *viz.*, 1 + 6 = 2 + 5 = 3 + 4 = 7.
- Die means one (single) die
- Dice means more than one die.
- In throwing a die, the outcome is the number of holes on the uppermost face



EXAMPLE 4 When two unbiased dice are rolled (or tossed) simultaneously then there are total $6 \times 6 = 36$ possible outcomes.

So, the sample space

$$S = \begin{Bmatrix} (1,1), (1,2), (1,3), (1,4), (1,5), (1,6) \\ (2,1), (2,2), (2,3), (2,4), (2,5), (2,6) \\ (3,1) \ldots\ldots (3,6) \\ (4,1) \ldots\ldots (4,6) \\ (5,1) \ldots\ldots (5,6) \\ (6,1) \ldots\ldots (6,6) \end{Bmatrix}$$

EXAMPLE 5 When a die and a coin are tossed simultaneously, then there are total 12 possible outcomes. So the sample space

$$S = \begin{Bmatrix} (1,H), (2,H), (3,H), (4,H), (5,H), (6,H) \\ (1,T), (2,T), (3,T), (4,T), (5,T), (6,T) \end{Bmatrix}$$

EXAMPLE 6 A coin is tossed twice. If the second throw results in a tail, then a die is thrown. So in this random experiment sample space.

$$S = \begin{Bmatrix} HH, TH, HT1, HT2, HT3, HT4, HT5, HT6, \\ TT1., TT2, , TT3, TT4, TT5, TT6, \end{Bmatrix}$$

EXAMPLE 7 From a bag containing 2 black and 3 white balls we draw two balls. Let B_1, B_2 be the black balls and W_1, W_2 and W_3 be the white balls then the sample space

$$S = \begin{Bmatrix} B_1W_1, & B_1W_2, & B_1W_3 \\ B_2W_1, & B_2W_2, & B_2W_3 \\ B_1B_2, & W_1W_2, & W_2W_3 \\ W_1W_3 & & \end{Bmatrix}$$

Event : Any subset of a sample space is called an event.

EXAMPLE 1 In a single throw of a die, the event of getting an even number is given by $E = \{2, 4, 6\}$

Clearly, here the sample space $S = \{1, 2, 3, 4, 5, 6\}$

Hence $E \subset S$ *i.e.*, E is the subset of S.

EXAMPLE 2 Consider a random experiment of tossing two dice at a time. The sample space $S = \{(1,1), (1,2), (1,3), (1,4), (1,5), (1,6), (2,1), (2,2), (2,3), (2,4), (2,5) \ldots (6,1), (6,2), (6,6)\}$

Some different events associated with the above sample space are given below.

$E_1 = \{(1,1), (2,2), (3,3), (4,4), (5,5), (6,6)\}$

$E_2 = \{(1,8), (2,7), (3,6), (4,5), (5,4), (6,3), (7,2), (8,1)\}$

$E_3 = \{(1,2), (1,4), (1,6), (3,2), (3,4), (3,6), (5,2), (5,4), (5,6)\}$

$E_4 = \{(2,2), (2,3), (2,5), (3,2), (3,3), (3,5), (5,2), (5,3), (5,5)\}$ etc.

Clearly $E_1 \subset S, E_2 \subset S, E_3 \subset S, E_4 \subset S$

Where E_1 is the event of getting a doublet

and E_2 is the event of getting 9 as the sum.

E_3 is the event of getting odd number on the first die and an even number on the second die

E_4 is the event of getting only prime number on each of the two dice.

EXAMPLE 3 Consider a random experiment of tossing three coins at a time. The sample space $S = \{HHH, HHT, HTH, THH, TTH, HTT, THT, TTT\}$

Following are the various events associated with the above sample space.

$E_1 = \{HHH, HHT, HTH, THH\}$

$E_2 = \{HHT, HTH, THH, TTH, HTT, THT\}$

$E_3 = \{HHH, TTT\}$

$E_4 = \{THH, TTH, THT, TTT\}$

Where E_1 is the event of getting atleast two heads and

E_2 is the event of getting atleast one head and atmost two heads.

E_3 is the event of getting all the three coins identical and E_4 is the event of getting tail on the first coin.

Elementary Events : An event containing only a single sample point is called an elementary event, or simple event.

EXAMPLE 1 In a simultaneous toss of two coins the sample space $S = \{HH, HT, TH, TT\}$

then $E_1 = \{HH\}$

$E_2 = \{TT\}$ are the elementary events.

EXAMPLE 2 Consider a random experiment in which two dice rolled simultaneously, the sample space

$S = \{(1,1), (1,2) \ldots (6,5), (6,6)\}$

then $E_1 = \{(1,1)\}$

Scanned by CamScanner

yoursmahboob.wordpress.com

$E_2 = \{(6, 6)\}$

$E_3 = \{(5, 5)\}$ are the elementary events.

Here E_1 is the event of getting the sum of two.

E_2 is the event of getting the sum of twelve

E_3 is the event of getting the product of 25.

Compound Events : Events which are not elementary are known as compound events or the events which contains more than one element are called compound or composite events.

Example 1 Consider a random experiment in which two dice are rolled simultaneously, the sample space

$S = \{(1, 1), (1, 2) \ldots\ldots (6, 5), (6, 6)\}$.

then $E_1 = \{(1, 5), (2, 4), (3, 3), (4, 2), (5, 1)\}$

$E_2 = \{(1, 1), (2, 2), (3, 3), (4, 4), (5, 5), (6, 6)\}$

$E_3 = \{(1, 2), (2, 4), (3, 6)\}$

are the compound events.

Here E_1 is the event of getting the sum of 6

E_2 is the event of getting identical results

E_3 is the event of getting the twice number by the second die than that by first die.

Occurrence of Events : In a random experiment, let S be the sample space and E be the event such that $E \subseteq S$, Let w be an outcome of a trial such that $w \in A$, then we say that the event E has occurred. If $w \notin E$, we say that the event E has not occurred.

EXAMPLE 1 Consider the random experiment of throwing an unbiased die. Let E be the event of getting an odd number, then $E = \{1, 3, 5\}$

Now, in a trial, let the outcome be 3, Since $3 \in E$, so in this trial, the event E has occurred.

In another trial, let the outcome be 4.

Since $4 \notin E$ so in this trial, the event E has not occurred.

EXAMPLE 2 Consider the random experiment of throwing a die. Let the outcome of the trial is 6. Then we can say that the following events have occurred.

(i) Getting a number greater than or equal to 3, represented by the set $\{3, 4, 5, 6\}$

(ii) Getting an even number represented by the set $\{2, 4, 6\}$

We can also say that the following events have not occurred :

(i) Getting an odd number represented by the set $\{1, 3, 5\}$.

(ii) Getting a prime number represented by the set $\{2, 3, 5\}$

Impossible Events : Let S be a sample space associated with a random experiment,

Now, since $\phi \subseteq S$, so ϕ is an event, called an impossible event.

Sure (or certain) Event : Let S be a sample space associated with a random experiment.

Now, since $S \subseteq S$, so S is an event, called a sure or certain event.

EXAMPLE Consider the random experiment of throwing an unbiased die. The sample space $S = \{1, 2, 3, 4, 5, 6\}$.

Let E_1 be the event of getting a number less than 1.

and E_2 be the event of getting a number greater than 6.

Here E_1 and E_2 both are impossible events.

Let E_3 be the event of getting a number less than or equal to 7.

and E_4 be the event of getting a number multiple of 2 but less than 7.

Here E_3 and E_4 are the certain events.

Equally Likely Events : Events are said to be equally likely, if none of them is expected to occur in preference to the other.

EXAMPLE 1 If an unbiased die is rolled, then each outcome is equally likely to happen *i.e.*, all elementary events are equally likely to happen. If however, the die is so formed that a particular face occurs most often, then the die is biased. So in this case, the outcomes are not equally likely to happen.

Favourable Events : Let S be the sample space associated with a random experiment and let $E \subset S$. Then the elementary events belonging to E are known as the favourable events to A.

EXAMPLE 1 Consider a random experiment of throwing a die. Let E be the event of getting an even number, then $E = \{2, 4, 6\}$.

So there are three favourable events of event E *viz.* $\{2\}$, $\{4\}$ and $\{6\}$

EXAMPLE 2 Consider a random experiment of throwing a pair of dice. Let E be the event of getting the sum as 8, then

$E = \{(1, 7), (2, 6), (3, 5), (4, 4), (5, 3), (6, 2), (7, 1)\}$

So, there are 7 favourable events to event E.

Complementary Events : In a random experiment, let S be the sample space and let E be an event. Then $E \subseteq S$. Clearly, $E^c \subseteq S$. So E^c is also an event, called the complementary of E.

Sometimes E^c is denoted by $\overline{E}$ or E'.

Where $\overline{E}$ is called as "not-E"

Thus it is clear that $\overline{E}$ occurs only when E does not occur. Also in a trial one and only of E and $\overline{E}$ must occur.

Algebra of Events : In a random experiment, let the sample space be S. Let $E \subseteq S$, $F \subseteq S$ and $G \subseteq S$, then we can define the following relations in the set theory mode.

(i) $\overline{E}$ is an event that occurs only when E does not occur.

(ii) $(E \cup F)$ is an event that occurs only when E occurs or F occurs or both occurs.

(iii) $(E \cap F)$ is an event that occurs only when each one of E and F occurs.

(iv) $(E \cap \overline{F})$ is an event that occurs only when E occurs but not F.

(v) $(\overline{E} \cap \overline{F}) = \overline{(E \cup F)}$ is an event that occurs when neither E nor F occurs.

(vi) $(E \cup F \cup G)$ is an event that occurs when at least one of E, F or G occurs.

Scanned by CamScanner

yoursmahboob.wordpress.com

(vii) $(E \cap F \cap G)$ is an event that occurs when all three E, F and G occurs.

(viii) $(E \cap \overline{F}) \cup (\overline{E} \cap F)$ is an event that occurs when exactly one of E and F occurs.

(ix) $(E \cap F \cap \overline{G}) \cup (E \cap \overline{F} \cap G) \cup (\overline{E} \cap F \cap G)$ is an event that occurs when exactly two of E, F and G occurs.

Mutually Exclusive Events : Let S be the sample space associated with a random experiment and let E_1 and E_2 be the two events. Then E_1 and E_2 are mutually exclusive events if $E_1 \cap E_2 = \phi$

EXAMPLE 1 Consider a random experiment of throwing a die. Let E_1, E_2 and E_3 be three events such that

$E_1 = \{1, 3, 5\}$, the event of getting an odd number

$E_2 = \{2, 4, 6\}$, the event of getting an even number

$E_3 = \{2, 3, 5\}$, the event of getting a prime number.

Clearly $E_1 \cap E_2 = \phi$ and $E_1 \cap E_3 \neq \phi$, $E_2 \cap E_3 \neq \phi$

Hence E_1 and E_2 are mutually exclusive events but E_1 and E_3, E_2 and E_3 are not mutually exclusive.

MUTUALLY EXCLUSIVE & EXHAUSTIVE SYSTEM OF EVENTS

Let S be the sample space associated with a random experiment. Let $E_1, E_2, \ldots E_n$ be the subsets of S such that

(i) $E_i \cap E_j = \phi$ for $i \neq j$ and

(ii) $E_1 \cup E_2 \cup E_3 \cup \ldots \cup E_n = S$

then the set of events $E_1, E_2, E_3 \ldots E_n$ is said to form a mutually exclusive and exhaustive system of events.

EXAMPLE 1 In a sample space all the elementary events form a mutually exclusive and exhaustive system of events.

EXAMPLE 2 Let $S = \{1, 2, 3, 4, 5, 6\}$ be the sample space when an unbiased die is rolled.

Let $E_1 = \{1, 3, 5\}$ and $E_2 = \{2, 4, 6\}$, then E_1 and E_2 form the mutually exclusive and exhaustive system of events.

Also, let $E_3 = \{1, 2\}$, $E_4 = \{4, 5\}$, then E_3 and E_4 do not form the mutually exclusive and exhaustive system of events since E_3 and E_4 do not include all the elementary events of S.

Again if $E_5 = \{3, 6\}$ and $E_6 = \{2, 4, 6\}$, then E_5 and E_6 do not form mutually exclusive and exhaustive system of events since $E_5 \cap E_6 \neq \phi$ and E_5, E_6 do not include all the elementary events of the sample space S.

- A pack of cards consists of 52 cards. There are four suits each containing 13 cards called as spades, clubs, hearts and diamonds.

All the spades and clubs are black faced cards while hearts and diamonds are red faced cards. The aces, kings, queens and jacks are known as face cards.

In each suit there is one ace, one king, one queen and one jack and rest 9 cards are numbered cards.

Definition of Probability : In a random experiment, let S be the sample space and let $E \subseteq S$.

where E is an event.

The probability of occurrence of the event E is defined as

$$P(E) = \frac{\text{number of favourable outcomes}}{\text{number of possible outcomes}}$$

$$= \frac{\text{number of elements in } E}{\text{number of elements in } S} = \frac{n(E)}{n(S)}$$

$$= \frac{\text{number of elementary events in } E}{\text{number of elementary events in } S}$$

From the above definitions it is clear that

(i) $0 \leq P(E) \leq 1$

(ii) $P(\phi) = 0$

(iii) $P(S) = 1$

Also, $P(\overline{E}) = \frac{\text{number of elementary events in } \overline{E}}{\text{number of elementary events in } S}$

$$= \frac{n(S) - n(E)}{n(S)} = 1 - \frac{n(E)}{n(S)} = 1 - P(E)$$

$\Rightarrow \quad P(\overline{E}) = 1 - P(E)$

$\therefore \quad P(E) + P(\overline{E}) = 1$

Odds In Favour of An Event and Odds Against An Event

In m be the number of ways in which an event occurs and n be the number of ways in which it does not occur, then

(i) odds in favour of the event $= \frac{m}{n}$ (or $m : n$)

(ii) odds against the event $= \frac{n}{m}$ (or $n : m$)

INTRODUCTORY EXERCISE-20.1

1. Find the probability of getting a head in a throw of a coin.

(a) $\frac{1}{2}$ (b) 1

(c) 2 (d) none of these

Directions for question number 2-5 : Two fair coins are tossed simultaneously. Find the probability of

2. Getting only one head.

(a) 1/2 (b) 1/3

(c) 2/3 (d) 3/4

3. Getting atleast one head.

(a) $\frac{1}{4}$ (b) $\frac{3}{4}$

(c) $\frac{1}{2}$ (d) $\frac{3}{8}$

Scanned by CamScanner

yoursmahboob.wordpress.com

4. Getting two heads.
(a) $\frac{2}{7}$ (b) $\frac{1}{4}$
(c) $\frac{1}{2}$ (d) $\frac{4}{5}$

5. Getting atleast two heads :
(a) $\frac{3}{4}$ (b) $\frac{1}{2}$
(c) $\frac{1}{4}$ (d) 1

Directions for question number 6-12 : Three fair coins are tossed simultaneously. Find the probability of

6. Getting one head.
(a) 0 (b) 3/4
(c) $\frac{5}{8}$ (d) $\frac{3}{8}$

7. Getting one tail.
(a) 1 (b) $\frac{1}{4}$
(c) $\frac{5}{8}$ (d) $\frac{3}{8}$

8. Getting atlest one head.
(a) $\frac{7}{8}$ (b) $\frac{1}{8}$
(c) $\frac{3}{4}$ (d) $\frac{1}{4}$

9. Getting two heads.
(a) $\frac{3}{5}$ (b) $\frac{3}{8}$
(c) $\frac{5}{8}$ (d) $\frac{2}{5}$

10. Getting atleast two heads.
(a) $\frac{3}{8}$ (b) $\frac{7}{8}$
(c) $\frac{1}{2}$ (d) $\frac{1}{4}$

11. Getting atleast one head and one tail.
(a) $\frac{2}{8}$ (b) $\frac{1}{2}$
(c) $\frac{3}{10}$ (d) $\frac{3}{4}$

12. Getting more heads than the number of tails.
(a) 2 (b) 7/8
(c) $\frac{5}{8}$ (d) $\frac{1}{2}$

Directions for question number 13-16 : An unbiased die is rolled. Find the probability of

13. Getting a number less than 7 but greater than zero.
(a) 0 (b) 3/4
(c) 1 (d) $\frac{7}{8}$

14. Getting a multiple of 3.
(a) $\frac{1}{6}$ (b) $\frac{1}{3}$
(c) $\frac{5}{6}$ (d) none of these

15. Getting a prime number.
(a) $\frac{1}{2}$ (b) $\frac{3}{5}$
(c) $\frac{5}{7}$ (d) $\frac{5}{8}$

16. Getting an even number.
(a) $\frac{1}{2}$ (b) $\frac{4}{5}$
(c) $\frac{2}{8}$ (d) $\frac{3}{4}$

Directions for question number 17 and 18 : A coin is tossed successively three times. Find the probability of

17. Getting exactly one head or two heads.
(a) $\frac{1}{4}$ (b) $\frac{3}{4}$
(c) $\frac{1}{2}$ (d) $\frac{3}{8}$

18. Getting no heads.
(a) 0 (b) $\frac{1}{7}$
(c) $\frac{1}{8}$ (d) $\frac{1}{8}$

Directions for question number 19-27 : Two dice are rolled simultaneously. Find the probability of

19. Getting a total of 9.
(a) $\frac{1}{3}$ (b) $\frac{1}{9}$
(c) $\frac{8}{9}$ (d) $\frac{9}{10}$

20. Getting a sum greater than 9.
(a) $\frac{10}{11}$ (b) $\frac{5}{6}$
(c) $\frac{1}{6}$ (d) $\frac{8}{9}$

21. Getting a total of 9 or 11.
(a) $\frac{2}{99}$ (b) $\frac{20}{99}$
(c) $\frac{1}{6}$ (d) $\frac{1}{10}$

22. Getting a doublet.
(a) 1/12 (b) 0
(c) 5/8 (d) 1/6

23. Getting a doublet of even numbers.
(a) 5/8 (b) 1/12
(c) 3/4 (d) 1/4

24. Getting a multiple of 2 on one die and a multiple of 3 on the other.
(a) $\frac{15}{36}$ (b) $\frac{25}{36}$
(c) $\frac{11}{36}$ (d) $\frac{5}{6}$

25. Getting the sum of numbers on the two faces divisible by 3 or 4.
(a) $\frac{4}{9}$ (b) $\frac{1}{7}$
(c) $\frac{5}{9}$ (d) $\frac{7}{12}$

Scanned by CamScanner

yoursmahboob.wordpress.com

26. Getting the sum as a prime number.
(a) $\frac{3}{5}$ (b) $\frac{5}{12}$
(c) $\frac{1}{2}$ (d) $\frac{3}{4}$

27. Getting atleast one '5'.
(a) $\frac{3}{5}$ (b) $\frac{1}{5}$
(c) $\frac{5}{36}$ (d) $\frac{11}{36}$

✍ ***Directions for question number 28-35 :*** *One card is drawn from a pack of 52 cards, each of the 52 cards being equally likely to be drawn. Find the probability that*

28. The card drawn is black.
(a) $\frac{1}{2}$ (b) $\frac{1}{4}$
(c) $\frac{8}{13}$ (d) can't be determine

29. The card drawn is a queen.
(a) $\frac{1}{12}$ (b) $\frac{1}{13}$
(c) $\frac{1}{4}$ (d) $\frac{3}{4}$

30. The card drawn is black and a queen.
(a) $\frac{1}{13}$ (b) $\frac{1}{52}$
(c) $\frac{1}{26}$ (d) $\frac{5}{6}$

31. The card drawn is either black or a queen.
(a) $\frac{15}{26}$ (b) $\frac{13}{17}$
(c) $\frac{7}{13}$ (d) $\frac{15}{26}$

32. The card drawn is either king or a queen.
(a) $\frac{5}{26}$ (b) $\frac{1}{13}$
(c) $\frac{2}{13}$ (d) $\frac{12}{13}$

33. The card drawn is either a heart, a queen or a king.
(a) $\frac{17}{52}$ (b) $\frac{21}{52}$
(c) $\frac{19}{52}$ (d) $\frac{9}{26}$

34. The card drawn is neither a spade nor a king.
(a) 0 (b) $\frac{9}{13}$
(c) $\frac{1}{2}$ (d) $\frac{4}{13}$

35. The card drawn is neither an ace nor a king.
(a) $\frac{11}{13}$ (b) $\frac{1}{2}$
(c) $\frac{2}{13}$ (d) $\frac{11}{26}$

36. From a well shuffled pack of 52 cards, three cards are drawn at random. Find the probability of drawing an ace, a king and a jack.
(a) $\frac{16}{5525}$ (b) $\frac{16}{625}$
(c) $\frac{16}{3125}$ (d) none of these

37. Four cards are drawn at random from a pack of 52 cards. Find the probability of getting all the four cards of same number.
(a) $\frac{17}{1665}$ (b) $\frac{1}{20825}$
(c) $\frac{7}{25850}$ (d) none of these

38. From a well shuffled pack of 52 playing cards, four cards are accidently dropped. Find the probability that one card is missing from each suit.
(a) $\frac{17}{20825}$ (b) $\frac{2197}{20825}$
(c) $\frac{197}{1665}$ (d) none of these

39. Four cards are drawn at random from a pack of 52 cards. Find the probability of getting all the four cards of different numbers.
(a) $\frac{141}{4165}$ (b) $\frac{117}{833}$
(c) $\frac{264}{4165}$ (d) none of these

✍ ***Directions for question number 40-43 :*** *Four dice are thrown simultaneously. Find the probability that :*

40. All of them show the same face.
(a) $\frac{1}{216}$ (b) $\frac{15}{16}$
(c) $\frac{15}{36}$ (d) $\frac{1}{2}$

41. All of them show the different face.
(a) $\frac{3}{28}$ (b) $\frac{5}{18}$
(c) $\frac{15}{36}$ (d) $\frac{11}{36}$

42. Two of them show the same face and remaining two show the different faces.
(a) $\frac{4}{9}$ (b) $\frac{5}{9}$
(c) $\frac{11}{18}$ (d) $\frac{7}{9}$

43. Atleast two of them show the same face.
(a) $\frac{37}{72}$ (b) $\frac{11}{36}$
(c) $\frac{47}{72}$ (d) $\frac{25}{36}$

44. What is the probability that a number selected from the numbers 1, 2, 3, ..., 20, is a prime number when each of the given numbers is equally likely to be selected?
(a) 7/10 (b) 2/15
(c) 2/5 (d) 3/5

45. Tickets are numbered from 1 to 18 are mixed up together and then 9 ticket is drawn at random. Find the probability that the ticket has a number, which is a multiple of 2 or 3.

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) $\frac{1}{3}$ (b) $\frac{3}{5}$
(c) $\frac{2}{3}$ (d) $\frac{5}{6}$

46. In a lottery of 100 tickets numbered 1 to 100, two tickets are drawn simultaneously. Find the probability that both the tickets drawn have prime numbers.
(a) $\frac{2}{33}$ (b) $\frac{7}{50}$
(c) $\frac{7}{20}$ (d) $\frac{5}{66}$

47. In the previous question (number 46), find the probability that none of the tickets drawn has a prime number.
(a) $\frac{29}{66}$ (b) $\frac{17}{33}$
(c) $\frac{37}{66}$ (d) $\frac{17}{50}$

48. Find the probability that a leap year selected at random will contain 53 Sundays.
(a) $\frac{5}{7}$ (b) $\frac{3}{4}$
(c) $\frac{4}{7}$ (d) $\frac{2}{7}$

Directions for question number **49-53:** *A bag contains 8 red and 4 green balls. Find the probability that*

49. The ball drawn is red when one ball is selected at random.
(a) $\frac{2}{3}$ (b) $\frac{1}{3}$
(c) $\frac{1}{6}$ (d) $\frac{5}{6}$

50. All the 4 balls drawn are red when four balls are drawn at random.
(a) $\frac{17}{32}$ (b) $\frac{14}{99}$
(c) $\frac{7}{12}$ (d) none of these

51. All the 4 balls drawn are green when four balls are drawn at random.
(a) $\frac{1}{495}$ (b) $\frac{7}{99}$
(c) $\frac{5}{12}$ (d) $\frac{2}{3}$

52. Two balls are red and one ball is green when three balls are drawn at random.
(a) $\frac{56}{99}$ (b) $\frac{112}{495}$
(c) $\frac{78}{495}$ (d) none of these

53. Three balls are drawn and none of them is red.
(a) $\frac{68}{99}$ (b) $\frac{7}{99}$
(c) $\frac{4}{495}$ (d) none of these

54. The odds in favour of an event are 2 : 7. Find the probability of occurrence of this event.
(a) $\frac{2}{9}$ (b) $\frac{5}{12}$
(c) $\frac{7}{12}$ (d) $\frac{2}{5}$

55. The odds against of an event are 5 : 7, find the probability of occurrence of this event.
(a) $\frac{3}{8}$ (b) $\frac{7}{12}$
(c) $\frac{2}{7}$ (d) $\frac{5}{12}$

56. If there are two children in a family, find the probability that there is atleast one girl in the family.
(a) $\frac{1}{4}$ (b) $\frac{1}{2}$
(c) $\frac{3}{4}$ (d) none of these

57. From a group of 3 men and 2 women, two persons are selected at random. Find the probability that atleast one woman is selected.
(a) $\frac{1}{5}$ (b) $\frac{7}{10}$
(c) $\frac{2}{5}$ (d) $\frac{5}{6}$

58. A box contains 5 defective and 15 non-defective bulbs. Two bulbs are chosen at random. Find the probability that both the bulbs are non-defective.
(a) $\frac{5}{19}$ (b) $\frac{3}{20}$
(c) $\frac{21}{38}$ (d) none of these

59. In the previous question (number 58), find the probability that atleast 3 bulbs are defective when 4 bulbs are selected at random.
(a) $\frac{31}{969}$ (b) $\frac{7}{20}$
(c) $\frac{1}{20}$ (d) none of these

IMPORTANT RESULTS

1. $P(E) \geq 0$
2. $P(\phi) = 0$
3. $P(S) = 1$

Addition Theorem 1 : If A and B are two events associated with a random experiment.

Then $P(A \cup B) = P(A) + P(B) - P(A \cap B)$

$\Rightarrow$ $P(A \text{ or } B) = P(A) + P(B) - P(A \text{ and } B)$

Corollary: If A and B are mutually exclusive events.

then $P(A \cap B) = 0$, therefore

$P(A \cup B) = P(A) + P(B)$

Addition Theorem 2 : If A, B and C three events associated with a random experiment,

then $P(A \cup B \cup C) = P(A) + P(B) + P(C) - P(A \cap B) - P(B \cap C) - P(A \cap C) + P(A \cap B \cap C)$

Scanned by CamScanner

yoursmahboob.wordpress.com

Corollary : If A, B and C are the three mutually exclusive events, then

$$P(A \cap B) = P(B \cap C) = P(A \cap C) = P(A \cap B \cap C) = 0$$

$$\therefore \quad P(A \cup B \cup C) = P(A) + P(B) + P(C)$$

Theorem 3. If A and B be two events such that $A \subseteq B$, then $P(A) \leq P(B)$

Theorem 4. If E is an event associated with a random experiment, then

$$0 \leq P(E) \leq 1$$

Theorem 5. For any two events A and B

$$P(A - B) = P(A) - P(A \cap B)$$

$$P(B - A) = P(B) - P(A \cap B)$$

$$P(\overline{A} \cap B) = P(B) - P(A \cap B)$$

$$P(A \cap \overline{B}) = P(A) - P(A \cap B)$$

SOME IMPORTANT RESULTS

(A) If A, B and C are three events, then

(i) P [Exactly one of A, B, C occurs]

$$= P(A) + P(B) + P(C) - 2[(A \cap B) + (B \cap C) + (A \cap C)] + 3P(A \cap B \cap C)$$

(ii) P [Exactly two of A, B, C occur]

$$= P(A \cap B) + P(B \cap C) + P(A \cap C) - 3P(A \cap B \cap C)$$

(iii) P (Atleast two of A, B, C occur)

$$= P(A \cap B) + P(B \cap C) + P(A \cap C) - 2P(A \cap B \cap C)$$

(B) If A and B are two events, then

P(Exactly one of A, B occurs)

$$= P(A) + P(B) - 2P(A \cup B)$$

$$= P(A \cup B) - P(A \cap B)$$

INTRODUCTORY EXERCISE-20.2

1. The probability of occurrence of two events A and B are 1/4 and 1/2 respectively. The probability of their simultaneous occurrence is $\frac{7}{50}$. Find the probability that either A or B must occur.

(a) $\frac{61}{100}$ (b) $\frac{29}{100}$

(c) $\frac{39}{100}$ (d) $\frac{56}{99}$

2. In the previous question, find the probability that neither A nor B occurs.

(a) $\frac{25}{99}$ (b) $\frac{39}{100}$

(c) $\frac{61}{100}$ (d) $\frac{17}{100}$

3. If A and B be two events in a sample space such that $P(A) = \frac{3}{10}$ and $P(B) = \frac{1}{2}$ and $P(A \cap B) = \frac{1}{5}$. Find $P(A \cup B)$.

(a) $\frac{1}{5}$ (b) $\frac{2}{5}$

(c) $\frac{3}{5}$ (d) $\frac{4}{5}$

4. If A and B be two events in a sample space such that $P(A) = \frac{2}{5}$, $P(B) = \frac{1}{2}$ and $P(A \cup B) = \frac{3}{5}$, find $P(A \cap B)$.

(a) $\frac{3}{10}$ (b) $\frac{7}{10}$

(c) $\frac{4}{7}$ (d) $\frac{4}{15}$

Directions for question number 5-10 : If A and B be two mutually exclusive events in a sample space such that, $P(A) = \frac{2}{5}$ and $P(B) = \frac{1}{2}$, then

5. Find $P(\overline{A})$:

(a) $\frac{2}{5}$ (b) $\frac{3}{5}$

(c) $\frac{4}{5}$ (d) $\frac{6}{7}$

6. Find $P(\overline{B})$:

(a) $\frac{1}{4}$ (b) $\frac{3}{4}$

(c) $\frac{1}{2}$ (d) $\frac{4}{5}$

7. Find $P(A \cup B)$:

(a) $\frac{7}{16}$ (b) $\frac{9}{16}$

(c) $\frac{9}{10}$ (d) $\frac{1}{2}$

8. Find $P(\overline{A} \cap \overline{B})$:

(a) $\frac{4}{5}$ (b) $\frac{1}{10}$

(c) $\frac{8}{9}$ (d) $\frac{13}{20}$

9. Find $P(\overline{A} \cap B)$:

(a) $\frac{1}{2}$ (b) $\frac{3}{5}$

(c) $\frac{4}{7}$ (d) $\frac{7}{15}$

10. Find $P(A \cap \overline{B})$:

(a) $\frac{1}{5}$ (b) $\frac{2}{5}$

(c) $\frac{4}{15}$ (d) $\frac{3}{10}$

11. If $P(\overline{A}) = 0{\cdot}65$, $P(A \cup B) = 0{\cdot}65$, where A and B are two mutually exclusive events, then find $P(B)$.

(a) 0·60 (b) 0·30

(c) 0·70 (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

12. If A, B and C are three mutually exclusive and exhaustive events. Find $P(A)$, if $P(B) = \frac{3}{2} P(A)$ and $P(C) = \frac{1}{2} P(B)$.
(a) $\frac{8}{13}$ (b) $\frac{5}{13}$
(c) $\frac{4}{13}$ (d) $\frac{9}{13}$

13. Two dice are tossed once. Find the probability of getting an even number on first die, or a total of 8.
(a) $\frac{4}{9}$ (b) $\frac{2}{3}$
(c) $\frac{5}{9}$ (d) $\frac{1}{3}$

14. A die is thrown twice, what is the probability that atleast one of the two throws comes up with the number 5?
(a) $\frac{11}{36}$ (b) $\frac{5}{6}$
(c) $\frac{15}{36}$ (d) none of these

15. In a single throw of two dice, find the probability that neither a doublet nor a total of 8 will appear.
(a) $\frac{7}{15}$ (b) $\frac{5}{18}$
(c) $\frac{13}{18}$ (d) $\frac{3}{16}$

16. A die is thrown twice, what is the probability that atleast one of the two numbers is 6?
(a) $\frac{11}{12}$ (b) $\frac{11}{36}$
(c) $\frac{1}{6}$ (d) $\frac{7}{36}$

17. A card is drawn at random from a well-shuffled deck of 52 cards. Find the probability of its being a heart or a king.
(a) $\frac{4}{13}$ (b) $\frac{9}{13}$
(c) $\frac{8}{13}$ (d) $\frac{11}{26}$

18. Two cards are drawn at random from a well-shuffled pack of 52 cards. What is the probability that either both are red or both are queens?
(a) $\frac{17}{112}$ (b) $\frac{55}{221}$
(c) $\frac{55}{121}$ (d) $\frac{33}{221}$

19. A card is drawn from a deck of 52 cards. Find the probability of getting a red card or a heart or a king.
(a) $\frac{6}{13}$ (b) $\frac{7}{13}$
(c) $\frac{11}{26}$ (d) $\frac{15}{26}$

20. Four cards are drawn at a time from a pack of 52 playing cards. Find the probability of getting all the four cards of the same suit.
(a) $\frac{5}{13}$ (b) $\frac{12}{65}$
(c) $\frac{44}{4165}$ (d) $\frac{44}{169}$

21. From a well-shuffled pack of 52 cards, a card is drawn at random. Find the probability that the drawn card is a king or a queen.
(a) $\frac{2}{13}$ (b) $\frac{8}{13}$
(c) $\frac{11}{13}$ (d) none of these

22. Two cards are drawn at random from a pack of 52 cards. What is the probability that either both are black or both are jacks?
(a) $\frac{65}{121}$ (b) $\frac{55}{221}$
(c) $\frac{17}{221}$ (d) none of these

23. A natural number is chosen at random from amongst the first 300. What is the probability that the number, so chosen is divisible by 3 or 5?
(a) $\frac{48}{515}$ (b) $\frac{4}{150}$
(c) 1/2 (d) none of these

24. A natural number is chosen at random from the first 100 natural numbers. What is the probability that the number chosen is a multiple of 2 or 3 or 5?
(a) $\frac{30}{100}$ (b) $\frac{1}{33}$
(c) $\frac{74}{100}$ (d) $\frac{7}{10}$

25. A box contains 5 red balls, 8 green balls and 10 pink balls. A ball is drawn at random from the box. What is the probability that the ball drawn is either red or green?
(a) $\frac{13}{23}$ (b) $\frac{10}{23}$
(c) $\frac{11}{23}$ (d) $\frac{13}{529}$

26. A basket contains 10 apples and 20 oranges out of which 3 apples and 5 oranges are defective. If we choose two fruits at random, what is the probability that either both are oranges or both are non defective?
(a) $\frac{136}{345}$ (b) $\frac{17}{87}$
(c) $\frac{316}{435}$ (d) $\frac{158}{435}$

27. In a class 40% of the students offered Physics 20% offered Chemistry and 5% offered both. If a student is selected at random, find the probability that he has offered Physics or Chemistry only.
(a) 45% (b) 55%
(c) 36% (d) none of these

28. The probability that an MBA aspirant will join IIM is $\frac{2}{5}$ and that he will join XLRI is $\frac{1}{3}$. Find the probability that he will join IIM or XLRI.
(a) $\frac{4}{15}$ (b) $\frac{7}{15}$
(c) $\frac{11}{15}$ (d) $\frac{8}{15}$

Scanned by CamScanner

yoursmahboob.wordpress.com

29. In a given race, the odds in favour of horses H_1, H_2, H_3 and H_4 are 1 : 2, 1 : 3, 1 : 4, 1 : 5 respectively. Find the probability that one of them wins the race.

(a) $\frac{57}{60}$ (b) $\frac{1}{20}$ (c) $\frac{2}{7}$ (d) $\frac{7}{60}$

CONDITIONAL PROBABILITY

Let A and B be two events associated with a random experiment. Then, the probability of occurrence of A under the condition that B has already occurred and $P(B) \neq 0$, is called the conditional probability and it is denoted by $P\left(\frac{A}{B}\right)$

Thus, $P\left(\frac{A}{B}\right)$ = Probability of occurrence of A given that B has already occurred.

Similarly, $P\left(\frac{B}{A}\right)$ = Probability of occurrence of B given that A has already occurred.

NOTE

(i) Sometimes $P\left(\frac{A}{B}\right)$ is used to denote the probability of occurrence of A when B occurs.

(ii) Similarly $P\left(\frac{B}{A}\right)$ is used to denoted the probability of occurrence of B when A occurs.

The above two cases happens due to the simultaneous occurrence of two events since the two events are the subsets of the same sample space.

EXAMPLE 1 *An urn contains 6 red and 9 blue balls. Two balls are drawn from the urn one after another without replacement. Find the probability of drawing a red ball when a blue ball has been drawn from the urn.*

SOLUTION Let A = drawing of a red ball in the second draw and B = drawing of a blue ball in the first draw

Now $P\left(\frac{A}{B}\right)$ = Probability of drawing a red ball in second draw when a blue ball has been drawn in the first draw.

Now, since there are only 14 balls after drawing a blue ball in first draw and out of these 14 balls, 6 balls are red.

Therefore $P\left(\frac{A}{B}\right) = \frac{6}{14} = \frac{3}{7}$

EXAMPLE 2 *A pair of dice is thrown simultaneously, find the probability that the sum is obtained 9 when there is an odd number on the first die.*

SOLUTION Let A be the event of getting a sum of 9 and B be the event of getting an odd number on the first die.

$\therefore$ $A = \{(3, 6)(4, 5), (5, 4), (6, 3)\}$

$B = \{(1, 1), (1, 2), (1, 3) \ldots (3, 1), (3, 2), (3, 3) \ldots (5, 1), (5, 2) \ldots (5, 6)\}$

$P(A) = \frac{4}{36} = \frac{1}{9}$ and $P(B) = \frac{18}{36} = \frac{1}{2}$

$\therefore P\left(\frac{A}{B}\right)$ = Probability of occurrence of A when B Occurs.

$\Rightarrow P\left(\frac{A}{B}\right)$ = Probability of getting 9 as the sum when there is an odd number on first die.

$\Rightarrow$ $P\left(\frac{A}{B}\right) = \frac{n(A \cap B)}{n(B)} = \frac{2}{18} = \frac{1}{9}$

[Here $(A \cap B) = (3, 6), (6, 3)$]

MULTIPLICATION THEOREM

Let A and B be two events associated with the same random experiment then

$$P(A \cap B) = P(A)\, P\left(\frac{B}{A}\right), \quad \text{if } P(A) \neq 0 \ldots \text{(i)}$$

or $$P(A \cap B) = P(B)\, P\left(\frac{A}{B}\right), \quad P(B) \neq 0 \ldots \text{(ii)}$$

NOTE $P\left(\frac{B}{A}\right) = \frac{P(A \cap B)}{P(A)}$ from (i)

and $P\left(\frac{A}{B}\right) = \frac{P(A \cap B)}{P(B)}$ from (ii)

In general, if $A_1, A_2, A_3 \ldots A_n$ are events associated with the same random experiment, then

$$P(A_1 \cap A_2 \cap A_3 \cap \ldots \cap A_n) = P(A_1)\, P\left(\frac{A_2}{A_1}\right) P\left(\frac{A_3}{A_1 \cap A_2}\right) \ldots P\left(\frac{A_n}{A_1 \cap A_2 \cap \ldots \cap A_{n-1}}\right)$$

EXAMPLE 1 *Let A and B be the two events such that $P(A) = \frac{1}{2}$, $P(B) = \frac{1}{3}$ and $P(A \cap B) = \frac{1}{4}$, find*

(i) $P\left(\frac{A}{B}\right)$ (ii) $P\left(\frac{B}{A}\right)$ (iii) $P(A \cup B)$ (iv) $P\left(\frac{\overline{A}}{B}\right)$

SOLUTION (i) $P\left(\frac{A}{B}\right) = \frac{P(A \cap B)}{P(B)} = \frac{1/4}{1/3} = \frac{3}{4}$

(ii) $P\left(\frac{B}{A}\right) = \frac{P(A \cap B)}{P(A)} = \frac{1/4}{1/2} = \frac{1}{2}$

(iii) $P(A \cup B) = P(A) + P(B) - P(A \cap B)$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{1}{2} + \frac{1}{3} - \frac{1}{4} = \frac{7}{12}$$

(iv) $P\left(\frac{\bar{A}}{\bar{B}}\right) = \frac{P(\bar{A} \cap \bar{B})}{P(\bar{B})} = \frac{P(\overline{A \cup B})}{P(\bar{B})} = \frac{1 - P(A \cup B)}{1 - P(B)}$

$$= \frac{1 - \frac{7}{12}}{1 - \frac{1}{3}} = \frac{\frac{5}{12}}{\frac{2}{3}} = \frac{5}{8}$$

EXAMPLE 2 *An urn contains 6 red balls and 9 green balls. Two balls are drawn in succession without replacement. What is the probability that first is red and second is green.*

SOLUTION Let A be the event of drawing a red ball in first draw and B be the event of getting a green ball in the second draw.

$$\therefore \quad P(A) = \frac{{}^6C_1}{{}^{15}C_1} = \frac{6}{15} = \frac{2}{5}$$

$P\left(\frac{B}{A}\right)$ = Probability of getting a green ball in second draw when a red ball has been selected in first draw $= \frac{{}^9C_1}{{}^{14}C_1} = \frac{9}{14}$

$\therefore$ Required probability $= P(A \cap B) = P(A)P\left(\frac{B}{A}\right)$

$$= \frac{2}{5} \times \frac{9}{14} = \frac{9}{35}$$

INTRODUCTORY EXERCISE-20.3

1. If A and B are two events such that $P(A) = 0 \cdot 5$, $P(B) = 0.6$ and $P(A \cup B) = 0.8$. Find $P\left(\frac{A}{B}\right)$.
   (a) $\frac{1}{3}$ (b) $\frac{1}{2}$
   (c) $\frac{1}{4}$ (d) none of these

2. If A and B are two events such that $P(A) = 0.4$, $P(B) = 0.8$ and $P\left(\frac{B}{A}\right) = 0.6$, find $P(A \cup B)$:
   (a) 0.24 (b) 0.96
   (c) 0.04 (d) none of these

3. Three fair coins are tossed. Find the probability that they are all tails, if one of the coins shows a tail.
   (a) $\frac{2}{7}$ (b) $\frac{5}{14}$
   (c) $\frac{1}{7}$ (d) none of these

4. A coin is tossed twice and the four possible outcomes are assumed to be equally likely. If E is the event, "Both head and tail have appeared and F be the event, at most one tail is observed ; find $P\left(\frac{E}{F}\right)$ and $P\left(\frac{F}{E}\right)$.
   (a) $\frac{2}{3}, 1$ (b) $\frac{1}{3}, \frac{2}{3}$
   (c) $1, \frac{2}{3}$ (d) none of these

5. A coin is tossed twice if the coin shows head it is tossed again but if it shows a tail then a die is tossed. If 8 possible outcomes are equally likely. Find the probability that the die shows a number greater than 4, if it is known that the first throw of the coin results in a tail.
   (a) $\frac{1}{3}$ (b) $\frac{2}{3}$
   (c) $\frac{2}{5}$ (d) $\frac{4}{15}$

6. A die is rolled. If the outcome is an odd number, what is the probability that it is a prime number?
   (a) $\frac{3}{8}$ (b) $\frac{7}{9}$
   (c) $\frac{2}{3}$ (d) none of these

7. A die is thrown twice and the sum of the numbers appearing is observed to be 9. What is the conditional probability that the number 4 has appeared atleast once?
   (a) $\frac{1}{2}$ (b) $\frac{2}{3}$
   (c) $\frac{3}{4}$ (d) none of these

8. Two dice are thrown. Find the probability that the sum is 8 or greater than 8, if 4 appears on the first die.
   (a) $\frac{3}{8}$ (b) $\frac{5}{8}$
   (c) $\frac{1}{2}$ (d) none of these

9. A die is rolled. If the outcome is an odd number, what is the probability that it is a number greater than 1 ?
   (a) $\frac{2}{3}$ (b) $\frac{1}{3}$
   (c) $\frac{3}{8}$ (d) $\frac{5}{6}$

10. In a class 45% students read English, 30% read French and 20% read both English and French. One student is selected at random. Find the probability that he reads English, if it is known that he reads French.
    (a) $\frac{1}{3}$ (b) $\frac{2}{3}$
    (c) $\frac{5}{6}$ (d) none of these

11. In the previous question, find the probability that he reads French, if it is known that he reads English.
    (a) $\frac{4}{9}$ (b) $\frac{5}{9}$
    (c) $\frac{2}{9}$ (d) $\frac{1}{9}$

Scanned by CamScanner

yoursmahboob.wordpress.com

12. A couple has two children. Find the probability that both are boys, if it is known that one of the children is a boy.

(a) $\frac{1}{9}$ (b) $\frac{1}{3}$

(c) $\frac{2}{3}$ (d) $\frac{4}{5}$

13. In the previous question find the probability that both are boys, if it is known that the older child is a boy.

(a) $\frac{3}{8}$ (b) $\frac{1}{2}$

(c) $\frac{5}{8}$ (d) $\frac{3}{4}$

Directions for question number 14-17 : A bag contains 3 red and 4 black balls and another bag has 4 red and 2 black balls. One bag is selected at random and from the selected bag a ball is drawn. Let E be the event that the first bag is selected, F be the event that the second bag is selected, G be the event that ball drawn is red.

14. Find $P(E)$.

(a) $\frac{1}{2}$ (b) $\frac{3}{4}$

(c) $\frac{1}{4}$ (d) $\frac{5}{8}$

15. Find $P(F)$.

(a) $\frac{3}{4}$ (b) $\frac{1}{2}$

(c) $\frac{1}{4}$ (d) $\frac{1}{6}$

16. Find $P\left(\frac{G}{E}\right)$.

(a) $\frac{5}{6}$ (b) $\frac{5}{14}$

(c) $\frac{3}{7}$ (d) none of these

17. Find $P\left(\frac{G}{F}\right)$.

(a) $\frac{2}{3}$ (b) $\frac{1}{9}$

(c) $\frac{5}{9}$ (d) $\frac{4}{5}$

18. Two balls are drawn from a bag containing 2 white, 3 red and 4 black balls one by one without replacement. What is the probability that atleast one ball is red?

(a) $\frac{7}{12}$ (b) $\frac{5}{12}$

(c) $\frac{3}{10}$ (d) none of these

19. A bag contains 6 red and 9 blue balls. Two successive drawing of four balls are made such that the balls are not replaced before the second draw. Find the probability that the first draw gives 4 red balls and second draw gives 4 blue balls.

(a) $\frac{3}{715}$ (b) $\frac{7}{715}$

(c) $\frac{15}{233}$ (d) none of these

20. An urn contains 4 white 6 black and 8 red balls. If 3 balls are drawn one by one without replacement, find the probability of getting all white balls.

(a) $\frac{5}{204}$ (b) $\frac{1}{204}$

(c) 13/204 (d) none of these

21. Two numbers are selected at random from the integers 1 through 9. If the sum is even, find the probability that both numbers are odd.

(a) 5/8 (b) 3/8

(c) 3/10 (d) none of these

22. A box contains 25 tickets, numbered 1, 2, 3, .. 25. A ticket is drawn and then another ticket is drawn without replacement. Find the probability that both tickets will show odd numbers.

(a) $\frac{37}{50}$ (b) $\frac{13}{50}$

(c) 13/25 (d) none of these

INDEPENDENT EVENTS

Events are said to be independent, if the occurrence of one does not depend upon the occurrence of the other.

Suppose an urn contains m red balls and n green balls. Two balls are drawn from the urn one after the other.

If the ball drawn in the first draw is not replaced back in the bag, then two events of drawing the ball are dependent because first draw of the ball determine the probability of drawing the second ball.

If the ball drawn in the first draw is replaced back in the bag, then two events are independent because first draw of a ball has no effect on the second draw.

Theorem 1. Two events A and B associated with the same sample space of a random experiment are independent if and only if

$$P(A \cap B) = P(A) \cdot P(B)$$

Theorem 2. If $A_1, A_2, A_3 \ldots A_n$ are independent events associated with a random experiment, then

$$P(A_1 \cap A_2 \cap A_3 \ldots \cap A_n) = P(A_1)\,P(A_2) \ldots P(A_n)$$

Theorem 3. If $A_1, A_2 \ldots A_n$ are n independent events associated with a random experiment, then

$$P(A_1 \cup A_2 \cup \ldots \cup A_n) = 1 - P(\bar{A}_1)\,P(\bar{A}_2) \ldots P(\bar{A}_n)$$

IMPORTANT RESULTS

If A and B are independent events then the following events are also independent.

(i) $A \cap \bar{B}$ (ii) $\bar{A} \cap B$ (iii) $\bar{A} \cap \bar{B}$

LAW OF TOTAL PROBABILITY

Let $E_1, E_2, \ldots E_n$ be n mutually exclusive and exhaustive events associated with a random experiment. If A is any event which occurs with E_1 or E_2 or ... or E_n, then

$$P(A) = P(E_1)\,P\left(\frac{A}{E_1}\right) + P(E_2)\,P\left(\frac{A}{E_2}\right) + \ldots P(E_n)\,P\left(\frac{A}{E_n}\right)$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Baye's Rule : Let $E_1, E_2, \ldots E_n$ be n mutually exclusive and exhaustive events associated with a random experiment. If A is any event which occurs with E_1 or E_2 or ... or E_n, then

$$P\left(\frac{E_i}{A}\right)=\frac{P(E_i)\,P\left(\frac{A}{E_i}\right)}{\sum_{i=1}^{n} P(E_i)\,P\left(\frac{A}{E_i}\right)}, \qquad i=1,2,\ldots n$$

EXAMPLE 1 *A coin is tossed twice and all 4 outcomes are equally likely. Let A be the event that first throw results in a head and B be the event that second throw results in a tail, then show that the events A and B are independent.*

SOLUTION

$S=\{HH, HT, TH, TT\}$

$A=\{HH, HT\}$

$B=\{HT, TT\}$

$A\cap B=\{HT\}$

$\therefore \quad P(A)=\frac{2}{4}=\frac{1}{2},\ P(B)=\frac{2}{4}=\frac{1}{2}$

and $\quad P(A\cap B)=\frac{1}{4}$

Clearly $\quad P(A\cap B)=\frac{1}{4}=P(A)\cdot P(B)$

Hence A and B are independent events.

EXAMPLE 2 *A bag contains 10 red balls and 10 green balls. Two balls are drawn at random, one at a time, with replacement. Let A be the event that first ball is red, B be the event that second ball is green and C be the event that both balls are either red or green, then show that the events A, B and C are pair wise independent and A, B, C are mutually dependent.*

SOLUTION We have $P(A)=\frac{1}{2}, \quad P(B)=\frac{1}{2},$

$$P(C)=\frac{1}{2}\times\frac{1}{2}+\frac{1}{2}\times\frac{1}{2}=\frac{1}{2}$$

$P(A\cap B)$ = Probability that the first is red and second is green

$\Rightarrow \quad P(A)\cdot P(B)=\frac{1}{2}\times\frac{1}{2}=\frac{1}{4}$

$P(B\cap C)$ = Probability that both the balls are green

$\Rightarrow \quad P(B)\cdot P(C)=\frac{1}{2}\times\frac{1}{2}=\frac{1}{4}$

and $P(A\cap C)$ = Probability that both the balls are red

$\Rightarrow \quad P(A)\,P(C)=\frac{1}{2}\times\frac{1}{2}=\frac{1}{4}$

Hence A, B, C are pairwise independent

Now, $P(A\cap B\cap C)$ = Probability that the first ball is red and the second ball is green and the first and second are both red or green = 0

and $\quad P(A)\,P(B)\,P(C)=\frac{1}{8}$

$\therefore \quad P(A\cap B\cap C)\neq P(A)\,P(B)\,P(C)$

Thus, A, B, C are not mutually independent.

EXAMPLE 3 *(For explanation of law of total probability) There are two bags. The first bag contains 4 white and 5 black balls and the second bag contains 5 white and 4 black balls. Two balls are drawn at random from the first bag and are put into the second bag without noticing their colours. Then two balls are drawn from the second bag. Find the probability that the balls are white and black.*

SOLUTION A white and a black ball can be drawn from the second bag in the following mutually exclusive ways :

(i) By transferring 2 white balls from the first bag to the second bag and then drawing a white and a black ball from it.

(ii) By transferring 2 black balls from the first bag to the second bag and then drawing a white and a black ball from it .

(iii) By transferring 1 white and 1 black ball from first bag to the second bag and then drawing a white and a black ball from it.

Let A, B, C and D be the events as defined below :

A = Two white balls are drawn from the first bag

B = Two black balls are drawn from the first bag.

C = One white and one black ball is drawn from the first bag.

D = Two balls drawn from the second bag are white and black.

We, have $\quad P(A)=\frac{{}^4C_2}{{}^9C_2}=\frac{6}{36}=\frac{1}{6}$

$$P(B)=\frac{{}^5C_2}{{}^9C_2}=\frac{10}{36}=\frac{5}{18}$$

$$P(C)=\frac{{}^4C_1\times{}^5C_1}{{}^9C_2}=\frac{20}{36}=\frac{5}{9}$$

If A has already occurred, *i.e.* if two white balls have been transferred from the first bag to the second bag, then the second bag will contain 7 white and 4 black balls, therefore the probability of drawing a white and a black from the second bag is

$$P\left(\frac{D}{A}\right)=\frac{{}^7C_1\times{}^4C_1}{{}^{11}C_2}=\frac{28}{55}$$

Similarly, $\quad P\left(\frac{D}{B}\right)=\frac{{}^5C_1\times{}^6C_1}{{}^{11}C_2}=\frac{30}{55}=\frac{6}{11}$

and $\quad P\left(\frac{D}{C}\right)=\frac{{}^6C_1\times{}^5C_1}{{}^{11}C_2}=\frac{30}{55}=\frac{6}{11}$

$\therefore$ By the law of total probability, we have

$$P(D)=P(A)\,P\left(\frac{D}{A}\right)+P(B)P\left(\frac{D}{B}\right)+P(C)\,P\left(\frac{D}{C}\right)$$

$$=\frac{1}{6}\times\frac{28}{55}+\frac{5}{18}\times\frac{6}{11}+\frac{5}{9}\times\frac{6}{11}$$

$$=\frac{14}{165}+\frac{5}{33}+\frac{10}{33}$$

$$=\frac{14+25+50}{165}$$

$$=\frac{89}{165}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXAMPLE 4 *(For explanation of Baye's rule) Three boxes contain 6 red, 4 black, ; 5 red, 5 black and 4 red, 6 black balls respectively. One of the box is selected at random and a ball is drawn from it. If the ball drawn is red, find the probability that it is drawn from the first bag.*

SOLUTION Let A, B, C and D be the events defined as follows :

A = first box is chosen

B = second box is chosen

C = third box is chosen

D = ball drawn is red.

Since there are three boxes and one of the three boxes is chosen at random, therefore

$$P(A) = P(B) = P(C) = \frac{1}{3}$$

If A has already occurred, then first box has been chosen which contains 6 red and 4 black balls. The probability of drawing a red ball from it is $\frac{6}{10}$

So, $$P\left(\frac{D}{A}\right) = \frac{6}{10}$$

Similarly, $P\left(\frac{D}{B}\right) = \frac{5}{10}$ and $P\left(\frac{D}{C}\right) = \frac{4}{10}$

We are required to find $P\left(\frac{A}{D}\right)$ *i.e.,* given that the ball drawn is red, what is the probability that it is drawn from the first box.

By Baye's rule.

$$P\left(\frac{A}{D}\right) = \frac{P(A)\cdot P\left(\frac{D}{A}\right)}{P(A).P\left(\frac{D}{A}\right) + P(B)\cdot P\left(\frac{D}{B}\right) + P(C)\cdot P\left(\frac{D}{C}\right)}$$

$$= \frac{\frac{1}{3}\times\frac{6}{10}}{\left(\frac{1}{3}\times\frac{6}{10}\right)+\left(\frac{1}{3}\times\frac{5}{10}\right)+\left(\frac{1}{3}\times\frac{4}{10}\right)} = \frac{2}{5}$$

INTRODUCTORY EXERCISE-20.4

Directions for question number 1-5 : Let A and B be independent events such that $P(A) = 0.6$ and $P(B) = 0.4$

1. Find $P(A \cap B)$.
(a) 0.24 (b) 0.76
(c) 0.56 (d) none of these

2. Find $P(A \cup B)$.
(a) 0.24 (b) 0.76
(c) 0.36 (d) none of these

3. Find $P(\bar{A} \cap B)$.
(a) 0.24 (b) 0.16
(c) 0.36 (d) none of these

4. Find $P(A \cap \bar{B})$.
(a) 0.24 (b) 0.56
(c) 0.36 (d) 0.76

5. Find $P(\bar{A} \cap \bar{B})$.
(a) 0.76 (b) 0.54
(c) 0.36 (d) 0.24

6. If A and B are two independent events such that $P(\bar{A}) = 0.65, P(A \cup B) = 0.65$ and $P(B) = p$, find the value of p.
(a) $\frac{7}{13}$ (b) $\frac{6}{13}$
(c) $\frac{37}{65}$ (d) none of these

7. An unbiased die is tossed twice. Find the probability of getting a 1, 2, 3 or 4 on the first toss and a 4, 5 or 6 on the second toss.
(a) $\frac{1}{3}$ (b) $\frac{2}{3}$
(c) $\frac{5}{6}$ (d) $\frac{1}{6}$

8. Two persons A and B throw a die alternatively till one of them gets a three and wins the game. Find their respective probabilities of winning.
(a) $\frac{6}{11}, \frac{5}{11}$ (b) $\frac{5}{11}, \frac{8}{11}$
(c) $\frac{3}{11}, \frac{7}{11}$ (d) $\frac{8}{11}, \frac{3}{11}$

9. Two persons A and B throw a coin alternatively till one of them gets head and wins the game. Find their respective probabilities of winning.
(a) $\frac{1}{3}, \frac{5}{6}$ (b) $\frac{3}{5}, \frac{4}{5}$
(c) $\frac{2}{3}, \frac{1}{3}$ (d) $\frac{1}{6}, \frac{5}{6}$

10. Three persons A, B, C throw a die in succession till one gets a six and wins the game. Find their respective probabilities of winning.
(a) $\frac{36}{91}, \frac{30}{91}, \frac{25}{91}$ (b) $\frac{10}{71}, \frac{16}{91}, \frac{22}{81}$
(c) $\frac{13}{61}, \frac{15}{61}, \frac{17}{61}$ (d) none of these

11. A and B take turn in throwing two dice; the first to throw 9 being awarded. Find the ratio of probabilities of their winning if A has the first throw.
(a) 7/8 (b) 9/8
(c) 8/7 (d) 9/10

12. From a pack of 52 cards, two are drawn one by one without replacement. Find the probabilities that both of them are kings.
(a) $\frac{11}{21}$ (b) $\frac{13}{121}$
(c) $\frac{1}{221}$ (d) $\frac{1}{121}$

Scanned by CamScanner

yoursmahboob.wordpress.com

13. Ashmit can solve 80% of the problem given in a book and Amisha can solve 70%. What is the probability that at least one of them will solve a problem, selected at random from the book?
(a) 0.60 (b) 0.06
(c) 0.94 (d) 0.56

14. The probability that A hits a target is $\frac{1}{3}$ and the probability that B hits it, is $\frac{2}{5}$. What is the probability that the target will be hit, if each one of A and B shoots the target?
(a) $\frac{5}{6}$ (b) $\frac{3}{5}$
(c) $\frac{11}{15}$ (d) $\frac{1}{6}$

15. A problem is given to three students whose chances of solving it are $\frac{1}{2}, \frac{1}{3}$ and $\frac{1}{4}$ respectively. What is the probability that the problem will be solved?
(a) $\frac{1}{4}$ (b) $\frac{1}{2}$
(c) $\frac{3}{4}$ (d) $\frac{7}{12}$

16. The probabilities of A, B, C solving a problem are $\frac{1}{3}, \frac{2}{7}$ and $\frac{3}{8}$ respectively. If all the three try to solve the problem simultaneously, find the probability that exactly one of them will solve it.
(a) $\frac{25}{52}$ (b) $\frac{25}{56}$
(c) 13/42 (d) none of these

17. A, B and C shoot to hit a target. If A hits the target 4 times in 5 trials, B hits it 3 times in 4 trials and C hits it 2 times in 3 trials. What is the probability that the target is hit by atleast 2 persons?
(a) $\frac{5}{6}$ (b) $\frac{3}{4}$
(c) $\frac{4}{5}$ (d) $\frac{1}{9}$

18. An airgun can take a maximum of 4 shots at a balloon at some distance. The probabilities of hitting the balloon at the first, second, third and fourth shot are 0.1, 0.2, 0.3 and 0.4 respectively. What is the probability that the balloon is hit?
(a) 0.6976 (b) 0.6576
(c) 0.786 (d) none of these

19. The probability that A can solve a problem is $\frac{2}{3}$ and the probability that B can solve the same problem is $\frac{3}{5}$. Find the probability that atleast one of A and B will be able to solve the problem.
(a) $\frac{12}{15}$ (b) $\frac{13}{15}$
(c) $\frac{19}{45}$ (d) none of these

20. In the previous question (number 19), find the probability that none of the two will be able to solve the problem.
(a) $\frac{13}{15}$ (b) $\frac{4}{15}$
(c) $\frac{2}{15}$ (d) $\frac{23}{30}$

✍ ***Directions for question number 21-24 :*** *The probabilities that a student will receive an A, B, C or D grade are 0.4, 0.3, 0.2 and 0.1 respectively. Find the probability that a student will receive*

21. Not an A grade.
(a) 0.4 (b) 0.6
(c) 0.56 (d) none of these

22. At most a C grade.
(a) 0.3 (b) 0.7
(c) 0.36 (d) none of these

23. B or C grade.
(a) 0.2 (b) 0.5
(c) 0.8 (d) 0.6

24. Atleast B grade.
(a) 0.21 (b) 0.3
(c) 0.7 (d) none of these

✍ ***Directions for question number 25-28 :*** *Ajay and his wife Kajol appear in an interview for two vaccancies in the same post. The probability of Ajay's selection is $\frac{1}{7}$ and that of his wife Kajol's selection is $\frac{1}{5}$. What is the probability that*

25. Both of them will be selected?
(a) $\frac{1}{12}$ (b) $\frac{1}{35}$
(c) $\frac{13}{35}$ (d) $\frac{12}{35}$

26. Only one of them will be selected ?
(a) $\frac{5}{7}$ (b) $\frac{1}{5}$
(c) $\frac{2}{7}$ (d) $\frac{2}{35}$

27. None of them will be selected?
(a) $\frac{12}{35}$ (b) $\frac{6}{35}$
(c) $\frac{24}{35}$ (d) none of these

28. Atleast one of them will be selected?
(a) $\frac{11}{35}$ (b) $\frac{24}{35}$
(c) $\frac{2}{7}$ (d) $\frac{1}{35}$

29. A speaks truth in 60% and B in 80% of the cases. In what percentage of cases are they likely to contradict each other narrating the same incident?
(a) 44% (b) 36%
(c) 64% (d) 48%

Scanned by CamScanner

yoursmahboob.wordpress.com

Directions for question number 30 and 31 : The odds against a husband who is 50 years old, living till he is 70 are 7 : 5 and the odds against his wife who is now 40, living till she is 60 are 5 : 3. Find the probability that

30. The couple will be alive 20 years hence.
(a) $\frac{21}{32}$ (b) $\frac{5}{32}$
(c) $\frac{15}{32}$ (d) $\frac{12}{35}$

31. Atleast one of them will be alive 20 years hence.
(a) $\frac{61}{96}$ (b) $\frac{31}{96}$
(c) $\frac{41}{70}$ (d) none of these

32. Three critics review a book. Odds in favour of the book are 5 : 2, 4 : 3 and 3 : 4 respectively for the critics. Find the probability that majority are in favour of the book.
(a) $\frac{108}{343}$ (b) $\frac{209}{343}$
(c) $\frac{1}{7}$ (d) $\frac{1}{243}$

33. An article manufactured by a company consists of two parts X and Y. In the process of manufacture of the part X, 9 out of 100 parts may be defective. Similarly, 5 out of 100 are likely to be defective in the manufacture of the part Y. Calculate the probability that the assembled product will not be defective.
(a) 0.6485 (b) 0.6565
(c) 0.8645 (d) none of these

34. A bag contains 4 red and 3 black balls. A second bag contains 2 red and 4 black balls. One bag is selected at random. From the selected bag, one ball is drawn. Find the probability that the ball drawn is red.
(a) $\frac{23}{42}$ (b) $\frac{19}{42}$
(c) $\frac{7}{32}$ (d) $\frac{16}{39}$

35. In a toys making factory, machine A, B and C manufacture respectively 25%, 35% and 40% of the total toys. Of their output 5%, 4% and 2% respectively are defective toys. A toy is drawn at random from the product. What is the probability that the toy drawn is defective?
(a) 0.225 (b) 0.345
(c) 0.235 (d) none of these

36. A box contains 20 bulbs. The probability that the box contains exactly 2 defective bulbs is 0.4 and the probability that the box contains exactly 3 defective bulbs is 0.6. Bulbs are drawn at random one by one without replacement and tested till the defective bulbs are found. What is the probability that the testing procedure ends at the twelfth testing?
(a) 0 (b) 1
(c) can't be determined (d) none of these

37. In a toys making factory, machines A, B and C manufacture respectively 25%, 35% and 40% of the total toys of their output 5%, 4% and 2% respectively are defective toys. A toy is drawn at random from the product. If the toy drawn is found to be defective, what is the probability that it is manufactured by the machine B?
(a) $\frac{17}{69}$ (b) $\frac{28}{69}$
(c) $\frac{35}{69}$ (d) none of these

38. An architecture company built 200 bridges 400 hospitals and 600 hotels. The probability of damage due to earthquake of a bridge, hospital and hotel is 0.01, 0.03 and 0.15 respectively. One of the construction gets damaged with earthquake. What is the probability that it is a bridge?
(a) $\frac{1}{26}$ (b) $\frac{1}{52}$
(c) $\frac{7}{52}$ (d) none of these

39. There are 3 boxes each containing 3 red and 5 green balls. Also there are 2 boxes, each containing 4 red and 2 green balls. A green ball is selected at random. Find the probability that this green ball is from a box of the first group.
(a) $\frac{54}{61}$ (b) $\frac{45}{61}$
(c) $\frac{8}{31}$ (d) none of these

40. A man speaks truth 3 out of 4 times. He throws a die and reports that it is a six. Find the probability that it is actually a six.
(a) $\frac{3}{8}$ (b) $\frac{5}{8}$
(c) $\frac{7}{8}$ (d) $\frac{1}{12}$

41. A card from a pack of 52 cards is lost. From the remaining cards of pack, two cards are drawn and are found to be diamonds. Find the probability of the missing card to be diamond.
(a) $\frac{39}{50}$ (b) $\frac{11}{50}$
(c) $\frac{23}{25}$ (d) $\frac{3}{26}$

Scanned by CamScanner

yoursmahboob.wordpress.com

EXERCISE

LEVEL 1

1. The digits 1, 2, 3, 4, 5, 6, 7, 8, 9 are written in random order to form a nine digit number. Find the probability that this number is divisible by 4 :
   (a) $\frac{4}{9}$ (b) $\frac{2}{9}$
   (c) $\frac{17}{81}$ (d) none of these

2. A four digit number is formed with the digits 1, 3, 4, 5 without repetition. Find the chance that the number is divisible by 5 :
   (a) $\frac{3}{4}$ (b) $\frac{1}{4}$
   (c) $\frac{9}{16}$ (d) $\frac{1}{16}$

3. Five persons entered the lift cabin on the ground floor of an 8-floor house. Suppose each of them independently and with equal probability can leave the cabin at any floor beginning with the first. Find out the probability that all persons leaving at different floors :
   (a) $\frac{365}{2401}$ (b) $\frac{360}{2401}$
   (c) $\frac{35}{2410}$ (d) none of these

4. If from each of the three boxes containing 3 white and 1 black, 2 white and 2 black, 1 white and 3 black balls, one ball is drawn at random, then the probability that 2 white and 1 black ball will be drawn is :
   (a) $\frac{13}{32}$ (b) $\frac{27}{32}$
   (c) $\frac{19}{32}$ (d) none of these

5. A fair coin is tossed repeatedly. If tail appears on first four tosses, then the probability of head appearing on fifth toss equals :
   (a) $\frac{5}{12}$ (b) $\frac{1}{2}$
   (c) $\frac{5}{6}$ (d) $\frac{1}{6}$

6. There are four calculators and it is known that exacly two of them are defective. They are tested one by one , in a random order till both the defective calculators are identified. Then the probability that only two tests are required is :
   (a) $\frac{5}{6}$ (b) $\frac{1}{2}$
   (c) $\frac{1}{6}$ (d) $\frac{1}{3}$

7. 20 girls, among whom are A and B sit down at a round table. The probability that there are 4 girls between A and B is :
   (a) $\frac{17}{19}$ (b) $\frac{2}{19}$
   (c) $\frac{13}{19}$ (d) $\frac{6}{19}$

8. Two integers x and y are chosen with replacement out of the set $\{0, 1, 2, 3, \ldots 10\}$. Then the probability that $|x - y| > 5$ is :
   (a) $\frac{7}{11}$ (b) $\frac{40}{121}$
   (c) $\frac{35}{121}$ (d) $\frac{30}{121}$

9. The probability that the birthdays of 4 different persons will fall in exactly two calendar months is :
   (a) $\frac{77}{1728}$ (b) $\frac{17}{87}$
   (c) $\frac{11}{144}$ (d) none of these

10. If 6 objects are distributed at random among 6 persons, the probability that atleast one of them will not get any thing is :
    (a) $6 \cdot (6!)$ (b) $\frac{5^6}{6!}$
    (c) $\frac{6^6 - 6!}{6^6}$ (d) none of these

11. There is 4 volume encyclopaedia among 40 books arranged on a shelf in a random order. If the volumes are not necessarily kept side by side, the probability that they occur in increasing order from left to right is :
    (a) $\frac{1}{24}$ (b) $\frac{1}{12}$
    (c) $\frac{1}{10}$ (d) none of these

12. Four numbers are multiplied together. Then the probability that the product will be divisible by 5 or 10 is :
    (a) $\frac{169}{625}$ (b) $\frac{369}{625}$
    (c) $\frac{169}{1626}$ (d) none of these

13. 8 couples (husband and wife) attend a dance show 'Nach Baliye' in a popular TV channel ; A lucky draw in which 4 persons picked up for a prize is held, then the probability that there is atleast one couple will be selected is :
    (a) $\frac{8}{39}$ (b) $\frac{15}{39}$
    (c) $\frac{12}{13}$ (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

14. Three persons A, B and C are to speak at a function along with 4 other persons. if they all speak in random order, the probability that A speaks before B and B speaks before C is :

(a) $\frac{5}{6}$ (b) $\frac{1}{6}$

(c) $\frac{1}{2}$ (d) $\frac{1}{3}$

15. A bag contains 16 coins of which 2 coins are counterfeit with heads on the both sides. The rest are fair coins. One is selected at random from the bag and tossed. The probability of getting a head is :

(a) $\frac{3}{16}$ (b) $\frac{13}{16}$

(c) $\frac{9}{16}$ (d) $\frac{7}{16}$

16. A committee of five persons is to be chosen from a group of 9 people. The probability that a certain married couple will either serve together or not at all is :

(a) 4/9 (b) 5/9

(c) 13/18 (d) none of these

17. A speaks truth in 60% cases and B speaks truth in 80% cases. The probability that they will say the same thing while describing a single event is :

(a) 0.36 (b) 0.56

(c) 0.48 (d) 0.20

18. Two squares are chosen at random on a chessboard, the probability that they have a side in common is :

(a) $\frac{3}{32}$ (b) $\frac{1}{32}$

(c) 1/18 (d) none of these

19. An old person forgets the last two digits of a telephone number, remembering only that these are different dialled at random. The probability that the number is dialled correctly is :

(a) 1/90 (b) 81/91

(c) 2/99 (d) none of these

20. Three squares of a chessboard are chosen at random, the probability that two are of one colour and one of another is :

(a) $\frac{67}{992}$ (b) $\frac{16}{21}$

(c) $\frac{31}{32}$ (d) none of these

21. The probability that a leap year selected at random contains either 53 Sundays or 53 Mondays, is :

(a) $\frac{17}{53}$ (b) $\frac{1}{53}$

(c) $\frac{3}{7}$ (d) none of these

22. In order to get atleast once a head with probability $P \geq 0.9$, the number of times a coin needs to be tossed is :

(a) 3 (b) 2

(c) 5 (d) 4

23. Out of 13 applicants for a job, there are 5 women and 8 men. It is desired to select 2 persons for the job. The probability that atleast one of the selected persons will be a woman is :

(a) $\frac{25}{39}$ (b) $\frac{31}{65}$

(c) $\frac{25}{69}$ (d) $\frac{5}{13}$

24. Nine squares are chosen at random on a chessboard. What is the probability that they form a square of size 3×3?

(a) $\frac{9}{{}^{64}C_9}$ (b) $\frac{36}{{}^{64}C_9}$

(c) $\frac{6}{{}^{64}C_9}$ (d) none of these

25. Seven digits from the numbers 1, 2, 3, 4, 5, 6, 7, 8 and 9 are written in random order. The probability that this seven digit number is divisible by 9 is :

(a) $\frac{7}{9}$ (b) $\frac{1}{9}$

(c) $\frac{2}{91}$ (d) $\frac{4}{9}$

LEVEL 2

1. What is the probability that four S's come consecutively in the word MISSISSIPPI?

(a) $\frac{4}{165}$ (b) $\frac{4}{135}$

(c) $\frac{24}{165}$ (d) none of these

2. Each coefficient in the equation $ax^2 + bx + c = 0$ is determined by throwing ordinary six faced die. Find the probability that the equation will have real roots.

(a) $\frac{34}{161}$ (b) $\frac{43}{216}$

(c) $\frac{25}{36}$ (d) none of these

3. A and B throw alternately a pair of dice. A wins if he throws 6 before B throws 7 and B wins if he throws 7 before A throws 6. Find their respective chance of winning, if A begins.

(a) $\frac{13}{16}, \frac{31}{16}$ (b) $\frac{30}{61}, \frac{31}{61}$

(c) $\frac{31}{61}, \frac{41}{61}$ (d) $\frac{38}{61}, \frac{23}{61}$

4. A consignment of 15 wristwatches contains 4 defectives. The wristwatches are selected at random, one by one and examined. The ones examined are not put back. What is the probability that ninth one examined is the last defective?

(a) $\frac{11}{195}$ (b) $\frac{17}{195}$

(c) $\frac{8}{195}$ (d) $\frac{16}{195}$

5. In a test, an examinee either guesses or copies or knows the answer to a multiple choice question with four choices. The probability that he makes a guess is $\frac{1}{3}$ and the probability that he copies the answer is 1/6. The probability that his answer is correct, given that he copied it, is 1/8. Find the probability that he knew the answer to the question, given that he correctly answered it.

(a) $\frac{17}{39}$ (b) $\frac{13}{29}$

(c) $\frac{24}{29}$ (d) $\frac{24}{39}$

Scanned by CamScanner

yoursmahboob.wordpress.com

6. Given that the sum of two non-negative quantities is 200, the probability that their product is not less than $\frac{3}{4}$ times their greatest product value is :

(a) $\frac{99}{200}$ (b) $\frac{101}{200}$

(c) $\frac{87}{100}$ (d) none of these

7. A pack of cards consists of 9 cards numbered 1 to 9. Three cards are drawn at random with replacement. Then the probability of getting 1 even and 2 odd numbered cards is :

(a) $\frac{3}{143}$ (b) $\frac{100}{243}$

(c) $\frac{50}{343}$ (d) $\frac{7}{72}$

8. Three numbers are to be selected at random without replacement from the set of numbers $\{1, 2, \ldots n\}$. The conditional probability that the third number lies between the first two, if the first number is known to be smaller than the second is :

(a) $\frac{1}{3}$ (b) $\frac{2}{3}$

(c) $\frac{5}{6}$ (d) $\frac{7}{12}$

9. Two numbers b and c are chosen at random with replacement from the numbers 1, 2, 3, 4, 5, 6, 7, 8 and 9. The probability that $x^2 + bx + c > 0$ for all $x \in R$ is :

(a) $\frac{23}{81}$ (b) $\frac{7}{9}$

(c) $\frac{32}{81}$ (d) $\frac{65}{729}$

10. The probabilities that a student passes in Mathematics, Physics and Chemistry are m, p and c, respectively. Of these subjects the student has 75% chance of passing in atleast one, a 50% chance of passing in atleast two and a 40% chance of passing in exactly, two, which of the following relations are true.

(a) $p + m + c = \frac{27}{20}$ (b) $p + m + c = \frac{13}{20}$

(c) $pmc = \frac{1}{10}$ (d) both (a) and (c)

11. A student appears for tests A, B and C. The student is successful if he passes either in tests A and B or tests A and C. The probabilities of the student passing in tests A, B, C are p, q and 1/2 respectively. If the probability that the student is successful is $\frac{1}{2}$ then,

(a) $p = 1, q = 0$

(b) $p = 0, q = 1$

(c) $\frac{p}{q} = 1$

(d) infinitely many solutions

12. If $\frac{1+4p}{p}, \frac{1-p}{4}, \frac{1-2p}{2}$ are probabilities of three mutually exclusive events then

(a) $p = \frac{1}{2}$ (b) $p = \frac{3}{4}$

(c) $p = \frac{1}{3}$ (d) none of these

13. A letter is takenout at random from 'ASSISTANT' and another is taken out from "STATISTICS'. The probability that they are the same letters is :

(a) $\frac{35}{96}$ (b) $\frac{19}{90}$

(c) $\frac{19}{96}$ (d) none of these

14. Two numbers a and b are chosen at random from the set of first 30 natural numbers. The probability that $a^2 - b^2$ is divisible by 3 is :

(a) $\frac{37}{87}$ (b) $\frac{47}{87}$

(c) $\frac{17}{29}$ (d) none of these

15. A man takes a step forward with probability 0.4 and backward with probability 0.6. The probability that at the end of eleven steps he is one step away from the starting point is :

(a) ${}^{11}C_6(0.1)^{11}$ (b) ${}^{11}C_6(0.24)^5$

(c) ${}^{11}C_6(0.2)^{11}$ (d) none of these

16. Three of the six vertices of a regular hexagon are chosen at random. The probability that the triangle with these three vertices is equilateral equals :

(a) $\frac{1}{6}$ (b) $\frac{1}{3}$

(c) $\frac{1}{10}$ (d) none of these

17. A man can take a step forward, backward, left or right with equal probability. Find the probability that after nine steps he will be just one step away from his initial position.

(a) $\frac{3696}{7^4}$ (b) $\frac{3969}{4^7}$

(c) $\frac{4^4}{10}$ (d) none of these

18. Urn A contains six red and four black balls and urn B has four red and six black balls. One ball is drawn at random from urn A and placed in urn B. Then one ball is transfered at random from urn B to urn A. If one ball is now drawn at random from urn A, find the probability that it is red.

(a) $\frac{32}{65}$ (b) $\frac{32}{55}$

(c) $\frac{23}{55}$ (d) $\frac{56}{65}$

19. The digits 1, 2, 3, ..., 9 are written in random order to form a nine digit number. Find the probability that this number is divisible by 11.

(a) $\frac{11}{63}$ (b) $\frac{11}{81}$

(c) $\frac{11}{126}$ (d) none of these

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE- 20.1

1 (a)	2. (a)	3. (b)	4. (b)	5. (c)	6. (d)	7. (d)	8. (a)	9. (b)	10. (c)
11. (d)	12. (d)	13. (c)	14. (b)	15. (a)	16. (a)	17. (b)	18. (c)	19. (b)	20. (c)
21. (c)	22. (d)	23. (b)	24. (c)	25. (c)	26. (b)	27. (d)	28. (a)	29. (b)	30. (c)
31. (c)	32. (c)	33. (c)	34. (b)	35. (a)	36. (a)	37. (b)	38. (b)	39. (c)	40. (a)
41. (b)	42. (b)	43. (c)	44. (c)	45. (c)	46. (a)	47. (c)	48. (d)	49. (a)	50. (b)
51. (a)	52. (b)	53. (c)	54. (a)	55. (b)	56. (c)	57. (b)	58. (c)	59. (a)	

INTRODUCTORY EXERCISE- 20.2

1 (a)	2. (b)	3. (c)	4. (a)	5. (b)	6. (c)	7. (c)	8. (b)	9. (a)	10. (b)
11. (b)	12. (c)	13. (c)	14. (a)	15. (b)	16. (b)	17. (a)	18. (b)	19. (b)	20. (c)
21. (a)	22. (b)	23. (c)	24. (c)	25. (a)	26. (c)	27. (b)	28. (c)	29. (a)	

INTRODUCTORY EXERCISE- 20.3

1 (b)	2. (b)	3. (c)	4. (a)	5. (a)	6. (c)	7. (a)	8. (c)	9. (a)	10. (b)
11. (a)	12. (b)	13. (b)	14. (a)	15. (b)	16. (c)	17. (a)	18. (a)	19. (a)	20. (b)
21. (a)	22. (b)								

INTRODUCTORY EXERCISE- 20.4

1 (a)	2. (b)	3. (b)	4. (c)	5. (d)	6. (b)	7. (a)	8. (a)	9. (c)	10. (a)
11. (b)	12. (c)	13. (c)	14. (b)	15. (c)	16. (b)	17. (a)	18. (a)	19. (b)	20. (c)
21. (b)	22. (a)	23. (b)	24. (c)	25. (b)	26. (c)	27. (c)	28. (a)	29. (a)	30. (b)
31. (a)	32. (b)	33. (c)	34. (b)	35. (b)	36. (d)	37. (b)	38. (b)	39. (b)	40. (a)
41. (b)									

LEVEL-1

1 (b)	2. (b)	3. (b)	4. (a)	5. (b)	6. (c)	7. (b)	8. (d)	9. (a)	10. (c)
11. (a)	12. (b)	13. (b)	14. (b)	15. (c)	16. (a)	17. (b)	18. (c)	19. (a)	20. (b)
21. (c)	22. (d)	23. (a)	24. (b)	25. (b)					

LEVEL-2

1 (a)	2. (b)	3. (b)	4. (c)	5. (c)	6. (b)	7. (b)	8. (a)	9. (c)	10. (d)
11. (d)	12. (a)	13. (b)	14. (b)	15. (b)	16. (c)	17. (b)	18. (b)	19. (c)	

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 20.1

1. Here the sample space $S = \{H, T\} \Rightarrow n(S) = 2$
Event of getting head $= \{H\} \Rightarrow n(E) = 1$
∴ Probability of getting a head is given by $P(E) = \frac{1}{2}$

Solutions for question number 2-5 :

$S = \{HH, HT, TH, TT\} \Rightarrow n(S) = 4$

2. $E = \{HT, TH\} \Rightarrow n(E) = 2$
$\therefore P(E) = \frac{n(E)}{n(S)} = \frac{2}{4} = \frac{1}{2}$

3. $E = \{HH, HT, TH\} \Rightarrow n(E) = 3$
$\therefore P(E) = \frac{3}{4}$

4. $E = \{H, H\} \Rightarrow n(E) = 1$
$\therefore P(E) = \frac{1}{4}$

5. $E = \{H, H\} \Rightarrow n(E) = 1$
$\therefore P(E) = \frac{1}{4}$

Solutions for question number 6-12 :

$S = \{HHH, HHT, HTH, HTT, THH, THT, TTH, TTT\}$
$\Rightarrow n(S) = 8$

6. $E = \{HTT, THT, TTH\} \Rightarrow n(E) = 3$
$\therefore P(E) = \frac{3}{8}$

7. $E = \{HHT, HTH, THH\} \Rightarrow n(E) = 3$
$\therefore P(E) = \frac{3}{8}$

8. $E = \{HHH, HHT, HTH, HTT, THH, THT, TTH\}$
$\Rightarrow n(E) = 7$
$\therefore P(E) = \frac{7}{8}$

9. $E = \{HHT, HTH, THH\} \Rightarrow n(E) = 3$
$\therefore P(E) = \frac{3}{8}$

10. $E = \{HHH, HHT, HTH, THH\} \Rightarrow n(E) = 4$
$\therefore P(E) = \frac{4}{8} = \frac{1}{2}$

11. $E = \{HHT, HTH, HTT, THH, THT, TTH\}$
$\Rightarrow n(E) = 6$
$\therefore P(E) = \frac{6}{8} = \frac{3}{4}$

12. $E = \{HHH, HHT, HTH, THH\} \Rightarrow n(E) = 4$
$\therefore p(E) = \frac{4}{8} = \frac{1}{2}$

Solutions for question number 13-16 :

$S = \{1, 2, 3, 4, 5, 6\} \Rightarrow n(S) = 6$

13. $E = \{1, 2, 3, 4, 5, 6\} \Rightarrow n(E) = 6$
$\therefore P(E) = \frac{6}{6} = 1$

14. $E = \{3, 6\} \Rightarrow n(E) = 2$
$\therefore P(E) = \frac{2}{6} = \frac{1}{3}$

15. $E = \{2, 3, 5\} \Rightarrow n(E) = 3$
$\therefore P(E) = \frac{3}{6} = \frac{1}{2}$

16. $E = \{2, 4, 6\} \Rightarrow n(E) = 3$
$\therefore P(E) = \frac{3}{6} = \frac{1}{2}$

Solution for question number 17 and 18 :

$S = \{HHH, HHT, HTH, THH, TTH, THT, HTT, TTT\}$
$\Rightarrow n(S) = 8$

17. $E = \{HHT, HTH, THH, TTH, THT, HTT\}$
$\Rightarrow n(E) = 6 \quad \therefore P(E) = \frac{6}{8} = \frac{3}{4}$

18. $E = \{TTT\} \Rightarrow n(E) = 1$
$\therefore P(E) = \frac{1}{8}$

Solutions for question number 19-27 :

$S = \{(1, 1), (1, 2), (1, 3), (1, 4), (1, 5), (1, 6), (2, 1), (2, 2), \ldots (6, 5), (6, 6)\}$
$\Rightarrow n(S) = 6 \times 6 = 36$

19. $E = \{(6, 3), (5, 4), (4, 5), (3, 6)\}$
$n(E) = 4$
$\therefore P(E) = \frac{4}{36} = \frac{1}{9}$

20. $E = \{(6, 4), (5, 5), (4, 6), (6, 5), (5, 6), (6, 6)\}$
$n(E) = 6$
$\therefore P(E) = \frac{6}{36} = \frac{1}{6}$

21. $E = \{(6, 3), (5, 4), (4, 5), (3, 6), (6, 5), (5, 6)\}$
$\Rightarrow n(E) = 6$
$\therefore P(E) = \frac{6}{36} = \frac{1}{6}$

22. $E = \{(1, 1), (2, 2), (3, 3), (4, 4), (5, 5), (6, 6)\}$
$n(E) = 6$
$\therefore P(E) = \frac{6}{36} = \frac{1}{6}$

Scanned by CamScanner

yoursmahboob.wordpress.com

23. $E = \{(2, 2), (4, 4), (6, 6)\} \Rightarrow n(E) = 3$

$\therefore \quad P(E) = \frac{3}{36} = \frac{1}{12}$

24. $E = \{(2, 3), (2, 6), (4, 3), (4, 6), (6, 3), (6, 6) (3, 2), (6, 2), (3, 4), (6, 4), (3, 6)\}$

$\Rightarrow \quad n(E) = 11$

$\therefore \quad P(E) = \frac{11}{36}$

25. $E = \{(1, 2), (1, 5), (2, 1), (2, 4), (3, 3), (3, 6), (4, 2), (4, 5), (5, 1), (5, 4), (6, 3), (6, 6), (1, 3), (2, 2), (2, 6), (3, 1), (3, 5), (4, 4), (5, 3), (6, 2)\}$

$\Rightarrow \quad n(E) = 20$

$\therefore \quad P(E) = \frac{20}{36} = \frac{5}{9}$

26. $E = \{(1, 1), (1, 2), (1, 4), (1, 6), (2, 1), (2, 3), (2, 5), (3, 2), (3, 4), (4, 1), (4, 3), (5, 2), (5, 6), (6, 1), (6, 5)\}$

$\Rightarrow \quad n(E) = 15$

$\therefore \quad P(E) = \frac{15}{36} = \frac{5}{12}$

27. $E = \{(1, 5), (2, 5), (3, 5), (4, 5), (5, 5), (6, 5), (5, 1), (5, 2), (5, 3), (5, 4), (5, 6)\}$

$\Rightarrow \quad n(E) = 11$

$\therefore \quad P(E) = \frac{11}{36}$

✍ ***Solutions for question number 28-35 :*** $S = \{52 \text{ cards}\}$



In each of the four suits there is one ace, one king, one queen and one jack (or knave) and rest 9 cards are numbered.

$\therefore \quad n(S) = 52$

28. $n(E) = 26$

$\therefore \quad P(E) = \frac{26}{52} = \frac{1}{2}$

29. $n(E) = 4$

$\therefore \quad P(E) = \frac{4}{52} = \frac{1}{13}$

30. Since drawn card must be black so there are only two queens.

Hence $n(E) = 2$

$\therefore \quad P(E) = \frac{2}{52} = \frac{1}{26}$

31. There are 26 black cards (including two queens). Besides it there are two more queens (in red colours)

Thus $n(E) = 26 + 2 = 28$

$\therefore \quad P(E) = \frac{28}{52} = \frac{7}{13}$

32. There are 4 kings and 4 queens

$\therefore \quad E = K \cup Q$

$\therefore \quad n(E) = 4 + 4 = 8$

$\therefore \quad P(E) = \frac{8}{52} = \frac{2}{13}$

33. There are 13 hearts (including one queen and one king). Besides it there are 3 queens and 3 kings in remaining 3 suits each.

Thus $n(E) = 13 + 3 + 3 = 19$

$\therefore \quad P(E) = \frac{19}{52}$

34. There are 13 spades (including one king). Besides there are 3 more kings in remaining 3 suits).

Thus $n(E) = 13 + 3 = 16$

Hence $n(\bar{E}) = 52 - 16 = 36$

$\therefore \quad P(\bar{E}) = \frac{36}{52} = \frac{9}{13}$

35. There are 4 aces and 4 kings

$\therefore \quad n(E) = 4 + 4 = 8$

$\therefore \quad n(\bar{E}) = 52 - 8 = 44$

$\therefore \quad P(\bar{E}) = \frac{44}{52} = \frac{11}{13}$

36. There are 4 aces, 4 kings and 4 jacks and their selection can be made in following ways.

$${}^{12}C_1 \times {}^{8}C_1 \times {}^{4}C_1 = 12 \times 8 \times 4$$

$$n(E) = 12 \times 8 \times 4$$

Total selection can be made $= {}^{52}C_3 = 52 \times 51 \times 50$

$$P(E) = \frac{12 \times 8 \times 4}{52 \times 51 \times 50} = \frac{16}{5525}$$

37. $E = \{(1, 1, 1, 1), (2, 2, 2, 2) \ldots\ldots (13, 13, 13, 13)\}$

$\therefore \quad n(E) = 13$

and $n(S) = {}^{52}C_4 = 270725$

$\therefore \quad P(E) = \frac{n(E)}{n(S)} = \frac{13}{270725} = \frac{1}{20825}$

38. $n(E) = {}^{13}C_1 \times {}^{13}C_1 \times {}^{13}C_1 \times {}^{13}C_1 = (13)^4$

$n(S) = {}^{52}C_4 = 270725$

$\therefore \quad P(E) = \frac{n(E)}{n(S)} = \frac{(13)^4}{270725} = \frac{2197}{20825}$

39. $n(E) = {}^{13}C_1 \times {}^{12}C_1 \times {}^{11}C_1 \times {}^{10}C_1 = 13 \times 12 \times 11 \times 10$

$n(S) = {}^{52}C_4 = 270725$

$\therefore \quad P(E) = \frac{13 \times 12 \times 11 \ 10}{270725} = \frac{264}{4165}$

✍ ***Solutions for question number 40-43 :***

$$n(S) = 6 \times 6 \times 6 \times 6 = 6^4$$

40. $n(E) = 6$

$\because \quad E = \{(1, 1, 1, 1), (2, 2, 2, 2), (3, 3, 3, 3) \ldots (6, 6, 6, 6)\}$

$\therefore \quad P(E) = \frac{n(E)}{n(S)} = \frac{6}{6^4} = \frac{1}{6^3} = \frac{1}{216}$

41. $n(E) = {}^{6}C_1 \times {}^{5}C_1 \times {}^{4}C_1 \times {}^{3}C_1 = 360$

$\therefore \quad P(E) = \frac{360}{6^4} = \frac{5}{18}$

42. Select a number which occurs on two dice out of six numbers (1, 2, 3, 4, 5, 6). This can be done in ${}^{6}C_1$, ways.
Now select two distinct number out of remaining 5 numbers which can be done in ${}^{5}C_2$ ways. Thus these 4 numbers can be arranged in $\frac{4!}{2!}$ ways.

Scanned by CamScanner

yoursmahboob.wordpress.com

So, the number of ways in which two dice show the same face and the remaining two show different faces is

$$^6C_1 \times {}^5C_2 \times \frac{4!}{2!} = 720$$

$$n(E) = 720$$

$$\therefore \quad P(E) = \frac{720}{6^4} = \frac{5}{9}$$

$\therefore$

43. There are 3 possible cases-
(i) 2 similar faces + 2 different faces
(ii) 3 similar faces + 1 different face
(iii) all 4 faces are similar
$\therefore$ Required number of ways

$$= \left({}^6C_1 \times {}^5C_2 \times \frac{4!}{2!}\right) + \left({}^6C_1 \times {}^5C_1 \times \frac{4!}{3!}\right) + \left({}^6C_1 \times \frac{4!}{4!}\right)$$

$$= (6 \times 10 \times 12) + (6 \times 5 \times 4) + 6 = 846$$

$$\therefore \quad n(E) = 846$$

and $\quad n(S) = 6^4$

$$\therefore \quad P(E) = \frac{846}{6^4} = \frac{47}{72}$$

44. $E = \{2, 3, 5, 7, 11, 13, 17, 19\}$

$$\Rightarrow \quad n(E) = 8$$

$$S = \{1, 2, 3, 4, \ldots 20\}$$

$$\Rightarrow \quad n(S) = 20$$

$$\therefore \quad P(E) = \frac{n(E)}{n(S)} = \frac{8}{20} = \frac{2}{5}$$

45. $S = \{1, 2, 3, 4, \ldots . 18\} \Rightarrow n(S) = 18$

$E_1 = \{2, 4, 6, 8, 10, 12, 14, 16, 18\}$

$$\Rightarrow \quad n(E_1) = 9$$

$E_2 = \{3, 6, 9, 12, 15, 18\} \Rightarrow n(E_2) = 6$

$(E_1 \cap E_2) = E_3 = \{6, 12, 18\} \Rightarrow n(E_3) = 3$

$$\therefore \quad E = E_1 \cup E_2 = E_1 + E_2 - E_3$$

$$n(E) = 9 + 6 - 3$$

$$n(E) = 12$$

where $E = \{2, 3, 4, 6, 8, 9, 10, 12, 14, 15, 16, 18\}$

$$\therefore \quad P(E) = \frac{n(E)}{n(S)} = \frac{12}{18} = \frac{2}{3}$$

NOTE For any problem refer set theory and number system.

46. $$n(S) = {}^{100}C_2 = \frac{100 \times 99}{2} = 4950$$

$$n(E) = {}^{25}C_2 = 300$$

$$\therefore \quad P(E) = \frac{300}{4950} = \frac{2}{33}$$

HINT There are total 25 prime numbers upto 100.

47. $$n(S) = {}^{100}C_2 = 4950$$

$$n(E) = {}^{75}C_2 = 2775 \qquad (100 - 25 = 75)$$

$$\therefore \quad P(E) = \frac{2775}{4950} = \frac{37}{66}$$

48. $366 = 7 \times 52 + 2$
It means a leap year has 52 full weeks and 2 more days. These 2 days can be :
(i) Sunday and Monday
(ii) Monday and Tuesday
(iii) Tuesday and Wednesday
(iv) Wednesday and Thursday
(v) Thursday and Friday
(vi) Friday and Saturday
(vii) Saturday and Sunday
Clearly atleast there are 52 Sundays.
Now, for having 53 Sundays in the year, one of the above 2 consecutive, days must be Sunday.
Thus, out of the above 7 possibilities, 2 possibilities are in favour [(i) and (vii)] of the event that one of the two days is a Sunday.

$\therefore$ Required probability $= \frac{2}{7}$

49. $$n(S) = 8 + 4 = 12$$

$$n(E) = 8$$

$$\therefore \quad P(E) = \frac{8}{12} = \frac{2}{3}$$

50. $$n(S) = {}^{12}C_4 = 495$$

$$n(E) = {}^8C_4 = 70$$

$$\therefore \quad P(E) = \frac{70}{495} = \frac{14}{99}$$

51. $$n(S) = {}^{12}C_4 = 495$$

$$n(E) = {}^4C_4 = 1$$

$$\therefore \quad P(E) = \frac{1}{495}$$

52. $$n(S) = {}^{12}C_4 = 495$$

$$n(E) = {}^8C_2 \times {}^4C_1 = 112$$

$$\therefore \quad P(E) = \frac{112}{495}$$

53. $$n(S) = 495$$

$$n(E) = {}^4C_3 = 4$$

$$\therefore \quad P(E) = \frac{4}{495}$$

54. Total number of outcomes $= 2 + 7 = 9$
Favourable number of cases $= 2$

$$\therefore \quad P(E) = \frac{2}{9}$$

55. Total number of outcomes $= 5 + 7 = 12$
Number of cases against the occurrence of event $= 5$
$\therefore$ Number of cases in favour of event $= 12 - 5 = 7$

$$\therefore \quad P(E) = \frac{7}{12}$$

56. $S = \{GG, GB, BG, BB\}$

and $\quad E = \{GG, GB, BG\}$

$$\therefore \quad P(E) = \frac{n(E)}{n(S)} = \frac{3}{4}$$

57. $$n(S) = {}^5C_2 = 10$$

$$n(E) = ({}^2C_1 \times {}^3C_1) + ({}^2C_2) = 7$$

$$\therefore \quad P(E) = \frac{7}{10}$$

58. $$n(S) = {}^{20}C_2 = 190$$

$$n(E) = {}^{15}C_2 = 105$$

$$\therefore \quad P(E) = \frac{105}{190} = \frac{21}{38}$$

59. $$n(S) = {}^{20}C_4 = 4845$$

$$n(E) = ({}^5C_3 \times {}^{15}C_1) + ({}^5C_4) = 155$$

$$\therefore \quad P(E) = \frac{155}{4845} = \frac{31}{969}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

INTRODUCTORY EXERCISE 20.2

1. $P(A)=\frac{1}{4}, P(B)=\frac{1}{2}$ and $P(A\cap B)=\frac{7}{50}$

$\therefore$ $P(A \text{ or } B)=P(A\cup B)$

$=P(A)+P(B)-P(A\cap B)$

$=\frac{1}{4}+\frac{1}{2}-\frac{7}{50}=\frac{61}{100}$

2. P (neither A nor B) $=P(\bar{A}$ and $\bar{B})$

$=P(\bar{A}\cap\bar{B})=P(\overline{A\cup B})=1-P(A\cup B)$

$=1-\frac{61}{100}=\frac{39}{100}$

3. $P(A\cup B)=P(A)+P(B)-P(A\cap B)$

$=\frac{3}{10}+\frac{1}{2}-\frac{1}{5}=\frac{6}{10}=\frac{3}{5}$

4. $P(A\cup B)=P(A)+P(B)-P(A\cap B)$

$\frac{3}{5}=\frac{2}{5}+\frac{1}{2}-P(A\cap B)$

$\Rightarrow$ $P(A\cap B)=\frac{3}{10}$

5. $P(\bar{A})=1-P(A)=1-\frac{2}{5}=\frac{3}{5}$

6. $P(\bar{B})=1-P(B)=1-\frac{1}{2}=\frac{1}{2}$

7. $P(A\cup B)=P(A)+P(B)-P(A\cap B)$

$=\frac{2}{5}+\frac{1}{2}-0=\frac{9}{10}$ $(\because P(A\cap B)=0)$

8. $P(\bar{A}\cap\bar{B})=P(\overline{A\cup B})=1-P(A\cup B)$

$=1-\frac{9}{10}=\frac{1}{10}$

9. $P(\bar{A}\cap B)=P(B)-P(A\cap B)$

$=P(B)=\frac{1}{2}$ $(\because P(A\cap B)=0)$

10. $P(A\cap\bar{B})=P(A)-P(A\cap B)=\frac{2}{5}$

11. $P(A\cup B)=P(A)+P(B)$

$0.65=0.35+P(B)$ $(\because P(A)=1-P(\bar{A}))$

$\Rightarrow$ $P(B)=0.30$

12. Let $P(A)=x$, then $P(B)=\frac{3}{2}x$ and $P(C)=\frac{1}{2}\times\frac{3}{2}x=\frac{3}{4}x$

$\therefore$ $P(A)+P(B)+P(C)=P(A\cup B\cup C)=P(S)=1$

$\therefore$ $x+\frac{3}{2}x+\frac{3}{4}x=1$

$\Rightarrow$ $x=\frac{4}{13}$

$\therefore$ $P(A)=\frac{4}{13}$

13. $n(S)=6\times6=36$

Let A = Event of getting an even number on the first die

$\therefore$ $n(A)=3\times6=18$

and B = Event of getting a total of 8

$n(B)=5$

$A=\begin{Bmatrix}(2,1),(2,2),(2,3)\ldots.(2,6)\\(4,1)\ldots\ldots\ldots\ldots\ldots(4,6)\\(6,1)\ldots\ldots\ldots\ldots\ldots(6,6)\end{Bmatrix}$

$B=\{(6,2),(5,3),(4,4),(3,5),(2,6)\}$

$\therefore$ $n(A)=3\times6=18$

and $n(B)=5$

$\therefore$ $(A\cap B)=\{(2,6),(6,2),(4,4)\}$

$\therefore$ $n(A\cap B)=3$

$P(A)=\frac{18}{36}=\frac{1}{2}$, $P(B)=\frac{5}{36}$

and $P(A\cap B)=\frac{3}{36}=\frac{1}{12}$

$\therefore$ P (Even number on first die or a total of 8)

$=p(A \text{ or } B)=P(A\cup B)$

$=P(A)+P(B)-P(A\cap B)$

$=\frac{1}{2}+\frac{5}{36}-\frac{1}{12}=\frac{5}{9}$

14. $A=\{(5,1),)\ (5,2),(5,3),(5,4),(5,5),(5,6)\}$

$B=\{(1,5),(2,5),(3,5),(4,5),(5,5),(6,5)\}$

$A\cap B=\{(5,5)\}$

Also $n(S)=36$

$\therefore$ $P(A)=\frac{6}{36}=\frac{1}{6}$

$P(B)=\frac{6}{36}=\frac{1}{6}$

and $P(A\cap B)=\frac{1}{36}$

$\therefore$ Required probability $=P(A)+P(B)-P(A\cap B)$

$=\frac{1}{6}+\frac{1}{6}-\frac{1}{36}=\frac{11}{36}$

15. $n(S)=36$

$A=\{(1,1),)\ (2,2),(3,3),(4,4),(5,5),(6,6)\}$

$B=\{(2,6),(3,5),(4,4),(5,3),(6,2)\}$

$(A\cap B)=\{(4,4)\}$

$n(A)=6,\ n(B)=5,\ n(A\cap B)=1$

$\therefore$ Required probability $=P(A\cup B)$

$=P(A)+P(B)-P(A\cap B)$

$=\frac{6}{36}+\frac{5}{36}-\frac{1}{36}$

$=\frac{10}{36}=\frac{5}{18}$

16. See the solution of question number 14

P (atleast one die shows 6) $=\frac{11}{36}$

17. $n(S)=52$

$A\rightarrow$ The event of getting a heart

$B\rightarrow$ The event of getting a king

then $A\cap B\rightarrow$ The event of getting a king of heart.

$\therefore$ $P(A)=\frac{13}{52}=\frac{1}{4}$, $P(B)=\frac{4}{52}=\frac{1}{13}$

Scanned by CamScanner

yoursmahboob.wordpress.com

and $P(A \cap B) = \frac{1}{52}$

$\therefore$ P (a heart or a king) $= P(A \text{ or } B) = P(A \cup B)$

$= P(A) + P(B) - P(A \cap B)$

$= \frac{1}{4} + \frac{1}{13} - \frac{1}{52} = \frac{4}{13}$

18. $n(S) = {}^{52}C_2 = 1326$

Let A = event of getting both red cards

and B = event of getting both queens

then $A \cap B$ = event of getting two red queens

$n(A) = {}^{26}C_2 = 325, n(B) = {}^{4}C_2 = 6$

$n(A \cap B) = {}^{2}C_2 = 1$

$\therefore$ $P(A) = \frac{325}{1326}$, $P(B) = \frac{6}{1326} = \frac{1}{221}$

$P(A \cap B) = \frac{1}{1326}$

$\therefore P$ (both red or both queens) $= P(A \cup B)$

$= P(A) + P(B) - P(A \cap B)$

$= \frac{325}{1326} + \frac{1}{221} - \frac{1}{1326} = \frac{55}{221}$

19. $n(S) = 52$

Let A, B, C be the events of getting a red card, a heart and a king respectively.

then $n(A) = 26$, $n(B) = 13$, $n(C) = 4$

Clearly $n(A \cap B) = 13$, $n(B \cap C) = 1$,

$n(A \cap C) = 2$, $n(A \cap B \cap C) = 1$

$\therefore P(A) = \frac{26}{52} = \frac{1}{2}$, $P(B) = \frac{13}{52} = \frac{1}{4}$, $P(C) = \frac{4}{52} = \frac{1}{13}$

$P(A \cap B) = \frac{13}{52} = \frac{1}{4}$, $P(B \cap C) = \frac{1}{52}$,

$P(A \cap C) = \frac{2}{52} = \frac{1}{26}$

$P(A \cap B \cap C) = \frac{1}{52}$

$\therefore P$ (a red card, or a heart or a king) $= P(A \cup B \cup C)$

$= P(A) + P(B) + P(C) - (P(A \cap B) + P(B \cap C) + P(A \cap C)$

$+ P(A \cap B \cap C)$

$= \frac{1}{2} + \frac{1}{4} + \frac{1}{13} - \left(\frac{1}{4} + \frac{1}{52} + \frac{1}{26}\right) + \frac{1}{52} = \frac{7}{13}$

20. $n(S) = {}^{52}C_4$

Let E_1, E_2, E_3, E_4 be the events of getting all spades, all clubs, all hearts and all diamonds respectively.

Then $n(E_1) = {}^{13}C_4$

$n(E_2) = {}^{13}C_4$

$n(E_3) = {}^{13}C_4$

$n(E_4) = {}^{13}C_4$

$\therefore$ $P(E_1) = \frac{{}^{13}C_4}{{}^{52}C_4}$, $P(E_2) = \frac{{}^{13}C_4}{{}^{52}C_4}$,

$P(E_3) = \frac{{}^{13}C_4}{{}^{52}C_4}$, $P(E_4) = \frac{{}^{13}C_4}{{}^{52}C_4}$

Since E_1, E_2, E_3 and E_4 are mutually exclusive events.

$\therefore P$ (getting all the 4 cards of the same suit)

$P(E_1 \text{ or } E_2 \text{ or } E_3 \text{ or } E_4) = P(E_1) + P(E_2) + P(E_3) + P(E_4)$

$= 4 \times \left(\frac{{}^{13}C_4}{{}^{52}C_4}\right) = \frac{44}{4165}$

21. $n(S) = 52$

A = The event of getting a king

B = The event of getting a queen

$(A \cap B)$ = The event of getting a king and a queen both

$\therefore$ $n(A) = 4$, $n(B) = 4$, $n(A \cap B) = 0$

$P(A) = \frac{4}{52}$, $P(B) = \frac{4}{52}$

$\therefore$ $P(A \cup B) = P(A) + P(B) = \frac{4}{52} + \frac{4}{52} = \frac{2}{13}$

22. $n(S) = {}^{52}C_2 = 1326$

Let A be the event of getting two black cards

and B be the event of getting two jacks

and $(A \cap B)$ be the event of getting two black jacks.

$\therefore$ $n(A) = {}^{26}C_2$, $n(B) = {}^{4}C_2$, $n(A \cap B) = {}^{2}C_2$

$\therefore$ $P(A) = \frac{{}^{26}C_2}{{}^{52}C_2}$, $P(B) = \frac{{}^{4}C_2}{{}^{52}C_2}$, $P(A \cap B) = \frac{{}^{2}C_2}{{}^{52}C_2}$

$\therefore$ Required probability $= P(A \cup B)$

$= P(A) + P(B) - P(A \cap B)$

$= \frac{{}^{26}C_2}{{}^{52}C_2} + \frac{{}^{4}C_2}{{}^{52}C_2} - \frac{{}^{2}C_2}{{}^{52}C_2}$

$= \frac{325}{1326} + \frac{1}{221} - \frac{1}{1326} = \frac{55}{221}$

23. $n(S) = 300$

Let A be the event of getting a number divisible by 3 and

B be the event of getting a number divisible by 5 and

$(A \cap B)$ be event of getting a number divisible by 3 and 5 both

$\therefore$ $n(A) = 100$, $n(B) = 60$, $n(A \cap B) = 20$

$\therefore$ $P(A) = \frac{100}{300} = \frac{1}{3}$, $P(B) = \frac{60}{300} = \frac{1}{5}$, $P(A \cap B) = \frac{20}{600} = \frac{1}{30}$

$\therefore$ $P(A \cup B) = P(A) + P(B) - P(A \cap B)$

$= \frac{1}{3} + \frac{1}{5} - \frac{1}{30} = \frac{1}{2}$

24. $n(S) = 100$

Let A be the event of getting a number divisible by 2 and

B be the event of getting a number divisible by 3 and

C be the event of getting of number divisible by 5.

$\therefore (A \cap B)$ be the event of getting a number divisible by both 2 and 3.

$(B \cap C)$ be the event of getting a number divisible by both 3 and 5.

$(A \cap C)$ be the event of getting a number divisible by both 2 and 5.

$(A \cap B \cap C)$ be the event of getting a number divisible by A, B and C.

Now, $n(A) = 50$, $n(B) = 33$, $n(C) = 20$, $n(A \cap B) = 16$,

$n(B \cap C) = 6$, $n(A \cap C) = 10$, $n(A \cap B \cap C) = 3$

$\therefore$ $P(A) = \frac{50}{100} = \frac{1}{2}$, $P(B) = \frac{33}{100}$,

$P(C) = \frac{20}{100} = \frac{1}{5}$, $n(A \cap B) = \frac{16}{100}$

Scanned by CamScanner

yoursmanboob.wordpress.com

$$n(B \cap C)=\frac{6}{100},\quad n(A \cap C)=\frac{10}{100},$$

$$n(A \cap B \cap C)=\frac{3}{100}$$

Required probability $= P(A \cup B \cup C)$

$$= P(A)+P(B)+P(C)-[P(A \cap B) + P(B \cap C)+P(A \cap C)]+P(A \cap B \cap C)$$

$$=\frac{50}{100}+\frac{33}{100}+\frac{20}{100}-\left(\frac{16}{100}+\frac{6}{100}+\frac{10}{100}\right)+\frac{3}{100}$$

$$=\frac{74}{100}$$

25. $n(S)=5+8+10=23$

$n(A)=5$

$n(B)=8$ $\quad [n(A \cap B)=0]$

$\therefore \quad P(A)=\frac{5}{23}$ and $P(B)=\frac{8}{23}$ $\quad P(A \cap B)=0$

$\therefore \quad P(A \cup B)=P(A)+P(B)=\frac{5}{23}+\frac{8}{23}=\frac{13}{23}$

26. $n(S)={}^{30}C_2$

Let A be the event of getting two oranges and
B be the event of getting two non-defective fruits.
and $(A \cap B)$ be the event of getting two non-defective oranges

$\therefore \quad P(A)=\frac{{}^{20}C_2}{{}^{30}C_2}, P(B)=\frac{{}^{22}C_2}{{}^{30}C_2}$

and $\quad P(A \cap B)=\frac{{}^{15}C_2}{{}^{30}C_2}$

$\therefore \quad P(A \cup B)=P(A)+P(B)-P(A \cap B)$

$$=\frac{{}^{20}C_2}{{}^{30}C_2}+\frac{{}^{22}C_2}{{}^{30}C_2}-\frac{{}^{15}C_2}{{}^{30}C_2}=\frac{316}{435}$$

HINT There are 20 oranges, and $30-(3+5)=22$ non-defective fruits and $20-5=15$ non-defective oranges.

27. $n(S)=100$

$n(A)=40, \quad n(B)=20, \quad n(A \cap B)=5$

$\therefore \quad P(A \cup B)=P(A)+P(B)-P(A \cap B)$

$$=\frac{40}{100}+\frac{20}{100}-\frac{5}{100}$$

$$P(A \cup B)=\frac{55}{100}=55\%$$

28. $P(A)=\frac{2}{5}, \quad P(B)=\frac{1}{3}$

$\therefore \quad P(A \cup B)=\frac{2}{5}+\frac{1}{3}=\frac{11}{15}$

($\because A$ and B are mutually exclusive events)

29. $P(H_1)=\frac{1}{3}, P(H_2)=\frac{1}{4}, P(H_3)=\frac{1}{5}, P(H_4)=\frac{1}{6}$

$\therefore P(H_1 \cup H_2 \cup H_3 \cup H_4)=P(H_1)+P(H_2)+P(H_3)+P(H_4)$

$$=\frac{1}{3}+\frac{1}{4}+\frac{1}{5}+\frac{1}{6}=\frac{57}{60}$$

HINT Here, H_1, H_2, H_3 and H_4 are the mutually exclusive events.

INTRODUCTORY EXERCISE 20.3

1. $P\left(\frac{A}{B}\right)=\frac{1}{2}$ (see the example 1)

2. $P(A \cup B)=0.96$ (see the example 1)

3. Here $S=\{HHH, HHT, HTH, THH, HTT, THT, TTH, TTT\}$

Let A be the event that one of the coins shows a tail

$\therefore \quad A=\{HHT, HTH, THH, HTT, THT, TTH, TTT\}$

$\therefore \quad P(A)=\frac{7}{8}$

Now, let B be the event that they are all tails

$\therefore \quad B=\{TTT\}$

$\therefore \quad P(B)=\frac{1}{8}$

$\therefore \quad (A \cap B)=\{TTT\}$

$\Rightarrow \quad P(A \cap B)=\frac{1}{8}$

$\therefore \quad P\left(\frac{B}{A}\right)=\frac{P(A \cap B)}{P(A)}=\frac{1/8}{7/8}=\frac{1}{7}$

4. Here sample space $S=\{HH, HT, TH, TT\}$

$E=\{HT, TH\}$

$F=\{HH, HT, TH\}$

$\therefore \quad E \cap F=\{HT, TH\}$

$\therefore \quad P(E)=\frac{2}{4}=\frac{1}{2}$ and $P(F)=\frac{3}{4}$

and $\quad P(E \cap F)=\frac{2}{4}=\frac{1}{2}$

$\therefore \quad P\left(\frac{E}{F}\right)=\frac{P(E \cap F)}{P(F)}=\frac{\frac{1}{2}}{\frac{3}{4}}=\frac{2}{3}$

$$P\left(\frac{F}{E}\right)=\frac{P(E \cap F)}{P(E)}=\frac{\frac{1}{2}}{\frac{1}{2}}=1$$

5. Here sample space

$S=\{HH, HT, T1, T2, T3, T4, T5, T6\}$

Let A be the event that the die shows a number greater than 4 and B be the event that the first throw of the coin results in a tail then,

$A=\{T5, T6\}$

$B=\{T1, T2, T3, T4, T5, T6\}$

$\therefore$ Required probability $= P\left(\frac{A}{B}\right)=\frac{P(A \cap B)}{P(B)}=\frac{\frac{2}{8}}{\frac{6}{8}}=\frac{1}{3}$

6. $S=\{1, 2, 3, 4, 5, 6\}$

Let A be the event of getting an odd number and
B be the event of getting a prime number

$\therefore \quad A=\{1, 3, 5\}, \quad B=\{2, 3, 5\}$

Scanned by CamScanner

yoursmahboob.wordpress.com

and $(A \cap B) = \{3, 5\}$

$\therefore P(A) = \frac{3}{6} = \frac{1}{2}, \quad P(B) = \frac{3}{6} = \frac{1}{2}, \quad P(A \cap B) = \frac{2}{6} = \frac{1}{3}$

$\therefore$ Required probability $= P\left(\frac{B}{A}\right) = \frac{P(A \cap B)}{P(A)}$

$= \frac{1/3}{1/2} = \frac{2}{3}$

7. Let A be the event of getting the sum 9 and B be the event of getting atleast one 4.

Then $A = \{(3, 6), (4, 5), (5, 4), (6, 3)\}$

$B = \{(1, 4), (2, 4), (3, 4), (4, 4), (5, 4), (6, 4), (4, 1), (4, 2), (4, 3), (4, 5), (4, 6)\}$

then $A \cap B = \{(4, 5) (5, 4)\}$

$\therefore$ Required probability $= P\left(\frac{B}{A}\right) = \frac{P(A \cap B)}{P(A)}$

$= \frac{n(A \cap B)}{n(A)} = \frac{2}{4} = \frac{1}{2}$

8. Let A = the event of getting 4 on the first die.

and B = the event of getting the sum 8 or greater

$\therefore A = \{(4, 1), (4, 2), (4, 3), (4, 4), (4, 5), (4, 6)\}$

$B = \{(4, 4), (4, 5), (4, 6), (5, 4), (5, 5), (5, 6), (6, 2), (2, 6), (3, 5), (3, 6), (5, 3), (6, 3), (6, 4), (6, 5), (6, 6)\}$

$\therefore A \cap B = \{(4, 4)\}, (4, 5), (4, 6)\}$

$\therefore$ Required probability $= P\left(\frac{B}{A}\right) = \frac{P(A \cap B)}{P(A)}$

$= \frac{n(A \cap B)}{n(A)} = \frac{3}{6} = \frac{1}{2}$

9. Let A = event of getting an odd number

and B = the event of getting a number greater than 1.

$\therefore A = \{1, 3, 5\}, B = \{3, 5\}, A \cap B = \{3, 5\}$

$\therefore$ Required probability $= P\left(\frac{B}{A}\right) = \frac{P(A \cap B)}{P(A)} = \frac{n(A \cap B)}{n(A)} = \frac{2}{3}$

10. Let A be the event of reading English and

B be the event of reading French.

Then $P(A) = \frac{45}{100} = \frac{9}{20}, \quad P(B) = \frac{30}{100} = \frac{3}{10}$

and $P(A \cap B) = \frac{20}{100} = \frac{1}{5}$

$\therefore P\left(\frac{A}{B}\right) = \frac{P(A \cap B)}{P(B)} = \frac{\frac{1}{5}}{\frac{3}{10}} = \frac{2}{3}$

11. $P\left(\frac{B}{A}\right) = \frac{P(A \cap B)}{P(A)} = \frac{1/5}{9/20} = \frac{4}{9}$

12. $S = (B_1B_2, B_1G_2, G_1B_2, G_1G_2)$

Where $B \to$ Boy and $G \to$ Girl

Let A be the event that both are boys

and B be the event that one of two is a boy.

Then $A = \{B_1B_2\}$ and $B = \{B_1B_2, B_1G_2, G_1B_2\}$

So $A \cap B = \{B_1B_2\}$

$\therefore$ Required probability $= P\left(\frac{A}{B}\right) = \frac{n(A \cap B)}{n(B)} = \frac{1}{3}$

13. A be the event that both children are boys

and B be the event that the other child is a boy.

then $A = \{B_1, B_2\}$ and $B = \{B_1B_2, B_1G_2\}$

So $(A \cap B) = \{B_1B_2\}$

$\therefore$ Required probability $= P\left(\frac{A}{B}\right) = \frac{n(A \cap B)}{n(B)} = \frac{1}{2}$

14. $P(E) = \frac{1}{2}$

15. $P(F) = \frac{1}{2}$

16. $P\left(\frac{G}{E}\right)$ = Probability of drawing a red ball when first bag is selected

= Probability of drawing a red ball from first bag

$= \frac{3}{7}$

17. $P\left(\frac{G}{F}\right)$ = Probability of drawing a red ball from second bag

$= \frac{4}{6} = \frac{2}{3}$

18. Let A be the event of not getting a red ball in first draw and B be the event of not getting a red ball in second draw. Then Required probability

= Probability that atleast one ball is red

= 1 – Probability that none is red

= 1 – P(A and B)

$= 1 - P(A \cap B)$

$= 1 - P(A) \cdot P\left(\frac{B}{A}\right)$

$= 1 - \left(\frac{2}{3} \times \frac{5}{8}\right) = \frac{7}{12}$

Here $P(A) = \frac{6}{9} = \frac{2}{3}$

and $P\left(\frac{B}{A}\right) = \frac{5}{8}$ [There are 5 balls (excluding 3 red balls) after the selection of one non-red ball]

19. Let A be the event drawing 4 red ball in first draw and B be the event of drawing 4 blue balls in the second draw.

Then $P(A) = \frac{{}^6C_4}{{}^{15}C_4} = \frac{15}{1365} = \frac{1}{91}$

$P\left(\frac{B}{A}\right) = \frac{{}^9C_4}{{}^{11}C_4} = \frac{126}{330} = \frac{21}{55}$

Hence, the required probability $= P(A \cap B)$

$= P(A) P\left(\frac{B}{A}\right)$

$= \frac{1}{91} \times \frac{21}{55} = \frac{3}{715}$

20. Let A, B, C be the events of getting a white ball in first, second and third draw respectively, then

Required probability $= P(A \cap B \cap C)$

$= P(A) P\left(\frac{B}{A}\right) P\left(\frac{C}{A \cap B}\right)$

Scanned by CamScanner

yoursmahboob.wordpress.com

Now, $P(A)$ = Probability of drawing a white ball in first draw

$$= \frac{4}{18} = \frac{2}{9}$$

When a white ball is drawn in the first draw there are 17 balls left in the urn, out of which 3 are white.

$$\therefore \quad P\left(\frac{B}{A}\right) = \frac{3}{17}$$

Since the ball drawn is not replaced, therefore after drawing a white ball in the second draw there are 16 balls left in the urn, out of which 2 are white.

$$\therefore \quad P\left(\frac{C}{A \cap B}\right) = \frac{2}{16} = \frac{1}{8}$$

Hence the required probability $= \frac{2}{9} \times \frac{3}{17} \times \frac{1}{8} = \frac{1}{204}$

21. There are 4 even numbers and 5 odd numbers

Let A = the event of choosing odd numbers

B = the event of getting the sum an even number.

Then $A \cap B$ = The event of choosing odd numbers whose sum is even.

$$\therefore \quad n(B) = {}^4C_2 + {}^5C_2 = 16$$

and $\quad n(A \cap B) = {}^5C_2 = 10$

$$\therefore \quad \text{Required probability} = P\left(\frac{A}{B}\right)$$

$$= \frac{n(A \cap B)}{n(B)} = \frac{10}{16} = \frac{5}{8}$$

22. Let A be the event of drawing an odd numbered ticket in the first draw and B be the event of drawing an odd numbered ticket in the second draw. Then

$$\text{Required probability} = P(A \cap B) = P(A)\,P\left(\frac{B}{A}\right)$$

$P(A) = \frac{13}{25}$, since there 13 odd numbers 1, 3, 5, ... 25.

Since the ticket drawn in the first draw is not replaced, therefore second ticket drawn is from the remaining 24 tickets, out of which 12 are odd numbered.

$$\therefore \quad P\left(\frac{B}{A}\right) = \frac{12}{24} = \frac{1}{2}$$

Hence, Required probability $= \frac{13}{25} \times \frac{1}{2} = \frac{13}{50}$

INTRODUCTORY EXERCISE 20.4

1. $P(A \cap B) = P(A) \cdot P(B) = 0.6 \times 0.4 = 0.24$

2. $P(A \cup B) = P(A) + P(B) - P(A \cap B)$

$= 0.6 + 0.4 - 0.24 = 0.76$

3. $P(\bar{A} \cap B) = \{1 - P(A)\}\,P(B)$

$= 0.4 \times 0.4 = 0.16$

4. $P(A \cap \bar{B}) = P(A)\{1 - P(B)\}$

$= 0.6 \times 0.6 = 0.36$

5. $P(\bar{A} \cap \bar{B}) = \{1 - P(A)\}\{1 - P(B)\}$

$= 0.4 \times 0.6 = 0.24$

6. $P(\bar{A}) = 0.65 \Rightarrow P(A) = 0.35$

$P(A \cup B) = P(A) + P(B) - P(A \cap B)$

$\Rightarrow \quad P(A \cup B) = P(A) + P(B) - P(A) \cdot P(B)$

$\Rightarrow \quad 0.65 = 0.35 + p - 0.35p$

$\Rightarrow \quad 0.65p = 0.30$

$\Rightarrow \quad p = \frac{6}{13}$

7. $S = \{1, 2, 3, 4, 5, 6\}$, for each case

Let A = event of getting a 1,2, 3 or 4 on the first toss

and B = event of getting a 4, 5 or 6 on the second toss

Then, clearly A and B are independent events.

$$\therefore \quad P(A) = \frac{4}{6} = \frac{2}{3} \quad \text{and} \quad P(B) = \frac{3}{6} = \frac{1}{2}$$

So, required probability $= P(A \cap B)$

$$= P(A) \cdot P(B) = \frac{2}{3} \times \frac{1}{2} = \frac{1}{3}$$

8. Let E = the event that A gets a three

and F = the event that B gets a three

Then, $\quad P(E) = \frac{1}{6}, \quad P(F) = \frac{1}{6}$

$$P(\bar{E}) = \frac{5}{6}, \quad P(\bar{F}) = \frac{5}{6}$$

Suppose A wins then, he gets a three in 1st or 3rd of 5th ... throw etc.

$\therefore P$ (A wins) $= P[E$ or $(\bar{E}\,\bar{F}\,E)$ or $(\bar{E}\,\bar{F}\,\bar{E}\,\bar{F}\,E)$ or ... $\infty]$

$= P[E$ or ($\bar{E}$ and $\bar{F}$ and E) or ($\bar{E}$ and $\bar{F}$ and $\bar{E}$ and $\bar{F}$ and E) or ....]

$= P(E) + P(\bar{E}$ and $\bar{F}$ and $E) + P(\bar{E}$ and $\bar{F}$ and $\bar{E}$ and $\bar{F}$ and $E)$ + ... ∞

$= P(E) + P(\bar{E})\,P(\bar{F})\,P(E) + P(\bar{E})\,P(\bar{F})$ $\cdot P(\bar{E})\,P(\bar{F}) \cdot P(E)$ + ... ∞

$$= \frac{1}{6} + \frac{5}{6} \times \frac{5}{6} \times \frac{1}{6} + \frac{5}{6} \times \frac{5}{6} \times \frac{5}{6} \times \frac{5}{6} \times \frac{1}{6} + \ldots \infty$$

$$= \frac{1}{6} + \frac{1}{6}\left(\frac{5}{6}\right)^2 + \frac{1}{6}\left(\frac{5}{6}\right)^4 + \ldots \infty$$

$$= \frac{1}{6}\left[1 + \left(\frac{5}{6}\right)^2 + \left(\frac{5}{6}\right)^4 + \ldots \infty\right]$$

$$= \frac{1}{6} \cdot \frac{1}{\left[1 - \left(\frac{5}{6}\right)^2\right]} = \left(\frac{1}{6} \cdot \frac{36}{11}\right) = \frac{6}{11}$$

Thus, P (A wins) $= \frac{6}{11}$ and $P(B$ wins$) = \frac{5}{11}$

9. We have, $P(H) = \frac{1}{2}$ and $P(T) = \frac{1}{2}$

Now, A wins if he throws a head in 1st, or 3rd or 5th or ... draw.

$\therefore P(A$ wins$) = P[H$ or $(T\,TH)$ or $(T\,T\,T\,TH)$ or $(T\,T\,T\,T\,T\,TH)$ or ...]

$= P(H) + P(T\,TH) + P(T\,T\,T\,TH) + \ldots$

$= P(H) + P(T)\,P(T)\,P(H) + P(T)\,P(T)P(T)$ $P(T)P(H) + \cdots$

Scanned by CamScanner

yoursmahboob.wordpress.com

$$= \frac{1}{2} + \left(\frac{1}{2}\right)^2 \frac{1}{2} + \left(\frac{1}{2}\right)^4 \frac{1}{2} + \ldots \infty$$

$$= \frac{1}{2} + \left(\frac{1}{2}\right)^3 + \left(\frac{1}{2}\right)^5 + \ldots \infty$$

$$= \frac{1}{2}\left[1 + \left(\frac{1}{2}\right)^2 + \left(\frac{1}{2}\right)^4 + \ldots \infty\right]$$

$$= \frac{1}{2} \cdot \frac{1}{\left[1 - \left(\frac{1}{2}\right)^2\right]} = \left(\frac{1}{2} \times \frac{4}{3}\right) = \frac{2}{3}$$

Thus $P(A \text{ wins}) = \frac{2}{3}$ and $P(B \text{ wins}) = \left(1 - \frac{2}{3}\right) = \frac{1}{3}$

10. Let E be the event of 'getting a six'. Then $\bar{E}$ is the event of 'not getting a six'.

Then $P(E) = \frac{1}{6}$ and $P(\bar{E}) = \frac{5}{6}$

Now, A wins if he throws a six in 1st, 4th or 7th or ... draw.

$\therefore P(A \text{ wins}) = P(E \text{ or } (\bar{E}\,\bar{E}\,\bar{E}\,E) \text{ or } (\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,E) \text{ or } \ldots]$

$$= P(E) + P(\bar{E}\,\bar{E}\,\bar{E}\,E) + P(\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,E) + \ldots$$

$$= \frac{1}{6} + \left(\frac{5}{6}\right)^3 \cdot \frac{1}{6} + \left(\frac{5}{6}\right)^6 \cdot \frac{1}{6} + \ldots \infty$$

$$= \frac{1}{6}\left[1 + \left(\frac{5}{6}\right)^3 + \left(\frac{5}{6}\right)^6 + \ldots \infty\right]$$

$$= \frac{1}{6} \cdot \frac{1}{\left[1 - \left(\frac{5}{6}\right)^3\right]} = \left(\frac{1}{6} \cdot \frac{216}{91}\right) = \frac{36}{91}$$

Now, B wins if he throws a six in 2nd or 5th or 8th or ..draw.

$\therefore P(B \text{ wins}) = P[(\bar{E}E) \text{ or } (\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,E) \text{ or } (\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,E) \text{ or } \ldots]$

$$= P(\bar{E}E) + P(\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,E) + P(\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,\bar{E}\,E) + \ldots$$

$$= \frac{5}{6} \cdot \frac{1}{6} + \left(\frac{5}{6}\right)^4 \cdot \frac{1}{6} + \left(\frac{5}{6}\right)^7 \cdot \frac{1}{6} + \ldots \infty$$

$$= \frac{5}{36}\left[1 + \left(\frac{5}{6}\right)^3 + \left(\frac{5}{6}\right)^6 + \ldots \infty\right]$$

$$= \frac{5}{36} \cdot \frac{1}{\left[1 - \left(\frac{5}{6}\right)^3\right]} = \left(\frac{5}{36} \cdot \frac{216}{91}\right) = \frac{30}{91}$$

Thus, $P(A \text{ wins}) = \frac{36}{91}$ and $P(B \text{ wins}) = \frac{30}{91}$

$\therefore P(A \text{ wins or } B \text{ wins}) = P(A \text{ wins}) + P(B \text{ wins})$

$$= \frac{36}{91} + \frac{30}{91} = \frac{66}{91}$$

and $P(C \text{ wins}) = 1 - P(A \text{ wins or } B \text{ wins})$

$$= 1 - \frac{66}{91} = \frac{25}{91}$$

11. Let E = Event of getting a sum 9 on two dice.

Then, $E = \{(3, 6), (4, 5), (5, 4), (6, 3)\}$

$\therefore PE = \frac{4}{36} = \frac{1}{9}$ and $P(\bar{E}) = \frac{8}{9}$

$\therefore P(A \text{ wins}) = P[E_1 \text{ or } \bar{E}_1\,\bar{E}_2E_3 \text{ or } \bar{E}_1\bar{E}_2\bar{E}_3\bar{E}_4E_5 \text{ or } \ldots]$

$$= \left[\frac{1}{9} + \frac{8}{9} \cdot \frac{8}{9} \cdot \frac{1}{9} + \frac{8}{9} \cdot \frac{8}{9} \cdot \frac{8}{9} \cdot \frac{8}{9} \cdot \frac{1}{9} + \ldots \infty\right]$$

$$= \frac{9}{17}$$

$\therefore P(B \text{ wins}) = \left(1 - \frac{9}{17}\right) = \frac{8}{17}$

$\therefore$ Required ratio $= \frac{9}{8}$

12. Required probability $= \frac{4}{52} \times \frac{3}{51} = \frac{1}{221}$

13. Let A = the event that Ashmit solves the problem.
and B = the event that Amisha solves the problem.
Clearly, A and B are independent events.

Now, $P(A) = \frac{80}{100} = \frac{8}{10}$

and $P(B) = \frac{70}{100} = \frac{7}{10}$

$\therefore P(A \cap B) = P(A) \cdot P(B) = \frac{8}{10} \times \frac{7}{10} = \frac{56}{100}$

So $P(A \text{ or } B) = P(A \cup B)$

$$= P(A) + P(B) - P(A \cap B)$$

$$= \frac{8}{10} + \frac{7}{10} - \frac{56}{100}$$

$$= \frac{94}{100} = 0.94$$

14. Let A = the event that A hits the target
and B = the event that B hits the target
As given, we have $P(A) = \frac{1}{3}$ and $P(B) = \frac{2}{5}$

Clearly, A and B are independent events

$\therefore P(A \cap B) = P(A) \cdot P(B) = \frac{1}{3} \times \frac{2}{5} = \frac{2}{15}$

$\therefore P$ (target is hit) $= P(A \text{ hits or } B \text{ hits})$

$$= P(A \cup B) = P(A) + P(B) - P(A \cap B)$$

$$= \frac{1}{3} + \frac{2}{5} - \frac{2}{15} = \frac{3}{5}$$

15. Let A, B, C be the respective events of solving the problem and $\bar{A}, \bar{B}, \bar{C}$ be the respective events of not solving the problem. Then A, B, C are independent events
$\therefore \bar{A}, \bar{B}, \bar{C}$ are independent events

Now, $P(A) = \frac{1}{2}\, P(B) = \frac{1}{3}$ and $P(C) = \frac{1}{4}$

$$P(\bar{A}) = \frac{1}{2}, \quad P(\bar{B}) = \frac{2}{3} \quad \text{and} \quad P(\bar{C}) = \frac{3}{4}$$

$\therefore P$(none solves the problem)

$= P$(not A) and (not B) and (not C)]

$= P(\bar{A} \cap \bar{B} \cap \bar{C})$

$= P(\bar{A})\, P(\bar{B})\, P(\bar{C})$ ($\because \bar{A}, \bar{B}$ and $\bar{C}$ are independent)

$$= \frac{1}{2} \times \frac{2}{3} \times \frac{3}{4} = \frac{1}{4}$$

Hence, P(the problem will be solved)

$= 1 - P$ (none solves the problem)

$$= 1 - \frac{1}{4} = \frac{3}{4}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

16. Let A, B, C respectively.
Then $\bar{A}, \bar{B}, \bar{C}$ are the respective events of not solving the problem by them

Now, $P(A)=\frac{1}{3}$, $P(B)=\frac{2}{7}$ and $P(C)=\frac{3}{8}$

$\therefore$ $P(\bar{A})=\frac{2}{3}$, $P(\bar{B})=\frac{5}{7}$ and $P(\bar{C})=\frac{5}{8}$

$\therefore$ The probability that exactly one of them will solve it

$= P\{[A \cap (\text{not } B) \cap (\text{not } C)]$ or $[(\text{not } A) \cap B \cap (\text{not } C)]$ or $[(\text{not } A) \cap (\text{not } B) \cap C]\}$

$= P\{(A \cap \bar{B} \cap \bar{C}) \cup (\bar{A} \cap B \cap \bar{C}) \cup (\bar{A} \cap \bar{B} \cap C)\}$

$= P(A \cap \bar{B} \cap \bar{C}) + P(\bar{A} \cap B \cap \bar{C}) + P(\bar{A} \cap \bar{B} \cap C)$

$[\because (A \cap \bar{B} \cap \bar{C}) \cap (\bar{A} \cap B \cap \bar{C}) \cap (\bar{A} \cap \bar{B} \cap C) = \phi]$

$= P(A)P(\bar{B})P(\bar{C}) + P(\bar{A}).P(B).P(\bar{C}) + P(\bar{A}).P(\bar{B}).P(C)$

$= \left(\frac{1}{3}\times\frac{5}{7}\times\frac{5}{8}\right) + \left(\frac{2}{3}\times\frac{2}{7}\times\frac{5}{8}\right) + \left(\frac{2}{3}\times\frac{5}{7}\times\frac{3}{8}\right)$

$= \frac{25}{168} + \frac{5}{42} + \frac{5}{28} = \frac{25}{56}$

17. Let A, B, C be the events that A hits the target, B hits the target and C hits the target respectively.

Then, $P(A)=\frac{4}{5}$, $P(B)=\frac{3}{4}$, $P(C)=\frac{2}{3}$

$P(\bar{A})=\frac{1}{5}$, $P(\bar{B})=\frac{1}{4}$, $P(\bar{C})=\frac{1}{3}$

Case 1. $P(A, B,$ and $C,$ all hit the target$) = P(A \cap B \cap C)$

$= P(A)P(B)P(C) = \frac{4}{5}\times\frac{3}{4}\times\frac{2}{3} = \frac{2}{5}$

Case II. $P(A$ and B hit but not $C) = P[A \cap B \cap \bar{C}]$

$= P(A)P(B)P(\bar{C})$

$= \frac{4}{5}\times\frac{3}{4}\times\frac{1}{3} = \frac{1}{5}$

Case III. $P(A$ and C hit but not $B) = P(A \cap C \cap \bar{B})$

$= P(A)P(C)P(\bar{B})$

$= \frac{4}{5}\times\frac{2}{3}\times\frac{1}{4} = \frac{2}{15}$

Case IV. $P(B$ and C hit but not $A) = P(B \cap C \cap \bar{A})$

$= P(B)P(C)P(\bar{A})$

$= \frac{3}{4}\times\frac{2}{3}\times\frac{1}{5} = \frac{1}{10}$

All the above cases being mutually exclusive, we have the required probability

$= \frac{2}{5} + \frac{1}{5} + \frac{2}{15} + \frac{1}{10} = \frac{5}{6}$

18. Let $P_1 = 0.1, P_2 = 0.2, P_3 = 0.3, P_4 = 0.4$

$\therefore P$ (The balloon is hit) $= P$ (the balloon is hit atleast once)

$= 1 - P$(the balloon is hit in none of the shots)

$= 1 - (1-P_1)(1-P_2)(1-P_3)(1-P_4)$

$= 1 - (0.9)(0.8)(0.7)(0.6) = 0.6976$

19. $P(A)=\frac{2}{3}$, $P(B)=\frac{3}{5}$

Required probability $= P(A$ or $B) = P(A \cup B)$ be the events of solving the problem by A, B, C

$= P(A) + P(B) - P(A)P(B)$

$= \frac{2}{3} + \frac{3}{5} - \frac{2}{3}\cdot\frac{3}{5} = \frac{13}{15}$

20. $P(\text{none}) = 1 - P(\text{atleast one})$

$= 1 - P(A \cup B) = 1 - \frac{13}{15} = \frac{2}{15}$

21. $P(\text{not } A) = 1 - P(A) = 1 - 0.4 = 0.6$

22. $P(\text{at most } C) = P(D \text{ or } C) = P(D) + P(C)$

$= (0.1) + (0.2) = 0.3$

23. $P(B \text{ or } C) = P(B) + P(C)$

$= (0.3) + (0.2) = 0.5$

24. $P(\text{atleast } B) = P(B \text{ or } A) = P(B) + P(A)$

$= (0.3) + (0.4) = 0.7$

Solutions for question number 25-28 :

Let E = the event that Ajay is selected
and F = the event that Kajol is selected
Clearly, E and F are independent events

Now, $P(E)=\frac{1}{7}$ and $P(F)=\frac{1}{5}$

$\therefore$ $P(\bar{E})=\frac{6}{7}$ *and* $P(\bar{E})=\frac{4}{5}$

25. $P(\text{Both of them will be selected}) = P(E \text{ and } F) = P(E \cap F)$

$= P(E)P(F) = \frac{1}{7}\times\frac{1}{5} = \frac{1}{35}$

26. $P(\text{only one of them will be selected})$

$= P[(E \text{ and not } F) \text{ or } (F \text{ and not } E)]$

$= P[(E \cap \bar{F}) \cup (F \cap \bar{E})]$

$= P(E \cap \bar{F}) + P(F \cap \bar{E})$

$= P(E)P(\bar{F}) + P(F)P(\bar{E})$

$= \frac{1}{7}\times\frac{4}{5} + \frac{1}{5}\times\frac{6}{7} = \frac{2}{7}$

27. $P(\text{none of them will be selected})$

$= P[(\text{not } E) \text{ and } (\text{not } F)]$

$= P(\bar{E} \cap \bar{F}) = P(\bar{E}) \times P(\bar{F})$

$= \frac{6}{7}\times\frac{4}{5} = \frac{24}{35}$

28. $P(\text{atleast one of them will be selected})$

$= 1 - P(\text{none will be selected})$

$= 1 - \frac{24}{35} = \frac{11}{35}$

29. Let E = the event that A speaks the truth
and F = the event that B speaks the truth
then $\bar{E}$ = the event that A tells a lie
and $\bar{F}$ = the event that B tells a lie.
Clearly, E and F are independent events, So, E and $\bar{F}$ as well as $\bar{E}$ and F are independent.

Now, $P(E)=\frac{60}{100}=\frac{3}{5}$, $P(F)=\frac{80}{100}=\frac{4}{5}$

$\therefore$ $P(\bar{E})=\frac{2}{5}$, $P(\bar{F})=\frac{1}{5}$

$\therefore P(A$ and B contradict each other$)$

$= P(A$ speaks the truth and B tells a lie$)$

Scanned by CamScanner

yoursmahboob.wordpress.com

Probability

or (A tells a lie and B speaks the truth)

$$= P[(E \cap \bar{F}) \cup (\bar{E} \cup F)]$$
$$= P(E \cap \bar{F}) + P(\bar{E} \cap F)$$
$$= P(E)\,P(\bar{F}) + P(\bar{E})\,P(F)$$
$$= \frac{3}{5} \times \frac{1}{5} + \frac{2}{5} \times \frac{4}{5}$$
$$= \frac{11}{25} \Rightarrow 44\%$$

So A and B contradict each other in 44% cases.

Solutions for question number 30 and 31 : Let E = the event that the husband will be alive 20 years hence and F = the event that the wife will be alive 20 years hence.

Then $P(E) = \frac{5}{12}$ *and* $P(F) = \frac{3}{8}$

$\therefore$ $P(\bar{E}) = \frac{7}{12}$ *and* $P(\bar{F}) = \frac{5}{8}$

Clearly, E and F are independent events.

30. P(Couple will be alive 20 years hence)

$$= P(E \text{ and } F) = P(E \cap F)$$
$$= P(E).\,P(F) = \frac{5}{12} \times \frac{3}{8} = \frac{5}{32}$$

31. P(atleast one of them will be alive 20 years hence)

$$= 1 - P(\text{none will be alive 20 years hence})$$
$$= 1 - P(\bar{E} \cap \bar{F})$$
$$= 1 - P(\bar{E})\,P(\bar{F}) \qquad (\because \bar{E} \text{ and } \bar{F} \text{ are independent})$$
$$= 1 - \left(\frac{7}{12} \times \frac{5}{8}\right) = \frac{61}{96}$$

32. Let A, B, C denote the events of favouring the book by the first, the second and the third critic respectively.

Then $P(A) = \frac{5}{7}$, $P(B) = \frac{4}{7}$ and $P(C) = \frac{3}{7}$

$\therefore$ $P(\bar{A}) = \frac{2}{7}$, $P(\bar{B}) = \frac{3}{7}$ and $P(\bar{C}) = \frac{4}{7}$

$\therefore$Required probability

$= P$ (two favour the book or three favour the book)

$= P$ (two favour the book) + P (three favour the book)

$= P[\{A \text{ and } B \text{ (not } C)\} \text{ or } \{A \text{ and (not } B) \text{ and } C\}$ or $\{(\text{not } A) \text{ and } B \text{ and } C\}] + P(A \text{ and } B \text{ and } C)$

$= P[(A \cap B \cap \bar{C}) \cup P(A \cap \bar{B} \cap C) \cup (\bar{A} \cap B \cap C)]$
$+ P(A \cap B \cap C)$

$= P(A)\,P(B)P(\bar{C}) + P(A)\,P(\bar{B})\,P(C) + P(\bar{A})P(B)P(C)$
$+ P(A)\,P(B)\,P(C)$

$$= \left(\frac{5}{7} \times \frac{4}{7} \times \frac{4}{7}\right) + \left(\frac{5}{7} \times \frac{3}{7} \times \frac{3}{7}\right) + \left(\frac{2}{7} \times \frac{4}{7} \times \frac{3}{7}\right) + \left(\frac{5}{7} \times \frac{4}{7} \times \frac{3}{7}\right)$$
$$= \frac{209}{343}$$

33. Required probability

$$= P\ (X \text{ not defective and } Y \text{ not defective})$$
$$= P(\bar{X})\,P(\bar{Y})$$
$$= \{1 - P(X)]\ \{1 - P(Y)\}$$
$$= \frac{91}{100} \times \frac{95}{100} = \frac{8645}{10000} = 0.8645$$

34. A red ball can be drawn in two mutually exclusive ways

(i) Selecting bag I and then drawing a red ball from it.

(ii) Selecting bag II and then drawing a red bal form it.

Let E_1, E_2 and A denote the events defined as follows :

E_1 = selecting bag I,

E_2 = selecting bag II

A = drawing a red ball.

Since one of the two bags is selected randomly, therefore

$$P(E_1) = \frac{1}{2} \quad \text{and} \quad P(E_2) = \frac{1}{2}.$$

Now, $P\left(\frac{A}{E_1}\right)$ = probability of drawing a red ball when the first bag has been chosen $= \frac{4}{7}$

$P\left(\frac{A}{E_2}\right)$ = probability of drawing a red ball when the second bag has been selected $= \frac{2}{6}$

Using the law of total probability, we have

$$P(\text{red ball}) = P(A) = P(E_1)\,P\left(\frac{A}{E_1}\right) + P(E_2)P\left(\frac{A}{E_2}\right)$$
$$= \frac{1}{2} \times \frac{4}{7} + \frac{1}{2} \times \frac{2}{6} = \frac{19}{42}$$

35. Let E_1, E_2, E_3 and A be the events defined as follows.

E_1 = the toy is manufactured by machine A

E_2 = the toy is manufactured by machine B

E_3 = the toy is manufactured by machine C

and A = the toy is defective then

$$P(E_1) = \frac{25}{100} = \frac{1}{4}, \quad P(E_2) = \frac{35}{100} = \frac{7}{20}$$
$$P(E_3) = \frac{40}{100} = \frac{2}{5}$$

and $P\left(\frac{A}{E_1}\right)$ = Probability that the toy drawn is defective given the condition that it is a manufactured by machine $A = \frac{5}{100}$

Similarly, $P\left(\frac{A}{E_2}\right) = \frac{4}{100}$ and $P\left(\frac{A}{E_3}\right) = \frac{2}{100}$

Using law of total probability, we have

$$P(A) = P(E_1)\,P\left(\frac{A}{E_1}\right) + P(E_2)\,P\left(\frac{A}{E_2}\right) + P(E_3)\,P\left(\frac{A}{E_3}\right)$$
$$= \frac{25}{100} \times \frac{5}{100} + \frac{35}{100} \times \frac{4}{100} + \frac{40}{100} \times \frac{2}{100}$$
$$= 0.345$$

36. The testing procedure may terminate at the twelfth testing in two mutually exclusive ways

(i) When lot contain 2 defective bulbs.

(ii) When lot contains 3 defective bulbs .

Consider the following events :

A = testing procedure ends the twelfth testing

E_1 = lot contains 2 defective bulbs.

E_2 = lot contains 3 defective bulbs.

Scanned by CamScanner

yourSmahboob.wordpress.com

Required Probability $= P(A)$

$$= P(A \cap E_1) \cap P(A \cap E_2)$$
$$= P(A \cap E_1) + P(A \cap E_2)$$
$$= P(E_1)P\left(\frac{A}{E_1}\right) + P(A_2)P\left(\frac{A}{E_2}\right)$$

Now, $P\left(\frac{A}{E_1}\right)$ = Probability that first 11 draws contain 10 non defective and one defective and 12^{th} draw contains a defective article.

$$= \frac{{}^{18}C_{10} \times {}^{2}C_1}{{}^{20}C_{11}} \times \frac{1}{9}$$

and $P\left(\frac{A}{E_2}\right)$ = Probability that first 11 draws contain 9 non-defective and 2 defective articles and twelfth draw contains a defective article.

$$= \frac{{}^{17}C_9 \times {}^{3}C_2}{{}^{20}C_{11}} \times \frac{1}{9}$$

Hence, Required probability

$$= 0.4 \times \frac{{}^{18}C_{10} \times {}^{2}C_1}{{}^{20}C_{11}} \times \frac{1}{9} + 0.6 \times \frac{{}^{17}C_9 \times {}^{3}C_2}{{}^{20}C_{11}} \times \frac{1}{9}$$

37. Let E_1, E_2, E_3 and A be the events defined as follows :

E_1 = the toy is manufactured by machine A

E_2 = the toy is manufactured by machine B

E_3 = the toy is manufactured by machine C

A = the toy is defective

Then $P(E_1)$ = probability that the toy drawn is manufactured by machine $A = \frac{25}{100}$

Similarly, $P(E_2) = \frac{35}{100}$ and $P(E_3) = \frac{40}{100}$

$P\left(\frac{A}{E_1}\right)$ = probability that the toy drawn is defective given that it is manufactured by machine $A = \frac{5}{100}$

Similarly $P\left(\frac{A}{E_2}\right) = \frac{4}{100}$, $P\left(\frac{A}{E_3}\right) = \frac{2}{100}$

Now, required probability

$$= \frac{P(E_2)P\left(\frac{A}{E_2}\right)}{P(E_1)P\left(\frac{A}{E_1}\right) + P(E_2)P\left(\frac{A}{E_2}\right) + P(E_3)P\left(\frac{A}{E_3}\right)}$$

$$= \frac{\frac{35}{100} \times \frac{4}{100}}{\frac{25}{100} \times \frac{5}{100} + \frac{35}{100} \times \frac{4}{100} + \frac{40}{100} \times \frac{2}{100}} = \frac{28}{69}$$

38. Let E_1, E_2, E_3 and A be the events defined as follows :

E_1 = construction chosen is a bridge.

E_2 = construction chosen is a hospital

E_3 = construction chosen is a hotel.

A = construction gets damaged

Since there are 1200 constructions, therefore

$$P(E_1) = \frac{200}{1200} = \frac{1}{6}, \quad P(E_2) = \frac{400}{1200} = \frac{1}{3}$$

and $$P(E_3) = \frac{600}{1200} = \frac{1}{2}$$

It is given that $P\left(\frac{A}{E_1}\right)$ =Probability that a construction gets damaged is a bridge = 0.01

Similarly, $P\left(\frac{A}{E_2}\right) = 0.03$ and $P\left(\frac{A}{E_3}\right) = 0.15$

We are required to find $P\left(\frac{E_1}{A}\right)$ by Baye's rule.

$$P\left(\frac{E_1}{A}\right) = \frac{P(E_1)P\left(\frac{A}{E_1}\right)}{P(E_1)P\left(\frac{A}{E_1}\right) + P(E_2)P\left(\frac{A}{E_2}\right) + P(E_3)P\left(\frac{A}{E_3}\right)}$$

$$= \frac{\frac{1}{6} \times 0.01}{\frac{1}{6} \times 0.01 + \frac{1}{3} \times 0.03 + \frac{1}{2} \times 0.15}$$

$$= \frac{1}{1 + 6 + 45} = \frac{1}{52}$$

39. Let E_1, E_2 and A be the events defined as follows :

E_1 = selecting a box from the first group

E_2 = selecting a box from the second group and

A = ball drawn is green

Since there are 5 boxes out of which 3 boxes belong to first group and 2 boxes belong the second group. Therefore

$$P(E_1) = \frac{3}{5}, P(E_2) = \frac{2}{5}$$

If E_1 has already occurred, then a box from the first group is chosen. The box chosen contains 5 green balls and 3 red balls.

Therefore the probability of drawing a green ball from it is $\frac{5}{8}$.

So $$P\left(\frac{A}{E_1}\right) = \frac{5}{8}$$

Similarly, $$P\left(\frac{A}{E_2}\right) = \frac{2}{6} = \frac{1}{3}$$

Now, we have to find $P\left(\frac{E_1}{A}\right)$

By Baye's rule, we have

$$P\left(\frac{E_1}{A}\right) = \frac{P(E_1)P\left(\frac{A}{E_1}\right)}{P(E_1)P\left(\frac{A}{E_1}\right) + P(E_2)P\left(\frac{A}{E_2}\right)}$$

$$= \frac{\frac{3}{5} \times \frac{5}{8}}{\frac{3}{5} \times \frac{5}{8} + \frac{2}{5} \times \frac{1}{3}} = \frac{45}{61}$$

40. Let E_1, E_2 and A be the events defined as follows :

E_1 = six occurs, E_2 = six does not occur

and A = the man reports that it is a six.

Scanned by CamScanner

yoursmahboob.wordpress.com

We have, $P(E_1)=\frac{1}{6}, P(E_2)=\frac{5}{6}$

Now $P\left(\frac{A}{E_1}\right)$ = probability that the man reports that there is a six on the die given that six has occurred on the die.

= probability that the man speaks truth $=\frac{3}{4}$

and $P\left(\frac{A}{E_2}\right)$ = probability that the man reports that there is six on the die given that six has not occurred on the die.

= probability that the man does not speak truth

$=1-\frac{3}{4}=\frac{1}{4}$

We have to find $P\left(\frac{E_1}{A}\right)$

By Baye's rule, we have

$$P\left(\frac{E_1}{A}\right)=\frac{P(E_1)P\left(\frac{A}{E_1}\right)}{P(E_1)P\left(\frac{A}{E_1}\right)+P(E_2)P\left(\frac{A}{E_2}\right)}$$

$$=\frac{\frac{1}{6}\times\frac{3}{4}}{\frac{1}{6}\times\frac{3}{4}+\frac{5}{6}\times\frac{1}{4}}=\frac{3}{8}$$

41. Let E_1, E_2, E_3, E_4 and A be the events as defined below :

E_1 = the missing card is diamond

E_2 = the missing card is heart

E_3 = the missing card is spade

E_4 = the missing card is club

A = drawing two diamonds cards from the remaining cards

Then $P(E_1)=\frac{13}{52}=\frac{1}{4}$, $P(E_2)=\frac{13}{52}=\frac{1}{4}$

$P(E_3)=\frac{13}{52}=\frac{1}{4}$

and $P(E_4)=\frac{13}{52}=\frac{1}{4}$

$P\left(\frac{A}{E_1}\right)$ = probability of drawing two diamonds cards given that one diamond card is missing $=\frac{^{12}C_2}{^{51}C_2}$

$P\left(\frac{A}{E_2}\right)$ = probability of drawing two diamond cards given that one heart card is missing.

$=\frac{^{13}C_2}{^{51}C_2}$

Similarly, $P\left(\frac{A}{E_3}\right)=\frac{^{13}C_2}{^{51}C_2}$

and $P\left(\frac{A}{E_4}\right)=\frac{^{13}C_2}{^{31}C_2}$

By, Baye's rule

Required probability $=P\left(\frac{E_1}{A}\right)$

$$=\frac{P(E_1)P\left(\frac{A}{E_1}\right)}{P(E_1)P\left(\frac{A}{E_1}\right)+P(E_2)P\left(\frac{A}{E_2}\right)+P(E_3)P\left(\frac{A}{E_3}\right)+P(E_4)P\left(\frac{A}{E_4}\right)}$$

$=\frac{11}{50}$

LEVEL 1

1. Total possible nine digit numbers = 9!

Out of these 9! numbers only those numbers are divisible by 4 which have their last digits as even natural number and the numbers formed by their last two digits are divisible by 4.

The possible numbers of last two digits are

12, 32, 52, 72, 92, 24, 64, 84, 16, 36, 56, 76, 96, 28, 48, 68.

Thus there are 16 ways of choosing the last two digits. Corresponding to each of these ways the remaining 7 digits can be arranged in 7! ways. Therefore, the total number of 9 digits numbers divisible by 4 is $16\times7!$.

Hence, required probability $=\frac{16\times7!}{9!}=\frac{2}{9}$

2. Total possible number of 4 digits = 4! = 24

The number is divisible by 5 if unit digit itself is 5. Therefore we fix 5 at unit place and then remaining 3 places can be filled up in 3! ways.

Hence, the required probability $=\frac{3!}{4!}=\frac{6}{24}=\frac{1}{4}$

3. Excluding ground floor there are 7 floors. A person can leave the cabin at any of the 7 floors. Therefore, the total number of ways in which each of the 5 persons can leave the cabin at any of the 7 floors = 7^5.

$\therefore$ Exhaustive number of ways = 7^5

Five persons can leave the cabin at five different floors in $^7P_5$ ways.

$\therefore$ The favourable number of cases = $^7P_5$

Hence, the required probability $=\frac{^7P_5}{7^5}=\frac{360}{2401}$

4.

Box 1	Box 2	Box 3
3W	2W	1W
1B	2B	3B

There can be three mutually exclusive cases of drawing 2 white balls and 1 black ball.

	Box 1	Box 2	Box 3
Case 1	1W	1W	1B
Case 2	1W	1B	1W
Case 3	1B	1W	1W

Scanned by CamScanner

yoursmahboob.wordpress.com

$\therefore$ Required probability

$= P(W_1 \cap W_2 \cap B_3) \cup (W_1 \cap B_2 \cap W_3) \cup (B_1 \cap W_2 \cap W_3)$

$= P(W_1)P(W_2)P(B_3) + P(W_1)P(B_2)P(W_3) + P(B_1)P(W_2)P(W_3)$

$= \frac{3}{4} \times \frac{2}{4} \times \frac{3}{4} + \frac{3}{4} \times \frac{2}{4} \times \frac{1}{4} + \frac{1}{4} \times \frac{2}{4} \times \frac{1}{4} = \frac{26}{64} = \frac{13}{32}$

5. Since coin is fair i.e., with equal probability a heads and a tail can be obtained. Also all the trials are independent so the probability that head appears on the fifth toss does not depend upon previous results of the tosses.

Hence, required probability $= \frac{1}{2}$

6. The total number of ways in which two calculators can be chosen out of four calculators is ${}^4C_2 = 6$. If only two tests are required to identify defective calculators, then in first two tests defective calculators are identified. This can be done in one way only.

$\therefore$ Required probability $= \frac{1}{6}$

7. 20 girls can be seated around a round table in 19! ways.

So, exhaustive number of cases = 19!

Excluding A and B, out of remaining 18 girls, 4 girls can be selected ${}^{18}C_4$ ways which can be arranged in 4! ways.

Remaining $20 - (4 - 2) = 14$ girls can be arranged in 14! ways. Also A and B mutually can be arranged in 2! ways.

$\therefore$ Required number of arrangements $= {}^{18}C_4 \times 4! \times 2! \times 14!$

$= 18! \times 2$

$\therefore$ Required probability $= \frac{18! \times 2}{19!} = \frac{2}{19}$

8. Since x and y can take values from 0 to 10. So, the total number of ways of selecting x and y is $11 \times 11 = 121$

Now, $|x - y| > 5 \Rightarrow x - y < -5$ or $x - y > 5$

There are 30 pairs of values of x and y satisfying these two inequalities, so favourable number of ways = 30

Hence, required probability $= \frac{30}{121}$

9. Since a persons's birthday can fall in any of the 12 months.

So, total number of ways $= 12^4$.

Now, any two months can be chosen in ${}^{12}C_2$ ways. The 4 persons birthday can fall in these two months in 2^4 ways. Out of these 2^4 ways there are two ways when all of the four birthdays fall in one month.

So, favourable number of ways $= \frac{{}^{12}C_2 \times (2^4 - 2)}{12^4} = \frac{77}{1728}$

10. 6 objects can be distributed among 6 persons in 6^6 ways.

$\therefore$ Total number of ways $= 6^6$

The number of ways of distribution in which each one gets only one thing is 6!. So, the number of distribution in which atleast one of them does not get any thing is $6^6 - 6!$

Hence, required probability $= \frac{6^6 - 6!}{6^6}$

11. Total number of ways of arranging 40 books on a shelf = 40!

Out of 40 places, 4 places for the four volumes can be chosen in ${}^{40}C_4$ ways. In the remaining 36 places the remaining 36 books can be arranged in 36! ways. In the 4 places four volumes of encyclopedia can be arranged in increasing order in one way only.

So, favourable number of ways $= {}^{40}C_4 \times 36!$

Hence, required probability $= \frac{{}^{40}C_4 \times 36!}{40!} = \frac{1}{24}$

12. The divisibility of the product of four numbers depends upon the value of the last digit of each number. The last digit of a number can be any of the 10 digits 0, 1, 2 ... 9 . So, the total number of ways of selecting last digits of four numbers is $10 \times 10 \times 10 \times 10 = 10^4$.

If the product of the 4 numbers is not divisible by 5 or 10. Then the number of choices for the last digit of each number is 8 (excluding 0 or 5).

So, favourable number of ways $= 8 \times 8 \times 8 \times 8 = 8^4$

$\therefore$ The probability that the product is not divisible by 5 or 10

$= \frac{8^4}{10^4} = \left(\frac{8}{10}\right)^4$

Hence, Required probability $= 1 - \left(\frac{8}{10}\right)^4 = \frac{369}{625}$

13. P(selecting atleast one couple) $= 1 - P$(selecting none of the couples for the prize.)

$= 1 - \left(\frac{{}^{16}C_1 \times {}^{14}C_1 \times {}^{12}C_1 \times {}^{10}C_1}{{}^{16}C_4}\right) = \frac{15}{39}$

14. Total number of ways in which 7 (= 4 + 3) persons can speak is 7!.

The number of ways in which A, B, C speak in the given order is ${}^7C_3$ ways and remaining 4 persons can be arranged in 4! ways.

$\therefore$ Favourable number of ways $= {}^7C_3 \times 4!$

$\therefore$ Required probability $= \frac{{}^7C_3 \times 4!}{7!} = \frac{1}{6}$

15. Let A be the event of selecting a counterfeit coin and B the event of getting head, then

Required probability $= P(A \cap B) \cup (\bar{A} \cap B)$

$= P(A \cap B) + P(\bar{A} \cap B)$

$= P(A)P\left(\frac{B}{A}\right) + P(\bar{A})P\left(\frac{B}{\bar{A}}\right)$

$= \frac{2}{16} \times 1 + \frac{14}{16} \times \frac{1}{2} = \frac{9}{16}$

16. Total number of ways in which 5 people can be chosen out of 9 people $= {}^9C_5 = 126$

Number of ways in which the couple serves the committee

$= {}^7C_3 \times {}^2C_2 = 35$

Number of ways in which the couple does not serve the committee $= {}^7C_5 = 21$

$\therefore$ Favourable number of cases $= 35 + 21 = 56$

Hence, the required probability $= \frac{56}{126} = \frac{4}{9}$

17. E_1 = The event in which A speaks truth

E_2 = The event in which B speaks truth

Then $P(E_1) = \frac{60}{100} = \frac{3}{5}$, $P(E_2) = \frac{80}{100} = \frac{4}{5}$

Scanned by CamScanner

yoursmahboob.wordpress.com

and $P(\bar{E}_1)=\frac{2}{5}, \quad P(\bar{E}_2)=\frac{1}{5}$

$\therefore$ Required probability $= P[(E_1 \cap E_2) \cup (\bar{E}_1 \cap \bar{E}_2)]$

$= P(E_1 \cap E_2) + P(\bar{E}_1 \cap \bar{E}_2)$

$= P(E_1).P(E_2) + P(\bar{E}_1).P(\bar{E}_2)$

$= \left(\frac{3}{5}\times\frac{4}{5}\right) + \left(\frac{2}{5}\times\frac{1}{5}\right) = \frac{14}{25} = 0.56$

18. Two different squares can be chosen in 64×63 ways.
For each of the four corner squares, the favourable number of cases is 2.
For each of the 24 non-corner squares on all the four sides of the chessboard, the favourable number of cases is 3.
For each of the 36 remaining squares, the favourable number of cases is 4.
Thus, the total number of favourable cases

$= 4\times 2 + 24\times 3 + 36\times 4 = 224$

Hence, the required probability $= \frac{224}{64\times 63} = \frac{1}{18}$

19. The last two digits can be dialled in ${}^{10}P_2 = 90$ ways.
Out of these 90 cases only one case is favourable.
Hence, the required probability $= \frac{1}{90}$.

20. 3 squares on a chessboard can be chosen in ${}^{64}C_3$ ways.
Two squares of one colour and third square of different colour can be chosen in two mutually exclusive way.
(i) 2 white and one black (ii) 2 black and one white
Thus the favourable number of cases

$= {}^{32}C_2 \times {}^{32}C_1 + {}^{32}C_1 \times {}^{32}C_2$

$= 2({}^{32}C_2 \times {}^{32}C_1)$

Hence, the required probability $= \frac{2({}^{32}C_2 \times {}^{32}C_1)}{{}^{64}C_3} = \frac{16}{21}$

21. A leap year contains 366 days comprising of 52 full weeks and 2 extra days. Thus there can be following 7 possibilities for 2 extra days.
(i) Sunday, Monday, (ii) Monday, Tuesday
(iii) Tuesday, Wednesday (iv) Wednesday, Thursday
(v) Thursday, Friday (vi) Friday, Saturday
(vii) Saturday, Sunday
Let A be the event that the leap year contains 53 Sundays.
and B be the event that leap year contains 53 Mondays.
Then, we have

$P(A)=\frac{2}{7}, \quad P(B)=\frac{2}{7}, \quad P(A\cap B)=\frac{1}{7}$

So, required probability $= P(A \cup B)$

$= P(A) + P(B) - P(A \cap B)$

$= \frac{2}{7} + \frac{2}{7} - \frac{1}{7} = \frac{3}{7}$

22. Since, the probability of getting atleast one head in n times

$= 1 - \left(\frac{1}{2}\right)^n$

Therefore, $1 - \left(\frac{1}{2}\right)^n \geq 0.9$

$\Rightarrow \quad \left(\frac{1}{2}\right)^n \leq 0.1$

$\Rightarrow \quad 2^n \geq 10 \Rightarrow n \geq 4$

Hence, the least value of n is 4.

23. Total number of ways in which 2 persons can be selected out of 13 persons is ${}^{13}C_2$

Now, favourable number of cases $= \frac{{}^5C_1 \times {}^8C_1 + {}^5C_2}{{}^{13}C_2} = \frac{25}{39}$

24. We can choose 9 squares out of 64 squares in ${}^{64}C_9$ ways.
Hence, exhaustive number of cases $= {}^{64}C_9$
From the figure it is clear that the given square of size 3×3



can be formed by using four consecutive horizontal and 4 consecutive vertical lines, which can be done in

${}^6C_1 \times {}^6C_1 = 36$ ways

Basically you can make 6 squares of size 3×3 in vertical direction and 6 squares of the size 3×3 in horizontal direction. Hence total $6 \times 6 = 36$ squares can be chosen.

$\therefore$ The required probability $= \frac{36}{{}^{64}C_9}$

25. Total 7 digit numbers can be formed from the 9 digits $= {}^9P_7$
There are four exclusive cases of selecting 7 digits out of 9 digits which can form 7 digit numbers which are divisible by 9.
2, 3, 4, 5, 6, 7, 9 } 36removing 1 and 8
1, 3, 4, 5, 6, 8, 9 } 36 removing 2 and 7
1, 2, 4, 5, 7, 8, 9} 36 removing 3 and 6
1, 2, 3, 6, 7, 8, 9 } 36 removing 4 and 5
All the 7 numbers of each of the 4 sets can be arranged in 7! ways.
Hence the favourable number of numbers $= 4 \times 7!$

$\therefore$ Required probability $= \frac{4\times 7!}{{}^9P_7} = \frac{1}{9}$

Scanned by CamScanner

yourmathbook.wordpress.com

LEVEL 2

1. Total number of words that can be formed from the letters of the word MISSISSIPPI is $\frac{11!}{4!4!2!}$

When all the S's are together then the number of words can be formed $= \frac{8!}{4!2!}$

$$\text{Required probability} = \frac{\frac{8!}{4!2!}}{\frac{11!}{4!4!2!}} = \frac{4}{165}$$

2. Since each of the coefficients a, b and c can take values from 1 to 6. Therefore the total number of equations

$$= 6 \times 6 \times 6 = 216$$

Hence the exhaustive number of cases = 216

Now, the roots of the equation $ax^2 + bx + c = 0$ will be real if $b^2 - 4ac \geq 0 \Rightarrow b^2 \geq 4ac$

Following are the number of favourable cases

a	c	ac	$4ac$	b^2 ($\geq 4ac$)	b	Number of cases
1	1	1	4	4, 9, 16, 25, 36	2, 3, 4, 5, 6	$1 \times 5 = 5$
1 2	2 1	2	8	9, 16, 25, 36	3, 4, 5, 6	$2 \times 4 = 8$
1 3	3 1	3	12	16, 25, 36	4, 5, 6	$2 \times 3 = 6$
1 2 4	4 2 2	4	16	16, 25, 36	4, 5, 6	$3 \times 3 = 9$
1 5	5 1	5	20	25, 36	5, 6	$2 \times 2 = 4$
1 2 3 6	6 3 2 1	6	24	25, 36	5, 6	$4 \times 2 = 8$
2 4	4 2	8	32	36	6	$2 \times 1 = 2$
3	3	9	36	36	6	$1 \times 1 = 1$
					Total	$= 43$

Note → $ac = 7$ is not possible

Since $b^2_{(max)} = 36$ and $4ac \leq b^2$ hence $ac = 10, 11, 12, \ldots$ etc. is not possible.

Hence, total number of favourable cases = 43

So, the required probability $= \frac{43}{216}$.

3. 6 can be thrown with a pair of dice in the following ways (1, 5), (5, 1), (2, 4), (4, 2), (3, 3)

So, probability of throwing a '6' $= \frac{5}{36}$

and probability of not throwing a '6' $= \frac{31}{36}$

And 7 can be thrown with a pair of dice in the following ways. (1, 6), (6, 1), (2, 5), (5, 2), (3, 4), (4, 3)

so probability of throwing a '7' $= \frac{6}{36} = \frac{1}{6}$

and probability of not throwing a '7' $= \frac{5}{6}$

Let E_1 be the event of the throwing a '6' in a single throw of a pair of dice and

E_2 be the event of throwing a 7 in a single throw of a pair of dice.

Then $P(E_1) = \frac{5}{36}, \quad P(E_2) = \frac{1}{6}$

and $P(\bar{E}_1) = \frac{31}{36}, \quad P(\bar{E}_2) = \frac{5}{6}$

A wins if he throws '6' in first or third or fifth .. throws.

Probability of A throwing a 6 in first throw $= p(E_1) = \frac{5}{36}$

and probability of A throwing a 6 in third throw

$$= P(\bar{E}_1 \cap \bar{E}_2 \cap E_1) = P(\bar{E}_1)\,P(\bar{E}_2)\,P(E_1)$$

$$= \frac{31}{36} \times \frac{5}{6} \times \frac{5}{36}$$

Similarly, probability of A throwing a '6' in fifth throw

$$= P(\bar{E}_1)\,P(\bar{E}_2)\,P(\bar{E}_1)\,P(\bar{E}_2)\,P(E_1)$$

$$= \left(\frac{31}{36}\right)^2 \times \left(\frac{5}{6}\right)^2 \times \frac{5}{36}$$

Hence, probability of winning of A

$$= P[E_1 \cup (\bar{E}_1 \cap \bar{E}_2 \cap E_1) \cup (\bar{E}_1 \cap \bar{E}_2 \cap \bar{E}_1 \cap \bar{E}_2 \cap E_1) \cup \ldots]$$

$$= P(E_1) + P(\bar{E}_1 \cap \bar{E}_2 \cap E_1) + P(\bar{E}_1 \cap \bar{E}_2 \cap \bar{E}_1 \cap \bar{E}_2 \cap \bar{E}_1) +$$

$$= \frac{5}{36} + \left(\frac{31}{36} \times \frac{5}{6}\right) \times \frac{5}{36} + \left(\frac{31}{36} \times \frac{5}{6}\right)^2 \times \frac{5}{36} + \ldots$$

$$= \frac{\frac{5}{36}}{1 - \left(\frac{31}{36}\right) \times \left(\frac{5}{6}\right)} = \frac{30}{61}$$

Thus, probability of winning of $B = 1 - \frac{30}{61} = \frac{31}{61}$

4. Let A be the event of getting exactly 3 defectives in the examination of 8 wristwatches.

And B be the event of getting nineth wristwatch defective. Then

$$\text{Required probability} = P(A \cap B) = P(A)\,P\left(\frac{B}{A}\right)$$

Now, $P(A) = \frac{{}^4C_3 \times {}^{11}C_5}{{}^{15}C_8}$

And $P\left(\frac{B}{A}\right)$ = Probability that the nineth examined wristwatch is defective given that there were 3 defectives in the first 8 pieces examined $= \frac{1}{7}$

Hence, required probability $= \frac{{}^4C_3 \times {}^{11}C_5}{{}^{15}C_8} \times \frac{1}{7} = \frac{8}{195}$

Scanned by CamScanner

yoursmahboob.wordpress.com

5. Let E_1, E_2, E_3 and A be the events defined as follows :
E_1 = the examinee guesses the answer
E_2 = the examinee copies the answer
E_3 = the examinee knows the answer and
A = the examinee answers correctly
We have $P(E_1)=\frac{1}{3}, P(E_2)=\frac{1}{6}$

Since E_1, E_2 and E_3 are mutually exclusive and exhaustive events therefore

$$P(E_1)+P(E_2)+P(E_3)=1$$

$$\Rightarrow \quad P(E_3)=\frac{1}{2}$$

If E_1 has already occurred, then the examinee guesses. Since there are four choices out of which only one is correct, therefore the probability that he answers correctly given that he has made a guess is $\frac{1}{4}$ i.e., $P\left(\frac{A}{E_1}\right)=\frac{1}{4}$

It is a given that $P\left(\frac{A}{E_2}\right)=\frac{1}{8}$ and $P\left(\frac{A}{E_3}\right)$ is the probability that he answers correctly given that he knew the answer = 1
By Baye's rule,

Required probability $= P\left(\frac{E_3}{A}\right)$

$$=\frac{P(E_3)P\left(\frac{A}{E_3}\right)}{P(E_1)P\left(\frac{A}{E_1}\right)+P(E_2)P\left(\frac{A}{E_2}\right)+P(E_3)P\left(\frac{A}{E_3}\right)}$$

$$=\frac{\frac{1}{2}\times 1}{\frac{1}{3}\times\frac{1}{4}+\frac{1}{6}\times\frac{1}{8}+\frac{1}{2}\times 1}=\frac{24}{29}$$

6. Let x and y be the two non-negative integers
since $x+y=200$

$$\therefore \quad (xy)_{max}=100\times 100=10000 \quad (xy_{max} \text{ at } x=y)$$

Now, $xy \not\geq \frac{3}{4}\times 10000 \Rightarrow xy \geq \frac{3}{4}\times 10000$

$$\Rightarrow \quad xy \geq 7500 \Rightarrow x(200-x)\geq 7500$$

$$\Rightarrow \quad x^2-200x+7500\leq 0$$

$$\Rightarrow \quad 50\leq x\leq 150$$

So favourable number of ways = 150 − 50 + 1 = 101
Total number of ways = 200

Hence, required probability $=\frac{101}{200}$

7. Let $E_i (i = 1, 2, 3$ etc.) denote the event of drawing an even numbered card in i^{th} draw and F_i $(i = 1, 2, 3)$ denote the event of drawing an odd numbered card in i^{th} draw, then required probability

$$=P[(E_1\cap F_2\cap F_3)\cup(F_1\cap E_2\cap F_3)\cup(F_1\cap F_2\cap E_3)]$$
$$=P(E_1)P(F_2)P(F_3)+P(F_1)P(E_2)P(F_3)+P(F_1)P(F_2)P(E_3)$$
$$=\frac{4}{9}\times\frac{5}{9}\times\frac{5}{9}+\frac{5}{9}\times\frac{4}{9}\times\frac{5}{9}+\frac{5}{9}\times\frac{5}{9}\times\frac{4}{9}$$
$$=3\times\frac{4\times(5)^2}{(9)^3}=\frac{100}{243}$$

8. Consider the following events
A = The first number is less than the second number
B = The third number lies between the first and the second.

Now, we have to find $P\left(\frac{B}{A}\right)$.

Also, we have $P\left(\frac{B}{A}\right)=\frac{P(A\cap B)}{P(A)}$

Any 3 numbers can be chosen out of n numbers in ${}^nC_3$ ways.
Let the selected numbers be x_1, x_2, x_3. Then they satisfy exactly one of the following inequalities.

$$x_1<x_2<x_3,\quad x_1<x_3<x_2,\quad x_2<x_1<x_3,$$
$$x_2<x_3<x_1,\quad x_3<x_1<x_2,\quad x_3<x_2<x_1$$

The total number of ways of selecting three numbers and then arranging them $= {}^nC_3\times 3! = {}^nP_3$

$$\therefore \quad P(A)=\frac{{}^nC_3\times 3}{{}^nC_3\times 3!}$$

and $$P(A\cap B)=\frac{{}^nC_3}{{}^nC_3\times 3!}$$

Hence $$P\left(\frac{B}{A}\right)=\frac{P(A\cap B)}{P(A)}=\frac{1}{3}$$

9. Since b and c each can assume 9 values from 1 to 9.
So, total number of ways of choosing b and c is $9\times 9=81$
Now, $x^2+bx+c>0$ for all $x\in R$

$$\Rightarrow \quad D<0$$
$$\Rightarrow \quad b^2-4ac<0 \Rightarrow b^2-4c<0 \Rightarrow b^2<4c$$

Alternatively : $x^2+bx+c>0$

$$\Rightarrow \quad \left(x+\frac{b}{2}\right)^2+\frac{4c-b^2}{4}>0$$

$$\Rightarrow \quad 4c-b^2>0$$

$$\Rightarrow \quad b^2<4c$$

Now, the following table shows the possible values of b and c for which $b^2<4c$

c	b	Total
1	1,	1
2	1, 2	2
3	1, 2, 3	3
4	1, 2, 3,	3
5	1, 2, 3, 4	4
6	1, 2, 3, 4	4
7	1, 2, 3, 4, 5	5
8	1, 2, 3, 4, 5	5
9	1, 2, 3, 4, 5	5
		32

So, favourable number of cases = 32
Hence required probability $=\frac{32}{81}$

10. We have, $P(A\cup B\cup C)=\frac{3}{4}$

i.e., $$P(A)+P(B)+P(C)-P(A\cap B)$$
$$-P(B\cap C)-P(A\cap C)+P(A\cup B\cup C)=\frac{3}{4}$$

Scanned by CamScanner

yoursmahboob.wordpress.com

and $P(A\cap B)+P(B\cap C)+P(A\cap C)-2P(A\cap B\cap C)=\frac{1}{2}$

and $P(A\cap B)+P(B\cap C)+P(A\cap C)-3P(A\cap B\cap C)=\frac{2}{5}$

Solving the above equations (last two), we get

$$P(A\cap B\cap C)=\frac{1}{2}-\frac{2}{5}=\frac{1}{10}$$

$$\Rightarrow \quad P(A)P(B)P(C)=\frac{1}{10} \Rightarrow pmc=\frac{1}{10}$$

Also, $P(A)+P(B)+P(C)-[P(A\cap B)+P(B\cap C)+P(A\cap C)]+P(A\cup B\cup C)=\frac{3}{4}$

$$p+m+c-\left(\frac{1}{2}+\frac{2}{10}\right)+\frac{1}{10}=\frac{3}{4}$$

$$\Rightarrow \quad p+m+c=\frac{27}{20}$$

11. Let E, F, G be the events that the student is successful in tests A, B and C respectively. Then the probability that the students is successful is

$$=P[(E\cap F\cap\bar{G})\cup(E\cap\bar{F}\cap G)\cup(E\cap F\cap G)]$$
$$=P(E\cap F\cap\bar{G})+P(A\cap\bar{F}\cap G)+P(E\cap F\cap G)$$
$$=P(E)P(F)P(\bar{G})+P(E)P(\bar{F})P(G)+P(E)P(F)P(G)$$
$$=pq\left(1-\frac{1}{2}\right)+p(1-q)\left(\frac{1}{2}\right)+pq\left(\frac{1}{2}\right)$$
$$=\frac{pq+p-pq+pq}{2}$$
$$=\frac{p(1+q)}{2}$$

But the probability that the student is successful $=\frac{1}{2}$

$$\therefore \quad \frac{P(1+q)}{2}=\frac{1}{2} \Rightarrow p(1+q)=1$$

This is satisfied by $p=1, q=0$

Also there are other values (infinite numbers) of p, q for which the above relation is satisfied.

Hence, (d) is the correct option.

12. Since $\frac{1+4p}{p}, \frac{1-p}{4}, \frac{1-2p}{2}$ are the probabilities of 3 mutually exclusive events, therefore

$$0\le\frac{1+4p}{p}\le 1, \quad 0\le\frac{1-p}{4}\le 1, \quad 0\le\frac{1-2p}{2}\le 1$$

and $0\le\frac{1+4p}{p}+\frac{1-p}{4}+\frac{1-2p}{2}\le 1$

$$\Rightarrow \quad -\frac{1}{4}\le p\le\frac{3}{4}, \quad -1\le p\le 1, \quad -\frac{1}{2}\le p\le\frac{1}{2}$$

and $\frac{1}{2}\le p\le\frac{5}{2}$

$$\Rightarrow \max\left\{-\frac{1}{4},-1,-\frac{1}{2},\frac{1}{2}\right\}\le p\le\min\left\{\frac{3}{4},1,\frac{1}{2},\frac{5}{2}\right\}$$

$$\Rightarrow \quad \frac{1}{2}\le p\le\frac{1}{2} \Rightarrow p=\frac{1}{2}$$

13. ASSISTANT $\rightarrow$ *AA I N SSS TT*

STATISTICS $\rightarrow$ *A II C SSS TTT*

Here N and C are not common and same letters can be A, I, S, T. Therefore

Probability of choosing $A=\frac{{}^2C_1}{{}^9C_1}\times\frac{{}^1C_1}{{}^{10}C_1}=\frac{1}{45}$

Probability of choosing $I=\frac{1}{{}^9C_1}\times\frac{{}^2C_1}{{}^{10}C_1}=\frac{1}{45}$

Probability of choosing $S=\frac{{}^3C_1}{{}^9C_1}\times\frac{{}^3C_1}{{}^{10}C_1}=\frac{1}{10}$

Probability of choosing $T=\frac{{}^2C_1}{{}^9C_1}\times\frac{{}^3C_1}{{}^{10}C_1}=\frac{1}{15}$

Hence, required probability

$$=\frac{1}{45}+\frac{1}{45}+\frac{1}{10}+\frac{1}{15}=\frac{19}{90}$$

14. Out of 30 numbers 2 numbers can be chosen in ${}^{30}C_2$ ways.

So, exhaustive number of cases $={}^{30}C_2=435$

Since a^2-b^2 is divisible by 3 iff either a and b are divisible by 3 or none of a and b is divisible by 3. Thus, the favourable numbers, of cases $={}^{10}C_2+{}^{20}C_2=235$

Hence, required probability $=\frac{235}{435}=\frac{47}{87}$

15. The man will be one step away from the starting point if (A) either he is one step ahead or (B) one step behind the starting point.

Therefore, required probability $=P(A)+P(B)$

The man will be one step ahead at the end of eleven steps if he moves six steps forward and five steps backward. The probability of this event $={}^{11}C_6(0.4)^6\,(0.6)^5$

The man will be one step behind at the end of the eleven steps if he moves six steps backward and five steps forward. The probability of this event $={}^{11}C_6(0.6)^6\,(0.4)^5$.

Hence, the required probability

$$={}^{11}C_6(0.4)^6(0.6)^5+{}^{11}C_6(0.6)^6\,(0.4)^5$$
$$={}^{11}C_6(0.4)^5\,(0.6)^5\,(0.4+0.6)={}^{11}C_6(0.24)^5$$

16. There are 6 vertices in a hexagon. Using 3 vertices out of 6 vertices we can form ${}^6C_3$ triangles. But there can be only two triangles out of ${}^6C_3$ triangles which are equilateral (see the figure, (i) ΔACE, (ii) ΔBDF)



Hence, the required probability $=\frac{2}{{}^6C_3}=\frac{2}{20}=\frac{1}{10}$

17. Let F, B, L and R denote the forward, backward, left and right steps (or movements) then the following mutually exclusive ways are possible.

Scanned by CamScanner

yoursmahboob.wordpress.com

F	B	L	R
0	0	4	5
1	1	3	4
2	2	2	3
3	3	1	2
4	4	0	1
0	0	5	4
1	1	4	3
2	2	3	2
3	3	2	1
4	4	1	0

In this case he cancels out his forward and backward movements by moving equal steps in forward and backward directions each and he creates a difference of 1 step by moving one step extra either in right or left direction.

F	B	L	R
4	5	0	0
3	4	1	1
2	3	2	2
1	2	3	3
0	1	4	4
5	4	0	0
4	3	1	1
3	2	2	2
2	1	3	3
1	0	4	4

In this case he cancels out his left or right movement by moving equal number of steps in left and right directions each and he creates a difference of 1 step by moving one step extra either in forward or backward directions.

The number of permutations of these five arrangements is

$$4\left[\frac{9!}{5!4!}+\frac{9!}{1!1!3!4!}+\frac{9!}{2!2!2!3!}+\frac{9}{3!3!1!2!}+\frac{9!}{4!4!1!}\right]$$

$= 4(126 + 2520 + 7560 + 5040 + 630)$

$= 4 \times 15876$

But the total number of ways of arranging nine steps $= 4^9$.

$\therefore$ The required probability $= \dfrac{4 \times 15876}{4^9} = \dfrac{3969}{4^7}$

18. Let E_{rr} denote that a red colour ball is transferred from urn A to urn B tourn then a red colour ball is transferred from urn B to urn A.

E_{rb} denote that a red colour ball is transferred from urn A to urn B then a black colour ball is transferred from urn B to urn A

E_{br} denote that a black colour ball is transferred from urn A to urn B then a red colour ball is transferred from urn B to urn A.

E_{bb} denote that a black colour ball is transferred from urn A to urn B then a black colour ball is transferred from urn B to urn A. Then

$$P(E_{rr}) = \left(\frac{6}{10}\right)\left(\frac{5}{11}\right) = \frac{3}{11},$$

$$P(E_{rb}) = \left(\frac{6}{10}\right)\left(\frac{6}{11}\right) = \frac{18}{55}$$

$$P(E_{br}) = \left(\frac{4}{10}\right)\left(\frac{4}{11}\right) = \frac{8}{55},$$

$$P(E_{bb}) = \left(\frac{4}{10}\right)\left(\frac{7}{11}\right) = \frac{14}{55}$$

Let A be the event of drawing a red colour ball after these transfers. Then

$$P\left(\frac{A}{E_{rr}}\right) = \frac{6}{10}, P\left(\frac{A}{E_{rb}}\right) = \frac{5}{10}$$

$$P\left(\frac{A}{E_{br}}\right) = \frac{7}{10}, P\left(\frac{A}{E_{bb}}\right) = \frac{6}{10}$$

Therefore, the required probability is

$$P(A) = P(E_{rr})P\left(\frac{A}{E_{rr}}\right) + P(E_{rb})P\left(\frac{A}{E_{rb}}\right) + P(E_{br})P\left(\frac{A}{E_{br}}\right) + P(E_{bb})P\left(\frac{A}{E_{bb}}\right)$$

$$= \left(\frac{3}{11}\right)\left(\frac{6}{10}\right) + \left(\frac{5}{10}\right)\left(\frac{18}{55}\right) + \left(\frac{8}{55}\right)\left(\frac{7}{10}\right) + \left(\frac{14}{55}\right)\left(\frac{6}{10}\right)$$

$$= \frac{90 + 90 + 56 + 84}{550} = \frac{32}{55}$$

19. A number is divisible by 11 only if the difference of the sum of the digits at odd places and sum of the digits at even places is divisible by 11 *i.e*, 0, 11, 22, 33 ....

Here the sum of all the 9 digits (1, 2, 3, ...9) is 45.

We cannot create the difference of zero since $x + y = 45$, which is odd hence cannot be broken into two equal parts in integers.

Now, we will look for the possibilities of 11 which are as follows :

{1, 2, 6, 8}{1, 2, 5, 9}{1, 3, 6, 7}
{1, 3, 5, 8} {1, 3, 4, 9}{1, 4, 5, 7}
{2, 3, 5, 7}{2, 3, 4, 8}{2, 4, 5, 6}
and {4, 7, 8, 9}{5, 6, 8, 9}

The above set of values either gives the sum of 17 or 28.

Since if the sum of 4 digits at even places be 17 or 28 then the sum of rest of the digits (*i.e.*, digits at odd places) be 28 or 17 respectively and thus we can get the difference of 11.

Further we cannot get the difference of 22 or 33...

So there is only possible difference that can be created is 11 and there are only 11 set of values given above containing 4 digits which can be arranged in 4! ways and the remaining 5 digits can be arranged in 5! ways.

Thus the favourable number of numbers $= 11 \times 4! \times 5!$

But the total number of ways of arranging a nine digit number is ${}^9P_9 = 9!$

$\therefore$ Exclusive number of cases $= 9!$

$\therefore$ Required probability $= \dfrac{11 \times 4! \times 5!}{9!} = \dfrac{11}{126}$.

Scanned by CamScanner

yoursmahboob.wordpress.com

21 CO-ORDINATE GEOMETRY

It is one of those chapters which contributes least number of problems in CAT. Perhaps this chapter is more or less algebraic instead of being logical, since most of the problems require formula to solve them.

But some other MBA entrance exams ask the question from this chapter.

It is not fool proof but this chapter may be optional particularly for CAT aspirants who feel difficulty in algebraic problems. But it does not mean that this chapter is difficult or can not be learned.

1. CARTESIAN COORDINATE SYSTEM

1.1 Rectangular Co-ordinate Axes

Let $X'OX$ and $Y'OY$ be the two mutually perpendicular lines through any point O in the plane of paper. The point O is called the origin.



The line $X'OX$ is called the x-axis and the line $Y'OY$ is called the y-axis. These two lines taken together are called the **coordinate axes.**

1.2 Cartesian Co-ordinate of a Point

Each axes is calibrated as a scale into several points which are equidistant from each other.



The point O is assumed to be zero.



Let P be any point on the plane, then we draw a perpendicular from P on the X-axis and another on the Y-axis. Then the distance MP (which is parallel to the X-axis) is called the x-coordinate or abscissa of point P. Similarly, the length PN (which is parallel to the Y-axis) is called the y-coordinate or ordinate of point P.

Then the position of the point P in the plane with respect to the coordinate axes is represented by the ordered pair (x, y). The ordered pair (x, y) is called the coordinates of point P.

1.3 Quadrants

In the adjacent figure the two axes intersect each other perpendicular at point O.



The regions XOY, $X'OY$, $X'OY'$ and $Y'OX$ are known as first, second, third and fourth quadrant respectively.

The nature of values of x and y in different quadrants is different which is shown in figure also given below

Quadrant	Sign of (x, y)
I	$(+, +)$
II	$(-, +)$
III	$(-, -)$
IV	$(+, -)$

For example, let P be a point in second quadrant, then it is denoted as $(-1, 2)$, $(-2, 3)$, $(-3, 5)$, $(-6, 8)$, $(-7, 10)$ etc.

The coordinates of point O (i.e, origin) are taken as $(0, 0)$. The coordinates of any point on x-axis are of the form $(x, 0)$ and the coordinates of any point on y-axis are of the form $(0, y)$.

2. DISTANCE FORMULA

The distance between two points $P((x_1, y_1)$ and $Q(x_2, y_2)$ is given by

$$PQ = \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$$

Also, Distance of point (x_1, y_1) from origin $= \sqrt{x_1^2 + y_1^2}$

Scanned by CamScanner

yoursmahboob.wordpress.com

3. SECTION FORMULA

If $R(x, y)$ divides the line segment joined by the points $P(x_1, y_1)$ and $Q(x_2, y_2)$ internally in the ratio $m:n$ then

$$x = \frac{mx_2 + nx_1}{m+n}, \quad y = \frac{my_2 + ny_1}{m+n}$$

If $R(x, y)$ divides the line segment joined by the points $P(x_1, y_1)$ and $Q(x_2, y_2)$ externally in the ratio $m:n$ then

$$x = \frac{mx_2 - nx_1}{m-n}, \quad y = \frac{my_2 - ny_1}{m-n}$$

4.1 AREA OF A TRIANGLE

The area of a triangle ABC whose vertices are $A(x_1, y_1), B(x_2, y_2)$ and $C(x_3, y_3)$ is denoted by Δ.

$$\therefore \quad \Delta = \frac{1}{2}\begin{vmatrix} x_1 & y_1 & 1 \\ x_2 & y_2 & 1 \\ x_3 & y_3 & 1 \end{vmatrix}$$

$$= \frac{1}{2}[x_1(y_2 - y_3) + x_2(y_3 - y_1) + x_3(y_1 - y_2)]$$

4.2 AREA OF POLYGON

The area of the polygon whose vertices are $(x_1, y_1), (x_2, y_2), (x_3, y_3) \ldots (x_n, y_n)$ is

$$\Delta = \frac{1}{2}[(x_1y_2 - x_2y_1) + (x_2y_3 - x_3y_2) + \ldots + (x_ny_1 - x_1y_n)]$$

5. CONDITION OF COLLINEARITY OF THREE POINTS

The three given points are collinear *i.e.*, lie on the same straight line if

(i) Area of triangle ABC is zero.

(ii) Slope of AB = Slope of BC = Slope of AC

(iii) Distance between A and B + distance between B and C = Distance between A and C.

(iv) Find the equation of the line passing through any two points, if third point satisfies the equation of the line then three points are collinear.

6. SOME IMPORTANT RESULTS

6.1 If the vertices of a triangle have integral co-ordinates then the triangle can not be equilateral.

6.2 In order to prove that a given figure is a square, parallelogram, rectangle etc. We will prove the following points given in the table below corresponding the name of the figure.

	Name of the figure	Conditions
1.	Square	Four sides are equal and the diagonals are also equal.
2.	Rhombus	Four sides are equal
3.	Rectangle	Opposite sides are equal and diagonals are also equal
4.	Parallelogram	Opposite sides are equal
5.	Parallelogram but not a rectangle	Opposite sides are equal but the diagonals are not equal.
6.	Rhombus but not a square	All sides are equal but the diagonals are not equal

7. SOME IMPORTANT POINTS IN A TRIANGLE

7.1 Centroid

If $(x_1, y_1), (x_2, y_2)$ and (x_3, y_3) are the vertices of a triangle, then the coordinates of its centroid are $\left(\frac{x_1 + x_2 + x_3}{3}, \frac{y_1 + y_2 + y_3}{3}\right)$

7.2 Incentre

If $A(x_1, y_1), B(x_2, y_2)$ and $C(x_3, y_3)$ are the vertices of a triangle ABC such that $BC = a$, $CA = b$ and $AB = c$, then the coordinates of its centre are $\left(\frac{ax_1 + bx_2 + cx_3}{a+b+c}, \frac{ay_1 + by_2 + cy_3}{a+b+c}\right)$

NOTE If the equations of the sides of the triangle are given then we find the bisectors of internal angles and then their point of intersection to determine the in-centre.

7.3 Circumcentre

If 'O' is the circumcentre of a triangle ABC, then $OA = OB = OC$ and OA is called the circumradius.

To find the circumcentre of ΔABC, we use the relation $OA = OB = OC$. This gives two simultaneous linear equation and their solution provides the coordinates of circumcentre.

7.4 Orthocentre

To determine the orthocentre, first we find equations of lines passing through vertices and perpendicular to the opposite sides. Solving any two of these three equations we get the coordinates of orthocentre.

NOTE The circumcentre O, centroid G and othrocentre O' of a triangle ABC are collinear such that G divides $O'O$ in the ratio 2 : 1 *i.e.*, $O'G : OG = 2:1$

8. SHIFTING OF ORIGIN

Let O be the origin and $X'OX$ and $Y'OY$ be the axis of x and y respectively. Let O' and P be two points in the plane having coordinates (h, k) and (x, y) respectively referred to $X'OX$ and $Y'OY$ as coordinate axes.

Let the origin be transferred to O' and let $X'O'X$ and $Y'O'Y$ be new rectangular axes. Let the co-ordinates of P referred to new axes as the co-ordinate axes be (X, Y)



Thus if (x, y) are coordinates of a point referred to old axis and (X, Y) are the coordinates of the same point referred to new axis then.

$$x = X + h \quad \text{and} \quad y = Y + k$$

If therefore the origin is shifted at a point (h, k) we must substitute $X + h$ and $Y + k$ for x and y respectively.

Scanned by CamScanner

The transformation formula from new axes to old axes is

$$X = x - h, \quad Y = y - k$$

The coordinates of the old origin referred to the new axes are $(-h, -k)$

9. DEFINITION OF A STRAIGHT LINE

A straight line is a curve such that every point on the line segment joining any two points on it lies on it.

9.1 The general form of the equation of straight line

$$ax + by + c = 0$$

where a, b and c are real constants and x, y are two unknowns.

9.2 Slope (Gradient) of a Line

$$m = \tan\theta = -\frac{a}{b}$$

$$\{\because ax + by + c = 0 \Rightarrow by = -ax - c \Rightarrow y = -\frac{a}{b}x - \frac{c}{b}$$

$$\Rightarrow \quad y = mx + c, \quad \text{where } m = -\frac{a}{b} \text{ and } c \text{ is a constant}\}$$

Here m is called the slope or gradient of a line and c is the intercept on y-axis. The slope of a line is always measured in anticlockwise.





9.3 Slope of a line in terms of coordinates of any two points on it.

If (x_1, y_1) and (x_2, y_2) are coordinates of any two points on a line, then its slope is

$$m = \frac{y_2 - y_1}{x_2 - x_1} = \frac{\text{Difference of ordinates}}{\text{Difference of abscissae}} = \frac{\text{rise}}{\text{run}}$$

10.1 Angle between two lines

$$\tan\theta = \pm\left(\frac{m_2 - m_1}{1 + m_1 m_2}\right)$$



10.2 Condition of Parallelism of lines

If the slopes of two lines is m_1 and m_2 and if they are parallel then,

$$m_1 = m_2$$

10.3 Condition of Perpendicularity of lines

If the slopes of two lines is m_1 and m_2 and if they are perpendicular to each other, then

$$m_1 \cdot m_2 = -1$$

10.4 Intercepts of a line on the axis

If a straight line cuts x-axis at A and the y-axis at B then OA and OB are known as the intercepts of the line on x-axis and y-axis respectively where O is the origin.



INTRODUCTORY EXERCISE-21.1

1. The point (– 2, 3) lies in the quadrant :
   (a) First (b) Second
   (c) Third (d) Fourth
2. The point (2, – 3) lies in the quadrant :
   (a) First (b) Second
   (c) Third (d) Fourth
3. Find the distance between the points (– 5, 3) and (3, 1):
   (a) $2\sqrt{7}$ (b) $3\sqrt{14}$
   (c) $5\sqrt{17}$ (d) $2\sqrt{17}$
4. Let the vertices of a triangle ABC be (4, 3), (7, – 1), (9, 3) then the triangle is :
   (a) Scalene (b) Isosceles
   (c) Equilateral (d) none of (a), (b),(c)
5. Let the vertices of a triangle ABC be (4, 4), (3, 5), (– 1, – 1), then the triangle is :
   (a) scalene
   (b) equilateral
   (c) right angled
   (d) none of (a), (b), (c)
6. Let the vertices of a triangle ABC be (7, 9), (3, – 7), and (– 3, 3) then the triangle is :
   (a) right angled (b) equilateral
   (c) isosceles (d) both (a) and (c)
7. A(– 3, 2) and B(5, 4) are the end points of a line segment, find the coordinates of the mid points of the line segment :
   (a) (1, 3) (b) (2, 3)
   (c) (3, 2) (d) (4, 3)
8. In the previous question (no. 7) find the co-ordinates of the point which divides AB in the ratio 2 : 3 :
   (a) $\left(\frac{1}{5}, \frac{14}{5}\right)$ (b) (2, 3)
   (c) $\left(\frac{1}{5}, 3\right)$ (d) $\left(3, \frac{1}{2}\right)$
9. Find the co-ordinates of the point which divides the join of the points (2, 4) and (6, 8) externally in the ratio 5 : 3:
   (a) (5, 6) (b) (12, 14)
   (c) (3, 8) (d) (2, 7)

Scanned by CamScanner

yoursmahboob.wordpress.com

10. The coordinates of the vertices of a triangle are (3, 1), (2, 3) and (−2, 2). Find the coordinates of the centroid of the triangle ABC :
(a) (1, 2) (b) (2, 3)
(c) (4, 5) (d) (5, 6)

11. Find the co-ordinates of the incentre of the triangle whose vertices are the points (4, − 2), (5, 5) and (− 2, 4):
(a) $\left(\frac{7}{3}, \frac{2}{3}\right)$ (b) $\left(\frac{5}{2}, \frac{5}{2}\right)$
(c) $\left(\frac{6}{5}, 5\right)$ (d) none of these

12. Find the coordinates of the circum centre of the triangle whose vertices are (8, 6), (8, − 2) and (2, − 2):
(a) (2, 3) (b) (5, 2)
(c) (5, 3) (d) (7, 2)

13. If the coordinates of the mid points of the sides of a triangle are (1, 1), (2, − 3) and (3, 4). Find its centroid :
(a) $\left(3, \frac{2}{3}\right)$ (b) $\left(2, \frac{3}{4}\right)$
(c) $\left(2, \frac{2}{3}\right)$ (d) none of these

14. If the previous problem (no. 13) find the incentre for the given triangle :
(a) $\left(8, \frac{3}{2}\right)$ (b) $\left(\frac{7}{2}, 5\right)$
(c) $(2\sqrt{3}, 5)$ (d) none of these

15. $A(-2, -1)$, $B(1, 0)$, $C(4, 3)$ and $D(1, 2)$ are the four points of a quadrilateral. The quadrilateral is a :
(a) Square (b) Rhombus
(c) Parallelogram (d) none of (a), (b),(c)

16. The three vertices of a parallelogram taken in a order are (−1, 0), (3, 1) and (2, 2) respectively. Find the coordinates of the fourth vertex :
(a) (−1, 2) (b) (− 2, 1)
(c) (2, 3) (d) (3, − 2)

17. If the coordinates of the mid points of the sides of a triangle are (1, 2), (0, − 1) and (2, − 1) . Find the coordinates of its vertices :
(a) (1, − 4), (3, 2), (− 1, 2) (b) (1, 2), (2, 3), (3, − 4)
(c) (3, 4), (5, 2), (1, 2) (d) none of these

18. Points $A(4, -1)$, $B(6, 0)$, $C(7, 2)$ and $D(5, 1)$ are the vertices of the following quadrilateral which is a :
(a) Square (b) Rectangle
(c) Rhombus (d) none of (a), (b), (c)

19. Find the area of quadrilateral formed by joining the points (− 4, 2), (1, − 1), (4, 1) and (2, 5):
(a) 25.4 (b) 20.5
(c) 24.5 (d) none of these

20. Find (x, y) if (3, 2), (6, 3), (x, y) and (6, 5) are the vertices of a parallelogram :
(a) (5, 6) (b) (6, 5)
(c) (9, 6) (d) (9, 5)

21. Determine the ratio in which $y - x + 2 = 0$ divides the line joining (3, − 1) and (8, 9) :
(a) 3 : 5 (b) 4 : 3
(c) 2 : 3 (d) none of these

22. If the area of the quadrilateral whose angular points taken in order are (1, 2), (− 5, 6), (7, − 4) and $(h - 2)$ be zero, find the value of h :
(a) 2 (b) 3
(c) 5 (d) 6

23. The co-ordinates of A, B, C are (6, 3), (− 3, 5), (4, − 2) respectively and P is a point (x, y), then find the value of $\frac{\Delta PBC}{\Delta ABC}$:
(a) $\frac{x + y - 2}{7}$ (b) $\frac{x - y}{4}$
(c) $\frac{x + y - 3}{5}$ (d) none of these

24. Find the slope of the line joining the points (7, 5) and (9, 7):
(a) 1 (b) 2
(c) $\frac{1}{2}$ (d) 3

25. If $A(-2, 1)$, $B(2, 3)$ and $C(-2, -4)$ are three points, find the angle between BA and BC :
(a) $\tan^{-1}\left(\frac{3}{5}\right)$ (b) $\tan^{-1}\left(\frac{2}{3}\right)$
(c) $\tan^{-1}\left(\frac{3}{2}\right)$ (d) none of these

26. What is the slope of the line perpendicular to the line passing through the points (3, 5) and (− 4, 2)?
(a) $-\frac{3}{5}$ (b) $-\frac{2}{3}$
(c) $-\frac{7}{3}$ (d) none of these

27. A line passes through the points $A(2, -3)$ and $B(6, 3)$. Find the slope of the line which is parallel to AB :
(a) $\frac{2}{3}$ (b) $\frac{3}{2}$
(c) $\frac{1}{2}$ (d) $\frac{3}{4}$

28. In the previous question (no. 27), find the slope of the line which is perpendicular to AB :
(a) $-\frac{4}{3}$ (b) $\frac{5}{6}$
(c) $-\frac{2}{3}$ (d) none of these

29. Points $A(6, 6)$, $B(2, 3)$ and $C(4, 7)$ are the vertices of a triangle which is :
(a) right angled (b) acute angled
(c) obtuse angled (d) none of these

30. Three points $A(1, -2)$, $B(3, 4)$ and $C(4, 7)$ form :
(a) a straight line
(b) an equilateral triangle
(c) a right angled triangle
(d) none of (a), (b), (c)

Scanned by CamScanner

yoursmahboob.wordpress.com

11. EQUATIONS OF LINES PARALLEL TO THE COORDINATE AXES

11.1 Equation of a line parallel to x-axis and at a distance k from it is $y = k$

11.2 Equation of a line parallel to the y-axis and at a distance h from it is $x = h$.

11.3 Equation of the x-axis is $y = 0$

11.4 Equation of the y-axis is $x = 0$

12. DIFFERENT STANDARD FORMS OF THE EQUATIONS OF A STRAIGHT LINE

12.1 Slope Intercept Form

(a) The equation of a line with slope m and making an intercept on y-axis is $y = mx + c$.

(b) The equation of a line with slope m and passing through the origin (here $c = 0$) is $y = mx$.

12.2 Point Slope Form

The equation of a line passes through the point (x_1, y_1) and has the slope 'm' is $y - y_1 = m(x - x_1)$

12.3 Two Point Form

The equation of a line passing through two points (x_1, y_1) and (x_2, y_2) is $y - y_1 = \left(\frac{y_2 - y_1}{x_2 - x_1}\right)(x - x_1)$

12.4 Intercept Form

The equation of a line which cuts off intercepts a and b respectively from the x-axis and y-axis is $\frac{x}{a} + \frac{y}{b} = 1$.

12.5 Normal (or Perpendicular) Form

The equation of the straight line on which the length of the perpendicular from the origin (0, 0) is p and this perpendicular makes an angle α with x-axis is $x\cos\alpha + y\sin\alpha = p$.

12.6 Distance (or Symmetrical) Form

The equation of the straight line passing through (x_1, y_1) and making an angle θ with positive direction of x-axis is $\frac{x - x_1}{\cos\theta} = \frac{y - y_1}{\sin\theta} = r$

Where r is the distance of the point (x, y) on the line from the point (x_1, y_1)

- Since different values of r determine different points on the line, therefore the above form of the line is also called parametric form or symmetric form.

13. REDUCTION (OR TRANSFORMATION) OF THE GENERAL EQUATION

The general equation of a straight line is $Ax + By + C = 0$ which can be transformed into various standard forms.

13.1 General Equation ($Ax + By + C = 0$) → Slope Intercept form ($y = mx + c$)

$$Ax + By + C = 0 \Rightarrow By = -Ax - C$$

$$\Rightarrow y = \left(-\frac{A}{B}\right)x + \left(-\frac{C}{B}\right)$$

$$\Rightarrow y = mx + c$$

where $m = -\frac{A}{B} = -\frac{\text{Coefficient of } x}{\text{coefficient of } y}$

and intercept on y-axis $= -\frac{C}{B} = -\frac{\text{Constant trem}}{\text{coefficient of } y}$

13.2 General Equation ($Ax + By + C = 0$) → Intercept form $\left(\frac{x}{a} + \frac{y}{b} = 1\right)$

$$Ax + By + C = 0 \Rightarrow \frac{Ax}{-C} + \frac{By}{-C} = 1$$

$$\Rightarrow \frac{x}{\left(-\frac{C}{A}\right)} + \frac{y}{\left(-\frac{C}{B}\right)} = 1$$

$$\Rightarrow \frac{x}{a} + \frac{y}{b} = 1$$

$\Rightarrow$ Where, intercept on x-axis $= -\frac{C}{A} = -\frac{\text{Constant term}}{\text{Coefficient of } x}$

Intercept on y-axis $= -\frac{C}{B} = -\frac{\text{Constant term}}{\text{Coefficient of } y}$

13.3 General Equation ($Ax + By + C = 0$) → Normal Form ($x\cos\alpha + y\sin\alpha = p$)

$$Ax + By + C = 0 \quad \ldots(1)$$

$$x\cos\alpha + y\sin\alpha - p = 0 \quad \ldots(2)$$

Comparing (1) and (2)

$$\frac{A}{\cos\alpha} = \frac{B}{\sin\alpha} = \frac{C}{-p}$$

$$\Rightarrow \cos\alpha = -\frac{Ap}{C} \text{ and } \sin\alpha = -\frac{Bp}{C}$$

$$\Rightarrow 1 = \cos^2\alpha + \sin^2\alpha = \frac{p^2}{C^2}(A^2 + B^2)$$

$$\text{or } p^2 = \frac{C^2}{A^2 + B^2} \Rightarrow p = \frac{C}{\sqrt{A^2 + B^2}}$$

$$\therefore \cos\alpha = \frac{-A}{\sqrt{A^2 + B^2}}, \sin\alpha = \frac{B}{\sqrt{A^2 + B^2}}$$

$\therefore$ The required equation is

$$-\frac{A}{\sqrt{A^2 + B^2}}x - \frac{B}{\sqrt{A^2 + B^2}}y = \frac{C}{\sqrt{A^2 + B^2}}$$

14. POINT OF INTERSECTION OF TWO LINES

Let the equations of two lines be

$$a_1x + b_1y + c_1 = 0 \quad \ldots(1)$$

and $$a_2x + b_2y + c_2 = 0 \quad \ldots(2)$$

Scanned by CamScanner

yoursmahboob.wordpress.com

Let (x_1, y_1) be the coordinates of the point of intersection of the two lines. Then

$$a_1x_1 + b_1y_1 + c_1 = 0 \quad \ldots(3)$$

and $$a_2x_1 + b_2y_1 + c_2 = 0 \quad \ldots(4)$$

$\therefore$ By the method of cross multiplication

$$\frac{x_1}{b_1c_2 - b_2c_1} = \frac{y_1}{c_1a_2 - c_2a_1} = \frac{1}{a_1b_2 - a_2b_1}$$

$$\therefore \quad x_1 = \frac{b_1c_2 - b_2c_1}{a_1b_2 - a_2b_1}, \; y_1 = \frac{c_1a_2 - c_2a_1}{a_1b_2 - a_2b_1},$$

where $a_1b_2 - a_2b_1 \neq 0$

Thus the coordinates of the point of intersection of the two lines are

$$\frac{b_1c_2 - b_2c_1}{a_1b_2 - a_2b_1}, \frac{c_1a_2 - c_2a_1}{a_1b_2 - a_2b_1}$$

Remark : To find the coordinates of the point of intersection of two non parallel lines, we solve the given equations simultaneously and the values of x and y so obtained determine the coordinates of the point of intersection.

15. CONDITION OF CONCURRENCY OF THREE LINES

Three lines are said to be concurrent if they pass through a common point *i.e.*, they meet at a single common point.

Thus if three lines are concurrent the point of intersection of any two lines lies on the third line.

Let $$a_1x + b_1y + c_1 = 0 \quad \ldots(1)$$

$$a_2x + b_2y + c_2 = 0 \quad \ldots(2)$$

$$a_3x + b_3y + c_3 = 0 \quad \ldots(3)$$

be three concurrent lines then

$$a_3(b_1c_2 - b_2c_1) + b_3(c_1a_2 - c_2a_1) + c_3(a_1b_2 - a_2b_1) = 0$$

$$\Rightarrow \quad \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix} = 0$$

Which is the required condition for concurrency of three lines.

- Find the point of intersection of any two lines by solving them simultaneously. If this point satisfies the third equation also, then the given lines are concurrent.

16. ANGLE BETWEEN TWO STRAIGHT LINES

Let the two straight lines be

$$y = m_1x + c_1 \quad \ldots(1)$$

and $$y = m_2x + c_2 \quad \ldots(2)$$

and θ be the angle between them, then

$$\theta = \tan^{-1}\left|\frac{a_2b_1 - a_1b_2}{a_1a_2 + b_1b_2}\right|$$

17. CONDITIONS FOR PARALLELISM AND PERPENDICULARITY OF TWO LINES

17.1 If the two lines $a_1x + b_1y + c_1 = 0$ and $a_2x + b_2y + c_2 = 0$ are parallel, then

$$m_1 = m_2 \Rightarrow -\frac{a_1}{b_1} = \frac{-a_2}{b_2} \Rightarrow \frac{a_1}{a_2} = \frac{b_1}{b_2}$$

17.2 If the two lines $a_1x + b_1y + c_1 = 0$ and $a_2x + b_2y + c_2 = 0$ are perpendicular, then

$$m_1.m_2 = -1 \Rightarrow -\frac{a_1}{b_1} \times -\frac{a_2}{b_2} = -1$$

$$\Rightarrow \quad a_1a_2 + b_1b_2 = 0$$

Thus two lines $a_1x + b_1y + c_1 = 0$ and $a_2x + b_2y + c_2 = 0$ are

(i) Coincident, if $\frac{a_1}{a_2} = \frac{b_1}{b_2} = \frac{c_1}{c_2}$

(ii) Parallel, if $\frac{a_1}{a_2} = \frac{b_1}{b_2} \neq \frac{c_1}{c_2}$

(iii) Intersecting, if $\frac{a_1}{a_2} \neq \frac{b_1}{b_2}$

(iv) Perpendicular, if $\frac{a_1}{a_2} \neq \frac{b_1}{b_2}$

18. DISTANCE OF A POINT FROM A GIVEN LINE OR LENGTH OF PERPENDICULAR FROM THE POINT (x_1, y_1) TO THE STRAIGHT LINE $ax + by + c = 0$

Let the length of perpendicular be p, then

$$p = \frac{|ax_1 + by_1 + c|}{\sqrt{a^2 + b^2}}$$

19. DISTANCE BETWEEN TWO PARALLEL LINES

If two lines are parallel, then they have the same distance between these throughout. Therefore to find the distance between two parallel lines find the coordinates of any point on one of the given lines, preferably putting $x = 0$ or $y = 0$. Then the perpendicular distance of this point from the other line is the required distance between the lines.

Alternatively : Let the two parallel lines be $ax + by + c_1 = 0$ and $ax + by + c_2 = 0$, then the perpendicular distance between the lines is $\left|\frac{c_2 - c_1}{\sqrt{a^2 + b^2}}\right|$

20. EQUATIONS OF STRAIGHT LINES PASSING THROUGH (x_1, y_1) MAKING ANGLE θ WITH THE GIVEN LINE $y = mx + c$ ARE

$$y - y_1 = \frac{m \pm \tan\theta}{1 \mp m\tan\theta}(x - x_1)$$

Scanned by CamScanner

yoursmahboob.wordpress.com

21. EQUATION OF ANY LINE PASSING THROUGH THE POINT OF INTERSECTION OF TWO GIVEN LINES

Any line passing through the point of intersection of the lines $a_1x+b_1y+c_1=0$ and $a_2x+b_2y+c_2=0$ can be represented by the equation

$$(a_1x+b_1y+c_1)+\lambda(a_2x+b_2y+c_2)=0$$

where λ is an arbitrary constant.

22. POSITION OF A POINT WITH RESPECT TO A LINE

Any line $ax+by+c=0$ $(c\neq 0)$ divides the whole plane into two parts (i) One part containing the origin called the origin side, (ii) the other part not containing the origin called non-origin side of the line.

The length of the perpendicular from the origin on the line $ax+by+c=0$ is $\dfrac{c}{\sqrt{a^2+b^2}}$; if $c>0$.

If $c>0$, we say that the origin is on the positive side of the line and if $c<0$, the origin is said to be on the negative side of the line.

A point $P(x_1, y_1)$ is on the origin side or non-origin side of the line $ax+by+c=0$ according as ax_1+by_1+c and c are the same or opposite sign.

If $c>0$, then $P(x_1, y_1)$ is on the origin side or non-origin side of line $ax+by+c=0$ according as ax_1+by_1+c is positive or negative.

23. EQUATIONS OF BISECTORS OF THE ANGLES BETWEEN TWO GIVEN LINES

Let $a_1x+b_1y+c=0$ and $a_2x+b_2y+c_2=0$ be the equations of two given lines AB and AC respectively then the equations of the two bisectors are

$$\frac{a_1x+b_1y+c_1}{\sqrt{a_1^2+b_1^2}}=\pm\frac{a_2x+b_2y+c_2}{\sqrt{a_2^2+b_2^2}}$$

INTRODUCTORY EXERCISE-21.2

1. Find the equation of the line with slope $\frac{2}{3}$ and intercept on the y-axis is 5 :
(a) $y=\frac{2}{3}x+5$ (b) $y=\frac{3}{2}x+5$
(c) $y=3x+6$ (d) none of these

2. Find the slope and the intercept on the y-axis of the line $\sqrt{3}x+3y=6$:
(a) $\frac{1}{\sqrt{2}}$ (b) $\frac{1}{5}$
(c) $\frac{2}{\sqrt{3}}$ (d) $-\frac{1}{\sqrt{3}}$

3. Find the equation of the line passing through the point $(2,-3)$ and having its slope $\frac{5}{4}$:
(a) $4x-5y=20$ (b) $3x-2y=5$
(c) $5x-4y=22$ (d) none of these

4. Find the equation of the line which cuts off intercepts 2 and 3 from the axes :
(a) $9x-7y=6$ (b) $3x+2y=6$
(c) $4x+3y=7$ (d) none of these

5. Find the intercepts made by the line $3x+4y-12=0$ on the axes :
(a) 2 and 3 (b) 4 and 3
(c) 3 and 5 (d) none of these

6. Find the equation of the line through the points $(-1,-2)$ and $(-5,2)$:
(a) $2x+y=3$ (b) $3x-2y+7=0$
(c) $x+y+3=0$ (d) none of these

7. Find the equation of the straight line passing through the point $(-1,4)$ and having a gradient of 2.5 :
(a) $2x-5y+13=0$ (b) $5x-9y=13$
(c) $13x-15y+17=0$ (d) $5x-2y+13=0$

8. Find the equation of the straight line which makes equal intercepts on the axes passes through the point $(3,-5)$:
(a) $x-y=2$ (b) $x+y+2=0$
(c) $y-x+2=0$ (d) none of these

9. Find the equation of the straight line making intercepts on the axes equal in magnitude but opposite in sign and passing through the point $(-5,-8)$:
(a) $x-y=7$ (b) $2x+y=3$
(c) $x-y=3$ (d) none of these

10. Find the equation of the line passing through the point $(-4,-5)$ and perpendicular to the line joining the points $(1,2)$ and $(5,6)$:
(a) $x+y+17=0$ (b) $3x+2y+11=0$
(c) $x+y+9=0$ (d) $x-y+20=0$

11. A straight line intersects the x-axis at A and the y-axis at B. AB is divided internally at $C(8,10)$ in the ratio 5 : 4. Find the equation of AB :
(a) $x+y=18$ (b) $x+y+2=0$
(c) $x+y-2=0$ (d) none of these

12. Find the equation of the straight line which passes through the point $(3,4)$ and has intercepts on the axes such that their sum is 14 :
(a) $4x+3y=24$ (b) $x+y=7$
(c) $3x+7y=43$ (d) both (a) and (b)

13. A straight line passes through the points $(a,0)$ and $(0,b)$. The length of the line segment contained between the axis is 13 and the product of the intercepts on the axes is 60. Find the equation of the straight line :
(a) $5x+12y=60$ (b) $7x-12y=50$
(c) $5x+12y+60=0$ (d) both (a) and (c)

14. A firm produces 50 units of a good for Rs. 320 and 80 units for Rs. 380. Supposing that the cost curve is a straight line, estimate the cost of producing 110 units :

Scanned by CamScanner

yoursmahboob.wordpress.com

(a) Rs. 330 (b) Rs. 1665
(c) Rs. 440 (d) Rs. 365

15. Find the equation of the line on which length of the perpendicular from the origin is 5 and the angle which this perpendicular makes with the x-axis is 60° :
(a) $x\sqrt{3} + 2y + 8 = 0$ (b) $x + \sqrt{2}y - 7 = 0$
(c) $x + \sqrt{3}y = 10$ (d) none of (a),(b), (c)

16. Find the equation of the line which passes through the point (3, – 4) and makes an angle of 60° with the positive direction of x-axis :
(a) $x\sqrt{2} + y\sqrt{3} = 0$ (b) $\sqrt{3}x - y = 4 + 3\sqrt{3}$
(c) $x\sqrt{3} + y = 3\sqrt{2} + 5$ (d) none of (a), (b),(c)

17. Find the equation of the line joining the points of intersection of $2x + y = 4$ with $x - y + 1 = 0$ and $2x - y - 1 = 0$ with $x + y - 8 = 0$:
(a) $2x + 3y + 6 = 0$ (b) $3x + 2y + 12 = 0$
(c) $3x - 2y + 1 = 0$ (d) none of (a), (b),(c)

18. Find the equation of one of the two lines which pass through the point (4, 5) which make an acute angle 45° with the line $2x - y + 7 = 0$:
(a) $x - 2y = 0$ (b) $7x + 5y - 3 = 0$
(c) $3x + y + 8 = 0$ (d) $x - 3y + 11 = 0$

19. Find the equation of the straight line which passes through the point (5, – 6) which is parallel to the line $8x + 7y + 5 = 0$:
(a) $3x - 5y + 8 = 0$ (b) $7x + 8y + 5 = 0$
(c) $7x - 8y + 2 = 0$ (d) $8x + 7y + 2 = 0$

20. Find the equation of the straight line which passes through the point of intersection of the straight lines $x + y = 8$ and $3x - 2y + 1 = 0$ and is parallel to the straight line joining the points (3, 4) and (5, 6) :
(a) $x - y + 2 = 0$ (b) $x + y - 2 = 0$
(c) $3x - 4y + 8 = 0$ (d) none of these

21. Find the length of the perpendicular from the point (3, – 2) to the straight line $12x - 5y + 6 = 0$:
(a) 5 (b) 4
(c) 6 (d) 8

22. Find the distance between two parallel lines $5x + 12y - 30 = 0$ and $5x + 12y - 4 = 0$
(a) 3 (b) 7
(c) $\frac{5}{2}$ (d) 2

23. Find the equation of the line through the point of intersection of $2x - 3y + 1 = 0$ and $x + y - 2 = 0$ which is parallel to the y-axis.
(a) $x = 1$ (b) $8x = 7$
(c) $x + 3 = 0$ (d) $x = 6$

24. Find the equation of the line which passes through the point of intersection of the lines $x + 2y - 3 = 0$ and $4x - y + 7 = 0$ and is parallel to the line $y - x + 10 = 0$.
(a) $2x + 2y + 5 = 0$ (b) $3x - 3y = 10$
(c) $3x + 2y - 8 = 0$ (d) none of these

25. Find the equation of the line which passes through the point of intersection of the lines $2x - y + 5 = 0$ and $5x + 3y - 4 = 0$ and is perpendicular to the line $x - 3y + 21 = 0$
(a) $2x + y + 8 = 0$ (b) $3x + 4y - 7 = 0$
(c) $3x + y = 0$ (d) none of these

26. Find the equation of the line through the intersection of the lines $3x + 4y = 7$ and $x - y + 2 = 0$ having slope 3.
(a) $4x - 3y + 7 = 0$ (b) $21x - 7y + 16 = 0$
(c) $8x + y + 8 = 0$ (d) none of these

27. Find the equation of the straight line which passes through the point of intersection of the straight lines $3x - 4y + 1 = 0$ and $5x + y - 1 = 0$ and cuts off equal intercepts from the axis.
(a) $32x + 32y + 11 = 0$ (b) $23x + 23y = 11$
(c) $9x + 18y + 5 = 0$ (d) none of these

28. A straight line $\frac{x}{a} - \frac{y}{b} = 1$ passes through the point (8, 6) and cuts off a triangle of area 12 units from the axes of coordinates. Find the equations of the straight line.
(a) $3x - 2y = 12$ (b) $4x - 3y = 12$
(c) $3x - 8y + 24 = 0$ (d) both (a) and (c)

29. Find the equations of the bisectors of the angle between the straight line $3x + 4y + 2 = 0$ and $5x - 12y - 6 = 0$.
(a) $8x + y + 7 = 0$ (b) $16x - 12y - 1 = 0$
(c) $x + 8y + 4 = 0$ (d) both (b) and (c)

30. Find the area of the triangle formed by the lines whose equations are $2y - x = 5$, $y + 2x = 7$ and $y - x = 1$.
(a) $\frac{3}{10}$ (b) 10
(c) 6 (d) $\frac{2}{5}$

31. Find the coordinates of the orthocentre of the triangle whose vertices are (1, 2), (2, 3) and (4, 3).
(a) (2, 5) (b) (3, 4)
(c) (1, 6) (d) none of these

32. Two vertices of a triangle ABC are B(5, – 1) and C(– 2, 3). If the orthocentre of the triangle is the origin, find the third vertex.
(a) $\left(\frac{7}{2}, \frac{13}{2}\right)$ (b) $\left(\frac{3}{2}, \frac{11}{2}\right)$
(c) (– 4, – 7) (d) none of these

33. The area of a triangle is 5. Two of its vertices are (2, 1) and (3, – 2). The third vertex lies on $y = x + 3$. Find the third vertex :
(a) $\left(\frac{2}{7}, \frac{13}{5}\right)$ (b) $\left(\frac{7}{2}, \frac{13}{2}\right)$
(c) $\left(\frac{9}{2}, \frac{13}{2}\right)$ (d) $\left(\frac{7}{2}, \frac{13}{2}\right)$ or $\left(-\frac{3}{2}, \frac{3}{2}\right)$

34. A straight line L is perpendicular to the line $5x - y = 1$. The area of the triangle formed by the line L and coordinate axes is 5. Find the equation of the line :
(a) $x + 5y = \pm 5\sqrt{2}$ (b) $x - 3y = 0$
(c) $2x + y = 0$ (d) $x + 4y = 5\sqrt{2}$

35. (1, 2) and (3, 8) are a pair of a opposite vertices of square. Find the diagonals of the square passing through (1, 2) :
(a) $x - 2y = 1$ (b) $2x + 7y = 0$
(c) $3x + 2y + 7 = 0$ (d) $3x - y = 1$

Scanned by CamScanner

yoursmahboob.wordpress.com

Answers

INTRODUCTORY EXERCISE- 21.1

1. (b)	2. (d)	3. (d)	4. (b)	5. (c)	6. (d)	7. (a)	8. (a)	9. (b)	10. (a)
11. (b)	12. (b)	13. (c)	14. (d)	15. (c)	16. (b)	17. (a)	18. (c)	19. (c)	20. (c)
21. (c)	22. (b)	23. (a)	24. (a)	25. (b)	26. (c)	27. (b)	28. (c)	29. (a)	30. (d)

INTRODUCTORY EXERCISE- 21.1

1. (a)	2. (d)	3. (c)	4. (b)	5. (b)	6. (c)	7. (d)	8. (b)	9. (c)	10. (c)
11. (a)	12. (d)	13. (d)	14. (c)	15. (c)	16. (b)	17. (c)	18. (d)	19. (d)	20. (a)
21. (b)	22. (d)	23. (a)	24. (b)	25. (c)	26. (b)	27. (b)	28. (d)	29. (d)	30. (a)
31. (a)	32. (c)	33. (d)	34. (d)	35. (d)					

Scanned by CamScanner

yoursmahboob.wordpress.com

Hints & Solutions

INTRODUCTORY EXERCISE 21.1

1. The point $(-2, 3)$ lies in the second quadrant.

2. The point $(2, -3)$ lies in the fourth quadrant

3. Distance between two points $= \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$

Let $(x_1, y_1) \equiv (-5, 3)$ and $(x_2, y_2) \equiv (3, 1)$

$\therefore$ Required distance $= \sqrt{(3+5)^2 + (1-3)^2}$

$= \sqrt{64+4} = \sqrt{68} = 2\sqrt{17}$ unit

4. Let $A \equiv (4, 3)$, $B \equiv (7, -1)$, $C \equiv (9, 3)$

$AB = \sqrt{(7-4)^2 + (-1-3)^2} = \sqrt{25} = 5$

$BC = \sqrt{(9-7)^2 + (3+1)^2} = \sqrt{20} = 2\sqrt{5}$

$CA = \sqrt{(4-9)^2 + (3-3)^2} = \sqrt{25} = 5$

$\therefore \quad AB = CA = 5$

Hence ABC is an isosceles triangle.

5. Let $A \equiv (4, 4)$, $B \equiv (3, 5)$, $C \equiv (-1, -1)$

Then $AB = \sqrt{(3-4)^2 + (5-4)^2} = \sqrt{2}$

$BC = \sqrt{(-1-3)^2 + (-1-5)^2} = \sqrt{52}$

$AC = \sqrt{(-1-4)^2 + (-1-4)^2} = \sqrt{50}$

$\therefore \quad AB^2 + AC^2 = BC^2$

Hence by the Pythagorus Theorem, ABC is a right angled triangle.

6. Let $A \equiv (7, 9)$, $B \equiv (3, -7)$ and $C \equiv (-3, 3)$

Then $AB = \sqrt{(3-7)^2 + (-7-9)^2} = \sqrt{272}$

$BC = \sqrt{(-3-3)^2 + (3+7)^2} = \sqrt{136}$

$AC = \sqrt{(7+3)^2 + (9-3)^2} = \sqrt{136}$

$\therefore \quad AB^2 = BC^2 + AC^2$

Hence by Pythagorus Theorem, triangle ABC is a right angled triangle.

Also, since $BC = CA$, hence ABC is an isosceles triangle.

Thus ABC is a right angled isoceles triangle.

7. The coordinates of the mid points of AB

$= \left(\frac{x_1 + x_2}{2}, \frac{y_1 + y_2}{2}\right) = \left(\frac{-3+5}{2}, \frac{2+4}{2}\right) = (1, 3)$

8. Here $(x_1, y_1) = (-3, 2)$ and $(x_2, y_2) = (5, 4)$

The coordinates of the point which divides AB in the ratio $2:3$

$= \left(\frac{2\times 5 + 3\times -3}{2+3}, \frac{2\times 4 + 3\times 2}{2+3}\right) = \left(\frac{1}{5}, \frac{14}{5}\right)$

9. The required coordinates of the point which divides the join of $(2, 4)$ and $(6, 8)$ externally in the ratio $5:3$ are $\left(\frac{mx_2 - nx_1}{m-n}, \frac{my_2 - ny_1}{m-n}\right)$

Here, $m : n = 5 : 3$, $(x_1, y_1) = (2, 4)$, $(x_2, y_2) = (6, 8)$

Hence the required co-ordinates $= (12, 14)$.

10. Let the co-ordinate of the centroid of ΔABC be (x, y) then

$(x, y) = \left(\frac{x_1 + x_2 + x_3}{3}, \frac{y_1 + y_2 + y_3}{3}\right)$

$= \left(\frac{3+2-2}{3}, \frac{1+3+2}{3}\right) = (1, 2)$

11. Let $A \equiv (4, -2)$, $B \equiv (5, 5)$ and $C \equiv (-2, 4)$

Then $a = BC = \sqrt{(-2-5)^2 + (4-5)^2} = 5\sqrt{2}$

$b = AC = \sqrt{(4+2)^2 + (-2-4)^2} = 6\sqrt{2}$

$c = AB = \sqrt{(5-4)^2 + (5+2)^2} = 5\sqrt{2}$

and $(x_1, y_1) \equiv (4, -2)$, $(x_2, y_2) \equiv (5, 5)$, $(x_3, y_3) \equiv (-2, 4)$

$\therefore$ The coordinates of the incentre of the ΔABC are

$\left(\frac{ax_1 + bx_2 + cx_3}{a+b+c}, \frac{ay_1 + by_2 + cy_3}{a+b+c}\right)$

$= \left(\frac{5}{2}, \frac{5}{2}\right)$ {Substitute the values of (a, b, c) x_1, x_2, x_3, y_1, y_2 and y_3}

12. Let $S(x, y)$ be the circumcentre, then $AS = BS = CS = R$, where R is the circumradius

Now $(AS)^2 = (BS)^2$ where $S \equiv (x, y)$, $A \equiv (8, 6)$, $B \equiv (8, -2)$

$\therefore \quad (x-8)^2 + (y-6)^2 = (x-8)^2 + (y+2)^2$

$\Rightarrow \quad 36 - 12y = 4 + 4y$

$\Rightarrow \quad y = 2$

Again $(BS)^2 = (CS)^2$, where $S \equiv (x, y)$ $B \equiv (8, -2)$, $C \equiv (2, -2)$

$\therefore \quad (x-8)^2 + (y+2)^2 = (x-2)^2 + (y+2)^2$

$\Rightarrow \quad x^2 + 64 - 16x + y^2 + 4 + 4y = x^2 + 4 - 4x + y^2 + 4 + 4y$

$\Rightarrow \quad -12x + 60 = 0$

$\Rightarrow \quad x = 5$

$\therefore$ The circumcentre $S \equiv (x, y) = (5, 2)$

13. Let $P(1, 1)$, $Q(2, -3)$, $R(3, 4)$ be the midpoints of sides AB, BC and CA respectively triangle ABC.

Let $A(x_1, y_1)$, $B(x_2, y_2)$ and $C(x_3, y_3)$ be the vertices of triangle ABC.

Then, P is the mid point of AB

$\Rightarrow \quad \frac{x_1 + x_2}{2} = 1, \frac{y_1 + y_2}{2} = 1$

$\Rightarrow \quad x_1 + x_2 = 2$ and $y_1 + y_2 = 2$ ...(1)

Q is the mid point of BC

$\Rightarrow \quad \frac{x_2 + x_3}{2} = 2, \frac{y_2 + y_3}{2} = -3$

$\Rightarrow \quad x_2 + x_3 = 4$ and $y_2 + y_3 = -6$

R is the mid point of AC

$\Rightarrow \quad x_1 + x_3 = 6$ and $y_1 + y_3 = 8$

Scanned by CamScanner

yoursmahboob.wordpress.com

From (1), (2) and (3), we get

$(x_1, y_1) \equiv (2, 8)$, $(x_2, y_2) \equiv (0, -6)$

and $(x_3, y_3) \equiv (4, 0)$

Then the coordinates of the centroid

$$= \left(\frac{x_1 + x_2 + x_3}{3}, \frac{y_1 + y_2 + y_3}{3}\right)$$

$$= \left(\frac{2+0+4}{3}, \frac{8-6+0}{3}\right) = \left(2, \frac{2}{3}\right)$$

14. Since $(x_1, y_1) \equiv A(2, 8)$, $(x_2\ y_2) \equiv B(0, -6)$

and $(x_3, y_3) \equiv C(4, 0)$

Now, $a = BC = 2\sqrt{3}$, $b = AC = 2\sqrt{17}$, $c = AB = 10\sqrt{2}$

The coordinates of the in-centre of the triangle ABC are $\left(\frac{ax_1 + bx_2 + cx_3}{a+b+c}, \frac{ay_1 + by_2 + cy_3}{a+b+c}\right)$

$\therefore$ Required coordinates of incentre are

$$\left(\frac{2\sqrt{13} + 20\sqrt{2}}{\sqrt{13} + \sqrt{17} + 5\sqrt{2}}, \frac{2\sqrt{13} - 6\sqrt{17}}{\sqrt{13} + \sqrt{17} + 5\sqrt{2}}\right)$$

15. Let A, B, C and D be the vertices of the quadrilateral whose coordinates are $(-2, -1)$ $(1, 0)$, $(4, 3)$ and $(1, 2)$ respectively.

Now, $AB = \sqrt{10}$, $BC = \sqrt{18}$, $DC = \sqrt{10}$, $AD = \sqrt{18}$

$\therefore$ $AB = CD$ and $BC = AD$ *i.e.*, the opposite sides are equal.

Hence $ABCD$ is a parallelogram.

16. Let $A(-1, 0)$, $B(3, 1)$, $C(2, 2)$ and $D(x, y)$ be the vertices of a parallelogram $ABCD$ taken in order. Since the diagonals of a parallelogram bisect each other.

$\therefore$ Coordinates of the mid point of AC = Coordinates of the mid point of BD

$$\Rightarrow \left(\frac{-1+2}{2}, \frac{0+2}{2}\right) = \left(\frac{3+x}{2}, \frac{1+y}{2}\right)$$

$$\Rightarrow \left(\frac{1}{2}, 1\right) = \left(\frac{3+x}{2}, \frac{y+1}{2}\right)$$

$$\Rightarrow \frac{3+x}{2} = \frac{1}{2} \text{ and } \frac{y+1}{2} = 1$$

$$\Rightarrow x = -2 \text{ and } y = 1$$

Hence the fourth, vertex of the parallelogram is $(-2, 1)$

17. Solve as the question no. 13 has been solved. The required vertices of the triangle are $(1, -4)$, $(3, 2)$, $(-1, 2)$.

18. Let the vertices be $A(4, -1)$, $B(6, 0)$, $C(7, 2)$, $D(5, 1)$ then the coordinates of the mid point of AC are

$$\left(\frac{4+7}{2}, \frac{-1+2}{2}\right) = \left(\frac{11}{2}, \frac{1}{2}\right)$$

Coordinates of the mid point of BD are

$$\left(\frac{6+5}{2}, \frac{0+1}{2}\right) = \left(\frac{11}{2}, \frac{1}{2}\right)$$

Thus AC and BD have the same mid point. Hence $ABCD$ is a parallelogram.

Now, $AB = \sqrt{5}$, $BC = \sqrt{5}$ $\therefore AB = BC$

So, $ABCD$ is a parallelogram whose adjacent sides are equal. Hence, $ABCD$ is a rhombus.

Also, we have $AC = 3\sqrt{2}$ and $BD = \sqrt{2}$

Clearly, $AC \neq BD$. So $ABCD$ is not a square.

19. Let A, B, C, D be the points $(-4, 2)$, $(1, -1)$, $(4, 1)$ and $(2, 5)$ respectively. Then the area of the quadrilateral $ABCD$

$$= \frac{1}{2}\{-4 \times -1 - 2 \times 1 + 1 \times 1 - 4 \times -1 + 4 \times 5 - 2 \times 1 + 2 \times 2 \times -5 \times -4)$$

$$= \frac{1}{2}(4 - 2 + 1 + 4 + 20 - 2 + 4 + 20)$$

$$= \frac{49}{2} = 24 \cdot 5 \text{ square units.}$$

HINT $-4 \quad 1 \quad 4 \quad 2 \quad -4$
$\quad 2 \quad -1 \quad 1 \quad 5 \quad 2$

NOTE Area of quadrilateral $= \frac{1}{2}\{(x_1y_2 - x_2y_1) + (x_2y_3 - x_2y_3) + (x_3y_4 - x_4y_3) + (x_4y_1 - x_1y_4)\}$

20. Let A, B, C, D be the points $(3, 2)$, $(6, 3)$, $(x\ y)$ and $(6, 5)$ respectively.

Since $ABCD$ is a parallelogram, the diagonals AC and BD must bisect each other *i.e.*, the mid points of AC and the mid point of BD must coincide and hence the coordinates of the two mid points are the same

$$\therefore \frac{3+x}{2} = \frac{6+6}{2} \text{ and } \frac{2+y}{2} = \frac{3+5}{2}$$

or $3 + x = 12$ and $2 + y = 8$

or $x = 9$ and $y = 6$

Hence $(x, y) = (9, 6)$

21. Let the line $y - x + 2 = 0$ divide the join of $(3, -1)$ and $(8, 9)$ at the point P in the ratio $k : 1$. Then the coordinates of P are

$$\left(\frac{k \cdot 8 + 1 \cdot 3}{k+1}, \frac{k \cdot 9 + 1(-1)}{k+1}\right) = \left(\frac{8k+3}{k+1}, \frac{9k-1}{k+1}\right)$$

Since, this point lies on the line $y - x + 2 = 0$, we have

$$\frac{9k-1}{k+1} - \frac{8k+3}{k+1} + 2 = 0$$

or $k = \frac{2}{3}$

Hence the required ratio is $k : 1 = \frac{2}{3} : 1 = 2 : 3$

22. Let the points be $A(1, 2)$, $B(-5, 6)$, $C(7, -4)$, $D(h, -2)$

Given, area of the quadrilateral $ABCD = 0$

or $\frac{1}{2}\{(6 + 10) + (20 - 42) + (-14 + 4h) + (2h + 2)\} = 0$

or $h = 3$

23. Area of $\Delta PBC = \frac{1}{2}\{(5x + 3y) + (6 - 20) + (4y + 2x)\}$

$$= \frac{1}{2}(7x + 7y - 14)$$

$$= \frac{7}{2}(x + y - 2)$$

and area of $\Delta ABC = \frac{1}{2}\{(30 + 9) + (6 - 20) + (12 + 12)\}$

$$= \frac{49}{2}$$

Hence $\frac{\Delta PBC}{\Delta ABC} = \frac{x + y - 2}{7}$

Scanned by CamScanner

yoursmahboob.wordpress.com

24. Slope of the line $= \frac{y_2 - y_1}{x_2 - x_1} = \frac{7-5}{9-7} = 1$

Here $(x_1, y_1) \equiv (7, 5)$ and $(x_2, y_2) \equiv (9, 7)$

25. Let m_1 and m_2 be the slopes of BA and BC respectively. Then

$$m_1 = \frac{3-1}{2-(-2)} = \frac{1}{2} \quad \text{and} \quad m_2 = \frac{-4-3}{-2-2} = \frac{7}{4}$$

Let θ be the angle between BA and BC. Then

$$\tan\theta = \left|\frac{m_2 - m_1}{1 + m_1 m_2}\right| = \left|\frac{\frac{7}{4} - \frac{1}{2}}{1 + \frac{7}{4} \times \frac{1}{2}}\right| = \pm\frac{2}{3}$$

$$\Rightarrow \quad \theta = \tan^{-1}\left(\frac{2}{3}\right)$$

26. If m_1 be the slope of the line passing through the points $A(3, 5)$ and $B(-4, 2)$, then

$$m_1 = \frac{2-5}{-4-3} = \frac{3}{7}$$

If m_2 be the slope of the perpendicular line CD then $m_1 \cdot m_2 = -1$ or $\frac{3}{7} m_2 = -1$

or $$m_2 = -\frac{7}{3}$$

27. Let m_1 be the slope of line AB

$$\therefore \quad m_1 = \frac{3-(-3)}{6-2} = \frac{3}{2}$$

If m_2 be the slope of a line parallel to AB, then

$$m_2 = m_1 = \frac{3}{2}$$

28. Let m_3 be the slope of line perpendicular to AB, then

$$m_1 \cdot m_3 = -1$$

$$\Rightarrow \quad \frac{3}{2} \cdot m_3 = -1$$

$$\Rightarrow \quad m_3 = -\frac{2}{3}$$

29. $$m_1 = \text{Slope of } AB = \frac{3-6}{2-6} = \frac{3}{4}$$

$$m_2 = \text{Slope of } BC = \frac{7-3}{4-2} = 2$$

and $$m_3 = \text{Slope of } AC = \frac{7-6}{4-6} = -\frac{1}{2}$$

$$\therefore \quad m_2 \cdot m_3 = 2 \times -\frac{1}{2} = -1$$

This shows that BC is perpendicular to AC.
Hence, ABC is a right-angled triangle.

30. $$m_1 = \text{Slope of } AB = \frac{4-(-2)}{3-1} = 3$$

and $$m_2 = \text{Slope of } BC = \frac{7-4}{4-3} = 3$$

$$\therefore \quad m_1 = m_2$$

$\therefore AB$ is parallel to BC and B is common to both AB and BC.
Hence, the point $A(1, -2)$, $B(3, 4)$ and $C(4, 7)$ are collinear.

INTRODUCTORY EXERCISE 21.2

1. The equation of the line with slope 2/3 and intercept on the y-axis 5 is $y = \frac{2}{3}x + 5 \; (\because y = mx + c)$

2. We have $\sqrt{3}x + 3y = 6$

or $$3y = -\sqrt{3}x + 6$$

or $$y = -\frac{1}{\sqrt{3}}x + 2$$

Comparing the above equation with $y = mx + c$

we get $m = -\frac{1}{\sqrt{3}}$ and $c = 2$

Hence slope is $\left(-\frac{1}{\sqrt{3}}\right)$ and intercept on the y-axis is 2.

3. We have $m = \frac{5}{4}$ and $(x_1, y_1) = (2, -3)$

$\therefore$ The equation of the line as point slope form is

$$y - y_1 = m(x - x_1)$$

or $$y - (-3) = \frac{5}{4}(x - 2)$$

or $$y + 3 = \frac{5}{4}(x - 2)$$

or $$5x - 4y = 22$$

4. Here $a = 2$ and $b = 3$

$\therefore$ The required equation of the line is $\frac{x}{2} + \frac{y}{3} = 1$

$\Rightarrow$ $$3x + 2y = 6$$

5. We have $3x + 4y - 12 = 0$

$\Rightarrow$ $$3x + 4y = 12$$

$\Rightarrow$ $$\frac{3x}{12} + \frac{4y}{12} = 1 \Rightarrow \frac{x}{4} + \frac{y}{3} = 1$$

Which is of the form $\frac{x}{a} + \frac{y}{b} = 1$

Thus the required intercepts on the axes are 4 and 3.

6. The equation of the line through the points $(-1, -2)$ and $(-5, 2)$ is $(y - y_1) = \frac{y_2 - y_1}{x_2 - x_1}(x - x_1)$

where $(x_1, y_1) \equiv (-1, -2)$

and $(x_2, y_2) \equiv (-5, 2)$

$\therefore$ Required equation is

$$y - (-2) = \frac{2-(-2)}{-5-(-1)}[x - (-1)]$$

or $$y + 2 = \frac{4}{-4}(x + 1)$$

or $$x + y + 3 = 0$$

7. Let $(-1, 4)$ be the point as shown in figure and let $P(x, y)$ be any point on the line. Then the gradient (or slope) of the line is

$$\frac{y-4}{x-(-1)} = 2.5$$



Scanned by CamScanner

yoursmahboob.wordpress.com

$\Rightarrow \quad \frac{y-4}{x+1}=\frac{5}{2}$

$\Rightarrow \quad 5x-2y+13=0$

8. Let the equation of the straight line in the intercept form be

$$\frac{x}{a}+\frac{y}{b}=1 \qquad ...(1)$$

Since the intercepts are equal, therefore $a=b$

$\therefore$ From equation (1)

$$x+y=a \qquad ...(2)$$

Since this line passes through the point $(3, -5)$

$\therefore \quad 3+(-5)=a$

$\Rightarrow \quad a=-2$

$\therefore$ From equation (2), the required equation of the straight line is $x+y=-2$ or $x+y+2=0$

9. Let the equation of the straight line be

$$\frac{x}{a}+\frac{y}{b}=1 \qquad ...(1)$$

Since intercepts a, b are equal in magnitude but opposite in sign.

$\therefore \quad b=-a$

$\therefore$ From eq. (1) $\frac{x}{a}+\frac{y}{(-a)}=1$

or $\quad x-y=a \qquad ...(2)$

Since this line passes through the point $(-5, -8)$

$\therefore \quad -5-(-8)=a$

$\Rightarrow \quad a=3$

Hence, from (2) the required equation of the line is $x-y=3$

10. Let m_1 = slope of the line 'joining' $(1, 2)$ and $(5, 6)$

$\therefore \quad m_1=\frac{6-2}{5-1}=\frac{4}{4}=1$

If m_2 be the slope of the perpendicular line, then $m_1m_2=-1$

$\Rightarrow m_2=-1 \ (\because m_1=1)$

$\therefore$ The required line has slope $m_2=-1$ and passes through the point $(-4, -5)$

Hence, the required equation of the line in the point slope form is

$$(y-y_1)=m_2(x_2-x_1)$$

or $\quad y-(-5)=-1\{x-(-4)\}$

or $\quad x+y+9=0$

11. Let the equation of the line AB be $\frac{x}{a}+\frac{y}{b}=1 \qquad ...(1)$

Then the coordinates of A and B are respectively $(a, 0)$ and $(0, b)$.

Since $C(8, 10)$ divides AB in the ratio $5:4$, we have

$$\frac{5\times 0+4\times a}{5+4}=8$$

and $\quad \frac{5\times b+4\times 0}{5+4}=10$

or $\quad a=18 \quad$ and $\quad b=18$



Hence from (1), the required equation of the line AB is

$$\frac{x}{18}+\frac{y}{18}=1 \quad \text{or} \quad x+y=18$$

12. Let the equation of the line in the intercept form be $\frac{x}{a}+\frac{y}{b}=1$,

where a and b are intercepts on the axes.

Then $\quad a+b=14 \quad$ or $\quad b=14-a$

Since the line $\frac{x}{a}+\frac{y}{b}=1$ passes through the point $(3, 4)$;

$\therefore \quad \frac{3}{a}+\frac{4}{b}=1 \quad$ or $\quad \frac{3}{a}+\frac{4}{14-a}=1$

or $\quad a^2-13a+42=0$

or $\quad (a-6)(a-7)=0$

$\therefore \quad a=6, 7$

If $a=6$ then $b=8$

If $a=7$ then $b=7$

Hence the required equation of the line are

$$\frac{x}{6}+\frac{y}{8}=1 \quad \text{and} \quad \frac{x}{7}+\frac{y}{7}=1$$

or $\quad 4x+3y=24 \quad$ and $\quad x+y=7$

13. Since the line passes through $A(a, 0)$ and $B(0, b)$, it makes intercepts a and b on the axes of x and y. Let the equation of the line be

$$\frac{x}{a}+\frac{y}{b}=1 \qquad ...(1)$$

By the given conditions,

$$AB=13 \ \Rightarrow \ a.b=60 \qquad ...(2)$$

From (1) $\sqrt{a^2+b^2}=13$

$\Rightarrow \quad a^2+b^2=169$

$\Rightarrow \quad a+b=\pm 17$

Again $(a-b)^2=(a+b)^2-4ab=289-240=49$

$\therefore$ we get $a=12, b=5$ and $a=-12, b=-5$

$\therefore$ The required equations of the straight line are

$$\frac{x}{12}+\frac{y}{5}=1 \quad \text{and} \quad \frac{x}{-12}+\frac{y}{-5}=1$$

i.e., $\quad 5x+12y=60$ and $5x+12y+60=0$

14. Let the equation of the cost curve as a straight line be

$$y=mx+c \qquad ...(1)$$

where x = number of units of a good produced and y = cost of x units in rupees.

Given, when $x=50$, $y=320$ and when $x=80$, $y=380$

from (1) $\quad 320=50m+c \qquad ...(2)$

and $\quad 380=80m+c \qquad ...(3)$

Subtracting (2) from (3), we get $m=2$

Substituting $m=2$ in equation (2), we get $c=220$

$\therefore$ From (1) $y=2x+220$

when $x=110$, $y=2\times 110+220=440$

Hence, the required cost of producing 110 units is Rs. 440.

15. Here $p=5$ and $\alpha=60°$

$\therefore$ The required equation of the line is

$$x\cos\alpha+y\sin\alpha=p$$

Scanned by CamScanner

yoursmahboob.wordpress.com

or $x\cos 60° + y\sin 60° = 5$

$\Rightarrow$ $x + \sqrt{3}y = 10$ $\left(\because \sin 60° = \frac{\sqrt{3}}{2} \text{ and } \cos 60° = \frac{1}{2}\right)$

16. Here $(x_1, y_1) \equiv (3, -4)$ and $\theta = 60°$

The required equation of the line in the symmetric form is

$\frac{x - x_1}{\cos\theta} = \frac{y - y_1}{\sin\theta}$

$\Rightarrow$ $\frac{x-3}{\cos 60°} = \frac{y-(-4)}{\sin 60°}$

$\Rightarrow$ $\sqrt{3}x - y = 4 + 3\sqrt{3}$

17. We have $2x + y = 4$ ...(1)

and $x - y + 1 = 0$ ...(2)

Solving equations (1) and (2), we get

$x = 1$ and $y = 2$

$\therefore$ The point of intersection of (1) and (2) is (1, 2).

Again $2x - y - 1 = 0$ ...(3)

$x + y - 8 = 0$ ...(4)

Solving equations (3) and (4), we get $(x, y) \equiv (3, 5)$

$\therefore$ The point of intersection of (3) and (4) is (3, 5)

$\therefore$ The required equation of the straight line joining the points of intersection (1, 2), (3, 5) is

$y - 2 = \frac{(5-2)}{(3-1)} \cdot (x - 1)$

$\Rightarrow$ $3x - 2y + 1 = 0$

18. The equation of the line through the point (4, 5) is

$y - 5 = m(x - 4)$ ...(1)

where m is the slope of the line.

Now the given line is $2x - y + 7 = 0$

$\Rightarrow$ $y = 2x + 7$ ...(2)

If m_1 be the slope of the line (2), then $m_1 = 2$

If equation (1) makes an angle of 45° with equation (2), then we have

$\tan 45° = \frac{m_1 - m}{1 + m \cdot m_1} = \frac{2-m}{1+2m}$ *i.e.*, $\frac{2-m}{1+2m}$

$\therefore$ either $1 = \frac{m-2}{1+2m}$ or $1 = \frac{2-m}{1+2m}$

If $\frac{m-2}{1+2m} = 1$ then $m = -3$

If $\frac{2-m}{1+2m} = 1$ then $m = \frac{1}{3}$

Hence, from (1) the required equation of the two lines is

$y - 5 = -3(x - 4)$ and $y - 5 = \frac{1}{3}(x - 4)$

$\Rightarrow$ $3x - y - 17 = 0$ and $x - 3y + 11 = 0$

19. The equation of any straight line parallel to the line $8x + 7y + 5 = 0$ is $8x + 7y + c = 0$ ...(1)

where c is an arbitrary constant.

If the line (1) passes through the point (5, −6), then

$8 \times 5 + 7 \times (-6) + c = 0 \Rightarrow c = 2$

Hence from (1), the required equation of the straight line is $8x + 7y + 2 = 0$

20. Solving $x + y = 8$ and $3x - 2y + 1 = 0$, we get the point of intersection.

$\therefore$ The point of intersection is (3, 5).

Now, the equation of the line joining the points (3, 4) and (5, 6) is $(y - 4) = \frac{(6-4)}{(5-3)}(x - 3)$

$\Rightarrow$ $x - y + 1 = 0$ ...(1)

$\therefore$ The equation of the line parallel to the line $x - y + 1 = 0$ is

$x - y + c = 0$ ...(2)

Where c is an arbitrary constant. If the line passes through the point (3, 5) then

$3 - 5 + c = 0$ or $c = 2$

Hence from (2), the required equation of the line is $x - y + 2 = 0$.

21. Length of the perpendicular from the point (3, −2) to the straight line $12x - 5y + 6 = 0$ is

$\frac{12 \times 3 - 5 \times -2 + 6}{\sqrt{(12)^2 + (-5)^2}} = \frac{36 + 10 + 6}{\sqrt{169}} = 4$ units.

22. Putting $y = 0$ in $5x + 12y - 30 = 0$, we get

$5x - 30 = 0$ or $x = 6$

$\therefore$ (6, 0) is a point on the first line $5x + 12y - 30 = 0$

Required distance between the parallel lines = Perpendicular distance of the point (6, 0) from the second line $5x + 12y - 4 = 0$.

$= \frac{5.6 + 12.0 - 4}{\sqrt{5^2 + 12^2}} = \frac{30 - 4}{13} = 2$ units

23. The equation of the line through the point of intersection of $2x - 3y + 1 = 0$ and $x + y - 2 = 0$, is

$(2x - 3y + 1) + k(x + y - 2) = 0$

i.e., $(2 + k)x + (k - 3)y + (1 - 2k) = 0$ ...(1)

If this line is parallel to the y-axis, then its equation must be of the form $x = h$, *i.e*, the coefficient of y in (1) must be zero.

$\therefore$ $k - 3 = 0$ or $k = 3$

Hence, from (1) the required equation of the line is $(2 + 3)x + 0 \cdot y + (1 - 2 \times 3) = 0$ [Putting $k = 3$]

$\Rightarrow$ $x = 1$

24. The equation of any line passing through the point of intersection of the lines $x + 2y - 3 = 0$ and $4x - y + 7 = 0$ is

$x + 2y - 3 + k(4x - y + 7) = 0$ ...(1)

or $(1 + 4k)x + (2 - k)y + (7k - 3) = 0$ ...(2)

m_1 = Slope of the line (2) $= \frac{4k+1}{k-2}$

and m_2 = (Slope of the line $y - x + 10 = 0$) = 1

If the line (1) be parallel to the line $y - x + 10 = 0$

then $\frac{4k+1}{k-2} = 1 \Rightarrow k = -1$

Hence from (1), the required equation of the line is

$(x + 2y - 3) - 1 \cdot (4x - y + 7) = 0$

$\Rightarrow$ $3x - 3y + 10 = 0$

Scanned by CamScanner

yoursmahboob.wordpress.com

25. Solving $2x - y + 5 = 0$ and $5x + 3y - 4 = 0$, we get $x = -1$ and $y = 3$ *i.e.*, the point of intersection of the given lines is $(-1, 3)$.

$\therefore$ The equation of any line perpendicular to the line $x - 3y + 21 = 0$ is $3x + y + k = 0$ ...(1)

If this line (1) passes through the point $(-1, 3)$ then

$$3 \times -1 + 3 + k = 0 \Rightarrow k = 0$$

$\therefore$ From (1), the required equation of the line is $3x + y = 0$.

26. The equation of any line passing through the intersection of the lines $3x + 4y - 7 = 0$ and $x - y + 2 = 0$ is

$$(3x + 4y - 7) + k(x - y + 2) = 0 \quad ...(1)$$

Slope of the line $= -\dfrac{3 + k}{4 - k} = 3$

$$\Rightarrow \quad k = \frac{15}{2}$$

Hence, from (1) the required equation of the line is

$$(3x + 4y - 7) + \frac{15}{2}(x - y + 2) = 0$$

$$\Rightarrow \quad 21x - 7y + 16 = 0$$

27. The equation of any line passing through the point of intersection of the lines $3x - 4y + 1 = 0$ and $5x + y - 1 = 0$ is

$$(3x - 4y + 1) + k(5x + y - 1) = 0 \quad ...(1)$$

for intercept of this line with the x-axis, $y = 0$

$$\therefore \quad 3x + 1 + k(5x - 1) = 0$$

$$\Rightarrow \quad x = \frac{k - 1}{5k + 3}$$

For intercept of the line (1) on the y-axis, $x = 0$

$$\therefore \quad -4y + 1 + k(y - 1) = 0$$

$$\Rightarrow \quad y = \frac{k - 1}{k - 4}$$

Since the intercepts on the axes are equal.

$$\therefore \quad \frac{k - 1}{5k + 3} = \frac{k - 1}{k - 4} \Rightarrow k = 1, \text{ or } x = -\frac{7}{4}$$

But $k \neq 1$, because if $k = 1$, the line (1) becomes $8x - 3y = 0$ which passes through the origin and therefore cannot make non-zero intercepts on the axis.

$$\therefore \quad k = -\frac{7}{4} \text{ and from (1), we get}$$

$$3x - 4y + 1 - \frac{7}{4}(5x + y - 1) = 0$$

$\Rightarrow 23x + 23y = 11$, which is the required equation of the line.

28. We have $\dfrac{x}{a} - \dfrac{y}{b} = 1$ ...(1)

Since (1) passes through the point $(8, 6)$

$$\therefore \quad \frac{8}{a} - \frac{6}{b} = 1 \quad ...(2)$$

The line (1) meets the x-axis at the point given by $y = 0$ and from (1) $x = a$ *i.e.*, the line (1) meets the x-axis at the point $A(a, 0)$.

Similarly, the line meets the y-axis ($x = 0$) at the point $B(0, -b)$.

By the given condition, area of $\Delta = 12$

$$\Rightarrow \quad \frac{1}{2}ab = 12$$

$$\Rightarrow \quad ab = 24 \Rightarrow b = \frac{24}{a}$$

Substituting $b = \dfrac{24}{a}$ in (2), we get

$$\frac{8}{a} - \frac{6}{\frac{24}{a}} = 1 \Rightarrow a = 4 \text{ or } -8 \text{ and } b = 6 \text{ or } -3$$

Hence, from (1) the equation of the straight line are

$$\frac{x}{4} - \frac{y}{6} = 1 \text{ and } \frac{x}{-8} - \frac{-y}{-3} = 1$$

$$\Rightarrow \quad 3x - 2y = 12 \text{ and } 3x - 8y + 24 = 0$$

29. The equation of the lines may be written as $3x + 4y + 2 = 0$ and $-5x + 12y + 6 = 0$ in which the constant terms 2 and 6 are both positive.

The equation of the bisector of the angle in which the origin lies is $\dfrac{3x + 4y + 2}{\sqrt{3^3 + 4^2}} = \dfrac{-5x + 12y + 6}{\sqrt{(-5)^2 + (12)^2}}$

$$\Rightarrow \quad 16x - 12y - 1 = 0$$

The equation of the other bisector is

$$\frac{3x + 4y + 2}{\sqrt{3^2 + 4^2}} = \frac{-(-5x + 12y + 6)}{\sqrt{(-5)^2 + (12)^2}}$$

$$\Rightarrow \quad x + 8y + 4 = 0$$

30. Let the equations of the sides BC, CA and AB of the triangle ABC be represented by

$$2y - x = 5 \quad ...(1)$$

$$y + 2x = 7 \quad ...(2)$$

$$y - x = 1 \quad ...(3)$$

Solving the above 3 equations (1), (2) and (3), we get $A(2, 3)$, $B(3, 4)$ and $C\left(\dfrac{9}{5}, \dfrac{17}{5}\right)$

$\therefore$ The area of ΔABC

$$= \frac{1}{2}\left\{2 \times 4 - 3 \times 3 + 3 \times \frac{17}{5} - 4 \times \frac{9}{5} + \frac{9}{5} \times 3 - \frac{17}{5} \times 2\right\}$$

$$= \frac{1}{2}\left(8 - 9 + \frac{51}{5} - \frac{36}{5} + \frac{27}{5} - \frac{34}{5}\right) = \frac{3}{10} \text{ units.}$$

31. Let $A(1, 2)$, $B(2, 3)$ and $C(4, 3)$ be the vertices of ΔABC.

$m_1 =$ Slope of $BC = \dfrac{3 - 3}{4 - 2} = 0$ *i.e.*, BC is parallel to the x-axis.

$\therefore$ The perpendicular from $A(1, 2)$ to BC is parallel to the y-axis and its equation is $x = h$, which passes through $A(1, 2)$

$\therefore h = 1$ *i.e.*, the equation of the perpendicular from $A(1, 2)$ on BC is $x = 1$ ...(1)

$$m_2 = \text{Slope of } AC = \frac{3 - 2}{4 - 1} = \frac{1}{3}$$

If m_2' be the slope of a line perpendicular to AC then $m_2 m_2' = -1$ or $\dfrac{1}{3} \cdot m_2' = -1$ or $m_2' = -3$

$\therefore$ The equation of the perpendicular from $B(2, 3)$ on AC whose slope is -3 is

Scanned by CamScanner

yoursmahboob.wordpress.com

$$y - 3 = -3(x - 2)$$

$$\Rightarrow \quad 3x + y = 9 \qquad \ldots(2)$$

The orthocentre is the point of intersection of two lines (1) and (2)

$\therefore$ From (1) and (3), we get $3 \times 1 + y = 9$

$$\Rightarrow \quad y = 6$$

$\therefore$ The required coordinates of the orthocentre are (1, 6)

32. Let $A(x_1, y_1)$ be the third vertex. Let AD, BE, CF be the perpendiculars from the vertices on the opposite side BC, CA, AB respectively. Then the orthocentre $O(0, 0)$ is the point of intersection of AD, BE and CF.

Since AD i.e. OA is perpendicular to BC.

$\therefore$ Slope of $BA \times$ slope of $BC = -1$

or $$\frac{y_1 - 0}{x_1 - 0} \times \frac{3 - (-1)}{-2 - 5} = -1$$

$$\Rightarrow \quad y_1 = \frac{7x_1}{4} \qquad \ldots(1)$$

Again, since OB is perpendicular to CA

$$\therefore \quad \frac{-1 - 0}{5 - 0} \times \frac{y_1 - 3}{x_1 + 2} = -1$$

$$\Rightarrow \quad 5x_1 + 10 = y_1 - 3$$

$$\Rightarrow \quad x_1 = -4 \qquad \left(\because y_1 = \frac{7x_1}{4}\right)$$

From (1), $y_1 = \frac{7x_1}{4} = \frac{7 \times (-4)}{4} = -7$

Hence, the required coordinates of the third vertex A are $(x_1, y_1) = (-4, -7)$

33. Let (x_1, y_1) be the third vertex then $y_1 = x_1 + 3 \ldots(1)$

The area of the triangle formed by the points (2, 1), (3, – 2) and (x_1, y_1)

$$= \frac{1}{2}\{-4 - 3 + 3y_1 + 2x_1 + x_1 - 2y_1\}$$

$$= \frac{1}{2}(3x_1 + y_1 - 7)$$

By the given condition,

$$\pm \frac{1}{2}(3x_1 + y_1 - 7) = 5$$

$$\Rightarrow \quad 3x_1 + y_1 - 7 = \pm 10$$

$$\Rightarrow \quad 3x_1 + y_1 = 17 \qquad \ldots(2)$$

and $$3x_1 + y_1 = -3 \qquad \ldots(3)$$

Solving (1) and (2) we get $x_1 = \frac{7}{2}, y_1 = \frac{13}{2}$

Solving (1) and (3) we get $x_1 = -\frac{3}{2}$ and $y_1 = \frac{3}{2}$

Hence, the coordinates of the third vertex is either $\left(\frac{7}{2}, \frac{13}{2}\right)$ or $\left(-\frac{3}{2}, \frac{3}{2}\right)$

34. Equation of any line L perpendicular to

$$5x - y = 1 \text{ is } x + 5y = k \qquad \ldots(1)$$

Where k is an arbitrary constant.

If this line cuts x-axis at A and y-axis at B, then for A, $y = 0$ and from (1) $x = k$ i.e., A is the point $(k, 0)$ for B, $x = 0$ and from (1) $y = \frac{k}{5}$ i.e., B is the point $\left(0, \frac{k}{5}\right)$

$\therefore$ Area of the given $\Delta OAB = \frac{1}{2}(x_1 y_2 - x_2, y_1)$

$$= \frac{1}{2}\left(\frac{k^2}{5} - 0\right) = \frac{k^2}{10}$$

But the given condition $\frac{k^2}{10} = 5$

or $$k^2 = 50 \quad \therefore k = \pm 5\sqrt{2}$$

Hence, from (1), the required equation of the line is

$$x + 5y = 5\sqrt{2} \quad \text{or} \quad x + 5y = -5\sqrt{2}$$

35. Let $ABCD$ be the square and let (1, 2) and (3, 8) be the coordinates of opposite vertices A and C respectively.

The equation of the diagonal AC is $y - 2 = \frac{8 - 2}{3 - 1}(x - 1)$

$$\Rightarrow \quad 3x - y = 1$$

Scanned by CamScanner